

STATE HIGHWAY CONTRACTS

Contract # & PS&E #	Prog.#	Federal - Aid or State / Local	SR, US or I	Section	County(s)	Length	Width	Depth	Grade & Drain	Gravel & Stone	Treated Base	BST Cl. A	BST CL B,C,D	Cement Conc.	Asph. Conc.	Expanitory and / or Miscellaneous	Br. No	Br. Width	Br. Length	Br. Length	Engineers' Est. and Award Amount	Contractor	Award Date			
						km/mi .	m/ft .	m/ft .	km/mi .	km/mi .	km/mi .	km/mi .	km/mi .	km/mi .	km/mi .							m/ft .	m/ft .	km/mi .		
03A044	P2	BH-0901(417)	90	MP 9.24 to MP 9.60	King	NL										THIS PROJECT WILL BRING BRIDGES 90/43 S-E, 90/43 S-C AND 90/43 W-N TO CURRENT SEISMIC STANDARD BY RETROFITTING THEM USING FULL-HEIGHT STEEL JACKETING. IT WILL ALSO MODIFY ACCESS HATCHES FOR SAFE ACCESS TO THE EARTHQUAKE RESTRAINERS IN THESE					\$2,477,367.60	MOWAT CONSTRUCTION	1/20/2004			
006701				I-405 Vicinity Bridges - Seismic																						
Northwest																										
03A031	P1, I2	STP0529(014)	528 529	MP 0.43 to MP 1.33	Snohomish	8.05 Lane Miles	24'	.15	2.10 miles						8.05 Lane Miles	Planing Bituminous Pavement, Surfacing, Crack Sealing, Prelevel and pave with ACP, Pavement marking, Traffic control, guardrail, signing, curb and gutter, sidewalk, monument adj., catch basin adj., erosion control					\$1,250,266.51	WILDER CONSTRUCTION	1/20/2004			
006702				Columbia Ave to 55th Dr NE Vic and Snohomish River Br to I 5 Vic																						
Northwest																										
006703				THIS CONTRACT NUMBER NOT USED												THIS CONTRACT NUMBER NOT USED										
03Z017	P1	NH-0127(007)	127	MP 10.00 to MP 18.00	Whitman	16.15 Lane Miles	24'	.15'							16.15 Lane Miles	THIS PROJECT PROVIDES FOR IMPROVEMENTS TO SR 127 BY: ROADWAY EXCAVATION, EMBANKMENT, DRAINAGE, PLANING BITUMINOUS PAVEMENT, PAVEMENT REPAIR, ASPHALT CONC. PAVEMENT CL. SUPERPAVE 1/20, SEEDING, GUARDRAIL, PAVEMENT MARKINGS, GUIDE					\$1,326,466.80	TRANSTATE PAVING CO.	1/20/2004			
006704				Central Ferry to Church Hill Road																						
Eastern																										
03Z020	P1	STP-9999(409)	21	ET AL.	Adams, stevens, Linclon, Pend	271.75 Lane miles	Varies						271.75 Lane Miles			BITUMINOUS SURFACE TREATMENT CL. A MODIFIED, C MODIFIED, AND D MODIFIED, ACP CL. SUPERPAVE 1/2" CRACKSEALING, FOG SEAL, PRELEVELING, PAVEMENT PEPLACEMENT AND PAVEMENT MARKINGS .					\$2,845,638.49	SUPERIOR PAVING CO.	2/4/2004			
006705				2004 EASTERN REGION CHIP SEAL																						
Eastern																										
03A056	P3	FED	20	MP 114.9, 117.2, 121.7, 121.9, 124.4, 126.8	Whatcom											Paving with ACP, Guardrail, Culvert Replacement, Culvert Cleaning, slide debris removal, striping					\$706,586.00	SCARSELLA BROS. INC.	12/29/2003			
006706				Diablo Vic Emergency Repair																						
Northwest																										
04B012	P1	STP-9999(404)	17	ET AL	Adamd, Grant	22.27 Lane Miles	Varies	.10'							22.27 Lane Miles	0.10' OF PRELEVEL IN SPECIFIC AREAS, A BITUMINOUS SURFACE TREATMENT CLASS D, GUIDE POSTS, TRAFFIC MARKINGS, AND ADJUSTING MONUMENT CASES AND COVERS					\$2,489,495.00	SUPERIOR PAVING CO.	1/20/2004			
006707				NCR Seal 2004																						
North Central																										
03Z018	P1	IM-0905(097)	90	Adams County Line to Spokane County Line	Linclon, Spokane	64.56 Lane Miles										THIS PROJECT CONSISTS OF GRINDING AND PAVING ASPHALT CONCRETE PAVEMENT, SLOPE FLATTENING, DRAINAGE, GUARDRAIL, ILLUMINATION, PERMANENT SIGNING, PAVEMENT MARKINGS AND OTHER WORK.					\$3,881,981.50	INLAND ASPHALT COMPANY, A	2/24/2004			
006708																										
Eastern																										
03Z019	P1	IM-0905(096)	90	MP 231.76 to MP 239.12	Adams	30.56 Lane Miles	2@24'	.15'	7.64 grading						30.56 Lane Miles	THIS PROJECT CONSISTS OF: PLANING, GRADING, PAVEMENT REPAIR, CRACK SEAL, PAVING WITH ASPHALT CONCRETE PAVEMENT CLASS SUPERPAVE 1/2 " PG 70-28, FOG SEAL, PERMANENT SIGNING, GUARDRAIL, TRAFFIC CONTROL, AND OTHER WORK.					\$1,725,594.80	POE ASPHALT PAVING, INC.	2/4/2004			
006709				Tokio to Lincoln County Line Paving																						
Eastern																										
03A041	I2	County and State Project	203	MP 12.46 to MP 12.76	King	.3 miles	Varies	155 mm	.3 miles						.3 miles	ROUNDABOUT CONSTRUCTION, Drainage, Illumination, Paving with ACP Cl. Superpave, wetland mitigation, erosion control, traffic control					\$1,534,757.00	WILDER CONSTRUCTION	1/26/2004			
006710				NE 124th / Novelty Rd Vic Roundabout																						
Northwest																										
03A046	I1	State Project	527	MP 8.82 to MP 10.45	Snohomish	1.47 miles	43.89 meters	.20 meters								GRADING, DRAINAGE, STORM SEWER, SANITARY SEWER, WATER LINES, STRUCTURES, SURFACING, PLANING BITUMINOUS PAVEMENT, PAVING WITH ASPHALT CONCRETE CL. A, EROSION CONTROL AND PLANTING, CURBING, PAVEMENT MARKING, PERMANENT SIGNING,					\$15,815,999.70	KLB CONSTRUCTION INC.	3/1/2004			
006711				132nd St SE to 112th St SE																						
Northwest				Widen to Five Lanes																						
006712				THIS CONTRACT NUMBER NOT USED												THIS CONTRACT NUMBER NOT USED										
03A052	I2	NH-0018(029)	18	MP 2.49 to MP 2.73	King	.21 mies	varies	.15'	.21						.21 miles	AC overlay, installing guardrail, pavement markings, permanent signing, traffic signal and illumination work, replacing detection loops, traffic control					\$791,747.96	TRI-STATE CONSTRUCTION,	1/26/2004			
006713				EB Off Ramp to West Valley Highway																						
Northwest																										
04B008	I2	State Project	24	South Wahluke Slope - Guardrail	Grant	NL										grading, drainage, erosion control and planting, beam guardrail, traffic control					\$284,516.00	NORTH CENTRAL	1/26/2004			
006714																										
North Central																										
03Z021	P3	NH-0026(020)	26	MP 135.34 to MP 126.44	Whitman	NL										REMOVING CONC. BARRIER, EMBANKMENT, DITCH EXCAVATION, STRUCTURE EXCAVATION, RIP RAP, QUARRY SPALLS, FILTER BLANKET, SEEDING, gUARDRAIL, FENCING					\$105,623.50	M.L. ALBRIGHT & SONS, INC.	2/4/2004			
006715				Union Flat Creek improvement Drainage																						
Eastern																										
03W161	W4 X5	State Project	Architectu re	Pier 52 Interm Retail Improvements	King	NL										Retail Improvements					\$1,826,646.00	BIWELL CONSTRUCTION INC.	4/7/2004			
006716																										
HQ																										
04B013	P1	STP-PM01(001)	12	ET AL.	Yakima, Columbia, Benton, Kittitas,	23.31 Lane Miles	Varies	Varies	19.25 grading				19.25 miles			INSTALLING GUARDRAIL, GUIDE POSTS, PERMANENT SIGNING, PAVEMENT MARKING, CHIP SEAL					\$1,855,236.21	CENTRAL OREGON PAVERS,	2/17/2004			
006717				SCR Seal 2004																						
South Central																										
03Y013	P1	IM-NH-9999(411)	82 22	MP 82.14 TO MP 84.35	BENTON	6.65 miles	Varies	.15'	6.65 miles Grading						6.65 miles	This project will consist of rehabilitating the existing ramps and westbound mainline by rotomilling to a depth of 0.08', sealing existing cracks, and paving with a 0.15' full width ACP overlay. The estimate					\$682,640.00	TRANSTATE PAVING CO.	3/15/2004			
006718				PROSSER VICINITY - PAVING																						
South Central																										
03Y012	P1	IM-0823(058)	82	MP 122.17 TO MP 122.73	BENTON	3.55 Lane Miles	Varies	.15'							3/55 Lane Miles	THIS PROJECT CONSISTS OF PLANING BITUMINOUS PAVEMENT, CRACK SEALING, PAVING WITH ASPHALT CONCRETE PAVEMENT, INSTALLING BEAM GUARDRAIL, PAVEMENT MARKING, PERMANENT SIGNING, ILLUMINATION					\$345,820.00	INLAND ASPHALT COMPANY, A	2/17/2004			
006719				COFFIN ROAD VICINITY - PAVING																						
South Central																										
03Z014	I1	State Project	395	MP 165.46 TO MP 165.90	Spokane	.31	Variers	.20"	.31 miles							CLEARING AND GRUBBING, EARTHWORK, DRAINAGE, CONSTRUCTING 17 GEOSYNTHETIC WALLS, 4 PRESTRESSED CONCRETE BOX GIRDER BRIDGES, SANITARY SEWER, UTILITY CONDUIT, EROSION CONTROL, TRAFFIC CONTROL	N-S@ F SB-Ramp	37' 38'	148' 136'	.01.01	\$5,886,707.00	MAX J. KUNEY COMPANY	3/8/2004			
006720				NSC - FARWELL ROAD LOWERING																						
Eastern																										
03X311	P1	NH-0502(008)	502	I 5 To Battle Ground	Clark	11.08 Lane Miles	24'	.15'								GRADING, SURFACING, PRELEVELING WITH HMA , PAVING WITH HMA,					\$1,111,773.97	MORSE BROS., INC.	3/15/2004			
006721																										
Southwest																										
006722				THIS CONTRACT NUMBER NOT USED												THIS CONTRACT NUMBER NOT USED										
03Y011	P1, P3	State Project	97	MP 62.02 to MP 69.09	Yakima	NL										THIS PROJECT CONSISTS OF INSTALLING NEW CATCH BASINS, LOWERING EXISTING CATCH BASINS, GRINDING TO PROMOTE DRAINAGE, TRENCHING, STORM SEWER PIPE INSTALLATION, PATCHING WITH ASPHALT CONCRETE PAVEMENT, TRAFFIC CONTROL, TRAFFIC SIGNAL LOOP					\$346,580.50	COLUMBIA ASPHALT &	4/12/2004			
006723				Toppenish to Wapato - Drainage																						
South Central																										
04W600	P3	FED	Architectu re	I 5 Scatter Creek Safety Rest Area Water Rehab	Thurston	NL										REPLACE EXISTING UNDERGROUND WATER SERVICE.					\$80,070.00					
006724																										
HQ																										
03A040	P3	STP 0542(020)	542	MP 15.30 Vicinity Truck Rd Vicinity Culvert Repl.	Whatcom	NL										REPLACEMENT OF EXISTING PIPE CULVERET BY OPEN cUTTING THE ROAD WAY AND INSTALLING PRECAST BOX CULVERT, RESTORATION OF ROADWAY, PAVING WITH ASPHALT CONCRETE CLASS B, RECONSTRUCTION OF EXISTING SLOPES, EROSION CONTROL AND PLANTING,					\$133,830.00	C W WILLIAMS	2/23/2004			
006725																										
Northwest																										