

1 (BSP June 11, 2003)  
2 The column(s) at the Bridge and Pier location(s) specified below has (have)  
3 received a waiver of the pre-fabrication field measuring requirement, and no  
4 separate waiver request from the Contractor is required for this (these) specific  
5 column(s):  
6  
7 \*\*\* \$\$1\$\$ \*\*\*  
8  
9 However, the Contractor shall conform to all other requirements specified above for  
10 columns receiving a waiver of the pre-fabrication field measuring requirement,  
11 including field measuring the above ground portion of the column, and submitting  
12 the method, template, and equipment used to field cut the column jacket assembly  
13 at the site to the Engineer for approval.