

1
2
3
4
5

(BSP August 4, 2003)

For the prestressed girders of ***\$1\$***, the Contractor may substitute compressive strength testing at 28 days provided that the 28 day compressive strength is equal to or greater than 95 percent of the required 56 day compressive strength.