

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11

(BSP August 4, 2003)

The first paragraph of Section 6-02.3(25)M is revised to read as follows:

After the girder has reached its 28-day design strength, or 95 percent of the 56 day design strength for the girders of \*\*\* ~~\$\$\$~~ ~~1\$~~ ~~\$~~ ~~\*\*\*~~, and the fabricator believes it to comply with the specification, the girder and a completed Certification of Compliance, signed by a Precast/Prestressed Concrete Institute Technician or a professional engineer, acceptable to the Contracting Agency, shall be submitted to the Engineer for inspection. If the Engineer finds the certification and the girder to be acceptable, the Engineer will stamp the girder "Approved for Shipment".