1 (BSP December 5, 2005) 2 "Prestressed Conc. Girder _____", per meter. 3 The unit contract price per meter for "Prestressed Conc. Girder" shall be full pay 4 for performing the work as specified, including shop drawing submittals, fabrication, 5 storage, handling, shipping, erection, furnishing and removing oak block wedges, 6 furnishing and removing temporary bracing, and furnishing and cutting temporary 7 strands. For deck bulb tee girders and PCPS members, all work related to equalizing 8 girder camber, connecting weld-ties, and grouting keyways, shall also be included. For 9 spliced prestressed concrete girders, all work related to cast-in-place concrete closures and post-tensioning shall be included. Payment will be made based on the quantity 10 11 specified in the Proposal, unless changes are made to this quantity in accordance with 12 Section 1-04.4, in which case the quantity specified in the Proposal will be adjusted by the amount of the change and will be paid for in accordance with Section 1-04.4. 13