

1 **(BSP December 2, 2002)**

2 **Checking Polyester Concrete For Bond**

3 After the requirements for curing have been met, the entire overlaid surface shall
4 be sounded by the Contractor, in a manner approved by and in the presence of the
5 Engineer, to ensure total bond of the concrete to the bridge deck. Polyester
6 concrete in unbonded areas shall be removed and replaced with polyester concrete
7 by the Contractor, at no additional expense to the Contracting Agency.

8
9 All cracks, except those that are significant enough to require removal as
10 determined by the Engineer, shall be thoroughly filled and sealed with HMWM
11 resin. Cracks 1/16 inch and greater in width shall receive two applications of
12 HMWM resin. Immediately following the application of HMWM resin, the wetted
13 surface shall be coated with sand for abrasive finish.