Accelerated Bridge Design Using Performance Specifications (Mile Bridge) & Accelerated Construction

Presenters:
Raymond Mabey, PE
Brian Bierwagen, PE, PMP






Original Design Bid Build Project

Hwy 26: Zigzag to Rhododendron
Phase II Project
Mt. Hood Highway

DBB to Construct Three Structures

- Zigzag River Bridge replacement with 250' long steel plate girders
- Bear Creek Woodlands Access Bridge new 30' long steel beam
- Variable message sign bridge first cantilever truss sign bridge in the state

Zigzag – Rhododendron, Phase 2



Zigzag River Bridge



Bear Creek (Woodlands) Bridge



Variable Message Sign Bridge




Work Added Late in Project


Three Weeks Prior to Completion of PS&E for Zigzag – Rhododendron, Phase 2 Design Bid Build project

- Zigzag River (Mile Bridge) was added
- Pedestrian bridge added
- Mile Bridge project was expanded from two to three lanes

Mile Bridge Added to DBB Project




Mile Bridge Simulations




Pedestrian and Mile Bridge



Schedule Comparison



Mt. Hood to Chemult Bridges DB



Why Add This Work

- Located 2 Miles from the DBB Project
- Hwy 26 provides a parallel freight and emergency route to I-84
- Replaced substandard bridge to satisfy OTIA III
 Stage 1 capacity requirements
- Design resources and schedule were not available to meet construction Ad date
- Innovative project delivery method

Project Challenges

- Adding construction work to a project
 3 weeks prior to when Final Bid
 Documents were to be completed
- Selecting a Contractor and DB team as part of the traditional DBB Project



Selection of Contractor & DB Team

- One contractor was selected for both
 DBB and DB components using a traditional Low Bid Process
- Did not include a Best Value component
- Parametrix was selected by Contractor based on Technical and Design Build experience
- One Performance Specification defined a list of Bid Items for design and construction of DB work

Performance Specification

Provided the Program Requirements

- Applicable design codes
- Performance parameters (loading, design speed, traffic volumes, etc.)
- Deliverables (list of required drawings and calculations)
- Quality Review Submittals



Meeting Program Requirements

Accelerated design schedule was met by

- Bridge was straightforward and low-risk to contractor with very few alternatives
- TS&L of Mile Bridge completed
- Technical studies/incidental tasks were in-progress or complete
- Contractor Designer collaboration provides efficiencies
- One major review by ODOT with verification submittals

Incidental Tasks Completed

- Survey
- Geotechnical / Hydraulics
- EnvironmentalPermits
 - Historical
 - Biological (Fish & Eagle)

- Public Outreach
- FHWACoordination
- UtilityCoordination
- Right-of-Way



Design Build Schedule Benefits

- Shifts design detailing to the contractor
- Allows design to reflect Contractor operations
- A portion of design work is moved to after contract award
- Allows some construction activities to proceed (survey, clearing and earthwork etc.)
 while design is finalized
- Obligates funds quicker increases project velocity

ODOT Quality Reviews

Performance Specification Required Review Submittals

- Plan review submittal requirements
 - First submittal 90%
 - ODOT approval of 90% plans
- Final submittal to ODOT
 - Incorporated ODOT's comments



Agency Perspective

- Less control than traditional design
- ODOT used the same construction
 management approach as conventional DBB
- Difficult to incorporate requested changes
- Cost effective contractor details not readily approved by ODOT

A Contractor's Perspective

- Overall process was very appealing
- Flexibility to design and construct details suited to the contractor
- Construction services roles and responsibilities were not properly defined
- Contractor needed more deviation from typical ODOT details

A Consultant's Perspective

- No construction services budget and no mechanism for additional funds
- Consultant at times was placed between opposing sides—ODOT requested changes and contractor's unwillingness to make them
- ODOT personnel had difficulty letting go of the normal role that they have on DBB projects
- During design, roles and responsibilities were not always clear

Lessons Learned

- Provide ODOT personnel a greater understanding of the unusual contracting mechanism
- Clearly define the roles and responsibilities of the agency/contractor/engineer in the Performance Specification
- On future projects, if ODOT requires the same level of detail, more time should be allocated for document preparation

ODOT's Future DB Low-Bid

Lessons Learned provides input to future Design Build Low-Bid Process

- To be used on \$1M to \$20M projects
 (signals, intersection improvements, widening)
- Regions can use the process to deliver projects themselves
- Risk analysis approach used to determine level of pre-work
- EOR information submitted with bid package
- Selection based strictly on low bid

Pedestrian and Mile Bridges



Mile Bridge



Questions?





ZIGZAG RIVER (MILE) BRIDGE #03026A

ZIGZAG - RHODODENDRON PHASE II SECTION MT. HOOD HIGHWAY (MP 46.02) CLACKAMAS COUNTY



Parametrix

