



Sauvie Island Bridge Arch Span

Multnomah County, Oregon



Presented by:

Ian Cannon, PE – Multnomah County

Eric Rau, PE – David Evans and Associates, Inc.

Project Team

- Owner and construction manager: **Multnomah County**
- Contracting agency: **Oregon Department of Transportation**
- Designer: **David Evans and Associates, Inc.**
- Architect: **H2L2**
- General contractor: **Max J. Kuney Co.**
- Steel fabricator: **Fought & Co.**
- Steel assembly sub: **Schneider Up**
- Load/transport/install sub: **Dix/Norsar**



Agenda

- Project background
- Replacement Bridge Design
- Steel Shop Fabrication
- Arch Assembly and Transportation
- Completed Construction
- Questions



Project Background

Presented by

Ian Cannon, Multnomah County

CONNECTING COMMERCE AND COMMUNITY

MULTNOMAH COUNTY
BRIDGES



Sauvie Island

- 24,000-acre island
- Bounded by the Columbia River, Willamette River and Multnomah Channel
- Existing bridge provides only vehicular access



Existing Sauvie Island Bridge

- Existing bridge constructed in 1950 and was the first bridge to the Island
- 14 spans, 1198' long
- Eligible for listing on National Register of Historic Places
- Carries local residential, agricultural, industrial and recreational traffic
- Vessel traffic in channel – pleasure craft to commercial vessels



Existing Sauvie Island Bridge

- After 50 years of life the existing bridges was functionally obsolete and structurally deficient
- David Evans and Associates (DEA) provided design services to Multnomah County
 - Completed an Alternative Study in 2002
 - DEA completed final design in 2005
- Contract awarded to Max J. Kuney Co. in 2005
 - Construction completed in 2008



Replacement Bridge

Presented by

Eric Rau, David Evans and Associates, Inc.



DAVID EVANS
AND ASSOCIATES INC.



Replacement Bridge

- 5 spans, 1177' long
- 365' steel tied arch main span
- Concrete box girder approach spans
- Large-diameter drilled shaft foundations



Approach Spans and Substructure Construction



Bridge Foundation

- Crossbeam on 2 Column/Shaft foundation at Pier Bents
- 10 feet Diameter Drilled Shafts
- Precast Column Base




Drilled Shaft Casing Installation



Approach Spans

- 4 Cast-in-place post-tensioned approach spans, 2 each side of channel
- Approximate span length of 200 ft
- Parabolic structure depth varies from 7'-6" to 11'-0" ft
- Variable width structure
- Horizontally Curved near Island



Rebar and Post-Tensioning Ducts for Box Girder



Steel Tied Arch Channel Span



Benefits of the Steel Tied Arch

- Aesthetically pleasing
- Shallow depth over channel
- SHPO – portion of structure above deck
- Reduced number of piers in channel
- Increased width of navigation opening
- Coast Guard – no falsework in channel, minimal disruption to navigation




Features of Tied Arch Design

- Two methods of steel erection allowed
 - Cantilever erection with temporary towers and stays
 - Assemble offsite and float in
- A709 Grade 50W weathering steel with portions painted for extra corrosion protection
- Tie girders designated fracture-critical
- Hanger cables in “radial” pattern
- Cast-in-place concrete roadway deck and sidewalks




Steel Design

- AASHTO LRFD
- Permit loadings per ODOT and Multnomah County
- Arch rib geometry – minimize bending and live load deflection
- Hanger cables – maintain tension
- Redundancy
 - Tie girder – loss of plate or flange
 - Hanger cables – loss of any one cable
- Fatigue
 - Floor beam connection – prevent web distortion



Arch Span - Typical Section



DATE	REVISION	BY	DRAWN
		J. Patton	
		Shann Mills	
		Clifford Coulter	

REVIEWED

REGISTERED PROFESSIONAL ENGINEER
 STATE OF OREGON
 EXPIRES: 12-31-07

DAVID EVANS AND ASSOCIATES INC.
 530 Center Street S.E., Suite 505
 Salem Oregon 97301
 Phone: 503 381 8636

MULTNOMAH COUNTY BRIDGES

TRANSPORTATION DIVISION


OREGON DEPARTMENT OF TRANSPORTATION
 BRIDGE ENGINEERING SECTION

BRIDGE NO. 20136	MULTNOMAH CHANNEL & PNWR ETC., SAUVIE ISLAND RD.
DATE Sept. 2005	
CALC. BOOK	
TYPICAL SECTION - SPAN 3	

SHEET 27 OF 173
DRAWING NO. 70214




Arch Span - Part Elevation




Tie Girders

- Tie girders designated fracture-critical
- Built-up steel box sections
- Connected by bolted corner angles
- No welding
- Designed for fracture of a web or flange plate – special Extreme Event load combination



Arch Ribs

- Welded steel box sections with bolted splices
- Geometry to minimize bending and live load deflection
- Shape driven by cable pattern behavior
- Sensitivity of cable forces to arch geometry



Hanger Cable Systems

Vertical cables

- Simplicity

Cross cables

- Reduction in deflections and moments

Radial cables

- Aesthetics



Vertical cables



Cross cables (network)





Radial cables




Hanger Cables

- Radial cable pattern - aesthetics
- 2-1/2" diameter structural strand
- ASTM A 586 Class A zinc coating
- Stressing from lower connection
- Installation sequence to maintain cables in tension under all loadings
- Designed for loss of any one cable



Floor System

- Longitudinal stringers – composite rolled sections
- Floor beams – composite welded plate girders located at hanger supports
- Shallow depth – stringers frame into floor beams with moment connections



Lateral Bracing

- Bottom lateral bracing – WT sections in a “K” pattern
- Top lateral bracing – aesthetics
 - Variable depth “I” sections in a diamond pattern
 - Web cutouts




Arch ribs and top lateral bracing



Top lateral brace section




Corrosion Protection



- Project goal – minimize maintenance
 - Weathering steel
- Corrosion protection
 - Paint critical locations
 - Provide drains and vents in box sections
 - Caulk critical locations
 - Galvanized hanger cables, sockets, stirrup rods, and pins



Global Analysis





- Performed using RM2000
- Construction stage analysis
- Live load, wind, thermal and seismic



Local Analysis



- Detailed finite element analysis of arch knuckle
- Performed using ABAQUS



Structure Data

- Bridge costs: \$26,400,000 including removal and temporary works
- Main span: 365 feet
- Steel tonnage: 1250 tons
- Steel weight: 102 lbs per sq. ft. of deck
- Arch rib
 - Span to rise ratio = 4.7
 - Span to depth ratio = 76 (based on access req'ts)
- Tie girder
 - Span to depth ratio = 63



Shop Fabrication



Fought & Company



Knuckle Fabrication



Arch Assembly & Transportation

Presented by

Ian Cannon, Multnomah County



Setting Tie Girder Section



Setting Girder on Timber Cribbing



First Arch Rib Sections



03/27/2007 15:20



Arch Rib Sections and Bracing



Arch Ribs and Support Struts



Assembling Arch Rib Splice



Arch System Nearing Completion



Erecting Arch Rib Closure Piece





04/27/2007 13:32




Load-out and Jack-up Process

- The following slides are used by permission from Norsar, LLC, Everett, WA
- Process to move erected arch about 8 miles from Port of Portland Terminal 2 to Sauvie Island.



Load-out

- Skid forward until over dolly truss, then transfer load




Skidding Equipment in Use



Dolly Equipment




Loaded out



Shoring and Jacking frame



Jack-up



Transportation to Island



Departure From Terminal 2



Leaving Portland



Nearing Bridge Site



Positioning into Final Location



Lowering onto Bents



Completed Structure

