



Arizona Department of Transportation


# Emergency Rehabilitation of I-10 Mescal Road TI UP

Navaphan Viboolmate, PE  
ADOT Bridge Group Design Section Leader

# Arizona Fire Damaged Bridges in the last 15 years

- I-10 Oglesby Road Ramp C UP in 1998
- SR 260 Gordon Canyon Bridge in 1998
- I-15 Virgin River BR #7 in 2001
- SR 87 Slate Creek RCB in 2003 and 2007
- I-10 335<sup>th</sup> Ave UP in 2006
- I-17 Union Hills Drive TI OP in 2006
- I-10 Hassayampa River Bridge EB in 2008
- SR 95 Bill Williams River Bridge in 2006
- I-10 Mescal Road TI UP in 2011

# State Milepost System



**I-15 Virgin River BR # 7**

**SR 95 Bill Williams River Bridge**

**SR 260 Gordon Canyon Bridge**

**I-17 Union Hills Drive TI OP**

**SR 87 Slate Creek RCB**

**I-10 355<sup>th</sup> Ave UP**

**I-10 Hassayampa River Bridge EB**

**I-10 Oglessby Road Ramp**

**I-10 Mescal Road TI UP  
MP 297.17**

# Mescal Road TI UP Background

- Built 1959
  - 5- Span Steel Girder
- Barrier Replacement 1993
- Sidewalk Widening 2003
  - 6 ft. Sidewalk on the east side
- Heat Straightening Jan 2011

# Presentation Overview

- Damage Assessments
- Emergency Repairs
- Project Schedule
- Design
- Construction

# Fire Incident

- March 15, Approximate 11:00 pm
- Two semi-trucks collided under the bridge
- Magnesium fire lasted approximately 6 hours



# Special Damage Inspection

- Approximately 6" upward deflection at pier 1
- Approximately 2" Lateral deflection
- Concrete spalls from columns and pier cap















# Damage Assessments

- Material Properties
- Effects of heat residuals




Figure 2.1. Reduction of steel yield strength with temperature (Astaneh-Asl et al. 2009)




Figure 2.2. Reduction in concrete compressive strength with temperature (Astaneh-Asl et al. 2009)






Figure 2.3. Reduction in strength of prestressing steel and high strength alloy bars with temperature (Astaneh-Asl et al. 2009)




Figure 2.4. Reduction in strength of bolts, welds, reinforcing bars with temperature (Astaneh-Asl et al. 2009)

# Conclusions

- Steel Girders have to be replaced
- Replace all pier caps
- Replace columns at pier 1

# Emergency Repairs


- Install Temporary Concrete Barrier around the area
- Install Pedestrian Fence
- Set up a detour for locals
- Deck demolition
- Remove steel girders
- Remove south pier cap and columns






TO ACCOMPANY CHANGE ORDER NO. \_\_\_\_\_


PLANS	REVISED	PROJECT NO.	SHEET NO.	TOTAL SHEETS	DATE
3		610-0300N			
000 CH 300					



**TYPICAL FENCE ELEVATION**  
Scale:  $\frac{1}{4}$ " = 1'-0"



**SECTION 2**  
Scale:  $\frac{1}{4}$ " = 1'-0"



**FENCE MOUNTING DETAIL**  
Scale: 3" = 1'-0"

**CONCRETE ANCHOR NOTE:**


The concrete anchors shall have the capacity to develop tensile pullout strength of 8 kips minimum. Anchors shall be set at sufficient edge distance to avoid spalling or cracking of existing concrete.

DESIGNED BY L. M. BISHOP	CHECKED BY L. M. BISHOP	DATE 1-20-57	PROJECT NO. 610-0300N	SHEET NO. 3	TOTAL SHEETS 4
MEDICAL ROAD TIE UP FENCE DETAILS			MEDICAL ROAD TIE UP FENCE DETAILS		
TRACS NO. H 5804 GBC			610-0300N		
DATE 1-20-57			DRAWN BY CF		




TO ACCOMPANY CHANGE ORDER NO. \_\_\_\_\_


FIGURE NUMBER	DATE	PROJECT NO.	SHEET NO.	TOTAL SHEETS	AS BUILT
3		000-02000			
000 CH 300					




**PIER 1**  
Scale: 1/8" = 1'-0"



**PIER 2**  
Scale: 1/8" = 1'-0"



**PIER 3**  
Scale: 1/8" = 1'-0"



**PIER 4**  
Scale: 1/8" = 1'-0"

**DEMOLITION NOTES:**

Sawcut the existing concrete deck between the steel girders. Remove each existing steel girder along with the concrete deck and dispose off of the project site.

Temporary support may be required for all steel girders during demolition.

Damage to existing box beams, slabs, piers and I-10 resulting from the contractor's work shall be repaired at no additional cost to the Department.

**LEGEND:**

Limits of Removal

DESIGNED BY D. Woodruff SEP	CHECKED BY D. Park SEP	APPROVED BY D. Woodruff SEP	DATE 1-30 2017	PROJECT NO. 000-02000	SHEET NO. 000 CH 300	TOTAL SHEETS 1	AS BUILT
<p>1-30 2017 000-02000</p> <p>TRACS NO. H 8804 000</p>				<p>APPROVED BY THE DEPARTMENT OF TRANSPORTATION</p> <p>INTERSTATE 10 CORRIDOR PROJECT</p> <p>SECTION GROUP</p> <p>MISCAL ROAD T1 LP</p> <p>REMOVAL LIMITS</p>			
<p>1-30 2017 000-02000</p> <p>TRACS NO. H 8804 000</p>				<p>MISCAL ROAD T1 LP</p> <p>000-02000</p>		<p>SHEET 3-02 OF 2</p> <p>CF</p>	

Friday April 8, 2011 (24 days after the incident)
















# Project Schedule

- Design 4 weeks
- Bid advertisement April 2011
- Finish Construction by September 10, 2011

# Critical Path








# Design


- Precast-Prestressed Concrete Box Beam
  - Design spans 31', 55', 47', 55', and 28'
  - Initial Concrete Strength 4,500 psi
  - 28-day Concrete Strength 5,500 psi
  - Minimum strands = 12
  - Maximum strand = 18
  - Precast overhang and barrier Strength 4,500 psi

# Integral Overhang and Barrier

FED. ROAD DISTRICT	STATE	PROJECT NO.	SHEET NO.	TOTAL SHEETS	AS BUILT
9	NEV.	010-E1921A	40	50	
D10 CH 257					




Barrier Closure Pour at Continuous Pier  
Scale: 3/8" = 1'-0"



Barrier Closure Pour at Expansion Pier  
Scale: 3/8" = 1'-0"

Barrier Closure Pour at Abutment  
Scale: 3/8" = 1'-0"

Indicates f'c = 4,500psi



SECTION  
(Exterior Box Beam)  
Scale: 1" = 1'-0"

**THREADED INSERT NOTE:**

Inserts are Std. threaded with enclosed threads for 3/8 Dia. threaded rod (typ.) Inserts shall be ferrule loop type which develop an ultimate pullout strength of 10,800 lbs. The inserts shall be placed normal to the girder web.

**NOTES:**

- Lifting points for the precast box beams shall be determined by the precastor to account for additional barrier and deck overhang weight. Calculations shall be submitted as part of the shop drawing submittal.
- Special consideration shall be given during transportation and placement of the exterior girders due to additional weight.
- Precast Barrier Length = 199'-6"
- Cast-in-place Barrier = 22'-6"
- Precast Barrier and Cast-in-place Barrier are paid with Item No. 6011130 F-Shape Bridge Concrete Barrier & Transition (32')

MHC DRAWING				DATE	ARIZONA DEPARTMENT OF TRANSPORTATION INTERMODAL TRANSPORTATION DIVISION MULTIMODAL GROUP/TYPE	
DESIGN	L. Woodruff	CS-U				
DESIGN BY	L. Duff	GS-U				
DATE	L. Duff	GS-U				
PREP BY	L. Duff	GS-U				
APPROVED FOR DESIGN	L. Woodruff	GS-U				
APPROVED FOR CONSTRUCTION	L. Woodruff	GS-U				
F-10	297.JT	0517	05/07		MESCAL ROAD TI UP #0517	
PUBLIC	UNREVISED	STANDARD				
TRACS NO. H 8336 OIC					D10-E1211A	DWG. 5-01.25 OF 29
						OF

# Results

- Project advertisement April 29
- Bid opening May 11, Design Bid process
- Contract time 130 days
- Vastco, INC Low bidder \$956,000
- Royden Construction for Precastor Start June
- Construction Start July
- Construction Completed September

# Construction

- Began July
- Finished September





HIGHWAY TECHNOLOGIES

HIGHWAY TECHNOLOGIES















Mescal Rd TIUP #517 MP 297.17 9/7/11  
Looking North







Mescal Rd TIUP #517 MP 297.17 9/7/11  
Deck







A 3D grid of spheres on a blue background. The spheres are arranged in a regular, repeating pattern, creating a perspective effect that recedes into the distance. The background is a solid, dark blue color.

End

Question?

