

Snake River Bridge Load Test Addressing Bridge Management Issues WBES 2015 – Reno, NV

Brice Carpenter, P.E.

Bridge Diagnostics, Inc.
1995 57th Court North, Suite 100
Boulder, CO 80301
(303) 494-3230
bricec@bridgetest.com

Shanon Murgoitio, P.E.


Idaho Transportation Department
P.O. Box 7129 Boise, ID 80301
(208) 334-8547
Shanon.Murgoitio@itd.idaho.gov

Presentation Outline




1. Description of the Structure
2. Standard Load Rating Results
3. General Problem & Selected Resolution
4. Testing Plan Overview
5. Data Review & Model Creation
6. Model Calibration Results
7. Refined Load Rating Results
8. Project Conclusions

Snake River Bridge – Location



Snake River Bridge – Overall Details



Snake River Bridge – Initial Load Rating Results

Oregon DOT Rating (LRFR) Using BRASS Software

Vehicle	Vehicle Wt. (kips)	LRFR Legal Rating Factors	Controlling Member	Controlling Location	Controlling Limit State
ODOT Type 3	50	1.00	Steel Girder	Span 2 @ 0.35L	Positive Flexure
ODOT Type 3S2	80	0.73	Steel Girder	Span 2 @ 0.35L	Positive Flexure
ODOT Type 3-3	80	0.73	Steel Girder	Span 2 @ 0.35L	Positive Flexure

TD Rating (LFR) Using AASHTOWare Bridge Rating Software

Vehicle	Vehicle Wt. (kips)	LFR Operating Rating Factors	Controlling Member	Controlling Location	Controlling Limit State
Idaho Type 3	54	0.62	Steel Stringer	Span 4 @ 2.0	Negative Flexure
Idaho Type 3S2	79	0.69	Steel Stringer	Span 3 @ 2.0	Negative Flexure
Idaho Type 3-3	79	0.72	Steel Stringer	Span 2 @ 9.0	Negative Flexure



Snake River Bridge – General Problem & Resolution



Diagnostic Testing Overview

Testing Goal - To capture the overall structural behavior of the primary girders and floor system.


Key factors of testing plan:

- ❖ Recorded continuous data under a moving load
- ❖ Installed enough sensors to measure global structural behavior
- ❖ Applied large enough load to capture reliable readings


Instrumentation Plan Overview

The instrumentation plan included:


- 62 Strain Transducers
- 6 Rotation Sensors
- 1 Load Position Sensor



Overall Plan




Span 2 Plan



Cross-section near Bay Point




Instrumentation Details



Girder Flexure & Composite Action with Deck



Girder Rotations & Support Behavior





Stringer Flexure & Floor System Distribution



Bracing Forces & Distribution

Testing Plan Overview

- ❖ Single & double truck configurations
- ❖ Test vehicles were the only vehicle on the bridge
- ❖ Crossed the structure at 3-5 mph
- ❖ Symmetric load paths



Load Configurations Used





Test along Truck Path Y2



Setup of Tandem Double Truck Test

Data Quality Review

Girder Stress Reproducibility Plot





Bottom Flange Stress near Midspan



Response Behavior Review

Verification of Composite Behavior using gage pairs





Gage Pair on Girder – Showing composite action



Response Behavior Review

Verification of Composite Behavior using gage pairs





Partial composite action in Stringer



Response Behavior Review


Verification of Composite Behavior using gage pairs



Non-composite action in Stringer



Model Creation and Test Simulation



Plan View of Structure Model

Beam Section Properties

Properties	
E (Kips/in. ²)	29000.000
G (Kips/in. ²)	12609.000
I _x (in. ⁴)	561020.000
I _y (in. ⁴)	3572.300
J (in. ⁴)	30.453
C _w (in. ⁴)	OFF
Area (in. ²)	195.750
Orientation (deg)	0.00
Ecc (in.)	0.00
Wgt (Kips/in. ³)	2.836E-04

Manual Non-composite
Edit X-Section Deck Properties

Description: Girder_4

OK Cancel

Diagram dimensions: Total height 124.50, Flange thickness 20.00, Web height 62.25, Neutral Axis (N.A.) indicated.

Modeling of Members

SH52_Snooper (ft.)

Truck Definition Dialog

Axis	Weight (Kip)	Width (ft.)	Spacing (ft.)
1	30.820	7.250	0.00
2	18.217	7.250	25.917
3	18.221	7.250	4.580

Change Wheel Cancel OK

Diagram dimensions: Truck height 7.25, axle positions -10.310, -4.557, -4.580, total width 25.42.


Modeling of Test Load



Model Calibration – Response Comparisons



Initial Model Comparison Plot



Girder Bottom Stress near Midspan

Model Calibration Overview


Key optimization parameters:

- ❖ Composite action in the girders and stringers
- ❖ End restraint at the supports
- ❖ Continuity between spans
- ❖ Load distribution of the floor system
- ❖ Load distribution between girders

Model Calibration – Response Comparisons



Final Model Comparison Plot



Girder Bottom Stress near Midspan

Model Calibration – General Results

- ❖ Girder composite action with deck varied
 - Composite at midspan
 - Non-composite near the ends of the steel spans
 - Partially composite near and over the piers
- ❖ Varying composite action in the stringers but did not greatly effect the floor systems' distribution
- ❖ The bottom cross-bracing (at bay points) was found to play a large part in the girders' load distribution
- ❖ Friction based end-restraint behavior reduced the girder moments

Refined Load Rating Procedures

Once calibrated, the model was adjusted to ensure the reliability of all optimized model parameters.

- ❖ All girder and stringer elements were made fully non-composite with the deck
- ❖ The end-restraint at the supports was significantly reduced
- ❖ The slab stiffness was reduced

Once the model was adjusted:

- ❖ Structural responses were obtained from the adjusted model
- ❖ Member capacities were determined from AASHTO LFD Standard Specifications

Refined Load Rating Procedures & Results

Load rating was performed on all stringer & girder elements using AASHTO LFR guidelines

RATING VEHICLE	LOCATION/LIMITING CAPACITY	INVENTORY RATING FACTOR	INVENTORY RATING WEIGHT, TONS	OPERATING RATING FACTOR	OPERATING RATING WEIGHT, TONS
HS-20	Girder Midspan / Positive Flexure	1.27	45.7	2.12	76.3
Idaho Type 3	Stringer / Positive Flexure	1.86	50.2	3.10	83.7
Idaho Type 3S2	Girder Midspan / Positive Flexure	1.50	59.3	2.50	98.8
Idaho Type 3-3	Girder Midspan / Positive Flexure	1.48	58.5	2.47	97.6
Idaho 121K	Girder Midspan / Positive Flexure	1.09	65.9	1.82	110.1
Idaho NRL	Girder Midspan / Positive Flexure	1.32	52.4	2.20	88.0



Testing Conclusions #1 - Girders


The distribution of live-load between the girders was **8 to 20 %** better than AASHTO distribution factors.

Structural conditions that influenced the actual load distribution included:

- ❖ The presence of the bay point bracing
- ❖ Wheel loads applied near the middle of the roadway reach the girders in a distributed fashion rather than as point loads



VS



Overall Conclusions - ITD

- ❖ ITD used BDI's findings and reanalyzed the structure internally
- ❖ POSTING REMOVED!
- ❖ User costs were not increased due to retrofit and the community's economy and fire response time was no longer hindered
- ❖ This case study shows how bridge owners used evaluation tools at their disposal to solve a bridge management problem

THANK YOU! QUESTIONS?

