



Faith Duncan, PE & Greg Hasbrouck, PE

# Replacing the Aging US 52 Mississippi River Bridge

*September 6, 2017*




# Project Overview

- US 52 / IL 64 over the Mississippi River
- Connecting Savanna, IL to Sabula, IA
- Illinois DOT Led Project
- Replacing Existing Cantilever Truss Bridge
  - 520 ft main span
- Proposed 546 ft Main Span Tied Arch
  - Bolted Box Tie Girder
  - Floating Deck
- Proposed “Coffercell” Footing Construction
  - Drilled Shafts
  - Waterline Footing



# Project Location



US 52 / IL 64 OVER THE MISSISSIPPI RIVER

**PARSONS**

# Aerial Views

- Sabula
- “Iowa’s only island city”
- Pop. 576



# Aerial Views

- “Savanna, Illinois a Sportsman’s Paradise”
- Pop. 2,945



# Mississippi Palisades



# BNSF Railroad

- Heavily used line
- 2 Tracks
- 60+ Trains per day
- Minimal closure windows
- Construction coordination required for river access



# Vital Transportation Link

- Low ADT – 2400
- Education, Emergency and Jobs
- Nearest alternate crossings
  - Clinton, IA to Fulton, IL – 20 miles south
  - Dubuque, IA to East Dubuque, IL – 45 miles north





# Existing Bridge

- Constructed in 1932
- Savanna-Sabula Bridge Company
- Private Toll Bridge before being turned over to Iowa
- Illinois took over jurisdiction in 1987



# Existing Bridge



- 947 ft Iowa Approach
- 282 ft Simple Span Truss
- 1,160 ft Cantilever Truss
- 520 ft main span
- 78 ft Illinois Approach
- 2,468 ft in total length

# Existing Bridge



# Repairs

- Major repairs in 1985
- Minor repairs in 1999
- Partial replacement of steel grid deck in 2008
  - 28 day road closure and \$2.9M
  - Major out cry from public
- Identified more repairs in 2009
  - \$8M repairs + \$8M user cost
  - 9 month closure, 37 mile detour
- Future repairs?




# Key Issues

- **Structurally Deficient**
  - Entire Iowa approach substructure
  - Repairs needed for truss spans
  - Weight Limit
- **Functionally Obsolete**
  - 2 narrow 10 ft lanes
  - Trucks encroach into lane
  - Tight turning radius
  - Steel grid deck
- **Remaining Service Life**
  - 8 to 10 years in current state



# Replacement


- **District Recommended Replacement**
  - Substandard Roadway
  - Extensive Environmental Coordination
  - Economic Impact of Closure
  - Future Maintenance and Closures
- **New Structure**
  - Parallel alignment – keep existing open
  - 40 ft clear roadway – improve geometrics



# Environmental

Exhibit 4-1  
US 52/IL 64 Over The Mississippi River

## ENVIRONMENTAL FEATURES




# Constraints

- Iowa Causeway
  - Minimize Environmental Impacts
  - Minimize Causeway Construction
- Illinois Intersection
  - Between bluff and railroad
  - Minimal change to existing IL 84
  - Tie-in at highpoint
  - Limit ROW Impact
- Minimize grades to 4% if possible






# Navigation Clearance



- Maintain Existing Clearances
  - Channel near Illinois bank
  - Steep grade with existing tie-in (> 4%)
  - Minimal Superstructure Depth

# Navigation Channel Shift



- Approach USCG with Channel Shift
  - Proposed 200 ft shift to west
  - Agreed to 150 ft shift to west
  - Maintain 350 ft channel during construction
  - 7.5 ft superstructure depth and 4% max grade

# Bridge Type Study

- Evaluated 3 Types – Tied Arch, Cable-stayed, Plate Girder



# Bridge Type Study Evaluation

## Criteria

- Initial Cost
- Inspection & Maintenance
- Aesthetics
- Durability
- Constructability
- Environmental Impacts
- Structure Depth
- Geotech
- Hydraulics
- Future Widening

## Results


- Tied Arch
  - Float-in Erection
  - Replaceable Deck
- Cable-stayed
  - Not fracture critical
- Similar costs
- Selected Tied Arch
  - Less length of complex structure
  - IDOT familiarity

# Preliminary Design Development

- Advance Structural Decisions before Final Design
  - Vessel Collision Study
  - Approved Design Criteria
  - Optimized Span Layout / Pier Locations
  - Foundation Type Study
- Tied Arch Concepts Advanced
  - Sections defined and sized (H, I, Box)
  - Floor beam sized and spacing optimized
  - Hanger arrangement and spacing
  - Floating deck concept advanced
  - Stringer fixities defined
- Final Design completed in 12 months to meet schedule


# Proposed Structure

8-span Steel Plate Girder = 1420 ft




546 ft Tied Arch

3-span Steel Plate Girder = 488 ft




# Tied Arch



- 546 ft span, 100 ft rise, span to rise ~ 5.5:1
- Floor Beam Spacing – 31'-9"


# Cross Section






# Floating Floor System

- Replaceable deck with 1 lane of traffic
- Stringers spanning over floor beams
  - Bearings at center span fixed
  - Elastomeric bearings elsewhere
  - Deck full length of span
  - Allows deck replacement half at a time
  - Deck connected to tie at center
- Lower lateral K bracing for wind
  - Braces floor beam at mid-span
- Galvanized floor system
  - Lengths under 60 ft
  - Corrosion protection




# Tie Girder and Lower Hanger

- Bolted Box Tie full length
  - Tab plates
  - 6 ft deep
  - HPS50W
- Hanger connection offset from Floor beam
  - Simplifies detailing
- Connection precompressed
- 4 anchor rods provide redundancy
- Shim plates for length adjustment



# Arch Rib and Upper Hanger

- Welded Box Rib
  - Longitudinal stiffener
  - 5 ft deep
- Hanger connection offset from bracing connection
  - Simplifies detailing
- Two hangers
  - minimize strand size
  - easier replacement
- Hanger connections bolted to rib



# Upper Bracing

- X-bracing chosen
  - Smaller members than Vierendeel
  - Tension & Compression only
  - More modern look than K-bracing
- HSS 16x16
  - Efficient member section
  - Consistent box section
- Galvanized
  - Corrosion protection on inside of box
  - Distinct contrast with blue rib
  - Low maintenance / impact to traffic




# Redundancy


- Tie Girder
  - HPS50W and bolted box provides internal member redundancy
  - Limits propagation of fracture
  - Still Fracture Critical
  - Designed for loss of tie web or flange plate
  - $1.25 DC + 1.5 DW + 1.3 (LL+IM)$ , 2 striped lanes
- Hangers
  - Two hangers per location
  - Loss of one hanger with fracture dynamic force (FDF)
  - Loss of both hangers without dynamic force
  - $1.1 DC + 1.35 DW + 0.75 (LL+IM) + 1.1 FDF$ , 2 striped lanes

# River Pier Foundations

- Minimal cost aesthetic enhancement for arch piers
- Rock close to surface in IL
- 130 ft of sand + on IA side
- Deep river pool
- Waterline footings



# Drilled Shaft with Coffercell




# Constructability Review

- **Provided IDOT a constructability review**
  - During preliminary design phase
- **Parsons Construction Group**
  - Experience in Large River Bridge Construction
  - Identified staging and access areas
  - Identified potential construction issues
- **Provided IDOT a contractor style estimate**
  - Preliminary and Final Design
  - Parsons construction estimating group



# 3D Printing Model for Public Communication

- In house capability for conveying signature or complex details



On client's desk!

# Construction

- Five Bids Received Sept. 18, 2015
- Winning Bid of \$80.6M from Kraemer N.A.
  - Steel Fabricator – Veritas
- Within 3.9% of Engineer's Estimate
- Cantilever Erection of Tied Arch
- New bridge open in November 2017



# Aerial June 2016




# Aerial June 2016



# Aerial June 2016



# Aerial June 2016



August 2016



August 2016



US 52 / IL 64 OVER THE MISSISSIPPI RIVER



August 2016



April 2017



April 2017



April 2017



US 52 / IL 64 OVER THE MISSISSIPPI RIVER

PARSONS

44

April 2017



US 52 / IL 64 OVER THE MISSISSIPPI RIVER

**PARSONS**

45

June 2017



US 52 / IL 64 OVER THE MISSISSIPPI RIVER

June 2017



June 2017





June 2017




US 52 / IL 64 OVER THE MISSISSIPPI RIVER

August 2017



# Summary

- Aging Bridge key to local economy
- Replace with Tied Arch
  - Improved geometrics
  - Replaceable deck
  - Provided redundancy for tension members
  - Waterline footing construction
- Keys to Success
  - Strong Community Support
  - Early Client Involvement
  - Preliminary Design Development
  - Contractor Constructability Review
  - Led to efficient Final Design phase





Questions?



**PARSONS**