

NOTES:

- 1. THIS PLAN IS USED IN CONJUNCTION WITH 2-LANE FREEWAY LEFT LANE CLOSURE, RIGHT SHOULDER SHIFT TRAFFIC CONTROL PLAN (PCMSs REPLACED WITH ONES SHOWN ON THIS PLAN).
- 2. SEE QUEUE WARNING SYSTEM (QWS) SPECIAL PROVISION OR RFP FOR DETAILS.
- 3. MODIFICATIONS TO PCMS MESSAGES SHALL BE ACCEPTED BY THE ENGINEER.
- 4. ADJUST QWS COMPONENTS LOCATION TO AVOID CONFLICTS WITH TRAFFIC CONTROL DEVICES, NARROW SHOULDERS, AND RAMPS. WHEN LOCATED BEHIND BARRIER/GUARDRAIL OR WITHIN LANE CLOSURE, TRANSVERSE TRAFFIC DRUMS OPTIONAL.
- 5. LOCATE PCMSs PER STANDARD SPECIFICATION 1-10.3(3)C. PCMS MAY BE PLACED ON OPPOSITE SHOULDER BUT AVOID RAMP GORES. MINIATURE PCMSs (~6'WIDE, 12+ INCH CHARACTERS) ALLOWED FOR ALL PCMSs.
- 6. IF SYSTEM FAILS, SEE "QUEUE WARNING SYSTEM FAILURE PROTOCOL" PROVISION.
- 7. IF TRAFFIC QUEUES REACH 5.5 MILES, PLACE ADDITIONAL PCMS AT 8± MILES. RELOCATE FARTHER BACK AS NEEDED TO REMAIN IN ADVANCE OF QUEUE. TRUCK-MOUNTED PCMS WITH 10+ INCH CHARACTERS ACCEPTABLE. TRANSVERSE TRAFFIC SAFETY DRUMS OPTIONAL. REMOVE PCMS WHEN DISSIPATING QUEUES ARE LESS THAN 5 MILES.

 ADDED PCMS MESSAGE: TRAFFIC BACKUPS PRESENT / SLOW TRAFFIC AHEAD
- 8. "ROADWAY NARROWS 12' WIDE" PCMS MESSAGE MODIFIED TO MATCH THE ACTUAL MINIMUM TRAVEL WIDTH AVAILABLE THROUGH WORK ZONE MEASURED FROM FACE OF DEVICE TO FACE OF OPPOSITE DEVICE TRANSVERSELY.


LEGEND:	
•	28" TRAFFIC CONE
Ø	TRAFFIC SAFETY DRUM
#	TRAFFIC SENSOR
((•)	SMART SEQUENTIAL ARROW SIGN (CONNECTED)
PCMS	PORTABLE CHANGEABLE MESSAGE SIGN (SEE NOTE 5)

SYMBOL	TRIGGER SPEED (mph)	TRAFFIC CONDITION
FF	35+	Free Flow
SL	<35	Slowed

				- OL			Cic		·									
	QUEUE LOCATION			TRAFFIC SENSORS		PCM	IS 5	PCN	PCMS 4		PCMS 3		IS 2	PCMS 1				
				Е	D	С	В	Α	1	2	1	2	1	2	1	2	1	2
	(mi	les)	TR	AFFIC	CO	NDITI	ON	2.0 SEC	2.0 SEC	2.0 SEC	2.0 SEC	2.0 SEC	2.0 SEC	2.0 SEC	2.0 SEC	2.0 SEC	2.0 SEC
															LEFT	2	ROADWAY	SHOULDER
	No	one		FF	FF	FF	FF	FF		(Blank)		(Blank)		(Blank)	LANE	MILES	NARROWS	DRIVING
															CLOSURE	AHEAD	12' W I DE	AHEAD
													LANE	TRAFFIC	ROADWAY	SHOULDER	SLOW OR	NEXT
0.0)1]	ГО	0.9	FF	FF	FF	FF	SL		(Blank)		(Blank)	CLOSURE	BACKUPS	NARROWS	DRIVIVING	STOPPED	1
													3 MILES	PRESENT	12' WIDE	2 MILES	TRAFFIC	MILE
													LANE	TRAFFIC	SLOW OR	NEXT	ZIPPER	ROADWAY
0.9	91 7	ГО	1.9	FF	FF	FF	SL	SL		(Blank)		(Blank)	CLOSURE	BACKUPS	STOPPED	2	MERGE	NARROWS
									-				3 MILES	PRESENT	TRAFFIC	MILES	1 MILE	12' WIDE
											LANE	TRAFFIC	SLOW OR	NEXT	2 MILES	USE	ZIPPER	ROADWAY
1.9	91 7	ГО	2.9	FF	FF	SL	SL	SL		(Blank)	CLOSURE	BACKUPS	STOPPED	3	TO MERGE	ALL	MERGE	NARROWS
											4.5 MILES	PRESENT	TRAFFIC	MILES	POINT	LANES	1 MILE	12' WIDE
									LANE	TRAFFIC	SLOW OR	NEXT	3 MILES	USE	2 MILES	USE	ZIPPER	ROADWAY
2.9	91 7	ГО	4.4	FF	SL	SL	SL	SL	CLOSURE	BACKUPS	STOPPED	4.5	TO MERGE	ALL	TO MERGE	ALL	MERGE	NARROWS
									6 MILES	PRESENT	TRAFFIC	MILES	POINT	LANES	POINT	LANES	1 MILE	12' WIDE
									SLOW OR	NEXT	LANE	USE	3 MILES	USE	2 MILES	USE	ZIPPER	ROADWAY
	4.4	41+		SL	SL	SL	SL	SL	STOPPED	6	CLOSURE	ALL	TO MERGE	ALL	TO MERGE	ALL	MERGE	NARROWS
									TRAFFIC	MILES	4.5 MILES	LANES	POINT	LANES	POINT	LANES	1 MILE	12' W I DE

6-MILE QUEUE WARNING SYSTEM FREEWAY (2 LANES): SINGLE LEFT LANE CLOSURE, RIGHT SHOULDER SHIFT

									NOT TO SCALE			
FILE NAME	C:\Users\LintzF\OneDrive - W	ashIngton State Department of Transportation\Desktop\W	ork Zone TCF	Ps\153I	Fwy6Mll	eQWS1L	_tRlghtShldrShlft.dgn					Plot 1
TIME	1:10:37 PM				REGION NO.	STATE	FED.AID PROJ.NO.					PLAN REF NO
DATE	1/5/2024				10 \	WASH						TC153
PLOTTED BY	LintzF											
DESIGNED BY					JOB NU	MBER				Washington State		SHEET
ENTERED BY												1 1
CHECKED BY					CONTRA	CT NO.	LOCATION NO.			Department of Transportation		OF OF
PROJ. ENGR.								DATE	DATE	-	TYPICAL TRAFFIC CONTROL PLANS	1 SHEETS
REGIONAL ADM		REVISION	DATE	BY				P.E. STAMP BOX	P.E. STAMP BOX			SHEETS



NOTES:

- 1. THIS PLAN IS USED IN CONJUNCTION WITH 2-LANE FREEWAY LEFT LANE CLOSURE, RIGHT SHOULDER SHIFT TRAFFIC CONTROL PLAN (PCMSs REPLACED WITH ONES SHOWN ON THIS PLAN).
- 2. SEE QUEUE WARNING SYSTEM (QWS) SPECIAL PROVISION OR RFP FOR DETAILS.
- 3. MODIFICATIONS TO PCMS MESSAGES SHALL BE ACCEPTED BY THE ENGINEER.
- 4. ADJUST QWS COMPONENTS LOCATION TO AVOID CONFLICTS WITH TRAFFIC CONTROL DEVICES, NARROW SHOULDERS, AND RAMPS. WHEN LOCATED BEHIND BARRIER/GUARDRAIL OR WITHIN LANE CLOSURE, TRANSVERSE TRAFFIC DRUMS OPTIONAL.
- 5. LOCATE PCMSs PER STANDARD SPECIFICATION 1-10.3(3)C. PCMS MAY BE PLACED ON OPPOSITE SHOULDER BUT AVOID RAMP GORES. MINIATURE PCMSs (~6'WIDE, 12+ INCH CHARACTERS) ALLOWED FOR ALL PCMSs.
- 6. IF SYSTEM FAILS, SEE "QUEUE WARNING SYSTEM FAILURE PROTOCOL" PROVISION.
- 7. IF TRAFFIC QUEUES REACH 5.5 MILES, PLACE ADDITIONAL PCMS AT 8± MILES. RELOCATE FARTHER BACK AS NEEDED TO REMAIN IN ADVANCE OF QUEUE. TRUCK-MOUNTED PCMS WITH 10+ INCH CHARACTERS ACCEPTABLE. TRANSVERSE TRAFFIC SAFETY DRUMS OPTIONAL. REMOVE PCMS WHEN DISSIPATING QUEUES ARE LESS THAN 5 MILES. ADDED PCMS MESSAGE: TRAFFIC BACKUPS PRESENT / SLOW TRAFFIC AHEAD
- 8. "ROADWAY NARROWS 12' WIDE" PCMS MESSAGE MODIFIED TO MATCH THE ACTUAL MINIMUM TRAVEL WIDTH AVAILABLE THROUGH WORK ZONE MEASURED FROM FACE OF DEVICE TO FACE OF OPPOSITE DEVICE TRANSVERSELY.

LEGEND:	
	28" TRAFFIC CONE
Ø	TRAFFIC SAFETY DRUM
#	TRAFFIC SENSOR
((•D)D	SMART SEQUENTIAL ARROW SIGN (CONNECTED)
PCMS	PORTABLE CHANGEABLE MESSAGE SIGN (SEE NOTE 5)

SYMBOL	TRIGGER SPEED (mph)	TRAFFIC CONDITION
FF	35+	Free Flow
SL	<35	Slowed

		ᇰᆫ		.JJ	3101	wcu										
LOCATION		TRAFFIC SENSORS					PCM	IS 5	PCN	IS 4	PCMS 3		PCMS 2		PCMS 1	
		EDCBA			1	2	1	2	1	2	1	2	1	2		
(miles)		TRAFFIC CONDITION			2.0 SEC 2.0 SEC		2.0 SEC	2.0 SEC	2.0 SEC	2.0 SEC	2.0 SEC	2.0 SEC	2.0 SEC	2.0 SEC		
	П												LEFT	2	ROADWAY	SHOULDEF
None		FF	FF	FF	FF	FF		(Blank)		(Blank)		(Blank)	LANE	MILES	NARROWS	DRIVING
							-		-		-		CLOSURE	AHEAD	12' WIDE	AHEAD
											LANE	TRAFFIC	ROADWAY	SHOULDER	SLOW OR	NEXT
0.01 TO 0).9	FF	FF	FF	FF	SL		(Blank)		(Blank)	CLOSURE	BACKUPS	NARROWS	DRIVIVING	STOPPED	1
							-		-		3 MILES	PRESENT	12' WIDE	2 MILES	TRAFFIC	MILE
	\neg										LANE	TRAFFIC	SLOW OR	NEXT	ZIPPER	ROADWAY
0.91 TO 1	1.9	FF	FF	FF	SL	SL		(Blank)		(Blank)	CLOSURE	BACKUPS	STOPPED	2	MERGE	NARROWS
							-		-		3 MILES	PRESENT	TRAFFIC	MILES	1 MILE	12' WIDE
	П								LANE	TRAFFIC	SLOW OR	NEXT	2 MILES	USE	ZIPPER	ROADWAY
1.91 TO 2	2.9	FF	FF	SL	SL	SL		(Blank)	CLOSURE	BACKUPS	STOPPED	3	TO MERGE	ALL	MERGE	NARROWS
							-		4.5 MILES	PRESENT	TRAFFIC	MILES	POINT	LANES	1 MILE	12' WIDE
	П						LANE	TRAFFIC	SLOW OR	NEXT	3 MILES	USE	2 MILES	USE	ZIPPER	ROADWAY
2.91 TO 4	1.4	FF	SL	SL	SL	SL	CLOSURE	BACKUPS	STOPPED	4.5	TO MERGE	ALL	TO MERGE	ALL	MERGE	NARROWS
							6 MILES	PRESENT	TRAFFIC	MILES	POINT	LANES	POINT	LANES	1 MILE	12' WIDE
							SLOW OR	NEXT	LANE	USE	3 MILES	USE	2 MILES	USE	ZIPPER	ROADWAY
4.41+		SL	SL	SL	SL	SL	STOPPED	6	CLOSURE	ALL	TO MERGE	ALL	TO MERGE	ALL	MERGE	NARROWS
							TRAFFIC	MILES	4.5 MILES	LANES	POINT	LANES	POINT	LANES	1 MILE	12' WIDE

6-MILE QUEUE WARNING SYSTEM FREEWAY (2 LANES): SINGLE LEFT LANE CLOSURE, RIGHT SHOULDER SHIFT NOT TO SCALE

FILE NAME	C:\Users\LintzF\OneDrive - Wa	ashIngton State Department of Transportation\Desktop\V	Vork Zone TCF	Ps\153Fwy6MlleQ\	VS1LtRightShidrShift.dgn					Plot 1
TIME	1:10:38 PM			REGION STA	FED.AID PROJ.NO.					PLAN REF NO
DATE	1/5/2024			10 WA	eu					TC153
PLOTTED BY	LintzF			10 WA	30					10133
DESIGNED BY				JOB NUMBER				Washington State		SHEET
ENTERED BY								,		1
CHECKED BY				CONTRACT N	D. LOCATION NO.			Department of Transportation		OF OF
PROJ. ENGR.						DATE	DATE	-	TYPICAL TRAFFIC CONTROL PLANS	1 SHEETS
REGIONAL ADM	,	REVISION	DATE	BY		P.E. STAMP BOX	P.E. STAMP BOX			SHEETS

WORK ZONE MICROSTATION CELLS: Updated work zone cells incorporated (January 2024).	DESIGNER NOTES:
WSDOT CAE automatically updates cell libraries on WSDOT and on-site consultant staff computers (no action needed); however, external users or off-site consultants must manually install them. For additional information email HQCAEHelpDesk@wsdot.wa.gov.	A. Region Transportation Operations will determine if and what queue mitigation system is needed using work zone traffic analysis (Traffic Manual 5-9). For additional information, see Traffic Manual 5-17 or Work Zone Traffic Control Fundamentals presentation.
Division 4 in WSDOT Plans Preparation Manual, Section 400.06(29), provides updated work zone cell library policy and information for PS&Es. See https://wsdot.wa.gov/engineering-standards/all-manuals-and-standards/manuals/plans-preparation-manual	B. These typical traffic control plans may be modified for site-specific situations and/or WSDOT Region Transportation Operations standard practices. Typical Traffic Control Plans are not "Standard Plans".
TYPICAL TCP USAGE EXPLANATION:	C. When used, include the following Queue Warning System General Special Provisions listed below: 1-10.3(3).OPT4.FR1 Specifications
Plot 1: Supplements Typical Traffic Control Plans TC234 and TC254 when 6-mile Queue Warning System utilized on 2-Lane Freeways.	1-10.4(2).OPT7.GR1 Measurement (Traffic Control as Bid Items) 1-10.5(2).OPT4.GR1 Payment
	D. If traffic queues regularly exceed 6 miles, this plan can be modified into a 8-mile or 9-mile queue warning system without needing additional PCMSs or traffic sensors. Contact State Work Zone Engineers for guidance at HQWorkZone@wsdot.wa.gov.
	E. Except for projects requiring them in the Provisions, Pan-Tilt-Cameras (PTZ Cameras) are optional and may be mounted on various PCMSs as desired. PTZ Cameras are used remotely by Agency to monitor incidents and queues.
	WARNING SYSTEM ANE CLOSURE, RIGHT SHOULDER SHIFT
	INFORMATIONAL USE ONLY
	DO NOT INCLUDE THIS SHEET IN CONTRACT PS&Es or TCP SUBMITTALs.
	DESIGNER GUIDANCE