







12. SINGLE FLAGGER (WITH RED FLAG/RED GLOW CONE FLASHLIGHT) MAY BE ADDED TO THE INTERSECTING ROADWAY APPROACH TO HELP GUIDE ALTERNATING & TURNING TRAFFIC.



ALTERNATING 1-LANE, 2-WAY TRAFFIC: FLAGGER-CONTROLLED + TEMP. RUMBLE STRIPS (HIGHWAYS, 40 MPH OR LESS)

NOT TO SCALE


FILE NAME C:\Users\LintzF\OneDrive - Washington State Department of Transportation\Desktop\Work Zone TCPS\422Hwy40-AKTrafficFlaggerRumbleStrips.dgn										Plot 2	
TIME	11:19:27 AM				REGION NO.	STATE	FED.AID PROJ.NO.			PLAN REF NO	
DATE	5/16/2025				10	WASH				TC422	
PLOTTED BY	LintzF				JOB NUMBER					SHEET	
DESIGNED BY										2	
ENTERED BY										OF	
CHECKED BY										4	
PROJ. ENGR.					CONTRACT NO.		LOCATION NO.			SHEETS	
REGIONAL ADM.											
		REVISION		DATE	BY						

RECOMMENDED SIGN SPACING = X (1)		
RURAL ROADS & URBAN ARTERIALS	35-40 MPH	350'±
RURAL ROADS & URBAN ARTERIALS RESIDENTIAL & BUSINESS DISTRICTS	25-30 MPH	200'± (2)
URBAN STREETS	25 MPH OR LESS	100'± (2)
(1) ALL SPACING MAY BE ADJUSTED TO ACCOMMODATE INTERCHANGE RAMPS, AT-GRADE INTERSECTIONS AND DRIVEWAYS. (2) THIS SPACING MAY BE REDUCED IN URBAN AREAS TO FIT ROADWAY CONDITIONS.		


MAXIMUM CHANNELIZATION DEVICE SPACING (feet)		
MPH	TAPER	TANGENT
35 - 40	10-20	60
20 - 30	10-20	40

mPCMS	
1	2
FLAGGER 1 MILE AHEAD	WATCH 4 STOPPED TRAFFIC
2.0 SEC	2.0 SEC

FIELD LOCATE 1± MILE PRIOR TO FLAGGER OR PRIOR TO EXPECTED TRAFFIC QUEUE PER STD. SPEC. 1-10.3(3)C.



LEGEND:	
	TEMPORARY SIGN LOCATION
	28" REFLECTIVE TRAFFIC CONE (SEE NOTE 3)
	OPTIONAL CHANNELIZATION DEVICE
	PROTECTIVE VEHICLE
	FLAGGER
	TEMP. PORTABLE RUMBLE STRIPS (SEE NOTE 8)
	mini PORTABLE CHANGEABLE MESSAGE SIGN (PCMS OK, SEE NOTE 9)



SECTION A-A

ALTERNATING 1-LANE, 2-WAY TRAFFIC: FLAGGER-CONTROLLED (HIGH VOLUME HIGHWAYS, 40 MPH OR LESS)

NOT TO SCALE

NOTES:

- DISTANCE GREATER THAN 500' BETWEEN MAINLINE FLAGGERS REQUIRES ACCEPTANCE FROM REGION TRANSPORTATION OPERATIONS THRU THE ENGINEER. THIS ENHANCED PLAN IS APPLICABLE TO HIGH VOLUME HIGHWAYS WITH 800+ VEHICLES/HOUR IN ALL DIRECTIONS. WORK AREA LENGTH ADJUSTS ACCORDINGLY.
- FLAGGERS' GOAL IS TO MAXIMIZE TRAFFIC CAPACITY BY MINIMIZING TRAFFIC GAPS & LOST TIME. STRATEGIES:
(A) WAVE SLOWER DRIVERS THRU TO "CLOSE THE GAP"
(B) DON'T WAIT FOR APPROACHING TRAFFIC AFTER QUEUE RELEASED. LET THEM WAIT FOR THE NEXT TURN
(C) EFFECTIVELY USE 2-WAY RADIOS TO MINIMIZE LOST TIME WHEN CHANGING TRAFFIC RELEASE DIRECTIONS
- MAY SHIFT LATERALLY. 36" TRAFFIC CONES, 42" TALL CHANNELIZATION DEVICES, OR TRAFFIC SAFETY DRUMS OK.
- PEDESTRIAN & BICYCLIST ACCOMMODATIONS (ENGINEER TO ACCEPT ANY ALTERNATIVE STRATEGIES):
(A) ALLOW PEDESTRIANS TO USE THE PAVED SHOULDER OR ADJACENT PATH OPPOSITE THE WORK AREA
(B) COMBINE BIKES & VEHICULAR TRAFFIC. BIKES TO CLEAR PRIOR TO RELEASING ONCOMING TRAFFIC
(C) PROVIDE FREE SHUTTLE (WORK TRUCK, VAN, OR BUS MAY BE USED)
- SEE **STANDARD SPECIFICATIONS** FOR ADDITIONAL REQUIREMENTS:
1-07.8(1) HIGH-VISIBILITY APPAREL
1-10.3(1)A FLAGGERS AND NIGHTTIME ILLUMINATION
1-10.3(2)A TRAFFIC CONTROL PROCEDURES
9-35.1 24-INCH STOP/SLOW PADDLE SIZE
- FOR PROJECT-SPECIFIC REQUIREMENTS, SEE **SPECIAL PROVISIONS**.
- SIGNS ARE BLACK ON ORANGE UNLESS OTHERWISE INDICATED.
- AVOID PLACING TEMPORARY TRANSVERSE RUMBLE STRIPS WITHIN HORIZONTAL CURVES, ADJUST SIGN SPACING IF NEEDED. USE ONE OF THE FOLLOWING RUMBLE STRIPS:
* PSS Roadquake 2 Temporary Portable Rumble Strip (Black)
* PSS Roadquake 2F Temporary Portable Rumble Strip (Black)
- FULL-SIZE PCMS (11'x 6'DISPLAY) MAY BE USED IN LIEU OF mPCMSs. PCMS MESSAGES MAY BE MODIFIED.
- EXISTING PAVEMENT MARKINGS MAY VARY.

FILE NAME	C:\Users\LintzF\OneDrive - Washington State Department of Transportation\Desktop\Work Zone TCPs\422Hwy40-AltTrafficFlaggerRumbleStrips.dgn				FED.AID PROJ.NO.	
TIME	11:19:28 AM				REGION NO.	STATE
DATE	5/16/2025				10	WASH
PLOTTED BY	LintzF				JOB NUMBER	
DESIGNED BY					CONTRACT NO.	
ENTERED BY					LOCATION NO.	
CHECKED BY						
PROJ. ENGR.						
REGIONAL ADM.		REVISION	DATE	BY		

P.E. STAMP BOX

DATE

P.E. STAMP BOX

DATE



Washington State
Department of Transportation

TYPICAL TRAFFIC CONTROL PLANS

Plot 3

PLAN REF NO

TC422

SHEET





3

OF


4

SHEETS

14. FLAGGERS MAY COLLABORATE TO RELEASE APPROACH/ACCESS AND MAINLINE TRAFFIC TRAVELING IN THE SAME DIRECTION CONCURRENTLY.




**DETAIL NOT USED
FOR HIGH VOLUME CONFIGURATIONS**



ALTERNATING 1-LANE, 2-WAY TRAFFIC: FLAGGER-CONTROLLED (HIGH VOLUME HIGHWAYS, 40 MPH OR LESS)

NOT TO SCALE

FILE NAME C:\Users\LintzF\OneDrive - Washington State Department of Transportation\Desktop\Work Zone TCPs\422Hwy40-AktTrafficFlaggerRumbleStrips.dgn										Plot 4	
TIME	11:19:28 AM				REGION NO.	STATE	FED.AID PROJ.NO.			PLAN REF NO TC422	
DATE	5/16/2025				10	WASH					
PLOTTED BY	LintzF				JOB NUMBER		<div><div></div><div>Washington State Department of Transportation</div></div> <div>TYPICAL TRAFFIC CONTROL PLANS</div>				
DESIGNED BY											
ENTERED BY											
CHECKED BY											
PROJ. ENGR.					CONTRACT NO.		LOCATION NO.			SHEET 4 OF 4 SHEETS	
REGIONAL ADM.											
		REVISION	DATE	BY							

WORK ZONE MICROSTATION CELLS: Updated work zone cells incorporated (April 2024).

WSDOT CAE automatically updates cell libraries on WSDOT and on-site consultant staff computers (no action needed); however, external users or off-site consultants must manually install them. For additional information e-mail HQCAEHlpDesk@wsdot.wa.gov.

Division 4 in WSDOT Plans Preparation Manual, Section 400.06(29), provides updated work zone cell library policy and information for PS&Es. See <https://wsdot.wa.gov/engineering-standards/all-manuals-and-standards/manuals/plans-preparation-manual>

TYPICAL TCP USAGE EXPLANATION:

Plot 1: Flagger-controlled 1-lane, 2-way alternating traffic on the mainline for 2-lane highways 40 mph or less with a shared bicycle-vehicle lane with portable temporary rumble strips in advance.

Plot 2: Details for intersecting roadways and driveway/business access for Plot 1.

Plot 3: Flagger-controlled 1-lane, 2-way alternating traffic on the mainline for 2-lane highways 40 mph or less with a shared bicycle-vehicle lane with portable temporary rumble strips in advance for high traffic volumes (800+ vehicles/hour in all directions) by minimizing the distance between mainline flaggers.

Plot 4: Details for intersecting roadways and driveway/business access for Plot 3.

Other Alternating Traffic TCPs (45+ mph): See Typical Traffic Control Plan Library (<https://wsdot.wa.gov/engineering-standards/all-manuals-and-standards/plan-sheet-library/work-zone-typical-traffic-control-plans-tcp>)

- * TC320s for flagger-controlled alternating traffic plans
- * TC330s for AFAD-controlled alternating traffic plans
- * TC340s for temporary signal-controlled alternating traffic plans
- * TC350s for traffic holds

If not published yet, they will be added in the future.

Other Alternating Traffic TCPs (40 mph or less): See Typical Traffic Control Plan Library (<https://wsdot.wa.gov/engineering-standards/all-manuals-and-standards/plan-sheet-library/work-zone-typical-traffic-control-plans-tcp>)

- * TC420s for other variations of flagger-controlled alternating traffic
- * TC430s for AFAD-controlled alternating traffic
- * TC440s for temporary signal-controlled alternating traffic plans
- * TC450s for traffic holds

If not published yet, they will be added in the future.

DESIGNER NOTES:

- A. Contact Region Transportation Operations to determine which Typical TCP(s) to utilize, as their are several variations available (or soon will be).
- B. These typical traffic control plans may be modified for site specific situations and/or WSDOT Region Transportation Operations standard practices. **Typical TCPs are not "Standard Plans".**
- C. **Do not use intermittent (old: "variable") regulatory work zone speed limit reductions for flagging or AFAD operations.** Instead, maintain the existing speed limit (or continuous regulatory work zone speed limit reduction, if applicable). See WSDOT Traffic Manual Section 5-18 and Executive Order E1060 regulatory speed limit reductions & advisory speed approval policy for work zones thru Region Transportation Operations.
- D. See MUTCD Table 6F-1 for additional temporary sign size information. Work zone signs are usually smaller than those used permanently.
- E. WAC 468-95-300 modifies MUTCD Table 6-1 "Recommended Advance Warning Sign Minimum Spacing". Sign spacing may be adjusted for field conditions based on engineering judgement. The Sign Spacing table is acceptable to use in Typical TCPs; however, site-specific traffic control plans should include actual sign spacing values (with Å) that have been verified in the field, on SR view, or via Google Maps.
- F. When positioned behind channelizing devices, temporary signs should be mounted at 5' minimum.
- G. For this Typical TCP, the work zone design speed is based on the existing posted speed limit for sign spacing, channelizing device spacing, buffer, and roll ahead distances.
- H. "Flagger tapers" are always 50'-100' per closed lane with 6 devices minimum (10'-20' spacing on the taper), regardless of the posted speed limit or lane width per MUTCD 6C.08, Paragraph 15. Never use "L" for these tapers.
- I. Channelization devices types may be modified (vertical panel channelizing devices prohibited). 28" reflective traffic cones are recommended on flagger-controlled alternating traffic (especially for access delineation to maintain visibility for turning motorists). 36" reflective traffic cones, 42" tall channelizing devices, or traffic safety drums may be used. Warning lights on channelizing devices is being phased out in Washington. Contact Region Transportation Operations for information regarding their standard practices.
- J. Maximum channelizing device spacing table for tangents is based on WAC 468-95-301 and may ALWAYS be reduced.
- K. Sequential arrow boards are prohibited at flagger tapers per WSDOT standard practice and per MUTCD Guidance TA-10.
- L. Per MUTCD Section 6C.06, longitudinal buffer spaces are optional. Using longitudinal buffer spaces listed in MUTCD Table 6C-2 is recommended as best practice when feasible, but may be adjusted based on engineering judgement. The Longitudinal Buffer Space table is acceptable in Typical TCPs; however, site-specific traffic control plans should include actual buffer distances that have been verified in the field, on SR view, or via Google Maps.
- M. The lateral buffer (transverse distance between open travel lanes and work area) is optional. No lateral buffer has been provided in these Typical TCPs due to the low speeds of alternating traffic. Actual work area limits may be modified.
- N. On roadways 40 mph or less, WSDOT best practice is to place a protective vehicle (PV) in the closed lane in advance of the work area with a full longitudinal buffer space to provide errant vehicles an opportunity to stop before impacting the PV. On roadways 40 mph or less, the longitudinal buffer is optional and may be eliminated (still okay to use PV, upgrading to transportable attenuator is not required). Additional PVs (or TAs) may be added prior to multiple work crews within a work area. Contact Region Transportation Operations for their standard practice.
- O. Placing channelizing devices transversely (at 45° and 5-foot spacing) is an optional strategy to stop move errant drivers traveling within the closed lane(s) but is not shown in the Typical TCP.
- P. The downstream taper of 50'-100' is required on 1-lane, 2-way traffic configurations.
- Q. Duration of traffic holds for driveways, business accesses, and/or roadway approaches is listed as 5 minutes (1 minute on high volume highways) in this Typical Traffic Control Plan, but may be adjusted. Contact Region Transportation Operations for additional guidance.
- R. When utilizing temporary portable transverse rumble strips in Contracts, include the following General Special Provisions for Materials, Specification, Measurement, and Payment. <https://wsdot.wa.gov/publications/fulltext/projectdev/gspspdf/egsp1.pdf>
- * 1-10.2(9-35).OPT1.GR1 (Temp Rumble Strip Materials GSP)
 - * 1-10.3(3).OPT5.GR1 (Temp Rumble Strip Specifications GSP)
 - * 1-10.4(2).OPT8.GR1 (Temp Rumble Strip Measurement GSP)
 - * 1-10.5(2).OPT6.GR1 (Temp Rumble Strip Payment GSP)

ALTERNATING 1-LANE, 2-WAY TRAFFIC: FLAGGER-CONTROLLED + TEMP. RUMBLE STRIPS (HIGHWAYS, 40 MPH OR LESS)

	INFORMATIONAL USE ONLY	Plot 5
	DO NOT INCLUDE THIS SHEET IN CONTRACT PS&Es or TCP SUBMITTALS.	TC422
	DESIGNER GUIDANCE	