





<u>STOP CONDITION</u>	<u>SLOW CONDITION</u>	<u>TRANSITION TO STOP</u>
 <p><b>SOLID RED</b> 12" LENS ILLUMINATED</p> <p>DULL BLACK SIGNAL BACKPLATE</p>	 <p><b>FLASHING YELLOW</b> 12" LENS ILLUMINATED</p>	 <p><b>SOLID YELLOW</b> 12" LENS ILLUMINATED FOR 5 SECONDS</p>




**AFAD RED/YELLOW LENS DETAIL**



<p><b>PROTECTIVE VEHICLE ROLL AHEAD DISTANCE = R</b></p> <p>STRATEGICALLY POSITION WORK VEHICLE TO PROTECT WORK CREW. 40' - 80' RECOMMENDED.</p>
--

MAXIMUM CHANNELIZATION DEVICE SPACING (feet)		
MPH	TAPER	TANGENT
35 - 40	10 to 20	60
20 - 30	10 to 20	40








OPTIONAL LONGITUDINAL BUFFER SPACE = B					
SPEED (MPH)	20	25	30	35	40
B (feet)	115	155	200	250	305
Buffer space may be adjusted (±) based on field conditions.					




- NOTES:**
1. AVOID PLACING LANE CLOSURE TAPERS WITHIN OR IMMEDIATELY FOLLOWING HORIZONTAL & VERTICAL CURVE BY ADJUSTING LONGITUDINAL BUFFER SPACE.
  2. **PROTECTIVE VEHICLE MAY ALWAYS BE USED ON ROADWAYS 40 MPH OR LESS, EVEN IF THE LONGITUDINAL BUFFER SPACE IS REDUCED OR ELIMINATED.** ADDITIONAL PVs MAY BE ADDED AT SEPARATE WORK CREWS.
  3. MAY SHIFT Laterally. 36" TRAFFIC CONES, 42" TALL CHANNELIZATION DEVICES, OR TRAFFIC SAFETY DRUMS OK.
  4. PEDESTRIAN & BICYCLIST ACCOMMODATIONS (ENGINEER TO ACCEPT ANY ALTERNATIVE STRATEGIES):
    - (A) ALLOW PEDESTRIANS TO USE THE PAVED SHOULDER OR ADJACENT PATH OPPOSITE THE WORK AREA
    - (B) COMBINE BIKES & VEHICULAR TRAFFIC. BIKES TO CLEAR PRIOR TO RELEASING ONCOMING TRAFFIC
    - (C) PROVIDE FREE SHUTTLE (WORK TRUCK, VAN, OR BUS MAY BE USED)
  5. SEE STANDARD SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS:


1-07.8(1)	HIGH-VISIBILITY APPAREL
1-10.3(1)A	FLAGGERS AND NIGHTTIME ILLUMINATION
1-10.3(2)A	TRAFFIC CONTROL PROCEDURES
9-35.1	24-INCH STOP/SLOW PADDLE SIZE
  6. FOR PROJECT-SPECIFIC REQUIREMENTS, SEE SPECIAL PROVISIONS.
  7. SIGNS ARE BLACK ON ORANGE UNLESS OTHERWISE INDICATED.
  8. EACH AFAD OPERATED BY AFAD-TRAINED FLAGGER WHO VISUALLY SEES BOTH AFAD AND APPROACHING TRAFFIC (DIGITAL ALTERNATIVES OK). LEAVING AFAD UNATTENDED WHEN IN OPERATION IS PROHIBITED.
  9. AFAD GATE ARM DESCENDS AFTER RED LENS DISPLAYED & SHALL REACH HALFWAY ACROSS THE CONTROLLED LANE AND ASCENDS TO UPRIGHT POSITION ON FLASHING YELLOW LENS DISPLAY.
  10. AVOID PLACING TEMPORARY TRANVERSE RUMBLE STRIPS WITHIN HORIZONTAL CURVES, ADJUST SIGN SPACING IF NEEDED. USE ONE OF THE FOLLOWING RUMBLE STRIPS:

* PSS Roadquake 2 or 2F Temporary Portable Rumble Strip (Black)
* TrafFlx Alert High Speed Rumble Strip (Black)
  11. EXISTING PAVEMENT MARKINGS MAY VARY.

<b>LEGEND:</b>	
	TEMPORARY SIGN LOCATION
	28" REFLECTIVE TRAFFIC CONE (SEE NOTE 3)
	OPTIONAL CHANNELIZATION DEVICE
	PROTECTIVE VEHICLE (SEE NOTE 2)
	AUTOMATED FLAGGER ASSISTANCE DEVICE (SEE NOTES 8 & 9)
	FLAGGER (SEE NOTE 8)
	TEMP. PORTABLE RUMBLE STRIPS (SEE NOTE 10)









**ALTERNATING 1-LANE, 2-WAY TRAFFIC: AFAD-CONTROLLED + TEMPORARY RUMBLE STRIPS**  
**(HIGHWAYS, 40 MPH OR LESS)**  
 NOT TO SCALE

FILE NAME C:\Users\LintzF\OneDrive - Washington State Department of Transportation\Desktop\Work Zone TCPs\432Hwy40-AltTrafficAFAD\RumbleStrips.dgn				REGION NO.		STATE		FED.AID PROJ.NO.		 <p>Washington State Department of Transportation</p>	<div>Plot 1</div> <div>PLAN REF N</div> <div>TC432</div> <div> <div>SHEET</div> <div>1</div> <div>OF</div> <div>4</div> <div>SHEETS</div> </div>
TIME 7:00:01 AM				10		WASH					
DATE 7/18/2023				JOB NUMBER		LOCATION NO.					
PLOTTED BY LintzF				CONTRACT NO.				TYPICAL TRAFFIC CONTROL PLANS			
DESIGNED BY											
ENTERED BY											
CHECKED BY											
PROJ. ENGR.											
REGIONAL ADM.				REVISION		DATE		BY			




14. SINGLE FLAGGER (WITH RED FLAG/RED GLOW CONE FLASHLIGHT) MAY BE ADDED TO THE INTERSECTING ROADWAY APPROACH TO HELP GUIDE ALTERNATING & TURNING TRAFFIC.



## ALTERNATING 1-LANE, 2-WAY TRAFFIC: AFAD-CONTROLLED + TEMP. RUMBLE STRIPS (HIGHWAYS, 40 MPH OR LESS)

**NOT TO SCALE**



FILE NAME C:\Users\LintzF\OneDrive - Washington State Department of Transportation\Desktop\Work Zone TCPs\432Hwy40-AltTrafficAFADRRumbleStrips.dgn										Plot 2	
TIME 7:00:02 AM						REGION NO.		STATE		FED.AID PROJ.NO.	
DATE 7/18/2023						10		WASH			
PLOTTED BY LintzF						JOB NUMBER					
DESIGNED BY											
ENTERED BY											
CHECKED BY						CONTRACT NO.				LOCATION NO.	
PROJ. ENGR.											
REGIONAL ADM.		REVISION		DATE		BY					
<div style="display: flex; justify-content: space-around; align-items: center;"> <div style="text-align: center;">  <p><b>Washington State Department of Transportation</b></p> </div> <div style="text-align: center;"> <p><b>TYPICAL TRAFFIC CONTROL PLANS</b></p> </div> </div>										<div style="text-align: center;"> <p>PLAN REF NO</p> <p><b>TC432</b></p> </div> <div style="text-align: center;"> <p>SHEET <b>2</b> OF <b>4</b> SHEETS</p> </div>	







16. FLAGGERS MAY COLLABORATE TO RELEASE APPROACH/ACCESS AND MAINLINE TRAFFIC TRAVELING IN THE SAME DIRECTION CONCURRENTLY.









FILE NAME	C:\Users\LintzF\OneDrive - Washington State Department of Transportation\Desktop\Work Zone TCPs\432Hwy40-AltTrafficAFADRumbleStrIPS.dgn						
TIME	7:00:02 AM				REGION NO.	STATE	FED.AID PROJ.NO.
DATE	7/18/2023				10	WASH	
PLOTTED BY	LintzF				JOB NUMBER		LOCATION NO.
DESIGNED BY							
ENTERED BY							
CHECKED BY					CONTRACT NO.		
PROJ. ENGR.							
REGIONAL ADM.		REVISION	DATE	BY			








- NOTES:**
12. FOR LEGEND, TABLES, AND ADDITIONAL NOTES: SEE TC432, SHEET 1.
13. WORK MAY BRIEFLY OCCUR WITHIN LANE CLOSURE ACROSS INTERSECTING ROADWAY APPROACHES, BUSINESS ACCESSES, OR DRIVEWAYS. **MAY HOLD APPROACH OR ACCESS TRAFFIC FOR 5 MINUTES OR LESS** (ENGINEER MAY ACCEPT HOLDS UP TO 10 MINUTES) WHILE RESTRICTING TURNS FROM MAINLINE. CHANNELIZATION DEVICES DELINEATING APPROACH OR ACCESS MAY BE REMOVED OR RELOCATED AS NEEDED.
14. SINGLE FLAGGER (WITH RED FLAG/RED GLOW CONE FLASHLIGHT) MAY BE ADDED TO THE INTERSECTING ROADWAY APPROACH TO HELP GUIDE ALTERNATING & TURNING TRAFFIC.



**ALTERNATING 1-LANE, 2-WAY TRAFFIC: AFAD-CONTROLLED + TEMP. RUMBLE STRIPS (HIGHWAYS, 40 MPH OR LESS)**  
NOT TO SCALE



FILE NAME C:\Users\LintzF\OneDrive - Washington State Department of Transportation\Desktop\Work Zone TCPs\432Hwy40-AltTrafficAFADRumbleStrips.dgn														 <b>Washington State</b> <b>Department of Transportation</b>		Plot 2 PLAN REF NO <b>TC432</b>	
TIME 7:00:03 AM								REGION NO. STATE		FED.AID PROJ.NO.							
DATE 7/18/2023								10 WASH									
PLOTTED BY LintzF										JOB NUMBER							
DESIGNED BY										CONTRACT NO.		LOCATION NO.					
ENTERED BY																	
CHECKED BY																	
PROJ. ENGR.																	
REGIONAL ADM.				REVISION		DATE		BY						DATE		P.E. STAMP BOX	
														DATE		P.E. STAMP BOX	
														<b>TYPICAL TRAFFIC CONTROL PLANS</b>		SHEET <b>2</b> OF <b>4</b> SHEETS	



RECOMMENDED SIGN SPACING = X (1)		
RURAL HIGHWAYS	60-65 MPH	800' ±
RURAL ROADS	45-55 MPH	500' ±



(1) ALL SPACING MAY BE ADJUSTED TO ACCOMMODATE INTERCHANGE RAMPs, AT-GRADE INTERSECTIONS AND DRIVEWAYS.

MAXIMUM CHANNELIZATION DEVICE SPACING (feet)	
MPH	TAPER TANGENT
50 - 65	10 80
45	10 60





mPCMS	
1	2
ROBO- FLAGGER AHEAD	WATCH 4 STOPPED TRAFFIC
2.0 SEC	2.0 SEC

FIELD LOCATE 1 ± MILE  
PRIOR TO AFAD OR PRIOR  
TO EXPECTED TRAFFIC  
QUEUE PER STD. SPEC.  
1-10.3(3)C.



- NOTES:**

1. DISTANCE GREATER THAN 500' BETWEEN MAINLINE FLAGGERS REQUIRES ACCEPTANCE FROM REGION TRANSPORTATION OPERATIONS. THIS ENHANCED PLAN IS APPLICABLE TO HIGH VOLUME HIGHWAYS WITH 800+ VEHICLES/HOUR IN ALL DIRECTIONS. WORK AREA LENGTH ADJUSTS ACCORDINGLY.
2. FLAGGERS' GOAL IS TO MAXIMIZE TRAFFIC CAPACITY BY MINIMIZING TRAFFIC GAPS & LOST TIME. STRATEGIES:  
(A) DON'T WAIT FOR APPROACHING TRAFFIC AFTER QUEUE RELEASED. LET THEM WAIT FOR THE NEXT TURN
3. MAY SHIFT Laterally. 36" Traffic Cones, 42" Tall Channelization Devices, OR Traffic Safety Drums OK.
4. PEDESTRIAN & BICYCLIST ACCOMMODATIONS (ENGINEER TO ACCEPT ANY ALTERNATIVE STRATEGIES):  
(A) ALLOW PEDESTRIANS TO USE THE PAVED SHOULDER OR ADJACENT PATH OPPOSITE THE WORK AREA  
(B) COMBINE BIKES & VEHICULAR TRAFFIC. BIKES TO CLEAR PRIOR TO RELEASING ONCOMING TRAFFIC  
(C) PROVIDE FREE SHUTTLE (WORK TRUCK, VAN, OR BUS MAY BE USED)
5. SEE STANDARD SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS:  
1-07.8(1) HIGH-VISIBILITY APPAREL  
1-10.3(1)A FLAGGERS AND NIGHTTIME ILLUMINATION  
1-10.3(2)A TRAFFIC CONTROL PROCEDURES  
9-35.1 24-INCH STOP/SLOW PADDLE SIZE
6. FOR PROJECT-SPECIFIC REQUIREMENTS, SEE SPECIAL PROVISIONS.
7. SIGNS ARE BLACK ON ORANGE UNLESS OTHERWISE INDICATED.
8. EACH AFAD OPERATED BY AFAD-TRAINED FLAGGER WHO VISUALLY SEES BOTH AFAD AND APPROACHING TRAFFIC (DIGITAL ALTERNATIVES OK). LEAVING AFAD UNATTENDED WHEN IN OPERATION IS PROHIBITED.
9. AFAD GATE ARM DESCENDS AFTER RED LENS DISPLAYED & SHALL REACH HALFWAY ACROSS THE CONTROLLED LANE AND ASCENDS TO UPRIGHT POSITION ON FLASHING YELLOW LENS DISPLAY.
10. AVOID PLACING TEMPORARY TRANVERSE RUMBLE STRIPS WITHIN HORIZONTAL CURVES, ADJUST SIGN SPACING IF NEEDED. USE ONE OF THE FOLLOWING RUMBLE STRIPS:  
\* PSS Roadquake 2 or 2F Temporary Portable Rumble Strip (Black)  
\* Traffix Alert High Speed Rumble Strip (Black)
11. FULL-SIZE PCMS (11'x 6' DISPLAY) MAY BE USED IN LIEU OF mPCMSs. PCMS MESSAGES MAY BE MODIFIED.
12. EXISTING PAVEMENT MARKINGS MAY VARY.



SECTION **A-A**

11. FULL-SIZE PCMS (11'x 6'DISPLAY) MAY BE USED IN LIEU OF mPCMSs. PCMS MESSAGES MAY BE M

12. EXISTING PAVEMENT MARKINGS MAY VARY.

**ALTERNATING 1-LANE, 2-WAY TRAFFIC: AFAD-CONTROLLED + TEMPORARY RUMBLE STRIPS**  
**(HIGH VOLUME HIGHWAYS, 40 MPH OR LESS)**


NOT TO SCALE

FILE NAME C:\Users\LintzF\OneDrive - Washington State Department of Transportation\Desktop\Work Zone TCPS\432Hwy40-AltTrafficAFADRumbleStrips.dgn									
TIME	7:00:04 AM					REGION NO.	STATE	FED.AID PROJ.NO.	
DATE	7/18/2023					10	WASH		
PLOTTED BY	LintzF					JOB NUMBER			
DESIGNED BY						CONTRACT NO.		LOCATION NO.	
ENTERED BY									
CHECKED BY									
PROJ. ENGR.									
REGIONAL ADM.		REVISION			DATE	BY			

		<div></div> <div>Washington State Department of Transportation</div>		Plot 3
				PLAN REF NO TC432
			<div>P.E. STAMP BOX</div> <div>DATE</div>	<div>P.E. STAMP BOX</div> <div>DATE</div>
			TYPICAL TRAFFIC CONTROL PLANS	



16. FLAGGERS MAY COLLABORATE TO RELEASE APPROACH/ACCESS AND MAINLINE TRAFFIC TRAVELING IN THE SAME DIRECTION CONCURRENTLY.





**WORK ZONE MICROSTATION CELLS: Updated work zone cells incorporated (July 2023).**

WSDOT CAE automatically updates cell libraries on WSDOT and on-site consultant staff computers (no action needed); however, external users or off-site consultants must manually install them. For additional information email HQCAEHlpDesk@wsdot.wa.gov.

Division 4 in WSDOT Plans Preparation Manual, Section 400.06(29), provides updated work zone cell library policy and information for PS&Es. See <https://wsdot.wa.gov/engineering-standards/all-manuals-and-standards/manuals/plans-preparation-manual>

**TYPICAL TCP USAGE EXPLANATION:**

- Plot 1:** AFAD-controlled 1-lane, 2-way alternating traffic on the mainline for 2-lane highways 40 mph or less with a shared bicycle-vehicle lane with portable temporary rumble strips in advance.
- Plot 2:** Details for intersecting roadways and driveway/business access for Plot 1.
- Plot 3:** AFAD-controlled 1-lane, 2-way alternating traffic on the mainline for 2-lane highways 40 mph or less with a shared bicycle-vehicle lane with portable temporary rumble strips in advance for high traffic volumes (800+ vehicles/hour in all directions) by minimizing the distance between mainline AFAD/flaggers.
- Plot 4:** Details for intersecting roadways and driveway/business access for Plot 3.
- Other Alternating Traffic TCPs (45+ mph):** See Typical Traffic Control Plan Library (<https://wsdot.wa.gov/engineering-standards/all-manuals-and-standards/plan-sheet-library/work-zone-typical-traffic-control-plans-tcp>)
- \* TC320s for flagger-controlled alternating traffic plans
  - \* TC330s for AFAD-controlled alternating traffic plans
  - \* TC340s for temporary signal-controlled alternating traffic plans
  - \* TC350s for traffic holds
- If not published yet, they will be added in the future.
- Other Alternating Traffic TCPs (40 mph or less):** See Typical Traffic Control Plan Library (<https://wsdot.wa.gov/engineering-standards/all-manuals-and-standards/plan-sheet-library/work-zone-typical-traffic-control-plans-tcp>)
- \* TC420s for flagger-controlled alternating traffic
  - \* TC430s for other variations of AFAD-controlled alternating traffic
  - \* TC440s for temporary signal-controlled alternating traffic plans
  - \* TC450s for traffic holds
- If not published yet, they will be added in the future.
- DESIGNER NOTES:**
- A. Contact Region Transportation Operations to determine which Typical TCP(s) to utilize, as their are several variations available (or soon will be).
- B. These typical traffic control plans may be modified for site specific situations and/or WSDOT Region Transportation Operations standard practices. **Typical TCPs are not "Standard Plans".**
- C. **Do not use intermittent (old: "variable") regulatory work zone speed limit reductions for flagging or AFAD operations.** Instead, maintain the existing speed limit (or continuous regulatory work zone speed limit reduction, if applicable). See WSDOT Traffic Manual Section 5-18 and Executive Order E1060 regulatory speed limit reductions & advisory speed approval policy for work zones thru Region Transportation Operations.
- D. See MUTCD Table 6F-1 for additional temporary sign size information. Work zone signs are usually smaller than those used permanently.
- E. WAC 468-95-300 modifies MUTCD Table 6-1 "Recommended Advance Warning Sign Minimum Spacing". Sign spacing may be adjusted for field conditions based on engineering judgement. The Sign Spacing table is acceptable to use in Typical TCPs; however, site-specific traffic control plans should include actual sign spacing values (with Å) that have been verified in the field, on SR view, or via Google Maps.
- F. When positioned behind channelization devices, temporary signs should be mounted at 5' minimum.
- G. For this Typical TCP, the work zone design speed is based on the existing posted speed limit for sign spacing, channelization device spacing, buffer, and roll ahead distances.
- H. "Flagger tapers" are always 50'-100' per closed lane with 6 devices minimum (10'-20' spacing on the taper), regardless of the posted speed limit or lane width per MUTCD 6C.08, Paragraph 15. Never use "L" for these tapers.
- I. Channelization devices types may be modified (vertical panel channelization devices prohibited). 28" reflective traffic cones are recommended on AFAD-controlled alternating traffic (especially for access delineation to maintain visibility for turning motorists). 36" reflective traffic cones, 42" tall channelization devices, or traffic safety drums may be used. Warning lights on channelization devices is being phased out in Washington. Contact Region Transportation Operations for information regarding their standard practices.
- J. Maximum channelization device spacing table for tangents is based on WAC 468-95-301 and may ALWAYS be reduced.
- K. Sequential arrow boards are prohibited at flagger tapers per WSDOT standard practice and per MUTCD Guidance TA-10.
- L. Per MUTCD Section 6C.06, longitudinal buffer spaces are optional. Using longitudinal buffer spaces listed in MUTCD Table 6C-2 is recommended as best practice when feasible, but may be adjusted based on engineering judgement. The Longitudinal Buffer Space table is acceptable in Typical TCPs; however, site-specific traffic control plans should include actual buffer distances that have been verified in the field, on SR view, or via Google Maps.
- M. The lateral buffer (tranverse distance between open travel lanes and work area) is optional. No lateral buffer has been provided in these Typical TCPs due to the low speeds of alternating traffic. Actual work area limits may be modified.
- N. On roadways 40 mph or less, WSDOT best practice is to place a protective vehicle (PV) in the closed lane in advance of the work area with a full longitudinal buffer space to provide errant vehicles an opportunity to stop before impacting the PV. On roadways 40 mph or less, the longitudinal buffer is optional and may be eliminated (still okay to use PV, upgrading to transportable attenuator is not required). Additional PVs (or TAs) may be added prior to multiple work crews within a work area. Contact Region Transportation Operations for their standard practice.
- O. Placing channelization devices transversely (at 45° and 5-foot spacing) is an optional strategy to stop move errant drivers traveling within the closed lane(s) but is not shown in the Typical TCP.
- P. The downstream taper of 50'-100' is required on 1-lane, 2-way traffic configurations.
- Q. Duration of traffic holds for driveways, business accesses, and/or roadway approaches is listed as 5 minutes (1 minute on high volume highways) in this Typical Traffic Control Plan, but may be adjusted. Contact Region Transportation Operations for additional guidance.
- R. When utilizing AFADs in Contracts, include the three Section 1-10 General Special Provisions for Specification, Measurement, and Payment. <https://wsdot.wa.gov/publications/fulltext/projectdev/gspspdf/egsp1.pdf> <https://wsdot.wa.gov/publications/fulltext/projectdev/gspspdf/egsp1.pdf>
- \* 1-10.1(1).OPT1.GR1 (AFAD Materials GSP)
  - \* 1-10.3(3).OPT1.GR1 (AFAD Specifications GSP)
  - \* 1-10.4(2).OPT2.GR1 (AFAD Measurement GSP)
  - \* 1-10.5(2).OPT1.GR1 (AFAD Payment GSP)
- S. When utilizing temporary portable transverse rumble strips in Contracts, include the following General Special Provisions for Materials, Specification, Measurement, and Payment. <https://wsdot.wa.gov/publications/fulltext/projectdev/gspspdf/egsp1.pdf>
- \* 1-10.2(9-35).OPT1.GR1 (Temp Rumble Strip Materials GSP)
  - \* 1-10.3(3).OPT5.GR1 (Temp Rumble Strip Specifications GSP)
  - \* 1-10.4(2).OPT8.GR1 (Temp Rumble Strip Measurement GSP)
  - \* 1-10.5(2).OPT6.GR1 (Temp Rumble Strip Payment GSP)

**ALTERNATING 1-LANE, 2-WAY TRAFFIC: AFAD-CONTROLLED + TEMP. RUMBLE STRIPS (HIGHWAYS, 40 MPH OR LESS)**

	<b>INFORMATIONAL USE ONLY</b>	Plot 5
	<b>DO NOT INCLUDE THIS SHEET IN CONTRACT PS&amp;Es or TCP SUBMITTALS.</b>	<b>TC432</b>
	<b>DESIGNER GUIDANCE</b>	