

WASHINGTON STATE
 DEPARTMENT OF TRANSPORTATION
 CHANGE ORDER

DATE: 06/18/24
 PAGE 1 of

CONTRACT NO: 009845 FEDERAL AID NO: HSIP-9999(862)
 CONTRACT TITLE: SR 10 ET AL, KITTITAS & YAKIMA CO & SE W CENTERLIN
 CHANGE ORDER NO: 2 SR 410 ADDITIONAL WORK

PRIME CONTRACTOR: XXXXXXXXXX CONSTRUCTION AHEAD, INC. DBA
 9312 W 10TH AVENUE 99336-8521
 KENNEWICK WA 99336-0616

(X) Ordered by Engineer under the terms of Section 1-04.4 of the Standard Specifications
 () Change proposed by Contractor

ENDORSED BY: <i>Signature on file</i> Matt McDaniel (Jun 18, 2024 09:28 PDT)	SURETY CONSENT:
CONTRACTOR SIGNATURE Jun 18, 2024 <hr/> DATE	ATTORNEY IN FACT <hr/> DATE

ORIGINAL CONTRACT AMOUNT: 2,530,478.90
 CURRENT CONTRACT AMOUNT: 3,686,035.54
 ESTIMATED NET CHANGE THIS ORDER: 1,453,254.99
 ESTIMATED CONTRACT TOTAL AFTER CHANGE: 5,139,290.53

Signature Required: (X) Project Engineer (X) State Construction Engineer
 (X) Regional Administrator () Other Agency

<i>Signature on file</i> Scott Golbek (Jun 18, 2024 11:26 PDT)	<i>Signature on file</i>
PROJECT ENGINEER SIGNATURE Jun 18, 2024 <hr/> DATE	STATE CONSTRUCTION ENGINEER SIGNATURE Jun 18, 2024 <hr/> DATE
<i>Signature on file</i>	OTHER APPROVAL WHEN REQUIRED
REGIONAL ADMINISTRATOR SIGNATURE Jun 18, 2024 <hr/> DATE	SIGNATURE _____ DATE _____ REPRESENTING

CONTRACT NO:009845

CHANGE ORDER NO: 2

All work, materials, and measurements to be in accordance with the provisions of the Standard Specifications and Special Provisions for the type of construction involved.

This contract is revised as follows:

This work consists of the removal of failed pavement and rumble strips, preparation for paving, and placement and compaction of commercial HMA on SR 410 at locations indicated below.

The following new items are added:

- C.O. 2; Mobilization
- C.O. 2; Project Temporary Traffic Control
- C.O. 2; Pavement Repair Excavation Incl. Haul
- C.O. 2; Commercial HMA
- C.O. 2; Temporary Pavement Marking Short Duration

Materials:

Commercial HMA shall meet the requirements of Section 5-04.2(1).

Temporary Pavement Marking Short Duration shall meet the requirements of Section 8-23.2

Construction Requirements:

Project Temporary Traffic Control shall be in accordance with Section 1-10.

Pavement Repair Excavation Incl. Haul shall be removed in accordance with Section 5-04.3(4)C.

Commercial HMA shall be placed and compacted in accordance with Section 5-04.3.

Temporary Pavement Marking Short Duration shall meet the requirements of Section 8-23.3.

At the following locations the Contractor shall mill a two foot wide strip centered on the existing rumble strip. Immediately following milling the Contractor shall prepare and pave the void left by milling with Commercial HMA.

- MP 99.10 to 100.47; 0.15' depth
- MP 100.47 to 104.55; 0.12' depth
- MP 104.55 to 113.00; 0.15' depth

Measurement:

C.O. 2; Mobilization, no particular unit of measurement will apply. Measurement will include labor and equipment to mobilize to each area of added work.

C.O. 2; Project Temporary Traffic Control, no particular unit of measurement will apply. Measurement will include all labor and equipment to provide traffic control to complete the added work included in this change order.

C.O. 2; Pavement Repair Excavation Incl. Haul, measurement will be in accordance with Section 5-04.4

C.O. 2; Commercial HMA, measurement will be in accordance with Section 5-04.4.

C.O. 2; Temporary Pavement Marking Short Duration, measurement will be in accordance with Section 8-23.4.

Payment:

"C.O. 2; Mobilization", Lump Sum. The lump sum payment will be considered full payment to perform the work as specified.

"C.O. 2; Project Temporary Traffic Control", Lump Sum. The lump sum payment will be considered full payment to perform the work as specified.

"C.O. 2; Pavement Repair Excavation Incl. Haul", per square yard.

CONTRACT NO:009845

CHANGE ORDER NO: 2

"C.O. 2; Commercial HMA", per ton.

"C.O. 2; Temporary Pavement Marking Short Duration", per linear foot.

Working Days:

In accordance with Section 1-08.8, 19 working days are added to the Contract.

WASHINGTON STATE
DEPARTMENT OF TRANSPORTATION
CHANGE ORDER

DATE: 06/18/24
PAGE 4 of

CONTRACT NO: 009845	CHANGE ORDER NO: 2
---------------------	--------------------

ITEM NO	GROUP NO	STD ITEM	UNIT OF MEASURE	UNIT PRICE	EST QTY CHANGE	EST AMT CHANGE
ITEM DESCRIPTION: C.O. 2; MOBILIZATION						
1004	16	0001	L.S.	0.00	0.00	4,243.35
ITEM DESCRIPTION: C.O. 2; MOBILIZATION						
1005	17	0001	L.S.	0.00	0.00	54,739.15
ITEM DESCRIPTION: C.O. 2; PROJECT TEMPORARY TRAFFIC CONTROL						
1006	16	6971	L.S.	0.00	0.00	8,557.43
ITEM DESCRIPTION: C.O. 2; PROJECT TEMPORARY TRAFFIC CONTROL						
1007	17	6971	L.S.	0.00	0.00	110,390.84
ITEM DESCRIPTION: C.O. 2; PAVEMENT REPAIR EXCAVATION INCL.						
1008	16	0332	S.Y.	38.09	1,174.00	44,717.66
ITEM DESCRIPTION: C.O. 2; PAVEMENT REPAIR EXCAVATION INCL.						
1009	17	0332	S.Y.	38.09	15,136.00	576,530.24
ITEM DESCRIPTION: C.O. 2; COMMERCIAL HMA						
1010	16	5875	TON	388.64	120.27	46,741.73
ITEM DESCRIPTION: C.O. 2; COMMERCIAL HMA						
1011	17	5875	TON	388.64	1,511.73	587,518.75
ITEM DESCRIPTION: C.O. 2; TEMPORARY PAVEMENT MARKING-SHORT						
1012	16	6895	L.F.	0.27	5,280.00	1,425.60
ITEM DESCRIPTION: C.O. 2; TEMPORARY PAVEMENT MARKING-SHORT						
1013	17	6895	L.F.	0.27	68,112.00	18,390.24

AMOUNT TOTAL

1,453,254.99
=====

CONTRACT 009845

DISTRICT 5

CHANGE ORDER NUMBER 002

TYPE OF CHANGE ORDER CONSTRUCTION

DATED 06-18-2024

TIME 16:02:52

ITEM	GROUP	STD ITEM	UNIT OF MEAS	UNIT PRICE	QUANTITY	CHANGE	AMOUNT	CHANGE
027	16		L.S.	\$4,243.3500		.00		\$4,243.35
CCIS TEMP ITEM NUMBER: 1004								
DESC...: C.O. 2; MOBILIZATION								
028	17		L.S.	\$54,739.1500		.00		\$54,739.15
CCIS TEMP ITEM NUMBER: 1005								
DESC...: C.O. 2; MOBILIZATION								
029	16		L.S.	\$8,557.4300		.00		\$8,557.43
CCIS TEMP ITEM NUMBER: 1006								
DESC...: C.O. S; PROJECT TEMPORARY TRAFFIC CONTROL								
030	17		L.S.	\$110,390.8400		.00		\$110,390.84
CCIS TEMP ITEM NUMBER: 1007								
DESC...: C.O. S; PROJECT TEMPORARY TRAFFIC CONTROL								
031	16		S.Y.	\$38.0900		1,174.00		\$44,717.66
CCIS TEMP ITEM NUMBER: 1008								
DESC...: C.O. 2; PAVEMENT REPAIR EXCAVATION INCL.								
032	17		S.Y.	\$38.0900		15,136.00		\$576,530.24
CCIS TEMP ITEM NUMBER: 1009								
DESC...: C.O. 2; PAVEMENT REPAIR EXCAVATION INCL.								
033	16		TON	\$388.6400		120.27		\$46,741.73
CCIS TEMP ITEM NUMBER: 1010								
DESC...: C.O. 2; COMMERCIAL HMA								
034	17		TON	\$388.6400		1,511.73		\$587,518.75
CCIS TEMP ITEM NUMBER: 1011								
DESC...: C.O. 2; COMMERCIAL HMA								
035	16		L.F.	\$.2700		5,820.00		\$1,571.40
CCIS TEMP ITEM NUMBER: 1012								
035	16		L.F.	\$.2700		540.00-		\$145.80-
CCIS TEMP ITEM NUMBER: 1012								
DESC...: C.O. 2; TEMPORARY PAVEMENT MARKING-SHORT								
036	17		L.F.	\$.2700		68,112.00		\$18,390.24
CCIS TEMP ITEM NUMBER: 1013								
DESC...: C.O. 2; TEMPORARY PAVEMENT MARKING-SHORT								
TOTAL NET CHANGE								\$1,453,254.99