Washington State Department of Transportation

Design Manual

M 22-01.14

July 2017

Division 1 – General Information
Division 2 – Hearings, Environmental, and Permits
Division 3 – Project Documentation
Division 4 – Surveying
Division 5 – Right of Way and Access Control
Division 6 – Soils and Paving
Division 7 – Structures
Division 8 – Hydraulics
Division 9 – Roadside Development
Division 10 – Traffic Safety Elements
Division 11 – Practical Design
Division 12 – Geometrics
Division 13 – Intersections and Interchanges
Division 14 – HOV and Transit
Division 15 – Pedestrian and Bicycle Facilities
Division 16 – Roadside Safety Elements
Division 17 – Roadside Facilities

Engineering and Regional Operations
Development Division, Design Office

Americans with Disabilities Act (ADA) Information

Materials can be made available in an alternative format by emailing the WSDOT Diversity/ADA Affairs Team at wsdotada@wsdot.wa.gov or by calling toll free: 855-362-4ADA (4232). Persons who are deaf or hard of hearing may contact that number via the Washington Relay Service at 7-1-1.

Title VI Notice to Public

It is Washington State Department of Transportation (WSDOT) policy to ensure no person shall, on the grounds of race, color, national origin, or sex, as provided by Title VI of the Civil Rights Act of 1964, be excluded from participation in, be denied the benefits of, or be otherwise discriminated against under any of its federally funded programs and activities. Any person who believes his/her Title VI protection has been violated may file a complaint with WSDOT's Office of Equal Opportunity (OEO). For Title VI complaint forms and advice, please contact OEO's Title VI Coordinator at 360-705-7082 or 509-324-6018.

To get the latest information on individual WSDOT publications, sign up for email updates at:
www.wsdot.wa.gov/publications/manuals

Foreword

The *Design Manual* is for use by Washington State Department of Transportation engineering personnel and consultant workforces. It provides policies, procedures, and methods for developing and documenting the design of improvements to the transportation network in Washington. It has been developed for state facilities and may not be appropriate for all county roads or city streets that are not state highways.

The *Design Manual* supplements the engineering analyses and judgment inherent with practical design. It provides uniform procedures for documenting and implementing design decisions.

The Federal Highway Administration has agreed to approve designs that follow the guidance in the *Design Manual*; therefore, following the guidance is mandatory for state highway projects. When proposed designs meet the requirements contained in the *Design Manual*, little additional documentation is required.

The complexity of transportation design requires designers to make fundamental trade-off decisions that balance competing spatial considerations. Although this adds to the complexity of design, it acknowledges the unique needs of specific projects and the relative priorities of various projects and programs. Projects are designed in light of finite transportation funding. The *Design Manual* emphasizes "practical design" as a means to produce environmentally conscious, sustainable, context-based designs that achieve the purpose and need for the lowest cost. Implementing practical design considers the needs of all users, fostering livable communities and modally integrated transportation systems used safely by all, including motorists, freight haulers, transit, pedestrians, and bicyclists.

Updating the *Design Manual* is an ongoing process and revisions are issued regularly. The addition of new or modified design criteria to the *Design Manual* through the revision process does not imply that existing features are deficient or inherently dangerous. Nor does it suggest or mandate immediate engineering review or initiation of new projects. Comments, questions, and improvement ideas are welcomed. Use the comment form on the next page or the contact information on the Design Policy Internet Page: www.wsdot.wa.gov/design/policy

/s/ Jeff Carpenter
Jeff Carpenter, P.E.
Director & State Design Engineer,
Development Division

Comment Form

From: _____ Date: _____

_____ Phone: _____

_____

To: WSDOT Headquarters
Development Division, Design Office
Attn: Policy, Standards, and Research Section
PO Box 47329
Olympia, WA 98504-7329

Subject: *Design Manual* Comment

Comment (marked copies attached):

Contents

Division 1 – General Information

Chapter 100 Manual Description
100.01 Purpose
100.02 Presentation and Revisions
100.03 Practical Solutions
100.04 Manual Applications
100.05 Manual Use
100.06 Manual Organization

Chapter 110 Design-Build Projects
110.01 General
110.02 Terminology and Language Used
110.03 Design and Documentation Responsibility
110.04 References

Division 2 – Hearings, Environmental, and Permits

Chapter 210 Public Involvement and Hearings
210.01 General
210.02 References
210.03 Definitions
210.04 Public Involvement
210.05 Public Hearings
210.06 Environmental Hearing
210.07 Corridor Hearing
210.08 Design Hearing
210.09 Limited Access Hearing
210.10 Combined Hearings
210.11 Administrative Appeal Hearing
210.12 Follow-Up Hearing
210.13 Documentation

Chapter 225 Environmental Coordination
225.01 General
225.02 References
225.03 Determining the Environmental Documentation
225.04 Identifying the Project Classification
225.05 Environmental Commitment File
225.06 Environmental Permits and Approvals
225.07 Documentation

Division 3 – Project Documentation

Chapter 300 Design Documentation, Approval, and Process Review
300.01 General
300.02 WSDOT Project Delivery
300.03 Design Documentation and Records Retention Policy
300.04 Project Design Approvals
300.05 FHWA Oversight and Approvals
300.06 Project Documents and Approvals
300.07 Process Review
300.08 References

Chapter 301 Design and Maintenance Coordination
301.01 Introduction
301.02 Communication
301.03 Incorporating Maintenance Considerations in Design
301.04 Documentation
301.05 References

Chapter 305 Project Management
305.01 Introduction
305.02 Project Management
305.03 Project Management Tools
305.04 Cost and Risk Management
305.05 References

Chapter 310 Value Engineering
310.01 General
310.02 Statewide VE Program
310.03 VE Procedure
310.04 Value Engineering Job Plan
310.05 Project Management Accountability
310.06 Documentation
310.07 References

Chapter 320 Traffic Analysis
320.01 General
320.02 Design Year and Forecasting Considerations
320.03 Traffic Analysis Software
320.04 Travel Demand Forecasting
320.05 Traffic Impact Analysis (TIA)
320.06 TIA Scope
320.07 TIA Methods and Assumptions Document
320.08 TIA Methodologies
320.09 TIA Mitigation Measures
320.10 TIA Report
320.11 References

Chapter 321 Sustainable Safety Analysis
321.01 Sustainable Safety Related Policy
321.02 HQ Safety Technical Group
321.03 Project Related Safety Analysis
321.04 Stand Alone Safety Analysis
321.05 Reports and Documentation
321.06 References

Division 4 – Surveying

Chapter 400 Surveying and Mapping
400.01 General
400.02 References
400.03 Procedures
400.04 Datums
400.05 Global Positioning System
400.06 WSDOT Survey Monument Database
400.07 Geographic Information System
400.08 Photogrammetric Surveys
400.09 Documentation

Chapter 410 Monumentation
410.01 General
410.02 References
410.03 Control Monuments
410.04 Alignment Monuments
410.05 Property Corners
410.06 Other Monuments
410.07 Filing Requirements
410.08 Documentation

Division 5 – Right of Way and Access Control

Chapter 510 Right of Way Considerations
510.01 General
510.02 Special Features
510.03 Easements and Permits
510.04 Programming for Funds
510.05 Appraisal and Acquisition
510.06 Transactions
510.07 Documentation
510.08 References

Chapter 520 Access Control
520.01 General
520.02 References
520.03 Definitions
520.04 Vocabulary

Chapter 530 Limited Access Control
530.01 General
530.02 Achieving Limited Access
530.03 Full Control (Most Restrictive)
530.04 Partial Control
530.05 Modified Control (Least Restrictive)
530.06 Access Approaches
530.07 Frontage Roads
530.08 Turnbacks
530.09 Adjacent Railroads
530.10 Changes to Existing Limited Access Rights of Way (including Access, Occupancy, and Use)
530.11 Documentation

Chapter 540 Managed Access Control
540.01 General
540.02 Design Considerations
540.03 Managed Access Highway Classes
540.04 Corner Clearance Criteria
540.05 Access Connection Categories
540.06 Access Connection Permit
540.07 Permitting and Design Documentation
540.08 Other Considerations
540.09 Preconstruction Conference
540.10 Adjudicative Proceedings
540.11 Documentation
540.12 References

Chapter 550 Interchange Justification Report
550.01 General
550.02 Procedures
550.03 Interchange Justification Report and Supporting Analyses
550.04 Report Organization and Appendices
550.05 IJR Review and Approval
550.06 Updating an IJR
550.07 Documentation
550.08 References

Chapter 560 Fencing
560.01 General
560.02 Design Criteria
560.03 Fencing Types
560.04 Gates
560.05 Procedure
560.06 Documentation
560.07 References

Division 6 – Soils and Paving

Chapter 610 Investigation of Soils, Rock, and Surfacing Materials
610.01 General
610.02 References
610.03 Materials Sources
610.04 Geotechnical Investigation, Design, and Reporting
610.05 Use of Geotechnical Consultants
610.06 Geotechnical Work by Others
610.07 Surfacing Report
610.08 Documentation

Chapter 620 Design of Pavement Structure
620.01 General
620.02 Estimating Tables

Chapter 630 Geosynthetics
630.01 General
630.02 References
630.03 Geosynthetic Types and Characteristics
630.04 Geosynthetic Function Definitions and Applications
630.05 Design Approach for Geosynthetics
630.06 Design Responsibility
630.07 Documentation

Division 7 – Structures

Chapter 700 Project Development Roles and Responsibilities for Projects With Structures
700.01 General
700.02 Procedures

Chapter 710 Site Data for Structures
710.01 General
710.02 Required Data for All Structures
710.03 Additional Data for Waterway Crossings (Bridges and Buried Structures)
710.04 Additional Data for Grade Separations

710.05 Additional Data for Widenings
710.06 Documentation
710.07 References

Chapter 720 Bridges
720.01 General
720.02 Bridge Locations
720.03 Bridge Site Design Elements
720.04 Documentation
720.05 References

Chapter 730 Retaining Walls and Steep Reinforced Slopes
730.01 General
730.02 References
730.03 Design Principles
730.04 Design Requirements
730.05 Guidelines for Wall/Slope Selection
730.06 Design Responsibility and Process
730.07 Documentation

Chapter 740 Noise Barriers
740.01 General
740.02 Design
740.03 Procedures
740.04 Documentation
740.05 References

Division 8 – Hydraulics

Chapter 800 Hydraulic Design
800.01 General
800.02 References
800.03 Hydraulic Considerations
800.04 Safety Considerations
800.05 Design Responsibility
800.06 Documentation

Division 9 – Roadside Development

Chapter 900 Roadsides
900.01 General
900.02 References
900.03 Project Development
900.04 Documentation

Chapter 950 Public Art
950.01 General
950.02 References
950.03 Standard Architectural Design
950.04 Criteria for Public Art
950.05 Process and Project Delivery Timing
950.06 Approvals
950.07 Documentation

Division 10 – Traffic Safety Elements

Chapter 1010 Work Zone Safety and Mobility
1010.01 General
1010.02 Definitions
1010.03 Work Zone Safety and Mobility
1010.04 Transportation Management Plans and Significant Projects
1010.05 Developing TMP Strategies
1010.06 Capacity Analysis
1010.07 Work Zone Design
1010.08 Temporary Traffic Control Devices
1010.09 Positive Protection Devices
1010.10 Other Traffic Control Devices or Features
1010.11 Traffic Control Plan Development and PS&E
1010.12 Training and Resources
1010.13 Documentation
1010.14 References

Chapter 1020 Signing
1020.01 General
1020.02 Design Components
1020.03 Overhead Installation
1020.04 State Highway Route Numbers
1020.05 Mileposts
1020.06 Guide Sign Plan
1020.07 Documentation
1020.08 References

Chapter 1030 Delineation
1030.01 General
1030.02 Definitions
1030.03 Pavement Markings
1030.04 Guideposts
1030.05 Barrier Delineation
1030.06 Object Markers
1030.07 Documentation
1030.08 References

Chapter 1040 Illumination
1040.01 General
1040.02 Definitions
1040.03 Design Considerations
1040.04 Required Illumination
1040.05 Additional Illumination
1040.06 Design Criteria
1040.07 Documentation
1040.08 References

Chapter 1050 Intelligent Transportation Systems
1050.01 General
1050.02 References
1050.03 Systems Engineering
1050.04 FHWA Washington Division ITS Project Contracting Guidance
1050.05 Documentation

Division 11 – Practical Design

Chapter 1100 Practical Design
1100.01 General
1100.02 Practical Design Procedure
1100.03 Community Engagement
1100.04 Advisory Team
1100.05 Need and Performance Identification
1100.06 Context Identification
1100.07 Design Control Selection
1100.08 Alternative Formulation and Evaluation
1100.09 Design Element Selection and Dimensions
1100.10 Documentation Tools
1100.11 References

Chapter 1101 Need Identification
1101.01 General
1101.02 Baseline Needs
1101.03 Contextual Needs
1101.04 Contributing Factors Analysis
1101.05 Project Need Statement
1101.06 Documentation
1101.07 References

Chapter 1102 Context Determination
1102.01 General Overview
1102.02 Land Use Context
1102.03 Transportation Context
1102.04 Documentation
1102.05 References

Chapter 1103 Design Control Selection
1103.01 General Overview
1103.02 Control: Design Year
1103.03 Control: Modal Priority
1103.04 Control: Access Control
1103.05 Control: Design Speed
1103.06 Control: Terrain Classification
1103.07 Documentation
1103.08 References

Chapter 1104 Alternatives Analysis
1104.01 General
1104.02 Alternative Solution Formulation
1104.03 Alternative Solution Evaluation
1104.04 Documentation
1104.05 References

Chapter 1105 Design Element Selection
1105.01 General
1105.02 Selecting Design Elements
1105.03 Related Elements
1105.04 Documentation
1105.05 References

Chapter 1106 Design Element Dimensions
1106.01 General
1106.02 Choosing Dimensions
1106.03 The Mode/Function/Performance Approach
1106.04 Design Up Method
1106.05 Quantitative Analysis Methods and Tools
1106.06 Documenting Dimensions
1106.07 Design Analysis
1106.08 References

Chapter 1120 Preservation Projects
1120.01 General
1120.02 Structures Preservation (P2) and Other Facilities (P3)
1120.03 Pavement Preservation (P1)

Division 12 – Geometrics

Chapter 1210 Geometric Plan Elements
1210.01 General
1210.02 Horizontal Alignment
1210.03 Distribution Facilities
1210.04 Number of Lanes and Arrangement
1210.05 Pavement Transitions
1210.06 Procedures
1210.07 Documentation
1210.08 References

Chapter 1220 Geometric Profile Elements
1220.01 General
1220.02 Vertical Alignment
1220.03 Coordination of Vertical and Horizontal Alignments
1220.04 Airport Clearance
1220.05 Railroad Crossings
1220.06 Procedures
1220.07 Documentation
1220.08 References

Chapter 1230 Geometric Cross Section Basics
1230.01 General
1230.02 Guidance for Specific Facility Types
1230.03 Common Elements
1230.04 Jurisdiction for Design and Maintenance
1230.05 References

Chapter 1231 Geometric Cross Section – Highways
1231.01 General
1231.02 Design Up
1231.03 Common Elements
1231.04 Vehicle Lanes
1231.05 Modally Integrated Cross Sections

1231.06 Road Diets and Retrofit Options
1231.07 References

Chapter 1232 Geometric Cross Section – Freeways
1232.01 General
1232.02 Lane Width
1232.03 Shoulder Width
1232.04 Other Elements
1232.05 Design Flexibility
1232.06 References

Chapter 1238 Geometric Cross Section – Streetside and Parking
1238.01 General
1238.02 Parking
1238.03 Streetside
1238.04 Retrofit Options
1238.05 References

Chapter 1239 Geometric Cross Section – Shoulders, Side Slopes, Curbs, and Medians
1239.01 Introduction
1239.02 Shoulders
1239.03 Side Slopes and Ditches
1239.04 Roadway Sections in Rock Cuts
1239.05 Curbs
1239.06 Lateral Clearance to Curb and Barrier
1239.07 Medians & Outer Separations

Chapter 1240 Turning Roadways
1240.01 General
1240.02 Turning Roadway Widths
1240.03 Documentation
1240.04 References

Chapter 1250 Cross slope and Superelevation
1250.01 General
1250.02 Roadway Cross Slope
1250.03 Superelevation Rate Selection
1250.04 Existing Curves
1250.05 Turning Movements at Intersections
1250.06 Runoff for Highway Curves
1250.07 Runoff for Ramp Curves
1250.08 Documentation
1250.09 References

Chapter 1260 Sight Distance
1260.01 General
1260.02 References
1260.03 Stopping Sight Distance
1260.04 Passing Sight Distance
1260.05 Decision Sight Distance
1260.06 Documentation

Chapter 1270 Auxiliary Lanes
1270.01 General
1270.02 Climbing Lanes
1270.03 Passing Lanes

1270.04 Slow-Moving Vehicle Turnouts
1270.05 Shoulder Driving for Slow Vehicles
1270.06 Emergency Escape Ramps
1270.07 Chain-Up and Chain-Off Areas
1270.08 Documentation
1270.09 References

Division 13 – Intersections and Interchanges

Chapter 1300 Intersection Control Type
1300.01 General
1300.02 Intersection Control Objectives
1300.03 Common Types of Intersection Control
1300.04 Modal Considerations
1300.05 Procedures
1300.06 Documentation
1300.07 References

Chapter 1310 Intersections
1310.01 General
1310.02 Design Considerations
1310.03 Design Elements
1310.04 U-Turns
1310.05 Intersection Sight Distance
1310.06 Signing and Delineation
1310.07 Procedures
1310.08 Documentation
1310.09 References

Chapter 1320 Roundabouts
1320.01 General
1320.02 Roundabout Types
1320.03 Capacity Analysis
1320.04 Geometric Design
1320.05 Pedestrians
1320.06 Bicycles
1320.07 Signing
1320.08 Pavement Marking
1320.09 Illumination
1320.10 Road Approach, Parking, and Transit Facilities
1320.11 Geometric Design Peer Review
1320.12 Documentation and Approvals
1320.13 References

Chapter 1330 Traffic Control Signals
1330.01 General
1330.02 Procedures
1330.03 Intersection Design Considerations
1330.04 Conventional Traffic Signal Design
1330.05 Preliminary Signal Plan
1330.06 Operational Considerations for Design
1330.07 Documentation
1330.08 References

Chapter 1340 Driveways
1340.01 General
1340.02 References
1340.03 Design Considerations
1340.04 Driveway Design Templates
1340.05 Sidewalks
1340.06 Driveway Sight Distance
1340.07 Stormwater and Drainage
1340.08 Mailboxes
1340.09 Documentation

Chapter 1350 Railroad Grade Crossings
1350.01 General
1350.02 References
1350.03 Plans
1350.04 Traffic Control Systems
1350.05 Nearby Roadway Intersections
1350.06 Pullout Lanes
1350.07 Crossing Surfaces
1350.08 Crossing Closure
1350.09 Traffic Control During Construction and Maintenance
1350.10 Railroad Grade Crossing Petitions and WUTC Orders
1350.11 Grade Crossing Improvement Projects
1350.12 Light Rail
1350.13 Documentation

Chapter 1360 Interchanges
1360.01 General
1360.02 Interchange Design
1360.03 Ramps
1360.04 Interchange Connections
1360.05 Ramp Terminal Intersections at Crossroads
1360.06 Interchanges on Two-Lane Highways
1360.07 Interchange Plans for Approval
1360.08 Documentation
1360.09 References

Chapter 1370 Median Crossovers
1370.01 General
1370.02 Analysis
1370.03 Design
1370.04 Plan Updates and Approvals
1370.05 Documentation

Division 14 – HOV and Transit

Chapter 1410 High-Occupancy Vehicle Facilities
1410.01 General
1410.02 References
1410.03 Definitions
1410.04 Preliminary Design and Planning
1410.05 Operations
1410.06 Design Criteria
1410.07 Documentation

Chapter 1420 HOV Direct Access
1420.01 General
1420.02 HOV Access Types and Locations
1420.03 Direct Access Geometrics
1420.04 Passenger Access
1420.05 Traffic Design Elements
1420.06 Documentation
1420.07 References

Chapter 1430 Transit Facilities
1430.01 General
1430.02 Bus Stops and Pullouts
1430.03 Passenger Amenities
1430.04 Park and Ride Lots
1430.05 Transfer/Transit Centers
1430.06 Roadway and Intersection Design
1430.07 Documentation
1430.08 References

Division 15 – Pedestrian and Bicycle Facilities

Chapter 1510 Pedestrian Facilities
1510.01 General
1510.02 References
1510.03 Definitions
1510.04 Policy
1510.05 ADA Requirements by Project Type
1510.06 Pedestrian Circulation Paths
1510.07 Pedestrian Access Routes (PARs)
1510.08 Sidewalks
1510.09 Curb Ramps
1510.10 Crosswalks
1510.11 Raised Medians/Traffic Islands
1510.12 Pedestrian Pushbuttons at Signals
1510.13 At-Grade Railroad Crossings
1510.14 Pedestrian Grade Separations (Structures)
1510.15 Other Pedestrian Facilities
1510.16 Illumination and Signing
1510.17 Work Zone Pedestrian Accommodation
1510.18 Documentation

Chapter 1515 Shared-Use Paths
1515.01 General
1515.02 References
1515.03 Definitions
1515.04 Shared-Use Path Design – The Basics
1515.05 Intersections and Crossings Design
1515.06 Grade Separation Structures
1515.07 Signing, Pavement Markings, and Illumination
1515.08 Restricted Use Controls
1515.09 Documentation

Chapter 1520 Roadway Bicycle Facilities
1520.01 General
1520.02 Roadway Bicycle Facility Types
1520.03 Bicycle Facility Selection

1520.04 Intersection Design Treatments
1520.05 Additional Bicycle Design Requirements and Considerations
1520.06 Documentation
1520.07 References

Division 16 – Roadside Safety Elements

Chapter 1600 Roadside Safety
1600.01 General
1600.02 Clear Zone
1600.03 Mitigation Guidance
1600.04 Medians
1600.05 Other Roadside Safety Features
1600.06 Documentation
1600.07 References

Chapter 1610 Traffic Barriers
1610.01 Introduction
1610.02 Barrier Impacts
1610.03 General Barrier Design Considerations
1610.04 Beam Guardrail
1610.05 High-Tension Cable Barrier
1610.06 Concrete Barrier
1610.07 Bridge Traffic Barriers
1610.08 Other Barriers
1610.09 References

Chapter 1620 Impact Attenuator Systems
1620.01 General
1620.02 Design Criteria
1620.03 Selection
1620.04 Impact Attenuator Systems
1620.05 Documentation

Division 17 – Roadside Facilities

Chapter 1710 Safety Rest Areas and Traveler Services
1710.01 General
1710.02 References
1710.03 Definitions
1710.04 Safety Rest Area Project Team
1710.05 Location, Access, and Site Design
1710.06 Buildings
1710.07 Utilities
1710.08 Documentation

Chapter 1720 Weigh Sites
1720.01 General
1720.02 Definitions
1720.03 Planning, Development, and Responsibilities
1720.04 Permanent Facilities
1720.05 Portable Facilities
1720.06 Shoulder Sites
1720.07 Federal Participation
1720.08 Procedures
1720.09 Documentation

Glossary

Exhibits

110-1	Design Documentation Sequence for a Typical Design-Build Project
210-1	Types of Public Hearings
210-2	Public Hearing Formats
210-3	Prehearing Packet Checklist
210-4	Sequence for Corridor, Design, and Environmental Hearings
210-5	Sequence for Limited Access Hearing
210-6	Hearing Summary Approvals
300-1	Approval Authorities
300-2	Approvals
300-3	PS&E Process Approvals NHS (Including Interstate) and Non-NHS
300-4	Design to Construction Transition Project Turnover Checklist Example
301-1	General Input Form with Listed Performance Objectives
301-2	Design Option Worksheet Showing Example of Life Cycle Cost Assessment
301-3	Excerpts from Olympic Region Review Checklist
305-1	WSDOT Project Management Process
310-1	Seven-Phase Job Plan for VE Studies
310-2	VE Analysis Team Tools
310-3	Value Engineering Job Plan
400-1	Interagency Agreement
400-2	Report of Survey Mark Example
410-1	Monument Documentation Summary
410-2	DNR Permit Application
410-3	DNR Completion Report Form
410-4	Land Corner Record
510-1	Appraisal and Acquisition
520-1	Access Control Vocabulary
530-1a	Full Access Control Limits: Interchange
530-1b	Full Access Control Limits: Interchange
530-1c	Full Access Control Limits: Interchange With Roundabouts
530-1d	Full Access Control Limits: Ramp Terminal With Transition Taper
530-1e	Full Access Control Limits: Single Point Urban Interchange
530-2a	Partial Access Control Limits: At-Grade Intersections
530-2b	Partial Access Control Limits: Roundabout Intersections
530-3a	Modified Access Control Limits: Roundabout Intersections
530-3b	Modified Access Control Limits: Intersections
540-1	Managed Access Highway Class Description

540-2	Minimum Corner Clearance: Distance From Access Connection to Public Road or Street
550-1	Interstate Routes: IJR Content and Review Levels
550-2	Non-Interstate Routes: IJR Content and Review Levels
550-3	Interstate IJR: Process Flow Chart
550-4	Non-Interstate IJR: Process Flow Chart
550-5	Methods and Assumptions Document for IJR: Concurrence Form Example
550-6	IJR: Stamped Cover Sheet Example
610-1	Materials Source Development
620-1	Estimating: Miscellaneous Tables
620-2	Estimating: Hot Mix Asphalt Pavement and Asphalt Distribution Tables
620-3	Estimating: Bituminous Surface Treatment
620-4	Estimating: Base and Surfacing Typical Section Formulae and Example
620-5a	Estimating: Base and Surfacing Quantities
620-5b	Estimating: Base and Surfacing Quantities
620-5c	Estimating: Base and Surfacing Quantities
620-5d	Estimating: Base and Surfacing Quantities
620-5e	Estimating: Base and Surfacing Quantities
620-5f	Estimating: Base and Surfacing Quantities
620-5g	Estimating: Base and Surfacing Quantities
620-5h	Estimating: Base and Surfacing Quantities
630-1	Selection Criteria for Geotextile Class
630-2	Maximum Sheet Flow Lengths for Silt Fences
630-3	Maximum Contributing Area for Ditch and Swale Applications
630-4	Design Process for Drainage and Erosion Control: Geotextiles and Nonstandard Applications
630-5	Design Process for Separation, Soil Stabilization, and Silt Fence
630-6	Examples of Various Geosynthetics
630-7	Geotextile Application Examples
630-8	Definition of Slope Length
630-9	Definition of Ditch or Swale Storage Length and Width
630-10	Silt Fences for Large Contributing Area
630-11	Silt Fence End Treatment
630-12	Gravel Check Dams for Silt Fences
700-1	Determination of the Roles and Responsibilities for Projects With Structures: Project Development Phase
710-1	Structure Site Data Checklist
720-1	Phased Development of Multilane Divided Highways
720-2	Highway Structure Over Railroad
720-3	Bridge Vertical Clearances
720-4	Embankment Slope at Bridge Ends

730-1 Summary of Mechanically Stabilized Earth (MSE) Gravity Wall/Slope Options Available
730-2 Summary of Prefabricated Modular Gravity Wall Options Available
730-3 Summary of Rigid Gravity and Semigravity Wall Options Available
730-4 Summary of Nongravity Wall Options Available
730-5 Summary of Anchored Wall Options Available
730-6 Other Wall/Slope Options Available
730-7 Typical Mechanically Stabilized Earth Gravity Walls
730-8 Typical Prefabricated Modular Gravity Walls
730-9 Typical Rigid Gravity, Semigravity Cantilever, Nongravity Cantilever, and Anchored Walls
730-10 Typical Rockery and Reinforced Slopes
730-11 MSE Wall Drainage Detail
730-12 Retaining Walls With Traffic Barriers
730-13a Retaining Wall Design Process
730-13b Retaining Wall Design Process: Proprietary
740-1 Standard Noise Wall Types
1010-1 General Lane Closure Work Zone Capacity
1010-2 Minimum Work Zone Clear Zone Distance
1010-3 Transportation Management Plan Components Checklist
1020-1 Reflective Sheeting Requirements for Overhead Signs
1020-2 Timber Posts
1020-3 Wide Flange Steel Posts
1020-4 Laminated Wood Box Posts
1030-1 Pavement Marking Material Guide – Consult Region Striping Policy
1030-2 Guidepost Placement
1040-1a Freeway Lighting Applications
1040-1b Freeway Lighting Applications
1040-1c Freeway Lighting Applications
1040-2 Freeway Ramp Terminals
1040-3 Ramp With Meter
1040-4a HOT (High-Occupancy Toll) Lane Enter/Exit Zone
1040-4b HOT (High-Occupancy Toll) Lane Access Weave Lane
1040-5 Lane Reduction
1040-6a Intersection With Left-Turn Channelization: Divided Highway
1040-6b Intersections With Left-Turn Channelization
1040-6c Intersections With Raised Left-Turn Channelization
1040-7 Intersections With Traffic Signals
1040-8 Intersection Without Channelization
1040-9 Roundabout
1040-10 Railroad Crossing With Gates or Signals

1040-11	Midblock Pedestrian Crossing
1040-12	Transit Flyer Stop
1040-13	Major Parking Lot
1040-14	Minor Parking Lot
1040-15	Truck Weigh Site
1040-16	Safety Rest Area
1040-17	Chain-Up/Chain-Off Parking Area
1040-18	Bridge Inspection Lighting System
1040-19	Traffic Split Around an Obstruction
1040-20	Construction Work Zone and Detour
1040-21	Diverging Diamond Interchange
1040-22	Light Levels and Uniformity Ratios
1050-1	Systems Engineering Process (“V” Diagram)
1050-2	Intelligent Transportation Systems (ITS) Systems Engineering Analysis Worksheet
1050-3	FHWA Washington Division – ITS Project Contracting Guidance
1100-1	Basis of Design Flowchart
1102-1	Factors for Determining Initial Land Use Context
1103-1	WSDOT Design Controls
1103-2	Initial Modal Accommodation Level
1103-3	Example Characteristics Related to Modal Accomodation
1103-4	Target Speed Based on Land Use Context and Roadway Type
1103-5	Speed Transition Segment Example
1103-6	Geometric Traffic Calming Treatments and Considerations
1103-7	Roadside, Streetside, and Pavement-Oriented Traffic Calming Treatments
1105-1	Required Design Elements
1106-1	Dimensioning Guidance Variations
1106-2	Mode/Function/Performance Approach
1210-1	Maximum Angle Without Curve
1210-2a	Alignment Examples
1210-2b	Alignment Examples
1210-2c	Alignment Examples
1220-1	Grade Length
1220-2a	Coordination of Horizontal and Vertical Alignments
1220-2b	Coordination of Horizontal and Vertical Alignments
1220-2c	Coordination of Horizontal and Vertical Alignments
1220-3	Grading at Railroad Crossings
1230-1	Geometric Cross Section - Guide to Chapters
1230-2	State and City Jurisdictional Responsibilities
1231-1	Lane Widths for Highways

1231-2	Lane Width Considerations
1231-3	Motor Vehicle Oriented Cross Sections
1231-4	Cross Sections Featuring Bicycle Facilities
1231-5	Cross Sections Featuring Pedestrian Facilities
1231-6	Cross Sections Featuring Transit Facilities
1231-7	Complete Street Cross Sections
1232-1	Geometric Cross Section - Interstate (4 lanes shown, can vary)
1232-2	Geometric Cross Section – Non-Interstate (4 lanes shown, can vary)
1232-3	Median Section without Median Barrier
1238-1	Zones within the Streetside
1239-1	Shoulder Widths for Highways
1239-2	Shoulder Function & Modal Accommodation Width Considerations
1239-3	Shoulder Details
1239-3	Shoulder Details (continued)
1239-4	Drainage Ditch Details
1239-5a	Bridge End Slopes
1239-5b	Bridge End Slope Details
1239-6	Roadway Sections in Rock Cuts: Design A
1239-7	Roadway Sections in Rock Cuts: Design B
1239-8	Stepped Slope Design
1239-9	Minimum Lateral Clearance to Barrier and Curb
1239-10	Median Functions and Guidance: High and Intermediate Speeds
1239-11	Median Functions and Guidance: Low and Intermediate Speeds
1239-12a	Divided Highway Median Sections
1239-12b	Divided Highway Median Sections
1239-12c	Divided Highway Median Sections
1240-1a	Traveled Way Width for Two-Lane Two-Way Turning Roadways
1240-1b	Traveled Way Width for Two-Lane Two-Way Turning Roadways: Based on the Delta Angle
1240-2a	Traveled Way Width for Two-Lane One-Way Turning Roadways
1240-2b	Traveled Way Width for Two-Lane One-Way Turning Roadways: Based on the Delta Angle
1240-3a	Traveled Way Width for One-Lane Turning Roadways
1240-3b	Traveled Way Width for One-Lane Turning Roadways: Based on the Delta Angle, Radius on Outside Edge of Traveled Way
1240-3c	Traveled Way Width for One-Lane Turning Roadways: Based on the Delta Angle, Radius on Inside Edge of Traveled Way
1250-1	Minimum Radius for Normal Crown Section
1250-2	Minimum Radius for Existing Curves
1250-3	Side Friction Factor

1250-4a Superelevation Rates (10% Max)
1250-4b Superelevation Rates (8% Max)
1250-4c Superelevation Rates (6% Max)
1250-5 Superelevation Rates for Intersections and Low-Speed Urban Roadways
1250-6a Superelevation Transitions for Highway Curves
1250-6b Superelevation Transitions for Highway Curves
1250-6c Superelevation Transitions for Highway Curves
1250-6d Superelevation Transitions for Highway Curves
1250-6e Superelevation Transitions for Highway Curves
1250-7a Superelevation Transitions for Ramp Curves
1250-7b Superelevation Transitions for Ramp Curves
1260-1 Design Stopping Sight Distance
1260-2 Design Stopping Sight Distance on Grades
1260-3 Stopping Sight Distance on Grades
1260-4 Stopping Sight Distance: Crest Vertical Curves
1260-5 Sight Distance: Crest Vertical Curve
1260-6 Stopping Sight Distance for Sag Vertical Curves
1260-7 Sight Distance: Sag Vertical Curve
1260-8 Horizontal Stopping Sight Distance
1260-9 Sight Distance: Horizontal Curves
1260-10 Sight Distance: Overlapping Horizontal and Crest Vertical Curves
1260-11 Existing Stopping Sight Distance
1260-12 Passing Sight Distance
1260-13 Passing Sight Distance: Crest Vertical Curve Calculations
1260-14 Passing Sight Distance: Crest Vertical Curves
1260-15 Decision Sight Distance
1270-1 Climbing Lane Example
1270-2a Speed Reduction Warrant: Performance for Trucks
1270-2b Speed Reduction Warrant Example
1270-3 Auxiliary Climbing Lane
1270-4 Passing Lane Example
1270-5 Length of Passing Lanes
1270-6 Passing Lane Configurations
1270-7 Buffer Between Opposing Passing Lanes
1270-8 Auxiliary Passing Lane
1270-9 Emergency Escape Ramp Example
1270-10 Emergency Escape Ramp Length
1270-11 Rolling Resistance (R)
1270-12 Typical Emergency Escape Ramp

1270-13 Chain Up/Chain Off Area
1300-1 Intersection Design Considerations
1300-2 Median U-Turn Intersection Example
1300-3 Restricted Crossing U-Turn Intersection Example with Stop-control
1300-4 Displaced Left Turn Intersection Example
1310-1 Lane Alignment Taper Rate
1310-2 Ramp Terminal Intersection Details
1310-3 Median at Two-Way Ramp Terminal
1310-4 Intersection Balance Example
1310-5 Diamond Interchange With Advance Storage
1310-6 Initial Ranges for Right-Turn Corner (Simple Curve-Taper)
1310-7a Left-Turn Storage Guidelines: Two-Lane, Unsignalized
1310-7b Left-Turn Storage Guidelines: Four-Lane, Unsignalized
1310-8a Left-Turn Storage Length: Two-Lane, Unsignalized (40 mph)
1310-8b Left-Turn Storage Length: Two-Lane, Unsignalized (50 mph)
1310-8c Left-Turn Storage Length: Two-Lane, Unsignalized (60 mph)
1310-9 Left-Turn Storage With Trucks (ft)
1310-10a Median Channelization: Widening
1310-10b Median Channelization: Median Width 11 ft or More
1310-10c Median Channelization: Median Width 23 ft to 26 ft
1310-10d Median Channelization: Median Width of More Than 26 ft
1310-10e Median Channelization: Minimum Protected Storage
1310-10f Median Channelization: Two-Way Left-Turn Lane
1310-11 Right-Turn Lane Guidelines
1310-12 Right-Turn Pocket and Right-Turn Taper
1310-13 Right-Turn Lane
1310-14 Acceleration Lane
1310-15a Traffic Island Designs
1310-15b Traffic Island Designs: Compound Curve
1310-15c Traffic Island Designs
1310-16 U-Turn Spacing
1310-17 U-Turn Roadway
1310-18 U-Turn Median Openings
1310-19a Sight Distance at Intersections
1310-19b Sight Distance at Intersections
1320-1 Suggested Initial Design Ranges
1320-2 Radii-Speed Relationship on Approach Legs and R Value Relationships
1320-3 Intersection Sight Distance
1330-1 Responsibility for Facilities

1330-2 Example Continuous Green “T” (CGT) Intersection Layout
1330-3 Left-Turn Lane Configuration Examples
1330-4 Basic Level Clear Space for Pedestrian Pushbuttons
1330-5a Example Basic Perpendicular Ramp PPB Level Clear Space
1330-5b Example Basic Parallel Ramp PPB Level Clear Space
1330-6 Recommended Features for Intersections Near Rail Crossings
1330-7 Standard Intersection Movements, Head Numbers, and Phase Operation
1330-8 Detector Numbering Examples
1330-9a Signal Display Placements – Key to Diagrams
1330-9b Signal Displays for Single Lane Approach
1330-9c Signal Display Mounting Locations for Multi-Lane Approaches
1330-9d Signal Displays for Dedicated Left Turn Lanes
1330-9e Signal Displays for Shared Through-Left Lanes – Multiple Through Lanes
1330-9f Signal Displays for Shared Through-Right Lanes
1330-9g Signal Displays for Dedicated Right Turn Lanes
1330-9h Signal Displays for Multiple Turn Lanes
1330-10 Example Signal Display Placement for Skew Intersection
1330-11 Signal Display Maximum Heights
1330-12 Pedestrian Display Placement Requirements
1330-13 PPB Placement Requirements
1330-14a PPB Placement on Vertical Shaft Poles
1330-14b PPB Placement on Large Signal Standards
1330-15 Signal Display Surface Areas
1330-16 Timber Strain Pole Classes
1330-17 Fixed Vehicle Detection Placement
1330-18 Decision Zone Detection Placement
1330-19 Video Detector Placement
1330-20 Signal Display Layout for Rail Crossings
1330-21 Conduit and Conductor Sizes
1330-22 Phase Diagrams: Four-Way Intersections
1330-23 Phase Diagrams: Three-Way Intersections
1330-24 Phasing at Railroad Crossings
1340-1 Driveway Design Template SU-30 and Smaller
1340-2 Driveway Design Template SU-30 and Larger
1340-3 Driveway Sight Distance
1350-1 Sight Distance at Railroad Crossing
1350-2 Typical Pullout Lane at Railroad Crossing
1360-1 Basic Interchange Patterns
1360-2 Interchange Spacing

1360-3 Minimum Ramp Connection Spacing
1360-4 Ramp Design Speed
1360-5 Maximum Ramp Grade
1360-6 Ramp Widths
1360-7a Lane Balance
1360-7b Lane Balance
1360-8 Main Line Lane Reduction Alternatives
1360-9 Acceleration Lane Length
1360-10 Deceleration Lane Length
1360-11a Gore Area Characteristics
1360-11b Gore Area Characteristics
1360-12 Length of Weaving Sections
1360-13a On-Connection: Single-Lane, Tapered
1360-13b On-Connection: Single-Lane, Parallel
1360-13c On-Connection: Two-Lane, Parallel
1360-13d On-Connection: Two-Lane, Tapered
1360-14a Off-Connection: Single-Lane, Tapered
1360-14b Off-Connection: Single-Lane, Parallel
1360-14c Off-Connection: Single-Lane, One-Lane Reduction
1360-14d Off-Connection: Two-Lane, Tapered
1360-14e Off-Connection: Two-Lane, Parallel
1360-15a Collector-Distributor: Outer Separations
1360-15b Collector Distributor: Off-Connections
1360-15c Collector Distributor: On-Connections
1360-16 Loop Ramp Connections
1360-17 Temporary Ramps
1360-18 Interchange Plan
1410-1 Minimum Traveled Way Widths for Articulated Buses
1410-2 Typical HOV Lane Sections
1410-3 Roadway Widths for Two-Lane Ramps With an HOV Lane
1410-4a Single-Lane Ramp Meter With HOV Bypass
1410-4b Two-Lane Ramp Meter With HOV Bypass
1410-5a Enforcement Area: One Direction Only
1410-5b Enforcement Area: Median
1430-1 Bus Zone Dimensions
1430-2 Pullout for Bus Stop along a Road
1430-3 Bus Stop Pullouts: Arterial Streets
1430-4 Bus Zone and Pullout After Right Turn
1430-5 Bus Stop Accessibility Features

1430-6 Bus Berth Design
1430-7 Design Alternative for a Combination of Bus Berths at a Platform
1510-1 Pedestrian Circulation Paths
1510-2 Relationship Between Pedestrian Circulation Paths and Pedestrian Access Routes
1510-3 Obstructed Pedestrian Access Route
1510-4 Beveling Options
1510-5 Surface Discontinuities (Noncompliant)
1510-6 Sidewalks With Buffers
1510-7 Typical Sidewalk Designs
1510-8 Typical Driveways
1510-9 Perpendicular Curb Ramp
1510-10 Perpendicular Curb Ramp Common Elements
1510-11 Parallel Curb Ramp
1510-12 Parallel Curb Ramp Common Elements
1510-13 Combination Curb Ramp
1510-14 Typical Curb Ramp Drainage
1510-15 Unmarked Crosswalks
1510-16 Marked Pedestrian Crossing
1510-17 Vacant
1510-18 Midblock Pedestrian Crossing
1510-19 Obstructed Line of Sight at Intersection
1510-20 Improved Line of Sight at Intersection
1510-21 Curb Extension Examples
1510-22 Raised Islands With Curb Ramps and Pedestrian Cut-Throughs
1510-23 Typical Pedestrian Pushbutton
1510-24 Clear Space Parallel and Forward Approach Orientation
1510-25 Accessible Pedestrian Signal Pushbutton Stations
1510-26 Pedestrian Railroad Crossings
1510-27 Pedestrian Railroad Warning Device
1510-28 Pedestrian Bridges
1510-29 Pedestrian Tunnel
1510-30 Access Ramp With Accessible Handrails
1510-31 Work Zones and Pedestrian Facilities
1515-1 Shared-Use Path
1515-2 Bicycle Design Speeds
1515-3 Two-Way Shared-Use Path: Independent Alignment
1515-4a Two-Way Shared-Use Path: Adjacent to Roadway (≤ 35 mph)
1515-4b Two-Way Shared-Use Path: Adjacent to Roadway (> 35 mph)
1515-4c Two-Way Shared-Use Path: Attached to Roadway (>35 mph)

1515-5 Shared-Use Path Side Slopes and Railing
1515-6 Shared-Use Path Landing Profile
1515-7 Shared-Use Path Landing and Rest Area
1515-8 Typical Redesign of a Diagonal Midblock Crossing
1515-9 Adjacent Shared-Use Path Intersection
1515-10 Roadway Crossing Refuge Area
1515-11 Shared-Use Path Bridge and Approach Walls
1515-12 Bridge and Pedestrian Rail
1515-13 Shared-Use Path in Limited Access Corridor
1515-14a Stopping Sight Distance for Downgrades
1515-14b Stopping Sight Distance for Upgrades
1515-15 Minimum Lengths for Crest Vertical Curves
1515-16 Lateral Clearance for Horizontal Curves
1520-1 Raised and Curb-Separated Bike Facility
1520-2 Separated Buffered Bike Lane
1520-3 Buffered Bike Lane
1520-4 Bike Lane
1520-5 Shared Lane Markings
1520-6a Bicycle Facility Selection Chart – Interested, but Concerned Cyclists
1520-6b Bicycle Facility Selection Chart – Confident Cyclists
1520-7 Approach Through Lanes
1520-8 Bike Box and Intersection Crossing Markings
1520-9 Two-Stage Left-Turn Queue Box
1520-10 Median Refuge Island for Cyclists
1520-11 Length of Solid Green Pavement Marking Preceding Conflict Area
1520-12 At-Grade Railroad Crossings
1520-13 Barrier Adjacent to Bicycle Facilities
1520-14a Bike Facility Crossing On and Off Ramps
1520-14b Bicycle Facility Crossing Single Lane On Ramp
1520-14c Bicycle Facility Crossing Option for Dual Lane On-Ramp Configuration
1520-14d Bicycle Facility Crossing Option for Dual Off-Ramp
1600-1 City and State Responsibilities and Jurisdictions
1600-2 Design Clear Zone Distance Table
1600-3 Design Clear Zone Inventory Form (# 410-026 EF)
1600-4 Recovery Area
1600-5 Design Clear Zone for Ditch Sections
1600-6 Guidelines for Embankment Barrier
1600-7 Mailbox Location and Turnout Design
1600-8 Glare Screens

1610-1	Concrete Barrier Placement Guidance: Assessing Impacts to Wildlife
1610-2	Traffic Barrier Locations on Slopes
1610-3	Longitudinal Barrier Deflection
1610-4	Longitudinal Barrier Flare Rates
1610-5	Barrier Length of Need on Tangent Sections
1610-6	Barrier Length of Need
1610-7	Barrier Length of Need on Curves
1610-8	W-Beam Guardrail Trailing End Placement for Divided Highways
1610-9	Beam Guardrail Installation on 6:1 to 10:1 Slopes
1610-10	Beam Guardrail Post Installation
1610-11	Vacant
1610-12	Guardrail Connections
1610-13	Transitions and Connections
1610-14a	Median Cable Barrier Placement
1610-14b	Roadside Cable Barrier Placement
1610-15	Cable Barrier Placement for Divided Highways
1610-16	Concrete Barrier Shapes
1610-17	Type 7 Bridge Rail Upgrade Criteria
1610-18	Thrie Beam Rail Retrofit Criteria
1620-1a	Impact Attenuator System Comparison
1620-1b	Impact Attenuator Systems: Universal TAU II and QuadGuard Configurations
1620-2	Impact Attenuator Distance Beyond Length of Need
1710-1	WSDOT Safety Rest Area
1710-2	WSDOT's SRA Project and Programming Roles
1710-3	Additional Safety Rest Area Resources
1710-4	Roadside Facilities Level of Development
1710-5	Typical Truck Storage
1710-6	WSDOT Safety Rest Area Building – Adaptive Reuse Historic Preservation
1720-1	Truck Weigh Site: Multilane Highways
1720-2	Truck Weigh Site: Two-Lane Highways
1720-3	Vehicle Inspection Installation
1720-4	Minor Portable Scale Site
1720-5	Major Portable Scale Site
1720-6	Small Shoulder Site
1720-7	Large Shoulder Site
1720-8	MOU Related to Vehicle Weighing and Equipment: Inspection Facilities on State Highways

Chapter 100 Manual Description

100.01 Purpose
100.02 Presentation and Revisions
100.03 Practical Solutions
100.04 Manual Applications
100.05 Manual Use
100.06 Manual Organization

100.01 Purpose

The Washington State Department of Transportation (WSDOT) has developed the *Design Manual* to reflect policy, outline a uniformity of methods and procedures, and communicate vital information to its employees and others who develop projects on state highways. When properly used, the manual will facilitate the development of a highway system consistent with the needs of the multimodal traveling public.

WSDOT designers are required to comply with the *Design Manual*. The Federal Highway Administration (FHWA) has agreed to approve designs that follow guidance in the *Design Manual*; therefore, adherence to the guidance presented is not optional for state highway projects.

The information, guidance, and references contained herein are not intended as a substitute for sound engineering judgment. The *Design Manual* is not a comprehensive textbook on highway engineering, nor does it attempt to cover all the possible scenarios Washington's highways present. It is recognized that some situations encountered are beyond the scope of this presentation.

If you have design questions not answered by the *Design Manual*, contact the Headquarters (HQ) Design Office.

100.02 Presentation and Revisions

The *Design Manual* is available on the Internet. It can be accessed through the:

- WSDOT Home Page:
  www.wsdot.wa.gov/
- Design Policy Web Page:
  www.wsdot.wa.gov/design/policy/
- Active *Design Manual* Revisions Web Page:
  www.wsdot.wa.gov/design/manual/activerevisions.htm
- Publications Services Web Page:
  www.wsdot.wa.gov/publications/manuals/index.htm

The online version of the manual enables you to conduct a word search of the entire manual. Opening an individual chapter is faster, but a word search is limited to that chapter.

The *Design Manual* is continually revised to reflect changing processes, procedures, regulations, policies, and organizations. Feedback from users is encouraged to improve the manual for everyone. Comments may be submitted by any method that is convenient for you. There is a comment form in the front of the manual, or comments may be made via the contact names on the Design Policy Internet page (see link above). Note that the Design Policy Internet page includes a link to an errata page, which provides a list of known technical errors in the manual. Manual users are encouraged to view this page on a regular basis.

A contents section lists all chapters and the major headings of the sections/pages. The exhibits section lists all the exhibits in the manual.

Most chapters include a list of references, including laws, administrative codes, manuals, and other publications, which are the basis for the information in the chapter. The definitions for terms used in the *Design Manual* are found in the Glossary.

100.03 Practical Solutions

WSDOT deploys Practical Solutions to enable more flexible and sustainable transportation investment decisions. It encourages this by: (1) increasing the focus on addressing identified performance gaps (needs) throughout all phases of development, and (2) engaging local stakeholders at the earliest stages of scope definition to ensure their input is included at the right stage of the solution development process. Practical Solutions includes one or a combination of strategies, including, but not limited to, operational improvements, off-system solutions, transportation demand management, and incremental strategic capital solutions. (See Chapter 1100 for more information.)

100.04 Manual Applications

Design Manual guidance is provided to encourage the statewide uniform application of design details under normal conditions. It also guides designers through the project development process used by WSDOT. The *Design Manual* is used by the department to:

- Interpret current design principles, including American Association of State Highway and Transportation Officials (AASHTO) and other appropriate policy sources, findings, and federal and state laws.
- Develop projects that address modal and community performance needs.
- Balance the competing performance needs of highway construction projects.
- Design for low-cost solutions.

The *Design Manual* is designed to allow for flexibility in design for specific and unusual situations. For unusual circumstances, the manual provides mechanisms for documenting the reasons for the choices made.

The *Design Manual* is developed for use on Interstate and state highways and may not be suitable for projects on county roads or city streets.

100.05 Manual Use

The WSDOT *Design Manual* is intended to be used for design of department-owned facilities, especially the transportation facilities associated with state highways as designated by RCW 47.17.

For state highway routes, projects are designed using the *Design Manual* practical design approach (see Chapter 1100 and Division 11). If WSDOT guidance is not used on a project, appropriate documentation and approvals are required (see Chapters 300 and 1100).

When WSDOT designs facilities that will be turned over to local jurisdictions, those facilities are to be designed using appropriate local geometric design criteria.

When local jurisdictions design any element of state highway facilities, the *Design Manual* must be used. Local jurisdictions are free to adopt this manual for their local criteria or to develop their own specialized guidance for facilities not on state highway routes.

100.06 Manual Organization

The *Design Manual* is divided into a series of divisions that address a portion of the project development and design processes. The divisions are composed of chapters that address the general topic in detail and are, in some cases, specific to a particular discipline.

Division 1 – General Information: Presents general background on planning, managing project delivery, project development, and programming.

- **Chapter 100 – Manual Description:** Chapter content/resources within the *Design Manual*.
- **Chapter 110 – Design-Build Projects:** How the *Design Manual* applies to design-build projects: includes terminology and reference to design-build contract documents.

Division 2 – Hearings, Environmental, and Permits: Provides the designer with information about the public involvement and hearings process, the environmental documentation process, and the permit process.

- **Chapter 210 – Public Involvement and Hearings:** Developing a project-specific public involvement plan; the ingredients of an effective public involvement plan; and methods for public involvement.
- **Chapter 225 – Environmental Coordination:** Provides a summary of the relevant provisions in the *Environmental Manual*. Gives designers a brief overview and direction to environmental resources.

Division 3 – Project Documentation: Provides designers with information on value engineering, traffic analysis, design documentation, and approvals.

- **Chapter 300 – Design Documentation, Approval, and Process Review:** Building the Project File (PF) and the Design Documentation Package (DDP) and recording the recommendations and decisions that lead to a project by preserving the documents from the planning, scoping, programming, and design phases (includes permits, approvals, contracts, utility relocation, right of way, advertisement and award, and construction). Links to websites to download documentation templates.

- **Chapter 301 – Design and Maintenance Coordination – Best Practices:** Means and methods for coordinating design with maintenance concerns and needs.
- **Chapter 305 – Project Management:** Brief description and links to WSDOT project management resources.
- **Chapter 310 – Value Engineering:** A systematic, multidisciplinary process study early in the project design stage to provide recommendations to improve scope, functional design, constructability, environmental impacts, or project cost—required by federal law for high-cost, complex projects.
- **Chapter 320 – Traffic Analysis:** Procedural guidance and general requirements for conducting traffic analyses.
- **Chapter 321 – Sustainable Safety Analysis:** Informational and procedural guidance for conducting safety analyses, within the current extent of the applications.

Division 4 – Surveying: Includes criteria for surveying, mapping, and monumentation requirements.

- **Chapter 400 – Surveying and Mapping:** The procedures within WSDOT for project surveying.
- **Chapter 410 – Monumentation:** The requirements and procedures for Monumentation.

Division 5 – Right of Way and Access Control: Provides guidance on right of way considerations; interchange justification reports; limited/managed access; and fencing.

- **Chapter 510 – Right of Way Considerations:** The right of way and easement acquisition process.
- **Chapter 520 – Access Control:** WSDOT Access Control program information.
- **Chapter 530 – Limited Access Control:** Clarification on full, partial, and modified limited access control.
- **Chapter 540 – Managed Access Control:** The classes of managed access highways and the access connection permitting process.
- **Chapter 550 – Interchange Justification Report:** The process for access point revisions on limited access controlled highways and the steps for producing an interchange justification report.
- **Chapter 560 – Fencing:** The purpose of fencing, types of fencing, and fencing design criteria.

Division 6 – Soils and Paving: Presents guidance for investigating soils, rock, and surfacing materials; estimating tables; and guidance and criteria for the use of geosynthetics.

- **Chapter 610 – Investigation of Soils, Rock, and Surfacing Materials:** The requirements for qualifying a materials source, geotechnical investigations, and the documentation to be included in the Project File.
- **Chapter 620 – Design of Pavement Structures:** Estimating tables for the design of pavement structures.
- **Chapter 630 – Geosynthetics:** The types/applications of geosynthetic drainage, earthwork, erosion control, and soil reinforcement materials.

Division 7 – Structures: Provides guidance for the design of structures for highway projects, including site data for structures, bridges, retaining walls, and noise walls.

- **Chapter 700 – Project Development Roles and Responsibilities for Projects With Structures:** WSDOT's project development process: roles and responsibilities for projects with structures during the project development phase of a project.
- **Chapter 710 – Site Data for Structures:** Information required by the HQ Bridge and Structures Office to provide structural design services.
- **Chapter 720 – Bridges:** Basic design considerations for developing preliminary bridge plans and guidelines on basic bridge geometric features.
- **Chapter 730 – Retaining Walls and Steep Reinforced Slopes:** Design principles, requirements, and guidelines for retaining walls and steep reinforced slopes.
- **Chapter 740 – Noise Barriers:** Factors considered when designing a noise barrier.

Division 8 – Hydraulics: Addresses the issue of hydraulics and serves as a guide to highway designers to identify and consider hydraulic-related factors that may impact the design.

- **Chapter 800 – Hydraulic Design:** Hydraulic considerations for highway projects involving flood plains, stream crossings, channel changes, and groundwater.

Division 9 – Roadside Development: Provides guidance on the portion of state highways between the traveled way and the right of way boundary.

- **Chapter 900 – Roadside Development:** Managing the roadside environment, including the area between the traveled way and the right of way boundary, unpaved median strips, and auxiliary facilities such as rest areas, wetlands, and stormwater treatment facilities.
- **Chapter 950 – Public Art:** Policies and procedures for including public art in state transportation corridors.

Division 10 – Traffic Safety Elements: Introduces the designer to traffic safety elements such as work zone traffic control, signing, delineation, illumination, traffic control signals, and Intelligent Transportation Systems (ITS).

- **Chapter 1010 – Work Zone Safety and Mobility:** Planning, design, and preparation of highway project plans that address work zone safety and mobility requirements.
- **Chapter 1020 – Signing:** The use of signing to regulate, warn, and guide motorists.
- **Chapter 1030 – Delineation:** The use of pavement markings to designate safe traffic movement.
- **Chapter 1040 – Illumination:** Illumination design on state highway construction projects.
- **Chapter 1050 – Intelligent Transportation Systems (ITS):** Applying computer and communication technology to optimize the safety and efficiency of the highway system.

Division 11 – Practical Design: Provides practical design guidance for WSDOT projects.

- **Chapter 1100 – Practical Design:** Includes an overview and description of the WSDOT Practical Solutions initiative, the practical design process, and the relevant chapter information necessary to complete each process step.

- **Chapter 1101 – Need Identification:** Includes guidance on accurate and concise identification of project needs for practical design.
- **Chapter 1102 – Context Identification:** Guidance provided to help determine the highway's land use context and transportation context.
- **Chapter 1103 – Design Control Selection:** Provides guidance on design controls used in WSDOT projects.
- **Chapter 1104 – Alternatives Analysis:** Discusses how information determined from planning phases and *Design Manual* chapters is utilized in alternative solution formation, and how to evaluate the alternative solutions developed.
- **Chapter 1105 – Design Element Selection:** Provides guidance on selecting design elements for projects.
- **Chapter 1106 – Design Element Dimensions:** Discusses the practical design approach to selecting design element dimensions.
- **Chapter 1120 – Preservation Projects:** Provides scoping links and elements and features to be evaluated in preservation projects.

Division 12 – Geometrics: Covers geometric plan elements; horizontal alignment; lane configurations and pavement transitions; geometric profile elements; vertical alignment; geometric cross sections; and sight distance.

- **Chapter 1210 – Geometric Plan Elements:** The design of horizontal alignment, lane configuration, and pavement transitions.
- **Chapter 1220 – Geometric Profile Elements:** The design of vertical alignment.
- **Chapter 1230 – Geometric Cross Section – Basics:** Roadway cross section introductory chapter; guide to other cross section chapters; provides jurisdictional guidance.
- **Chapter 1231 – Geometric Cross Section – Highways:** Geometric cross section guidance for all highways except freeways.
- **Chapter 1232 – Geometric Cross Section – Freeways:** cross section guidance for freeways and Interstates.
- **Chapter 1238 – Geometric Cross Section – Streetside and Parking**: provides information on parking and streetside elements.
- **Chapter 1239 – Geometric Cross Section – Shoulders, Side Slopes, Curbs, and Medians:** Provides information on geometric cross section components common to many facility types. Cross section elements include: shoulders, medians and outer separations, side slopes, and curbing
- **Chapter 1240 – Turning Roadways:** Widening curves to make the operating conditions comparable to those on tangent sections.
- **Chapter 1250 – Cross Slope and Superelevation:** Cross slope design information is provided as well as superelevating curves and ramps so design speeds can be maintained.
- **Chapter 1260 – Sight Distance:** Stopping, passing, and decision sight distance design elements.

- **Chapter 1270 – Auxiliary Lanes:** Auxiliary facilities such as climbing lanes, passing lanes, slow-vehicle turnouts, shoulder driving for slow vehicles, emergency escape ramps, and chain-up areas.

Division 13 – Intersections and Interchanges: Addresses the design considerations of at-grade intersections, roundabouts, road approaches, railroad grade crossings, and traffic interchanges.

- **Chapter 1300 – Intersection Control Type:** Guidance on preliminary intersection analysis and selection of control type.
- **Chapter 1310 – Intersections:** Designing intersections at grade, including at-grade ramp terminals.
- **Chapter 1320 – Roundabouts:** Guidance on the design of roundabouts.
- **Chapter 1330 – Traffic Control Signals:** The use of power-operated traffic control devices that warn or direct traffic.
- **Chapter 1340 – Driveways:** The application and design of road approaches on state highways.
- **Chapter 1350 – Railroad Grade Crossings:** The requirements for highways that cross railroads.
- **Chapter 1360 – Traffic Interchanges:** The design of interchanges on interstate highways, freeways, and other multilane divided routes.
- **Chapter 1370 – Median Crossovers:** Guidance on locating and designing median crossovers for use by maintenance, traffic service, emergency, and law enforcement vehicles.

Division 14 – HOV and Transit: Provides design guidance on HOV lanes and transit facilities.

- **Chapter 1410 – High-Occupancy Vehicle Facilities:** Evaluating and designing high-occupancy vehicle (HOV) facilities.
- **Chapter 1420 – HOV Direct Access:** Design guidance on left-side direct access to HOV lanes and transit facilities.
- **Chapter 1430 – Transit Facilities:** Operational guidance and information for designing transit facilities such as park & ride lots, transfer/ transit centers, and bus stops and pullouts.

Division 15 – Pedestrian and Bicycle Facilities: Provides guidance on pedestrian and bicycle facility design.

- **Chapter 1510 – Pedestrian Facilities:** Designing facilities that encourage efficient pedestrian access that meets ADA.
- **Chapter 1515 – Shared-Use Paths:** Guidance that emphasizes pedestrians are users of shared-use paths and accessibility requirements apply in their design.
- **Chapter 1520 – Roadway Bicycle Facilities:** Selecting and designing useful and cost-effective bicycle facilities.

Division 16 – Roadside Safety Elements: Addresses design considerations for the area outside the roadway, and includes clear zone, roadside hazards, safety mitigation, traffic barriers, and impact attenuator systems.

- **Chapter 1600 – Roadside Safety:** Clear zone design, roadside hazards to consider for mitigation, and some roadside safety features.
- **Chapter 1610 – Traffic Barriers:** Design of traffic barriers based on the design levels identified in the design matrices.
- **Chapter 1620 – Impact Attenuator Systems:** Permanent and work zone impact attenuator systems.

Division 17 – Roadside Facilities: Provides design guidance for the area outside the roadway, including rest areas and truck weigh sites.

- **Chapter 1710** – **Safety Rest Areas and Traveler Services**: Typical layouts for safety rest areas.
- **Chapter 1720 – Weigh Sites:** Guidance on designing permanent, portable, and shoulder-sited weigh sites.

Chapter 110 Design-Build Projects

110.01 General
110.02 Terminology and Language Used
110.03 Design and Documentation Responsibility
110.04 References

110.01 General

This chapter emphasizes that the *Design Manual* applies to the delivery methods of all Washington State Department of Transportation (WSDOT) capital projects, including design-build projects. Certain terms are defined to coincide with WSDOT design-build project delivery; however, it is beyond the scope of this manual to extensively define design-build projects. Design-build projects are based on their own contractual documents (such as a Request for Proposal), which present directive language intended to legally define the project and identify requirements and controls, roles and responsibilities, and procedures and outcomes.

Design-build is a method of project delivery in which WSDOT executes a single contract with one entity (the design-builder) for design and construction services to provide a finished product. In a traditional WSDOT design-bid-build contract, the design process is completed independent of the construction contract. Under WSDOT policy, the Basis of Design (see Chapters 1100 and 300) is approved prior to issuing an RFP.

Delivering a project using design-build contracting eliminates *very few steps* when compared to the typical WSDOT design-bid-build process. The same project work tasks and products are normally required whether performed by WSDOT or the design-builder. The timing, order, and level of task detail performed are what make design-build contracting different than design-bid-build. The design-build process may shift many tasks and responsibilities from WSDOT to the design-builder depending on the project's scope/risk analysis. The shift changes the order and development detail of the tasks and thus must be reflected in the process through contractual documents.

According to state law, to be considered for design-build designation in Washington State, a project must be greater than $2 million and provide the opportunity for one of the following:

- Highly specialized construction activities requiring significant input into the design.
- Greater innovation and efficiencies between the designer and the builder.
- Significant savings in project delivery time.

110.02 Terminology and Language Used

110.02(1) Application of Terminology

Several terms are encountered throughout the *Design Manual* that are not normally applicable to design-build project delivery. They are expanded in this chapter to provide appropriate meaning for design-build projects and design-build personnel. It is intended that design-build personnel acknowledge these expanded meanings and apply them throughout the manual, which will eliminate the need to restate them each time they are encountered.

design-builder The firm, partnership, joint venture, or organization that contracts with WSDOT to perform the work.

designer This term applies to WSDOT design personnel. Wherever "designer" appears in this manual, design-build personnel shall deem it to mean: Engineer of Record, Design Quality Assurance Manager, design-builder, or any other term used in the design-build contract to indicate design-build personnel responsible for the design elements of a design-build project, depending on the context of information being conveyed.

Project Engineer This term applies to WSDOT personnel. Wherever "Project Engineer" appears in this manual, the design-builder shall deem it to mean "Engineer of Record."

Request for Proposal (RFP) The document package issued by WSDOT requesting submittal of proposals for the project and providing information relevant to the preparation and submittal of proposals, including the instructions to proposers, contract documents, bidding procedures, and reference documents.

Additional terms are presented in the *Design Manual* Glossary.

110.02(2) Language Used for Design Flexibility

The *Design Manual* is primarily written for WSDOT engineering personnel; however, design-builders, local agencies, and developers also use it for state and local agency projects. Under WSDOT practical design, flexibility is encouraged to develop independent designs tailored to context and identified performance need. (See chapters in the 1100 series for more information about practical design policy and guidance.)

With the exclusion of this chapter, the *Design Manual* is intentionally written to avoid or minimize the use of directive words like "shall" and "should" in order to retain this important flexibility for the larger set of users.

In the case of design-build projects, design flexibility applies to the extent allowed by the contract. The design-builder shall refer to the project-specific RFP for design guidance. The RFP will identify design decisions and provide technical specifications relating to the project's design.

110.03 Design and Documentation Responsibility

In the traditional design-bid-build format, WSDOT bears the entire responsibility and risk for any design-related issues. As the owner, all responsibility for design decisions and conformance to standards rests with WSDOT.

For design-build projects, many design responsibilities shift to the design-builder once the Notice to Proceed is issued. WSDOT is still responsible for establishing the scope, performance measurements, and existing conditions of the site as part of preliminary design. Any preliminary design done by WSDOT would be filed and documented in the Design Documentation Package (DDP) and/or the Project File (PF), which are provided to the selected design-builder to maintain throughout the design-build project design phase and then returned to WSDOT for retention.

It is important to note that the design content presented in this manual has valid application based not on delivery method, but on practical design procedures and specified needs such as roadway and land use context, traffic volumes, and identified performance needs, as presented in Chapter 1100 (and other chapters).

It is also important to specify that design documentation is a requirement for WSDOT projects, regardless of delivery method. WSDOT still holds the valid requirement to have an organized design documentation file and as-constructed plans for future reference after the project is built.

Plan accuracy, conformance with established design guidelines, and constructability of the project rests with the design-builder.

The DDP and the PF include all the elements identified in the project RFP. The RFP specifies various DDP and PF submittals to WSDOT, identifying how each item will be submitted (report, plan sheet element, Basis of Design and design parameter element, and so on) and who is responsible for the development status (such as *complete, in progress,* or *not started*) of each item. The RFP also indicates that some of the DDP and PF items have components that were started by WSDOT and that the design-builder shall complete or update those item(s). It is the design-builder's responsibility to obtain copies of the information from WSDOT for use in completing the DDP and PF items.

The DDP and the PF require retention of original, signed documents—not copies.

The RFP typically specifies that the design-builder shall provide WSDOT with updates to the DDP and PF items throughout construction of the project.

For further guidance on design documentation and WSDOT acceptance thereof, see Chapter 300, the project RFP, and the Design Documentation Checklist.


110.04 References

110.04(1) Design-Build Guidance

The Design-Build Guidance Statements listed below are available at:
www.wsdot.wa.gov/projects/delivery/designbuild/

- Design Quality Control, Quality Assurance, and Quality Verification on Design-Build Projects
- Project Basic Configuration Development
- Use of Reference Documents on Design-Build Projects

Exhibit 110-1 Design Documentation Sequence for a Typical Design-Build Project



Notes:

- The Design Documentation Package (DDP) is started by WSDOT during scoping/pre-RFP design. The design-builder completes the DDP as the project proceeds.
- The design-builder shall refer to the RFP for specific review and approval processes. The RFP will specify procedures for design submittals, including notifications to WSDOT and the time allowed for reviews.
- WSDOT will review design submittals for conformance with requirements of the contract.

Chapter 210 Public Involvement and Hearings

210.01 General
210.02 References
210.03 Definitions
210.04 Public Involvement
210.05 Public Hearings
210.06 Environmental Hearing
210.07 Corridor Hearing
210.08 Design Hearing
210.09 Limited Access Hearing
210.10 Combined Hearings
210.11 Administrative Appeal Hearing
210.12 Follow-Up Hearing
210.13 Documentation

210.01 General

The Washington State Department of Transportation (WSDOT) strives to keep the public informed about transportation issues, involve the public in transportation decision making, and make transportation decisions based on the public's best interests.

One of the best ways to achieve WSDOT's goals is to collaborate with the public, community groups, and various agencies. These participants often have differing, and sometimes conflicting, perspectives and interests. In addition, many participants and organizations are not able to spend the time and effort required to fully engage in transportation decision making. Despite these challenges, active collaboration:

- Gives WSDOT access to important information and new ideas.
- Puts us in a position to help solve problems and resolve conflicts.
- Creates a sense of community.
- Fosters greater acceptance of projects.
- Helps us build and sustain a credible and trusting relationship with the public.
- Ultimately leads to transportation improvements that better meet the public's needs and desires.

When collaborating with the public about transportation projects or issues, WSDOT uses more formal techniques like public hearings, direct mail, and presentations to city councils and legislators; as well as less formal but equally important techniques, like telephone and e-mail discussions, meetings with community groups, media relations, and project Internet pages.

Law requires that many types of capital transportation projects go through a formal public hearing process; thus, the legal procedures necessary for public hearings is the primary focus of this chapter. Public involvement plans are briefly discussed, and referrals to WSDOT's communications resources are included to further guide their development and implementation.

210.02 References

(1) Federal/State Laws and Codes

United States Code (USC) Title 23, Highways, Sec. 128, Public hearings

USC Title 23, Highways, Sec. 771.111, Early coordination, public involvement, and project development

23 Code of Federal Regulations (CFR) 200.7, FHWA Title VI Policy

23 CFR 200.9(b)(4), Develop procedures for the collection of statistical data of participants and beneficiaries of state highway programs

23 CFR 200.9(b)(12), Develop Title VI information for dissemination to the general public

23 CFR 450.212, Public involvement

28 CFR Part 35, Nondiscrimination on the basis of disability in state and local government services

49 CFR Part 27, Nondiscrimination on the basis of disability in programs or activities receiving federal financial assistance

Americans with Disabilities Act of 1990 (ADA) (28 CFR Part 36, Appendix A)

Civil Rights Restoration Act of 1987

Executive Order 12898, Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations

Executive Order 13166, Improving Access to Services for Persons with Limited English Proficiency

Revised Code of Washington (RCW) 47.50, Highway Access Management

RCW 47.52, Limited Access Facilities

Section 504 of the Rehabilitation Act of 1973, as amended

Title VI of the Civil Rights Act of 1964

(2) Design Guidance

Design Manual, Chapter 225, for environmental references, and Division 5 chapters for access control and right of way references

Environmental Manual, M 31-11
www.wsdot.wa.gov/publications/manuals/m31-11.htm

WSDOT Headquarters (HQ) Access and Hearings Section Manager, (360) 705-7266
home page:
www.wsdot.wa.gov/design/accessandhearings

(3) Supporting Information

Improving the Effectiveness of Public Meetings and Hearings, Federal Highway Administration (FHWA) Guidebook

Public Involvement Techniques for Transportation Decision-Making, FHWA September 1996; provides tools and techniques for effective public involvement:
www.fhwa.dot.gov/reports/pittd/cover.htm

Relocation brochures: www.wsdot.wa.gov/realestate

WSDOT *Communications Manual* for public involvement:
www.wsdot.wa.gov/communications/

WSDOT Context Sensitive Solutions Internet site and national context sensitive site:
http://www.wsdot.wa.gov/design/policy/csdesign
www.contextsensitivesolutions.org/

210.03 Definitions

affidavit of publication A notarized written declaration stating that a ***notice of hearing*** (or ***notice of opportunity for a hearing***) was published in the legally prescribed manner.

affidavit of service by mailing A notarized written declaration stating that the limited access hearing packet was mailed at least 15 days prior to the hearing and entered into the record at the hearing.

auxiliary aids and services (1) Qualified interpreters, notetakers, transcription services, written materials, telephone handset amplifiers, assistive listening devices, assistive listening systems, telephones compatible with hearing aids, open and closed captioning, telecommunications devices for deaf persons (TDDs), videotext displays, or other effective methods for making aurally delivered materials available to individuals with hearing limitations; (2) Qualified readers, taped texts, audio recordings, Brailled materials, large print materials, or other effective methods for making visually delivered materials available to individuals with visual impairments; (3) Acquisition or modification of equipment or devices; (4) Other similar services and actions; and (5) Providing and disseminating information, written materials, and notices in languages other than English, where appropriate.

context sensitive solutions (CSS) *A collaborative, interdisciplinary approach that involves all stakeholders to develop a transportation facility that fits its physical setting and preserves scenic, aesthetic, historic, and environmental resources while maintaining safety and mobility. CSS is an approach that considers the total context within which a transportation improvement project will exist.** (See 210.02 and 210.04(2) for more information.)

*From *"Understanding Flexibility in Transportation Design – Washington,"* WSDOT, April 2005

court reporter A person with a license to write and issue official accounts of judicial or legislative proceedings.

findings and order A document containing the findings and conclusions of a limited access hearing approved by the Assistant Secretary, Engineering & Regional Operations (see 210.09(12) and (13)).

hearing An assembly to which the public is invited and at which participation is encouraged. Types of hearings include:

- ***administrative appeal hearing*** A formal process whereby a property owner may appeal WSDOT's implementation of access management legislation. The appeal is heard by an administrative law judge (ALJ), who renders a decision. (See Chapter 540 for administrative appeal hearing procedures.)

- ***combined hearing*** A hearing held when there are public benefits to be gained by combining environmental, corridor, design, and/or limited access subjects.
- ***corridor hearing*** A formal or informal hearing that presents the corridor alternatives to the public for review and comment before a commitment is made to any one route or location. This type of hearing is beneficial for existing corridors with multiple Improvement projects programmed over a long duration.
- ***design hearing*** A formal or informal hearing that presents the design alternatives to the public for review and comment before the selection of a preferred alternative.
- ***environmental hearing*** A formal or informal hearing documenting that social, economic, and environmental impacts have been considered and that public opinion has been solicited.
- ***limited access hearing*** A formal hearing that gives local public officials, owners of abutting properties, and other interested persons an opportunity to be heard about the limitation of access to the highway system.
- ***formal hearing format*** A hearing conducted by a moderator using a formal agenda, overseen by a hearing examiner, and recorded by a court reporter, as required by law. Limited access hearings require the use of the formal hearing format (see 210.05(3)).
- ***informal hearing format*** A hearing where oral comments are recorded by a court reporter, as required by law. An informal hearing often uses the "open house" format (see 210.04(1)(a)). A formal agenda and participation by a hearing examiner are optional.

hearing agenda An outline of the actual public hearing elements, used with formal hearings. (See 210.05(9)(a) for contents.)

Hearing Coordinator The HQ Access and Hearings Section Manager, (360) 705-7266.

hearing examiner An administrative law judge from the Office of Administrative Hearings, or a WSDOT designee, appointed to moderate a hearing.

hearing script A written document of text to be presented orally by department representatives at a hearing.

hearing summary Documentation prepared by the region and approved by Headquarters that summarizes environmental, corridor, and design hearings. (See 210.05(10) for content requirements.)

hearing transcript A document prepared by the court reporter that transcribes verbatim all oral statements made during the hearing, including public comments. This document becomes part of the official hearing record.

NEPA National Environmental Policy Act.

notice of appearance A form provided by WSDOT for anyone wanting to receive a copy of the findings and order and the adopted limited access plan (see 210.09(3) and (8)).

notice of hearing (or ***hearing notice***) A published advertisement that a public hearing will be held.

notice of opportunity for a hearing An advertised offer to hold a public hearing.

order of hearing The official establishment of a hearing date by the Director & State Design Engineer, Development Division.

prehearing packet A concise, organized collection of all necessary prehearing data, prepared by the region and approved by the HQ Access and Hearings Section Manager prior to the hearing (see 210.05(4) and Exhibit 210-3).

project management plan A formal, approved document that defines how the project is executed, monitored, and controlled. It may be in summary or detailed form and may be composed of one or more subsidiary management plans and other planning documents. For further information, see the *Project Management Online Guide*: http://www.wsdot.wa.gov/projects/projectmgmt/pmog.htm

public involvement plan A plan to collaboratively involve the public in decision making, tailored to the specific needs and conditions of a project and the people and communities it serves. It is often part of a broader communications plan.

relocation assistance program A program that establishes uniform procedures for relocation assistance that will ensure legal entitlements and provide fair, equitable, and consistent treatment to persons displaced by WSDOT-administered projects, as defined in the *Right of Way Manual*.

résumé An official notification of action taken by WSDOT following adoption of a findings and order (see 210.09(14)).

SEPA State Environmental Policy Act.

study plan A term associated with environmental procedures, this plan proposes an outline or "road map" of the environmental process to be followed during the development of a project that requires complex NEPA documentation. (See 210.06 and the *Environmental Manual*.)

210.04 Public Involvement

Developing and implementing an effective plan for collaboration with the public:

- Is critical to the success of WSDOT's project delivery effort.
- Provides an opportunity to understand and achieve diverse community and transportation goals.

Effective public involvement must begin with clearly defined, project-related goals that focus on specific issues, specific kinds of input needed, and specific people or groups that need to be involved. The more detailed a public involvement plan, the greater its chances of obtaining information WSDOT can use in decision making.

Transportation projects with high visibility or community issues or effects often attract the attention of a broad range of interested people. These types of projects will best benefit from early public involvement, which can influence the project's success and community acceptance.

Developing a profile (through demographic analysis) of the affected community is critical to achieving successful public involvement and should be the first order of business when developing a public involvement plan. The profile will enable the department to tailor its outreach efforts toward the abilities and needs of the community.

Individuals from minority and ethnic groups and low-income households, who are traditionally underserved by transportation, often find participation difficult. While these groups form a growing portion of the population, particularly in urban areas, historically they have experienced barriers to participation in the public decision-making process and are therefore underrepresented. These barriers arise from both the historical nature of the public involvement process and from cultural, linguistic, and economic differences. For example, a community made up of largely senior citizens (with limited mobility/automobile usage) may mean:

- Meetings/open houses are planned in locations easily accessible to them, such as senior centers and neighborhood community centers.
- Meetings are scheduled in the mornings or midday to accommodate individuals who prefer not to leave home after dark.
- Meetings are scheduled in the evenings to accommodate persons who work during the day.

A project's affected area might consist of a population with limitations in speaking or understanding English. This may entail:

- Developing/disseminating materials in other languages, as appropriate.
- Having a certified translator on hand at the meetings.

Extra effort may be needed to elicit involvement from people unaccustomed to participating in the public involvement process. They often have different needs and perspectives than those who traditionally participate in transportation decision making, and they may have important, unspoken issues that should be heard. They not only may have greater difficulty getting to jobs, schools, recreation, and shopping than the population at large, but also they are often unaware of transportation proposals that could dramatically change their lives.

NEPA and SEPA environmental policies and procedures are intended to provide relevant environmental information to public officials, agencies, and citizens, and allow public input to be considered before decisions are made. There are also various other laws, regulations, and policies that emphasize public involvement, including 23 CFR, Title VI of the Civil Rights Act, the Americans with Disabilities Act, and Executive Orders 12898 and 13166.

WSDOT's collaborative process with the public should be open, honest, strategic, consistent, inclusive, and continual. Initiating a project in an atmosphere of collaboration and partnership can go a long way toward providing equal opportunities for all parties (local, state, tribal, private, nonprofit, or federal) to participate in a project vision. This collaboration requires an intensive communications effort that is initiated during project visioning and extends through construction and eventual operation of the facility.

Department specialists in public communications, environmental procedures, traffic engineering, real estate services, and limited access control are routinely involved with public outreach efforts and project hearings. Depending on the scale and complexity of a project, the region is encouraged to engage the participation of interdisciplinary experts when developing a public involvement plan and communicating project details.

(1) Public Involvement Plan

The region develops a public involvement plan for its own use and guidance. To engage the public, share the decision-making process, identify issues, and resolve concerns, the region communicates with the affected community through group presentations, open house meetings, newspaper articles, fliers, and other methods. The public involvement plan includes methods that will elicit the best participation from the community, including traditionally underrepresented groups.

Developing an effective public involvement plan is a strategic effort. WSDOT must identify audiences, messages, strategies, and techniques that will meet the unique needs of a proposed transportation project, as well as the needs of the public.

The ultimate goal of the public involvement plan is to allow members of the public opportunities throughout the process to:

- Learn about the project.
- Provide information and options.
- Collaborate.
- Provide input intended to influence WSDOT decisions.

The plan will outline ways to identify and involve the communities affected by the project; provide them with accessible information through reader-friendly documents, graphics, plans, and summaries; and involve them in decision making.

An effective public involvement plan:

- Is tailored to the project.
- Encourages interactive communication.
- Demonstrates to residents that their input is valued and utilized.
- Includes all affected communities.
- Identifies and resolves issues early in the project development process.
- Ensures public access to relevant and comprehensible information.
- Informs the public of the purpose, need for, and benefits of the proposed action.
- Informs the public about the process that will be used to make decisions.
- Gains public support.
- Provides equal opportunity, regardless of disability, race, national origin, color, gender, or income.

The region Communications and Environmental offices can provide expertise in developing a public involvement plan tailored to a specific project. The HQ Access and Hearings Section specializes in procedures for public hearings. Real Estate Services personnel can provide expertise regarding acquisition, relocation assistance, and other related programs. Enlisting the support of these groups is essential to the success of WSDOT projects.

WSDOT recognizes local, state, federal, and tribal staff and elected officials as active sponsors of proposed projects. Those officials might help develop and implement the public involvement plan. Early and continued contact with these resources is key to the success of a project.

The public involvement plan might include:

- Objectives.
- Strategies.
- Tactics (or a list of proposed activities).
- Proposed time schedule to accomplish each project.
- Methods to track public comments.
- Methods used to consider comments during the decision-making process, including follow-up procedures.
- Personnel, time, and funds needed to carry out the plan.
- Identification of the project partners and stakeholders.

Early use of demographics can help identify the public to be involved. After identification, a variety of methods can be chosen to encourage the most effective public involvement. This might include (directly or indirectly) any or all of the following:

- Adjacent property owners and tenants
- Indian tribes
- Low-income groups
- Minority groups
- Cooperating and participating agencies
- Local, state, and federal government staff and elected officials
- Community groups such as clubs, civic groups, business groups, environmental groups, labor unions, disability advocacy groups, and churches
- Commuters and the traveling public
- Emergency and utility service providers
- Adjacent billboard owners and clients
- The general public and others known to be affected
- Others expressing interest

The following are examples of common outreach methods:

- Public and open house meetings
- Drop-in information centers or booths
- Advisory committee meetings
- Design workshops
- Meetings with public officials
- Individual (one-on-one) meetings
- Meetings with community groups
- Project Internet pages
- WSDOT project e-mail alert lists
- Surveys
- Questionnaires
- Telephone hot lines
- Using established media relations and contacts
- Internet blogs
- Direct mail

- Individual e-mails and letters
- Advisory committees and groups
- Public hearings

(a) **Public Meetings and Open Houses**

Public meetings range from large informational workshops to small groups using one-on-one meetings with individuals. They are less formal than hearings. The region evaluates the desired outcome from a meeting, decides how the input will be tracked, and then plans accordingly.

- Open house meetings can be effective for introducing a project to the public and stimulating an exchange of ideas.
- Small meetings are useful for gaining information from community groups, underrepresented groups, neighborhood groups, and advisory committees.
- Workshop formats, where large groups are organized into small discussion groups, serve to maximize the participation of all attendees while discouraging domination by a few groups or individuals.

(b) **Follow-Up Procedures**

Effective public involvement is an ongoing collaborative exchange, and it is necessary to provide follow-up information several times during a large project to maintain a continuing exchange of information.

At significant stages, the region provides information about the project. Follow-up information conveys, as accurately as possible, how public input was considered during development of the project.

It may become necessary to revise the public involvement plan as the project evolves, conditions change, oppositional groups emerge, or new issues arise. Sometimes innovative methods must be used to ensure the inclusion of affected community members. This is especially important for underrepresented groups, such as minority and low-income groups, and in communities where a significant percentage of the affected population does not speak English. Consider the need for translators, interpreters, and providing written information in languages other than English. Reference information on limited English proficiency is provided in 210.04(2)(d). A resident advisory committee can often help identify community issues and concerns as well as recommend effective methods for public involvement.

(2) Public Involvement References

Following are a number of recommended publications, references, and training courses available to assist regions in developing public involvement plans for their projects.

(a) **WSDOT Project Management Online Guide**

A project's public involvement plan is an essential element of the overall project management plan. The WSDOT *Project Management Online Guide* is an Internet resource intended to support delivery of transportation projects through effective project management and task planning. The guide includes best practices, tools, templates, and examples to enhance the internal and external communication processes: www.wsdot.wa.gov/projects/projectmgmt/onlineguide/preconstruction.htm

(b) WSDOT Communications Intranet Page

The WSDOT Communications Intranet page provides guidance for effective communications. This resource includes a *Communications Manual*, key messaging, and WSDOT's communications philosophy, and is an excellent resource for developing a public involvement plan:
http://wwwi.wsdot.wa.gov/communications/

(c) Context Sensitive Solutions and Community Involvement

A proposed transportation project must consider both its physical aspects as a facility serving specific transportation objectives and its effects on the aesthetic, social, economic, and environmental values within a larger community setting. context sensitive solutions is a collaborative, interdisciplinary approach that involves the community in the development of a project. WSDOT's philosophy encourages collaboration and consensus-building as highly advantageous to all parties to help avoid delays and other costly obstacles to project implementation. WSDOT endorses the context sensitive solutions approach for all projects, large and small, from early planning through construction and eventual operation of the facility. For further information, see WSDOT Executive Order E 1028 on context sensitive solutions:
http://wwwi.wsdot.wa.gov/publications/policies/fulltext/1028.pdf
http://www.wsdot.wa.gov/design/policy/csdesign.htm
http://www.wsdot.wa.gov/design/policy/csdesignresources.htm

Additionally, the following HQ Design, Highways and Local Programs, and Environment Internet pages offer an excellent array of publications, training, and resources for public involvement:
www.wsdot.wa.gov/environment/ej/

(d) Federal Highway Administration References

Improving the Effectiveness of Public Meetings and Hearings, FHWA Guidebook, provides a variety of techniques and processes based on the practical community involvement experience of its authors:
www.ntl.bts.gov/docs/nhi.html

Public Involvement Techniques for Transportation Decision-Making, FHWA September 1996, provides tools and techniques for effective public involvement:
www.fhwa.dot.gov/reports/pittd/cover.htm

How to Engage Low-Literacy and Limited-English-Proficiency Populations in Transportation Decisionmaking, FHWA 2006, provides tools and techniques for identifying and including these populations:
www.fhwa.dot.gov/hep/lowlim/index.htm

23 CFR 630, Subpart J, Final Rule on Work Zone Safety and Mobility, Work Zone Public Information and Outreach Strategies. This Internet guide is designed to help transportation agencies plan and implement effective public information and outreach campaigns to mitigate the effects of road construction work zones:
www.ops.fhwa.dot.gov/wz/info_and_outreach/index.htm

(3) Legal Compliance Statements

All public announcements shall include the required statements relative to the Americans with Disabilities Act of 1990 (ADA) and Title VI legislation. The region Communications Office and the HQ Communications Office Intranet page can provide the current version of both of these statements for legal compliance.

(a) **ADA Compliance**

The ADA and Section 504 of the Rehabilitation Act require WSDOT to inform the general public of its obligation to ensure programs and activities are accessible to and usable by persons with disabilities. For publications, the notice must provide a way to obtain the materials in alternative formats (such as Braille or taped). For public meetings and hearings, the notice must inform the public that reasonable accommodations can be made for a variety of needs.

The public meeting/hearing facility must always meet minimum ADA accessibility standards (such as ramps for wheelchair access, wide corridors, and accessible rest rooms). Additionally, WSDOT must provide, upon request, reasonable accommodations to afford equal access for persons with disabilities to information, meetings, and so on. Reasonable accommodations can include services and auxiliary aids such as qualified interpreters, transcription services, assistive listening devices for persons who are deaf or hard of hearing, or additional lighting for persons with visual impairments. The WSDOT Office of Equal Opportunity can provide assistance for reasonable accommodation provisions.

(b) **Title VI of the Civil Rights Act**

Title VI of the Civil Rights Act of 1964 requires that WSDOT inform the general public of its obligation to ensure that no person shall, on the grounds of race, color, national origin and/or sex, be excluded from participation in, be denied the benefits of, or be otherwise discriminated against under any of its federally funded programs and activities.

210.05 Public Hearings

By state and federal law, certain capital transportation projects propose actions that require a public hearing. The remainder of this chapter provides guidance on public hearing procedures.

The common types of public hearings associated with WSDOT projects include environmental, design, corridor, and limited access hearings, which are discussed in subsequent sections. The guidance in this chapter covers project actions that trigger a hearing and the procedures for effectively planning, conducting, and completing the hearing process.

The different types of public hearings follow similar steps for planning and preparation of project materials and information. These steps facilitate efficient reviews and approvals required for the hearing to proceed as planned. Special attention to the scheduling of deliverables and notifications leading up to the hearing help the process progress smoothly.

Public hearing formats are either *formal* or *informal*. Limited access hearings are always conducted as formal hearings. An informal process can be used for most other hearings.

Hearings are often conducted in accordance with NEPA/SEPA procedures for public involvement during the environmental documentation phase of the project. The region reviews the requirements for hearings during the early stages of project development and before completion of the draft environmental documents.

(1) Coordinating the Hearing

Preparing for and conducting a successful public hearing requires considerable coordination and effort. The best way to do this is by establishing a support team to identify and carry out the tasks and arrangements. It is crucial to identify and schedule tasks and deliverables well in advance of a public hearing. A project team might enlist the support of region specialists from Communications, Environmental, Government Relations, Right of Way, Real Estate, and Traffic offices, as well as the HQ Hearing Coordinator, HQ NEPA Policy staff, Office of Equal Opportunity, and others involved with the project. The following exhibits and narrative help identify whether a public hearing is required and how to prepare.

(2) Selecting the Hearing Type

By law, certain project actions or proposed conditions require that specific types of public hearings are conducted. Exhibit 210-1 identifies project conditions and their associated hearing requirements. If one or more of the conditions in Exhibit 210-1 occurs, a notice of opportunity for a hearing is required by federal and state law (USC Title 23 §771.111 and RCW 47.52) and by WSDOT policy. Consult the Hearing Coordinator in the HQ Access and Hearings Section, as well as project environmental specialists, for hearing requirements.

(3) Selecting the Hearing Format

The types of public hearing formats used by WSDOT are known as formal and informal. Hearing formats are different than hearing types. In some cases, the hearing type will dictate the required format, such as with limited access hearings. The following text and Exhibit 210-2 provide guidance on formats.

(a) **Formal Hearings**

A formal hearing is conducted by a moderator using a formal agenda, overseen by a hearing examiner, and recorded by a court reporter, as required by law. Limited access hearings and administrative appeal hearings require the use of the formal hearing format. For projects that require a formal public hearing, it is common for WSDOT to hold a public open house preceding the hearing.

The following are required for all formal hearings:

- Hearing notice with a fixed time and date (see 210.05(5) and (6))
- Fixed agenda and script
- Hearing examiner
- Hearing moderator (may be the hearing examiner)
- Court reporter

- Specified comment period
- Hearing summary (see 210.05(10))

In addition to providing oral comments, people can write opinions on the comment forms available at or after the hearing and submit them before the announced deadline.

(b) **Informal Hearings**

An informal hearing is also known as an open format hearing. Individual oral comments are recorded by a court reporter. The presence of a hearing examiner and a formal agenda are optional.

These events are typically scheduled for substantial portions of an afternoon or evening so people can drop by at their convenience and fully participate. Activities usually include attending a presentation, viewing exhibits, talking to project staff, and submitting written or oral comments.

The following items are features of an open format (or informal) hearing:

- They can be scheduled to accommodate people's work schedules.
- Brief presentations about the project and hearing process are advertised at preset times in the hearing notice. Presentations can be live, videotaped, or computerized.
- Agency or technical staff is present to answer questions and provide details of the project.
- Information is presented buffet-style, allowing participants access to specific information.
- Graphics, maps, photos, models, videos, and related documents are frequently used.
- People have the opportunity to clarify their comments by reviewing materials and asking questions before commenting.
- People can comment formally before a court reporter, or they can write opinions on comment forms and submit them before the announced deadline.

(4) Hearing Preparation

When region staff have determined that a formal or informal public hearing will be held, they should contact the HQ Hearing Coordinator to discuss preliminary details. The HQ Hearing Coordinator specializes in assisting with preparations for the hearing and will usually attend. Other WSDOT groups involved with the project and tasked with developing and implementing the public involvement plan can assist with hearing preparations and provide assistance at the hearing.

The exhibits in this chapter can be used as checklists to identify important milestones and work products needed. Important elements include setting an initial target date for the hearing and agreeing on staff roles and responsibilities at the hearing.

(a) **Setting the Hearing Date and Other Arrangements**.

The Director & State Design Engineer, Development Division, sets the hearing date at the recommendation of the HQ Hearing Coordinator. This is known as the order of hearing. Final arrangements for the hearing date can be handled by telephone or brief check-in meetings between the HQ Hearing Coordinator and the region.

The region proposes a hearing date based on the following considerations:

- Convenient for community participation. Contact local community and government representatives to avoid possible conflict with local activities. Consider times and locations that are most appropriate for the community.
- For corridor and design hearings, at least 30 days after circulation of the draft environmental impact statement (DEIS) or the published notice of availability of any other environmental document.
- In most cases, more than 45 days after submittal of the prehearing packet.

The region makes other arrangements as follows:

- Reviews the location of the hearing hall to ensure it is easily accessed by public transportation (whenever possible), convenient for community participation, and ADA accessible.
- Arranges for a court reporter.
- Requests that the HQ Hearing Coordinator provide a hearing examiner for all limited access hearings and for other hearings, if desired.
- Develops a hearing agenda for all limited access hearings and for other types of hearings, if desired.
- If requested in response to the hearing notice, provides communication auxiliary aids and other reasonable accommodations required for persons with disabilities. Examples include interpreters for persons who are deaf; audio equipment for persons who are hard of hearing; language interpreters; and the use of guide animals and Braille or taped information for persons with visual impairments.
- All public hearings and meetings require the development of procedures for the collection of statistical data (race, color, sex, and national origin) on state highway program participants and beneficiaries such as relocatees, impacted citizens, and affected communities. Public Involvement Forms should be available for meeting attendees to complete. This form requests attendees to provide information on their race, ethnicity, national origin, and gender. It is available in English, Spanish, Korean, Russian, Vietnamese, Tagalog, and Traditional and Simplified Chinese at:
  www.wsdot.wa.gov/equalopportunity/PoliciesRegs/titlevi.htm
- If demographics indicate that 5% or 1000 persons or more in the affected project area speak a language other than English, vital documents, advertisements, notices, newspapers, mailing notices, and other written and verbal media and informational materials may need to be translated into other languages to ensure social impacts to communities and people are recognized and considered throughout the transportation planning and decision-making process. In addition, language interpreters may need to be present during the hearings or public meetings to ensure individuals and minority communities are included throughout the process.

(b) **Developing the Prehearing Packet**

The region prepares a prehearing packet, which contains an organized grouping of project information to be used at the hearing. The project team members and specialists enlisted to support the public involvement and hearing processes typically coordinate to produce the prehearing packet elements. Much of the information needed in the prehearing packet will come from the project's public involvement plan.

The following information is included in the prehearing packet:

1. **Project Background Information and Exhibits**

   A project vicinity map and pertinent plans and exhibits for the hearing. The prehearing packet also contains a brief written narrative of the project. Usually, this narrative is already prepared and available in Project File documents, public involvement plans, or on a project Internet page.

2. **Proposed Hearing Type, Format, and Logistics**

   The prehearing packet identifies the type of hearing required. A hearing support team provides various planning details and helps with arrangements (date, time, place, and announcements). A public open house is often scheduled on the same day, preceding a formal hearing, to provide opportunity for community involvement.

3. **News Release**

   The region Communications Office can assist in preparing announcements for the hearing and other public events.

4. **Legal Hearing Notice**

   Notices must contain certain legal statements provided by the HQ Access and Hearings Section. (See 210.05(5) and (6) for guidance on notices.)

5. **List of Newspapers and Other Media Sources**

   These are the media sources used to announce the hearing. The region Communications Office has developed relations with reporters and media outlets, including minority publications and media, and is accustomed to working these issues. Enlist the office's support for hearing preparations.

6. **List of Legislators and Government Agencies Involved**

   Special notice is sent to local officials and legislators announcing public hearings. At formal hearings, the moderator and agenda typically identify those officials so they can interact with the public. The HQ Government Relations Office can assist with identifying and notifying legislators and key legislative staff within the project area.

7. **The Hearing Agenda and Script**

   These are required for formal hearings and are prepared by the region. The HQ Access and Hearings Section can provide sample agendas and scripts to support the region in its hearing preparations.

Exhibit 210-3 provides a checklist of prehearing packet contents, including additional items needed for limited access hearings.

(c) **Preparing and Sending a Prehearing Packet**

You should prepare a prehearing packet at least 45 days in advance of the public hearing and send it to the HQ Access and Hearings Section. The HQ Hearing Coordinator reviews and concurs with the region's plans and recommends the Director & State Design Engineer, Development Division's approval of the hearing date. Headquarters concurrence with the prehearing packet typically requires two weeks after receipt of the information.

(5) Public Hearing Notices: Purpose and Content

There are two types of public notices for hearings: notice of hearing and notice of opportunity for a hearing. Consult the HQ Hearing Coordinator for specific project hearing requirements and implementation strategies.

(a) **Notice of Hearing**

A notice of hearing is prepared and published when a hearing is required by law and cannot be waived.

(b) **Notice of Opportunity for a Hearing**

In select cases, a notice of opportunity for a hearing is prepared and published in order to gauge the public's interest in having a particular hearing. This kind of notice is only used if the requirements for a hearing can be legally waived. In these cases, documentation is required as set forth in 210.05(7).

(c) **Content Requirements**

The HQ Access and Hearings Section provides sample notices to the region upon request. Public notices include statements that are required by state and federal statutes. Some important elements of a notice include the following:

- A map or graphic identifying project location and limits.
- For a notice of opportunity for a hearing, include the procedures for requesting a hearing and the deadline, and note the existence of the relocation assistance program for persons or businesses displaced by the project.
- For an environmental, corridor, design, or combined corridor-design hearing, or for a notice of opportunity for a hearing, announce the availability of the environmental document and accessible locations.
- Project impacts to wetlands; flood plains; prime and unique farmlands; Section 4(f), 6(f), or 106 properties; endangered species or related habitats; or affected communities.
- Information on any associated prehearing presentation(s).
- Americans with Disabilities Act and Title VI legislation statements.

(6) Publishing Hearing Notices: Procedure

To advertise a legal notice of hearing or a notice of opportunity for a hearing, use the following procedure for appropriate media coverage and timing requirements:

(a) **Headquarters Concurrence**

As part of the prehearing packet, the region transmits the proposed notice and a list of the newspapers in which the notice will appear to the HQ Hearing Coordinator for concurrence prior to advertisement.

(b) **Region Distribution of Hearing Notice**

Upon receiving Headquarters concurrence, the region distributes copies of the hearing notice and news release as follows:

- Send a copy of the hearing notice and a summary project description to appropriate legislators and local officials one week before the first publication of a hearing notice. Provide the HQ Government Relations Office with a copy of all materials that will be distributed to legislators, along with a list of legislative recipients.
- Advertise the hearing notice in the appropriate newspapers within one week following the mailing to legislators. The advertisement must be published in a newspaper with general circulation in the vicinity of the proposed project or with a substantial circulation in the area concerned, such as foreign language and local newspapers. If affected limited-English-proficient populations have been identified, other foreign language newspapers may be appropriate as well. The legal notices section may be used or, preferably, a paid display advertisement in a prominent section of the newspaper, such as the local news section. With either type of advertisement, request that the newspaper provide an affidavit of publication.
- Distribute the project news release to all appropriate news media about three days before the first publication of a hearing notice, using newspapers publishing the formal advertisement of the notice.
- Additional methods may also be used to better reach interested or affected groups or individuals, including notifications distributed via project e-mail lists, ads in local community news media, direct mail, fliers, posters, and telephone calls.
- For corridor and design hearings, the first notice publication must occur at least 30 days before the date of the hearing. The second publication must be 5 to 12 days before the date of the hearing (see Exhibit 210-4). The first notice for a corridor or design hearing shall not be advertised prior to public availability of the draft environmental document.
- For limited access and environmental hearings, the notice must be published at least 15 days prior to the hearing. The timing of additional publications is optional (see Exhibit 210-5).
- For a notice of opportunity for a hearing, the notice must be published once each week for two consecutive weeks. The deadline for requesting a hearing must be at least 21 days after the first date of publication and at least 14 days after the second date of publication.
- A copy of the published hearing notice is sent to the HQ Hearing Coordinator at the time of publication.

(c) **Headquarters Distribution of Hearing Notice**

The HQ Hearing Coordinator sends a copy of the notice of hearing to the Transportation Commission, Attorney General's Office, HQ Communications Office, and FHWA (if applicable).

For a summary of the procedure and timing requirements, see Exhibit 210-4 (for environmental, corridor, and design hearings) or Exhibit 210-5 (for limited access hearings).

(7) No Hearing Interest: Procedure and Documentation

As described in 210.05(5), in select cases the region can satisfy certain project hearing requirements by advertising a notice of opportunity for a hearing. This procedure can be beneficial, particularly with limited access hearings in cases where very few abutting property owners are affected. If no hearing requests are received after issuing the notice of opportunity, the following procedures and documentation are required to waive a hearing.

(a) Corridor or Design Hearing

If no requests are received for a corridor or design hearing, the region transmits a package, which includes the notice of opportunity for a hearing, the affidavit of publication of the notice, and a letter stating that there were no requests for a hearing, to the HQ Access and Hearings Section.

(b) Limited Access Hearing

When a notice of opportunity for a hearing is used to fulfill the requirements for a limited access hearing and there are no requests for a hearing, the following steps are taken:

- The region must secure signed hearing waivers from every abutting property owner whose access rights will be affected by the project, as well as the affected local agency. The HQ Access and Hearings Section can supply a sample waiver to the region.
- The Project Engineer must contact every affected property owner of record (not tenant) and the local agency to explain the proposed project. This explanation must include information on access features, right of way acquisition (if any), and the right to a hearing. Property owners must also be advised that signing the waiver will not affect their right to fair compensation for their property, nor will it affect their access rights or relocation benefits.
- The region transmits the original signed waivers to the HQ Access and Hearings Section, along with the affidavit of publication of the notice of opportunity for a limited access hearing and a recommendation for approval of the right of way plan. Once the completed package is received by the HQ Access and Hearings Section, it is submitted to the Director & State Design Engineer, Development Division, for review and approval.

(c) Environmental Hearing

Environmental hearings cannot use the process of waivers to satisfy project hearing requirements.

(8) Prehearing Briefs and Readiness

After publication of a hearing notice, the region should expect to receive public requests for information and project briefings, including requests for information in languages other than English.

(a) Presentation of Material for Inspection and Copying

The information outlined in the hearing notice and other engineering and environmental studies, as well as information intended to be presented at the hearing, must be made available for public review and copying throughout

the period between the first advertisement and the approval of the hearing summary or findings and order. The information may also need to be available in languages other than English if indicated by demographics. The information need not be in final form, but it must include every item currently included in the hearing presentation. The environmental documents must also be available for public review.

These materials are made available in the general locality of the project. The region reviews the variables (the locations of the Project Office and project site; the interested individuals; and the probability of requests for review) and selects a mutually convenient site for the presentation of the information. In accordance with RCW 42.56, a record should be kept for future evidence, stating who came in, when, and what data they reviewed and copied.

(b) **Hearing Briefing**

On controversial projects, the HQ Hearing Coordinator arranges for a briefing (held before the hearing) for those interested in the project. Attendants typically include appropriate Headquarters, region, and FHWA personnel, with special notice to the Secretary of Transportation. Region personnel present the briefing.

(c) **Prehearing Presentation**

The region is encouraged to give an informal presentation to the public for discussion of the project prior to the hearing. A prehearing presentation is informal, with ample opportunity for exchange of information between WSDOT and the public. Providing community members with opportunities to talk about their concerns in advance of the hearing promotes positive public relationships, and can make the actual hearing proceed more smoothly. Prehearing presentations can be open house meetings, drop-in centers, workshops, or other formats identified in the public involvement plan.

The prehearing presentation is usually held about one week before the hearing for more controversial projects, modified as needed.

Include the date, time, and place in the hearing notice and ensure it is mailed in time to give adequate notice of the prehearing presentation.

(9) Conducting the Hearing

The hearing is facilitated by the Regional Administrator or a designee. Normally, a hearing examiner is used when significant controversy or considerable public involvement is anticipated. A hearing examiner is required for limited access hearings.

A verbatim transcript of the proceedings is made by a court reporter.

Hearings are generally more informative and gain more public participation when an informal format is used, where people's views and opinions are openly sought in a casual and personal way. The informal hearing format may be used for all hearings except limited access hearings. At least one court reporter is required to take individual testimony. Use displays, exhibits, maps, and tables, and have knowledgeable staff available to answer specific questions about the proposed project.

It is the responsibility of the hearing moderator and other department representatives to be responsive to all reasonable and appropriate questions. If a question or proposal is presented at the limited access hearing that can only be answered at a later date, the region shall reserve an exhibit to respond to the comment in the findings and order. The hearing moderator must not allow any person to be harassed or subjected to unreasonable cross-examination.

(a) **Hearing Agenda Items**

For all limited access hearings, and for other formal hearings, the region prepares a hearing agenda to ensure all significant items are addressed. A hearing agenda includes the following:

1. **Opening Statement**
   - Highway and project name.
   - Purpose of hearing.
   - Description of how the hearing will be conducted.
   - Introduction of elected officials.
   - Federal/State/County/City relationship.
   - Statutory requirements being fulfilled by the hearing.
   - Status of the project with regard to NEPA/SEPA documents.
   - Description of information available for review and copying.
   - For environmental, corridor, or design hearings, notice that written statements and other exhibits can be submitted during the open record period following the hearing.
   - Statement that all who want to receive written notification of WSDOT's action as a result of the hearing may add their names to the interest list or file a notice of appearance for limited access hearings.

2. **Project History**

   Present a brief project history, including purpose and need for the project, public involvement program, future hearing opportunities, and hearings held.

3. **Presentation of Plans**

   Develop alternatives that include comparable levels of detail, and present them equally. Include the no-action alternative. Refer to any supporting studies that are available to the public.

   Identify a preliminary preferred alternative, if selected by WSDOT, for more detailed development. When a preliminary preferred alternative has been identified, stress that it is subject to revision and reevaluation based on public comments, additional studies, and other information that may become available.

4. **Environmental, Social, and Economic Discussion**

   Discuss all positive and negative environmental, social, and economic effects (or summarize the major effects), and refer to the environmental documentation.

5. **Statements, Plans, or Counterproposals From the Public**

   Accept public views or statements regarding the proposal presented, the alternatives, and the social, economic, and environmental effects identified. Avoid evaluating the views presented while conducting the hearing.

6. **Relocation Assistance Program**

   Explain the relocation assistance program and relocation assistance payments available. At all hearings, the relocation assistance brochure must be available for free distribution, including (if appropriate) brochures in languages other than English. Real Estate Services personnel should be available.

   If the project does not require any relocations, the relocation assistance discussion may be omitted. Make a simple statement to the effect that relocation assistance is provided, but currently no relocations have been identified for the project. The relocation brochure and personnel should still be available to the public at the hearing.

7. **Acquisition**

   Discuss right of way acquisition, estimated cost, and currently proposed construction schedules and critical activities that may involve or affect the public.

8. **Closing**

   Summarize the hearing and announce proposed future actions.

9. **Adjournment**

   Adjourn the hearing with sincere gratitude for the public's valuable participation.

(10) Hearing Summary and Adoption

Upon completion of a public hearing, a documentation and approval procedure leads to official adoption of the hearing proceedings. After the hearing, a summary is prepared by the region. There are two types of summary documents used, depending on the type of hearing. For environmental, corridor, and design hearings, a hearing summary is produced. Following a limited access hearing, a findings and order document is prepared. Each of these packages is comprised of documentation assembled by the region and approved by Headquarters.

(a) Hearing Summary Contents

The hearing summary includes the following elements:

1. Hearing transcript.
2. Copy of the affidavit of publication of the hearing notice.
3. Hearing material:
   - Copies of the letters received before and after the hearing.
   - Copies or photographs of, or references to, every exhibit used in the hearing.

4. Summary and analyses of all oral and written comments. Include consideration of the positive and negative social, economic, and environmental aspects of these comments.

(b) **Limited Access Hearing Findings and Order**

Following a limited access hearing, the "summary" document is labeled the findings and order. Refer to 210.09(12) for the process description and required documentation for findings and order documents.

(c) **Adoption and Approval**

For specific hearing types, see subsequent sections in this chapter related to adoption procedures.

Exhibit 210-6 identifies the Headquarters approval authority for hearing summary and findings and order documents.

210.06 Environmental Hearing

Early coordination with appropriate agencies and the public may help to determine the appropriate level of environmental documentation, the scope of the document, the level of analysis, and related environmental disciplines to be analyzed.

Environmental documents address the positive and negative social, economic, and environmental project effects, as described in Chapter 225 and the *Environmental Manual*. The project environmental documentation is the first step in the environmental hearing procedure. Each step of the hearing procedure is dovetailed into the environmental process and is important in achieving the appropriate project documentation. Corridor and design hearings are not normally required for Environmental Assessments, SEPA Checklists, and categorically excluded projects. However, the opportunity for an environmental hearing might be required or advisable for controversial proposals. When an environmental hearing is not required, an informational meeting may serve as a useful forum for public involvement in the environmental process. Consult with region environmental staff and the HQ Hearing Coordinator for specific project requirements.

Projects requiring an Environmental Impact Statement (EIS) must use an evaluation process called *scoping* in the NEPA and SEPA requirements. This process helps the project proponents identify the significant issues and possible alternatives analyzed and documented in the Draft EIS, and it must follow the public involvement plan included in the environmental study plan for the project.

After the project has been thoroughly analyzed through the environmental evaluation process and discussed within the community using informal public involvement methods, a hearing is held to present and gather testimony. The hearing is timed to fall within the comment period for the Draft EIS.

For an environmental hearing, the hearing notice must be published at least 15 days prior to the hearing. The timing of additional publications is optional (see Exhibit 210-4).

Responses to comments on the Draft EIS must be addressed in the Final EIS.

(1) Environmental Hearing Summary

The environmental hearing summary includes the items outlined in 210.05(10).

(2) Adoption of Environmental Hearing

Chapter 225 and the *Environmental Manual* provide guidance on NEPA and SEPA procedures, documentation requirements, and approvals.

210.07 Corridor Hearing

A corridor hearing is a public hearing that:

- Is held before WSDOT is committed to a preferred alternative establishing the final route corridor.
- Is held to ensure opportunity is afforded for effective participation by interested persons in the process of determining the need for and location of a state highway.
- Provides the public an opportunity to present views on the social, economic, and environmental effects of the proposed alternative highway corridors.

A corridor hearing is required if any of the following project actions would occur:

- Proposed route on new location.
- Substantial social, economic, or environmental impacts.
- Significant change in layout or function of connecting roads or streets.

When a corridor hearing is held, the region must provide enough design detail on the proposed alignment(s) within the corridor(s) that an informed presentation can be made at the hearing. Justification to abandon an existing corridor must also be presented.

For general procedures and notification requirements, see 210.05 and Exhibit 210-4.

(1) Corridor Hearing Summary

After the hearing, the region:

- Reviews the hearing transcript.
- Responds to all questions or proposals submitted at or subsequent to the hearing.
- Compiles a corridor hearing summary.
- Transmits three copies (four copies for Interstate projects) to the HQ Access and Hearings Section.

When appropriate, the hearing summary may be included in the FEIS. If not included, submit the complete corridor hearing summary to the HQ Access and Hearings Section within approximately two months following the hearing.

The corridor hearing summary includes the items outlined in 210.05(10).

(2) Adoption of Corridor Hearing Summary

The HQ Access and Hearings Section prepares a package that contains the corridor hearing summary and a formal description of the project and forwards it to the Assistant Secretary, Engineering & Regional Operations, for adoption. The HQ Hearing Coordinator notifies the region when adoption has occurred and returns an approved copy to the region.

210.08 Design Hearing

A design hearing is a public hearing that:

- Is held after a route corridor is established and approved, but before final design of a highway is engineered.
- Is held to ensure an opportunity is afforded for the public to present its views on each proposed design alternative, including the social, economic, and environmental effects of those designs.

A design hearing is required if any of the following project actions will occur:

- Substantial social, economic, or environmental impacts.
- Significant change in layout or function of connecting roads or streets.
- Acquisition of a significant amount of right of way results in relocation of individuals, groups, or institutions.

For general procedures and notification requirements, see 210.05 and Exhibit 210-4.

(1) Design Hearing Summary

The design hearing summary includes the elements outlined in 210.05(10).

Submit the complete hearing summary to the HQ Access and Hearings Section within approximately two months following the hearing.

If new studies or additional data are required subsequent to the hearing, the region compiles the information in coordination with the HQ Design Office.

(2) Adoption of Design Hearing Summary

After the hearing, the region reviews the hearing transcript, responds to all questions or proposals submitted at or subsequent to the hearing, compiles a hearing summary, and transmits three copies (four copies for Interstate projects) to the HQ Access and Hearings Section. When appropriate, the design hearing summary may be included in the final environmental document. The HQ Access and Hearings Section prepares a formal document that identifies and describes the project and submits it to the Director & State Design Engineer, Development Division, for approval. One approved copy is returned to the region. The HQ Hearing Coordinator notifies the region that adoption has occurred.

On Interstate projects, the Director & State Design Engineer, Development Division, (or designee) submits the approved design hearing summary to the FHWA for federal approval. If possible, this submittal is timed to coincide with the submittal of the Design Decision Summary to the FHWA.

(3) Public Notification of Action Taken

The region prepares a formal response to individuals who had unresolved questions at the hearing. The region keeps the public advised regarding the result(s) of the hearing process, such as project adoption or revision to the plan. A project newsletter sent to those on the interest list is an effective method of notification. Project news items can be sent via e-mail or by more traditional methods.

210.09 Limited Access Hearing

Limited access hearings are required by law (per RCW 47.52) whenever limited access is established or revised on new or existing highways. Decisions concerning limited access hearings are made on a project-by-project basis by the Director & State Design Engineer, Development Division, based on information that includes the recommendations submitted by the region (see Chapters 510, 520, 530, and 540).

Limited access hearing procedures generally follow those identified in 210.05; however, several unique products and notifications are also prepared. These include limited access hearing plans and notifications sent to abutting property owners and local jurisdictions. (See 210.09(4) and Exhibit 210-3 for a listing of these products.) Exhibit 210-5 presents a summary of the limited access hearing procedures.

Prior to the limited access hearing (RCW 47.52.131), discussions with the local jurisdictions shall be held on the merits of the limited access report and the limited access hearing plan(s). These are required exhibits for the limited access hearing. (See Chapter 530 for guidance on limited access reports.)

The following information applies only to limited access hearings and procedures for approval of the findings and order.

(1) Hearing Examiner

The HQ Access and Hearings Section hires an administrative law judge from the Office of Administrative Hearings to conduct the limited access hearing.

(2) Order of Hearing

The order of hearing officially establishes the hearing date. The Director & State Design Engineer, Development Division, approves the order of hearing. The HQ Hearing Coordinator then notifies the region, the Attorney General's Office, and the hearing examiner of the official hearing date.

(3) Limited Access Hearing Plan

The region prepares a limited access hearing plan to be used as an exhibit at the formal hearing and forwards it to the HQ Plans Engineer for review and approval approximately 45 days before the hearing. This is a Phase 2 Plan (see Chapter 510). The HQ Plans Engineer schedules the approval of the limited access hearing plan on the Director & State Design Engineer, Development Division's calendar.

(4) Limited Access Hearing Information to Abutters

The region prepares an information packet that must be mailed to abutters, and other entities as specified below, at least 15 days prior to the hearing and concurrent with advertisement of the hearing notice. These items are elements of the prehearing packet as described in 210.05(4)(b) and in Exhibit 210-3. If some of the limited access hearing packets are returned as undeliverable, the region must make every effort to communicate with the property owners.

The limited access hearing packet for abutters contains the following:

- Limited access hearing plan
- Limited access hearing notice
- Notice of appearance

The region also sends the limited access hearing packet to:

- The county and/or city.
- The owners of property listed on the county tax rolls as abutting the section of highway, road, or street being considered at the hearing as a limited access facility.
- Local agencies and public officials who have requested a notice of hearing or who, by the nature of their functions, objectives, or responsibilities, are interested in or affected by the proposal.
- Every agency, organization, official, or individual on the interest list.

The limited access hearing packet is also sent, when applicable, to:

- State resource, recreation, and planning agencies.
- Tribal governments.
- Appropriate representatives of the Department of the Interior and the Department of Housing and Urban Development.
- Other federal agencies.
- Public advisory groups.

(5) Affidavit of Service by Mailing

The region prepares an affidavit of service by mailing. This affidavit states that the limited access hearing packet was mailed at least 15 days prior to the hearing and that it will be entered into the record at the hearing.

(6) Limited Access Hearing Plan Revisions

The limited access hearing plan cannot be revised after the Director & State Design Engineer, Development Division (or designee), approves the plan without rescheduling the hearing. If significant revisions to the plan become necessary during the period between the approval and the hearing, the revisions can be made and must be entered into the record as a revised (red and green) plan at the hearing.

(7) Limited Access Hearing Notice

The limited access hearing notice must be published at least 15 calendar days before the hearing. This is a legal requirement and the hearing must be rescheduled if the advertising deadline is not met. Publication and notice requirements are the same as those required in 210.05, except that the statutory abutter mailing must be mailed after notification to the appropriate legislators.

(8) Notice of Appearance

The HQ Hearing Coordinator transmits the notice of appearance form to the region. Anyone wanting to receive a copy of the findings and order and the adopted right of way and limited access plan must complete a notice of appearance form and return it to WSDOT either at the hearing or by mail.

(9) Reproduction of Plans

The HQ Hearing Coordinator submits the hearing plans for reproduction at least 24 days prior to the hearing. The reproduced plans are sent to the region at least 17 days before the hearing, for mailing to the abutters at least 15 days before the hearing.

(10) Limited Access Hearing Exhibits

The region retains the limited access hearing exhibits until preparation of the draft findings and order is complete. The region then submits all the original hearing exhibits and three copies to the HQ Access and Hearings Section as part of the findings and order package. Any exhibits submitted directly to Headquarters are sent to the region for inclusion with the region's submittal.

(11) Limited Access Hearing Transcript

The court reporter furnishes the original limited access hearing transcript to the region. The region forwards the transcript to the hearing examiner, or presiding authority, for signature certifying that the transcript is complete. The signed original and three copies are returned to the region for inclusion in the findings and order package.

(12) Findings and Order

The findings and order is a document containing the findings and conclusions of a limited access hearing, based entirely on the evidence in the hearing record. The region reviews a copy of the transcript from the court reporter and prepares a findings and order package. The package is sent to the HQ Access and Hearings Section.

The findings and order package contains:

- The draft findings and order.
- Draft responses to comments (reserved exhibits).
- A draft findings and order Plan as modified from the hearing plan.
- All limited access hearing exhibits: originals and three copies.
- The limited access hearing transcript: original and three copies.
- The notice of appearance forms.
- Estimate of the number of copies of the final findings and order plan and text the region will need for the mailing.

(13) Adoption of Findings and Order

The Assistant Secretary, Engineering & Regional Operations, adopts the findings and order based on the evidence introduced at the hearing and any supplemental exhibits.

Following adoption of the findings and order, the HQ Plans Section makes the necessary revisions to the limited access hearing plan, which then becomes the findings and order plan.

The HQ Access and Hearings Section arranges for reproduction of the findings and order plan and the findings and order text and transmits them to the region.

The region mails a copy of the findings and order plan and the findings and order text to all parties that filed a notice of appearance and to all local governmental agencies involved. Subsequent to this mailing, the region prepares an affidavit of service by mailing and transmits it to the HQ Access and Hearings Section.

At the time of mailing, but before publication of the résumé, the region notifies the appropriate legislators of WSDOT's action.

(14) Résumé

The résumé is an official notification of action taken by WSDOT following adoption of a findings and order. The HQ Access and Hearings Section provides the résumé to the region. The region must publish the résumé once each week for two consecutive weeks, not to begin until at least ten days after the mailing of the findings and order.

(15) Final Establishment of Access Control

When the findings and order is adopted, the findings and order plan becomes a Phase 4 Plan (see Chapter 510). The establishment of access control becomes final 30 days from the date the findings and order is mailed by the region, as documented by the affidavit of service by mailing.

(16) Appeal Process

An appeal from the county or city must be in the form of a written disapproval, submitted to the Secretary of Transportation, requesting a hearing before a board of review.

An appeal from abutting property owners must be filed in the Superior Court of the state of Washington, in the county where the limited access facility is to be located, and shall affect only those specific ownerships. The plan is final for all other ownerships.

210.10 Combined Hearings

A combined hearing often alleviates the need to schedule separate hearings to discuss similar information. A combined hearing is desirable when the timing for circulation of the draft environmental document is simultaneous with the timing for corridor and design hearings and when all alternative designs are available for each alternative corridor.

When deciding whether to combine hearings, consider:

- Whether there is controversy.
- Whether alternative corridors are proposed.
- The nature of the environmental concerns.
- The benefits to the public of a combined hearing.

210.11 Administrative Appeal Hearing

Administrative appeal hearings apply only to managed access highways, are conducted as formal hearings, and are initiated by a property owner seeking to appeal a decision made to restrict or remove an access connection. This is also known as an adjudicative proceeding, and the procedure is presented in Chapter 540.

210.12 Follow-Up Hearing

A new hearing or the opportunity for a hearing is required for any previously held hearing when any one of the following occurs (USC 23, §771.111):

- Major actions (such as adoption of findings and order and approval of hearing summaries) did not occur within three years following the date the last hearing was held or the opportunity for a hearing was afforded.
- A substantial change occurs in the area affected by the proposal (due to unanticipated development, for example).
- A substantial change occurs in a proposal for which an opportunity for a hearing was previously advertised or a hearing was held.
- A significant social, economic, or environmental effect is identified that was not considered at earlier hearings.

210.13 Documentation

For the list of documents required to be preserved in the Design Documentation Package and the Project File, see the Design Documentation Checklist:
www.wsdot.wa.gov/design/projectdev/

Proposed Project Actions or Conditions	Types of Hearings[1]					
	Environmental	Design	Corridor	Limited Access	Combined	Follow-Up
Proposed route on new location			X	X		
Substantial social, economic, or environmental impacts	X	X	X	X		
Significant change in layout or function of connecting roads or streets		X	X	X		
Acquisition of significant amount of right of way results in relocation of individuals, groups, or institutions	X	X				
Significant adverse impact on abutting real property	X					
An EIS is required or a hearing is requested for an EA	X					
Significant public interest or controversy	X					
Regulatory agencies have hearing requirements that could be consolidated into one hearing process	X					
Limited access control is established or revised				X		
If several hearings are required, consider efficiency of combining					X	
Major actions not taken within 3 years after date last hearing was held						X[2]
An unusually long time has elapsed since the last hearing or the opportunity for a hearing						X
Substantial change in proposal since prior hearing						X
Significant social, economic, or environmental effect is identified and was not considered at prior hearing						X

Notes:

[1] This table presents a list of project actions that correspond to required public hearings. The list is intended as a guide and is not all-inclusive. In cases where several types of hearings are anticipated for a project, a combined hearing may be an effective method. Consult with region and Headquarters environmental staff, the designated Assistant State Design Engineer, and the HQ Access and Hearings Section to identify specific hearing requirements and strategies.

[2] Posthearing major actions include: FHWA approvals (for Interstate projects); adoption of hearing summaries and findings and order; and public notification of action taken, such as publishing a résumé.

Types of Public Hearings

Exhibit 210-1

Hearing Type	Hearing Format	
	Formal	**Informal**
Limited Access	Required	Not allowed
Environmental	Either format acceptable	
Design	Either format acceptable	
Corridor	Either format acceptable	
Combined	Format depends on type*	
Follow-Up	Format depends on type*	

Notes:

Check with the HQ Hearing Coordinator to identify specific hearing type and appropriate hearing format.

* If a combined or follow-up hearing includes a limited access hearing, then that portion of the hearing must adhere to the formal format.

Public Hearing Formats
Exhibit 210-2

Prehearing Packet Items	All Hearings	Additional Items for Limited Access Hearings
Brief project description; purpose and public benefit; history; known public perceptions; and support or opposition	X	
Proposed hearing type	X	
Hearing arrangements: proposed date, time, and place	X	
Proposed hearing format: formal or informal	X	[1]
Notice of whether an open house event will precede the hearing	X	
Vicinity map	X	
Plans for corridor and design alternatives with descriptions	X	
News release	X	
Legal notice of hearing	X	X[2]
List of newspapers and other media sources that will cover the news release and hearing notice	X	
List of legislators and government agencies involved	X	
Hearing agenda	[3]	X[3]
Hearing script	[3]	X[3]
Limited access report (see Chapter 530)		X
Limited access hearing plan(s) (see Chapter 530)		X
List of abutting property owners		X
Notice of appearance form		X

Notes:

The prehearing packet is prepared by the region and transmitted to the HQ Access and Hearings Section for review, concurrence, and processing. This information is assembled in advance of the hearing to facilitate timely announcements and a smooth-flowing event. The HQ Hearing Coordinator requires the prehearing packet 45 days (or sooner) in advance of the proposed hearing date.

[1] Limited access hearings are required by law to be formal.

[2] For a limited access hearing, each abutting property owner affected by the project must receive the hearing notice, along with the notice of appearance form and specific limited access hearing plan(s) showing their parcel(s). Indicate in the prehearing packet the number of affected property owners to whom the packets will be mailed.

[3] A hearing agenda and hearing script are required for a limited access hearing. Any formal hearing requires a fixed agenda and a script. It is recognized that the script may be in draft format at the time of submittal of the prehearing packet. The HQ Hearing Coordinator can assist in its completion and can provide sample scripts and agendas.

Prehearing Packet Checklist
Exhibit 210-3

Sequence for Corridor, Design, and Environmental Hearings	
Preparatory Work	
Consult with HQ Hearing Coordinator and environmental specialists to determine specific requirements for a hearing or a notice of opportunity for a hearing.	[see 210.05 & Exhibit 210-1]
Assemble support team; identify and schedule tasks and deliverables.	[see 210.05(4)]
Prepare prehearing packet (news releases, legal notices, exhibits).	[see 210.05(4)(b) & Exhibit 210-3]
♦ **Minimum 45 Days Prior to Hearing: Transmit Prehearing Packet to HQ** HQ Hearing Coordinator reviews and concurs; schedules hearing.	[see 210.05(4)(b)]
Public Notifications and News Releases	[see 210.05(5) & (6)]
♦ **35–40 Days Prior to Hearing** (1 week prior to first public ad) Send notice to legislators and local officials.	
♦ **33–35 Days Prior to Hearing** (about 3 days before advertisement) Send letter with news release to media.	
♦ **30 Days Prior to Hearing** Draft EIS becomes available and its open comment period begins.	
Corridor and Design Hearings ♦ **30 Days Prior to Hearing: Publish First Notice*** Advertise at least 30 days in advance of hearing, but not prior to public availability of draft environmental document. ♦ **5–12 Days Prior to Hearing: Publish Second Notice**	
Environmental Hearings ♦ **15 Days Prior to Hearing: Publish First Notice** Advertise at least 15 days in advance; timing of additional notices optional. (If done in combination with design or corridor hearing, use 30-day advance notice.)	
Prehearing Briefings	[see 210.05(8)]
♦ **5–12 Days Prior to Hearing** Region confers with local jurisdictions; conducts hearing briefings and presentations; and makes hearing materials and information available for public inspection and copying.	
Conduct the Hearing	[see 210.05(9)]
Conduct environmental, corridor, or design hearing.	
Posthearing Actions	
Court reporter provides hearing transcript to region (usually within 2 weeks).	
♦ **2 Months After Hearing: Prepare Hearing Summary and Send to HQ** Region addresses public comments from hearing and throughout comment period; prepares hearing summary and transmits to HQ Hearing Coordinator for processing.	[see 210.05(10)]
HQ Hearing Coordinator transmits hearing summary package to HQ approval authority for approval.	[see Exhibit 210-6]
HQ Hearing Coordinator notifies region of adoption and returns a copy of approved hearing summary to region.	

Notes:

Important timing requirements are marked ♦

* If the advertisement is a notice of opportunity for a hearing, requests must be received within 21 days after the first advertisement. If there are no requests, see 210.05(7).

Sequence for Corridor, Design, and Environmental Hearings
Exhibit 210-4

Sequence for Limited Access Hearing	
Preparatory Work	
Consult with HQ Access and Hearings Section. Determine requirements for a limited access hearing or a notice of opportunity for a hearing.	[see 210.05 & Exhibit 210-1]
Assemble support team; identify and schedule tasks and deliverables.	[see 210.05(4)]
Prepare limited access report and limited access hearing plan(s).	[see Chapters 510 & 530]
Prepare prehearing packet (legal notice, exhibits, information packets for abutting property owners).	[see 210.05(4)(b) & Exhibit 210-3]
♦ **Minimum 45 Days Prior to Hearing: Transmit Prehearing Packet to HQ – Transmit Limited Access Report and Hearing Plans for Approval** HQ Hearing Coordinator reviews and concurs; schedules hearing; transmits limited access report and limited access hearing plan.	[see 210.05(4)(b) & 210.09]
♦ **45 Days Prior to Hearing** HQ actions: Calendar order of hearing & limited access hearing plan approved	[see 210.09(2)&(3)]
♦ **24 Days Prior to Hearing: HQ Reproduction of Plans** HQ action: Approved limited access hearing plan(s) are reproduced in number sufficient for mailing to abutters and other handout needs; one set to be used as hearing exhibit.	[see 210.09(9)]
Notifications, News Releases, Confer With Local Agencies	
♦ **35–40 Days Prior to Hearing** Send notice to legislators and local officials (1 week prior to first public ad).	[see 210.05(6)]
♦ **33–35 Days Prior to Hearing** Send letter with news release to media (about 3 days before advertisement).	[see 210.05(6)]
♦ **15 Days Prior to Hearing: Publish First Notice*** Advertise at least 15 days in advance; timing of additional notices optional.	[see 210.05(6)]
♦ **15 Days Prior to Hearing: Send Hearing Packets to Abutters** (Hearing notice, limited access hearing plan, notice of appearance form).	[see 210.05(4)]
♦ **15 Days Prior to Hearing: Confer With Local Jurisdictions**	[see 210.05(8)]
Conduct the Hearing	[see 210.05(6)]
Using agenda and script, conduct formal limited access hearing.	
Posthearing Actions	
Court reporter provides limited access hearing transcript to region.	[see 210.09(11)]
Region prepares findings and order document and transmits to HQ Hearing Coordinator.	[see 210.09(12)]
Assistant Secretary, Engineering & Regional Operations, adopts findings and order.	[see 210.09(13)]
Limited access hearing plan becomes findings and order plan.	[see 210.09(15)]
Findings and order reproduced and mailed to abutters and local jurisdictions.	[see 210.09(13)]
HQ provides résumé to region and region publishes.	[see 210.09(14)]

Notes:
Important timing requirements are marked ♦

* If the advertisement is a notice of opportunity for a hearing, requests must be received within 21 days after the first advertisement. If there are no requests, see 210.05(7).

Sequence for Limited Access Hearing
Exhibit 210-5

Hearing Summary Document	WSDOT HQ Approval Authority
Limited access hearing findings and order	Assistant Secretary, Engineering & Regional Operations
Corridor hearing summary	Assistant Secretary, Engineering & Regional Operations
Environmental hearing summary	Director, Environmental Services
Design hearing summary	Director & State Design Engineer, Development Division

Hearing Summary Approvals
Exhibit 210-6

Chapter 225 Environmental Coordination

225.01 General
225.02 References
225.03 Determining the Environmental Documentation
225.04 Identifying the Project Classification
225.05 Environmental Commitment File
225.06 Environmental Permits and Approvals
225.07 Documentation

225.01 General

The term "environmental documentation" refers to the documents produced for a project to satisfy the requirements contained in the National Environmental Policy Act (NEPA) and the State Environmental Policy Act (SEPA). The *Environmental Manual* and supporting web pages provide detailed instructions on how to determine what level of documentation is required and how to prepare the documents. This chapter provides a summary of the relevant provisions in the *Environmental Manual*.

The purpose of the environmental document is to provide decision makers, agencies, and the public with information on a project's environmental impacts, alternatives to the proposed action, and mitigation measures to reduce unavoidable impacts. Final environmental documents identify and evaluate the project to be constructed. Because projects vary in their level of environmental impacts, the rules on environmental documentation allow for different levels of documentation. As a project's impacts increase, so does the level of documentation.

The region Environmental Office and the NEPA/SEPA Compliance Section of the Headquarters Environmental Services Office routinely provide environmental documentation assistance to designers and project engineers.

225.02 References

225.02(1) Federal/State Laws and Codes

42 United States Code (USC) 4321, National Environmental Policy Act of 1969 (NEPA)

23 Code of Federal Regulations (CFR) Part 771, Environmental Impact and Related Procedures

23 CFR Part 774; 49 USC Section 303, Policy on Lands, Parks, Recreation Areas, Wildlife and Waterfowl Refuges, and Historic Sites

36 CFR Part 800, Protection of Historic and Cultural Properties

40 CFR Parts 1500-1508, Council for Environmental Quality Regulations for Implementing NEPA

Chapter 43.21C Revised Code of Washington (RCW), State Environmental Policy Act (SEPA)

Chapter 197-11 Washington Administrative Code (WAC), SEPA Rules

Chapter 468-12 WAC, WSDOT SEPA Rules

225.02(2) WSDOT Environmental Resources

WSDOT region environmental staff

Environmental Permitting webpage:
www.wsdot.wa.gov/environment/permitting/default.htm

Environmental Manual, M 31-11, WSDOT
www.wsdot.wa.gov/publications/manuals/m31-11.htm

225.03 Determining the Environmental Documentation

The Environmental Review Summary (ERS) provides the first indication of what form the environmental documentation will take. The ERS is developed as part of the Project Summary, which is prepared during the scoping phase of all projects in the construction program. The Project Summary (see Chapter 300 for additional information) includes two components:

- Project Definition
- Environmental Review Summary

The ERS is part of the Project Summary database. The ERS describes the potential environmental impacts, proposed mitigation, and necessary permits for a project. It establishes the initial environmental classification and identifies the key environmental elements addressed in the NEPA/SEPA process. The ERS database includes fully integrated "Help" screens. Contact your region Environmental Office or Program Management Office to get set up to work in the database.

The typical process for classifying projects and determining the level of environmental documentation is as follows:

- Once the project has been sufficiently developed to assess any environmental impacts, the region completes the ERS based on the best information available at the scoping phase of development.
- The region Environmental Manager then concurs with the classification by approving the ERS, which enables the completed form to be included in the Project Summary package.
- For NEPA, if a project has been determined to be a Categorical Exclusion (CE), the Environmental Classification Summary/SEPA Checklist (ECS/SEPA Checklist) is completed. The NEPA environmental review process is considered complete when the region Environmental Manager approves the ECS package (guidance is provided in the online Help in the ECS/SEPA Checklist database). If it is determined that a Categorical Exclusion (CE), an Environmental Assessment (EA), or Environmental Impact Statement (EIS) is required, the region evaluates the project schedule and arranges for preparation of the appropriate document.
- For SEPA, the signing and submittal of the ECS/SEPA Checklist completes the environmental classification process. On projects that are categorized as exempt from SEPA, the environmental process is complete unless the project requires consultation under the Endangered Species Act. On projects that do not meet the criteria for a SEPA Categorical Exemption (WACs 197-11-800 and 468-12) and require a SEPA checklist (WAC 197-11-960) or an EIS, those documents are prepared as necessary prior to Project Development Approval.

At this early stage, the ERS allows environmental staff to consider potential impacts and mitigations and required permits. For many projects, the WSDOT Geographic Information System (GIS) Workbench coupled with a site visit provides sufficient information to fill out the ERS (see the GIS Workbench online Help).

For most WSDOT projects, the Federal Highway Administration (FHWA) is the lead agency for NEPA. Other federal lead agencies on WSDOT projects are the U.S. Army Corps of Engineers, Federal Aviation Administration, Federal Railroad Administration, and Federal Transit Administration.

225.04 Identifying the Project Classification

Based on the environmental considerations identified during preparation of the ERS, WSDOT projects are classified for NEPA/SEPA purposes to determine the type of environmental documentation required. Projects with a federal nexus (using federal funds, involving federal lands, or requiring federal approvals or permits) are subject to NEPA and SEPA. Projects that are state funded only, with no federal nexus, follow SEPA guidelines. Since many WSDOT projects are prepared with the intent of obtaining federal funding, NEPA guidelines are usually followed. (See Chapter 300 of the *Environmental Manual* for more information.)

225.05 Environmental Commitment File

As an initial part of project development, the region establishes a project commitment file. Establishment of this file generally coincides with preparation of the environmental documentation. The file consists of proposed mitigation measures; commitments made to regulatory agencies, tribes, and other stakeholders; and other documented commitments made on the project. Further commitment types (right of way, maintenance, and so on) may be added at the region's discretion.

The region Environmental Office is responsible for creating and maintaining the commitment file as a project progresses through its development process. Whenever commitments are made, they are incorporated into project documents and added to the environmental commitment file once they are finalized. Commitments are typically included within, but not limited to, the following documents or approvals and any of their supplements or amendments:

- Memoranda, Agreements, Letters, Electronic Communications
- No-Effect Letters
- Biological Assessments
- Biological Opinions
- Concurrence Letters
- SEPA Checklists
- NEPA Categorical Exclusions
- NEPA Environmental Assessments
- NEPA/SEPA Environmental Impact Statements
- Finding of No Significant Impact (FONSI)
- Record of Decision (ROD)

- Section 106 Concurrence Letter from Tribes and Department of Archaeology & Historic Preservation
- Mitigation Plans
- Environmental Permits and Applications, and Associated Drawings and Plans

Additional information (see Procedure 490-a) for establishing a commitment file is available online at WSDOT's Tracking Commitments webpage. WSDOT has a Commitment Tracking System to organize and track commitments from the commitment file. Refer to the *Environmental Manual* (Chapter 490) for policies associated with tracking commitments.

225.06 Environmental Permits and Approvals

WSDOT projects are subject to a variety of federal, state, and local environmental permits and approvals. Understanding and anticipating what permits and approvals may be required for a particular project type will assist the designer in project delivery. The Environmental Permitting website provides guidance on the applicability of permits and approvals. Because the facts of each project vary and the environmental regulations are complex, reliance on either the Design Manual or the *Environmental Manual* is insufficient. Consult region environmental staff.

The Environmental Review Summary, which is prepared as part of the Project Summary, identifies some of the most common environmental permits that might be required based on the information known at that stage. As the project design develops, additional permits and approvals can be identified. Conducting project site visits for engineering and environmental features may reduce project delays caused by late discoveries. Coordinate with and communicate any project changes to region environmental staff.

The permit process begins well in advance of the actual permit application. For some permits, WSDOT has already negotiated permit conditions through the use of programmatic and general permits. These permits typically apply to repetitive, relatively simple projects, and the permit conditions apply regardless of the actual facts of the project type. For complex projects, the negotiations with permit agencies often begin during the environmental documentation phase for compliance with the National Environmental Policy Act (NEPA) and the State Environmental Policy Act (SEPA). The mitigation measures developed for the NEPA/SEPA documents are captured as permit conditions on the subsequent permits.

Environmental permits require information prepared during the design phase to demonstrate compliance with environmental rules, regulations, and policies. To avoid delays in project delivery, it is necessary for the designer to understand and anticipate this exchange of information. The timing of this exchange often affects design schedules, while the permit requirements can affect the design itself. In complex cases, the negotiations over permit conditions can result in iterative designs as issues are raised and resolved.

225.07 Documentation

Refer to Chapter 300 for design documentation requirements.

Chapter 300 Design Documentation, Approval, and Process Review

300.01 General
300.02 WSDOT Project Delivery
300.03 Design Documentation and Records Retention Policy
300.04 Project Design Approvals
300.05 FHWA Oversight and Approvals
300.06 Project Documents and Approvals
300.07 Process Review
300.08 References

300.01 General

This chapter provides the WSDOT design procedures, documentation and approvals necessary to deliver successful projects on the transportation network in Washington, including projects involving the Federal Highways Administration.

This chapter presents critical information for design teams, including:

- WSDOT's Project Development process.
- Design documentation tools, procedures, and records retention policy.
- Major Project approvals including Design Approval, Project Development Approval, Basis of Design, Design Analysis, and other specific project documents for design-bid-build and for design-build delivery methods.
- FHWA oversight and approvals on Projects of Division Interest (PoDI).
- WSDOT and FHWA approvals for non-PoDI projects including Interstate new and reconstruction and other specific documents as shown in the approvals exhibits.
- Information about conducting project process reviews.
- Additional references and resources.

For local agency and developer projects on state highways, design documentation is also needed. It is retained by the region office responsible for the project oversight, in accordance with the WSDOT records retention policy. All participants in the design process are to provide the appropriate documentation for their decisions. For more information about these types of projects, see the *Local Agency Guidelines* and *Development Services Manual* available at the Publications Services Index website:
www.wsdot.wa.gov/Publications/Manuals/index.htm

For operational changes identified by the Traffic Office Low Cost Enhancement or Field Assessment Program that are included in a project, design documentation is also needed. It is retained by the region office responsible for the project oversight, in accordance with the WSDOT records retention policy. This documentation will be developed by the region Traffic Office in accordance with HQ Traffic Office direction and included in the design documentation for the project.

For emergency projects, also refer to the *Emergency Relief Procedures Manual*. It provides the legal and procedural guidelines for WSDOT employees to prepare all necessary documentation to respond to, and recover from, emergencies and disasters that affect the operations of the department.

300.02 WSDOT Project Delivery

A project, and its delivery method, is developed in accordance with all applicable procedures, Executive Orders, Directives, Instructional Letters, Supplements, and manuals; the Washington State Highway System Plan; approved corridor sketches and planning studies; the FHWA/WSDOT Stewardship and Oversight Agreement; scoping phase documentation, and the Basis of Design.

The delivery method is determined using the WSDOT Project Delivery Method Selection Guidance Memorandum found here:
www.wsdot.wa.gov/Projects/delivery/designbuild/PDMSG.htm

See the implementation memorandum for procedural policy and guidance in the selection of probable and final project delivery method, timing for these determinations, and approval and endorsement levels.

The region develops and maintains documentation for each project using this chapter and the Project File / Design Documentation Package checklists (see 300.03(3))

Refer to the *Plans Preparation Manual* for PS&E documentation. Exhibit 300-4 is an example checklist of recommended items to be turned over to the construction office at the time of project transition. An expanded version is available here:
www.wsdot.wa.gov/design/projectdev/

300.02(1) Environmental Requirements

All projects involving a federal action require National Environmental Policy Act (NEPA) documentation. WSDOT uses the Environmental Review Summary (ERS) portion of Project Summary for FHWA concurrence on the environmental class of action (EIS/EA/CE). The environmental approval levels are shown in Exhibit 300-2.

Upon receipt of the ERS approval for projects requiring an EA or EIS under NEPA, the region proceeds with environmental documentation, including public involvement, appropriate for the magnitude and type of the project (see Chapter 210 and *WSDOT Community Engagement Plan*).

300.02(2) Real Estate Acquisition

Design Approval and approval of right of way plans are required prior to acquiring property. A temporary construction easement may be acquired prior to Design Approval for State funded projects and with completion of NEPA for Federally funded projects. For early acquisition of right of way, consult the Real Estate Services Office, the April 2, 2013 memorandum on early acquisition policy, and *Right of Way Manual* Chapter 6-3.

300.03 Design Documentation and Records Retention Policy

300.03(1) Purpose

Design documentation records the evaluations and decisions by the various disciplines that result in design recommendations. Design assumptions and decisions made prior to and during the scoping phase are included. Changes that occur throughout project development are documented. Required justifications and approvals are also included.

300.03(2) Certification of Documents by Licensed Professionals

All original technical documents must bear the certification of the responsible licensee as listed in Executive Order E 1010.

300.03(3) Project File and Design Documentation Package

The Project File and Design Documentation Package include documentation of project work, including planning; scoping; community engagement; environmental action; the Basis of Design; right of way acquisition; Plans, Specifications, and Estimates (PS&E) development; project advertisement; and construction.

The **Project File (PF)** contains the documentation for planning, scoping, programming, design, approvals, contract assembly, utility relocation, needed right of way, advertisement, award, construction, and maintenance review comments for a project. A Project File is completed for all projects and is retained by the region office responsible for the project. Responsibility for the project may pass from one office to another during the life of a project, and the Project File follows the project as it moves from office to office. With the exception of the DDP, the Project File may be purged when retention of the construction records is no longer necessary.

See the Project File checklist for documents to be preserved in the Project File:
www.wsdot.wa.gov/Design/Support.htm

The **Design Documentation Package (DDP)** is a part of the Project File and preserves the decision documents generated during the design process. In each package, a summary (list) of the documents included is recommended. The DDP documents and explains design decisions, design criteria, and the design process that was followed. The DDP is retained in a permanent retrievable file for a period of 75 years, in accordance with the Washington State Department of Transportation (WSDOT) records retention policy.

The Basis of Design, Design Parameters, Alternatives Comparison Table, and Design Analyses are tools developed to document WSDOT practical design and decisions. Retain these in the DDP.

Refer to the remainder of this chapter and DDP checklist for documents to be preserved in the DDP. See Design Documentation Package Checklist here:
www.wsdot.wa.gov/Design/Support.htm

300.04 Project Design Approvals

This section describes WSDOT's project design milestones known as Design Approval and Project Development Approval. They are required approvals regardless of delivery method chosen by WSDOT. Many of the documents listed under these milestones are described further in 300.06.

Information pertaining to FHWA approvals and oversight is provided in 300.05 which describes Projects of Division Interest (PoDI) which are governed by a separate plan that specifies FHWA and State responsibilities for the project. Documents for projects requiring FHWA review, Design Approval, and Project Development Approval are submitted through the HQ Design Office.

300.04(1) Design Approval

When the Project Summary (see 300.06) documents are approved, and the region is confident that the proposed design adequately addresses the purpose and need for the project, a Design Approval should be pursued and granted at this early stage. Early approval is beneficial at this point in the design phase and is most relevant to larger projects with longer PE phases Design Approval establishes the policy for three years. This is a benefit for longer PE phases in that it avoids design changes due to policy updates during that time and provides consistency when purchasing right of way or producing environmental documentation.

The items below are included in the combined Design Approval/Project Development Approval Package. Design Approval may occur prior to NEPA approval. Generally, Design Approval will not be provided prior to an IJR being approved on an Interstate project. Approval levels for design and PS&E documents are presented in Exhibits 300-1 through 300-3.

The following items are to be provided for Design Approval. See 300.06 for additional information.

- Stamped cover sheet (project description)
- A reader-friendly memo that describes the project
- Project Summary documents
- Basis of Design
- Alternatives Comparison Table
- Design Parameters worksheets
- Crash Analysis Report or Safety Analysis
- Design Analysis
- List of known Variances (contact your ASDE)
- Channelization plans, intersection plans, or interchange plans (if applicable)
- Alignment plans and profiles (if project significantly modifies either the existing vertical or horizontal alignment)
- Current cost estimate with a Basis of Estimate
- Completed Environmental Review Summary (see Section 300.02(1)). Required environmental documentation (Design-Build projects only) Required environmental documentation (Design-Build projects only)

Design Approval is entered into the Design Documentation Package and remains valid for three years or as approved by the HQ Design Office.

- If the project is over this three-year period and has not advanced to Project Development Approval, evaluate policy changes or revised design criteria that are adopted by the department during this time to determine whether these changes would have a significant impact on the scope or schedule of the project.
- If it is determined that these changes will not be incorporated into the project, document this decision with a memo from the region Project Development Engineer that is included in the DDP.
- For an overview of design policy changes, consult the Detailed Chronology of Design Manual revisions: www.wsdot.wa.gov/design/policy/default.htm

300.04(1)(a) Design-Build Projects

Design Approval applies to design-build projects and is required prior to issuing a design-build request for proposal (RFP).

Environmental documentation completion is recommended prior to issuing RFP, but is required prior to contract execution.

300.04(2) Project Development Approval

When all project development documents are completed and approved, Project Development Approval is granted by the approval authority designated in Exhibit 300-1. The Project Development Approval becomes part of the DDP.

Refer to this chapter and the DDP checklist for design documents that may lead to Project Development Approval. Exhibits 300-1 through 300-3 provide approval levels for project design and PS&E documents.

The following items must be approved prior to Project Development Approval:

- Required environmental documentation
- Design Approval documents (and any supplements)
- Updated Basis of Design
- Updated list of Variances (Contact your ASDE)
- Updated Cost estimate
- Stamped cover sheet (project description)

Project Development Approval remains valid for three years.

- Evaluate policy changes or revised design criteria that are adopted by the department during this time to determine whether these changes would have a significant impact on the scope or schedule of the project.
- If it is determined that these changes will not be incorporated into the project, document this decision with a memo from the region Project Development Engineer that is included in the DDP.

- For an overview of design policy changes, consult the Detailed Chronology of Design Manual revisions: www.wsdot.wa.gov/design/policy/default.htm

300.04(2)(a) Design-Build Projects

For design-build projects, the design-builder shall refer to the project Request for Proposal (RFP) for specification on final and intermediate deliverables and final records for the project. Project Development Approval is required prior to project completion.

It is a prudent practice to start the compilation of design documentation early in a project and to acquire Project Development Approval before the completion of the project. At the start of a project, it is critical that WSDOT project administration staff recognize the importance of all required documentation and how it will be used in the design-build project delivery process.

300.05 FHWA Oversight and Approvals

The March 2015 Stewardship & Oversight (S&O) Agreement between WSDOT and FHWA Washington Division created new procedures and terminology associated with FHWA oversight and approvals. One such term, and new relevant procedure, is "Projects of Division Interest" (PoDI) described below.

For all projects, on the National Highway System (NHS), the level of FHWA oversight and approvals can vary for numerous reasons such as type of project, the agency doing the work, PoDI/non-PoDI designation, and funding sources. Oversight and funding do not affect the level of design documentation required for a project.

Documents for projects requiring FHWA review, Design Approval, and Project Development Approval are submitted through the HQ Design Office.

300.05(1) FHWA Projects of Division Interest (PoDI)

Projects of Division Interest (PoDI) are a primary set of projects for which FHWA determines the need to exercise oversight and approval authority. These are projects that have an elevated risk, contain elements of higher risk, or present a meaningful opportunity for FHWA involvement to enhance meeting program or project objectives. Collaborative identification of these projects allows FHWA Washington Division to concentrate resources on project stages or areas of interest. It also allows WSDOT to identify which projects are PoDIs and plan for the expected level of engagement with FHWA.

The Stewardship & Oversight Agreement generally defines Projects of Division Interest as:

- Major Projects (A federal aid project with total cost >$500M)
- TIGER Discretionary Grant Projects
- NHS Projects that may require FHWA Project or Program Approvals
- Projects Selected by FHWA based on Risk or Opportunity

The S&O Agreement also states: Regardless of retained project approval actions, any Federal-aid Highway Project either on or off the NHS that the Division identifies as having an elevated level of risk can be selected for risk-based stewardship and oversight and would then be identified as a PoDI.

For each project designated as a PoDI, FHWA and WSDOT prepare a Project-Specific PoDI Stewardship & Oversight Agreement which identifies project approvals and related responsibilities specific to the project.

300.05(2) FHWA Approvals on Non-PoDI Projects

On projects that are not identified as PoDI, FHWA approvals are still required for various items as shown in Exhibit 300-1. For example, FHWA approval is still required for any new or revised access point (including interchanges, temporary access breaks, and locked gate access points) on the Interstate System, regardless of funding source or PoDI designation (see Chapter 550).

The Exhibit 300-1 approval table refers to New/Reconstruction projects on the Interstate. New/Reconstruction projects include the following types of work:

- Capacity changes: add a through lane, convert a general-purpose (GP) lane to a special-purpose lane (such as an HOV or HOT lane), or convert a high-occupancy vehicle (HOV) lane to GP.
- Other lane changes: add or eliminate a collector-distributor or auxiliary lane. (A rural truck climbing lane that, for its entire length, meets the warrants in Chapter 1270 is not considered new/reconstruction.)
- New interchange.
- Changes in interchange type such as diamond to directional or adding a ramp.
- New or replacement bridge (on or over, main line, or interchange ramp).
- New Safety Rest Areas Interstate.

Documents for projects requiring FHWA review, Design Approval, and Project Development Approval are submitted through the HQ Design Office.

300.06 Project Documents and Approvals

This section lists several major design documents generated for a project and they all are retained in the Design Documentation Package. The Basis of Design, Alternatives Comparison Table, Design Parameters, and Design Analyses are tools used to document practical design decisions.

See the Project File and Design Documentation Package checklists described in 300.03(3) for complete list of documents.

For approval levels see Exhibits 300-1 through 300-3 or a project-specific S&O Agreement for PoDI projects.

300.06(1) Project Summary

The Project Summary provides information on the results of the scoping phase; links the project to the Washington State Highway System Plan and the Capital Improvement and Preservation Program (CIPP); and documents the design decisions, the environmental classification, and agency coordination. The Project Summary is developed and approved before the project is funded for design and construction, and it consists of the ERS, and PD documents. The Project Summary database contains specific online instructions for completing the documents.

300.06(1)(a) Project Definition (PD)

The PD identifies the various disciplines and design elements that are anticipated to be encountered in project development. It also states the purpose and need for the project, the program categories, and the recommendations for project phasing. The PD is initiated early in the scoping phase to provide a basis for full development of the ERS, schedule, estimate, Basis of Estimate, and Basis of Design (where indicated in scoping instructions). If circumstances necessitate a change to an approved PD, process a Project Change Request Form for approval by the appropriate designee.

300.06(1)(b) Environmental Review Summary (ERS)

The ERS lists the potentially required environmental permits and approvals, environmental classifications, and environmental considerations. The ERS is prepared during the scoping phase and is approved by the region. If there is a change in the PD, the information in the ERS must be reviewed and revised to match the rest of the Project Summary. For actions classified as a CE under NEPA, the approved ERS becomes the ECS when the project is funded and moves to design. The region may revise the ECS as appropriate (usually during final design) as the project advances. The ECS serves as the NEPA environmental documentation for CE projects. The region Environmental Manager approves the ECS and may send it to FHWA for their approval. The ERS/ECS database includes fully integrated help screens that provide detailed guidance. Contact your region Environmental Office for access.

300.06(2) Basis of Design (BOD)

The BOD captures important decisions that control the outcome of a project, including identified performance needs, context, design controls and design elements necessary to design the practical alternative. When applicable attach supporting documents, such as the Alternatives Comparison Table and Design Parameters to the BOD. (See Chapter 1100 for further discussion on these documents). The Basis of Design (BOD) is part of the DDP.

300.06(3) Basis of Estimate (BOE)

The BOE contains the assumptions, risks, and information used to develop an estimate. The BOE is reviewed and updated during each phase of a project. The confidence of the estimate, either overall or for particular items, is also identified within the BOE. Generally, the BOE is started during the scoping phase because it is required for Project Summary approval; however, in more complex situations the BOE may have begun during the planning phase. For more information, see the *Cost Estimating Manual for WSDOT Projects*.

300.06(4) Design Analysis

A Design Analysis is a process and tool used to document important design decisions, summarizing information needed for an approving authority to understand and support the decision.

A Design Analysis is required where a dimension chosen for a design element that will be changed by the project is outside the range of values provided for that element in the *Design Manual*. A Design Analysis is also required where the need for one is specifically referenced in the *Design Manual*.

A region approved Design Analysis is required if a dimension or design element meets current AASHTO guidance adopted by the Federal Highway Administration (FHWA), such as A Policy on Geometric Design of Highways and Streets, but is outside the corresponding *Design Manual* criteria. See Exhibit 300-1 for Design Analysis approval authorities.

In the case of a shoulder width reduction at an existing bridge pier or abutment, sign structure or luminaire base in a run of median barrier, the Design Parameter Sheet may be used instead of a Design Analysis to document the dimensioning decision for the shoulder at that location.

A template is available to guide the development of the Design Analysis document here: www.wsdot.wa.gov/design/support.htm.

Email a PDF copy of all Region approved Design Analyses to the ASDE supporting your region.

300.07 Process Review

The Assistant State Design Engineers work with the regions on project development and conduct process reviews on projects. The process review is done to provide reasonable assurance that projects are prepared in compliance with established policies and procedures and that adequate records exist to show compliance with state and federal requirements. Process reviews are conducted by WSDOT, FHWA, or a combination of both.

The design and PS&E process review is performed at least once each year by the HQ Design Office. The documents used in the review process are the Design Documentation Package Checklist(s), Basis of Design, Basis of Estimate, the PS&E Review Checklist, and the PS&E Review Summary. These are generic forms used for all project reviews. Copies of these working documents are available for reference when assembling project documentation. The HQ Design Office maintains current copies at: www.wsdot.wa.gov/design/support.htm.

Each project selected for review is examined completely and systematically beginning with the scoping phase (including planning documents) and continuing through contract plans and, when available, construction records and change orders. Projects are normally selected after contract award. For projects having major traffic design elements, the HQ Traffic Operations Office is involved in the review. The WSDOT process reviews may be held in conjunction with FHWA process reviews.

The HQ Design Office schedules the process review and coordinates it with the region and FHWA.

300.07(1) Process Review Agenda

When conducting joint process review with FHWA, the Process Review Report will outline specific agenda items.

A WSDOT process review follows this general agenda:

1. Review team meets with region personnel to discuss the objective of the review.
2. Review team reviews the design and PS&E documents, construction documents, and change orders (if available) using the checklists.
3. Review team meets with region personnel to ask questions and clarify issues of concern.
4. Review team meets with region personnel to discuss findings.

5. Review team submits a draft report to the region for comments and input.
6. If the review of a project shows a serious discrepancy, the region design authority is asked to report the steps that will be taken to correct the deficiency.
7. Process review summary forms are completed.
8. Summary forms and checklists are evaluated by the Director & State Design Engineer, Development Division.
9. Findings and recommendations of the Director & State Design Engineer, Development Division, are forwarded to the region design authority for action and/or information within 30 days of the review.

300.08 References

300.08(1) Federal/State Laws and Codes

23 Code of Federal Regulations (CFR) 635.111, Tied bids

23 CFR 635.411, Material or product selection

Revised Code of Washington (RCW) 47.28.030, Contracts – State forces – Monetary limits – Small businesses, minority, and women contractors – Rules

RCW 47.28.035, Cost of project, defined

"Washington Federal-Aid Stewardship Agreement,"
www.wsdot.wa.gov/publications/fulltext/design/ASDE/2015_Stewardship.pdf

300.08(2) Design Guidance

WSDOT Directional Documents Index, including the one listed below:
http://wwwi.wsdot.wa.gov/publications/policies

Executive Order E 1010, "Certification of Documents by Licensed Professionals," WSDOT

WSDOT technical manuals, including those listed below:

www.wsdot.wa.gov/publications/manuals/index.htm

- *Advertisement and Award Manual*, M 27-02, WSDOT
- *Cost Estimating Manual for WSDOT Projects*, M 3034.03, WSDOT
- *Design Manual*, M 22-01, WSDOT
- *Emergency Relief Procedures Manual*, M 3014, WSDOT
- *Environmental Manual*, M 31-11, WSDOT
- *Hydraulics Manual*, M 23-03, WSDOT
- *Highway Runoff Manual*, M 31-16, WSDOT
- *Plans Preparation Manual*, M 22-31, WSDOT
- *Project Control and Reporting Manual*, M 3026, WSDOT
- *Roadside Manual*, M 25-30, WSDOT
- *Roadside Policy Manual*, M 3110, WSDOT
- *Temporary Erosion and Sediment Control Manual*, M 3109, WSDOT

Limited Access and Managed Access Master Plan, WSDOT
www.wsdot.wa.gov/design/accessandhearings/

Washington State Highway System Plan, WSDOT
www.wsdot.wa.gov/planning/

300.08(3) Supporting Information

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO, 2011

Mitigation Strategies for Design Exceptions, FHWA, July 2007. This publication provides detailed information on design exceptions and mitigating the potential adverse impacts to highway safety and traffic operations.

Highway Capacity Manual (HCM), latest edition, Transportation Research Board, National Research Council

Highway Safety Manual (HSM), AASHTO

Exhibit 300-1 Approval Authorities

Project Type	Basis of Design (BOD) Approval	Design Analysis Approval [1] [2] [11]	Design Approval and Project Development Approval
Project of Division Interest (PoDI)	[10]	[10]	[10]
Interstate			
New/Reconstruction Regardless of funding source [3]	FHWA	FHWA	FHWA [4]
Intelligent Transportation Systems (ITS) Improvement Project over $1 million Preservation project	 HQ Design HQ Design	 HQ Design HQ Design	 HQ Design Region
All Other Regardless of funding source [12]	HQ Design	HQ Design	Region
National Highway System (NHS)			
Projects on all limited access highways, or on managed access highways outside of incorporated cities and towns	HQ Design	HQ Design [5]	Region
Projects on managed access highways within incorporated cities and towns Inside curb or EPS [6][7] Outside curb or EPS	 HQ Design City/Town	 HQ Design HQ LP	 Region City/Town
Non-National Highway System (Non-NHS)			
Improvement projects on all limited access highways, or on managed access highways outside of incorporated cities and towns	HQ Design	HQ Design	Region
Improvement projects on managed access highways within incorporated cities and towns [9] Inside curb or EPS [6][7] Outside curb or EPS	 HQ Design City/Town	 HQ Design HQ LP	 Region City/Town
Preservation projects on limited access highway, or on managed access highways outside of incorporated cities and towns, or within unincorporated cities and towns [8]	Region	Region	Region
Preservation projects on managed access highways within incorporated cities and towns [8] Inside curb or EPS [6][7] Outside curb or EPS	 Region City/Town	 Region HQ LP	 Region City/Town

FHWA = Federal Highway Administration
HQ = WSDOT Headquarters
HQ LP = WSDOT Headquarters Local Programs Office
EPS = Edge of paved shoulder where curbs do not exist
NHS = National Highway System
www.wsdot.wa.gov/mapsdata/travel/hpms/NHSRoutes.htm

For table notes, see the following page.

Exhibit 300-1 Approval Authorities (continued)

Notes:

[1] These approval levels also apply to Design Analysis processing for local agency and developer work on a state highway.

[2] See 300.06(4). Where still encountered in the *Design Manual* replace the term *deviation* with *Design Analysis*.

[3] For definition of New/Reconstruction, see 300.05(2).

[4] FHWA will provide Design Approval prior to NEPA Approval, but will not provide Project Development Approval until NEPA is complete.
http://www.wsdot.wa.gov/publications/fulltext/design/ASDE/2015_Stewardship.pdf

[5] For guidance on the need for Design Analyses related to access management, see Chapters 530 and 540.

[6] Includes raised medians (see Chapter 1600).

[7] Curb ramps are still included (see Chapter 1510).

[8] For Bridge Replacement projects in the Preservation program, follow the approval level specified for Improvement projects.

[9] Refer to RCW 47.24.020 for more specific information about jurisdiction and responsibilities that can affect approvals.

[10] Projects of Division Interest (PoDI) must receive FHWA approvals per the PoDI Agreement regardless of funding source or project type.

[11] A region approved Design Analysis is required if a dimension or design element meets current AASHTO guidance adopted by the Federal Highway Administration (FHWA), such as *A Policy on Geometric Design of Highways and Streets*, but is outside the range of corresponding *Design Manual* criteria. Email a PDF copy of all Region approved Design Analyses to the ASDE supporting your region.

[12] Reduction of through lane or shoulder widths (regardless of project type) requires FHWA review and approval, except shoulder reductions for existing bridge pier or abutment, sign structure or luminaire base in a run of median barrier as allowed by 300.06(4).

Exhibit 300-2 Approvals

Item	Approval Authority		
	Region	HQ	FHWA
Program Development			
Work Order Authorization		**X**	**X** [1]
Public Hearings			
Corridor Hearing Summary		**X** [2]	
Design Hearing Summary		**X** [3]	**X** [8]
Limited Access Hearing Plan		**X** [4]	
Limited Access Findings and Order		**X** [5]	
Environmental Document			
Class l NEPA (EIS)		[7]	**X**
SEPA (EIS)		**X**	
Class II NEPA – Categorical Exclusion (CE) Documented in ECS form	**X**		
SEPA – Categorical Exemption (CE)	**X**		
Class lll NEPA – Environmental Assessment (EA)		[7]	**X**
SEPA Environmental Checklist & Determination of Non-Significance (DNS)	**X**		
Design			
Basis of Design (BOD)	[9]	[9]	[9]
Intersection Control Type	**X** [20]	X [22]	
Experimental Features		**X**	**X**
Environmental Review Summary	**X**		
Final Project Definition		**X** [10]	
Interstate Interchange Justification Report		[7]	**X**
Any Break in Interstate Limited Access		[7]	**X**
Non-Interstate Interchange Justification Report		**X**	
Break in Partial or Modified Limited Access		**X**	
Intersection or Channelization Plans	**X**		
Right of Way Plans	[11]	**X**	
Monumentation Map	**X**		
Materials Source Report		**X** [12]	
Pavement Determination Report		**X** [12]	
Roundabout Geometric Design (see Chapter 1320 for guidance)	**X**		
Resurfacing Report		**X** [12]	
Signal Permits	**X** [13]		
Geotechnical Report		**X** [12]	
Tied Bids	**X** [14]		

Table continued on the following page, which also contains the notes.

Exhibit 300-2 Approvals (continued)

Item	Approval Authority		
	Region	HQ	FHWA
Bridge Design Plans (Bridge Layout)	X	X	
Preliminary Bridge Plans for Unusual/Complex Bridges on the Interstate		[7]	X
Structures Requiring TS&Ls		X	
Hydraulic Report	X [15]	[15]	
Preliminary Signalization Plans		X [6][18]	
Signalization Plans	X [20]		
Illumination Plans	X [20]		
Intelligent Transportation System (ITS) Plans	X [20]		
ITS Systems Engineering Analysis Worksheet (Exhibit 1050-2)	X [20]		
Rest Area Plans		X	
Roadside Restoration Plans	X [16]	X [17]	
Planting Plans	X [16]	X [17]	
Grading Plans	X		
Continuous Illumination – Main Line		X [18]	
Tunnel Illumination		X [18]	
High Mast Illumination		X [18]	
Project Change Request Form	X [19]	X [19]	
Work Zone Transportation Management Plan/Traffic Control Plan	X [20]		
Public Art Plan – Interstate (see Chapter 950)	X [16]	X [17][21]	X
Public Art Plan – Non-Interstate (see Chapter 950)	X [16]	X [17][21]	
Crash Analysis Report	X [20]	X	
ADA Maximum Extent Feasible Document (see Chapter 1510)	X	X	

Notes:

[1] Federal-aid projects only.

[2] Approved by Assistant Secretary, Engineering & Regional Operations.

[3] Approved by Director & State Design Engineer, Development Division.

[4] Approved by Right of Way Plans Manager.

[5] Refer to Chapter 210 for approval requirements.

[6] Final review & concurrence required at the region level prior to submittal to approving authority.

[7] Final review & concurrence required at HQ prior to submittal to approving authority.

[8] On Interstate projects, the Director & State Design Engineer, Development Division, (or designee) submits the approved design hearing summary to the FHWA for federal approval. (See Chapter 210.)

[9] See Exhibit 300-1 for BOD Approvals.

[10] Approved by HQ Capital Program Development and Management (CPDM).

[11] Certified by the responsible professional licensee.

[12] Submit to HQ Mats Lab for review and approval.

[13] Approved by Regional Administrator or designee.

[14] Per 23 CFR 635.111.

[15] See the *Hydraulics Manual* for approvals levels.

[16] Applies to regions with a Landscape Architect.

[17] Applies to regions without a Landscape Architect.

[18] Approved by State Traffic Engineer.

[19] Consult CPDM for clarification on approval authority.

[20] Region Traffic Engineer or designee.

[21] The State Bridge and Structures Architect reviews and approves the public art plan (see Chapter 950 for further details on approvals).

[22] State Traffic Engineer or designee.

Exhibit 300-3 PS&E Process Approvals NHS (including Interstate) and Non-NHS

Item	Headquarters or Region Approval Authority
DBE/training goals * **	Office of Equal Opportunity
Right of way certification for federal-aid projects***	Region; HQ Real Estate Services Office or HQ Local Programs Right of Way Manager [7]
Right of way certification for state or local funded projects***	Region; HQ Real Estate Services Office or HQ Local Programs Right of Way Manager
Railroad agreements	HQ Design Office
Work performed for public or private entities *	Region [1][2]
State force work *	Region [3][4]
Use of state-furnished materials *	Region [3][4]
Work order authorization	Capital Program Development and Management [5]
Ultimate reclamation plan approval through DNR	Region
Proprietary item use *	[4][6] HQ Design Office
Mandatory material sources and/or waste sites *	Region [4]
Nonstandard bid item use *	Region
Incentive provisions	HQ Construction Office
Nonstandard time for completion liquidated damages *	HQ Construction Office
Interim liquidated damages *	Statewide Travel and Collision Data Office

Notes:
FHWA PS&E Approval has been delegated to WSDOT unless otherwise stated differently in a Project Specific PoDI S&O Agreement.

[1] This work requires a written agreement.
[2] Region approval subject to $250,000 limitation.
[3] Use of state forces is subject to $60,000 limitation and $100,000 in an emergency situation, as stipulated in RCWs 47.28.030 and 47.28.035. Region justifies use of state force work and state-furnished materials and determines if the work is maintenance or not. HQ CPDM reviews to ensure process has been followed.
[4] Applies only to federal-aid projects; however, document for all projects.
[5] Prior FHWA funding approval required for federal-aid projects.
[6] The HQ Design Office is required to certify that the proprietary product is either: (a) necessary for synchronization with existing facilities, or (b) a unique product for which there is no equally suitable alternative.
[7] For any federal aid project FHWA only approves Right of Way Certification 3s (All R/W Not Acquired), WSDOT approves Right of Way Certification 1s and 2s for all other federal aid projects.

References:
* *Plans Preparation Manual*
** *Advertisement and Award Manual*
*** *Right of Way Manual*

Exhibit 300-4 Design to Construction Transition Project Turnover Checklist Example

This checklist is recommended for use when coordinating project transition from design to construction.

1. Survey

- ❑ End areas (cut & fill)
- ❑ Staking data
- ❑ Horizontal/Vertical control
- ❑ Monumentation/Control information

2. Design Backup

- ❑ Index for all backup material
- ❑ Backup calculations for quantities
- ❑ Geotech shrink/swell assumptions
- ❑ Basis of Design, Design decisions and constraints
- ❑ Approved Design Analyses
- ❑ Hydraulics/Drainage information
- ❑ Clarify work zone traffic control/workforce estimates
- ❑ Geotechnical information (report)
- ❑ Package of as-builts used (which were verified) and right of way files
- ❑ Detailed assumptions for construction CPM schedule (working days)
- ❑ Graphics and design visualization information (aerials)
- ❑ Specific work item information for inspectors (details not covered in plans)
- ❑ Traffic counts
- ❑ Management of utility relocation

3. Concise Electronic Information With Indices

- ❑ Detailed survey information (see Survey above)
- ❑ Archived InRoads data
- ❑ Only one set of electronic information
- ❑ "Storybook" on electronic files (what's what)
- ❑ CADD files

4. Agreements, Commitments, and Issues

- ❑ Agreements and commitments by WSDOT
- ❑ RES commitments
- ❑ Summary of environmental permit conditions/commitments
- ❑ Other permit conditions/commitments
- ❑ Internal contact list
- ❑ Construction permits
- ❑ Utility status/contact
- ❑ Identification of the work elements included in the Turnback Agreement (recommend highlighted plan sheets)

5. Construction Support

- ❑ Assign a Design Technical Advisor (Design Lead) for construction support

An expanded version of this checklist is available at: www.wsdot.wa.gov/design/projectdev

Chapter 301 Design and Maintenance Coordination

301.01 Introduction
301.02 Communication
301.03 Incorporating Maintenance Considerations in Design
301.04 Documentation
301.05 References

301.01 Introduction

Maintenance plays an important role in the Washington State Department of Transportation's (WSDOT's) asset management program by meeting the daily requirements of maintaining and operating over 18,000 lane miles, approximately 2,000 miles of ramps and special-use lanes, and over 3,700 bridge and culvert structures, as well as hundreds of other special-use sites vital to the state's transportation system. Activities in the highway maintenance program protect the public infrastructure as well as provide services necessary for daily operation of the highway system. Typical maintenance activities include patching potholes, cleaning ditches, painting stripes on the roadway, repairing damage to guardrail, and controlling noxious weeds. In addition to maintaining assets, operational services are also provided. They include plowing snow, cleaning rest areas, responding to incidents, operating structures like draw bridges, and operating traffic signals, lighting, and Intelligent Transportation Systems (ITS). This limited list of maintenance and operational activities highlights the significant undertaking of maintaining and operating the State Highway System as designed.

Highway maintenance and operations staff are unique stakeholders, because they utilize, maintain, and operate the facilities' engineering designs and constructs. Given the nature and cost of maintenance work, as well as the exposure inherent in maintenance and operational activities, it is important for designers to consider maintenance and operations staff as major stakeholders in every project. It is also important for maintenance and operations staff to understand the purpose of the project and to participate in determining the best method(s) to keep it functioning as designed while maintaining their responsibilities outside of the specific project limits.

This chapter provides multiple options to help improve coordination with maintenance and operations staff during project design. These "best practices" are a culmination of responses from *Design Manual* user surveys, interviews with maintenance and operations superintendents, and various regional practices that have demonstrated potential improvement related to the coordination of design and maintenance efforts and personnel. ***Note:*** The concepts and methods presented herein do not replace any approved communication or documentation processes that may be currently required by a WSDOT region during the project development process.

301.02 Communication

Communication is the most fundamental component of coordination. Executing communication is often oversimplified by the phrase "communicate early and often." In reality, effective communication is significantly more complex. For example: *Who are you communicating with, what methods of communication are being used, what is being communicated, how are you responding to communication, where is the communication taking place, and when does the communication need to occur to maximize effectiveness?*

The following sections highlight areas that may increase the necessary communication between design and maintenance staff.

301.02(1) Maintenance Organizational Roles

The most important component of communication is knowing who you are communicating with and what their role is within the organization. Just as engineering has multiple disciplines that cover specific areas within engineering, WSDOT's maintenance organization is also divided into multiple discipline areas, each with focused expertise and specific needs that may be relevant to a particular project.



Access to maintain luminaire is provided through use of full shoulder

When asking for maintenance input, it is not sufficient to contact just the Area Maintenance Office that covers that physical geographic area. Depending on the scope of the project, engineering must consult with the appropriate maintenance discipline area. It is a project management responsibility to properly identify and communicate with the appropriate project stakeholders (see EO 1032 – Project Management). It should not be assumed that the Area Maintenance Office will coordinate with all other maintenance disciplines, unless agreed to organizationally or identified within a particular Project Management Plan (PMP). The PMP is the documentation mechanism for identifying the various contacts and their roles within the project. Each region maintenance organization is different, but in general, the following discipline areas are present:

- Area Maintenance
  - Pavement
  - Roadside vegetation control
  - Rest area management
  - Seasonal and emergent maintenance needs
- Signal, Illumination, and ITS Maintenance
- Bridge
- Traffic Operational Maintenance
  - Pavement markings
  - Sign management
  - Incident response



Striping crew restriping after patching pavement

To access a list of superintendents, go to:
http://wwwi.wsdot.wa.gov/maintops/pdf/maintenanceofficephonelist.pdf

To access a list of maintenance performance measures, go to:
http://www.wsdot.wa.gov/maintenance/accountability/default.htm

301.02(2) Communicating Expectations

Project design is heavily influenced by the subprogram and scope of a particular project. While this becomes a learned experience within engineering design, maintenance staff does not routinely work within these types of funding and project constraints. It is important to identify the type of project and elements that can be addressed under the particular subprogram, in order to effectively manage expectations for maintenance stakeholders participating in the project. It is also important to redirect issues presented by maintenance staff that may not be appropriate for your project, but may meet a future need. The project team should work together with maintenance to redirect identified issues to region Program Management to evaluate their relevance for other subprograms or future identified projects, or determine if there are funding mechanisms to include the requested feature(s) on the project in question.



Traffic control needs to maintain the roadside

301.02(3) Communication Timing

There are multiple constraints to consider when establishing the timing of maintenance stakeholder input. *What is the project timeline, when will maintenance involvement be most effective, and which work season(s) are maintenance and operations staff involved with when you need to communicate with them?* Each one of these questions needs to be understood to yield the most effective communication result.



This procession of snow plows clearing the roadway demonstrates the urgency of labor and equipment necessary to maintain operations on the highway during certain seasons

Maintenance staff has identified scoping through the 30% design phase as a critical period for their input. The scoping phase presents opportunities to identify maintenance concerns and adequately address them within the project scope and budget. The period between scoping and 30% design presents opportunities to evaluate and refine options, as well as gain more understanding of project constraints that may impact a previously identified or requested maintenance feature. As the constraints and design trade-offs become evident, it is necessary to review the impacts to maintenance needs and requests that were originally captured in the project scope and ensure they are not impacted by constraints or the options under evaluation.

Maintenance staff are obligated to respond to immediate incidents and weather conditions. They are not often able to delay their work functions and activities to make time for a design project review. It is essential that designers understand this issue and plan for reviews through scheduling techniques (see 301.03(1)(a)). In general, the best time to involve maintenance staff is during their slower work seasons.



Maintenance responds to emergencies, which are more likely to occur during certain seasons

301.02(4) Communication Methods

Maintenance has identified field reviews as the primary and most effective method of communication for their staff. Designers are strongly encouraged to perform multiple field reviews with the appropriate maintenance disciplines. Depending on the size, scope, and location of the project, it may be appropriate to first meet in the office and review the project scope and plans, confirm and endorse the Pre-Activity Safety Plan, then proceed with the field review. Field reviews are recommended at the following periods:

- Scoping phase
- Prior to the 30% design milestone (may need multiple meetings to evaluate design options)
- Each time a previously agreed-to maintenance feature is impacted through design iterations, as appropriate
- Prior to other major design review milestones



Maintenance clearing highway from rockfall overburdening catchment area


A primary purpose for performing field reviews with maintenance is to assist with visualizing the project and to understand existing conditions. When performing the field review, it is important to emphasize the following:

- Reiterate the purpose of the project and subprogram, and discuss maintenance expectations.
- Determine the deficiency being corrected and the understood contributing factors. It is important to gain an understanding from maintenance staff on any other contributing factors or physical conditions that engineers may not be aware of.
- Visualize the project with maintenance:
  - What will be new?
  - What will be removed?
  - What will be replaced, and what is the replacement?
  - Where will new features be located?
  - How will project changes affect neighbors?

- Determine whether the project can be operated and maintained with existing equipment.
  - It is necessary for design and maintenance staff to fully understand the impacts to both the maintenance and project budgets to analyze and balance the obligations for the investments as assets are identified on a project. For example, new lighting means maintenance will be billed for the utility costs. Generally, this increased cost has not resulted in increased funding.
    - Will proprietary item requests be needed so maintenance can maintain the project items with the tools and equipment they currently have?
    - Will new equipment be needed, and who will fund that equipment acquisition?
  - What is the maintenance frequency for affected assets? Will this change?
  - What are the environmental and permit restrictions related to the asset or feature?
  - How might maintenance physically maintain features to understand safety and access needs for the asset or feature?
- Identify explicit action items for design and maintenance staff to follow up on as design iterations continue.
- Document the outcomes of the field meeting, and follow up to ensure maintenance needs are addressed, or provide specific explanations.

In order for maintenance to assist in brainstorming alternative options, engineering design must explain the reasons and constraints behind the previous design options considered and abandoned through the design iteration process.

- Provide maintenance stakeholders the reasons and justification behind design decisions.
- Allow for the time and discussions necessary to brainstorm other options to provide the desired accommodations and features, given the constraints and conflicting performance outcomes identified.
- Before removing any previously discussed maintenance features, always discuss and work on the issue with maintenance staff first.



Cleaning bridge drains requires special equipment and traffic control

While independent reviews of plan sheets are meaningful for engineers, it may be an inappropriate expectation that maintenance staff will see the same value. The repeated familiarity of reviewing plan sheets is not necessarily present within the maintenance staff, and plan review training may or may not be feasible for a given regional maintenance organization based on staffing, workloads, and skill retention.

In some larger regional maintenance organizations, a liaison position has been designated for designers to coordinate plan reviews. This approach has seen some success. However, this liaison cannot possibly be aware of all comments/concerns for every maintenance discipline. Don't assume that coordinating plan reviews through the liaison meets the expectation for maintenance stakeholder input. Always check with the various maintenance disciplines for their preferred contacts and include those contacts within the PMP.

301.03 Incorporating Maintenance Considerations in Design

The intent of this section is to provide some project management options and potential strategies or products to help manage the incorporation of maintenance considerations into a design project.

301.03(1) Project Management and Review Strategies

Design iterations are necessary as information is gained throughout the design process. Designers are constantly forced to balance competing stakeholder needs, regulatory requirements, design criteria, performance outcomes, and physical and political constraints. The following subsections include some recommended strategies for designers throughout the course of a design project.

301.03(1)(a) Project Management and Schedules

1. Include maintenance discipline representatives within the PMP, and identify their specific roles and responsibilities within the design project.

   - This is important for team members, to ensure their inclusion on interdisciplinary decision making and brainstorming options for specific features that may affect only a single or all maintenance disciplines.

2. Schedule the appropriate duration and timing within the project schedule to complete the necessary field reviews with maintenance staff.

   - There are multiple scheduling techniques that may assist you, ensuring this will be well planned based on maintenance staff availability and changing work priorities. Contingency activities, providing more activities detailing the effort, or expanding the duration for single activities may all be appropriate. If uncertain how to best represent the needed time within the schedule, consult the Region Project Management and Reporting System (PMRS) Coordinator for options.

3. As the project works toward constructability reviews, be sure to include appropriate durations for procuring materials.

   - There have been reported instances where maintenance and operations staff has been contacted to temporarily provide equipment while awaiting procurement and acceptance. This creates additional work efforts for maintenance staff to install and remove their equipment to keep a project operational, because inadequate procurement timelines were identified during the design phase.

     Note: Some regions have an internal policy that prohibits use of maintenance equipment on a temporary basis due to poor execution and management of procurement timelines. Designers should verify what options exist if procurement timelines appear problematic in construction staging exercises.



Whenever possible, design should avoid creating environments that might be desirable to the homeless, both for their safety and the safety of maintenance staff

301.03(1)(b) Project Reviews

The skill sets of individuals throughout the department vary with experience and training. Strictly utilizing independent plan reviews to gain maintenance stakeholder input may be inappropriate. While field reviews are an optimal means of communicating and visualizing the project with maintenance, it is not prudent to meet in the field for every change or design iteration of a specific feature. However, design engineers frequently engage multiple stakeholders on a project, and those stakeholders are generally provided visual aids and descriptions in addition to a set of plans.

The same effort can be applied to the maintenance stakeholders. Use pictures of completed products, or generate 3D PDFs and/or working drawings, to better illustrate and visualize the features under discussion. Take the time to understand what matters regarding a particular feature and how it will be maintained, and ensure the illustrations provided depict the worst case for their concerns, not the average. For example, if the steepness of side slopes matters regarding how the feature will be accessed or maintained, be sure to depict how the slope will vary, including the steepest portion, not the typical slope. Every effort should be made to ensure stakeholders understand the balancing act design is working through and how it affects the various maintenance features or assets.



Vactor truck cleaning a catch basin placed directly under guardrail run

Maintenance staff should never be in a position to review project details from a plan sheet without a meeting/discussion, examples, or other means of communicating what feature or issues they are reviewing on the plan sheet. This effort will help ensure there are "no surprises" for maintenance and operations staff when the planned project enters construction.

301.03(2) Maintenance Design Considerations –Tips, Tools, and End Products

There are multiple potential products that design teams should consider to effectively document maintenance considerations. Note that some options presented in the following subsections may be more effective if implemented on a regionwide basis. However, all options can be described as project procedures and should be identified and explained within the PMP.

301.03(2)(a) Establish Maintenance Performance Measures

For a given corridor or project location, it may be advantageous to identify desired performance measures and their established goal(s). Providing a performance-based outcome provides something tangible for designers to evaluate when exploring options. These performance objectives should be specific and state the actual needed outcome, not necessarily a proposed solution (see annotated example in Exhibit 301-1).

Exhibit 301-1 General Input Form with Listed Performance Objectives

MAINTENANCE CONCERNS AND INPUT

WIN	SR	REGION	COUNTY	DATE
D00521I	005	Southwest	Clark	5/21/2014

PROJECT: I-5/Widen and Construct Interchange

TYPE OF WORK: Widening for additional lane and construct two overcrossings, one overcrossing will be a half diamond interchange.

BEGIN MP: 30.0	END MP: 50.0	LENGTH OF PROJECT: 20 miles

FUNCTIONAL CLASS: Interstate – Principal Arterial			
NHS STATUS: NHS			
ROADWAY IS: (check one)	2 lane	multi-lane X	other
NEW/RECONSTRUCTION: (check one)	YES X	NO	

STATEMENT OF PURPOSE: (brief description of work to be completed by the Design Engineer)
This section of Interstate 5 needs additional capacity and improved auto mobility. Capacity will be provided in three ways; improving local circulation by constructing a new overcrossing at Y Street which will remove local auto trips from the Interstate, providing for additional half interchange at Z Street to improve existing X Street Interchange, as well as providing an additional lane on the interstate.

STATEMENT OF CONCERNS: (known maintenance issues within the scope of the proposed project)
It is unclear at this time what assets will remain and what new assets will be installed along this urbanizing location. Since this facility is high speed and high ADT, maintenance offices' primary concern is locating protected access to assets placed and maintaining or improving access to assets planned to remain. Maintenance anticipates significant collaboration needs consisting of multiple site visits with all maintenance disciplines (not just this area office). We have prioritized a list of maintenance performance outcomes to consider when weighing specific asset design options as follows:

- Reduction in Maintenance Exposure to Traffic
- Reduction in Maintenance Frequency to Maintain and Operate
- Lowest Maintenance Life Cycle Cost

Area Superintendent:	Date:
John Doe	5/21/2014
Area Supervisor:	Date:
Jonny Smith	5/15/2014
Lead Tech:	Date:
Jane Smith	5/1/2014

301.03(2)(b) Evaluate Maintenance Lifecycle Cost

Designers should work with maintenance to understand the full life cycle cost for maintaining a certain feature. Maintenance will need to provide and explain to design:

- The frequency of maintaining the asset
- Labor costs
- Material costs
- Traffic control costs
- Utility costs
- Additional equipment costs (cost to repair if equipment owned, rental costs, or purchase cost of new equipment needed)
- Cost of procuring replacement parts for the asset

Additionally, maintenance and operations staff should identify some qualitative risks and opportunities associated with certain assets. Some opportunities, like the one presented in Exhibit 301-2, may not be possible depending on material availability or funding restrictions.

It is important for designers to understand that some products may have a short shelf-life. Procuring new replacement parts in the future may not be possible, which may result in a search for used parts or the total replacement of the particular asset. These are future risks that need to be identified so design engineers will understand what options or special provisions may be required to help address the potential risks. Maintenance staff can help design understand the history of different assets and determine options that have been successful for a given maintenance location. Design engineers also need to communicate the requirements and disadvantages of proprietary items specifically requested by maintenance. While it may be the desired product that maintenance is familiar with, it may not be the best product for what is being designed.



Replacing a guardrail is not a simple activity

It is necessary to both determine the life span for a particular asset and utilize discounted cash flow techniques to understand the present worth of the future expenditures. The discounting process can be complex; however, for the purposes of evaluating maintenance life cycle cost, it is acceptable to use a flat discount rate applied to the sum of all future maintenance expenditures. In Exhibit 301-2, the asset life span is 20 years, and the discount rate is approximately 80% (based on a 4% interest rate per year). If the asset life span is different, then the discount rate will also change. To determine the life span of a particular asset type and the approximate discount rate for that life span, contact the Asset Management Group within the Capital Program Development and Management Office.

After analyzing the life cycle cost to maintain a particular asset, and demonstrating an understanding of the associated risks, design and maintenance staff can justify the best return on the construction investment. While the primary intent of this process is to document justification for an asset decision, it is important that region Maintenance is supplied with the information as well. Providing this information during the design process can inform maintenance budgetary scenarios. Allow sufficient time for maintenance to capture budget impacts and apply for the necessary funding in the bi-annual maintenance budgeting process.

Exhibit 301-2 Design Option Worksheet Showing Example of Life Cycle Cost Assessment

Design Options Worksheet



Engineer: Jane Smith
Maintenance Representative: John Doe

Project Information:
Title: SR Rural Highway/BST and Guardrail Repair
Design Speed: 60 mph
2 lane rural arterial highway
P1 – Paving and P3 – Guardrail Replacement
Project Deficiencies: Pavement degradation due to normal wear; non-standard guardrail height at various locations
Proposed Scope: pavement repair, BST travelled way from MP 15 to MP 32, and replace identified guardrail priorities from MP16.5 to 17; 20.2 to 20.3; 30.6 to 31.1

Segment Problem Statement:
Maintenance has identified this segment of highway as a high frequency repair location. Maintenance records for the past 3 years has indicated location requires guardrail repair on average twice a year. Collision data does not show any run off the road collision reporting. The lack of shoulder and work area behind the guardrail requires one way traffic control operations, and exposes maintenance staff to traffic. Maintenance staff has requested additional analysis of design options at this location.

Segment Location Information:
300 ft Guardrail section on outside of horizontal curve
Natural Land use
Lane widths are 12 ft
Shoulder widths vary from 0.5 to 1 ft
ADT is 5000 with 11% trucks

Typical Section:




Exhibit 301-2 Design Option Worksheet Showing Example of Life Cycle Cost Assessment (continued)

On May 20, 2014, the project team, materials engineer and area maintenance staff performed a second scoping visit to develop pavement repair quantities and methods. We also discussed the maintenance concern for the guardrail repair location at MP 20.2 to 20.3, together we brainstormed and vetted potential contributing factors and design options for this location.

Potential Contributing Factors:

- Geometric cross section: Lack of shoulder and sight distance around the curve, outside orientation of the curve may be a factor for drivers negotiating this area. There may be a tendency for driver concern about opposing direction of travel, and to position the vehicle on the outside of the curve. This could result in the minor unreported collisions with the close proximity of guardrail to the travelled way.


Potential Solutions:

- Replace guardrail at same location
- Replace with pinned pre-cast concrete barrier
- Widen for 2' shoulder, install shoulder rumble strip and install long post guardrail run
- Widen for an 8' shoulder, install rumble strips and install long post guardrail
- Cut into slope and widen pavement section (will require realignment and/or superelevation change)

Design Option Evaluation:

Option 1 – Replace guardrail in kind

Contract Investment Calc:
Materials and Labor from UBA
6757 @ 27.5 LF for 300 ft = $8250
Traffic Control Costs
Flaggers @$50/hr x 4 hr x 2persons = $400
TCS @$100/hr x 4 hr = $400
Portable Attenuator = $3500
Total Traffic Control = $3500+$400+$400 = $4300
Total Contract Investment = $8250+$4300 = **$12550**




Maintenance Costs Calc (per repair):
Maintenance records show repairs consist of two sections of guardrail and two posts or post blocks need replacement each repair. Records average repairs 2x each year.
Materials and Labor from Area Maintenance:
26' beam @ $27.5/LF = $715
2 posts or blocks @ $80/ea = $160
3 persons @ $35/hr x 4 hr (includes PASP and travel) = $420
Traffic Control Labor
2 persons @ $35/hr x 4 hr (includes PASP and travel) = $280
All equipment necessary for repair @ $90/hr X 4 hr = $360
Total Maintenance per repair = $360+$715+$160+$420+$280 = $1935 x 2/yr = $3870
Total Maintenance Net Present Worth = ($3870 X 19)(0.8) = **$58824**

Total Life Cycle Cost = $12550 + $58824 =**$71374**

Exhibit 301-2 Design Option Worksheet Showing Example of Life Cycle Cost Assessment (continued)

Option 2 – Install pinned pre-cast concrete barrier



Additional value not captured:
-less frequent exposure for maintenance staff
-maintenance staff time saved for other work


Additional value lost not captured:
-may need to use all extra shoulder width in opposing direction to accommodate width

Contract Investment Calc:
Materials and Labor from UBA
6776 @ $39/LF for 300 ft = $11700
5767 @$85/ton for 33tons = $2805
5100 @$50/ton for 30 tons =$1500
Other costs = $1000
Traffic Control Costs (TC for HMA placement assumed incidental to BST)
Flaggers @$50/hr x 6 hr x 2persons = $600
TCS @$100/hr x 6 hr = $600
Portable Attenuator = $3500
Total Traffic Control = $3500+$600+$600 = $4700
Total Contract Investment = $11700+2805+1500+1000+$4700 = **$21705**

Maintenance Costs Calc (per repair):
Maintenance records for a similar location and context show repairs consist of resetting a barrier section once every 5 years.
Materials and Labor from Area Maintenance:
3 persons @ $35/hr x 4 hr (includes PASP and travel) = $420
Traffic Control Labor
2 persons @ $35/hr x 4 hr (includes PASP and trave) = $280
All equipment necessary for repair @ $110/hr X 4 hr = $440
Total Maintenance per repair = $440+$420+$280 = $1140 every 5 yrs
Total Maintenance Net Present Worth = ($1140 X 4)(0.8) = **$3648**

Total Life Cycle Cost = $21705 + $3648 = **$25353**

Option 3 – Widen shoulder, install rumble shoulder rumble strips and long post guardrail



Contract Investment Calc:
Materials and Labor from UBA
6711 @ $34/LF for 300 ft = $10200
5767 @$85/ton for 25tons = $2125
5100 @$50/ton for 22 tons =$1100
Other costs = $1000
Traffic Control Costs (TC for HMA placement assumed incidental to BST)
Flaggers @$50/hr x 4 hr x 2persons = $400
TCS @$100/hr x 4 hr = $400
Portable Attenuator = $3500
Total Traffic Control = $3500+$400+$400 = $4300
Total Contract Investment = $10200+$2125+$1100+$1000+$4300 = **$18725**

Maintenance Costs Calc (per repair):
Maintenance records for a similar location and context (but higher ADT) show repairs consist of two sections of guardrail and two posts or post blocks need replacement each repair. Records average repairs 1 every other year.
Materials and Labor from Area Maintenance:
26' beam @ $27.5/LF = $715
2 long posts or blocks @ $100/ea = $200
3 persons @ $35/hr x 3.5 hr (includes PASP and travel) = $368
Traffic Control Labor
2 persons @ $35/hr x 3.5 hr (includes PASP and travel) = $245
All equipment necessary for repair @ $90/hr X 3.5 hr = $315
Total Maintenance per repair = $715+$200+$368+$245+$315 = $1843 every other year
Total Maintenance Net Present Worth = ($1843 X 10)(0.8) = **$14744**

Total Life Cycle Cost = $18725 + $14744 = **$33469**

Exhibit 301-2 Design Option Worksheet Showing Example of Life Cycle Cost Assessment (continued)

Options 4 & 5 - Widen for an 8' shoulder, install rumble strips and install long post guardrail & Cut into slope and widen pavement section (will require realignment and/or superelevation change). Field visit participants determined these options would be significantly out of scope for the project. Additionally all parties agreed that initial costs are significantly more than the three previous options. Other concerns were permitting, specialty design needs, and potential need to add a ROW phase makes these design options fatally flawed.

SUMMARY:

Field participants agreed that Design Option 2 presents the best maintenance performance outcome; with potential to reduce the maintenance frequency, and thereby reducing the exposure of maintenance staff to the inherent risks of working on the roadway. The option also presents the lowest long term costs associated with maintaining the asset. However, the option does create an potential project funding issue at approximately $10,000 higher costs than option 1.

Next steps:

This project is currently within the scoping stage and the final project budget is yet to be determined. The design team will seek endorsement for Option 2 with the project PE, responsible maintenance superintendent and region program manager. Following this endorsement the design office will facilitate a project funding meeting with region program management, region project development, maintenance, and CPDM to confirm budget endorsement for Option 2. Assuming confirmation of budgeting, this option will be identified on the project summary and carried into the design scope for the project.

CONCLUSION:

On June 23, 2014, the endorsed Option 2 was discussed for budgeting. The P3 program was determined to have minimal flexibility to fund the additional cost without impacting other projects or other locations on the same project. Maintenance identified a surplus stockpile of the appropriate type of pre-cast concrete barrier, that could be utilized for state supplied materials on the contract, reducing the initial investment by $5000-6000. Parties agreed to move forward with Option 2 with state supplied material from the area maintenance stockpile.

301.03(2)(c) CAE Design Tools

Projects create assets that need to be maintained. The various CADD and modeling programs used for engineering design allow for significant flexibility to show maintenance considerations related to the project. This is true even if a feature won't be physically built by the project, but we want to ensure its visibility throughout the design. Indicate maintenance work zones and access routes within the working files. Refer to the *Electronic Engineering Data Standards Manual* for symbology requirements and standards.



Ideal utility vault and Variable Message Sign access

301.03(2)(d) Maintenance Review and Quality Control Products

There are a number of different ways to support design reviews and quality control for maintenance features associated with a project. Some regions use maintenance review checklists to remind designers and reviewers of common maintenance needs on projects (see example in Exhibit 301-3).

Worksheets for each asset are another means to document the discussion, options considered, and the decided outcome for a particular asset placed or retained within the project limits (see example in Exhibit 301-2).

Even if these review and documentation options are not specifically required by region documentation and approval processes, a decision to utilize these tools can be made at the project level.

The established quality control and quality assurance (QA/QC) procedure within each region provides an additional process for ensuring maintenance comments and concerns have been addressed and the agreed-on features are in place. This procedure becomes increasingly important at the 60%, 90%, and constructability review milestones, where design iterations may have neglected to account for impacts to previously agreed-on features or treatments specific to maintenance and operational needs. Discuss increasing the visibility of maintenance-related quality control within the project or region QA/QC plan and identify the assigned staff responsible for quality control and quality assurance.



Poor utility vault access

Exhibit 301-3 Excerpts from Olympic Region Review Checklist

Maintenance Review Checklist
Considerations for Scoping, Design and Construction

Project Title:I-5/Shoulder Widening and Bridge Replacement — Ad Date:4/1/2024
Project Type:I-1 and P-2 — PIN/WIN:300520I & 300521B/C00520I & C00521B

Maintenance Preferred Outcomes	Reason	General Outcome Notes	Discussed(Y/N) & Comments
Shoulders			
• 12-foot shoulders at locations where electrical equipment (HAR stations, VMS signs, light poles, CCTV cameras, data stations and RWIS are installed)	This allows man-lift and other service equipment to park and safely work, may be gravel area in combination with standard paved shoulder.	Could be in the form of widened gravel area.	12 foot shoulders provided for maintenance of multiple assets (ie closed system drainage, walls, illumination, etc.
• Parking area (access areas) for maintenance to load and unload	Safety, negates need to take lanes for maintenance work.	Could be in the form of widened gravel area.	Yes – agreed that this project will not be able to create parking areas for some assets given the right of way constraints. Foot access and 12' shoulders provided for project
• Full depth shoulders	This would allow the use of the shoulder when detouring traffic		Yes – Provided for multiple reasons including hard running shoulder use.
• Tapered shoulder edge (safety) edge	Improved water runoff. Keeps sod and debris from blocking shoulder drainage.	Reduced maintenance practices and herbicide use. Attachment A	Not discussed yet, revisit at 60% design
Electrical			
• Junction boxes	It is best to place J-boxes out of the traveled area (4-foot off pavement edge). Use traffic bearing J-boxes as a last resort.		Yes – box type TBD. Attempting to widen within existing ROW, creating need for retaining walls and J-boxes for illumination will need to be relocated. See design options worksheet for initial options discussed, but this and other roadside needs have resulted in a terraced wall design allowing for J boxes and other equipment to be accessed by foot on the terrace. Fall protection system will be needed.
• Lighting on outside of multi-lane highways	Median lights are not being constructed in 2010. Keep in mind access (a safe area) for repairing and re-lamping.		Yes – Luminar foundations will be placed behind the first terraced retaining wall. Full shoulder provided for bucket truck to access luminar head. However, project plans on using Hard Running Shoulders for transit priority and maintenance work requiring the shoulder will likely result in night work and/or coordination with transit authority. Night work is acceptable and typical for interstate work on this segment of the corridor

Maintenance considerations for Scoping, Design and Construction 5/21/14
Olympic Region Maintenance and Operations Office 1

Endorsement

This checklist has been reviewed, and issues have been discussed as noted. This checklist should be filed within the Design Documentation Package.

OR Maintenance: Jonny Appleseed
name *date*

Design PEO: Jane Smith, PE
name *date*

301.03(2)(e) Asset Management and Maintenance Owner's Manual

Maintenance and operations staff will need to maintain the assets placed or retained within a project location. It is important to be aware of the various asset management systems:

- Highway Activity Tracking System (HATS)
- Roadside Features Inventory Program (RFIP)
- Signal Maintenance Management System (SIMMS)
- Maintenance Productivity Enhancement Tool (MPET)
- Traffic Sign Management System (TSMS)

The asset management system reviews are necessary to confirm the assets present on a project, as well as any identification numbers associated with the assets to track and list those that will be removed, replaced, or remain. Work with the appropriate maintenance staff and confirm the assets identified during field reviews with maintenance staff. Post-construction, any new assets placed will need to be logged into the appropriate asset management system(s) by maintenance or construction staff, depending on region procedures.

Maintenance and operations personnel have experience maintaining a variety of products and features on state highways. However, not every asset is strictly typical for the maintenance discipline or area responsible for maintaining or operating it. Review the assets planned for placement within a project and understand what information maintenance crews may need to adequately maintain the asset or feature. This should include the following:



Well-designed access for luminaire maintenance

- Recommended equipment
- Frequency of maintenance activities
- Limits or boundaries (particularly for stormwater BMPs)
- Access location and route
- Any other relevant information discussed with maintenance or supplied by the product provider, including information on brand, make, and model of the asset

Information about these assets should be compiled into an *Owner's Manual* for maintenance to reference.

- The *Owner's Manual* will be provided in hard copy, an editable electronic copy, and static electronic versions.
- Electronic versions of the *Owner's Manual* must be titled in the following format: [YYYYMMDD]_Owner's Manual_[route]_[MP Limits]_[Contract Number].
- Hard copies will be bound in a binder and labeled on the cover and binding with the same information provided in the required PDF title.

The *Owner's Manual* versions will be supplied to both maintenance and the construction office, upon contract advertisement. ***Note:*** This may not be necessary if needed content is captured within the area's Integrated Vegetation Management (IVM) Plan.

If changes occur during post advertisement for a particular asset or feature listed in the *Owner's Manual*, it is the responsibility of the construction office and maintenance to coordinate an update of the *Owner's Manual*, as appropriate. As the construction phase ends, after punch list items are resolved, Maintenance staff should undergo a final review to ensure the *Owner's Manual* is complete and accurate.

301.03(2)(f) Maintenance Agreements

Some project locations may have multiple maintenance jurisdictions, at both the state and local levels. In these circumstances, involve all maintenance jurisdictions throughout the planning and design process. They can help you understand their capabilities and the reasonable accommodations necessary for frequent maintenance operations. To understand the likely split between local and state jurisdictions, refer to Chapter 1230 and the Conformed Agreement… for the Construction, Operations and Maintenance Responsibilities…
www.wsdot.wa.gov/localprograms/lag/construction.htm

Some maintenance and operations agreements between state and local agencies exist for streets that are also state highways, and are important to the success of these projects. These agreements may need to be created, updated, or replaced due to the nature of the project. The potential agreements need to identify the maintenance, operational, and jurisdictional boundaries, roles, and responsibilities of the parties entering into the agreement, including liability, indemnification, and insurance. The Conformed Agreement (above) lists the likely split of jurisdictional responsibilities. However, maintenance jurisdiction(s) may want to create an operational plan or agreement for the infrequent maintenance functions that designs may not be able to accommodate. It is also possible that one maintenance jurisdiction will be better equipped to handle certain maintenance elements than another. It will be necessary to document the split of maintenance responsibilities even if responsibilities remain the same as those listed within the Conformed Agreement.

Agreements require a level of detail that will not be known early in project development, so it is important to document trade-offs, benefits, and impacts with the affected maintenance jurisdictions while early decisions are being made.



Maintenance patching pavement at an intersection requires significant planning, night work, and traffic control

301.04 Documentation

Refer to Chapter 300 for design documentation requirements. Examples of documentation and checklists can be found at: www.wsdot.wa.gov/design/policy/default.htm

301.05 References

301.05(1) Federal/State Laws, Codes and Agreements

City Streets as Part of State Highways Guidelines Reached by the Washington State Department of Transportation and the Association of Washington Cities on Interpretation of Selected Topics of RCW 47.24 and Figures of WAC 468-18-050 for the Construction, Operations and Maintenance Responsibilities of WSDOT and Cities for such Streets, 4-30-1997, amended 4-2-2013
www.wsdot.wa.gov/localprograms/lag/construction.htm

301.05(2) Design Guidance and Supporting Information

A Policy on Geometric Design of Highways and Streets, AASHTO, current edition

Cost Estimating Manual for WSDOT Projects, M 3034, WSDOT

Electronic Engineering Data Standards, M 3028, WSDOT

Highway Runoff Manual, M 31-16, WSDOT

Maintenance Manual, M 51-01, WSDOT

Roadside Design Guide, AASHTO, current edition

Roadside Policy Manual, M 3110, WSDOT

Secretary's Executive Order 1032, Project Management

Chapter 305 Project Management

305.01 Introduction
305.02 Project Management
305.03 Project Management Tools
305.04 Cost and Risk Management
305.05 References

305.01 Introduction

The Washington State Department of Transportation (WSDOT) utilizes best practices to develop project management plans to successfully deliver projects on schedule and within budget. WSDOT's project management process provides an organized approach to building collaborative teams. Resources including methods, processes, tools, templates, and examples offer the opportunity to enhance project management.

This chapter serves as a reference and gives a brief overview of project management resources and links for your use. This chapter outlines the steps of project management. Project management includes strategies to manage:

- Teams – identify roles and responsibilities; align team project goal
- Collaboration – engage internal and external stakeholders and participants
- Deliverables – identify what must be produced
- Tasks – plan and organize sequence and levels of effort work to provide the deliverables
- Schedules – determine duration and task linkages
- Costs – plan and control project budget
- Risks – determine project exposure to threats and opportunities
- Integration and coordination of processes – eliminate waste
- Change – describe decision making, approving and reporting change
- Quality – assure, control and verify quality
- Communication – based on project needs, project team and external parties.

Effective project management must include a strong commitment to communication about the project within and external to the design team. Following are descriptions and links to project management resources.

Executive Orders 1032, 1038, and 1053 ensure a consistent process for practical design, project management, and risk management statewide.

305.02 Project Management

Project management processes provide the framework for project managers and team members to deliver projects on time and within scope and budget. Project management

resources are consistent with a practical design approach and offer structure for organizing collaborative teams to engage stakeholders and the community.

Exhibit 305-1 shows the project management process used to deliver projects. Each of the five parts shown is briefly described in the sections that follow.

Exhibit 305-1 WSDOT Project Management Process



305.02(1) Initiate and Align

Teams deliver projects; hence one of the first orders of business in project management is to initiate and align the team. Our projects are successful based on the effectiveness of the team delivering them. To that end initiating and aligning the team is an important early accomplishment. Aligning the team establishes communications and responsibilities of the project manager and team. The Initiate and Align worksheet is a tool that can be helpful in this phase.

305.02(2) Planning the Work

Plan the Work is the portion of the project management process that produces the Project Management Plan.

The Project Management Plan defines the project performance baseline – including deliverables, schedule and budget plans – and the management methods used to deliver the project. As we plan the work for our projects we integrate and coordinate processes in a manner that optimizes resources and reduces waste. For example if your project requires an interchange justification report (IJR), national environmental policy act (NEPA) documentation, or a value engineering study (VE) coordinate and align these efforts in a manner that makes use of common information and subject matter experts and in a way that ensures the need statements and function work together for the project.

The performance baseline documents the team goals for project performance. Performance baseline includes:

- Scope – the deliverables to be produced by the project team.
- Schedule – the logical sequence of work and related milestones.
- Budget – the allocation for the project.
- Risk – uncertainty that affects project objectives.

The Project Management Plan includes management plans for Risk, Change, Communication, Quality, Transition and Closure. These plans align the team toward uniform goals. A complete project management plan considers how the project will start, how it will be executed, monitored, and controlled, and how the project will close.

305.02(3) Executing the Work

The executing process is where we actually perform the planned work. During execution, we coordinate our team, subject matter experts and others as necessary to produce the deliverables. During execution, we ensure the integration of various project development and design processes that are optimal for completing the required work and meeting the performance objectives.

305.02(4) Monitoring and Controlling

As the work is being executed we track and report progress. If changes or course corrections are required, we want to identify those and take appropriate action in a timely manner. As we monitor progress and control variance we may need to take actions that include: developing and implementing recovery strategies, updating the project management plan, implementing risk response strategies and updating the risk assessment. Obtain change request approvals as necessary and ensure the quality plan is being implemented. Report on the performance of the team and provide early and meaningful communication to management, staff and team.

305.02(5) Closing the Project

As a project comes to an end it will either close or transition to a new phase. We want to perform the closure and transition in an orderly and appropriate manner. This involves demobilizing and reassigning staff and transferring resources or facilities.

Address the closure and transition phase of the project management process during creation of the project management plan and the work plan.

At the end of the project it is helpful to review lessons learned and to reward and recognize the team for successes. Capturing lessons learned and recognize people occurs throughout the project however, the closure phase provides an opportunity to finalize this and bring it to conclusion.

Project transitions can be aided by using the Deliverable Expectation Matrix which provides a range of project development deliverables and the general order in which they will occur.

A project is complete after transition and closure is accomplished and the project manager is released from responsibility for the project.

305.03 Project Management Tools

For an overview of project management, with links to the WSDOT project management process and tools for delivering the WSDOT Capital Construction Program, see the following website:
www.wsdot.wa.gov/projects/projectmgmt

The three more common tools are described below.

305.03(1) WSDOT's Master Deliverables List (MDL)

The Master Deliverables List (MDL) is a comprehensive listing of project elements. This list serves as a starting point for creating the project Work Breakdown Structure (WBS) and ensures:

- Appropriate project deliverables are included in the project management plan and schedule.
- A common vocabulary across project teams, region and Headquarters (HQ), and specialty/support groups.

For additional information, see the MDL:
www.wsdot.wa.gov/projects/projectmgmt/masterdeliverables.htm

305.03(2) Deliverables Expectation Matrix

The Deliverables Expectation Matrix (DEM) is another tool used to identify design project deliverables. The DEM is a simpler presentation than the MDL and shows recommended deliverables at project phases like 30% design. The DEM is here:
www.wsdot.wa.gov/publications/fulltext/design/demintro.pdf

305.03(3) Project Management and Reporting System (PMRS)

The PMRS is a tool for effective and efficient management of design project schedules, resources, and costs. The following website provides tools for project planning, work breakdown structure (WBS) development, scheduling, and resource and cost management:
http://wwwi.wsdot.wa.gov/planning/cpdmo/pmrs.htm

305.04 Cost and Risk Management

There are several WSDOT sources for cost estimating guidance, including:

- Strategic Analysis and Estimating:
  http://www.wsdot.wa.gov/Design/SAEO/
- Estimating Information
  http://www.wsdot.wa.gov/Projects/ProjectMgmt/RiskAssessment/Information.htm
- Cost Estimating Manual
  http://www.wsdot.wa.gov/publications/manuals/m3034.htm

Risk management, as an integral part of project management, occurs regularly.
With proactive risk management, projects are monitored to assess and document risks and uncertainty. For more information on risk planning and risk management, see:
www.wsdot.wa.gov/publications/fulltext/cevp/projectriskmanagement.pdf

For more information on risk assessment, see:
www.wsdot.wa.gov/projects/projectmgmt/riskassessment/

Document each estimate review in the Project File, and clearly show any changes made to the estimate as a result of the review.

305.05 References

305.05(1) Federal/State Laws and Codes

23 United States Code (USC) 106, Project approval and oversight

305.05(2) WSDOT Policies

Directives, Executive Orders, Instructional Letters, Manuals, and Policy Statements
http://wwwi.wsdot.wa.gov/publications/policies/default.htm

Executive Order E 1032, Project Management
http://wwwi.wsdot.wa.gov/publications/policies/fulltext/1032.pdf

Executive Order E 1038, Enterprise Risk Management
http://wwwi.wsdot.wa.gov/publications/policies/fulltext/1038.pdf

Executive Order E 1053, Project Risk Management and Risk Based Estimating
www.wsdot.wa.gov/publications/fulltext/cevp/1053policy.pdf

Executive Order E 1090, Moving Washington Forward: Practical Solutions
http://wwwi.wsdot.wa.gov/publications/policies/fulltext/1090.pdf

Executive Order E 1096, WSDOT 2015–17: Agency Emphasis and Expectations
http://wwwi.wsdot.wa.gov/publications/policies/fulltext/1096.pdf

Executive Order E 1082, Business Practices for Moving Washington
http://wwwi.wsdot.wa.gov/publications/policies/fulltext/1082.pdf

Policy Statement P 2047.00 "Estimating Project Budget and Uncertainty"
http://wwwi.wsdot.wa.gov/publications/policies/fulltext/2047.pdf

Project Delivery Memos
www.wsdot.wa.gov/design/projectdev/memos.htm

305.05(3) WSDOT Project Management References

Project Management Guide:
http://www.wsdot.wa.gov/Projects/ProjectMgmt/OnlineGuide/ProjectManagementOnlineGuide.htm

Project Management Glossary:
www.wsdot.wa.gov/publications/fulltext/projectmgmt/pmog/pm_glossary.pdf

Glossary for Cost Risk Estimating Management:
http://www.wsdot.wa.gov/publications/fulltext/CEVP/Glossary.pdf

Cost Estimating Manual for Projects:
http://www.wsdot.wa.gov/publications/manuals/fulltext/M3034/EstimatingGuidelines.pdf

Project Risk Management Guide:
www.wsdot.wa.gov/projects/projectmgmt/riskassessment/default.htm

Chapter 310 Value Engineering

310.01 General
310.02 Statewide VE Program
310.03 VE Procedure
310.04 Value Engineering Job Plan
310.05 Project Management Accountability
310.06 Documentation
310.07 References

310.01 General

Value engineering (VE) is a systematic review of a project by a multidisciplinary team not directly involved in the planning and development phases of the project. The VE process includes consideration of design; construction; maintenance; contractor; state, local, and federal approval agencies; other stakeholders; and the public.

Properly timing a Value analysis influences its benefits. Value analyses are typically conducted fairly early in project development to identify ideas to reduce cost and; refine scope. Section 310.02(3) VE Analysis Timing, of this chapter offers additional information about timing.

A VE analysis [1] may be applied as a quick-response study to address a problem or as an integral part of an overall organizational effort to stimulate innovation and improve performance characteristics.

Project managers are accountable for ensuring their projects meet all applicable value engineering requirements. In addition, local programs projects are accountable for ensuring they comply with Local Agency Guidelines requirements. In all cases, when a VE study is completed, the project manager is accountable for completing, signing, and submitting the VE Recommendations Approval Form.

310.02 Statewide VE Program

310.02(1) Annual VE Plan

The State VE Manager coordinates annually with the Capital Program Development and Region VE Coordinators to prepare an annual VE Plan, with specific projects scheduled quarterly. The VE Plan is the basis for determining the projected VE program needs, including team members, team leaders, consultants, and training. The Statewide VE Plan is a working document that reflects coordination between Headquarters (HQ) and the regions to keep it updated and projects on schedule.

[1] The terms "value management", "value engineering", "value study" and "value analysis" are used interchangeably.

310.02(2) Selecting Projects for VE Analysis

310.02(2)(a) Requirements

WSDOT projects for VE studies may be selected from any of the categories identified in the Highway Construction Program, including Preservation and Improvement projects, depending on the size and/or complexity of the project. In addition to cost, other issues adding to the complexity of the project design or construction are considered in the selection process. These include projects that have critical constraints, difficult technical issues, expensive solutions, external influences, and complicated functional requirements, regardless of the estimated project cost. These include projects that have critical constraints, difficult technical issues, expensive solutions, external influences, and complicated functional requirements, regardless of the estimated project cost.

WSDOT may conduct VE analyses on any projects the project manager determines will benefit from the exercise. In addition, WSDOT conducts VE analyses for all projects as required by the criteria set forth in Federal Highway Administration (FHWA) Value Engineering Policy Order.

1. WSDOT policy requires a value engineering analysis for:
   - Any project with an estimated cost (which includes project development, design, right of way, and construction costs) of $25 million or more, regardless of funding;
   - Each bridge project located on or off of the federal-aid system with an estimated total cost of $20 million or more (WSDOT policy is to conduct a VE analysis regardless of funding source); and
   - Any other projects the Secretary or FHWA determines to be appropriate.
2. In addition to the projects described above, WSDOT strongly encourages a VE analysis on other projects where there is a high potential for cost savings or improved project performance or quality. Projects involving complex technical issues, challenging project constraints, unique requirements, and competing community and stakeholder objectives offer opportunities for improved value by conducting VE analyses.
3. Any use of Federal-Aid Highway Program (FAHP) funding on a Major Project[2] requires that a VE analysis be conducted. In some cases, regardless of the amount of FAHP funding, a project team may be required to perform more than one VE analysis for a Major Project.
4. After completing the required VE analysis, if the project is subsequently split into smaller projects in final design or is programmed to be completed by the advertisement of multiple construction contracts, an additional VE analysis is not required. However, splitting a project into smaller projects or multiple construction contracts is not an accepted method to avoid the requirements to conduct a VE analysis.
5. WSDOT may require a VE analysis to be conducted if a region or public authority encounters instances when the design of a project has been completed but the project does not immediately proceed to construction.
   a. If a project meeting the above criteria encounters a three-year or longer delay prior to advertisement for construction, and a substantial change to the project's scope or

[2] Based on the *Safe, Accountable, Flexible, Efficient Transportation Equity Act: A Legacy for Users (SAFETEA-LU),* signed into law on August 10, 2005, a Major Project is defined as "a project with a total estimated cost of $500 million or more that is receiving financial assistance." FHWA also has the discretion to designate a project with a total cost of less than $500 million as a Major Project.

design is identified, WSDOT may require a new VE analysis or an update to the previous VE analysis; or

b. If a project's estimated cost was below the criteria identified above but the project advances to construction advertisement, and a substantial change occurs to the project's scope or design, causing an increase in the project cost so that it meets the criteria identified above and results in a required re-evaluation of the environmental document, WSDOT requires that a VE analysis be conducted.

6. When the design of a project has been completed but the project does not immediately proceed to construction, the requirement to conduct a VE analysis is considered to be satisfied, or not necessary, if:

   a. A project met the criteria identified above and had a VE analysis conducted, and the project advances to advertisement for construction without any substantial changes in its scope or its design; or

   b. A project's estimated cost initially fell below the criteria identified above, but when advancing to advertisement for construction, falls above the criteria due to inflation, standard escalation of costs, or minor modifications to the project's design or contract.

Other projects that should be considered for value engineering have a total estimated cost exceeding $5 million and include one or more of the following:

- Alternative solutions that vary the scope and cost
- New alignment or bypass sections
- Capacity improvements that widen the existing highway
- Major structures
- Interchanges
- Extensive or expensive environmental or geotechnical requirements
- Materials that are difficult to acquire or that require special efforts
- Inferior materials sources
- New/Reconstruction projects
- Major traffic control requirements or multiple construction stages

310.02(3) VE Analysis Timing

310.02(3)(a) When to Conduct the VE Analysis

Timing is very important to the success of the VE analysis. A VE analysis should be coordinated with other project development activities. For example, a project requiring an Interchange Justification Report (IJR), NEPA and a VE should consider how to best integrate the processes with development of project need statements.

Optimizing the timing of a VE analysis minimizes impacts of approved recommendations on previous commitments (agency, community, or environmental) and project's scope. VE analyses can also be coordinated with project risk assessments.
See www.wsdot.wa.gov/design/saeo/

Benefits can be realized by performing a VE analysis at any time during project development; however, the WSDOT VE program identifies the following three windows of opportunity for performing a VE analysis.

1. Scoping Phase

Early in preliminary engineering is a good time for value analysis consideration. This is a time to consider alternatives or design solutions with a high potential for implementing VE recommendations. At the conclusion of the VE study, the project scope, preliminary costs, and major design decisions are informed by the recommendations.

When conducting value engineering during the scoping phase of a project, the VE analysis focuses on project drivers. This stage often provides an opportunity for community engagement and building consent with stakeholders.

2. Start of Design

At the start of design, the project scope and preliminary costs have been established and major design decisions have been made. Some Plans, Specifications, and Estimates (PS&E) activities may have begun, and coordination with support groups and subject matter experts is underway. At this stage, the project scope, costs, and schedule define the limits of the VE analysis. There is opportunity to focus on the technical issues of the design elements.

3. Design Approval

After Design Approval, most of the important project decisions have been made and the opportunity to affect the design is limited. Provided there is time to incorporate VE recommendations, the VE analysis may likely focus on constructability, construction sequencing, staging, traffic control, and significant design issues.

An additional VE analysis may be beneficial late in the development stage when the estimated cost of the project exceeds the project budget. The value engineering process can be applied to the project to lower the cost while maintaining the value and quality of the design.

310.02(4) VE Program Roles and Responsibilities

310.02(4)(a) Region VE Coordinator

- Identifies region projects for VE analyses (from Project Summaries and available planning documents).
- Makes recommendations for timing of the VE analysis for each project.
- Presents a list of the identified projects to region management to prioritize into a regional annual VE Plan.
- Identifies potential team facilitators and members for participation statewide.

310.02(4)(b) State VE Manager

- Reviews regional VE Plans regarding content and schedule.

310.02(4)(c) State VE Coordinator

- Incorporates the regional annual VE Plans and the Headquarters Plan to create the Statewide VE Plan.
- Prepares annual VE Report.
- Maintains policy documents for the department.
- Coordinates studies.

- Arranges training for future VE team leaders and members.

310.02(4)(d) VE Team Leader

The quality of the VE analysis largely depends on the skills of the VE team leader. This individual guides the team's efforts and is responsible for its actions during the analysis. The VE team leader should be knowledgeable and proficient in transportation design and construction and in the VE analysis process for transportation projects.

The VE team leader's responsibilities include the following:

- Plans, leads, and facilitates the VE study.
- Ensures proper application of a value methodology.
- Follows the Job Plan.
- Guides the team through the activities needed to complete the pre-study, the VE study, and the post-study stages of a VE study.
- Schedules a pre-workshop meeting with the project team and prepares the agenda for the VE study.

Team leaders from within WSDOT are encouraged, but not required, to be certified by the Society of American Value Engineers (SAVE) as an Associate Value Specialist, Certified Value Specialist (CVS) or as a Value Methodology Practitioner (VMP). Team leadership can be supplied from within the region, from another region, or from Headquarters. A statewide pool of qualified team leaders is maintained by the State VE Coordinator, who works with the Region VE Coordinator to select the team leader.

Consultants who lead VE teams are required to be SAVE certified.

310.02(4)(e) VE Team Members

The VE teams are usually composed of six to ten people with diverse expertise relevant to the project under study. The team members may come from regions; Headquarters; other local, state, or federal agencies; or the private sector.

Team members are not directly involved in the planning and development phases of the project. They are selected based on the expertise needed to address major functional areas and critical high-cost issues of the study. All team members must be committed to the time required for the study. It is desirable for team members to have attended Value Engineering Module 1 training before participating in a VE study.

310.03 VE Procedure

The WSDOT VE analysis uses the Seven-Phase Job Plan shown in Exhibit 310-1. A detailed discussion of how each phase is supposed to be conducted can be found in the document, Value Methodology Standard and Body of Knowledge, developed by SAVE International, The Value Society. This document can be downloaded at the SAVE website: www.value-eng.org/

310.03(1) Pre-Study Preparation

To initiate a VE study, the project manager submits a Request for Value Engineering Study form to the Region VE Coordinator at least two months before the proposed study date. The form is located on the WSDOT value engineering website:
www.wsdot.wa.gov/design/valueengineering/tools/

The Region VE Coordinator then works with the State VE Coordinator to determine the team leader and team members for the VE study. Contacts are listed on the WSDOT value engineering website: www.wsdot.wa.gov/design/valueengineering

The design team prepares a study package of project information for each of the team members. (A list of potential items is shown in Exhibit 310-2). Work with the State VE Coordinator for the best/most concise list of materials to send to the team members. If the package is provided via a network drive or FTP site, make sure the materials are well titled and sorted in a well-titled file structure. The VE team members should receive this information or a link to this information at least one week prior to the study so they have time to review the material.

The region provides a facility and the equipment for the study (see Exhibit 310-2).

310.03(2) VE Analysis Requirements

The time required to conduct a VE analysis varies with the complexity and size of the project, but typically ranges from three to five days. The VE team leader working with the project manager will determine the best length of time for the study.

The VE analysis Final Report includes an executive summary; a narrative description of project information; the background, history, constraints, and controlling decisions; the VE team's focus areas; a discussion of the team's speculation and evaluation processes; and the team's final recommendations. All of the team's evaluation documentation, including sketches, calculations, analyses, and rationale for recommendations, is included in the Final Report. A copy of the Final Report is to be included in the Project File. A copy of the report is also provided to FHWA for projects on the National Highway System or federal-aid system.

Post-VE analysis activities include:

- The Project Manager and Project team are responsible for:
  - Implementation and evaluation of the approved recommendations.
  - Documentation of reasons recommendations were not implemented.

310.03(3) Implementation (Phase 7 of VE)

As soon as possible, preferably no more than two weeks following the VE analysis, the project manager reviews and evaluates the VE team's recommendation(s). The project manager completes the VE Recommendation Approval form included in the Final Report and returns it to the Statewide VE Manager.

Recommendations not approved or modified by the project manager require a brief justification in the VE Recommendation Approval form.

The project manager sends the completed VE Recommendation Approval form to the State VE Manager following receipt of the Final Report and not later than September 1 of each year, whichever comes first, so the results can be included in WSDOT's annual VE Report to FHWA.

Exhibit 310-1 Seven-Phase Job Plan for VE Studies

VE Study Phase	Job Plan
1. Information	Gather project information, including project commitments and constraints. • *Investigate technical reports and field data* • *Develop team focus and objectives*
2. Function Analysis	Analyze the project to understand the required functions. • *Define project functions using active verb/measurable noun context* • *Review and analyze these functions to determine which need improvement, elimination, or creation to meet project goals*
3. Creative	Generate ideas on ways to accomplish the required functions that improve project performance, enhance quality, and lower project costs. • *Be creative* • *Brainstorm alternative proposals and solutions to lower project costs, improve project performance, and enhance quality*
4. Evaluation	Evaluate and select feasible ideas for development. • *Analyze design alternatives, technical processes, and life cycle costs*
5. Development	Develop the selected alternatives into fully supported recommendations. • *Develop technical and economic supporting data to prove the benefits and feasibility of the desirable concepts* • *Develop team recommendations (long-term as well as interim solutions)*
6. Presentation	Present the VE recommendation to the project stakeholders. • *Present the VE recommendation to the project team and region management in an oral presentation* • *Provide a written report*
7. Implementation	The decision to implement or not implement recommendations is documented in the signed VE Recommendation Approval form. The Project Manager implements approved recommendations.
Note: Phases 1–6 are performed during the study; see *Value Standard and Body of Knowledge* for procedures during these steps.	

Exhibit 310-2 VE Analysis Team Tools

Project-Related Input* and Design Resources (Study Package)
Project Management Plan
Vicinity map
Aerial photos
Large-scale aerial photographs
Pertinent maps - Land use, contours, quadrant, etc.
Crash data with collision analysis
Existing as-built plans
Design file
Cross sections and profiles
Environmental documents Environmental constraints, and commitments
Estimates (and associated Basis Of Estimate)
Geotechnical reports
Hydraulic Report
Plan sheets
Quantities
Right of way plans
Bridge List/Bridge condition report
Design Manual
Field Formulas and *Field Tables*
Standard Plans
Standard Specifications
State Highway Log
Other manuals as needed

Study-Related Facilities and Equipment
AASHTO *Green Book*
Calculators
Computer (with network if available) / projector
Easel(s) and easel paper pads
Marking pens
Masking and clear tape
Power strip(s) and extension cords
Room with a large table and adequate space for the team
Scales, straight edges, and curves
Telephone
Vehicle or vehicles with adequate seating to transport the VE team for a site visit**

*Not all information listed may be available to the team, depending on the project stage. Work with your Region VE Coordinator or the State VE Coordinator to verify that all needed information is available.


**If a site visit is not possible, perform a “virtual” tour of the project.

310.04 Value Engineering Job Plan

The VE process is comprised of a 6-step Job Plan. FHWA adds a "7th" step known as implementation. Exhibit 310-3 depicts the process for Value Engineering. An interactive version of this exhibit is available at:

http://www.wsdot.wa.gov/publications/fulltext/CEVP/VE_JobPlan.pdf

Exhibit 310-3 Value Engineering Job Plan



310.05 Project Management Accountability

Project Managers are required to make a determination for each VE recommendation. To that end, project managers, in consultation with their project teams, support staff, other management support, and subject matter experts, decide the action to be taken for each recommendation.

310.06 Documentation

Refer to Chapter 300 for design documentation requirements.

The following value engineering documentation is required:

- **Project File** – Value Engineering Final Report
- **Design Approval** – Design Documentation Package for Approval – the Value Engineering Recommendation Approval Form
- **Project File** – Value Engineering Recommendation Approval Form

310.07 References

310.07(1) Federal Laws and Codes

Title 23 U.S.C. Section 106(e) – Value Engineering Analysis

Title 23 CFR Part 627 – Value Engineering

MAP-21 (Moving Ahead for Progress in the 21st Century), Section 1503

Circular A-131, Office of Management and Budget (OMB)
http://www.whitehouse.gov/omb/circulars_a131

FHWA Value Engineering Policy
https://www.fhwa.dot.gov/legsregs/directives/orders/13111b.cfm

310.07(2) Design Guidance

Value Engineering for Highways, Study Workbook, U.S. Department of Transportation, FHWA
Value Standard and Body of Knowledge, SAVE International, The Value Society:
http://www.value-eng.org/

WSDOT Value Engineering website:
www.wsdot.wa.gov/design/valueengineering/

Chapter 320 Traffic Analysis

320.01 General
320.02 Design Year and Forecasting Considerations
320.03 Traffic Analysis Software
320.04 Travel Demand Forecasting
320.05 Traffic Impact Analysis (TIA)
320.06 TIA Scope
320.07 TIA Methods and Assumptions Document
320.08 TIA Methodologies
320.09 TIA Mitigation Measures
320.10 TIA Report
320.11 References

320.01 General

This chapter is intended to address policy-related issues associated with Washington State Department of Transportation (WSDOT) multimodal traffic analysis. It is not intended to address the specifics of demand forecasting; mesoscopic, analytical/deterministic, stochastic microsimulation; or safety performance analyses. For those items, see the latest versions of the *Highway Capacity Manual*, *Traffic Analysis Procedures Manual* (TAPM), and *Highway Safety Manual* (HSM).

Traffic analysis is intended to produce information for decision makers; it is not intended as a stand-alone tool for making decisions. Consideration of empirical data, similar traffic situations, studies, local knowledge, and seasoned traffic engineering and planning experience can also add to a pool of traffic information that is provided to decision makers.

Traffic analysis is either "operational" or "planning" in nature. Operational analysis is associated with engineering concepts focusing on near-term or existing/opening year, while planning analyses are generally focused on a horizon year or interim phase years. Planning-level analyses are also used to determine impacts for environmental documentation phases of Environmental Assessment (EA) or Environmental Impact Statement (EIS) work. Much caution should be used when operational tools are used with planning-level future year projection data.

Be aware that operational models were not primarily intended for use with planning-level future year projected volumes, but there is a need to understand the difference between proposed future scenarios. Therefore, operational models need to use data from forecasting models, but analysts need to do so with an understanding of the imperfections.

Forecasting demand volumes 20 years into the future can be difficult to do well, so there should be little expectation that intersection turning movement projection-related traffic analyses by themselves will be sufficient to produce actionable designs. Consequently, some future year Measures of Effectiveness (MOEs) such as turn lane queue length should not be considered accurate, but they may be useful when comparing various scenarios if the reported differences are substantial.

With the aforementioned limitations, project-specific traffic volumes, forecasts, and system capacities are used to establish the extent of improvements needed for facilities to operate acceptably from year of opening or through interim phases and, eventually, through to the horizon year; for example:

- Number of general purpose/HOV/HOT lanes
- Length and number of ramp or auxiliary lanes
- Intersection or interchange spacing
- Channelization
- Signal timing
- Right of way needs
- Roundabout design parameters
- Width of sidewalks
- Extent of bike lanes
- Ferry holding lanes

Traffic analysis should examine multimodal access, mobility, and safety objectives; project benefits and costs; development impacts; and mitigation needs.

Not all projects will require the same level of effort. The specific depth and complexity of a traffic analysis will depend on a variety of factors, including:

- Project proponents (federal, tribal, state, local, and private sector)
- Legal requirements (laws, regulations, procedures, and contractual obligations)
- Lead agency
- Purpose or scope of the traffic analysis
- Data availability
- Time of day (am/pm peak hour or other)
- Funding
- ROW availability

For projects that fall under FHWA approval, coordinate with the Headquarters (HQ) Traffic Office for concurrence on traffic analysis details. Other projects can be coordinated through region Traffic offices. (See Chapter 300 for FHWA oversight and approval policy.)

320.02 Design Year and Forecasting Considerations

Project evaluation requirements can be (1) focused on near-term functionality, (2) contain interim phases, and/or (3) require a long-term focus. The project proponent can be the state (WSDOT or other state agencies) or developers (other public agencies or private concerns).

For Interchange Justification Reports (IJRs), the design year and multimodal travel demand forecasting methodologies are to be documented by the project stakeholders in the Methods and Assumptions (M&A) Documents.

Guidance on the horizon year and interim design year(s) for projects is given in Chapter 1103, Design Controls.

When selecting horizon year and interim design year phases, stakeholders need to consider the regional significance of a proposed project, how it functions within the existing system, and the expected lifespan. The traffic analysis for developer-related projects will typically focus on existing conditions and the build-out year of the proposed project. Some larger developer projects will need to be evaluated in multiple phases, as they have the potential to significantly impact the transportation system and will thus require a longer-term focus. Mitigation measures may also be phased with these projects.

Project teams are encouraged to consider the strategic importance, economic potential, network constraints, and investment scale when determining the analysis methodologies for project phasing, design year, and forecasts. With acceptance/concurrence by the Traffic Office of purview,[1] the following are possible approaches to be used individually or in concert to develop future year demand volumes:

- Travel demand models
- Trend line projections
- Cumulative impacts
- Limitations of the surrounding network

320.03 Traffic Analysis Software

With acceptance by the Traffic Office of purview, use the least complex and data-intensive software deemed reasonable for any given project. Agreement for software and versions must be documented in the study's M&A. Use the latest version sanctioned by WSDOT HQ Traffic.

- For near-term analysis of locations that do not require an understanding of interactions between various transportation systems, Sidra, Rodel, Synchro, and HCS are the primary analytical tools.
- For systemwide multimodal complex forecasting, EMME3, TransCad, and Visum are the primary tools.
- For choosing between scenarios involving multimodal traffic and/or where various transportation system elements interact, CORSIM, Vissim, or Dynameq are the primary tools.

The software mentioned above may have version limitations due to WSDOT purchased rights and contract limitations. For details about these and other traffic analysis software used by WSDOT, see the *Traffic Analysis Procedures Manual* or contact the region or HQ Traffic Office.

320.04 Travel Demand Forecasting

Designers, planners, and analysts need to be aware of the practical limitations of the selected method of multimodal traffic demand forecasting and should consider the impact of demand uncertainty when conducting analyses and drawing conclusions from those analyses. Special attention should be given to any post-processing efforts. For guidance in the selection of analysis methodology, refer to the *Traffic Analysis Procedures Manual*. Following are brief descriptions of the four main methods for demand forecasting.

[1] See Chapter 300 and the Federal-Aid Highway Program Stewardship and Oversight Agreement: Generally, region for non-Highways of Statewide Significance (HSS) or non-National Highway System (NHS), and Headquarters for HSS and NHS.

320.04(1) Travel Demand Models

For the vast majority of projects, this will be the proper approach for developing future year demand volumes. However, caution should be taken when using this approach to draw conclusions from operational model Measures of Effectiveness (MOEs) that are based on such forecasts, because specific and accurate turning movement volumes are needed to produce credible MOEs. Forecast models are most commonly used to produce general volumes that can help traffic planners evaluate and compare the relative merits of potential solutions against each other.

320.04(2) Trend Line Projections

Where travel demand models are not established or are otherwise considered inadequate, trend data can be used but must be constrained by system flow limitations. Trend line growth cannot account for peak spreading when traffic demand exceeds system supply. Use with caution and consult the HQ Transportation Data & GIS Office (TDGO) for further details about this method and any inherent limitations.

320.04(3) Cumulative Impacts

This method is typically used to forecast volumes in areas that demonstrate uniform growth and exhibit only minor changes and marginal impacts to the region. It is also useful for analyzing growth in suburban areas that are experiencing rapid development, as other methods may not be as reliable. The basic concept is to add volumes for developments to the trending background traffic growth. The comprehensive plan for such areas should be consistent with the expected growth predicted by a project (and include other anticipated projects) in order to result in a reasonable estimate of cumulative impacts. Use with caution due to an inability to fully account for secondary impacts like future environmental issues, local network connectivity, public services, and multimodal demands.

320.04(4) Limitations of the Surrounding Network

For projects that contain infrastructure of particular importance, extraordinary expense, life span expectancy beyond 20 years, or where travel demand will likely always exceed transportation system capacity constraints, give consideration to the concept of facility capacity balancing within the context of the larger transportation system.

This approach needs to demonstrate that the maximum amount of upstream traffic flowing into a project, as well as all project-area traffic flowing into downstream sections, can be handled acceptably. This does not require traditional travel demand forecasting, which has a limitation of about 20 years. Instead, it requires a sensitivity approach where maximum up- and downstream flows are used to right-size the project area's proposed improvements. The simplest example is the SR 520 Floating Bridge: constraints on either end of the bridge limit the usefulness of adding more lanes on the bridge.

TIAs and IJRs (see Chapter 550) shall clearly describe the methodology and process used to develop forecasts in support of a proposed project's analysis. For example, include only those projects that:

- Are on the six-year Transportation Improvement Plan.
- Are fully funded.
- Have entered the environmental review process.

320.05 Traffic Impact Analysis (TIA)

TIA is a term used for all analyses that are not structured IJRs (see Chapter 550) or planning-level efforts like corridor studies. The quality and level of service[2] for state-owned and state-interest facilities shall be based upon MOEs that support the project purpose and need. They shall also be developed and presented in accordance with the latest versions of the *Highway Capacity Manual* (HCM), FHWA Traffic Analysis Toolbox, *Traffic Analysis Procedures Manual*, and WSDOT Vissim Protocol.

For some example MOEs, see the FHWA MOE List, which describes measures typically used for analyzing state and local agency facilities such as freeway segments, signalized intersections, ramp terminals/junctions, sidewalks, and transit services.

Depending on the facility and when HCM Level of Service MOE is used, WSDOT thresholds are "C" for rural and "D" for urban non-NHS facilities, unless a WSDOT region specifies otherwise for specific route segments. (See each WSDOT region for details.) Refer to the WSDOT State Highway Log for a determination of existing route segment definitions for urban or rural status.

Depending on the project type and purpose, multimodal MOEs may be employed.

320.05(1) Updating an Existing TIA

TIAs require either updating or a sensitivity analysis if they become more than 3 years old; however, a TIA will require updating sooner in rapidly developing areas. TIAs can avoid such update efforts in slowly developing areas. To determine if an update is required, an assessment of critical infrastructure functionality must be documented.

If the amount or character of traffic in the study area is significantly different from an earlier analysis, an update will be required. The definition of significant is 10% (volume, flow rate, travel time, delay, density, or other key MOEs) where existing operations are currently acceptable. If they are not currently acceptable, the threshold is reduced to 5%. In cases where greater than 10% change or failed MOEs have been found, consultation and concurrence with WSDOT Traffic Office of purview is required to avoid a full IJR or TIA update.

Developer-initiated TIAs are typically valid for 5 or 6 years, as that is the window provided under the Growth Management Act for concurrency. The Development Services Office should be consulted regarding the need for updates to TIAs for developer, tribal, and local agency projects.

320.06 TIA Scope

To establish the appropriate scope, consultation between the lead agency, WSDOT, and those preparing the TIA is encouraged before beginning work. TIA-required elements can be found in the *Traffic Analysis Procedures Manual* (an abbreviated list is provided below). ***Note:*** For developer-initiated TIAs, the local agency may prescribe the scope of the TIA per the local agency's adopted standards.

[2] WSDOT sets level of service (LOS) standards for state highways and ferry routes of statewide significance (HSS) based on RCW 47.06.140(2). Regional transportation planning organizations (RTPOs) and WSDOT jointly develop and RTPOs establish LOS standards for regionally significant state highways and ferry routes (non-HSS) based on RCW 47.80.030(1)(c).

320.06(1) TIA Boundaries

The traffic impacts of local streets and roads can impact intersections on state highway facilities. In these cases, include in the TIA an analysis of adjacent local facilities (driveways, intersections, main lines, and interchanges) upstream and downstream of the intersection with the state highway. A "lesser analysis" may include obtaining traffic counts, preparing signal warrants, or a focused TIA. For developer projects, the boundaries of the analysis (such as the city limits) may be determined in consultation with local agencies and WSDOT. For further guidance, consult the *Traffic Analysis Procedures Manual* and *Development Services Manual*.

320.06(2) Traffic Analysis Scenarios

WSDOT must understand the effects of plan updates and amendments, as well as the effects of specific project elements (including site plans, conditional use permits, subdivisions, and rezoning) that have the potential to impact state facilities. Consultation between the lead agency, WSDOT, and those preparing the TIA is essential early in the process to help determine appropriate scenario analyses and goals. For further guidance, consult the *Traffic Analysis Procedures Manual* and *Development Services Manual*.

Depending on the type of work being analyzed, required TIA scenarios can range from simple "existing conditions with and without project," to more complex analyses where TIA scenarios could include: existing; opening year with and without project; interim years with and without project; and design year with and without project. If developed with WSDOT, and if following IJR guidance, pre-IJR work such as Area Study TIAs can be used in future IJRs.

The appropriate and necessary scenarios shall be agreed upon by the TIA study team and documented in the TIA Methods and Assumptions (M&A) Document.

For existing networks, calibrate models to existing conditions.

If a near-term baseline network is required, only funding-secured projects should be added to the existing network. This is typical of opening year models that are a few years beyond existing year.

For interim scenario networks, include only projects or developments within the forecasting process that have the highest probability within the 10-year horizon. For example, include projects that are fully funded or have a construction phase in the six-year Transportation Improvement Plan.

For scenarios with phases beyond 10 years, TIA or IJR teams should discuss and document the merits of including other potential projects. For example:

- Projects on current long-range regional transportation plans (or the locally-adopted transportation plan, if the TIA is not on a regionally-significant facility)
- Projects on the HSP or MTP

All other potential influences with lower probability should not be allowed to affect travel or trip demand forecast results—with one exception: TIAs and IJRs may include multiple scenarios for the design year. For example, if a major assumption for unfunded additional lanes "feeding traffic into" or "allowing traffic from" the project is desired for the design year to allow for a better understanding of expensive infrastructure sizing (such as ultimate bridge widths), ensure a constrained design year scenario is included so that proper funding-based phasing solutions are communicated.

320.07 TIA Methods and Assumptions Document

The TIA M&A is similar to an IJR M&A in that it documents the "who, what, where, when, how, and why" items associated with the traffic analysis portion of a project.

Prior to any substantial fieldwork or traffic/facility data collection, consultation between the lead agency, WSDOT, and those preparing the TIA is encouraged to help reach and document consensus on study data needs and assumptions. These and other items should be documented and the M&A signed by all lead staff that conduct work in association with the TIA M&A document. For further guidance, consult the *Traffic Analysis Procedures Manual* and *Development Services Manual*.

320.08 TIA Methodologies

The FHWA Traffic Analysis Toolbox, Volume 2, provides a methodology for selecting traffic analysis tools. However, in general, traffic analysis methodologies for those facility types indicated below are used by WSDOT and will be accepted if agreed upon by those who sign TIA or IJR M&A Documents.

- **Freeway Segments:** *Highway Capacity Manual*/Software (HCM/S); operational and design analysis; macroscopic, mesoscopic, and microsimulation
- **Weaving Areas:** *Design Manual* (DM); HCM/S; operational and design analysis; microsimulation
- **Ramps and Ramp Terminals:** HCM/S; operational and design analysis; DM; microsimulation
- **Multilane Highways:** HCM/S; operational and design analysis; macroscopic, mesoscopic, and microsimulation
- **Two-Lane Highways:** HCM/S; operational and design analysis
- **Intersection, Signalized:** Sidra; Synchro; SimTraffic; HCM/S; Vissim,
- **Intersection, Roundabout:** Sidra; Rodel; HCM; Vissim
- **Corridors:** Sidra; Synchro; SimTraffic; HCM; Vissim
- **Stop-Controlled Intersections:** HCM/S for capacity; DM Chapter 1330 and the MUTCD for signal warrants (if a signal is being considered)
- **Transit:** HCM/S; operational and design analysis; *Traffic Manual*
- **Pedestrians:** HCM/S
- **Bicycles:** HCM/S

- **WSDOT Criteria/Warrants:** MUTCD (signals, stop signs); *Traffic Manual* (school crossings); DM Chapter 1040 (freeway lighting, conventional highway lighting)
- **Channelization:** DM

The procedures in the *Highway Capacity Manual* do not explicitly address operations of closely spaced signalized intersections, nor does WSDOT currently endorse microsimulation or roundabout guidance as noted in the HCM/S. Under such conditions, several unique characteristics must be considered, including spill-back potential from the downstream intersection to the upstream intersection; effects of downstream queues on upstream saturation flow rates; and unusual platoon dispersion or compression between intersections. An example of such closely spaced operations is signalized ramp terminals at urban interchanges. Queue interactions between closely spaced intersections can seriously distort the results of analyses that follow the procedures in the HCM.

Other analysis methods may be accepted; however, consultation between the lead agency, region or HQ Traffic, and those preparing the TIA is encouraged to reach consensus on the data necessary for the analysis if meso- or microsimulation is employed. When a state highway has saturated flows, the use of a meso- or microsimulation models can provide additional understanding. Note, however, that the simulation model must be calibrated and validated for reliable results and is intended for near-term operational analyses (see the *Traffic Analysis Procedures Manual* for guidance on calibration and validation).

Operational MOEs for simulation models based on long-term forecasts should be used primarily to determine which scenarios are better than others. The models can only do so if the resultant MOEs demonstrate significant differentiation between scenarios. TIA or IJR teams will determine what is considered significant and will document those findings in the study. However, at a minimum, significant must be greater than the expected error band of the models used. For example, if Vissim is considered to be calibrated to a given MOE within 15% of existing conditions (a very wide band), the scenarios need to show greater than 15% differentiation between each other to be significant.

320.09 TIA Mitigation Measures

Consultation between the lead agency, WSDOT, and the responsible parties preparing the TIA is recommended in order to reach consensus on the project mitigation measures. Mitigation measures, if applicable, need to be included in the TIA to determine whether a project's impacts can be eliminated or reduced to a level of insignificance. Eliminating or reducing impacts to a level of insignificance is the standard pursuant to the State Environmental Policy Act (SEPA) and National Environmental Policy Act (NEPA). The lead agency is responsible for administering the SEPA and/or NEPA review process. WSDOT is responsible for reviewing the TIA for impacts that pertain to state highway facilities. However, the authority vested in the lead agency under SEPA/ NEPA does not take precedence over other authorities in law.

Development work in the state highway right of way requires a WSDOT permit or agreement. Normally, this work is coordinated by the region Development Services Office.

Mitigation measures may take the following forms:

- Channelization such as turn lanes or raised islands
- Installation of a roundabout or, if necessary, a traffic signal (signal warrant analysis per MUTCD is required)
- Frontage improvements
- Donation of right of way
- Addressing any design or operational deficiencies created by the proposal
- Possible restrictions of turning movements
- Sight distance enhancements
- Traffic mitigation payment (pro rata share contribution) to a programmed WSDOT project (see Chapter 4 of the *Development Services Manual*)
- Satisfaction of local agency guidelines and interlocal agreements

320.10 TIA Report

320.10(1) TIA Minimum Contents

The minimum contents of a TIA report are listed in the *Traffic Analysis Procedures Manual* and *Development Services Manual*. Listed below is a summary; however, the depth and detail of content under each element varies in relation to the scale and complexity of the project.

(a) Executive Summary

(b) Table of Contents

1. List of Exhibits (Maps)
2. List of Tables

(c) Introduction

1. Description of the proposed project with purpose and need.
2. Traffic Impact Analysis Methods and Assumptions summary.
3. Map of project location.
4. Site plan, including all access to state highways (site plan, map).
5. Circulation network, including all access to state highways (vicinity map).
6. Land use and zoning.
7. Phasing plan, including proposed dates of project (phase) completion.
8. Project sponsor and contact person(s).
9. References to other traffic impact studies.
10. Other mitigation measures considered.

(d) Traffic Analysis

1. TIA M&A (see the *Traffic Analysis Procedures Manual* for a template or the *Development Services Manual*).
2. Existing and projected conditions of the site: posted speed; traffic counts (to include turning movements); sight distance; channelization; design analyses; pedestrian and bicycle facilities; design vehicle; and traffic controls, including signal phasing and multi-signal progression where appropriate (exhibit(s)).
3. DHV and ADT; project trip generation and distribution map, including references and a detailed description of the process involved in forecasting the projected trips, including tables.
4. Project-related transportation mode split, with a detailed description of the process involved in determining transportation mode split.
5. Project-generated trip distribution and assignment with a detailed description of the process involved in distributing and assigning the generated traffic, including exhibit(s).
6. If intersection control additions are employed and traffic signals are assumed, include functionality and warrant analyses. With roundabouts or signals, include existing conditions, cumulative conditions, and full-build of plan conditions with and without project.
7. Safety performance analysis (see Chapter 321 and the *Traffic Analysis Procedures Manual*).

(e) Conclusions and Recommendations

1. Quantified or qualified LOS, QOS, and other appropriate MOEs of impacted facilities with and without mitigation measures.
2. Predicted safety performance with and without mitigation measures.
3. Mitigation phasing plan with dates of proposed mitigation measures.
4. Defined responsibilities for implementing mitigation measures.
5. Cost estimates for mitigation measures and financing plan.

(f) Appendices

1. Description of traffic data and how data was collected and manipulated.
2. Description of methodologies and assumptions used in analyses.
3. Worksheets used in analyses; for example, signal warrants, LOS, QOS, and traffic count information.
4. If microsimulation is used, provide a copy of the Confidence and Calibration Report.

320.11 References

320.11(1) Federal/State Laws and Codes

42 United States Code 4321, National Environmental Policy Act (NEPA) of 1969

Revised Code of Washington (RCW) 43.21C, State environmental policy (Chapter 197-11 WAC and Chapter 468-12 WAC)

RCW 36.70a, Growth Management Act

RCW 36.70A.070, Comprehensive plans – Mandatory elements

RCW 47.06.140, Transportation facilities and services of statewide significance – Level of service standards

Washington Administrative Code (WAC) 365-196-430, Transportation elements of comprehensive plans

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)

320.11(2) Design Guidance

Design Manual, Chapter 321, for sustainable safety

Design Manual, Chapter 550, for interchange justification report guidelines

Design Manual, Chapter 1300, for selecting intersection control type

Design Manual, Chapter 1310, for intersection guidelines

Design Manual, Chapter 1320, for roundabout guidelines

Federal-Aid Highway Program Stewardship and Oversight Agreement:
http://www.wsdot.wa.gov/nr/rdonlyres/0f8eaddb-7fcc-4ea0-8609-5bca74634ebd/0/fhwawsdotstewardshipagreement.pdf

Highway Capacity Manual (HCM), latest edition, Transportation Research Board, National Research Council

Level of Service Standards for Washington State Highways

Roadside Design Guide and *A Policy on Geometric Design of Highways and Streets,* latest editions, American Association of State Highway and Transportation Officials (AASHTO)

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT

Traffic Analysis Procedures Manual (TAPM)

WSDOT Traffic Analysis web page:
http://www.wsdot.wa.gov/design/traffic/analysis/

320.11(3) Supporting Information

Development Services Manual, M 3007.00, WSDOT

FHWA Traffic Analysis Toolbox:
http://www.ops.fhwa.dot.gov/trafficanalysistools/index.htm

Traffic Manual, M 51-02, WSDOT

"Trip Generation," Institute of Transportation Engineers (ITE)

WSDOT's Highway Segment Analysis Program

WSDOT's *Mobility Project Prioritization Process Manual* and Workbook:
www.wsdot.wa.gov/mapsdata/travel/mobility.htm

WSDOT's Planning Level Cost Estimation (PLCE) Tool

Chapter 321 Sustainable Safety Analysis

321.01 Sustainable Safety Related Policy
321.02 HQ Safety Technical Group
321.03 Project Related Safety Analysis
321.04 Stand Alone Safety Analysis
321.05 Reports and Documentation
321.06 References

321.01 Sustainable Safety Related Policy

The Washington State Strategic Highway Safety Plan, "Target Zero" has a vision to reduce traffic fatalities and serious injuries to zero by 2030. WSDOT is pursuing this goal along with partners such as Washington State Patrol (WSP) and Washington Traffic Safety Commission (WTSC). WSDOT recognizes that risk exists in all modes of transportation. The universal objective is to reduce the number of fatal and serious injury crashes within the limits of available resources, science, technology, and legislatively mandated priorities.

The Secretary's Executive Order E 1085, Sustainable Highway Safety Program, sets the policy for the Washington State Department of Transportation (WSDOT) to embark on a targeted and scientifically-based Engineering approach for identifying and addressing crash risks that is multimodal and coordinated with the other three "E"s, Education, Enforcement, and Emergency Services. Sustainable Safety employs a "5th E", Evaluation, this is the analysis and diagnosis of crashes and to target their contributing factors in addressing highway safety performance. Evaluation relies on quantifying safety performance using scientific tools and assessment techniques to determine appropriate safety countermeasures.

Sustainable Safety is the approach to transportation safety at WSDOT through the use of "…tools and procedures based on accepted science, data, and proven practice" in accordance with Secretary's Executive Order E 1096, Agency Emphasis and Expectations, to target safety needs, and "deliver the right solutions at the right time and at the right location."

Practical Solutions is an approach to making project decisions that focus on resolving the project need for the least cost without adversely impacting safety performance. Sustainable Safety is the approach for resolving safety performance within WSDOT's Practical Solutions as directed in both E 1096 and Secretary's Executive Order E 1090, Moving Washington Forward: Practical Solutions.

E 1085 directs engineers to base project-level decisions on safety analysis of specific locations and corridors and focus on proven lower-cost targeted countermeasures at specific locations that optimize the return on investment of safety dollars. These lower-cost investments allow for additional identified locations to be addressed. Sustainable Safety is therefore an essential part of successful Practical Design implementation. It provides the process and methods to incorporate safety performance assessment and peer-review into Performance-Based Practical Design. Sustainable Safety allows the planner, engineer, and decision maker, to identify and quantify the safety performance of alternatives during project development.

Implementing Sustainable Safety improves WSDOT's effectiveness in reducing the risk of fatal and serious injury crashes statewide. It focuses on the contributing factors and types of crashes through the use of state-of-the-art principles and analytical methods to diagnose, quantify, and

predict safety performance. The Sustainable Highway Safety Policy directs WSDOT to use effective and efficient resources, like the AASHTO Highway Safety Manual (HSM) to achieve the goals of the Washington State Strategic Highway Safety Plan: Target Zero. This approach:

1. Optimizes the reduction in fatal and serious injury crash potential on Washington's highways.
2. Provides quantifiable assessment of crash potential.
3. Identifies locations that have a higher potential for crash reduction.
4. Provides reliable and accurate assessment of potential crash reduction benefits.
5. Identifies and deploys solutions with optimal benefit/cost within the WSDOT priority array or through low cost operational improvements.
6. Reduces waste by focusing on design elements that provide a reduction in crash potential.
7. Addresses locations that will result in a higher crash risk reduction potential for a given investment level.
8. Provides an accurate assessment of project and program performance.
9. Provides scientific and engineering tools to continually improve and refine safety analyses.

Sustainable Safety is a critical, integral part of Practical Solutions that supports Washington in reaching its Target Zero goal.

321.02 HQ Safety Technical Group

The HQ Safety Technical Group is comprised of experts in safety analysis. The team has several duties including maintaining the Safety Analysis Guide, safety analysis training, review of complex safety analysis, review of Collision Analysis Reports, and approve the use of crash modification factors. The team can also provide assistance to a project office as they conduct safety analysis.

321.03 Project Related Safety Analysis

All projects are required to have a safety analysis for Design Approval (see Chapter 300). The safety analysis is intended to be scalable. The HQ Safety Technical Group has written the Safety Analysis Guide to provide direction on the scope and scale of safety analysis for each funding subprogram (i.e. I-1, I-2, P-3) and each document needing a safety analysis (i.e. Design Analyses, IJRs, ICAs). Contact the HQ Safety Technical Group if your project is not covered by the Safety Analysis Guide or if you have questions regarding how to use the guide.

321.04 Safety Analysis

The *Safety Analysis Guide* contains guidance on the content of stand-alone safety analyses for Design Analyses, Crash Analysis Reports, Intersection Control Analyses, Transportation Management Plans, Road Safety Audits, Environmental Impact Statements, and Interchange Justification Reports. Contact the HQ Safety Technical Group if you have any questions or need to develop a stand-alone safety analysis that is not covered in the Safety Analysis Guide.

321.05 Reports and Documentation

The Crash Analysis Report (CAR), Intersection Control Analysis (ICA), and Basis of Design (BOD) utilize safety analysis. They are described in the following subsections. For approval requirements, refer to Chapter 300.

321.05(1) Crash Analysis Report (CAR)

A CAR is developed during the scoping phase for I-2 Collision Reduction projects and is required for funding to be released. A template of the Crash Analysis Report with instructions is available here: http://wwwi.wsdot.wa.gov/Planning/CPDMO/PlanningProgrammingSafety_I-2.htm

If a CAR was developed using the template for the 2019-21 biennium or newer, the project does not need a BOD.

321.05(2) Intersection Control Analysis (ICA)

Projects that require an ICA need to do a safety analysis on the alternatives. If a project has a completed CAR, the ICA may reference this CAR. If not, the safety analysis for the ICA should have a scale and scope associated with its funding source as noted in the Safety Analysis Guide.

321.05(3) Basis of Design (BOD)

The BOD utilizes metrics and targets in the baseline and contextual needs. If the chosen metric is safety related utilize a safety analysis to determine the potential for crash reduction for various alternatives. The safety analysis may also be used as a component in the Alternative Comparison Table (ACT) to allow easier comparison across alternatives. The scale and scope of a safety analysis for a BOD is associated with its program type and is explained in the Safety Analysis Guide.

321.06 References

321.06(1) Federal/State Directives, Laws, and Codes

23 United States Code (USC) 148 – Federal requirements for the Highway Safety Improvement Program (HSIP)

Revised Code of Washington (RCW) 47.05.010 – The statement of purpose for priority programming of transportation projects

Secretary's Executive Order 1085 – Sustainable Highway Safety Program

Secretary's Executive Order 1090 – Moving Washington Forward: Practical Solutions

Secretary's Executive Order 1096 – WSDOT 2015-17: Agency Emphasis and Expectations

321.06(2) Design Guidance

Safety Analysis Guide, WSDOT; See Sustainable Highway Safety Tools here:
http://www.wsdot.wa.gov/Design/Support.htm

Highway Safety Manual (HSM), AASHTO, 2010

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO, 2011

321.06(3) Supporting Information

Strategic Highway Safety Plan: Target Zero – Washington State´s strategic traffic safety plan developed by the Washington Traffic Safety Commission: http://www.targetzero.com/

Sustainable Highway Safety Internal Web Page – Contains all of the procedures and tools to implement highway safety: http://wwwi.wsdot.wa.gov/HighwaySafety/

Washington Transportation Plan – Washington State Transportation Commission´s recommended strategic transportation plan; includes a highway safety element: http://www.wstc.wa.gov/wtp/documents/wtp2030_201012.pdf

Chapter 400 Surveying and Mapping

400.01 General
400.02 References
400.03 Procedures
400.04 Datums
400.05 Global Positioning System
400.06 WSDOT Survey Monument Database
400.07 Geographic Information System
400.08 Photogrammetric Surveys
400.09 Documentation

400.01 General

The Washington State Department of Transportation (WSDOT) is permitted, by an agreement with the Board of Registration for Professional Engineers and Land Surveyors, to practice land surveying "under the direct supervision of a licensed professional land surveyor OR a licensed professional engineer" (see Exhibit 400-1, Interagency Agreement).

400.02 References

400.02(1) Federal/State Laws and Codes

Revised Code of Washington (RCW) 58.09, Surveys – Recording

RCW 58.20.120, System designation – Permitted uses

RCW 58.24.040(8), " . . . temporary removal of boundary marks or monuments"

Washington Administrative Code (WAC) 332-120, Survey monuments – Removal or destruction

WAC 332-130, Minimum standards for land boundary surveys and geodetic control surveys and guidelines for the preparation of land descriptions

Interagency Agreement Between the Washington State Department of Transportation and the Board of Registration for Professional Engineers and Land Surveyors (1990)

400.02(2) Design Guidance

Construction Manual, M 41-01, WSDOT

Highway Surveying Manual, M 22-97, WSDOT

Plans Preparation Manual, M 22-31, WSDOT

WSDOT Survey Monument Database
www.wsdot.wa.gov/monument/

400.03 Procedures

For WSDOT projects, it is recommended that surveying activities include (if appropriate) but not be limited to the following items.

400.03(1) Project Definition Phase

During the Project Definition phase, perform the following:

(a) Record any pertinent surveying information as detailed in the Design Documentation Checklist: www.wsdot.wa.gov/design/projectdev/

(b) Conduct research to find recorded survey monuments existing within the project area.

(c) Determine and prioritize project survey needs and tasks to be completed. Needs and tasks may include the following issues:

- Cadastral
- Right of way
- Geodetic
- Photogrammetry
- Other issues as needed

(d) Contact city, county, state, and federal agencies, the Region Survey Office, and the GeoMetrix Geodetic Survey section for potential impact to existing monuments.

400.03(2) Design and Development of the Plans, Specifications, and Estimates

During the design and development of the Plans, Specifications, and Estimates (PS&E), perform the following:

(a) The project manager and project surveyor hold a preliminary survey meeting, regarding:

- Project schedule.
- Anticipated survey requests.

For preliminary survey meeting specifics and roles and responsibilities of the project manager and project surveyor, see the *Highway Surveying Manual*.

(b) Perform field reconnaissance, mark existing recorded survey monuments, and determine the location of possible new survey monuments. Also, mark found unrecorded monuments for preservation if practical.

(c) Contact the GeoMetrix Geodetic Survey section by email, memo, or other written notification for assistance in determining the impact to state and federal geodetic monuments.

(d) Refer to the *Highway Surveying Manual* to:

- Convert Washington State Plane Coordinates to project datum.
- Document the procedure and combined factor used for converting between datums.
- Determine survey collection methods.
- Collect primary, secondary, and tertiary survey data.
- Process and import secondary, tertiary, or other survey data into design software for use by designers.

(e) Apply to the Department of Natural Resources (DNR) for permits for monuments that will be disturbed or removed (see Chapter 410).

(f) The GeoMetrix Geodetic Survey section will archive new primary survey control data in the WSDOT Monument Database for future retrieval.

(g) Ensure that all survey monuments within the project right of way are shown on the contract plans in order to avoid accidental damage.

(h) Develop a Record of Survey (RCW 58.09) or a Monumentation Map as required (see Chapter 410).

400.03(3) After Construction is Completed

(a) Complete a post construction survey as described in the *Highway Surveying Manual*.

(b) Have the DNR Completion Report signed and stamped by the appropriate professional in direct charge of the surveying work, then file with DNR as described in Chapter 410.

400.04 Datums

A datum is a geometrical quantity (or set of quantities) that serves as a reference, forming the basis for computation of horizontal and vertical control surveys in which the curvature of the earth is considered. Adjusted positions of the datum, described in terms of latitude and longitude, may be transformed into State Plane Coordinates.

All engineering work (mapping, planning, design, right of way, and construction) for WSDOT projects is based on a common datum.

400.04(1) Horizontal

WAC 332-130-060 states, "The datum for the horizontal control network in Washington shall be NAD83 (1991) [the North American Datum of 1983] as officially adjusted and published by the National Geodetic Survey of the United States Department of Commerce and as established in accordance with Chapter 58.20 RCW. The datum adjustment shall be identified on all documents prepared; i.e., NAD83 (1991)." (See the *Highway Surveying Manual* for further information.)

400.04(2) Vertical

The North American Vertical Datum of 1988 (NAVD88) as defined by the National Geodetic Survey (NGS) is the official civilian datum for surveying and mapping activities in the United States. WSDOT has adopted this datum. (See the *Highway Surveying Manual* for further information.)

400.05 Global Positioning System

A Global Positioning System (GPS) uses a constellation of satellites and earth stationed receivers to determine geodetic positions (latitude and longitude) on the surface of the earth. WSDOT personnel use this survey technology. (See the *Highway Surveying Manual* for more detailed discussions.)

GPS technology is changing rapidly. The key point is for the designer and surveyor to select the best tool (GPS or conventional applications) for doing the survey fieldwork. Often, a combination of GPS and conventional (Total Station) surveying is appropriate.

400.06 WSDOT Survey Monument Database

The WSDOT Survey Monument Database provides storage and retrieval capabilities for data associated with survey control monuments set by WSDOT. This database supports and tracks the Report of Survey Mark and aids in fulfilling WSDOT's obligation to contribute to the body of public record, thereby minimizing the duplication of survey work. The Report of Survey Mark provides data on specific GPS stations. (See Exhibit 400-2 for an example of a Report of Survey Mark.)

To access the WSDOT Survey Monument Database, see the following website:
www.wsdot.wa.gov/monument/

400.07 Geographic Information System

The Geographic Information System (GIS) is a compilation of information from many sources. Its purpose is to assemble data into a central database for the common good. The data is stored on many levels so the desired information can be selected and combined to achieve the desired product. Surveying and photogrammetric data are vital elements of this system.

400.08 Photogrammetric Surveys

Photogrammetric surveys are performed to furnish topographic or planimetric maps and cross sections for use in the reconnaissance, location, and preliminary design phases of highway work. To use photogrammetric surveys for final design and construction requires that the ground be nearly bare to obtain the necessary accuracy. By using well-planned aerial photography in stereoscopic plotters, contours and other physical features are delineated on map sheets to a scale consistent with the accuracies or detail required.

The usefulness of aerial photography is not limited to mapping. Taking the form of enlargements, mosaics, and digital images, it can be used as a visual communication tool (displays and exhibits) for planning, design, property acquisition, engineering, construction, litigation, and public relations.

To obtain information on preparation, procedure, and programming of aerial photography and photogrammetric mapping and applications, contact the HQ GeoMetrix Office. When requesting a photogrammetric survey, specify the desired units and check the units of the product. Allow for the time required to communicate the complex and detailed work request, develop the service, and accomplish the product.

400.09 Documentation

For documentation related to monuments, see Chapter 410.

Primary and secondary survey control data are archived in the WSDOT Survey Monument Database and GIS when available.

For the list of documents required to be preserved in the Design Documentation Package and the Project File, see the Design Documentation Checklist:
www.wsdot.wa.gov/design/projectdev/

Exhibit 400-1 Interagency Agreement

INTERAGENCY AGREEMENT BETWEEN
THE WASHINGTON STATE DEPARTMENT OF TRANSPORTATION
AND THE BOARD OF REGISTRATION FOR PROFESSIONAL
ENGINEERS AND LAND SURVEYORS

THE FOLLOWING Interagency Agreement is hereby entered into between the Washington State Department of Transportation (hereafter referred to as "WSDOT") and the Washington State Board of Registration for Professional Engineers and Land Surveyors (hereafter referred to as "BOARD").

I

DECLARATIONS OF THE PARTIES

A. WHEREAS the BOARD has the exclusive authority to regulate the practice of engineering and land surveying in Washington; and

B. WHEREAS WSDOT employees are required to practice land surveying as defined by RCW 18.43.020 in carrying out the program of said agency; and

C. WHEREAS WSDOT is exempted from necessarily using a licensed land surveyor to perform said surveys in accordance with the provisions of the Survey Recording Act, RCW 58.09.090; and

D. WHEREAS both the BOARD'S and WSDOT'S goals include the performance of land surveys in conformance with recognized standards of practice and relevant laws and administrative codes in order to safeguard life, health and property; and

E. WHEREAS the parties to this Agreement agree to the following Principles of Agreement.

II

PRINCIPLES OF AGREEMENT

A. The practice of land surveying performed by WSDOT employees shall be under the direct supervision of a licensed professional land surveyor OR licensed professional engineer. Said licensee shall hold a valid Washington license issued in conformance with RCW 18.43.

B. All surveys performed by WSDOT employees shall be performed in accordance with the Survey Standards promulgated under Chapter 332-130 WAC.

C. When a survey has been performed by WSDOT employees a survey map shall be prepared and filed with the county engineer in compliance with RCW 58.09.090(1)(a). Said map's contents shall be in conformance with the requirements of RCW 58.09.060 and WAC 332-130. Furthermore, said map shall contain the stamp and signature of the licensee who was in direct responsible charge of the work.

Exhibit 400-1 Interagency Agreement (continued)

D. A record of corner information shall be filed in accordance with RCW 58.09.040(2) and 58.09.090(2) where WSDOT employees replace or restore an existing or obliterated general land office corner. Said record of corner information shall be signed and stamped by the professional land surveyor or professional engineer responsible for said work.

E. The temporary removal or destruction of any section corner or any other land boundary mark or monument shall be permitted if performed in compliance with RCW 58.24.040(7)(8).

F. Whether performed by a licensed professional engineer or a licensed professional land surveyor, any surveys performed by WSDOT shall be in accordance with the standards generally expected of those practicing professional land surveying.

IN WITNESS WHEREOF: The Washington State Department of Transportation and the Board of Registration have signed this Agreement.

/S/ 1/5/90

Ed W. Ferguson, PE Date
DEPUTY SECRETARY
Department of Transportation

This Agreement approved by motion of the Board dated January 19, 1990.

/S/ 1/19/90

Wesley E. Taft, PE Date
CHAIRMAN, Board of Registration

Exhibit 400-2 Report of Survey Mark Example

Washington State Department of Transportation **Geographic Services**

SURVEY INFORMATION SYSTEM **Report of Survey Mark**

GENERAL MONUMENT INFORMATION

Designation:	GP29530-21	**T.R.S:**	31N, 5E , 2		
Monument ID:	8	**Corner Code:**			
State:	WASHINGTON	**State Route:**	530	**ACCOUNTS INFORMATION**	
County:	SNOHOMISH	**Mile Post:**	20.590	**BOOK**	**PROJECT** **INVOICE**
Region:	NW	**Station:**		49	0L2030 23-94042
Nearest Town:	ARLINGTON	**Offset:**			
Usgs Quad:	ARLINGTON WEST	**Owner:**	GS		
		Bearing:	M		

Description

TO REACH THE STATION FROM THE INTERSECTION OF SR 530 AND SR 009 AT ARLINGTON, GO WEST 0.2 MILES ALONG SR 530 TO THE STATION ON THE RIGHT. IT IS LOCATED 1.1 METERS SOUTH OF A WITNESS POST, 33.5 METERS WEST OF THE APPROXIMATE CENTERLINE OF DIKE ROAD AND 1.2 METERS NORTH OF A GUARD RAIL. THE STATION IS A STANDARD WSDOT BRASS DISK SET IN A ROUND CONCRETE MONUMENT PROJECTING 0.2 FEET ABOVE THE GROUND. NOTE: 'POSITION UP-DATE BY OCCUPYING WITH G.P.S.' NOTE: TIED TO HPN 4/94. THIS IS A NAVD88 UPDATE.



CURRENT SURVEY CONTROL

DATUM	LATITUDE	UNIT	LONGTITUDE	UNIT	NETWORK	METHOD	ACCURACY
NAD 83/91	48 11 54.567381	N	122 08 03.530464	W	PRIMARY	GPS	2 CM

Chapter 410 Monumentation

410.01 General
410.02 References
410.03 Control Monuments
410.04 Alignment Monuments
410.05 Property Corners
410.06 Other Monuments
410.07 Filing Requirements
410.08 Documentation

410.01 General

Proper monumentation is important in referencing a highway's alignment, which is used to define its right of way. The Washington State Department of Transportation (WSDOT) can contribute to the body of public records and minimize duplication of survey work by establishing and recording monuments that are tied to a state plane coordinate system and to a standard vertical datum. WSDOT is required by law to perpetuate existing recorded monuments (Chapter 58.09 RCW). The department provides monuments for realignments and new highway alignments and perpetuates existing monuments impacted by a project.

The Department of Natural Resources (DNR) is designated as the official agency for surveys and maps. New monuments set to establish property corners, highway alignment, and so on, shall be recorded on a Record of Survey or Monumentation Map and filed with the DNR Public Land Survey Office and the appropriate county auditor or county engineer. Records of Survey and Monumentation Maps are retained at DNR. Geodetic monuments are established and the Headquarters (HQ) GeoMetrix Office retains their placement records. Geodetic monuments are recorded on a Report of Survey Mark. These records are made available to the public on the following website: www.wsdot.wa.gov/monument/

Existing monuments are not to be disturbed without first obtaining the DNR permits required by state law. DNR allows the temporary covering of a string of monuments under a single permit. State law requires replacement of land boundary monuments after temporary removal according to permit procedures. WSDOT control and alignment monuments may not be removed without replacement unless the location of the original position is perpetuated by reference and the appropriate document(s) prepared and filed with the county and the HQ Right of Way Plans Section. Other requirements pertaining to specific monuments are discussed below.

Exhibit 410-1 summarizes the documentation requirements for new and existing monuments.

The region is responsible for identifying and locating existing monuments, obtaining required permits before any existing monument is disturbed, and conducting the research to locate existing monuments as required by WAC 332-120-030, as follows:

> *Any person, corporation, association, department, or subdivision of the state, county or municipality responsible for an activity that may cause a survey monument to be removed or destroyed shall be responsible for ensuring that the original survey point is perpetuated. It shall be the responsibility of the governmental agency or others performing construction work or other activity (including road or street resurfacing projects) to adequately search the records and the physical area of the proposed construction work or other activity for the purpose of locating and referencing any known or existing survey monuments.*

410.02 References

410.02(1) Federal/State Laws and Codes

Chapter 18.43 Revised Code of Washington (RCW), Engineers and land surveyors

Chapter 58.09 RCW, Surveys – Recording

Chapter 58.24 RCW, State agency for surveys and maps – Fees

Chapter 332-120 Washington Administrative Code (WAC), Survey monuments – Removal or destruction

Chapter 332-130 WAC, Minimum standards for land boundary surveys and geodetic control surveys and guidelines for the preparation of land descriptions

410.02(2) Design Guidance

Electronic Engineering Data Standards
www.wsdot.wa.gov/publications/manuals/m3028.htm

Highway Surveying Manual
www.wsdot.wa.gov/publications/manuals/m22-97.htm

Manual of Instructions for the Survey of the Public Lands of the United States, BLM, U.S. Department of the Interior, 1973

Plans Preparation Manual
www.wsdot.wa.gov/publications/manuals/m22-31.htm

410.03 Control Monuments

Horizontal and vertical control monuments are permanent references required for the establishment of project coordinates tied to the Washington State plane system and elevations tied to a standard vertical datum. By establishing and recording permanent control monuments, WSDOT eliminates duplication of survey work and contributes to the body of public records.

Provide the horizontal and vertical control monuments for highway projects that require the location of existing or proposed alignment or right of way limits. Monuments set by other agencies may be used if within 1 mile of the project and where the required datum and accuracy were used.

When control monuments are required for a given project, show the existing and proposed control monuments on the contract plans.

For horizontal control:

- Use North American Datum 1983, revised 1991 (NAD83/91).
- Use a minimum of second order, Class II procedures as defined in the *Highway Surveying Manual*.
- Provide two monuments near the beginning of the project. Where possible, when setting horizontal control, set points to act as azimuth points. Place points so that line of sight is preserved between them and in an area that will not be disturbed by construction.
- Provide two monuments near the end of the project.
- Provide a pair of monuments at about 3-mile intervals throughout the length of the project.

For vertical control:

- Use North American Vertical Datum 1988 (NAVD88). (See the *Highway Surveying Manual* for orders of accuracy required.)
- Use at least second order procedures for primary vertical control within project limits as defined in the *Highway Surveying Manual*. Use third order for secondary control throughout the project.
- Provide vertical control throughout the length of the project. Desirable spacing is at or near each milepost. Maximum spacing is 3 miles apart.

All control monuments that are established, reestablished, or reset must be filed with the county engineer and the Department of Natural Resources (DNR). Submit a Record of Survey or a Monumentation Map that has been signed by the supervising, licensed, professional engineer or licensed, professional land survey. If the monument is not used to reference right of way or land corners, submit a Report of Survey Mark. (See the *Highway Surveying Manual* for more detailed guidance on Control Monuments.)

410.04 Alignment Monuments

Alignment monuments are permanent references required for the establishment or reestablishment of the highway and its right of way. Placing monuments at random points, in safe locations and tied to the Washington State plane coordinate system is recommended (see the *Highway Surveying Manual*).

Establishment, reestablishment, or resetting of alignment monuments is required on the following highway projects:

- New highway alignment projects.
- Highway realignment projects involving new right of way (monuments are only required for the realigned highway section).
- Highway projects where alignment monuments already exist.

Before an existing alignment monument is reestablished or reset, a DNR permit is required.

All alignment monuments that are established, reestablished, or reset must be filed with the appropriate county auditor or county engineer. The Record of Survey is filed with the county auditor in the county in which the monument is located, and a recorded copy is sent to the HQ Right of Way Plans Section. The original Monumentation Map is filed with the county engineer of the county in which the monument is located, and a recorded copy, with the filing signatures, is sent to the HQ Right of Way Plans Section. The HQ Right of Way Plans Section will forward a copy to DNR for its records.

410.05 Property Corners

A new property corner monument will be provided where an existing recorded monument, or an unrecorded monument set by a professional land surveyor (PLS) prior to the Recording Act of 1973 (RCW 58.09), has been invalidated as a direct result of a right of way purchase by the department. The property corner monument will be set on the new right of way line or at a point in reference thereto. Property corner monuments may also be set at the location of new acquisitions such as wetlands or stormwater mitigation sites or properties shown on Sundry Site Plans. The new property corner monument shall be set by or under the direct supervision of a licensed PLS.

When any property corner monument is set, the licensed land surveyor shall file a Record of Survey with the county auditor. A copy of the recorded Record of Survey is sent to the HQ Right of Way Plans Section and HQ Real Estate Services.

410.06 Other Monuments

A DNR permit is required before any monument may be removed or destroyed.

Existing section corners and BLM or GLO monuments impacted by a project shall be reset to perpetuate their existence. After completing the work, a DNR Land Corner Record is required.

Other permanent monuments established by any other governmental agency must not be disturbed until the agency has been contacted to determine specific requirements for the monument. If assistance is needed to identify a monument, contact the HQ GeoMetrix Office.

Resetting monuments must be done by or under the direct supervision of a licensed professional engineer or a licensed professional land surveyor. If a Record of Survey is prepared, it will be filed with the county auditor in the county in which the monument is located. If a Monumentation Map is prepared, it is filed with the county engineer in the county in which the monument is located, and a recorded copy is sent to the HQ Right of Way Plans Section. The HQ Right of Way Plans Section will forward a copy to DNR for its records.

410.07 Filing Requirements

410.07(1) DNR Permit

When a DNR permit is required, use the application form shown in Exhibit 410-2. The completed application must be signed by a licensed professional engineer or a licensed professional land surveyor and submitted to DNR. The DNR permit applications can be downloaded in TIFF, PDF, or Word format at the following website:

www.dnr.wa.gov/businesspermits/howto/landownersindustrycontractors/pages/eng_plso_forms.aspx

Monumentation work cannot be done until DNR has approved the permit. In extraordinary circumstances, verbal authorization may be granted by DNR pending the issuance of a written permit.

After resetting the monument, the survey method used must be filed with DNR using the completion report form shown in Exhibit 410-3. The form is to be signed by a licensed professional engineer or a licensed professional land surveyor.

410.07(2) Monumentation Map

When a Monumentation Map is required, a plan sheet is prepared. Generally, the plan sheet is based on a right of way plan obtained from the HQ Right of Way Plans Section. A Monumentation Map contains a description of all new and existing monuments indicating their kind, size, and location. In addition, it must contain the seal and signature of a licensed professional engineer or a licensed professional land surveyor (see the *Plans Preparation Manual*).

A copy of a Monumentation Map is filed with the county engineer in the county in which the monument is located, and a recorded copy is sent to the HQ Right of Way Plans Section. The HQ Right of Way Plans Section will forward a copy to DNR for its records.

410.07(3) Land Corner Record

When a Land Corner Record is required, use the forms shown in Exhibit 410-4. The completed forms are to be signed and stamped by a licensed professional engineer or a licensed professional land surveyor and submitted to the county auditor for the county in which the monument is located.

410.08 Documentation

Refer to Chapter 300 for design documentation requirements.

SET NEW
WSDOT Control Monument
Before: No permit required.
After: File a copy of the Monumentation Map with the county engineer. Send the original to the HQ Right of Way Plans Section.
Alignment Monument
Before: No permit required.
After: File a Record of Survey with the county auditor or a Monumentation Map with the county engineer. Send a copy to the HQ Right of Way Plans Section.
Property Corner Monument*
Before: Engage a licensed professional land surveyor.
After: Licensed professional land surveyor files Record of Survey with county auditor, or a licensed professional engineer files a Monumentation Map with the county engineer and sends a copy to the HQ Right of Way Plans Section.
DISTURB EXISTING*
Control Monument
Before: Obtain DNR permit.
After: File a copy of the Monumentation Map with the county engineer. Send the original to the HQ Right of Way Plans Section.
Alignment Monument
Before: Obtain DNR permit.
After: File a copy of the Monumentation Map with the county engineer. Send the original to the HQ Right of Way Plans Section.
Section Corner, BLM, or GLO Monument
Before: Obtain DNR permit.
After: File Land Corner Record with the county engineer. Send a copy to the HQ Right of Way Plans Section.
All Other Monuments
Before: Obtain DNR permit. Contact governmental agency.
After: File a copy of the Monumentation Map with the county engineer. Send the original to the HQ Right of Way Plans Section.
* Property corner monuments must be filed within 90 days of establishment, re-establishment, or restoration.

Monument Documentation Summary
Exhibit 410-1

APPLICATION FOR PERMIT TO REMOVE OR DESTROY A SURVEY MONUMENT

PERMIT NO.
You are hereby authorized to remove or destroy the described survey monument(s):

AUTHORIZING SIGNATURE/DATE
(DNR or Other Authorizing Agency)

APPLICANT INFORMATION:

NAME: TELEPHONE NO: DATE:

COMPANY OR AGENCY NAME AND ADDRESS:

I estimate that this work will be finished by (date)_____.

_____I request a variance from the requirement to reference to the Washington Coordinate System. (Please provide your justification in the space below.)

The variance request is approved; not approved. (FOR DNR USE ONLY) Reason for not approving:

MULTIPLE MONUMENTS:
_____Check here if this form is being used for more than one monument. You must attach separate sheets showing the information required below for each monument affected. You must seal, sign and date each sheet.

INDEXING INFORMATION FOR AN INDIVIDUAL MONUMENT:
1) THE MONUMENT IS LOCATED IN: SEC TWP RGE 1/4-1/4
2) ADDITIONAL IDENTIFIER: (e.g., BLM designation for the corner, street intersection, plat name, block, lot, etc.)

MONUMENT INFORMATION: Describe: 3) the monument/accessories found marking the position, 4) the temporary references set to remonument the position (include coordinates when applicable), and 5) the permanent monument(s) to be placed on completion (if a permanent witness monument(s) is set include the references to the original position).

SEAL/SIGNATURE/DATE SIGNED

(Form prescribed 2/94 by the Public Land Survey Office, Dept. of Natural Resources, pursuant to RCW 58.24.040 (8).)

DNR Permit Application
Exhibit 410-2

COMPLETION REPORT FOR MONUMENT REMOVAL OR DESTRUCTION

(TO BE COMPLETED AND SENT TO THE DNR AFTER THE WORK IS DONE.)

_____

_____I have perpetuated the position(s) as per the detail shown on the application form.

_____
SEAL/SIGNATURE/DATE SIGNED

OR

_____I was unable to fulfill the plan as shown on the application form. Below is the detail of what I did do to perpetuate the original position(s). (If the application covered multiple monuments attach sheets providing the required information. Seal, sign and date each sheet.)

_____
SEAL/SIGNATURE/DATE SIGNED

DNR Completion Report Form
Exhibit 410-3

LAND CORNER RECORD

GRANTOR/SURVEYOR/PUBLIC OFFICER: This corner record correctly represents work performed by me or under my direction in conformance with the Survey Recording Act.

COMPANY OR AGENCY:

ADDRESS:

GRANTEE: PUBLIC SEAL/SIGNATURE/DATE

LEGAL: TWP: RGE: CORNER CODE:

ADDITIONAL IDENTIFIER:(BLM designation, street or plat names, block, lot, etc.)

COUNTY:

WASHINGTON PLANE COORDINATES: N: E:

ORDER: ZONE: DATUM (Date of adjustment):

CORNER INFORMATION: Discuss the history, evidence found, and perpetuation of the corner. Diagram the references; provide the date of work; and, if applicable, a reference to a map of record and/or the field book/page no. Use the back, if needed.


This form is in compliance with the intent of RCW 65.04.045 and prescribed by the Public Land Survey Office, Department of Natural Resources - 1/97.

Land Corner Record
Exhibit 410-4

MARK THE CORNER LOCATION BELOW AND FILL IN THE CORNER CODE BLANK ON THE OTHER SIDE:
For corners at the intersection of two lines, the corner code is the alphanumeric coordinate that corresponds to the appropriate intersection of lines.

For corners that are only on one line, the corner code is the line designation and the related line segment; i.e., a corner on line 5 between "B" and "C" is designated BC-5.

For corners that are between lines, the corner code is both line segments; i.e., a corner in the SE1/4 of the SE1/4 of section 18 is designated MN 4-5.



RCW 58.09.060 (2) requires the following information on this form: an accurate description and location, in reference to the corner position, of all monuments and accessories (a) found at the corner and (b) placed or replaced at the corner; (c) basis of bearings used to describe or locate such monuments or accessories; and (d) corollary information that may be helpful to relocate or identify the corner position.

SPACE FOR ADDITIONAL COMMENT:

Land Corner Record
Exhibit 410-4 (continued)

Chapter 510 Right of Way Considerations

510.01 General
510.02 Special Features
510.03 Easements and Permits
510.04 Programming for Funds
510.05 Appraisal and Acquisition
510.06 Transactions
510.07 Documentation
510.08 References

510.01 General

Washington State Department of Transportation (WSDOT) Real Estate Services personnel participate in the project definition phase of a project to assist in minimizing right of way costs, defining route locations and acquisition areas, and determining potential problems and possible solutions.

Due to the variables in land acquisition, the categories of right of way costs considered in the project definition phase are:

- Purchase costs (acquisition compensation).
- Relocation assistance benefits payments.
- Other Real Estate Services staff expenses (acquisition services, relocation services, and interim property management services).

Right of way cost estimates are made by Real Estate Services specialists. When the parcels from which additional right of way will be acquired are known, title reports (including assessors' land areas) can be requested.

Real Estate Services personnel also make project field inspections at appropriate times throughout the development of a project to ensure adequate consideration is given to significant right of way elements involved (including possible social, economic, and environmental effects) in accordance with the *Right of Way Manual*.

During plan development:

- Title reports are examined for easements or other encumbrances that would reveal the existence and location of water lines, conduits, drainage or irrigation lines, and so on, that must be provided for in construction.
- Easements that indicate other affected ownerships are added to the right of way and limited access plan.
- Arrangements are made to obtain utility, railroad, haul road, detour routes, or other essential agreements, as instructed in the *Utilities Manual* and the *Agreements Manual*.
- Right of way acquisition, disposal, and maintenance are planned.
- Easements and permits are planned (to accommodate activities outside of the right of way).

Engineering considerations for right of way are contained in many chapters in this manual. Examples include chapters in the 700 series related to bridges and walls and in Chapter 1230, Geometric Cross Section. (See Chapter 1102, Context Identification, as a recommended first read for discussion of right of way.) Preliminary right of way widths are developed and may be modified based on Real Estate Services' input, but cannot be moved to coincide with property boundaries in anticipation of a total take. Jogs in the final widths of the right of way are held to a minimum. (See *Right of Way Manual*, Chapter 6, for discussion of remainders.)

All acquisition documents are processed through Headquarters (HQ) Real Estate Services except temporary permits that are not shown on right of way plans and are not needed for the project (such as for driveway connections).

510.02 Special Features

510.02(1) Road Approaches

On managed access highways, the department will reconstruct legally existing road approaches that are removed or destroyed as part of the highway construction. New approaches required by new highway construction are negotiated by the region with the approval of the Regional Administrator. The negotiator coordinates with the region's design section to ensure new approaches conform to the requirements of Chapter 1340 for road approaches. All new approaches will be by permit through the appropriate region office.

On limited access highways, road approaches of any type must be approved by the Director & State Design Engineer, Development Division, before there is legal basis for negotiation by Real Estate Services. When approved, approaches will be specifically reserved in the right of way transaction and will contain the identical limitations set by the Director & State Design Engineer, Development Division, and as shown on the approved right of way and limited access plan.

510.02(2) Cattle Passes

The desirability of or need for a cattle pass will be considered during the appraisal or negotiation process. A cattle pass will be approved only after complete studies of location, utilization, cost, and safety elements have proved its necessity. Upon approval, such an improvement and appurtenant rights will be established. Future right of access for maintenance is negotiated during acquisition.

On limited access highways, approval by the Director & State Design Engineer, Development Division, and the addition of a traffic movement note on the right of way and limited access plan (see the *Plans Preparation Manual*) are required.

510.02(3) Pit, Stockpile, and Waste Sites

These sites are investigated and planned as outlined in the *Plans Preparation Manual*. Detour and haul road agreements, approved by the Regional Administrator, are necessary when the state proposes to use city streets or county roads for the purpose of detouring traffic or hauling certain materials. (See the *Utilities Manual* for detour and haul road agreement guidelines.)

510.02(4) International Boundaries

Construction proposed "within a 20-foot strip, 10 feet on each side of the international boundary," must be coordinated between the department and the British Columbia Ministry of Highways and Public Works.

Permission of the International Boundary Commission is required to work "within 10 feet of an international boundary." Their primary concern is monumentation of the boundary line and the line of sight between monuments. The Commission requires a written request stating what, when, and why construction will be done, sent to:

International Boundary Commission
United States and Canada
2000 L Street NW, Suite 615
Washington, DC 20036
(www.internationalboundarycommission.org)

510.03 Easements and Permits

510.03(1) General

If others request rights within existing WSDOT ownership, they are to contact the region Real Estate Services Office.

Easements and permits to accommodate WSDOT activities outside the right of way usually fall into one of the categories defined below.

Easements and permits are processed in accordance with the requirements of the *Right of Way Manual*. The region Real Estate Services Office drafts the legal descriptions for all easements and permits for acquisition of property and property rights. HQ Real Estate Services drafts the legal description for all easements and permits for disposition of property or property rights. The region Real Estate Services Office either obtains or assists in obtaining easements and permits. The region is responsible for compliance with and appropriate retention of the final documents. Records of permanent property rights acquired are maintained by HQ Real Estate Services. Easements and permits are to be shown on the contract plans in accordance with the *Plans Preparation Manual*.

510.03(2) Perpetual Easements

Perpetual easements are shown on the right of way plans in accordance with the *Plans Preparation Manual*.

510.03(2)(a) State Maintenance Easement

Used when the state is to construct a facility and provide all maintenance. Examples are slope and drainage easements.

510.03(2)(b) Dual Maintenance Easement

Used when the state is to construct and maintain a facility and the owner is to maintain the remainder. Examples include the surface area above a tunnel and the area behind a retaining wall or noise wall.

510.03(2)(c) Transfer Easement

On occasion an easement must be acquired for transfer to another party. In these cases, contact the region Real Estate Services Office for early involvement. The right of way and limited access plan is modified to identify the party to whom the easement will be transferred. The department cannot obtain easements for transfer across lands under the jurisdiction of the Department of Natural Resources, and WSDOT cannot condemn for a transfer easement.

510.03(3) Temporary Easements

Temporary easements are used when the state requires a temporary property right that involves either more than minor work or construction activities on privately owned property. In the cases where the rights required or the work to be performed is not beneficial to the property owner, just compensation must be paid.

When WSDOT is paying for the rights or when the encroachment is significant, temporary easements are shown on the right of way plans, in accordance with the *Plans Preparation Manual*. Consult the region Plans and Real Estate Services personnel for exceptions. If the easement is not mapped, mark and submit plans according to the following information.

(a) The region provides a right of way plan with the required temporary easement(s) delineated in red to the region Real Estate Services Office. These plan sheets provide:

- Ownership boundaries. Confirmation of ownership and parcel boundaries may be completed by a search of county records and mapping; a formal title report is required for temporary easements.
- A parcel number assigned to each ownership.
- Sufficient engineering detail to write legal descriptions.
- A statement of the intended use of each temporary easement area.

(b) In limited access areas, contact the HQ Access and Hearings Office.

510.03(4) Construction Permits

Construction permits are used for temporary rights during construction. They are not used when WSDOT needs a perpetual right. A construction permit is only valid with the current owner and must be renegotiated if property ownership changes before construction begins. For private ownerships, a temporary construction easement is recommended. A construction permit is recommended for rights of entry to publicly owned property. Local agencies might require the use of specific forms when applying for these rights of entry. Regardless of the form or its name, the region is responsible for appropriate central storage of the original document.

When there is a benefit to the property owner (for example, driveway or parking lot approach improvements) the construction permit is usually obtained without the payment of compensation (for example, donation or mutual benefits). Consult the region Plans and Real Estate Services offices for exceptions.

510.04 Programming for Funds

For plan development, the phases in Exhibit 510-1 apply to the authorization of stage programming.

When federal funds are involved, special attention must be given to Federal Highway Administration (FHWA) requirements. When federal participation in right of way costs is anticipated, specific authorization must be obtained from the FHWA. The rules and procedures provided in RCW 8.26, WAC 468-100, and the *Right of Way Manual* must be followed to ensure federal and state participation. In many cases, federal funds are contingent upon the department setting up a relocation advisory procedure for any owner or tenant who is displaced by a project and desires such assistance. Relocation advisory assistance is a function of HQ Real Estate Services.

510.05 Appraisal and Acquisition

510.05(1) All Highways

Exhibit 510-1 shows plan development phases for both limited access highways and managed access highways; thus, it applies to the authorization of right of way acquisition for all state highways.

510.05(2) Exceptions

Exceptions can be made to the requirements in Exhibit 510-1 if unusual hardships result for the individual or the state. The approval of right of way hardship action will be based on the individual parcel merit and is processed in accordance with hardship acquisition policy (see the *Right of Way Manual*).

510.06 Transactions

510.06(1) Private Ownerships

Right of way is ordinarily acquired from private property owners by region-level negotiation between the owner and the right of way agent.

510.06(2) Utilities

The region determines the ownership of all utilities and makes arrangements for necessary adjustment, including relocation of portions of the utility, if necessary. Provisions for relocation or adjustment are included in the Plans, Specifications, and Estimates (PS&E) when:

- The items are normal construction items and the department is obligated for the moving expense.
- The utility requests that relocation be performed by the department and the department has approved the request.

Readjustment may require WSDOT to purchase substitute rights of way or easements for eventual transfer to the utility. Such rights of way or easements must be shown on the right of way plans with the same engineering detail as highway right of way. On limited access highways, if an approach is required for maintenance of a utility, the approach will be shown on the approach schedule. (See the *Utilities Accommodation Policy* regarding location of and access to utilities.)

Negotiations with the utilities are often done by HQ Real Estate Services. Because of the considerable time required to obtain approvals, processing of utility relocation agreements must begin as soon as possible.

510.06(3) Railways

Right of way is generally not acquired in fee from a railroad company. Instead, the state acquires a perpetual easement for encroachment or crossing. A construction and maintenance agreement may also be required. The easement must be shown on the right of way plan and identified by both highway and railroad stationing.

The HQ Design Office coordinates with the railroad design staff to determine a mutually agreeable location before the proposed easement is sent to Real Estate Services. The negotiations with the railroads are generally done by HQ Real Estate Services. Because of the considerable time required to obtain approvals, processing of railroad agreements must begin as soon as possible.

The perpetual easement document is executed by the Real Estate Services Director.

510.06(4) Federal Agencies

Acquisition of right of way from most federal agencies must be negotiated and processed through several federal offices. Allow at least one year for efficient and economical right of way acquisition. Depending upon the particular federal agency involved, special exhibit maps and other documentation may be required, and the right of way may be acquired as an easement rather than in fee. The negotiations with the federal agencies are generally done by HQ Real Estate Services.

510.06(5) Other State Agencies

Acquisition from other state agencies must be negotiated and processed through the individual agencies or designees. Negotiations with other state agencies are generally handled by HQ Real Estate Services. As in the case of federal agencies, substantial time must be allowed for compliance with applicable statutes and regulations peculiar to the agency before right of way will be granted.

510.06(6) Condemnations

Condemnation can result from a disagreement between the department and the owner regarding a fair settlement or a faulty title. Since several months might elapse between the filing of a condemnation case and a court decision, the region Real Estate Services Office can be requested to investigate the possibility of obtaining a negotiated possession and use agreement as in the case of an emergency project or when a sundry site is required immediately.

510.07 Documentation

Refer to Chapter 300 for design documentation requirements.

510.08 References

510.08(1) Federal/State Laws and Codes

23 Code of Federal Regulations (CFR) Part 710

49 CFR Part 24, Uniform Relocation Assistance and Real Property Acquisition for Federal and Federally Assisted Programs

Revised Code of Washington (RCW) 8.26, Relocation assistance – Real property acquisition policy

Washington Administrative Code (WAC) 468-100, Uniform relocation assistance and real property acquisition

510.08(2) Design Guidance

Agreements Manual, M 22-99, WSDOT

Plans Preparation Manual, M 22-31, WSDOT

Right of Way Manual, M 26-01, WSDOT

Utilities Manual, M 22-87, WSDOT

Exhibit 510-1 Appraisal and Acquisition

Plan Approval	Plan Approval	Programming of Funds for Appraisal and Acquisition
Limited Access Highways		
PHASE 1 Access Report Plan	Director & State Design Engineer, Development Division,* approves access report plan for prehearing discussion with county and city officials. The access report plan may be used for preparation of federal-aid program data for appraisals if federal funds are to be used for right of way acquisition. It may be used for requesting advance appraisal funds through the Planning and Capital Program Management for all projects with either state or federal funds.	Program appraisals of total takes. (No acquisition.)
PHASE 2 Access Hearing Plan	Director & State Design Engineer, Development Division,* approves access hearing plan for use at a public access hearing. R/W information is complete. The access hearing plan may be used for the preparation of federal-aid program data for negotiations on federally funded projects and for the preparation of true cost estimates and fund requests.	Program all appraisals and acquisitions. **Note:** Do not appraise or purchase partial takes in areas subject to controversy. Appraise or purchase total takes only if federal design hearing requirements are met.
PHASE 3 Findings and Order Plan	No signature required. Results of findings and order access hearing are marked in red and green on access hearing plan and sent to HQ R/W Plans Section.	Program appraisals of partial takes where data is available to appraisers. Acquisition of total takes.
PHASE 4 Final R/W and L/A Plan	Director & State Design Engineer, Development Division,* approves final R/W and L/A plans or approves revisions to established R/W and L/A plans.	Program all remaining appraisals and all remaining acquisitions. **Note:** If appeal period is not complete, delay action in areas subject to controversy and possible appeal.
Managed Access Highways		
PHASE 5 Final R/W Plan	R/W plan submitted to HQ R/W Plans Section for approval.	Program appraisals.
	Director & State Design Engineer, Development Division,* approves new R/W plans or approves revisions to established R/W plans.	Program all appraisals and acquisitions.

*Or a designee.

Chapter 520 Access Control

520.01 General
520.02 References
520.03 Definitions
520.04 Vocabulary

520.01 General

The Washington State Department of Transportation (WSDOT) controls access to the state's highways (with a few exceptions) in order to preserve the safety and efficiency of these highways as well as the public investment. All Washington State highways are distinguished as being either *limited access* or *managed access* highways. Control of access is accomplished by either acquiring rights of access from abutting property owners (limited access control) or by regulating access connections to the highway (managed access control). Until limited access rights have been acquired from abutting property owners, the route is a managed access highway. Managed access permits are issued either by a local authority (city or town) or by WSDOT.

Numerous studies have shown that controlling and limiting access to highways is a cost-effective way to help maintain the safety, capacity, and functional integrity of a highway. Adding more lanes to an existing highway is expensive and frequently not possible. Controlling access to our state highways by promoting the use of frontage roads or other existing county or city roads, and advocating the internal shared circulation within adjacent developments, is a proactive and cost-effective way to accomplish this objective.

WSDOT has been purchasing access rights and implementing limited access control since 1951 (RCW 47.52). While this has been effective, it is an expensive way to control access to the state highway system. Adequate funding to accomplish the purchasing of access rights has not kept up with the state's continual population growth and land use development over the years. As a result, state lawmakers introduced a bill in the early 1990s recognizing that controlling access to the state highway system by regulation was a cost-effective means to preserve the safety and capacity of our state highway system.

In 1991, the Legislature passed and the Governor approved RCW 47.50, titled "Highway access management." This new law directed WSDOT to develop new rules to be included in the Washington Administrative Code for those state highways not already limited access highways. The result was a new class of access control called *managed access*.

Chapter 530 describes limited access highways in greater detail. Chapter 540 describes managed access highways in greater detail.

The following references and definitions apply to Washington's access control as presented in Chapters 530 and 540.

520.02 References

520.02(1) Federal/State Laws and Codes

Revised Code of Washington (RCW) 18.43, Engineers and land surveyors

RCW 35.78, Streets – Classification and design standards

RCW 46.61, Rules of the road

RCW 47.17, State highway routes

RCW 47.24, City streets as part of state highways

RCW 47.32, Obstructions on right-of-way

RCW 47.50, Highway access management

RCW 47.52, Limited access facilities

Washington Administrative Code (WAC) 468-51, Highway access management access permits – Administrative process

WAC 468-52, Highway access management – Access control classification system and standards

WAC 468-54, Limited access hearings

WAC 468-58, Limited access highways

520.02(2) Design Guidance

Agreements Manual, M 22-99, WSDOT

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on Uniform Traffic Control Devices for Streets and Highways" (MUTCD)

Plans Preparation Manual, M 22-31, WSDOT

Right of Way Manual, M 26-01, WSDOT

Utilities Accommodation Policy, M 22-86, WSDOT

WSDOT Headquarters (HQ) Access and Hearings Section's Internet page:
www.wsdot.wa.gov/design/accessandhearings

520.02(3) Supporting Information

Access Management Manual, Transportation Research Board (TRB), Washington DC, 2003

Highways Over National Forest Lands, MOU between WSDOT and USFS, M 22-50, 2002:
www.wsdot.wa.gov/publications/manuals/m22-50.htm

520.03 Definitions

access A means of entering or leaving a public road, street, or highway with respect to abutting property or another public road, street, or highway.

access control The limiting and regulating of public and private access to Washington State's highways, as required by state law.

Access Control Tracking System Limited Access and Managed Access Master Plan A database list, related to highway route numbers and mileposts, that identifies either the level of limited access or the class of managed access: www.wsdot.wa.gov/design/accessandhearings

access connection See ***approach and access connection***.

access connection permit A written authorization issued by the permitting authority for a specifically designed access connection to a managed access highway at a specific location; for a specific type and intensity of property use; and for a specific volume of traffic for the access connection based on the final stage of the development of the applicant's property. The actual form used for this authorization is determined by the permitting authority.

access design analysis A design analysis (see Chapter 300) that authorizes deferring or staging acquisition of limited access control, falling short of a 300-foot requirement, or allowing an existing access point to stay within 130 feet of an intersection on a limited access highway. Approval by the Director & State Design Engineer, Development Division, is required (see Chapter 530).

access hearing plan A limited access plan prepared for presentation at an access hearing.

access point Any point that allows private or public entrance to or exit from the traveled way of a state highway, including "locked gate" access and maintenance access points.

access point spacing On a managed access highway, the distance between two adjacent access points on one side of the highway, measured along the edge of the traveled way from one access point to the next (see also ***corner clearance***).

access report plan A limited access plan prepared for presentation to local governmental officials at preliminary meetings before preparation of the access hearing plan.

access rights Property rights that allow an abutting property owner to enter and leave the public roadway system.

allowed Authorized.

application for an access connection An application provided by the permitting authority to be completed by the applicant for access to a managed access highway.

approach and access connection These terms are listed under the specific access section to which they apply. The first section below is for limited access highways and uses the term *approach*. The second section below is for managed access highways and uses the term *access connection*. Approaches and access connections include any ability to leave or enter a highway right of way other than at an intersection with another road or street.

(a) ***limited access highways: approach*** An access point, other than a public road/street, that allows access to or from a limited access highway on the state highway system. There are five types of approaches to limited access highways that are allowed:

- ***Type A*** An off and on approach in a legal manner, not to exceed 30 feet in width, for the sole purpose of serving a single-family residence. It may be reserved by the abutting owner for specified use at a point satisfactory to the state at or between designated highway stations. This approach type is allowed on partial and modified control limited access highways.

- ***Type B*** An off and on approach in a legal manner, not to exceed 50 feet in width, for use necessary to the normal operation of a farm, but not for retail marketing. It may be reserved by the abutting owner for specified use at a point satisfactory to the state at or between designated highway stations. This approach type is allowed on partial and modified control limited access highways. This approach type may be used for wind farms when use of the approach is limited to those vehicles necessary to construct and maintain the farm for use in harvesting wind energy.
- ***Type C*** An off and on approach in a legal manner, for a special purpose and width to be agreed upon. It may be specified at a point satisfactory to the state at or between designated highway stations. This approach type is allowed on partial and modified control limited access highways and on full control limited access highways where no other reasonable means of access exists, as solely determined by the department.
- ***Type D*** An off and on approach in a legal manner, not to exceed 50 feet in width, for use necessary to the normal operation of a commercial establishment. It may be specified at a point satisfactory to the state at or between designated highway stations. This approach type is allowed only on modified control limited access highways.
- ***Type E*** This type is no longer allowed to be constructed because of the requirements that there be only one access point per parcel on a limited access state highway.
- ***Type F*** An off and on approach in a legal manner, not to exceed 30 feet in width, for the sole purpose of serving a wireless communication site. It may be specified at a point satisfactory to the state at or between designated highway stations. This approach type is allowed only on partial control limited access highways. (See WAC 468-58-080(vi) for further restrictions.)

(b) ***managed access highways: access connection*** An access point, other than a public road/ street, that permits access to or from a managed access highway on the state highway system. There are five types of access connection permits:

- ***conforming access connection*** A connection to a managed access highway that meets current WAC and WSDOT location, spacing, and design criteria.
- ***grandfathered access connection*** Any connection to the state highway system that was in existence and in active use on July 1, 1990, and has not had a significant change in use.
- ***joint-use access connection*** A single connection to a managed access highway that serves two or more properties.
- ***nonconforming access connection*** A connection to a managed access highway that does not meet current WSDOT location, spacing, or design criteria, pending availability of a future conforming access connection.
- ***variance access connection*** A connection to a managed access highway at a location not normally allowed by current WSDOT criteria.

(c) ***managed access connection category*** There are four access connection permit categories for managed access connections to state highways: Category I, Category II, Category III, and Category IV (see Chapter 540).

annual daily traffic (ADT) The volume of traffic passing a point or segment of a highway, in both directions, during a period of time, divided by the number of days in the period, and factored to represent an estimate of traffic volume for an average day of the year.

average annual daily traffic (AADT) The average volume of traffic passing a point or segment of a highway, in both directions, during a year.

average weekday vehicle trip ends (AWDVTE) The estimated total of all trips entering plus all trips leaving the applicant's site based on the final stage of proposed development.

connection See ***approach and access connection***.

contiguous parcels Two or more pieces of real property, under the same ownership, with one or more boundaries that touch and have similarity of use.

corner clearance On a managed access highway, the distance from an intersection of a public road or street to the nearest access connection along the same side of the highway. The minimum corner clearance distance (see Chapter 540, Exhibit 540-2) is measured from the closest edge of the intersecting road or street to the closest edge of the traveled way of the access connection, measured along one side of the traveled way (through lanes) (see also ***access point spacing***).

DHV Design hourly volume.

E&EP WSDOT's Environmental and Engineering Programs Division.

easement A documented right, as a right of way, to use the property of another for designated purposes.

findings and order (F&O) A legal package containing information based on the hearing record from a limited access hearing (see Chapters 210 and 530).

findings and order (F&O) plan A limited access plan, prepared after a limited access hearing, which is based on the hearing record.

HQ WSDOT's Headquarters in Olympia.

intersection An at-grade access point connecting a state highway with a road or street duly established as a public road or public street by the local governmental entity.

limited access Full, partial, or modified access control is planned and established for each corridor and then acquired as the right to limit access to each individual parcel.

- ***planned limited access control*** Limited access control is planned for some time in the future; however, no access hearing has been held.
- ***established limited access control*** An access hearing has been held and the Assistant Secretary, Environmental and Engineering & Regional Operations Programs Director, has adopted the findings and order, which *establishes* the limits and level of control.
- ***acquired limited access control*** Access rights have been purchased.

limited access highway All highways listed as "Established L/A" on the Limited Access and Managed Access Master Plan (see below) and where the rights of direct access to or from abutting lands have been acquired from the abutting landowners.

- ***full access control*** This most restrictive level of limited access provides access, using interchanges, for selected public roads/streets only, and prohibits highway intersections at grade.
- ***partial access control*** The second most restrictive level of limited access. At grade intersections with selected public roads are allowed, and there may be some crossings and some driveway approaches at grade. Direct commercial access is not allowed.
- ***modified access control*** The least restrictive level of limited access. Characteristics are the same as for partial access control except that direct commercial access is allowed.

Limited Access and Managed Access Master Plan A map of Washington State that shows established and planned limited access highways:
www.wsdot.wa.gov/design/accessandhearings

managed access highway Any highway not listed as "Established L/A" on the Limited Access and Managed Access Master Plan and any highway or portion of a highway designated on the plan as "Established L/A" until such time as the limited access rights are acquired. Under managed access legislation, the property owner's access rights are regulated through an access connection permitting process.

median The portion of a divided highway separating vehicular traffic traveling in opposite directions.

median opening An opening in a continuous median for the specific purpose of allowing vehicle movement.

MOU Memorandum of Understanding. There is one MOU (*Highways Over National Forest Lands*) between the United States Forest Service (USFS) and WSDOT that requires the USFS to obtain a road approach permit for new access to a state highway that is crossing Forest Service land.

permit holder The abutting property owner or other legally authorized person to whom an access connection permit is issued by the permitting authority.

permitted access connection A connection for which an access connection permit has been issued by a permitting authority.

permitting authority The agency that has legal authority to issue managed access connection permits. For access connections in unincorporated areas, the permitting authority is WSDOT; for access connections within corporate limits, the permitting authority is a city or town.

right of way (R/W) A general term denoting land or interest therein, acquired for or designated for transportation purposes. More specifically, lands that have been dedicated for public transportation purposes or land in which WSDOT, a county, or a municipality owns the fee simple title, has an easement devoted to or required for use as a public road/street and appurtenant facilities, or has established ownership by prescriptive right.

right of way and limited access plan (R/W and L/A plan) A right of way plan that also shows limited access control details.

road approach A road or driveway built to provide private access to or from the state highway system.

shoulder The portion of the highway contiguous with the traveled lanes for the accommodation of stopped vehicles for emergency use and, where allowed, for bicycles (see Chapter 530).

state highway system All roads, streets, and highways designated as state routes in compliance with RCW 47.17.

520.04 Vocabulary

The entries shown in Exhibit 520-1 are examples of suitable wording for the distinctly different types of access control in Chapters 530 and 540.

These entries demonstrate the difference in terminology between limited access and managed access in the applicable WACs. For instance, there is nothing about *permit, connection, category,* or *class* in the limited access vocabulary and, likewise, nothing about *approach* or *type* in the managed access vocabulary.

Also note that Chapter 1340 uses *road approach, access, and driveway* in a generic way, unrelated to WAC legal terminology, and makes no distinction related to access control.

Exhibit 520-1 Access Control Vocabulary

Access Control Vocabulary	
intersections at grade, geometrics roundabout geometrics road approach geometrics interchange geometrics freeway access point functional classification of highways	Chapter 1310 Chapter 1320 Chapter 1340 Chapter 1360 Chapter 550 WSDOT Functional Classification web site: http://www.wsdot.wa.gov/mapsdata/travel/hpms/functionalclass.htm
Limited Access Highway (Chapter 530)	**Managed Access Highway (Chapter 540)**
Access point (freeway ramp or other access break) Approach (street, road, driveway) • Road approach (street, road, driveway) • Driveway approach (not street or road)	Access point (public or not) • Public access point • Access connection (not public)
(Level of) limited access (highway) • Full/partial/modified control limited access highway	Managed access highway class • Class (1-5) managed access highway
Type (A, B, C, D, F) approach Type A approach = Type A road approach	Category (I-IV) access connection
Allowed (policy)	Permitted (a document) or allowed (policy)
	Conforming access connection permit (among others)
Terms Not Used in Chapter 530	**Terms Not Used in Chapter 540**
class	classification (except functional)
category	type
connection	approach
permit or permitted	

Chapter 530 Limited Access Control

530.01 General
530.02 Achieving Limited Access
530.03 Full Control (Most Restrictive)
530.04 Partial Control
530.05 Modified Control (Least Restrictive)
530.06 Access Approaches
530.07 Frontage Roads
530.08 Turnbacks
530.09 Adjacent Railroads
530.10 Changes to Existing Limited Access Rights of Way (including Access, Occupancy, and Use)
530.11 Documentation

530.01 General

Limited access control is established to preserve the safety and efficiency of specific highways and to preserve the public investment. Limited access control is achieved by acquiring access rights from abutting property owners and by selectively limiting approaches to a highway. (For an overview of access control and the references list and definitions of terminology for this chapter, see Chapter 520, Access Control.)

Requirements for the establishment of limited access highways are set forth in the Revised Code of Washington (RCW) 47.52. The type of access control applied to a location is considered a design control (see Chapter 1103), and is determined during planning, scoping, or the early stages of design in conformance with this chapter.

Highways controlled by acquiring abutting property owners' access rights are termed limited access highways and are further distinguished as having full, partial, or modified control. The number of access points per mile, the spacing of interchanges or intersections, and the location of frontage roads or local road/street approaches are determined by the:

- Functional classification and importance of the highway
- Character of the traffic
- Current and future land use
- Environment and aesthetics
- Highway design and operation
- Economic considerations involved

The Federal Highway Administration (FHWA) has jurisdiction on the Interstate System. The Washington State Department of Transportation (WSDOT) has full jurisdiction on all other limited access highways, whether they are inside or outside incorporated city limits.

WSDOT maintains a record of the status of limited access control, by state route number and milepost, in the Access Control Tracking System Limited Access and Managed Access Master Plan database (Access Master Plan).

Nothing in this chapter is to be construed in any way that would prevent acquisition of short sections of full, partial, or modified control of access.

530.02 Achieving Limited Access

530.02(1) Evaluation

The benefits of maintaining or acquiring full, partial, or modified control is to be evaluated during project development if the route is shown in the Access Control Tracking System Limited Access and Managed Access Master Plan database as either "established" or "planned" for limited access. It is generally known that full limited access control applies to interstates and freeways. However, state highways that do not fall under full access control may have more flexibility in the type of control applied (whether limited or managed control). These highways can benefit by having access control evaluations conducted early in project development.

The cost of acquiring limited access is evaluated to determine whether those costs will be included in the project. The evaluation includes the societal costs of crashes, current and future land use development, and the improved level of service of limited access highways. Use the Basis of Design documentation tool to summarize key results of the evaluation process. (See chapters in the 1100 series for more information on using the Basis of Design tool.)

530.02(2) Process

All Washington State highways are managed access highways (see Chapter 540), except where limited access rights have been acquired. The right of way and limited access plans for routes show the acquired limited access boundaries. This is further represented in the Access Control Tracking System, a database that identifies the status and type of access control for all state highways. The database lists the specific types of limited access control (full, partial, or modified) and identifies whether the control is planned, established, or acquired for a specific route segment. If limited access has not been acquired, the database reports the type of managed access classification that currently applies.

The existing access classification is periodically updated to reflect changes on a corridor segment. The planned limited access reflects the vision for access on a corridor by resolution from the Washington Transportation Commission in the 1960s and 1970s. Conditions may have changed since the plan for limited access was envisioned. It is important to re-evaluate this plan and determine the access design control most appropriate for the agreed context. (See Chapters 1102 and 1103 for context and design control guidance, respectively.) For help determining the status of limited access control for any state highway, consult the Headquarters (HQ) Access and Hearings Section.

The Access Master Plan database is available at:
www.wsdot.wa.gov/design/accessandhearings

530.02(2)(a) Procedure for Limited Access Control

Use the following procedure to achieve limited access control:

1. The Secretary of Transportation (or a designee) first identifies a highway as "Planned for Limited Access."
2. To establish or revise limited access on a new or existing highway, a limited access hearing is held. (See Chapter 210, Public Involvement and Hearings, regarding hearings, and Chapter 510, Right of Way, for the phases of appraisal and acquisition.)

a. Phase 1

The region develops a limited access report and a limited access report plan for department approval and presentation to local officials. The plan notes the level of limited access proposed to be established.

b. Phase 2

The region develops a limited access hearing plan for Director & State Design Engineer, Development Division (or designee), approval and for presentation at the hearing.

c. Phase 3

After the hearing, the region develops the findings and order and revises the limited access hearing plan to become the findings and order plan (see Chapter 210). The findings and order is processed and sent to the HQ Access and Hearings Section for review and approval. The Assistant Secretary, Engineering & Regional Operations, adopts the findings and order and thus establishes the limits and level of limited access control to be acquired.

d. Phase 4

The findings and order plan is now revised by the HQ Right of Way Plans Section for approval by the Director & State Design Engineer, Development Division (or designee), as a Phase 4 final right of way and limited access plan.

3. Real Estate Services acquires limited access rights from individual property owners based on final design decisions and updates the right of way and limited access plans and the property deed.
4. These highways or portions thereof are now limited access highways and no longer fall under the managed access program.

530.02(3) Access Report (RCW 47.52.131)

The Access Report is developed by the region to legally inform local governmental officials of the proposed limited access highway and the principal access features involved, and to secure their approval. This report is not furnished to abutting property owners. Submit the report to the HQ Access and Hearings Section for review and approval prior to submission to local authorities. Including local agencies as stakeholders from the onset of the project helps establish project expectations and positive working relationships, making reviews and approvals run as smoothly as possible.

530.02(3)(a) Access Report Content

The Access Report consists of the following:

1. A description of the existing and proposed highways, including data on the history of the existing highway, which may include references to crashes and locations identified in WSDOT's Priority Array.
2. Traffic analyses pertaining to the proposed highway, including available information about current and potential future traffic volumes on county roads and city streets crossing or severed by the proposed highway and reference sources such as origin-destination surveys.

Traffic data developed for the Design Decision Summary, together with counts of existing traffic available from state or local records, is normally adequate. Special counts of existing traffic are obtained only if circumstances indicate that the available data is inadequate or outdated.

3. A discussion of factors affecting the design of the subject highway, including:
   - Functional classification
     www.wsdot.wa.gov/mapsdata/travel/hpms/functionalclass.htm
   - Level and limits of limited access control.
   - Roadway section.
   - Interchange, grade separation, and intersection spacing.
   - Pedestrian and bicycle trails or paths.
   - Operational controls with emphasis on proposed fencing, the general concept of illumination, signing, and other traffic control devices.
   - Location of utilities and how they are affected.
   - Proposed plan for landscaping and beautification, including an artist's graphic rendition or design visualization.
4. Governmental responsibility, and comprehensive planning, land use, and community service relative to the new highway.
5. The disposition of frontage roads, city street and county road intersections, and excess right of way.
6. An appendix containing:
   - A glossary of engineering terms.
   - A traffic volume diagram(s).
   - Pages showing diagrammatically or graphically the roadway section(s), operational controls, and rest areas (if rest areas are included in the project covered by the report).
   - A vicinity map.
   - An access report plan and profiles for the project.

   The limited access report plan shows the effects of the proposed highway on the street and road system by delineating the points of public access. (See the *Plans Preparation Manual* for a list of the minimum details to be shown on the plan and for a sample plan.)
7. Notifications and reviews. Upon receipt of the Phase 1 approval (see Exhibit 510-1) from the Director & State Design Engineer, Development Division, the region publishes the necessary copies, submits the limited access report to the county or city officials for review and approval, and meets with all involved local governmental agencies to discuss the report. Providing a form letter with a signature block for the local agency to use to indicate its approval of the limited access report can help expedite the review and approval process.

   The region reviews any requests for modification and submits recommendations, with copies of any correspondence or related minutes, to the HQ Access and Hearings Section.

530.02(4) Limited Access Hearing Plan

The region prepares a limited access hearing plan to be used as an exhibit at the public hearing (see Chapter 210 for hearings) and forwards it to the HQ Right of Way Plans Section for review.

(See the *Plans Preparation Manual* for a list of data to be shown on the access hearing plan in addition to the access report plan data.)

When the plan review is completed by Headquarters, the access hearing plan is placed before the Director & State Design Engineer, Development Division, for approval of Phase 2 authority (see Exhibit 510-1).

530.02(5) Documentation

Documentation for the establishment of limited access control is in Chapter 210.

530.03 Full Control (Most Restrictive)

530.03(1) Introduction

Full control limited access highways provide almost complete freedom from disruption by allowing access only through interchanges at selected public roads/streets, rest areas, viewpoints, or weigh stations, and by prohibiting at-grade crossings and approaches. Gated approaches are occasionally allowed, with approval of the requirements listed in Chapter 550 and Exhibits 550-1 and 2.

At times, on state highways (except interstate) where full access control has been established, staged acquisition of limited access may be used, subject to the approval of an access design analysis, with initial acquisition as partial or modified control and with ultimate acquisition of full control planned on the highway. When there is no feasible alternative within a reasonable cost, the decision to defer acquisition of limited access control must be documented and is subject to the approval of an access design analysis.

530.03(2) Application

Terminate full control limited access sections at apparent logical points of design change. The following guidelines are to be used for the application of full control on limited access highways.

530.03(2)(a) Interstate

Full control is required on interstate highways.

530.03(2)(b) Principal Arterial

Documentation assessing the evaluation of full control is required for principal arterial highways requiring four or more through traffic lanes within a 20-year design period unless approved for partial or modified control on existing highways.

530.03(2)(c) Minor Arterial and Collector

Minor arterial and collector highways will not normally be considered for development to full control.

530.03(3) Crossroads at Interchange Ramps

The extension of limited access control beyond an intersection is measured from the centerline of ramps, crossroads, or parallel roads (as shown in Exhibits 530-1a, 1b, and 1c), from the terminus of transition tapers (see Exhibit 530-1d), and in the case of ramp terminals at single

point urban interchanges (as shown in Exhibit 530-1e). For guidance on interchange spacing, see Chapter 1360.

530.03(3)(a) Ramps

At-grade intersections and approaches are prohibited within the full length of any interchange ramp. The ramp is considered to terminate at its intersection with the local road or street.

530.03(3)(b) Frontage Roads

Direct access from the highway to a local service or frontage road is allowed only via the interchange crossroad (see Exhibits 530-1a, 1b, and 1c).

530.03(3)(c) Interchange Crossroads

In both urban and rural areas, full control limited access must be established and then acquired along the crossroad at an interchange for a minimum distance of 300 feet beyond the centerline of the ramp or the end of the transition taper.

If a frontage road or local road is located at or within 350 feet of a ramp, limited access will be established and then acquired along the crossroad and for an additional minimum distance of 130 feet in all directions from the centerline of the intersection of the crossroad and the frontage or local road (see Exhibits 530-1a, 1b, and 1c).

For interchanges incorporating partial cloverleaf or buttonhook ramps (see Exhibit 530-1b), limited access is required for all portions of the crossroad and frontage roads between the ramp terminals and for a distance of 300 feet beyond the ramp terminals. If an at-grade intersection for a local road or street is served directly opposite the ramp terminals, limited access will be extended for a minimum of 300 feet along that leg of the intersection.

When the intersection in question is a roundabout, see Exhibit 530-1c. This shows extension of full control to be 300 feet, measured from the center of the roundabout for an intersection with a ramp terminal. Exhibit 530-1c also shows that if a frontage road or local road is located at or within 350 feet of a ramp terminal, limited access will be established and then acquired along the crossroad (between the roundabouts) and for an additional minimum distance of 130 feet in all directions along the local frontage roadway, measured from the outside edge of the circulating roadway of the roundabout.

Exhibit 530-1d shows the terminus of transition taper and that full control limited access is extended a minimum distance of 300 feet beyond the end of the farthest taper.

For a single point urban interchange (SPUI) with a right- or left-turn “ramp branch” separated by islands, limited access control is established and acquired for a minimum distance of 300 feet from the intersection of the centerline of the ramp branch with the centerline of the nearest directional roadway (see Exhibit 530-1e.)

Not all interchange configurations match with the basic illustrations in this chapter. Consult with the HQ Access and Hearings Section for confirmation of limited access boundary requirements for non-traditional interchange configurations.

530.03(3)(d) Levels of Limited Access: Location of Approaches

Provide full control for a minimum of 300 feet from the centerline of the ramp or terminus of a transition taper (see Exhibits 530-1a, 1b, 1c, 1d, and 1e). The intent is to ensure approaches are far enough away from a frontage road intersection to provide efficient intersection operation.

If the economic considerations to implement full control for the entire 300 feet are excessive, then provide full control for at least the first 130 feet; partial or modified control may be provided for the remainder, for a total minimum distance of 300 feet of limited access. Full limited access should be extended as far as possible before any partial or modified access is implemented. Contact the HQ Access and Hearings Section when considering this option.

An approved access design analysis is required if the limited access control falls short of 300 feet or for any approach that has been allowed to remain within the first 130 feet.

530.03(4) Location of Utilities, Bus Stops, and Mailboxes

530.03(4)(a) Utilities

Connecting utility lines are allowed along the outer right of way line between intermittent frontage roads. (See the *Utilities Accommodation Policy* regarding the location of and access to utilities.)

530.03(4)(b) Bus Stops

Common carrier or school bus stops are not allowed, except at:

- Railroad crossings (see Chapter 1350).
- Locations provided by the state on the interchanges (such as flyer stops).
- In exceptional cases, along the main roadway where pedestrian separation is available.

530.03(4)(c) Mailboxes

Mailboxes are not allowed on full control limited access highways. Mail delivery will be from frontage roads or other adjacent local roads.

530.03(5) Pedestrian and Bicycle Crossings and Paths

All nonmotorized traffic is limited as follows:

- At-grade pedestrian crossings are allowed only at the at-grade intersections of ramp terminals.
- Pedestrian separations or other facilities are provided specifically for pedestrian use.
- Bicyclists use facilities provided specifically for bicycle use (separated paths).
- Shared-use paths are only for bicyclists, pedestrians, and other forms of nonmotorized transportation.
- Bicyclists use the right-hand shoulders, except where such use has been specifically prohibited. Information pertaining to such prohibition is available from the WSDOT website: wsdot.wa.gov/bike/closed.htm

Paths and trails, and access to and from, within a limited access highway are best planned and designed with the local agency's participation. Pedestrians and bicycles are allowed, consistent with "Rules of the Road" (RCW 46.61), within the limits of full control limited access highways. Where paths are allowed they must be documented on the right of way and limited access plan. The plan shows the location of the path and where the path crosses limited access and provides movement notes (see 530.10(1)).

530.04 Partial Control

530.04(1) Introduction

Partial control may be established, when justified, on any highway except interstate. Partial control provides a considerable level of protection from traffic interference and protects the highway from future strip-type development.

Upon acquisition of partial control limited access rights, the number, type, and use of access approaches of abutting property are frozen. The abutting property access rights and type of use are recorded on the property deed. The rights and use may not be altered by the abutting property owner, the local jurisdiction, or the region. This authority resides with the Director & State Design Engineer, Development Division (see 530.10).

530.04(2) Application

Partial control will not normally be used in urban areas or inside corporate limits on existing principal arterial highways where traffic volumes are less than 700 design hourly volume (DHV).

Terminate limited access sections at apparent logical points of design change.

530.04(2)(a) Principal Arterial

Partial control is required when the estimated traffic volumes exceed 3,000 average daily traffic (ADT) within a 20-year design period on principal arterial highways requiring two through traffic lanes. For multilane principal arterial highways, see 530.03(2)(b).

530.04(2)(b) Minor Arterial

The minimum route length is: urban, 2 miles; rural, 5 miles; and combination urban and rural, 3 miles.

Partial control is required on:

- Rural minor arterial highways at both new and existing locations.
- Urban minor arterial highways at new locations requiring four or more through traffic lanes within a 20-year design period or requiring only two through traffic lanes where the estimated traffic volumes exceed 3,000 ADT within a 20-year design period.

Other rural minor arterial highways with only two lanes may be considered for partial control if any of the following conditions applies:

- The partial control can be acquired at a reasonable cost.
- The route connects two highways of a higher functional classification.

- The potential land development can result in numerous individual approaches, such as encountered in recreational or rapidly developing areas.
- The highway traverses publicly owned lands where partial control is desirable.

530.04(2)(c) Collector: New Alignment

Partial control is required on collector highways in new locations requiring four or more through traffic lanes in a 20-year design period.

530.04(2)(d) Collector: Existing

Existing collector highways will normally be considered for partial control limited access only when all of the following conditions apply:

- The highway serves an area that is not directly served by a higher functional classification of highway.
- Existing or planned development will result in traffic volumes significantly higher than what is required for partial control on minor arterials.
- Partial control can be established without a major impact on development of abutting properties within the constraints of established zoning at the time the partial control is proposed.

530.04(3) Interchanges and Intersections

530.04(3)(a) Interchanges

Where an interchange occurs on a partial control limited access highway, full control applies at the interchange and interchange ramps. Refer to 530.03(3) and see Exhibits 530-1a, 1b, and 1c for required minimum lengths of access control along the crossroad. For these and other interchange configurations not shown, consult with the HQ Access and Hearings Section for support developing limits of access control. (See Chapter 1360 for guidance on interchange spacing.)

530.04(3)(b) Intersections

At an at-grade intersection on a partial control limited access highway, control will be established and acquired along the crossroad for a minimum distance of 300 feet from the centerline of the highway (see Exhibit 530-2a).

If another frontage or local road is located at or within 350 feet of the at-grade intersection, limited access will be established and then acquired along the crossroad, between the intersections, and:

- For an additional minimum distance of 130 feet in all directions from the centerline of the intersection of the frontage or local road (see Exhibit 530-2a).
- In the case of a roundabout, for an additional minimum distance of 300 feet along the crossroad, measured from the center of the roundabout (as shown in Exhibit 530-2b).

On multilane highways, measurements will be made from the centerline of the nearest directional roadway (see Exhibit 530-2a).

An approved access design analysis is required if the limited access control falls short of 300 feet or for any access that has been allowed to remain within the first 130 feet.

At-grade intersections with public roads are limited to the number allowed for the functional classification of highway involved, as follows:

530.04(3)(b)(1) Principal Arterial

If the ADT of the crossroad is less than 2,000, 1-mile spacing (minimum), centerline to centerline. If over 2,000 ADT within 20 years, plan for grade separation.

530.04(3)(b)(2) Minor Arterial

If the ADT of the crossroad is less than 2,000, ½-mile spacing (minimum), centerline to centerline. If over 2,000 ADT within 20 years, plan for grade separation.

530.04(3)(b)(3) Collector

Road (or street) plus property approaches, not more than six per side per mile.

With approval from the Director & State Design Engineer, Development Division, shorter intervals may be used where topography or other conditions (such as parcel sizes in some cases) restrict the design. Where intersecting roads are spaced farther apart than one per mile, median crossings may be considered for U-turns, in accordance with Chapter 1310. Keep U-turns to a minimum, consistent with requirements for operation and maintenance of the highway.

To discourage movement in the wrong direction on multilane highways, locate private approaches 300 feet or more from an at-grade intersection. At a tee intersection, a private approach may be located directly opposite the intersection or a minimum of 300 feet away from the intersection. Ensure a private approach directly opposite a tee intersection cannot be mistaken for a continuation or part of the public traveled way.

530.04(4) Access Approach

Partial control is exercised to the level that, in addition to intersections with selected public roads, some crossings and private driveways may be allowed.

530.04(4)(a) Approach Types

Partial control limited access highways allow at-grade intersections with selected public roads and private approaches using Type A, B, C, and F approaches. (See Chapter 520 for the definitions of approach types.)

Type D, commercial approaches, are not allowed direct access to partial control limited access highways. Commercial access is allowed only by way of public roads.

The type of approach provided for each parcel is based on current and potential land use and on an evaluation. (See 530.05(4) for a list of evaluation criteria.)

530.04(4)(b) Design Considerations

The following considerations are used to determine the number and location of access approaches on partial control limited access highways.

1. Access approaches must be held to a minimum. The number is limited as follows:
   - Principal arterial: two per side per mile
   - Minor arterial: four per side per mile
   - Collector: six per side per mile, including at-grade intersections
2. Approaches in excess of the number listed above may be allowed as staged construction (until full buildout is complete) if approved by the Director & State Design Engineer, Development Division.
3. Approaches are not allowed for parcels that have reasonable access to other public roads unless a parcel has extensive highway frontage.
4. Relocate or close approaches in areas where sight limitations create undue hazards.
5. Allow only one approach for each parcel, except for very large ownerships, or where terrain features do not allow the property to be served by a single approach. This includes contiguous parcels under a single ownership.
6. Where possible, locate a single approach to serve two or more parcels.
7. The approved design is to provide for future development of frontage roads that will eliminate an excessive number of approaches.

530.04(5) Location of Utilities, Bus Stops, and Mailboxes

530.04(5)(a) Utilities

Connecting utility lines are allowed along the outer right of way line between intermittent frontage roads. (See the *Utilities Accommodation Policy* regarding the location of and access to utilities.)

530.04(5)(b) Bus Stops

Bus stops for both common carriers and school buses are not allowed on either two-lane or four-lane highways except:

- At railroad crossings (see Chapter 1350).
- At locations of intersections with necessary pullouts to be constructed by the state.
- Where shoulder widening has been provided for mail delivery service.
- For a designated school bus loading zone on or adjacent to the traveled lane, that has been approved by WSDOT.

Buses are not allowed to stop in the traveled lanes blocking at-grade intersections or private approaches to load or unload passengers.

School bus loading zones on partial control limited access highways must be posted with school bus loading zone signs, in accordance with the latest edition of the *Manual on Uniform Traffic Control Devices* (MUTCD).

530.04(5)(c) Mailboxes

Locate mailboxes on frontage roads or at intersections, with the following exceptions for properties that are served by Type A or B approaches:

- Locate mailboxes on a four-lane highway only on the side of the highway on which the deeded approach is provided.
- Locate mailboxes on a two-lane highway on the side of the highway that is on the right in the direction of the mail delivery.

Wherever mailboxes are allowed on a partial control limited access highway, provide mailbox turnouts to allow mail delivery vehicles to stop clear of the through traffic lanes.
(See Chapter 1600 for additional information concerning mailbox locations and turnouts.)

530.04(6) Pedestrian and Bicycle Crossings and Paths

Pedestrian crossings are allowed on partial control limited access highways when they are grade-separated.

At-grade pedestrian crossings are allowed:

- Only at intersections where an at-grade crossing is provided in accordance with Chapter 1510.
- On two-lane highways at mailbox locations.
- On two-lane highways not less than 100 feet from a school bus loading zone (pullout) adjacent to the traveled lane, if school district and WSDOT personnel determine that stopping in the traveled lane is hazardous.
- On two-lane highways where the school bus is stopped on the traveled lane to load or unload passengers and the required sign and signal lights are displayed.

On partial control limited access highways, pedestrian and bicycle traffic is allowed, consistent with "Rules of the Road" (RCW 46.61), except where unusual safety conditions support prohibition. Information pertaining to such prohibitions is available from the WSDOT website:
wsdot.wa.gov/bike/closed.htm

Paths and trails, and access to and from, within a partial control limited access highway are best planned and designed with the local agency's participation. Where paths are allowed, they must be documented on the right of way and limited access plan. The plan shows the location of the path and where the path crosses limited access, and it provides movement notes (see 530.10(1)).

530.05 Modified Control (Least Restrictive)

530.05(1) Introduction

Modified control is intended to prevent further deterioration in the safety and operational characteristics of existing highways by limiting the number and location of access points.

Upon acquisition of modified control limited access, the number, type, and use of access approaches of abutting property are frozen. The abutting property access rights and type of use are recorded on the property deed. The rights and use may not be altered by the abutting

property owner, the local jurisdiction, or the region. This authority resides with the Director & State Design Engineer, Development Division (see 530.10).

530.05(2) Application

In general, modified control is applied where some level of control is desired, but existing and potential commercial development precludes the implementation of full or partial control.

530.05(2)(a) Existing Highways

Modified control may be established and acquired on existing highways other than main line interstate. Priority is given to highway segments where one or more of the following conditions applies:

- Commercial development potential is high, but most of the adjoining property remains undeveloped.
- There is a reasonable expectation that the adjoining property will be redeveloped to a more intensive land use, resulting in greater traffic congestion.
- At interchange areas if full or partial access cannot be provided as described in 530.03(3)(d).

530.05(2)(b) Modified Control Evaluation

Selection of highways on which modified control may be applied is based on an evaluation that includes the following contextual factors:

- The current form of managed access control
- Traffic volumes
- Level of service, or other selected mobility performance metric
- Selected safety performance
- Functional class
- Route continuity
- Mix of residential and employment densities
- Operational considerations related to achieving the selected target speed
- Local land use planning
- Current and potential land use
- Predicted growth rate
- Economic analysis

530.05(2)(c) Exceptions

Where modified control is to be established, developed commercial areas may be excepted from control when all or most of the abutting property has been developed to the extent that few, if any, additional commercial approaches will be needed with full development of the area. Contact the HQ Access and Hearings Section when considering this option. If this exception is within the limits of access control, an approved access design analysis is required.

530.05(3) Intersections

At an intersection on a modified control limited access highway, access control will be established and acquired along the crossroad for a minimum distance of 130 feet:

- Measured from the centerline of a two-lane highway (see Exhibit 530-3b).
- Measured from the centerline of the nearest directional roadway of a four-lane highway (see Exhibit 530-3b).
- Measured from the outside edge of the circulating roadway of a roundabout (see Exhibit 530-3a).

Approaches are allowed within this area only when there is no reasonable alternative. An approved access design analysis is required for any access that has been allowed to remain within the first 130 feet.

530.05(4) Access Approach

The number and location of approaches on a highway with modified control must be carefully planned and monitored to provide a safe and efficient highway compatible with present and potential land use.

530.05(4)(a) Approach Types

Modified control limited access highways allow at-grade intersections with selected public roads and with private approaches using Type A, B, C, and D approaches. (See Chapter 520 for definitions of the approach types.)

The type of approach provided for each parcel is based on present and potential land use and an evaluation of the following criteria:

- Local comprehensive plans, zoning, and land use ordinances
- Property covenants and agreements
- City or county ordinances
- The highest and best use of the property
- The highest and best use of adjoining lands
- A change in use by merger of adjoining ownerships
- All other factors bearing upon proper land use of the parcel

530.05(4)(b) Design Considerations

The following items are used to determine the number and location of approaches:

1. Parcels that have access to another public road or street are not normally allowed direct access to the highway.
2. Relocate or close approaches located in areas where sight limitations create undue hazards.

3. Hold the number of access approaches to a minimum. Access approaches are limited to one approach for each parcel of land or where adjoining parcels are under one contiguous ownership.
4. Encourage joint use of access approaches where similar use of land and topography allows.
5. Additional approaches may be allowed for future development consistent with local zoning. Once limited access has been acquired, this will require a value determination process (see 530.10).

Close existing access approaches not meeting the above.

530.05(5) Location of Utilities, Bus Stops, and Mailboxes

530.05(5)(a) Utilities

Connecting utility lines are allowed along the outer right of way line between intermittent frontage roads. (See the *Utilities Accommodation Policy* regarding location of and access to utilities.)

530.05(5)(b) Bus Stops and Pedestrian Crossings

Bus stops and pedestrian crossings are allowed as follows:

- In rural areas, bus stops and pedestrian crossings are subject to the same restrictions as in 530.04(5) and (6).
- In urban areas, bus stops for both commercial carriers and school buses are allowed. (See Chapter 1430 for requirements.)

530.05(5)(c) Mailboxes

Locate mailboxes adjacent to or opposite all authorized approaches as follows:

- On a four-lane highway only on the side of the highway on which the deeded approach is provided.
- On a two-lane highway on the side of the highway that is on the right in the direction of the mail delivery.

Where mailboxes are allowed, a mailbox turnout is recommended to allow mail delivery vehicles to stop clear of the through traffic lanes. (See Chapter 1600 for additional information concerning mailbox locations and turnouts.)

530.05(6) Pedestrian and Bicycle Traffic and Paths

Pedestrians and bicyclists are allowed, consistent with "Rules of the Road" (RCW 46.61), on modified control limited access highways except where unusual safety considerations support prohibition. Information pertaining to such prohibitions is available from the WSDOT website: wsdot.wa.gov/bike/closed.htm

Paths and trails, and access to and from, within a modified control limited access highway are best planned and designed with the local agency's participation. Where paths are allowed, they must be documented in the right of way and limited access plan. The plan shows the location of the path and where the path crosses limited access, and it provides movement notes (see 530.10(1)).

530.06 Access Approaches

530.06(1) General

Access approaches may be allowed on limited access highways, consistent with the requirements outlined in 530.03, 530.04, and 530.05.

For additional information pertaining to approaches, refer to Chapters 1320 (roundabouts), 1340 (approach design templates), and 510 (right of way), and the *Plans Preparation Manual*.

The widths for the approach types are negotiated, and only the negotiated widths are shown on the right of way and limited access plan. (See Chapter 520 for definitions of the approach types.)

530.07 Frontage Roads

Local agency approval is required for any planned frontage roads, county roads, city streets, or cul-de-sacs. The local agency must also agree in writing to accept and maintain the new section as a county road or city street.

530.07(1) General

Frontage roads are provided in conjunction with limited access highways to:

- Limit access to the main line.
- Provide access to abutting land ownerships.
- Restore the continuity of the local street or roadway system.

Refer to Chapter 1210 for frontage road general policy and Chapter 300 for required documentation.

By agreement under which the state is reimbursed for all costs involved, frontage roads that are not the responsibility of the state may be built by the state upon the request of a local political subdivision, a private agency, or an individual.

530.07(2) County Road and City Street

To connect roads or streets that have been closed off by the highway, short sections of county roads or city streets that are not adjacent to the highway may be constructed if they will serve the same purpose as, and cost less than, a frontage road.

530.07(3) Cul-de-sacs

For a frontage road or local street bearing substantial traffic that is terminated or closed at one end, provide a cul-de-sac or other street or roadway consistent with local policy or practice, that is sufficient to allow vehicles to turn around without encroachment on private property.

530.08 Turnbacks

When WSDOT transfers jurisdiction of operating right of way to a city, town, or county, a turnback agreement is required. (See the *Agreements Manual* for turnback procedures.)

Locate the turnback limits at points of logical termination. This will allow WSDOT to retain an adequate amount of right of way for maintenance of the highway and for other operational functions.

In areas where limited access rights have been acquired from the abutting property owners, the limited access rights will continue to be required for highway purposes; therefore, the limited access rights will not be included as part of a turnback agreement.

When a signalized intersection is in the area of a turnback, locate the turnback limit outside the detector loops if WSDOT is continuing the ownership, operation, and maintenance of the signal system. For a roundabout, locate the turnback limit at the back of the raised approach splitter island if WSDOT is continuing the ownership, operation, and maintenance of the roundabout.

530.09 Adjacent Railroads

530.09(1) General

A limited access highway and a railroad are considered adjacent when they have a common right of way border with no other property separating them. The allowed approaches apply only to adjacent railroad property that is directly used for current railroad operation.

530.09(2) Requirements

It is in the public's interest to provide access to the railroad right of way, from limited access highways, for maintenance of the railroad and the utilities located on the railroad right of way where other access is not feasible. This applies to both new highways and to existing highways where limited access has been acquired.

Direct access is allowed where local roads are infrequent or there are few highway-railroad crossings from which trail-type access for maintenance purposes is feasible, and where unique topography or other unusual conditions lead to its use.

To provide direct approaches for access to railroad right of way, all of the following conditions must be met:

- A maximum of one approach is allowed for every 2 miles of highway.
- The approach must not adversely affect the design, construction, stability, traffic safety, or operation of the highway.
- Except where the railroad is located in the median area, the approach is to be accomplished in a legal manner by right turns only, to and from the roadway nearest the railroad. Median crossing is not allowed.
- The approach is secured by a locked gate under arrangements satisfactory to the department. (See the Definitions section in Chapter 520 for Approach Type C, and Chapter 550.)
- The parking of any vehicles or railroad equipment is prohibited within limited access highway right of way.
- A special emergency maintenance permit must be obtained for periods of intensive railroad maintenance.
- The approach must be closed if the railroad operation ceases.

- Approaches are limited to use by the railroad company unless specific provisions for other use are shown on the right of way and limited access plan and included in the right of way negotiations.

530.09(3) Restrictions

Direct access from the highway is considered unnecessary and is not allowed where:

- There are local roads adjacent to or crossing the railroad.
- A trail-type road can be provided by the railroad between crossroads.
- The limited access highway is paralleled by a frontage road adjacent to the railroad.
- No highway previously existed adjacent to the railroad.

530.10 Changes to Existing Limited Access Rights of Way (including Access, Occupancy, and Use)

This section addresses three topics:

- 530.10(1) applies to all changes to access, occupancy & use of limited access rights of way on full, partial and modified highways.
- 530.10(2) provides specific detail on changes for private approaches.
- 530.10(3) provides specific guidance on changes for public approaches.

530.10(1) General

Changes to limited access control on state highways can only be made by the application of current design requirements and with the approval of the Assistant Secretary, Engineering & Regional Operations (or designee), and FHWA (when appropriate).

This means changes to access, use and occupancy (either temporary or permanent) for all limited access state highways require procedures and approval prior to implementation of those changes. On interstate routes, 23 CFR 710.401 requires prior approval from FHWA before allowing any changes on the interstate system. On non-interstate limited access routes, WSDOT approves changes to access, use and occupancy.

Example changes to limited access control:

- Constructing new fence openings
- Closing existing fence openings
- Adding new roadway connections, like an at-grade intersection
- Adding shared-use paths or trails that cross into and out of the right of way
- Widening existing approaches
- Allowing cranes or other equipment to temporarily encroach into the interstate airspace
- Constructing a new interchange or rebuilding an existing interchange (See Chapter 550)

Any changes proposed on interstate limited access facilities must include environmental documentation in the request, as required by FHWA. Contact the HQ Access and Hearings Section for assistance.

Consider the following factors when evaluating a request for modification of a limited access highway:

- Existing level of control on the highway
- Functional classification and importance of the highway
- Percentage of truck traffic
- Highway operations
- Present or future land use
- Environment or aesthetics
- Economic considerations
- Safety considerations

The Region will work with the requesting party to compile and submit all access, use and occupancy documents to the HQ Access and Hearings Section. The request documents should provide adequate detail, including a specific need statement, for the intended access, occupancy or use. The request packet will become a part of the historical record for the state route.

For permanent access, use or occupancy approvals involving existing property rights, the right of way and limited access plan must be revised and deeds may need to be rewritten. Contact Region and/or HQ Real Estate Services for this effort.

Evaluate all revisions to limited access highways to determine if access hearings are required.

For requirements to be met for selected modifications to full control limited access highways such as the Interstate System and multilane state highways, see Chapter 550, Interchange Justification Report.

530.10(2) Changes for Private Access Approaches (Modified/Partial Control Only)

Private accesses are allowed within modified control and sometimes allowed within partial control (WAC 468-58-010).

530.10(2)(a) Requirements

Examples of access modifications requested by abutting property owners include additional road approaches, changes in the allowed use, or additional users of existing road approaches.

Plan revisions that provide for additional access to abutting properties after WSDOT has purchased the access rights are discouraged. However, these revisions may be considered if all of the following can be established:

- There are no other reasonable alternatives.
- The efficiency and safety of the highway will not be adversely impacted.
- The existing situation causes extreme hardship on the owner(s).
- The revision is consistent with the limited access highway requirements.

530.10(2)(b) Procedures

The region initiates a preliminary engineering review of the requested modification to or break in limited access. This preliminary review will be conducted with the HQ Access and Hearings

Section to determine whether conceptual approval can be granted for the request. If conceptual approval can be granted, then:

- The region initiates an engineering review of the requested modification.
- The region prepares and submits to the HQ Right of Way Plans Section a preliminary right of way and limited access plan revision, together with a recommendation for Headquarters approval. When federal-aid funds are involved in any phase of the project, the proposed modification will be sent to FHWA for review and approval.
- The recommendation will include an item-by-item analysis of the factors listed in 530.10(1) and 530.10(2)(a).

530.10(2)(c) Valuation Determination

Upon preliminary approval, region Real Estate Services prepares an appraisal for the value of the access change using a before and after appraisal.

- The appraisal follows the requirements set forth in the *Right of Way Manual*.
- The appraisal package is sent to HQ Real Estate Services for review and approval.
- If federal-aid funds were involved in purchasing access control, HQ Real Estate Services will send a copy of the appraisal package to FHWA for review and approval.

530.10(2)(d) Final Processing

- Region Real Estate Services informs the requester of the approved appraised value for the change.
- If the requester is still interested, the region prepares a "Surplus Disposal Package" for HQ Real Estate Services' review and approval.
- At the same time, the preliminary right of way and limited access plan revision previously transmitted is processed for approval.
- After the department collects the payment from the requester, the region issues a permit for the construction, if required.
- If an existing approach is being surrendered, region Real Estate Services obtains a conveyance from the property owner.
- HQ Real Estate Services prepares and processes a deed granting the change to the access rights.

530.10(3) Changes for Public At-Grade Intersections (Modified/Partial Control Only)

530.10(3)(a) Requirements

- Public at-grade intersections on partial or modified control limited access highways serve local arterials that form part of the local transportation network.
- Requests for new intersections on limited access highways must be made by or through the local governmental agency to WSDOT. The region will forward this request, including the data referenced in 530.10(1) and 530.10(2)(a) to the HQ Access and Hearings Section.

- WSDOT must comply with the hearing, or waiver, process as outlined in Chapter 210. The access acquisition and conveyance must be completed prior to beginning construction of the new intersection. The new intersection is to meet WSDOT design and spacing requirements.

530.10(3)(b) Procedures

- The region evaluates the request for modification and contacts the HQ Access and Hearings Section for conceptual approval.
- The region submits an intersection plan for approval (see Chapter 1310) and a right of way and limited access plan revision request (see the *Plans Preparation Manual*). This plan includes the limited access design requirements along the proposed public at-grade intersection.
- The Director & State Design Engineer, Development Division, approves the intersection plan.
- The Assistant Secretary, Engineering & Regional Operations (or designee), approves the access revision.
- The region submits the construction agreement to the Director & State Design Engineer, Development Division (see the *Agreements Manual*).
- The Assistant Secretary, Engineering & Regional Operations (or designee), approves the construction agreement.

530.10(3)(c) Valuation Determination

- When a requested public at-grade intersection will serve a local arterial that immediately connects to the local transportation network, compensation will not be required.
- When a requested public at-grade intersection will serve only a limited area, does not immediately connect to the local transportation network, or is primarily for the benefit of a limited number of developers, compensation for the access change will be addressed in the plan revision request. In these situations, compensation is appropriate and a value will be determined as outlined in 530.10(2)(c).

530.11 Documentation

Refer to Chapters 210, 300, and 550 for design documentation requirements.

Exhibit 530-1a Full Access Control Limits: Interchange




Exhibit 530-1b Full Access Control Limits: Interchange




Exhibit 530-1c Full Access Control Limits: Interchange with Roundabouts




Exhibit 530-1d Full Access Control Limits: Ramp Terminal with Transition Taper




Exhibit 530-1e Full Access Control Limits: Single Point Urban Interchange




Exhibit 530-2a Partial Access Control Limits: At-Grade Intersections






Exhibit 530-2b Partial Access Control Limits: Roundabout Intersections



Note:

Partial access control is measured from the center of the roundabout.


Exhibit 530-3a Modified Access Control Limits: Roundabout Intersections




Note:

Modified access control is measured from the outside edge of the circulating roadway.

Exhibit 530-3b Modified Access Control Limits: Intersections





Chapter 540 Managed Access Control

540.01 General
540.02 Design Considerations
540.03 Managed Access Highway Classes
540.04 Corner Clearance Criteria
540.05 Access Connection Categories
540.06 Access Connection Permit
540.07 Permitting and Design Documentation
540.08 Other Considerations
540.09 Preconstruction Conference
540.10 Adjudicative Proceedings
540.11 Documentation
540.12 References

540.01 General

Access management is the systematic regulation of the location, spacing, design, and operation of driveway, city street, and county road connections to state highways. This chapter describes the access management process for granting permission to connect to managed access highways within cities and unincorporated areas. For an overview of access control, references to related state laws and codes, and definitions of terminology for this chapter, see Chapter 520, Access Control.

In Washington State, managed access highways include all state highways that are not limited access highways. State highways that are planned for or established as limited access, are treated as managed access highways until the limited access rights are acquired.

The Access Control Tracking System Limited Access and Managed Access Master Plan (Access Master Plan) identifies not only the limits of limited access control, but also managed access control segments. The current managed access classification is based on access connection densities, distance between access connections, spacing of intersections, and context (see Washington Administrative Code (WAC) 468-52-040). The existing access classification is periodically updated by Headquarters (HQ) with region input to reflect changes on a corridor segment. Conditions may have changed since the Access Master Plan was envisioned or the last managed access classification update. On non-freeways it is important to consider the current classification and any classifications previously planned, and determine the access design control most appropriate for the agreed context (see Chapters 1102 and 1103 for context and design control guidance, respectively). The Access Master Plan database is available at:
www.wsdot.wa.gov/design/accessandhearings

Access to managed access highways is regulated by the governmental entity with jurisdiction over a highway's roadsides. Access connection permits are issued on managed access highways. The Washington State Department of Transportation (WSDOT) has access connection permitting authority over all state highways outside incorporated towns and cities. Incorporated towns and cities have access connection permitting authority for city streets that are part of state highways, as specified in Revised Code of Washington (RCW) 47.24.020. When any project is developed on a state highway outside an incorporated city or town, state law requires that existing access connections be evaluated to determine whether they are consistent with all current department spacing, location, and design standards (see 540.03).

540.02 Design Considerations

Evaluate access connections by using the Access Master Plan database to identify the route classification and determine access connection requirements in conformance with this chapter or Chapter 530 as appropriate. See also Chapter 1100, Practical Design, and chapters in that series for guidance on how access control is used as a design control.

Review all connections and verify whether they are in the Roadway Access Management Permit System (RAMPS) database. Contact the region Development Services Office or the HQ Access and Hearings Section for permission to log on to the link through this page:
www.wsdot.wa.gov/design/accessandhearings

If a nonconforming connection is identified, consider relocating, modifying, or eliminating the connection. It is not the intent of the managed access program that modifications to the connection will change the general functionality of the property.

Where current department standards cannot be met while providing the same general functionality, classify the connection as nonconforming and process the appropriate documentation as discussed below. This documentation is part of the permit process.

540.03 Managed Access Highway Classes

The principal objective of the managed access classification system is to maintain the safety and capacity of existing highways. This is accomplished by establishing access management criteria, which are to be adhered to in the planning and regional approval of access connections to the state highway system.

The classification system for state managed access highways consists of five classes. The classes are arranged from the most restrictive, Class 1, to the least restrictive, Class 5. In general, most state highways outside the incorporated limits of a city or town have been designated as Class 1 or Class 2, with only the most urban and lowest-speed state highways within an incorporated town or city designated as Class 5. Exhibit 540-1 shows the five classes of highways, with a brief description of each class. WSDOT keeps a record of the assigned managed access classifications, by state route and milepost, in the Access Control Tracking System database:
www.wsdot.wa.gov/design/accessandhearings

One of the goals of state law is to restrict or keep access connections to a minimum in order to help preserve the safety, operation, and functional integrity of the state highway. On Class 1 highways, mobility is the primary function, while on Class 5 highways, access needs have priority over mobility needs. Class 2 highways also favor mobility, while Class 3 and Class 4 highways generally achieve a balance between mobility and access.

The most notable distinction between the five highway classes is the minimum spacing requirements of access connections. Exhibit 540-1 shows the minimum distances between access points on the same side of the highway. Exhibit 540-2 applies to the minimum clearance from a public road or street.

In all five highway classes, access connections are to be located and designed to minimize interference with transit facilities and high-occupancy vehicle (HOV) facilities on state highways where such facilities exist or are proposed in state, regional, metropolitan, or local transportation plans. In these cases, if reasonable access is available to the local road/street

system, access is to be provided to the local road/street system rather than directly to the state highway. Following are the functional characteristics and the legal requirements for each class.

540.03(1) Class 1

540.03(1)(a) Functional Characteristics

Class 1 highways provide for high-speed and/or high-volume traffic movements for interstate, interregional, and intercity (and some intracity) travel needs. Service to abutting land is subordinate to providing service to major traffic movements.

Highways in Class 1 are typically distinguished by a highly-controlled, limited number of (public and private) access points, restrictive medians with limited median openings on multilane facilities, and infrequent intersections.

540.03(1)(b) Legal Requirements

1. It is the intent that Class 1 highways be designed to have a posted speed limit of 50 to 65 mph. Intersecting streets, roads, and highways are planned with a minimum spacing of 1 mile. Spacing of ½ mile may be allowed, but only when no reasonable alternative access exists.

2. Private access connections to the state highway are not allowed except where the property has no other reasonable access to the local road/street system. When a private access connection must be provided, the following conditions apply:

   - The access connection continues until such time other reasonable access to a highway with a less restrictive access control class or access to the local road/street system becomes available and is allowed.
   - The minimum distance to another (public or private) access point is 1,320 feet along the same side of the highway. Nonconforming access connection permits may be issued to provide access connections to parcels whose highway frontage, topography, or location otherwise precludes issuance of a conforming access connection permit; however, variance permits are not allowed.
   - No more than one access connection may be provided to an individual parcel or to contiguous parcels under the same ownership.
   - All private access connections are for right turns only on multilane facilities. Where special conditions apply, justify the exception in a traffic analysis in the access connection permit application that is signed and sealed by a qualified professional engineer who is registered in accordance with RCW 18.43.
   - Additional access connections to the state highway are not allowed for newly created parcels resulting from property divisions. All access for these parcels must be provided by an internal road/street network. Access to the state highway will be at existing permitted locations or revised locations.

3. Restrictive medians are provided on multilane facilities to separate opposing traffic movements and to prevent unauthorized turning movements.

540.03(2) Class 2

540.03(2)(a) Functional Characteristics

Class 2 highways provide for medium-to-high-speed and medium-to-high-volume traffic movements over medium and long distances for interregional, intercity, and intracity travel needs. Direct access service to abutting land is subordinate to providing service to traffic movements.

Highways in Class 2 are typically distinguished by existing or planned restrictive medians on multilane facilities and by large minimum distances between (public and private) access points.

540.03(2)(b) Legal Requirements

1. It is the intent that Class 2 highways be designed to have a posted speed limit of 35 to 50 mph in urbanized areas and 45 to 55 mph in rural areas. Intersecting streets, roads, and highways are planned with a minimum spacing of ½ mile. Intersection spacing of less than ½-mile may be allowed, but only when no reasonable alternative access exists.

   In urban areas and developing areas where higher volumes are present or growth that will require a change to intersection control is expected in the foreseeable future, it is imperative that the location of any public access point be planned carefully to ensure adequate traffic progression. The addition of all new public or private access points that might require signalization or other form of intersection control will require an engineering analysis that is signed and sealed by a qualified professional engineer who is registered in accordance with RCW 18.43.

2. Private access connections to the state highway system are allowed only where the property has no other reasonable access to the local road/street system or where access to the local road/street system will cause unacceptable traffic operational conditions or safety concerns on that system. When a private access connection must be provided, the following conditions apply:

   - The access connection continues until such time other reasonable access to a highway with a less restrictive access control class or acceptable access to the local road/street system becomes available and is allowed.
   - The minimum distance to another (public or private) access point is 660 feet on the same side of the highway. Nonconforming access connection permits may be issued to provide access to parcels whose highway frontage, topography, or location precludes issuance of a conforming access connection permit.
   - Only one access connection is allowed for an individual parcel or to contiguous parcels under the same ownership. This applies unless the highway frontage exceeds 1,320 feet and it can be shown that the additional access connection will not adversely affect the desired function of the state highway in accordance with the assigned managed access Class 2 or the safety or operation of the state highway.
   - Variance permits may be allowed if there are special conditions and the exception can be justified to the satisfaction of the department by a traffic analysis in the

access connection permit application that is signed and sealed by a qualified professional engineer who is registered in accordance with RCW 18.43.

- All private access connections are for right turns only on multilane facilities. This applies unless there are special conditions and the exception can be justified to the satisfaction of the department by a traffic analysis in the access connection permit application that is signed and sealed by a qualified professional engineer who is registered in accordance with RCW 18.43 and only if left-turn channelization is provided.
- Additional access connections to the state highway are not allowed for newly created parcels that result from property divisions. All access for these parcels must be provided by an internal road/street network. Access to the state highway will be at existing permitted locations or at revised locations.

3. On multilane facilities, restrictive medians are provided to separate opposing traffic movements and to prevent unauthorized turning movements. However, a nonrestrictive median or a two-way left-turn lane may be used where special conditions exist and main line volumes are below 20,000 average daily traffic (ADT).

540.03(3) Class 3

540.03(3)(a) Functional Characteristics

Class 3 highways provide for moderate travel speeds depending on context, and moderate traffic volumes for medium and short travel distances for intercity, intracity, and intercommunity travel needs. There is a reasonable balance between access and mobility needs for highways in this class. This class is to be used primarily where the existing level of development of the adjoining land is less intensive than maximum buildout and where the probability of significant land use change and increased traffic demand is high.

Highways in Class 3 are typically distinguished by planned restrictive medians on multilane facilities and by meeting minimum distances between (public and private) access points. Two way left-turn lanes may be used where justified and main line traffic volumes are below 25,000 ADT. Development of properties with internal road/street networks and joint access connections is encouraged.

540.03(3)(b) Legal Requirements

1. It is the intent that Class 3 highways be designed to have a posted speed limit of 30 to 40 mph in urbanized areas and 45 to 55 mph in rural areas. In rural areas, intersecting streets, roads, and highways are planned with a minimum spacing of ½ mile. Intersection spacing of less than ½-mile may be allowed, but only when no reasonable alternative access exists.

   In urban areas and developing areas where higher volumes are present or growth that will require a change to intersection control is expected in the foreseeable future, it is imperative that the location of any public access point be planned carefully to ensure adequate traffic progression. Where feasible, major intersecting roadways that might ultimately require signalization or other intersection control type are planned with a minimum of ½-mile spacing. The addition of all new public or private access points that may require signalization or other intersection control type, will require an engineering analysis

that is signed and sealed by a qualified professional engineer who is registered in accordance with RCW 18.43.

2. Private Access Connections

   - No more than one access connection may be provided to an individual parcel or to contiguous parcels under the same ownership. This applies unless it can be shown that additional access connections will not adversely affect the desired function of the state highway in accordance with the assigned managed access Class 3 and will not adversely affect the safety or operation of the state highway.
   - The minimum distance to another (public or private) access point is 330 feet on the same side of the highway. Nonconforming access connection permits may be issued to provide access to parcels whose highway frontage, topography, or location precludes issuance of a conforming access connection permit.
   - Variance permits may be allowed if there are special conditions and the exception can be justified to the satisfaction of the department by a traffic analysis in the access connection permit application that is signed and sealed by a qualified professional engineer who is registered in accordance with RCW 18.43.

540.03(4) Class 4

540.03(4)(a) Functional Characteristics

Class 4 highways provide for moderate travel speeds and moderate traffic volumes for medium and short travel distances for intercity, intracity, and intercommunity travel needs. There is a reasonable balance between direct access and mobility needs for highways in this class. This class is to be used primarily where the existing level of development of the adjoining land is more intensive and where the probability of major land use changes is less than on Class 3 highway segments.

Highways in Class 4 are typically distinguished by existing or planned nonrestrictive medians. Restrictive medians may be used to mitigate unfavorable operational conditions such as turning, weaving, and crossing conflicts. Minimum access connection spacing requirements apply if adjoining properties are redeveloped.

540.03(4)(b) Legal Requirements

1. It is the intent that Class 4 highways be designed to have a posted speed limit of 30 to 35 mph in urbanized areas and 35 to 45 mph in rural areas. In rural areas, intersecting streets, roads, and highways are planned with a minimum spacing of ½ mile. Intersection spacing of less than ½ mile may be allowed, but only when no reasonable alternative access exists.

   In urban areas and developing areas where higher volumes are present or growth that will require a change in intersection control is expected in the foreseeable future, it is imperative that the location of any public access point be planned carefully to ensure adequate traffic progression. Where feasible, major intersecting roadways that might ultimately require intersection control changes are planned with a minimum of ½-mile spacing. The addition of all new public or private access points that may require signalization, or other intersection control type, will require an engineering analysis that is

signed and sealed by a qualified professional engineer who is registered in accordance with RCW 18.43.

2. Private Access Connections

   - No more than one access connection may be provided to an individual parcel or to contiguous parcels under the same ownership. This applies unless it can be shown that additional access connections will not adversely affect the desired function of the state highway in accordance with the assigned managed access Class 4 and will not adversely affect the safety or operation of the state highway.
   - The minimum distance to another (public or private) access point is 250 feet on the same side of the highway. Nonconforming access connection permits may be issued to provide access connections to parcels whose highway frontage, topography, or location precludes issuance of a conforming access connection permit.
   - Variance permits may be allowed if there are special conditions and the exception can be justified to the satisfaction of the department by a traffic analysis in the access connection permit application that is signed and sealed by a qualified professional engineer who is registered in accordance with RCW 18.43.

540.03(5) Class 5

540.03(5)(a) Functional Characteristics

Class 5 highways provide for moderate travel speeds and moderate traffic volumes for primarily short travel distances for intracity and intracommunity trips and for access to state highways of a higher class. Access needs generally may be higher than the need for through-traffic mobility without compromising the public's health, welfare, or safety. These highways will normally have nonrestrictive medians.

540.03(5)(b) Legal Requirements

1. It is the intent that Class 5 highways be designed to have a posted speed limit of 25 to 35 mph. In rural areas, intersecting streets, roads, and highways are planned with a minimum spacing of ¼ mile. Spacing of less than ¼ mile may be allowed where no reasonable alternative exists. In urban areas and developing areas where higher volumes are present or growth that will require changes to intersection control is expected in the foreseeable future, it is imperative that the location of any public access point be planned carefully to ensure adequate traffic progression. Where feasible, major intersecting roadways that might ultimately require changes to intersection control are planned with a minimum of ¼ mile spacing. The addition of all new public or private access points that might require signalization, or other control type, will require an engineering analysis that is signed and sealed by a qualified professional engineer who is registered in accordance with RCW 18.43.

2. Private Access Connections

   - No more than one access connection may be provided to an individual parcel or to contiguous parcels under the same ownership. This applies unless it can be shown that additional access connections will not adversely affect the desired function of

the state highway in accordance with the assigned managed access Class 5 and will not adversely affect the safety or operation of the state highway.

- The minimum distance to another (public or private) access point is 125 feet on the same side of the highway. Nonconforming access connection permits may be issued to provide access to parcels whose highway frontage, topography, or location precludes issuance of a conforming access connection permit.
- Variance permits may be allowed if there are special conditions and the exception can be justified to the satisfaction of the department by a traffic analysis in the access connection permit application that is signed and sealed by a qualified professional engineer who is registered in accordance with RCW 18.43.

Exhibit 540-1 Managed Access Highway Class Description

Class	Non-Conforming[1]	Variance[2]	Conforming[3]	Access Point Spacing**	Limitations[4]
Class 1 Mobility is the primary function	Yes*	No	No	1,320 ft	• One access only to contiguous parcels under same ownership • Private access connection is not allowed unless no other reasonable access exists (must use local road/ street system if possible)
Class 2 Mobility is favored over access	Yes*	Yes*	No	660 ft	• One access connection only to contiguous parcels under same ownership unless frontage > 1,320 ft • Private access connection not allowed unless no other reasonable access exists; must use local road/street system if possible
Class 3 Balance between mobility and access in areas with less than maximum buildout	Yes	Yes	Yes	330 ft	• One access connection only to contiguous parcels under same ownership • Joint access connection for subdivisions preferred; private connection allowed, with justification
Class 4 Balance between mobility and access in areas with less than maximum buildout	Yes	Yes	Yes	250 ft	One access connection only to contiguous parcels under same ownership, except with justification
Class 5 Access needs may have priority over mobility	Yes	Yes	Yes	125 ft	More than one access connection per ownership, with justification

*The access connection continues only until such time other reasonable access to a highway with a less restrictive class or acceptable access to the local road/street system becomes available and is allowed.

**Minimum, on the same side of the highway.

[1] See 540.07(2).
[2] See 540.07(3).
[3] See 540.07(1).
[4] Unless grandfathered (see 540.06).

540.03(6) Changes in Managed Access Classification

WSDOT, RTPOs, MPOs, or other entities such as cities, towns, or counties may initiate a review of managed access classifications per the process identified by WAC 468-52. In all cases, WSDOT consults with the RTPOs, MPOs, and local agencies and takes into consideration comments received during the review process. For city streets that are designated as state highways, the department will obtain concurrence in the final classification assignment from the city or town.

The modified highway classification list shall be submitted to Headquarters for approval by the Director & State Design Engineer, Development Division, or a designee. WSDOT regions shall notify the RTPOs, MPOs, and local governmental entities in writing of the final determination of the reclassification.


540.04 Corner Clearance Criteria

In addition to the five access control classes, there are also corner clearance criteria that must be used for access connections near intersections (see Exhibit 540-2).

Corner clearance spacing must meet or exceed the minimum access point spacing requirements of the applicable managed access highway class. A single access connection may be placed closer to the intersection, in compliance with the permit application process specified in WAC 468-51 and in accordance with the following criteria:

- The minimum corner clearance criteria in Exhibit 540-2 may be used where access point spacing cannot be obtained due to property size and where a joint-use access connection cannot be secured or where it is determined by WSDOT not to be feasible because of conflicting land use or conflicting traffic volumes or operational characteristics.
- Some local agencies have adopted corner clearance as a design element in their design standards; these standards are to meet or exceed WSDOT standards. Coordinate with the local agency regarding corner clearance of an access connection on or near an intersecting local road or street.
- When a joint-use access connection or an alternate road/street system access—meeting or exceeding the minimum corner clearance requirements—becomes available, the permit holder must close the permitted access connection unless the permit holder shows to WSDOT's satisfaction that such closure is not feasible.

Exhibit 540-2 Minimum Corner Clearance: Distance From Access Connection to Public Road or Street



With Restrictive Median		
Position	**Access Allowed**	**Minimum (ft)**
Approaching Intersection	Right In/Right Out	115
Approaching Intersection	Right In Only	75
Departing Intersection	Right In/Right Out	230*
Departing Intersection	Right Out Only	100
Without Restrictive Median		
Position	**Access Allowed**	**Minimum (ft)**
Approaching Intersection	Full Access**	230*
Approaching Intersection	Right In Only	100
Departing Intersection	Full Access**	230*
Departing Intersection	Right Out Only	100

*125 ft may be used for Class 5 facilities with a posted speed of 35 mph or less.
**Full Access = All four movements (Right in/Right out; Left in/Left out)

540.05 Access Connection Categories

Whenever an access connection permit is issued on a managed access state highway, the permit must also specify one of four access connection categories: Category I to Category IV. Categories I through III are based on the maximum vehicular usage of the access connection. Category IV specifies temporary use, usually for less than a year. Access connection permits must specify the category and the maximum vehicular usage of the access connection in the permit.

All access connections are determined by WSDOT to be in one of the following categories (WAC 468-51-040):

540.05(1) Category I

"Category I – minimum connection" provides connection to the state highway system for up to ten single-family residences, a duplex, or a small multifamily complex of up to ten dwelling units that use a common access connection. This category also applies to permanent access connections to agricultural and forestlands, including field entrances; access connections for the operation, maintenance, and repair of utilities; and access connections serving other low-volume traffic generators expected to have average weekday vehicle trip ends (AWDVTE) of 100 or less.

540.05(2) Category II

"Category II – minor connection" provides connection to the state highway system for medium-volume traffic generators expected to have an AWDVTE of 1,500 or less, but not included in Category I.

540.05(3) Category III

"Category III – major connection" provides connection to the state highway system for high-volume traffic generators expected to have an AWDVTE exceeding 1,500.

540.05(4) Category IV

"Category IV – temporary connection" provides a temporary, time-limited connection to the state highway system for a specific property for a specific use with a specific traffic volume. Such uses include, but are not limited to, logging, forestland clearing, temporary agricultural uses, temporary construction, and temporary emergency access. The department reserves the right to remove any temporary access connection at its sole discretion and at the expense of the property owner after the expiration of the permit. Further, a temporary access connection permit does not bind the department, in any way, to the future issuance of a permanent access connection permit at the temporary access connection location.

540.06 Access Connection Permit

RCW 47.50 requires all access connections to be permitted. This can be accomplished by the permitting process (see 540.07) or by the connection being "grandfathered" (in place prior to July 1, 1990).

All new access connections to state highways, as well as alterations and improvements to existing access connections, require an access connection permit. Every owner of property that abuts a managed access state highway has the right to reasonable access, but not a particular means of access. This right may be restricted with respect to the highway if reasonable access can be provided by way of another local road/street.

When a new private road or street is to be constructed, approval by the permitting authority is required for intersection design, spacing, and construction work on the right of way. However, if an access connection permit is issued, it will be rendered null and void if and when the road or street is duly established as a local road or street by the local governmental entity.

It is the responsibility of the applicant or permit holder to obtain all necessary local, state, and federal approvals and permits (which includes all environmental permits and documentation).

The access connection permit only allows the applicant permission to connect to the state highway. It is also the responsibility of the applicant to acquire any and all property rights necessary to provide continuity from the applicant's property to the state highway.

The alteration or closure of any existing access connection caused by changes to the character, intensity of development, or use of the property served by the access connection or the construction of any new access connection must not begin before an approved access connection permit is obtained.

If a property owner or permit holder with a valid access connection permit wishes to change the character, use, or intensity of the property or development served by the access connection, the permitting authority must be contacted to determine whether an upgraded access connection permit will be required.

540.07 Permitting and Design Documentation

An access connection permit is obtained from the department by submitting the appropriate application form, including the fee, plans, traffic data, and access connection information, to the department for review. All access connection and roadway design documents for Category II and III permits must bear the seal and signature of a professional engineer registered in Washington State.

The permitting process begins with the application. Upon submittal of the application with all the attached requirements, it is reviewed and either denied or accepted. If denied, the department must notify the applicant in writing stating the reasons, and the applicant will have thirty (30) days to submit a revised application. Once the application is approved and the permit is issued, the applicant may begin construction.

The Access Manager in each region keeps a record of all access points, including those that are permitted and those that are grandfathered (see 540.08). A permit for a grandfathered access point is not required but may be issued for recordkeeping reasons.

540.07(1) Conforming Access Connection Permit

Conforming access connection permits may be issued for access connections that conform to the functional characteristics and all legal requirements for the designated class of the highway.

540.07(2) Nonconforming Access Connection Permit

Nonconforming access connection permits may be issued:

- For short-term access connections pending the availability of a future joint-use access connection or local road/street system access.
- For location and spacing not meeting requirements.
- For Category I through IV permits.
- After an analysis and determination by the department that a conforming access connection cannot be made at the time of permit application submittal.
- After a finding that the denial of an access connection will leave the property without a reasonable means of access to the local road/street system.

In such instances, the permit is to be noted as being a nonconforming access connection permit and may contain the following specific restrictions and provisions:

- Limits on the maximum vehicular use of the access connection.
- The future availability of alternate means of reasonable access for which a conforming access connection permit can be obtained.
- The removal of the nonconforming access connection at the time the conforming access is available.
- The properties to be served by the access connection.
- Other conditions as necessary to carry out the provisions of RCW 47.50.

540.07(3) Variance Access Connection Permit

Variance access connection is a special nonconforming or additional access connection permit issued for long-term use where future local road/street system access is not foreseeable:

- For location and spacing not meeting requirements or for an access connection that exceeds the number allowed for the class.
- After an engineering study demonstrates, to the satisfaction of the department, that the access connection will not adversely affect the safety, maintenance, or operation of the highway in accordance with its assigned managed access class.

In such instances, the permit is to be noted as being a variance access connection permit and may contain the following specific restrictions and provisions:

- Limits on the maximum vehicular use of the access connection
- The properties to be served by the access connection
- Other conditions as necessary to carry out the provisions of RCW 47.50

This permit will remain valid until modified or revoked by the permitting authority unless an upgraded permit is required due to changes in property site use (see 540.08(1)).

A variance access connection permit must not be issued for an access connection that does not conform to minimum corner clearance requirements (see 540.04).

540.07(4) Corner Clearance Design Analysis

540.07(4)(a) Outside Incorporated City Limits

A design analysis request will be required for nonconforming access connections if corner clearance criteria are not met. The HQ Design Office is to be involved early in the process. Such an access will be outside the corner radius and as close as feasible to the property line farthest away from the intersection.

For WSDOT projects, record the approved design analysis in the Design Variance Inventory System (DVIS) and include it in the Design Documentation Package (see Chapter 300).

For non-WSDOT projects, the region Development Services Office or Local Programs Office is responsible for entering the design analysis into the DVIS.

An exception to the above may be allowed for a single-family residence, serving a single residence, not meeting the minimum corner clearance criteria and having no feasible connection to the local cross street. One single family home generates a very low volume of traffic and will pose a low conflict potential for traffic on the State Highway System. A single-family access connection exception is to comply with the following criteria:

- Serves a single residence
- Access is to be outside the corner radius
- Access is to be located as close as feasible to the property line farthest away from the intersection
- The denial of an access connection would leave the property without a reasonable means of access.
- The connection is to be relocated to a local road/street system, if one becomes available.

Document the above criteria in the access connection permit.

540.07(4)(b) Within Incorporated Cities

In accordance with RCW 35.78.030 and RCW 47.50, incorporated cities and towns have jurisdiction over access permitting on streets designated as state highways and, therefore, no design analysis by WSDOT will be required. On WSDOT projects, document decisions made on these accesses in the DDP.

540.08 Other Considerations

540.08(1) Changes in Property Site Use With Permitted Access Connection

The access connection permit is issued to the permit holder for a particular type of land use generating specific projected traffic volumes at the final stage of proposed development. Any changes made in the use, intensity of development, type of traffic, or traffic flow require the permit holder, an assignee, or the property owner to contact the department to determine whether further analysis is needed because the change is significant and will require a new permit and modifications to the access connection (WAC 468-51-110).

A significant change is one that will cause a change in the category of the access connection permit or one that causes an operational, safety, or maintenance problem on the state highway system based on objective engineering criteria or available collision data. Such data will be provided to the property owner and/or permit holder and tenant upon written request (WAC 468-51-110).

540.08(2) Existing Access Connections

540.08(2)(a) Closure of Grandfathered Access Connections

Any access connections that were in existence and in active use on July 1, 1990, are grandfathered.

The grandfathered access connection may continue unless:

- There are changes from the 1990 AWDVTE.
- There are changes from the 1990 established use.
- The department determines that the access connection does not provide minimum acceptable levels of highway safety and mobility based on collision and/or traffic data or accepted traffic engineering criteria, a copy of which must be provided to the property owner, permit holder, and/or tenant upon written request (WAC 468-51-130).

540.08(2)(b) Department Construction Projects

540.08(2)(b)(1) Notification

The department must notify affected property owners, permit holders, business owners, and emergency services in writing, when appropriate, whenever the department's work program requires the modification, relocation, or replacement of its access connections. In addition to written notification, the department will facilitate, when appropriate, a process that may include, but is not limited to, public notices, meetings, or hearings, as well as individual meetings.

540.08(2)(b)(2) Modification Considerations

When the number, location, or design of existing access connections to the state highway is being modified by a department construction project, the resulting modified access connections must provide the same general functionality for the existing property use as they did before the modification, taking into consideration the existing site design, normal vehicle types, and traffic circulation requirements. These are evaluated on an individual basis.

It is important to remember that the intent is not to damage the property owner by removing nonconforming access connections, but to eliminate access connections that are both nonconforming and not needed.

The permitting authority evaluates each property individually to make a determination about which category of access connection (see 540.05) and which design template (see Chapter 1340) will be reasonable. If it is a commercial parcel, determine whether the business can function with one access connection. Each parcel, or contiguous parcels under the same ownership being used for the same purpose, is allowed only one access connection. If the business cannot function properly with only one access connection, a variance permit may be issued for additional access connections. If the property is residential, only one access connection is allowed; however, certain circumstances might require an additional access connection (see 540.07(4)(a)).

540.08(2)(b)(3) Costs: Replacement of/Modifications to Existing Access Connections

The costs of modifying or replacing the access points are borne by the department if the department construction project caused the replacement or modification. Modification of the connection may require a change to the existing permit.

540.08(3) Work by Permit Holder's Contractor

The department requires that work by the owner's contractor be accomplished at the completion of the department's contract or be scheduled so as not to interfere with the department's contractor. The department may require a surety bond prior to construction of the access connection in accordance with WAC 468-51-070.

540.09 Preconstruction Conference

All new access connections, including alterations and improvements to existing access connections to the highway, require an access connection permit. The permitting authority may require a preconstruction conference prior to any work being performed on the access. The preconstruction conference must be attended by those necessary to ensure compliance with the terms and provisions of the permit. Details regarding the individual access connections will be included in the construction permit. This may include access connection widths, drainage requirements, surfacing requirements, mailbox locations, and other information (WAC 468-51-090).

540.10 Adjudicative Proceedings

Any person who can challenge any of the following departmental actions may request an adjudicative proceeding (an appeal to an Administrative Law Judge) within thirty (30) days of the department's written decision (WAC 468-51-150):

- Denial of an access connection permit application pursuant to WAC 468-51-080
- Permit conditions pursuant to WAC 468-51-150
- Permit modifications pursuant to WAC 468-51-120
- Permit revocation pursuant to WAC 468-51-120
- Closure of permitted access connection pursuant to WAC 468-51-120
- Closure of grandfathered access connection pursuant to WAC 468-51-130

An appeal of a decision by the department can be requested only if the administrative fee has been paid. If the fee has not been paid, the permit application is considered incomplete and an adjudicative proceeding cannot be requested.

540.10(1)(a) Adjudicative Proceedings Process

Following is a brief summary of the adjudicative proceeding process. For the purpose of this summary, the responsibilities of the department are separated into those actions required of the region and those actions required of Headquarters. The summary is written as if the appealable condition was a denial of an access connection request.

1. The region receives an access connection permit application, with fee.
2. The region processes the application and makes a determination that the access connection request will be denied.
3. The region sends the applicant a written letter denying the access connection. Included in this letter is notification that the applicant has thirty (30) days to request an adjudicative proceeding if the applicant disagrees with the region's denial decision. The region must

notify affected property owners, permit holders, business owners, tenants, lessees, and emergency services, as appropriate.

4. The applicant requests, within thirty (30) days, an adjudicative proceeding.

5. The region reviews its initial denial decision and determines whether there is any additional information presented that justifies reversing the original decision.

6. If the region determines that the original denial decision will stand, the region then forwards copies of all applicable permit documentation to the HQ Development Services & Access Manager for review and processing.

7. The HQ Development Services & Access Manager reviews the permit application and sends the permit documentation and appeal request to the Office of the Attorney General (AG).

8. If the initial findings of the AG agree with the region's denial decision, the AG's Office sends the applicant a written letter, with the AG's signature, informing the applicant that a hearing will be scheduled for the applicant to appeal in person the department's decision to deny access.

9. The region reserves a location and obtains a court reporter, and Headquarters obtains an Administrative Law Judge (ALJ) to conduct the proceeding. The AG, by written letter, notifies the applicant of the time and place for the hearing. The AG's Office has ninety (90) days from receipt of the applicant's appeal to approve or deny the appeal application, schedule a hearing, or decide not to conduct a hearing. The actual hearing date can be set beyond this ninety-day (90-day) review period.

10. The AG's Office leads the department's presentation and works with the region regarding who will testify and what displays and other information will be presented to the ALJ. The HQ Development Services & Access Manager will typically not attend these proceedings.

11. After hearing all the facts, the ALJ issues a decision, usually within a few weeks after the proceedings. However, the ALJ has ninety (90) days in which to serve a written Initial Order stating the decision.

12. The ALJ's decision is final unless the applicant, or the department through the HQ Development Services & Access Manager, decides to appeal the ALJ's decision to the Director & State Design Engineer, Development Division. This second appeal must occur within twenty (20) days of the ALJ's written decision.

13. If appealed to the Director & State Design Engineer, Development Division, the Director & State Design Engineer has ninety (90) days to review the Initial Order and all the facts and supporting documentation and issue a Final Order. The review by the Director & State Design Engineer does not require the applicable parties to be present and may involve only a review of the material submitted at the adjudicative proceeding.

14. The Director & State Design Engineer's decision is final unless appealed within thirty (30) days to the Washington State Superior Court.

The above represents a general timeline if all appeals are pursued. Based on the noted timelines, it can take nearly a year before a Final Order is issued. If appealed to Superior Court, up to an additional 18 months can be added to the process. In any case, contact the region

Development Services Engineer for further guidance and direction if an appeal might be forthcoming.

540.11 Documentation

Refer to Chapter 300 for design documentation requirements.

540.12 References

540.12(1) State Laws and Codes

Chapter 520, Access Control, provides reference to laws and codes

540.12(2) Design Guidance

Chapter 520, Access Control

Chapters in the 1100 series for guidance on practical design, context, and design controls

Chapter 1230, Geometric Cross Section

Chapters 1300 and 1310, for intersection design policy and guidance

Chapter 1340, Driveways

Chapter 1600, Roadside Safety

Chapter 550 Interchange Justification Report

550.01 General
550.02 Procedures
550.03 Interchange Justification Report and Supporting Analyses
550.04 Report Organization and Appendices
550.05 IJR Review and Approval
550.06 Updating an IJR
550.07 Documentation
550.08 References

550.01 General

The primary function of limited access freeways and highways is to provide safe and reliable travel for people, goods, and services from state to state and region to region within a state. They should not be used for local trips as an extension of the local street network. Adding or revising access can adversely impact the safety and operations of these facilities; therefore, access revisions must be done with caution. For this reason, new and/or modified access must be justified, and this chapter contains the process for seeking access approval.

An Interchange Justification Report (IJR) is the document used to justify a new access point or access point revision on existing limited access freeways and highways in Washington State. This chapter provides policy and guidance on developing the required documentation for an IJR, and the sequence of an IJR presentation, for both Interstate and non-Interstate limited access routes.

Federal law requires Federal Highway Administration (FHWA) approval of all revisions to the Interstate system, including changes to limited access. Both FHWA and Washington State Department of Transportation (WSDOT) policy require the formal submission of a request to either break or revise the existing limited access on Interstate routes. This policy also facilitates decision-making regarding proposed changes in access to the Interstate system in a manner that considers and is consistent with the vision, goals, and long-range transportation plans of a metropolitan area, region, and state. Breaking or revising existing limited access on state routes must be approved in accordance with Chapter 530, Limited Access Control. An IJR is a document that includes all of the necessary supporting information needed for a request. It documents the IJR team's assumptions and the design of the preferred alternative, the planning process, the evaluation of the alternatives considered, and the coordination that supports and justifies the request for an access revision.

FHWA cannot give final approval to the IJR unless environmental analysis/documentation has been approved for the project. Therefore, the IJR process and the environmental analysis should be conducted concurrently. The level of environmental analysis should be consistent with the project context and significance of the potential environmental impacts. The project may qualify as Categorically Excluded (CE). This option should always be examined before proceeding with environmental documentation.

Engineers at the WSDOT Headquarters (HQ) Design Office Access and Hearings Section specialize in providing support for meeting the guidance provided in this chapter. To ensure project success, consult with them before any of the IJR work is started. They can help during

the development of the study, Methods and Assumptions Document, and the Interchange Justification Report.

An IJR support team, including HQ Access and Hearings, agrees upon what an IJR will include. IJRs on the Interstate require that all eight policy points contained in the FHWA Policy on Adding Additional Interchanges be addressed. The scale and complexity of the report varies considerably with the scope of the proposal. Exhibit 550-1 lists typical projects for Interstates and the required policy points to address. The level of effort is set by the support team and documented in the Methods and Assumptions Document. For non-Interstate IJRs, Exhibit 550-2 lists project types and required policy points to address. Both Exhibits show what approval levels are required.

When a local agency or developer is proposing an access point revision, WSDOT requires that a support team be formed.

The IJR will contain a signature page that will be stamped by the Engineer of Record responsible for the report's preparation and the Traffic Analysis Engineer responsible for the traffic analysis included in Policy Point 3. (See Exhibit 550-6 for an example.)

550.02 Procedures

An access point revision is a multistep process. It begins with assembling a support team to conduct a feasibility or planning-level study. The purpose of this study is to determine whether there are improvements that can be made to the local roadway network to meet the purpose and need of the proposed access modification. If the study shows that the purpose and need of the proposal cannot be achieved with the local infrastructure only, the next step would normally be to prepare an IJR (see the Interstate IJR: Process Flow Chart, Exhibit 550-3).

The IJR is typically initiated early in the environmental process. Traffic analyses help define the area of impact and the range of alternatives. Since the traffic data required for the National Environmental Policy Act (NEPA) or the State Environmental Policy Act (SEPA) and the operational/safety analyses of the IJR are the same, these documents need to be coordinated and developed together, using the same data sources and procedures.

Consider implementing Planning and Environmental Linkage (PEL) principles during the feasibility/planning study phase of the IJR to eliminate rework in the environmental review/NEPA stage of the project. Using the PEL approach is most valuable for a project where an Environmental Assessment (EA) or Environmental Impact Statement (EIS) is required. If the project is classified as a CE, information from the Corridor Sketch Plan can be useful. Application of PEL principles may require:

- Public and agency involvement effort with increased opportunity for comment and comprehensive documentation of process, meetings held, attendance, comments received and response to those comments;
- Analysis of potentially high-risk environmental areas and multidisciplinary assessment of project impacts; and
- Documentation of the methodology and data sources used to assess environmental resources.

Contact the HQ NEPA Specialist for additional guidance about PEL process and requirements.

The required steps in the IJR process are described in detail in this chapter, and include:

- Assemble the support team to engage subject experts and decision makers.
- Define purpose and need of the proposal (team).
- Determine whether a feasibility study needs to be conducted or already exists (team).
- Prepare Methods and Assumptions Document to lay the groundwork for the IJR, including scope of IJR and team roles and responsibilities (team).
- Endorse Methods and Assumptions Document to prepare the IJR (team).
- Prepare draft IJR (team or consultant).
- Review draft IJR (team).
- Finalize IJR by addressing comments and issues.
- Review and approve IJR (or conceptual approval).

550.02(1) Organize Support Team and Conduct Study

550.02(1)(a) Support Team

Establish a support team before beginning the feasibility study. This same support team is also involved with the IJR process if the study shows that either a revision or a new access point is needed to meet the proposal purpose and need.

The support team normally consists of the following:

- FHWA Area Engineer and FHWA Safety and Geometric Design Engineer (for Interstate projects)
- Region Planning, Design, or Project Development Engineer (or designee), Region Traffic
- HQ Assistant State Design Engineer
- HQ Development Services & Access Manager
- HQ Traffic Office Representative
- Representative from local agencies (city, county, port, or tribal government)
- Recorder (records and prepares meeting minutes for documentation purposes)

The support team enlists specialists, including but not limited to:

- Metropolitan Planning Organization (MPO)
- Regional Transportation Planning Organization (RTPO)
- WSDOT region (planning, design, environmental, maintenance, and traffic)
- WSDOT Headquarters (design, environmental, bridge, traffic, and geotechnical)
- Project proponent specialists (region, local agency, developer)
- Transit agencies
- Other identified stakeholders/partners

The support team's role is to:

- Develop processes for reaching agreement, resolving disputes, and assigning responsibility for final decisions. This is especially important for complex proposals.
- Review regional and state transportation plans to see if the request is consistent with the needs and solutions shown in those plans.
- Develop purpose and need statements for the proposal, consistent with the project environmental document or PEL process.
- Expedite the study steps (and, if needed, the IJR development and review process) through early communication and agreement.

The support team works together, from the corridor study through preparation of the assumptions document and completion of the IJR.

- Establish the agreed-upon study area (including baseline transportation improvements) and future travel demand forecasts for each of the alternatives being considered.
- Develop and endorse the Methods and Assumptions Document.
- Provide guidance and support.
- Evaluate data and identify possible alternatives for the proposal during the study and, if needed, for an IJR.
- Contribute material for the report that documents the discussions and decisions.
- Review results and determine whether an IJR is warranted.
- Ensure the compatibility of data used in adjacent or overlapping studies.
- Ensure integration of the following as required: Project Definition process, value engineering studies, public involvement efforts, environmental analyses, operational analyses, safety analyses, and other analyses for the study. This encourages the use of consistent data. If conducting a feasibility/planning level study, consider implementing PEL process to minimize re-work.
- Address design elements and known design analyses, drawing from the Basis of Design (see Chapter 300), to support Policy Point 4.

550.02(1)(b) Methods and Assumptions Document

This document is developed to record assumptions used in the IJR, the purpose and need, along with analysis methodologies, criteria, and support team decisions. The document presents the proposed traffic analysis tool and approach, safety analysis methodology, study area, peak hour(s) for analysis, traffic data, design year, opening year, travel demand forecasts, baseline conditions, and design year conditions. It also documents the team's decisions on how much detail will be included in each policy point, the required level of environmental documentation (CE, EA, EIS), and the anticipated timing of the work (concurrent with, or subsequent to the IJR). The timing of environmental documentation determines the level of approval for the IJR, see 550.01.

The signed Methods and Assumptions Document represents endorsement by the support team on the IJR approach, tools, data, and criteria used throughout the IJR process. This document is used on both interstate & non-interstate IJRs.

The Methods and Assumptions Document is dynamic, and is updated and re-endorsed when changed conditions warrant. The document also serves as a historical record of the processes,

dates, and decisions made by the team. WSDOT and FHWA require the development and acceptance of the document, because early agreement on details results in the highest level of success for the IJR process.

Use the WSDOT Methods and Assumptions Document template here:
www.wsdot.wa.gov/design/accessandhearings

Refer to Exhibit 550-5 for an example form for support team's concurrence to Methods and Assumptions Document.

550.02(1)(c) Feasibility Study

The feasibility study will include practical design procedures described in Division 11 of this Design Manual. The support team identified in 550.02(1)(a) will assume the role of the Multiagency and Interdisciplinary Stakeholder Advisory team described in Chapter 1100. Prior to commencing the feasibility study it is critical to establish the project performance needs (see Chapter 1101) with the support team.

Study the transportation network in the area. This study must identify the segments of both the local and regional network that are currently experiencing congestion or safety deficiencies, or where planned land use changes will prompt the need to evaluate the demands on and the capacity of the transportation system. The study area includes the affected existing and proposed interchanges/ intersections upstream and downstream from the proposed access point revision. Extend the study area far enough that the proposal creates no significant impacts to the adjacent interchanges/intersections, then analyze only through the area of influence. When the area of influence extends beyond one interchange/intersection upstream and downstream, extend the analysis to include the extent of the traffic impacts.

Segments of the local and regional network within the study area will be evaluated for system improvements. Part of the study process is to identify local infrastructure needs and develop a proposal. The study must investigate investments in local infrastructure improvements to meet the purpose and need of the proposal. It must be shown that the local infrastructure alone cannot be improved to address the purpose and need. The limited access facility should not be used to solve congestion problems on the local network.

During the feasibility study process and while developing a proposal, it is important to use the data and analysis methods required for an IJR. If the study indicates that an IJR is warranted, the study data can then be utilized in the IJR. The feasibility study and the IJR can also be used to support the transportation analysis requirements in the project's environmental documentation (CE, EA, or EIS).

550.02(1)(d) Analysis and Data to Support Proposal

The proposal analysis tools, data, and study area must be agreed upon by the support team. Use the Methods and Assumptions Document to detail the specific items and record the team's agreement to them. Establishing assumptions upfront ensures the project will have the highest rate of success. For further guidance and examples on assumptions documents, see:
www.wsdot.wa.gov/design/accessandhearings

Show that a preliminary (planning level) analysis, comparing build to no-build data, was conducted for the current year, year of opening, and design year, comparing baseline, no-build condition, and build alternatives. Include the following steps:

1. Define the study area. The study area is a minimum of one interchange upstream and downstream from the proposal. The study area should be expanded as necessary to capture operational impacts of adjacent interchanges in the vicinity that are, or will be, bottlenecks or chokepoints that influence the operations of the study interchange.
2. Establish baseline transportation networks and future land use projections for the study area. The baseline transportation network typically includes local, regional, and state transportation improvement projects that are funded. The land use projection includes population and employment forecasts consistent with the regional (MPO or RTPO) and local jurisdiction forecasts.
3. Establish the environmental classification (CE, EA, EIS), level of environmental analysis (feasibility study or NEPA documentation), and timing of environmental work (concurrent with or subsequent to IJR analysis). If a feasibility study is selected, determine if PEL principles will be implemented and if resource agencies will be invited to participate.
4. Collect and analyze current traffic volumes to develop current year, year of opening, and design year (see Chapter 1103) peak hour traffic estimates for the regional and local systems in the area of the proposal. Use regional transportation planning organization-based forecasts, refined by accepted travel demand estimating procedures. Forecasts for specific ramp traffic may require other methods of estimation procedures and must be consistent with the projections of the travel demand models. Modeling must include increased demand caused by anticipated development.
5. Identify the origins and destinations of trips on the local systems, the existing interchange/intersections, and the proposed access using existing information.
6. Develop travel demand forecasts corresponding to proposed alternatives that might be made to the following:
   - The local system: widen, add new surface routes, coordinate the signal system, control access, improve local circulation, or improve parallel roads or streets.
   - The existing interchanges: lengthen or widen ramps, add park & ride lots, or add frontage roads.
   - The freeway lanes: add collector-distributor roads or auxiliary lanes.
   - Transportation system management and travel demand management measures.
7. Describe the current year, year of opening, and design year level of service at all affected locations within the study area, including local systems, existing ramps, and freeway lanes.

550.02(2) Conduct Analysis and Prepare IJR

Prepare a detailed IJR using the guidance in 550.03, Interchange Justification Report and Supporting Analyses, and Exhibit 550-3.

550.02(2)(a) IJR Policy Points

The IJR addresses the following eight specific policy points, which are described in detail in 550.04:

1. Need for the Access Point Revision
2. Reasonable Alternatives
3. Operational and Crash Analyses

4. Access Connections and Design
5. Land Use and Transportation Plans
6. Future Interchanges
7. Coordination
8. Environmental Processes

550.03 Interchange Justification Report and Supporting Analyses

The eight policy points are presented below. Factors that affect the scope include location (rural or urban), access points (new or revised), ramps (new or existing), ramp terminals (freeway or local road), complexity of the environmental context, and potential for significant environmental impacts or controversy on environmental grounds.

550.03(1) Policy Point 1: Need for the Access Point Revision

What are the current and projected needs? Why are the existing access points and the existing or improved local system unable to meet the proposal needs? Is the anticipated demand short or long trip?

Describe the need for the access point revision and why the existing access points and the existing or improved local system cannot address the need. How does the proposal meet the design year travel demand? Provide the analysis and data to support the need for the access request.

550.03(1)(a) Project Description

Describe the needs being addressed, and define the current problem or deficiency that the project is looking to address or overcome. Using specific performance measures can be helpful; for example, state the average speed or throughput during the A.M. or P.M. peak. The need for improvement should be established using factors such as existing conditions and the conditions anticipated to occur in the analysis years under the "no-build" alternative, or other factors such as the need for system linkage.

Demonstrate that improvements to the local transportation system and the existing interchanges cannot be improved to satisfactorily accommodate the design year travel demands. Describe traffic mitigation measures considered at locations where the level of service (LOS) is (or will be) below agreed-upon service standards in the design year. (See the State Highway System Plan for further information on LOS standards.) Additional measures of effectiveness (such as density, speed changes, delay, and travel times) should be discussed and documented in the Methods and Assumptions Document.

The access point revision should meet regional, not local, travel demands. Describe the local and regional traffic (trip link and/or route choice) benefiting from the proposal.

550.03(2) Policy Point 2: Reasonable Alternatives

Describe the reasonable alternatives that have been evaluated.

Describe all reasonable alternatives that have been considered. These include the design options, locations, project phasing, and transportation system management-type improvements such as ramp metering, public transportation, and HOV facilities that have been assessed and that meet the proposal's design year needs. The alternatives analysis must be the same as that used in the environmental documentation.

After describing each of the alternatives that were proposed, explain why reasonable alternatives were omitted or dismissed from further consideration. Where operational and safety concerns are some of the reasons that alternatives are rejected, the support group may need operational and/or safety analyses for those alternatives (see Policy Point 3 below).

Future projects must be coordinated as described in Policy Point 7, Coordination.

Environmental concerns may preclude consideration of some alternatives. Detailed analysis of sensitive resources and possible concurrence by resource agencies may be required (see Policy Point 8 below).

550.03(3) Policy Point 3: Operational and Crash Analyses

How will the proposal affect safety and traffic operations at year of opening and design year?

Policy Point 3 documents the operational and safety effects of the proposal(s) and the results that support the final proposal, including any mitigation measures that compensate for operational and/or safety tradeoffs. Information from the Basis of Design and Alternatives Comparison Table (see Division 11) can be used to support the analysis in Policy Point 3. Include a conceptual plan of the type and location of the signs proposed to support the design alternative.

The preferred operational alternative is selected, in part, by showing that it will meet the access needs without causing a significant adverse impact on the operation and safety of the freeway and the affected local network, or that the proposal impacts will be mitigated.

Document the results of the following analyses in the report:

- Operational Analysis – "No-Build" Alternative: An operational analysis of the current year, year of opening, and design year for the existing limited access freeway and the affected local roadway system. This is the baseline plus state transportation plan and comprehensive plan improvements expected to exist at the year of opening or design year. All of the alternatives will be compared to the no-build condition. The report should document the calibration process and results that show the current year operations closely match actual field conditions.
- Operational Analysis – "Build" Alternative: An operational analysis of the year of opening and design year for the proposed future freeway and the affected local roadway system.
- Crash Analysis – "Observed crash history": Document the observed crash history, for the most current data years, of the existing limited access freeway and the affected local roadway system. The support team will determine the number of years as well as the scope and detail of this section.

- Crash Analysis – "Proposal(s)": A crash analysis should be performed for the year of opening and design year of the existing limited access freeway and the affected local roadway system for the "no-build," "build," and possibly other scenarios as determined by the support team. The support team will also determine the year of opening and design year as well as the scope and detail of this section.

The data used for the operational and safety analyses must be the same as the data used in the environmental documentation (see Policy Point 8 below). If not, describe and justify the discrepancies in the Methods and Assumptions Document as well as in this section of the IJR. The transportation section of the environmental document should include a similar discussion, and the Methods and Assumption Document should be included in the appendix of the environmental document.

550.03(3)(a) Operational Analyses

Demonstrate that the proposal does not have a significant adverse impact on the operation of the freeway and the affected local roadway system. If there are proposal impacts, explain how the impacts will be mitigated.

To understand the proposal's positive and negative impacts to main line, crossroad, and local system operations, the selection of the appropriate analysis tool(s) is critical. This is a major piece of the assumptions process. Record the support team's tool selection agreement in the Methods and Assumptions Document. FHWA's Traffic Analysis Toolbox provides an overview and details for making the best tool category selection.

Document the selected operational analysis procedures. For complex urban projects, a refined model might be necessary. WSDOT supports the traffic analysis and traffic simulation software listed on the HQ Traffic Operations website: www.wsdot.wa.gov/design/traffic/analysis/

All operational analyses shall be of sufficient detail, and include sufficient data and procedure documentation, to allow independent analysis during FHWA and Headquarters evaluation of the proposal. For Interstate proposals, Headquarters must provide concurrence before it transmits the proposal to FHWA with its recommendation.

Prepare a layout displaying adjacent interchanges/intersections and the data noted below, based on support team determination, which should show:

- Distances between intersections or ramps of a proposed interchange, and those of adjacent existing and known proposed interchanges.
- Design speeds. WSDOT uses a target speed approach for determining design speed. The objective of the target speed approach is to establish the design speed at the desired operating speed (see Chapter 1103).
- Grades.
- Truck volume percentages on the freeway, ramps, and affected roadways.
- Adjustment factors (such as peak hour factors).
- Affected freeway, ramp, and local roadway system traffic volumes for the "no-build" and each "build" option. This will include: A.M. and P.M. peaks (noon peaks, if applicable); turning volumes; average daily traffic (ADT) for the current year; and forecast ADT for year of opening and design year.

- Affected main line, ramp, and local roadway system lane configurations.

The study area of the operational analysis on the local roadway system includes documenting that the local network is able to safely and adequately collect and distribute any new traffic loads resulting from the access point revision. Expand the limits of the study area, if necessary, to analyze the coordination required with an in-place or proposed traffic signal system. Record the limits of the analysis as well as how the limits were established in the project Methods and Assumptions Document.

Document the results of analyzing the existing access and the proposed access point revision at all affected locations within the limits of the study area, such as weave, merge, diverge, ramp terminals, crash sites, and HOV lanes; along the affected section of freeway main line and ramps; and on the affected local roadway system. In the report, highlight the following:

- Any location for which there is a significant adverse impact on the operation or safety of the freeway facility, such as causing a reduction of the operational efficiency of a merge condition at an existing ramp; introducing a weave; or significantly reducing the level of service on the main line due to additional travel demand. Note what will be done to mitigate this adverse impact.
- Any location where a congestion point will be improved or eliminated by the proposal, such as proposed auxiliary lanes or collector-distributor roads for weave sections.
- Any local roadway network conditions that will affect traffic entering or exiting the freeway. If entering traffic is to be metered, explain the effect on the connecting local system (for example, vehicle storage).
- When the existing local and freeway network does not meet agreed-upon level of service standards, show how the proposal will improve the level of service or keep it from becoming worse than the no-build condition in the year of opening and the design year. Level of service should not be the only performance measure evaluated. There are other measures of effectiveness that can be used to illustrate a broader traffic operation perspective.

550.03(3)(b) Crash Analysis

This section describes the two parts of an IJR crash analysis: the existing (observed) condition as well as the proposed “no-build,” “build,” and possibly other scenarios as determined by the support team. It is the intent of this section that future readers will fully understand the existing condition and all of the presented scenarios without the need for other documents. The study limits (area and years) are the same as the study limits of the operational analyses. If the support team determines that some limits are different from the operational analysis, document them by describing and justifying the differences in the Methods and Assumptions Document as well as in Policy Point 3 of the IJR. Document all the tools used and all assumptions made and agreed to as well as the basis and reason(s) for using those tools and assumptions. The data used for the crash analysis must be the same as the data used in the operational analysis and the environmental documentation. If not, describe and justify the differences. (Chapter 321, Sustainable Safety, gives crash analysis guidance.)

Crash analysis data needs to include a disclaimer: “Under Section 409 of Title 23 of the United States Code, crash data is prohibited from use in any litigation against state, tribal, or local government that involves the location(s) mentioned in the crash data.”

550.03(3)(b)(1) Existing (Observed) Portion of Crash Analysis

Identify and document the crash histories, severities, and types for the existing freeway section and the adjacent affected local surface system within the study area as determined by the support team. A five-year crash history is a good default; however, the support team will determine the number of years.

Document all the tools used and all assumptions made and agreed to as well as the basis and reason(s) for using those tools and assumptions.

Detailed list of the existing (observed) portion of the crash analysis:

Document the existing safety performance of the freeway section and the adjacent affected local surface system within the study area.

- Produce a diagram of the crash history of the freeway section and the adjacent affected local surface system within the study limits.
- Analyze the existing performance of the freeway section and the adjacent affected local surface system within the study area for over dispersions of crash types, contributing circumstances, and/or severities.
  - What types of crashes are occurring (overturns, rear-ends, enter-at-angle, hitting fixed object)?
  - What types of crashes are most prevalent?
  - Are there any patterns of crash type or cause?
  - Use ISATe (Enhanced Interchange Safety Analysis Tool) to determine if there are any over dispersions of crash types or causes.
- Determine severity (fatalities, serious injuries, evident injuries, possible injuries, and/or property damage only).
  - What crash severities are most prevalent?
  - Are there any crash severity patterns?
  - Use ISATe to determine if there are any over dispersions of severities.
- Use ISATe to perform an expected safety performance analysis using the observed crashes to determine if the existing safety performance is normal for the existing configuration as compared to others like it (see Chapter 321 for guidance).

550.03(3)(b)(2) Proposed Portion of Crash Analysis

Identify and document the predicted safety performance of the proposed access point revision proposal(s), including the freeway section, speed change lanes, ramps, collector-distributor (c-d) lanes, ramp terminal intersections, and the adjacent affected local surface system, including segments and intersections.

Demonstrate that (1) the final proposal does not have a significant adverse impact on the safety of the freeway or the adjacent affected local surface system, or (2) a list of the mitigation measures mitigate each adverse impact.

Document all the tools used and all assumptions made and agreed to as well as the basis and reason(s) for using those tools and assumptions.

Detailed list of the predicted safety performance portion of the crash analysis.

- Document the predicted safety performance of the freeway section using the Highway Safety Manual (to access ISATe), speed change lanes, ramps, c-d lines, ramp terminal intersections, and the adjacent affected local surface system, including segments and intersections within the study limits for each of the proposed "no-build," "build," and possibly other scenarios and alternatives as determined by the support team.
- Document the design elements that contribute to the predicted safety performance, including types and severities of crashes, especially design elements that contribute to significant adverse safety impacts of the freeway or the adjacent affected local surface system.
- Compare the safety performances of the "no-build" scenario(s) with the safety performance of the proposed scenario(s) to demonstrate that the final proposal(s) do not have a significant adverse impact on the safety of the freeway or the adjacent affected local surface system.
    - Break out fatal and serious injuries in this analysis.

550.03(4) Policy Point 4: Access Connections and Design

Will the proposal provide fully directional interchanges connected to public streets or roads, spaced appropriately, and designed to meet the identified performance needs?

Provide for all directions of traffic movement on Interstate system-to-system type interchanges, unless justified. The intent is to provide full movement at all interchanges, whenever feasible. Partial interchanges are discouraged and will not likely be approved for Interstate access. Less than fully directional interchanges for special-purpose access for transit vehicles, for HOVs, or to or from park & ride lots will be considered on a case-by-case basis.

A proposed new or revised interchange access must connect to a public freeway, road, or street and be endorsed by the local governmental agency or tribal government having jurisdiction over said public freeway, road, or street.

Explain how the proposed access point relates to present and future proposed interchange configurations and the Design Manual spacing criteria. Note that urban and rural interchange spacing for crossroads also includes additional spacing requirements between adjacent ramps, as noted in Chapter 1360.

Develop the proposal in sufficient detail to conduct a design and operational analysis. Include the number of lanes, horizontal and vertical curvature, lateral clearance, lane width, shoulder width, weaving distance, ramp taper, interchange spacing, and all traffic movements. This information is presented as a sketch or a more complex layout, depending on the complexity of the proposal. The resulting footprint should be used to assess the potential environmental impacts for each alternative (See Policy Point 8 below).

The status of all known or anticipated project design analyses must be noted in this policy point, as described in Chapter 300.

550.03(5) Policy Point 5: Land Use and Transportation Plans

Is the proposed access point revision compatible with all land use and transportation plans for the area?

Show that the proposal is consistent with local and regional land use and transportation plans. Before final approval, all requests for access point revisions must be consistent with the regional or statewide transportation plan, as appropriate. The proposed access point revision may affect adjacent land use and, conversely, land use may affect the travel demand generated. Therefore, reference and show compatibility with the land use plans, zoning controls, and transportation ordinances in the affected area.

Explain the consistency of the proposed access point revision with the plans and studies, the applicable provisions of 23 CFR Part 450, the applicable transportation conformity requirements of 40 CFR Parts 51 and 93, and Chapter 36.70A RCW.

The support team reviews regional and state transportation plans to determine whether the need and proposed solution are already identified. Proposals to request new or reconstructed interchanges must be consistent with those plans.

If the proposed access is not specifically referenced in the transportation plans, define its consistency with the plans and indicate the process for the responsible planning agency to incorporate the project. In urbanized areas, the plan refinement must be adopted by the metropolitan planning organization (MPO) before the project is designed. The action must also be consistent with the multimodal State Transportation Plan. The results should be consistent with the data used to support the Social and Economic analysis conducted in the Environmental Documentation (see Policy Point 8 below).

550.03(6) Policy Point 6: Future Interchanges

Is the proposed access point revision compatible with a comprehensive network plan? Is the proposal compatible with other known new access points and known revisions to existing points?

The report must demonstrate that the proposed access point revision is compatible with other planned access points and revisions to existing points.

Reference and summarize any comprehensive freeway network study, plan refinement study, or traffic circulation study.

Explain the consistency of the proposed access point revision with those studies.

550.03(7) Policy Point 7: Coordination

Are all coordinating projects and actions programmed and funded?

When the request for an access point revision is generated by new or expanded development, demonstrate appropriate coordination between the development and the changes to the transportation system. Coordination will include local agencies, local groups, and public outreach. See Section 1100.03 Community Engagement.

Show that the proposal includes a commitment to complete the other non-interchange/non-intersection improvements that are necessary for the interchange/intersection to function as proposed. For example, if improvements to the local circulation system are necessary for the

proposal to operate, they must be in place before new ramps are opened to traffic. If future reconstruction is part of the mitigation for design year level of service, the reconstruction projects must be in the State Highway System Plan and Regional Transportation Plan.

All elements for improvements are encouraged to include known fiscal commitments and an anticipated time for completion. If the project is to be constructed in phases, it must be demonstrated in Policy Point 3 that each phase can function independently and does not affect the safety and operational efficiency of the freeway. Identify the funding sources, both existing and projected, and the estimated time of completion for each project phase. Review PEL principles to ensure that community engagement efforts implemented during a planning/feasibility study IJR will be robust enough to carry forward into the environmental documentation phase (see Policy Point 8 below).

550.03(8) Policy Point 8: Environmental Processes

What is the status of the proposal's environmental processes? This section should be something more than just a status report of the environmental process; it should be a brief summary of the environmental process.

All requests must closely adhere to the planning and environmental review processes as required in 23 CFR parts 450 and 771. This means the final FHWA approval of requests for new or revised access cannot precede the completion of these processes or necessary actions.

All requests for access point revisions on freeways must contain information on the status of the environmental approval and permitting processes.

The following are just a few examples of environmental status information that may apply:

- Have the environmental documents been approved? If not, when is the anticipated approval date?
- Did the study team determine that a planning/feasibility study will be completed for the IJR? Will PEL principles be followed during the study to minimize rework during the environmental documentation phase of the project as recorded in the Methods and Assumptions document?
- What applicable permits and approvals have been obtained and/or are pending?
- Are there hearings still to be held?
- Is the environmental process waiting for an engineering and operational acceptability decision?
- Are the assumptions, methodology, study area, traffic analysis, crash data, coordination and public outreach results used in the environmental analysis consistent with the IJR? If no, explain why not and provide justification.

The environmental documentation process followed for the IJR will be the same process used for any other WSDOT project consistent with the respective environmental classification (CE, EA, EIS). Follow the procedures outlined in the *Environmental Manual* Chapter 400 and the WSDOT EA/EIS and CE web pages. A general description of how this work coincides with the IJR process is provided in Exhibits 550-3 and 550-4. Consult with your Region Environmental Office and the HQ NEPA/SEPA Specialist prior to beginning work on the Environmental Documentation to

ensure that the effort is still consistent with the environmental classification made in the Methods and Assumption document.

If the project is being led by a local agency, follow the guidance provided in *NEPA Categorical Exclusions A Guidebook for Local Agencies*, WSDOT.

550.04 Report Organization and Appendices

Begin the IJR with an executive summary. Briefly describe the access point revision being submitted for a decision and why the revision is needed. Include a brief summary of the proposal.

The IJR must be assembled in the policy point order noted in 550.02(2).

Formatting for the IJR includes providing numbered tabs in the report for each policy point section and each appendix and numbering all pages, including references and appendices. A suggestion for page numbering is to number each individual section, such as "Policy Point 3, PP3–4" and "Appendix 2, A2–25." This allows for changes without renumbering the entire report.

On the bottom of each page, place the revision date for each version of the IJR. As an individual page is updated, this revision date will help track the most current version of that page. Also, include the title of the report on the bottom of each page.

Use a three-ring binder for ease of page replacement. Do not use comb or spiral binding.

Appendix A is reserved for the Methods and Assumptions Document. Include meeting notes where subsequent decisions are made as additional appendices to the original signed document.

Additional appendices may include documents such as Intersection Control Analysis, technical memorandums, memos, and traffic analysis operations output.

550.05 IJR Review and Approval

Concurrence and approval of a new or revised access point is based on the IJR. The IJR must contain sufficient information about and evaluation/analysis of the proposal to provide assurance that the safety and operations of the freeway and local systems are not significantly impacted.

The region, or proponents, with the help of the support team, prepares the IJR and submits four draft copies, including backup traffic data, to the HQ Access and Hearings Section for review.

For a final IJR submittal, contact the HQ Access and Hearing Section for the necessary number of copies.

550.05(1) Interstate IJR Approval

On Interstate projects, a submittal letter is sent by the region to the HQ Access and Hearings Section, requesting final FHWA approval of the IJR. Interstate IJRs are submitted by Headquarters to FHWA for approval.

Interstate access point revisions are reviewed by both WSDOT Headquarters and FHWA. This can be a two-step process:

- If environmental documentation has not yet been approved, an FHWA finding of engineering and operational acceptability can be given.
- If the environmental documentation is complete, final approval can be given.

Some Interstate IJRs are reviewed and approved by the Washington FHWA Division Office. Other Interstate IJRs are reviewed and approved by the FHWA Headquarters Office in Washington DC. Additional review time is necessary for reports that have to be submitted to Washington DC (see Exhibit 550-1).

Final IJR approval by FHWA is provided when the appropriate final environmental decision is complete: ECS, FONSI, or ROD.

550.05(2) Non-Interstate IJR Approval

On non-Interstate projects, concurrence from the support team is required on the Methods and Assumptions to document the acceptance of the scope and complexity of the IJR or the acceptance of the decision that an IJR is not required. If an IJR is prepared, the appropriate WSDOT HQ Assistant State Design Engineer grants the final approval (see Exhibits 550-2 and 550-4).

This can be a two-step process:

- If environmental documentation has not yet been approved, a finding of engineering and operational acceptability can be given.
- If the environmental documentation is complete, final approval can be given.

550.06 Updating an IJR

Recognizing that the time period between the approval of the IJR, completion of the environmental documentation, and the construction contract commonly spans several years, the approved IJR will be reviewed and updated to identify changes that may have occurred during this time period. If no work has begun within three years of completion of the environmental documentation, a re-evaluation of the CE/EA/EIS will be required. Submit a summary assessment to the HQ Design Office for evaluation to determine whether the IJR needs to be updated. Contact the HQ NEPA/SEPA Specialist to determine if the environmental documentation must be re-evaluated. The HQ Design Office will forward the assessment to FHWA if necessary. The assessment is a document summarizing the significant changes since it was approved. Contact the HQ Access and Hearings Section and the NEPA/SEPA Specialist to coordinate this summary assessment.

If the project is being led by a local agency, follow the guidance provided in *NEPA Categorical Exclusions A Guidebook for Local Agencies*, WSDOT.

550.07 Documentation

Refer to Chapter 300 for design documentation requirements.

550.08 References

550.08(1) Federal/State Laws and Codes

23 Code of Federal Regulations (CFR) Part 450 (implementing 23 United States Code [USC] Section 135)

40 CFR Parts 51 and 93 (regarding federal conformity with state and federal air quality implementation plans)

23 USC Sections 111 (requires the U.S. Secretary of Transportation to approve access revisions to the Interstate System), 134 (metropolitan transportation planning), and 135 (statewide transportation planning)

FHWA "Interstate System Access Information Guide"
www.fhwa.dot.gov/design/interstate/pubs/access/access.pdf

Notice of policy statement: "Additional Interchanges to the Interstate System," FHWA notice published in the Federal Register, February 11, 1998 (Vol. 63, No. 28)
www.access.gpo.gov/su_docs/fedreg/a980211c.html

Revised Code of Washington (RCW) 36.70A, Growth management – Planning by selected counties and cities

550.08(2) Design Guidance and Supporting Information

Design Manual, Chapter 320, Traffic Analysis

Design Manual, Chapter 321, Sustainable Safety

Design Manual Glossary – Defines many of the terms encountered in this chapter

FHWA Traffic Analysis Toolbox (tools used in support of traffic operations analyses)
www.ops.fhwa.dot.gov/trafficanalysistools/index.htm

FHWA Environmental Review Toolkit
www.environment.fhwa.dot.gov/integ/index.asp

Highway Capacity Manual, (HCM) 2010, Transportation Research Council

Highway Safety Manual (HSM), AASHTO, 2010

Local Agency Guidelines (LAG), M 36-63, WSDOT

NEPA Categorical Exclusions A Guidebook for Local Agencies, WSDOT

State Highway System Plan www.wsdot.wa.gov/planning/HSP

WSDOT GeoPortal – Tool for viewing WSDOT spatial data (like Functional Class, Interchange Drawings, City Limits, and State Routes) via a web browser. Users can check a box to select from a variety of base maps and data layers.
http://wwwi.wsdot.wa.gov/planning/data/gis/tools/geoportal_int.htm

WSDOT HQ Access and Hearings web page (provides guidance and timelines for preparing IJRs and example Methods and Assumptions Documents):
www.wsdot.wa.gov/design/accessandhearings

Exhibit 550-1 Interstate Routes: IJR Content and Review Levels

Project Type	Support Team	Policy Point								Concurrence	Approval
		1	2	3	4	5	6	7	8		
Interstate Routes											
New freeway-to-crossroad interchange in a Transportation Management Area[1]	Yes	✓	✓	✓	✓	✓	✓	✓	✓	FHWA and HQ	FHWA DC
New partial interchange	Yes	✓	✓	✓	✓	✓	✓	✓	✓	FHWA and HQ	FHWA DC
New HOV direct access	Yes	✓	✓	✓	✓	✓	✓	✓	✓	FHWA and HQ	FHWA DC
New freeway-to-freeway interchange	Yes	✓	✓	✓	✓	✓	✓	✓	✓	FHWA and HQ	FHWA DC
Revision to freeway-to-freeway interchange in a Transportation Management Area[1][2]	Yes	✓	✓	✓	✓	✓	✓	✓	✓	FHWA and HQ	FHWA
New freeway-to-crossroad interchange not in a Transportation Management Area[1]	Yes	✓	✓	✓	✓	✓	✓	✓	✓	HQ	FHWA
Revision to freeway-to-freeway interchange not in a Transportation Management Area[1][2]	Yes	✓	✓	✓	✓	✓	✓	✓	✓	HQ	FHWA
Revision to interchange[2][3]	Yes	✓	✓	✓	✓	✓	✓	✓	✓	HQ	FHWA
Transit flyer stop on main line	Yes	✓	✓	✓	✓	✓	✓	✓	✓	HQ	FHWA
Transit flyer stop on an on-ramp	No	✓		✓	✓				✓	HQ	FHWA
Addition of entrance or exit ramps that complete basic movements at an existing interchange	Yes	✓	✓	✓	✓	✓	✓	✓	✓	HQ	FHWA
Abandonment of a ramp[4]	Yes	✓	✓	✓	✓	✓	✓	✓	✓	HQ	FHWA
Locked gate [6]	No	✓			[5]				✓	HQ	FHWA
Access breaks that do not allow any type of access to main line or ramps	No	✓	✓		[5]				✓	HQ	FHWA
Pedestrian structure	No	✓			[5]				✓	HQ	FHWA
Construction/emergency access break	No	✓	✓	✓	✓				✓	Region	FHWA

Notes:

All policy points must be addressed on all studies. The scale and scope of the project dictate the level of effort needed to address each policy point. Blank cells in the table above indicate that the policy point will need to be addressed briefly in the IJR. Consult the HQ Access and Hearings Section for direction.

[1] In Washington, designated Transportation Management Areas include Clark, King, Kitsap, Pierce, Snohomish, and Spokane counties.

[2] "Revision" includes changes in interchange configuration, even though the number of access points does not change. Changing from a cloverleaf to a directional interchange is an example of a "revision."

[3] Revisions that might adversely affect the level of service of the through lanes. Examples include: doubling lanes for an on-ramp with double entry to the freeway; adding a loop ramp to an existing diamond interchange; and replacing a diamond ramp with a loop ramp. Revisions to the ramp terminal intersections may not require an IJR unless the traffic analysis shows an impact to the main line traffic.

[4] Unless it is a condition of the original approval.

[5] Update the right of way/limited access plan as necessary.

[6] As part of Policy Point 1, include a narrative stating that all other alternatives are not feasible.

Exhibit 550-2 Non-Interstate Routes: IJR Content and Review Levels

Project Type	Support Team	Policy Point								Concurrence	Approval
		1	2	3	4	5	6	7	8		
Non-Interstate Routes											
New freeway-to-crossroad interchange on a predominately grade-separated corridor	Yes	✓	✓	✓	✓	✓	✓	✓	✓	Region	HQ
New freeway-to-freeway interchange	Yes	✓	✓	✓	✓	✓	✓	✓	✓	Region	HQ
Revision to freeway-to-freeway interchange	Yes	✓	✓	✓	✓	✓	✓	✓	✓	Region	HQ
New freeway-to-crossroad interchange on a predominately at-grade corridor[5]	No	✓		✓	✓				✓	Region	HQ
Revision to interchange[1]	No	✓		✓	✓				✓	Region	HQ
Addition of entrance or exit ramps that complete basic movements at an existing interchange	No	✓		✓	✓				✓	Region	HQ
Abandonment of a ramp[2]	No	✓		✓					✓	Region	HQ
Transit flyer stop on main line	Yes	✓	✓	✓	✓	✓	✓	✓	✓	Region	HQ
Transit flyer stop on an on-ramp	No	✓		✓	✓				✓	Region	HQ
Locked gate[4]	No	✓			[3]				✓	Region	HQ
Pedestrian structure	No	✓			[3]				✓	Region	HQ
Construction/emergency access break	No	✓	✓	✓					✓	Region	HQ

Notes:

Policy points to be addressed will be determined by the IJR support team. The scale and scope of the project dictate the level of effort needed to address each policy point. Blank cells in the table above indicate that the policy point will need to be addressed briefly in the IJR as determined by the support team. Consult the HQ Access and Hearings Section for direction.

[1] Revisions that might adversely affect the level of service of the through lanes. Examples include: doubling lanes for an on-ramp with double entry to the freeway; adding a loop ramp to an existing diamond interchange; and replacing a diamond ramp with a loop ramp.

[2] Unless it is a condition of the original approval.

[3] Update the right of way/limited access plan as necessary.

[4] As part of Policy Point 1, include a narrative stating that all other alternatives are not feasible.

[5] Example: Revising an existing at-grade intersection into an access controlled grade-separated interchange.

Exhibit 550-3 Interstate IJR: Process Flow Chart




Exhibit 550-3 Interstate IJR: Process Flow Chart (continued)




Exhibit 550-4 Non-Interstate IJR: Process Flow Chart




Exhibit 550-5 Methods and Assumptions Document for IJR: Concurrence Form Example

Methods and Assumptions Document Concurrence Form
for Interchange Justification Report
"Project Title" "MP to MP"

We the undersigned hereby concur with the methods and assumptions used for the (INSERT PROJECT NAME) Interchange Justification Report.	
IJR Engineer of Record:	**By:**_____ **Date:**_____
Traffic Analysis Engineer	**By:**_____ **Date:**_____
Region Traffic Engineer	**By:**_____ **Date:**_____
Project Development Engineer	**By:**_____ **Date:**_____
Development Services and Access Manager	**By:**_____ **Date:**_____
Region Environmental Manager	**By:**_____ **Date:**_____
Assistant State Design Engineer	**By:**_____ **Date:**_____
FHWA Area Engineer	**By:**_____ **Date:**_____
FHWA Safety and Design Engineer	**By:**_____ **Date:**_____
City Representative	**By:**_____ **Date:**_____
County Representative	**By:**_____ **Date:**_____

Exhibit 550-6 IJR: Stamped Cover Sheet Example

Interchange Justification Report
"Project Title"
"MP to MP"

This **Interchange Justification Report** has been prepared under my direct supervision, in accordance with Chapter 18.43 RCW and appropriate Washington State Department of Transportation manuals.

☐ **IJR Engineer of Record**

By:_____ **P.E.**
Project Engineer

Date:_____

☐ **Traffic Analysis Engineer**

By:_____ **P.E.**
Traffic Analysis Engineer

Date:_____

☐ **Concurrence –**
Region Traffic Engineer

By:_____ **P.E.**

Date:_____

☐ **Concurrence –**
Project Development Engineer

By:_____ **P.E.**

Date:_____

☐ **Concurrence –**
Environmental Manager

By:_____

Date:_____

☐ **WSDOT Approval –**
Development Services and Access Manager

By:_____ **P.E.**

Date:_____

☐ **WSDOT Approval –**
Assistant State Design Engineer

By:_____ **P.E.**

Date:_____

☐ **FHWA Approval –**
FHWA Safety and Design Engineer

By:_____

Date:_____

Chapter 560 Fencing

560.01 General
560.02 Design Criteria
560.03 Fencing Types
560.04 Gates
560.05 Procedure
560.06 Documentation
560.07 References

560.01 General

Fencing is provided primarily to discourage encroachment onto Washington State Department of Transportation (WSDOT) highway right of way from adjacent property, to delineate the right of way, and to replace fencing that has been disrupted by construction.

Encroachment onto the right of way is discouraged to limit the presence of people and animals that might disrupt the efficient flow of traffic on the facility. Although not the primary intent, fencing does provide some separation between people, animals, traffic flow, and other features.

560.02 Design Criteria

560.02(1) General

Fencing on a continuous alignment usually has a pleasing appearance and is the most economical to construct and maintain. The recommended practice is to locate fencing on or, depending on the terrain, 12 inches inside the right of way line.

Where the anticipated or existing right of way line has abrupt irregularities over short distances, coordinate with Maintenance and Real Estate Services personnel to dispose of the irregularities as excess property (where possible) and fence the final property line in a manner acceptable to Maintenance.

Whenever possible, preserve the natural assets of the surrounding area and minimize the number of fence types on any particular project.

560.02(2) Limited Access Highways

On highways with full and partial limited access control, fencing is mandatory unless it has been established that such fencing may be deferred. Fencing is not required for modified limited access control areas, but may be installed where appropriate. Fencing is required between frontage roads and adjacent parking or pedestrian areas (such as rest areas and flyer stops) and highway lanes or ramps unless other barriers are used to discourage access violations.

On new alignment, fencing is not provided between the frontage road and abutting property unless the abutting property was enclosed prior to highway construction. Such fencing is normally part of the right of way negotiation.

Unless there is a possibility of access control violation, fencing installation may be deferred until needed at the following locations:

- In areas where rough topography or dense vegetation provides a natural barrier.
- Along rivers or other natural bodies of water.
- In sagebrush country that is sparsely settled.
- In areas with high snowfall levels and sparse population.
- On long sections of undeveloped public or private lands not previously fenced.

When in doubt about fencing installation, consult the Headquarters (HQ) Access and Hearings Manager.

560.02(3) Managed Access Highways

Fencing is not required for managed access highways. When highway construction will destroy the fence of an abutting property owner (which was originally constructed on private property), the cost of replacement fencing may be included in the right of way payment. When the fences of several property owners will be impacted, it may be cost-effective to replace the fences as part of the project.

If fencing is essential to the safe operation of the highway, it will be constructed and maintained by the state. An example is the separation of traveled highway lanes from adjacent facilities with parking or pedestrian areas (such as rest areas and flyer stops).

560.02(4) Special Sites

Fencing may be needed at special sites such as pit sites, stockpiles, borrow areas, and stormwater detention facilities.

Fencing is not normally installed around stormwater detention ponds. Evaluate the need to provide fencing around stormwater detention facilities when pedestrians or bicyclists are frequently present. Document your decision in the Design Documentation Package.

The following conditions suggest a need to evaluate fencing:

- Children or persons with mobility impairments are frequently present in significant numbers in locations adjacent to the facility, such as routes identified in school walk route plans or nearby residential areas or parks.
- Water depth reaches or exceeds 12 inches for several days.
- Sideslopes into the facility are steeper than 3H:1V.

Fencing proposed at sites that will be outside WSDOT right of way requires that local ordinances be followed if they are more stringent than WSDOT's.

Wetland mitigation sites are not normally fenced. When evaluating fencing for wetland mitigation sites, balance the need to restrict human access for safety considerations (such as the presence of children) with the need to provide animal habitat.

Other special sites where fencing may be required are addressed in the following chapters:

- Chapter 720, Bridges (refers to protective screening)
- Chapter 1510, Pedestrian Design Considerations

- Chapter 1520, Bicycle Facilities

The fencing types and designs for special sites are determined by the requirements of each situation.

560.03 Fencing Types

560.03(1) Chain Link

Installation of chain link fence is appropriate for maximum protection against right of way encroachment on sections of high-volume highways in the following locations:

- Along existing business districts adjacent to a freeway.
- Between freeways and adjacent parallel city streets.
- Where existing streets have been cut off by freeway construction.
- In industrial areas.
- At large residential developments.
- On military reservations.
- At schools and colleges.
- In recreational and athletic areas.
- In developed areas at the intersection of two limited access highways.
- At any other location where a barrier is needed to protect against pedestrian, bicyclist, or livestock encroachment in limited access areas.

For roadway sections in rock cuts, see Chapter 1239.

The *Standard Plans* contains details for the approved types of chain link fence. The recommended uses for each type of fence are as follows:

560.03(1)(a) Type 3

This is a high fence for areas of intensified use, such as industrial areas or school playgrounds. Use this fence for new installations of high fencing. It may be used within the Design Clear Zone.

560.03(1)(b) Type 4

This is a lower fence for special use, such as between the traveled highway lanes and a rest area or flyer stop or as a rest area boundary fence if required by the development of the surrounding area. This fence may be used along a bike path or hiking trail to separate it from an adjacent roadway.

Justify why corrective action is not taken when existing fencing with a rigid top rail will be left in place within the limits of a proposed project. For cases where a more rigid fence is needed, contact the HQ Design Office.

Coated galvanized chain link fence is available in various colors and may be considered in areas where aesthetic considerations are important. Coated ungalvanized chain link fence is not recommended.

560.03(2) Wire Fencing

The *Standard Plans* and the *Standard Specifications* contain details for the two approved types of wire fence. The recommended uses for each type of fence are as follows:

560.03(2)(a) Type 1

This fence is used in urban and suburban areas where improvements along the right of way are infrequent and future development is not anticipated. It may also be used adjacent to livestock grazing areas. The lower portion of this fence is wire mesh and provides a barrier to children and small animals.

560.03(2)(b) Type 2

This fence is used in farming areas to limit highway crossings by farm vehicles to designated approaches. These areas include irrigation districts to prevent ditch riders, maintenance personnel, and farmers from making unauthorized highway crossings, and where new alignment crosses parcels previously enclosed by barbed wire.

560.03(3) Other Considerations

Extremely tall fences (7 to 10 feet high) may be used in areas where there are exceptional conditions such as large concentrations of deer or elk. (See the region Environmental Services Office and the *Roadside Manual* concerning wildlife management.)

Metal fencing can interfere with airport traffic control radar. When locating fencing in the vicinity of an airport, contact the Federal Aviation Administration to determine whether metal fence will create radar interference at the airport. If so, use nonmetallic fencing.

Do not straddle or obstruct surveying monuments with any type of fencing.

560.04 Gates

Keep the number of fence gates along limited access highways to a minimum. On limited access highways, all new gates must be approved as described in Chapter 550.

Usually such gates are necessary only to allow highway maintenance personnel and operating equipment to reach the state right of way without using the highway or freeway main line. Gates may be needed to provide access to utility supports, manholes, and so on, located within the right of way.

Use gates of the same type as each fence, and provide locks to deter unauthorized use.

In highly developed and landscaped areas where maintenance equipment is parked outside the fence, provide the double gate shown in the Standard Plans.

Where continuous fencing is not provided on limited access highways (see Chapter 530), approaches are normally gated and locked, with a short section of fence on both sides of the gate.

560.05 Procedure

Fencing is addressed in the access report (see Chapter 530) and the Plans, Specifications, and Estimates, in accordance with the *Plans Preparation Manual*.

560.06 Documentation

Refer to Chapter 300 for design documentation requirements.

560.07 References

560.07(1) Design Guidance

Plans Preparation Manual, M 22-31, WSDOT

Roadside Manual, M 25-30, WSDOT

Standard Plans for Road, Bridge, and Municipal Construction (*Standard Plans*), M 21-01, WSDOT

Standard Specifications for Road, Bridge, and Municipal Construction (*Standard Specifications*), M 41-10, WSDOT

Chapter 610 Investigation of Soils, Rock, and Surfacing Materials

610.01 General
610.02 References
610.03 Materials Sources
610.04 Geotechnical Investigation, Design, and Reporting
610.05 Use of Geotechnical Consultants
610.06 Geotechnical Work by Others
610.07 Surfacing Report
610.08 Documentation

610.01 General

It is the Washington State Department of Transportation's (WSDOT's) responsibility to understand the characteristics of the soil and rock materials that support or are adjacent to a transportation facility so that, when designed, constructed, and maintained, the facility will be adequate to safely carry the estimated traffic. It is also the responsibility of WSDOT to ensure the quality and quantity of all borrow, soils, rock, and surfacing materials used in the construction of transportation facilities. Specific requirements for geotechnical investigation, design, construction, and maintenance support are set forth in the WSDOT *Geotechnical Design Manual*.

The following information serves as guidance in the above areas. When a project consists of a surface overlay on an existing highway, the *WSDOT Pavement Policy* is used.

Before making project budget and schedule commitments to the Legislature, other agencies, and the public, it is necessary to identify the extent and estimated cost for a project. Contact the Region Materials Engineer (RME) and the Headquarters (HQ) Geotechnical Office as early as possible to obtain conceptual-level recommendations regarding how the project soil, rock, and groundwater conditions may affect the design of the project elements. The project soil, rock, and groundwater conditions, and the availability, quantity, and quality of borrow and surfacing materials, can affect the project scope, schedule, and budget.

Coordinate early in your project for geotechnical reporting and design.

The RME and the HQ Geotechnical Office will use existing subsurface information and their knowledge of the project area to assess the subsurface conditions within the project limits. If there is little information available or the information is poor, and the subsurface conditions have the potential to significantly affect the project budget or schedule, it may be necessary to obtain a limited number of geotechnical borings or test pits during Project Definition to assess soil, rock, and groundwater conditions within the project limits. Once the Project Definition has been developed and project funding secured, a more detailed geotechnical investigation follows during the design and Plans, Specifications, and Estimates (PS&E) phases.

It is essential to involve the RME and the HQ Geotechnical Office in the design as soon as possible once the need for geotechnical work is identified. (See 610.04(3) for time-estimate information.) If major changes occur as the project is developed, inform the RME and the HQ Geotechnical Office as soon as possible so that the geotechnical design can be adapted to the changes without significant delay to the project.

610.02 References

610.02(1) Design Guidance

Construction Manual, M 41-01, WSDOT

Geotechnical Design Manual, M 46-03, WSDOT

Hydraulics Manual, M 23-03, WSDOT

Plans Preparation Manual, M 22-31, WSDOT

Standard Plans for Road, Bridge, and Municipal Construction (*Standard Plans*), M 21-01, WSDOT

Standard Specifications for Road, Bridge, and Municipal Construction (Standard Specifications), M 41-10, WSDOT

WSDOT Pavement Policy – See Pavements website:
www.wsdot.wa.gov/business/materialslab/pavements/default.htm

610.03 Materials Sources

610.03(1) General

The region Project Development Engineer determines when a materials source is needed. The RME determines the best materials source for the project (see Exhibit 610-1). It is preferred that existing approved materials source sites be used when there are suitable sites available. When there are no approved sites available, the RME determines the locations for new materials sources. The RME contacts the HQ Geotechnical Office to provide a geotechnical investigation for the proposed site. The HQ Geotechnical Office provides geologic mapping of the site; develops a subsurface exploration plan and cost estimate; conducts the subsurface investigation; develops a subsurface geologic model including groundwater; evaluates slope stability issues; and makes recommendations. The HQ Geotechnical Office develops and provides a geotechnical report with materials source development recommendations to the RME. The RME uses this report and materials source recommendations to develop the Materials Source Report and to identify the quantity and quality of material that are intended for the life of the materials source.

Specific requirements for materials source investigations are set forth in the *Geotechnical Design Manual*.

610.03(2) Materials Source Approval

The HQ Geotechnical Office must review and approve the Materials Source Report produced by the RME to ensure consistency with the geotechnical report produced by the HQ Geotechnical Office.

The HQ Materials Office and the HQ Design Office must approve each pit or quarry site before it is purchased, leased, or acquired on a royalty basis. Until the approval process is complete, the project cannot be advertised for bids. Local and state permits are required for materials sources. To avoid delay in advertising the project, begin the site investigations and permitting process in the early stages of the Project Definition phase.

610.04 Geotechnical Investigation, Design, and Reporting

610.04(1) General

A geotechnical investigation is conducted on all projects that involve significant grading quantities (including state-owned materials source development), unstable ground, foundations for structures, and groundwater impacts (including infiltration). The goal of the geotechnical investigation is to preserve the safety of those who use the facility, as well as to preserve the economic investment by the state of Washington. Additional requirements regarding geotechnical investigations and who conducts these investigations are set forth in the *Geotechnical Design Manual*.

610.04(2) Key Contacts for Initiating Geotechnical Work

For regions, the RME is the first person to contact for geotechnical work. Projects with structures designed by the HQ Bridge and Structures Office, Washington State Ferries (WSF) projects, and Urban Corridors projects generally require the involvement of the HQ Geotechnical Office. These particular WSDOT offices should contact the HQ Geotechnical Office directly for their geotechnical project needs. The specific roles and responsibilities of the RME and HQ Geotechnical Office, including application to the Project Management Process (PMP), are set forth in the *Geotechnical Design Manual*.

For information on retaining walls and noise walls, see *Design Manual* Chapters 730 and 740, respectively. For geosynthetic design, see Chapter 630.

610.04(3) Scheduling Considerations for Geotechnical Work

The region Project Office, the HQ Bridge and Structures Office, the WSF, and the HQ Facilities Office are responsible for identifying the potential need for geotechnical work and requesting time and budget estimates from the RME or the HQ Geotechnical Office as early as possible to prevent delays to the project.

Once the geotechnical design request and the site data are received by the RME or the HQ Geotechnical Office, it can take from two to six months or more to complete the geotechnical design. Design completion depends on the complexity of the project, whether or not test holes are needed, current workload, the need to give the work to consultants, and how long it takes to obtain environmental permits and rights of entry.

If a consultant must be used, the minimum time required to complete a design (for even a simple project) is typically two and a half months.

In true emergency situations (such as a highway blocked by a landslide or a collapsed bridge), it is possible to get geotechnical design work completed (in-house or by consultants) more rapidly to at least provide a design for temporary mitigation.

Consider all of these factors when deciding how soon (in general, as early as possible) to initiate the geotechnical work for a project.

To incorporate geotechnical scheduling considerations into the overall project schedule, see the *Geotechnical Design Manual*, which provides a description and discussion of the Master Deliverables List (MDL) as it applies to geotechnical work.

610.04(4) Site Data and Permits Needed to Initiate Geotechnical Work

610.04(4)(a) Geotechnical Work During Project Definition Phase

To initiate geotechnical work on a project during the Project Definition phase, provide the following information:

1. Project description.
2. Plan view or description showing the proposed alignment or alignment alternative(s).
3. Description of project scope as it relates to geotechnical features such as major cuts and fills, walls, structures, and potential stormwater facilities.

610.04(4)(b) Geotechnical Work During Design and PS&E Phases

To initiate geotechnical work on a project during the design and PS&E phases, provide the following information:

1. Project description.
2. Plan sheets showing:
   - Station and location of cuts, fills, walls, bridges, retention/detention ponds, and other geotechnical features to be designed.
   - Existing utilities; as-built plans are acceptable.
   - Right of way limits.
   - Wetlands.
   - Drainage features.
   - Existing structures.
   - Other features or constraints that could affect the geotechnical design or investigation.
3. Electronic files, or cross sections every 50 feet or as appropriate, to define existing and new ground line above and below walls, cuts, fills, and other pertinent information.
   - Show stationing.
   - Show locations of existing utilities, right of way lines, wetlands, and other constraints.
   - Show locations of existing structures that might contribute load to the cut, fill, wall, or other structure.
4. Right of entry agreements and permits required for geotechnical investigation.
5. Due date and work order number.
6. Contact person.

When the alignment and any constraints (as noted above) are staked, the stationing on the plans and in the field must be in the same units. Physical surveys are preferred to photogrammetric surveys to ensure adequate accuracy of the site data.

Permits and agreements to be supplied by the region might include the following:

- HPA
- Shoreline permits
- Tribal lands and waters
- Railroad easement and right of way
- City, county, or local agency use permits
- Sensitive area ordinance permits

The region Project Office is also responsible for providing survey locations of test holes once the test holes have been drilled. The survey information includes the station, offset, elevation, and test hole coordinates. Coordinates are the latitude and longitude or state plane coordinates (north or south as appropriate), but not project coordinates.

610.04(5) Overview of Geotechnical Design Objectives for the Various Project Stages

Geotechnical design objectives for the various design phases are described in the *Geotechnical Design Manual*.

610.04(6) Earthwork

610.04(6)(a) Project Definition

The designer contacts and meets with the RME (and the HQ Geotechnical Office as needed) at the project site to conduct a field review to help identify the geotechnical issues for the project.

In general, if soil/rock conditions are poor and/or large cuts or fills are anticipated, the RME requests that the HQ Geotechnical Office participate in the field review and reporting efforts.

The designer provides a description and location of the proposed earthwork to the RME as follows:

- For widening of existing facilities, the anticipated width, length, and location of the widening, relative to the current facility, are provided.
- For realignments, the approximate new location proposed for the facility is provided.
- Locations in terms of length can be by milepost or stations.

A brief conceptual-level report that summarizes the results of the investigation is provided to the designer.

610.04(6)(b) Project Design

Geotechnical data necessary to allow completion of the PS&E-level design is compiled during the design phase. This includes soil borings, testing, and geotechnical design based on final geometric data. Detailed design of cut and fill slopes can be done once the roadway geometry is established and geotechnical data are available. The purpose of this design effort is to determine the maximum stable cut or fill slope and, for fills, the potential for short- and long-term settlement. Also, the usability of the cut materials and the type of borrow needed for the project (if any) are evaluated. Evaluate the use of soil bioengineering as an option for building steeper slopes or to prevent surface erosion. (See Roadside Manual Chapter 740, Soil Bioengineering, for more information.)

The designer requests a geotechnical report from the RME. The site data given in 610.04(4), as applicable, is provided. It is important that the request for the geotechnical report be made as early as possible in the design phase. Cost and schedule requirements to generate the report are project-specific and can vary widely. The time required to obtain permits and rights of entry must be considered when establishing schedule requirements.

The *Geotechnical Design Manual*, Chapter 24, summarizes the type of information and recommendations that are typically included in the geotechnical report for earthwork. The recommendations should include the background regarding analysis approach and any agreements with the region or other customers regarding the definition of acceptable level of risk.

The region Project Office uses the report to finalize design decisions for the project. To meet slope stability requirements, additional right of way might be required or a wall might be needed. Wall design is covered in Chapter 730. Construction timing might require importing material rather than using cut materials. The report is used to address this and other constructibility issues. The report is also used to proceed with completion of the PS&E.

610.04(6)(c) PS&E Development

Adequate geotechnical design information to complete the PS&E is typically received during the design phase. Additional geotechnical work might be needed when right of way cannot be acquired, restrictions are included in permits, or other requirements are added that result in changes to the design.

Special provisions and plan details, if not received as part of the report provided during design, are developed with the assistance of the RME or the HQ Geotechnical Office. The designer uses this information, as well as the design phase report, to complete the PS&E documents. Both the region Materials Laboratory and the HQ Geotechnical Office can review (if requested) the contract plans before the PS&E review process begins. Otherwise, they will review the contract plans during the normal PS&E review process.

610.04(7) Hydraulic Structures, Ponds, and Environmental Mitigation

610.04(7)(a) Project Definition

The designer provides a description and location of the proposed hydraulic/ environmental improvements and other pertinent site information and discusses the extent of the improvements with both the RME and the HQ Hydraulics Section to identify the geotechnical issues to be investigated. At this stage, only the identification and feasibility of the proposed hydraulic structures or environmental mitigation are investigated. The cost and schedule requirements for the geotechnical investigation are also determined at this time.

Examples of hydraulic structures include, but are not limited to, large culverts, pipe arches, underground detention vaults, and fish passage structures. Examples of environmental mitigation include, but are not limited to, detention/retention ponds, wetland creation, and environmental mitigation measures on fill slopes.

It is especially important to identify the potential to encounter high groundwater at the proposed hydraulic structure or pond location. In general, avoid high groundwater locations (see the *Highway Runoff Manual*) as groundwater can greatly affect design, constructibility, operations, performance, and maintenance.

610.04(7)(b) Project Design

The designer requests a geotechnical report from the RME. The site data given in 610.04(4), as applicable, is provided along with the following information:

- Pertinent field observations (such as unstable slopes, existing soft soils or boulders, evidence of high groundwater, or erosion around and damage to existing culverts or other drainage structures).
- Jurisdictional requirements for geotechnical design of berms/dams.

It is important that the request for the geotechnical report be made as early as possible in the design phase. Cost and schedule requirements to generate the report are project-specific and can vary widely. The time required to obtain permits and rights of entry must be considered when establishing schedule requirements. Furthermore, since the depth to groundwater can be critical to the feasibility of these types of facilities, and since seasonal variation of groundwater

is typically important to know, it is essential to have adequate time to determine the effect of seasonal variations on groundwater.

The RME, with support from the HQ Geotechnical Office as needed, provides the following information in addition to the overall requirements specified in the *Geotechnical Design Manual*, when requested and where applicable, as part of the project geotechnical report:

- Soil boring logs.
- Soil pH and resistivity.
- Water table elevation.
- Soil infiltration rates (the highest rate for assessing spill containment/aquifer protection and the long-term rate for determining pond capacity).
- Bearing capacity and settlement for hydraulic structure foundations.
- Slope stability for ponds.
- Retention berm/dam design.
- Potential for and amount of differential settlement along culverts and pipe arches and the estimated time required for settlement to occur.
- Soil pressures and properties (primarily for underground detention vaults).
- Erosion potential.
- Geosynthetic design in accordance with Chapter 630.
- Recommendations for mitigation of the effects of soft or unstable soil on the hydraulic structures.
- Recommendations for construction.

Note that retaining walls that are part of a pond, fish passage, and so on, are designed in accordance with Chapter 730 and the *Geotechnical Design Manual*.

The designer uses the geotechnical information to:

- Finalize design decisions.
- Evaluate and mitigate environmental issues.
- Proceed with completion of the PS&E design. This includes determining the most cost-effective hydraulic structure/pond to meet the desired objectives; locating and sizing ponds and foundations for hydraulic structures; structural design; mitigating the effects of settlement; and satisfying local jurisdictional requirements for design.

610.04(7)(c) PS&E Development

During PS&E development, the designer uses the information provided in the geotechnical report to:

- Select pipe materials in accordance with corrosion, resistivity, and abrasion guidelines in the *Hydraulics Manual*.
- Consider and include construction recommendations.

Additional design and specification guidance and support from the RME or the HQ Geotechnical Office are sought as needed. Both sections provide careful review of the contract plans before the PS&E review process begins, if requested. Otherwise, they will review the contract plans during the normal PS&E review process.

610.04(8) Signals, Sign Bridges, Cantilever Signs, and Luminaire Foundations

610.04(8)(a) Project Definition and Design

Geotechnical information is usually not required for signals, sign bridges, cantilever signs, and luminaires during Project Definition.

The region Traffic Design Office contacts the RME for conceptual foundation recommendations. The conceptual recommendations are based on existing information in the area and identify whether Standard Plan foundations are feasible or whether special-design foundations are required. If good soils are anticipated or the foundations will be placed in fill, Standard Plan foundations can be assumed. If special-design foundations are required, additional time and money can be included in the project to accommodate increased field exploration for foundation design, HQ Geotechnical Office involvement, and structural design by the HQ Bridge and Structures Office.

610.04(8)(b) PS&E Development

Foundation recommendations are made by either the RME or the HQ Geotechnical Office. The recommendations provide all necessary geotechnical information to complete the PS&E.

The region Traffic Design Office (or region Project Engineer in some cases) is responsible for delivering the following project information to the RME:

- Plan sheet showing the location of the structures (station and offset) and the planned structure type.
- Applicable values for: XYZ coordinates, strain pole class, sign bridge span length, luminaire height, variable message sign weight, wind load, CCTV pole height, and known utility information in the area.

The RME provides the following information to the requester if *Standard Plans* foundation types can be used:

- Allowable lateral bearing capacity of the soil
- Results of all field explorations
- Groundwater elevation
- Foundation constructibility

The region uses this information to complete the plan sheets and prepare any special provisions. If utilities are identified during the field investigation that could conflict with the foundations, the region pursues moving or accommodating the utility. Accommodation could require special foundation designs.

If special designs are required, the RME notifies the requester that special designs are required and forwards the information received from the region to the HQ Geotechnical Office. The HQ Geotechnical Office provides the HQ Bridge and Structures Office with the necessary geotechnical recommendations to complete the foundation designs. The region coordinates with the HQ Bridge and Structures Office to ensure they have all the information necessary to complete the design. Depending on the structure type and complexity, the HQ Bridge and Structures Office might produce the plan sheets and special provisions for the foundations, or they might provide the region with information so they can complete the plan sheets and special provisions.

Additional guidelines and requirements for design of foundations for these types of structures are contained in the *Geotechnical Design Manual*.

610.04(9) Buildings, Park & Ride Lots, Communication Towers, and Rest Areas

In general, the RME functions as the clearinghouse for the geotechnical work to be conducted in each of the phases, for technical review of the work if it is performed by consultants, or for getting the work done in-house. For sites and designs that are more geotechnically complex, the RME contacts the HQ Geotechnical Office for assistance. (See the *Geotechnical Design Manual* for geotechnical investigation and design requirements for these types of facilities.)

610.04(9)(a) Site Selection

Conceptual geotechnical investigation (based on historical data and minimal subsurface investigation) of several alternative sites is performed in which the geotechnical feasibility of each site for its intended use is evaluated, allowing the sites to be ranked. In this phase, geological hazards (such as landslides, rockfall, compressible soils, and liquefaction) are identified, and geotechnical data adequate to determine a preliminary cost to develop and build on the site is gathered.

610.04(9)(b) Schematic Design

For the selected site, the best locations for structures, utilities, and other elements of the project are determined based on site constraints and ground conditions. In this phase, the site is characterized more thoroughly than in the site selection phase, but subsurface exploration is not structure specific.

610.04(9)(c) Design and PS&E Development

The final locations of each of the project structures, utilities, and other project elements determined from the schematic design phase are identified. Once these final locations are available, a geotechnical investigation is conducted that is adequate to complete the final design of each of the project elements, such as structure foundations, detention/retention facilities, utilities, parking lots, roadways, and site grading. From this investigation and design, the final PS&E is developed.

610.04(10) Retaining Walls, Reinforced Slopes, and Noise Walls

610.04(10)(a) Project Definition

The designer provides the RME with a description and location of the proposed walls or reinforced slopes, including the potential size of the proposed structures and other pertinent site information. At this stage, only the identification and feasibility of the proposed walls or reinforced slopes are investigated. A field review may also be conducted as part of the investigation effort. In general, if soil/rock conditions are poor and/or large walls or reinforced slopes are anticipated, the RME requests that the HQ Geotechnical Office participate in the field review and reporting efforts. The cost and schedule requirements for the geotechnical investigation are also determined at this time.

A brief conceptual-level report that summarizes the results of the investigation may be provided to the designer at this time, depending on the complexity of the geotechnical issues.

610.04(10)(b) Project Design and PS&E Development

Geotechnical data necessary to allow completion of the PS&E-level design for walls and reinforced slopes are compiled during the design and PS&E development phases. These include soils borings, testing, and final geometric data. Detailed designs of walls and reinforced slopes can be done once the roadway geometry is established and geotechnical data are available. The purpose of this design effort is to determine the wall and slope geometry needed for stability; noise wall and retaining wall foundation requirements; and the potential for short- and long-term settlement.

The designer requests a geotechnical report from the RME for retaining walls, noise walls, and reinforced slopes that are not part of the bridge preliminary plan. For walls that are part of the bridge preliminary plan, the HQ Bridge and Structures Office requests the geotechnical report for the walls from the HQ Geotechnical Office. (See Chapter 730 for the detailed design process for retaining walls and reinforced slopes, Chapter 740 for the detailed design process for noise walls, and the *Geotechnical Design Manual* for design requirements for all walls.) It is important that requests for a geotechnical report be made as early as possible in the design phase. The time required to obtain permits and rights of entry must be considered when establishing schedule requirements.

For retaining walls and reinforced slopes, the site data to be provided with the request for a geotechnical report are as given in Chapter 730. Supply right of entry agreements and permits required for the geotechnical investigation. The site data given in 610.04(4), as applicable, are provided for noise walls.

The RME or the HQ Geotechnical Office provides the information (see Chapter 730 or 740 for specific responsibilities for design) specified in the *Geotechnical Design Manual* as part of the project geotechnical report.

The recommendations may also include the background regarding the analysis approach and any agreements with the region or other customers regarding the definition of acceptable level of risk. Additional details and design issues to be considered in the geotechnical report are as provided in Chapter 730 for retaining walls and reinforced slopes and in Chapter 740 for noise walls. The designer uses this information for final wall/reinforced slope selection and to complete the PS&E.

For final PS&E preparation, special provisions and plan details (if not received as part of the report provided during design) are developed with the assistance of the region Materials Laboratory or the HQ Geotechnical Office. Both the region Materials Laboratory and the HQ Geotechnical Office can review the contract plans before the PS&E review process begins, if requested. Otherwise, they will review the contract plans during the normal PS&E review process.

610.04(11) Unstable Slopes

Unstable slope mitigation includes the stabilization of known landslides and rockfall that occur on slopes adjacent to the WSDOT transportation system and that have been programmed under the P3 Unstable Slope Program.

610.04(11)(a) Project Definition

The region Project Office provides the RME with a description and location of the proposed unstable slope mitigation work. Location of the proposed work can be milepost limits or stationing. The designer meets at the project site with the RME and HQ Geotechnical Office to conduct a field review, discuss project requirements, and identify geotechnical issues associated with the unstable slope project. The RME requests that the HQ Geotechnical Office participate in the field review and Project Definition reporting.

The level of work in the Project Definition phase for unstable slopes is conceptual in nature, not a final design. The geotechnical investigation generally consists of a field review, a more detailed assessment of the unstable slope, review of the conceptual mitigation developed during the programming phase of the project, and proposed modification (if any) to the original conceptual-level unstable slope mitigation. The design phase geotechnical services cost and schedule, including any required permits, are determined at this time. A brief conceptual-level report is provided to the designer that summarizes the results of the Project Definition investigation.

610.04(11)(b) Project Design

Geotechnical information and field data necessary to complete the unstable slope mitigation design is compiled during this design phase. This work includes, depending on the nature of the unstable slope problem, test borings, rock structure mapping, geotechnical field instrumentation, laboratory testing, and slope stability analysis. The purpose of this design effort is to provide design-level geotechnical recommendations to stabilize the known unstable slope.

The designer requests a geotechnical report from the HQ Geotechnical Office through the RME. The site data given in 610.04(4), as applicable, is provided along with the following information:

- A plan sheet showing the station and location of the proposed unstable slope mitigation project.
- If requested, the Digital Terrain Model (DTM) files necessary to define the on-ground topography of the project site (the limits of the DTM will have been defined during the Project Definition phase).

It is important that the request for the geotechnical report be made as early as possible in the design phase. Cost and schedule requirements to generate the report are project-specific and can vary widely. Unstable slope design investigations might require geotechnical monitoring of ground movement and groundwater over an extended period of time to develop the required field information for the unstable slope mitigation design. The time required to obtain rights of entry and other permits, as well as the long-term monitoring data, must be considered when establishing schedule requirements for the geotechnical report.

In addition to the geotechnical report requirements specified in the *Geotechnical Design Manual*, the HQ Geotechnical Office provides the following information as part of the project geotechnical report (as applicable):

- Unstable slope design analysis and mitigation recommendations.
- Constructibility issues associated with the unstable slope mitigation.
- Appropriate special provisions for inclusion in the contact plans.

The region Project Office uses the geotechnical report to finalize the design decisions for the project and the completion of the PS&E design.

610.04(11)(c) PS&E Development

Adequate geotechnical design information to complete the PS&E is typically obtained during the project design phase. Additional geotechnical work might be needed when right of way cannot be acquired, restrictions are included in permits, or other requirements are added that result in changes to the design.

Special provisions, special project elements, and design details, if not received as part of the design phase geotechnical report, are developed with the assistance of the RME and the HQ Geotechnical Office. The designer uses this information in conjunction with the design phase geotechnical report to complete the PS&E document. The RME and the HQ Geotechnical Office can review the contract plans before the PS&E review begins, if requested. Otherwise, they will review the contract plans during the normal PS&E review process.

610.04(12) Rockslope Design

610.04(12)(a) Project Definition

The region Project Office provides the RME with a description and location of the proposed rock excavation work. For widening of existing rock cuts, the anticipated width and length of the proposed cut in relationship to the existing cut are provided. For new alignments, the approximate location and depth of the cut are provided. Location of the proposed cut(s) can be milepost limits or stationing. The designer meets at the project site with the RME and the HQ Geotechnical Office to conduct a field review, discuss project requirements, and identify any geotechnical issues associated with the proposed rock cuts. The RME requests that the HQ Geotechnical Office participate in the field review and Project Definition reporting.

The level of rockslope design work for the Project Definition phase is conceptual in nature. The geotechnical investigation generally consists of the field review, review of existing records, an assessment of existing rockslope stability, and preliminary geologic structure mapping. The focus of this investigation is to assess the feasibility of the rock cuts for the proposed widening or realignment, not final design. A brief conceptual-level report that summarizes the result of the Project Definition investigation is provided to the designer.

610.04(12)(b) Project Design

Detailed rockslope design is done once the roadway geometrics have been established. The rockslope design cannot be finalized until the roadway geometrics have been finalized. Geotechnical information and field data necessary to complete the rockslope design are compiled during this design phase. This work includes rock structure mapping, test borings, laboratory testing, and slope stability analysis. The purpose of this design effort is to determine the maximum stable cut slope angle and any additional rockslope stabilization measures that could be required.

The designer requests a geotechnical report from the HQ Geotechnical Office through the RME. The site data given in 610.04(4), as applicable, is provided.

It is important that the request for the geotechnical report be made as early as possible in the design phase. Cost and schedule requirements to generate the report are project-specific and can vary widely. The time required to obtain permits and rights of entry must be considered when establishing schedule requirements.

In addition to the geotechnical report requirements specified in the *Geotechnical Design Manual*, the HQ Geotechnical Office provides the following information as part of the project geotechnical report pertaining to rockslope design analysis and recommendations:

- Type of rockslope design analysis conducted and limitation of the analysis. Also included will be any agreements with the region and other customers regarding the definition of "acceptable risk."
- The slope(s) required for stability.
- Additional slope stabilization requirements (such as rock bolts or rock dowels).
- Rockslope ditch criteria (see Chapter 1239).
- Assessment of rippability.

- Blasting requirements, including limitations on peak ground vibrations and air blast over-pressure if required.
- Usability of the excavated material, including estimates of shrink and swell.
- Constructibility issues associated with the rock excavation.

The region Project Office uses the geotechnical report to finalize the design decisions for the project and the completion of the PS&E design for the rockslope elements of the project.

610.04(12)(c) PS&E Development

Adequate geotechnical design information to complete the PS&E is typically obtained during the design phase. Additional geotechnical work might be needed when right of way cannot be acquired, restrictions are included in permits, or other requirements are added that result in change to the design.

Special provisions, special blasting requirements, and plan details, if not received as part of the design phase geotechnical report, are developed with the assistance of the RME or the HQ Geotechnical Office. The designer uses this information in conjunction with the design phase geotechnical report to complete the PS&E documents. The RME and the HQ Geotechnical Office can review (if requested) the contract plans before the PS&E review begins. Otherwise, they will review the contract plans during the normal PS&E review process.

610.04(13) Bridge Foundations

610.04(13)(a) Project Definition

The HQ Geotechnical Office supports the development of reasonably accurate estimates of bridge substructure costs beginning with the Project Definition phase. A field review is recommended for major projects and projects that are located in areas with little or no existing geotechnical information. The region office responsible for Project Definition coordinates field reviews. Subsurface exploration (drilling) is usually not required at this time, but might be needed if cost estimates cannot be prepared within an acceptable range of certainty.

Once it has received the necessary site data from the region Project Office, the HQ Bridge and Structures Office is responsible for delivering the following project information to the HQ Geotechnical Office:

- Alternative alignments and/or locations of bridge structures.
- A preliminary estimate of channelization (structure width).
- Known environmental constraints.

The HQ Geotechnical Office provides the following to the HQ Bridge and Structures and region offices:

- Summary of existing geotechnical information.
- Identification of geotechnical hazards (such as slides, liquefiable soils, and soft-soil deposits).
- Identification of permits that might be required for subsurface exploration (drilling).
- Conceptual foundation types and depths.
- If requested, an estimated cost and time to complete a geotechnical foundation report.

The HQ Bridge and Structures Office uses this information to refine preliminary bridge costs. The region Project Office uses the estimated cost and time to complete a geotechnical foundation report to develop the project delivery cost and schedule.

610.04(13)(b) Project Design

The HQ Geotechnical Office assists the HQ Bridge and Structures Office with preparation of the bridge preliminary plan. Geotechnical information gathered for Project Definition will normally be adequate for this phase, as test holes for the final bridge design cannot be drilled until accurate pier location information is available. For selected major projects, a type, size, and location (TS&L) report might be prepared, which usually requires some subsurface exploration to provide a more detailed, though not final, estimate of foundation requirements.

The HQ Bridge and Structures Office is responsible for delivering the following project information, based on bridge site data received from the region Project Office, to the HQ Geotechnical Office:

- Anticipated pier locations.
- Approach fill heights.
- For TS&L, alternate locations/alignments/structure types.

The HQ Bridge and Structures Office can expect to receive the following:

- Conceptual foundation types, depths, and capacities.
- Permissible slopes for bridge approaches.
- For TS&L, a summary of site geology and subsurface conditions, and more detailed preliminary foundation design parameters and needs.
- If applicable or requested, the potential impact of erosion or scour potential (determined by the HQ Hydraulics Section) on foundation requirements.

The HQ Bridge and Structures Office uses this information to complete the bridge preliminary plan. The region Project Office confirms right of way needs for approach embankments. For TS&L, the geotechnical information provided is used for cost estimating and preferred alternate selection. The preliminary plans are used by the HQ Geotechnical Office to develop the site subsurface exploration plan.

610.04(13)(c) PS&E Development

During this phase, or as soon as a 95% preliminary plan is available, subsurface exploration (drilling) is performed and a geotechnical foundation report is prepared to provide all necessary geotechnical recommendations needed to complete the bridge PS&E.

The HQ Bridge and Structures Office is responsible for delivering the following project information to the HQ Geotechnical Office:

- 95% preliminary plans, concurrent with distribution for region approval.
- Estimated foundation loads and allowable settlement criteria for the structure when requested.

The HQ Bridge and Structures Office can expect to receive:

- The bridge geotechnical foundation report.

The HQ Bridge and Structures Office uses this information to complete the bridge PS&E. The region Project Office reviews the geotechnical foundation report for construction considerations and recommendations that might affect region items, estimates, staging, construction schedule, or other items.

Upon receipt of the structure PS&E review set, the HQ Geotechnical Office provides the HQ Bridge and Structures Office with a Summary of Geotechnical Conditions for inclusion in Appendix B of the contract.

610.04(14) Geosynthetics

For design guidance on geosynthetics, refer to Chapter 630.

610.04(15) Washington State Ferries Projects

610.04(15)(a) Project Design

The HQ Geotechnical Office assists the Washington State Ferries (WSF) with determining the geotechnical feasibility of all offshore facilities, terminal facility foundations, and bulkhead walls. For upland retaining walls and grading, utility trenches, and pavement design, the RME assists WSF with determining geotechnical feasibility.

In addition to the site data provided in Section 610.04(4), as applicable, the following information is supplied by WSF to the HQ Geotechnical Office or the RME, as appropriate, with the request for the project geotechnical report:

- A plan showing anticipated structure locations as well as existing structures.
- Relevant historical data for the site.
- A plan showing utility trench locations.
- Anticipated utility trench depths.
- Proposed roadway profiles.

WSF can expect to receive the following:

- Results of any borings or laboratory tests conducted.
- A description of geotechnical site conditions.
- Conceptual foundation types, depths, and capacities.
- Conceptual wall types.
- Assessment of constructibility issues that affect feasibility.
- Surfacing depths and/or pavement repair and drainage schemes.
- If applicable or requested, potential impact of erosion or scour potential (determined by the HQ Hydraulics Section) on foundation requirements.

WSF uses this information to complete the design report, design decisions, and estimated budget and schedule.

WSF is responsible for obtaining any necessary permits or right of entry agreements needed to access structure locations for the purpose of subsurface exploration (such as test hole drilling). The time required for obtaining permits and rights of entry must be considered when developing project schedules. Possible permits and agreements might include, but are not limited to:

- City, county, or local agency use permits.
- Sensitive area ordinance permits.

610.04(15)(b) PS&E Development

Subsurface exploration (drilling) is performed and a geotechnical foundation report is prepared to provide all necessary geotechnical recommendations needed to complete the PS&E.

The designer requests a geotechnical report from the HQ Geotechnical Office or the RME, as appropriate. The site data given in 610.04(4), as applicable, is provided along with the following information:

- A plan showing final structure locations as well as existing structures.
- Proposed structure loadings.

WSF can expect to receive the following:

- Results of any borings or laboratory tests conducted.
- A description of geotechnical site conditions.
- Final foundation types, depths, and capacities.
- Final wall types and geotechnical designs/parameters for each wall.
- Assessment of constructibility issues to be considered in foundation selection and when assembling the PS&E.
- Pile driving information: driving resistance and estimated overdrive.
- Surfacing depths and/or pavement repair and drainage schemes.

WSF uses this information to complete the PS&E.

Upon receipt of the WSF PS&E review set, the HQ Geotechnical Office provides WSF with a Summary of Geotechnical Conditions for inclusion in Appendix B of the Contract. A Final Geotechnical Project Documentation package is assembled by the HQ Geotechnical Office and sent to WSF or the Plans Branch, as appropriate, for reproduction and sale to prospective bidders.

610.05 Use of Geotechnical Consultants

Prior to authorizing a consultant to conduct the geotechnical investigation for a project, the region Project Office, the HQ Geotechnical Office, and the RME determine the scope of work and schedule for the project and whether or not the project will go to a geotechnical consultant.

Once the decision has been made to have a consultant conduct the geotechnical investigation for a project, the HQ Geotechnical Office or the RME assists in developing the geotechnical scope and estimate for the project (WSDOT Consultant Services assists in this process). A team meeting between the consultant team, the region or Washington State Ferries (depending on whose project it is), and the HQ Geotechnical Office/RME is conducted early in the project to develop technical communication lines and relationships. Good proactive communication between all members of the project team is crucial to the success of the project due to the complex supplier-client relationships.

Additional guidelines on the use of geotechnical consultants and the development of a scope of work for the consultant are provided in the *Geotechnical Design Manual*.

610.06 Geotechnical Work by Others

Geotechnical design work conducted for the design of structures, or other engineering works by other agencies or private developers within the right of way, is subject to the same geotechnical engineering requirements as for engineering works performed by WSDOT. Therefore, the provisions contained within this chapter also apply in principle to such work. All geotechnical work conducted for engineering works within the WSDOT right of way or that otherwise directly impacts WSDOT facilities must be reviewed and approved by the HQ Geotechnical Office or the RME, depending on the nature of the work.

Additional requirements for geotechnical work by others that impacts WSDOT facilities and land within the WSDOT right of way are set forth in the *Geotechnical Design Manual*.

610.07 Surfacing Report

Detailed criteria and methods that govern pavement rehabilitation can be found in the *WSDOT Pavement Policy*. The RME provides the surfacing report to the region Project Office. This report provides recommended pavement types, surfacing depths, pavement drainage recommendations, and pavement repair recommendations.

610.08 Documentation

610.08(1) Design Documentation


Refer to Chapter 300 for design documentation requirements.

610.08(2) Final Geotechnical Project Documentation and Geotechnical Information for the Construction Contract

Once a project PS&E is near completion, all of the geotechnical design memorandums and reports are compiled together to form the Final Geotechnical Project Documentation, to be published for the use of prospective bidders. The detailed process for this is located in the *Plans Preparation Manual*.

Geotechnical information included in the contract consists of the final project boring logs and, as appropriate for the project, a Summary of Geotechnical Conditions. The boring logs from the geotechnical reports are incorporated into the contract by the region, WSF, or Urban Corridors Office (UCO) staff. The Summary of Geotechnical Conditions is provided to the region, WSF, or UCO by the HQ Geotechnical Office and/or RME.

Additional geotechnical project documentation requirements are set forth in the *Geotechnical Design Manual*.



Materials Source Development
Exhibit 610-1

Chapter 620 Design of Pavement Structure

620.01 General
620.02 Estimating Tables

620.01 General

Detailed criteria and methods that govern pavement design are in the Washington State Department of Transportation (WSDOT) Pavement Policy, which is available from the Pavements website: www.wsdot.wa.gov/business/materialslab/pavements/default.htm

The pavement design for all Design-Build project Request For Proposals (RFPs) will be conducted by the State Materials Lab, Pavement Division.

620.02 Estimating Tables

The tables in Exhibits 620-1 through 620-5h are for developing estimates of quantities for pavement sections, shoulder sections, stockpiles, asphalt distribution, and fog seal.

Exhibit 620-1 Estimating: Miscellaneous Tables

Unit Dry Weight – Gravel Base and Surfacing				
Type of Material	Truck Measure		Compacted on Roadway	
	lb/cy	T/cy	lb/cy	T/cy
Ballast	3,100	1.55	3,900	1.95
Crushed Surfacing Top Course	2,850	1.43	3,700	1.85
Crushed Surfacing Base Course	2,950	1.48	3,700	1.85
Screened Gravel Surfacing			3,700	1.85
*Gravel Base			3,400 – 3,800	1.70 – 1.90
Permeable Ballast			2,800	1.40
*3,700 lb/cy (1.85 tons/cy) is recommended as the most suitable factor; however, if the grading approaches the coarseness of ballast, the factor would approach 3,800 lb/cy (1.90 tons/cy), and if the grading contains more than 45% sand, the factor would decrease, approaching 3,400 lb/cy (1.70 tons/cy) for material that is essentially all sand.				

Notes:

- Weights shown are dry weights and corrections are required for water contents.
- The tabulated weights for the materials are reasonably close; however, apply corrections in the following order:

For specific gravity: $\text{Wt.} = \dfrac{\text{tabular wt. x specific gravity on surface report}}{2.65}$

For water content: Wt. = tabular wt. x (1 + free water % in decimals)

- If material is to be stockpiled, increase required quantities by 10% to allow for waste.
- Consider the inclusion of crushed surfacing top course material for keystone when estimating quantities for projects having ballast course.

Exhibit 620-2 Estimating: Hot Mix Asphalt Pavement and Asphalt Distribution Tables

Fog Seal						
Asphalt						
Application	Type of Emulsified Asphalt	Application gal* per sy	Tons* per sy	Tons/Mile Width (ft)		
				10	11	12
Fog Seal	CSS-1/CSS-1h	0.07	0.000292	1.7	1.9	2.1

*Quantities shown are retained (residual) asphalt.

Specific Data[1][2]														
Hot Mix Asphalt Paving Quantities (tons/mile)*														
Width (ft)	Depth of Pavement (ft)													
	0.10	0.15	0.20	0.25	0.30	0.35	0.40	0.45	0.50	0.55	0.60	0.65	0.70	0.75
4	161	241	321	402	482	563	643	723	804	884	964	1045	1125	1206
6	241	362	482	603	723	844	964	1085	1206	1326	1447	1567	1688	1808
8	321	482	643	804	964	1125	1286	1447	1607	1768	1929	2090	2250	2411
10	402	603	804	1005	1206	1407	1607	1808	2009	2210	2411	2612	2813	3014
11	442	663	884	1105	1326	1547	1768	1989	2210	2431	2652	2873	3094	3315
12	482	723	964	1206	1447	1688	1929	2170	2411	2652	2893	3135	3376	3617
22	884	1326	1768	2210	2652	3094	3536	3978	4421	4863	5305	5747	6189	6631
24	964	1447	1929	2411	2893	3376	3858	4340	4822	5305	5787	6269	6751	7234

*Based on 137 lbs/sy (0.0685 tons/sy) of 0.10 ft compacted depth = 2.05 tons/cy

Notes:

[1] The specific gravity of the aggregate will affect the weight of aggregate in the completed mix.

[2] Quantities shown do not provide for widening, waste from stockpile, or thickened edges.

Exhibit 620-3 Estimating: Bituminous Surface Treatment

Bituminous Surface Treatment[1]																
Type of Application	Average Application		Mineral Aggregate						Average Spread	Asphalt[2][4]						Basic[3] Asphalt Used
			10 ft		11 ft		12 ft			10 ft		11 ft		12 ft		
	lb/sy	cy/sy	T/mi	cy/mi	T/mi	cy/mi	T/mi	cy/mi	gal/sy	gal/mi	T/mi	gal/mi	T/mi	gal/mi	T/mi	
New Construction 3/4 inch – 1/2 inch																
First Application									0.50	2933	11.8	3227	13.0	3520	14.1	CRS-2P
Crushed Screenings 3/4 inch – 1/2 inch	35	0.0146	103	86	113	94	123	103								
Second Application									0.48	2787	11.2	3065	12.3	3344	13.4	CRS-2P
Crushed Screenings 1/2 inch – No. 4	32	0.0121	93	71	103	78	113	85								
Choke Stone No. 4 – 0	5	0.0017	15	10	16	11	18	12								
Totals	72	0.0284	211	167	232	183	254	200	0.98	5720	23.0	6292	25.3	6864	27.5	
New Construction 1/2 inch – No. 4																
First Application									0.50	2933	11.8	3227	13.0	3520	14.1	CRS-2P
Crushed Screenings 1/2 inch – No. 4	35	0.0132	102	77	113	85	123	93								
Second Application									0.48	2787	11.2	3065	12.3	3344	13.4	CRS-2P
Crushed Screenings 1/2 inch – No. 4	32	0.0121	93	71	103	78	113	85								
Choke Stone No. 4 – 0	5	0.0017	15	10	16	11	18	12								
Totals	72	0.0270	210	158	232	174	254	190	0.98	5720	23.0	6292	25.3	6864	27.5	
Seal Coats 5/8 inch – No. 4																
Seal Coat									0.53	3109	12.5	3420	13.7	3731	15.0	CRS-2P
Crushed Screenings 5/8 inch – No. 4	35	0.0130	102	76	113	84	124	92								
Choke Stone No. 4 – 0	5	0.0017	15	10	16	11	18	12								
Totals	40	0.0147	117	86	129	95	142	104	0.53	3109	12.5	3420	13.7	3731	15.0	

Table and notes continued on the next page.

Exhibit 620-3 Estimating: Bituminous Surface Treatment (continued)

Bituminous Surface Treatment[1]																
Type of Application	Average Application		Mineral Aggregate						Average Spread	Asphalt[2][4]						Basic[3] Asphalt Used
			10 ft		11 ft		12 ft			10 ft		11 ft		12 ft		
	lb/sy	cy/sy	T/mi	cy/mi	T/mi	cy/mi	T/mi	cy/mi	gal/sy	gal/mi	T/mi	gal/mi	T/mi	gal/mi	T/mi	
Seal Coats 1/2 inch – No. 4																
Seal Coat									0.45	2640	10.6	2904	11.7	3168	12.7	CRS-2P
Crushed Screenings 1/2 inch – No. 4	28	0.0106	81	62	89	68	97	74								
Choke Stone No. 4 – 0	5	0.0017	15	10	16	11	18	12								
Totals	33	0.0123	96	72	105	79	115	86	0.45	2640	10.6	2904	11.7	3168	12.7	
Seal Coats 3/8 inch – No. 4																
Seal Coat									0.45	2640	10.6	2904	11.7	3168	12.7	CRS-2P
Crushed Screenings 3/8 inch - No. 4	30	0.0106	88	62	96	68	106	75								
Choke Stone No. 4 – 0	5	0.0017	15	10	16	11	18	12								
Totals	35	0.0123	103	72	112	79	124	74	0.45	2640	10.6	2904	11.7	3168	12.7	

Notes:


[1] Quantities shown do not provide for widening, waste from stockpile, or thickened edges.

[2] Quantities of asphalt shown are based on 60°F temperature. Recompute to the application temperature for the particular grade.

[3] The column “Basic Asphalt Used” is shown for the purpose of conversion to proper weights for the asphalt being used and does not imply that the particular grade shown is required for the respective treatment.

[4] For stress-absorbing membrane (rubberized asphalt), increase asphalt by 25%.

Exhibit 620-4 Estimating: Base and Surfacing Typical Section Formulae and Example



W_S = Shoulder Width (Varies 4 ft, 6 ft, 8 ft, 10 ft, 12 ft)
d = Depth of Section (Varies 0.05 ft to 2 ft)
S = Side Slope (H:V) (Varies 2:1, 3:1, 4:1, and 6:1)
S_1 = Top Shoulder Slope (Varies -0.02 ft/ft or -0.05 ft/ft)
S_2 = Bottom Shoulder Slope (Varies -0.02 ft/ft or -0.05 ft/ft)

Formula for Shoulder Section		
Tons/mile = (A)(K) K=(5280/27)(1.85 tons/cy) $A = \frac{[d + W_S(1/S - S_1)]^2 S}{2(1 - SS_2)} - \frac{W_S^2}{2}(1/S - S_1)$		
Case 1	$S_1 = S_2 = -0.02$ ft/ft	$A = \frac{[d + W_S(1/S - 0.02)]^2 S}{2(1 - 0.02S)} - \frac{W_S^2}{2}(1/S - 0.02)$
Case 2	$S_1 = -0.02$ ft/ft, $S_2 = -0.05$ ft/ft	$A = \frac{[d + W_S(1/S - 0.02)]^2 S}{2(1 - 0.05S)} - \frac{W_S^2}{2}(1/S - 0.02)$
Case 3	$S_1 = -0.05$ ft/ft, $S_2 = -0.02$ ft/ft	$A = \frac{[d + W_S(1/S - 0.05)]^2 S}{2(1 - 0.02S)} - \frac{W_S^2}{2}(1/S - 0.05)$ *
Case 4	$S_1 = S_2 = -0.05$ ft/ft	$A = \frac{[d + W_S(1/S - 0.05)]^2 S}{2(1 - 0.05S)} - \frac{W_S^2}{2}(1/S - 0.05)$

*Limit: Positive Values of A only when d = $W_S(0.03)$

EXAMPLE: Shoulder Section

Given:

Shoulder Width (W_S)	=	8 ft
Top Course	=	0.25 ft
Base Course	=	0.80 ft
Total Depth (d)	=	1.05 ft
Side Slope (S)	=	3:1
Shoulder Slope (S_1)	=	-0.05
Subgrade Slope (S_2)	=	-0.02

Depth	1.05 ft (Case 3)	= 3,070 tons/mile
Top Course	0.25 ft (Case 4)	= - 763 tons/mile
Base Course		= 2,307 tons/mile
Top Course		= 763 tons/mile
Base Course		= 2,307 tons/mile

Exhibit 620-5a Estimating: Base and Surfacing Quantities

Shoulder Section											
Shldr. Width W_S (ft)	Side Slope S:1	Case	Quantity in Tons Per Mile*								
			Surfacing Depth (ft)								
			0.05	0.10	0.15	0.20	0.25	0.30	0.35	0.40	0.45	0.50
4	2	1	73	148	226	304	385	468	553	639	728	818
		2	171	251	333	417	504	592	682	774	869	965
		3	N/A	N/A	131	205	281	360	440	522	605	691
		4	73	149	226	306	387	470	556	643	733	824
	3	1	74	150	230	313	398	486	577	671	768	868
		2	178	262	350	442	536	634	734	838	945	1056
		3	N/A	N/A	131	206	285	366	450	537	627	720
		4	74	151	231	315	402	492	585	681	780	883
	4	1	74	153	235	321	411	505	603	705	810	920
		2	185	275	370	469	572	681	793	910	1032	1158
		3	N/A	N/A	131	208	288	373	461	554	650	750
		4	75	154	237	326	418	516	617	724	834	950
	6	1	75	157	245	339	439	545	658	776	901	1032
		2	204	307	417	535	661	794	936	1085	1242	1406
		3	N/A	N/A	131	210	296	387	485	589	699	815
		4	76	160	252	351	459	574	696	827	965	1111
6	2	1	109	221	334	449	566	685	806	929	1053	1180
		2	325	444	565	688	812	939	1068	1199	1332	1467
		3	N/A	N/A	N/A	239	349	461	575	691	809	929
		4	110	221	335	450	568	687	809	933	1058	1186
	3	1	110	223	339	457	579	703	830	961	1094	1230
		2	338	462	590	722	856	994	1134	1278	1426	1576
		3	N/A	N/A	N/A	239	350	464	581	701	824	949
		4	110	223	340	460	583	709	838	970	1106	1245
	4	1	110	225	343	466	592	722	856	994	1136	1282
		2	352	483	619	760	905	1055	1209	1368	1531	1699
		3	N/A	N/A	N/A	239	351	467	587	711	839	971
		4	111	226	346	470	599	733	871	1013	1160	1311
	6	1	112	229	353	483	620	762	911	1066	1227	1394
		2	386	534	690	853	1025	1204	1391	1585	1788	1998
		3	N/A	N/A	N/A	239	353	474	600	733	871	1016
		4	112	233	360	496	640	791	950	1116	1291	1473
8	2	1	146	293	443	594	747	902	1059	1218	1379	1541
		2	526	683	843	1004	1167	1333	1500	1670	1841	2015
		3	N/A	N/A	N/A	N/A	376	522	670	820	972	1125
		4	146	293	443	595	749	904	1062	1222	1384	1548
	3	1	146	295	447	602	760	920	1084	1250	1419	1591
		2	546	711	879	1050	1224	1402	1583	1766	1954	2144
		3	N/A	N/A	N/A	N/A	376	523	673	825	981	1139
		4	146	296	448	604	763	926	1091	1260	1432	1607
	4	1	147	297	452	610	773	939	1109	1284	1462	1644
		2	568	741	919	1101	1288	1479	1675	1875	2080	2290
		3	N/A	N/A	N/A	N/A	376	524	675	831	990	1153
		4	147	298	454	615	780	950	1124	1302	1486	1673
	6	1	148	302	462	628	801	979	1164	1355	1552	1755
		2	622	816	1017	1226	1443	1668	1900	2140	2388	2643
		3	N/A	N/A	N/A	N/A	376	525	681	842	1009	1183
		4	149	305	469	641	820	1008	1203	1406	1616	1835

*Tabulated quantities are based on compacted weight of 1.85 tons/yd^3

Exhibit 620-5b Estimating: Base and Surfacing Quantities

Shoulder Section											
Shldr. Width W_s (ft)	Side Slope S:1	Case	Quantity in Tons Per Mile*								
			Surfacing Depth (ft)								
			0.55	0.60	0.65	0.70	0.75	0.80	0.85	0.90	0.95	1.00
4	2	1	910	1004	1100	1198	1297	1399	1502	1608	1715	1824
		2	1063	1163	1266	1370	1476	1585	1695	1807	1922	2038
		3	779	868	960	1053	1148	1245	1344	1445	1548	1652
		4	918	1013	1110	1210	1311	1415	1520	1628	1738	1849
	3	1	971	1076	1185	1296	1410	1527	1647	1770	1896	2024
		2	1169	1286	1406	1529	1655	1785	1918	2053	2193	2335
		3	816	914	1016	1120	1228	1338	1451	1567	1686	1807
		4	989	1098	1210	1326	1444	1566	1691	1820	1951	2086
	4	1	1034	1151	1273	1398	1528	1661	1798	1939	2085	2234
		2	1289	1424	1564	1708	1857	2010	2168	2330	2497	2668
		3	855	963	1075	1191	1311	1435	1562	1694	1830	1969
		4	1070	1194	1323	1456	1594	1737	1884	2035	2191	2352
	6	1	1169	1312	1462	1617	1779	1947	2121	2301	2488	2680
		2	1579	1759	1947	2142	2346	2557	2776	3002	3237	3479
		3	937	1066	1200	1341	1488	1641	1800	1966	2138	2315
		4	1265	1426	1596	1773	1957	2150	2350	2558	2774	2998
6	2	1	1308	1438	1570	1704	1840	1978	2117	2259	2402	2548
		2	1603	1742	1883	2026	2171	2318	2467	2618	2771	2926
		3	1050	1174	1299	1426	1555	1686	1819	1954	2090	2229
		4	1315	1447	1581	1716	1854	1994	2135	2279	2425	2573
	3	1	1369	1510	1655	1802	1953	2106	2262	2421	2583	2748
		2	1729	1886	2046	2209	2376	2545	2718	2894	3073	3255
		3	1078	1209	1343	1480	1620	1763	1909	2058	2209	2363
		4	1387	1532	1681	1832	1987	2145	2306	2471	2638	2809
	4	1	1432	1586	1743	1905	2070	2240	2413	2591	2772	2957
		2	1871	2048	2229	2415	2606	2801	3000	3204	3412	3625
		3	1106	1246	1389	1537	1688	1843	2003	2166	2333	2504
		4	1467	1628	1793	1963	2137	2315	2499	2686	2878	3075
	6	1	1567	1746	1932	2124	2322	2526	2736	2953	3175	3404
		2	2215	2441	2674	2916	3164	3421	3685	3957	4237	4525
		3	1167	1325	1488	1658	1833	2015	2203	2398	2598	2805
		4	1663	1861	2066	2279	2500	2729	2965	3209	3461	3721
8	2	1	1706	1872	2040	2211	2383	2557	2732	2910	3090	3271
		2	2190	2367	2547	2728	2912	3097	3285	3475	3666	3860
		3	1281	1438	1597	1758	1921	2086	2253	2422	2592	2765
		4	1713	1881	2051	2223	2397	2573	2751	2930	3112	3296
	3	1	1766	1944	2125	2309	2495	2685	2877	3072	3271	3472
		2	2338	2534	2734	2937	3144	3353	3566	3782	4001	4223
		3	1300	1464	1631	1801	1974	2149	2328	2509	2693	2880
		4	1785	1966	2151	2339	2530	2724	2921	3122	3326	3533
	4	1	1830	2020	2214	2411	2613	2819	3028	3242	3459	3681
		2	2504	2722	2945	3172	3404	3641	3882	4128	4378	4632
		3	1320	1491	1666	1845	2028	2215	2405	2600	2799	3001
		4	1865	2062	2263	2469	2679	2894	3114	3337	3566	3799
	6	1	1965	2181	2402	2630	2864	3105	3351	3604	3863	4128
		2	2907	3178	3457	3743	4038	4340	4650	4967	5292	5626
		3	1363	1549	1741	1940	2144	2355	2572	2795	3024	3259
		4	2061	2295	2536	2786	3043	3308	3580	3861	4149	4445

*Tabulated quantities are based on compacted weight of 1.85 tons/yd^3

Exhibit 620-5c Estimating: Base and Surfacing Quantities

Shoulder Section											
Shldr. Width W_s (ft)	Side Slope S:1	Case	Quantity in Tons Per Mile*								
			Surfacing Depth (ft)								
			0.05	0.10	0.15	0.20	0.25	0.30	0.35	0.40	0.45	0.50
10	2	1	182	366	551	739	928	1119	1312	1507	1704	1903
		2	773	969	1167	1367	1569	1773	1979	2187	2397	2609
		3	N/A	N/A	N/A	N/A	N/A	543	724	908	1094	1281
		4	182	366	552	740	930	1122	1315	1511	1709	1909
	3	1	182	368	556	747	941	1137	1337	1539	1745	1953
		2	802	1007	1215	1426	1640	1858	2079	2303	2530	2760
		3	N/A	N/A	N/A	N/A	N/A	543	725	910	1098	1289
		4	182	368	557	749	944	1143	1344	1549	1757	1968
	4	1	183	370	560	755	954	1156	1363	1573	1787	2006
		2	834	1049	1268	1492	1721	1954	2191	2433	2679	2930
		3	N/A	N/A	N/A	N/A	N/A	543	726	912	1103	1298
		4	183	371	563	760	961	1167	1377	1592	1811	2035
	6	1	184	374	570	773	982	1196	1417	1644	1878	2117
		2	913	1153	1399	1654	1916	2186	2464	2750	3043	3344
		3	N/A	N/A	N/A	N/A	N/A	543	727	917	1113	1316
		4	185	377	578	786	1001	1225	1456	1695	1942	2197
12	2	1	218	438	660	883	1109	1336	1566	1797	2030	2265
		2	1066	1301	1537	1776	2016	2259	2504	2750	2999	3249
		3	N/A	N/A	N/A	N/A	N/A	N/A	N/A	956	1175	1397
		4	218	438	660	884	1110	1339	1569	1801	2035	2271
	3	1	219	440	664	891	1121	1354	1590	1829	2071	2315
		2	1106	1351	1599	1850	2104	2362	2623	2887	3154	3424
		3	N/A	N/A	N/A	N/A	N/A	N/A	N/A	956	1177	1401
		4	219	441	666	894	1125	1360	1598	1839	2083	2330
	4	1	219	442	669	900	1134	1373	1616	1862	2113	2367
		2	1151	1407	1668	1933	2203	2478	2757	3040	3328	3621
		3	N/A	N/A	N/A	N/A	N/A	N/A	N/A	956	1179	1405
		4	219	443	672	904	1142	1384	1630	1881	2137	2397
	6	1	220	446	679	918	1162	1413	1671	1934	2203	2479
		2	1259	1544	1836	2136	2444	2759	3083	3414	3752	4099
		3	N/A	N/A	N/A	N/A	N/A	N/A	N/A	957	1182	1413
		4	221	450	686	930	1182	1442	1709	1985	2268	2558
Pavement Section												
Width W_P (ft)			**0.05**	**0.10**	**0.15**	**0.20**	**0.25**	**0.30**	**0.35**	**0.40**	**0.45**	**0.50**
11			199	398	597	796	995	1194	1393	1592	1791	1990
12			217	434	651	868	1085	1302	1519	1737	1954	2171
22			398	796	1194	1592	1990	2388	2786	3184	3582	3980
24			434	868	1302	1737	2171	2605	3039	3473	3907	4341

*Tabulated quantities are based on compacted weight of 1.85 tons/yd^3

Exhibit 620-5d Estimating: Base and Surfacing Quantities

Shoulder Section											
Shldr. Width W_s (ft)	Side Slope S:1	Case	Quantity in Tons Per Mile*								
			Surfacing Depth (ft)								
			0.55	0.60	0.65	0.70	0.75	0.80	0.85	0.90	0.95	1.00
10	2	1	2104	2306	2511	2717	2925	3135	3347	3561	3777	3995
		2	2823	3039	3257	3477	3699	3923	4149	4378	4608	4840
		3	1471	1662	1855	2050	2247	2446	2646	2849	3053	3260
		4	2111	2315	2521	2729	2939	3151	3366	3582	3800	4020
	3	1	2164	2378	2595	2815	3038	3264	3492	3724	3958	4195
		2	2994	3230	3470	3714	3960	4209	4462	4718	4977	5239
		3	1483	1680	1880	2082	2288	2496	2707	2921	3138	3358
		4	2183	2401	2621	2845	3072	3303	3536	3773	4013	4256
	4	1	2228	2454	2684	2918	3156	3398	3643	3893	4147	4404
		2	3186	3446	3710	3980	4253	4531	4814	5101	5393	5689
		3	1496	1699	1905	2116	2330	2548	2770	2996	3227	3460
		4	2263	2496	2734	2976	3222	3473	3729	3989	4253	4522
	6	1	2363	2615	2873	3137	3407	3684	3966	4255	4550	4851
		2	3653	3969	4294	4626	4965	5313	5668	6031	6402	6781
		3	1524	1739	1960	2187	2420	2660	2906	3157	3415	3679
		4	2459	2729	3007	3292	3585	3887	4195	4512	4836	5168
12	2	1	2502	2740	2981	3224	3468	3714	3962	4212	4464	4718
		2	3502	3757	4013	4272	4533	4795	5060	5327	5596	5866
		3	1620	1845	2072	2301	2532	2765	2999	3236	3474	3714
		4	2509	2750	2992	3236	3482	3730	3981	4233	4487	4743
	3	1	2562	2813	3066	3322	3581	3843	4107	4375	4645	4919
		2	3698	3975	4255	4538	4824	5114	5406	5702	6001	6304
		3	1627	1857	2089	2324	2562	2803	3047	3294	3544	3796
		4	2581	2835	3092	3352	3615	3882	4151	4424	4700	4980
	4	1	2626	2888	3154	3424	3698	3976	4258	4544	4834	5128
		2	3918	4220	4526	4837	5152	5472	5796	6125	6458	6796
		3	1635	1869	2107	2348	2594	2844	3098	3355	3617	3882
		4	2661	2930	3204	3482	3765	4052	4344	4640	4941	5246
	6	1	2761	3049	3343	3643	3950	4262	4581	4906	5237	5575
		2	4453	4815	5185	5562	5948	6341	6742	7150	7566	7991
		3	1651	1894	2144	2400	2662	2930	3205	3485	3772	4065
		4	2857	3163	3477	3799	4128	4465	4810	5163	5524	5892

Pavement Section										
Width W_P (ft)	0.55	0.60	0.65	0.70	0.75	0.80	0.85	0.90	0.95	1.00
11	2189	2388	2587	2786	2985	3184	3383	3582	3781	3980
12	2388	2605	2822	3039	3256	3473	3690	3907	4124	4341
22	4378	4775	5173	5571	5969	6367	6765	7163	7561	7959
24	4775	5210	5644	6078	6512	6946	7380	7814	8249	8683

*Tabulated quantities are based on compacted weight of 1.85 tons/yd^3

Exhibit 620-5e Estimating: Base and Surfacing Quantities

Shoulder Section											
Shldr. Width W_s (ft)	Side Slope S:1	Case	Quantity in Tons Per Mile*								
			Surfacing Depth (ft)								
			1.05	1.10	1.15	1.20	1.25	1.30	1.35	1.40	1.45	1.50
4	2	1	1935	2048	2163	2279	2398	2518	2640	2765	2891	3019
		2	2157	2277	2399	2524	2650	2779	2909	3042	3176	3312
		3	1759	1867	1977	2089	2203	2319	2437	2557	2678	2802
		4	1963	2078	2196	2315	2437	2561	2686	2814	2943	3075
	3	1	2156	2290	2428	2568	2711	2857	3006	3157	3312	3470
		2	2480	2629	2781	2936	3094	3255	3420	3588	3759	3933
		3	1932	2059	2190	2323	2459	2598	2740	2885	3033	3183
		4	2223	2364	2509	2656	2806	2960	3117	3277	3441	3607
	4	1	2387	2543	2704	2869	3038	3210	3387	3567	3752	3940
		2	2844	3025	3210	3399	3593	3792	3995	4202	4415	4631
		3	2113	2260	2412	2567	2726	2890	3057	3228	3403	3582
		4	2517	2686	2860	3039	3222	3410	3602	3799	4000	4206
	6	1	2879	3084	3295	3513	3736	3966	4201	4443	4691	4946
		2	3729	3986	4252	4525	4806	5094	5391	5695	6007	6327
		3	2499	2689	2886	3088	3297	3512	3733	3960	4193	4433
		4	3229	3468	3715	3969	4232	4502	4779	5065	5358	5659
6	2	1	2695	2844	2995	3147	3302	3459	3617	3778	3940	4104
		2	3083	3242	3403	3566	3731	3898	4067	4238	4411	4586
		3	2369	2511	2655	2802	2949	3099	3251	3404	3560	3717
		4	2722	2874	3028	3184	3341	3501	3663	3827	3993	4160
	3	1	2916	3086	3260	3436	3615	3798	3983	4170	4361	4555
		2	3440	3629	3821	4016	4214	4416	4620	4828	5039	5253
		3	2521	2681	2844	3010	3179	3351	3525	3703	3883	4067
		4	2983	3160	3341	3524	3711	3901	4094	4290	4490	4692
	4	1	3146	3339	3536	3737	3942	4151	4364	4580	4801	5026
		2	3843	4065	4291	4523	4758	4998	5243	5492	5746	6004
		3	2679	2858	3041	3228	3418	3613	3812	4014	4221	4431
		4	3276	3482	3692	3907	4127	4350	4579	4812	5049	5291
	6	1	3639	3880	4127	4381	4640	4906	5178	5456	5741	6031
		2	4820	5123	5434	5753	6079	6413	6755	7105	7462	7827
		3	3017	3236	3461	3693	3930	4174	4423	4679	4941	5210
		4	3989	4264	4547	4837	5136	5442	5756	6078	6407	6745
8	2	1	3454	3640	3827	4016	4207	4399	4594	4791	4989	5189
		2	4055	4253	4452	4654	4858	5063	5271	5480	5692	5906
		3	2939	3115	3293	3473	3655	3839	4024	4212	4401	4592
		4	3482	3670	3860	4052	4246	4442	4640	4840	5042	5246
	3	1	3675	3882	4092	4304	4520	4738	4959	5183	5410	5640
		2	4449	4677	4909	5144	5382	5624	5869	6116	6367	6622
		3	3070	3263	3459	3658	3859	4064	4271	4481	4695	4911
		4	3743	3956	4173	4392	4615	4841	5071	5303	5539	5778
	4	1	3906	4135	4368	4606	4847	5092	5341	5593	5850	6111
		2	4891	5155	5423	5696	5973	6255	6541	6832	7127	7427
		3	3208	3418	3632	3851	4073	4299	4529	4763	5001	5243
		4	4036	4278	4524	4775	5031	5291	5556	5825	6098	6376
	6	1	4399	4676	4959	5249	5545	5847	6155	6469	6790	7116
		2	5966	6315	6671	7035	7407	7787	8174	8569	8972	9383
		3	3501	3749	4002	4262	4529	4801	5079	5364	5655	5952
		4	4748	5060	5379	5706	6040	6383	6733	7091	7456	7830

*Tabulated quantities are based on compacted weight of 1.85 tons/yd^3

Exhibit 620-5f Estimating: Base and Surfacing Quantities

Shoulder Section											
Shldr. Width W_s (ft)	Side Slope S:1	Case	Quantity in Tons Per Mile*								
			Surfacing Depth (ft)								
			1.55	1.60	1.65	1.70	1.75	1.80	1.85	1.90	1.95	2.00
4	2	1	3148	3280	3414	3549	3687	3826	3967	4110	4255	4402
		2	3451	3591	3734	3878	4025	4173	4324	4477	4631	4788
		3	2927	3054	3183	3314	3447	3582	3718	3857	3997	4139
		4	3209	3344	3482	3622	3763	3907	4053	4201	4350	4502
	3	1	3630	3793	3959	4129	4300	4475	4653	4834	5017	5203
		2	4110	4291	4475	4662	4852	5045	5242	5441	5644	5850
		3	3337	3493	3652	3814	3979	4147	4318	4492	4668	4848
		4	3777	3950	4126	4305	4488	4673	4862	5054	5250	5448
	4	1	4133	4329	4529	4733	4941	5153	5369	5589	5812	6040
		2	4852	5078	5308	5543	5782	6026	6274	6527	6784	7046
		3	3764	3951	4142	4337	4535	4738	4944	5155	5369	5587
		4	4416	4631	4850	5074	5302	5535	5773	6015	6261	6512
	6	1	5206	5473	5745	6024	6310	6601	6898	7202	7512	7828
		2	6654	6989	7332	7683	8041	8407	8781	9163	9552	9950
		3	4678	4930	5188	5452	5722	5999	6282	6570	6865	7166
		4	5968	6285	6609	6941	7281	7628	7984	8347	8718	9096
6	2	1	4270	4438	4608	4779	4953	5128	5306	5485	5666	5849
		2	4763	4942	5123	5306	5491	5678	5868	6059	6252	6447
		3	3876	4038	4201	4365	4532	4701	4871	5044	5218	5394
		4	4330	4502	4676	4852	5030	5210	5391	5575	5761	5949
	3	1	4752	4951	5153	5359	5567	5778	5992	6208	6428	6651
		2	5471	5691	5915	6142	6372	6605	6842	7082	7325	7571
		3	4253	4442	4634	4829	5026	5227	5430	5637	5846	6058
		4	4898	5107	5320	5535	5754	5976	6201	6429	6660	6895
	4	1	5254	5486	5723	5963	6207	6455	6707	6963	7223	7487
		2	6267	6534	6806	7082	7363	7648	7938	8233	8532	8835
		3	4645	4864	5086	5312	5542	5776	6014	6256	6501	6751
		4	5537	5788	6044	6304	6569	6838	7111	7389	7672	7959
	6	1	6328	6630	6939	7254	7576	7903	8237	8577	8923	9275
		2	8200	8581	8969	9365	9769	10181	10600	11028	11463	11905
		3	5484	5765	6051	6344	6643	6949	7260	7578	7901	8231
		4	7090	7442	7803	8171	8547	8931	9322	9721	10128	10543
8	2	1	5391	5595	5801	6009	6219	6431	6644	6859	7077	7296
		2	6121	6339	6559	6780	7004	7230	7457	7687	7919	8153
		3	4785	4980	5177	5376	5577	5779	5984	6190	6398	6608
		4	5452	5660	5870	6082	6296	6512	6730	6950	7172	7396
	3	1	5873	6109	6347	6589	6833	7080	7330	7583	7839	8098
		2	6879	7140	7403	7670	7940	8214	8490	8770	9053	9339
		3	5129	5351	5576	5803	6034	6267	6503	6743	6985	7229
		4	6020	6265	6514	6765	7020	7278	7539	7804	8071	8342
	4	1	6376	6644	6917	7193	7473	7758	8046	8338	8634	8934
		2	7731	8040	8354	8671	8994	9321	9652	9988	10329	10674
		3	5488	5738	5992	6249	6511	6776	7046	7319	7596	7877
		4	6659	6946	7238	7534	7835	8140	8450	8764	9083	9406
	6	1	7449	7788	8133	8485	8842	9206	9575	9951	10333	10722
		2	9801	10227	10661	11103	11552	12009	12474	12947	13427	13915
		3	6255	6565	6880	7202	7530	7864	8204	8550	8903	9262
		4	8211	8600	8997	9401	9813	10233	10661	11096	11539	11990

*Tabulated quantities are based on compacted weight of 1.85 tons/yd^3

Exhibit 620-5g Estimating: Base and Surfacing Quantities

Shoulder Section											
Shldr. Width W_s (ft)	Side Slope S:1	Case	Quantity in Tons Per Mile*								
			Surfacing Depth (ft)								
			1.05	1.10	1.15	1.20	1.25	1.30	1.35	1.40	1.45	1.50
10	2	1	4214	4436	4659	4884	5111	5340	5571	5804	6038	6275
		2	5074	5310	5548	5788	6031	6275	6521	6769	7019	7272
		3	3468	3678	3890	4104	4320	4537	4757	4978	5201	5427
		4	4242	4466	4692	4920	5150	5382	5617	5853	6091	6331
	3	1	4435	4678	4924	5173	5424	5679	5936	6196	6460	6726
		2	5505	5774	6045	6320	6599	6880	7165	7453	7744	8038
		3	3581	3806	4035	4266	4501	4738	4978	5221	5467	5715
		4	4503	4752	5005	5261	5520	5782	6048	6316	6588	6863
	4	1	4666	4931	5201	5474	5751	6032	6317	6606	6899	7196
		2	5990	6295	6605	6919	7238	7561	7889	8221	8558	8900
		3	3698	3940	4186	4436	4689	4947	5208	5474	5743	6017
		4	4796	5074	5357	5644	5935	6232	6532	6838	7147	7462
	6	1	5158	5472	5792	6117	6449	6787	7132	7482	7839	8202
		2	7167	7561	7963	8373	8790	9215	9648	10088	10537	10993
		3	3950	4226	4509	4798	5093	5394	5701	6015	6334	6660
		4	5508	5856	6211	6574	6945	7323	7710	8104	8506	8915
12	2	1	4974	5231	5491	5752	6015	6281	6548	6816	7087	7360
		2	6139	6414	6691	6969	7250	7533	7818	8104	8393	8684
		3	3956	4200	4446	4694	4944	5195	5449	5704	5961	6220
		4	5002	5262	5524	5788	6055	6323	6593	6866	7140	7416
	3	1	5195	5474	5756	6041	6329	6619	6913	7209	7509	7811
		2	6609	6918	7230	7545	7863	8184	8509	8837	9168	9502
		3	4052	4310	4571	4836	5103	5372	5645	5921	6199	6481
		4	5262	5548	5837	6129	6424	6723	7024	7329	7637	7948
	4	1	5425	5727	6033	6342	6656	6973	7294	7619	7948	8282
		2	7138	7485	7836	8192	8553	8917	9287	9661	10039	10422
		3	4151	4425	4702	4983	5268	5557	5850	6147	6448	6753
		4	5556	5870	6189	6512	6840	7172	7509	7851	8197	8547
	6	1	5918	6268	6624	6986	7354	7728	8109	8495	8888	9287
		2	8422	8862	9309	9764	10227	10698	11176	11662	12156	12657
		3	4364	4669	4981	5298	5622	5952	6288	6630	6979	7333
		4	6268	6652	7043	7442	7849	8264	8687	9117	9555	10001

Pavement Section										
Width W_P (ft)	1.05	1.10	1.15	1.20	1.25	1.30	1.35	1.40	1.45	1.50
11	4179	4378	4576	4775	4974	5173	5372	5571	5770	5969
12	4558	4775	4993	5210	5427	5644	5861	6078	6295	6512
22	8357	8755	9153	9551	9949	10347	10745	11143	11541	11939
24	9117	9551	9985	10419	10853	11287	11722	12156	12590	13024

*Tabulated quantities are based on compacted weight of 1.85 tons/yd^3

Exhibit 620-5h Estimating: Base and Surfacing Quantities

Shoulder Section											
Shldr. Width W_s (ft)	Side Slope S:1	Case	Quantity in Tons Per Mile*								
			Surfacing Depth (ft)								
			1.55	1.60	1.65	1.70	1.75	1.80	1.85	1.90	1.95	2.00
10	2	1	6513	6753	6995	7239	7485	7733	7983	8234	8488	8743
		2	7526	7782	8041	8301	8563	8827	9094	9362	9632	9905
		3	5654	5883	6113	6346	6581	6817	7056	7296	7538	7782
		4	6573	6818	7064	7312	7562	7814	8069	8325	8583	8843
	3	1	6995	7266	7541	7819	8099	8382	8669	8958	9250	9545
		2	8335	8636	8940	9247	9557	9870	10187	10506	10829	11156
		3	5967	6221	6479	6739	7002	7268	7537	7809	8084	8361
		4	7141	7423	7707	7995	8286	8581	8878	9179	9482	9789
	4	1	7497	7802	8111	8423	8740	9060	9385	9713	10045	10381
		2	9246	9596	9951	10311	10675	11043	11416	11794	12176	12563
		3	6294	6575	6860	7149	7442	7739	8040	8344	8653	8966
		4	7780	8104	8432	8764	9101	9442	9788	10139	10494	10853
	6	1	8571	8946	9327	9715	10108	10508	10914	11326	11744	12169
		2	11457	11928	12408	12895	13390	13892	14403	14921	15447	15980
		3	6992	7330	7674	8025	8382	8744	9113	9488	9870	10257
		4	9333	9758	10191	10631	11079	11536	11999	12471	12950	13437
12	2	1	7634	7911	8189	8469	8751	9035	9321	9609	9899	10190
		2	8977	9272	9569	9868	10168	10471	10776	11083	11392	11703
		3	6481	6744	7009	7276	7544	7814	8087	8361	8637	8915
		4	7695	7975	8258	8542	8828	9117	9407	9700	9994	10291
	3	1	8116	8424	8735	9049	9365	9685	10007	10333	10661	10992
		2	9840	10180	10524	10871	11221	11575	11931	12291	12654	13020
		3	6765	7052	7342	7635	7931	8230	8532	8836	9144	9454
		4	8263	8581	8901	9225	9553	9883	10216	10553	10893	11236
	4	1	8619	8960	9304	9653	10006	10363	10723	11088	11456	11829
		2	10810	11202	11599	12000	12405	12816	13230	13650	14073	14502
		3	7061	7374	7691	8011	8335	8664	8996	9332	9672	10017
		4	8902	9262	9626	9994	10367	10745	11127	11514	11905	12300
	6	1	9692	10103	10521	10945	11374	11810	12253	12701	13155	13616
		2	13167	13684	14209	14741	15282	15830	16386	16949	17521	18100
		3	7694	8061	8434	8813	9199	9590	9988	10392	10802	11218
		4	10454	10915	11384	11861	12346	12838	13338	13846	14361	14885

Pavement Section										
Width W_P (ft)	1.55	1.60	1.65	1.70	1.75	1.80	1.85	1.90	1.95	2.00
11	6168	6367	6566	6765	6964	7163	7362	7561	7760	7959
12	6729	6946	7163	7380	7597	7814	8031	8249	8466	8683
22	12337	12735	13133	13530	13928	14326	1472	14122	15520	15918
24	13458	13892	14326	14761	15195	15629	16063	16497	16931	17365

*Tabulated quantities are based on compacted weight of 1.85 tons/yd^3

Chapter 630 Geosynthetics

630.01 General
630.02 References
630.03 Geosynthetic Types and Characteristics
630.04 Geosynthetic Function Definitions and Applications
630.05 Design Approach for Geosynthetics
630.06 Design Responsibility
630.07 Documentation

630.01 General

Geosynthetics include a variety of manufactured products that are used by the Washington State Department of Transportation (WSDOT) in drainage, earthwork, erosion control, and soil reinforcement applications.

The following geosynthetic applications are addressed in the *Standard Specifications for Road, Bridge, and Municipal Construction (Standard Specifications)*:

- Low survivability underground drainage
- Moderate survivability underground drainage
- Separation
- Soil stabilization
- Moderate survivability permanent erosion control
- High survivability permanent erosion control
- Ditch lining
- Temporary silt fence

The *Standard Specifications* addresses geosynthetic properties as well as installation requirements and are not site-specific. The geosynthetic properties provided are based on the range of soil conditions likely to be encountered in Washington for the applications defined. Other applications, such as prefabricated edge drains, pond liners, and geotextile retaining walls, are currently handled by special provision.

Design responsibilities are discussed in 630.05 and illustrated in Exhibits 630-4 and 630-5.

This chapter does not address applications where geosynthetics are used to help establish vegetation through temporary prevention of erosion (vegetation mats).

630.02 References

Highway Runoff Manual, M 31-15, WSDOT

Hydraulics Manual, M 23-03, WSDOT

Plans Preparation Manual, M 22-31, WSDOT

Standard Specifications for Road, Bridge, and Municipal Construction (Standard Specifications), M 41-10, WSDOT

Temporary Erosion and Sediment Control Manual, M 3109, WSDOT

WSDOT *Pavement Policy*, available at the Pavements website:
www.wsdot.wa.gov/business/materialslab/pavements/default.htm

630.03 Geosynthetic Types and Characteristics

Geosynthetics include woven and nonwoven geotextiles, geogrids, geonets, geomembranes, and geocomposites. (Examples of the various types of geosynthetics are provided in Exhibit 630-6.) Terms used in the past for these construction materials include *fabrics*, *filter fabric*, or *filter cloth,* which are for the most part synonymous with the newer term *geotextile*.

(1) Definitions

Definitions of the geosynthetic types are as follows:

(a) **Woven Geotextiles**

Slit polymer tapes, monofilament fibers, fibrillated yarns, or multifilament yarns simply woven into a mat. Woven geotextiles generally have relatively high strength and stiffness and, except for the monofilament wovens, relatively poor drainage characteristics.

(b) **Nonwoven Geotextiles**

A sheet of continuous or staple fibers entangled randomly into a felt for needle-punched nonwovens and pressed and melted together at the fiber contact points for heat-bonded nonwovens. Nonwoven geotextiles tend to have low-to-medium strength and stiffness with high elongation at failure and relatively good drainage characteristics. The high elongation characteristic gives them superior ability to deform around stones and sticks.

(c) **Geogrids**

A polymer grid mat constructed either of coated yarns or a punched and stretched polymer sheet. Geogrids usually have high strength and stiffness and are used primarily for soil reinforcement.

(d) **Geonets**

Similar to geogrids, but typically lighter weight and weaker, with smaller mesh openings. Geonets are used in light reinforcement applications or are combined with drainage geotextiles to form a drainage structure.

(e) **Geomembranes**

Impervious polymer sheets that are typically used to line ponds or landfills. In some cases, geomembranes are placed over moisture-sensitive swelling clays to control moisture.

(f) **Geocomposites**

Prefabricated edge drains, wall drains, and sheet drains that typically consist of a cuspated or dimpled polyethylene drainage core wrapped in a geotextile. The geotextile wrap keeps the core clean so that water can freely flow through the drainage core, which acts as a conduit. Prefabricated edge drains are used in place of shallow geotextile-wrapped trench drains at the edges of the roadway to provide subgrade and base drainage. Wall drains and sheet drains are typically placed between the back of the wall and the soil to drain the soil retained by the wall.

630.04 Geosynthetic Function Definitions and Applications

The function of the geosynthetic varies with the application. (See Exhibit 630-7 for examples of the various applications.) The geosynthetic must be designed with its application function(s) in mind. Typical geosynthetic functions include filtration, drainage, separation, reinforcement, and erosion control.

(1) Definitions

Definitions of these functions and examples of their dominant applications are as follows:

(a) **Geosynthetic Filtration**

The passage of water through the geosynthetic relatively unimpeded (permeability or permittivity) without allowing passage of soil through the geosynthetic (retention). This is the primary function of geotextiles in underground drainage applications.

(b) **Drainage**

The carrying of water in the plane of the geosynthetic as a conduit (transmissivity) is a primary function of geocomposite drains. In some cases, the function includes thick, nonwoven needle-punched geotextiles placed in underground drainage applications where water must be transported away from a given location by the geosynthetic itself.

(c) **Separation**

The prevention of the mixing of two dissimilar materials. This is a primary function of geotextiles placed between a fine-grained subgrade and a granular base course beneath a roadway.

(d) **Reinforcement**

The strengthening of a soil mass by the inclusion of elements (geosynthetics) that have tensile strength. This is the primary function of high-strength geotextiles and geogrids in geosynthetic reinforced wall or slope applications, or in roadways placed over very soft subgrade soils that are inadequate to support the weight of the construction equipment or even the embankment itself.

(e) **Geosynthetic Erosion Control**

The minimizing of surficial soil particle movement due to the flow of water over the surface of bare soil or due to the disturbance of soil caused by construction activities under or near bodies of water. This is the primary function of geotextiles used as silt fences or placed beneath riprap or other stones on soil slopes. Silt fences keep eroded soil particles on the construction site, whereas geotextiles placed beneath riprap or other stones on soil slopes prevent erosion from taking place at all. In general, the permanent erosion control methods described in this chapter are only used where more natural means (like the use of biodegradable vegetation mats to establish vegetation to prevent erosion) are not feasible.

These functions control some of the geosynthetic properties, such as apparent opening size (AOS) and permittivity, and in some cases load-strain characteristics.

The application will also affect the geosynthetic installation conditions. These installation conditions influence the remaining geosynthetic properties needed, based on the *survivability* level required.

(f) **Geosynthetic Survivability**

The ability of the geosynthetic to resist installation conditions without significant damage, such that the geosynthetic can function as intended. Survivability affects the strength properties of the geosynthetic required.

630.05 Design Approach for Geosynthetics

The following questions must be answered to complete a geosynthetic design:

- Is a geosynthetic really needed?
- What geosynthetic properties will ensure the geosynthetic functions as intended?
- Where should the geosynthetic be located?
- Will maintenance of the geosynthetic, or the structure of which it is a part, be needed? If so, how will it be maintained?

The site conditions and purpose for the geotextile are reviewed to determine whether or not a geotextile is needed.

- For most drainage, separation, soil stabilization, permanent erosion control, and silt fence applications, if a geotextile is needed, the geotextile properties in the *Standard Specifications* can be used.
- In some situations where soil conditions are especially troublesome or in critical or high-risk applications, a project-specific design may be needed.
- The location of the geosynthetic will depend on how it is intended to function. (See Exhibit 630-7 for examples.)
- Consider the flow path of any groundwater or surface water when locating and selecting the geotextile to be used. For example, in permanent erosion control applications, water may flow to the geotextile from the existing ground as well as from the surface through wave action, stream flow, or overland sheet flow. For saturated fine sandy or silty subgrades, water must be able to flow from the subgrade through the geotextile soil stabilization layer during the pumping action caused by traffic loads.

Background information and the answers to each of these questions, or at least guidance to obtaining the answers to these questions, are provided for each of the following *Standard Specifications* applications:

(1) Underground Drainage: Low and Moderate Survivability

Geotextiles used for underground drainage must provide filtration to allow water to reach the drain aggregate without allowing the aggregate to be contaminated by finer soil particles.

Geotextile filtration properties are a function of the soil type. For underground drainage applications, if the subgrade soil is relatively clean gravel or coarse sand, a geotextile is probably not required. At issue is whether or not there are enough fines in the surrounding soil to eventually clog the drain rock or drain pipe if unrestricted flow toward the drain is allowed.

To approximately match the geotextile filtration properties to various soil types, specifications for three classes of Construction Geotextile for Underground Drainage are available in the *Standard Specifications*. For underground drainage applications, use the gradation of the soil, specifically the percent by weight passing the #200 sieve, to select the drainage geotextile class required. Base your selection of the appropriate class of geotextile on Exhibit 630-1.

Percent Passing the #200 Sieve	Geotextile Class
Less than 15%	A
15% to 50%	B
Greater than 50%	C

Selection Criteria for Geotextile Class
Exhibit 630-1

Obtain soil samples for geotextile underdrain design every 300 feet along the roadway alignment, using hand holes, and at major soil type transitions. This may be spread to every 1000 feet if the soil conditions appear to be uniform. Use existing soil data where feasible instead of taking new soil samples.

If soil conditions vary widely along the alignment where underground drainage geotextile is anticipated, different classes of drainage geotextile may be required for specific sections of a continuous system.

Strength properties for the underground drainage geotextile depend on the survivability level required to resist installation stresses.

Low survivability designates that the installation stresses placed on the geotextile will be relatively low, requiring only moderate geotextile strength to resist potentially damaging installation conditions. Examples of low survivability level underground drainage applications include:

- Trench drains.
- Drains placed behind walls or other structures to drain the backfill.
- A geotextile filter sheet placed behind a gabion wall to prevent fines from being washed through the gabion wall face. Trench depths, or the height of the geotextile filter sheet behind gabion walls, must be less than or equal to 6 feet for the low survivability level.

In moderate survivability applications, significant installation stresses may occur, requiring higher geotextile strength. Examples of the moderate survivability application include:

- Trench drains with a depth of greater than 6 feet.
- A geotextile filter sheet behind a gabion wall with a height greater than 6 feet.
- Any area drain.

An area drain is defined as a geotextile placed over or under a horizontal-to-moderately sloping (1.5H:1V or flatter slope) layer of drainage aggregate. Examples of area drains include:

- Drainage layers over cut-and-cover tunnels.
- Rock buttress drainage.

- Permeable base beneath highway pavement (see the *WSDOT Pavement Policy* for additional information on permeable bases).
- A parking lot drainage layer.

Note that pipe wrapping (the geotextile is wrapped around the surface of the pipe) is not included as an underground drainage application.

Locate the geotextile such that it will function as intended. For example, if the objective is to keep the drainage aggregate surrounding a drain pipe clean, locate the geotextile so that it completely separates the drainage aggregate from more silty surrounding soils, which may include native soils as well as relatively silty roadway base or fill materials.

Consider the flow path of any groundwater or surface water when locating the geotextile.

The flow path from the geotextile, as part of the groundwater drainage, is typically directed to a surface water conveyance system. Design of surface water conveyance is guided by the *Hydraulics Manual*. The surface water conveyance must be low enough to prevent backflow and charging of the groundwater drainage—typically, by matching inverts of groundwater drainage to crowns of surface water conveyance pipes. A 1-foot allowance is usually applied when connecting to open water or ditches.

(2) Separation

Geotextile used for separation must prevent penetration of relatively fine grained subgrade soil into the ballast or other roadway or parking lot surfacing material to prevent contamination of the surfacing material (the separation function). This application may also apply to situations other than beneath roadway or parking lot surfacing where it is not necessary for water to drain through the geotextile unimpeded (filtration), but where separation of two dissimilar materials is required.

Separation geotextile should only be used in roadway applications where the subgrade is can be prepared and compacted as required in the *Standard Specifications*, but without removal and replacement of the subgrade soil with granular material. Such removal and replacement defeats the purpose of the geotextile separator.

Separation geotextile placed beneath roadway surfacing is feasible if the subgrade resilient modulus is greater than 5,800 psi and if a saturated fine sandy, silty, or clayey subgrade is not likely to be present. Note that the feasibility of separation geotextile may be dependent on the time of year and weather conditions expected when the geotextile is to be installed.

For separation applications, a geotextile is not needed if the subgrade is dense and granular (silty sands and gravels), but is not saturated fine sands. In general, a separation geotextile is not needed if the subgrade resilient modulus is greater than 15,000 psi.

(3) Soil Stabilization

Geotextile used for soil stabilization must function as a separator, a filtration layer, and (to a minor extent) a reinforcement layer. This application is similar to the separation application, except the subgrade is anticipated to be softer and wetter than in the separation application.

Soil stabilization geotextile is used in roadway applications if the subgrade is too soft and wet to be prepared and compacted as required in the *Standard Specifications*. Soil stabilization geotextile is placed directly on the soft subgrade material, even if some overexcavation of the subgrade is performed. Backfill to replace the overexcavated subgrade is not placed below the geotextile soil stabilization layer, as this would defeat the purpose of the geotextile.

Anticipate the need for soil stabilization geotextile if the subgrade resilient modulus is less than or equal to 5,800 psi, or if a saturated fine sandy, silty, or clayey subgrade is likely to be present.

Consider the flow path of any groundwater or surface water when locating the soil stabilization geotextile and when selecting the geotextile to be used. For saturated fine sandy or silty subgrades, water must be able to flow from the subgrade through the geotextile soil stabilization layer during the pumping action caused by traffic loads.

Even if the subgrade is not anticipated to be saturated based on available data, if the subgrade is silty or clayey and it is anticipated that the geotextile will be installed during prolonged wet weather, a soil stabilization geotextile may still be needed.

Soil stabilization geotextile should not be used for roadway fills greater than 5 feet high or when extremely soft and wet silt, clay, or peat is anticipated at the subgrade level (for example, the deposits encountered in wetlands). In such cases, the reinforcement function becomes more dominant, requiring a site-specific design.

(4) Permanent Erosion Control: Moderate and High Survivability

The primary function of geotextile used for permanent erosion control is to protect the soil beneath it from erosion due to water flowing over the protected soil.

The need for a permanent erosion control geotextile depends on the type and magnitude of water flow over the soil being considered for protection, the soil type in terms of its erodability, and the type and amount of vegetative cover present (see the *Highway Runoff Manual*).

The source of flowing water could be streams, constructed channels, wave action, or runoff. Water may also flow from the soil behind the geotextile depending on the groundwater level.

If groundwater cannot escape through the geotextile, an erosion control system failure termed *ballooning* (resulting from water pressure buildup behind the geotextile) or soil piping could occur. Therefore, the geotextile must have good filtration characteristics.

Three classes of permanent erosion control geotextile are available to approximately match geotextile filtration characteristics to the soil. In order to select the drainage geotextile class, determine the gradation of the soil, specifically the percent by weight passing the #200 sieve. Base selection of the appropriate class of geotextile on Exhibit 630-1.

A minimal amount of soil sampling and testing is needed to determine the geotextile class required. Permanent erosion control geotextile generally does not extend along the roadway alignment for significant distances as does underground drainage geotextile. One soil sample per permanent erosion control location is sufficient. If multiple erosion control locations are anticipated along a roadway alignment, soil sampling requirements for underground drainage can be applied.

If soil conditions vary widely along the alignment where permanent erosion control geotextile is anticipated, different classes of erosion control geotextile may be required for specific sections of a continuous system.

Examples of the permanent erosion control application are the placement of geotextile beneath riprap or gabions along drainage channels, shorelines, and waterways; around bridge piers; and under slope protection for highway cut or fill slopes.

If a moderate survivability geotextile is to be used, the geotextile must be protected by a 12-inch aggregate cushion and be placed on slopes of 2H:1V or flatter to keep installation stresses to a relatively low level. Large stones can cause significant damage to a moderate survivability geotextile if the geotextile is not protected in this manner. If these conditions are not met, then a high survivability erosion control geotextile must be used.

(5) Ditch Lining

The primary function of the geotextile in a ditch lining application is to protect the soil beneath it from erosion. This ditch lining application is limited to constructed ditches less than 16 feet wide at the top with side slopes of 2H:1V or flatter. If the ditch does not meet these requirements, then permanent erosion control, with moderate or high survivability geotextile, must be used. It is assumed that only quarry spall-sized stones or smaller will be placed on the geotextile, so only a moderate survivability geotextile will be required.

Filtration is not a significant function in this application. Since the ditch is relatively shallow, it is expected that the main water source will be the water carried by the ditch, and little water will pass through the geotextile.

Another application with a similar geotextile function is the placement of geotextile below culvert outlets to prevent erosion at the outlet.

(6) Temporary Silt Fence

The primary function of geotextile used in a temporary silt fence is to prevent eroded material from being transported away from the construction site by runoff water. The silt fence acts primarily as a temporary dam and secondarily as a filter.

In some cases, depending on the topography, the silt fence may also function as a barrier to direct flow to low areas at the bottom of swales where the water can be collected and temporarily ponded. It is desirable to avoid the barrier function as much as possible, as silt fences are best suited to intercepting sheet flow rather than the concentrated flows that would occur in swales or intermittent drainage channels.

To function as intended, the silt fence should have a low enough permeability to allow the water to be temporarily retained behind the fence, allowing suspended soil particles in the water to settle to the ground. If the retention time is too long, or if the flow rate of water is too high, the silt fence could be overtopped, thus allowing silt-laden water to escape. Therefore, a minimal amount of water must be able to flow through the fence at all times.

Temporary water ponding is considered the primary method of silt removal and the filtration capabilities of the fence are the second line of defense. However, removal of silt-sized particles from the water directly by the geotextile creates severe filtration conditions for the geotextile, forcing the geotextile to either blind or allow the fines to

pipe through the geotextile. (*Blinding* is the coating of the geotextile surface with soil particles such that the openings are effectively plugged.) If the geotextile openings (AOS) are designed to be small enough to capture most of the suspended soil particles, the geotextile will likely blind, reducing the permeability enough to allow water to overtop the fence. Therefore, it is best to allow some geotextile openings that are large enough to allow the silt-sized particles to easily pass through. Even if some silt particles pass through the fence, the water flow rate below the fence will be decreased and the volume of silt-laden water passing through the geotextile is likely to be relatively small and the water is partially filtered.

The geotextile apparent opening size (AOS) and permittivity are typically used to specify the filtration performance of geotextiles. The geotextile function in silt fence applications is more complex than this and AOS and permittivity do not relate directly to how well a silt fence will perform. However, nominal values of AOS and permittivity can be specified such that the types of geotextile products known to perform satisfactorily in this application are selected. These values are provided in the *Standard Specifications*.

The source of load on the geotextile is from silt buildup at the fence and water ponding. The amount of strength required to resist this load depends on whether or not the geotextile is supported with a wire or polymer grid mesh between the fence posts. Obviously, unsupported geotextile must have greater strength than supported geotextile. If the strength of the geotextile or its support system is inadequate, the silt fence could fail. Furthermore, unsupported geotextile must have enough stiffness that it does not deform excessively and allow silt-laden water to go over the top of the fence.

(a) **Need for Silt Fence**

The need for a silt fence can be anticipated where construction activities disturb and expose soil that could erode. The ground surface is considered disturbed if vegetative cover is at least partially removed over a significant area by construction activities. Consider whether or not silt-laden runoff water from the disturbed area can reach an environmentally sensitive area or a constructed stormwater system. If the exposed soil is a clean sand or gravel or if a significant zone of heavy vegetative cover separates the exposed soil from the environmentally sensitive area, a silt fence may not even be needed. Contact the Headquarters (HQ) Hydraulics Section for help in determining whether or not a silt fence is needed in such situations.

(b) **Feasibility of Silt Fence**

The feasibility of a geotextile silt fence depends on the magnitude of water flow to the fence, the steepness of the slope behind the fence ,and whether or not flow is concentrated at the fence. If the silt fence is not feasible, alternative erosion control methods may be needed (see the *Temporary Erosion and Sediment Control Manual*).

Consider all feasible erosion control options in terms of potential effectiveness and economy before making the final decision to use a silt fence. Select the best option for the site conditions, including site geometry and contours, soil type, and rainfall potential. Consider silt fences for temporary erosion control in disturbed areas in the following circumstances:

- Fully covering disturbed areas temporarily with polyethylene sheeting or other temporary covering is not feasible or practical.

- Permanent ground cover for disturbed areas is not yet established.
- Runoff water reaches the silt fence primarily as sheet flow rather than as concentrated flows, with the exception of some ditch and swale applications.
- Slopes above the silt fence are not steeper than 1.5H:1V.
- The sheet flow length (length of slope contributing runoff water to the silt fence) is not too long.

(c) Sheet Flow Length

Maximum sheet flow lengths allowed for silt fences are provided in Exhibit 630-2, which is based on the typical 2-year, 24-hour design storm for Washington, resulting in a 24-hour rainfall of 3 inches.

Slope	Sheet Flow Length
1.5H:1V	100 ft
2H:1V	115 ft
4H:1V	150 ft
6H:1V	200 ft

Maximum Sheet Flow Lengths for Silt Fences
Exhibit 630-2

The sheet flow length represents the area contributing runoff water from precipitation. The sheet flow length is defined in Exhibit 630-8. The sheet flow lengths provided in Exhibit 630-2 were determined assuming a bare soil condition, with the soil classified as a silt. These are worst-case assumptions because less runoff would be expected for sand or gravel soils or when some vegetation is present.

The sheet flow length is usually equal to or greater than the disturbed soil slope length. However, undisturbed sloping ground above the disturbed slope area may also contribute runoff to the silt fence area. The length of undisturbed sloping ground above the disturbed slope to be included in the total contributing slope length depends on the amount and type of vegetation present, the slope steepness, and the degree of development above the slope.

If unsure whether the proposed silt fence meets the requirements in Exhibit 630-2, contact the HQ Hydraulics Section for assistance.

Average or Ditch Swale Grade	Ditch or Swale Storage Length	Allowable Contributing Area per Foot of Ditch or Swale Storage Width
16%	13 ft	200 ft^2
10%	20 ft	250 ft^2
5%	40 ft	300 ft^2
4%	50 ft	400 ft^2
3%	65 ft	500 ft^2
2%	100 ft	600 ft^2
1%	200 ft	1000 ft^2

Maximum Contributing Area for Ditch and Swale Applications
Exhibit 630-3

(d) **Temporary Silt Fence**

Temporary silt fences may also be used in ditch or swale applications. If the area contributing runoff to the fence exceeds the value determined from Exhibit 630-3, hydraulic overload will occur. The ditch or swale storage length and width are defined in Exhibit 630-9. The assumptions used in the development of Exhibit 630-3 are the same as those used for Exhibit 630-2 in terms of the design storm and ground conditions.

As an example, if a site has a 13-foot-wide ditch with an average slope of 2%, the fence can be located such that 7800 ft^2 of area drain to it. If it appears that the area draining to the fence will be larger than the allowable, it may be possible to divide the contributing area into smaller areas and add a silt fence for each smaller area as shown in Exhibit 630-10.

The minimum storage length for the ditch behind each silt fence must be maintained. If this is not possible, it may be necessary to use an alternate erosion control structure, as described in the *Temporary Erosion and Sediment Control Manual*, or develop a special silt fence design.

Exhibit 630-3 was developed with the assumption that water will be able to pond to a depth of at least 2 feet behind the fence. If this is not the case (the ditch or swale depth is less than 2 feet), the table cannot be used. Furthermore, the ditch depth must be greater than the height of the silt fence at its lowest point within the ditch. Otherwise, there will not be enough storage available behind the fence and water will circumvent the fence by flowing around it.

(e) **Locating a Silt Fence**

Locate silt fences on contour as much as possible. At the ends of the fence, turn it up hill such that it captures the runoff water and prevents water from flowing around the end of the fence. This is illustrated in Exhibit 630-11.

Silt fences are designed to capture up to a 2-foot depth of water behind the fence. Therefore, the ground line at the ends of the fence must be at least 2 feet above the ground line at the lowest part of the fence. This 2-foot requirement applies to ditches as well as to general slope erosion control.

If the fence must cross contours (except for the ends of the fence), use gravel check dams placed perpendicular to the back of the fence to minimize concentrated flow and erosion along the back of the fence (see Exhibit 630-12).

- The gravel check dams are approximately 1 foot high at the back of the fence and are continued perpendicular to the fence at the same elevation until the top of the dam intercepts the ground surface behind the fence.
- Locate the gravel check dams every 10 feet along the fence.
- In general, the slope of the fence line is not to be steeper than 3H:1V.
- For the gravel check dams, use Crushed Surfacing Base Course, Gravel Backfill for Walls, or Permeable Ballast (see the *Standard Specifications*).

If the silt fence application is considered critical (such as when the fence is placed immediately adjacent to environmentally sensitive areas like streams, lakes, or wetlands), place a second silt fence below the first silt fence to capture any silt that passes through the first fence and/or place straw bales behind the silt fence. Locate silt fences at least 7 feet from an environmentally sensitive area.

Where this is impossible, and a silt fence must be used, a special design may be necessary.

Temporary silt fences are sometimes used to completely encircle underground drainage inlets or other similar features to prevent silt from entering the drainage system. This is acceptable, but the silt fence functions primarily as a barrier, and not as a ponding or filtering mechanism, unless the drainage inlet is in a depression that is large enough to allow water to pond behind the silt fence.

- If the drainage inlet and silt fence are not in a large enough depression, silt-laden water will simply be directed around the fence and must be captured by another fence or sedimentation pond downslope.
- If the depression is deep, locate the silt fence no more than 2 feet below the top of the depression to prevent overtopping. A site-specific design may be needed if the silt fence is located deeper than 2 feet within the depression.

It may be necessary to relocate silt fences during the course of a construction project as cuts and fills are built or as disturbed areas change. An erosion control/silt fence plan that accounts for the anticipated construction stages (and eventual removal) should be developed. Do not assume that one silt fence location can routinely be used for the entire life of the contract. Periodically check the locations in the field during the construction project, and field-adjust the silt fence locations as necessary to ensure the silt fences function as intended.

(7) Standard Specification Geotextile Application Identification in the Contract Plans

Identify the geotextile in the contract plan detail in a way that ties it to the appropriate application in the *Standard Specifications*. For example:

- If a geotextile is to be used to line an underground trench drain 3 feet deep and the native soil has less than 15% passing the #200 sieve, identify the geotextile on the plan sheet as "Construction Geotextile for Underground Drainage, Low Survivability, Class A."
- If the geotextile is to be placed beneath riprap on a slope without a cushion layer between the geotextile and the riprap, and the native soil contains 35% passing the #200 sieve, identify the geotextile on the plan sheet as "Construction Geotextile for Permanent Erosion Control, High Survivability, Class B."
- If the geotextile is to be placed between the roadway base course and a moist silt subgrade with a resilient modulus of 6,500 psi, and the roadway is planned to be constructed during the dry summer and early fall months, identify the geotextile on the plan sheet as "Construction Geotextile for Separation."

(8) Site-Specific Designs (All Applications)

A site-specific design is required:

- For all reinforcement applications.
- For applications not covered by the *Standard Specifications*.

Consider a site-specific design for:

- High-risk applications.
- Exceptionally large geotextile projects: if the geotextile quantity in a single application is over 35,000 yd^2 or over 85,000 yd^2 for the separation application.
- Severe or unusual soil or groundwater conditions.

- Soil in the vicinity of the proposed geotextile location that consists of alternate thin layers of silt or clay with potentially water-bearing sand layers on the order of 1 to 3 inches thick or less.
- Soil known through past experience to be problematic for geosynthetic drains.
- Drains in native soil behind structures except drains contained within granular backfill.
- Drains designed to stabilize unstable slopes.
- Drains designed to mitigate frost heave.

In such cases, obtain assistance from the HQ Materials Laboratory, Geotechnical Office. To initiate the special design, provide a plan and cross section showing:

- The geosynthetic structure to be designed.
- The structure's relative location to other adjacent structures that it could potentially affect.
- The structure's intended purpose.
- Any soil data in the vicinity.

Consider a site-specific design for temporary silt fences:

- If silt fence must be used in intermittent streams or where a significant portion of the silt fence functions as a barrier that directs flow to the lower portions of the silt fence.
- If the fence must be located on steep slopes.
- In situations not meeting the requirements in Exhibits 630-2 and 630-3.
- If the 2-year, 24-hour design storm for the site is greater than the 3 inches assumed for the development of Exhibits 630-2 and 630-3.
- Where concentrated flow is anticipated.
- If closer than 7 feet from an environmentally sensitive area.
- If more than 2 feet of storage depth is needed.

For a site-specific temporary silt fence design, obtain assistance from the HQ Hydraulics Section. To initiate the design, send the following information to the HQ Hydraulics Section and a copy to the HQ Materials Laboratory, Geotechnical Office:

- Plan sheets showing proposed silt fence locations and grading contours.
- Estimate of the area contributing runoff to each silt fence, including percentage and general type of vegetative cover within the contributing area.
- Any available site soil information.

For all site-specific designs of applications not covered by the *Standard Specifications*, complete plans and special provisions are needed. In general, for site-specific designs of *Standard Specifications* applications, only a minor modification of the appropriate geotextile property table will be needed.

630.06 Design Responsibility

The design responsibility and process for geotextile design are illustrated in Exhibits 630-4 and 630-5. The region Project Development Office, in particular the region Project Manager, is responsible to initiate and develop all geotextile designs for the *Standard Specifications*, except for roadway separation and soil stabilization applications, which are initiated and developed by the region Materials Laboratory.

The region Materials Laboratory assists the region Project Manager with *Standard Specifications* underground drainage and permanent erosion control designs.

The region Environmental Design Office assists with *Standard Specifications*, permanent erosion control, and temporary silt fence designs.

Once the region Project Manager or Materials Laboratory has determined that a geotextile is appropriate, development of a geotextile design for the *Standard Specifications* includes the development of plan details showing the plan location and cross section of the geotextile installation. Standard details for geotextiles as provided in the *Plans Preparation Manual* may be used or modified to adapt to the specific project situation. Note that only minimum dimensions for drains are provided in these standard details.

Site-specific geosynthetic designs and applications not addressed by the *Standard Specifications* are designed by the region with the assistance of the HQ Materials Laboratory, Geotechnical Office, or the HQ Hydraulics Section as described in 630.05.

Design assistance by the HQ Geotechnical Office or HQ Hydraulics Section for site-specific design of *Standard Specifications* applications includes determination of geosynthetic properties and other advice as needed to complete the geosynthetic plans and any special provisions required.


The HQ Geotechnical Office is fully responsible to develop and complete the following:

- Geosynthetic design, plan details that can be used to develop the contract plan sheets, and special provisions for geosynthetic reinforced walls, slopes, and embankments.
- Deep trench drains for landslide stabilization.
- Other applications that are an integral part of a Headquarters geotechnical design.


The region Project Manager incorporates the plan details and special provisions into the PS&E.

630.07 Documentation


Refer to Chapter 300 for design documentation requirements.




Design Process for Drainage and Erosion Control: Geotextiles and Nonstandard Applications
Exhibit 630-4




Design Process for Separation, Soil Stabilization, and Silt Fence
Exhibit 630-5



Slit Film Woven Geotextile




Monofilament Woven Geotextile




Multifilament Woven Geotextile

Examples of Various Geosynthetics


Exhibit 630-6





Needle-Punched Nonwoven Geotextile




Heat-Bonded Nonwoven Geotextile








Geocomposite Drains (Geotextile With Core)




Extruded and Woven Geogrids

Examples of Various Geosynthetics


Exhibit 630-6 (continued)




A. Underground Drainage:
Low Survivability
(Roadway Trench Drain)




B. Underground Drainage:
Moderate Survivability
(Area Drain Beneath Buttress)




C. Underground Drainage:
Moderate Survivability
(Geotextile Sheet Drain)



D. Underground Drainage:
Moderate Survivability
(Area Drain Under Parking Lot or Roadway)




E. Underground Drainage:
Low Survivability
(Wrapped Drain Behind Foundation)




F. Underground Drainage:
Moderate Survivability
(Deep Trench Drain for Slope Stabilization)


Geotextile Application Examples
Exhibit 630-7




G. Separation or Soil Stabilization for New Roadway
(Depends on Subgrade Condition)



H. Separation or Soil Stabilization for Widened Roadway
(Depends on Subgrade Condition)




I. Permanent Erosion Control:
Moderate Survivability




J. Permanent Erosion Control:
High Survivability

Geotextile Application Examples


Exhibit 630-7 (continued)



K. Ditch Lining




L. Silt Fence Not Immediately Adjacent to Environmentally Sensitive Area




M. Silt Fence Immediately Adjacent to Environmentally Sensitive Area

Geotextile Application Examples


Exhibit 630-7 (continued)




N. Prefabricated Edge Drain for Roadway




O. Prefabricated Drain Strip Behind Wall Face




P. Geosynthetic Wall



Q. Geosynthetic Reinforced Slope




R. Geosynthetic Reinforced Embankment



S. Geosynthetic Subgrade Reinforcement for Temporary Roads


Geotextile Application Examples

Exhibit 630-7 (continued)




* May need to be included as part of slope length depending on vegetative cover, slope steepness, and degree of development above slope

Definition of Slope Length
Exhibit 630-8




Storage Length



Storage Width


Definition of Ditch or Swale Storage Length and Width

Exhibit 630-9




Method to keep contributing area to ditch or swale within allowable limits if contributing area is too large based on Exhibit 630-3.

Silt Fences for Large Contributing Area
Exhibit 630-10




Silt Fence Plan



Silt Fence Profile

Silt fence plan and profile illustrating how silt fence will capture runoff water and not allow water to run around ends of fence.

Silt Fence End Treatment
Exhibit 630-11



Gravel Check Dams for Silt Fences
Exhibit 630-12

Chapter 700 Project Development Roles and Responsibilities for Projects With Structures

700.01 General
700.02 Procedures

700.01 General

This chapter presents the project development process used by the Washington State Department of Transportation (WSDOT) in the regions and the Headquarters (HQ) Bridge and Structures Office to determine the roles and responsibilities for projects with structures during the project development phase of a project. This chapter complements WSDOT's *Project Management Online Guide*:
http://www.wsdot.wa.gov/projects/projectmgmt/pmog.htm

For design procedures, see Division 7 chapters and the *Bridge Design Manual*.

The primary objective of this process is to provide a consistent means of selecting a bridge design team to perform the structural design work, whether it is by a consultant or the HQ Bridge and Structures Office.

If the local agency will be requesting any services from WSDOT, the local agency will contact WSDOT's Local Programs Engineer, who will help define the level of WSDOT's involvement in design and construction.


700.02 Procedures

The flow diagram (see Exhibit 700-1) begins at the left with the initial approval and funding of the project and ends at the right with the start of the project delivery process.


After a project is programmed, WSDOT is tasked with confirming the project scope and defining the structural team's level of involvement in design and construction. If a consultant is not used, the bridge design work will be performed by the HQ Bridge and Structures Office. If a consultant is used, the region and the HQ Bridge and Structures Office will determine the level of involvement and responsibility for the design.

Agreements defining the level of involvement and responsibility will be developed and executed between the region office responsible for project development and the HQ Bridge and Structures Office, and the appropriate project delivery process will be implemented.

More information on this process and the desired outcomes is available on the HQ Bridge and Structures Office's home page:
http://www.wsdot.wa.gov/bridge/structures



Determination of the Roles and Responsibilities for Projects With Structures: Project Development Phase
Exhibit 700-1



Determination of the Roles and Responsibilities for Projects With Structures: Project Development Phase
Exhibit 700-1 (continued)

Chapter 710 Site Data for Structures

710.01 General
710.02 Required Data for All Structures
710.03 Additional Data for Waterway Crossings (Bridges and Buried Structures)
710.04 Additional Data for Grade Separations
710.05 Additional Data for Widenings
710.06 Documentation
710.07 References

710.01 General

The Washington State Department of Transportation (WSDOT) Headquarters (HQ) Bridge and Structures Office provides preliminary site data reviews to determine the applicability of, and requirements surrounding, proprietary structural solutions, or the need for specific structural design strategies, as well as structural design services to the regions. This chapter describes the information required by the HQ Bridge and Structures Office to perform these functions.

710.02 Required Data for All Structures

Structure site data provides information about the type of crossing, topography, type of structure, and potential future construction. Submit structure site data to the HQ Bridge and Structures Office for all structures meeting the Chapter 720 definition of a bridge: essentially all structures of with an interior span equal to 20 feet or greater measured along the overcrossing alignment. This includes all buried structures such as precast concrete arch structures, reinforced concrete arch structures, precast reinforced concrete three-sided structures, precast reinforced concrete box culverts, and precast reinforced concrete split box culverts with an interior span of 20 feet or greater. Site data can also provide information on nonstandard retaining walls requiring project-specific design by the HQ Bridge and Structures Office.

Provide a cover memo that gives general information on the project, describes the attachments, and transmits the forms and data included in the submittal. Submit site data as a CAD file, supplemental drawings, and a report. (See Exhibit 710-1 for items to include in a structure site data submittal). Direct any questions relating to the preparation of structure site data to the HQ Bridge and Structures Office. The *Bridge Design Manual* shows examples of required WSDOT forms.

710.02(1) Scour

At any location where a structure can be in contact with water (such as culvert outfall, lake, river, or floodplain), there is a risk of scour. This risk is to be analyzed. Contact the HQ Geotechnical Office and the HQ Hydraulics Office to determine whether a scour analysis is required.

710.02(2) CAD Files and Supplemental Drawings

CAD files prepared for use as structure site data will be accepted in DGN (preferred) or DWG (acceptable) format.

Prepare plan, profile, and section drawings for all structures. Include copies of the CAD site data and supplemental drawings in the 11 x 17 plan sheet format with the submittal.

Use a complete and separate CAD file for each structure. Create the base map in 2D expanded level format only at 1:1 scale, with only one model per DGN or DWG file, and all base map levels in accordance with the *Electronic Engineering Data Standards* manual. Create a separate base map in 3D with the alignment and contour lines only—no contour text. Turn on all levels (existing and proposed) and merge all reference files, leaving the reference file list empty. Put the new and existing alignments in the same file.

The *Bridge Design Manual* contains examples of completed bridge preliminary plans. These plans show examples of the line styles and drawing format for site data in CAD.

Structure site data is used to prepare the layout plan, which is to be used in the contract plans. Include the following information in the CAD files or in the supplemental drawings.

710.02(2)(a) Plan

- Vertical and horizontal datum control (see Chapters 400 and 410).
- Contours of the existing ground surface (index and intermediate). Use intervals of 2 feet. Show contours beneath an existing or proposed structure and beneath the water surface of any waterway. Do not partially delete contour lines that cover index contour text.
- Alignment of the proposed highway and traffic channelization in the vicinity.
- Location by section, township, and range.
- Type, size, and location of all existing or proposed sewers, telephone and power lines, water lines, gas lines, traffic barriers, culverts, bridges, buildings, and walls.
- Location of right of way lines and easement lines.
- Distance and direction to nearest state highway intersections along the main alignment in each direction.
- Location of all roads, streets, and detours.
- Stage construction plan and alignment.
- Type, size, and location of all existing and proposed sign structures, light standards, and associated conduits and junction boxes. Provide proposed signing and lighting items when the information becomes available.
- Location of existing and proposed drainage.
- Horizontal curve data. Provide the Inroads report for each alignment. Include coordinates for all control points.

710.02(2)(b) Profile

- Profile view showing the grade line of the proposed or existing alignment and the existing ground line along the alignment line.
- Vertical curve data. Provide the Inroads report for each alignment along with the CAD detail.

- Superelevation transition diagram for each alignment as applicable.

710.02(2)(c) Section

- Channelization roadway sections on the structure and at structure approaches. Indicate the lane and shoulder widths, cross slopes and side slopes, ditch dimensions, and traffic barrier requirements.
- Stage construction roadway geometrics with the minimum lane and roadway widths specified.

710.02(3) Report

Submit DOT Form 235-002, Bridge Site Data-General. Supplement the CAD drawings with the following items:

- Vicinity maps
- Class of highway
- Design speed
- Special requirements for replacing or relocating utility facilities
- ADT and DHV counts
- Truck traffic percentage
- Requirements for road or street maintenance during construction

710.02(4) Video and Photographs

Submit a video of the site. Show all the general features of the site and details of existing structures. Scan the area slowly, spending extra time showing existing bridge pier details and end slopes. A "voice over" narrative on the video is necessary for orientation.

Color photographs of the structure site are desirable. Include detailed photographs of existing abutments, piers, end slopes, and other pertinent details for widenings, bridge replacements, or sites with existing structures.

710.03 Additional Data for Waterway Crossings (Bridges and Buried Structures)

Coordinate with the HQ Hydraulics Section and supplement the structure site data for all waterway crossings with the DOT Form 235-001, Bridge Site Data for Stream Crossings, and the following:

- Show riprap or other slope protection requirements at the structure site (type, plan limits, and cross section) as determined by the HQ Hydraulics Section.
- Show a profile of the waterway. The extent will be determined by the HQ Hydraulics Section.
- Show cross sections of the waterway including new streambed design, defining the bankfull width and the bank shelf widths and slopes. The extent will be determined by the HQ Hydraulics Section. The requirements for waterway profile and cross sections

may be less stringent if the HQ Hydraulics Section has sufficient documentation (FEMA reports, for example) to make a determination. Contact the HQ Hydraulics Section to verify the extent of the information needed. Coordinate any rechannelization of the waterway with the HQ Hydraulics Section.

- Many waterway crossings require a permit from the U.S. Coast Guard (see *Bridge Design Manual* Chapter 2.2.4 and the *Environmental Manual*). Generally, ocean tide-influenced waterways and waterways used for commercial navigation require a Coast Guard permit. These structures require the following additional information:
  - Names and addresses of the landowners adjacent to the bridge site.
  - Quantity of new embankment material within the floodway. This quantity denotes, in cubic yards, the material below and the material above normal high water.

For all waterway crossings, where the structure parallel to the centerline of roadway width is less than 20 feet, the Region's designer shall contact the Coast Guard for permit requirements. For all waterway crossings, where the structure parallel to the centerline of roadway width is 20 feet or greater, the Bridge and Structure's Coast Guard Liaison shall contact the Coast Guard for permit requirements.

The region is responsible for coordination with the HQ Bridge and Structures Office, U.S. Army Corps of Engineers, and U.S. Coast Guard for waterways that may qualify for a permit exemption. The HQ Bridge and Structures Office is responsible for coordination with the U.S. Coast Guard for waterways that require a permit.

710.04 Additional Data for Grade Separations

710.04(1) Highway-Railroad Separation

Supplement structure site data for structures involving railroads with the following:

710.04(1)(a) Plan

- Alignment of all existing and proposed railroad tracks.
- Center-to-center spacing of all tracks.
- Angle, station, and coordinates of all intersections between the highway alignment and each track.
- Location of railroad right of way lines.
- Horizontal curve data. Include coordinates for all circular and spiral curve control points.

710.04(1)(b) Profile

- For proposed railroad tracks: profile, vertical curve, and superelevation data for each track.
- For existing railroad tracks: elevations accurate to 0.1 foot taken at 10-foot intervals along the top of the highest rail of each track. Provide elevations to 50 feet beyond the extreme outside limits of the existing or proposed structure. Tabulate elevations in a format acceptable to the HQ Bridge and Structures Office.

710.04(2) Highway-Highway Separation

Supplement structure site data for structures involving other highways by the following:

710.04(2)(a) Plan

- Alignment of all existing and proposed highways, streets, and roads.
- Angle, station, and coordinates of all intersections between all crossing alignments.
- Horizontal curve data. Include coordinates for all curve control points.

710.04(2)(b) Profile

- For proposed highways: profile, vertical curve, and superelevation data for each.
- For existing highways: elevations accurate to 0.1 foot taken at 10-foot intervals along the centerline or crown line and each edge of shoulder, for each alignment, to define the existing roadway cross slopes. Provide elevations to 50 feet beyond the extreme outside limits of the existing or proposed structure. Tabulate elevations in a format acceptable to the HQ Bridge and Structures Office.

710.04(2)(c) Section

- Roadway sections of each undercrossing roadway indicating the lane and shoulder widths, cross slopes and side slopes, ditch dimensions, and traffic barrier requirements.
- Falsework or construction opening requirements. Specify minimum vertical clearances, lane widths, and lateral clearances.

710.05 Additional Data for Widenings

Bridge rehabilitations and modifications that require new substructure are defined as bridge widenings.

710.05(1) Bridge Widenings

Submit DOT Form 235-002A, Supplemental Bridge Site Data-Rehabilitation/ Modification. Supplement structure site data for structures involving bridge widenings by the following:

710.05(1)(a) Plan

- Stations for existing back of pavement seats, expansion joints, and pier centerlines based on field measurements along the survey line and each curb line.
- Locations of existing bridge drains. Indicate whether these drains are to remain in use or be plugged.

710.05(1)(b) Profile

- Elevations accurate to 0.1 foot taken at 10-foot intervals along the curb line of the side of the structure being widened. Pair these elevations with corresponding elevations (same station) taken along the crown line or an offset distance (10-foot minimum from the curb line). This information will be used to establish the cross slope of the existing bridge. Tabulate elevations in a format acceptable to the HQ Bridge and Structures Office.

Take these elevations at the level of the concrete roadway deck. For bridges with concrete overlay, elevations at the top of the overlay will be sufficient. For bridges with a nonstructural overlay, such as an asphalt concrete overlay, take elevations at the level of the concrete roadway deck. For skewed bridges, take elevations along the crown line or at an offset distance (10-foot minimum from the curb line) on the approach roadway for a sufficient distance to enable a cross slope to be established for the skewed corners of the bridge.

710.06 Documentation

Refer to Chapter 300 for design documentation requirements.

710.07 References

Bridge Design Manual, M 23-50, WSDOT

Electronic Engineering Data Standards, M 3028

Environmental Manual, M31-11

Hydraulics Manual, M 23-03

Exhibit 710-1 Structure Site Data Checklist

PLAN (in CAD file)

_____ Survey Lines and Station Ticks
_____ Survey Line Intersection Angles
_____ Survey Line Intersection Stations
_____ Survey Line Bearings
_____ Roadway and Median Widths
_____ Lane and Shoulder Widths
_____ Sidewalk Width
_____ Connection/Widening for Traffic Barrier
_____ Profile Grade and Pivot Point
_____ Roadway Superelevation Rate (if constant)
_____ Lane Taper and Channelization Data
_____ Traffic Arrows
_____ Mileage to Towns Along Main Line
_____ Existing Drainage Structures
_____ Existing Utilities: Type/Size/Location
_____ New Utilities: Type/Size/Location
_____ Light Standards, Junction Boxes, Conduits
_____ Bridge-Mounted Signs and Supports
_____ Contours
_____ Bottom of Ditches
_____ Test Holes (if available)
_____ Riprap Limits
_____ Stream Flow Arrow
_____ R/W Lines and/or Easement Lines
_____ Exist. Bridge No. (to be removed, widened)
_____ Section, Township, Range
_____ City or Town
_____ North Arrow
_____ SR Number
_____ Scale

TABLES (in tabular format in CAD file)

_____ Curb Line Elevations at Top of Existing Bridge Deck
_____ Undercrossing Roadway Existing Elevations
_____ Undercrossing Railroad Existing Elevations
_____ Curve Data

OTHER SITE DATA (may be in CAD file or on supplemental sheets or drawings)

_____ Superelevation Diagrams
_____ End Slope Rate
_____ Profile Grade Vertical Curves
_____ Coast Guard Permit Status
_____ Railroad Agreement Status
_____ Highway Classification
_____ Design Speed
_____ ADT, DHV, and % Trucks
_____ InRoads reports

FORMS (information noted on the form or attached on supplemental sheets or drawings)

Bridge Site Data General

_____ Slope Protection
_____ Pedestrian Barrier/Pedestrian Rail Height Requirements
_____ Construction/Falsework Openings
_____ Stage Construction Channelization Plans
_____ Bridge (before/with/after) Approach Fills
_____ Datum
_____ Video of Site
_____ Photographs of Site
_____ Control Section
_____ Project Number
_____ Region Number
_____ Highway Section

Bridge Site Data for Stream Crossings

_____ Water Surface Elevations and Flow Data
_____ Riprap Cross Section Detail
_____ Bankfull width
_____ Bank shelf width

Supplemental Bridge Site Data: Rehabilitation/ Modification

BRIDGE, CROSSROAD, AND APPROACH ROADWAY CROSS SECTIONS (may be in CAD file or on separate drawings)

_____ Bridge Roadway Width
_____ Lane and Shoulder Widths
_____ Profile Grade and Pivot Point
_____ Superelevation Rate
_____ Survey Line
_____ PB/Pedestrian Rail Dimensions
_____ Stage Construction Lane Orientations
_____ Locations of Temporary Barrier
_____ Conduits/Utilities in Bridge
_____ Location and Depth of Ditches
_____ Shoulder Widening for Barrier
_____ Side Slope Rate

Chapter 720 Bridges

720.01 General
720.02 Bridge Locations
720.03 Bridge Site Design Elements
720.04 Documentation
720.05 References

720.01 General

The National Bridge Inspection Standards (NBIS), published in the Code of Federal Regulations (23 CFR 650, Subpart C), defines a bridge as:

> *A structure including supports erected over a depression or an obstruction, such as water, highway, or railway, and having a track or passageway for carrying traffic or other moving loads, and having an opening measured along the center of the roadway of more than 20 feet between undercopings of abutments or spring lines of arches, or extreme ends of openings for multiple boxes; it may also include multiple pipes, where the clear distance between openings is less than half of the smaller contiguous opening.*

The term "bridge" as used in this chapter applies to all structures conforming to the above definition. This includes all buried structures of a span greater than 20 feet measured along the overcrossing alignment, such as precast reinforced concrete three-sided structures, precast reinforced concrete box culverts, and precast reinforced concrete split box culverts.

Bridge design is the responsibility of the Washington State Department of Transportation (WSDOT) Headquarters (HQ) Bridge and Structures Office, which develops a preliminary bridge plan for a new or modified structure in collaboration with the region. This chapter provides basic design considerations for the development of this plan. Unique staging requirements, constructability issues, and other considerations are addressed during plan development. Contact the HQ Bridge and Structures Office early in the planning stage regarding issues that might affect the planned project (see Chapter 700).

720.02 Bridge Locations

Bridge locations are chosen to conform to the alignment of the highway. Conditions that can simplify design efforts, minimize construction activities, and reduce structure costs are:

- A perpendicular crossing.
- The minimum required horizontal and vertical clearances.
- A constant bridge width (without tapered sections).
- A tangential approach alignment of sufficient length not to require superelevation on the bridge.
- A crest vertical curve profile that will facilitate drainage.
- An adequate construction staging area.

720.03 Bridge Site Design Elements

720.03(1) Structural Capacity

The structural capacity of a bridge is a measure of the structure's ability to carry vehicle loads. For new bridges, the bridge designer chooses the design load that determines the structural capacity. For existing bridges, the structural capacity is calculated to determine the "load rating" of the bridge. The load rating is used to determine whether or not a bridge is "posted" for legal weight vehicles or "restricted" for overweight permit vehicles.

720.03(1)(a) New Structures

All new structures that carry vehicular loads are designed to HL-93 notional live load in accordance with AASHTO's LRFD Bridge Design Specifications.

720.03(1)(b) Existing Structures

When the structural capacity of a bridge will be affected by the project, the Region requests a Structural Capacity Report from the Risk Reduction Engineer in the HQ Bridge and Structures Office. Permanent redistribution of traffic, introduction of median barrier, and widening or deck rehabilitation are among the triggers for evaluation of a bridge's structural capacity. The report will state:

- The structural capacity status of the structures within the project limits.
- What action, if any, is appropriate.

The Region requests the Bridge and Structures Asset Manager to provide status about whether a bridge is included in the 6-year or 20-year plans for replacement or rehabilitation under the P2 program and, if so, in which biennium the P2 project is likely to be funded.

The criteria used by the Bridge and Structures office to evaluate the structural capacity of a bridge are as follows:

1. On National Highway System (NHS) routes (including Interstate routes):
   - The operating load rating is at least 36 tons (which is equal to HS-20).
   - The bridge is not permanently posted for legal weight vehicles.
   - The bridge is not permanently restricted for vehicles requiring overweight permits.
2. On non-NHS routes:
   - The bridge is not permanently posted for legal weight vehicles.
   - The bridge is not permanently restricted for vehicles requiring overweight permits.

Include the Structural Capacity Report in the Project File (see Chapter 300).

720.03(2) Bridge Widths

The Design Manual contains multiple chapters that provide geometric cross section criteria and procedures relevant to determining design element widths. See Chapter 1230 for a guide to chapters that provide geometric cross section element widths.

While it is preferred not to alter the continuity of a roadway, there may be situations where providing a structure width more or less than the roadway approaching the structure is appropriate.

All structures on city or county routes crossing over a state highway must conform to the Local Agency Guidelines.

For structures involving railroads, contact the HQ Design Office Railroad Liaison.

720.03(3) Horizontal Clearance

Horizontal clearance for structures is the distance from the edge of the traveled way to bridge piers and abutments, traffic barrier ends, or bridge end embankment slopes. Minimum distances for this clearance vary depending on the type of structure. (See Chapters 1239, 1600, and 1610 and the *Bridge Design Manual* for guidance on horizontal clearance.)

For structures involving railroads, contact the HQ Design Office Railroad Liaison.

720.03(4) Bridge Medians

Designs for bridges on divided multilane highways often include the decision to join parallel bridges as one or build them as independent structures. There are several factors in this decision, such as in new corridor construction, phased construction of corridors, and the general median width of the divided highway. This section covers some common design considerations related to bridge medians.

Advances in crash barriers and their applications have resulted in an expanded set of choices for bridge medians on divided highways.

Modern barrier designs and applications have allowed for longer runs of traffic barrier, different barrier types, and bullnose guardrail designs for shielding the gap between parallel structures. These tools have reduced collisions with abrupt bridge ends as well as shielded the opening between bridges.

Some highway corridors are initially planned as multilane divided highways but may be developed in logical, affordable phases and individual projects. This could result in an initial phase where a corridor may open as a two-lane rural highway used by both travel directions. A later phase could convert the facility to a divided highway, bringing with it the need for median separation. Consider the long-range plans when determining median widths for bridges. The photos in Exhibit 720-1 show a completed multilane highway where two separate bridges were ultimately constructed years apart and a new corridor underway where one bridge is now built.

Joining two structures may not be the most cost-effective or sustainable solution for all projects. Coordinate with the Bridge and Structures Office and the local Maintenance Office when discussing options and concerns. For bridges on parallel horizontal and vertical alignments, practical considerations for joining two structures as one include, but are not limited to:

- Phased development where one structure exists and another is planned.

- Old and new structure types and compatibility (with phased corridor construction).
- Median width.
- Median barrier treatment options.
- Environmental contexts and regulations.
- Seismic conditions and load ratings.
- Bridge maintenance and inspection techniques: accessibility options and equipment for terrain in specific contexts. An open area between structures may be needed for bridge inspection.
- Skew angles and/or curvature of waterways or roadways beneath the structures.
- Economics.
- Historical/aesthetic value of existing bridges to remain in place.

If structures will not be joined, evaluate the median as described here:

When there is a median gap between bridges of 6 inches or more, the Region PEO will evaluate whether or not the median gap needs to be screened. Address the potential for pedestrians on the bridge and if closing the median gap to less than 6 inches, or installing fencing, netting, or other elements to enclose the area between the bridges would be beneficial. Document this evaluation in the Basis of Design and Alternatives Comparison Table.

Exhibit 720-1 Phased Development of Multilane Divided Highways





720.03(5) Vertical Clearance

Vertical clearance is the critical height under a structure that will accommodate vehicular and rail traffic based on its design characteristics. This height is the least height available from the lower roadway surface (including usable shoulders) or the plane of the top of the rails to the bottom of the bridge. Usable shoulders are the design shoulders for the roadway and do not include paved widened areas that may exist under the structure.

In addition to the following vertical clearance guidance, consider whether the corridor experiences overheight loads. Consider a vertical clearance such that it will not create a new "low point" in the corridor.

720.03(5)(a) Vertical Falsework Clearance for Bridges Over Highways

Construction of new bridges and the reconstruction or widening of existing structures often requires the erection of falsework across the traveled way of a highway. The erection of this falsework can reduce the vertical clearance for vehicles to pass under the work area. The potential for collisions to occur by hitting this lower construction stage falsework is increased.

1. On all routes that require a 16.5-foot vertical clearance, maintain this same clearance for falsework vertical clearance.
   - On structures that currently have less than a 16.5-foot vertical clearance for the falsework envelope, maintain existing clearance.
   - On new structures, maintain the falsework vertical clearance at least to those of the minimum vertical clearances referenced below.
2. Any variance from the above must be approved by the Regional Administrator or designee in writing and made a part of the Project File.

720.03(5)(b) Minimum Clearance for New Structures

For new structures, the minimum vertical clearances are as follows:

720.03(5)(b)(1) Bridge Over a Roadway

The minimum vertical clearance for a bridge over a roadway is 16.5 feet.


720.03(5)(b)(2) Bridge Over a Railroad Track

The minimum vertical clearance for a bridge over a railroad track is 23.5 feet (see Exhibit 720-2). A lesser clearance may be negotiated with the railroad company based on certain operational characteristics of the rail line; however, any clearance less than 22.5 feet requires the approval of the Washington State Utilities and Transportation Commission (WUTC) per WAC 480-60. Vertical clearance is provided for the width of the railroad clearance envelope. Coordinate railroad clearance issues with the HQ Design Office Railroad Liaison.

720.03(5)(b)(3) Pedestrian Bridge Over a Roadway

The minimum vertical clearance for a pedestrian bridge over a roadway is 17.5 feet.

Exhibit 720-2 Highway Structure Over Railroad



Notes:

- Use 22.5-foot vertical clearance for existing structures.
- Lesser vertical clearance may be negotiated (see 720.03(5)).
- Increase horizontal clearance when the track is curved.
- Coordinate railroad clearance issues with the HQ Design Office Railroad Liaison.

720.03(5)(c) Minimum Clearance for Existing Structures

The criteria used to evaluate the vertical clearance for existing structures depend on the work being done on or under that structure. When evaluating an existing structure on the Interstate System, see 720.03(5)(e), Coordination. This guidance applies to bridge clearances over state highways and under state highways at interchanges. For state highways over local roads and streets, city or county vertical clearance requirements may be used as minimum design criteria. (See Exhibit 720-3 for bridge vertical clearances.)

720.03(5)(c)(1) Bridge Over a Roadway

For a project that will widen an existing structure over a highway or where the highway will be widened under an existing structure, the vertical clearance can be as little as 16.0 feet on the Interstate System or other freeways or 15.5 feet on nonfreeway routes. An approved design analysis is required for clearance less than 16.0 feet on Interstate routes or other freeways and 15.5 feet on nonfreeway routes.

For a planned resurfacing of the highway under an existing bridge, if the clearance will be less than 16.0 feet on the Interstate System or other freeways and 15.5 feet on nonfreeway routes, evaluate the following options and include in a design analysis request:

- Pavement removal and replacement
- Roadway excavation and reconstruction to lower the roadway profile
- Providing a new bridge with the required vertical clearance

Reducing roadway paving and surfacing thickness under the bridge to achieve the minimum vertical clearance can cause accelerated deterioration of the highway and is not recommended. Elimination of the planned resurfacing in the immediate area of the bridge might be a short-term solution if recommended by the Region Materials Engineer (RME). Solutions that include milling the existing surface followed by overlay or inlay must be approved by the RME to ensure adequate pavement structure is provided.

For other projects that include an existing bridge where no widening is proposed on or under the bridge, and the project does not affect vertical clearance, the clearance can be as little as 14.5 feet. For these projects, document the clearance in the Design Documentation Package. For an existing bridge with less than a 14.5-foot vertical clearance, an approved design analysis request is required.

720.03(5)(c)(2) Bridge Over a Railroad Track

For an existing structure over a railroad track (see Exhibit 720-2), the vertical clearance can be as little as 22.5 feet. A lesser clearance can be used with the agreement of the railroad company and the approval of the Washington State Utilities and Transportation Commission. Coordinate railroad clearance issues with the HQ Design Office Railroad Liaison.

Exhibit 720-3 Bridge Vertical Clearances

Project Type	Vertical Clearance [8]	Documentation Requirement (see notes)
Interstate and Other Freeways [1]		
New Bridge	> 16.5 ft	[2]
Widening Over or Under Existing Bridge	> 16 ft	[2]
	< 16 ft	[4]
Resurfacing Under Existing Bridge	> 16 ft	[2]
	< 16 ft	[4]
Other With No Change to Vertical Clearance	> 14.5 ft	[3]
	< 14.5 ft	[4]
Nonfreeway Routes		
New Bridge	> 16.5 ft	[2]
Widening Over or Under Existing Bridge	> 15.5 ft	[2]
	< 15.5 ft	[4]
Resurfacing Under Existing Bridge	> 15.5 ft	[2]
	< 15.5 ft	[4]
Other With No Change to Vertical Clearance	> 14.5 ft	[3]
	< 14.5 ft	[4]
Bridge Over Railroad Tracks [7]		
New Bridge	> 23.5 ft < 23.5 ft	[2] [4][5]
Existing Bridge	> 22.5 ft < 22.5 ft	[2] [4][5]
Pedestrian Bridge Over Roadway		
New Bridge	> 17.5 ft	[2]
Existing Bridge	17.5 ft	[6]

Notes:

[1] Applies to all bridge vertical clearances over highways and under highways at interchanges.

[2] No documentation required.

[3] Document to Design Documentation Package.

[4] Approved design analysis required.

[5] Requires written agreement between railroad company and WSDOT and approval via petition from the WUTC.

[6] Maintain 17.5-ft clearance.

[7] Coordinate railroad clearance with the HQ Design Office Railroad Liaison.

[8] See 720.03(5).

720.03(5)(d) Signing

Low-clearance warning signs are necessary when the vertical clearance of an existing bridge is less than 15 feet 3 inches. Refer to the *Manual on Uniform Traffic Control Devices* and the *Traffic Manual* for other requirements for low-clearance signing.

720.03(5)(e) Coordination

The Interstate System is used by the Department of Defense (DOD) for the conveyance of military traffic. The Military Traffic Management Command Transportation Engineering Agency (MTMCTEA) represents the DOD in public highway matters. The MTMCTEA has an inventory of vertical clearance deficiencies over the Interstate System in Washington State. Contact the MTMCTEA, through the Federal Highway Administration (FHWA), if either of the following changes is proposed to these bridges:

- A project would create a new deficiency of less than a 16.0-foot vertical clearance over an Interstate highway.
- The vertical clearance over the Interstate is already deficient (less than 16.0 feet) and a change (increase or decrease) to vertical clearance is proposed.

Coordination with MTMCTEA is required for these changes on all rural Interstate highways and for one Interstate route through each urban area.

720.03(6) Liquefaction Impact Considerations

To determine the amount of settlement and the potential for the soil to flow laterally during the design level earthquake due to liquefaction, an analysis performed by the HQ Geotechnical Office is needed for each bridge project site location. The information collected is used by bridge engineers to determine the bridge's capability to withstand the movement and loading in a seismic event and to explore other foundation mitigation options not necessitating total bridge replacement.

The HQ Bridge and Structures Office, in collaboration with the HQ Geotechnical Office, evaluates bridge-widening projects involving liquefiable soils and recommends appropriate liquefaction mitigation.

See the *Bridge Design Manual LRFD* for further information.

720.03(7) Pedestrian and Bicycle Facilities

When pedestrians or bicyclists are anticipated on bridges, provide facilities consistent with guidance in Chapters 1510, 1515, and 1520.

Evolving programs and technologies such as incident response, personal cell phones, and ITS cameras have further reduced the probability of motorists becoming pedestrians. Investigate other methods of treatment such as pedestrian scale signing or other low-cost safety improvement measures. Document decisions in the Basis of Design.

720.03(8) Bridge Approach Slab

Bridge approach slabs are reinforced concrete pavement installed across the full width of the bridge ends. They provide a stable transition from normal roadway cross section to the bridge ends, and they compensate for differential expansion and contraction of the bridge and the roadway.

Bridge approach slabs are provided on all new bridges. If an existing bridge is being widened and it has an approach slab, slabs are required on the widenings. The region, with the concurrence of the State Geotechnical Engineer and the State Bridge Design Engineer, may decide to omit bridge approach slabs. Document decisions in the DDP.

720.03(9) Traffic Barrier End Treatment

Plans for new bridge construction and bridge traffic barrier modifications include provisions for the connection of bridge traffic barriers to the longitudinal barrier approaching and departing the bridge. Indicate the preferred longitudinal barrier type and connection during the review of the bridge preliminary plan.

720.03(10) Bridge End Embankments

The design of embankment slopes at bridge ends depends on several factors. The width of the embankment is determined not only by the width of the roadway, but also by the presence of traffic barriers, curbs, and sidewalks, all of which create the need for additional widening. Examples of the additional widening required for these conditions are shown in the Standard Plans.

The end slope is determined by combining the recommendations of several technical experts within WSDOT. Exhibit 720-4 illustrates the factors taken into consideration and the experts involved in the process.

720.03(11) Bridge Slope Protection

Slope protection provides a protective and aesthetic surface for exposed slopes under bridges. Slope protection is normally provided under:

- Structures over state highways.
- Structures within an interchange.
- Structures over other public roads unless requested otherwise by the public agency.
- Railroad overcrossings if requested by the railroad.


Slope protection is usually not provided under pedestrian structures.

The type of slope protection is selected at the bridge preliminary plan stage. Typical slope protection types are concrete slope protection, and rubble stone.

720.03(12) Slope Protection at Water Crossings

The HQ Hydraulics Section determines the slope protection requirements for structures that cross waterways. The type, limits, and quantity of slope protection are shown on the bridge preliminary plan.

Exhibit 720-4 Embankment Slope at Bridge Ends



Bridge End Elevation

Applies to retaining wall or wing wall (or combination) extending beyond bridge superstructure (barrier omitted for clarity)

Legend

A = Superstructure depth: recommended by HQ Bridge and Structures Office

B = Vertical clearance from bottom of superstructure to embankment: recommended by Bridge Preservation Engineer

C = Distance from end of retaining wall or wing wall to back of pavement seat: recommended by HQ Bridge and Structures Office

H & V = Embankment slope: recommended by Geotechnical Engineer

720.03(13) Screening for Highway Structures

The Washington State Patrol (WSP) classifies the throwing of an object from a highway structure as an assault, not an accident or collision. Therefore, records of these assaults are not contained in WSDOT's crash databases. Contact the Region Traffic Engineer, RME's office and the WSP for the history of reported incidents.

Screening might reduce the number of incidents, but will not stop a determined individual at that location, or deter them from moving to other locations in the area. Enforcement provides the most effective deterrent and is typically the first approach used.

Installation of screening is analyzed on a case-by-case basis at the following locations:

- On existing structures where there is a history of multiple incidents of objects being dropped or thrown and where enforcement has not changed the situation.
- On new structures near schools, playgrounds, or areas frequently used by children not accompanied by adults.
- In urban areas on new structures used by pedestrians where surveillance by local law enforcement personnel is not likely.
- On new structures with walkways where experience on similar structures within a 1 mile radius indicates a need.
- On private property structures, such as buildings or power stations, subject to damage.

In most cases, the installation of a screen on a new structure can be postponed until there are indications of need.

Submit all proposals to install screening on structures to the Director & State Design Engineer, Development Division, for approval. Contact the HQ Bridge and Structures Office for approval to attach screening to structures and for specific design and mounting details.

720.04 Documentation

Refer to Chapter 300 for design documentation requirements.

720.05 References

720.05(1) Federal/State Laws and Codes

23 CFR Part 650, Subpart C – National Bridge Inspection Standards

Washington Administrative Code (WAC) 480-60, Railroad companies – Clearances

720.05(2) Design Guidance

Bridge Design Manual LRFD, M 23-50, WSDOT

Geotechnical Design Manual, M 46-03, WSDOT

Local Agency Guidelines (LAG), M 36-63, WSDOT

LRFD Bridge Design Specifications, AASHTO, Current Edition

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-10, WSDOT

Standard Specifications for Road, Bridge, and Municipal Construction (Standard Specifications), M 41-10, WSDOT

Traffic Manual, M 51-02, WSDOT

720.05(3) Supporting Information

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO, current edition

Manual for Railway Engineering, American Railway Engineering and Maintenance-of-Way Association (AREMA)

Chapter 730 Retaining Walls and Steep Reinforced Slopes

730.01 General
730.02 References
730.03 Design Principles
730.04 Design Requirements
730.05 Guidelines for Wall/Slope Selection
730.06 Design Responsibility and Process
730.07 Documentation

730.01 General

The function of a retaining wall is to form a nearly vertical face through confinement and/or strengthening of a mass of earth or other bulk material. Likewise, the function of a reinforced slope is to strengthen the mass of earth or other bulk material such that a steep (up to 1H:2V) slope can be formed. In both cases, the purpose of constructing such structures is to make maximum use of limited right of way. The difference between the two is that a wall uses a structural facing, whereas a steep reinforced slope does not require a structural facing. Reinforced slopes typically use a permanent erosion control matting with low vegetation as a slope cover to prevent erosion. (See the *Roadside Manual* for more information.)

To lay out and design a retaining wall or reinforced slope, consider the following items:

- Functional classification
- Highway geometry
- Design Clear Zone requirements (see Chapter 1600)
- Amount of excavation required
- Traffic characteristics
- Constructibility
- Impact to adjacent environmentally sensitive areas
- Impact to adjacent structures
- Potential added lanes
- Length and height of wall
- Material to be retained
- Foundation support and potential for differential settlement
- Groundwater
- Earthquake loads
- Right of way costs
- Need for construction easements
- Risk
- Overall cost
- Visual appearance

If the wall or toe of a reinforced slope is to be located adjacent to the right of way line, consider the space needed in front of the wall/slope to construct it.

(1) Retaining Wall Classifications

Retaining walls are generally classified as gravity, semigravity, nongravity cantilever, or anchored. The various wall types and their classifications are summarized in Exhibits 730-1 through 730-6.

(a) Gravity Walls

Gravity walls derive their capacity to resist lateral soil loads through a combination of dead weight and sliding resistance. Gravity walls can be further subdivided into rigid gravity walls, prefabricated modular gravity walls, and mechanically stabilized earth (MSE) gravity walls.

Rigid gravity walls consist of a solid mass of concrete or mortared rubble, and they use the weight of the wall itself to resist lateral loads.

Prefabricated modular gravity walls consist of interlocking soil or rock-filled concrete, steel, or wire modules or bins (such as gabions). The combined weight resists the lateral loads from the soil.

MSE gravity walls use strips, bars, or mats of steel or polymeric reinforcement to reinforce the soil and create a reinforced soil block behind the face. The reinforced soil block then acts as a unit and resists the lateral soil loads through the dead weight of the reinforced mass. MSE walls may be constructed as fill walls, with fill and reinforcement placed in alternate layers to create a reinforced mass, or reinforcement may be drilled into an existing soil/rock mass using grouted anchor technology to create a reinforced soil mass (soil nail walls).

(b) Semigravity Walls

Semigravity walls rely more on structural resistance through cantilevering action of the wall stem. Generally, the backfill for a semigravity wall rests on part of the wall footing. The backfill, in combination with the weight of the wall and footing, provides the dead weight for resistance. An example of a semigravity wall is the reinforced concrete wall provided in the *Standard Plans*.

(c) Nongravity Cantilever Walls

Nongravity cantilever walls rely strictly on the structural resistance of the wall in which vertical elements of the wall are partially embedded in the soil or rock to provide fixity. These vertical elements may consist of piles (such as soldier piles or sheet piles), caissons, or drilled shafts. The vertical elements may form the entire wall face or they may be spanned structurally using timber lagging or other materials to form the wall face.

(d) Anchored Walls

Anchored walls derive their lateral capacity through anchors embedded in stable soil or rock below or behind all potential soil/rock failure surfaces. Anchored walls are similar to nongravity cantilevered walls except that anchors embedded in the soil/rock are attached to the wall facing structure to provide lateral resistance. Anchors typically consist of deadman or grouted soil/rock anchors.

Reinforced slopes are similar to MSE walls in that they also use fill and reinforcement placed in alternate layers to create a reinforced soil mass. However, the face is typically built at a 1.2H:1V to 1H:2V slope.

Rockeries (rock walls) behave to some extent like gravity walls. However, the primary function of a rockery is to prevent erosion of an oversteepened but technically stable slope. Rockeries consist of large, well-fitted rocks stacked on top of one another to form a wall.

An example of a rockery and reinforced slope is provided in Exhibit 730-10.

730.02 References

(1) Federal/State Laws and Codes

Washington Administrative Code (WAC) 296-155, Safety standards for construction work

(2) Design Guidance

Bridge Design Manual, M 23-50, WSDOT

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT

Plans Preparation Manual, M 22-31, WSDOT

Roadside Manual, M 25-30, WSDOT

730.03 Design Principles

The design of a retaining wall or reinforced slope consists of the following principal activities:

- Develop wall/slope geometry
- Provide adequate subsurface investigation
- Evaluate loads and pressures that will act on the structure
- Design the structure to withstand the loads and pressures
- Design the structure to meet aesthetic requirements
- Ensure wall/slope constructibility
- Coordinate with other design elements

The structure and adjacent soil mass also needs to be stable as a system, and the anticipated wall settlement needs to be within acceptable limits.

730.04 Design Requirements

(1) Wall/Slope Geometry

Wall/slope geometry is developed considering the following:

- Geometry of the transportation facility itself
- Design Clear Zone requirements (see Chapter 1600)
- Flare rate and approach slope when inside the Design Clear Zone (see Chapter 1610)
- Right of way constraints
- Existing ground contours
- Existing and future utility locations
- Impact to adjacent structures
- Impact to environmentally sensitive areas

For wall/slope geometry, also consider the foundation embedment and type anticipated, which requires coordination between the various design groups involved.

Retaining walls are designed to limit the potential for snagging vehicles by removing protruding objects (such as bridge columns, light fixtures, or sign supports).

Provide a traffic barrier shape at the base of a new retaining wall constructed 12 feet or less from the edge of the nearest traffic lane. The traffic barrier shape is optional at the base of the new portion when an existing vertical-faced wall is being extended (or the existing wall may be retrofitted for continuity). Depending on the application, precast or cast-in-place Single Slope Concrete Barrier with vertical back or Type 4 Concrete Barrier may be used for both new and existing walls except when the barrier face can be cast as an integral part of a new wall. Design analyses may be considered, but they require approval as prescribed in Chapter 300. A design analysis is not required where sidewalk exists in front of the wall or in other situations where the wall face is otherwise inaccessible to traffic.

(2) Investigation of Soils

All retaining wall and reinforced slope structures require an investigation of the underlying soil/rock that supports the structure. Chapter 610 provides guidance on how to complete this investigation. A soil investigation is an integral part of the design of any retaining wall or reinforced slope. The stability of the underlying soils, their potential to settle under the imposed loads, the usability of any existing excavated soils for wall/reinforced slope backfill, and the location of the groundwater table are determined through the geotechnical investigation.

(3) Geotechnical and Structural Design

The structural elements of the wall or slope and the soil below, behind, and/or within the structure are designed together as a system. The wall/slope system is designed for overall external stability as well as internal stability. Overall external stability includes stability of the slope the wall/reinforced slope is a part of and the local external stability (overturning, sliding, and bearing capacity). Internal stability includes resistance of the structural members to load and, in the case of MSE walls and reinforced slopes, pullout capacity of the structural members or soil reinforcement from the soil.

(a) **Scour**

At any location where a retaining wall or reinforced slope can be in contact with water (such as a culvert outfall, ditch, wetland, lake, river, or floodplain), there is a risk of scour at the toe. This risk must be analyzed. Contact the HQ Geotechnical Office and HQ Hydraulics Office to determine whether a scour analysis is required.

(4) Drainage Design

One of the principal causes of retaining wall/slope failure is the additional hydrostatic load imposed by an increase in the water content in the material behind the wall or slope. This condition results in a substantial increase in the lateral loads behind the wall/slope since the material undergoes a possible increase in unit weight, water pressure is exerted on the back of the wall, and the soil shear strength undergoes a possible reduction. To alleviate this, adequate drainage for the retaining wall/slope

needs to be considered in the design stage and reviewed by the region Materials Engineer during construction. The drainage features shown in the *Standard Plans* are the minimum basic requirements. Underdrains behind the wall/slope need to daylight at some point in order to adequately perform their drainage function. Provide positive drainage at periodic intervals to prevent entrapment of water.

Native soil may be used for retaining wall and reinforced slope backfill if it meets the requirements for the particular wall/slope system. In general, use backfill that is free-draining and granular in nature. Exceptions to this can be made depending on the site conditions as determined by the Geotechnical Office of the Headquarters (HQ) Materials Laboratory.

A typical drainage detail for a gravity wall (in particular, an MSE wall) is shown in Exhibit 730-11. Include drainage details with a wall unless otherwise recommended to be deleted by the Region Materials Engineer or HQ Geotechnical Office.

(5) Aesthetics

Retaining walls and slopes can have a pleasing appearance that is compatible with the surrounding terrain and other structures in the vicinity. To the extent possible within functional requirements and cost-effectiveness criteria, this aesthetic goal is to be met for all visible retaining walls and reinforced slopes.

Aesthetic requirements include consideration of the wall face material, top profile, terminals, and surface finish (texture, color, and pattern). Where appropriate, provide planting areas and irrigation conduits. These will visually soften walls and blend them with adjacent areas. Avoid short sections of retaining wall or steep slope where possible.

In higher walls, variations in slope treatment are recommended for a pleasing appearance. High continuous walls are generally not desirable from an aesthetic standpoint, because they can be quite imposing. Consider stepping high or long retaining walls in areas of high visibility. Plantings may be considered between wall steps.

Approval by the State Bridge and Structures Architect is required on all retaining wall aesthetics, including finishes, materials, and configuration (see Chapter 950).

(6) Constructability

Consider the potential effect that site constraints might have on the constructability of the specific wall/slope. Constraints to be considered include but are not limited to site geometry, access, time required to construct the wall, environmental issues, and impact on traffic flow and other construction activities.

(7) Coordination With Other Design Elements

(a) Other Design Elements

Retaining wall and slope designs are to be coordinated with other elements of the project that might interfere with or impact the design or construction of the wall/slope. Also consider drainage features; utilities; luminaire or sign structures; adjacent retaining walls or bridges; concrete traffic barriers; and beam guardrails. Locate these design elements in a manner that will minimize the impacts to the wall elements. In general, locate obstructions within the wall backfill (such as

guardrail posts, drainage features, and minor structure foundations) a minimum of 3 feet from the back of the wall facing units.

Greater offset distances may be required depending on the size and nature of the interfering design element. If possible, locate these elements to miss reinforcement layers or other portions of the wall system. Conceptual details for accommodating concrete traffic barriers and beam guardrails are provided in Exhibit 730-12.

Where impact to the wall elements is unavoidable, the wall system needs to be designed to accommodate these impacts. For example, it may be necessary to place drainage structures or guardrail posts in the reinforced backfill zone of MSE walls. This may require that holes be cut in the upper soil reinforcement layers or that discrete reinforcement strips be splayed around the obstruction. This causes additional load to be carried in the adjacent reinforcement layers due to the missing soil reinforcement or the distortion in the reinforcement layers.

The need for these other design elements and their impacts on the proposed wall systems are to be clearly indicated in the submitted wall site data so the walls can be properly designed. Contact the HQ Bridge and Structures Office (or the Geotechnical Office for geosynthetic walls/slopes and soil nail walls) for assistance regarding this issue.

(b) **Worker Fall Protection**

Department of Labor and Industries regulations require that, when employees are exposed to the possibility of falling from a location 4 feet or more above the roadway (or other lower area), the employer is to ensure fall restraint or fall arrest systems are provided, installed, and implemented.

Design fall protection in accordance with WAC 296-155-24609 for walls that create a potential for a fall of 4 feet or more. During construction or other temporary or emergency condition, fall protection will follow WAC 296-155. Any need for maintenance of the wall's surface or the area at the top can expose employees to a possible fall. If the area at the top will be open to the public, see Chapter 1510, Pedestrian Facilities.

For maintenance of a tall wall's surface (10 feet or more), consider harness tie-offs if other protective means are not provided.

For maintenance of the area at the top of a tall wall, a fall restraint system is required when all of the following conditions will exist:

- A possible fall will be of 4 feet or more.
- Periodic maintenance will be performed on the area at the top.
- The area at the top is not open to the public.

Recommended fall restraint systems are:

- Wire rope railing with top and intermediate rails of ½-inch-diameter steel wire rope.
- Steel pipe railing with 1½-inch nominal outside diameter pipe as posts and top and intermediate rails.
- Concrete as an extension of the height of the retaining wall.

A fall restraint system is to be 42 inches high, plus or minus 3 inches, measured from the top of the finished grade, and capable of withstanding a 200 lb force from any direction, at the top, with minimal deflection. An intermediate cable or rail shall be halfway between the top rail and the platform. A toe board with a minimum height of 4 inches will be provided. Post spacing is no more than 8 feet on centers. (See the *Construction Manual* and WAC 296-155 for fall arrest and protection information.) For wire rope railing, the top railing shall be flagged at not more than 6-foot intervals with high-visibility material.

The designer is to contact maintenance personnel regarding fall protection and debris removal considerations.

Contact the HQ Bridge and Structures Office for design details for any retrofit to an existing retaining wall and for any attachments to a new retaining wall.

730.05 Guidelines for Wall/Slope Selection

Wall/slope selection is dependent on:

- Whether the wall/slope will be located primarily in a cut or fill (how much excavation/shoring will be required to construct the wall or slope).
- If located in a cut, the type of soil/rock present.
- The need for space between the right of way line and the wall/slope or easement.
- The amount of settlement expected.
- The potential for deep failure surfaces to be present.
- The structural capacity of the wall/slope in terms of maximum allowable height.
- The nature of the wall/slope application.
- Whether or not structures or utilities will be located on or above the wall.
- Architectural requirements.
- Overall economy.

(1) Cut and Fill Considerations

Due to the construction technique and base width required, some wall types are best suited for cut situations, whereas others are best suited for fill situations. For example, anchored walls and soil nail walls have soil reinforcements drilled into the in-situ soil/rock and are therefore generally used in cut situations. Nongravity cantilevered walls are drilled or cut into the in-situ soil/rock, have narrow base widths, and are also well suited to cut situations. Both types of walls are constructed from the top down. Such walls are also used as temporary shoring to allow other types of walls or other structures to be constructed where considerable excavation will otherwise be required.

MSE walls and reinforced slopes, however, are constructed by placing soil reinforcement between layers of fill from the bottom up and are therefore best suited to fill situations. Furthermore, the base width of MSE walls is typically on the order of 70% of the wall height, which requires considerable excavation in a cut situation. Therefore, in a cut situation, base width requirements usually make MSE structures uneconomical and possibly unconstructible.

Semigravity (cantilever) walls, rigid gravity walls, and prefabricated modular gravity walls are free-standing structural systems built from the bottom up, but they do not rely on soil reinforcement techniques (placement of fill layers with soil reinforcement) to provide stability.

These types of walls generally have a narrower base width than MSE structures (on the order of 50% of the wall height). Both of these factors make these types of walls feasible in fill situations as well as many cut situations.

Reinforced slopes generally require more room overall to construct than a wall because of the sloping face, but they typically are a feasible alternative to a combination wall and fill slope to add a new lane. Reinforced slopes can also be adapted to the existing ground contours to minimize excavation requirements where fill is placed on an existing slope. Reinforced slopes might also be a feasible choice to repair slopes damaged by landslide activity or deep erosion.

Rockeries are best suited to cut situations as they require only a narrow base width, on the order of 30% of the rockery height. Rockeries can be used in fill situations, but the fill heights they support need to be kept relatively low. It is difficult to get the cohesive strength needed in granular fill soils to provide minimal stability of the soil behind the rockery at the steep slope typically used for rockeries in a cut (such as 1H:6V or 1H:4V).

The key considerations in deciding which walls or slopes are feasible are the amount of excavation or shoring required and the overall height. The site geometric constraints are defined to determine these elements. Another consideration is whether or not an easement will be required. For example, a temporary easement might be required for a wall in a fill situation to allow the contractor to work in front of the wall. For walls in cut situations, especially anchored walls and soil nail walls, a permanent easement may be required for the anchors or nails.

(2) Settlement and Deep Foundation Support Considerations

Settlement issues, especially differential settlement, are of primary concern in the selection of walls. Some wall types are inherently flexible and can tolerate a great deal of settlement without suffering structurally. Other wall types are inherently rigid and cannot tolerate much settlement. In general, MSE walls have the greatest flexibility and tolerance to settlement, followed by prefabricated modular gravity walls. Reinforced slopes are also inherently very flexible. For MSE walls, the facing type used can affect the ability of the wall to tolerate settlement. Welded wire and geosynthetic wall facings are the most flexible and the most tolerant to settlement, whereas concrete facings are less tolerant to settlement. In some cases, after the wall settlement is complete, concrete facing can be placed such that the concrete facing does not limit the wall's tolerance to settlement. Facing may also be added for aesthetic reasons.

Semigravity (cantilever) walls and rigid gravity walls have the least tolerance to settlement. In general, total settlement for these types of walls needs to be limited to approximately 1 inch or less. Rockeries also cannot tolerate much settlement, as rocks can shift and fall out. Therefore, semigravity cantilever walls, rigid gravity walls, and rockeries are not used in settlement prone areas.

If very weak soils are present that will not support the wall and are too deep to be overexcavated, or if a deep failure surface is present that results in inadequate slope stability, select a wall type capable of using deep foundation support and/or anchors. In general, MSE walls, prefabricated modular gravity walls, and some rigid gravity walls are not appropriate for these situations. Walls that can be pile-supported, such as concrete semigravity cantilever walls, nongravity cantilever walls, and anchored walls, are more appropriate for these situations.

(3) Feasible Wall Heights and Limitations

Feasible wall heights are affected by issues such as the capacity of the wall structural elements, past experience with a particular wall, current practice, seismic risk, long-term durability, and aesthetics.

For height limitations, see Exhibits 730-1 through 730-6.

(4) Supporting Structures or Utilities

Not all walls are acceptable to support other structures or utilities. Issues that are to be considered include the potential for the wall to deform due to the structure foundation load, interference between the structure foundation and the wall components, and the potential long-term durability of the wall system. Using retaining walls to support other structures is considered to be a critical application, requiring a special design. In general, soil nail walls, semigravity cantilever walls, nongravity cantilever walls, and anchored walls are appropriate for use in supporting bridge and building structure foundations. In addition to these walls, MSE and prefabricated modular gravity walls may be used to support other retaining walls, noise walls, and minor structure foundations such as those for sign bridges and signals. On a project-specific basis, MSE walls can be used to support bridge and building foundations as approved by the HQ Bridge and Structures Office.

Consider the location of any utilities behind the wall or reinforced slope when making wall/slope selections. This is mainly an issue for walls that use some type of soil reinforcement and for reinforced slopes. It is best not to place utilities within a reinforced soil backfill zone because it will be impossible to access the utility from the ground surface without cutting through the soil reinforcement layers, thereby compromising the integrity of the wall.

Sometimes utilities, culverts, pipe arches, and so on must penetrate the face of a wall. Not all walls and facings are compatible with such penetrations. Consider how the facing can be formed around the penetration so that backfill soil cannot pipe or erode through the face. Contact the HQ Bridge and Structures Office for assistance regarding this issue.

(5) Facing Options

Facing selection depends on the aesthetic and structural needs of the wall system. Wall settlement may also affect the feasibility of the facing options. More than one wall facing may be available for a given system. Consider the available facing options when selecting a particular wall.

(a) MSE Walls

For MSE walls, facing options typically include:

- Precast modular panels.
- In some cases, full height precast concrete panels. Full height panels are generally limited to walls with a maximum height of 20 feet placed in areas where minimal settlement is expected.
- Welded wire facing.
- Timber facing.
- Shotcrete facing with treatment options that vary from a simple broom finish to a textured and colored finish.

- Segmental masonry concrete blocks.
- Cast-in-place concrete facing with various texturing options.

Plantings on welded wire facings can be attempted in certain cases. The difficulty is in providing a soil at the wall face that is suitable for growing plants and meets engineering requirements in terms of soil compressibility, strength, and drainage. If plantings in the wall face are attempted, use only small plants, vines, and grasses. Small bushes may be considered for plantings between wall steps. Larger bushes or trees are not considered in these cases due to the loads they can create on the wall face.

Geosynthetic facings are not acceptable for permanent facings due to potential facing degradation when exposed to sunlight. For permanent applications, use some type of timber, welded wire, or concrete face for geosynthetic walls. Shotcrete, masonry concrete blocks, cast-in-place concrete, welded wire, or timber are typically used for geosynthetic wall facings.

(b) **Soil Nail Walls**

Soil nail walls can use either architecturally treated shotcrete or a cast-in-place facia wall textured as needed to produce the desired appearance.

(c) **Prefabricated Modular Gravity Walls**

For prefabricated modular gravity walls, the facing generally consists of the structural bin or crib elements used to construct the walls. For some walls, the elements can be rearranged to form areas for plantings. In some cases, textured structural elements might also be feasible. This is also true of rigid gravity walls, though planting areas on the face of rigid gravity walls are generally not feasible. The concrete facing for semigravity cantilever walls can be textured as needed to produce the desired appearance.

(d) **Nongravity Cantilevered Walls**

For nongravity cantilevered walls and anchored walls, a textured cast-in-place or precast facia wall is usually installed to produce the desired appearance.

(6) Cost Considerations

Usually, more than one wall type is feasible for a given situation. Consider initial and future maintenance costs throughout the selection process, as the decisions made may affect the overall cost. For example, you may have to decide whether to shut down a lane of traffic to install a low-cost gravity wall system that requires more excavation room or use a more expensive anchored wall system that will minimize excavation requirements and impacts to traffic. In this case, determine whether the cost of traffic impacts and more excavation justifies the cost of the more expensive anchored wall system. Consider long-term maintenance costs when determining wall type.

Decisions regarding aesthetics can also affect the overall cost of the wall system. In general, the least expensive aesthetic options use the structural members of the wall as facing (welded wire or concrete or steel cribbing or bins), whereas the most expensive aesthetic options use textured cast-in-place concrete facias. In general, concrete facings increase in cost in the following order: shotcrete, segmental masonry concrete blocks, precast concrete facing panels, full height precast concrete facing panels, and cast-in-place concrete facing panels. Special architectural treatments

usually increase the cost of any of these facing systems. Special wall terracing to provide locations for plants will also tend to increase costs. Therefore, weigh the costs against the value of the desired aesthetics.

Other factors that affect the costs of wall/slope systems include wall/slope size and length; access at the site and distance to the material supplier location; overall size of the project; and competition between wall suppliers. In general, costs tend to be higher for walls or slopes that are high, but short in length, due to lack of room for equipment to work. Sites that are remote or have difficult local access increase wall/slope costs. Small wall/slope quantities result in high unit costs. Lack of competition between materials or wall system suppliers can result in higher costs as well.

Some of the factors that increase costs are required parts of a project and are therefore unavoidable. Always consider such factors when estimating costs because a requirement may not affect all wall types in the same way. Current cost information can be obtained by consulting the *Bridge Design Manual* or by contacting the HQ Bridge and Structures Office.

(7) Summary

For wall/slope selection, consider factors such as the intended application; the soil/rock conditions in terms of settlement, need for deep foundations, constructibility, and impacts to traffic; and the overall geometry in terms of wall/slope height and length, location of adjacent structures and utilities, aesthetics, and cost. Exhibits 730-1 through 730-6 provide a summary of many of the various wall/slope options available, including their advantages, disadvantages, and limitations. Note that specific wall types in the exhibits may represent multiple wall systems, some or all of which will be proprietary.

730.06 Design Responsibility and Process

(1) General

The retaining walls available for a given project include standard walls, nonstandard walls, and reinforced slopes.

Standard walls are those walls for which standard designs are provided in the Washington State Department of Transportation (WSDOT) *Standard Plans*. These designs are provided for reinforced concrete cantilever walls up to 35 feet in height. The internal stability design and the external stability design for overturning and sliding stability have already been completed for these standard walls. Determine overall slope stability and allowable soil bearing capacity (including settlement considerations) for each standard-design wall location.

Nonstandard walls may be either proprietary (patented or trademarked) or nonproprietary. Proprietary walls are designed by a wall manufacturer for internal and external stability, except bearing capacity, settlement, and overall slope stability, which are determined by WSDOT. Nonstandard nonproprietary walls are fully designed by WSDOT.

The geosynthetic soil reinforcement used in nonstandard nonproprietary geosynthetic walls is considered to be proprietary. It is likely that more than one manufacturer can supply proprietary materials for a nonstandard nonproprietary geosynthetic wall.

Reinforced slopes are similar to nonstandard nonproprietary walls in terms of their design process.

(a) **Preapproved Proprietary Walls**

Some proprietary wall systems are preapproved. Preapproved proprietary wall systems have been extensively reviewed by the HQ Bridge and Structures Office and the Geotechnical Office. Design procedures and wall details for preapproved walls have already been agreed upon between WSDOT and the proprietary wall manufacturers, allowing the manufacturers to competitively bid a particular project without having a detailed wall design provided in the contract plans.

Note that proprietary wall manufacturers might produce several retaining wall options, and not all options from a given manufacturer have necessarily been preapproved. For example, proprietary wall manufacturers often offer more than one facing alternative. It is possible that some facing alternatives are preapproved, whereas others are not preapproved. WSDOT does not preapprove the manufacturer, but specific wall systems by a given manufacturer can be preapproved.

It is imperative with preapproved systems that the design requirements for all preapproved wall alternatives for a given project be clearly stated so that the wall manufacturer can adapt the preapproved system to specific project conditions. For a given project, coordination of the design of all wall alternatives with all project elements that impact the wall is critical to avoid costly change orders or delays during construction. These elements include drainage features, utilities, luminaires and sign structures, noise walls, traffic barriers, guardrails, or other walls or bridges.

In general, standard walls are the easiest walls to incorporate into project Plans, Specifications, and Estimates (PS&E), but they may not be the most cost-effective option. Preapproved proprietary walls provide more options in terms of cost-effectiveness and aesthetics and are also relatively easy to incorporate into a PS&E. Nonstandard state-designed walls and nonpreapproved proprietary walls generally take more time and effort to incorporate into a PS&E because a complete wall design needs to be developed. Some nonstandard walls (such as state-designed geosynthetic walls) can be designed relatively quickly, require minimal plan preparation effort, and only involve the region and the Geotechnical Office. Other nonstandard walls such as soil nail and anchored wall systems require complex designs, involve both the HQ Bridge and Structures Office and Geotechnical Office, and require a significant number of plan sheets and considerable design effort.

The HQ Bridge and Structures Office maintains a list of the proprietary retaining walls that are preapproved. The region consults the HQ Bridge and Structures Office for the latest list. The region consults the HQ Geotechnical Office for the latest geosynthetic reinforcement list to determine which geosynthetic products are acceptable if a critical geosynthetic wall or reinforced slope application is anticipated.

(b) **Experimental Wall Systems**

Some proprietary retaining wall systems are classified as experimental by the Federal Highway Administration (FHWA). The HQ Bridge and Structures Office maintains a list of walls that are classified as experimental. If the wall intended

for use is classified as experimental, a work plan is to be prepared by WSDOT and approved by the FHWA.

An approved public interest finding, signed by the Director & State Design Engineer, Development Division, is required for the use of a sole source proprietary wall.

(c) **Gabion Walls**

Gabion walls are nonstandard walls that are to be designed for overturning, sliding, overall slope stability, settlement, and bearing capacity. A full design for gabion walls is not provided in the *Standard Plans*. Gabion baskets are typically 3 feet high by 3 feet wide, and it is typically safe to build gabions two baskets high (6 feet) but only one basket deep. This results in a wall base width of 50% of the wall height, provided soil conditions are reasonably good (medium-dense to dense granular soils are present below and behind the wall).

(2) Responsibility and Process for Design

A flow chart illustrating the process and responsibility for retaining wall/reinforced slope design is provided in Exhibit 730-13a. As shown in the exhibit, the region initiates the process except for walls developed as part of a preliminary bridge plan. These are initiated by the HQ Bridge and Structures Office. In general, it is the responsibility of the design office initiating the design process to coordinate with other groups in the department to identify all wall/slope systems that are appropriate for the project in question. Coordinate with the region and the HQ Bridge and Structures Office, Geotechnical Office, and State Bridge and Structures Architect as early in the process as feasible.

Headquarters or region consultants, if used, are considered an extension of the Headquarters staff and must follow the process summarized in Exhibit 730-13a. All consultant designs, from development of the scope of work to the final product, are to be reviewed and approved by the appropriate Headquarters offices.

(a) **Standard Walls**

The regions are responsible for detailing retaining walls for which standard designs are available.

For standard walls greater than 10 feet in height, and for all standard walls where soft or unstable soil is present beneath or behind the wall, a geotechnical investigation will be conducted, or reviewed and approved, by the HQ Geotechnical Office. Through this investigation, provide the foundation design, including bearing capacity requirements and settlement determination, overall stability, and the selection of the wall types most feasible for the site.

For standard walls 10 feet in height or less where soft or unstable soils are not present, it is the responsibility of the region Materials Laboratory to perform the geotechnical investigation. If it has been verified that soil conditions are adequate for the proposed standard wall that is less than or equal to 10 feet in height, the region establishes the wall footing location based on the embedment criteria in the *Bridge Design Manual*, or places the bottom of the wall footing below any surficial loose soils. During this process, the region also evaluates other wall types that may be feasible for the site in question.

The *Standard Plans* provides design charts and details for standard reinforced concrete cantilever walls. The *Standard Plans* are used to size the walls and determine the factored bearing pressure to compare with the factored bearing resistance determined from the geotechnical investigation. The charts provide maximum soil pressure for the LRFD service, strength, and extreme event limit states. Factored bearing resistance for the LRFD service, strength, and extreme event limit states can be obtained from the HQ Geotechnical Office for standard walls over 10 feet in height and from the region Materials Laboratory for standard walls less than or equal to 10 feet in height. The *Standard Plans* can be used for the wall design if the factored bearing resistance exceeds the maximum soil pressure shown in the *Standard Plans* for the respective LRFD limit states.

Contact the HQ Bridge and Structures Office if the factored bearing resistance provided by the geotechnical investigation does not exceed the maximum soil pressure shown in the *Standard Plans* for one or all of the LRFD limit states. The wall is considered a nonstandard wall design and the *Standard Plans* cannot be used.

If the standard wall must support surcharge loads from bridge or building foundations, other retaining walls, noise walls, or other types of surcharge loads, a special wall design is required. The wall is considered to be supporting the surcharge load and is treated as a nonstandard wall if the surcharge load is located within a 1H:1V slope projected up from the bottom of the back of the wall. Contact the HQ Bridge and Structures Office for assistance

The *Standard Plans* provides eight types of reinforced concrete cantilever walls (which represent eight loading cases). Reinforced concrete retaining walls Types 5 through 8 are not designed to withstand western Washington earthquake forces and are not to be used in western Washington (west of the Cascade crest).

Once the geotechnical and architectural assessments have been completed, the region completes the PS&E for the standard wall option(s) selected, including a generalized wall profile and plan, a typical cross section as appropriate, and details for desired wall appurtenances, drainage details, and other details as needed.

Metal bin walls, Types 1 and 2, have been deleted from the *Standard Plans* and are therefore no longer standard walls. Metal bin walls are seldom used due to cost and undesirable aesthetics. If this type of wall is proposed, contact the HQ Bridge and Structures Office for plan details and toe bearing pressures. The applied toe bearing pressure will then have to be evaluated by the HQ Geotechnical Office to determine whether the site soil conditions are appropriate for the applied load and anticipated settlement.

(b) Preapproved Proprietary Walls

Final approval of preapproved proprietary wall design, with the exception of geosynthetic walls, is the responsibility of the HQ Bridge and Structures Office. Final approval of the design of preapproved proprietary geosynthetic walls is the responsibility of the HQ Geotechnical Office. It is the region's responsibility to coordinate the design effort for all preapproved wall systems.

The region Materials Laboratory performs the geotechnical investigation for preapproved proprietary walls 10 feet in height or less that are not bearing on soft or unstable soils. In all other cases, it is the responsibility of the HQ Geotechnical Office to conduct, or review and approve, the geotechnical investigation for the wall. The region also coordinates with the State Bridge and Structures Architect to ensure that the wall options selected meet the aesthetic requirements for the site.

Once the geotechnical and architectural assessments have been completed and the desired wall alternatives selected, it is the responsibility of the region to contact the suppliers of the selected preapproved systems to confirm in writing the adequacy and availability of the systems for the proposed use.

Include a minimum of three different wall systems in the PS&E for any project with federal participation that includes a proprietary wall system unless specific justification is provided. Standard walls can be alternatives.

Once confirmation of adequacy and availability has been received, the region contacts the HQ Bridge and Structures Office for special provisions for the selected wall systems and proceeds to finalize the contract PS&E in accordance with the *Plans Preparation Manual*. Provide the allowable bearing capacity and foundation embedment criteria for the wall, as well as backfill and foundation soil properties, in the Special Provisions. In general, assume that gravel borrow or better-quality backfill material will be used for the walls when assessing soil parameters.

Complete wall plans and designs for the proprietary wall options will not be developed until after the contract is awarded, but will be developed by the proprietary wall supplier as shop drawings after the contract is awarded. Therefore, include a general wall plan; a profile showing neat line top and bottom of the wall; a final ground line in front of and in back of the wall; a typical cross-section; and the generic details for the desired appurtenances and drainage requirements in the contract PS&E for the proprietary walls. Estimate the ground line in back of the wall based on a nominal 1.5-foot facing thickness (and state this on the wall plan sheets). Include load or other design acceptance requirements for these appurtenances in the PS&E. Contact the HQ Bridge and Structures Office for assistance.

It is best to locate catch basins, grate inlets, signal foundations, and the like outside the reinforced backfill zone of MSE walls to avoid interference with the soil reinforcement. In those cases where conflict with these reinforcement obstructions cannot be avoided, indicate the location(s) and dimensions of the reinforcement obstruction(s) relative to the wall on the plans. Contact the HQ Bridge and Structures Office for preapproved wall details and designs for size and location of obstructions and to obtain the generic details that are to be provided in the plans. If the obstruction is too large or too close to the wall face, a special design may be required to accommodate the obstruction, and the wall is treated as a nonpreapproved proprietary wall.

A special design is required if the wall will support structure foundations, other retaining walls, noise walls, signs or sign bridges, luminaires, or other types of surcharge loads. The wall is considered to be supporting the surcharge load if the surcharge is located within a 1H:1V slope projected from the bottom of the

back of the wall. For MSE walls, the back of the wall is considered to be the back of the soil reinforcement layers. If this situation occurs, the wall is treated as a nonpreapproved proprietary wall.

For those alternative wall systems that have the same face embedment criteria, the wall face quantities depicted in the plans for each alternative are to be identical. To provide an equal basis for competition, the region determines wall face quantities based on neat lines.

Once the detailed wall plans and designs are available as shop drawings after contract award, the HQ Bridge and Structures Office will review and approve the wall shop drawings and calculations, with the exception of geosynthetic walls. They are reviewed and approved by the HQ Geotechnical Office.

(c) **Nonpreapproved Proprietary Walls**

Final approval authority for nonpreapproved proprietary wall design is the same as for preapproved proprietary walls. The region initiates the design effort for all nonpreapproved wall systems by submitting wall plan, profile, cross section, and other information for the proposed wall to the HQ Bridge and Structures Office, with copies to the HQ Geotechnical Office and the State Bridge and Structures Architect. The HQ Bridge and Structures Office coordinates the wall design effort.

Once the geotechnical and architectural assessments have been completed and the desired wall types selected, the HQ Bridge and Structures Office contacts suppliers of the selected nonpreapproved wall systems to obtain and review detailed wall designs and plans to be included in the contract PS&E.

To ensure fair competition between all wall alternatives included in the PS&E, make the wall face quantities identical for those wall systems subject to the same face embedment requirements.

The HQ Bridge and Structures Office develops the special provisions and cost estimates for the nonpreapproved proprietary walls and sends the wall PS&E to the region for inclusion in the final PS&E in accordance with the *Plans Preparation Manual*.

(d) **Nonstandard Nonproprietary Walls**

With the exception of rockeries over 5 feet high, nonproprietary geosynthetic walls and reinforced slopes, and soil nail walls, the HQ Bridge and Structures Office coordinates with the HQ Geotechnical Office and the State Bridge and Structures Architect to carry out the design of all nonstandard, nonproprietary walls. The HQ Bridge and Structures Office develops the wall preliminary plan from site data provided by the region, completes the wall design, and develops the nonstandard nonproprietary wall PS&E package for inclusion in the contract.

For rockeries over 5 feet high, nonproprietary geosynthetic walls and reinforced slopes, and soil nail walls, the region develops wall/slope profiles, plans, and cross sections and submits them to the HQ Geotechnical Office to complete a detailed wall/slope design.

For geosynthetic walls and slopes and for rockeries, the region provides overall coordination of the wall/slope design effort, including coordination with the State Bridge and Structures Architect regarding aesthetics and finishes, and the region or HQ Landscape Architect if the wall uses vegetation on the face.

The HQ Geotechnical Office has overall approval authority for the wall design. Once the wall design has been completed, the HQ Geotechnical Office, and in some cases the HQ Bridge and Structures Office, provides geotechnical and structural plan details to be included in the region plan sheets and special provisions for the PS&E. The region then completes the PS&E package.

For soil nail walls, once the HQ Geotechnical Office has performed the geotechnical design, the HQ Bridge and Structures Office, in cooperation with the HQ Geotechnical Office, coordinates the design effort and completes the PS&E package.

(3) Guidelines for Wall/Slope Data Submission for Design

(a) **Standard Walls, Proprietary Walls, Geosynthetic Walls/Slopes, and Soil Nail Walls**

Where Headquarters involvement in retaining wall/slope design is required (as it is for standard walls and preapproved proprietary walls over 10 feet in height, gabions over 6 feet in height, rockeries over 5 feet in height, all nonpreapproved proprietary walls, geosynthetic walls/slopes, and all soil nail walls), the region submits the following information to the HQ Geotechnical Office or HQ Bridge and Structures Office as appropriate:

- Wall/slope plans.
- Profiles showing the existing and final grades in front of and behind the wall.
- Wall/slope cross sections (typically every 50 feet) or InRoads files that define the existing and new ground line above and below the wall/slope and show stations and offsets.
- Location of right of way lines and other constraints to wall/slope construction.
- Location of adjacent existing and/or proposed structures, utilities, and obstructions.
- Desired aesthetics.
- Date design must be completed.
- Key region contacts for the project.

Note that for the purpose of defining the final wall geometry, it is best to base existing ground measurements on physical survey data rather than solely on photogrammetry. In addition, the region is to complete a Retaining Wall/ Reinforced Slope Site Data Check List, DOT Form 351-009 EF, for each wall or group of walls submitted.

(b) **Nonstandard Walls, Except Geosynthetic Walls/Slopes and Soil Nail Walls**

In this case, the region is to submit site data in accordance with Chapter 710. Additionally, the region is to complete a Retaining Wall/Reinforced Slope Site Data Check List, DOT Form 351-009 EF, for each wall or group of walls.

730.07 Documentation

Refer to Chapter 300 for design documentation requirements.

Specific Wall Type	Advantages	Disadvantages	Limitations
Steel soil reinforcement with full height precast concrete panels	Relatively low cost.	Can tolerate little settlement; generally requires high-quality backfill; wide base width required (70% of wall height).	Applicable primarily to fill situations; maximum feasible height is approximately 20 feet.
Steel soil reinforcement with modular precast concrete panels	Relatively low cost; flexible enough to handle significant settlement.	Generally requires high-quality backfill; wide base width required (70% of wall height).	Applicable primarily to fill situations; maximum height of 33 feet; heights over 33 feet require a special design.
Steel soil reinforcement with welded wire and cast-in-place concrete face	Can tolerate large short-term settlements.	Relatively high cost; cannot tolerate long-term settlement; generally requires high-quality wall backfill soil; wide base width required (70% of wall height); typically requires a settlement delay during construction.	Applicable primarily to fill situations; maximum height of 33 feet for routine designs; heights over 33 feet require a special design.
Steel soil reinforcement with welded wire face only	Can tolerate large short-term settlements; low cost.	Aesthetics, unless face plantings can be established; generally requires high-quality backfill; wide base width required (70% of wall height).	Applicable primarily to fill situations; maximum height of 33 feet for routine designs; heights over 33 feet require a special design.
Segmental masonry concrete block-faced walls, generally with geosynthetic soil reinforcement	Low cost; flexible enough to handle significant settlement.	Internal wall deformations may be greater for steel reinforced systems, but are acceptable for most applications; generally requires high-quality backfill; wide base required (70% of wall height).	Applicable primarily to fill situations; in general, limited to a wall height of 20 feet or less; greater wall heights may be feasible by special design in areas of low seismic activity and when geosynthetic products are used in which long-term product durability is well defined. (See *Qualified Products List*.)
Geosynthetic walls with a shotcrete or cast-in-place concrete face	Very low cost, especially with shotcrete face; can tolerate large short-term settlements.	Internal wall deformations may be greater than for steel reinforced systems, but are still acceptable for most applications; generally requires high-quality backfill; wide base width required (70% of wall height).	Applicable primarily to fill situations; in general, limited to wall height of 20 feet or less unless using geosynthetic products in which long-term product durability is well defined. (See *Qualified Products List*.) For qualified products, heights of 33 feet or more are possible.

Summary of Mechanically Stabilized Earth (MSE) Gravity Wall/Slope Options Available
Exhibit 730-1

Specific Wall Type	Advantages	Disadvantages	Limitations
Geosynthetic walls with a welded wire face	Very low cost; can tolerate large long-term settlements.	Internal wall deformations may be greater than for steel reinforced systems, but are still acceptable for most applications; generally requires high-quality wall backfill soil; wide base width required (70% of wall height).	Applicable primarily to fill situations; in general, limited to wall height of 20 feet or less unless using geosynthetic products in which long-term product durability is well defined. (See *Qualified Products List*.) For qualified products, heights of 33 feet or more are possible.
Geosynthetic walls with a geosynthetic face	Lowest cost of all wall options; can tolerate large long-term settlements.	Internal wall deformations may be greater than for steel reinforced systems, but are still acceptable for most applications; generally requires high-quality backfill; wide base width required (70% of wall height); durability of wall facing.	Applicable primarily to fill situations; use only for temporary applications due to durability of facing; can be designed for wall heights of 40 feet or more.
Soil nail walls	Relatively low cost; can be used in areas with restricted overhead or lateral clearance.	Allow adequate standup time for soil/rock to stand in a vertical cut approximately 6 feet high for at least 1 to 2 days; not feasible for bouldery soils; may require an easement for the nails.	Applicable to cut situations only; not recommended in clean or water-bearing sands and gravels, in bouldery soils that can interfere with nail installation, or in landslide deposits, especially where deep potential failure surfaces are present; maximum wall heights of 35 feet are feasible, though greater wall heights are possible in excellent soil/rock conditions. A special design is always required.

Summary of Mechanically Stabilized Earth (MSE) Gravity Wall/Slope Options Available

Exhibit 730-1 (continued)

Specific Wall Type	Advantages	Disadvantages	Limitations
Concrete crib walls	Relatively low cost; quantity of high-quality backfill required relatively small; relatively narrow base width, on the order of 50 to 60% of the wall height; can tolerate moderate settlements.	Aesthetics.	Applicable to cut and fill situations; reinforced concrete typically can be designed for heights of up to 33 feet and unreinforced concrete up to 16 feet; not used to support bridge or building foundations.
Metal crib walls	Quantity of high-quality backfill required relatively small; relatively narrow base width, on the order of 50 to 60% of the wall height; can tolerate moderate settlements.	Relatively high cost; aesthetics.	Applicable to cut and fill situations; can be designed routinely for heights up to 35 feet; not used to support bridge or building foundations.
Timber crib walls	Low cost; minimal high-quality backfill required; relatively narrow base width, on the order of 50 to 60% of the wall height; can tolerate moderate settlements.	Design life relatively short; aesthetics.	Applicable to cut and fill situations; can be designed for heights up to 16 feet; not used to support structure foundations.
Concrete bin walls	Relatively low cost; narrow base width, on the order of 50 to 60% of the wall height; can tolerate moderate settlements.	Aesthetics.	Applicable to cut and fill situations; can be designed routinely for heights up to 25 feet; not used to support bridge or building foundations.
Gabion walls	Relatively narrow base width, on the order of 50 to 60% of the wall height; can tolerate moderate settlements.	Relatively high cost, depending on proximity to source of high-quality angular rock to fill baskets.	Applicable to cut and fill situations; can be designed routinely for heights up to 15 feet, and by special design up to 21 feet; not used to support structure foundations.

Summary of Prefabricated Modular Gravity Wall Options Available
Exhibit 730-2

Specific Wall Type	Advantages	Disadvantages	Limitations
Mortar rubble masonry walls	Quantity of high-quality backfill required is relatively small.	High cost; relatively wide base width, on the order of 60 to 70% of the wall height; cannot tolerate settlement.	Applicable mainly to fill situations where foundation conditions consist of very dense soil or rock; due to expense, only used in areas where other mortar rubble masonry walls are present and it is desired to match aesthetics; typically can be designed for maximum heights of 25 feet.
Unreinforced concrete gravity walls	Quantity of high-quality backfill required is relatively small.	High cost; relatively wide base width, on the order of 60 to 70% of the wall height; cannot tolerate settlement.	Applicable mainly to fill situations where foundation conditions consist of very dense soil or rock; due to expense, only used in areas where other gravity walls are present and it is desired to match aesthetics; typically can be designed for maximum heights of 25 feet.
Reinforced concrete cantilever walls	Relatively narrow base width on the order of 50 to 60% of the wall height; can be used to support structure foundations by special design.	High cost; cannot tolerate much settlement; relatively deep embedment might be required on sloping ground due to toe in front of face wall.	Applicable to cut and fill situations; can be routinely designed for heights up to 35 feet.
Reinforced concrete counterfort walls	Relatively narrow base width on the order of 50 to 60% of the wall height; can be used to support structure foundations by special design.	High cost; cannot tolerate much settlement; relatively deep embedment might be required on sloping ground due to toe in front of wall face.	Applicable to cut and fill situations; can be routinely designed for heights up to 50 feet; proprietary versions are typically 33 feet maximum.

Summary of Rigid Gravity and Semigravity Wall Options Available
Exhibit 730-3

Specific Wall Type	Advantages	Disadvantages	Limitations
Soldier pile wall	Very narrow base width; deep embedment to get below potential failure surfaces; relatively easy to obtain.	Relatively high cost.	Applicable mainly to cut situations; maximum feasible exposed height is on the order of 10 feet; difficult to install in bouldery soil or soil with water-bearing sands.
Sheet pile wall	Low to moderate cost; very narrow base width.	Difficult to get embedment in dense or bouldery soils; difficult to protect against corrosion.	Applicable mainly to cut situations in soil; maximum feasible exposed height is on the order of 10 feet.
Cylinder pile wall	Relatively narrow base width; can produce stable wall even if deep potential failure surfaces present.	Very high cost.	Applicable mainly to cut situations; maximum feasible exposed height is on the order of 20 to 25 feet depending on the passive resistance available; can be installed in bouldery conditions, though cost will increase.
Slurry wall	Relatively narrow base width; can produce stable wall even if deep potential failure surfaces present.	Very high cost; difficult construction.	Applicable mainly to cut situations; maximum feasible exposed height is on the order of 20 to 25 feet, depending on passive resistance available.


Summary of Nongravity Wall Options Available
Exhibit 730-4

Specific Wall Type	Advantages	Disadvantages	Limitations
All nongravity cantilever walls with tiebacks	Relatively narrow base width; can produce stable wall even if deep potential failure surfaces present.	Very high cost; difficult to install in areas where vertical or lateral clearance is limited; easements may be necessary; installation activities may impact adjacent traffic.	Applicable only to cut situations; can be designed for heights of 50 feet or more depending on the specifics of the structure of the wall.
All nongravity cantilever walls with deadman anchors	Relatively narrow base width; can produce stable wall even if deep potential failure surfaces present.	Moderate to high cost; access required behind wall to dig trench for deadman anchor; may impact traffic during deadman installation; easements may be necessary.	Applicable to partial cut/ fill situations; can be designed for wall heights of approximately 16 feet.


Summary of Anchored Wall Options Available
Exhibit 730-5

Wall/Slope Classification	Specific Wall Type	Advantages	Disadvantages	Limitations
Rockeries	Only variations are in rock sizes used and overall wall dimensions.	Low cost; narrow base width on the order of 30% of the wall height required.	Slope needs to be at least marginally stable without rockery present; cannot tolerate much settlement.	Applicable to both cut and fill situations; maximum feasible height in a cut, even for excellent soil conditions, is approx. 16 feet and 8 feet in fill situations.
Reinforced slopes	Only variations are in geosynthetic products used and in erosion-control techniques used on slope face.	Low cost; can tolerate large settlements; can adapt well to sloping ground conditions to minimize excavation required; high-quality fill is not a requirement.	Room required between the right of way line and the edge of the shoulder to install a 1H:1V slope.	Best suited to sloping fill situations; maximum height limited to 30 feet unless geosynthetic products are used in which long-term product durability is well defined. Certain products can be used in critical applications and for greater slope heights on the order of 60 feet or more, but consider need, landscaping maintenance, and the reach of available maintenance equipment.


Other Wall/Slope Options Available
Exhibit 730-6



MSE Wall with Modular Precast Concrete Facing Panels




MSE Wall with Geosynthetic Reinforcement and CIP Concrete or Shotcrete Facing




MSE Wall with Segmental Concrete Block Facing


Typical Mechanically Stabilized Earth Gravity Walls
Exhibit 730-7




Metal Bin Wall



Precast Concrete Crib Wall




Precast Concrete Bin Wall




Gabion Wall


Typical Prefabricated Modular Gravity Walls
Exhibit 730-8




Mortar Rubble Masonry
Ridgid Gravity Wall




Reinforced Concrete Cantilever
Semigravity Wall




Reinforced Concrete Counterfort
Semigravity Wall



Slurry or Cylinder Pile
Nongravity Cantilever Wall




Soldier Pile Tieback Wall




Soil Nail Wall
in Cut

Typical Rigid Gravity, Semigravity Cantilever, Nongravity Cantilever, and Anchored Walls
Exhibit 730-9




Rockery




Reinforced Slope


Typical Rockery and Reinforced Slopes
Exhibit 730-10




MSE Wall Drainage Detail
Exhibit 730-11




Concrete Traffic Barrier with Asphalt Roadway



Beam Guardrail on Top of MSE Retaining Wall




Concrete Traffic Barrier with Concrete Roadway




Beam Guardrail on Top of Gabion Wall

Retaining Walls With Traffic Barriers
Exhibit 730-12



Retaining Wall Design Process
Exhibit 730-13a



Notes:

"HQ Bridge Office" refers to the WSDOT HQ Bridge and Structures Office.

"Geotech Office" refers to the WSDOT HQ Geotechnical Office.

"State Bridge and Structures Architect" refers to the Architecture Section, HQ Bridge and Structures Office.

Regarding time estimates:

- Assumes no major changes in the wall scope during design.
- Actual times may vary depending on complexity of project.
- Contact appropriate design offices for more accurate estimates of time.

Legend:

Region provides courtesy copy of geotechnical report to HQ Geotechnical Office.

*Assumes soft or unstable soil not present and wall does not support other structures.

**The preapproved maximum wall height is generally 33 feet. Some proprietary walls might be less. (Check with the HQ Bridge and Structures Office.)

***If the final wall selected is a different type than assumed, go back through the design process to ensure that all the steps have been taken.

Retaining Wall Design Process: Proprietary

Exhibit 730-13b

Chapter 740 Noise Barriers

740.01 General
740.02 Design
740.03 Procedures
740.04 Documentation
740.05 References

740.01 General

The function of a noise barrier is to reduce traffic noise levels in adjoining areas. The noise abatement decisions are made during the environmental stage of project development, which is a highly interactive process. Before a noise barrier is designed, the Washington State Department of Transportation (WSDOT) needs to be confident that there is significant need, a cost-effective and environmentally acceptable noise barrier, a source of funds, and acceptance by adjacent property owners, local governmental agencies, and the general public.

Preliminary design information that may be found in the noise report includes:

- Sources of noise.
- Noise receiver locations.
- Predicted level of noise reduction.
- Locations of existing and future noise ¬impacts along the project corridor.
- Barrier location and height recommendations based on what is feasible and reasonable.

Design of a noise barrier project is the result of a team effort coordinated by the Project Engineer.

This chapter addresses the factors that are considered when designing a noise barrier and the associated procedures and documentation requirements.

740.02 Design

The two basic types of noise barriers are the earth berm and the noise wall. An earth berm can be constructed to the full height required for noise abatement or to partial height in conjunction with a noise wall to reach the required height. A noise wall can be made of concrete, masonry, metal, wood, or other approved innovative products, and can be supported by spread, pile, shaft, or trench footings.

Consideration of the noise report and the visual characteristics of adjacent land forms, vegetation, and structural elements (such as buildings, bridges, and retaining walls) will determine whether a proposed noise barrier might be berm, wall, or both.

An earth berm is the primary alternative if the visual and environmental quality of the corridor will be preserved or enhanced and materials and right of way widths are available. (See the *Roadside Manual* for criteria for determining whether a vegetated earth berm is appropriate.)

The region uses the noise report and other environmental documents (see the *Environmental Manual*) to help determine the location, exposure conditions, length, and height of the proposed noise barrier.

To design and locate a noise barrier of any kind, consider the following:

- Desired noise abatement
- Future right of way needs
- Cost and constructability
- Neighborhood character
- Visual character and quality of the corridor
- Future maintenance of the noise barrier and the whole right of way
- Wind
- Supporting soil
- Earthquakes
- Groundwater
- Existing drainage systems and water courses
- Exposure to vehicular impacts
- Potential for vandalism
- Existing vegetation and roadside restoration required
- Access for maintenance equipment and enforcement, traffic service, and emergency vehicles
- Access to fire hydrants from both sides
- Pedestrian and bicycle access
- Available and attainable width of right of way for berms
- Aesthetic and structural characteristics of available wall designs
- Visual compatibility of each wall design with other transportation structures within the corridor
- Construction limits for footings
- Locations of existing survey monuments
- Access to and maintenance of right of way behind a wall, including drainage structures
- Use of right of way and wall by adjacent property owners
- Drainage and highway runoff
- Drainage from adjacent land
- Existing utilities and objects to relocate or remove
- Water and electricity needs, sources, and access points

Avoid objects such as bridge columns, light fixtures, or sign supports that protrude and may present a potential for snagging vehicles.

740.02(1) Earth Berm

Berm slopes are a function of the material used, the attainable right of way width, and the desired visual quality. Slopes steeper than 2H:1V (3H:1V for mowing) are not recommended. Design the end of the berm with a lead-in slope of 10H:1V and curve it toward the right of way line.

Refer to the *Roadside Manual* for guidance regarding vegetation on berms.

740.02(2) Noise Wall

When feasible, to encourage competitive bidding, include several alternate noise wall designs in the contract and permit the ¬contractor to submit alternate designs under the value engineering specification.

There are noise wall designs in the *Standard Plans*. Additional designs are in various stages of development to become standard plans. The draft-standard design sheets and other preapproved plans are available from the Headquarters (HQ) Bridge and Structures Office. The HQ Bridge and Structures Office also works with the regions to facilitate the use of other designs as bidding options.

When a noise wall has ground elevations that are independent of the roadway elevations, a survey of ground breaks (or cross sections at 25 foot intervals) along the entire length of the wall is needed for evaluation of constructability and to assure accurate determination of panel heights.

Size of openings (whether lapped, door, or gated) depends on the intended users. Agencies such as the local fire department can provide the necessary requirements. Unless an appropriate standard plan is available, such openings are designed and detailed for the project.

When a noise wall is inside the Design Clear Zone, design its horizontal and vertical (ground elevation) alignment as if it were a rigid concrete traffic barrier. (See Chapter 1610 for maximum flare rates.)

Provide a concrete traffic barrier shape at the base of a new noise wall constructed 12 feet or less from the edge of the nearest traffic lane. The traffic barrier shape is optional at the base of the new portion when an existing vertical-faced wall is being extended (or the existing wall may be retrofitted for continuity). Standard Concrete Barrier Type 4 is recommended for both new and existing walls except when the barrier face can be cast as an integral part of a new wall. Design analyses may be considered, but they require approval as prescribed in Chapter 300. A design analysis is not required where sidewalk exists in front of the wall or in other situations where the wall face is otherwise inaccessible to traffic. For flare rates and approach slopes for concrete barriers, see Chapter 1610, Traffic Barriers.

To designate a standard noise wall, select the appropriate general special provisions (GSPs) and state the standard plan number, type, and foundation type.

Wall type is a function of exposure and wind speed (see Exhibit 740-1).

A geotechnical report identifying the angle of internal friction “f” and the allowable bearing pressure is needed for selection of a standard foundation. The standard spread footing designs require an allowable bearing pressure of 1 Tsf. The standard trench and shaft footing designs require an “f” of at least 32° for D1 and 38° for D2.

A special design of the substructure is required for noise walls on substandard soil, where winds exceed 90 mph, and for exposures other than B1 and B2 as defined in Exhibit 740-1.

For maintenance of the surface of a tall wall (10 feet or more), consider harness tie offs for the fall protection required by the Department of Labor and Industries.

Exhibit 740-1 Standard Noise Wall Types

	Exposure				
	B1		B2		C
Wind Speed	80 mph	90 mph	80 mph	90 mph	
Wall Type	A	B	C	D	Special Design *

Wind speed is according to Figure 1-2.1.2.A of the (AASHTO) *Guide Specifications for Structural Design of Sound Barriers*. Assume the wind to be perpendicular to the wall on both sides and design for the most exposed side.

Exposure is determined by the nature of the immediately adjacent ground surface and the extension of a plane at the adjacent ground surface elevation for 1500 feet to either side of the noise wall:

Exposure B1 = Urban and suburban areas with numerous closely spaced obstructions having the size of single-family or larger dwellings that prevail in the upwind direction from the noise barrier for a distance of at least 1,500 feet.

Exposure B2 = Urban and suburban areas with more open terrain not meeting the requirements of Exposure B1.

Exposure C = Open terrain with scattered obstructions that includes flat, open country, grasslands, and elevated terrain.

*For a noise wall with Exposure C, on a bridge or overpass or at the top of a slope, consult the HQ Bridge and Structures Office, as a special design will probably be necessary.

740.03 Procedures

The noise unit notifies the Project Engineer's Office when a noise barrier is recommended in the noise report.

The Project Engineer's Office is responsible for interdisciplinary teams, consultation, and coordination with the public, noise specialists, maintenance, construction, region Landscape Architecture Office (or the HQ Roadside and Site Development Section), right of way personnel, Materials Laboratory, State Bridge and Structures Architect, HQ Bridge and Structures Office, CAE Support Team, HQ Development Services & Access Manager, consultants, and many others.

If a noise wall is contemplated, the region evaluates the soils (see Chapters 610 and 710) and obtains a list of acceptable wall design options. The list is obtained by sending information pertaining to soils and drainage conditions, alignment, and height of the proposed wall to the State Bridge and Structures Architect.

If a vegetated earth berm is considered, see the *Roadside Manual* for procedures.

The State Bridge and Structures Architect coordinates with the HQ Bridge and Structures Office, HQ Hydraulics Section, HQ Geotechnical Office, and the region to provide a list of acceptable standard, draft-standard, and preapproved proprietary noise wall designs, materials, and finishes that are compatible with existing visual elements of the corridor. Only wall designs from

this list may be considered as alternatives. Limit design visualizations of the highway side of proposed walls (available from the CAE Support Team in Olympia) to options from this list. The visual elements of the private property side of a wall are the responsibility of the region unless addressed in the environmental documents.

After the noise report is completed, any changes to the ¬dimensions or location of a noise barrier must be reviewed by the appropriate noise unit to determine the impacts of the changes on noise abatement.

On limited access highways, coordinate any opening in a wall or fence (for pedestrians or vehicles) with the HQ Development Services & Access Manager and obtain approval from the Director & State Design Engineer, Development Division.

On nonlimited access highways, an access connection permit is required for any opening (approach) in a wall or fence.

The HQ Bridge and Structures Office provides special substructure designs to the regions upon request; reviews contract design data related to standard, draft-standard, and preapproved designs; and reviews plans and calculations that have been prepared by others (see Chapter 710).

Approval by the State Bridge and Structures Architect is required for any attachment or modification to a noise wall and for the design, appearance, and finish of door and gate-type openings.

Approval by the State Bridge and Structures Architect is also required for the final selection of noise wall appearance, finish, materials, and configuration.

740.04 Documentation

Refer to Chapter 300 for design documentation requirements.

740.05 References

740.05(1) Design Guidance

Guide Specifications for Structural Design of Sound Barriers, AASHTO, 2002

Standard Plans for Road, Bridge, and Municipal Construction (*Standard Plans*), M 21-01, WSDOT

740.05(2) Supporting Information

Environmental Manual, M 31-11, WSDOT
Roadside Manual, M 25-30, WSDOT

Chapter 800 Hydraulic Design

800.01 General
800.02 References
800.03 Hydraulic Considerations
800.04 Safety Considerations
800.05 Design Responsibility
800.06 Documentation

800.01 General

Hydraulic design factors can significantly influence the corridor, horizontal alignment, grade, location of interchanges, and necessary appurtenances required to convey water across, along, away from, or to a highway or highway facility. An effective hydraulic design conveys water in the most economical, efficient, and practical manner to ensure reasonable public safety without incurring excessive maintenance costs or appreciably damaging the highway or highway facility, adjacent property, or the total environment.

This chapter is intended to serve as a guide to highway designers so they can identify and consider hydraulic-related factors that impact design. Detailed criteria and methods that govern highway hydraulic design are in the Washington State Department of Transportation (WSDOT) *Hydraulics Manual* and *Highway Runoff Manual*.

Some drainage, flood, and water quality problems can be easily recognized and resolved; others might require extensive investigation before a solution is developed. Specialists experienced in hydrology and hydraulics can contribute substantially to the planning and project definition phases of a highway project by recognizing potentially troublesome locations, making investigations, and recommending practical solutions. Regions may request that the Headquarters (HQ) Hydraulics Section provide assistance regarding hydraulic problems.

Since hydraulic factors can affect the design of a proposed highway or highway facility from its inception, consider these factors at the earliest possible time during the planning phase.

In the project definition phase, begin coordination with all state and local governments and Indian tribes that issue or approve permits for the project.

800.02 References

(1) Design Guidance

Highway Runoff Manual, M 31-16, WSDOT

Hydraulics Manual, M 23-03, WSDOT

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT

Standard Specifications for Road, Bridge, and Municipal Construction (Standard Specifications), (Amendments and General Special Provisions), M 41-10, WSDOT

Utilities Manual, M 22-87, WSDOT

(2) Special Criteria

Special criteria for unique projects are available by request from the HQ Hydraulics Section.

800.03 Hydraulic Considerations

(1) The Flood Plain

Encroachment of a highway or highway facility into a flood plain might present significant problems. A thorough investigation includes the following:

- The effect of the design flood on the highway or highway facility and the required protective measures.
- The effect of the highway or highway facility on the upstream and downstream reaches of the stream and the adjacent property.
- Compliance with hydraulic-related environmental concerns and hydraulic aspects of permits from other governmental agencies per Chapter 225.

Studies and reports published by the Federal Emergency Management Agency (FEMA) and the U.S. Army Corps of Engineers are very useful for flood plain analyses. The HQ Hydraulics Section has access to all available reports and can provide any necessary information to the region.

(2) Stream Crossings

When rivers, streams, or surface waters (wetland) are crossed with bridges or culverts (including open-bottom arches and three-sided box culverts), consider:

- Locating the crossing where the stream is most stable.
- Effectively conveying the design flow(s) at the crossing.
- Providing for passage of material transported by the stream.
- The effects of backwater on adjacent property.
- Avoiding large skews at the crossing.
- The effects on the channel and embankment stability upstream and downstream from the crossing.
- Location of confluences with other streams or rivers.
- Fish and wildlife migration.
- Minimizing disturbance to the original streambed.
- Minimizing wetland impact.

For further design details, see the *Hydraulics Manual*.

(3) Channel Changes

It is generally desirable to minimize the use of channel changes because ongoing liability and negative environmental impacts might result. Channel changes are permissible when the designer determines that a reasonable, practicable alternative does not exist. Consult the HQ Hydraulics Section for the best guidance when channel changes are considered.

When channel changes are used, consider the following:

(a) Restoration of the original stream characteristics as nearly as practicable. This includes:
- Meandering the channel change to retain its sinuosity.
- Maintaining existing stream slope and geometry (including meanders) so stream velocity and aesthetics do not change in undisturbed areas.
- Excavation, selection, and placement of bed material to promote formation of a natural pattern and prevent bed erosion.
- Retention of streambank slopes.
- Retention or replacement of streamside vegetation.

(b) The ability to pass the design flood.

(c) The effects on adjacent property.

(d) The effects on the channel and embankment upstream and downstream from the channel change.

(e) Erosion protection for the channel change.

(f) Environmental requirements such as wetlands, fish migration, and vegetation reestablishment.

(g) The drainage pattern. Do not redirect flow from one drainage basin to another; follow the historical drainage pattern.

(4) Roadway Drainage

Effective collection and conveyance of stormwater is critical. Incorporate the most efficient collection and conveyance system considering initial highway costs, maintenance costs, and legal and environmental considerations. Of particular concern are:

- Combinations of vertical grade and transverse roadway slopes that might inhibit drainage.
- Plugging of drains on bridges as the result of construction projects. This creates maintenance problems and might cause ponding on the structure. The use of drains on structures can be minimized by placing sag vertical curves and crossovers in superelevation outside the limits of the structure.

For discussion of the relationship of roadway profiles to drainage profiles, see Chapter 1220.

(5) Subsurface Drainage

Subsurface drainage installations control groundwater encountered at highway locations. Groundwater, as distinguished from capillary water, is free water occurring in a zone of saturation below the ground surface. The subsurface discharge depends on the effective hydraulic head and on the permeability, depth, slope, thickness, and extent of the aquifer.

The solution of subsurface drainage problems often calls for specialized knowledge of geology and the application of soil mechanics. The Region Materials Engineer evaluates the subsurface conditions and includes findings and recommendations for design in the geotechnical report.

Typical subdrain installations control seepage in cuts or hillsides, control base and shallow subgrade drainage, or lower the groundwater table (in swampy areas, for example).

Design a system that will keep the stormwater out of the subsurface system when stormwater and subsurface drainage systems are combined.

(6) Subsurface Discharge of Highway Drainage

Consider subsurface discharge of highway drainage when it is a requirement of the local government or when existing ground conditions are favorable for this type of discharge system. Criteria for the design of drywells or subsurface drainage pipe for this type of application are described in the *Hydraulics Manual*. The criteria for the design of infiltration ponds are described in the *Highway Runoff Manual*.

(7) Treatment of Runoff

On certain projects, effective quantity control of runoff rates and removal of pollutants from pavement are intended to address flooding and water quality impacts downstream. (See the *Highway Runoff Manual* for specific criteria on quantity and quality control of runoff.)

800.04 Safety Considerations

Locate culvert ends outside the Design Clear Zone when feasible. (See Chapter 1600 for culvert end treatments when this is infeasible.)

For detention ponds and wetland mitigation sites, see Chapter 560 regarding fencing.

800.05 Design Responsibility

The *Hydraulics Manual* describes the responsibilities of the regions and the HQ Hydraulics Section regarding hydraulic design issues.

800.06 Documentation

For the list of documents required to be preserved in the Design Documentation Package and the Project File, see the Design Documentation Checklist:
www.wsdot.wa.gov/design/projectdev

Chapter 900 Roadsides

900.01 General
900.02 References
900.03 Project Development
900.04 Documentation

900.01 General

The Washington State Department of Transportation (WSDOT) recognizes roadsides as an asset. WSDOT manages roadsides, balancing operational and environmental functions and lowest life cycle costs consistent with a reliable, safe, and sustainable transportation system.

The roadside is the primary place used to blend transportation facilities into the context of the natural and built environments. The roadside is the green infrastructure that contributes to the transportation system. It integrates natural processes into the built environment and includes the concepts of low-impact development (LID). Good roadside design coordinates many elements, including, but not limited to: structures; vegetation; signs; pedestrian and bicycle movement; stormwater treatment facilities; and other right of way functions. All the elements work together to provide visual continuity in the highway corridor.

WSDOT is committed to ensuring designs meet the needs and functions of the project and the community in a way that is safe, cost-effective, attractive, and maintainable. WSDOT is also committed to building transportation facilities in context with the surrounding environment, which is reflected in the Context Sensitive Solutions Executive Order (E 1028) and the Washington Transportation Plan (WTP).

The WSDOT *Roadside Manual* is the "how-to" manual for roadside design. It shows the links and coordination necessary between all WSDOT partners responsible for roadside activities. It also provides in-depth information on how to restore the roadside, including chapters on law and policy, soil bioengineering, contour grading, vegetation, irrigation, and many more.

In the fall of 2013, WSDOT published the new *Roadside Policy Manual* (RPM). In conformance with current WSDOT policies, the roadside policy team developed the RPM into a comprehensive roadside policy that promotes our state's healthy economy, environment, and communities. It contains vital policy information needed to design roadsides in conjunction with the *Roadside Manual*. WSDOT's policy is to preserve and restore roadside functions through the preservation and use of soils, vegetation, and other roadside elements. Chapter 2 of the RPM defines these important project requirements. The RPM is intended for use in all phases of transportation asset management: Planning, Program Management, Project Development, Construction, and Maintenance. For further information, see: www.wsdot.wa.gov/design/roadside/

900.02 References

Maintenance Manual, M 51-01, WSDOT

Roadside Manual, M 25-30, WSDOT

Roadside Policy Manual, M 3110, WSDOT

Understanding Flexibility in Transportation Design – Washington, WSDOT, 2004

Utilities Accommodation Policy, M 22-86, WSDOT

For utility-related roadside issues, see the *Utilities Manual,* and for Scenic Classification ratings, see the *Utilities Accommodation Policy*

For WSDOT Project Management web resources, start here:
www.wsdot.wa.gov/projects/projectmgmt/

Roadside Design Guide, AASHTO, 2011

Roadside development concepts covered elsewhere in the *Design Manual* include the following:

- Fencing (Chapter 560)
- Jurisdiction (Chapters 300, 1100, 1600)
- Noise barriers (Chapter 740)
- Pedestrian facilities (Chapter 1510)
- Public art (Chapter 950)
- Retaining walls (Chapter 730)
- Roadside safety, traffic barriers, and energy attenuators (Chapters 1600, 1610, 1620)
- Safety rest areas, parks, viewpoints, and historical markers (Chapter 1710)
- Signs (Chapter 1020)

900.03 Project Development

900.03(1) Region Landscape Architect

The region Landscape Architect is responsible for the following:

- Designs, supervises, has approval authority over, and stamps plans for wetland mitigation, roadside restoration, and revegetation.
- Coordinates the visual elements within highway corridors, in conjunction with the State Bridge and Structures Architect.
- Designs and supervises other roadside work, such as site design for park & ride lots or safety rest areas, to ensure roadside restoration is designed and constructed to WSDOT guidelines and standards.
- Provides visual discipline reports for environmental documentation.
- Assists the region in completing the plant establishment phase of projects.

The Headquarters (HQ) Roadside and Site Development Section will provide roadside and mitigation design, visual impact assessment, and construction inspection work for the project offices in regions without a Landscape Architect. Refer to the Project Management Online Guide for further descriptions of the roles and responsibilities of project teams.

900.03(2) Roadside Restoration Projects

There are typically two types of roadside restoration projects pertaining to vegetation-related roadway construction projects: regulatory and restoration.

900.03(2)(a) Regulatory

The first type of project is work related to regulatory or permit requirements. Examples are wetland mitigation work or Hydraulic Permit Approvals (HPAs). This work typically must occur by the time the impacting project is complete.

900.03(2)(b) Restoration

The second type of project is the restoration of construction impacts to roadside functions to meet the WSDOT policy requirements outlined in the *Roadside Policy Manual*.

900.03(3) Stand-Alone Project or Part of Roadway Construction?

Roadside restoration work should be evaluated by the design team to determine whether it will be most efficient as part of the roadway construction contract or as a separate stage contract.

900.03(3)(a) Roadway Construction Contract

The benefits of roadside restoration during roadway construction include the following:

- All work can be done under one contract.
- The restoration can be completed without waiting for a new contract to be let and administered.
- Plant establishment can often begin sooner.

900.03(3)(b) Separate Stage Project

A separate stage contract provides the following opportunities because it would be done when road construction is completed:

- If construction impacts are different than originally anticipated, the restoration contract can be changed. For example, if disturbance is minimized, fewer plants and soil amendments may be needed.
- The site can be watched to see how the grading and hydrology interact before plants are planted.
- The prime contractor can be someone who specializes in roadside work.

900.03(4) Plant Establishment

Plant establishment periods are included as part of roadside restoration and on all environmental mitigation projects.

- A minimum of three years of plant establishment work is required for all planted areas in western Washington, and planted and/or seeded areas in eastern Washington.
- In situations where it is important to provide a full cover of vegetation to achieve the environmental or operational functions, five years of plant establishment may be needed.
- If the plant establishment period will last longer than three years on a roadside restoration contract, discussion should occur with Program Management to request and justify additional funding.
- In an environment that uses woody plants, plant establishment may take up to 10 years for the woody vegetation to exclude weeds and reach a condition with the lowest life cycle cost.
- Regulatory aspects of projects can require 10 years of plant establishment to ensure the standards of success outlined in the permit, although aggressive weed control and favorable weather can allow sites to close out early.

The goal is to give WSDOT Maintenance a site that is nearly self-sustaining after the plant establishment period is complete.

900.04 Documentation

Refer to Chapter 300 for design documentation requirements.

Chapter 950 Public Art

950.01 General
950.02 References
950.03 Standard Architectural Design
950.04 Criteria for Public Art
950.05 Process and Project Delivery Timing
950.06 Approvals
950.07 Documentation

950.01 General

There has been a growing interest on the part of communities to use art within the transportation facilities of the Washington State Department of Transportation (WSDOT). It can be used to provide visual interest along roadsides, make unique statements about community character, and create a positive public response that will last over time.

Proponents for public art might be local agencies or engaged citizens' groups with interest in the outcome of a WSDOT project. The environmental and public involvement processes offer opportunities for community partnership on the visual and aesthetic qualities of a corridor.

The public art policy in this chapter is intended to: provide guidance for managing public art on WSDOT facilities and within its rights of way; reinforce the existing policy in the *Roadside Policy Manual*; designate appropriate locations for the incorporation of public art features; and provide for the consistent use of statewide development, review, and approval processes on new and existing features.

What is public art?

For the purposes of WSDOT policy, public art is an enhancement to a functional element, feature, or place within a transportation corridor to provide visual interest. The enhancement could be an addition to a functional element, integrated into a design, or for purely aesthetic purposes.

An element is considered "public art" if it is beyond WSDOT standard practice for architectural treatment.

The appropriateness of public art is frequently dependent upon its location and composition. For example, an art piece or feature chosen for the back side of a noise wall, at a safety rest area, or along a bike path may not be suitable at the end of a freeway ramp or along the main line of a highway. In addition to appropriate placement, WSDOT must balance the requests for proposed public art projects with the need to provide corridor continuity, improve the unity of highway elements, and provide roadsides that do not divert motorists' attention from driving.

While some local jurisdictions dedicate a percentage of their project budgets for art, WSDOT has no such dedicated funding. Section 40 of the State Constitution specifies that gas tax money must be used for a "highway purpose." Therefore, public art beyond WSDOT standard design is typically funded by communities or other entities outside of WSDOT.

When city or community entrance markers are proposed, this policy should be used in conjunction with the guidance contained in Chapter 1600, Roadside Safety, the *Traffic Manual,* and the *Roadside Policy Manual*.

950.02 References

950.02(1) Federal/State Laws and Codes

Chapter 47.42 Revised Code of Washington (RCW), Highway advertising control act – Scenic vistas act

950.02(2) Design Guidance

Bridge Design Manual, M 23-50, WSDOT

Roadside Policy Manual, M 25-31, WSDOT

950.02(3) Supporting Information

A Guide for Achieving Flexibility in Highway Design, AASHTO, 2004

Flexibility in Highway Design, FHWA, 1997

Roadside Manual, M 25-30, WSDOT

Traffic Manual, M 51-02, WSDOT

Understanding Flexibility in Transportation Design – Washington, WSDOT, 2005
www.wsdot.wa.gov/research/reports/600/638.1.htm

950.03 Standard Architectural Design

WSDOT's public art policy does not apply to the standard design of transportation architectural elements such as simple geometric patterns; combinations of WSDOT standard concrete formliners; contrasting pavement patterns or colors in crosswalks or roundabouts; or earth-tone colors on structures or barriers.

To discuss the details of proposed public art projects, contact the State Bridge and Structures Architect, and the region or Headquarters (HQ) Landscape Architect for regions without a Landscape Architect. They are key members of the Public Art Specialty Services Team (described in 950.05) and can answer questions and assist in determining an appropriate course of action.

950.04 Criteria for Public Art

Placement and composition of public art is unique and is to be evaluated on a case-by-case basis. Prior to approval of public art, a public art plan is to be developed in coordination with the Public Art Specialty Services Team. The team will review the concept, guide the local agency or design team through the process, and approve the plan in accordance with 950.06.

The following criteria are to be addressed and documented in the public art plan:

- The public art proponent, the funding source, and those responsible for the installation and maintenance of the proposed art.
- Safe maintenance access.
- Maintenance Agreement with local agencies for maintenance where appropriate. If there is a potential for vandalism, address this issue in the associated maintenance agreement.

- Whether public art resulted from the specific recommendation(s) of a planning-level study.
- Subject of the recommended art.
- Visibility:
  - Art visible from the main line must contribute to corridor continuity and the view from the road.
  - Art visible to the community or adjacent to the neighborhood side of a structure may have more flexibility in design than that visible from the main line.
- Safety and security: Public art must not negatively impact safety nor create an attractive nuisance.
- Potential for traffic distraction: Proposed art must not distract motorists. It must be appropriate for the speed and angle at which it will be viewed.
- Scale and context: The public art plan should address the scale of the proposed work and its fit within the surrounding landscape and land use.
- Contribution of the art to community character.
- Impact of the proposed art on social, cultural, and environmental features:
  - In general, WSDOT would not approve the addition of art on a historic structure or within an ecologically sensitive area.
- Compliance with applicable laws, such as the Scenic Vistas Act and 23 CFR 752, Landscape and Roadside Development.
- Compliance with the *Traffic Manual* and the *Roadside Policy Manual*:
  - Lettering that can be construed as advertisement is not allowed.
  - "Welcome to [insert city name]" lettering is permissible at the end of ramps if it complies with the *Traffic Manual* section on Sign Design.
  - Locations for community gateway signs are described in the *Roadside Policy Manual*.
- Demonstrated responsible use of tax dollars and enhanced public trust in WSDOT judgment.

For further information on these criteria, see the *Roadside Manual*.

950.04(1) Acceptable Public Art Features

Public art must be in compliance with WSDOT corridor guidelines, such as the Mountains to Sound Greenway Implementation Plan or the I-90 Architectural Design Standards, and existing policies such as the *Roadside Policy Manual* and the *Bridge Design Manual*.

The following are examples of types and locations of acceptable public art features:

- Concrete surface treatments (beyond WSDOT standard)
- Colored paving/colored pavers/scoring patterns (beyond WSDOT standard)
- Specially designed benches, trash cans, planters, or other street furnishings
- Soft lighting and lighting fixtures
- Small-scale sculptures or art pieces (when not viewed from the main line)
- Attachments to decorative railings, light poles, or fences
- Decorative bus shelters

950.04(2) Unacceptable Public Art Features

The following are examples of unacceptable public art features:

- Kinetic sculptures
- Brightly lit or flashing art
- Art that poses a safety risk or liability
- Large sculptures (the size is relative to its context and location in the landscape)
- Art with highly reflective qualities or adverse colors
- Art that is a distraction to drivers or out of context with the surroundings
- Art with a topic/theme that could cause negative public reaction
- Art that resembles a traffic control device
- Art that contains advertising

950.05 Process and Project Delivery Timing

Begin the development and review of public art early in the design process, and conduct subsequent reviews during the course of its development. Do not include public art as a change order or addendum to a project without first having gone through the process described in this policy. Project Ad and Award dates will not be delayed due to an incomplete public art process.

A public art plan is developed to incorporate public art into projects on state highways. Include the review of the public art plan by the Public Art Specialty Services Team in project reviews.

950.05(1) Public Art Plan

The public art plan is developed by the Project Engineer's Office or by the local artist or community sponsoring the proposal. The plan provides enough detail and description to convey the intent of the proposed art project. The plan documents how the proposed art meets the criteria listed in 950.04 and includes the following elements:

- Cover sheet with appropriate approval signatures (see 950.06).
- Project overview.

- Location of the proposed art.
- Scale drawings of the proposed art, including proposed materials, attachments, and finishes. Any attachments to fencing or structures, or proposed new structures, will require structural engineering calculations.
- All criteria from 950.04, Criteria for Public Art, addressed and documented.
- Justification and recommendations for public art.
- Documentation showing support by the local community.

Without an approved public art plan, a Maintenance Agreement (as appropriate), and funding, the "art" will not be constructed or installed.

950.05(2) Public Art Specialty Services Team

Include the Public Art Specialty Services Team in the development of public art and the public art plan. The Team includes the following:

- Project Engineer or a designee (if the art is included in a project)
- State Bridge and Structures Architect
- Region or HQ Landscape Architect
- Region Traffic Engineer
- Region Local Programs Engineer (if the proponent is a local community)

For public art proposed within Interstate Limited Access, the following team members are also required:

- Assistant State Design Engineer
- Federal Highway Administration (FHWA) Safety/Geometric Engineer or a designee

Consider team membership from the following functional areas when their expertise is applicable:

- Maintenance
- Planning
- Environmental
- Real Estate Services

950.06 Approvals

950.06(1) Intermediate Approvals

The Public Art Specialty Services Team is responsible for approving the public art; therefore, be sure to involve them in the development of art during the earliest possible phase of project development. This will ensure approvals happen smoothly and WSDOT and FHWA are aware of the public art as soon as possible.

Project development phases include the following:

- Initial Art Concept review: input and approval.
- Selected Art Concept review: input and approval.
- Final Proposed Art review: input and approval.

950.06(2) Final Approval

Approval of the public art plan is considered approval for the public art. The public art plan cover letter needs to include the following approval signatures as appropriate.

950.06(2)(a) Within Limited Access

Public art within Limited Access on the Interstate is approved by:

- Project Engineer or a designee (if the art is included in a project)
- State Bridge and Structures Architect
- Region or HQ Landscape Architect
- Region Traffic Engineer
- Region Local Programs Engineer (if the proponent is a local community)
- Assistant State Design Engineer
- Region Administrator or designee
- FHWA Safety/Geometric Design Engineer or designee

950.06(2)(b) All Other Projects

Public art for all other projects is approved by:

- Project Engineer or a designee (if the art is included in a project)
- Region or HQ Landscape Architect
- State Bridge and Structures Architect
- Region Traffic Engineer
- Region Local Programs Engineer (if the proponent is a local community)
- Region Administrator or designee

950.07 Documentation

The public art plan, complete with approval signatures, is retained in the Design Documentation Package (DDP).

Refer to Chapter 300 for design documentation requirements.

Chapter 1010 Work Zone Safety and Mobility

1010.01 General
1010.02 Definitions
1010.03 Work Zone Safety and Mobility
1010.04 Transportation Management Plans and Significant Projects
1010.05 Developing TMP Strategies
1010.06 Capacity Analysis
1010.07 Work Zone Design
1010.08 Temporary Traffic Control Devices
1010.09 Positive Protection Devices
1010.10 Other Traffic Control Devices or Features
1010.11 Traffic Control Plan Development and PS&E
1010.12 Training and Resources
1010.13 Documentation
1010.14 References

1010.01 General

Addressing work zone impacts to all road users is an important component in the design of a project and needs to be given adequate consideration early in the design process. Most work zones create some level of traffic impacts and require additional safety features; therefore, all work areas and operations needed for construction must be identified and addressed during the project design. Planners, designers, construction engineers, maintenance personnel, and others all play a role in developing a comprehensive work zone design. Consider including Rail, Freight, and Ports, Commercial Vehicle Services, and Public Transportation Divisions for help coordinating with freight and transit industries. See the WSDOT Project Management website for information on project teams.

This chapter provides the designer with guidance to develop comprehensive work zone strategies and plans to address a project's safety and mobility benefits/improvements for all modes, as well as constructability. A systematic process for addressing work zone impacts is required by federal regulations and state policy.

For the purposes of this chapter high speed means 45 mph and above.

1010.02 Definitions

The following terms are defined in the *Design Manual* Glossary: ***transportation management area (TMA)***; ***transportation management plan (TMP)***; ***work zone; work zone impact***; ***work zone traffic control***; ***traveling public***.

1010.03 Work Zone Safety and Mobility

Washington State Department of Transportation (WSDOT) policy per Executive Order E 1001, Work Zone Safety and Mobility, is intended to support systematic consideration and management of work zone impacts across all stages of project development.

The policy states:

> *All WSDOT employees are directed to make the safety of workers and the traveling public our highest priority during roadway design, construction, maintenance, and related activities.*

Designers should be familiar with this document. The policy defines how WSDOT programs address work zone safety and mobility issues during project planning, design, and construction.

1010.04 Transportation Management Plans and Significant Projects

1010.04(1) Transportation Management Plan (TMP)

A transportation management plan is a set of strategies for managing the corridor-wide work zone impacts of a project. A TMP is required for all projects and is the key element in addressing all work zone safety and mobility impacts. The TMP development begins in the scoping phase of a project by assessing impacts known at the time and then selecting mitigating strategies and design solutions to manage those impacts. It is very important to continue the development of the TMP throughout the project development process.

Not all work zone impacts have to be addressed with traffic control plans only. Many work zone impacts can be reduced or eliminated through project design elements like alignment choice, materials selection, structure types, overbuilding, and phased construction. Work zone impacts related to work duration may be resolved or reduced through innovative bidding and contract administration.

The three major components of a TMP are described below.

1010.04(1)(a) Temporary Traffic Control (TTC)

The TTC components are those strategies for directing traffic through the work zone and minimizing the duration of the impacts. These components are to be included in the Plans, Specifications, and Estimates (PS&E) as traffic control plans (TCPs) and contract provisions. The TTC components may include but are not limited to the following strategies:

- TTC strategies such as lane closures or shifts, one-lane two-way operations (flagging and or pilot car), staged construction, or full road closures and detours.
- Traffic Control Devices such as temporary signing, channelizing devices (cones, drums), changeable message signs, arrow boards, temporary signals, and temporary pavement markings.
- Corridor Project Coordination, Contracting Strategies, and Innovative Construction Strategies such as A+B bidding, incentives/disincentives, and precast members or rapid cure materials.

1010.04(1)(b) Transportation Operations (TO)

The TO components are those strategies for improving traffic flow and safety through the work zone. Some of these strategies may be included in the PS&E, but could also be WSDOT-managed elements outside the contract. The TO components may include but are not limited to the following strategies:

- Demand Management Strategies such as Transit service improvements, transit incentives, and park & ride promotion.
- Corridor/Network Management (traffic operations) Strategies such as Signal timing/coordination improvements, temporary signals, bus pullouts, reversible lanes, and truck/heavy-vehicle restrictions.
- Work Zone Safety Management Strategies such as Positive protective device use, speed limit reductions, and automated flagger assistance devices.
- Traffic/Incident Management and Enforcement Strategies such as Work Zone Intelligent Transportation Systems (ITS), Washington State Patrol, tow service, WSDOT Incident Management vehicle(s), and traffic screens.

1010.04(1)(c) Public Information (PI)

The PI components are those strategies for raising awareness of the upcoming project impacts or current restrictions. Public awareness strategies may be developed and implemented by WSDOT through the region or Headquarters (HQ) Communications offices and implemented before and during construction. Motorist information strategies may be WSDOT-managed elements with state equipment outside the contract or identified on plans in the PS&E. The PI components may include, but are not limited to, the following strategies:

- Public Awareness Strategies such as Brochures or mailers, press releases, paid advertisements, and project website (consider providing information in other languages if appropriate).
- Motorist Information Strategies such as Highway advisory radio (HAR), changeable message signs, and transportation management center (TMC).

It is very important to continue the development of the TMP throughout the project development process. Not all work zone impacts have to be addressed with traffic control plans only. Many work zone impacts can be reduced or eliminated through project design elements like alignment choice, materials selection, structure types, overbuilding, and phased construction. Work zone impacts related to work duration may be resolved or reduced through innovative bidding and contract administration.

The TMP Checklist in Exhibit 1010-3 will help identify and organize TMP components. Include the completed checklist in the Project File. For significant projects, develop this checklist and the supporting plans, data, impacts assessment, strategies, capacity/delay analysis and endorsements into a formal TMP document to be included in the Project File. For TMP examples, see:
http://www.ops.fhwa.dot.gov/wz/resources/final_rule/tmp_examples/sample_tmps.htm
http://www.ops.fhwa.dot.gov/wz/resources/publications/trans_mgmt_plans/trans_mgmt_plans.pdf

1010.04(2) Significant Projects

The FHWA definition of a "significant project" is as follows:

> *A significant project is one that, alone or in combination with other concurrent projects nearby, is anticipated to cause sustained work zone impacts that are greater than what is considered tolerable based on state policy and/or engineering judgment.*
>
> *All Interstate system projects within the boundaries of a designated Transportation Management Area (TMA) that occupy a location for more than three days with either intermittent or continuous lane closures shall be considered as significant projects.*

Note: Significant projects require a Transportation Management Plan document addressing safety and mobility impacts with strategies or elements from all three TMP components. The size and scale of the TMP document will depend on the project's complexity and impacts. For examples of WSDOT TMP's see: http://www.wsdot.wa.gov/Safety/WorkZones/resources.htm

For projects not identified as significant, the Temporary Traffic Control components included in the PS&E will be considered the TMP. Transportation Operations and Public Information components may also be required to properly address the impacts as many projects can have significant work zone safety and mobility impacts, but are not necessarily a significant project as defined under the federal requirements stated above. Consider developing a TMP document for these types of projects as well.

The Project Summary must include a Work Zone Strategy Statement and indicate whether the project is significant in regard to work zone impacts.

Significant projects may require a Value Engineering (VE) study (see Chapter 310) and a Cost Risk Assessment (CRA) or Cost Estimate Validation Process (CEVP) that could help define strategies or identify risks: www.wsdot.wa.gov/projects/projectmgmt/riskassessment/

1010.05 Developing TMP Strategies

1010.05(1) Key Considerations

The following list is intended to alert the designer to actions and issues that need to be addressed as part of a TMP. Addressing these items is required per WSDOT's work zone policy and federal regulations, and they are key to the successful development of a project's TMP.

- Determine work zone impacts through an impact assessment process.
- Minimize, mitigate, and manage work zone impacts.
- Integrate work zone impacts strategies early, during planning, programming, and design.
- Develop an accurate scoping estimate based on the work zone strategies.
- Hold a Work Zone Design Strategy Conference early in the design process. (Include bridge, construction, traffic, maintenance, freight, transit, local agency, and law enforcement personnel.)
- Utilize the Work Zone TMP Checklist/TMP document (required for significant projects).
- Emphasize flagger safety.

- Assess work zone mobility through a capacity analysis.
- Integrate project constructability, work efficiency and cost containment into the work zone strategy.
- Attend work zone training.
- Address Washington State traffic and safety regulations as provided for by state law.
- Use the legally adopted *Manual on Uniform Traffic Control Devices* (MUTCD), with Washington State modifications as the minimum standard.
- Provide an appropriate level of traffic control plans (TCPs).
- Consider work zone ITS elements.
- Use established design criteria in work zone roadway and roadside design.
- Accommodate pedestrian access (including ADA requirements) and maintenance of existing transit stops and bicycle traffic.
- Consider maintenance issues and needs through the duration of the project.
- Consider school, hospital, emergency services, and postal delivery, impacts.
- Consider economic impacts (business access) due to traffic delay or restricted access.
- Consider freight mobility; total roadway widths to less than 16 feet should be avoided if possible. Truck routes can be found here: http://www.wsdot.wa.gov/Freight/EconCorridors.htm
- Address traffic impacts extending beyond the project limits and impacting other roads.
- Identify seasonal or special event impacts that affect recreation or business due to work zone impacts.
- Consider risk management and tort liability exposure.
- Approach the work zone design from the road user's perspective.
- Incorporate worker safety needs (positive protection) in your work zone designs.
- Account for all needed work areas, operations and possible staging areas.
- Address work vehicle ingress and egress to each work area.
- Use of law enforcement

1010.05(2) Impacts Assessment

One of the most important tasks in developing a TMP is assessing all of the project impacts to mobility and safety. Impacts that are not identified and addressed in the TMP will undoubtedly become issues during the construction phase of the project. A designer needs to possess a clear understanding of how project features will be constructed, including work methods, equipment, materials, and duration, to complete the work. Involve the construction PE when making decisions on assessing and addressing impacts.

A complete and accurate impacts assessment will allow for the development of an effective TMP that should only need minor modifications to address construction issues.

An early and ongoing impacts assessment allows time to:

- Develop TTC, TO, and PI strategies to address identified impacts as needed to effectively manage the project.
- Resolve potential work zone impacts within the design features of the project. Decisions that consider work zone impacts during bridge type selection, materials selection, advertisement dates, and others have the potential to resolve or minimize work zone impacts.

- Consider innovative mitigation strategies that may involve many stakeholders.

Some impacts may be difficult to completely solve and may ultimately need a management decision to determine the level of mitigation or impact that is acceptable. These types of impacts need to be clearly addressed in the TMP with documentation supporting and explaining the decision.

The following are some examples of impacts that need to be managed during the design of a project:

1. Bridge construction sequence or falsework opening plans need to match the TCC staging or channelization plans. Coordination with the HQ Bridge and Structures Office is essential as the bridge design schedule may differ than the project schedule. Maintain the legal height of 16 feet 6 inches as the minimum falsework opening whenever possible; anything less than this must consider overheight vehicle impacts, possible additional signing needs, and temporary bypass routes. Impacts to shoulder widths due to barrier or bridge staging may impact bicycle or pedestrian access and must be addressed in TCC plans. Refer to Chapter 720 for additional requirements and approvals. Coordination with the Permits Office may be needed.
2. If existing signal and illumination systems are not able to be maintained during the construction phases, plans for temporary systems or connections need to be included in the project.
3. Temporary relocation of existing signing (including overhead signing) may be required and should be detailed in the plans.
4. Permanent traffic loop installation (such as advance loops, turn pockets, and stop bars, and ITS loops) and pavement marking installations (crosswalks, arrows, and so on) may require specific TTC plans.
5. What type of temporary marking is most appropriate for the installation, work duration, and the pavement surface? Will the final pavement surface have a "ghost stripe" potential?
6. Lane shifts onto existing shoulders:
    - Is the depth of the existing shoulder adequate to carry the extra traffic and are there rumble stripe that need to be removed?
    - Are there any existing catch basins or junction boxes located in the shoulder that cannot accept traffic loads over them?
    - What is the existing side slope rate? If steeper than 4H:1V, does it need mitigation? Are there existing roadside objects that, when the roadway is shifted, are now within the clear zone limits?
    - Shifting of more than one lane in a direction is only allowed with temporary pavement markings. Shifting lanes by using channelizing devices is not allowed due to the high probability that devices used to separate the traffic will be displaced.
    - Signal head alignment: When the lane is shifted approaching the intersection, is the signal head alignment within appropriate limits?
7. Roundabout construction at an existing intersection requires site-specific staging plans. Roundabouts create many unique construction challenges and each roundabout has very site-specific design features.

1010.05(3) Work Duration

The duration of work is a major factor in determining a strategy and the amount and types of devices to use in traffic control work zones. A project may have work operations with durations that meet several or all of the following conditions:

1010.05(3)(a) Long-Term Stationary Work Zone

This is work that occupies a location continuously for more than three days. Construction signs should be post-mounted and larger; more stable channelizing devices should be used for increased visibility. Temporary barriers, pavement markings, illumination, and other considerations may be required for long-term stationary work. Staged construction or temporary alignment/channelization plans are required with this type of work.

1010.05(3)(b) Intermediate-Term Stationary Work Zone

This is work that occupies a location for up to three days. Signs may still be post-mounted if in place continuously. Temporary pavement markings, in addition to channelization devices, may be required for lane shifts. Barrier and temporary illumination would normally not be used in this work zone duration.

1010.05(3)(c) Short-Term Stationary Work Zone

This is work that occupies a location for more than one hour within a single day. At these locations, all devices are placed and removed during the single period.

1010.05(3)(d) Short-Duration Work Zone

This is work that occupies a location for up to one hour. Because the work time is short, the impact to motorists is usually not significant. Simplified traffic control set-ups are allowed, to reduce worker exposure to traffic. The time it may take to set up a full complement of signs and devices could approach or exceed the amount of time required to perform the work. Short-duration work zones usually apply to maintenance work and are not used on construction projects. (See Work Zone Traffic Control Guidelines for more information.)

1010.05(3)(e) Mobile Work Zone

This is work that moves intermittently or continuously. These operations often involve frequent stops for activities such as sweeping, paint striping, litter cleanup, pothole patching, or utility operations, and they are similar to short-duration work zones. Truck-mounted attenuators, warning signs, flashing vehicle lights, flags, and channelizing devices are used, and they move along with the work. When the operation moves along the road at low speeds without stopping, the advance warning devices are often attached to mobile units and move with the operation.

Pavement milling and paving activities are similar to mobile operations in that they can progress along a roadway several miles in a day. These operations, however, are not considered mobile work zones, and work zone traffic control consistent with construction operations is required.

1010.05(4) TMP Strategies

With a completed impacts assessment, strategy development can begin. There are often several strategies to address a work zone impact, and engineering judgment will be needed in selecting the best option. Constructability, along with addressing safety and mobility, is the goal. Selecting

a strategy is often a compromise and involves many engineering and non-engineering factors. Work closely with bridge, construction, maintenance and traffic office personnel when selecting and developing strategies for the TMP and PS&E.

Do not assume that strategies chosen for past projects will adequately address the impacts for similar current projects. There may be similarities with the type of work, but each project is unique and is to be approached in that manner. Always look for other options or innovative approaches; many projects have unique features that can be turned to an advantage if carefully considered. Even a basic paving project on a rural two-lane highway may have opportunities for detours, shifting traffic, or other strategies.

For a list of work zone analysis tools, see:
http://ops.fhwa.dot.gov/wz/traffic_analysis/index.htm#tools

1010.05(5) Temporary Traffic Control (TTC) Strategies

1010.05(5)(a) Lane Closure

One or more traffic lanes are closed. A capacity analysis is necessary to determine the extent of congestion that may result. Night work or peak hour restrictions may be required. Use traffic safety drums and truck-mounted attenuators for freeway or expressway lane closures. Channelization devices should not encroach on the open freeway lanes; an additional lane should be closed if encroachment is necessary. Consider closing additional lanes to increase the lateral buffer space for worker safety.

1010.05(5)(b) Shoulder Closure

A shoulder closure is used for work areas off the traveled way. On high-volume freeways or expressways, they should not be allowed during peak traffic hours. Channelization devices should not encroach on the open lanes of high-speed roadways.

1010.05(5)(c) Alternating One-Lane Two-Way Traffic

This strategy involves using one lane for both directions of traffic. Flaggers are used to alternate the traffic movements.

If flaggers are used at an intersection, a flagger is required for each leg of the intersection. Only law enforcement personnel are allowed to flag from the center of an intersection. Close lanes and turn pockets so only one lane of traffic approaches a flagger station. When a signal is present, it shall be turned off or set to red flash mode when flagging.

Law enforcement personnel may be considered for some flagging operations and can be very effective where additional driver compliance is desired. The *Traffic Manual* contains information on the use of law enforcement personnel at work zones.

Flagger safety is a high emphasis area. Do not include alternating traffic with flaggers as a traffic control strategy until all other reasonable means of traffic control have been considered. Flagging stations need to be illuminated at night. Flaggers need escape routes in case of errant vehicles. Provide a method of alerting them to vehicles approaching from behind. Two-way radios or cellular phones are required to allow flaggers to communicate with one another. The flagger's location, escape route, protection, signing, and any other safety-related issues all need to be incorporated into the traffic control plan for the flagging operation. Flaggers are not to be

used on freeways or expressways. Using flaggers solely to instruct motorists to proceed slowly is an unacceptable practice.

Removing flaggers from the roadway during alternating traffic operations can be done with portable temporary traffic control signals or automated flagging assistance devices (AFAD). Portable signals work best when the length between signals will be 1,500 feet maximum and no accesses lie between the temporary signals. Each AFAD unit will need a flagger operating the device from a safe location off the roadway. A traffic control plan should show the advance signing and the AFAD or signal locations. Temporary stop bars, and lighting at the stop bars is required for signal use. For assistance on using these devices, contact the region Traffic Office.

Refer to WAC 296-155-305 for flagging requirements.

1010.05(5)(d) Temporary Alignment and Channelization

Temporary alignments and/or channelization may be an option for long-term work zones or staged traffic control. The following are guiding principles for the design of temporary alignment and channelization plans:

- Use site-specific base data to develop site-specific traffic control plans.
- Use permanent geometric design criteria.
- Provide beginning and ending station ties and curve data.
- Include lane and shoulder widths.
- Provide temporary roadway sections.
- To avoid confusion, do not show existing conflicting or unnecessary details on the plan.
- Do not use straight line tapers through curves; use circular alignment.
- Be aware of existing crown points, lane/shoulder cross slope breaks, and super-elevation transitions that may affect a driver's ability to maintain control of a vehicle.
- If the project has multiple stages, from one stage to the next, show newly constructed features as existing elements. For example, if an edge line is removed in one stage, the following stage would show the change by indicating where the new edge line is located.
- Consider the time needed for removal of existing markings and placement of the new markings and possibly placement of barriers and attenuators. In urban areas where work hours for lane closures are limited, special consideration may be necessary to allow time to implement the plan, or an interim stage may be necessary.
- Use shoulder closure signing and channelizing devices to close a shoulder prior to a temporary impact attenuator and run of temporary concrete barrier.
- Existing signing may need to be covered or revised, and additional construction warning signs may be needed for the new alignment.
- Temporary pavement marking types and colors should be specified. Long-duration temporary markings should be installed per the Standard Plans for permanent markings.
- For better guidance through shifting or taper areas, consider solid lane lines. Return to broken lane lines between shift areas.

- Provide a list of the approved temporary impact attenuators that may be used for the plan if applicable.
- The plans must provide all the layout information for all the temporary features just as a permanent pavement marking plan would.

1010.05(5)(d)(1) Staged Construction

Staged construction entails combining multiple work areas into a logical order to provide large protected work areas for long durations, which maximizes work operations and minimizes daily impacts to traffic. Temporary alignment and channelization plans must be designed to place traffic in these semi-permanent locations. Minimum geometric design criteria are to be used when developing these plans. Design strategies such as overbuilding for future stages or the use of temporary structures are often part of staged construction on significant impact projects or mega projects. Develop detailed capacity analysis and traffic modeling for each stage.

1010.05(5)(d)(2) Lane Shift/Reduced Lane Width

Traffic lanes may be shifted and/or width-reduced in order to accommodate a long-duration work area when it is not practicable, for capacity reasons, to reduce the number of available lanes. Shifting more than one lane of traffic requires the removal of conflicting pavement markings and the installation of temporary markings; the use of channelization devices to delineate multiple lanes of traffic is not allowed. Use advanced warning signs to show the changed alignment when the lateral shifting distance is greater than one-half of a lane width, and consider the use of solid lane lines through the shift areas.

Utilizing the existing shoulder may be necessary to accommodate the shifting movement. First, determine the structural capacity of the shoulder to ensure its ability to carry the proposed traffic. Remove and inlay existing shoulder rumble strips prior to routing traffic onto the shoulder.

1010.05(5)(d)(3) Traffic Split or Island Work Zone

This strategy separates lanes of traffic traveling in one direction around a work area. On higher-speed roadways, temporary barriers are provided to prevent errant vehicles from entering the work area. Some drivers have difficulty understanding "lane split" configurations, which sometimes results in poor driving decisions such as unnecessary or late lane changes. Braking and erratic lane changes decrease the traffic capacity through the work zone, which results in an unstable traffic flow approaching the lane split. Evaluate other strategies, such as overbuilding, to keep traffic on one side of the work area to avoid a traffic split if possible.

Consider the following guidance for traffic split operations:

- Define the work operation and develop the traffic control strategy around the specific operation.

- Limit the duration the traffic split can be in place. Consider incentives and disincentives to encourage the contractor to be as efficient as possible. A higher level of traffic impacts may be acceptable if offset with fewer impacted days.
- Advance warning signs advising drivers of the approaching roadway condition are required. Consider the use of Portable Changeable Message Signs (PCMS), portable Highway Advisory Radio (HAR), and other dynamic devices. Overhead signing and in-lane pavement markings also may be necessary to give additional driver notice of the traffic split.
- Consider how the operation will impact truck traffic. If the truck volumes are high, additional consideration may be prudent to control in which lane the trucks drive. If the trucks are controlled, it eliminates much of the potential for truck/car conflicts and sorts out undesirable truck lane changes through the work zone. For questions concerning truck operations, contact the HQ Freight Systems Division.
- To discourage lane changing, consider the use of solid lane line markings to delineate traffic approaching the split or island. Refer to the MUTCD for additional details.
- Consider the use of STAY IN LANE (black on white) signs, or set up a "no pass" zone approaching the lane split and coordinate with the Washington State Patrol (WSP).
- Supplement the existing roadway lighting with additional temporary lighting to improve the visibility of the island work area (see exhibit in Chapter 1040).
- Coordinate with the region Traffic Office for signing and pavement marking details when designing island work zones.

1010.05(5)(d)(4) Temporary Bypass

This strategy involves total closure of one or both directions of travel on the roadway. Traffic is routed to a temporary bypass usually constructed within the highway right of way. An example of this is the replacement of an existing bridge by building an adjacent temporary structure and shifting traffic onto the temporary structure. A temporary channelization plan will show pavement markings, barrier and attenuators, sign and device placement.

1010.05(5)(d)(5) Median Crossover

This strategy involves placing all multilane highway traffic on one side of the median. Lanes are usually reduced in both directions and one direction is routed across the median. The design for elements of temporary crossovers needs to follow the same guidance as permanent design for alignment, barriers, delineation, and illumination.

- Design crossovers for operating speeds not less than 10 mph below the posted speed limit unless unusual site conditions require a lower design speed.
- Median paving may be required to create crossover locations (consider drainage for the added pavement).

- Use temporary barrier to separate the two directions of traffic normally separated by a median barrier,
- Temporary illumination at the crossover locations (see exhibit in Chapter 1040)
- Straight line crossover tapers work best for highways with narrow paved medians.
- Temporary pavement markings, removal of conflicting existing markings, and construction signs are also required.
- A good array of channelizing devices and properly placed pavement markings is essential in providing clear, positive guidance to drivers.
- Provide a clear roadside recovery area adjacent to the crossover. Consider how the roadway safety hardware (guardrail, crash cushions, and so on) may be impacted by the traffic using the crossover if the traffic is going against the normal traffic flow direction. Avoid or mitigate possible snagging potential. Avoid placing crossover detours near structures.

1010.05(5)(e) Total Closures and Detours

Total closures may be for the project duration or for a critical work operation that has major constructability or safety issues. The main requirement for total closures is the availability of a detour route and if the route can accommodate the increased traffic volumes and trucks turning movements. Local roads may have lower geometric criteria than state facilities. Placing additional and new types of traffic on a local road may create new safety concerns, especially when drivers are accustomed to the geometrics associated with state highways. Pavement integrity and rehabilitation may need to be addressed when traffic is detoured to specific local roadways.

For the traveling public, closing the road for a short time might be less of an inconvenience than driving through a work zone for an extended period of time (see the Traffic Manual and RCW 47.48). Advance notification of the closure is required, and a signed detour route may be required.

Consider the following road closure issues:

- Communication with all stakeholders, including road users, adjoining property owners, local agencies, transit agencies, the freight industry, emergency services, schools, and others, is required when considering a total closure strategy. This helps determine the level of support for a closure and development of an acceptable closure. Include Rail, Freight, and Ports; Commercial Vehicle Services; and Public Transportation Divisions to help coordinate.
- Analyze a closure strategy and compare it to other strategies, such as staged work zones, to determine which is overall more beneficial. This information helps stakeholders understand the impacts if a closure is not selected.
- A closure decision (other than short-term, minor-impact closures) will require stakeholder acceptance and management approval once impacts and benefits have been analyzed.

- Closures that reopen to a new, completed roadway or other noticeable improvements are generally more accepted by the public.
- Route-to-route connections and other strategic access points may have to be maintained or a reasonable alternative provided.
- Material selection, production rates, and work operation efficiencies have a direct tie to the feasibility of the closure strategy. A strong emphasis has been placed on this area and several successful strategies have been implemented, such as weekend-long closures or extended-duration single-shift closures. These strategies use specific materials such as quick-curing concrete, accelerated work schedules, prefabricated structure components, on-site mix plants, and so on, and are based on actual production rates. The WSDOT Materials Laboratory and the HQ Construction Office are good resources for more information on constructability as a component of an effective work zone strategy.
- Interstate or interstate ramp closures (including interstate closures with interchange ramps as detours) lasting more than 7 days require FHWA 60-day advance notice. (See the Stewardship and Oversight Agreement for closure notification requirements.)
- Short-duration closures of ramps or intersecting streets during off-peak hours do not require extensive approval if advance notice is provided and reasonable alternate routes are available.
- Detailed, project-specific traffic control plans, traffic operation plans, and public information plans are required.
- Depending on the duration of the closure/detour and the anticipated amount and type of traffic that will use the route, consider upgrades to the route such as signal timing, intersection turning radius for large vehicle, structural pavement enhancements, or shoulder widening.
- An approved detour agreement with the appropriate local agency is required for detour routes using local roadways and must be completed prior to project advertisement.
- Document road closure decisions and agreements in the Project File.

1010.05(5)(f) Intermittent Closure

This involves stopping all traffic for a short time to allow the work to proceed. Traffic volumes will determine the allowed duration of the closures. Typically, the closure would be limited to a ten-minute maximum and would occur in the lowest traffic volume hours. Equipment crossing and material delivery are where this type of closure may work well. Traffic is reduced to a single lane on a multilane highway, and a flagger or law enforcement is used to stop traffic.

1010.05(5)(g) Rolling Slowdown

Rolling slowdowns are commonly practiced by the Washington State Patrol (WSP) for emergency closures. They are a legitimate form of traffic control for contractors or utility and highway maintenance crews for very specific short-duration closures (to move large equipment across the highway, to pull power lines across the roadway, to switch traffic onto a new alignment, and so on). They are not to be used for routine work that can be addressed by lane closures or other formal traffic control strategies. Traffic control vehicles, during off-peak hours, form a moving blockade, which reduces traffic speeds and creates a large gap (or clear area) in

traffic, allowing very short-term work to be accomplished without completely stopping the traffic.

Consider other forms of traffic control as the primary choice before the rolling slowdown. A project-specific traffic control plan (TCP) must be developed for this operation. The TCP or contact provisions should list the work operations in which a rolling slowdown is allowed. The gap required for the work and the location where the rolling slowdown begins needs to be addressed on the TCP. Use of the WSP is encouraged whenever possible. Refer to the Standard Specifications and Work Zone Traffic Control Guidelines for additional information on rolling slowdown operations.

1010.05(5)(h) Pedestrian and Bike Detour Route

When existing pedestrian access routes and bike routes are disrupted due to construction activities, address detour routes with a traffic control plan. The plan must show enough detail and be specific enough to address the conflicts and ensure the temporary route is reasonably safe and adequate to meet the needs of the user. Also, consider the impacts to transit stops for pedestrians: Will the bus stops be able to remain in use during construction or will adjustments be necessary? (See Chapter 1510 for pedestrian work zone design requirements.)

1010.05(5)(i) Alternative Project Delivery

To reduce construction times and minimize impacts to the traveling public, consider alternative delivery techniques to accomplish this. For more information, see:
http://www.wsdot.wa.gov/projects/delivery/alternative/

1010.05(5)(j) Innovative Design/Construction Methods

- Overbuild beyond normal project needs to maintain additional traffic or facilitate staged construction.
- Replace bridges using new alignments so they can be built with minimal impacts.
- Bring adjacent lifts of hot mix asphalt (HMA) to match the latest lifts (lag up), and require a tapered wedge joint to eliminate drop-off and abrupt lane edges to improve motorist safety.
- Require permanent pavement markings at intervals during multi-season projects to limit the duration temporary markings are needed and to avoid temporary marking issues during winter shut-down.

1010.05(6) Transportation Operations (TO) Strategies

1010.05(6)(a) Demand Management

- Provide transit service improvements and possible incentives to help reduce demand.
- For long-term freeway projects, consider ramp metering.
- Provide a shuttle service for pedestrians and bicyclists.
- Provide local road improvements (signals modifications, widening, and so on) to improve capacity for use as alternate routes.
- Provide traffic screens to reduce driver distraction.

1010.05(6)(b) Corridor/Network Management

- Provide a temporary express lane with no access through the project.
- Consider signal timing or coordination modifications.
- Provide emergency pullouts for disabled vehicles on projects with long stretches of narrow shoulders and no other access points.
- Use heavy-vehicle restrictions and provide alternate routes or lane use restrictions.

1010.05(6)(c) Work Zone Safety Management

- Provide temporary access road approaches for work zone access.
- Use positive protective devices (barrier) for long-term work zones to improve the environment for workers and motorists.
- Install intrusion alarms or vehicle arresting devices.
- Use speed limit reductions when temporary conditions create a need for motorist slow-downs. Refer to the *Traffic Manual* for additional information, guidance and approval requirements for speed limit reductions in work zones.

1010.05(6)(d) Traffic/Incident Management and Enforcement

- Provide law enforcement patrols to reduce speeding and aggressive drivers.
- Provide incident response patrols during construction to reduce delays due to collisions in the work zone.
- Include work zone ITS elements in the project or coordinate with TMC to use existing equipment.
- Provide a dedicated tow service to clear incidents.

1010.05(7) Public Information (PI) Strategies

1010.05(7)(a) Public Awareness

One PI strategy is a public awareness campaign using the media, project websites, public meetings, e-mail updates, and mailed brochures. This gives regular road users advance notice of impacts they can expect and time to plan for alternate routes or other options to avoid project impacts. Involve the region or HQ Communications Office in developing and implementing these strategies. Coordinate transit travel information and restrictions with the Public Transportation Division. http://wwwi.wsdot.wa.gov/PubTran/

Coordinate freight travel information and restrictions with the Rail, Freight, and Ports Division.

http://www.wsdot.wa.gov/freight/

http://www.wsdot.wa.gov/Freight/Trucking/default

1010.05(7)(b) Driver Information

In addition to work zone signs, provide driver information using highway advisory radio (HAR) and changeable message signs (existing or portable). Provide additional work zone ITS features that could include traffic cameras or queue detection along with changeable message signs to

provide drivers with real time information on delays and traffic incidents. Involve the region TMC in the development and implementation of these strategies. Additional information on work zone ITS can be found on the Work Zone Safety web page:
www.wsdot.wa.gov/safety/workzones/

The Freight Alert system should be used to communicate information with freight industry on work zones. Each region has the capability to send alerts with this system.

http://www.wsdot.wa.gov/freight/

Work zone strategy development is a fluid process and may be ongoing as project information and design features are developed during the design process. There may be many factors involved with strategy development, and it is necessary to be well organized to make sure all the relative factors are identified and evaluated.

1010.05(7)(c) Pedestrian and Bicycle Information

Include pedestrian and bicycle access information and alternate routes in the public awareness plans. Pedestrian and bicyclist information signing, including alternate route maps specifically for these road users, could be considered.

1010.06 Capacity Analysis

Work zone congestion and delay is a significant issue for many highway projects. At high-volume locations with existing capacity problems, even shoulder closures will increase congestion.

All work zone traffic restrictions need to be analyzed to determine the level of impacts. Short-term lane closures may only require work hour restrictions to address delays; long-term temporary channelization, realignments, lane shifts, and more will require a detailed capacity analysis to determine the level of impact. Demand management and public information strategies may be required to address delays. Traffic capacity mitigation measures are important since many projects cannot effectively design out all the work zone impacts. Include a Work Zone & Traffic Analysis in the TMP.

Work zone mobility impacts can have the following effects:

- **Crashes:** Most work zone crashes are congestion-related, usually in the form of rear-end collisions due to traffic queues. Traffic queues beyond the advance warning signs increase the risk of crashes.
- **Driver Frustration:** Drivers expect to travel to their destinations in a timely manner. If delays occur, driver frustration can lead to aggressive or inappropriate driving actions.
- **Constructability:** Constructing a project efficiently relies on the ability to pursue work operations while maintaining traffic flow. Delays in material delivery, work hour restrictions, and constant installation and removal of traffic control devices all detract from constructability.
- **Local Road Impacts:** Projects with capacity deficiencies can sometimes cause traffic to divert to local roadways, which may impact the surrounding local roadway system and community.
- **Public Credibility:** Work zone congestion and delay can create poor credibility for WSDOT with drivers and the surrounding community in general.

- **Restricted Access:** Severe congestion can effectively gridlock a road system, preventing access to important route connections, businesses, schools, hospitals, and so on.
- **User Cost Impacts:** Traffic delays have an economic impact on road users and the surrounding community. Calculated user costs are part of a work zone capacity analysis and may be used to determine liquidated damages specifications.

WSDOT has a responsibility to maintain traffic mobility through and around its projects. The goal is to keep a project's work zone traffic capacity compatible with existing traffic demands. Maintaining the optimum carrying capacity of an existing facility during construction may not be possible, but an effort must be made to maintain existing traffic mobility through and/or around the work zone.

Maintaining mobility does not rule out innovative strategies such as roadway closures. Planned closures can accelerate work operations, reducing the duration of impacts to road users. These types of traffic control strategies must include demand management and public information plans to notify road users and mitigate and manage the impacts as much as possible.

A capacity analysis helps determine whether a work zone strategy is feasible. Mitigation measures that provide the right combination of good public information, advance signing and notification, alternate routes, detours, and work hour restrictions, as well as innovations such as strategic closures, accelerated construction schedules, or parallel roadway system capacity improvements, can be very effective in reducing mobility impacts.

Some of the impact issues and mitigating measures commonly addressed by traffic analyses include:

- Work hour time restrictions
- Hourly liquidated damage assessment
- Use of staged construction
- Working day assessment
- Public information campaign
- User cost assessment
- Local roadway impacts
- Special event and holiday time restrictions
- Closure and detour options
- Mitigation cost justification
- Level of service
- Queue lengths
- Delay time
- Running speed
- Coordination with adjoining projects (internal and local agency)

Many projects will have several potential work zone strategies, while other projects may only have one obvious work zone strategy. It is possible that a significant mobility impact strategy may be the only option. TMP strategies still need to be considered. An analysis will help show the results of these mitigating measures.

There is no absolute answer for how much congestion and delay are acceptable on a project; it may ultimately become a management decision.

Reductions in traffic capacity are to be mitigated and managed as part of the TMP. The traffic analysis process helps shape the TMP as the work zone strategies are evaluated and refined into traffic control plans and specifications. Maintain analysis documents in the Project File.

1010.06(1) Collecting Traffic Volume Data

Current volume data in the project vicinity is required for accurate traffic analysis results. Seasonal adjustment factors may be needed depending on when the data was collected and when the proposed traffic restrictions may be in place. Assess existing data as early as possible to determine whether additional data collection may be required. The region Traffic Office and the HQ Transportation Data & GIS Office can assist with collecting traffic volume data. Coordination with local agencies may be needed to obtain data on affected local roads.

1010.06(2) Short-Term Lane Closure Work Zone Capacity

For short-term lane closures on multilane highways or alternating one-way traffic on two-lane highways, see Exhibit 1010-1. It provides information for a quick analysis when compared to current hourly volumes on the highway. The basic traffic analysis programs QUEWZ 98, along with hourly volume input, the number of lanes to be closed, the hours of closure, and other default information, will output queue length, delay time, user costs, and running speed.

Exhibit 1010-1 General Lane Closure Work Zone Capacity

Roadway Type	Work Zone Capacity
Multilane Freeways/Highways	1300 VPHPL*
Multilane Urban/Suburban	600 VPHPL*
Two-Lane Rural Highway	400 VPHPL/ 800 VPH total*
*These are average capacity values. The actual values would be dependent on several factors, which include the existing number of lanes, number of lanes closed, traffic speed, truck percentage, interchanges/intersections, type of work, type of traffic control, and seasonal factors (among others). For further information, consult the *Highway Capacity Manual*.	

1010.06(3) Long-Term Work Zone Capacity

For complex strategies that change traffic patterns, a more detailed analysis is required using advanced traffic modeling software. These strategies could include reducing lane and shoulder widths for extended lengths, reducing the number of lanes for extended durations, moving all lanes of traffic onto a temporary alignment, changing access locations to and from the highway, or closures with detours (including public information and traffic operation plans with anticipated reduction in demand). Work with the region Traffic Office for assistance with this level of analysis.

The following resources are also available to assist with the actual analysis and mitigation strategy development upon request:

- HQ Transportation Data & GIS Office

- HQ Traffic Offices
- Region Work Zone Specialist
- Region Public Information Office

Training is also available to obtain further knowledge and expertise in traffic analysis (see 1010.12).

1010.07 Work Zone Design

Part 6 of the MUTCD mostly addresses short-duration temporary traffic control standards. Some long-duration work zones may require temporary alignments and channelization, including barrier and attenuator use, temporary illumination and signals, and temporary pedestrian and bicycle routes. Refer to the *Design Manual*'s chapters for permanent features for design guidance.

1010.07(1) Lane Widths

Maintain existing lane widths during work zone operations whenever practicable.

For projects that require lane shifts or narrowed lanes due to work area limits and staging, consider the following before determining the work zone lane configurations to be implemented:

- Overall roadway width available
- Posted speed limit
- Traffic volumes through the project limits
- Number of lanes
- Existing lane and shoulder widths
- Crown points and shoulder slope breaks
- Treat lane lines and construction joints to provide a smooth flow
- Length and duration of lane width reduction (if in place)
- Roadway geometry (cross slope, vertical and horizontal curves)
- Vertical clearances
- Transit and freight vehicles, including over-sized vehicles

Work zone geometric transitions should be minimized or avoided if possible. When necessary, such transitions should be made as smoothly as the space available allows. Maintain approach lane width, if possible, throughout the connection. Design lane width reductions prior to any lane shifts within the transition area. Do not reduce curve radii and lane widths simultaneously.

When determining lane widths, the objective is to use lane geometrics that will be clear to the driver and keep the vehicle in the intended lane. In order to maintain the minimum lane widths, temporary widening may be needed.

1010.07(2) Buffer Space

Buffer spaces separate road users from the work space or other areas off limits to travel. Buffer spaces also might provide some recovery space for an errant vehicle.

- A lateral buffer provides space between the vehicles and adjacent work space, traffic control device, or a condition such as an abrupt lane edge or drop-off. As a minimum, a 2-foot lateral buffer space is used. Positive Protective Devices may be required if workers are within one lane width of traffic. When temporary barriers are used, place a temporary edge line 2-foot laterally from the barrier.
- When feasible, a longitudinal buffer space is used immediately downstream of a closed or shifted traffic lane or shoulder. This space provides a recovery area for errant vehicles as they approach the work space.

Devices used to separate the driver from the work space should not encroach into adjacent lanes. If encroachment is necessary, it is recommended to close the adjacent lane to maintain the lateral buffer space.

In order to achieve the minimum lateral buffer, there may be instances where pavement widening or a revision to a stage may be necessary. In the case of short-term lane closure operations, the adjacent lane may need to be closed or traffic may need to be temporarily shifted onto a shoulder to maintain a lateral buffer space. During the design of the traffic control plan, the lateral buffer needs to be identified on the plan to ensure additional width is available; use temporary roadway cross sections to show the space in relation to the traffic and work area.

1010.07(3) Work Zone Clear Zone

The contractor's operations present opportunities for errant vehicles to impact the clear area adjacent to the traveled way. A work zone clear zone (WZCZ) is established for each project to ensure the contractor's operations provide an appropriate clear area. The WZCZ addresses items such as storage of the contractor's equipment and employee's private vehicles and storage or stockpiling of project materials. The WZCZ applies during working and nonworking hours and applies only to roadside objects introduced by the contractor's operations. It is not intended to resolve preexisting deficiencies in the Design Clear Zone or clear zone values established at the completion of the project. Those work operations or objects that are actively in progress and delineated by approved traffic control measures are not subject to the WZCZ requirements.

Minimum WZCZ values are presented in Exhibit 1010-2. WZCZ values may be less than Design Clear Zone values due to the temporary nature of the construction and limitations on horizontal clearance. To establish an appropriate project-specific WZCZ, it may be necessary to exceed the minimum values. The following conditions warrant closer scrutiny of the WZCZ values, with consideration of a wider clear zone:

- Outside of horizontal curves or other locations where the alignment presents an increased potential for vehicles to leave the traveled way.
- The lower portion of long downgrades or other locations where gradient presents an increased potential for vehicles to exceed the posted speed.

- Steep fill slopes and high traffic volumes. (Although it is not presented as absolute guidance, the Design Clear Zone exhibit in Chapter 1600 may be used as a tool to assess increases in WZCZ values.)

Exhibit 1010-2 Minimum Work Zone Clear Zone Distance

Posted Speed	Distance From Traveled Way (ft)
35 mph or less	10
40 mph	15
45 to 55 mph	20
60 mph or greater	30

1010.07(4) Abrupt Lane Edges and Drop-offs

Minimize, mitigate, or eliminate abrupt lane edges and drop-offs whenever practicable. When unavoidable, traffic control plans should provide a protection method. Consider temporary barriers for long duration drop off protection and contract provisions limiting the duration of edges from daily paving operations. Abrupt edges up to 0.20 foot may remain exposed with appropriate warning signs alerting motorists of the condition. Edges or drop-offs more than 0.20 foot are not allowed in the traveled way or auxiliary lane.

The best long duration protection method for drop-offs more than 0.20 feet is Temporary Barrier. Place barrier on the traffic side of the drop-off with 2 feet between the drop-off and the back of the barrier and a provide a new edge line on the traffic side of the barrier with a 2-foot lateral buffer space minimum. The space behind the barrier can be reduced if the barrier is anchored. Barrier end attenuators may be required.

Open trenches within the traveled way or auxiliary lane shall have a steel-plate cover placed and anchored over them. A wedge of suitable material, if required, shall be placed for a smooth transition between the pavement and the steel plate. Warning signs shall be used to alert motorists of the presence of the steel plates.

Abrupt lane edges, and drop-offs and steel plates require additional warning and considerations for motorcyclists, bicyclists, and pedestrians, including pedestrians with disabilities. Adequate signing to warn the motorcycle rider, bicyclists and pedestrians, including pedestrians with disabilities of these conditions is required. (See RCW 47.36.200 and WAC 468-95-305.) See *Design Manual* Chapter 1510 for work zone pedestrian accommodation guidance.

See *Standard Specifications* section 1-07.23(1) for the contract requirements for drop off protection and address project specific protection if necessary.

1010.07(5) Vertical Clearance

In accordance with Chapter 720, the minimum vertical clearance over new highways is 16.5 feet. Anything less than the minimum must follow the reduced clearance criteria discussed in Chapter 720 and be included in the temporary traffic control plans. Maintain legal height on temporary falsework for bridge construction projects. Anything less than this must consider over-height vehicle impacts and possible additional signing needs and coordination with permit offices. Widening of existing structures can prove challenging when the existing height is at or less than

legal height, so extra care is required in the consideration of over-height vehicles when temporary falsework is necessary. Coordination with the HQ Bridge and Structures Office is essential to ensure traffic needs have been accommodated. Vertical clearance requirements associated with local road networks may be different than what is shown in Chapter 720. Coordinate with the local agency.

1010.07(6) Reduced Speeds in Work Zones

Drivers tend to reduce their speed only if they perceive a need to do so. Reduced speed limits should only be used to address an altered geometry when not able to meet design standards for the existing speed, when the roadway will be narrowed with minimal shy distance to barriers, when roadway conditions warrant a reduction like BST operations, and when there will be workers on foot within a lane width of high-speed high-volume traffic without positive protection devices in place. Speed reductions are not applied as a means for selecting lower work zone design criteria (tapers, temporary alignment, device spacing, and so on).

Speed limit reductions are categorized as follows:

- Continuous Regulatory Speed Limit Reduction: A speed reduction in place 24 hours a day for the duration of the project, stage, or roadway condition.
- Variable Regulatory Speed Limit Reduction: A speed reduction in place only during active work hours (Class B construction signs may be used). This is a good option when positive protection devices are not used.
- Advisory Speed Reduction: In combination with a warning sign, an advisory speed plaque may be used to indicate a recommended safe speed through a work zone or work zone condition. Refer to the MUTCD for additional guidance.

Refer to the *Traffic Manual* for additional information, guidance and approval requirements for speed limit reductions in work zones. Include approval documents in the Project File.

1010.07(7) Accommodation for Pedestrians and Bicyclists

Many public highways and streets accommodate pedestrians and bicyclists, predominately in urban areas. During construction, access must be maintained through or around the work zones. When existing pedestrian routes that are accessible to pedestrians with disabilities are closed, the alternate routes must be designed and constructed to meet or exceed the existing level of accessibility. Temporary pedestrian facilities within the work zone must meet accessibility criteria to the maximum extent feasible. (See Chapter 1510 for pedestrian circulation path and pedestrian access route accessibility criteria.) Covered walkways are to be provided where there is a potential for falling objects.

In work areas where the speeds are low (25 mph), or the ADT is 2,000 or less, bicyclists can use the same route as motorized vehicles. For work zones on higher-speed facilities, bicyclists will need a minimum 4-foot shoulder or detour route to provide passage through or around a work zone. Bicyclists may be required to dismount and walk their bikes through a work zone on the route provided for pedestrians.

It may be possible to make other provisions to transport pedestrians and bicyclists through a work zone or with a walking escort around the active work area. Roadway surfaces are an important consideration for pedestrian and bicycle use. Unacceptable conditions such as loose

gravel, uneven surfaces, milled pavement, and asphalt tack coats endanger the bicyclist and restrict access to pedestrians with disabilities.

Information can be gathered on bike issues by contacting local bike clubs. Coordination with local bike clubs goes a long way to ensuring their members are notified of work zone impacts, and it helps maintain good public relations. (See Chapter 1520 for more bicycle design requirements and Chapter 1510 and MUTCD Chapter 6D for pedestrian work zone design requirements.)

1010.07(8) Motorcycles

The same road surfaces that are a concern for bicyclists are also a concern for motorcyclists. Stability at high speed is a far greater concern for motorcycles than cars on grooved pavement, milled asphalt, and transitions from existing pavement to milled surfaces. Contractors must provide adequate warning signs for these conditions to alert the motorcycle rider. For regulations on providing warnings to motorcyclists, see RCW 47.26.200.

1010.07(9) Oversized Vehicles

The region Maintenance offices and the HQ Commercial Vehicle Services Office issue permits to allow vehicles that exceed the legal width, height, or weight limits to use certain routes. If a proposed work zone will reduce roadway width or vertical clearance, or have weight restrictions, adequate warning signs and notification to the HQ Commercial Vehicle Services Office and the appropriate region Maintenance Office is required as a minimum. When the total width of a roadway is to be reduced to less than 16 feet for more than three days, communication with these offices and any other stakeholders is required; include documentation in the Project File. The contract documents shall include provisions requiring the contractor to provide a 30-calendar-day notice prior to placing the restriction.

In the permit notification, identify the type of restriction (height, weight, or width) and specify the maximum size that can be accommodated. On some projects, it may be necessary to designate a detour route for oversized vehicles. An important safety issue associated with oversized loads is that they can sometimes be unexpected in work zones, even though warning and restriction or prohibition signs may be in place. Some oversized loads can overhang the temporary barrier or channelization devices and endanger workers. Consider the potential risk to those within the work zone. Routes with high volumes of oversized loads or routes that are already strategic oversized load routes may not be able to rely only on warning or prohibition signs. Protective features or active early warning devices may be needed. If the risk is so great that one oversized load could potentially cause significant damage or injury to workers, failsafe protection measures may be needed to protect structures and workers. The structure design, staging, and falsework openings may need to be reconsidered to safely accommodate oversized loads.

1010.08 Temporary Traffic Control Devices

FHWA regulations require that devices such as portable sign stands, barricades, traffic barriers, barrier terminals, crash cushions, and work zone hardware be compliant with the National Cooperative Highway Research Program (NCHRP) Report 350 or the Manual for Assessing Safety Hardware (MASH) crash test requirements.

1010.08(1) Channelizing Devices

Channelizing devices are used to alert and guide road users through the work zone. They are used to channelize traffic away from the work space, pavement drop-offs, or opposing directions of traffic. Traffic Safety Drums are the preferred devices on freeways and expressways as they are highly visible and are less likely to be displaced by traffic wind. 28-inch cones are also used on WSDOT projects. They are a good choice for flagging operations. Tall channelization devices are 42-inch cone-type devices and should be used in place of tubular markers to separate opposing traffic. Tubular markers are not a recommended device unless they are being used to separate traffic on low-volume low-speed roadways. Longitudinal channelizing devices are interconnected devices that provide channelization with no gaps. These devices look like a temporary barrier, but are not approved as a positive protective device. Barricades are a channelization device mostly used to supplement other channelization devices in traffic control operations involving road, ramp, or sidewalk closures.

1010.08(2) Construction Signs

Portable and temporary signs (Class B Construction Signs) are generally used in short-term work zones. They are set up and removed daily or frequently repositioned as the work moves along the highway. These signs are mounted on crashworthy, collapsible sign supports. The minimum mount height is 1 foot above the roadway, but there are temporary sign supports that will provide 5- to 7-foot mounting heights. This may be useful when temporary signs are mounted behind channelizing device or in urban areas with roadside parking that may obstruct sign visibility and multilane facilities. Temporary signs need to be placed such that they do not obstruct pedestrian facilities. Warning signs in place longer than three days at one location must be post-mounted.

Fixed signing (Class A Construction Signs) are the signs mounted on conventional sign supports along or over the roadway. This signing is used for long-term stationary work zones. Details for their design are in Chapter 1020 and the *Standard Plans*. Sign messages, color, configuration, and usage are shown in the MUTCD and the *Sign Fabrication Manual*. Existing signs may need to be covered, removed, or modified during construction.

1010.08(3) Warning Lights

Warning lights are either flashing or steady burn and can be mounted on channelizing devices, barriers, and signs. Secure crashworthy mounting of warning lights is required.

- **Type A:** Low-intensity flashing warning light used on a sign or barricade to warn road users during nighttime hours that they are approaching a work zone.
- **Type B:** High-intensity flashing warning light used on a sign or barricade to warn road users during both daytime and nighttime hours.
- **Type C and Type D 360 degree:** Steady-burn warning lights designed to operate 24 hours a day to delineate the edge of the roadway.

1010.08(4) Arrow Board

The arrow board (Sequential Arrow Sign) displays either an arrow or a chevron pointing in the direction of the intended route of travel. Arrow board displays are required for lane closures on multilane roadways. When closing more than one lane, use an arrow board display for each lane

reduction. Place the arrow board at the beginning of the transition taper and out of the traveled way. The caution display (four corner lights) is only used for shoulder work. Arrow boards are not used on two-lane two-way roadways.

1010.08(5) Portable Changeable Message Signs (PCMS)

PCMS have electronic displays that can be modified and programmed with specific messages and may be used to supplement other warning signs. These signs are usually trailer mounted with solar power and batteries to energize the electronic displays. A two-second display of two messages is the recommended method to ensure motorists have time to read the sign's message twice. These devices are not crashworthy and should be removed when not in use, or placed behind barrier or guardrail. PCMS are best used to provide notice of unexpected situations like the potential for traffic delays or queuing and to provide a notice of future closures or restrictions. They should not be used in place of required signs or to provide redundant information.

1010.08(6) Portable Temporary Traffic Control Signals

These versatile trailer-mounted portable signals are battery powered, with the ability to be connected to AC power. They can operate on fixed timing or be traffic actuated. They are typically used on two-lane two-way highways to alternate traffic in a single lane for extended durations.

1010.08(7) Portable Highway Advisory Radio (HAR)

HAR can be used to broadcast AM radio messages about work zone traffic and travel-related information. The system may be a permanently located transmitter or a portable trailer-mounted system that can be moved from location to location as necessary. Contact the region Traffic Office for specific guidance and advice on the use of these systems.

1010.08(8) Automated Flagger Assistance Device (AFAD)

An AFAD is a flagging machine that is operated remotely by a flagger located off the roadway and away from traffic. This device could be used to enhance safety for flaggers on highways with reduced sight distance or limited escape routes. A traffic control plan is required for use of the AFAD. A flagger is required to operate each device.

Refer to the MUTCD for additional guidance on temporary traffic control zone devices.

1010.09 Positive Protection Devices

Channelizing devices will not provide adequate worker and road user protection in some work zones. Positive protective devices are required for the following conditions unless an engineering study determines otherwise:

- To separate opposing high-speed traffic normally separated by a median or existing median barrier.
- Where existing traffic barriers or bridge railings are to be removed.
- For drop-off protection during widening or excavations (see *Standard Specification* 1-07.23(1)).

- When temporary slopes change clear zone requirements.
- For bridge falsework protection.
- When equipment or materials must remain in the work zone clear zone.
- When newly constructed features in the clear zone will not have permanent protection until later in the project.
- Where temporary signs or light standards are not crashworthy.
- To separate workers from motorized traffic when work zone offers no means of escape for the worker, such as tunnels, bridges, and retaining walls, or for long-duration worker exposure within one lane-width of high-speed high-volume traffic.

1010.09(1) Temporary Barriers

Providing temporary barrier protection may become the key component of the work zone strategy. Barrier use usually requires long-term stationary work zones with pavement marking revisions, and will increase the traffic control costs of a project. The safety benefit versus the cost of using barrier requires careful consideration, and cost should not be the only or primary factor determining the use of barrier. (See Chapter 1610 for guidance on barriers.)

1010.09(1)(a) Temporary Concrete Barriers

These are the safety-shape barriers shown in the Standard Plans. Lateral displacement from impacts is usually in the range of 2 to 4 feet. (See Chapter 1610 for detailed information on deflection.) When any barrier displacement is unacceptable, these barriers are anchored to the roadway or bridge deck. Some deflection with anchored systems is still expected.) Anchoring systems are also shown in the Standard Plans.

1010.09(1)(b) Movable Barriers

Movable barriers are specially designed segmental barriers that can be moved laterally one lane width or more as a unit with specialized equipment. This allows strategies with frequent or daily relocation of a barrier. The ends of the barrier must be located out of the clear zone or fitted with an impact attenuator. Storage sites at both ends of the barrier will be needed for the barrier-moving machine.

1010.09(1)(c) Portable Steel Barriers

Portable steel barriers have a lightweight stackable design. They have options for gate-type openings and relocation without heavy equipment. Lateral displacement from impacts is in the range of 6 to 8 feet. Steel barriers can be anchored according to the manufacturer's specifications. Some deflection with anchored systems is still expected.

1010.09(2) Impact Attenuators

Within the Design Clear Zone, the approach ends of temporary barriers shall be fitted with impact attenuators. The information in Chapter 1620 provides all the needed impact attenuator performance information, but the actual work zone location may require careful consideration by the designer to ensure the correct application is used. Consider the dynamic nature of work operations where work zone ingress and egress, work area protection, worker protection, and traffic protection all factor into the final selection as well as the placement surface available.

Contract plans showing temporary impact attenuator placement need to include a list of the approved attenuators that a contractor may use for that installation.

1010.09(3) Transportable Attenuators

A transportable attenuator (TA) is a positive protection device that will provide protection for the work area only a short distance in front of the device. An impact attenuator device is attached to the rear of a large truck the weighs 15,000 lbs. total weight or more to minimize the roll-ahead distance when impacted by an errant vehicle. A TA should be used on all high-speed roadway operations.

1010.10 Other Traffic Control Devices or Features

1010.10(1) Delineation

Temporary pavement markings will be required when permanent markings are eliminated because of construction operations or when lane shifts or temporary alignments are needed for long-term work zone strategies. Temporary pavement markings can be made using paint, tape, or raised pavement markers. Short-duration temporary pavement markings are made with materials intended to last only until permanent markings can be installed on paving and BST projects, or for short durations between construction stages. Broken line patterns consist of a 4 foot line with a 36-foot gap. Temporary edge lines are usually not required on paving/BST projects and must be specified in the plans if desired. Long-duration temporary pavement markings are made with materials intended to last for staged construction on high-volume highways, for use between construction seasons, or for long-duration lane shifts. Existing contradictory pavement markings must be removed. These markings are installed in accordance with the Standard Plans for permanent markings. Long-duration markings need to be detailed in the contract plans for installation and material type. Removable tapes work well for broken lines and can be removed by hand, leaving no scar on the pavement surface. Complex projects will most likely require both long- and short-duration temporary markings.

Lateral clearance markers are used at the angle points of barriers where they encroach on or otherwise restrict the adjacent shoulder. Barrier delineation is necessary where the barrier is less than 4 feet from the edge of traveled way.

Guideposts may be considered to aid nighttime driving through temporary alignments or diversions. (See Chapter 1030 for delineation requirements.)

1010.10(2) Screening

Screening devices can be used to reduce motorists' distraction due to construction activities adjacent to the traveled way. Consider screening when a highway operates near capacity during most of the day. Screening should be positioned behind traffic barriers to prevent impacts by errant vehicles and should be anchored or braced to resist overturning when buffeted by wind. Commercially available screening or contractor-built screening can be used, provided the device meets crashworthy criteria if exposed to traffic and is approved by the Engineer prior to installation.

Glare screening may be required on concrete barriers separating two-way traffic to reduce headlight glare from oncoming traffic. Woven wire and vertical blade-type screens are commonly used in this installation. This screening also reduces the potential for motorist

confusion at nighttime by shielding construction equipment and the headlights of other vehicles on adjacent roadways. Make sure that motorists' sight distance is not impaired by these glare screens. Contact the HQ Design Office and refer to AASHTO's Roadside Design Guide for additional information on screening.

1010.10(3) Illumination

Illumination might be justified if construction activities take place on the roadway at night for an extended period of time. Illumination might also be justified for long-term construction projects at the following locations:

- Road closures with detours or diversions.
- Median crossovers on freeways.
- Complex or temporary alignment or channelization.
- Haul road crossings (if operational at night).
- Temporary traffic signals.
- Temporary ramp connections.
- Projects with lane shifts and restricted geometrics.
- Projects with existing illumination that needs to be removed as part of the construction process.

Illumination is required when:

- Traffic flow is split around or near an obstruction.
- Flaggers are necessary for nighttime construction activities (supplemental lighting of the flagger stations by use of portable light plants or other approved methods). Refer to *Standard Specification* 1-10.3(1)A.

For information on light levels and other electrical design requirements, see Chapter 1040.

1010.10(4) Signals

A permanent signal system can be modified for a temporary configuration such as temporary pole locations during intersection construction, span wire systems, and adjustment of signal heads and alternative detection systems to accommodate a construction stage (see Chapter 1330).

1010.10(5) Work Zone Intelligent Transportation Systems (ITS)

Intelligent Transportation Systems apply advanced technologies to optimize the safety and efficiency of the existing transportation network. Many permanent systems already exist throughout Washington State and provide the opportunity to greatly enhance construction projects that fall within the limits of the ITS network. Temporary portable ITS applications in work zones can be used to provide traffic monitoring and management, data collection, and traveler information.

ITS can provide real-time work zone information and associated traffic conditions such as queue detection for "slowed or stopped traffic ahead" before motorists see brake lights, or they can

advise of alternate routes, giving motorists options to avoid delays and warn drivers of haul vehicles entering or leaving a work area.

Work zone ITS technology is an emerging area that can provide the means to better monitor and manage traffic flow through and around work zones. Equipment used in work zones, such as portable camera systems, highway advisory radios, variable speed limits, ramp metering systems, and queue detection sensors, helps ensure a more efficient traffic flow with a positive impact on safety, mobility, access, and productivity.

Identify work zone ITS elements early in the strategy development process and include them in the preliminary estimate so they can be designed along with the other traffic control elements. For large mobility projects that have existing freeway cameras already in place, temporary ITS features (such as temporary poles and portable systems) may be necessary to ensure the network can be maintained during construction, especially if existing camera locations are in conflict with construction activities. In locations that do not have existing camera locations, but have significant construction projects planned, work zone ITS may be a good opportunity to bring ITS technology to the route.

Refer to Chapter 1050 and the work zone safety web page for additional ITS information and guidance.

1010.11 Traffic Control Plan Development and PS&E

WSDOT projects need to include plans and payment items for controlling traffic based on a strategy that is consistent with the project construction elements, even though there may be more than one workable strategy. A constructable and biddable method of temporary traffic control is the goal. The contractor has the option of adopting the contract plans or proposing an alternative method.

1010.11(1) Traffic Control Plans (TCPs)

"Typical" traffic control plans are generic in nature and are not intended to address all site conditions. They are intended for use at multiple work locations and roadways with little or no field modifications necessary. Typical plans may be all that are needed for basic paving projects. Some typical plans are located at: www.wsdot.wa.gov/design/standards/plansheet.htm

"Project-specific" traffic control plans are typical-type plans that have been modified to fit a specific project or roadway condition. Dimension lines for signs and device placement have the distances based on the project highway speed limit, and spacing charts have been removed; the lane and roadway configuration may also be modified to match the project conditions.

"Site-specific" traffic control plans are drawn for a specific location. Scaled base data drawn plans will be the most accurate as device placement and layout issues can be resolved by the designer. These types of plans should be used for temporary alignment and channelization for long-duration traffic control. Making a "project-specific" plan applicable for a site-specific location is another option, but the designer must ensure the device layout will match the site-specific location since it will not be a scaled plan.

The following plans, in addition to the TCP types above addressing the TTC strategies, may be included in the PS&E.

1010.11(1)(a) Construction Sign Plan

Show Class A Construction Signs that will remain in place for the duration of the project located by either station or milepost. Verify the locations to avoid conflicts with existing signing or other roadway features. These locations may still be subject to movement in the field to fit specific conditions. For simple projects these sign are often shown on the vicinity map sheet.

1010.11(1)(b) Construction Sign Specification Sheet

Provide a Class A Construction Sign Specifications sheet on complex or staged projects. Include location, post information, and notes for Standard Plans or other specific sign information and sign details.

1010.11(1)(c) Quantity Tabulation Sheets

Quantity Tabulation sheets are a good idea for barrier and attenuator items and temporary pavement markings on projects with large quantities of these items or for staged construction projects.

1010.11(1)(d) Traffic Control Plan Index

An Index sheet is a useful tool for projects that contain a large quantity of traffic control plans and multiple work operations at various locations throughout the project. The Index sheet provides the contractor a quick referencing tool indicating the applicable traffic control plan for the specific work operation.

1010.11(1)(e) Construction Sequence Plans

Sequence plans are placed early in the plan set and are intended to show the proposed construction stages and the work required for each stage. They should refer to the corresponding TCPs for the traffic control details of each stage.

1010.11(1)(f) Temporary Signal Plan

The temporary signal plan will follow conventions used to develop permanent signals (as described in Chapter 1330), but will be designed to accommodate temporary needs and work operations to ensure there will be no conflicts with construction operations. Ensure opposing left-turn clearances are maintained as described in Chapter 1310 if channelization has been temporarily revised, or adjust signal timing to accommodate. Some existing systems can be maintained using temporary span wires for signal heads and video, microwave actuation, or timed control.

1010.11(1)(g) Temporary Illumination Plan

Full lighting is normally provided through traffic control areas where power is available. The temporary illumination plan will follow conventions used to develop permanent illumination (as described in Chapter 1040), but will be designed to accommodate temporary needs and work operations to ensure there will be no conflicts with construction operations.

1010.11(2) Contract Specifications

Work hour restrictions for lane closure operations are to be specifically identified for each project where traffic impacts are expected and liquidated damages need to be applied to the

contract. Refer to the Plans Preparation Manual for additional information on writing traffic control specifications.

1010.11(3) Cost Estimating

Temporary traffic control devices and traffic control labor can be difficult to estimate. There is no way of knowing how many operations a contractor may implement at the same time. The best method is to follow the working day estimate schedule and the TCPs that will be used for each operation. Temporary signs and devices will be used on many plans, but the estimated quantity reflects the most used at any one time. To use the lump sum item to pay for all temporary traffic control, be certain how the contractor's work operations will progress and that the traffic control plans fully define the work zone expectations.

1010.12 Training and Resources

Temporary traffic control-related training is an important component in an effective work zone safety and mobility program. Federal regulations require that those involved in the development, design, implementation, operation, inspection, and enforcement be trained at a level consistent with their responsibilities.

1010.12(1) Training Courses

The following work zone related courses are available through the Talent Development office and the State Work Zone Training Specialist can assist with the availability and scheduling of classes:

- **Work Zone Traffic Control Plan Design Course:** This course, taught by the HQ Traffic Office, focuses on work zone safety and mobility through transportation management plan and temporary traffic control PS&E development.
- **Traffic Control Supervisor (TCS) Course:** The same course taught by the Evergreen Safety Council, NW Laborers Union, and ATSSA, for contractors is also taught by the HQ Traffic Office for WSDOT employees. Field personnel who have TCS related responsibilities or designers wanting basic temporary traffic control design and implementation training should attend this course. This course may be taken without the intention of becoming a certified TCS.
- **Flagger Certification Course:** This course is for employees who may have flagging duties or want to become a certified Traffic Control Supervisor. The safety offices can assist with class scheduling.

Traffic analysis, traffic engineering, pedestrian facilities design and other courses may also be available and apply to work zone safety and mobility.

The American Traffic Safety Services Association (ATSSA) offers free or low-cost training through an FHWA work zone safety grant.

1010.12(2) Resources

The responsibility of the designer to fully address all work zone traffic control impacts is very important because the level of traffic safety and mobility will be directly affected by the effectiveness of the transportation management plan (TMP). The following resources are available to assist the designer with various aspects of the work zone design effort.

1010.12(2)(a) Region Work Zone Resources

Each region has individuals and offices with various resources that provide work zone guidance and direction beyond what may be available at the project Design Office level. They include:

- Region Traffic Office
- Region Work Zone Specialist
- Region Construction and Design Offices

1010.12(2)(b) Headquarters (HQ) Work Zone Resources

The HQ Traffic Office has a work zone team available to answer questions, provide information, or otherwise assist. The HQ Design and Construction offices may also be able to assist with some work zone issues. They include:

- State Assistant Traffic Design Engineer
- State Work Zone Engineer
- State Work Zone Training Specialist
- WSDOT Work Zone Web Page

1010.12(2)(c) FHWA Work Zone Resources

The FHWA Washington Division Office and Headquarters (HQ) Office may be able to provide some additional information through the WSDOT HQ Traffic Office. The FHWA also has a work zone web page: www.ops.fhwa.dot.gov/wz/

1010.13 Documentation

Refer to Chapter 300 for design documentation requirements.

1010.14 References

1010.14(1) Federal/State Laws and Codes

23 Code of Federal Regulations (CFR) Part 630 Subpart J and Subpart K – Work Zone Safety and Mobility and Temporary Traffic Control Devices

See Chapter 1510 for Americans with Disabilities Act policy and references.

"Final Rule on Work Zone Safety and Mobility," Federal Highway Administration (FHWA), Published on September 9, 2004
www.ops.fhwa.dot.gov/wz/resources/final_rule.htm

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)

1010.14(2) Design Guidance

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO

Executive Order E 1001, Work Zone Safety and Mobility
http://wwwi.wsdot.wa.gov/publications/policies/fulltext/1001.pdf

Executive Order E 1060, Speed Limit Reductions in Work Zones
http://wwwi.wsdot.wa.gov/publications/policies/fulltext/1060.pdf

Executive Order E 1033, WSDOT Employee Safety
http://wwwi.wsdot.wa.gov/publications/policies/fulltext/1033.pdf

Plans Preparation Manual, M 22-31, WSDOT

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-10, WSDOT

Standard Specifications for Road, Bridge, and Municipal Construction (Standard Specifications), M 41-10, WSDOT

Traffic Manual, M 51-02, WSDOT

Work Zone Traffic Control Guidelines, M 54-44, WSDOT

1010.14(3) Supporting Information

Construction Manual, M 41-01, WSDOT

"Crashworthy Work Zone Traffic Control Devices," Report 553, NCHRP, 2006

Environmental Manual, M 31-11, WSDOT

Highway Capacity Manual, 2010, TRB

ITE Temporary Traffic Control Device Handbook, 2001

ITS in Work Zones www.ops.fhwa.dot.gov/wz/its/

"Recommended Procedures for the Safety Evaluation of Highway Features," Report 350, NCHRP, 1993

Roadside Design Guide, AASHTO, 2011

Manual for Assessing Safety Hardware, AASHTO, 2009

Work Zone & Traffic Analysis, FHWA www.ops.fhwa.dot.gov/wz/traffic_analysis.htm

Work Zone Operations Best Practices Guidebook, FHWA, 2007
www.ops.fhwa.dot.gov/wz/practices/practices.htm

Work Zone Safety and Mobility, FHWA www.ops.fhwa.dot.gov/wz/index.asp

Work Zone Safety Web Page, WSDOT www.wsdot.wa.gov/safety/workzones/

WSDOT Project Management website: http://www.wsdot.wa.gov/Projects/ProjectMgmt/

Exhibit 1010-3 Transportation Management Plan Components Checklist

Use the following checklist to develop a formal TMP document on significant projects.

TMP Component	✓
1. Introductory Material	
Cover page	
Licensed Engineer stamp page (if necessary)	
Table of contents	
List of figures	
List of tables	
List of abbreviations and symbols	
Terminology	
2. Executive Summary	
3. TMP Roles and Responsibilities	
TMP manager	
Stakeholders/review committee	
Approval contact(s)	
TMP implementation task leaders (public information liaison, incident management coordinator)	
TMP monitors	
Emergency contacts	
4. Project Description	
Project background	
Project type	
Project area/corridor	
Project goals and constraints	
Proposed construction phasing/staging	
General schedule and timeline	
Adjacent projects	
5. Existing and Future Conditions	
Data collection and modeling approach	
Existing roadway characteristics (history, roadway classification, number of lanes, geometrics, urban/suburban/rural)	
Existing and historical traffic data (volumes, speed, capacity, volume-to-capacity ratio, percent trucks, queue length, peak traffic hours)	
Existing traffic operations (signal timing, traffic controls)	
Incident and crash data	
Local community and business concerns/issues	
Traffic growth rates (for future construction dates)	
Traffic predictions during construction (volume, delay, queue)	
6. Work Zone Impacts Assessment Report	
Qualitative summary of anticipated work zone impacts	
Impacts assessment of alternative project design and management strategies (in conjunction with each other)	
• Construction approach/phasing/staging strategies	
• Work zone impacts management strategies	

Exhibit 1010-3 Transportation Management Plan Components Checklist (continued)

TMP Component	✓
Traffic analysis results (if applicable)	
• Traffic analysis strategies	
• Measures of effectiveness	
• Analysis tool selection methodology and justification	
• Analysis results	
Traffic (volume, capacity, delay, queue, noise)	
Safety	
Adequacy of detour routes	
Business/community impact	
Seasonal impacts	
Cost-effectiveness/evaluation of alternatives	
Selected alternative	
• Construction approach/phasing/staging strategy	
• Work zone impacts management strategies	
7. Selected Work Zone Impacts Management Strategies	
Temporary Traffic Control (TTC) strategies	
• Control strategies	
• Traffic control devices	
• Corridor Project coordination, contracting, and innovative construction strategies	
Public Information (PI)	
• Public awareness strategies	
• Motorist information strategies	
Transportation Operations (TO)	
• Demand management strategies	
• Corridor/network management strategies	
• Work zone safety management strategies	
• Traffic/incident management and enforcement strategies	
8. TMP Monitoring	
Monitoring requirements	
Evaluation report of successes and failures of TMP	
9. Contingency Plans	
Trigger points	
Decision tree	
Contractor's contingency plan	
Standby equipment or personnel	
10. TMP Implementation Costs	
Itemized costs	
Cost responsibilities/sharing opportunities	
Funding source(s)	
11. Special Considerations (as needed)	
12. Attachments (as needed)	

Chapter 1020 Signing

1020.01 General
1020.02 Design Components
1020.03 Overhead Installation
1020.04 State Highway Route Numbers
1020.05 Mileposts
1020.06 Guide Sign Plan
1020.07 Documentation
1020.08 References

1020.01 General

The Washington State Department of Transportation (WSDOT) uses signing as the primary mechanism for regulating, warning, and guiding traffic. Signing must be in place when any section of highway is open to the motoring public. Each highway project has unique and specific signing requirements. For statewide signing uniformity and continuity, it is sometimes necessary to provide signing beyond the project limits. Design characteristics of the facility determine the size and legend for a sign. As the design speed increases, larger sign sizes are necessary to provide adequate message comprehension time. The MUTCD, the *Traffic Manual*, and the *Sign Fabrication Manual* contain standard sign dimensions, specific legends, and reflective sheeting types for all new signs.

Guide signing provides the motorist with directional information to destinations. This information is always presented in a consistent manner. In some cases, there are specific laws, regulations, and policies governing the content of the messages on these signs. All proposed guide signs for a project require the approval of the region Traffic Engineer. The use of nonstandard signs is strongly discouraged and their use requires the approval of the State Traffic Engineer.

Apply the following criteria when determining whether to replace or modify existing signs:

- Current sign's service life is reached
- Lack of nighttime retroreflectivity
- Substantial damage, vandalism, or deterioration
- Replace signs with Type I sheeting
- Change in sign use policy
- Improper location
- Message or destination changes necessary to satisfy commitments to public or local agencies
- Substandard mounting height
- Change in jurisdiction (for example, a county road becomes a state route)

Address sign support breakaway features in accordance with Chapter 1600.

1020.02 Design Components

1020.02(1) Location

The MUTCD contains the guidelines for positioning signs. Check sign locations to ensure the motorist's view of the sign is not obscured by other roadside appurtenances. Also, determine whether the proposed sign will obstruct the view of other signs or limit the motorist's sight distance of the roadway. Reposition existing signs, when necessary, to satisfy these visibility requirements. Where possible, locate signs behind existing traffic barriers, on grade separation structures, or where terrain features will minimize their exposure to errant vehicles.

1020.02(2) Longitudinal Placement

The MUTCD and the *Traffic Manual* provide guidelines for the longitudinal placement of signs that are dependent on the type of sign. Select a location to fit the existing conditions to provide for visibility and adequate response time. In most cases, signs can be shifted longitudinally to enhance safety without compromising their intended purpose.

1020.02(3) Lateral Clearance

The *Standard Plans* and the MUTCD contain minimum requirements for the lateral placement of signs. Where possible, position the signs at the maximum feasible lateral clearance for safety and reduced maintenance costs. Locate large guide signs and motorist information signs beyond the Design Clear Zone (see Chapter 1600) where limited right of way or other physical constraints are not a factor. On steep fill slopes, an errant vehicle is likely to be partially airborne from the slope break near the edge of shoulder to a point 12 feet down the slope. When signs are placed on fill slopes steeper than 6H:1V, locate the support at least 12 feet beyond the slope break.

Use breakaway sign support features, when required, for signs located within the Design Clear Zone and for signs located beyond this zone where there is a possibility they might be struck by an errant vehicle. Breakaway features are not necessary on signposts located behind traffic barriers. Install longitudinal barriers to shield signs without breakaway features within the Design Clear Zone when no other options are available.

Sign bridges and cantilever sign structures have limited span lengths. Locate the vertical components of these structures as far from the traveled way as possible and, where appropriate, install traffic barriers (see Chapter 1610).

Do not locate signposts in the bottom of a ditch or where the posts will straddle the ditch. The preferred location is beyond the ditch or on the ditch backslope (see the *Standard Plans*). In high-fill areas where conditions require placement of a sign behind a traffic barrier, consider adding embankment material to reduce the length of the sign supports.

1020.02(4) Sign Heights

For ground-mounted signs installed at the side of the road, provide a mounting height of at least 7 feet, measured from the bottom of the sign to the edge of traveled way. Supplemental plaques, when used, are mounted directly below the primary sign. At these locations, the minimum mounting height of the plaque is 5 feet.

Do not attach supplemental guide signs to the posts below the hinge mechanism or the saw cut notch on multiple-post installations. The location of these hinges or saw cuts on the sign supports are shown in the *Standard Plans*.

A minimum 7-foot vertical height from the bottom of the sign to the ground directly below the sign is necessary for the breakaway features of the sign support to function properly when struck by a vehicle. The minimum mounting height for new signs located behind longitudinal barriers is 7 feet, measured from the bottom of the sign to the edge of traveled way. A lower mounting height of 5 feet may be used when replacing a sign panel on an existing sign assembly located behind the longitudinal barrier. The *Standard Plans* shows typical sign installations.

For ground-mounted signs installed on multiple posts that are a minimum of

12 feet from the edge of traveled way in cut sections, the minimum height clearance between the sign and the ground for the post farther from the edge of traveled way is as follows:

- For slopes 2H:1V and steeper, the minimum height clearance is 2 feet.
- For slopes 3H:1V or flatter, the minimum height clearance is 7 feet.

Signs used to reserve parking for people with disabilities are installed at each designated parking stall and are mounted 7 feet above the surface at the sign location.

1020.02(5) Foundations

Foundation details for timber and steel ground-mounted sign supports are shown in the *Standard Plans*, which also contains foundation designs for truss-type sign bridges and cantilever sign structures. Three designs, Types 1, 2, and 3, are shown for each structure.

An investigation of the foundation material is necessary to determine the appropriate foundation design. Use the data obtained from the geotechnical report to select the foundation type.

- The **Type 1** foundation design uses a large concrete shaft and is the preferred installation when the lateral bearing pressure of the soil is 2,500 psf or greater.
- The **Type 2** foundation design has a large rectangular footing design and is an alternative to the Type 1 foundation when the concrete shaft is not suitable.
- The **Type 3** foundation design is used in poorer soil conditions where the lateral bearing pressure of the soil is between 1,500 psf and 2,500 psf.

If a nonstandard foundation or monotube structure design is planned, forward the report to the Headquarters (HQ) Bridge and Structures Office for use in developing a suitable foundation design (see Chapter 610).

1020.02(6) Signposts

Ground-mounted signs are installed on either timber posts, laminated wood box posts, or steel posts. The size and number of posts required for a sign installation are based on the height and surface area of the sign, or signs, being supported. Use the information in Exhibits 1020-2, 1020-3, and 1020-4 and the *Standard Plans* to determine the posts required for each installation. Coordinate with the region Maintenance Office concerning signpost installation.

Use steel posts with breakaway supports that are multidirectional if the support is likely to be hit from more than one direction. For any wide flange multiple-steel post installations located within the Design Clear Zone, the total weight of all the posts in a 7-foot-wide path is not to exceed a combined post weight of 34 lbs/foot. Use the Wide Flange Beam Weights table in Exhibit 1020-3 to determine wide flange steel post weights. If the proposed sign configuration does not meet the weight criterion, relocate, resize, or provide barrier protection for the proposed installation.

All signposts are to be designed to 90 mph wind loads. Design features of breakaway supports are shown in the *Standard Plans*. Steel signposts commonly used are: Perforated Square Steel Tube (PSST); Square Steel Tube (SST); Round Pipe (RP); and Wide Flange "H-Beam." Steel posts with Type TP-A, TP-B, PL, PL-T, PL-U, AS, AP, SB-1, and SB-2 bases have multidirectional breakaway features.

1020.03 Overhead Installation

Guidance on the use of overhead sign installations is provided in the MUTCD. Where possible, mount overhead signs on grade separation structures rather than sign bridges or cantilever supports.

Details for the construction of truss-type sign bridges and cantilever sign supports are shown in the *Standard Plans*.

The HQ Bridge and Structures Office designs structure-mounted sign mountings, monotube sign bridges, and monotube cantilever sign supports. For overhead sign installation designs, provide sign dimensions, horizontal location in relation to the roadway, and location of the lighting fixtures to facilitate design of the mounting components by the HQ Bridge and Structures Office.

1020.03(1) Illumination

The retroreflectivity of currently approved sign sheeting removes the need to provide illumination for most sign installations.

The sign lights for existing illuminated overhead and ground-mounted signs can only be de-energized and removed if the retroreflective sheeting is adequate for nighttime legibility, or replace the existing sign with a new sign (see Exhibit 1020-1 for sheeting requirements). A nighttime assessment of all nonilluminated overhead signs within the project limits is required. Replace all signs that have inadequate retroreflectivity (contact the region Traffic Office). In situations where a nonhighway light source interferes with a sign's legibility, consider relocating the sign or providing sign lights.

Flashing beacon signs are used to alert motorists of unusual or unexpected driving conditions ahead. Sign lights are unnecessary on flashing beacon signs when appropriate sign sheeting, full circle or tunnel signal head visors, and automatic dimmer devices are used.

Exhibit 1020-1 Reflective Sheeting Requirements for Overhead Signs

Overhead Sign Type	Sheeting Type (Background)	Sheeting Type (Legend & Border)
EXIT ONLY guide sign	IV*	XI
Guide signs for left side exits	IV	XI
Other guide signs	IV	XI
Overhead street name signs	IV	XI
Regulatory signs	IV	n/a
Warning signs	IX or XI	n/a
*For Yellow Background Sheeting, use Type IX or XI Fluorescent Sheeting.		

All other overhead signs are illuminated only when one of the following conditions is present:

- Sign visibility is less than 800 feet due to intervening sight obstructions such as highway structures or roadside features.
- Signs directly adjacent to other overhead signs have sign lights.

1020.03(2) Vertical Clearance

The minimum vertical clearance from the roadway surface to the lowest point of an overhead sign assembly is 17 feet 6 inches. The minimum vertical clearance from the roadway surface to the lowest point of an overhead sign assembly without sign light(s) is 19 feet 6 inches. The maximum clearance is 21 feet. Contact the HQ Traffic Office regarding signs under bridges and in tunnels.

1020.03(3) Horizontal Placement

Consider roadway geometrics and anticipated traffic characteristics when locating signs above the lane(s) to which they apply. Install advance guide signs/exit direction signs that require an EXIT ONLY and "down arrow" panel directly above the drop lanes. To reduce driver confusion about which lane is being dropped, avoid locating a sign with an EXIT ONLY panel on a horizontal curve.

1020.03(4) Service Walkways

Walkways are provided on structure-mounted signs, truss-type sign bridges, and truss-type cantilever sign supports where roadway and traffic conditions prohibit normal sign maintenance activities. Monotube sign bridges/cantilever sign supports normally do not have service walkways.

Vandalism of signs, particularly in the form of graffiti, can be a major problem in some areas. Vandals sometimes use the service walkways and vandalize the signs. Maintenance costs for cleaning or replacing the vandalized signs at these locations can exceed the benefit of providing the service walkway.

1020.04 State Highway Route Numbers

For state routes, RCW 47.36.095 authorizes WSDOT to sign state highways using a system of state route numbers assigned to eliminate duplication of numbers. This numbering system follows the system employed by the federal government in the assignment of Interstate and U.S. routes: odd numbers indicate general north-south routes and even numbers indicate general east-west routes.

1020.05 Mileposts

Milepost markers are a part of a statewide system for all state highways and are installed in accordance with Executive Order E 1064, "State Route Mileposts," and Chapter 2 of the *Traffic Manual*.

1020.06 Guide Sign Plan

A preliminary guide sign plan is developed to identify existing and proposed guide signing on state highways and is reviewed by the region Traffic Engineer. Preliminary guide signs for Interstate routes are to be furnished to the HQ Traffic Office for review and concurrence. The plan provides an easily understood graphic representation of the signing and its continuity to motorist destinations, activities, and services. It is also used to identify deficiencies or poorly defined routes of travel. A guide sign plan for safety and mobility Improvement projects is desirable. When proposed highway work affects signing to a city or town, the guide sign plan can be furnished to the official governing body for review and consideration. The guide sign plan is reviewed and approved by the region Traffic Engineer.

1020.07 Documentation

Refer to Chapter 300 for design documentation requirements.

1020.08 References

1020.08(1) Federal/State Laws and Codes

23 Code of Federal Regulations (CFR) 655, Traffic Operations

WSDOT Executive Order E 1064, "State Route Mileposts," WSDOT

Revised Code of Washington (RCW) 47.36, Traffic control devices

1020.08(2) Design Guidance

Manual on Uniform Traffic Control Devices for Streets and Highways (MUTCD), 2003 Edition, FHWA, 2003, including the Washington State Modifications to the MUTCD, M 24-01, 2003

Plans Preparation Manual, M 22-31, WSDOT

Sign Fabrication Manual, M 55-05, WSDOT


Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT

Standard Specifications for Road, Bridge, and Municipal Construction (Standard Specifications), M 41-10, WSDOT

Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals, 4th Edition, Washington DC, AASHTO, 2001

Traffic Manual, M 51-02, WSDOT

Exhibit 1020-2 Timber Posts



Notes:

The following designs are *not permitted* when a sign is to be located in or outside the Design Clear Zone in an area where it is likely to be struck by an errant vehicle:

1. A sign with any post larger than 6x8 inches.
2. A 2-post, 3-post, or 4-post sign that uses 6x6-inch or larger posts and has two posts spaced less than 7 ft apart on center.

Table 1 Timber Post Selection

Post Size (in)	(X)(Y)(Z) (ft^3) Number of Posts				D (ft)
	1	2	3	4	
4 x 4	60	115	175	235	3
4 x 6	125	335	500	675	4
6 x 6	200	415	620	815	4
6 x 8	330	695	1150	1515	5
6 x 10	670	1355	2030	2700	6
8 x 10	835	1685	2515	3360	6
6 x 12	985	2005	2965	3945	7

Values shown are the maximum permitted.

For timber grade requirements, see the *Standard Specifications*.

Foundation depths are based on allowable lateral bearing pressure in excess of 2500 psf.

If the value (X)(Y)(Z) amount exceeds the limit for 6x12 post(s), use steel post(s) for sign installation.

A = Vertical distance from edge of traveled way to edge of shoulder

B = Vertical distance from slope catch point to centerline of longest post

C = Vertical distance between adjacent posts

X & Y = Single sign or back-to-back signs: Overall dimensions of the sign
Multiple signs: Dimensions of the area within the perimeter of a rectangle enclosing the extremities of the sign

Z = Height from ground line to midheight of sign at the centerline of the longest post

D = Embedment depth

H = Total post height

V = Vertical clearance from edge of traveled way

W= Distance from edge of traveled way to the centerline of the post nearest the roadway

Design Example – Single Post

Given:

Sign 3 ft wide, 3.5 ft high; a secondary sign 1.5 ft wide, 2 ft high, mounted 3 inches (0.25 ft) below; 8-ft shoulder with 2% slope; 6H:1V embankment; W = 15 ft; V = 5 ft

Solution:

X = 3 ft

Y = 3.5 + 2 + 0.25 = 5.75 ft

A = (0.02)(8) = 0.16

B = (W-8)/6 = (15-8)/6 = 1.17

Z = Y/2 + V + A + B

= (5.75/2) + 5 + 0.16 + 1.17 = 9.2 ft

(X)(Y)(Z) = (3)(5.75)(9.2) = 158.7 ft^3

Since 159 ft^3< 200 ft^3, from Table 1, select 6x6 post

H = 9.2 + (5.75/2) + 4 = 16.1 ft

Design Example – Double Post

Given:

Sign 12 ft wide, 4 ft high; 10-ft shoulder with 2% slope; 6H:1V embankment; W = 25 ft; V = 7 ft

Solution:

X = 12 ft; Y = 4 ft

A = (0.02)(10) = 0.2

B = [(W-10) + (0.6X)]/6 = [(25-10) + (0.6)(12)]/6 = 3.7

C = (0.6)(12)/6 = 1.2

Z = Y/2 + V + A + B = 4/2+7 + 0.2 + 3.7 = 12.9 ft

(X)(Y)(Z) = (12)(4)(12.9) = 619 ft^3

Since 619 ft^3 < 695 ft^3, select two 6x8 posts.

H_2 = Y/2 + Z + D = 4/2 + 12.9 + 5 = 19.9 ft

H_1 = H_2-C = 19.9-1.2 = 18.7 ft

Note: 6x6 and larger posts require 7-ft spacing. Sign may be installed within the Design Clear Zone.

Exhibit 1020-3 Wide Flange Steel Posts

X & Y = Single sign or back-to-back signs: Overall dimensions of the sign
Multiple signs: Dimensions of the area within the perimeter of a rectangle enclosing the extremities of the signs

Z = Height from the base connection (2½ inches above the post foundation for wide flange beams) to the midheight of the sign at the centerline of the longest post

H = Post length

V = Vertical clearance from the edge of traveled way

W= Distance from the edge of traveled way to the centerline of the longest post nearest the roadway

Design Example – Steel Post Selection

Given:

Sign 22 ft wide, 12 ft high; 10 ft shoulder with 2% slope; 3H:1V embankment; W = 32 ft; V = 7ft.

Solution:

X = 22
Y = 12
A = (0.02)(10) = 0.2
B = [(W-10) + (0.7)(X/3)] = [(32-10) + (0.7x22)]/3 = 12.5
C = (0.35)(22)/3 = 2.6
Z = Y/2 + V + A + B-0.21
= 12/2 + 7 + 0.2 + 12.5-0.21 = 25.5 ft
(X)(Y)(Z) = (22)(12)(25.5) = 6729 ft^3

Since 6729 ft^3 < 9480 ft^3, select three W10x26 (ASTM A36) or W10x22 (ASTM A992) (see the *Standard Plans*)
H3 = 12/2 + 25.5 = 31.5 ft
H2 = H3-C = 31.5-2.6 = 28.9 ft
H1 = H2-C = 28.9-2.6 = 26.3 ft

Table 1 Wide Flange Steel Post Selection

Wide Flange Beam			
Post Size		(X)(Y)(Z) (ft^3)	
		Number of Posts	
ASTM A992	ASTM A36	2	3
W6x9	W6x12	1570	2355
W6x12	W6x16	2340	3510
W8x18	W8x21	4120	6180
W10x22	W10x26	6320	9480
W12x26	W12x30	8700	- - -


Table 2 Wide Flange Beam Weights

Beam Size	Weight lbs/ft	Beam Size	Weight lbs/ft
W6x9	9	W8x21	21
W6x12	12	W10x22	22
W6x16	16	W10x26	26
W8x18	18	W12x26	26
		W10x30	30

Notes:

- Values shown in Table 1 are the maximum permitted.
- A single-wide flange post installation is not allowed.
- Consider using one of the following: perforated square steel tube posts, solid steel tube posts, or round steel posts.
- For post selection for other than wide flange beam supports and a single-post assembly, see the *Standard Plans*. To determine post sizes for these types of posts, use the wind load charts at: www.wsdot.wa.gov/design/traffic/signing

(See the *Standard Plans* for additional information.)







Exhibit 1020-4 Laminated Wood Box Posts



X & Y = Single sign or back-to-back signs:
Overall dimensions of the sign
Multiple signs: Dimensions of the area within the perimeter of a rectangle enclosing the extremities of the signs

Z = Height from ground line to the midheight of the sign at the centerline of the longest post

D = Embedment depth

H = Post length

V = Vertical clearance from edge of traveled way

W= Distance from edge of traveled way to the centerline of the post nearest the roadway (see the *Standard Plans*)

Design Example – M Post Selection

Given:

Two-post assembly sign 16 ft wide, 6 ft high; 10 ft shoulder with 2% slope; 6H:1V embankment; W = 25 ft; V = 7 ft

Solution:

X = 16
Y = 6
A = (0.02)(10) = 0.2
B = [(W-10) + 0.6X]/6
= [(25-10) + (0.6)(16)]/6 = 4.1
C = (0.6X)/6 = (0.6)(16)/6 = 1.6
Z = Y/2 + V + A + B = 6/2 + 7 + 0.2+4.1 = 14.3 ft
(X)(Y)(Z) = (16)(6)(14.3) = 1373 ft^3
Since 1373 ft^3 < 1661 ft^3, select a post type M from Table 1.

H2 = Y/2 + Z + D = 6/2 + 14.3 + 6 = 23.3 ft
H1 = H2-C = 23.3-1.6 = 21.7 ft

Table 1 Laminated Wood Box Post Selection

Post Type	Size (in)	Z (ft)	(X)(Y)(Z) ft^3
M	7 7/8 x 7 7/8	15 < Z≤ 26	1329
M	7 7/8 x 7 7/8	Z ≤ 15	1661
L	7 7/8 x 14 7/8	15 < Z ≤ 26	3502
L	7 7/8 x 14 7/8	Z ≤ 15	4378

Table 2 Embedment Depth (D)

Z (ft)	Sign Area ft^2					
	Up to 50	51 to 100	101 to 150	151 to 200	201 to 250	251 to 290
9 to 12	6	6	7	8	9	10
13 to 15	6	6	7.5	9	10	
16 to 18	7	7.5	9			
19 to 22	7	8	10			
23 to 26	7.5	8.5				

Design Example – L Post Selection

Given:

Two-post assembly sign 18 ft wide, 8 ft high;10 ft shoulder with 2% slope; 6H:1V embankment W = 25 ft; V = 7 ft

Solution:

X = 18
Y = 8
A = (0.02)(10) = 0.2
B = [(W-10) + (0.6X)]/6 = [(25-10) + (0.6)(18)]/6 = 4.3
C = 0.6X/6 = (0.618)/6 = 1.8
Z = Y/2 + V + A + B = 8/2 + 7 + 0.2 + 4.3 = 15.5 ft
(X)(Y)(Z) = (18)(8)(15.5) = 2232 ft^3

Since 2232 ft^3 < 3502 ft^3, select a post type L from Table 1.

H2 = Y/2 + Z + D = 8/2 + 15.5 + 9 = 28.5 ft
H1 = H2-C = 28.5 – 1.8 = 26.7 ft

Chapter 1030 Delineation

1030.01 General
1030.02 Definitions
1030.03 Pavement Markings
1030.04 Guideposts
1030.05 Barrier Delineation
1030.06 Object Markers
1030.07 Documentation
1030.08 References

1030.01 General

The primary function of delineation is to provide the visual information needed by a driver to operate a vehicle in a variety of situations. Delineation includes the marking of highways with painted or more durable pavement marking lines and symbols, guideposts, and other devices such as curbs. These devices can use retroreflectance, which is the reflecting of light from a vehicle's headlights back to the driver, to enhance an object's visibility at nighttime.

Delineation is a required design element (see Chapter 1105) on most projects. A decision to omit delineation is possible if the existing delineation is unaffected by construction and a safety performance evaluation (see Chapter 321) clearly shows that delineation is not a contributing factor to crashes. The Washington State Department of Transportation (WSDOT) uses the latest edition of the *Manual on Uniform Traffic Control Devises* (MUTCD) as a guide for the design, location, and application of delineation.

Consult with the region Traffic Office early in the design process to ensure the proposed delineation is compatible with current WSDOT policy and guidance regarding types of markings and material selection.

1030.02 Definitions

The following terms are defined in the *Design Manual* Glossary:

Delineation; *extrude*; *mcd/m2/lux*; *pavement marking*; *pavement marking beads*; *pavement marking durability*; *retroreflection, coefficient of (R_L)*; *traffic paint*; and *wet film thickness*.

1030.03 Pavement Markings

1030.03(1) Pavement Marking Types

Pavement markings have specific functions: they guide the movement of traffic and they promote increased safety performance. In some cases, they are used to supplement the messages of other traffic control devices. In other cases, markings are the only way to convey a message without distracting the driver. Pavement markings are intended to provide adequate performance year round. Guidelines for the application of various pavement markings are provided in the *Standard Plans* and the MUTCD.

1030.03(1)(a) Longitudinal Pavement Markings

Longitudinal pavement markings define the boundary between opposing traffic flows, and they identify the edges of traveled way, multiple traffic lanes, turn lanes, and special-use lanes. The *Standard Plans* shows the dimensions of longitudinal pavement markings. Longitudinal pavement markings are as follows:

barrier centerline A very wide—18 inches minimum, usually 20 inches: five 4 inch lines—solid yellow line or a combination of two single 4-inch solid yellow lines with yellow crosshatching between the lines, with a total width not less than 18 inches, used to separate opposing traffic movements where all movements over the line are prohibited. Barrier centerline locations require the approval of the region Traffic Engineer and Access Engineer.

centerline A broken yellow line used to separate lanes of traffic moving in opposite directions, where passing in the opposing lane is allowed.

dotted extension line A broken white or yellow line that is an extension of an edge line or centerline used at exit ramps, intersections on horizontal curves, multiple turn lanes, and other locations where the direction of travel for through or turning traffic is unclear.

double centerline Two parallel solid yellow lines used to separate lanes of traffic moving in opposite directions where passing in the opposing lane is prohibited.

double lane line Two solid white lines used to separate lanes of traffic moving in the same direction where crossing the lane line marking is prohibited.

double wide lane line Two solid wide white lines used to separate a concurrent preferential lane of traffic where crossing is prohibited.

drop lane line A wide broken white line used in advance of a wide line to delineate a lane that ends at an off-ramp or intersection.

edge line A solid white or yellow line used to define the outer edges of the traveled way. Edge lines are not required where curbs or sidewalks are 4 feet or less from the traveled way.

lane line A broken white line used to separate lanes of traffic moving in the same direction.

no-pass line A solid yellow line used in conjunction with a centerline where passing in the opposing lane is prohibited.

reversible lane line Two broken yellow lines used to delineate a lane where traffic direction is periodically reversed.

solid lane line A solid white line used to separate lanes of traffic moving in the same direction where crossing the lane line marking is discouraged.

two-way left-turn centerline Two yellow lines, one solid and one broken, used to delineate each side of a two-way left-turn lane.

wide broken lane line A wide broken white line used to designate a portion of a high-occupancy vehicle (HOV) lane located on a divided highway where general-purpose vehicles may enter to make an exit.

wide dotted lane line A wide broken white line used to designate a portion of a high-occupancy vehicle (HOV), or business access and transit (BAT) lane located on an arterial highway where general-purpose vehicles may enter to make a turn at an intersection.

wide lane line A wide solid white line used to separate lanes of traffic moving in the same direction, at ramp connections, storage lanes at intersections, and high-occupancy vehicle (HOV) lanes, or at business access and transit (BAT) lanes, bike lanes, and other preferential lanes where crossing is discouraged.

See MUTCD Chapter 3B for further information for these markings.

1030.03(1)(b) Transverse Pavement Markings

Transverse pavement markings define pedestrian crossings and vehicle stopping points at intersections. They are also used to warn motorists of approaching conditions, required vehicular maneuvers, or lane usage. See the *Standard Plans* for details of these pavement markings. Typical transverse pavement markings are as follows:

access parking space symbol A white marking used to designate parking stalls provided for motorists with disabilities. The marking may have an optional blue background and white border.

aerial surveillance marker White markings used at one-mile and one-half-mile intervals on sections of highways where the State Patrol uses airplanes to enforce speed limits.

bicycle lane symbol A white marking consisting of a symbol of a bicyclist and an arrow used in a marked bike lane. The bicycle lane symbol is to be placed immediately after an intersection and at other locations as needed (see the MUTCD). Typical spacing is 500 feet, with a maximum distance of 1,500 feet.

crosswalk line A series of parallel solid white lines used to define a pedestrian crossing.

drainage marking A white line used to denote the location of a catch basin, grate inlet, or other drainage feature in the shoulder of a roadway.

HOV symbol A white diamond marking used for high-occupancy vehicle lanes. The spacing of the markings is an engineering judgment based on the conditions of use. Typical spacing is 1000 feet for divided highways and 500 feet for arterial highways.

railroad crossing symbol A white marking used in advance of a railroad crossing where grade crossing signals or gates are located or where the posted speed of the highway is 40 mph or higher.

stop line A solid white line used to indicate the stopping point at an intersection or railroad crossing.

traffic arrow A white marking used in storage lanes and two-way left-turn lanes to denote the direction of turning movement. Arrows are also used at ramp terminals and intersections on divided highways to discourage wrong-way movements.

traffic letters White markings forming word messages, such as “ONLY,” used in conjunction with a traffic arrow at drop-lane situations. Traffic letters are not required for left- and right-turn storage lanes where the intended use of the lane is obvious.

wide line A wide solid line used for traffic islands, hash marks, chevrons, and other applications. A wide line used in conjunction with a centerline marking shall be yellow. A wide line used in conjunction with a lane line or right edge line marking shall be white.

Yield line markings A series of white triangular markings indicating that the lane yields.

1030.03(2) Pavement Marking Materials

Pavement markings are applied using various materials. These materials are divided into two categories: paint and plastic. When selecting the pavement marking material to use in a project, consider the initial cost of the material and its durability; the location; the traffic conditions; the snow and ice removal practices of the particular maintenance area; and the region's ability to maintain the markings.

Both painted and plastic pavement markings can accomplish the goal of providing a visible (daytime) and retroreflective (nighttime) pavement marking at the completion of a contract. The difference between the two marking materials is the projected durability of the markings. Paint used on sections of highway subjected to high traffic volumes and/or snow-removal operations might have a durability of only two to three months. Maintenance crews cannot restripe a highway during winter months; therefore, if a painted marking wears out prematurely, the highway will not have a stripe until maintenance crews can restripe in April or May. When these conditions are encountered in a highway project, consider a more durable plastic marking material and application type that will provide the desired durability for the marking.

Check with your region Traffic Office for any specific pavement marking policy. For the recommended pavement marking material for different highway types and snow-removal practices, see Exhibit 1030-1. Consult with the region's Traffic and Maintenance offices to select the best material for the project.

1030.03(2)(a) Paint

Paint is the most common pavement marking material. It is relatively easy to apply and dries quickly (30–90 seconds in warm, dry weather) after application. This allows the application to be a moving operation, which minimizes traffic control costs and delays to the roadway users. On construction contracts, paint is applied with two coats: the first coat is 10 mils thick, followed by a second coat 15 mils thick. The disadvantage of using paint as a pavement marking material is its limited durability when subjected to traffic abrasion, sanding, or snow-removal activities. Specify paint only where it will have a durability that will provide a retroreflective stripe until maintenance crews can repaint the line and extend its usefulness until the next repainting.

Paint is one of two material types dependent upon the solids carrier: solvent or water. The designer is encouraged to specify waterborne paint. Solvent paint is subject to a monetary penalty because it contains a high level of volatile organic compounds (VOCs). There is an Environmental Protection Agency (EPA) Clean Air Act penalty assessed on solvent paint that is passed on to those who purchase solvent paint in quantity.

Durable waterborne paint or high-build waterborne paint is formulated to allow application thicknesses greater than 15 mils. It is more durable than standard waterborne paint and provides additional service life. The additional thickness permits the use of larger beads that enhance wet night retroreflectivity.

Low-temperature waterborne paint is intended to extend the paint season later into the fall, although it may also be used earlier in the spring. The paint is formulated for application temperatures of 35° Fahrenheit and rising, though durability can be affected when applied during conditions where standard waterborne paint could have been used.

1030.03(2)(b) Plastic

Plastic markings have a higher installation cost than paint. They can, however, be a more cost-effective measure than paint because of their longer service life. Plastic marking materials may provide a year-round retroreflective pavement marking, while paint may not last until the next restriping. Plastic marking materials currently listed in the *Standard Specifications* include the following:

1. **Type A: Liquid Hot Applied Thermoplastic**

   Thermoplastic material consists of resins and filler materials in solid form at room temperature. The material is heated to a semiliquid, molten state (400° Fahrenheit) and is then applied to the roadway by spray or extrusion methods. This material can be used for both transverse and longitudinal line applications. Special equipment is required for both the initial application and subsequent maintenance renewal. Sprayed material can be applied at a thickness of 30 mils and dries in 30 to 60 seconds. The durability of material applied in this manner is slightly longer than that of paint. Extruded material is applied at a thickness of 125 mils and has a drying time of 15 minutes. This material can be applied as a flat line or applied with ridges or profiles (bumps) that enhance wet night visibility. These profiles produce a rumble effect similar to raised pavement markers when a vehicle crosses over the marking. (Profiles come in the shape of a raised bar at set intervals and are formed simultaneously with the extruded baseline.)

2. **Type B: Preformed Fused Thermoplastic**

   This material consists of a mixture of pigment, fillers, resins, and beads that are factory produced in sheet form, 125 mils thick. The material is applied by heating (drying) the pavement and top heating the material. The heating process fuses the preformed thermoplastic material to the pavement surface. These materials, which are used for transverse markings, are available in white, red, blue, and other colors.

3. **Type C: Cold Applied Preformed Tape**

   Preformed tape is composed of thermoplastic or other materials that are fabricated under factory conditions. After curing, the material is cut to size and shipped to the work site in rolls or in flat pieces. The material is then applied to the roadway with an adhesive on the underside of the tape. Preformed tape is available in 60, 90, or 125 mils (WSDOT does not currently specify 125 mil tape.) The most durable application of preformed tape is achieved when the tape is either inlaid (rolled) into hot asphalt with the top of the tape flush with the surface of the pavement, or placed in a groove cut into the pavement surface with the top of the tape slightly below the surface of the pavement.

ASTM has classified preformed tape into two categories: Type 1 and Type 2. Type 1 tape has a profiled surface and a requirement to have a retroreflectivity of over 500 mcd/m2/lux. Type 1 tape has proven to be very durable. It is used on high-volume, high-speed highways. Type 2 tape has a flat surface and a requirement to have a retroreflectivity of over 250 mcd/ m2/lux. Field tests show that Type 2 tape has a shorter durability than Type 1 tape.

4. Type D: Liquid Cold Applied Methyl Methacrylate (MMA)

Methyl methacrylate can be applied by either spraying or extrusion. Sprayed applications can be one or two coats, 30 to 45 mils thick. Extruded applications are 90 mils thick for asphalt concrete pavement or Portland cement concrete pavement, or 120 mils thick for open-graded asphalt pavement. MMA can also be extruded using specialized equipment to produce a textured line 150 mils thick. The material is not heated and can be applied within an approximate temperature range of 40° to 105° Fahrenheit, provided the pavement surface is dry. The material can be used for both transverse and longitudinal applications. The material can also be applied with profiles (bumps) that slightly enhance wet night retroreflectivity. The profiles also produce a rumble effect similar to raised pavement markers.

1030.03(2)(c) Beads

Glass beads are small glass spheres used in highway markings to provide the necessary retroreflectivity. The beads are dropped onto the wet marking material immediately after it is applied (drop-on beads), or premixed into the wet marking material.

Proper installation of glass beads is critical to achieving good pavement marking retroreflectivity. Each glass bead works like a light-focusing lens, reflecting light back to the driver. Glass beads are embedded into the pavement marking material; for optimum performance, the bead is embedded between 55% and 60% of its diameter.

Large glass and composite beads are effective when roads are wet. Large glass or composite beads are not appropriate for standard mil paint as the paint is too thin to properly embed the large glass or composite beads; therefore, WSDOT specifies small glass or composite beads for such paint applications. The use of large glass or composite beads is limited to high-build waterborne paint and other materials with a thickness of at least 22 mils.

1030.03(3) Pavement Marking Application Types

There are five application types used for pavement markings. Most pavement marking applications are applied directly to the pavement surface. In steel bit snow plowing areas, the pavement markings may be inlaid or grooved to protect the markings.

Because they are higher than the surrounding pavement surface, pavement markings are subject to rapid wear caused by traffic and snowplows. As they wear, they lose visibility and retroreflectivity, particularly in wet weather. Wear on the stripes can be greatly reduced and their durability considerably increased by placing them in a shallow groove in the surface of the pavement.

1030.03(3)(a) Application Types

The five application types for pavement markings are:

1. **Flat Lines**

   Flat lines are pavement marking lines with a flat surface.

2. **Profiled Marking**

   A profiled pavement marking consists of a baseline thickness and a profiled thickness, which is a portion of the pavement marking line that is applied at a greater thickness than the baseline thickness. Profiles are applied using the extruded method in the same application as the baseline. The profiles may be slightly rounded if the minimum profile thickness is provided for the entire length of the profile. (See the *Standard Plans* for the construction details.)

3. **Embossed Plastic Line**

   Embossed plastic lines consist of a flat line with transverse grooves. An embossed plastic line may also have profiles. (See the *Standard Plans* for the construction details.)

4. **Inlaid Plastic Line**

   Inlaid plastic line is constructed by rolling Type C tape into hot mix asphalt (HMA) with the finish roller. This application is used infrequently by WSDOT and is not in the *Standard Specifications*.

5. **Grooved Plastic Line**

   Grooved plastic line is constructed by cutting a groove into the pavement surface and spraying, extruding, or gluing pavement marking material into the groove. The groove depth is dependent upon the material used, the pavement surface, and the location. The groove is typically in the range of 20 to 250 mils deep and 4 inches wide. Coordinate with the region Traffic Office on the use and dimensions of grooved plastic line marking.

1030.03(4) Raised Pavement Markers

Raised pavement markers (RPMs) are installed as positioning guides with long line pavement markings. They can also be installed as a complete substitution for certain long line markings. RPMs have a durability of two years, and they provide good wet night visibility and a rumble effect. RPMs are made from plastic materials and are available in three different types:

- Type 1 markers are 4 inches in diameter, ¾ inch high, and non-reflectorized.
- Type 2 markers are 4 inches wide, 4 inches long, ¾ inch high, and reflectorized.
- Type 3 markers are 6, 8, 10, or 12 inches wide, 4 inches long, ¾ inch high, and non-reflectorized.

Type 2 RPMs are not used as a substitute for right edge lines. They may be used to supplement the right edge line markings at lane reductions, at sections with reduced lane widths such as

narrow structures, and at the gore of exit ramps. All other applications supplementing right edge line markings require the approval of the region Traffic Engineer.

Red-backed RPMs are not desired and thus are only used at the discretion of the Region Traffic Engineer for specific locations. Research regarding their effectiveness for addressing wrong-way driving has been inconclusive to date.

Type 3 RPMs are used in locations where additional emphasis is desired, including vehicle separations and islands. Obtain approval by the region Traffic Engineer for all installations of Type 3 RPMs. Retain approval in the Design Documentation Package.

Reflectorized RPMs are not required for centerline and lane line applications in continuously illuminated sections of highway. However, if illumination policies (see Chapter 1040) affect a section of limited access roadway, coordinate with the region Traffic Engineer for RPM placement details. If reflectorized RPMs are used at an intersection within an illuminated section, they are also to be used throughout that section.

For raised pavement marker application details, see the *Standard Plans*.

1030.03(5) Recessed Raised Pavement Markers

Recessed raised pavement markers (RRPMs) are raised pavement markers (RPMs) installed in a groove ground into the pavement in accordance with the *Standard Plans*. RRPMs provide guidance similar to RPMs in ice chisel and steel blade snow-removal areas. RRPMs can also be used in rubber or Cooper-style blade snow-removal areas in accordance with region policy.

Designers should be aware that the performance of RRPMs can be compromised, especially on curves, because the groove can block motorists' view of the markers. Also, the groove for RRPMs installed on flat grades can fill with water during rain events and cause the RRPM to be non-reflective.

RRPMs, when specified, are installed at the locations shown in the *Standard Plans* for Type 2W RPMs on multilane one-way roadways and Type 2YY RPMs on two-lane two-way roadways.

Do not recess side-to-side RPMs on wide dotted lane lines.

For recessed pavement marker application details, see the *Standard Plans*.

1030.04 Guideposts

1030.04(1) General

Guideposts are retroreflective devices installed at the side of the roadway to indicate alignment. They are guidance devices rather than warning devices. Guideposts are used as an aid to nighttime driving primarily on horizontal curves; multilane divided highways; ramps; tangent sections where they can be justified due to snow, fog, or other reduced-visibility conditions; and at intersections without illumination.

1030.04(1)(a) Types of Guideposts

The retroreflective device may be mounted on either a white or brown post. The types of guideposts and their application are as follows:

1. **Type W**

   Type W guideposts have silver-white reflective sheeting, are facing traffic, and are used on the right side of divided highways, ramps, right-hand acceleration and deceleration lanes, intersections, and ramp terminals.

2. **Type WW**

   Type WW guideposts have silver-white reflective sheeting on both sides and are used on the outside of horizontal curves on two-way undivided highways.

3. **Type Y**

   Type Y guideposts have yellow reflective sheeting, are facing traffic, and are used on the left side of ramps, left-hand acceleration and deceleration lanes, ramp terminals, intersections on divided highways, median crossovers, and horizontal curves on divided highways.

4. **Type YY**

   Type YY guideposts have yellow reflective sheeting on both sides and are used in the median on divided highways.

5. **Type IC1**

   Type IC1 guideposts have silver-white reflective sheeting on both sides and an additional silver-white piece of reflective sheeting below the standard silver-white sheeting on the side facing traffic. They are used at intersections of undivided highways without illumination.

6. **Type IC2**

   Type IC2 guideposts have silver-white reflective sheeting on both sides and an additional silver-white piece of reflective sheeting below the standard silver-white reflective sheeting on the back side. They are used at intersections of undivided highways without illumination.

1030.04(2) Placement and Spacing

Guideposts are placed not less than 2 feet and not more than 8 feet outside the outer edge of the shoulder. Place guideposts at a constant distance from the edge of the roadway. When an obstruction intrudes into this space, position the guideposts to smoothly transition to the inside of the obstruction. Guideposts are not required along continuously illuminated divided or undivided highways. (See Exhibit 1030-2 for guidepost placement requirements and the *Standard Plans* for information on the different types and placement of guideposts.)

1030.05 Barrier Delineation

Traffic barriers are delineated where guideposts are required, such as bridge approaches, ramps, and other locations on unilluminated roadways (see Exhibit 1030-2). At these locations, the barrier delineation has the same spacing as that of guideposts. Barrier delineation is also required when the traffic barrier is 4 feet or less from the traveled way. Use a delineator spacing of no more than 40 feet at these locations.

Beam guardrail can be delineated by either mounting flexible guideposts behind the rail or by attaching shorter flexible guideposts to the wood guardrail posts.

Concrete barrier can be delineated by placing retroreflective devices on the face of the barrier about 6 inches down from the top. Consider mounting these devices on the top of the barrier at locations where mud or snow accumulates against the face of the barrier.

1030.06 Object Markers

Object markers are used to mark obstructions within or adjacent to the roadway. The MUTCD details three types of object markers. The Type 3 object marker with yellow and black sloping stripes is the most commonly used object marker.

The MUTCD contains criteria for the use of object markers to mark objects in and/or adjacent to the roadway. Follow these criteria in project design.

The terminal ends of impact attenuators are delineated with modified Type 3 object markers. These are the impact attenuator markers in the *Sign Fabrication Manual*. When the impact attenuator is used in a roadside condition, the marker with diagonal stripes pointing downward toward the roadway is used. When the attenuator is used in a gore where traffic will pass on either side, the marker with chevron stripes is used.

End of Roadway markers are similar to Type 1 object markers and are detailed in the MUTCD. They are used to alert users about the end of the roadway. Follow the MUTCD criteria in project design.

1030.07 Documentation

Refer to Chapter 300 for design documentation requirements.

1030.08 References

1030.08(1) Federal/State Laws and Codes

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)

1030.08(2) Design Guidance

Roadway Delineation Practices Handbook, FHWA report, Washington, DC, 1994

Standard Plans for Road, Bridge, and Municipal Construction (*Standard Plans*), M 21-01, WSDOT

Standard Specifications for Road, Bridge, and Municipal Construction (*Standard Specifications*), M 41-10, WSDOT

Exhibit 1030-1 Pavement Marking Material Guide – Consult Region Striping Policy

Roadway Classification	Marking Type [3]				
	Centerlines [5]	Lane Lines [5]	Edge Lines	Wide Lines	Transverse Markings
Ice Chisel Snow Removal Areas					
Interstate	N.A.	Grooved Plastic [1]	Paint	Paint	Paint
Major Arterial	Paint & RRPMs[4] or Plastic[2] & RRPMs[4]	Paint	Paint	Paint	Paint
Minor Arterial	Paint	Paint	Paint	Paint	Paint
Collector	Paint	Paint	Paint	Paint	Paint
Steel Blade Snow Removal Areas					
Interstate-Urban	N.A.	Plastic [2]	Paint or Plastic[2]	Paint or Plastic[2]	Paint or Plastic[2]
Interstate-Rural	N.A.	Paint	Paint or Plastic[2]	Paint or Plastic[2]	Paint or Plastic[2]
Major Arterial	Paint & RRPMs[4] or Plastic[2] & RRPMs[4]	Paint	Paint or Plastic[2]	Paint or Plastic[2]	Paint or Plastic[2]
Minor Arterial	Paint	Paint	Paint	Paint or Plastic[2]	Paint or Plastic[2]
Collector	Paint	Paint	Paint	Paint or Plastic[2]	Paint or Plastic[2]
Rubber Blade Snow Removal Areas					
Interstate-Urban	N/A	PMMA [6] only or PMMA & RPMs	Paint or Plastic[2]	Plastic	FMMA [7]
Interstate-Rural	N/A	PMMA [6] only or PMMA & RPMs	Paint	Plastic [2]	FMMA [7]
Major Arterial	Paint & RPMs or Plastic [2] & RPMs		Paint	Plastic [2]	Plastic [2]
Minor Arterial	Paint & RPMs	Paint & RPMs	Paint	Plastic [2]	Plastic [2]
Collector	Paint & RPMs	Paint	Paint	Plastic [2]	Plastic [2]

Notes:

[1] Grooved Plastic is a line constructed by cutting a groove into the pavement surface and spraying, extruding, or gluing pavement marking material into the groove.

[2] Plastic refers to methyl methacrylate (MMA), thermoplastic, or preformed tape.

[3] For RPM substitute applications and RPM applications supplementing paint or plastic, see the *Standard Plans*, Section M.

[4] RRPMs refer to RPMs installed in a groove ground into the pavement. RRPMs are identified as "Recessed Pavement Markers" in the *Standard Specifications* and the *Standard Plans*.

[5] Type 2 RPMs are not required with painted or plastic centerline or lane line in continuously illuminated sections.

[6] PMMA refers to profiled methyl methacrylate.

[7] FMMA refers to flat methyl methacrylate.

Exhibit 1030-2 Guidepost Placement

Location	Guideposts on Tangents [1][3]	Guideposts on Horizontal curves [1][3]
Divided Highways With Continuous Illumination		
Main Line	None	None
Bridge Approaches	None	None
Intersections	None	None
Lane Reductions	[4]	[4]
Median Crossovers	None	None
Ramps	[4]	[4]
Divided Highways Without Continuous Illumination		
Main Line with RPMs	None	[4]
Main Line without RPMs	Right Side Only (0.10 mile spacing)	[4]
Bridge Approaches	[4]	[4]
Intersections	[4]	[4]
Lane Reductions	[4]	[4]
Median Crossovers	[4]	[4]
Ramps	[4]	[4]
Undivided Highways With Continuous Illumination		
Main Line	None	None
Bridge Approaches	None	None
Intersections	None	None
Lane Reductions	[4]	[4]
Undivided Highways Without Continuous Illumination		
Main Line	[2]	*Standard Plans*, Section M[2]
Bridge Approaches	[4]	[4]
Intersections with Illumination	None	None
Intersections without Illumination	[4]	[4]
Lane Reductions	[4]	[4]

Notes:

[1] For lateral placement of guideposts, see the *Standard Plans*, Section M.

[2] Installation of guideposts on tangents and on the inside of horizontal curves is allowed at locations approved by the region Traffic Engineer.

[3] Barrier delineation is required when the traffic barrier is 4 feet or less from the traveled way. Use delineator spacing of 40 feet or less.

[4] *Standard Plans*, Section M

Chapter 1040 Illumination

1040.01 General
1040.02 Definitions
1040.03 Design Considerations
1040.04 Required Illumination
1040.05 Additional Illumination
1040.06 Design Criteria
1040.07 Documentation
1040.08 References

1040.01 General

Illumination is provided along highways, in parking lots, and at other facilities to enhance the visual perception of conditions or features that require additional motorist, cyclist, or pedestrian alertness during the hours of darkness.

The Washington State Department of Transportation (WSDOT) is responsible for illumination on state highways and crossroads (WAC 468-18-040 and WAC 468-18-050) with partial limited access control, modified limited access control, or full limited access control, regardless of the location. WSDOT is responsible (WAC 468-18-050) for illumination on state highways and crossroads with managed access control located outside the corporate limits of cities. Cities are responsible for illumination on managed access state highways within their corporate limits.

For the definitions of limited access control and managed access control, see Chapter 520. For a listing (by milepost) of the limited access or managed access status of all state highways, refer to the Access Control Tracking System Limited Access and Managed Access Master Plan, under the "More Information" heading: www.wsdot.wa.gov/design/accessandhearings. For further information, refer to the WSDOT/Association of Washington Cities agreement "City Streets as Part of State Highways": www.wsdot.wa.gov/localprograms/lag/construction.htm

1040.02 Definitions

The following terms are defined in the Glossary: *adaptive lighting system, average light level, complex ramp alignment and grade, continuous load, footcandle (fc), lamp lumens, light emitting diode(LED), long tunnel, lumen, luminaire, luminance, luminous flux, maximum uniformity ratio, maximum veiling luminance ratio, minimum average light level, minimum light level, mounting height – luminaire, multimodal connection, negative illumination, nighttime, pedestrian crossing, pole height (H1), positive illumination, roadway luminance, security lighting, short tunnel, SIgnal Maintenance Management System (SIMMS), slip base, spacing, transit flyer stop, transit stop, uniformity ratio,* and *veiling luminance*.

1040.03 Design Considerations

An illumination system is built from many separate components. The simplest illumination system contains the following:

- A power feed from the local utility company.

- An electrical service cabinet containing a photocell and circuit breaker for each illumination circuit.
- Runs of conduit with associated junction boxes leading to each luminaire.
- Conductors routed from the service cabinet breaker to each luminaire.
- A concrete light standard foundation.
- A light standard with a slip base or a fixed base.
- A luminaire (light) over or near the roadway edge line.

There are design considerations that need to be addressed when performing even the most minimal work on an existing illumination system. An existing electrical system is acceptable for use under the design requirements and National Electric Code (NEC) rules that were in effect at the time of installation. When modifying an existing electrical service or transformer, the designer is responsible for bringing the whole system up to current NEC design standards. Retrofitting an existing fixed base light standard with a slip base feature requires the installation of quick disconnect fittings and fuses in the circuit, at the luminaire only. The existing conductor configuration for a fixed base luminaire is not acceptable for use on a breakaway (slip base) installation. Existing conductors and components that no longer meet current NEC requirements are to be replaced and the whole circuit is to be designed to current standards. This may mean replacing the whole circuit back to the nearest overcurrent protection device (circuit breaker). Address the following when modifying an existing illumination system:

- Whether the existing circuit is in compliance with current NEC standards (deficient electrical component).
- Whether existing luminaire system components, such as conductors, conduit, junction boxes, foundation, and pole comply with current standards.
- Whether conductors meet NEC requirements for temperature rating (deficient electrical component).
- Conductor material: aluminum conductors or copper conductors (deficient electrical component).
- Whether the existing bonding and grounding system is adequate: cabinets, poles, junction boxes, including lids, and other appurtenances are bonded and grounded per NEC requirements.
- The condition and adequacy of the existing conduit running between the luminaire and the nearest junction box (deficient electrical component).
- The condition of the junction box next to the luminaire (deficient electrical component).
- The suitability of the existing foundation to meet current design requirements.
- The suitability of the location to meet current design standards for illumination.
- The location and bolt pattern of the existing foundation to meet current design standards.
- The design life remaining for the existing light standard (deficient electrical component).
- The condition of the existing light standard (deficient electrical component).

- Maintenance personnel assessment of the electrical safety of the installation.

Involve appropriate Headquarters (HQ) and region Traffic Office design personnel early in the process. Ensure potential system deficiencies are reflected in the estimate of work.

Maintain required illumination during all construction activities, except when shutdown is permitted to allow for alterations or final removal of the system per the Engineer. Site preparation, widening, drainage, guardrail installation, or other work can easily impact existing conduit runs or luminaire locations. Also, changed conditions such as merging, weaving, or unusual alignment due to traffic control often require additional temporary illumination.

Note: The same lighting requirements apply whether a condition is temporary or permanent.

Illumination is not required for minor operational enhancement projects, unless that is the specific reasoning for the project.

1040.04 Required Illumination

The following items are to be considered for each project:

- Replace standard duty junction boxes that are located in paved areas with heavy-duty junction boxes, and bring electrical components to current standards. Relocate/remove junction boxes that are located in the travel way when practical.
- Review the age of the equipment as listed in SIMMS and consider replacing components that have reached the end of their design life. Replace poles, foundations, heads, and other equipment, that have reached their design life.
- Locate components so that they can be safely accessed from the right of way.
- Ensure existing slip base features are in accordance with current design standards.
- Consider additional illumination in accordance with 1040.05, if warranted, or design additional illumination if it is called for in the Project Definition.
- When it is necessary to relocate existing light standard foundations, evaluate the entire conduit run serving those light standards and replace deficient components to current (NEC) standards.

Exhibits 1040-1a through 1040-21 show examples of illumination for roadway, transit flyer stops, parking lots, truck weigh stations, tunnels, bridges, work zones, and detour applications.

A minimum of two light standards of standard pole height are required at all design areas, with the exception of ramp terminals and entrance/exit points at minor parking lots.

1040.04(1) Freeway Off-Ramps and On-Ramps

Provide the necessary illumination for the design area of all freeway off-ramp gore areas and on-ramp acceleration tapers (see 1040.06(2) and Exhibits 1040-1a, 1b, and 1c).

1040.04(2) Freeway Ramp Terminals

Provide the necessary illumination for the design area (see Exhibit 1040-2).

1040.04(3) Freeway On-Ramps With Ramp Meter Signals

Provide the necessary number of light standards to illuminate freeway on-ramps with ramp meters, from 150' before the ramp meter stop bar to 50' past the ramp meter stop bar. When there is an HOV bypass lane or a two-lane merge beyond the ramp meter, then also provide illumination from the point where the merging lane width is 10' to 200' downstream of that point (see Exhibit 1040-3). Illumination for the ramp merge with mainline is to be done per Exhibit 1040-1b.

1040.04(4) HOT (High-Occupancy Toll) Lane Enter/Exit Zones and Access Weave Lanes

Provide the necessary number of luminaires to illuminate the design area of the enter/exit zones and access weave lanes of the HOT lane (see Exhibits 1040-4a and 4b).

1040.04(5) Lane Reduction

Provide the necessary number of light standards to illuminate the design area of all highway lane reduction areas within the urban boundary (see Exhibit 1040-5). This requirement does not apply to:

- The end of slow-moving vehicle turnouts.
- The end of the area where driving on shoulders is allowed.

1040.04(6) Intersections With Left-Turn Lane Channelization

Illumination of the intersection area is required for intersections with painted or other low-profile pavement markings such as raised pavement markings. When the channelization is delineated with curbs, raised medians, or islands, illuminate the raised channelization on the State Route from 25' before the raised channelization begins (see Exhibits 1040-6a, 6b, and 6c).

1040.04(7) Intersections With Traffic Signals

Illuminate intersections with traffic signals on state highways (see Exhibit 1040-7). In cities with a population under 25,000, the state may assume responsibility for illumination installed on signal standards.

1040.04(8) Roundabouts

Provide the necessary number of light standards to illuminate the design areas of roundabouts (see Chapter 1320 and Exhibit 1040-9).

1040.04(9) Railroad Crossings with Gates or Signals

Railroad crossings with automated gates or signals on state highways are illuminated if there is nighttime train traffic. Within the corporate limits of a city, and outside limited access control, illumination is the responsibility of the city. Install luminaires beyond the railroad crossing, on the side of the roadway opposite the approaching traffic, to backlight the train (see Exhibit 1040-10).

1040.04(10) Midblock Pedestrian Crossings

Illuminate the entire midblock pedestrian crossing, including the crosswalks, the refuge area in the roadway, and the sidewalks or shoulders adjacent to the crosswalk. When a raised median pedestrian refuge design is used, illuminate the raised channelization (see Exhibit 1040-11).

1040.04(11) Transit Flyer Stops

Illuminate the pedestrian-loading areas of transit flyer stops located within the limited access boundaries (see Exhibit 1040-12).

1040.04(12) Major Parking Lots

All parking lots with usage exceeding 50 vehicles during the nighttime peak hour are considered major parking lots. Provide an illumination design that will produce the light levels shown in Exhibit 1040-22. (See Exhibit 1040-13 for the parking design area and bus loading zone design area.) During periods of low usage at night, security lighting is required only in the parking area and bus loading zone. Provide an electrical circuitry design that allows the illumination system to be reduced to approximately 25% of the required light level.

1040.04(13) Minor Parking Lots

Minor parking lots have a nighttime peak hour usage of 50 or fewer vehicles. Provide security-level lighting for those lots owned and maintained by the state. Security lighting for a minor parking lot consists of lighting the entrance and exit to the lot (see Exhibit 1040-14).

1040.04(14) Truck Weigh Sites

Provide illumination of the roadway diverge and merge sections, scale platforms, parking areas, and inspection areas of weigh sites (see Exhibit 1040-15).

1040.04(15) Safety Rest Areas

Provide illumination within rest areas at the roadway diverge and merge sections, the walkways between parking areas and rest room buildings, and the parking areas the same as for a major parking lot (see Exhibit 1040-16).

1040.04(16) Chain-Up/Chain-Off Parking Areas

Provide the necessary number of luminaires to illuminate the design area of the chain-up/chain-off parking areas (see Exhibit 1040-17) on State Routes 2, 12, and 90 where a power distribution point is within a half mile and power is readily accessible. Illumination is to be installed in the median and on the right shoulder to provide lighting on both sides of the stopped vehicles. Luminaires should only be energized during periods when traction tires are required and vehicles over 10,000 pounds are required to use chains.

1040.04(17) Tunnels, Lids, and Underpasses

For the purposes of this chapter, a tunnel is a structure over a roadway, which restricts the normal daytime illumination of a roadway section such that the driver's visibility is substantially diminished. Tunnels cover roadways and produce a shadow that limits the ability of the driver to see objects or obstructions within the tunnel. In most locations, no supplemental daytime

lighting is required for underpasses or structures less than 80 feet in length. Provide both nighttime and daytime lighting for long tunnels. (See ANSI/IES publication RP-22-11 for tunnel lighting design criteria.) Provide vandal-resistant daytime and nighttime security lighting in pedestrian tunnels. Short tunnels and underpasses where the exit portal is not visible from the entrance portal due to curvature of the roadway are to be considered long tunnels.

1040.04(18) Bridge Inspection Lighting

Provide the necessary number of light fixtures and electrical outlets to illuminate the interior inspection areas of floating bridges, steel box girder bridges and concrete box girder bridges where access is provided (see Exhibit 1040-18). Separate circuits are to be used for lighting and electrical outlets. Each electrical outlet is to be powered by 2 Duplex receptacles on two separate circuits. All electrical outlets are to be labeled with circuit identifications. Coordinate bridge illumination requirements with the HQ Bridge and Structures Office.

1040.04(19) Same Direction Traffic Split Around an Obstruction

Provide the necessary number of light standards to illuminate the design area where traffic is split around an obstruction. This requirement applies to permanent and temporary same-direction split channelization. For temporary work zones, illuminate the obstruction for the duration of the traffic split (see Exhibit 1040-19).

1040.04(20) Diverging Diamond Interchange

Provide the necessary number of light standards to illuminate the design area shown in Exhibit 1040-21. The design area starts 25’ before the raised channelization as you approach the interchange and continues through the interchange until 25’ past the raised channelization as you exit the interchange.

1040.05 Additional Illumination

At certain locations, additional illumination is desirable to provide better definition of nighttime driving conditions or to provide consistency with local agency goals and enhancement projects. For Improvement projects on state highways, additional illumination could be reviewed as a crash countermeasure under certain circumstances, which are listed in this section.

1040.05(1) Conditions for Additional Illumination

Following are some conditions used in making the decision to provide additional illumination:

1040.05(1)(a) Crash Analysis

The following conditions have to be met when making the decision to provide additional illumination:

- During the last full five calendar years, the site has experienced nighttime crashes that are correctable with illumination, AND
- The benefit-cost analysis for the proposed illumination exceeds 1, AND
- Alternative lower-cost countermeasures have been evaluated and did not address the particular nighttime crash history.

Nighttime crashes are defined as crashes occurring between half an hour after sunset and half an hour before sunrise. Correctable nighttime crashes are crashes that (a) meet the nighttime definition in this chapter, (b) have contributing factors related to a lack of lighting, and (c) where lighting, if installed, would directly address the contributing factor(s) to the crashes.

Collision reporting forms and the crash data are not adequate means to distinguish between day and nighttime conditions: the crash location, the reported crash times, and seasonal variations should be used to determine which crashes qualify as nighttime crashes. Also:

- For sites where the number of nighttime crashes equals or exceeds the number of daytime crashes, the above-mentioned crash and benefit-cost analysis should be performed.
- For sites where these nighttime crashes involve pedestrians, refer to 1040.05(11).

1040.05(1)(b) Locations With Nighttime Pedestrian Crashes

The mitigation of nighttime pedestrian crashes requires different lighting strategies than vehicular crash locations. Provide light levels to emphasize crosswalks and adjacent sidewalks by using positive lighting of the pedestrians.

Multilane highways with two-way left-turn lanes, in areas transitioning from rural land use to urban land use, or areas experiencing commercial growth or commercial redevelopment, are typically high-speed facilities with numerous road approaches and driveways. These approaches allow numerous vehicle entry and exit points and provide few crossing opportunities for pedestrians; consider additional illumination.

1040.05(2) Highways

Proposals to provide full (continuous) illumination require the approval of the Region and State Traffic Engineers. Regions may choose to develop (regional or corridor-specific) system plans for providing full (continuous) illumination. The State Traffic Engineer's approval of a system plan will eliminate the need for a project-specific approval from the State Traffic Engineer. Continuous illumination can be provided inside city limits at the city's request provided the city takes on the maintenance and operational costs and responsibilities of maintaining and operating the system.

The decision whether to provide full (continuous) illumination is to be made during the scoping stage and communicated to the designers as soon as possible.

Continuous illumination should be considered when the crash analysis requirements in 1040.05(1) are met and a benefit/cost analysis between the required and full (continuous) illumination exceeds 1.

On the main line of highways without full limited access control, consider full (continuous) illumination if the segment of highway is in a commercial area and the crash analysis requirements in 1040.05(1) are met, has raised channelization, has medium or high pedestrian activity during night time hours, and an engineering study indicates that nighttime driving conditions will be improved.

1040.05(3) Ramps

Consider additional illumination at ramps where the alignment or grade is complex.

1040.05(4) Crossroads

Consider additional illumination if the crossroad is in a short tunnel, an underpass, or a lid.

1040.05(5) Intersections Without Turn-Lane Channelization

Refer to Exhibit 1040-8.

1040.05(6) Short Tunnels, Underpasses, or Lids

Consider illumination of the sidewalk, walkway, or shared-use path if it is included as part of the short tunnels, underpasses, or lids.

1040.05(7) Work Zones and Detours

Consider temporary illumination of the highway through work zones and detours when changes to the highway alignment or grade remain in place during nighttime hours. Exhibit 1040-20 illustrates considerations for temporary illumination, such as reduced roadway widths, work zone lane shifts, and median cross overs.

For further information on illumination in work zones, see Chapter 1010.

1040.05(8) Transit Stops

The responsibility for lighting at transit stops is shared with the transit agency. Consider illuminating transit stops with shelters as they usually indicate greater passenger usage. Negotiation with the transit agencies is required for the funding and maintenance of this illumination. Negotiating a memorandum of understanding (MOU) with each transit agency is preferred over spot negotiations. If the transit agency is unable or unwilling to participate in the funding and maintenance of the illumination, consider a single light standard positioned to illuminate both the transit pullout area and the loading area.

1040.05(9) Bridges

Justification for illuminating the roadway/sidewalk portion of bridges is the same as that for highways on either end of the bridge with or without full limited access control, as applicable. Justification for illuminating the architectural features of a bridge structure requires the approval of the State Traffic Engineer. For justification for illuminating pedestrian walkways or bicycle trails under a bridge, see 1040.05(11).

1040.05(10) Railroad Crossing Without Gates or Signals

Consider the illumination of railroad crossings without gates or signals when:

- The crash history indicates that motorists experience difficulty in seeing trains or control devices.
- There are a substantial number of rail operations conducted during nighttime hours.
- The crossing is blocked for long periods due to low train speeds.
- The crossing is blocked for long periods during the nighttime.

For further information, see the MUTCD.

1040.05(11) Sidewalks, Walkways, and Shared-Use Paths

Consider illumination of a pedestrian walkway if the walkway is a connection between two highway facilities. This could be between parking areas and rest room buildings at rest areas; between drop-off/pick-up points and bus loading areas at flyer stops; or between parking areas and bus loading areas or ferry loading zones. Consider illuminating existing sidewalks, walkways, and shared-use paths if security problems have been reported or are anticipated. Under these conditions, these facilities are illuminated to the level shown in Exhibit 1040-22.

1040.06 Design Criteria

1040.06(1) Light Levels

Light levels vary with the functional classification of the highway, the development of the adjacent area, and the level of nighttime activity. Light level requirements for highways and other facilities are shown in Exhibit 1040-22. These levels are the minimum average light levels required for a design area at the end of rated lamp life for applications requiring a spacing calculation. Light level requirements are not applicable for single light standards or security lighting installations where:

- The light level is reduced to approximately 25% of the required light level in parking lots and parking lot loading areas during periods of low usage at night.
- Walkway or path illumination is installed only at areas where shadows and horizontal and vertical geometry obstruct a pedestrian's view.
- Light level requirements are applicable when:
- The complete walkway or path is to be illuminated for public safety.

The access areas used for interior inspection of floating bridges or steel box/concrete box girder bridges are exempt from lighting level and lighting ratio design requirements.

For functional classifications of highways, see:
www.wsdot.wa.gov/mapsdata/travel/hpms/functionalclass.htm

1040.06(1)(a) Activity Areas

The types of activity areas (shown below) are related to the number of pedestrian crossings through the design area. These crossings need not occur within a single crosswalk and can be at several locations along the roadway in an area with pedestrian generators. Land use and activity classifications are as follows:

1040.06(1)(a)(1) High Activity

Areas with over 100 pedestrian crossings during nighttime peak hour pedestrian usage. Examples include downtown retail areas; near outdoor stage theaters, concert halls, stadiums, and transit terminals; and parking areas adjacent to these facilities.

1040.06(1)(a)(2) Medium Activity

Areas with pedestrian crossings that number between 11 and 100 during nighttime peak hour pedestrian usage. Examples include downtown office areas; blocks with libraries, movie

theaters, apartments, neighborhood shopping, industrial buildings, and older city areas; and streets with transit lines.

1040.06(1)(a)(3) Low Activity

Areas with pedestrian crossings that number less than 11 during the nighttime peak hour pedestrian usage. Examples include suburban single-family areas, low-density residential developments, and rural or semirural areas.

1040.06(2) Design Areas

The design area is that portion of the roadway, parking lot, or other facility subject to the minimum light level, minimum average light level, uniformity ratio, and maximum veiling luminance ratio design requirements. This encompasses the area between the edges of the traveled way along the roadway; the outer edges of the stopping points at intersections; and, when present, a bike lane adjacent to the traveled way. When the roadway has adjacent sidewalks and is located in a medium or high pedestrian activity area, the design area includes these features; however, sidewalks adjacent to the traveled way are exempt from maximum veiling luminance ratio requirements.

1040.06(2)(a) Design Area Requirements

Design area requirements for various applications are shown in Exhibits 1040-1a through 1040-21 and are described in the following:

1040.06(2)(a)(1) Single-Lane Off-Ramp

Two main line through lanes and the ramp lane, including gore area, from the gore point (beginning of wide line) to a point 200 feet (minimum) downstream of the gore point. A 100 foot longitudinal tolerance either way from the gore point is allowed.

1040.06(2)(a)(2) Two-Lane Off-Ramp

Two main line through lanes and both ramp lanes, including gore area, from a point 200 feet upstream of the gore point (beginning of wide line) to a point 200 feet downstream of the gore point. A 100-foot longitudinal tolerance either way from the gore point is allowed.

1040.06(2)(a)(3) Single-Lane On-Ramp

Two main line through lanes and the ramp lane, from a point where the ramp lane is 10 feet wide to a point 200 feet downstream. A 100-foot longitudinal tolerance either way is allowed; this includes auxiliary lane on-connections and lane reductions.

1040.06(2)(a)(4) Two-Lane On-Ramp

Two main line through lanes and the ramp lanes from a point where the ramp width is 22 feet wide to a point 200 feet upstream and 200 feet downstream. A 100-foot longitudinal tolerance either way is allowed.

1040.06(2)(a)(5) Intersections Channelized With Pavement Markings

When the leg of an intersection is two lanes wide or less, the design area starts at the stop bar and encompasses the intersection area. When the leg of an intersection is three or more lanes wide, the design area starts 25’ before the stop bar and encompasses the intersection area.

1040.06(2)(a)(6) Intersections With Raised Channelization

The design area has two components: the intersection area and the approach areas. When the leg of an intersection is two lanes wide or less, the intersection design area starts at the stop bar and encompasses the intersection area. When the leg of an intersection is three or more lanes wide, the intersection design area starts 25 feet before the stop bar and encompasses the intersection area on both the main road and the minor road, including marked or unmarked crosswalks. The approach areas are the areas on the main roadway between the intersection design area and where the left-turn taper begins.

1040.06(2)(a)(7) Unchannelized Intersection

The area between the stopping points on both the main road and the minor road, including marked or unmarked crosswalks.

1040.06(2)(a)(8) Railroad Crossing

The roadway width from a point 50 feet on either side of the track (the approach side only for one-way roadways).

1040.06(2)(a)(9) Transit Loading Area

The lane width and length designated for loading.

1040.06(2)(a)(10) Major Parking Lot

The entire area designated for parking, including internal access lanes.

1040.06(2)(a)(11) Scale Platform at Weigh Site

The approach width from the beginning of the scale platform to the end of the platform.

1040.06(2)(a)(12) Inspection Area at Weigh Site

The area dedicated to inspection as agreed upon with the Washington State Patrol.

1040.06(2)(a)(13) Bridge Inspection Lighting System

Fixtures are to be ceiling mounted. For steel box girders bridges, the spacing shall not be greater than the smaller of 4 times the web depth or 25 ft. For concrete box girder bridges, the spacing shall not be greater than the smaller of 8 times the web depth or 50 ft. Illumination is to consists of a 100 watt incandescent (or fluorescent equivalent) fixture. The bulb should have a minimum of 1600 lumens. Each fixture is to be designed with a 20 amp rated ground fault circuit interrupt (GFCI) receptacle. A light switch is needed at each entrance to any common inspection area. For inspection areas with two or more entrances, three-way or four-way switches are required.

1040.06(3) Daytime Light Levels for Tunnels, Lids, and Underpasses

It is important to provide sufficient illumination inside a tunnel. When driving into and through a tunnel during the day, a driver's eyes have to adjust from a high light level (daylight) to a lower lighting level inside the tunnel. Motorists require sufficient time for their eyes to adapt to the lower light level of the tunnel itself. When sufficient lighting is not provided in the threshold, transition, or interior zones of a tunnel, a motorist's eyes may not have enough time to adapt and may experience a "black hole" or "blackout" effect. This "black hole" effect may cause a motorist to slow down, reducing the efficiency of the roadway. When leaving the tunnel, the

driver's eyes have to adjust from a low lighting level back to daytime conditions. The full design considerations for tunnel lighting are covered in 1040.08(2) in the Design Guidance section.

- All designs for illuminating tunnels are to be reviewed and approved by the State Traffic Engineer.
- Long tunnels are divided into zones for the determination of daytime light levels. The zones are Threshold Zone, Transition Zone(s), and Interior Zone. Each zone length is calculated using the method described in ANSI/IES RP-22-11.
- The designer of a long tunnel shall perform a Lseq (Equivalent Veiling Luminance) calculation. Lseq values obtained from this calculation shall be used to reduce (or increase) the Suggested Daytime Maintained Average Pavement Luminance Levels where indicated.
- Tunnel wall illumination is required.
- The approach and exit roadways shall have a nighttime luminance level of no less than one third of the tunnel interior level for one safe stopping sight distance (SSSD).
- Provide illumination of fire protection equipment, alarm pull boxes, phones, and emergency exits in long tunnels. (See NFPA 502 for additional information.)
- Short tunnels and underpasses in rural areas or with low pedestrian usage normally do not have daytime illumination. Short tunnels and underpasses in urban areas with high pedestrian usage may require daytime and nighttime illumination. Consultation with the affected local agency is recommended. Short tunnels and underpasses are treated the same as an entrance zone on a long tunnel to establish daytime light levels.
- Nighttime light level requirements for short tunnels on continuously illuminated roadways are the same as the light level required on the roadway outside the tunnel.

1040.06(4) Light Standards

1040.06(4)(a) Light Standards on State Highway Facilities

Light standards are the most common supports used to provide illumination for highway facilities. The 40-foot light standard with a slip bases and Type 1 mast arm is predominantly used on state highways. In areas with continuous illumination, 50-foot light standards may be used. Use Type 1 mast arms on all new systems and when modifying existing systems. Cities and counties may elect to use different mounting heights to address factors unique to their environments. On state highways, alternative colored light standards may be considered if requested by the city or county, provided they agree to pay any additional costs associated with this change.

The typical location for a light standard is on the right shoulder. When considering designs for light standards mounted on concrete barrier in the median, consider the total life cycle cost of the system, including the user costs resulting from lane closures required for relamping and repair operations, and higher maintenance costs since the work will most likely be done during night time hours due to decreased traffic volumes. Region Signal Maintenance approval is required for all median mounted luminaires except chain on/off areas. Light standards located in the vicinity of overhead power lines require a minimum 10 foot circumferential clearance from the power line (including the neutral conductor) to any portion of the light standard or luminaire. Depending on the line voltage, a distance greater than 10 feet may be required (WAC

296-24-960). Consult the HQ Bridge and Structures Office when mounting light standards on structures such as retaining walls and bridge railings.

It is preferable to locate a light standard as far from the traveled way as possible to reduce the potential for impacts from errant vehicles. The typical luminaire position is mounted directly over the edge line plus or minus 4 feet. However, some flexibility is acceptable with the luminaire position to allow for placement of the light standard provided light levels, uniformity, and maintenance considerations are also addressed and with the Region Traffic Engineer's approval. On Type III signal standards, luminaires may be placed more than 4 feet from the edge line.

Standard mast arm lengths are available in 2-foot increments between 6 and 16 feet. The preferred design for a single-arm light standard is a 16-foot mast arm installed on a 40-foot standard. The maximum allowable mast arm length for a single-arm light standard is 16 feet. The preferred design for a double mast arm light standard has mast arms between 6 feet and 12 feet in length, installed on a 40-foot standard. The maximum allowable mast arm length for a double luminaire light standard is 12 feet.

When light standards are located within the Design Clear Zone, breakaway and slip base features are used to reduce the severity of an impact. (See Chapter 1600 for additional guidance on clear zone issues.)

In curb and sidewalk sections, locate the light standard behind the sidewalk. In locations where the light standard cannot be placed behind the sidewalk and still have the luminaire mounted within 4' of the edge line, the luminaire should be located in the sidewalk. Slip bases on light standards are a safety requirement for roadways where the posted speed is 35 mph or higher. They are not always desirable at other locations. Fixed bases are installed in the following locations:

- Roadway with speeds below 35 mph.
- Parking lots.
- Medians where the light standard is mounted on median barrier.
- Behind traffic barrier, beyond the barrier's deflection design value (see Chapter 1610).
- Along pedestrian walkways, bike paths, and shared-use paths outside of the roadway clear zone.

1040.06(4)(b) Light Standard Heights

Standard pole heights (20-foot, 30-foot, or 40-foot) are readily available from local distributors and manufacturers. Light standards can also be supplied with other lengths. However, WSDOT Maintenance offices cannot stock poles with nonstandard lengths for use as replacements in the event of a knockdown. Nonstandard lengths in 5-foot increments (25-foot, 35-foot, or 45-foot) will require a longer delivery time. Other nonstandard lengths (for example, 27-foot, 33-foot, or 37-foot) will not only require a longer delivery time, they will also be more expensive.

In almost all cases, use a standard pole heights of 40 feet for roadway illumination. Structure-mounted light standards may need to be shorter than the standard 40-foot grade-mounted pole. It is acceptable to use 20-foot or 30-foot light standards on bridges, retaining walls, or other structures to compensate for top-of-structure elevation above the roadway surface. Luminaires with a mounting height over 40 feet should only be used in continuously illuminated areas that are not in residential areas. Use of these standard pole heights will result in variable mounting heights for the luminaires. Luminaire mounting height is defined as the actual

distance from the roadway surface directly under the luminaire to the luminaire itself. Use the actual mounting height at each location when calculating light standard spacing. Luminaires with a mounting height over 50 feet require lowering devices.

High mast light supports may be considered for complex interchanges where continuous lighting is justified. High mast lighting may be considered for temporary illumination areas during construction. Initial construction costs, long-term maintenance, clear zone mitigation, spillover light onto adjacent properties, and negative visual impacts are important factors when considering high mast illumination.

Shorter light standards of 30 feet or less may be used for minor parking lots, trails, pedestrian walkways, and locations with restricted vertical clearance.

1040.06(4)(c) Standard Luminaire

The standard luminaire in use now for roadway lighting is a cobra head style type III LED fixture. The list of LED fixtures approved for use on WSDOT projects can be found at:
http://www.wsdot.wa.gov/Design/Traffic/ledluminaires.htm

For continuously illuminated area a type V distribution pattern can be used for the interior areas with type III distribution on the perimeters.

1040.06(4)(d) Electrical Design

For an example of circuit layout, conductor sizing, conduit sizing, overcurrent protection device sizing, and other electrical design calculations, see the Power Supply Design material located at:
http://www.wsdot.wa.gov/design/traffic/electrical/training.htm

An example of illumination design grid layouts and calculations is located in the Illumination Design for Transportation Applications material located in the link above.

The illumination circuitry is to be laid out so that if four or more luminaires are installed, it should have a minimum of two circuits. The intent is to make sure that if a circuit fails, there will still be partial lighting from the other circuits.

The maximum allowable junction box spacing is as follows:

1. 360 feet allowed between in grade junction boxes with a straight pull.
2. 180 feet when conduit run is along a curve or when the conduit makes a 30 degree or greater change in direction.
3. 180 feet between NEMA junction boxes in traffic barrier, retaining wall, or structure.
4. A junction box is required within 5 feet minimum (preferred) & 10 feet maximum of the luminaire base, regardless of the luminaire spacing.
5. 360 feet between NEMA junction boxes when fiber optic cable is run through conduit in traffic barrier, retaining wall, or structure.
6. Pull Box interconnect to Traffic Signal – spacing is 500 feet maximum. Disclaimer: This would only apply to a single fiber optic cable.
7. 1,000 feet between cable vaults or pull boxes – main line fiber optic cable.

1040.06(5) Adaptive Lighting

Adaptive Lighting Systems may be used at select locations where changing traffic conditions allow for lowering of light levels or the changing of a required design area. Some examples would be: the Pedestrian/Area Classification changes requiring different levels; traffic volumes drop sharply; or chain up/chain off areas. Region and State Traffic Engineers' approval is required for adaptive lighting systems.

1040.07 Documentation

Justify and document any additional illumination in the Design Documentation Package (DDP).

The approval from maintenance to install median mounted luminaires can be an email or memo from the area maintenance superintendent and is kept in the design file.

Any areas in this section that says to "consider" a design element should have the logic of the consideration and decision documented in the design file for future reference.

Refer to Chapter 300 for design documentation requirements.

1040.08 References

1040.08(1) Federal/State Laws and Codes

National Electrical Code (NEC), NFPA, Quincy, MA

Revised Code of Washington (RCW) 47.24.020, Jurisdiction, control

Washington Administrative Code (WAC) 296-24-960, Working on or near exposed energized parts

WAC 468-18-040, Design standards for rearranged county roads, frontage roads, access roads, intersections, ramps and crossings

WAC 468-18-050, Policy on the construction, improvement and maintenance of intersections of state highways and city streets

1040.08(2) Design Guidance

American National Standard Practice for Roadway Lighting, IES RP-8-00, New York, NY 2000

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)

NFPA 502: Standard for Road Tunnels, Bridges, and Other Limited Access Highways, NFPA, Quincy, MA 2011

Recommended Practice for Tunnel Lighting, IESNA RP-22-05, New York, NY 2011

Roadway Lighting Design Guide, AASHTO, October 2005

Roadway Lighting Handbook, Addendum to Chapter Six: Designing the Lighting System Using Pavement Luminance, Federal Highway Administration, Addendum to Implementation Package 78-15, Washington, DC 1983

Roadway Lighting Handbook, Federal Highway Administration, Implementation Package 78-15, Washington, DC 1978 (Reprinted April 1984)

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT

1040.08(3) Supporting Information


A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO, Current Edition

An Informational Guide for Roadway Lighting, AASHTO, Washington, DC 1984


City Streets as Part of State Highways Guidelines Reached by the Washington State Department of Transportation and the Association of Washington Cities on Interpretation of Selected Topics of RCW 47.24 and Figures of WAC 468-18-050 for the Construction, Operations and Maintenance Responsibilities of WSDOT and Cities for such Streets, 4-30-1997 amended 4-2-2013

Light Trespass: Research Results and Recommendations, IES TM-11-00, New York, NY 2000


Exhibit 1040-1a Freeway Lighting Applications



Required Illumination for a Typical Diamond Interchange
Shown for single-lane ramp connection and a two-lane crossroad without channelization.




Single-Lane Off-Connection
The design area may be shifted up to 100 ft from the beginning of the wide line; a minimum of two light standards of standard pole height required for design area.




Two-Lane Off-Connection: One Exit Only Lane; One Optional Lane
The design area may be shifted up to 100 ft from the beginning of the wide line; a minimum of three light standards of standard pole height required for design area.

Exhibit 1040-1b Freeway Lighting Applications




Single-Lane On-Connection

The design area may be shifted up to 100 ft from the 10-ft-wide ramp point; a minimum of two light standards of standard pole height required for design area.



Auxiliary Lane at On-Connection


The design area may be shifted up to 100 ft from the end of wide line; a minimum of two light standards of standard pole height required for design area.



Two-Lane On-Connection: One Auxiliary Lane; One Merge Lane


The design area may be shifted up to 100 ft from the 22-ft-wide ramp point; a minimum of three light standards of standard pole height required for design area.

Exhibit 1040-1c Freeway Lighting Applications



Single Exit-Only Lane


The design area may be shifted up to 100 ft from the end of lane and the beginning of wide line; a minimum of two light standards of standard pole height required for design area.




Two Exit-Only Lanes

The design area may be shifted up to 100 ft from the end of lane and the beginning of wide line; a minimum of three light standards of standard pole height required for design area.

Exhibit 1040-2 Freeway Ramp Terminals




Off Ramp with Single-Lane Crossroad




Off-Ramp with Multilane Crossroad

Exhibit 1040-3 Ramp with Meter




Single-Lane On-Ramp




Multilane On-Ramp with HOV Bypass Lane

Exhibit 1040-4a HOT (High-Occupancy Toll) Lane Enter/Exit Zone




A minimum of two light standards of standard pole height required for each design area.

Exhibit 1040-4b HOT (High-Occupancy Toll) Lane ACCESS WEAVE LANE



TOLL LANE ACCESS WEAVE LANE

Exhibit 1040-5 Lane Reduction



A minimum of two light standards of standard pole height required for design area;

design area may be shifted 100 ft.

Exhibit 1040-6a Intersection with Left-Turn Channelization: Divided Highway






Exhibit 1040-6b Intersections with Left-Turn Channelization




Intersection with Low-Profile Left-Turn Channelization Pavement Markings

Exhibit 1040-6c Intersections with Raised Left-Turn Channelization




Intersection with Raised Left-Turn Channelization


Exhibit 1040-7 Intersections with Traffic Signals




Four-Way Intersection with Single-Lane Approaches



Four-Way Intersection with Multilane Major Approaches
A minimum of two light standards required for design area.



Minor Tee Intersection



Major Tee Intersection
A minimum of two light standards is required for design area.

Exhibit 1040-8 Intersection without Channelization





Exhibit 1040-9 Roundabout



Notes

1. Exclude Truck Apron from lighting calculations.
2. Exclude the portion inside the 2ft offset areas of the raised channelization islands from calculation.
3. All channelization 2ft wide or less is included in the Approach Design Area calculation.
4. When a leg of the roundabout is a one-way roadway, the Approach Design Area starts at the beginning of the raised channelization, or 50ft from the outside edge of the circulating roadway, or 50ft beyond a sidewalk, whichever is further.
5. A sidewalk is included in the Intersection Design Area calculation when a planting strip is less than 15ft wide.
6. Install luminaire to provide positive illumination of raised channelization. The preferred luminaire location would be from 20’ to one mounting height’s distance in front of the raised channelization.
7. Do not install luminaire in the area from 20’ in front of the crosswalk to 20’ past the crosswalk.
8. Install luminaire to provide positive illumination of the crosswalk for approaching vehicles. The preferred luminaire location would be one mounting height’s distance in front of the crosswalk.
9. If approach intersection area requires more than one luminaire, the last luminaire on that approach chain can be replaced with a ground-mounted, internally illuminated bollard with sign in place of 2nd luminaire.

Exhibit 1040-10 Railroad Crossing with Gates or Signals





Exhibit 1040-11 Midblock Pedestrian Crossing



A minimum of two light standards of standard height is required for the design area.

Exhibit 1040-12 Transit Flyer Stop




Exhibit 1040-13 Major Parking Lot




Exhibit 1040-14 Minor Parking Lot




Exhibit 1040-15 Truck Weigh Site





Exhibit 1040-16 Safety Rest Area



Legend

- Diverge/Merge Design Area
- Truck Parking Design Area
- Passenger Vehicle Parking Design Area
- Pedestrian Walkway Design Area
- Walkway/Bicycle Trail

Exhibit 1040-17 Chain-Up/Chain-Off Parking Area






Exhibit 1040-18 Bridge Inspection Lighting System



Maximum Lighting Fixture Spacing (S):

Steel Box Girder Bridge S= 4 x (WEB DEPTH) ≤ 25 FT
Conrecte Box Girder Bridge S = 8 x (WEB DEPTH) ≤ 50 FT


Exhibit 1040-19 Traffic Split Around an Obstruction




Note:

For temporary work zone plan applications, a site-specific traffic control plan is required. Refer to Chapters 1610 and 1620 for traffic barrier and attenuator information, Chapter 1010 for work zone information, and Chapter 1020 for signing information.

Exhibit 1040-20 Construction Work Zone and Detour



Detour Traffic



Legend

Design Area

Lane Closure with Barrier and Signals without Flaggers or Spotters

One-direction closure shown/other direction closure typical.

Note:

For temporary work zone plan applications, a site-specific traffic control plan is required. Refer to Chapters 1610 and 1620 for traffic barrier and attenuator information, Chapter 1010 for work zone information, and Chapter 1020 for signing information. Refer to the MUTCD Typical Application 12 for additional details.

Exhibit 1040-21 Diverging Diamond Interchange




Exhibit 1040-22 Light Levels and Uniformity Ratios

Light Level and Uniformity Ratio Chart					
Highway Design Class	**Minimum Average Maintained Horizontal Light Level** [2]			**Maximum Uniformity Ratio** [5]	**Maximum Veiling Luminance Ratio** [6]
	Pedestrian/Area Classification				
	High (footcandles)	**Medium (footcandles)**	**Low (footcandles)**		
Highways With Full Access Control [1][8]					
Main Line	0.6	0.6	0.6	4:1	0.3:1
Ramps	0.6	0.6	0.6	4:1	0.3:1
Crossroads	0.6	0.6	0.6	4:1	0.3:1
Ramp Intersections	0.9	0.9	0.9	4:1	0.3:1
Highways Without Full Access Control [3][8]					
Main Line	1.2	0.9	0.6	4:1	0.3:1
Intersections	1.2	0.9	0.9	4:1	0.3:1
Other Illuminated Features					
Construction Lanes and Detours	1.0	1.0	1.0	4:1	0.3:1
Major Parking Lots/Rest Areas	0.8	0.8	0.8	4:1	0.3:1
Vehicle Inspection Areas	2.0	2.0	2.0	4:1	0.3:1
Sidewalks, Walkways & Shared Use Paths	0.8	0.8	0.8	4:1	0.3:1
Weigh Scales	0.8	0.8	0.8	4:1	0.3:1
Transit Stops [4]	2.0	2.0	2.0	NA [7]	0.3:1
Midblock Ped X-ing	2.0	2.0	2.0	4:1	0.3:1

Notes:

[1] The minimum light level is 0.2 footcandle (fc) for any application with a minimum average maintained horizontal light level of 0.6 fc. The minimum light levels for all other applications are controlled by the uniformity ratio.

[2] Light level and uniformity ratio apply only when installation of more than one light standard is justified.

[3] Light levels shown also apply to modified and partial limited access control.

[4] For single light standard installations, provide the light level at the location where the bus stops for riders (see Exhibit 1040-12).

[5] Minimum Average Maintained Light Level/Minimum Light Level = Maximum Uniformity Ratio.

[6] Maximum Veiling Luminance/Average Luminance = Maximum Veiling Luminance Ratio.

[7] The Maximum Uniformity Ratio is 4:1 when more than one light standard is justified.

[8] Roundabout illumination shall meet intersection lighting requirements for the associated roadway classification.

Chapter 1050 Intelligent Transportation Systems

1050.01 General
1050.02 References
1050.03 Systems Engineering
1050.04 FHWA Washington Division ITS Project Contracting Guidance
1050.05 Documentation

1050.01 General

Intelligent Transportation Systems (ITS) have the potential to reduce crashes and increase mobility of transportation facilities. They also enhance productivity through the use of advanced communications technologies and their integration into vehicles and the transportation infrastructure. These systems involve a broad range of wireless and wire line communications-based information, electronics, or information processing technologies. Some of these technologies include cameras, variable message signs, ramp meters, road weather information systems, highway advisory radios, traffic management centers, and adaptive signal control technology (ASCT). ASCT is a traffic signal system that detects traffic conditions and adjusts signal timing remotely in response. More information on ASCT can be found at:
www.fhwa.dot.gov/everydaycounts/technology/adsc

The purpose and direction of ITS for the Washington State Department of Transportation (WSDOT) can be found in the Statewide Intelligent Transportation Systems Plan, which is available upon request from the Headquarters (HQ) Traffic Operations Office. The plan identifies the current and long-term ITS needs to meet the objectives identified in Moving Washington, WSDOT's program to fight traffic congestion.

The Statewide ITS Plan is a comprehensive document that discusses:

- The history of ITS deployment in Washington.
- How ITS meets WSDOT's transportation vision and goals.
- The current state of ITS deployment.
- WSDOT's near-term ITS plans.
- How projects are prioritized.
- What long-term ITS issues WSDOT needs to begin planning for.

Due to the dynamic nature of ITS, printed guidance is soon outdated. Detailed design guidance and current practices are located on the following websites. For additional information and direction, contact the region Traffic Engineer or the HQ Traffic Operations Office:
www.wsdot.wa.gov/design/traffic/

1050.02 References

23 Code of Federal Regulations (CFR), Part 940, Intelligent Transportation System Architecture and Standards
http://www.ecfr.gov

USDOT, *Systems Engineering for Intelligent Transportation Systems*, FHWA-HOP-07 069, January 2007
http://ops.fhwa.dot.gov/publications/seitsguide/index.htm

USDOT/CalTrans, *Systems Engineering Guidebook for Intelligent Transportation Systems*, Version 3, November 2009
http://www.fhwa.dot.gov/cadiv/segb/

USDOT, *Model Systems Engineering Documents for Adaptive Signal Control Technology (ASCT) Systems*, FHWA HOP-11-027, August 2012
http://www.ops.fhwa.dot.gov/publications/fhwahop11027/index.htm

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)
www.wsdot.wa.gov/publications/manuals/mutcd.htm

SAFETEA-LU (Safe Accountable Flexible Efficient Transportation Equity Act: A Legacy for Users)
http://www.fhwa.dot.gov/safetealu/index.htm

MAP-21 (Moving Ahead for Progress in the 21st Century Act)
http://www.fhwa.dot.gov/map21/

WSDOT Northwest Region Traffic Design
http://www.wsdot.wa.gov/northwest/trafficdesign

WSDOT Traffic Design
http://www.wsdot.wa.gov/design/traffic/

1050.03 Systems Engineering

Systems engineering is a typical part of any ITS project development process. It is required on any federal-aid project that has an ITS work element, per 23 CFR 940.11. Systems engineering is an interdisciplinary step-by-step process for complex projects (such as ITS projects) to:

- Assess a system's needs and its relationship to the regional architecture.
- Plan a project that meets those needs as well as stakeholder needs and expectations.
- Define other specific requirements for the project/system.
- Develop and implement the project/system.
- Define the operations and maintenance requirements for the system.
- Plan for the refinement or replacement of the system.

Using systems engineering on ITS projects has been shown to increase the likelihood of a project's success. A successful project is one that meets the project scope and stakeholder/ project sponsor expectations, is completed on time and within budget, and is efficient and cost-effective to operate and maintain.

The level of systems engineering used for a project should be on a scale commensurate with the scope, cost, and risk of the project. Complete the Intelligent Transportation Systems (ITS) Systems Engineering Analysis Worksheet in Exhibit 1050-2, or a document with the same information, for all federal-aid projects that include ITS elements. Completing the Worksheet will meet the minimum requirements in 23 CFR 940.11 for systems engineering, determine the project's risk, and determine if a more in-depth systems engineering analysis is required. The Worksheet and the four systems engineering documents outlined below are to be completed with coordination between the project engineer and region Traffic Engineer.

As shown in the Worksheet, a more in-depth analysis requires that the following four documents be completed and used to implement the project. These documents are produced as the result of the steps in the systems engineering process.

1. **Concept of Operations:** This document defines the problem, the project's goals, stakeholder needs and expectations, constraints, and the way the ITS system is required to operate and be maintained.

2. **System Requirements:** This document contains specifications of what the system is required to do, how well it is required to do it, and under what conditions. These requirements are based on the goals, stakeholder needs and expectations, constraints, and operation and maintenance requirements documented in the Concept of Operations.

3. **System Verification Plan:** This document describes how the agency will verify that the system being built meets the requirements in the System Requirements document. The agency will implement the System Verification Plan to ensure all system requirements are verified before it accepts the system.

4. **System Validation Plan:** This document describes how the agency will assess the system's performance against the goals, stakeholder needs and expectations, constraints, and operation and maintenance requirements documented in the Concept of Operations. The goal is for the agency to understand and review the strengths and weaknesses of the system and identify any new opportunities and needs if appropriate. The agency will implement the System Validation Plan after it accepts the system. This evaluation sets the stage for the next time the system/project is changed or expanded.

For specific guidance on developing the four systems engineering plans listed above, see the plan templates in the USDOT/CalTrans document, *Systems Engineering Guidebook for Intelligent Transportation Systems*, Version 3, November 2009. Pertinent page numbers include:

- Concept of Operations Template: Page 254
- System Requirements Template: Page 257
- Verification Documents Plan Template: Page 269
- Validation Documents Plan Template: Page 278

For Adaptive Signal Control Technology Projects (ASCT) using the latest edition of the USDOT *Model Systems Engineering Documents for Adaptive Signal Control Technology (ASCT) Systems*, FHWA-HOP-11-027, August 2012, is required.

As each phase of an ITS project is completed, a report is to be submitted by the Project Engineer to the region Traffic Engineer describing how the project is meeting the requirements outlined in the above systems engineering plans. Approvals for ITS projects are dependent upon project complexity and cost. (See Chapter 300 for ITS project approval requirements.)

Systems engineering costs are to be estimated and incorporated into the construction engineering (CE) and project engineering (PE) portions of the construction estimate.


For further project development guidance related to procurement and administration of Federal-Aid Intelligent Transportation System (ITS) contracts, see 1050.04.

1050.03(1) Systems Engineering Process "V" Diagram

The systems engineering process contains a number of steps that are not included in a traditional project delivery process. The systems engineering process is often referred to as the "V" diagram (see Exhibit 1050-1). An ITS project begins on the left side of the "V" and progresses down the left side and then up the right side. Then the project is evaluated by validating and verifying the elements on the right side of the "V" with the elements on the left side.

The Federal Highway Administration (FHWA) and WSDOT are in agreement that, for project development and delivery, the most critical portions of the systems engineering process are the Concept of Operations; System Requirements; System Verification; and System Validation. As a result, the Intelligent Transportation Systems (ITS) Systems Engineering Analysis Worksheet in Exhibit 1050-2 is focused on these core areas.

Exhibit 1050-1 Systems Engineering Process "V" Diagram



1050.04 FHWA Washington Division ITS Project Contracting Guidance

1050.04(1) Purpose

The purpose of this document is to provide basic guidance related to the procurement and administration of Federal-Aid ITS contracts.

1050.04(2) Scope

This document is intended to be used by the FHWA Washington Division Office, WSDOT, and local agencies as a guide on the proper types of procurement methods for various types of ITS projects. This guidance is not all-encompassing, as ITS projects can vary significantly in scope. However, it should provide adequate information to address a majority of situations. Specific questions about an individual ITS project should be directed to the Washington Division Office.

1050.043) Construction versus Non-Construction

ITS improvements may be incorporated as part of a traditional federal-aid construction contract, or the contracting agency may elect to procure ITS services under a separate contract (i.e., stand-alone ITS projects). When procured as a separate contract, the scope of an ITS contract will determine the applicability of federal procurement requirements. Title 23 United States Code 101(a)(4) provides a broad definition for construction for federal-aid eligibility purposes. FHWA generally interprets the definition broadly, resulting in many types of projects being classified as construction. Very simply, a contract that incurs costs incidental to the construction or reconstruction of a highway, including improvements that directly facilitate and control traffic flow (e.g., traffic control systems) are by definition construction contracts. This includes rehabilitation of an existing physical ITS infrastructure. Construction contracts must follow the regulatory requirements of 23 CFR 635 or 23 CFR 636 in the case of Design-Build.

Non-construction-type ITS contracts will be either Engineering Contracts or Service Contracts. Engineering is defined as professional services of an engineering nature as defined by state law. If the ITS contract primarily involves engineering, then qualifications-based selection (QBS) procedures, in compliance with the Brooks Act, must be followed. Service contracts (non-construction, non-engineering in nature) are to be procured in accordance with the Common Rule for Grants and Cooperative Agreements to States and Local Governments found at 49 CFR 18.36.

1050.04(4) Types of ITS Projects

Stand-alone ITS projects can generally be categorized into one of the following types of ITS projects: (1) planning/research, (2) preliminary engineering/project development, (3) software development/system integration, (4) system deployments, (5) traditional construction, and (6) operations and maintenance. All Federal-Aid ITS projects, regardless of the type, are directed in 23 CFR 940 to follow a systems engineering process.

Exhibit 1050-3 provides further information about each of these ITS project types.

1050.05 Documentation

Include all ITS systems engineering documentation in the Design Documentation Package (DDP). All systems engineering documentation requires region Traffic Engineer approval.

Exhibit 1050-2 Intelligent Transportation Systems (ITS) Systems Engineering Analysis Worksheet

Intelligent Transportation Systems
Systems Engineering Analysis Worksheet

This worksheet, or a document with the same information, must be completed for all federal-aid projects that include Intelligent Transportation Systems (ITS) elements. This worksheet must be completed prior to submitting a construction authorization request and must be kept in the project file for the entire document retention period of the project. If Concept of Operations, System Requirements, Verification Plan, and Validation Plan documents are required for the project, as determined by this spreadsheet, these documents must be submitted for review prior to submitting a construction authorization request and must be kept in the project file for the entire document retention period.

1. **Project Name:** Click here to enter text.

2. **Contract Number:** Click here to enter text.

3. **Total project cost (includes preliminary engineering/design, right of way, and construction phases):** Click here to enter text.

4. **Amount of total project cost for ITS elements:** Click here to enter text.

5. Will this project implement a new or expand an existing adaptive signal control technology (ASCT) system?

   ☐ Yes FHWA and WSDOT consider the project to be high risk. Four additional systems engineering documents (Concept of Operations, System Requirements, Verification Plan, and Validation Plan) are required. (See definitions in 1050.03 Systems Engineering.) These documents must be produced using the latest edition of the USDOT *Model Systems Engineering Documents for Adaptive Signal Control Technology (ASCT) Systems*, FHWA-HOP-11-027, August 2012. *Please skip questions 6 and 7.*

   ☐ No

Exhibit 1050-2 Intelligent Transportation Systems (ITS) Systems Engineering Analysis Worksheet (continued)

6. Select which of the following items, if any, apply to this project:

☐ The project includes new and unproven hardware and/or communications technology that is considered "cutting edge" or not in common use. This could include custom-developed or unproven commercial-off-the-shelf (COTS) technology that has not been used by the agency previously. *Please explain why you selected or did not select this item.*

Click here to enter text.

☐ The project will add new software that will be custom developed for this project or will make major modifications to existing custom-developed software. *Please explain why you selected or did not select this item.*

Click here to enter text.

☐ The project will add new interfaces to systems operated or maintained by other agencies. *Please explain why you selected or did not select this item.*

Click here to enter text.

☐ The project will develop new system requirements or require revisions to existing system requirements that are not well understood within the agency and/or well documented at this time. These system requirements will be included in a request for proposal, or plans, specifications, and estimate bid document package. Therefore, it will require significant stakeholder involvement and/or technical expertise to develop these items during the project delivery process. *Please explain why you selected or did not select this item.*

Click here to enter text.

☐ Multiple agencies will be responsible for one or more aspects of the project design, construction, deployment, and/or the ongoing operations and maintenance of the system. *Please explain why you selected or did not select this item.*

Click here to enter text.

Exhibit 1050-2 Intelligent Transportation Systems (ITS) Systems Engineering Analysis Worksheet (continued)

7. If you answered yes to any of the items in question 6, FHWA and WSDOT consider the project to be high risk. See the following table for additional requirements.

Project Risk Level	Total Project Cost for ITS Elements	
	Less than $1,000,000[3]	**Equal or Greater than $1,000,000**[3]
High-Risk ITS	Additional systems engineering documents (Concept of Operations, System Requirements, Verification Plan, and Validation Plan)[2] are recommended.[1]	Additional systems engineering documents (Concept of Operations, System Requirements, Verification Plan, and Validation Plan)[2] are required.

Notes:
[1] A decision not to complete the additional systems engineering documents for high-risk projects that have less than $1,000,000 of ITS elements requires FHWA concurrence prior to submitting a construction authorization request.
[2] See definitions in 1050.03, Systems Engineering.
[3] Use the amount from question 4.

8. What is the name of the regional ITS architecture and which portions of the architecture will be implemented? Is the project consistent with the architecture? Are revisions to the architecture required? Also, which user services, physical subsystem elements, information flows, and market/service packages will be completed, and how will these pieces be part of the architecture?

   Click here to enter text.

9. Identify the participating agencies, their roles and responsibilities, and the concept of operations. For the elements and market/service packages to be implemented, define the high-level operations of the system. This includes where the system will be used, its performance parameters, its life cycle, and who will operate and maintain it. Discuss the established requirements or agreements on information sharing and traffic device control responsibilities. The regional ITS architecture operational concept is a good starting point for discussion.

   If this is a high-risk project and a more extensive Concept of Operations document is being prepared for this project (see question 7), this answer can be a simple reference to that document.

   Click here to enter text.

Exhibit 1050-2 Intelligent Transportation Systems (ITS) Systems Engineering Analysis Worksheet (continued)

10. Define the system requirements. Based on the concept of operations, define the "what" and not the "how" of the system. Define the detailed requirements for eventual detailed design. The applicable high-level functional requirements from the regional architecture are a good starting point for discussion. A review of the requirements by the project stakeholders is recommended.

    If this is a high-risk project, and a more extensive System Requirements document is being prepared for this project (see question 7), this answer can be a simple reference to that document.

    Click here to enter text.

11. Provide an analysis of alternative system configurations and technology options to meet requirements. This analysis should outline the strengths and weaknesses, technical feasibility, institutional compatibility, and life cycle costs of each alternative. The project stakeholders should have had input in choosing the preferred solution.

    Click here to enter text.

12. Identify procurement/contracting options. Since there are different procurement methods for different types of projects, the decision regarding the best procurement option should consider the level of agency participation, compatibility with existing procurement methods, the role of the system integrator, and life cycle costs. Some options to consider include: consultant design/low-bid contractor, systems manager, systems integrator, task order, and design/build.

    If the ITS portions of the project significantly meet the definition of construction, then construction by low-bid contract would be used. Non-construction ITS portions of the project, such as services for software development, systems integration, systems deployment, systems management, or design, will be either engineering or service contracts. In these cases, a qualifications-based selection (QBS) or best value procurement may be more appropriate. For guidance on procurement options for ASCT systems, refer to Pages 15-20 of USDOT's *Model Systems Engineering Documents for Adaptive Signal Control Technology (ASCT) Systems*, FHWA-HOP-11-027, August 2012.

    Click here to enter text.

Exhibit 1050-2 Intelligent Transportation Systems (ITS) Systems Engineering Analysis Worksheet (continued)

13. Identify the applicable ITS standards and testing procedures. Include documentation on which standards will be incorporated into the system design. Also, include justification for any applicable standards not incorporated. The standards discussion in the regional architecture is a good starting point for discussion.

    Click here to enter text.

14. Outline the procedures and resources necessary for operations and management of the system. In addition to the concept of operations, document any internal policies or procedures necessary to recognize and incorporate the new system into the current operations and decision-making processes. Also, resources necessary to support continued operations, including staffing and training, must be recognized early and be provided for. Such resources must also be provided to support necessary maintenance and upkeep to ensure continued system viability.

    Click here to enter text.

Exhibit 1050-3 FHWA Washington Division – ITS Project Contracting Guidance

ITS Project Type	Description	Examples
Planning/Research	Generally, involves studies that research new concepts or develop plans or procedures at a broader agency- or region-wide level. These are generally not construction and are often done by agency personnel.	• Regional ITS architecture development and maintenance • Regional Concept of Operation • Traffic incident management planning • Standards testing and specification development • Public outreach and communication
Preliminary Engineering/Project Development	Generally, a project, or phase of a larger project, that leads to some type of ITS deployment/construction. Typically involve some type of service or engineering contact, or work done by agency personnel, and are generally not considered construction.	• Scoping/field surveys • Project-level Concept of Operation • Environmental Review • Development of RFPs • Development of PS&Es • Evaluation of technology, networking, systems architecture alternatives
Software Development/System Integration	Generally, involves projects that develop new or upgraded ITS-related software or involve integrating ITS services and equipment. These are typically not construction and often fall under a service contract.	• Traffic Management Center (TMC) central software design, development, installation • Modifying existing central system software to communicate with new field equipment • Incorporation of device control software into central systems • Acceptance testing and configuration management
System Deployments	Generally, includes total system implementation involving design, equipment, computer systems, telecommunications, and integration. Contracts are often non-construction in nature, depending on the amount and type of field work relative to the overall project. These types of projects will often be the least cut-and-dried in terms of the appropriate contracting method.	• Road-weather information systems (RWIS) • Surveillance camera procurement and installation on existing poles (non-construction when limited in scope) • Non-intrusive sensor procurement and installation on existing poles (non-construction when limited in scope) • Adaptive Signal Control Systems
Traditional Construction	Typical construction projects involving considerable installation of equipment or work in the field. Design-Bid-Build (low bid) or Design-Build contracting are appropriate for this type of work.	• Installation of variable message signs • Installation of poles, controller cabinets, foundations, guardrail, gantries • Installation of radio towers and civil infrastructure for wireless systems • Installation of tolling field equipment (tag readers, video cameras, etc.) • Installation of underground infrastructure (trenching, cable installation, etc.)
Operations/ Maintenance	Ongoing operations and/or maintenance of ITS services, software, and equipment. Typically is a service contract (non-construction).	• Operating costs for traffic monitoring, management, control systems (e.g., rent, communications, labor, utilities) • Preventative maintenance

Chapter 1100 Practical Design

1100.01 General
1100.02 Practical Design Procedure
1100.03 Community Engagement
1100.04 Advisory Team
1100.05 Need and Performance Identification
1100.06 Context Identification
1100.07 Design Control Selection
1100.08 Alternative Formulation and Evaluation
1100.09 Design Element Selection and Dimensions
1100.10 Documentation Tools
1100.11 References

1100.01 General

The Washington State Department of Transportation (WSDOT) is committed to context-appropriate, multimodal, performance-based designs. WSDOT's goal is to optimize existing system capacity and safety through better interconnectivity of all transportation modes. Community engagement is an essential element.

This chapter provides an overview of the practical design approach that WSDOT uses to make project decisions. The remaining chapters in Division 11 provide specific design policy details for each procedural step. WSDOT's practical design approach is context-appropriate, multi-modal and performance-based. Practical design utilizes a collaborative approach, design flexibility, and a high likelihood of variable solutions. As a result, WSDOT's practical design finds consistency through the procedural process applied rather than pre-determined outcomes for projects.

This chapter provides:

- An overview of the WSDOT Practical Solutions initiative.
- An overview of the practical design process.
- Information regarding the importance of design control selection.

1100.01(1) Practical Solutions

Practical Solutions includes practical solutions planning and practical design, as described in Executive Order (EO) E 1090.

Practical Solutions enables more flexible and sustainable transportation investment decisions. It encourages this by: (1) increasing the focus on addressing identified performance needs throughout all phases of development, and (2) engaging local partners and stakeholders at the earliest stages of scope definition to account for their input at the right stage of the development process. Practical Solutions includes one or a combination of strategies, including, but not limited to, operational improvements, off-system solutions, transportation demand management, and incremental strategic capital solutions.

1100.01(1)(a) Practical Solutions Planning

Practical Solutions planning is an approach to making planning decisions that considers a variety of conceptual strategies to achieve the desired system performance targets for the lowest cost.

Central to practical solutions planning is a process that identifies regional and corridor performance areas, engages communities to ascertain local contexts and needs, and applies methods to evaluate and implement short- and long-term solutions.

The outcome of practical solutions planning is a recommended set of multimodal strategies that are cost-effective and balance the goals and objectives of state and local needs. WSDOT's corridor sketch initiative and planning studies inform practical solutions through the following:

- Identify performance gaps for a corridor segment, now and in the future.
- Identify potential strategies to address the gaps.
- Integrate inputs from partners that support corridor segment performance.
- Define context and corridor variables.

Identify and rank demand management and operational improvements first, then consider capital solutions. Note that Executive Order (EO) E 1090 instructs that the solution may or may not be on a state corridor.

1100.01(1)(b) Practical Design

Practical design focuses on the specific problem or problems identified during the planning and scoping process. This performance-based approach looks for lower-cost solutions that meet outcomes that WSDOT, collaborating agencies, communities, and stakeholders have identified. Practical design is a fundamental component to the Vision, Mission, Values, Goals, and Reforms identified in Results WSDOT, the department's Strategic Plan. The primary objectives of the practical design approach are: (1) focusing on project need(s), and (2) seeking the most reasonable low-cost solution to meet that need(s).

Practical design allows flexibility and encourages innovation. Practical design considers incremental solutions to address uncertainties in future scenarios. Practical design can be applied at all phases of project development; however, it is most effective at the scoping level or earlier, where key decisions are made as to what design controls and elements are affected by alternatives and how they can best be configured to meet the project objectives.

With practical design, decision-making focuses on the maximum benefit to the system, rather than the maximum benefit to the project.

1100.02 Practical Design Procedure

Practical design begins when a location under evaluation moves from a discussion of strategies to one of potential solutions within those strategies. The beginning of the practical design approach occurs when the scoping phase requires a Basis of Design (BOD), or when the preliminary engineering phase for a funded project initiates. In each of these situations, practical design procedures apply whether or not practical solutions planning has occurred.

WSDOT's practical design process consists of seven primary procedural steps:

1. Assemble a project advisory team as needed (see 1100.04).
2. Clearly identify the baseline need. Define it in terms of performance, contributing factors, and underlying reasons for the baseline need (see Chapter 1101).
3. Identify the land use and transportation context (which includes environmental use and constraints) for the location (see Chapter 1102).

4. Select design controls compatible with the context (see Chapter 1103).
5. Formulate and evaluate potential alternatives that resolve the baseline need for the selected context and design controls (see Chapter 1104).
6. Select design elements that will be included in the alternatives (see Chapter 1105).
7. Determine design element dimensions consistent with performance needs, context, and design controls (see Chapter 1106).

The Basis of Design (BOD) documents the outcomes of applying these procedural steps. It also serves as a management tool throughout the design phase, to keep a project team focused on the baseline performance need and agreed performance trade-offs in order to prevent scope creep. During the design phase, a BOD is required on all projects unless design elements are not changed (see exceptions in 1100.10). During the scoping phase, a BOD is only required as determined by the Capital Program Development and Management (CPDM) Office. See 1100.10(1) for further information about the BOD.

1100.03 Community Engagement

WSDOT has a strategic goal of engaging the community in order to strengthen partnerships, increase credibility, drive priorities, and inform decision-making. Community input informs the project development process from planning to design. Engaging with the community helps us more fully understand:

- Performance issues and gaps
- Context identity
- Local environmental issues
- Modal priorities and needs

WSDOT encourages recognition of individual community contexts, values, and needs in developing transportation solutions. We do so in order to enhance public trust and develop targeted designs that meet the performance needs of the state, regional, and local transportation systems. – Executive Order 1096

Use the *WSDOT Community Engagement Plan* and document the findings of community engagement efforts (see 1100.10(5)).

1100.04 Advisory Team

Teams deliver projects. Collaborative decisions contribute to successful project delivery. Collaboration emphasizes context sensitive design as part of WSDOT's approach. The practical design approach is a team approach that involves external and internal stakeholders providing consent-based outcomes early in project development. This is consistent with WSDOT Executive Order 1096 - *WSDOT 2015-17: Agency Emphasis and Expectations* and Executive Order 1028 – *Context Sensitive Solutions*. The advisory team is a collaborative body that provides recommendations to the WSDOT project manager and engineer of record, specifically in these areas:

- Need identification (including performance metrics and targets)
- Context identification
- Design control selection
- Alternative formulation

- Performance trade-off decision preferences (including weighing environmental constraints and regulatory issues)
- Alternative evaluation

The Engineer of Record, or project manager, convenes an advisory team that has the skills, knowledge, and responsibilities needed for design decision-making; including planning, project development, environment, active transportation, and context sensitive design. Include WSDOT members on the advisory team who have positional or delegated authority to make decisions associated with the areas outlined in this chapter.

The project manager and project team consider recommendations offered by the advisory team. The project manager decides which recommendations, if any, will be included in the project and informs the advisory team, providing an opportunity for feedback. Document recommendations and their treatment to the Basis of Design prior to its approval.

The project manager has discretion in how to work with internal and external stakeholders in documenting decisions. For more information on organizing, managing, and collaborating with advisory teams, see the WSDOT Project Management Guide:
www.wsdot.wa.gov/projects/projectmgmt/onlineguide/preconstructioninitiatealign

1100.05 Need and Performance Identification

The most fundamental function of practical design is to focus on the primary reason a location is under evaluation. Ask why there is a project under consideration at this location, and identify the specific need. If it is a mobility project, why is there a mobility need and what is specifically contributing to that need?

WSDOT's practical design approach requires that the need be translated into specific performance metrics and that targets be selected to be achieved by the design. A contributing factors analysis (see Chapter 1101) refines focus in order to resolve the specific performance problems and helps define the potential scope of project alternatives.

Chapter 1101 provides guidance for identifying project performance needs. Understanding performance and associated performance terms is critical to the application of Chapter 1101. See the guidance document *Performance Based Design* before proceeding with application of Chapter 1101. Direct link to guidance document:
www.wsdot.wa.gov/publications/fulltext/design/ASDE/Practical_Design.pdf

1100.06 Context Identification

Context identification refers to understanding the characteristics, activities, and functions within a geographical area. WSDOT is committed to providing context sensitive solutions (see E 1028), and context identification is key to implementing this goal. WSDOT's context identification process involves two interrelated context facets: land use and transportation. Context identification also considers existing and future contexts. Chapter 1102 provides guidance for determining context.

1100.07 Design Control Selection

Design controls create significant boundaries and have significant influence on design. WSDOT uses five primary design controls:

1. Design Year
2. Modal Priority
3. Access Control
4. Design Speed
5. Terrain Classification

Chapter 1103 presents guidance related to choosing design controls.

1100.08 Alternative Formulation and Evaluation

Under practical design, the goal is to develop a solution for the baseline need at the lowest cost. However, it is critical to understand how the solution affects other known or identified needs, termed "contextual needs." This requires consideration of multimodal solutions. Chapter 1101 provides a discussion on baseline and contextual performance needs, and Chapter 1104 discusses using these needs to develop and evaluate alternatives.

Practical Solutions requires consideration of operational and demand management strategies prior to implementing a capital strategy. The intent is to find low-cost solutions before making large capital investments.



In some cases, the planning phase will have identified a strategy based on practical solutions planning. Focusing on the preferred strategy can help guide the development of alternative solutions. The guidance document *Alternative Strategies and Solutions* discusses primary strategies and examples of solutions within those strategies.

Design Support guidance document: http://www.wsdot.wa.gov/Design/Support.htm
Direct link to guidance document:
www.wsdot.wa.gov/publications/fulltext/design/ASDE/Practical_Design.pdf

1100.09 Design Element Selection and Dimensions

Design element selection is based entirely on the alternative selected to resolve the baseline need and balance performance trade-offs. Chapter 1105 provides instruction for design element selection. Chapter 1106 provides information related to choosing dimensions for design elements.

1100.10 Documentation Tools

Basis of Design (BOD), Basis of Estimate (BOE), Design Parameter Sheets, and Alternative Comparison Tables are all documentation tools used to record decisions and analyses needed in development of a solution that is consistent with WSDOT's practical design approach. The tools can be found at: http://www.wsdot.wa.gov/Design/Support.htm

1100.10(1) Basis of Design

The BOD organizes information around the practical design procedural steps (see 1100.02) necessary to support WSDOT's practical design approach. It provides a template for documenting each step in the process. The BOD includes the following information and sections:

- Planning Document Summary
- General Project Information
- Section 1 – Project Needs
- Section 2 – Context
- Section 3 – Design Controls
- Section 4 – Alternatives Analysis
- Section 5 – Design Element Selection

Exhibit 1100-1 shows the major activities associated with WSDOT's practical design approach and corresponding Design Manual chapters and Basis of Design sections.

When using a BOD, start as early as possible. During planning or scoping, a BOD may be only partially completed. Information documented on the BOD provides an opportunity for greater consistency between strategies developed in planning and solutions developed in scoping and design. Information documented in the BOD comes through use of consent-based recommendations (see Section 1100.04).

Contact the region Program Management regarding the need to initiate a BOD during the project-scoping phase. Since the BOD is ultimately a document that supports design decisions, the approval of a BOD, which ideally takes place at 30% design level or earlier, is a part of, and included in, the project Design Approval process (see Chapter 300).

Basis of Design: www.wsdot.wa.gov/Design/Support.htm

1100.10(1)(a) Basis of Design Exemptions

See 1100.02 for guidance regarding when a BOD is required for scoping projects. For design-phase projects, a BOD supports design decisions and is required on all projects where one or more design elements are changed (see Chapter 1105). Exceptions are listed below.

1100.10(1)(a)(1) All Projects

If the only design elements changed by the project are listed in Exhibit 1105-1, a Basis of Design (BOD) may not be required. The Assistant State Design Engineer (ASDE) shall concur with the request to exempt the BOD requirement. Submit a request, by email, for an exemption from the BOD requirement. The request should explain the unique circumstances that make use of the BOD unnecessary. Each request is evaluated on a case-by-case basis. If a BOD has been prepared for the project and no design elements were changed, an ASDE approval of the BOD is not required.

1100.10(1)(a)(2) Preservation Projects

A Basis of Design form is not required for Preservation projects if the only design elements changed are listed in Chapter 1120, and the criteria/guidance provided in Chapter 1120 is followed.

1100.10(1)(a)(3) Safety Projects

Safety projects (developed under the I-2 funding program) may not require a BOD even though design elements are changed. The Assistant State Design Engineer (ASDE) shall provide concurrence to exempt the project from the BOD requirement. Submit exemption requests to the ASDE by email explaining why an exemption is applicable. The request should explain the unique circumstances that make use of the BOD unnecessary. Exemption requests are evaluated on a case-by-case basis.

Circumstances that may contribute to a decision to exempt a safety project from the need to prepare a BOD include:

- A programmatic project endorsed by the WSDOT Highway Safety Panel (e.g. Intersection Improvement Program ISIP treatments, Rumble Strips, etc.)
- A Collision Analysis Report (CAR) was approved by the WSDOT Highway Safety Panel AND:
  - The CAR clearly identifies the project need.
  - The CAR compared and rated alternatives.

1100.10(2) Basis of Estimate

A Basis of Estimate is required for all project estimates, and is updated throughout all phases of project development. Refer to the *Cost Estimating Manual for WSDOT Projects* for additional information on estimating and the Basis of Estimate.

1100.10(3) Alternatives Comparison Table

The Alternative Comparison Table (ACT) provides solutions evaluated in accordance with WSDOT's Practical Solutions approach. This table allows comparison of alternatives to identify the optimum solution. The table enables discussions of performance trade-offs. The Alternative Comparison Table is supplemental documentation for Section 4 of the BOD. Alternative Comparison Table: www.wsdot.wa.gov/Design/Support.htm.

1100.10(4) Design Parameter Sheets

The Design Parameter Sheets document the dimensions selected for the various design elements selected and noted in Section 5 of the Basis of Design. Design Parameter Sheet template: www.wsdot.wa.gov/Design/Support.htm

1100.10(5) Documenting Community Engagement

Community engagement is a fundamental component of WSDOT's Practical Solutions strategy, and key to practical design implementation. Community engagement will be consistent with the *WSDOT Community Engagement Plan* (see www.wsdot.wa.gov/planning/)

Document community engagement for all projects. There is no strict format for this.

1100.11 References

1100.11(1) Federal/State Directives, Laws, and Codes

Revised Code of Washington (RCW) 47.04.280 – Transportation system policy goals


Revised Code of Washington (RCW) 47.05.010 – The statement of purpose for priority programming of transportation projects

Secretary's Executive Order 1090 – Moving Washington Forward: Practical Solutions

Secretary's Executive Order 1096 – WSDOT 2015-17: Agency Emphasis and Expectations

Secretary's Executive Order 1028 – Context Sensitive Solution

Exhibit 1100-1 Basis of Design Flowchart



Chapter 1101 Need Identification

1101.01 General
1101.02 Baseline Needs
1101.03 Contextual Needs
1101.04 Contributing Factors Analysis
1101.05 Project Need Statement
1101.06 Documentation
1101.07 References

1101.01 General

Practical design starts with identification of issues associated with the performance of a transportation facility. First, one or more project needs associated with these issues are identified. These project needs represent the gap in performance between the existing and desired state. Once they are identified, a project need statement is then developed which expresses only the most fundamental causes of these performance gaps.

This chapter provides:

- Instruction on the different types of needs—baseline and contextual.
- A method to diagnose and analyze the contributing factors of the identified need.
- Instruction on how to determine performance metrics and targets for each of the identified needs.
- How to develop project need statements.

1101.02 Baseline Needs

A baseline need is the primary reason a project has been proposed at a location. The baseline need usually evolves from a WSDOT planning and/or priority array process. There can be more than one baseline need such as when an agency partners with WSDOT on a project and the partner's need becomes another baseline need. It is important to consider the needs of all mode users.

> **Example:** A local agency desires to fund a revitalization project for a community bordering a state highway. The local agency's baseline need in this case is the local land use's economic vitality. If WSDOT also happens to have a prioritized and funded baseline need at the same location, and the two parties decide to partner in a combined project, that project will have at least two baseline needs. The two parties will work to develop solutions compatible for both baseline needs.

To determine, develop, and refine the project's baseline need(s), examine the conditions surrounding the original project identification, which was completed in the priority programming phase.

After developing and refining the baseline need(s), define the baseline performance metrics. (see 1101.02(1)) and determine the baseline need targets (see 1101.02(2)).

1101.02(1) Baseline Performance Metrics of the Baseline Need(s)

Baseline performance metrics are those "measurables" used to check that the project satisfies the need(s). Baseline performance metrics are also used in the development of the project need statement. Project alternatives must address the identified baseline performance metric(s).

Threshold performance metrics are used in the priority array programming process to screen the full state network under each performance category (for further information on threshold performance metrics and performance categories, see the guidance document Performance-Based Decisions: www.wsdot.wa.gov/Design/Support.htm). The baseline performance metric for preservation category projects is predetermined, and is the same as the threshold performance metrics determined by Subject Matter Experts (SMEs) and HQ Capital Program Development and Management (CPDM) Office.

The baseline performance metrics for a mobility or economic vitality category project may be different from the threshold performance metrics. However, the baseline metric chosen is to be consistent with the priority array performance category that identified the location to be evaluated.

> **Example:** A routinely congested corridor has been screened to identify locations with a potential mobility performance gap. Screening used a threshold performance metric of estimated operations at 70% of posted speed during the peak hour. After considering the context of the location, and the relevance of the threshold performance metric to the site specific conditions and operations, the advisory team recommends that travel time reliability is a more appropriate metric for the location.

WSDOT's practical design approach is committed to multimodal safety as identified in Washington State's Strategic Safety Plan (see www.targetzero.com/plan.htm). To meet this commitment, projects are required to include a baseline performance metric for evaluating the number of fatal and serious injury crashes in safety, mobility and economic vitality category projects. Other safety metrics to address the specific community or partnering agency needs may be included as contextual needs.

Safety projects are expected to continue project development as directed by the Multimodal Safety Executive Committee (MSEC), and described in the Safety Scoping Flowchart and Chapter 321.

Other projects are to coordinate up front with the HQ Safety Technical Group to determine the scale and scope of crash analyses appropriate for different types and sizes of projects. For additional information see Chapter 321.

1101.02(2) Baseline Performance Target

Performance targets are the outcome (or desired state) intended for a project. Use baseline performance metrics and targets to compare alternative designs based on how well the alternative meets the selected targets relative to their costs. Targets can be a single value or range of values.

There may be situations where the targets cannot practicably be met by any alternative or where there are unacceptable performance trade-offs in other performance categories. In these situations it may be appropriate to accept performance trade-offs, in one of the other

categories during the alternatives evaluation (see Chapter 1104), in order to balance competing needs and outcomes. In other situations, it may be appropriate to refine the performance target under consideration.

1101.03 Contextual Needs

Practical design requires that designers refrain from overdesigning the project by focusing the solution on the baseline need or needs. In doing so, opportunities are provided by projects to address other needs that may be identified through community engagement and/or increased project knowledge and understanding. These other needs are classified as "contextual needs." A contextual need is any identified need that is not a baseline need. Potential sources of contextual needs include:

- Performance gaps identified through the priority array network screening, that did not prioritize under a statewide biennial prioritization and budget exercise, but still exist at the project location.
- Needs identified through community engagement or identified by a partnering agency.
- Needs based on identified environmental regulations and constraints.
- Needs identified through coordination with WSDOT maintenance (see Chapter 301 for additional information).
- Needs identified through increased knowledge of the project site and context.

Develop metrics for contextual needs to compare alternatives. Interpret and translate each issue into a statement that is measureable, to the extent feasible. Contextual need metrics can be either quantitative or qualitative.

1101.03(1) Use in Alternative Formulation and Evaluation

Contextual needs serve a different role than baseline needs. Baseline needs primarily shape the alternatives developed, while contextual needs are important to the performance trade-offs discussion (see Chapter 1104). Not all contextual needs identified need to be addressed by a project. Contextual needs present opportunities for optimizing the design, provide for partnerships and modes, and ultimately determine the most optimal project alternative (in conjunction with SEPA/NEPA processes as discussed in Chapter 1104).

Whether a design alternative achieves a particular contextual performance target is a consideration during the tradeoffs analysis. When no alternative adequately balances performance, lower-cost countermeasures can be employed to help mitigate performance issues and improve the viability of alternatives. Modifications to one or more design controls are another approach that can be used to achieve performance targets (see Chapter 1103), without significantly burdening the alternative with additional cost. If all alternatives fail to find an acceptable performance balance targets may be refined. Performance targets are documented and approved as part of the Basis of Design approval process.

1101.04 Contributing Factors Analysis

Contributing factors analysis (CFA) is a process by which subject matter experts on the advisory team evaluate the contributing factors associated with performance gaps in order to identify the root reasons for each gap. In the transportation field, contributing factors are any geometric,

operational, context-based, or human factor that can reasonably be attributed to a performance need through data analysis and engineering judgment.

Practical design relies on CFA to find the root reason(s) a need exists, rather than focusing on a symptom that may only temporarily or partially resolve the need.

Note: It is recognized that completely solving a problem may not be possible by a single corrective action due to the number of contributing factors or because of constraints.

The CFA method will:

- Organize and identify multiple contributing factors and underlying root reasons.
- Formulate a number of potential countermeasures to solve the need as thoroughly and efficiently as possible.

Diagnosis of contributing factors yields the best results when data is available for the analysis. Comprehensive crash data, organized by travel mode, is important when considering safety performance. In other performance categories, where quantitative data is not available, qualitative analysis may be used to reveal the underlying contributing factor(s).

Contributing factor analysis is only required for evaluation of baseline performance needs. However, it may be relevant to perform CFA for contextual performance metrics.

Diagnosing contributing factors using CFA is not necessarily a simple linear process. It's possible to find that a contributing factor identified by one discipline is the root cause of another discipline's contributing factor. In some cases, mapping the contributing factors in a network or fishbone diagram can help identify these relationships more clearly (see the guidance document Contributing Factors Analysis: www.wsdot.wa.gov/Design/Support.htm).

1101.05 Project Need Statement

A project need statement (or statement of need) uses the baseline needs (see 1101.02) and results of contributing factors analysis to succinctly describe the real root project need(s). The objective is to provide a clear, accurate plain talk description of the root needs that will facilitate the development of efficient, focused project alternatives. A need statement should:

- Identify the objective, in simple, direct terms.
- Identify the performance metric(s) involved.
- Include one or more quantifiable statements.
- Exclude any description or discussion of potential solutions.

Consider other processes applicable to their projects that may require need statements such as: value engineering, NEPA/SEPA, and Interchange Justification reports. Consider timing of these processes as well as integration and alignment of the need statements with the processes required for the project.

For more information and examples of need statements, see the guidance document Writing Effective Needs Statement: www.wsdot.wa.gov/Design/Support.htm

1101.06 Documentation

Use the Basis of Design, Section 1, to document decision-making and conclusions associated with project need identification.

Download The BOD here: www.wsdot.wa.gov/Design/Support.htm

1101.07 References

Contributing Factors Analysis, WSDOT Guidance Document:
www.wsdot.wa.gov/Design/Support.htm

Performance-Based Design, WSDOT Guidance Document:
www.wsdot.wa.gov/Design/Support.htm

Writing Effective Needs Statement, WSDOT Guidance Document:
www.wsdot.wa.gov/Design/Support.htm

Washington State's Strategic Safety Plan: www.targetzero.com/plan.htm

WSDOT Safety Scoping Flowchart:
http://wwwi.wsdot.wa.gov/ppsc/pgmmgt/wwwi/PlanProg/Scoping/SafetyScopingProcessFlowChart.pdf

Chapter 1102 Context Determination

1102.01 General Overview
1102.02 Land Use Context
1102.03 Transportation Context
1102.04 Documentation
1102.05 References

1102.01 General Overview

Context refers to the environmental, economic, and social features that influence livability and travel characteristics. Context characteristics provide insight into the activities, functions, and performance that can be influenced by the roadway design. Context also informs roadway design, including the selection of design controls, such as target speed and modal priority, and other design decisions.

For the purposes of transportation planning and design, WSDOT divides context into two categories: land use and transportation. Each of these contexts is further defined and categorized in this chapter. Note that context categories, and the information pertinent to deriving them, may have been documented in a planning study.

The concepts and method described in this chapter are adapted from National Cooperative Highway Research Program project 15-52 final draft report: *Developing a Context-Sensitive Classification System for More Flexibility in Geometric Design*.

1102.02 Land Use Context

This section describes the procedure for determining the land use context category on non-freeway facilities. The guidance in this section does not apply for freeways (see Chapter 1232 for the definition of a freeway). For freeways, use Section 2 of the Basis of Design to document the urban/rural designation as listed for the route on the State Route Log.

On larger projects, more than one land use category may apply within project limits.

Step 1. Determine an initial land use context category (current state)

Land use context categories are described in detail in 1102.02(1). These categories represent distinctive land use environments beyond simply “rural” and “urban” to help determine a more accurate context. These categories influence roadway design, including determining appropriate operating speeds, mobility and access demands, and modal users. The land use categories are:

- Rural
- Suburban
- Urban
- Urban Core

Use the following factors to determine your initial land use context category:

1. Land uses (primarily residential, commercial, industrial, and/or agricultural)
2. Density
3. Setbacks

Quantify these factors through an assessment of the area adjacent to the existing or planned roadway (see Exhibit 1102-1).

Step 2. Determine an initial land use context category (future state)

Using the same factors and categories, consult with local agency staff, and review state, regional, and local planning documents to consider and document potential or anticipated changes to land use context. Sources of information include the local comprehensive plan, WSDOT Highway System Plan, WSDOT corridor sketches, and WSDOT planning studies in the corridor.

Exhibit 1102-1 Factors for Determining Initial Land Use Context

Factor	Criteria
Land Use	Land uses within ½ mi of roadway
Density	Housing units / acre
Density	Jobs / acre
Density	Intersections per sq. mi.
Density	Typical building height
Setback	Typical building setback
Setback	Parking (on street or off street)

Specific metrics guiding the use of these criteria in determining the initial land use context category (both current and future) are provided on the WSDOT Design Office website.

Step 3. Select final land use context category (current and future state)

Once an initial land use category is determined, additional (primarily qualitative) considerations are used to verify that the selected category is appropriate. Because data used in the initial determination may be incomplete, conflicting, or difficult to interpret, it's expected that professional judgment is used to confirm the context result. Even when the overall assessment is clear, discontinuities or transitions between categories may exist and require further interpretation.

Confirm or make adjustments to the initial context category based on a qualitative analysis. Use information gathered from consultations with local agency staff, as well as the project's community engagement processes, to validate a final determination about current and future context. Information about topography, soil type, land value, population density, average building square footage, visual assessments, aerial photos, zoning, and other local agency land use data and/or maps may also be used in this step.

Document the process used to make this final context determination. Include the data used, interdisciplinary input, and issues encountered and resolved in the process. Conclude with a final land use context determination that confirms, or adjusts, the initial category(s) for the project, and seek the endorsement of this final determination from the project advisory team (see Chapter 1100).

1102.02(1) Land Use Categories

The land use categories used to inform project design are described below.

1102.02(1)(a) Rural

The rural category ranges from no development (natural environment) to some light development (structures), with sparse residential and other structures mostly associated with farms. The land is primarily used for outdoor recreation, agriculture, farms, and/or resource extraction. Occasionally non-incorporated communities will include a few residential and commercial structures. Rural characteristics also include:

- No or very few pedestrians – except those locations used for outdoor recreation and modal connections, and where socioeconomic factors suggest that walking is likely to serve as an essential form of transportation
- Bicycle use mostly recreational– except for tourist destinations, modal connection locations and between communities where bicycle commuters may be expected or where socioeconomic factors suggest that bicycling is likely to serve as an essential form of transportation.
- Low development density
- Isolated residential or commercial activities
- Commercial uses include general stores, restaurants, and gas stations, normally at crossroads
- Setbacks for structures are usually large, except in the immediate vicinity of small settlements
- Transit service availability is often absent or highly limited, but varies widely depending on the jurisdiction. On-demand service is typically found to provide specialized transportation services

1102.02(1)(b) Suburban

Locations classified as suburban include a diverse range of commercial and residential uses that have a low or often, medium density. Suburban areas are usually (but not always) connected and closely integrated with an urban area. The buildings tend to be multi-story with off-street parking. Sidewalks are usually present and bicycle lanes may exist. These areas include mixed use town centers, commercial corridors, and residential areas. Big box commercial and light industrial uses are also common. The range of uses encompasses health services, light industrial (and sometimes heavy industrial), quick-stop shops, gas stations, restaurants, and schools and libraries. Suburban characteristics also include:

- Heavy reliance on passenger vehicles
- Transit may be present
- Residential areas may consist of single and/or multi-family structures
- Building and structure setbacks from the roadway vary from short to long
- May have well planned and arranged multi-uses that encourage walking and biking

- Planned multi-use clusters may integrate residential and commercial areas along with schools and parks
- Some highways that fit this category may be designated by WSDOT as "Main Street Highways" (see Appendix B: Identification of State Highways as Main Streets, http://www.wsdot.wa.gov/research/reports/fullreports/733.1.pdf.)

1102.02(1)(c) Urban

Urban locations are high density, consisting principally of multi-story and low to medium rise structures for residential and commercial use. Areas usually exist for light and sometimes heavy industrial use. Many structures accommodate mixed uses: commercial, residential, and parking. Urban areas usually include prominent destinations with specialized structures for entertainment, athletic and social events as well as conference centers and may serve as a Main Street (see 1102.03(6)). Urban characteristics also include:

- Various government and public use structures exist that are accessed regularly
- Building setbacks are both short and long
- Streets normally have on-street parking
- Wide sidewalks and plazas accommodate more intense pedestrian traffic
- Bicycle lanes and transit corridors are frequently present
- Off-street parking includes multi-level structures that may be integrated with commercial or residential uses
- Some highways that fit this category may be designated by WSDOT as "Main Street Highways" (see Appendix B: Identification of State Highways as Main Streets

Due to the differences in developmental scale among urban areas as well as growth demand urban-urban core, context boundaries change over time with the urban core area expanding in high growth situations and possibly contracting in low or no growth situations.

1102.02(1)(d) Urban Core

Urban core locations include the highest level of density with its mixed residential and commercial uses accommodated in high-rise structures. There is commonly on-street parking, although it is usually time restricted. Most parking is in multi-level structures attached or integrated with other structures. The area is accessible to automobiles, commercial delivery vehicles, biking, walking, and public transit. Urban Core characteristics also include:

- Sidewalks and pedestrian plazas are present
- Bicycle facilities and transit corridors are common
- Typical land uses are mixed commercial, residential, with some government or similar institutions present
- Commercial uses predominate, including financial and legal
- Structures (predominantly high rises) may have multiple uses
- With the highest land value of any category, setbacks from the street are small
- Some highways that fit this category may be designated by WSDOT as "Main Street Highways" (see Appendix B: Identification of State Highways as Main Streets

1102.03 Transportation Context

This section describes the procedure for determining the current and future transportation context for the roadway. On larger projects, more than one transportation context may apply within project limits. Network connections are also useful in understanding the transportation context.

Each transportation context is to be described in terms of the following categories and considerations:

- Roadway type
- Bicycle route type
- Pedestrian route type
- Freight route type
- Transit use considerations
- Complete streets and Main Street highways

Seek endorsement from the project advisory team (see Chapter 1100) for determinations of these transportation context types and considerations, including input from local agency (local jurisdictions and transit agencies) and stakeholders. Document determination of each of these transportation contexts for both current and future states in Section 2 of the Basis of Design, and carry these results forward into determination of modal compatibility and modal priority (Chapter 1103).

Additional information supporting work described in this section is provided on the WSDOT Design Office website.

1102.03(1) Roadway Type

The initial roadway type is defined by the designated functional classification on the WSDOT State Route Log for the route as listed below for non-freeway facilities. A final roadway type determination is based on an assessment of whether a different functional class description (given below) corresponds better to the current and future state of the facility, compared to the designated functional class for the facility. The future state is determined after an assessment of the future modal route types described below. Justify the selection of a final roadway type whether it is the same or different from the designated functional class.

Freeways (including Interstate freeways) are defined in Chapter 1232. These routes typically are limited access facilities. The roadway type for freeways is freeway.

Roadway types for non-freeway facilities are described as follows.

- Principal Arterial – Corridors of regional importance connecting large centers of activity. These routes may be limited access facilities.
- Minor Arterial – Corridors of regional or local importance connecting centers of activity.
- Collector – Roadways of local importance providing connections between arterials and local roads.
- Local – Roads with no regional importance for local circulation and access only

1102.03(2) Bicycle Route Type

Bicycle routes are categorized based on the purpose of the trip and the network connectivity a facility provides. Use quantitative and qualitative information about bicycle connections associated with the project location to determine the current and future bicycle route type using one of these three classifications:

- Citywide Connector (CC) — The route is part of a citywide network, provides a connection to major activity centers, or is a regional bike route stretching over several miles that attracts a high volume of use, serving a primary commute or recreational purpose. These routes are typically associated with arterials and collectors.
- Neighborhood Connector (NC) — The route provides a neighborhood or sub-area connection, making connections to higher order facilities or more local activity centers, such as neighborhood commercial centers. These routes are typically associated with minor arterials and collectors.
- Local Connector (LC) — The route provides local connections of short lengths, providing internal connections within neighborhoods, or linking neighborhoods to higher order facilities. These routes are typically associated with collectors and local roads.

1102.03(3) Pedestrian Route Type

Pedestrian use is described in terms of estimated volumes (current and potential future). The amount of pedestrian traffic impacts several factors, including pedestrian facility capacity, vehicular delays at signalized intersections, and most importantly, the level of risk associated from pedestrians in the travelled way. The four pedestrian route types are based on volume as follows:

- P-1: rare or occasional use
- P-2: low volume – best measured in pedestrians per day
- P-3: medium volume - best measured in pedestrians per hour
- P-4: high volume - best in pedestrians per hour, where sub-hour peak periods are typical

1102.03(4) Freight Route Type

Freight routes may not require significant additional facilities beyond those provided for other motorized vehicles, if mobility and speeds of vehicular routes are consistent with freight movement. Special design consideration is commonly related to the Freight and Goods Transportation System classification. Document the classification for the project area.

Contact Rail, Freight, and Ports Division for help identifying freight classifications, industry needs and truck operations.


Truck route classifications can be found here:
http://www.wsdot.wa.gov/Freight/EconCorridors.htm

Additional information: http://www.wsdot.wa.gov/freight/

1102.03(5) Transit Use Considerations

Transit can provide service on any roadway type. The purposes of transit trips are similar to those of automobile trips and include commuting, work related business, shopping, personal errands, and social/recreational. The facilities and design considerations for transit uses depend on the type of transit service being provided. Note that special design consideration is required for projects that involve one or more of the following elements:

- Fixed route type: there are three primary types of fixed-route transit service, operating along designated routes at set times (Local, Limited, and Express). If one of these services exists on the project, determine the route type using criteria shown in the illustration below and the following bullets:



Source: TRPC Report 165: Transit Capacity and Quality of Service Manual.

  - Local routes serve many stops along a route and emphasize access to transit over speed.
  - Limited stop routes (also known as frequent routes, including bus rapid transit) balance transit access with speed. These routes run frequently and serve higher volume stops (e.g. major activity centers and transfer points).
  - Express routes emphasize speed over transit access, and are often used for longer distance trips.

  Note that in addition to fixed-route service, many agencies provide demand-response paratransit services that provide specialized transportation services in both rural and urban areas.

- Bus rapid transit or light rail
- Transit signal priority installation
- Planned transit facilities and routes
- In lane bus stops and/or potential bus pullouts
- Facilities for people with specialized transportation needs (e.g. hospitals, senior centers, schools, transit-dependent communities, etc.)

When evaluating transit needs and the potential for transit to improve highway performance in the project area, document relevant information or data about current transit capacity and quality of service (as defined in the Transit Capacity and Quality of Service Manual) and current and potential future use and travel markets. Include consideration for people walking and biking to/from transit connections. Contact the Public Transportation Division for help or for more information about identifying and coordinating with transit agencies and local jurisdictions that serve the project area (http://wwwi.wsdot.wa.gov/PubTran/).

1102.03(6) Complete Streets and Main Street Highways

Complete street contexts consider all transportation modes and often require differing modal priorities based on the existing land uses or may even consider multiple modes of equal priority. Complete streets may be desirable in various land use contexts including urban core, urban, suburban, small town, and even some rural contexts.

The Main Streets designation for highways is a point of reference and consideration when documenting transportation context, and should be noted on the Basis of Design. Main Street highways serve the aesthetic, social, economic, and environmental values in a larger community setting in addition to transportation. They are set up as specific state route and milepost designations.

See the *Complete Streets and Main Street Highways Program* document listed in Supporting Information at the end of this chapter for more information. For the list of designated highways see *State Highways as Main Streets: A Study of Community Design and Visioning*, Appendix B: Identification of State Highways as Main Streets,
http://www.wsdot.wa.gov/research/reports/fullreports/733.1.pdf.

1102.04 Documentation

Document the following in Section 2 of the Basis of Design:

- Land use category
- Roadway type
- Bicycle route type
- Pedestrian route type
- Freight route classification
- Transit use considerations
- Main Streets designation

Describe the process that was followed to reach these designations. If the work involved review and verification of previous work, document that process as well. If characteristics vary within project limits include the milepost ranges to which each of the designations apply.

1102.05 References

1102.05(1) Federal/State Directives, Laws, and Codes

23 Code of Federal Regulations (CFR) 450, Subpart B, Statewide Transportation Planning

23 CFR 450, Subpart C, Metropolitan Transportation Planning and Programming

23 United States Code (USC) 134, Metropolitan Planning

23 USC 135, Statewide Planning

Revised Code of Washington (RCW) 35.58.2795, Public transportation systems – Six-year transit plans

RCW 35.77.010(2) and RCW 36.81.121(2), Perpetual advanced six-year plans for coordinated transportation program expenditures – Nonmotorized transportation – Railroad right-of-way

RCW 36.70A, Growth management – Planning by selected counties and cities

RCW 43.21C, State environmental policy

RCW 47.05, Priority programming for highway development

RCW 47.06, Statewide transportation planning

RCW 47.06B, Coordinating special needs transportation

Secretary's Executive Order 1028 – Context Sensitive Solutions

Secretary's Executive Order 1090 – Moving Washington Forward: Practical Solutions

Secretary's Executive Order 1096 – WSDOT 2015-17: Agency Emphasis and Expectations

1102.05(2) Supporting Information

WSDOT References

Understanding Flexibility in Transportation Design – Washington, WA-RD 638.1, WSDOT, 2005
http://www.wsdot.wa.gov/research/reports/600/638.1.htm

Complete Streets and Main Street Highways Program, WSDOT, 2011
https://www.wsdot.wa.gov/research/reports/fullreports/780.1.pdf

State Highways as Main Streets: A Study of Community Design and Visioning, WSDOT, 2009
Appendix B: Identification of State Highways as Main Streets
http://www.wsdot.wa.gov/research/reports/fullreports/733.1.pdf

WSDOT Functional Classification map application:
http://www.wsdot.wa.gov/mapsdata/travel/hpms/functionalclass.htm

Other References

Complete Streets Planning and Design Guidelines, North Carolina Department of Transportation, July 2012. http://www.pedbikeinfo.org/pdf/PlanDesign_SamplePlans_CS_NCDOT2012.pdf

Designing Walkable Thoroughfares: A Context Sensitive Approach, Institute of Transportation Engineers, Washington D.C., 2010
http://ecommerce.ite.org/IMIS/ItemDetail?iProductCode=RP-036A-E

Evaluating Transportation Land Use Impacts, Victoria Transport Policy Institute, 2015
http://www.vtpi.org/landuse.pdf

The Innovative DOT: A Handbook of Policy and Practice, Smart Growth America, Washington D.C., 2015
http://www.smartgrowthamerica.org/the-innovative-dot

Land Use and Regional Planning: Achieving Integration Between Transport and Land Use, European Commission, 2006 http://www.transport-research.info/Upload/Documents/200608/20060831_102457_87241_Land_use.pdf

Livability in Transportation Guidebook: Planning Approaches that Promote Livability, FHWA, 2010 http://www.fhwa.dot.gov/livability/case_studies/guidebook/

Measuring Sprawl 2014, Smart Growth America, Washington D.C., 2014
http://www.smartgrowthamerica.org/measuring-sprawl

Small Town and Rural Multimodal Networks (FHWA-HEP-17-024), December 2016.
https://www.fhwa.dot.gov/environment/bicycle_pedestrian/publications/small_towns/

Smart Transportation Guidebook, New Jersey Department of Transportation and Pennsylvania Department of Transportation, 2008.
http://www.state.nj.us/transportation/community/mobility/pdf/smarttransportationguidebook2008.pdf

Urban Street Design Guide, National Association of City Transportation Officials, New York, NY, 2013 http://nacto.org/

Chapter 1103 Design Control Selection

1103.01 General Overview
1103.02 Control: Design Year
1103.03 Control: Modal Priority
1103.04 Control: Access Control
1103.05 Control: Design Speed
1103.06 Control: Terrain Classification
1103.07 Documentation
1103.08 References


1103.01 General Overview

Design controls are specific factors that directly influence the selection of most design elements and their dimensions. Design controls establish fundamental boundaries for design alternatives. Selection of design controls is documented on the Basis of Design. This chapter provides guidance on the selection of design controls for state routes.

The five WSDOT design controls include:

- Design Year
- Modal Priority
- Access Control
- Design Speed
- Terrain Classification

Exhibit 1103-1 WSDOT Design Controls



Reciprocal connections between design controls and land use and transportation contexts

1103.02 Control: Design Year

Design year is the forecast year used for design. The year of opening is when the construction will be complete and the project location is fully operational. Design year selection is dependent on a decision to design for the year of opening, or for a future year based on forecast or planned conditions. Design year has historically been associated with a 20-year vehicle traffic forecast used in development of large mobility and capacity expansion projects. This is the origin of the term **horizon year**. Horizon year is typically considered to be 20 years from the year construction is scheduled to begin.

WSDOT policy on design year is intentionally flexible. The design year can be any interim year selected between the project year of opening year and the horizon year. Many lower-cost projects result in immediate performance improvements when construction is completed. Safety projects are an example of this where the basis of design may show design year as the year of opening.

Some projects may require horizon year analysis of an alternative regardless of the selected design year. A project may be required to evaluate alternatives based on the horizon year (20 years from the scheduled beginning of construction) if the project:

- Involves a federal nexus (federal funds involved, involves federal lands, or requires federal approvals or permits)
- Is a Project of Divisional Interest (See Chapter 300)
- Is a new/reconstruction project as defined in Chapter 300

Contact the region ASDE if there are questions.

1103.03 Control: Modal Priority

The concepts and method described in this section are adapted from National Cooperative Highway Research Program project 15-52 final draft report*: Developing a Context-Sensitive Classification System for More Flexibility in Geometric Design*.

1103.03(1) Design Users

"Design users" refers to the modes that are legally permitted to use a facility. The intent in identifying design users is to highlight all user needs, recognize modal interactions, and develop an integrated system for all users. Identifying the design users is the first step in determining which modes to accommodate and prioritize. On the Basis of Design, list design users with sufficient descriptive detail. Include consideration for all ages and abilities.

Division III of the document *Understanding Flexibility in Transportation Design – Washington* is a key resource for understanding the needs and characteristics of various design users.

1103.03(2) Modal Accommodation

Modal accommodation refers to the level to which a travel mode will be addressed in the design. It is expressed on a scale of low, medium, and high, where a higher accommodation level is associated with the use of design features or criteria that tend to improve the performance of that mode compared to a lower level. Once established, the modal accommodation level is used to inform the decision on modal priority (See 1103.03(3)). Determine the modal accommodation


level for both the current year (prior to opening) and the design year. These are referred to as existing and future conditions in the guidance that follows.

1. An **initial** modal accommodation determination, for both the current and design years, are made using Exhibit 1103-2. The initial determination uses the roadway type and land use contexts that were determined earlier and documented in Section 2 of the Basis of Design (See Chapter 1102).
2. A **final** determination for both the current and design years is made using additional information and evidence to validate or modify the initial determination.

Make the final modal accommodation determination for each mode in consultation with the project advisory team and/or subject matter expert(s), as they may recommend modifications to the initial determinations (see 1100.04 for more information about working with the project advisory team). Exhibit 1103-3 provides examples of land-use and transportation characteristics that a project advisory team or subject matter expert(s) may consider in adjusting accommodation up or down for any particular travel mode.

Exhibit 1103-2 – Initial Modal Accommodation Level

Corrected here per Technical Errata 8-8-2017



Additional guidance on the use of the following criteria in determining final modal accommodation level is provided on the Design Support site:
http://www.wsdot.wa.gov/Design/Support.htm

Exhibit 1103-3 Example Characteristics Related to Modal Accommodation

Land Use Characteristic	Increased Modal Accommodation Level
High proximity to activity centers	Pedestrian, Transit, Bicycle
Industrial and commercial land uses in surrounding area	Auto, Freight
High densities of both residential and employment	Bicycle, Pedestrian, Transit
Minimal building setbacks adjacent to roadway	Bicycle, Pedestrian
Human scale architecture present	Bicycle, Pedestrian, Transit
Transportation Characteristic	**Increased Modal Accommodation Level**
Well-established grid network	Bicycle, Pedestrian, Transit, Auto
T-2 freight route	Auto, Freight
Streetside elements	Bicycle, Pedestrian, Transit
Frequent signalized intersections along route	Auto, Transit, Pedestrian

1103.03(2)(a) Vehicle modal accommodation level

Consider the vehicle modal accommodation level when making design decisions that address or affect needs associated with vehicle travel. Start with the initial modal accommodation level for motor vehicles per Exhibit 1103-2, and adjust it to establish the final level based on documented project specific conditions related to the quality of travel experience, and identified performance targets, that can be influenced by the project design, such as vehicle Level of Service, travel time, access classification, and other factors determined by subject matter experts or the project advisory team.

1103.03(2)(b) Bicycle modal accommodation level

Consider the bicycle modal accommodation level when making design decisions that address or affect needs associated with bicycle travel. Start with the initial modal accommodation level for bicycles per Exhibit 1103-2, and adjust it to establish the final level based on documented project specific conditions related to the quality of travel experience, and identified performance targets, that can be influenced by the project design, such as bicycle route type, efficiency of travel, range, bicyclist safety, route spacing, bicycle volumes, and other factors determined by subject matter experts or the project advisory team.

1103.03(2)(c) Pedestrian modal accommodation level

Consider the pedestrian modal accommodation level when making design decisions that address or affect needs associated with pedestrian travel. Start with the initial modal accommodation level for pedestrians per Exhibit 1103-2, and adjust it to establish the final level based on documented project specific conditions related to the quality of travel experience, and identified performance targets, that can be influenced by the project design, such as pedestrian route type, efficiency of travel, range, pedestrian safety, block length, and other factors determined by subject matter experts or the project advisory team.

1103.03(3) Modal Priority

Accommodate means that the roadway will be designed so that the chosen modes can use it, while **accommodation level** refers to the extent to which that accommodation may be required. **Priority** refers to the decision to optimize the design based on the performance of one or more travel modes. Modal priority is used as input to choosing the appropriate geometric cross section (see Chapter 1230).

Modal priority addresses all modes expected to use the facility. Determine modal priority using the accommodation level results, as well as information about freight, transit, and any other modes considered in the analysis of transportation context (see Chapter 1102).

If the modal priority is inconsistent with assumptions made about the project during a planning or scoping phase, work with program management staff to consider the need for any changes to project scoping documentation, including scope, schedule, and budget.

Document the modal priority on the Basis of Design for both the current and future conditions.

1103.03(4) Intersection Design Vehicle

WSDOT policy provides flexibility when choosing the intersection design vehicle. The purpose for this policy is to balance user needs and avoid the unnecessary expense of oversizing intersections. Considerations include frequency of the design vehicle and effects on other design users, specifically pedestrian crossing distance and times, and bicycle turning and through movements. Consider providing more protected intersection treatments for pedestrians and bicyclists to mitigate turning conflicts.

An intersection design vehicle is a specific selection made at each intersection leg. Select a design vehicle that allows the largest vehicles commonly encountered to adequately complete a required turning maneuver. The objective is not necessarily to size the specific intersection curb radius (unless there is a baseline need associated with the larger vehicles), but rather to account for a reasonable path to accommodate the large vehicle turning maneuver without conflicts (see Chapter 1310). Use turn simulation software (such as AutoTURN®) to analyze turning movements.

> **Example:** An intersection with a pedestrian modal priority experiences infrequent turning movements by a WB-67. A smaller curb radius would benefit pedestrians due to shorter crossing times and reduced exposure to vehicles. Using turn simulation software, a practicable path for the WB-67 can be identified, even though path intrusion into the second same direction lane or painted median may be necessary. The infrequent use by a WB-67, along with the pedestrian modal priority, validate the decision for selecting a smaller design vehicle for the intersection while accommodating the WB-67 vehicle.
>
> Conversely, if the crossroad was identified as being within a Freight Economic Corridor, with frequent turning movements from larger vehicles, it would be appropriate to size the intersection to prevent the second lane incursion.

Consider origins and destinations of large vehicles to understand their needs at specific intersection locations. Also, consider alternatives that may help lower turning speeds and minimize pedestrian exposure. Work with stakeholders, businesses, and service providers to understand their needs (like transit, school bus and emergency vehicle movements) and define

the frequency of use at specific intersections. Municipalities may have established truck routes or restrictions that govern local freight patterns.

1103.04 Control: Access Control

Access is a critical component informed by an understanding of the land use and transportation contexts. The type of access control selected (see Chapter 520) affects accessibility and impacts the types of activities and functions that can occur on a segment. It is important for mobility and economic vitality projects to consider whether the current access classification and/or planned access classification conforms to the context selected for design (see Chapter 1102).

During development of the state highway system, access management functioned to preserve the safety and efficiency of regional highways. However, the level of access management can also significantly affect accessibility to land uses, modal mobility needs and the economic vitality of a place.

Unless access control has already been acquired by the purchase of access rights, it is necessary to select the appropriate type of limited access control or managed access control during planning and design. Appropriate access control should be considered so as not to hinder bicycle and pedestrian accessibility, mobility, and safety.

A choice to change the current or planned access control is a major decision and is to be consistent with the context, desired performance targets, and modal priorities for a location.

> **Example:** The area around a managed access Class 2 route has incurred significant development, increasing the number of local trips on a segment of the route. Over time, additional intersections and access connection permits have been granted. In this situation, it may be appropriate to consider selecting managed access Class 4 or 5 because of the changes in functions and activities along the segment over time.
>
> Conversely, a route may have a need to improve motor vehicle travel time performance, and managed access Class 1 may be appropriate.

If an alteration to current or planned access is determined necessary, consult the Headquarters Access and Hearings Manager for preliminary approval for the selection, and document on the Basis of Design (see Chapter 1100). For additional information on access control and access management, see Chapters 520, 530, and 540.

1103.05 Control: Design Speed

WSDOT uses a target speed approach for determining design speed. The objective of the target speed approach is to establish the design speed at the desired operating speed. The target speed selection is derived from other design controls, as well as transportation and land use context characteristics.

Exhibit 1103-4 shows possible (planning level) target speeds for the various roadway types and land use contexts discussed in Chapter 1102. The target speeds shown in the exhibit are suggestions only, and the target speed for the specific location may vary from those shown in the exhibit.

Exhibit 1103-4 Target Speed Based on Land Use Context and Roadway Type

Roadway Type	Land-Use Context			
	Rural	**Suburban**	**Urban**	**Urban Core**
Freeways	High	High	High	High
Principal Arterial	High	Intermediate / High	Low / Intermediate	Low
Minor Arterial	High	Low/ Intermediate	Low / Intermediate	Low
Collector	Low/ Intermediate	Low/ Intermediate	Low	Low
Local	Low/ Intermediate	Low	Low	Low

Engage the public, local agency staff and officials, and transit agencies prior to selecting the target speed. Once the target speed has been selected, it becomes the design speed for the project. The goal of the target speed approach is that the speed ultimately posted on the completed project is the same as the design, and ultimately, the operating speed. In order to achieve this outcome, consider:

- The impact of existing or proposed contextual characteristics
- Modal priorities
- Access control selection
- Performance need(s)
- Contributing factors analyses that have been developed for the project

Lowering target speed: When selecting a target speed in excess of the existing posted speed, or where excessive operating speeds were identified from contributing factors analysis of the baseline performance need, consider the use of roadway treatments that will help achieve the selected target speed (see 1103.05(2)) during alternatives formulation.

Speed management treatments are used to achieve lower vehicle speeds. When speed management treatments are proposed to accomplish a desired target speed operation concurrence of the Region Traffic Engineer is required. When a design speed is proposed for a project that is lower than the existing posted speed, the approval of the State Traffic Engineer is also required. See 1103.05(2) below for more on speed management. Careful consideration of other modal needs should be evaluated before raising target speeds.

Raising target speed: When selecting a target speed in excess of the existing posted speed, measures such as greater restriction of access control and segregation of modes may be necessary to reduce conflicts in activities and modal uses. Wider cross sectional elements like lanes and shoulders are used with higher speed facilities.

Setting the posted speed: Use caution when basing a target speed on one or more contextual characteristics that are proposed to take place after project opening, as the goal of ending up with a posted speed equal to the design speed at opening may be jeopardized.

The Region Traffic Engineer is responsible for setting the posted speed on the highway once the project is completed. Target speed is only one of the considerations used when establishing posted speed. Engage and include the Region Traffic Engineer and Traffic Office staff in key

decision-making that will affect the target, design, and operating speed selection. . Incorporate consideration of traffic calming measures as needed.

1103.05(1) Low, Intermediate, and High Speeds

To provide a general basis of reference between target speed and geometric design, WSDOT policy provides three classifications of target speed as follows:

1. **Low Speed is 35 mph and below.** A low target speed is ideal for roadways with pedestrian and bicycle modal priorities. Locations that include frequent transit stops, intermodal connections, moderate to high intersection density, or moderate to high access densities may also benefit from lower speed environments. Low speed facilities in urban areas typically use narrower cross section elements.
2. **Intermediate Speeds are 40 mph and 45 mph.** An intermediate target speed is ideal for speed transitions between high and low target speed environments. Locations with low access densities and few at-grade intersections are also examples of where intermediate speed may be appropriate. In these locations consider a higher degree of separation between motor vehicles and bicycles and pedestrians.
3. **High Speed is 50 mph and above.** A high target speed is ideal for motor vehicle oriented roadways such as freeways and highways, often serving regional or longer-distance local trips. Rural connector roadways with infrequent farm or residential accesses are also consistent with the use of high target speeds. In high target speed locations consider the highest degree of separation between motor vehicles and bicycles and pedestrians. Highways with high speeds are associated with wider cross section elements.

1103.05(2) Speed Management

Speed management is necessary within many highways to achieve an optimal multimodal facility that will support the land use and transportation contexts. Speed management may also be necessary to maintain consistent or desired speeds between adjacent roadway segments. Identify speed transition segment(s) as necessary to achieve desired speeds. Identify potential speed transition segments when scoping the project.


1103.05(2)(a) Speed Transition Segments

Include a speed transition segment where there is a need to obtain a target speed lower than the existing operating speed. A speed transition segment is not needed where existing operating speeds are within 5 mph of the target speed for a given location. The transition segment may not always directly precede the speed zone segment as shown in Exhibit 1103-5.

Example: A residential segment could benefit from introducing a speed transition segment farther upstream to increase the likelihood that approaching vehicles operate at the desired speed, for both segments.

The speed transition segment may incorporate a variety of treatments that alert motorists to a changing roadway environment. These treatments are intended to narrow driver focus and/or affect driver decision-making on that segment. Consider the transition segment location and length when providing multiple treatments in a short distance.

Exhibit 1103-5 Speed Transition Segment Example



1103.05(2)(b) Speed Reduction Traffic Calming Treatments

Traffic calming treatments can serve a variety of purposes, from deterring higher volumes of motorized traffic to providing speed management. This section presents traffic calming treatment options to increase the reliability of reducing vehicular speed. Speed reduction traffic calming treatments applied independently or in combination may be beneficial depending on the type and use of the treatments. Many speed management treatments have demonstrated varied effectiveness for single applications. Multiple treatments in series and parallel that build upon the context characteristics are more effective. Contact the Headquarters Design and Traffic offices for any project implementing a speed transition segment, for assistance on selection and monitoring of treatments.

Speed management techniques vary and have different results depending on the speed and types of users at a given location. The following subsections present different options for speed-reducing traffic calming treatments.

1103.05(2)(b)(1) Geometric Treatments

Geometric treatments can include overall changes of the horizontal or vertical geometry to introduce features that will support maintaining the targeted speed. Exhibit 1103-6 shows geometric traffic calming treatments and potential considerations when selecting these types of treatments.

1103.05(2)(b)(2) Roadside and Pavement Treatments

There are a number of treatments that create an environment that influences human factors and perception. Many successful roadside treatments use landscaping in an attempt to achieve the desired behavioral effect. It is important to coordinate with project partners to evaluate landscaping features and provide for traveled way operations and sight lines. The introduction of roadside features like trees, parking, and/or bicycle lanes to alert travelers to a change in conditions may be appropriate. Applying features like vegetated medians or trees is appropriate at some locations and contexts. In landscaping discussions, include Traffic Engineers,

Maintenance, Urban Forestry, Landscape Architects, and Human Factors and Safety Experts. If the landscaping proposed is in a managed access segment with local jurisdiction responsibility for the roadside, coordinate to understand the jurisdictions' capabilities to sustain the landscaping and that it meets their clear zone goals.

Pavement-related treatments can also produce undesirable impacts on other users. For pavement-related treatments, include Materials Engineers, Maintenance, Traffic, and ADA Compliance Experts to review what sustainable and effective treatments can be employed.

Exhibit 1103-7 lists roadside and pavement-related traffic calming treatments and considerations to evaluate.

Exhibit 1103-6 Geometric Traffic Calming Treatments and Considerations

Treatment	Considerations
Taper for Narrow Lanes	Narrowing the lane width can be achieved by restriping lane lines. A decision to taper in or out may depend on other treatments planned, such as introducing a median or chicanes. Base taper rates on the target speed entering the context or speed transition segment, as appropriate. It is recommended that this be the first treatment employed.
Chicanes/Lane Shifts	This treatment may be achieved with curbed features, like planter strips or striping combined with additional fixed delineators. These treatment types are more appropriate when reducing speeds from an initial intermediate speed or less. When introducing this treatment with initial high speeds, the treatment should utilize paint striping, in addition to using other treatments preceding the chicane/lane shift, rather than constructing hardscape features.
Pinch Points	Applies on intermediate to low target speed situations unless completed with striping or other pavement markings. This treatment uses striping, roadside features, or curb extensions to temporarily narrow the vehicle lane. It is likely more appropriate for maintaining a desired target speed within a segment than as part of a speed transition segment. Pinch points are not appropriate for high-speed segments. Use of pinch-point treatments on intermediate speed segments requires concurrence from the Region Traffic Engineer.
Speed Cushion/Humps/Tables	On state highways, this treatment will likely have limited application, but should not be excluded from consideration. Impacts to freight, transit, and emergency service vehicles need to be evaluated prior to selecting these vertical types of treatments. These treatments may only be used when maintaining a 25 mph target speed within a segment.
Raised Intersections	Raised intersections, similar to other vertical treatments, will have limited application on state highways. This treatment typically has higher costs to construct due to the pavement needs. This treatment may be a good option when a roundabout cannot be accommodated at a narrow intersection. It can also be considered where there is a need to improve visibility of the intersection and modal conflicts, especially at problematic stop control intersections planned to remain in place. This treatment may only be used when maintaining a 25 mph target speed within a segment.
Roundabouts	Roundabouts can be a unique feature, providing reduced serious injury collision potential, traffic calming, and gateway functions (See Chapter 1320 and the Roadside Policy Manual for details on roundabout design). Roundabouts are effective from a collision reduction and operational perspective, and they provide reduced driver workload, lower speeds, and limited conflict points. They can assist with access management or when turning movements are limited or restricted on a segment. To determine if a roundabout is appropriate at a specific location, follow the Intersection Control Analysis process described in Chapter 1300.

Exhibit 1103-7 Roadside, Streetside, and Pavement-Oriented Traffic Calming Treatments

Treatment	Considerations
Landscaping	Landscaping can be used in conjunction with other treatments to reinforce the surrounding context and the driver's perception of the context. It can also provide width for modal separation. Annual maintenance impacts need to be considered, weighed, and documented prior to selecting types of vegetation to be included.
Raised Vegetated Medians	Introduce a raised vegetated median following other treatments that prepare the driver for this feature. Appropriate for low to intermediate target speed locations and transition segments.
Transverse Rumble Strips	These in-lane rumble strips are intended to alert drivers to a condition change. They are likely placed in conjunction with and prior to traffic signing revisions or in advance of other speed-reducing traffic calming treatments. Appropriate for high, intermediate, or low target speed locations and transition segments.
Optical Speed Markings	This treatment is intended to influence a driver's perception. The treatment consists of 8-inch transverse paint strips within the vehicular lane extending from lane and edge markings (or curb). The striping intervals sequentially decrease, providing the perception of increasing speed, an indication to drivers to slow their operating speed. Optical Speed Markings are ideal for speed transition segments, and are recommended to be applied in conjunction with lane narrowing for high or intermediate target speed locations.
Dynamic Warning Systems	This treatment consists of actively alerting motorists about their operating speed. There are many different systems that accomplish this, including portable radar trailers and post-mounted systems. These can be either permanent or temporary installations. Appropriate for all speeds.
Gateways	The intent of a gateway feature is to alert travelers to a context change. A gateway feature is typically found on the edge of cities or towns, but can be used to highlight specific segments within cities or towns. The gateway can be anything from a banner/structure spanning the facility, to artistic work, landscaping, and/or a roundabout at the first intersection approaching a defined environment context. The gateway feature should be developed by the community. It may be of interest to design a gateway feature fitting the cultural and historic character of the location. Consideration for potential fixed object collisions is an important aspect of gateway design. Gateway features that span or are placed within state right of way will need specific approvals, as identified in Chapter 950. Appropriate for low to intermediate target speed locations and transition segments.

1103.06 Control: Terrain Classification

Terrain may limit operational and safety performance for particular modes. While terrain impacts may be addressed at specific locations, it is not cost beneficial to modify terrain continually throughout a corridor. The type of terrain, context, and speed influence the potential operating conditions of the highway, and should be a consideration when selecting mobility performance targets (See Chapter 1101). For more information on grades, see Chapter 1220.

To provide a general reference between terrain and geometric design, three classifications of terrain have been established:

1. **Level:** Level to moderately rolling, this terrain offers few or no obstacles to the construction of a highway having continuously unrestricted horizontal and vertical alignment.
2. **Rolling:** Hills and foothills, with slopes that rise and fall gently; however, occasional steep slopes might offer some restriction to horizontal and vertical alignment.
3. **Mountainous:** Rugged foothills; high, steep drainage divides; and mountain ranges.

Designate terrain as it pertains to the general character along the alignment of a corridor. Roadways in valleys or passes in mountainous areas might have the characteristics of roads traversing level or rolling terrain and are usually classified as level or rolling, rather than mountainous. See the *Highway Log* for terrain classification.

1103.07 Documentation

Document selections for design controls in Section 3 of the Basis of Design.

1103.08 References

1103.08(1) Federal/State Directives, Laws, and Codes

Secretary's Executive Order 1090 – Moving Washington Forward: Practical Solutions

Secretary's Executive Order 1096 – WSDOT 2015-17: Agency Emphasis and Expectations

Secretary's Executive Order 1028 – Context Sensitive Solutions

1103.08(2) Supporting Information

Designing Walkable Thoroughfares: A Context Sensitive Approach, Institute of Transportation Engineers, Washington D.C., 2010 www.ite.org

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO, Washington, D.C., Current Edition www.transportation.org/Pages/Default.aspx

Urban Street Design Guide, National Association of City Transportation Officials, New York, NY, 2013 www.nacto.org

Understanding Flexibility in Transportation Design – Washington, WA-RD 638.1, Washington State Department of Transportation, 2005
www.wsdot.wa.gov/research/reports/fullreports/638.1.pdf

NCHRP Report 613 – Guidelines for Selection of Speed Reduction Treatments at High Speed Intersections, Transportation Research Board, Washington D.C., 2008
http://onlinepubs.trb.org/onlinepubs/nchrp/nchrp_rpt_613.pdf

NCHRP Report 737 – Design Guidance for High-Speed to Low Speed Transition Zones for Rural Highways, Transportation Research Board, Washington D.C., 2012
http://onlinepubs.trb.org/onlinepubs/nchrp/nchrp_rpt_737.pdf

NCHRP Report 600 – Human Factors Guidelines for Road Systems, 2nd Edition, Transportation Research Board, Washington D.C., 2012
http://onlinepubs.trb.org/onlinepubs/nchrp/nchrp_rpt_600Second.pdf

NCHRP Synthesis 443 – Practical Highway Design Solutions, Transportation Research Board, Washington D.C., 2012 http://onlinepubs.trb.org/onlinepubs/nchrp/nchrp_syn_443.pdf

Measuring Sprawl 2014, Smart Growth America, Washington D.C., 2014
http://www.smartgrowthamerica.org/measuring-sprawl

Chapter 1104 Alternatives Analysis

1104.01 General
1104.02 Alternative Solution Formulation
1104.03 Alternative Solution Evaluation
1104.04 Documentation
1104.05 References

1104.01 General

Washington State Department of Transportation practical design policy requires formulating and evaluating alternatives while considering acceptable performance trade-offs to meet the need(s) of a project at the lowest level of investment. This chapter discusses how:

- Information determined from planning phases and Chapters 1101, 1102, and 1103 is utilized in alternative solution formation
- To evaluate the alternative solutions developed

This chapter presents methods for developing alternatives. For projects requiring an Environmental Assessment (EA) or an Environmental Impact Statement (EIS), a final proposed alternative may only be determined through the National Environmental Policy Act (NEPA) process and/or the State Environmental Policy Act (SEPA) process (see Chapter 400 of the Environmental Manual for more information). If an EA or EIS has not been initiated under NEPA/SEPA, follow the procedures in this chapter. To help advance the project, consider and use appropriate NEPA/SEPA terminology. Perform public and agency outreach and document all information regarding alternatives development for use later in the NEPA/SEPA process, according to 23 CFR 168(d). Terminology used in this chapter assumes that NEPA/SEPA have not been initiated. In the event that the NEPA/SEPA process has been initiated and an EA or EIS will be required, coordinate with the region Environmental Office staff to make sure that this alternative formulation and evaluation is performed in accordance with NEPA/SEPA guidance.

1104.02 Alternative Solution Formulation

An important function of alternative solution formulation is to identify alternatives that address the baseline need while balancing the performance trade-offs identified in the process. This can include analysis of multimodal trade-offs and the formulation of multimodal/intermodal solutions. Need identification and contributing factor analysis (CFA) are critical to alternative solution formulation (see Chapter 1101 and guidance document *Contributing Factors Analysis* for more information). Conduct alternative solutions formulation according to the following principles:

- Formulate alternatives compatible with context and design controls
- Form solutions around contributing factors or the underlying root reason(s) identified from CFA. Address the underlying root reason(s) determined from CFA in at least one alternative.
- Evaluate the relative benefit between each alternative against the baseline and contextual performance metrics to determine the optimally performing solution for the least cost. (See 1104.03(3) for information on calculating the benefit/cost of alternatives.)

Planning phase corridor sketches or studies may identify WSDOT's strategy for the corridor (see the guidance document section titled *Alternative Strategies and Solutions* for more information regarding different strategies that may be considered). If this has occurred, develop at least one alternative based on that identified strategy and bring forward into the alternative evaluation process (see 1104.03).

In some cases, planning studies may have developed specific alternatives. Carry planning phase alternatives into the alternative evaluation process, unless planning phase alternatives are obsolete. In some cases, alternatives may present opportunities for phased implementation.

1104.03 Alternative Solution Evaluation

Alternative solution evaluation involves understanding the performance benefits obtained from alternative solutions in relation to the selected design year and cost. It is the intent of the alternative solution evaluation process to:

- Compare solutions that resolve the baseline need(s) in consideration with the benefits or impacts associated with the contextual needs.
- Analyze the relative value of each alternative, including associated performance trade-offs.
- Mitigate unacceptable performance trade-offs with proven countermeasures.
- Refine targets if mitigation measures applied yield unacceptable performance trade-offs.

1104.03(1) Alternatives Comparison

WSDOT's alternatives comparison process is intended to align with performance-based decision-making. The process is complementary to a practical design approach. The process centers around achieving the basic performance need, while understanding and when necessary mitigating for the potential effects to other performance areas.

Use the Alternative Comparison Table (ACT) to assist in evaluating alternatives and identified baseline and contextual performance. The intent of comparing alternatives is to:

- Obtain an alternative solution for the least cost while understanding associated performance trade-offs.
- Compare alternatives against their ability to accomplish the baseline need.
- Evaluate alternatives against their relative effects on contextual needs.
- Provide the opportunity to incorporate mitigation or countermeasures.
- Document alternative formulation and evaluation outcomes that are consistent with the environmental process and expectations.

Note that if there are a large number of contextual needs under consideration, it may be beneficial to prioritize or use a weighted evaluation of the contextual needs in order to expedite the alternative evaluation.

As discussed in 1104.02, at least one alternative based on the outcome of Contributing Factors Analysis should be compared against other alternatives.

The Alternative Comparison Table template and examples can be found at:
www.wsdot.wa.gov/Design/Support.htm

1104.03(2) Performance Trade-off Decisions

In performance trade-off decisions, the intent is to give priority to the project's baseline needs. However, there will be situations where evaluations reveal that trade-offs are too significant, and there is an inability to adequately resolve them with low-cost countermeasures, phased solutions, or general acceptance of the performance trade-off. In these situations, it is appropriate to consider alternatives that still optimize the baseline performance metric, but do not necessarily obtain initial performance targets. Document refined performance targets on the Basis of Design.

1104.03(3) Benefit/Cost Analysis

Inherent with understanding the performance trade-offs being considered, is the overall benefit/cost for the alternatives proposed. In some cases, decisions will be based on life cycle cost for maintenance items, as discussed in Chapter 301. In other cases, perceived benefits are a challenge to quantify and will need analysis such as that discussed in *NCHRP Report 642: Quantifying the Benefits of Context Sensitive Solutions*:
www.trb.org/Publications/Blurbs/162282.aspx

1104.04 Documentation

The Alternative Comparison Table (ACT) is used to assist in evaluating alternatives. Summarize the alternatives evaluated with the ACT in Section 4 of the Basis of Design (BOD). Alternative formulation and evaluation will also be documented through the NEPA process. Environmental staff will help account for consistency with the environmental process, expectations and requirements throughout any alternative formulation and evaluation that occurs within project development.

1104.05 References

1104.05(1) Federal/State Directives, Laws, and Codes

42 United States Code (USC) 4321, National Environmental Policy Act of 1969 (NEPA)

Chapter 43.21C Revised Code of Washington (RCW), State Environmental Policy Act (SEPA)

Chapter 468-12 Washington Administrative Code (WAC), WSDOT SEPA Rules

Secretary's Executive Order 1090 – Moving Washington Forward: Practical Solutions

Secretary's Executive Order 1096 – WSDOT 2015-17: Agency Emphasis and Expectations

Secretary's Executive Order 1028 – Context Sensitive Solutions

Secretary's Executive Order 1018 – Environmental Policy Statement

1104.05(2) Guidance and Resources

Environmental Manual, M 31-11, WSDOT

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT

Understanding Flexibility in Transportation Design – Washington, WA-RD 638.1, Washington State Department of Transportation, 2005
www.wsdot.wa.gov/research/reports/fullreports/638.1.pdf

1104.05(3) Supporting Information

Designing Walkable Thoroughfares: A Context Sensitive Approach, Institute of Transportation Engineers, Washington D.C., 2010.
www.ite.org

NCHRP Report 642 – Guidelines for Quantifying the Benefits of Context Sensitive Solutions, Transportation Research Board, Washington D.C., 2014
http://www.trb.org/Publications/Blurbs/162282.aspx

NCHRP Synthesis 443 – Practical Highway Design Solutions, Transportation Research Board, Washington D.C., 2013
http://www.trb.org/Main/Blurbs/168619.aspx

Chapter 1105 Design Element Selection

1105.01 General
1105.02 Selecting Design Elements
1105.03 Related Elements
1105.04 Documentation
1105.05 References

1105.01 General

Design elements are specific components associated with roadway design, such as lane widths, shoulder widths, alignments, clear zone, etc. Design controls (see Chapter 1103) are carefully chosen and used to determine the dimensions of design elements. The relative effect that a given design element will have on performance will depend on the selected design controls and context identification. For more information, see the guidance document section titled *The Research Summary of Different Design Elements on Performance*.

1105.02 Selecting Design Elements

Design elements that are included in a project are documented in the *Basis of Design*. Include the design elements that are changed by the project. (See Chapter 1100 for more information about Basis of Design.)

An element is **changed** if one of the following applies:

- A new element is added
- An existing element is removed or relocated
- A dimension - such as a width - is modified

A design element that is **not changed** is not documented in the Basis of Design.

The next step after selecting design elements is to choose the appropriate dimension for each element. (See Chapter 1106 for information on selecting design element dimensions.)

1105.02(1) Required Design Elements and Criteria

There are also additional legal and policy-based considerations that require a decision of whether or not to include certain design elements in a project; this depends on the program or sub-program. See Exhibit 1105-1 for additional information regarding whether or not to include these design elements in a project.

Exhibit 1105-1 Required Design Elements

Program or Sub-Program	Design Elements						
	ADA	**Clear Zone [1]**	**Roadside Safety Hardware [3]**	**Signing & Delineation [4]**	**Illumination [7]**	**ITS [8]**	**Signal Hardware**
I-1 Mobility **I-3 Economic Initiative - Trunk System** **I-6 Sound Transit**	Apply the content in Chapter 1510 (1510.05)	Apply the content in Chapter 1600	Apply the content in Chapters 1600, 1610 and 1620	Apply the content in Chapter 1020 for signing and Chapter 1030 for delineation	Apply the content in Chapter 1040	Apply the content in Chapter 1050	[5]
All Preservation (P-1, P-2, P-3)	Apply the content in Chapter 1120 (1120.03(2))	[2]	Apply the content in Chapter 1120 (1120.03(7))	[2] [6]	[2]	[2]	[5]
I-2 Safety **I-4 Environmental Retrofit** **I-3 All Other**	Apply the content in Chapter 1510 (1510.05)	[2]	[2]	[2] [6]	[2]	[2]	[5]

Notes:

[1] See Chapter 1600

[2] Only include when changed as described in 1105.02.

[3] Includes all roadside safety design elements in Chapters 1600, 1610, and 1620.

[4] See Chapter 1020 for signing and Chapter 1030 for delineation

[5] Consult the Assistant State Design Engineer (ASDE), HQ Traffic Office, and Capital Program Development and Management Office (CPDM) to determine policy requirements.

[6] Consult the ASDE for policy requirements if the roadway channelization is changed.

[7] See Chapter 1040

[8] See Chapter 1050

1105.03 Related Elements

Design elements can be interrelated. Even if a specific design element has not changed in accordance with the definition in 1105.02, consider whether or not the preferred alternative has changed the conditions in a way that may affect the performance of an unchanged element, considering all modes.

Example: A project team proposes to provide a left-turn lane along a portion of their project in order to address a baseline need related to safety for turning traffic, by reducing the width of each highway shoulder. By reducing the shoulder width, the traveled way will be closer to the roadside than in the existing condition. The project team determines whether the project would adversely affect safety performance due to roadside conditions such as steep slopes or objects in the clear zone along with considering impacts to bike and pedestrian use.

1105.04 Documentation

Document design elements that are changed in Section 5 of the Basis of Design (BOD) form unless the exemptions listed in 1100.10(1) apply.

As a design alternative matures over time, it is likely that design elements may be added or dropped through the iterative process inherent with design. It is important to update the Basis of Design documentation with these changes at the various documentation and approval milestones.

The Basis of Design is available to download here:
www.wsdot.wa.gov/Design/Support.htm

1105.05 References

The *Research Summary of Different Design Elements on Performance*, WSDOT Guidance Document:
www.wsdot.wa.gov/Design/Support.htm

Chapter 1106 Design Element Dimensions

1106.01 General
1106.02 Choosing Dimensions
1106.03 The Mode/Function/Performance Approach
1106.04 Design Up Method
1106.05 Quantitative Analysis Methods and Tools
1106.06 Documenting Dimensions
1106.07 Design Analysis
1106.08 References

When choosing any dimension, read the guidance for the specific facility type (for example, for ramps see Chapter 1360) and also read the guidance for the specific element (for example for side slopes see Chapter 1239).

When a range of dimensions is given, consider modal needs, required function, and desired performance (1106.03) and, where possible, use quantitative tools to help choose a dimension within the range.

1106.01 General

Practical design resolves the project need with the least investment. Flexibility in the choice of design element dimensions helps accomplish this.

For guidance related to geometric cross-section elements, first see Chapter 1230. For guidance related to all other design elements, see the appropriate chapter.

1106.02 Choosing Dimensions

Depending on the facility type, *Design Manual* guidance may come in the form of a single dimension or a range of dimensions to choose from. See Exhibit 1106-1.


For some roadways, the optimum solution is very dependent on the location (context) of the roadway. In these cases, you will likely see a range of widths to choose from. For example, the geometric cross section guidance chapters for highways (Chapter 1231) and freeways (Chapter 1232) show cross-sections that list ranges to choose from for lane and shoulder widths.

The **mode/function/performance approach** described in 1106.03 is the tool to be used to choose the appropriate width from the range given.

Exhibit 1106-1 Dimensioning Guidance Variations



Example: *Exhibit 1360-14b calls out one specific dimension for the lane width of this section of a parallel off connection.*



Example: *Exhibit 1231-3 calls out a range of dimensions for the lane width.*

When a single dimension is given: If the decision is to use the dimension shown, no further evaluation is needed; just document the dimension choice on the Design Parameter Sheets.

If a particular roadway warrants use of a dimension that is different than the value given, the mode/function/performance approach described in 1106.03 can be used to determine the appropriate dimension. Results will need to be documented in a Design Analysis.

When a range of widths is given: Understand any width considerations specific to the design element (for example, lane width considerations are described in Chapter 1231). Use the mode/function/performance approach described in 1106.03 to choose the appropriate value within the range. If the dimension chosen is within the range given in the *Design Manual*, document the reasoning in the Design Parameter Sheets. If the value chosen is outside of the given range, document the decision in a Design Analysis.


Some dimension choices can be complex, and involve trade-off evaluations, including comparisons of alternatives, benefit/cost analysis, etc. In these instances, it may be appropriate to record the dimension choice on the Design Parameter Sheets and reference any related documents that support the dimension choice.

1106.03 The Mode/Function/Performance Approach

The **mode/function/performance approach** is the primary methodology to apply when a range of dimensions is given. Utilizing this approach ensures that modal needs, the function of the design element, and safety and mobility performance have all been considered. For example, lanes and shoulders have to accommodate the modes that use the roadway, provide functions that are appropriate for the specific roadway, and provide appropriate safety and mobility performance.

Modes, function and performance overlap and are interrelated. These considerations are part of a tradeoffs discussion. Cost is always a consideration in a tradeoffs discussion. Engineering judgment and stakeholder involvement will be required.

Exhibit 1106-2 Mode/Function/Performance Approach



Modal accommodation: It is important to understand the modal needs for a roadway. Accommodating a specific mode (or modes) may influence the dimension choice.

For example, it is important to understand the vehicle mix that will be using the lanes and to understand the modes that will be using the shoulder. For lanes, a significant number of trucks and oversized vehicles may affect the lane width choice, especially if the alignment is not tangent. Read Chapter 1231 when choosing lane widths.

For shoulders, it is important to understand bicyclist and pedestrian use. The width requirements that come with accommodating various modes are discussed in Chapter 1239.

Function(s): Function is closely related to modal accommodation. Providing a specific function may drive the dimension choice.

For example, the shoulder width requirements that come with providing various functions bring a wide range of associated widths (see Exhibit 1239-2, Shoulder Function & Modal Accommodation Width Considerations).

Performance: When choosing a dimension from a range of possible choices, consider safety performance and mobility performance. Meeting safety or mobility performance targets may drive the dimension choice.

When evaluating performance, the use of quantitative engineering methods and tools is encouraged whenever possible. See 1106.05 for more information on quantitative tools and methodology for evaluating safety and mobility performance.

An important consideration of performance evaluation is whether or not the project has an identified baseline (or contextual) safety need. If safety need has been identified, performance metrics and targets may play a major role in choosing dimensions. See Chapter 1101.

For some projects, modal accommodation needs may drive lane and shoulder width decisions. In other cases, the need to provide a specific function may drive width decisions. And, in some cases, meeting established performance targets may drive width decisions. Regardless of whether modal accommodation, function, or performance drives the dimension choice, the effect of the decision on mobility and safety performance has to be considered.

Accommodating modal needs, providing specific functions, or achieving specific performance targets may require widths that can bring significant investments. Consider the cost and associated trade-offs, and document why it is worthy of the associated investment.

In addition to being the primary method to choose a dimension when a range of dimensions is given, the mode/function/performance approach can also be used in support of a Design Analysis.

1106.04 Design Up Method

When a range of dimensions is given, guidance may specifically require a "design up" approach. For example, Chapter 1231 requires a design up approach for state highways other than freeways.

Design up means considering the smallest dimension first. Increasing dimensions are then considered until the smallest dimension is identified that accommodates modal needs, provides the desired functions, and provides appropriate safety and mobility performance. Using the mode/function/performance approach described in 1106.03 is an important part of design up.

1106.05 Quantitative Analysis Methods and Tools

Currently, two primary tools exist to quantitatively evaluate performance; the *Highway Safety Manual* (HSM) for evaluating modal safety performance and the *Highway Capacity Manual* (HCM) for evaluating traffic operational mobility performance.

1106.05(1) Highway Safety Manual and Safety Modeling

Safety is and always has been a primary performance category for WSDOT. Past design policy relied on the assumption that the application of design criteria equated to a desired level of safety performance for the expenditure. This assumption may not have always been true for all locations given their operational and geometric characteristics. The strict application of criteria to achieve safety performance is known as "nominal safety." To achieve a more reliable safety performance, scientific estimation of crashes using site conditions is necessary and is termed "substantive safety." A new understanding of safety performance, crash modification factors, and roadway functions has led to a growing body of knowledge about the relationship between roadway characteristics and safety performance.

The application of the *Highway Safety Manual* (HSM) and its companion tools provides an understanding of how a particular design can perform with respect to safety. This enables analysis of safety-specific performance metrics that may be more critical to address. The HSM covers multiple transportation road types and can be a valuable tool to analyze various geometric alternatives in any program type.

For guidance regarding whether or not to include a baseline safety need see Chapter 1101. For more information on sustainable highway safety tools and analysis, see Chapter 321.

1106.05(2) Highway Capacity Manual and Traffic Modeling

The *Highway Capacity Manual* (HCM) provides quantitative methods for evaluating mobility operational performance. However, some quantitative outputs from some HCM methods are specific to free-flow speed operations or level of service, and may not be appropriate for use given the baseline mobility performance metric selected for a specific location. Traffic modeling software provides a more relevant method for understanding the mobility operational performance; however, the reliability of the outputs varies given the traffic forecasting for design years further in the future. Utilize traffic modeling to ascertain potential mobility operational performance whenever feasible.

1106.06 Documenting Dimensions

While a primary function of the Basis of Design is to document the design elements selected to be included in a project, another primary function of the Design Parameter Sheets is to document the dimensions chosen for the various design elements included in a project.

Important Note: If the dimension for an existing design element does not change, no documentation is required on the Design Parameter sheets. A Design Parameter Sheet entry left blank means that the element was not selected to be included in the project. (See Chapter 1105 for design element selection guidance.) A Design Parameter Sheet template can be found here: http://www.wsdot.wa.gov/Design/Support.htm.

1106.07 Design Analysis

A Design Analysis is required when a dimension chosen does not meet the value, or fall within the range of values, provided for that element in the *Design Manual* (see Chapter 300.) The considerations described in 1106.03 may be useful when completing a Design Analysis.

1106.08 References

Highway Capacity Manual (HCM), latest edition, Transportation Research Board, National Research Council

Highway Safety Manual (HSM), AASHTO

Washington State's Target Zero Strategic Safety Plan

http://www.targetzero.com/plan.htm

Chapter 1120 Preservation Projects

1120.01 General
1120.02 Structures Preservation (P2) and Other Facilities (P3)
1120.03 Pavement Preservation (P1)

1120.01 General

This chapter provides information specific to preservation project types.

This chapter identifies those elements and features to be evaluated and potentially addressed during the course of a preservation project. The elements listed here may be in addition to the project need identified in the Project Summary or Basis of Design (see 1120.04). Preservation projects may also provide opportunities for project partnering and retrofit options involving additional elements (see 1231.06).

Preservation projects are funded in three program areas:

- **Roadway Preservation (P1) projects** preserve pavement structure, extend pavement service life, and restore the roadway for reasonably safe operations.
- **Structures Preservation (P2) projects** preserve the state's bridge network through cost effective actions. There are numerous types of bridge preservation actions including: deck rehabilitation, seismic retrofit, painting steel bridges, scour repair, and others.
- **Other Facilities (P3)** includes guardrail and signing, major drainage, major electrical, unstable slopes and other project types.

For more information on these programs see the Planning & Programming – Scoping website:
http://wwwi.wsdot.wa.gov/Planning/CPDMO/PlanProgScoping.htm

1120.02 Structures Preservation (P2) and Other Facilities (P3)

For Structures Preservation (P2) and Other Facilities (P3) projects see the scoping instructions specific to the sub-program and type of work to determine the likely design elements to be addressed by the project.

See Chapter 300 for documentation requirements. If the project changes a geometric design element, replaces an existing bridge or installs a new bridge additional documentation may be required; contact your ASDE to discuss appropriate documentation.

1120.03 Pavement Preservation (P1)

This section applies to features and design elements to be addressed on Pavement Preservation (P1) projects.

See 1120.03(8) Documentation for instructions on using the Basis of Design to document design elements and adjusted features.

1120.03(1) Adjust existing features

- Adjust existing features such as monuments, catch basins, and access covers that are affected by resurfacing.

- Evaluate drainage grates and replace as needed to address bicycle safety (see Drainage Grates and Manhole Covers in Chapter 1520).
- For guidance on existing curb see Chapter 1239.
- Reinstall centerline and shoulder rumble strips, if present, using criteria and guidance provided in Chapter 1600.

1120.03(2) ADA requirements

- Address ADA requirements according to WSDOT policy (see Chapter 1510 and any active project delivery memorandums or design memorandums).

1120.03(3) Cross slope lane

- Rebuild the cross slope to a minimum 1.5% when the existing cross slope is flatter than 1.5% and the steeper slope is needed to provide adequate highway runoff. See Chapter 1250 for more information about cross slope.

1120.03(4) Cross slope shoulder

- When rebuilding the lane cross slope, evaluate shoulder cross slope in accordance with Chapter 1250.

1120.03(5) Vertical clearance

- Paving projects, and seismic retrofit projects, may impact vertical clearances (see Chapter 720 for bridge clearances and Chapter 1020 for overhead sign assemblies.)
- If vertical clearance will be changed by the project, evaluate this in accordance with Chapter 720 and include this design element in the Basis of Design and the Design Parameters sheets and the Design Documentation Package.
- Contact the Commercial Vehicle Services Office when changes to vertical clearance are planned.

1120.03(6) Delineation

- Install and replace delineation in accordance with Chapter 1030 (this includes only pavement markings, guideposts, and barrier delineation).
- Replace rumble strips if they are removed through project actions, or if their average depth is less than 3/8”, unless there is a documented justification for their removal (see Chapter 1600).

1120.03(7) Barriers and terminals

- When the height of a guardrail, terminal, and/or transition as measured from the ground to the top of the rail element will be affected by the project, then adjust the height in accordance with guidance provided in Chapter 1610 if it meets the following conditions:
  - The height of a Type 1 guardrail, terminal or transition will be reduced to less than 26.5 inches or increased to greater than 30 inches.

  - The height of a Type 31 guardrail, terminal or transition will be reduced to less than 28 inches or increased to greater than 32 inches.

- One terminal that was used extensively on Washington's highways was the Breakaway Cable Terminal (BCT). This system used a parabolic flare similar to the Slotted Rail Terminal (SRT) and a Type 1 anchor (Type 1 anchor posts are wood set in a steel tube or a concrete foundation). For Roadway Preservation (P1) projects replace BCTs on limited access routes and ramps. On other non-limited access routes, BCTs that have at least a 3-foot offset (measured at face of rail relative to the tangent line of the guardrail run's face of rail) may remain in place unless the guardrail run or anchor is being reconstructed or reset. Raising the rail element is not considered reconstruction or resetting.
- Evaluate the guardrail length of need accordance with Chapter 1610 for runs that need to be raised as a result of an HMA overlay. Up to 250 feet of additional run length within each run is permissible in Pavement Preservation (P1) projects.
- Note that removal is an option if guardrail is no longer needed based on validation of the original guardrail purpose from past project documentation and after consulting Chapters 1600 and 1610. Document the location of removal and the reasoning for removal in the Design Documentation Package.
- When adjusting terminals that are equipped with CRT posts, the top-drilled holes in the posts need to remain at the surface of the ground.
- Pre-cast concrete barrier sections (either New Jersey or "F" shape) are normally installed at 32" height, which includes provision for up to 3" overlay. A 29" minimum height for this type of barrier must be maintained following an overlay.
- Single slope concrete barrier may be pre-cast or cast in place, and is installed new at a height of 42", 48", or 54". A 30" minimum height must be maintained for this type of barrier following an overlay.

1120.03(8) Documentation

For Pavement Preservation (P1) projects, use the Basis of Design to document decisions when the project changes any design elements that are not listed in 1120.03(1) through 1120.03(7). Document any changes to dimensions on the Design Parameter Sheets.

Chapter 1210 Geometric Plan Elements

1210.01 General
1210.02 Horizontal Alignment
1210.03 Distribution Facilities
1210.04 Number of Lanes and Arrangement
1210.05 Pavement Transitions
1210.06 Procedures
1210.07 Documentation
1210.08 References

1210.01 General

This chapter provides guidance on the design of horizontal alignment, frontage roads, number of lanes, arrangement of lanes, and pavement transitions. For additional information, see the following chapters:

Chapter	Subject
1230	Lane and shoulder widths
1240	Lane widths on turning roadways for full design level
1250	Superelevation rate and transitions
1260	Sight distance
1310	Guidelines for islands
1360	Ramp lane and shoulder guidelines

1210.02 Horizontal Alignment

1210.02(1) General

Horizontal and vertical alignments (see Chapter 1220) are the primary controlling elements for highway design. It is important to coordinate these two elements with design speed, drainage, intersection design, and aesthetic principles in the early stages of design. How horizontal alignments are designed depends largely on the context and selected design controls. Lower-speed environments can be more forgiving than higher-speed environments.

1210.02(1)(a) Low-Speed Alignments

Consider the following when designing low-speed horizontal alignments:

a. Determine whether sufficient contextual elements exist within the roadway cross section to indicate the desired low-speed environment (street trees, lack of building setbacks, streetside amenities, etc.).

b. Determine whether horizontal geometric traffic calming treatments will be needed to maintain the selected design speed (see Chapter 1103).

c. Avoid placing pedestrian midblock crossings within horizontal curves.

1210.02(1)(b) High-Speed Alignments

Horizontal alignments designed for high speed are likely to have modal priorities for freight and passenger vehicles, and it is necessary to strive for forgiving and predictable alignments within high-speed environments. Exhibits 1210-2a through 1210-2c show desirable and undesirable alignment examples for use with the following considerations:

a. Make the highway alignment as direct as practicable and still blend with the topography while considering developed and undeveloped properties, community boundaries, and environmental concerns.

b. Make highway alignment consistent by:

- Using gentle curves at the end of long tangents.
- Using a transition area of moderate curvature between the large radius curves of rural areas and the small radius curves of populated areas.
- Making horizontal curves visible to approaching traffic.

c. Avoid minimum radii and short curves unless:

- Restrictive conditions are present and alternatives are not readily or economically avoidable.
- On two-lane highways, minimum radii result in tangent sections long enough for needed passing.

d. Avoid any abrupt change in alignment. Design reverse curves with an intervening tangent long enough for complete superelevation transition for both curves. (See Chapter 1250 for more information on superelevation transitions.)

e. Avoid the use of curves in the same direction connected by short tangents (broken back curves); substitute a single larger curve.

f. Avoid compound curves on open highway alignment if a simple curve can be obtained. When compound curves are used, make the shorter radius at least two-thirds the longer radius. Make the total arc length of a compound curve not less than 500 feet.

g. On divided multilane highways, take advantage of independent alignment to produce a flowing alignment along natural terrain.

h. The desirable locations for bridges, interchanges, intersections, and temporary connections are on tangent sections in clear view of drivers.

i. On two-lane two-way highways, strive for as much passing sight distance as possible (see Chapter 1260).

1210.02(2) Horizontal Curve Radii

Design speed is the governing variable of horizontal curves. For guidance regarding design speed selection, see Chapter 1103, and see Chapter 1360 for ramps.

Use the following factors to determine the radius for a curve:

- Low to intermediate design speed environments may need to utilize horizontal curves to maintain the desired operating speed. Horizontal curvature, more than any other design element or treatment, provides the best speed management results. (See Chapter 1103 for more information on speed management.)
- Stopping sight distance where sight obstructions are on the inside of a curve. Median barriers, bridges, walls, cut slopes, wooded areas, buildings, and guardrails are examples of sight obstructions. (See Chapter 1260 to check for stopping sight distance for the selected design speed.)
- Superelevation is the rotation or banking of the roadway cross section to overcome part of the centrifugal force that acts on a vehicle traversing a curve. Design information on the relationship between design speed, radius of curve, and superelevation is in Chapter 1250.
- Coordinate vertical and horizontal alignment (see Chapter 1220).

Spiral curves, although no longer used on new highway construction or major realignment, still exist on Washington's highways. Spirals were used to transition between tangents and circular curves with the horizontal curvature rate increasing from tangent to the central curve and decreasing from curve to tangent. Spirals do not pose an operational concern and may remain in place. (See *A Policy on Geometric Design of Highways and Streets* for information on spirals.)

1210.02(3) Horizontal Curve Length

A curve is not required for small deflection angles. Exhibit 1210-1 gives the maximum allowable angle without a curve. (See Chapter 1310 for guidance on angle points or short radii curves in the vicinity of intersections at grade.)

To avoid the appearance of a kink in the road, the desirable length of curve for deflection angles larger than given in Exhibit 1210-1 is at least 500 feet.

Exhibit 1210-1 Maximum Angle Without Curve

Design Speed (mph)	Maximum Angle Without Curve
25	2°17′
30	1°55′
35	1°38′
40	1°26′
45	1°16′
50	1°09′
55	1°03′
60	0°57′
65	0°53′
70	0°49′
75	0°46′
80	0°43′

1210.03 Distribution Facilities

1210.03(1) General

In addition to the main highway under consideration, other facilities can be used to distribute traffic to and from the highway and to provide access. Highway flexibility can be augmented by:

- Frontage roads
- Collector-distributor roads
- On and off connections
- Parallel arterial routes with connections between them and the main highway
- Loop highways around large metropolitan areas

A city or county may be asked to accept a proposed distribution facility as a city street or county road. Plan and design these facilities according to the applicable design values as city streets or county roads (see Chapter 1230).

1210.03(2) Frontage Roads

Frontage roads constructed as part of highway development may serve to:

- Reestablish continuity of an existing road severed by the highway.
- Provide service connections to adjacent property that would otherwise be isolated as a result of construction of the highway.
- Control access to the highway.
- Maintain circulation of traffic on each side of the highway.
- Segregate local traffic from the higher speed through traffic and intercept driveways of residences and commercial establishments along the highway.
- Relieve congestion on the arterial highway during periods of high use or in emergency situations.

Frontage roads are generally not permanent state facilities. They are usually turned back to the local jurisdiction. Plan and design frontage roads as city streets or county roads (see Chapter 1230). Initiate coordination with the local agency that will be the recipient of the facility early in the planning process, and continue through design and construction. (See Chapter 530 for additional guidance on frontage roads and turnbacks.)

Outer separations function as buffers between the through traffic on the highway and the local traffic on the frontage road. The width is governed by requirements for grading, signing, barriers, aesthetics, headlight glare, and ramps. Where possible, make the separation wide enough to allow for development on both sides of the frontage road. Wider separations also move the intersection with the frontage road and a crossroad farther from the intersection with the through roadway, and they can reduce the amount of limited access control rights to be acquired (see Chapter 530).

Where two-way frontage roads are provided, make the outer separation wide enough to minimize the effects of approaching traffic on the right, particularly the headlight glare. (See Chapter 1600 for information on headlight glare considerations.) With one-way same-direction frontage roads, the outer separation need not be as wide as with two-way frontage roads.

Wide separations lend themselves to landscape treatment and can enhance the appearance of both the highway and the adjoining property.

A substantial width of outer separation is particularly advantageous at intersections with cross streets. The wider separation reduces conflicts with pedestrians and bicycles.

Where ramp connections are provided between the through roadway and the frontage road, the minimum outer separation width depends on design of the ramp termini.

1210.04 Number of Lanes and Arrangement

1210.04(1) General

The basic number of lanes is designated and maintained over a length of highway. The total number of lanes is the basic number of lanes plus any auxiliary lanes provided to meet:

- Level of service (volume-capacity)
- Lane balance
- Flexibility of operation

1210.04(2) Basic Number of Lanes

In certain situations, it is appropriate to keep the basic number of lanes constant over a highway route, or a significant portion thereof, regardless of changes in traffic volume. However, this can lead to unnecessary property or environmental impacts that need to be balanced throughout a design. Consider the impacts, human factors, and traffic analysis before making decisions regarding basic number of lane consistency throughout a highway route.

Change the basic number of lanes for general changes in traffic volume over a substantial length of the route. The desirable location for a reduction in the basic number of lanes is on a tangent section between interchanges or intersections. However, there can be advantages in using dedicated turn lanes at intersections as a means to reduce the number of lanes.

To accommodate high traffic volumes for short distances, such as between adjacent interchanges, use auxiliary lanes. When auxiliary lanes are provided on consecutive sections between interchanges, consider increasing the basic number of lanes through the entire length.

1210.04(3) Auxiliary Lanes

Auxiliary lanes are added to the basic number of lanes to allow additional traffic movements on short segments. These added lanes are based primarily on volume-to-capacity relationships (see Chapter 320). For efficient operation of auxiliary lanes, see the following:

Chapter	Subject
1270	Truck climbing and passing lanes
1310	Left- and right-turn lanes and storage for turning
1360	Weaving and auxiliary lanes associated with interchanges

1210.05 Pavement Transitions

1210.05(1) Lane Transitions

1210.05(1)(a) Change Lane Width

For lane width changes that create an angle point in an adjacent lane, the maximum angle is given in Exhibit 1210-1. When a lane width change does not create an angle point in an adjacent lane, a 25:1 taper is sufficient.

1210.05(1)(b) Reduce Number of Lanes

To reduce the number of lanes, provide a transition with the following guidelines:

- Locate transitions where decision sight distance exists, desirably on a tangent section and on the approach side of any crest vertical curve, except the end of climbing lanes, which are transitioned in accordance with Chapter 1270.
- Supplement the transition with traffic control devices.
- Reduce the number of lanes by dropping only one at a time from the right side in the direction of travel. (See the MUTCD when dropping more than one lane in a single direction.)
- Use the following formula to determine the minimum length of the lane transition for speeds 45 mph or more:

$$L = VT$$

Where:
L = Length of transition (ft)
V = Design speed (mph)
T = Tangential offset width (ft)

- Use the following formula to determine the minimum length of the lane transition for speeds less than 45 mph:

$$L = \frac{TV^2}{60}$$

Where:
L = Length of transition (ft)
V = Design speed (mph)
T = Tangential offset width (ft)

1210.05(1)(c) Increase Number of Lanes

To increase the number of lanes, a tangential rate of change in the range of 1:4 to 1:15 is sufficient. Aesthetics are the main consideration.

1210.05(1)(d) Turning Roadway

For turning roadway widening width transitions, see Chapter 1240.

1210.05(2) Median Width Transitions

Whenever two abutting sections have different median widths, use long, smooth transitions (L = VT or flatter). When horizontal curves are present, this can be accomplished by providing the transition throughout the length of the curve. For transitions on tangent sections, the transitions may be applied symmetrically about the centerline or on only one side of the median based on whether or not the abutting existing section is programmed for the wider median in the future. For aesthetics, make the transition length as long as feasible.

1210.06 Procedures

When the project realigns the roadway, develop horizontal alignment plans for inclusion in the Plans, Specifications & Estimates. Show the following as needed to maintain clarity and provide necessary information:

- Horizontal alignment details (tangent bearing, curve radius, and superelevation rate)
- Stationing
- Number of lanes
- Intersections, road approaches, railroad crossings, and interchanges (see Chapters 1310, 1340, 1350, and 1360)
- Existing roadways and features affecting or affected by the project

For additional plan guidance, see the *Plans Preparation Manual*.

Justify any realignment of the roadway. Include the reasons for the realignment, profile considerations, and alternatives considered, and the reasons the selected alignment was chosen.

When the project changes the number of lanes, include a capacity analysis supporting the number selected (see Chapter 320) with the justification for the number of lanes.

Include with the justification for a frontage road any traffic analyses performed; the social, environmental, and economic considerations; the options considered; and the reasons for the final decision.

1210.07 Documentation

Refer to Chapter 300 for design documentation requirements.

1210.08 References

1210.08(1) Federal/State Laws and Codes

Washington Administrative Code (WAC) 468-18-040, Design standards for rearranged county roads, frontage roads, access roads, intersections, ramps and crossings

1210.08(2) Design Guidance

Local Agency Guidelines (LAG), M 36-63, WSDOT

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)

Plans Preparation Manual, M 22-31, WSDOT


Right of Way Manual, M 26-01, WSDOT

Utilities Manual, M 22-87, WSDOT

1210.08(3) Supporting Information

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO, current edition

Exhibit 1210-2a Alignment Examples








Exhibit 1210-2b Alignment Examples




Desirable - Consistency with Topography




Undersirable - Heavy Cuts and Fills

Exhibit 1210-2c Alignment Examples



Desirable - Daylighting and a Simple Curve



Undesirable - Short Curve Reversals

Chapter 1220 Geometric Profile Elements

1220.01 General
1220.02 Vertical Alignment
1220.03 Coordination of Vertical and Horizontal Alignments
1220.04 Airport Clearance
1220.05 Railroad Crossings
1220.06 Procedures
1220.07 Documentation
1220.08 References

1220.01 General

Vertical alignment (roadway profile) consists of a series of gradients connected by vertical curves. It is mainly controlled by the following:

- Topography
- Class of highway
- Horizontal alignment
- Safety
- Sight distance
- Construction costs
- Drainage
- Adjacent land use
- Vehicular characteristics
- Aesthetics

This chapter provides guidance for the design of vertical alignment. For additional information, see the following chapters:

Chapter	Subject
1103	Design controls, terrain
1210	Horizontal alignment
1260	Sight distance
1310	Grades at intersections
1360	Maximum grade for ramps

1220.02 Vertical Alignment

1220.02(1) Design Principles

The following are general principles for developing vertical alignment (also see Exhibits 1220-2a through 2c):

- Use a smooth grade line with gradual changes, consistent with the context identification and character of terrain. Avoid numerous breaks and short grades.

- Avoid "roller coaster" or "hidden dip" profiles by use of gradual grades made possible by heavier cuts and fills or by introducing some horizontal curvature in conjunction with the vertical curvature.
- Avoid grades that affect truck speeds and, therefore, traffic operations.
- Avoid broken back grade lines with short tangents between two vertical curves.
- Use long vertical curves to flatten grades near the top of long, steep grades.
- Where at-grade intersections occur on roadways with moderate to steep grades, it is desirable to flatten or reduce the grade through the intersection.
- Establish the subgrade at least 1 foot above the high water table (real or potential), or as recommended by the Region Materials Engineer. Consider the low side of superelevated roadways.
- When a vertical curve takes place partly or wholly in a horizontal curve, coordinate the two as discussed in 1220.03.

1220.02(2) Minimum Length of Vertical Curves

The minimum length of a vertical curve is controlled by design speed, stopping sight distance, and the change in grade. Make the length of a vertical curve, in feet, not less than three times the design speed, in miles per hour. (See Chapter 1260 to design vertical curves to meet stopping sight distance criteria.) For aesthetics, the desirable length of a vertical curve is two to three times the length to provide stopping sight distance.

Sag vertical curves may have a length less than required for stopping sight distance when all three of the following are provided:

- An analysis to justify the length reduction.
- Continuous illumination.
- Design for the comfort of the vehicle occupants. For comfort, use:

$$L = \frac{AV^2}{46.5}$$

Where:

L = Curve length (ft)
A = Change in grade (%)
V = Design speed (mph)

The sag vertical curve lengths designed for comfort are about 50% of those for sight distance.

1220.02(3) Maximum Grades

Analyze grades for their effect on traffic operation because they may result in undesirable truck speeds. Maximum grades are controlled by terrain type and design speed (see Grade and Speed Considerations below and Chapters 1103 and 1360).

1220.02(4) Minimum Grades

Minimum grades are used to meet drainage requirements. Avoid selecting a “roller coaster” or “hidden dip” profile merely to accommodate drainage.


Minimum ditch gradients of 0.3% on paved materials and 0.5% on earth can be obtained independently of roadway grade. Medians, long sag vertical curves, and relatively flat terrain are examples of areas where independent ditch design may be justified. A closed drainage system may be needed as part of an independent ditch design.

1220.02(5) Length of Grade

The desirable maximum length of grade is the maximum length on an upgrade at which a loaded truck will operate without a 10 mph reduction. Exhibit 1220-1 gives the desirable maximum length for a given percent of grade. When grades longer than the desirable maximum are unavoidable, consider an auxiliary climbing lane (see Chapter 1270). For grades that are not at a constant percent, use the average.

When long, steep downgrades are unavoidable, consider an emergency escape ramp, and for grades longer than indicated, consider an auxiliary climbing lane (see Chapter 1270).

Exhibit 1220-1 Grade Length



For grades longer than indicated, consider an auxiliary climbing lane (see Chapter 1270).

1220.02(6) Grade and Speed Considerations

Grades can affect the operating performance of the vehicles negotiating them. The bicycle, transit, and freight modes are most affected by grades, while passenger cars can readily negotiate grades as steep as 5% without appreciable loss of operating speed. Steep downgrades can also impact operating speeds, particularly for heavy trucks, which display up to a 5% increase in speed on downgrades. Consider the selected performance for a location and corridor before making a determination on grade selection, to avoid unnecessary cuts or fills required for a vertical alignment. The following tables provide suggestions for determining maximum grades based on the context, terrain classification, and targeted speed. However, these grades may vary from these values depending on the performance targeted for a location.

Table 1 Maximum Grades for Rural Contexts

Type of Terrain	Design Speed (mph)											
	25	30	35	40	45	50	55	60	65	70	75	80
Level	6-7	6-7	6-7	5-7	5-7	4-6	4-6	3-5	3-5	3-4	3	3
Rolling	8-10	7-9	7-9	6-8	6-8	5-7	5-7	4-6	4-6	4-5	4	4
Mountainous	9-11	8-10	8-10	8-10	7-10	7-9	6-9	6-8	5-8	5-6	5	5

Table 2 Maximum Grades for Suburban and Urban Contexts

Type of Terrain	Design Speed (mph)								
	20	25	30	35	40	45	50	55	60
Level	8-9	8-9	8-9	7-9	7-9	6-8	6-7	5-7	5-6
Rolling	11-12	11-12	9-11	8-10	8-10	7-9	7-8	6-8	6-7
Mountainous	13-14	12-13	11-12	10-12	10-12	9-11	9-10	8-10	8-9

Table 3 Maximum Grades for Interstate and Full Limited Access Control Facilities

Type of Terrain	Design Speed (mph)						
	50	55	60	65	70	75	80
Level	4	4	3	3	3	3	3
Rolling	5	5	4	4	4	4	4
Mountainous	6-7	6-7	6-7	6-7	5-6	5-6	5-6

1220.02(6) Alignment on Structures

Where practicable, avoid high skew, vertical curvature, horizontal curvature, and superelevation on structures, but do not sacrifice safe roadway alignment to achieve this.

1220.03 Coordination of Vertical and Horizontal Alignments

Do not design horizontal and vertical alignments independently. Coordinate them to obtain uniform speed, pleasing appearance, and efficient traffic operation. Coordination can be achieved by plotting the location of the horizontal curves on the working profile to help visualize the highway in three dimensions. Perspective plots will also give a view of the proposed alignment. Exhibits 1220-2a and 2b show sketches of desirable and undesirable coordination of horizontal and vertical alignment.

Guides for the coordination of the vertical and horizontal alignment are as follows:

- Balance curvature and grades. Using steep grades to achieve long tangents and flat curves or excessive curvature to achieve flat grades are both poor designs.
- Vertical curvature superimposed on horizontal curvature generally results in a more pleasing facility. Successive changes in profile not in combination with horizontal curvature may result in a series of dips not visible to the driver.
- Do not begin or end a horizontal curve at or near the top of a crest vertical curve. A driver may not recognize the beginning or ending of the horizontal curve, especially at night. An alignment where the horizontal curve leads the vertical curve and is longer than the vertical curve in both directions is desirable.

- To maintain drainage, design vertical and horizontal curves so that the flat profile of a vertical curve is not located near the flat cross slope of the superelevation transition.
- Do not introduce a sharp horizontal curve at or near the low point of a pronounced sag vertical curve. The road ahead is foreshortened and any horizontal curve that is not flat assumes an undesirably distorted appearance. Further, vehicular speeds, particularly of trucks, often are high at the bottom of grades and erratic operation may result, especially at night.
- On two-lane roads, the need for passing sections (at frequent intervals and for an appreciable percentage of the length of the roadway) often supersedes the general desirability for the combination of horizontal and vertical alignment. Work toward long tangent sections to secure sufficient passing sight distance.
- On divided highways, consider variation in the width of medians and the use of independent alignments to derive the design and operational advantages of one-way roadways.
- Make the horizontal curvature and profile as flat as practicable at intersections where sight distance along both roads is important and vehicles may have to slow or stop.
- In residential areas, design the alignment to minimize nuisance factors to the neighborhood. Generally, a depressed facility makes a highway less visible and less noisy to adjacent residents. Minor horizontal adjustments can sometimes be made to increase the buffer zone between the highway and clusters of homes.
- Design the alignment to enhance attractive scenic views of the natural and constructed environment, such as rivers, rock formations, parks, and outstanding buildings.

When superelevation transitions fall within the limits of a vertical curve, plot profiles of the edges of pavement and check for smooth transitions.

1220.04 Airport Clearance

Contact the airport authorities early for proposed highway construction or alteration in the vicinity of a public or military airport, so that advance planning and design work can proceed within the required Federal Aviation Administration (FAA) regulations (see the *Environmental Manual*).

1220.05 Railroad Crossings

When a highway crosses a railroad at grade, design the highway grade to prevent low-hung vehicles from damaging the rails or getting hung up on the tracks. Exhibit 1220-3 gives guidance on designing highway grades at railroad crossings. For more information on railroad-highway crossings, see Chapter 1350.

1220.06 Procedures

When the project modifies the vertical alignment, develop vertical alignment plans for inclusion in the Plans, Specifications, and Estimates (PS&E) to a scale suitable for showing vertical alignment for all proposed roadways, including ground line, grades, vertical curves, and superelevation. (See the *Plans Preparation Manual* for guidance.)

When justifying any modification to the vertical alignment, include the reasons for the change, alternatives addressed (if any) and why the selected alternative was chosen. When the profile is a result of new horizontal alignment, develop vertical and horizontal alignments together, and include the profile with the horizontal alignment justification.

1220.07 Documentation

Refer to Chapter 300 for design documentation requirements.

1220.08 References

1220.08(1) Federal/State Laws and Codes

Washington Administrative Code (WAC) 468-18-040, Design standards for rearranged county roads, frontage roads, access roads, intersections, ramps and crossings

1220.08(2) Design Guidance

Local Agency Guidelines (LAG), M 36-63, WSDOT


Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)

Plans Preparation Manual, M 22-31, WSDOT

1220.08(3) Supporting Information


A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO, current edition

Exhibit 1220-2a Coordination of Horizontal and Vertical Alignments




Coinciding Horizontal and Crest Vertical Curves

When horizontal and crest vertical curves coincide, a satisfactory appearance results.



Coinciding Horizontal and Sag Vertical Curves

When horizontal and sag vertical curves coincide, a satisfactory appearance results.




Short Tangent on a Crest Between Two Horizontal Curves

This combination is deficient for several reasons:


- The curve reversal is on a crest, making the second curve less visible.
- The tangent is too short for the superelevation transition.
- The flat area of the superelevation transition will be near the flat grade in the crest.

Exhibit 1220-2b Coordination of Horizontal and Vertical Alignments




Profile With Tangent Alignment

Avoid designing dips on an otherwise long uniform grade.



Sharp Angle Appearance


This combination presents a poor appearance. The horizontal curve looks like a sharp angle.




Disjointed Effect

A disjointed effect occurs when the beginning of a horizontal curve is hidden by an intervening crest while the continuation of the curve is visible in the distance beyond the intervening crest.

Exhibit 1220-2c Coordination of Horizontal and Vertical Alignments




Desirable Coordination of Vertical and Horizontal Curves and the Use of Flowing Alignment



Undesirable - Vertical and Horizontal Curves Not Coordinated and Using Minimums

Exhibit 1220-3 Grading at Railroad Crossings



Chapter 1230 Geometric Cross Section Basics

1230.01 General
1230.02 Guidance for Specific Facility Types
1230.03 Common Elements
1230.04 Jurisdiction for Design and Maintenance
1230.05 References

When choosing any geometric cross section dimension, including lane or shoulder width, read the guidance that is specific to the facility type. Also, read the general guidance related to common elements such as lanes, shoulders, side slopes, etc.

See Chapter 1106 for the general dimensioning guidance.

This chapter also contains guidance related to jurisdiction.

1230.01 General

The geometric cross section is composed of multiple lateral design elements such as lanes, shoulders, medians, bike facilities, and sidewalks. The designer's task is to select, size, and document these elements appropriately. There is flexibility in the selection of design element dimensioning.

All WSDOT routes, regardless of context, are referred to in the *Design Manual* as "highways." Under this definition, freeways are a subset of highways while Interstate freeways are one specific type of freeway.

Refer to the *Design Manual* Glossary for many of the terms used in this chapter. See Chapter 300 for design documentation requirements.

1230.02 Guidance for Specific Facility Types

Guidance regarding geometric cross sections is located in various *Design Manual* chapters. The chapter depends on the facility type. Examples of specific facility types include:

- Highways (general)
- Freeways
- Ramps
- Auxiliary lanes
- Collector-Distributor lanes
- Service lanes
- Frontage roads
- HOV facilities
- Median U-turns and crossovers
- Transit facilities including bus pull-outs
- Enforcement areas
- Slow vehicle turn-outs
- Truck weighing facilities
- Shared use paths
- Sidewalks
- Bicycle Facilities

Exhibit 1230-1 shows some common facility types along with the corresponding chapter that geometric cross section guidance can be found in.

Exhibit 1230-1 Geometric Cross Section - Guide to Chapters

Facility Type	Lane width	Turning roadway width	Shoulder width	Median width	Lateral clearance to curb or barrier	Side slope	Cross slope
Highways (General)	1231	1240	1231	1239	1239	1239	1250
Freeways	1232	1240	1232	1239	1239	1239	1250
Ramps	1360	1240	1360	1360	1239	1239	1360 & 1250
Auxiliary lanes	1270 or 1360 [1]	1240	1270 or 1360 [1]	N/A	1239	1239	1270
C-D roadways	1360	1240	1360	N/A	1239	1239	1360
HOV lanes, ramp bypass lanes, etc.	1410	1410	1410	N/A	1410 & 1239	1239	1410
Left-side direct HOV access (DHOV) facilities	1420	1420	1420	1420 (for DHOV)	1420 & 1239	1239	1250
Shared use path	1515	1515	1515	N/A	1515	1515	1515
Other	Geometric cross section guidance for other special purpose facilities is in various chapters. Examples include special use lanes, bridges, transit facilities, bus pull outs, median U-turns and crossovers, enforcement areas, truck weighing facilities, pedestrian bridges and tunnels, sidewalks & bicycle facilities						

Notes:

General guidance for curb design is in Chapter 1239. Guidance for curb is also found for numerous types of facilities (Chapter 1310 and others.)

[1] Passing and climbing lanes, see Chapter 1270; Auxiliary lanes between interchanges see Chapter 1360.

Exhibit 1230-1 is not a comprehensive list of guidance associated with either a facility or a design element. It is intended to be a quick reference to the chapter containing the primary guidance related to the specific element and facility type.

For guidance related to intersections see Chapter 1310. For guidance related to sidewalks see Chapter 1510. For guidance related to bicycle facilities see Chapter 1520. For guidance related to bridges see Chapter 720.

1230.03 Common Elements

In addition to the guidance specific to the facility type, also see the general guidance related to cross-sectional elements that are common to various facility types:

- Lanes — Chapter 1231
- Shoulders, side slopes, medians & curbs — Chapter 1239
- Lateral clearance to curb and barrier — Chapter 1239
- Parking & streetside (behind the curb) elements — Chapter 1238
- Cross slope and superelevation — Chapter 1250

1230.04 Jurisdiction for Design and Maintenance


On all state highways in locations outside of cities or towns and within limited access design areas, geometric design is to be consistent with this *Design Manual*.


On state highways within an incorporated city or town, develop design features in cooperation with the local agency. For NHS routes, use the *Design Manual*. For non-NHS routes, the *Local Agency Guidelines* may be used for dimensioning design elements

Cross-sectional design within incorporated cities or towns can get complicated due to the joint-jurisdictional authority. WSDOT typically has jurisdiction between the curbs, and cities typically have jurisdiction outside the curbs (see Exhibit 1230-2). When no curb is present, the city or town holds responsibility for the roadside beyond the paved shoulder. Despite the jurisdictional differences, it is extremely important to cooperatively determine a cross-sectional design.

Refer to Chapter 301 for additional information on jurisdictional maintenance responsibilities and considerations for maintenance agreements.

Exhibit 1230-2 State and City Jurisdictional Responsibilities





1230.05 References

1230.05(1) Design Guidance

Highway Runoff Manual, M 31-16, WSDOT

Local Agency Guidelines (LAG), M 36-63, WSDOT

Plans Preparation Manual, M 22-31, WSDOT

Standard Plans for Road, Bridge, and Municipal Construction, M 21-01, WSDOT

Standard Specifications for Road, Bridge, and Municipal Construction, M 41-10, WSDOT

1230.05(2) Supporting Information

Understanding Flexibility in Transportation Design – Washington, WA-RD 638.1, Washington State Department of Transportation, 2005
www.wsdot.wa.gov/research/reports/fullreports/638.1.pdf

Urban Street Design Guide, National Association of City Transportation Officials, New York, NY, 2013
www.nacto.org

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO, current edition
www.transportation.org/Pages/Default.aspx

Chapter 1231 Geometric Cross Section – Highways

1231.01 General
1231.02 Design Up
1231.03 Common Elements
1231.04 Vehicle Lanes
1231.05 Modally Integrated Cross Sections
1231.06 Road Diets and Retrofit Options
1231.07 References

1231.01 General

Geometric cross sections for state highways are governed by the need to balance performance metrics, the context, and selected design controls. The objective is to optimize the use of available public space while avoiding an unreasonable investment in right of way acquisition.

The term "highways" refers to all WSDOT roadways, including freeways. However, note that freeways have their own geometric cross section guidance. This chapter is not intended for freeway design. See Chapter 1232 for freeways.

1231.02 Design Up

Unless otherwise specified, use the "design up" method described in Chapter 1106 to choose a design element width when a range of widths is given in this chapter.

1231.03 Common Elements

The geometric cross sections shown in this chapter have many elements that are also common to facilities addressed in other chapters. The following chapters contain guidance related to these common geometric cross section elements:

- Lanes — Chapter 1231
- Shoulders, side slopes & ditches, medians & curbs — Chapter 1239
- Lateral clearance to curb or barrier — Chapter 1239
- Parking & streetside (behind the curb) elements — Chapter 1238
- Cross slope and superelevation — Chapter 1250

1231.04 Vehicle Lanes

1231.04(1) Type of Lanes

There are many types of lanes that may exist in a cross section, and each has its own purpose and sizing needs. General-purpose traffic lanes need to accommodate a variety of vehicle types including buses, freight vehicles, personal automotive vehicles, and bicycles. The target speed, modal priority, balance of performance needs, and transportation context are all considerations when determining size, type, and number of lanes.

Some common types of vehicle lanes include:

Through Lanes

Through lanes are the most common lane type. All highways have at least one lane in each direction to provide unimpeded traffic flow from Point A to Point B.

Turn Lanes

Dedicated turn lanes are separated from the through lanes and provide storage for turning vehicles waiting for a signal or gap in opposing traffic. There are a number of different types of turn lanes which are discussed in detail in Chapter 1310. Turn lanes are critical to meet mobility and accessibility performance for motorized and bicycle modes. Traffic analysis determines the type, storage length, and number of turn lanes that are needed to achieve the balance of multimodal performance needs.

Turn lanes present potential conflicts, particularly with bicyclists and pedestrians. See Chapters 1510 and 1520 for additional discussion on ways to mitigate for these conflicts.

Bicycle Lanes

There are several different types of bicycle lanes and many different ways to arrange bike lanes within the geometric cross section (see Chapter 1520). Shoulders designed to function for bikes are not considered bike lanes.

Transit-Only Lanes

Transit-only lanes are ideal for improving transit mobility performance and segregating heavily used or complex intermodal connections. There are many different ways to configure these within a geometric cross section. Some configurations are limited due to passenger loading needs for both the transit vehicle type and the stop locations. Develop widths for transit-only lanes with the partnering transit agency. See Chapter 1430 for additional information on Transit Facility considerations.

Auxiliary lanes

Auxiliary lanes enhance mobility performance for motor vehicles. See Chapter 1270 for design guidance and a detailed discussion on the types of auxiliary lanes.

Managed and Shared Lanes

There are many different types of managed and shared lanes. Some examples include:

- High occupancy vehicle (HOV) lanes (see Chapter 1410)
- High occupancy toll lanes (discuss with Tolling Division and see Chapter 1410)
- Hard shoulder running
- Peak hour use
- Bicycle shared lane (see Chapter 1520)
- Business access and transit (BAT) lane (see Chapter 1410, Arterial Street HOV)

1231.04(2) Lane Width

Lane width ranges for highways are listed in Exhibit 1231-1.

Exhibit 1231-1 Lane Widths for Highways

Speed	Highway Type	Lane Width Range*
High Speed	Freeway (incl. Interstate)	See Chapter 1232
	Other Highway	11' - 12'
Intermediate Speed	All	11' - 12'
Low Speed	All	10' - 12'

* The width shown is exclusive of the gutter if the gutter is a color that contrasts with the roadway.

1231.04(2)(a) Lane Width Considerations

Exhibit 1231-2 lists some considerations that may be helpful in choosing the most appropriate lane width from the range given in Exhibit 1231-1. This is not a comprehensive list. The considerations listed are meant to help understand the modal needs and function associated with different lane widths. Work with your Region Traffic Office when choosing lane widths.

Exhibit 1231-2 Lane Width Considerations

Lane Width Considerations	
General	Roadways on curves, see Chapter 1240 Turning Roadway Widths
	Narrower lanes may be used as part of a speed reduction strategy
	Two-lane, two-way rural highways: 12 ft lanes provide clearance between large vehicles traveling in opposing directions. Especially beneficial when high volumes or high truck percentages expected
	On multilane facilities with width constraints, utilizing narrower inside lanes may permit wider outside lanes for bicycles, freight, and transit
	Reduced lane widths allow more lanes to be provided in areas with constraints and allow shorter pedestrian crossing times because of reduced crossing distances
Intermediate to High Speed	12 ft lanes provide increased benefit on high speed, free-flowing principle arterials
	12 ft lanes provide increased benefit where there are higher truck volumes, especially for intermediate and high speed facilities
	Safety and mobility performance difference between 11 ft and 12 ft lanes can be negligible. Work with Region Traffic Office to evaluate performance differences for the subject roadway
Low Speed	11 ft lanes are common on urban arterials
	Lane widths of 10 ft may be appropriate in constrained areas with low truck and bus volume
	In pedestrian oriented sections, 10 ft lanes can be beneficial in minimizing crossing distance

1231.05 Modally Integrated Cross Sections

WSDOT's goal is to optimize existing system capacity through better interconnectivity of all transportation modes. Choosing the appropriate geometric cross section relies heavily on designing for the appropriate modes. See Chapter 1103 for guidance in selecting modes to accommodate and choosing modal priorities.

Once a decision is made regarding which modes to accommodate and which modes will have priority, a geometric cross section can be developed. The cross sections in this chapter are organized by modal priority for the following primary modes:



Motor Vehicles, including freight

Bicycles

Pedestrians

Transit

The cross-section examples shown in Exhibits 1231-3 through 1231-7 depict various combinations of elements that may be included in a cross section. The examples are intended to stimulate designer creativity and awareness of modal accommodations, and are not intended to be standard cross sections to be reproduced for a given modal priority. It is expected that innovative project alternatives will result in diverse configurations that best balance baseline and contextual needs (see Chapter 1101).

Since the cross-sections shown are only examples, and are really combinations of various elements, it is important to read the guidance associated with the specific elements (see 1231.03) in order to understand the considerations that may affect a choice of width, and to understand documentation requirements.

The cross section examples provide a range of dimensions for different design elements. See Chapter 1106 for guidance regarding choosing a width when a range of widths is given.


Maintaining the continuity of a roadway is an important consideration, particularly for limited access and other high-speed highways. However, it is also appropriate to change continuity as context changes in order to influence driver behavior. When designing intentional changes to the continuity of the geometric cross section, consider what is needed to enable the transition. High-speed to low-speed changes will need to transition the geometric cross section over a distance utilizing a speed transition segment (see Chapter 1103).


1231.05(1) Auto-and Freight Oriented Cross Sections

Exhibit 1231-3 shows examples of motorized vehicle-oriented designs. Motorized vehicles come in a variety of types which are operated on many vehicle lanes and parking areas. The performance needs of freight and other automotive vehicle types are often similar. However, certain truck vehicle types may require additional turning roadway width for off-tracking (see Chapter 1240), or at other locations a truck climbing lane may be needed to facilitate mobility performance (see Chapter 1270). Generally, lane width within suburban and urban contexts is less critical for mobility and safety performance than in rural and high-speed contexts. Within urban areas, placement of and sizing for loading areas within the parking areas can depend on the freight vehicle type.




Exhibit 1231-3 Motor Vehicle Oriented Cross Sections







Barrier Present



Curb Present

Notes:

[1] Overall median width and design will vary. Some median designs include barrier and some do not. See Chapters 1239 and 1600.

[2] See Chapter 1239 for guidance on choosing a dimension from the range given.

[3] See 1231.04 for guidance on choosing a dimension from the range given. See Chapter 1410 for guidance on HOV facilities.


[4] See Chapter 1232 to see if your roadway meets the definition of a freeway.


1231.05(2) Cross Sections Featuring Bicycle Facilities

Exhibit 1231-4 Example A features bicycle facilities at an intermediate-speed location. Bike lane location within the cross section depends largely on how cyclists will interact with the land use and potential modal conflicts. Locating bike lanes on the outside of the motor vehicle lanes can improve accessibility for bicyclists. If cyclist mobility performance is a primary concern or intermodal conflicts (such as transit stop locations) are present, locating bike facilities in the center of the roadway may be more appropriate. Whether or not a bike lane buffer is needed depends mostly on the target speed and average daily traffic (ADT) of the facility; the intent of bike buffers or other protected bike facilities is to address safety performance for cyclists. Buffers and other means of modal segregation also benefit motor vehicle drivers and pedestrians by showing allocated spaces. Both roadway bike lane configurations and bike facility selection are discussed in more detail in Chapter 1520.



Exhibit 1231-4 Cross Sections Featuring Bicycle Facilities





Notes:

[1] See Chapter 1510.
[2] Minimum width specified is exclusive of the curb width.
[3] If no furnishing zone is provided, minimum width is exclusive of the curb width.
[4] See Chapter 1520 for bike facility options.
[5] See Chapter 1238.
[6] Overall median width and design will vary. See Chapter 1239 .
[7] See 1231.04 for guidance on choosing a dimension from the range given.


1231.05(3) Cross Sections Featuring Pedestrian Facilities


Exhibit 1231-5 shows cross-section examples featuring pedestrian facilities. The pedestrian mode is a vital transportation mode since, for most people, nearly every trip at least begins and ends by walking. Roadway facilities prioritized for pedestrians emphasize streetside elements. See Chapter 1238 for guidance regarding streetside elements.

The objective is to achieve the Pedestrian Circulation Path (PCP) necessary to support mobility, socioeconomic, and accessibility needs and provide access to intermodal connections. The configuration and dimension of streetside elements varies significantly depending on the performance needs being addressed. See Chapter 1510 for additional pedestrian design requirements and considerations.



Exhibit 1231-5 Cross Sections Featuring Pedestrian Facilities





Notes:

[1] See Chapter 1510.
[2] Minimum width specified is exclusive of curb width.
[3] If no furnishing zone is provided, minimum width is exclusive of the curb width.
[4] See Chapter 1238.
[5] Overall median width and design will vary. See Chapter 1239.
[6] See 1231.04 for guidance on choosing a dimension from the range given.


1231.05(4) Cross Sections Featuring Transit Facilities


Exhibit 1231-6 provides examples of different potential configurations oriented for the transit mode. Work with the transit provider to determine their ability to operate within a given cross-sectional arrangement. In general, transit configurations can be positioned toward the side or center of a roadway. Both side and center configurations can be implemented with medians or outer separations to improve safety performance for intermodal connections, or mobility performance for the transit service.


Exhibit 1231-6 Example A shows a central configuration for transit service that provides a separated bus-only lane. Other transit vehicle types may require different widths and may also require other center cross section configurations for passenger loading. Exhibit 1231-6 Example B shows a side configuration where transit vehicles occupy the outside lane. This example can also be configured as business access and transit [BAT] lanes. Note the importance of streetside elements to assist with intermodal connections. Exhibit 1231-6 Example C is an example of a type of special use lane for high-speed routes that are routinely congested. In this example, the shoulder allows the restricted use for buses.



Exhibit 1231-6 Cross Sections Featuring Transit Facilities







Notes:

[1] See Chapter 1510.
[2] Minimum width specified is exclusive of the curb width
[3] If no furnishing zone is provided, minimum width is exclusive of the curb width.
[4] See Chapter 1238.
[5] Verify width needs with transit provider, including lift extension needs. See Chapter 1510 for Pedestrian Access Route requirements, which may be affected by presence of a shelter. See Chapter 1430 Transit Facilities.
[6] Median width and design will vary. See Chapter 1239
[7] Verify width needs with transit provider. See Chapter 1239 for bus use only shoulder, requires a Design Analysis.
[8] See 1231.04 for guidance on choosing a dimension from the range given.
[9] See Chapter 1239 for guidance on choosing a dimension from the range given.

1231.05(5) Example Cross-Sections – Complete Streets

Complete street configurations attempt to balance the performance needs of all users, regardless of age, ability, or mode. The general intent is to provide context-appropriate designs that enable safe access for all design users. It is always important to consider modal connectivity and conflicts that may occur with complete street configurations, particularly at intersections and/or transit stop locations.

There are different potential configurations for complete streets, such as:


- A rural two-lane highway with wide shoulders; the shoulders can be used by motor vehicles in emergencies and by pedestrians and bicyclists.
- An urban highway or street with vehicle lanes, bike lanes, bus lanes, and sidewalks.
- Retrofitting a highway or street to clearly mark and sign a shared-use lane.
- An urban highway that undergoes a "road diet" (see 1231.06) or installation of additional pedestrian crossings.


The low speed examples in Exhibit 1231-7 illustrate roadway cross sections that:

- Separate access lanes from through traffic lanes using curbed islands.
- Reduce conflicts between pedestrian, bike, transit and auto modes by separating them.
- Provide transit stops integrated with raised islands.
- May result in improved operations for all modes.




Exhibit 1231-7 Complete Street Cross Sections





Notes:


[1] See Chapter 1510.
[2] See Chapter 1238.
[3] If no furnishing zone is provided, minimum width is exclusive of the curb width.
[4] See Chapter 1520 for bike facility options.
[5] Verify width needs with transit provider. See Chapter 1430.
[6] Overall median width and design will vary. See Chapter 1239.
[7] See 1231.04 for guidance on choosing a dimension from the range given.
[8] See Chapter 1239 for guidance on choosing a dimension from the range given.
[9] Minimum width specified is exclusive of the curb width.



1231.06 Road Diets and Retrofit Options

Generally, road diets refer to converting four-lane undivided highways to three lanes with the center lane for left turning movements and the remaining outside space repurposed for bicyclists or other functions. The center lane can consist of a two-way left-turn lane (TWLTL) or can be dedicated for directional left turns either by paint or other median treatments. The choice of how to configure the center lane depends largely on balancing the resulting safety and accessibility performance of different modes and land uses.

The application of road diets also has the benefit of reallocating existing space within a cross section, which provides distinct opportunities to improve roadway bicycle facilities and/or elements of the streetside. At intersections and access points, a road diet can improve sight distance, may improve access management along the road, and in some cases, improve mobility performance for motorists.



Typical Road Diet Basic Design from FHWA Road Diet Informational Guide

The success of road diet implementation varies due to a number of factors such as signal spacing and timing, access connection density, modal priority, and average daily traffic (ADT). ADT is a reasonable indicator for implementation. FHWA recommends limiting road diet applications to roadways of 20,000 ADT or less, although road diets have been successful at locations with 25,000 ADT in various parts of the country (see Chapter 540 for additional restrictions on the use of TWLTLs). Motor vehicle mobility performance is most likely deemed the primary measure of success for the road diet configurations with higher ADT values described. However, locations with a different modal priority and higher ADT may still be candidates for road diets. The Region Traffic Engineer must approve road diet applications on state highways.

Retrofit options refer to the application of lower-cost treatments that utilize paint and other delineation devices rather than hardscape features. See Chapter 1238 for more information on retrofit options such as relocating the curb, parklets and plazas.

1231.07 References

1231.07(1) Design Guidance

Highway Runoff Manual, M 31-16, WSDOT

Local Agency Guidelines (LAG), M 36-63, WSDOT

Plans Preparation Manual, M 22-31, WSDOT

Standard Plans for Road, Bridge, and Municipal Construction, M 21-01, WSDOT

Standard Specifications for Road, Bridge, and Municipal Construction, M 41-10, WSDOT

1231.07(2) Supporting Information

FHWA Road Diet Informational Guide, FHWA, 2014
www.safety.fhwa.dot.gov/road_diets/info_guide/

Understanding Flexibility in Transportation Design – Washington, WA-RD 638.1, Washington State Department of Transportation, 2005
www.wsdot.wa.gov/research/reports/fullreports/638.1.pdf

Urban Bikeway Design Guide, National Association of City Transportation Officials, New York, NY, 2012 revised 2013
www.nacto.org

Urban Street Design Guide, National Association of City Transportation Officials, New York, NY, 2013
www.nacto.org

Designing Walkable Thoroughfares: A Context Sensitive Approach, Institute of Transportation Engineers, Washington D.C., 2010.
www.ite.org

Guide for Geometric Design of Transit Facilities on Highways and Streets, AASHTO, Washington, D.C., 2011
www.transportation.org/Pages/Default.aspx

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO, current edition
www.transportation.org/Pages/Default.aspx

A Policy on Design Standards Interstate System, AASHTO, 2005
www.transportation.org/Pages/Default.aspx

NCHRP Synthesis 443 – Practical Highway Design Solutions, Transportation Research Board, Washington D.C., 2013
http://www.trb.org/Main/Blurbs/168619.aspx

NCHRP Report 785 – Performance-Based Analysis of Geometric Design of Highways and Streets, Transportation Research Board, Washington D.C., 2014
www.trb.org/Main/Blurbs/171431.aspx

NCHRP Report 783 – Evaluation of the 13 Controlling Criteria for Geometric Design, Transportation Research Board, Washington D.C., 2014
www.trb.org/Main/Blurbs/171358.aspx

NCHRP Report 505 – Review of Truck Characteristics as Factors in Roadway Design, Transportation Research Board, Washington D.C., 2003
http://onlinepubs.trb.org/onlinepubs/nchrp/nchrp_rpt_505.pdf

Chapter 1232 Geometric Cross Section – Freeways

1232.01 General
1232.02 Lane Width
1232.03 Shoulder Width
1232.04 Other Elements
1232.05 Design Flexibility
1232.06 References

If your roadway fits the definition of a freeway, use the guidance in this chapter for geometric cross-section elements. If your roadway is not a freeway, see Chapter 1230.

1232.01 General

Freeways are defined as divided highways with a minimum of two lanes in each direction for the exclusive use of vehicular traffic and with full control of access. Interstate is one type of freeway.

Freeways are high-speed facilities that prioritize through travel for vehicles, freight and transit. Lanes must be wide enough for all vehicles that use them. Shoulders provide very important functions for freeways.

Freeways can be thought of as a unique context. This is reflected by the fact that design controls (Chapter 1103) are fairly consistent for all freeways:

- **Modal priority:** motor vehicles
- **Access control:** full control
- **Design speed:** high


Freeways do not present the challenges of accommodating the competing needs of other modes such as pedestrians. Also, adjacent land use is generally not an issue due to freeways being limited access facilities. For these reasons, choosing cross-sectional element dimensions for freeways does not have as many complexities as for some other roadway types.

Note that there are locations where bicyclists are allowed use of the freeway shoulder.

The geometric cross-section for interstate freeways is shown in Exhibit 1232-1. The geometric cross-section for non-interstate freeways is shown in Exhibit 1232-2.

Refer to the *Design Manual* Glossary for terms used in this chapter. Refer to Chapter 300 for design documentation requirements.

Exhibit 1232-1 Geometric Cross Section - Interstate (4 lanes shown, can vary)



Notes:

See Chapter 1410 for HOV lane guidance.


Use of the shoulder on a freeway for transit only use or as an HOV lane requires a Design Analysis.

[1] 4 ft minimum on facilities up to 4 lanes, and 10 ft minimum on 6-lane facilities.
In mountainous terrain, inside shoulder may be reduced to 4 ft on facilities up to 6 lanes.

[2] In mountainous terrain, outside shoulders may be reduced to 8 ft on facilities up to 6 lanes.

[3] Overall median width and design will vary. See Chapter 1239 and 1610.

Exhibit 1232-2 Geometric Cross Section – Non-Interstate (4 lanes shown, can vary)



Notes:

See Chapter 1410 for HOV lane guidance.

Use of the shoulder on a freeway for transit only use or as an HOV lane requires a Design Analysis.

[1] 4 ft minimum on facilities up to 4 lanes, and 8 ft minimum on 6-lane facilities.
In mountainous terrain, inside shoulder may be reduced to 4 ft on facilities up to 6 lanes

[2] Overall median width and design will vary. See Chapter 1239 and 1610.

Exhibit 1232-3 Median Section without Median Barrier



1232.02 Lane Width

For freeways, travel-through mobility and safety for motor vehicles are prioritized performance areas. Lanes must be wide enough for all vehicles that use them to travel safely at high speeds. When a range is given for lane width, use the mode/function/performance approach described in Chapter 1106 and "design up" to choose a width within the range. See Chapter 1231 for considerations for choosing a lane width.

1232.03 Shoulder Width

The prioritization of travel-through mobility and safety for motor vehicles results in placing a high priority on providing some important shoulder functions (see Chapter 1239) for freeways:

- Stopping out of traffic
- Emergency services & incidence response
- Maintenance operations

The high-speed nature of freeways reinforces the importance of providing these functions. For instance, the high speed differential between a stopped vehicle and adjacent traffic leads to a greater need to get stopped traffic out of the travelled way. Also, the limited access nature of freeways generally means that there are fewer access points to provide potential refuge.

When a range is given for shoulder width, use the mode/function/performance approach described in Chapter 1106 and "design up" to choose a width within the range. See Chapter 1239 for additional considerations for choosing a shoulder width.

1232.04 Other Elements

See the following chapters for guidance related to these other common geometric cross section elements:

- Side slopes, medians & curbs Chapter 1239
- Lateral clearance Chapter 1239
- Cross slope and superelevation Chapter 1250

1232.05 Design Flexibility

There are always locations that warrant special consideration. Existing freeways may have constraints (right-of-way or environmental considerations, for example) that make the cost of widening outweigh the benefits. The optimum solution may include widths different than those shown.

If this is the case for your project, and you choose widths different than shown in the Design Manual, formulate alternative solutions that consider the tradeoffs associated with various lane and shoulder widths and document the decision in a Design Analysis. Where appropriate, include documentation of your consultation with the project advisory team (see Chapter 1100) in the Design Analysis. When compiling the Design Analysis, consider recent design resources that explore options, performance, functions, and mitigation associated with various lane and shoulder dimensions. One source is FHWA HOP-16-060 "Use of Narrow Lanes and Narrow Shoulders on Freeways." Another source is NCHRP 15-47, "Developing an Improved Highway Geometric Design Process".

1232.06 References

1232.06(1) Design Guidance

Highway Runoff Manual, M 31-16, WSDOT

Local Agency Guidelines (LAG), M 36-63, WSDOT

Plans Preparation Manual, M 22-31, WSDOT

Standard Plans for Road, Bridge, and Municipal Construction, M 21-01, WSDOT

Standard Specifications for Road, Bridge, and Municipal Construction, M 41-10, WSDOT

1232.06(2) Supporting Information

Understanding Flexibility in Transportation Design – Washington, WA-RD 638.1, Washington State Department of Transportation, 2005
www.wsdot.wa.gov/research/reports/fullreports/638.1.pdf

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO, current edition
www.transportation.org/Pages/Default.aspx

Chapter 1238 Geometric Cross Section – Streetside and Parking

1238.01 General
1238.02 Parking
1238.03 Streetside
1238.04 Retrofit Options
1238.05 References

1238.01 General

The geometric cross section of a roadway is composed of different elements. The cross sections shown in Chapter 1231 include parking and various zones within the streetside (see Exhibit 1238-1). This chapter provides information on parking and streetside elements. The need to provide a particular element is dependent on the context and modal needs for a given section of roadway.

1238.02 Parking

On-street parking is typically provided in urban and rural town center areas, but is not necessarily required. On-street parking can help visually narrow the street in places to assist in conveying the surrounding context for the segment. Refer to municipal codes regarding parking requirements, and coordinate with the municipality involved. Also, if on-street parking will be either delineated or metered, the ADA has requirements on the number and configuration of parking stalls for people with disabilities. Consult with a regional ADA subject matter expert.

On-street parking can be either parallel or angled. However, angled parking on any state route requires approval from the State Traffic Engineer.

Submit a request for angled parking approval through the region Traffic Office. Include an engineering study documenting that the parking will not unduly reduce safety and that the roadway is of sufficient width that parking will not interfere with the normal movement of traffic.

Provide for vehicle overhang within the furnishing zone for all angled parking locations. Consider back-in angled parking if bike lanes are present to improve conflict management through increased visibility.

When designing parking locations for freight loading areas, it is important to consider both the delivery vehicle size and how the vehicle loading/unloading is done. Consult with business owners and freight carriers to locate and configure the freight loading areas.

Width considerations: Cross sections in the Design Manual generally show a range for parallel parking of 7 to 9 feet. AASHTO defines a passenger car width as 7 feet. Additional width can allow a buffer for car doors opening, a buffer for bike riders, or a stall that can accommodate delivery trucks.

Work with stakeholders to determine the appropriate width to provide within the site-specific constraints.

1238.03 Streetside

The area behind the curb is referred to as the "streetside" and is described in terms of "zones." Information about each zone is provided below. Note, local agency partners may have policy containing additional streetside zones to consider.

WSDOT uses the following terminology to describe the zones found within the streetside:

- Frontage Zone
- Pedestrian Zone
- Furnishing Zone

Exhibit 1238-01 Zones within the Streetside



The streetside is the interface between pedestrians and land use. A robust streetside can serve as both a pedestrian thoroughfare and a destination, which is desirable in many urban core and main street contexts to help promote economic vitality. The streetside can also reinforce the target speed. The pedestrian zone will always be present in streetside design, but other zones are optional and dependent on the modal and contextual needs and desired balance of performance needs within the available right of way.

The Americans with Disabilities Act (ADA) requires specific design element dimensions for streetside elements, depending on the configuration. In general, the pedestrian zone and frontage zone will always be part of the pedestrian circulation path (PCP). The furnishing zone may or may not be part of the PCP, depending on how it is designed. See Chapter 1510 for detailed accessibility criteria and design guidance for pedestrian facilities.

1238.03(1) Frontage Zone

The frontage zone serves the retail functions, and is the portion of the sidewalk that provides the connection to the building. The frontage zone includes the building, the façade, and the space immediately adjacent to the building. The primary purpose is access to retail space

without interfering with the required pedestrian access route (PAR) within the pedestrian zone. The frontage zone may also provide space for sidewalk cafes, temporary retail product displays, advertisements, and/or outdoor seating for customers. If there is no retail or residential access need adjacent to the streetside, a frontage zone may not be necessary.

Width considerations: Cross sections in Design Manual generally show a range for the frontage zone width of 2 to 12 feet.

Narrow, 2-ft frontage zones provide for a clear area where protruding objects from the building can be located without compromising the pedestrian access route. Two feet also provides an offset from the building and minimal space for entering/exiting the building.

Wider frontage zones, such as 12-ft can provide width for a variety of possible elements, such as sidewalk café dining with tables and chairs along the building. If a frontage zone is to be provided, work with stakeholders to determine the appropriate width to provide within the site-specific constraints.

1238.03(2) Pedestrian Zone

The pedestrian zone is the space available to accommodate pedestrian travel that will:

- Create interconnectivity between different land uses
- Provide for the transfer between modes
- Separate pedestrians from vehicular traffic
- Support walking as a transportation mode

The pedestrian zone is located within the Pedestrian Circulation Path and includes the Pedestrian Access Route (PAR) needed to meet ADA accessibility criteria (see Chapter 1510). The pedestrian zone may be considerably wider than the PAR.

A generous pedestrian zone width promotes the mobility and accessibility typically anticipated within some urban and suburban contexts.

Consider wider pedestrian zones when the following are present:

- Transit facilities and passenger shelters
- Access routes to businesses
- School walking routes
- Other high pedestrian activity generators

Width considerations: The minimum pedestrian zone width of 5 feet corresponds to WSDOT's minimum sidewalk width (see Chapter 1510). Other considerations when choosing a pedestrian zone width include:

- In many downtown environments, the focus is on multimodal transportation and, in particular, pedestrian accessibility and use. Wider streetside zones promote a greater sense of safety, and can provide a comfortable and inviting area that can attract pedestrians.

- In urban/downtown environments where store fronts/businesses are located, a larger width is recommended. Consider providing wider sidewalks to increase pedestrian comfort levels and to promote walking.
- In places with higher pedestrian volumes, a 10 foot width allows for pedestrians walking side-by-side or in groups to pass others comfortably without changing directions or walking speed.
- A 10 foot width provides sufficient width for a wheelchair user to turn around and to pass another wheelchair user (5 foot width is typically adequate to perform these maneuvers).
- The minimum sidewalk width of 5 feet is appropriate in low pedestrian volume areas, such as where there are few stores abutting the street or in residential neighborhoods.

Work with stakeholders to determine the appropriate width to provide within site-specific constraints.

1238.03(3) Furnishing Zone

The furnishing zone is the key buffer component between the active pedestrian walking area (pedestrian zone) and the roadway. The furnishing zone provides area for multiple functions. The furnishing zone is not located within the Pedestrian Access Route (PAR). However, a PAR connection is required to many features that may be found in this zone (such as street furniture, parking meters, transit shelters, and transit boarding areas.)

The Furnishing zone:

- Promotes environmental and aesthetic features that improve people's experience
- Contains street trees, street furniture, benches, planter boxes, and artwork
- Provides for the travel of the various modes through modal segregation or clearance to obstructions
- Discourages crossings at less desirable locations along the facility with use of buffers.

Traffic signs and signal cabinets; utility poles; fire hydrants; parking meters; transit boarding, queuing, and shelters; and bike racks are also generally found within the furnishing zone.

Involve the local agency, regional Landscape Architect, and safety professionals to determine optimal vegetation types.

Other width accommodations for on-street parking may be needed for vehicle overhang or entering/exiting movements when parking is present.

Coordinate with region Program Management to understand potential funding limitations for furnishing zone features described within this section. Partnerships or grants may be necessary to complete all desired features within the furnishing zone.

Width considerations: A width of 2 feet provides the minimum width to accommodate utilities and street furniture. Greater widths accommodate a larger variety of possible features within the furnishing zone. Other considerations when choosing a furnishing zone width include:

- An 8-foot width or greater generally provides sufficient space to accommodate a bus transit stop (loading/unloading) and a transit shelter (see Chapter 1430 and work with the transit provider to determine needed space.)
- In commercial areas, a minimum furnishing zone width of 4 feet is recommended.
- In areas where snow accumulation can occur, the furnishing zone can provide snow storage space that does not decrease the width of the pedestrian zone.
- When higher vehicle speeds are present, providing a larger width to act as a buffer between vehicles and pedestrians is desirable.

If a furnishing zone is to be provided, work with stakeholders to determine the appropriate width to provide in order to accommodate the expected features within the site-specific constraints.

1238.04 Retrofit Options

Retrofit options refer to the application of lower-cost treatments that utilize paint and other delineation devices rather than hardscape features. Retrofit applications are particularly useful when:

- Construction will occur in phases over a timeline greater than one year between phases where overlapping areas of work occur, or when elements or features are funded by a partnering agency.
- Implementing speed management treatments (see Chapter 1103) that, after evaluating their effectiveness, may need to be reconfigured.
- Funding is unable to adequately accomplish the identified scope of work.

Applied retrofit options may require additional maintenance over long-duration applications. Coordination with maintenance jurisdictions as described in Chapter 301 is critical to evaluating the potential maintenance outcomes for retrofit options being considered. The retrofit options discussed within the following subsections are more likely to be applied in urban context settings. Note that cities over 25,000 population will have the responsibility of maintaining any retrofit delineation, and it will be critical to ensure they have the resources to maintain striped retrofit features.

The following subsections describe several common applications of retrofit options.

1238.04(1) Relocate Curbs

Changes to the geometric cross section may involve relocating the existing curb. While installing a new curb may be preferred, there are a number of additional considerations (like stormwater conveyance) that make relocating curb lines cost-prohibitive. However, there are multiple retrofit solutions that can provide effective accommodation including, but not limited to:

- Striping combined with MUTCD-approved channelization devices.
- Curb extensions offset from the original curb. Depending on the use of the new curbed section, retrofit designs may include slotted grates tying the existing curb and new curb together while maintaining the original stormwater conveyance system.
- Colorized pavement to delineate a change of use.

Use retrofit features as a low-cost solution to create wider sidewalk areas, curb extensions, bicycle parking areas, parklet areas, and/or green street low-impact development solutions.



Note that retrofits like this must comply with the accessibility criteria for pedestrian facilities in Chapter 1510.



"Moving the Curb" Photo courtesy of NACTO.org

1238.04(2) Parklets and Plazas

Parklets and plazas reuse existing right of way in urban and rural town centers, providing public space to support the economic vitality and social livability performance of a particular context. As geometric cross sections are reconfigured, spaces may become available at intersections or for repurposing a parking area into either plazas or parklets. The primary intent of presenting these treatments is for low-speed roadways or main streets with volumes at or below 20,000 ADT. However, there are many potential constraints external to the engineering design that may need resolution before application. Consult with Real Estate Services to discuss the specific property management-related concerns and any potential lease and/or economic payment considerations proportionally appropriate for utilization of the highway space in this manner, as further detailed in RCW 47.24.020(15).

A parklet specifically uses the area usually used for parking to create a space for pedestrians. A common application provides seating accommodations to support local restaurants and shops.



Parklet designs will vary depending on local jurisdiction regulations, but they typically include railing and/or planter boxes to provide a separation of uses between people and traffic. Parklet design should not cover catch basins or other features that may require frequent maintenance. Parklets interact with motorized vehicle traffic best when placed on tangent alignments.

Plazas can reuse right of way to define a relatively large common public space. Plazas are typically associated with a central gathering location for special events, and will likely have limited application on Washington state highways.



1238.05 References

1238.05(1) Design Guidance

Highway Runoff Manual, M 31-16, WSDOT

Local Agency Guidelines (LAG), M 36-63, WSDOT

Plans Preparation Manual, M 22-31, WSDOT

Standard Plans for Road, Bridge, and Municipal Construction, M 21-01, WSDOT

Standard Specifications for Road, Bridge, and Municipal Construction, M 41-10, WSDOT

1238.05(2) Supporting Information

Understanding Flexibility in Transportation Design – Washington, WA-RD 638.1, Washington State Department of Transportation, 2005
www.wsdot.wa.gov/research/reports/fullreports/638.1.pdf

Urban Street Design Guide, National Association of City Transportation Officials, New York, NY, 2013
www.nacto.org

Urban Street Stormwater Guide, National Association of City Transportation Officials, New York, NY, 2017
www.nacto.org

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO, current edition
www.transportation.org/Pages/Default.aspx

Chapter 1239 Geometric Cross Section – Shoulders, Side Slopes, Curbs, and Medians

1239.01 Introduction
1239.02 Shoulders
1239.03 Side Slopes and Ditches
1239.04 Roadway Sections in Rock Cuts
1239.05 Curbs
1239.06 Lateral Clearance to Curb and Barrier
1239.07 Medians & Outer Separations

1239.01 Introduction

This chapter provides information on geometric cross section components that are common to many facility types. Cross section elements include: shoulders, medians and outer separations, side slopes, and curbing.

Refer to the *Design Manual* Glossary for many of the terms used in this chapter. Refer to Chapter 300 for design documentation requirements.

1239.02 Shoulders

Shoulders are typically used on high or intermediate speed limited and non-limited access facilities, some rural contexts, as well as intermediate-speed locations that do not have streetsides (curb-sections) (see Chapter 1238). Intermediate-speed locations in suburban and urban contexts that utilize streetsides do not need to include a shoulder unless determined to be necessary by safety performance analysis, hydraulic analysis or engineering judgment.

Shoulders provide space to escape potential collisions or reduce their severity. They also provide a sense of openness, contributing to driver ease at higher speeds. Shoulders also reduce seepage adjacent to the traveled way by discharging stormwater farther away.

1239.02(1) Shoulder Width

Shoulder width ranges for highways are shown in Exhibit 1239-1. Use the mode/function/performance approach (Chapter 1106) to choose a dimension from the range given.

Exhibit 1239-1 Shoulder Widths for Highways

Highway Speed	Highway Type	Shoulder Width [1] [2]	
		Inside	Outside
High speed	Freeway (including Interstate)	See Chapter 1232	
	Other highway	4’ – 10’	4’ – 10’
Intermediate speed	All	4’ – 8’	4’ – 8’
Low speed	All	0’ – 8’ [2]	2’ – 8’

Notes:

[1] Bus use only shoulder width range is 12-ft to 14-ft.

[2] If curb or barrier present, see Exhibit 1239-9.

1239.02(1)(a) Shoulder Width Considerations

Exhibit 1239-2 lists considerations for choosing an appropriate shoulder width from the range given. The considerations listed help one to understand the modal needs and function associated with different shoulder widths.

Contact the Area Maintenance Superintendent to determine the shoulder width appropriate for maintenance operations. In some cases, a continuous width is not necessary; instead, the focus is placing the shoulder width near assets with high-frequency maintenance needs. Compare the added cost of the wider shoulders to the added benefits to maintenance operations as well as other benefits that may be derived (see Chapter 301).

The usable shoulder is the width necessary to provide the desired function (see Exhibit 1239-2). Usable shoulder width is less than the constructed shoulder width when vertical features (such as traffic barrier or walls) are at the edge of the shoulder. This is because drivers tend to shy away from the vertical feature. For widening for traffic barrier, see Chapter 1610. For requirements for lateral clearance to barrier or curb, see 1239.06.

Shoulder widths greater than 10 feet may encourage use as a travel lane. Therefore, use shoulders wider than 10 feet only to meet one of the listed functions (see Exhibit 1239-2).

When walls are placed adjacent to shoulders, see Chapters 730 and 740 for barrier guidance.

Exhibit 1239-2 Shoulder Function & Modal Accommodation Width Considerations

Shoulder Function	Shoulder Width Guidance [7]
Stopping out of the traffic lanes	8 ft – 12 ft [1]
Minimum lateral clearance to curb or barrier	See 1239.06
Hard shoulder running	11 ft to 14 ft [2]
Bicycle use	4 ft [3]
Pedestrian use	4 ft [3]
Large-vehicle off-tracking on curves	Use turn simulation software to determine shoulder needs
U-turn turnouts	Varies – See Chapter 1310
Maintenance operations	Varies [4] [5]
Law enforcement, emergency services & incident response	8 ft [5]
Transit stops	See Chapter 1430
Slow-vehicle turnouts and shoulder driving	See Chapter 1270
Ramp meter storage	8 – 12 ft [1]
HOV bypass	10 – 14 ft [6]
Ferry holding	8 ft – 12 ft [1]
For use as a lane during reconstruction of the through lanes	8 ft – 12 ft [1]
Structural support of pavement	2 ft
Improve sight distance in cut sections	See Chapter 1260

Notes:

[1] 10 foot minimum recommended for freight or transit vehicles.

[2] For bus use only shoulder, the range is 12 ft to 14 ft and the selected width should be determined with transit provider. For lateral clearance requirements see 1239.06.

[3] Minimum shoulder function width for bicycles. Additional width is recommended when combined with shoulder rumble strips, curb, or barrier (see Chapter 1600 and the *Standard Plans*). For guidance, see Chapter 1520 for accommodating bicycles and Chapter 1510 for accommodating pedestrians.


[4] 10 foot usable width to park a maintenance truck out of the through lane; 14 foot width for equipment with outriggers to work out of traffic.

[5] For additional information, see Chapters 1370, 1410 and 1720.


[6] Determine width with transit provider, and see 1239.06 for lateral clearance requirements.

[7] Presence of barrier or curb may require additional width. Use auto turn studies for non-tangent alignments.


Exhibit 1239-3 Shoulder Details




Shoulder Design on the Low Side of the Roadway for Cross Slopes Greater Than 2%



Shoulder Design on the High Side of the Roadway on Curves and Divided Roadways Shoulder Slopes With Roadway



Shoulder Design on the High Side of the Roadway on Curves and Divided Roadways Shoulder Slopes Away From Roadway




Shoulder Design with Curb [4] [5]

*AP = Angle point in the subgrade


Notes:

- The top three drawings illustrate angle points in subgrade to drain stormwater away from the roadbed.
- For applicable numbered notes, see next page.


Exhibit 1239-3 Shoulder Details (continued)




Asphalt Concrete Curb Placement



Shoulder Rounding [2]



Shoulder Widening for Guardrail



Shoulder Widening for Barrier

Notes:

[1] Shoulder cross slopes are normally the same as the cross slopes for adjacent lanes. (For examples and additional information for locations where it may be desirable to have a shoulder cross slope different than the adjacent lane, see Chapter 1250).

[2] Provide widening and slope rounding outside the usable shoulder when foreslope is steeper than 4H:1V.

[3] For shoulder width guidance, see Exhibit 1239-1.

[4] For additional requirements for sidewalks, see Chapter 1510.

[5] See 1239.05 for curb design guidance.

[6] Provide paved shoulders wherever extruded curb is placed. (See the *Standard Plans* for additional details and dimensions.)

[7] When rounding is provided, consider uniform application on all ramps and crossroads, as well as the main roadway. End rounding on the crossroad just beyond the ramp terminals and at a similar location where only a grade separation is involved.

[8] When widening beyond the edge of usable shoulder for curb or barrier, additional widening for slope rounding may be omitted.

[9] For widening guidelines for guardrail and concrete barrier, see Chapter 1610.

General:

On divided multilane highways, see Exhibits 1239-12a through 1239-12c for additional details for median shoulders.

1239.03 Side Slopes and Ditches

The design for side slopes can affect shoulder design, clear zone requirements, and whether or not traffic barrier is necessary. Side slopes are more commonly encountered in high-speed and/or rural contexts. After the foreslope has been determined, use the guidance in Chapter 1600 to determine the need for a traffic barrier.

When designing side slopes, attempt to fit the slope selected for any cut or fill into the existing terrain to give a smooth transitional blend from the construction to the existing landscape when practicable. Flatter slopes are desirable, especially with higher posted speeds and when the associated cost does not significantly exceed other design options. Side slopes not steeper than 4H:1V, with smooth transitions where the slope changes, will provide a reasonable opportunity to recover control of an errant vehicle. Side slopes designed to 4H:1V or flatter are preferred. Provide widening and slope rounding outside the usable shoulder when foreslope is steeper than 4H:1V. Do not disturb existing stable cut slopes just to meet the 4H:1V side slope preference. When an existing slope is to be revised, document the reason for the change in the BOD.

3H:1V side slopes are traversable, but not necessarily recoverable. If providing 3H:1V slopes, consider placement of a flat area extending from the toe of the slope for errant vehicle recovery (see Chapter 1600). Where mowing is contemplated, provide slopes not steeper than 3H:1V to allow for mowing. If there will be continuous traffic barrier on a fill slope, and mowing is not contemplated, the slope may be steeper than 3H:1V. When providing side slopes steeper than 3H:1V, document the reason for the decision.

Where unusual geological features or soil conditions exist, treatment of the slopes depends upon results of a review of the location by the Region Materials Engineer (RME).

Do not install traffic barrier unless an object or condition is present that calls for mitigation in accordance with Chapter 1600 criteria. Unmitigated critical slopes will require a Design Analysis. The steepest slope allowed is determined by the soil conditions. Where favorable soil conditions exist, higher fill slopes may be as steep as 1½H:1V. (See Chapter 1600 for clear zone and barrier criteria.)

If borrow is necessary, consider obtaining it by flattening cut slopes uniformly on one or both sides of the highway. Where considering wasting excess material on an existing side slope, consult the RME to verify that the foundation soil will support the additional material.

Provide for drainage from the roadway surface and drainage in ditches (see Chapter 800). For drainage ditches, see 1239.03(1). At locations where vegetated filter areas or detention facilities will be established to improve highway runoff water quality, provide appropriate slope, space, and soil conditions for that purpose. (See the *Highway Runoff Manual* for design criteria and additional guidance.)

Except under guardrail installations, it is desirable to plant and establish low-growing vegetation on non-paved roadsides. This type of treatment relies on the placement of a lift of compost or topsoil over base course material in the roadway cross section. Consult with the area Maintenance Superintendent and the region or HQ Landscape Architect to determine the appropriate configuration of the roadway cross section and soil and plant specifications.

Flatten crossroad and road approach foreslopes to 6H:1V where feasible, and consider at least to 4H:1V. Provide smooth transitions between the main line foreslopes and the crossroad or

road approach foreslopes. Where possible, move the crossroad or road approach drainage away from the main line. This can locate the pipe outside the Design Clear Zone and reduce the length of pipe.

Provide slope treatment as shown in the *Standard Plans* at the top of roadway cut slopes except for cuts in solid rock. Unless Class B slope treatment is called for, Class A slope treatment is used. Call for Class B slope treatment where space is limited, such as where right of way is restricted.

1239.03(1) Drainage Ditches

Exhibit 1239-4 provides general information regarding drainage ditch design. The preferred cross section of a ditch is trapezoidal as shown. A 'V' ditch can be used where constraints, such as limited right of way or sensitive areas, preclude a trapezoidal ditch. Ensure hydraulic design requirements are met.


Where a drainage ditch is located adjacent to the toe of a side slope, consider the stability of the foreslope and backslope. A drainage ditch placed immediately adjacent to the toe of side slopes has the effect of increasing the height of the side slope by the depth of the ditch. In cases where the foundation soil is weak, the extra height could result in a side slope failure. As a general rule, the weaker the foundation and the higher the side slopes, the farther the ditch should be from the toe of slope. Consult the Region Materials Engineer for the proper ditch location.

When topographic restrictions exist, consider an enclosed drainage system with appropriate inlets and outlets.

Maintenance operations are also facilitated by adequate width between the toe of the slope and an adjacent drainage ditch. Where this type of facility is anticipated, provide sufficient right of way for access to the facility and place the drainage ditch near the right of way line.

Exhibit 1239-4 Drainage Ditch Details

Corrected here per Technical Errata 10-04-17



Notes:

- Freeboard is the vertical distance from the bottom of base course to the 10-year storm water surface (see the *Hydraulics Manual* for more information.)
- Coordinate ditch design with region Hydraulics
- See other sections of this chapter for shoulder and side slope details.

1239.03(2) Bridge End Slopes

Bridge end slopes are determined by several factors, including context, fill height, depth of cut, soil stability, and horizontal and vertical alignment. Coordinate bridge end slope treatment with the HQ Bridge and Structures Office (see Chapter 720). Whenever possible, design to avoid creating environments that might be desirable to the homeless, both for their safety and the safety of maintenance staff.

Early in the bridge plan development, determine preliminary bridge geometrics, end slope rates, and toe of slope treatments. Exhibit 1239-5a provides guidelines for use of slope rates and toe of slope treatments for overcrossings. Exhibit 1239-5b shows toe of slope treatments to be used on the various toe conditions.

Exhibit 1239-5a Bridge End Slopes

<table>
<tr><th>Bridge End Condition</th><th colspan="2">Toe of Slope End Slope Rate</th><th colspan="2">Lower Roadway Treatment [1]</th><th>Slope Rate</th></tr>
<tr><td rowspan="2">End Piers on Fill</td><td>Height</td><td>Rate</td><td>Posted speed of lower roadway</td><td>Treatment</td><td></td></tr>
<tr><td>≤ 35 ft
> 35 ft</td><td>1¾H:1V
2H:1V [2]</td><td>> 50 mph
≤ 50 mph</td><td>Rounding
No rounding</td><td></td></tr>
<tr><td>End Piers in Cut</td><td colspan="2">Match lower roadway slope [3]</td><td colspan="2">No rounding, toe at centerline of the lower roadway ditch.</td><td>[4]</td></tr>
<tr><td>Lower Roadway in Cut</td><td colspan="2">Match lower roadway slope [3]</td><td colspan="2">No rounding, toe at centerline of the lower roadway ditch.</td><td>[4]</td></tr>
<tr><td rowspan="2">Ends in Partial Cut and Fill</td><td colspan="2">When the cut depth is > 5 ft and length is > 100 ft, match cut slope of the lower roadway</td><td colspan="2">When the cut depth is > 5 ft and length is > 100 ft, no rounding, toe at centerline of the lower roadway ditch</td><td>[4]</td></tr>
<tr><td colspan="2">When the cut depth is ≤ 5 ft or the length is ≤ 100 ft, it is designer’s choice</td><td colspan="2">When the cut depth is ≤ 5 ft or the length is ≤ 100 ft, it is designer’s choice</td><td>[4]</td></tr>
</table>

Notes:


[1] See Exhibit 1239-5b.

[2] Slope may be 1¾H:1V in special cases.


[3] In interchange areas, continuity may require variations.

[4] See 1239.03.

Exhibit 1239-5b Bridge End Slope Details



Rounding



No Rounding



Toe at ℄ of Roadway Ditch

1239.04 Roadway Sections in Rock Cuts

There are two basic design treatments applicable to rock excavation. Typical sections for rock cuts, illustrated in Exhibits 1239-6 and 1239-7, are guides for the design and construction of roadways through rock cuts. Design A applies to most rock cuts. Design B is a talus slope treatment. Changes in slope or fallout area are recommended when justified. Base the selection of the appropriate sections on an engineering study and the recommendations of the region Materials Engineer and region Landscape Architect. Obtain concurrence from the Headquarters (HQ) Materials Lab.

1239.04(1) Design A

This design is shown in stage development to aid the designer in selecting an appropriate section for site conditions in regard to backslope, probable rockfall, hardness of rock, and so on.

The following guidelines apply to the various stages shown in Exhibit 1239-6:

- **Stage 1** is used where the anticipated quantity of rockfall is small, adequate fallout width can be provided, and the rock slope is ½H:1V or steeper. Controlled blasting is recommended in conjunction with Stage 1 construction.
- **Stage 2** is used when a "rocks in the road" problem exists or is anticipated. Consider it on flat slopes where rocks are apt to roll rather than fall.
- **Stage 3** represents the full implementation of all protection and safety measures applicable to rock control. Use it when extreme rockfall conditions exist.

Show Stage 3 as the ultimate stage for future construction in the Plans, Specifications, and Estimates (PS&E) if there is any possibility that it will be needed.


The use of Stage 2 or Stage 3 alternatives (concrete barrier) is based on the designer's analysis of the particular site. Considerations include maintenance; size and amount of rockfall; probable velocities; availability of materials; ditch capacity; adjacent traffic volumes; distance from traveled lane; and impact severity. Incorporate removable sections in the barrier at approximately 200-foot intervals. Provide appropriate terminal treatment (see Chapter 1610).

Occasionally, the existing ground above the top of the cut is on a slope approximating the design cut slope. The height (H) is to include the existing slope or that portion that can logically be considered part of the cut. Select cut slopes for a project that provide stability for the existing material.

Benches may be used to increase slope stability; however, the use of benches may alter the design given in Exhibit 1239-6.

The necessity for benches, as well as their width and vertical spacing, is established after an evaluation of slope stability. Make benches at least 20 feet wide. Provide access for maintenance equipment to the lowest bench and to the higher benches if feasible. Greater traffic benefits in the form of added safety, increased horizontal sight distance on curves, and other desirable attributes may be realized from widening a cut rather than benching.

Exhibit 1239-6 Roadway Sections in Rock Cuts: Design A



Rock Slope	H (ft)	W (ft)
Near Vertical	20 – 30	12
	30 – 60	15
	> 60	20
0.25H:1V through 0.50H:1V	20 – 30	12
	30 – 60	15
	60 – 100	20
	>100	25

Notes:

[1] For widening for guardrail and concrete barrier, see Chapter 1610.

General:

- Treat cut heights less than 20 feet as a normal roadway unless otherwise determined by the Region Materials Engineer.
- Stage 2 and Stage 3 Alternates may be used when site conditions dictate.
- Fence may be used in conjunction with the Stage 3 Alternate. (See Chapter 1600 for clear zone guidelines.)

1239.04(2) Design B


A talus slope treatment is shown in 1239-7. The rock protection fence is placed at any one of the three positions shown, but not in more than one position at a particular location. Consult with the RME for the placement of the rock protection fence in talus slope areas.

- **Fence position a** is used when the cliff generates boulders less than 0.25 yd^3 in size and the length of the slope is greater than 350 feet.
- **Fence position b** is the preferred location for most applications.
- **Fence position c** is used when the cliff generates boulders greater than 0.25 yd^3 in size regardless of the length of the slope. On short slopes, this may require placing the fence less than 100 feet from the base of the cliff.
- Use of gabions may be considered instead of the rock protection shown in fence position a. Because gabion treatment is considered similar to a wall, provide appropriate face and end protection (see Chapters 730 and 1610).

Use of the alternate shoulder barrier is based on the designer's analysis of the particular site. Considerations similar to those given for Design A alternatives apply.

Evaluate the need for rock protection treatments other than those described above for cut slopes that have relatively uniform spalling surfaces (consult with the RME).

Exhibit 1239-7 Roadway Sections in Rock Cuts: Design B



Shoulder Barrier Alternate

Notes:

[1] For widening for guardrail and concrete barrier, see Chapter 1610.


General:

- Ordinarily, place fence within a zone of 100 feet to 200 feet maximum from base of cliff, measured along the slope.
- Rock protection fence may be used in conjunction with the Shoulder Barrier Alternate when site conditions dictate.

1239.04(3) Stepped Slopes

Stepped slopes are a construction method intended to promote early establishment of vegetative cover on the slopes. They consist of a series of small horizontal steps or terraces on the face of the cut slope. Soil conditions dictate the feasibility and necessity of stepped slopes. They are to be considered on the recommendation of the RME (see Chapter 610). Consult the region landscape personnel for appropriate design and vegetative materials to be used. Use Exhibit 1239-8 for stepped slope design.

Exhibit 1239-8 Stepped Slope Design



Notes:

[1] Staked slope line: Maximum slope 1H:1V.

[2] Step rise: Height variable 1 foot to 2 feet.

[3] Step tread: Width = staked slope ratio x step rise.

[4] Step termini: Width ½-step tread width.

[5] Slope rounding.

[6] Overburden area: Variable slope ratio.

1239.05 Curbs

Curbs are designated as either vertical or sloped. Vertical curbs have a face slope not flatter than 1H:3V. Sloped curbs have a sloping face that is more readily traversed.

Curbs can also be classified as mountable. Mountable curbs are sloped curb with a height of 6 inches or less; 4 inches or less is recommended to reduce underside vehicle damage if driven over. When the face slope is steeper than 1H:1V, the height of a mountable curb is limited to 4 inches or less.

(a) Use vertical curbs with a height of 6 inches or more:

- To inhibit vehicles from leaving the roadway on low-speed roadways.
- To discourage vehicles from leaving low - and intermediate-speed roadways.
- For walkway and pedestrian refuge separations.
- For raised islands on which a traffic signal or traffic signal hardware is located.
- For expediting transfer times for transit partners on low- speed roadways in urban and suburban contexts (verify curb height needed with transit provider).

(b) Consider vertical curbs with a height of 6 inches or more:

- To inhibit midblock left turns.
- For divisional and channelizing islands.
- For landscaped islands.
- For stormwater conveyance

(c) Provide sloped curbs where a curb is needed but vertical curb is not suitable.

(d) Provide mountable curbs where a curb is needed and accommodation for specific design users makes it necessary.

(e) See Chapter 1320 for use of curbs in roundabouts.

In general, curbs are not recommended on high-speed facilities. Avoid using curbs if the same objective can be attained with pavement markings. However, 4-inch-high sloped curbs may be used on high-speed facilities to control drainage or for access control. Locate sloped curb no closer to the traveled way than the outer edge of the shoulder. Provide sloping end treatments where the curb is introduced and terminated. 6-inch-high sloped curbs may be considered on high-speed urban and suburban contexts where streetside zones are provided or where traffic movements are to be restricted. Provide justification for the use of vertical curb when applied to high-speed facilities.

Intermediate speed facilities may use vertical or sloped curbs; however, consider sloped curbs for intermediate target speeds. Consider use of 12-inch to 18-inch vertical curb when analysis demonstrates a need to reduce lane departure concerns on intermediate-speed facilities. All curb types are appropriate for low-speed facilities.

Where curbing is to be provided, provide a design that collects the surface water at the curb and drains it without ponding or flowing across the roadway as much as practicable to meet the safety and mobility performance needs for a project.

In some areas, curb may be needed to control runoff water until ground cover is attained to control erosion. Plan to remove the curb when the ground cover becomes adequate. Arrange

for curb removal with region maintenance staff as part of the future maintenance plans (see Maintenance Owner's Manual guidance in Chapter 301). When curb is used in conjunction with guardrail, see Chapter 1610 for guidance. For existing curb, particularly on high-speed facilities, evaluate the continued need for the curb. Remove curbing that is no longer needed.

When an overlay will reduce the height of a curb, evaluate grinding (or replacing the curb) to maintain curb height if recommended by the pavement design and drainage needs. (See 1230.06(1) for shoulder cross slope considerations.) To maintain or restore curb height, consider lowering the existing pavement level and improving cross slope by grinding before an asphalt overlay or as determined by the pavement design. The cross slope of the shoulder may be steepened to maximize curb height and minimize other related impacts. Note that grinding can cause issues with meeting ADA criteria at curb ramps for counter slope and crosswalk running slope. See Chapter 1510 for more information.

Curbs can hamper snow-removal operations. In areas of heavy snowfall, get the Area Maintenance Superintendent's review for the use of curbing.

For curbs at traffic islands, see Chapter 1310. For curbs at roundabouts, see Chapter 1320 and the *Standard Plans*.

1239.06 Lateral Clearance to Curb and Barrier

Lateral clearance to curb or barrier is the perpendicular distance from edge of traveled way to the face of a curb or a traffic barrier (guardrail, concrete barrier, etc.). Lateral clearance includes the shoulder width. The minimum lateral clearance to the face of a curb or barrier is shown in Exhibit 1239-9. See also Chapter 1310 for intersections including clearance to curb at traffic islands.

Exhibit 1239-9 Minimum Lateral Clearance to Barrier and Curb

<table>
<tr><th></th><th>Curb
Left or Right [1] [2]</th><th>Barrier</th></tr>
<tr><td>High Speed</td><td rowspan="2">4 ft; curb not recommended</td><td rowspan="3">4 ft</td></tr>
<tr><td>Intermediate Speed</td></tr>
<tr><td>Low Speed</td><td>2 ft min. [3] [4]</td></tr>
<tr><td>Ramps [5]</td><td>4 ft</td><td></td></tr>
</table>

Notes:

[1] For HOV lanes on arterials streets, see Section 1410.06(4)(d)

[2] Measured from the edge of traveled way to the face of curb.

[3] When mountable curb is used on low speed routes (35 mph or less), maintaining shoulder width is desirable; however, with justification, curb may be placed at the edge of traveled way.

[4] On low speed urban roadways (35 mph or less), maintaining shoulder width is desirable; however, with justification, curb (mountable or non-mountable) may be placed at the edge of traveled way.

[5] Raised median for two-way ramps (see 1360.03(5).)

1239.07 Medians and Outer Separations

Medians are either restrictive or nonrestrictive. Restrictive medians physically limit motor vehicle encroachment, using raised curb, median barrier, fixed delineators, vegetative strips, or vegetative depressions. Nonrestrictive medians limit motor vehicle encroachment legally, and use pavement markings to define locations where turns are permissible. The main functions of an outer separation are to separate the main roadway from a frontage road or service lane, or to provide modal segregation. Consider medians or outer separations to optimize the desired performance objective, such as safety, throughput operations, pedestrian mobility needs, etc.

Provide a median or outer separation to:

- Separate traffic (such as with HOT lanes) and/or modal users (such as bike buffers).
- Separate differing alignments on divided highways.
- Reduce head-on collisions.
- Manage speed.
- Provide a refuge area for emergency parking.
- Allow for future widening of a planned phase.
- Separate collector-distributor lanes, weigh sites, or rest areas.
- Accommodate drainage facilities.
- Accommodate bridge piers at undercrossings.
- Provide vehicle storage space for crossing and left-turn movements at intersections.
- Accommodate headlight glare screens, including planted or natural foliage.
- Provide recovery areas for errant or disabled vehicles.
- Accommodate pedestrian refuge area at crossing locations.
- Provide storage space for snow and water from traffic lanes.
- Provide increased safety, comfort, and ease of operations for different modes.
- Control access.
- Provide enforcement areas.

The width of a median is measured from edge of traveled way to edge of traveled way and includes shoulders. Median widths can vary greatly based on the functional use of the median, target speed, and context. Guidance for median widths depending on their function and context is given in Exhibits 1239-10 and 1239-11.

1239.07(1) Median Design: High and Intermediate Speed

Exhibit 1239-10 lists width considerations for median functions common on high-speed facilities. Depending on the context and performance needs, this guidance may also apply to intermediate speed facilities as well.

When the horizontal and vertical alignments of the two roadways of a divided highway are independent of one another, determine median side slopes in conformance with 1239.03 and Chapters 1600 and 1610. Independent horizontal and vertical alignment, rather than parallel alignment, can allow for reduced grading or cut sections.

Considerable latitude in grading treatment is intended on wide, variable-width medians, provided the minimum performance needs are met or exceeded. Unnecessary clearing, grubbing, and grading are undesirable within wide medians. Use selective thinning and limited reshaping of the natural ground when feasible. For median clear zone criteria see Chapter 1600, and for slopes between the face of traffic barriers and the traveled way see Chapter 1610.

In areas where land is expensive, make an economic comparison of wide medians to narrow medians with barrier. Consider right of way, construction, maintenance, and safety performance. The widths of medians need not be uniform. Make the transition between median widths as long as practical. (See Chapter 1210 for minimum taper lengths.)

When using concrete barriers in depressed medians or on curves, provide for surface drainage on both sides of the barrier. The transverse notches in the base of precast concrete barrier are not intended to be used as a drainage feature, but rather as pick-up points when placing the sections.

At locations where the median will be used to allow vehicles to make a U-turn, consider increasing the width to meet the needs of the selected design vehicles making the U-turn. (For information on U-turn locations, see Chapter 1310.) Document the selected design vehicle and provide alternate route information for vehicles not serviced by the U-turn.

Where feasible, widen medians at intersections on rural divided multilane highways. Provide sufficient width to store vehicles crossing the expressway or entering the expressway with a left turn.

When the median is to be landscaped, or where rigid objects are to be placed in the median, see Chapter 1600 for traffic barrier and clear zone guidance. When the median will transition for use as a left-turn lane, see Chapter 1310 for left-turn lane design considerations.

Exhibit 1239-10 Median Functions and Guidance: High and Intermediate Speeds

Median Functional Use	Width Guidance
Separating opposing traffic	Varies[1] and see Chapters 1600 and 1610
Separating alignments	Varies See 1239.03 and Chapters 1600 and 1610 [2]
Recovery/Refuge areas for errant vehicles	See 1239.03 and Chapter 1600
Median signing and illumination – Undivided highways and ramps	6 ft [1] or as recommended for signing and illumination design
Storage space for snow	Consult Region Maintenance
Enforcement areas	See Chapters 1370 and 1410, and consult with Washington State Patrol
Vehicle storage space for crossing at intersections	See Chapter 1310, and consult with region traffic engineer
Median U-turn or Median crossover	See Chapters 1310 and 1370
Outer separation for frontage or collector-distributer	6 ft – or more [1] and see Chapters 1360, 1600 and 1610
Transit use	Varies; see Chapter 1420 and discuss with Transit Agency [3]

Notes:

[1] Conduct safety performance analysis and include potential countermeasures identified to obtain the desired safety performance. Consult with maintenance; additional width may be appropriate for unconstrained right of way locations, maintenance functions, or for divided highways on independent alignments.

[2] An economic comparison of wide medians to narrow medians with barrier is recommended.

[3] For planning and scoping purposes, 32 ft can be the assumed minimum for two-way transit operations or 22 ft for one-way transit operations.

1239.07(2) Median Design: Low and Intermediate Speeds

Exhibit 1239-11 provides design guidance for medians within low-speed transportation contexts. Depending on the context and performance needs, this guidance may also apply to intermediate speed facilities as well. In low-speed urban and suburban contexts, see Chapter 1600 for Design Clear Zone requirements.

A common form of restrictive median on urban managed access highways is the raised median. For more information on traffic volume thresholds for restrictive medians on managed access highways, see Chapter 540.

Exhibit 1239-11 Median Functions and Guidance: Low and Intermediate Speeds

Median Functional Use	Width Guidance
Access Control – Restrictive	Width of raised median feature [1] [2]
Access Control – Non-restrictive	1 ft minimum [3] (see Chapter 540)
Pedestrian refuge for crossing locations	6 ft minimum, excluding curb width (see Chapter 1510)
Speed management and/or aesthetic design – Vegetated	Varies [2] [4] (see Chapter 1103)
Drainage or treatment facilities	Varies [5]
Bike buffer treatment	2 ft – 3 ft (see Chapter 1520)
Transit connection	Varies [6] (see Chapters 1238 and 1430)
Outer separation used for a pedestrian zone	9 ft – 16 ft [4] [7] [8]

Notes:

[1] The width of a raised median can be minimized by using a dual-faced cement concrete traffic curb, a precast traffic curb, or an extruded curb.

[2] Consider width necessary for lateral clearance.

[3] 2 ft minimum if adjacent lane widths are less than 11 ft.

[4] Consult Region Landscape Architect; width will depend on type of plantings. Over-excavation may be necessary to prepare soil for the selected plantings to ensure mature heights are obtained.


[5] Consult Hydraulic Report for width necessary for drainage or treatment facilities.

[6] Consult with the transit provider. If a transit shelter is planned, a minimum 5 ft clear area measured from the edge of shelter roofing to face of curb width, is necessary for pedestrians to move to and around the shelter and for lift extension (see Chapter 1430).


[7] Consider width needed for plantings or street furniture to create the appropriate pedestrian zone segregation and environment.

[8] See also Chapter 1510


Exhibit 1239-12a Divided Highway Median Sections




Design A: Crowned Median



Design: B Depressed Median




Alternate Design 1: Treatment on Curves




Alternate Design 2: No Fixed Pivot Point [2]

Note:
For applicable notes, see Exhibit 1239-12c.


Exhibit 1239-12b Divided Highway Median Sections



Design C: Minimum Nonpaved Median For 4 or More Lanes [2]




Design D: Minimum for 4 or More Lanes With Future Lanes in Median



Design E: Minimum for 4 or More Lanes With Independent Alignment

Note:
For applicable notes, see Exhibit 1239-12c.

Exhibit 1239-12c Divided Highway Median Sections



Design F: Raised Median[13]

Notes:

[1] For guidance on median widths, see Exhibits 1239-10 and -11

[2] Consider vertical clearances, drainage, and aesthetics when locating the pivot point.

[3] Generally, slope pavement away from the median. When barrier is present and the roadway is in a superelevation, size the shoulder so that standing water is not in the travel lane. Where appropriate, a crowned roadway section may be used in conjunction with the depressed median.

[4] Design B may be used uniformly on both tangents and horizontal curves. Use Alternate Design 1 or Alternate Design 2 when the "rollover" between the shoulder and the inside lane on the high side of a superelevated curve exceeds 8%. Provide suitable transitions at each end of the curve for the various conditions encountered in applying the alternate to the basic median design.

[5] Method of drainage pickup to be determined by the designer.

[6] Median shoulders normally slope in the same direction and rate as the adjacent through lane. See 1250.02(2) for examples and additional information for locations where it may be desirable to have a shoulder cross slope different than the adjacent lane.

[7] For guidance on shoulder widths, see 1239.02.

[8] Future lane width of a planned phase.

[9] Widen and round foreslopes steeper than 4H:1V as shown in Exhibit 1239-3. See Chapter 1600 for barrier recommendations.

[10] Designs C, D, and E are rural high-speed median designs. See Exhibit 1239-10 for recommended median widths.

[11] Raised medians may be paved or landscaped. For clear zone and barrier guidelines when fixed objects or trees are in the median, see Chapter 1600.

[12] Lane and shoulders normally slope away from raised medians. When they slope toward the median, provide for drainage.

[13] See 1239.05 and 1239.06 for curb design guidance.

Chapter 1240 Turning Roadways

1240.01 General
1240.02 Turning Roadway Widths
1240.03 Documentation
1240.04 References

1240.01 General

The roadway on a curve may need to be widened to make the operating conditions comparable to those on tangents. There are two main reasons to do this. One is the off-tracking of vehicles such as trucks and buses. The other is the increased difficulty drivers have in keeping their vehicles in the center of the lane. Apply turning roadway widths only when there is a need to optimize the operational or safety performance of a particular segment of roadway with larger volumes of trucks or when trucks are the identified modal priority. The application of turning roadway width is not applicable on managed access low-speed roadways or managed access intermediate-speed highways in suburban or urban contexts.

For additional information, see the following chapters:

Chapter	Subject
1230	Cross section design element widths
1250	Superelevation
1360	Lane and shoulder widths for ramps

1240.02 Turning Roadway Widths

1240.02(1) Two-Lane Two-Way Roadways

Exhibit 1240-1a shows the traveled way width (W) for two-lane two-way roadways. For values of radius (R) between those given, interpolate W and round up to the next foot.

Minimum traveled way width (W), based on the delta angle of the curve (shown in Exhibit 1240-1b), may be used. Document the reasons for using the minimum width. Round W to the nearest foot.

Widths given in Exhibits 1240-1a and 1b are for facilities with 12-foot lanes. When 11-foot lanes are selected, width (W) may be reduced by 2 feet.

1240.02(2) Two-Lane One-Way Roadways

Exhibit 1240-2a shows the traveled way width (W) for two-lane one-way turning roadways, including two-lane ramps and four-lane highways. For values of radius (R) between those given, interpolate W and round up to the next foot. Treat each direction of travel on four-lane facilities as a one-way roadway.

Minimum traveled way width (W), based on the delta angle of the curve (shown in Exhibit 1240-2b), may be used. Document the reasons for using the minimum width. Round W to the nearest foot.

Widths given in Exhibits 1240-2a and 2b are for facilities with 12-foot lanes. When 11-foot lanes are selected, width (W) may be reduced by 2 feet.

To keep widths to a minimum, the traveled way widths for Exhibits 1240-2a and 2b were calculated using the WB-40 design vehicle. When volumes are high for trucks larger than the WB-40 and other traffic, consider using the widths from Exhibits 1240-1a and 1b.

1240.02(3) One-Lane Roadways

Exhibit 1240-3a shows the traveled way width (W) for one-lane turning roadways. For values of R between those given, interpolate W and round up to the next foot. Exhibit 1240-3a applies to one-lane ramps only when the largest vehicles present demonstrate a safety or operational need based on frequency of use and shoulder pavement depths, and when turn simulation software shows that the total roadway width cannot accommodate the turning movement within the structural pavement section.

Minimum width (W), based on the delta angle of the curve for one-lane roadways, may be used. Exhibit 1240-3b gives W using the radius to the outer edge of the traveled way. Exhibit 1240-3c gives W using the radius on the inner edge of the traveled way. Document the reasons for using the minimum width. Round W to the nearest foot.

Build shoulder pavements at full depth for one-lane roadways. To keep widths to a minimum, traveled way widths were calculated using the WB-40 design vehicle, which may force larger vehicles to encroach on the shoulders. This also helps to maintain the integrity of the roadway structure during partial roadway closures.

1240.02(4) Other Roadways

For roadways where the traveled way is more than two lanes in any direction:

- For each lane in addition to two, additional width in excess of the selected lane width dimension (see Chapters 1230 and 1106) is not needed.
- For three-lane ramps with HOV lanes, see Chapter 1410.

1240.02(5) Total Roadway Width

Shoulder widths for the highway or ramp are added to the traveled way width to determine the total roadway width.

Small amounts of widening add to the cost with little added benefit. When the traveled way width for turning roadways results in widening less than 0.5 foot per lane, or a total widening of less than 2 feet on existing roadways that are to remain in place, it may be disregarded.

When widening the traveled way:

- Widening may be constructed on the inside of the traveled way or divided equally between the inside and outside. Do not construct widening only on the outside of a curve.
- Place final marked lane lines, and any longitudinal joints, at equal spacing between the edges of the widened traveled way.

- Provide widening throughout the curve length.
- For widening on the inside, make transitions on a tangent where possible.
- For widening on the outside, develop the widening by extending the tangent. This avoids the appearance of a reverse curve that a taper would create.
- For widening of 6 feet or less, use a 1:25 taper. For widths greater than 6 feet, use a 1:15 taper.

1240.03 Documentation

Refer to Chapter 300 for design documentation requirements.

1240.04 References

1240.04(1) Design Guidance

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT

Standard Specifications for Road, Bridge, and Municipal Construction (Standard Specifications), M 41-10, WSDOT

1240.04(2) Supporting Information

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO, current edition

Exhibit 1240-1a Traveled Way Width for Two-Lane Two-Way Turning Roadways

Radius on Centerline of Traveled Way, R (ft)	Design Traveled Way Width, W (ft)[1]
3,000 to tangent	24
2,999	25
2,000	26
1,000	27
800	28
600	29
500	30
400	31
350	32
300	33
250	35
200	37
150	41

Note:

[1] Width (W) is based on:

- WB-67 design vehicle
- 3-ft clearance per lane (12-ft lanes)

When 11-ft lanes are selected, width may be reduced by 2 ft.





Exhibit 1240-1b Traveled Way Width for Two-Lane Two-Way Turning Roadways: Based on the Delta Angle



Note:

Width (W) is based on:

- WB-67 design vehicle
- 3-ft clearance per lane (12-ft lanes)

When 11-ft lanes are selected, width may be reduced by 2 ft.

Exhibit 1240-2a Traveled Way Width for Two-Lane One-Way Turning Roadway

Radius on Centerline of Traveled Way, R (ft)	Design Traveled Way Width, W (ft)[1]
3,000 to tangent	24
1,000 to 2,999	25
999	26
600	26
500	27
400	27
300	28
250	29
200	29
150	31
100	34

Note:

[1] Width (W) is based on:

- WB-40 design vehicle
- 3-ft clearance per lane (12-ft lanes)

When 11-ft lanes are selected, width may be reduced by 2 ft.





Exhibit 1240-2b Traveled Way Width for Two-Lane One-Way Turning Roadways: Based on the Delta Angle



Note:

Width (W) is based on:

- WB-40 design vehicle
- 3-ft clearance per lane (12-ft lanes)

When 11-ft lanes are selected, width may be reduced by 2 ft.

Exhibit 1240-3a Traveled Way Width for One-Lane Turning Roadways

Radius, R (ft)	Design Traveled Way Width, W (ft)	
	Radius on Outside Edge of Traveled Way	Radius on Inside Edge of Traveled Way
7,500 to tangent	13[1]	13[1]
1,600	14	14
300	15	15
250	16	16
200	17	17
150	17	17
100	19	18
75	21	19
50	26	22

Note:

[1] On tangents, the minimum lane width is selected based on Chapters 1230 and 1106.

Width (W) is based on:

- WB-40 design vehicle
- 4-ft clearance





Exhibit 1240-3b Traveled Way Width for One-Lane Turning Roadways: Based on the Delta Angle, Radius on Outside Edge of Traveled Way




Note:

All radii are to the outside edge of traveled way.

Width (W) is based on:

- WB-40 design vehicle
- 4-ft clearance

Exhibit 1240-3c Traveled Way Width for One-Lane Turning Roadways: Based on the Delta Angle, Radius on Inside Edge of Traveled Way



Note:

All radii are to the inside edge of traveled way.

Width (W) is based on:

- WB-40 design vehicle
- 4-ft clearance

Chapter 1250 Cross Slope and Superelevation

1250.01 General
1250.02 Roadway Cross Slope
1250.03 Superelevation Rate Selection
1250.04 Existing Curves
1250.05 Turning Movements at Intersections
1250.06 Runoff for Highway Curves
1250.07 Runoff for Ramp Curves
1250.08 Documentation
1250.09 References

1250.01 General

Use this chapter to design roadway cross slopes and superelevation. Cross slopes function to drain water away from the roadway and 2% is a commonly used slope rate. To maintain the design speed, highway and ramp curves are usually superelevated to overcome part of the centrifugal force that acts on a vehicle.

1250.02 Roadway Cross Slope

1250.02(1) Lanes

The cross slope on tangents and curves is a main element in roadway design. The cross slope or crown on tangent sections and large radius curves is complicated by the following two contradicting controls:

- Reasonably steep cross slopes aid in water runoff and minimize ponding as a result of pavement imperfections and unequal settlement.
- Steeper cross slopes are noticeable in steering, increase the tendency for vehicles to drift to the low side of the roadway, and increase the susceptibility of vehicles to slide to the side on icy or wet pavements.

A 2% cross slope is normally used for tangents and large-radius curves on high and intermediate pavement types, although cross slopes may vary from the target 2%.

The algebraic difference in cross slopes is an operational factor that can affect vehicles making a lane change across a grade-break during a passing maneuver on a two-lane two-way roadway. Its influence increases when increased traffic volumes decrease the number and size of available passing opportunities.

On ramps with metering, consider how cross slopes can impact driver comfort within the queue. Additionally, larger cross slopes may present concerns about maintaining vehicle lateral position within the queue lane, depending on weather and resulting pavement conditions.

A somewhat steeper cross slope may be needed to facilitate recommended drainage design, even though this might be less desirable from an operational point of view. In such areas, consider not exceeding design cross slopes of 2.5% with an algebraic difference of 5%.

For a two-lane two-way roadway, provide an algebraic difference to meet the appropriate conditions stated above except when drainage design recommends otherwise.

1250.02(2) Shoulders

Shoulder cross slopes are normally the same as the cross slopes for adjacent lanes. With justification, shoulder slopes may be increased to 6%. On the high side of a roadway with a plane section, such as a turning roadway in superelevation, the shoulder may slope in the opposite direction from the adjacent lane. The maximum difference in slopes between the lane and the shoulder is 8%. Locations where it may be desirable to have a shoulder slope different than the adjacent lane are:

- Where curbing is used.
- Where shoulder surface is bituminous, gravel, or crushed rock.
- Where overlays are planned and it is desirable to maintain the grade at the edge of the shoulder.
- On divided highways with depressed medians where it is desirable to drain the runoff into the median.
- On the high side of the superelevation on curves where it is desirable to drain stormwater or meltwater away from the roadway.
- At intersections where pedestrian signal accommodations are provided within the shoulder

Where extruded curb is used, see the *Standard Plans* for placement (see Chapter 1239 for information on curbs). Widening is also normally provided where traffic barrier is installed (see Chapter 1610 and the *Standard Plans*).

On ramps with metering, where the shoulder is or could be utilized for queuing, consider how the shoulder cross slope can impact driver comfort within the queue. Additionally, larger shoulder cross slopes may present concerns of maintaining vehicle lateral position within the queue lane, depending on weather and resulting pavement conditions.

The remainder of this chapter provides information to design superelevation.

1250.03 Superelevation Rate Selection

The maximum superelevation rate allowed is 10%.

Depending on design speed, construct large-radius curves with a normal crown section. The minimum radii for normal crown sections are shown in Exhibit 1250-1. Superelevate curves with smaller radii as follows:

- Exhibit 1250-4a (emax=10%) is desirable for all open highways, ramps, and long-term detours, especially when associated with a main line detour.
- Exhibit 1250-4b (emax =8%) may be used for freeways in urban design areas and areas where the emax =6% rate is allowed but emax =8% is preferred.
- Exhibit 1250-4c (emax =6%) may be used—with justification—for non-freeway highways in urban design areas, in mountainous areas, and for short-term detours, which are generally implemented and removed in one construction season.
- Exhibit 1250-5 may be used for turning roadways at intersections, urban managed access highways with a design speed of 40 mph or less, and—with justification—ramps in urban areas with a design speed of 40 mph or less.

When selecting superelevation for a curve, consider the existing curves on the corridor. To maintain route continuity and driver expectance on open highways, select the chart (see Exhibits 1250-4a, 4b, or 4c) that best matches the superelevation on the existing curves.

In locations that experience regular accumulations of snow and ice, limit superelevation from the selected chart to 6% or less. In these areas, provide justification for superelevation rates greater than 6%. Vehicles moving at slow speeds or stopped on curves with supers greater than 6% tend to slide inward on the radius (downslope).

Round the selected superelevation rate to the nearest full percent.

Exhibit 1250-1 Minimum Radius for Normal Crown Section

Design Speed (mph)	Minimum Radius for Normal Crown Section (ft)
15	945
20	1,680
25	2,430
30	3,325
35	4,360
40	5,545
45	6,860
50	8,315
55	9,920
60	11,675
65	13,130
70	14,675
75	16,325
80	18,065

1250.04 Existing Curves

Evaluate the superelevation on an existing curve to determine its adequacy. Use the equation in Exhibit 1250-2 to determine the minimum radius for a given superelevation and design speed.

Exhibit 1250-2 Minimum Radius for Existing Curves

$$R = \frac{6.68V^2}{e + f}$$

Where:
R = The minimum allowable radius of the curve (ft)
V = Design speed (mph)
e = Superelevation rate (%)
f = Side friction factor from Exhibit 1250-3

Address superelevation when the existing radius is less than the minimum radius calculated using the equation or when the maximum speed determined by a ball banking analysis is less than the design speed. When modifying the superelevation of an existing curve, provide superelevation as given in 1250.02.

Exhibit 1250-3 Side Friction Factor

Design Speed (mph)	Side Friction Factor (f)
15	32
20	27
25	23
30	20
35	18
40	16
45	15
50	14
55	13
60	12
65	11
70	10
75	9
80	8

1250.05 Turning Movements at Intersections

Curves associated with the turning movements at intersections are superelevated using the rates for low-speed urban roadway curves. Use superelevation rates as high as practicable, consistent with curve length and climatic conditions. Exhibit 1250-5 shows the minimum superelevation for the given design speed and radius. When using high superelevation rates on short curves, provide smooth transitions with merging ramps or roadways.

1250.06 Runoff for Highway Curves

Provide transitions for all superelevated highway curves as specified in Exhibits 1250-6a through 6e. Which transition to use depends on the location of the pivot point, the direction of the curve, and the roadway cross slope. The length of the runoff is based on a maximum allowable difference between the grade at the pivot point and the grade at the outer edge of traveled way for one 12-foot lane.

Pay close attention to the profile of the edge of traveled way created by the superelevation runoff; do not let it appear distorted. The combination of superelevation transition and grade may result in a hump and/or dip in the profile of the edge of traveled way. When this happens, the transition may be lengthened to eliminate the hump and/or dip. If the hump and/or dip cannot be eliminated this way, pay special attention to drainage in the low areas to prevent ponding. Locate the pivot point at the centerline of the roadway to help minimize humps and dips at the edge of the traveled lane and reduce the superelevation runoff length.

When reverse curves are necessary, provide sufficient tangent length for complete superelevation runoff for both curves—that is, from full superelevation of the first curve, to level to full superelevation of the second curve. If tangent length is longer than this, but not sufficient to provide full super transitions—that is, from full superelevation of the first curve, to normal crown to full superelevation of the second curve—increase the superelevation runoff lengths until they abut. This provides one continuous transition, without a normal crown section, similar to Designs C2 and D2 in Exhibits 1250-6c and 6d, except that full super will be attained rather than the normal pavement slope as shown.

Superelevation runoff on structures is permissible but not desirable. Whenever practicable, strive for full super or normal crown slopes on structures.

1250.07 Runoff for Ramp Curves

Superelevation runoff for ramps use the same maximum relative slopes as the specific design speeds used for highway curves. Multilane ramps have a width similar to the width for highway lanes; therefore, Exhibits 1250-6a through 6e are used to determine the superelevation runoff for ramps. Superelevation transition lengths (L_T) for single-lane ramps are given in Exhibits 1250-7a and 7b. Additional runoff length for turning roadway widening is not required.

1250.08 Documentation

Refer to Chapter 300 for design documentation requirements.

1250.09 References

1250.09(1) Design Guidance


Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT


Standard Specifications for Road, Bridge, and Municipal Construction (Standard Specifications), M 41-10, WSDOT

1250.09(2) Supporting Information

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO, current edition


Exhibit 1250-4a Superelevation Rates (10% Max)






Design Speed (mph)	15	20	25	30	35	40	45	50	55	60	65	70	75	80
Minimum Radius (ft)	40	75	130	205	295	415	545	700	880	1,095	1,345	1,640	1,980	2,380


Exhibit 1250-4b Superelevation Rates (8% Max)






Design Speed (mph)	15	20	25	30	35	40	45	50	55	60	65	70	75	80
Minimum Radius (ft)	40	80	135	215	315	450	590	760	965	1,205	1,490	1,820	2,215	2,675


Exhibit 1250-4c Superelevation Rates (6% Max)





Design Speed (mph)	15	20	25	30	35	40	45	50	55	60	65	70	75	80
Minimum Radius (ft)	40	85	145	235	345	490	645	840	1,065	1,340	1,665	2,050	2,510	3,055

Exhibit 1250-5 Superelevation Rates for Intersections and Low-Speed Urban Roadways



NC = Normal crown

Exhibit 1250-6a Superelevation Transitions for Highway Curves


e (%)	L_B=Basic Runoff in Feet for Design Speed*													
	15 mph	20 mph	25 mph	30 mph	35 mph	40 mph	45 mph	50 mph	55 mph	60 mph	65 mph	70 mph	75 mph	80 mph
2	30	30	35	35	40	40	45	50	50	55	55	60	65	70
3	45	50	50	55	60	60	65	70	75	80	85	90	95	105
4	60	65	70	75	75	85	90	95	100	105	110	120	125	135
5	75	80	85	90	95	105	110	120	130	135	140	150	160	170
6	90	95	105	110	115	125	135	145	155	160	170	180	190	205
7	110	115	120	130	135	145	155	170	180	185	195	210	220	240
8	125	130	135	145	155	165	180	190	205	215	225	240	250	275
9	140	145	155	165	175	185	200	215	230	240	250	270	285	310
10	155	160	170	180	195	205	220	240	255	265	280	300	315	345

*Based on one 12-ft lane between the pivot point and the edge of traveled way. When the distance exceeds 12 ft, use the following equation to obtain L_R:

$$L_R = L_B(1+0.04167X)$$

Where:


X = The distance in excess of 12 ft between the pivot point and the farthest edge of traveled way, in ft.




Design A – Pivot Point on Centerline Crown Section

c = Normal crown (%)
e = Superelevation rate (%)
n = Number of lanes between points
w = Width of lane

Exhibit 1250-6b Superelevation Transitions for Highway Curves




Design B[1] – Pivot Point on Edge of Traveled Way:
Outside of Curve Crowned Section




Design B[2] – Pivot Point on Edge of Traveled Way:
Inside of Curve Crowned Section

c = Normal crown (%)
e = Superelevation rate (%)
n = Number of lanes between points
w = Width of lane

Exhibit 1250-6c Superelevation Transitions for Highway Curves




Design C[1] – Pivot Point on Centerline Curve in Direction of Normal Pavement Slope: Plane Section




Design C[2] – Pivot Point on Centerline Curve Opposite to Normal Pavement Slope: Plane Section

c = Normal crown (%)
e = Superelevation rate (%)
n = Number of lanes between points
w = Width of lane

Exhibit 1250-6d Superelevation Transitions for Highway Curves




Design D[1] – Pivot Point on Edge of Traveled Way Curve in Direction of Normal Pavement Slope: Plane Section




Design D[2] – Pivot Point on Edge of Traveled Way Curve Opposite to Normal Pavement Slope: Plane Section

c = Normal crown (%)
e = Superelevation rate (%)
n = Number of lanes between points
w = Width of lane

Exhibit 1250-6e Superelevation Transitions for Highway Curves




Design E[1] – Six-Lane With Median, Pivot Point on Edge of Traveled Way: Inside of Curve Crown Section



Design E[2] – Six-Lane With Median, Pivot Point on Edge of Traveled Way: Outside of Curve Crown Section


c = Normal crown (%)
e = Superelevation rate (%)
n = Number of lanes between points
w = Width of lane

Exhibit 1250-7a Superelevation Transitions for Ramp Curves



e (%)	Length of Transition in Feet for Design Speed							
	20 mph	25 mph	30 mph	35 mph	40 mph	45 mph	50 mph	55 mph
	L_T	L_T	L_T	L_T	L_T	L_T	L_T	L_T
3	10	15	15	15	15	15	15	15
4	20	25	25	25	25	30	30	35
5	30	35	35	35	40	45	45	50
6	40	45	45	50	55	55	60	65
7	50	55	55	60	65	70	75	80
8	60	65	70	75	80	85	90	95
9	70	75	80	85	95	100	105	110
10	80	85	90	100	105	115	120	130

Table 1 Pivot Point on Centerline: Curve in Direction of Normal Pavement Slope




e (%)	Length of Transition in Feet for Design Speed							
	20 mph	25 mph	30 mph	35 mph	40 mph	45 mph	50 mph	55 mph
	L_T	L_T	L_T	L_T	L_T	L_T	L_T	L_T
2	40	40	45	50	55	55	60	65
3	50	55	55	60	65	70	75	80
4	60	65	70	75	80	85	90	95
5	70	75	80	85	90	100	105	110
6	80	85	90	95	105	115	120	130
7	90	95	100	110	120	125	135	145
8	100	105	115	120	130	140	150	160
9	110	120	125	135	145	155	165	175
10	120	130	135	145	160	170	180	190

Table 2 Pivot Point on Centerline: Curve in Direction Opposite to Normal Pavement Slope


W_L = Width of ramp lane

Exhibit 1250-7b Superelevation Transitions for Ramp Curves



e (%)	Length of Transition in Feet for Design Speed							
	20 mph	25 mph	30 mph	35 mph	40 mph	45 mph	50 mph	55 mph
	L_T	L_T	L_T	L_T	L_T	L_T	L_T	L_T
3	20	25	25	25	25	30	30	35
4	40	45	45	50	55	55	60	65
5	60	65	70	75	80	85	90	95
6	80	85	90	100	105	115	120	130
7	100	105	115	120	130	140	150	160
8	120	130	135	145	160	170	180	190
9	140	150	160	170	185	195	210	225
10	160	170	180	195	210	225	240	255

Table 3 Pivot Point on Edge of Traveled Way: Curve in Direction of Normal Pavement Slope



e (%)	Length of Transition in Feet for Design Speed							
	20 mph	25 mph	30 mph	35 mph	40 mph	45 mph	50 mph	55 mph
	L_T	L_T	L_T	L_T	L_T	L_T	L_T	L_T
2	80	85	90	100	105	115	120	130
3	100	105	115	120	130	140	150	160
4	120	130	135	145	160	170	180	190
5	140	150	160	170	185	195	210	225
6	160	170	180	195	210	225	240	255
7	180	190	205	220	235	255	270	290
8	200	210	225	245	265	280	300	320
9	220	235	250	265	290	310	330	350
10	240	255	270	290	315	340	360	385

Table 4 Pivot Point on Edge of Traveled Way: Curve in Direction Opposite to Normal Pavement Slope

W_L = Width of ramp lane

Chapter 1260 Sight Distance

1260.01 General
1260.02 References
1260.03 Stopping Sight Distance (Eye height – 3.5 ft, Object height – 2.0 ft)
1260.04 Passing Sight Distance (Eye height – 3.5 ft, Object height – 3.5 ft)
1260.05 Decision Sight Distance (Eye height – 3.5 ft, Object height – 2.0 ft)
1260.06 Documentation

1260.01 General

Sight distance allows the driver to assess developing situations and take actions appropriate for the conditions. Sight distance relies on drivers being aware of and paying attention to their surroundings and driving appropriately for conditions presented. For the purposes of design, sight distance is considered in terms of stopping sight distance, passing sight distance, and decision sight distance.

For additional information, see the following chapters:

Chapter	Subject
1250	Sight distance at railroad crossings
1310	Sight distance at intersections at grade
1320	Sight distance at roundabouts
1340	Sight distance at driveways
1515	Sight distance for shared-use paths

1260.02 References

1260.02(1) Design Guidance

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)

1260.02(2) Supporting Information

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO

Passing Sight Distance Criteria, NCHRP 605

1260.03 Stopping Sight Distance (Eye height – 3.5 ft, Object height – 2.0 ft)

1260.03(1) Design Criteria

Stopping sight distance is provided when the sight distance available to a driver equals or exceeds the stopping distance for a passenger car traveling at the design speed.

Stopping distance for design is very conservatively calculated, with lower deceleration and slower perception reaction time than normally expected from the driver. Provide design stopping sight distance at all points on all highways and on all intersecting roadways, unless a design analysis is deemed appropriate.

1260.03(1)(a) Stopping Sight Distance

Stopping sight distance is the sum of two distances: the distance traveled during perception and reaction time and the distance to stop the vehicle. The perception and reaction distance used in design is the distance traveled in 2.5 seconds at the design speed.



The design stopping sight distance is calculated using the design speed and a constant deceleration rate of 11.2 feet/second^2. For stopping sight distances on grades less than 3%, see Exhibit 1260-1; for grades 3% or greater, see Exhibit 1260-2.

1260.03(1)(b) Design Stopping Sight Distance

Exhibit 1260-1 gives the design stopping sight distances for grades less than 3%, the minimum curve length for a 1% grade change to provide the stopping sight distance for a crest (K_c) and sag (K_s) vertical curve, and the minimum length of vertical curve for the design speed (VCL_m). For stopping sight distances when the grade is 3% or greater, see Exhibit 1260-2.

Design Speed (mph)	Design Stopping Sight Distance (ft)	K_c	K_s	VCL_m (ft)
25	155	12	26	75
30	200	19	37	90
35	250	29	49	105
40	305	44	64	120
45	360	61	79	135
50	425	84	96	150
55	495	114	115	165
60	570	151	136	180
65	645	193	157	195
70	730	247	181	210
75	820	312	206	225
80	910	384	231	240

Design Stopping Sight Distance
Exhibit 1260-1

1260.03(2) Effects of Grade

The grade of the highway has an effect on the stopping sight distance. The stopping distance is increased on downgrades and decreased on upgrades. Exhibit 1260-2 gives the stopping sight distances for grades of 3% and steeper. When evaluating sight distance with a changing grade, use the grade for which the longest sight distance is needed.

Design Speed (mph)	Stopping Sight Distance (ft)					
	Downgrade			Upgrade		
	-3%	-6%	-9%	3%	6%	9%
25	158	165	173	147	143	140
30	205	215	227	200	184	179
35	257	271	287	237	229	222
40	315	333	354	289	278	269
45	378	400	427	344	331	320
50	446	474	507	405	388	375
55	520	553	593	469	450	433
60	598	638	686	538	515	495
65	682	728	785	612	584	561
70	771	825	891	690	658	631
75	866	927	1,003	772	736	704
80	965	1,035	1,121	859	817	782

Design Stopping Sight Distance on Grades
Exhibit 1260-2

For stopping sight distances on grades between those listed, interpolate between the values given or use the equation in Exhibit 1260-3.

$$S = 1.47V(2.5) + \frac{V^2}{30\left[0.347826 \pm \left(\frac{G}{100}\right)\right]}$$

Where:
S = Stopping sight distance on grade (ft)
V = Design speed (mph)
G = Grade (%)

Stopping Sight Distance on Grades
Exhibit 1260-3


1260.03(3) Crest Vertical Curves

When evaluating an existing roadway, refer to 1260.03(7).


Use Exhibit 1260-4 or the equations in Exhibit 1260-5 to find the minimum crest vertical curve length to provide stopping sight distance when given the algebraic difference in grades. Exhibit 1260-4 does not show the sight distance greater than the length of curve equation.

When the sight distance is greater than the length of curve and the length of curve is critical, the $S>L$ equation given in Exhibit 1260-5 shall be used to find the minimum curve length.

When a new crest vertical curve is built or an existing one is rebuilt with grades less than 3%, provide design stopping sight distance from Exhibit 1260-1. For grades 3% or greater, provide stopping sight distance from 1260.03(2).



The minimum length can also be determined by multiplying the algebraic difference in grades by the K_C value from Exhibit 1260-1 $(L=K_C*A)$. Both the exhibit and the equation give approximately the same length of curve. Neither use the $S>L$ equation.



Stopping Sight Distance: Crest Vertical Curves
Exhibit 1260-4

When $S>L$

$$L = 2S - \frac{2158}{A} \qquad S = \frac{L + \left(\frac{2158}{A}\right)}{2}$$

When $S<L$

$$L = \frac{AS^2}{2158} \qquad S = \sqrt{\frac{2158L}{A}}$$

Where:

L = Length of vertical curve (ft)
S = Sight distance (ft)
A = Algebraic difference in grades (%)

Sight Distance: Crest Vertical Curve
Exhibit 1260-5

1260.03(4) Sag Vertical Curves


When evaluating an existing roadway, refer to 1260.03(7).

Sight distance is not restricted by sag vertical curves during the hours of daylight. Therefore, headlight sight distance is used for the sight distance design criteria at sag vertical curves. In some cases, a lesser length may be allowed. For guidance, see Chapter 1220.


Refer to Exhibit 1260-6 or the equations in Exhibit 1260-7 to find the minimum length for a sag vertical curve to provide the headlight stopping sight distance when given the algebraic difference in grades. The value for S is shown as the distance between the vehicle and the point where a 1-degree angle upward of the headlight beam intersects with the roadway.

The sight distance greater than the length of curve equation is not used in Exhibit 1260-6. When the sight distance is greater than the length of curve and the length of curve is critical, the $S>L$ equation given in Exhibit 1260-7 shall be used to find the minimum length of curve.

When a new sag vertical curve is built or an existing one is rebuilt with grades less than 3%, provide design stopping sight distance from Exhibit 1260-1. For grades 3% or greater, provide stopping sight distance from 1260.03(2).



The minimum length can also be determined by multiplying the algebraic difference in grades by the K_S value from Exhibit 1260-1 $(L=K_S*A)$. Both the exhibit and equation give approximately the same length of curve. Neither use the $S>L$ equation.



Stopping Sight Distance for Sag Vertical Curves
Exhibit 1260-6

When $S>L$

$$L = 2S - \frac{400 + 3.5S}{A} \qquad S = \frac{LA + 400}{2A - 3.5}$$

When $S<L$

$$L = \frac{AS^2}{400 + 3.5S} \qquad S = \frac{3.5L \pm \sqrt{(3.5L)^2 + 1600AL}}{2A}$$

Where:

L = Curve length (ft)
A = Algebraic grade difference (%)
S = Sight distance (ft)

Note:

Values for A less than 1.75 are within the 1-degree diverge of the headlight beam and therefore do not need to be evaluated for SSD on sag curves.

Sight Distance: Sag Vertical Curve
Exhibit 1260-7


1260.03(5) Horizontal Curves


When evaluating an existing roadway, see 1260.03(7).

Use Exhibit 1260-8 or the equation in Exhibit 1260-9 to check stopping sight distance where sightline obstructions are on the inside of a curve. A stopping sight distance sightline obstruction is any roadside object within the horizontal sightline offset (M) distance (such as median barrier, guardrail, bridges, walls, cut slopes, buildings or wooded areas), 2.0 feet or greater above the roadway surface at the centerline of the lane on the inside of the curve (h_0). Exhibit 1260-8 and the equation in Exhibit 1260-9 are for use when the length of curve is greater than the sight distance and the sight restriction is more than half the sight distance from the end of the curve. Where the length of curve is less than the stopping sight distance or the sight restriction is near either end of the curve, the desired sight distance may be available with a lesser M distance. When this occurs, the sight distance can be checked graphically.



A sightline obstruction is any roadside object within the horizontal sightline offset (M) distance, 2.0 feet or greater above the roadway surface at the centerline of the lane on the inside of the curve.





Horizontal Stopping Sight Distance
Exhibit 1260-8

When the road grade is less than 3%, provide design stopping sight distance from Exhibit 1260-1. When the grade is 3% or greater, provide stopping sight distance from 1260.03(2).

Roadside objects with a height (h_0) between 2.0 feet and 2.75 feet might not be a stopping sight distance sightline obstruction. Objects with an h_0 between 2.0 feet and 2.75 feet can be checked graphically to determine whether they are stopping sight distance sightline obstructions.

Where a sightline obstruction exists and site characteristics preclude design modifications to meet criteria, consult with the region Traffic Engineer and Assistant State Design Engineer for a determination of appropriate action.

$$M = R\left[1-\cos\left(\frac{28.65S}{R}\right)\right] \qquad S = \frac{R}{28.65}\left[\cos^{-1}\left(\frac{R-M}{R}\right)\right]$$

Where:

M = Horizontal sightline offset measured from the centerline of the inside lane of the curve to the sightline obstruction (ft)

R = Radius of the curve (ft)

S = Sight distance (ft)

Sight Distance: Horizontal Curves
Exhibit 1260-9


1260.03(6) Overlapping Horizontal and Vertical Curves

Vertical curves on a horizontal curve have an effect on which roadside objects are sightline obstructions. Crest vertical curves make roadside objects *more* likely to become sightline obstructions. Sag vertical curves make roadside objects *less* likely to be sightline obstructions.

Exhibit 1260-10 can be used to determine the sight distance for crest vertical curves on horizontal curves with:

- Sightline obstructions inside the M distance.
- Sightline obstruction height (h_0) of 2.0 feet or less.

For other locations, the sight distance can be checked graphically.



The following equation may be used to determine the sight distance for roadside sightline obstructions inside the horizontal sightline offset (*M*) distance (see Exhibit 1260-9) with a height of 2.0 feet or less above the centerline of the lane on the inside of the curve on overlapping horizontal and crest vertical curves.

$$S = \sqrt{\frac{100L\left[\sqrt{2(h_1 - h_0)} + \sqrt{2(h_2 - h_0)}\right]^2}{A}}$$

Where:

L = Length of vertical curve (ft)

S = Sight distance (ft)

A = Algebraic difference in grades (%)

h_1 = Eye height (3.5 ft)

h_2 = Object height (2.0 ft)

h_0 = Height of roadside sightline obstructions above the centerline of the inside curve lane (2.0 ft or less)

Note:

The above equation cannot be used for sightline obstruction height (h_0) more than 2.0 ft above the centerline of the lane on the inside of the curve. The available sight distance must be checked graphically for these sightline obstructions.

Sight Distance: Overlapping Horizontal and Crest Vertical Curves
Exhibit 1260-10

1260.03(7) Existing Stopping Sight Distance

Existing stopping sight distance values from Exhibit 1260-11 may be used at all horizontal and vertical curves where all of the following are met at the curve:

- There is no identified collision trend.
- The existing vertical and horizontal alignment is retained.
- The existing roadway pavement is not reconstructed.
- The roadway will not be widened, except for minor shoulder widening requiring no work past the bottom of the ditch.
- The sightline obstruction is existing.
- Roadside improvements to sight distance are within existing right of way.

Crest Vertical Curves – The minimum length of an existing crest vertical curve may be found using the equations in Exhibit 1260-5 or using the K_C values from Exhibit 1260-11.

Sag Vertical Curves – The minimum length of an existing sag vertical curve may be found using the equations in Exhibit 1260-7 or using the K_S values from Exhibit 1260-11. In some cases, when continuous illumination is provided, a lesser length may be allowed. For guidance, see Chapter 1220.

Design Speed (mph)	Existing Stopping Sight Distance (ft)	K_C	K_S
20	115	6	16
25	145	10	23
30	180	15	31
35	220	22	41
40	260	31	52
45	305	43	63
50	350	57	75
55	400	74	89
60	455	96	104
65	495	114	115
70	540	135	127
75	585	159	140
80	630	184	152

Existing Stopping Sight Distance
Exhibit 1260-11

1260.04 Passing Sight Distance (Eye height – 3.5 ft, Object height – 3.5 ft)

1260.04(1) Design Criteria

Minimum passing sight distance is the distance (on a two-lane highway) used for a driver to execute a normal passing maneuver based on design conditions and design speed.

The potential for passing maneuver conflicts is ultimately determined by the judgments of the driver and the conditions present at the time of the maneuver. Exhibit 1260-12 gives the passing sight distances for various design speeds.

Design Speed (mph)	Minimum Passing Sight Distance (ft)
20	400
25	450
30	500
35	550
40	600
45	700
50	800
55	900
60	1000
65	1100
70	1200
75	1300
80	1400

Passing Sight Distance
Exhibit 1260-12

On two-lane two-way highways, provide passing opportunities to meet traffic volume demands. This can be accomplished with roadway sections that provide passing sight distance or by adding passing lanes at locations that would provide the greatest benefit to passing (see Chapter 1270).


In the design stage, passing sight distance can be provided by adjusting the alignment either vertically or horizontally to increase passing opportunities.

These considerations also apply to multilane highways where staged construction includes a two-lane two-way operation as an initial stage. Whether auxiliary lanes are provided, however, depends on the time lag proposed between the initial stage and the final stage of construction.

1260.04(2) Passing Sight Distance Vertical Curves


Exhibit 1260-14 gives the length of crest vertical curve used to provide passing sight distance for two lane highways. The distance from Exhibit 1260-12 and the equations in Exhibit 1260-13 may also be used to determine the minimum length of vertical curve to meet the passing sight distance criteria.

Sag vertical curves are not a restriction to passing sight distance.



When $S>L$	
$L = 2S - \frac{2800}{A}$	$S = \frac{L}{2} + \frac{1400}{A}$
When $S<L$	
$L = \frac{AS^2}{2800}$	$S = \sqrt{\frac{2800L}{A}}$
Where:	
L = Length of vertical curve (ft)	
A = Algebraic grade difference (%)	
S = Sight distance (ft)	

Passing Sight Distance: Crest Vertical Curve Calculations
Exhibit 1260-13



Passing Sight Distance: Crest Vertical Curves
Exhibit 1260-14

1260.04(3) Passing Sight Distance Horizontal Curves

Passing sight distance can be restricted on the inside of a horizontal curve by sightline obstructions that are 3.5 feet or more above the roadway surface. Use the distance from Exhibit 1260-12 and the equation in Exhibit 1260-9 to determine whether the object is close enough to the roadway to be a restriction to passing sight distance. The equation assumes that the curve length is greater than the sight distance. Where the curve length is less than the sight distance, the desired sight distance may be available with a lesser sightline offset (*M*) distance.

1260.05 Decision Sight Distance (Eye height – 3.5 ft, Object height – 2.0 ft)

Decision sight distance values are greater than stopping sight distance values because they give the driver an additional margin for error and afford sufficient length to maneuver at the same or reduced speed rather than to just stop.

Consider decision sight distances (see Exhibit 1260-15) at locations where there is high likelihood for driver error in information reception, decision making, or control actions. If site characteristics and budget allow, locate these highway features where decision sight distance can be provided. If this is not practicable, use suitable traffic control devices and positive guidance to give advanced warning of the conditions.

Design Speed (mph)	Decision Sight Distance for Maneuvers (ft)				
	A	B	C	D	E
30	220	490	450	535	620
35	275	590	525	625	720
40	330	690	600	715	825
45	395	800	675	800	930
50	465	910	750	890	1030
55	535	1030	865	980	1135
60	610	1150	990	1125	1280
65	695	1275	1050	1220	1365
70	780	1410	1105	1275	1445
75	875	1545	1180	1365	1545
80	970	1685	1260	1455	1650

Decision Sight Distance
Exhibit 1260-15

The maneuvers in Exhibit 1260-15 are as follows:

A = Rural stop

B = Urban stop

C = Rural speed/path/direction change

D = Suburban speed/path/direction change

E = Urban speed/path/direction change

Use the equations in Exhibits 1260-5, 1260-7, and 1260-9 to determine the available decision sight distance for crest vertical curves, sag vertical curves, and horizontal curves.

1260.06 Documentation

It is recognized that some designs do not allow all criteria and guidelines to be followed as outlined in this chapter.

Refer to Chapter 300 for design documentation requirements.

Chapter 1270 Auxiliary Lanes

1201.01 General
1270.02 Climbing Lanes
1270.03 Passing Lanes
1270.04 Slow-Moving Vehicle Turnouts
1270.05 Shoulder Driving for Slow Vehicles
1270.06 Emergency Escape Ramps
1270.07 Chain-Up and Chain-Off Areas
1270.08 Documentation
1270.09 References

1270.01 General

Auxiliary lanes are used to comply with capacity demand; maintain lane balance; accommodate speed change, weaving, and maneuvering for entering and exiting traffic; and encourage carpools, vanpools, and the use of transit.

For signing and delineation of auxiliary lanes, see the *Standard Plans*, the *Traffic Manual*, and the MUTCD. Contact the region Traffic Engineer for guidance.

Although slow-vehicle turnouts, shoulder driving for slow vehicles, and chain-up areas are not auxiliary lanes, they are covered in this chapter because they perform a similar function.

For additional information, see the following chapters:

Chapter	Subject
1103	Design controls, including speed
1230	Geometric cross section components
1310	Turn lanes
1310	Speed change lanes at intersections
1360	Collector-distributor roads
1360	Weaving lanes
1410	High-occupancy vehicle lanes

1270.02 Climbing Lanes

1270.02(1) General

Climbing lanes (see Exhibit 1270-1) are normally associated with truck traffic, but they may also be considered in recreational or other areas that are subject to slow-moving traffic. Climbing lanes are designed independently for each direction of travel.

1270.02(2) Climbing Lane Warrants

Generally, climbing lanes are provided when two warrants—speed reduction and level of service—are met. Either warrant may be waived if, for example, slow-moving traffic is causing an identified collision trend or congestion that could be corrected by the addition of a climbing lane. However, under most conditions, climbing lanes are built when both warrants are met.

1270.02(2)(a) Warrant No. 1: Speed Reduction

Exhibit 1270-2a shows how the percent and length of grade affect vehicle speeds. The data is based on a typical commercial truck.

The maximum entrance speed, shown in the graphs, is 60 mph. This is the maximum value regardless of the posted speed of the highway. When the posted speed is above 60 mph, use 60 mph in place of the posted speed. Examine the profile at least ¼ mile preceding the grade to obtain a reasonable approach speed.

If a vertical curve makes up part of the length of grade, approximate the equivalent uniform grade length.

Whenever the gradient causes a 10 mph speed reduction below the posted speed limit for a typical truck for either two-lane or multilane highways, the speed reduction warrant is met (see Exhibit 1270-2b).

1270.02(2)(b) Warrant No. 2: Level of Service (LOS)

The level of service warrant for two-lane highways is met when the upgrade traffic volume exceeds 200 vehicles per hour and the upgrade truck volume exceeds 20 vehicles per hour. On multilane highways, a climbing lane is warranted when a capacity analysis shows the need for more lanes on an upgrade than on a downgrade carrying the same traffic volume.

Exhibit 1270-1 Climbing Lane Example



1270.02(3) Climbing Lane Design

When a climbing lane is justified, design it in accordance with Exhibit 1270-3. Provide signing and delineation to identify the presence of the auxiliary lane. Begin climbing lanes at the point where the speed reduction warrant is met and end them where the warrant ends for multilane highways and 300 feet beyond for two-lane highways. Consider extending the auxiliary lane over the crest to improve vehicle acceleration and sight distance.

Design climbing lane width equal to that of the adjoining through lane and at the same cross slope as the adjoining lanes. Whenever possible, maintain a shoulder width equal to the adjacent roadway segments (preserve shoulder width continuity). On two-way two-lane highways, the shoulder may be reduced to 4 feet. If the shoulder width is reduced to 4 feet document the reasoning for the decision in the design parameter sheets. If the shoulder width is reduced to less than 4 feet, a design analysis is required.

Exhibit 1270-2a Speed Reduction Warrant: Performance for Trucks






Exhibit 1270-2b Speed Reduction Warrant Example






Given:
A two-lane highway meeting the level of service warrant, with the above profile, and a 60 mph posted speed.

Determine:
Is the climbing lane warranted? If so, what is its length?

Solution:
1. Follow the 4% grade deceleration curve from a speed of 60 mph to a speed of 50 mph at 1,200 ft. The speed reduction warrant is met and a climbing lane is needed.
2. Continue on the 4% grade deceleration curve to 4,000 ft. Note that the speed at the end of the 4% grade is 35 mph.
3. Follow the 1% grade acceleration curve from a speed of 35 mph for 1,000 ft. Note that the speed at the end of the 1% grade is 41 mph.
4. Follow the -2% grade acceleration curve from a speed of 41 mph to a speed of 50 mph, ending the speed reduction warrant. Note that the distance is 700 ft.
5. The total auxiliary lane length is (4,000-1,200)+1,000+700+300=4,800 feet. 300 ft is added to the speed reduction warrant for a two-lane highway (see 1270.02(3) and Exhibit 1270-3).

Exhibit 1270-3 Auxiliary Climbing Lane



1270.03 Passing Lanes

1270.03(1) Passing Lane Benefits

A passing lane (see Exhibit 1270-4) is an auxiliary lane provided in one or both directions of travel on a two-lane highway to improve passing opportunities. They may be intermittent or continuous passing lanes in level or rolling terrain and short four-lane sections. The objectives of passing lanes are to:

- Improve overall traffic operations on two-lane highways by breaking up traffic platoons and reducing delays caused by inadequate passing opportunities over substantial lengths of highway.
- Increase average travel speed within the passing lane itself; the speed benefits of passing lanes continue downstream of the lane. Passing lanes typically reduce the percent time spent following within the passing lane itself. These "percent time spent following" benefits can continue for some distance downstream of the passing lane.
- Improve safety by providing assured passing opportunities without the need for the passing driver to use the opposing traffic lane. Safety evaluations have shown that passing lanes and short four-lane sections reduce collision rates and severity.

1270.03(2) Passing Lane Length

Design passing lanes long enough to provide a reduction in traffic platooning. To maximize the traffic operational efficiency of a passing lane in level or rolling terrain, its length can vary from 0.5 mile to 2.0 miles depending on the directional flow rate, as shown in Exhibit 1270-5. Passing lanes longer than 2 miles can cause the driver to lose the sense that the highway is a two-lane facility. However, these lengths may vary for other reasons such as addressing safety-related issues. Passing lanes longer than 2.0 miles or shorter than 0.5 miles in length may be used depending on the identified need or other operational considerations within the design. Lengths shown do not include passing lane tapers at the beginning or end of the passing lane.

Exhibit 1270-4 Passing Lane Example



Exhibit 1270-5 Length of Passing Lanes

Directional Flow Rate (pc/h)	Passing Lane Length (mi)
100	≤0.50
200	>0.50-0.75
400	>0.75-1.00
≥700	>1.00-2.00
Source: Transportation Research Board, Highway Capacity Manual, 2000	

For assistance in developing a passing lane length, see the following website for an example of a self-modeling spreadsheet. This spreadsheet develops passing lane lengths based primarily on vehicle speed differentials and is to be used in conjunction with traffic modeling efforts. Contact the Headquarters Design Office for assistance (www.wsdot.wa.gov/design/policy/default.htm).

1270.03(3) Passing Lane Location

A number of factors are considered when selecting an appropriate location for a passing lane, including the following:

- Locate passing lanes where decision sight distance (see Chapter 1260) at the lane decrease tapers can be provided.
- Provide stopping sight distance continuously along the roadway
- Avoid locating passing lanes near high-volume intersections, existing structures, railroad crossings, areas of dense development, and two-way left-turn lanes.
- Locate passing lanes where they appear logical to the driver.
- Carefully consider highway sections with low-speed curves (curves with superelevation less than required for the design speed) before installing a passing lane, since they may not be suitable for passing. For information on superelevation, see Chapter 1250.
- Avoid other physical constraints, such as bridges and culverts, if they restrict the provision of a continuous shoulder.
- Consider the number, type, and location of intersections and road approaches.
- Consider grades when choosing the side on which to install the passing lane. Uphill grades are preferred but not mandatory.
- Preference for passing is normally given to the traffic departing a developed area such as a small town.

1270.03(3)(a) Traffic Operational Considerations

When passing lanes are provided at an isolated location, their typical objective is to reduce delays at a specific bottleneck; for example, climbing lanes (see 1270.02). The location of the passing lane is dictated by the needs of the specific traffic operational problem encountered.

When passing lanes are provided to improve traffic operations over a length of road, there is flexibility in the choice of passing lane locations to maximize their operational effectiveness and minimize construction costs.

If delay problems on an upgrade are severe, the upgrade will usually be the preferred location for a passing lane.

Passing lanes at upgrades begin before speeds are reduced to unacceptable levels and, where possible, continue over the crest of the grade so that slower vehicles can regain some speed before merging.

1270.03(3)(b) Construction Cost Considerations

The cost of constructing a passing lane can vary substantially, depending on terrain, highway structures, shoulders, and adjacent development. Thus, the choice of a suitable location for a passing lane may be critical to its cost-effectiveness.

Generally, passing lanes in level and rolling terrain can be placed where they are least expensive to construct, avoiding locations with high cuts and fills and existing structures that would be expensive to widen.

1270.03(3)(c) Intersection-Related Considerations

Consider a corridor evaluation of potential passing lane locations for each direction, avoiding placement of passing lanes near intersections. Avoid or minimize turning movements on a road section where passing is encouraged.

Low-volume intersections and driveways are allowed within passing lanes, but not within the taper transition areas.

Where the presence of higher-volume intersections and driveways cannot be avoided, consider including provisions for turning vehicles, such as left-turn lanes.

Provide right- and left-turn lanes in passing lane sections where they would be provided on a conventional two-lane highway.

Left turns within the first 1,000 feet of a passing lane are undesirable. Strategies to address the turning movement could include left-turn lanes, right-in/right-out access, beginning the passing lane after the entrance, and so on.

1270.03(4) Passing Lane Design

Where a passing lane is planned, evaluate several possible configurations (see 1270.03(4)(a)) that are consistent with the corridor and fit within the constraints of the specific location.

The recommended minimum transition distance between passing lanes in opposing directions is 500 feet for “tail-to-tail” and 1,500 feet for “head-to-head” (see Exhibit 1270-7).

Some separation between lanes in opposite directions of travel is desirable; however, passing lanes can operate effectively with no separation. In either situation, address pavement markings and centerline rumble strips as appropriate.

It is desirable to channelize the beginning of a passing lane to move traffic to the right lane in order to promote prompt usage of the right lane by platoon leaders and maximize passing lane efficiency.

Widening symmetrically to maintain the roadway crown at the centerline is preferred, including in continuous passing lane configurations. However, the roadway crown may be placed in other locations as deemed appropriate. Considerations for crown locations might include: costs, constructability, right of way, environmentally sensitive roadsides, or other factors.

1270.03(4)(a) Alternative Configurations

Where a passing lane will be provided, evaluate the configurations shown in Exhibit 1270-6. In the exhibit, general passing lane configurations and their typical applications are described in the following:

a. Isolated Passing Lane – Exhibit 1270-6 (a)

- Two-lane highway with passing lane provided at a spot location to dissipate queues.
- For isolated grades, consider climbing lanes (see 1270.02).

b. Intermittent Passing Lanes, Separated – Exhibit 1270-6 (b)

- Often pairs are used at regular intervals along a two-lane highway.
- Frequency of passing lanes depends on desired level of service.
- The spacing between passing lanes and between pairs may be adjusted to fit the conditions along the route (see 1270.03(3)).

c. Continuous Passing Lanes – Exhibit 1270-6 (c)

- Use only when constraints do not allow for the use of other configurations. The use of this configuration requires concurrence from the region Traffic Engineer. (See Exhibit 1270-7 for additional information regarding buffer areas.)
- Appropriate for two-lane roadways carrying relatively high traffic volumes where nearly continuous passing lanes are needed to achieve the desired level of service.
- Particularly appropriate over an extended section of roadway where a wide pavement is already available.
- May be used as an interim stage for an ultimate four-lane highway.

d. Short Four-Lane Section – Exhibit 1270-6 (d)

- Sufficient length for adjoining passing lanes is not available.
- Particularly appropriate where the ultimate design for the highway is four lanes.

e. Intermittent Three-Lane Passing Lanes – Exhibit 1270-6 (e)

- Does not require the slow vehicle to change lanes to allow passing.
- Requires the widening to transition from one side of the existing roadway to the other.
- Eliminates the head-to-head tapers.

1270.03(4)(b) Geometric Aspects

Carefully design transitions between passing lanes in opposing directions. Intersections, bridges, other structures, two-way left-turn lanes, painted medians, or similar elements can be used to provide a buffer area between opposing passing lanes. The length of the buffer area between adjoining passing lanes depends on the configuration (see Exhibit 1270-7).

Exhibit 1270-6 illustrates five passing lane design configurations. Part (c) illustrates a continuous three-lane section with alternating passing lanes. Consider a four-lane cross section when volume demand exceeds the capacity of a continuous three-lane roadway.


Exhibit 1270-8 illustrates taper rates, cross slopes, and section lengths for three and four-lane passing sections. Where practicable provide shoulder width in a passing lane section equal to the shoulder width on the adjacent segments of a two-lane highway. However, the shoulder may be reduced to 4 feet. If the shoulder width is reduced to 4 feet, document the reason for the decision on the design parameter sheets. If the shoulder width is reduced to less than 4 feet, a design analysis is required. See Chapter 1600 for shoulder rumble strip criteria and considerations.

Where practicable, design the passing lane width the same as the lane width on the adjacent segments of the two-lane highway.


Provide a 25:1 or flatter taper rate to increase the width for a passing lane. When all traffic is directed to the right lane at the beginning of the passing lane, provide a taper rate of the posted speed:1. Provide a posted speed:1 taper rate for the merging taper at the end of a passing lane. (Refer to the Lane Transitions section in Chapter 1210 for additional information on taper rates.) Consider a wide shoulder at the lane drop taper to provide a recovery area for drivers who encounter a merging conflict.

Provide signing and delineation to identify the presence of an auxiliary passing lane. Refer to the *Standard Plans*, the *Traffic Manual*, and the MUTCD for passing lane signing and marking guidance.


Exhibit 1270-6 Passing Lane Configurations




(a) Isolated Passing Lane




(b) Intermittent Passing Lane



(c) Continuous Three-Lane Section



(d) Short Four-Lane Section



(e) Intermittent Three-Lane Passing Lanes

Note:

[1] See Exhibit 1270-7 for buffer design.

Exhibit 1270-7 Buffer Between Opposing Passing Lanes





Exhibit 1270-8 Auxiliary Passing Lane



Notes:

[1] Provide a posted speed:1 taper when all traffic is directed to the right lane at the beginning of the passing lane.

[2] Where practicable provide the same lane and shoulder widths in the passing section as on adjacent segments. See 1270.03(4)(b).

1270.04 Slow-Moving Vehicle Turnouts

1270.04(1) General

RCW 46.61.427 states:

> *On a two-lane highway where passing is unsafe … a slow-moving vehicle, behind which five or more vehicles are formed in a line, shall turn off the roadway wherever sufficient area for a safe turn-out exists, in order to permit the vehicles following to proceed…*

A slow-moving vehicle turnout is not an auxiliary lane. Its purpose is to provide sufficient room for a slow-moving vehicle to pull out of through traffic and stop if necessary, allow vehicles to pass, and then return to the through lane. Generally, a slow-moving vehicle turnout is provided on existing roadways where passing opportunities are limited, where slow-moving vehicles such as trucks and recreational vehicles are predominant, and where the cost to provide a full auxiliary lane would be prohibitive.

1270.04(2) Design

Base the design of a slow-moving vehicle turnout primarily on sound engineering judgment. Designs may vary from one location to another. Provide a length between 100 and 1,320 feet, excluding tapers. Select a width adequate for the vehicle type expected to use the turn-out, between 8 to 12 feet in width. Surface the turnouts with a stable, unyielding material (such as BST or HMA) with adequate structural strength to support the heavier traffic.

To improve the ability of a vehicle to safely reenter through traffic, locate slow-moving vehicle turnouts where adequate sight distance is available. The minimum design range for slow-vehicle turnouts may be where at least design stopping sight distance is available. See Chapter 1260.

Sign slow-moving vehicle turnouts to identify their presence. For guidance, see the Standard Plans, the Traffic Manual, and the MUTCD.

1270.05 Shoulder Driving for Slow Vehicles

1270.05(1) General

Use of a shoulder driving section is an alternative means to meet the performance objectives provided by climbing or passing lanes.

Review the following when considering a shoulder driving section:

- Horizontal and vertical alignment
- Character of traffic
- Presence of bicycles
- Road approaches and intersections
- Clear zone (see Chapter 1600)

1270.05(2) Design

When designing a shoulder for shoulder driving, locate where full design stopping sight distance (speed/path/direction decision sight distance is desirable) and a minimum length of 600 feet are available. Where practicable, avoid sharp horizontal curves. When barriers or other roadside objects are present, the minimum width is 12 feet. The shoulder width depends on the vehicles that will be using the shoulder. Where trucks will be the primary vehicle using the shoulder, use a 12-foot width; when passenger cars are the primary vehicle, a 10-foot width may be used.

Shoulder driving and bicycles are not compatible. When the route has been identified as a local, state, or regional significant bike route, shoulder driving for slow vehicles is undesirable. Reconstruct the shoulders to provide adequate structural strength for the anticipated traffic. Select locations where the side slope meets the criteria of Chapter 1239. When providing a transition at the end of a shoulder driving section, use a 50:1 taper.

Signing for shoulder driving is required (see the Standard Plans, the Traffic Manual, and the MUTCD). Install guideposts when shoulder driving is to be permitted at night.

1270.06 Emergency Escape Ramps

1270.06(1) General

Consider an emergency escape ramp (see Exhibit 1270-9) whenever a long, steep downgrade is encountered. In this situation, the possibility exists of a truck losing its brakes and going out of control at a high speed. Consult local maintenance personnel and check crash data to determine whether or not an escape ramp is justified.

Exhibit 1270-9 Emergency Escape Ramp Example



1270.06(2) Design

1270.06(2)(a) Types

Escape ramps include the following types:

- Gravity escape ramps are ascending grade ramps paralleling the traveled way. They are commonly built on old roadways. Their long length and steep grade can present the driver with control problems, not only in stopping, but with rollback after stopping. Gravity escape ramps are the least desirable design.
- Sand pile escape ramps are piles of loose, dry sand dumped at the ramp site, usually not more than 400 feet in length. The deceleration is usually high and the sand can be affected by weather conditions; therefore, they are less desirable than arrester beds. However, where space is limited, they may be suitable.
- Arrester beds are parallel ramps filled with smooth, free-draining gravel. They stop the out-of-control vehicle by increasing the rolling resistance and are the most desirable design. Arrester beds are commonly built on an upgrade to add the benefit of gravity to the rolling resistance. However, successful arrester beds have been built on a level or descending grade.
- The Dragnet Vehicle Arresting Barrier consists of chain link or fiber net that is attached to energy-absorbing units. (See Chapter 1610 for additional information.)

1270.06(2)(b) Locations

The location of an escape ramp depends on terrain, length of grade, sight distance, and roadway geometrics. Desirable locations include before a critical curve, near the bottom of a grade, or before a stop. It is desirable that the ramp leave the roadway on a tangent at least 3 miles from the beginning of the downgrade.

1270.06(2)(c) Lengths

The length of an escape ramp depends on speed, grade, and type of design used. The minimum length is 200 feet. Calculate the stopping length using the equation in Exhibit 1270-10.

Exhibit 1270-10 Emergency Escape Ramp Length

$$L = \frac{V^2}{0.3(R \pm G)}$$

Where:

L = Stopping distance (ft)
V = Entering speed (mph)
R = Rolling resistance (see Exhibit 1270-11)
G = Grade of the escape ramp (%)

Speeds of out-of-control trucks rarely exceed 90 mph; therefore, the desirable entering speed is 90 mph. Other entry speeds may be used when justification and the method used to determine the speed are documented.

Exhibit 1270-11 Rolling Resistance (R)

Material	*R*
Roadway	1
Loose crushed aggregate	5
Loose non-crushed gravel	10
Sand	15
Pea gravel	25

1270.06(2)(d) Widths

The width of each escape ramp depends on the needs of the individual situation. It is desirable for the ramp to be wide enough to accommodate more than one vehicle. The desirable width of an escape ramp to accommodate two out-of-control vehicles is 40 feet and the minimum width is 26 feet.


The following items are additional considerations in the design of emergency escape ramps:

- If possible, at or near the summit, provide a pull-off brake check area. Also, include in this area informative signing about the upcoming escape ramp.
- Free-draining, smooth, non-crushed gravel is desirable for an arrester bed. To assist in smooth deceleration of the vehicle, taper the depth of the bed from 3 inches at the entry to a full depth of 18 to 30 inches in not less than 100 feet.
- Mark and sign in advance of the ramp. Discourage normal traffic from using or parking in the ramp. Sign escape ramps in accordance with the guidance contained in the MUTCD for runaway truck ramps.
- Provide drainage adequate to prevent the bed from freezing or compacting.
- Consider including an impact attenuator at the end of the ramp if space is limited.
- A surfaced service road adjacent to the arrester bed is needed for wreckers and maintenance vehicles to remove vehicles and make repairs to the arrester bed. Anchors are desirable at 300-foot intervals to secure the wrecker when removing vehicles from the bed.

Typical examples of arrester beds are shown in Exhibits 1270-9 and 1270-12.

Include justification, all calculations, and any other design considerations in the emergency escape ramp documentation.

Exhibit 1270-12 Typical Emergency Escape Ramp



1270.07 Chain-Up and Chain-Off Areas


Provide chain-up areas to allow chains to be put on vehicles out of the through lanes at locations where traffic enters chain enforcement areas. Provide chain-off areas to remove chains out of the through lanes for traffic leaving chain enforcement areas.

Chain-up or chain-off areas are widened shoulders, designed as shown in Exhibit 1270-13. Locate chain-up and chain-off areas where the grade is 6% or less and desirably on a tangent section.

Consider illumination for chain-up and chain-off areas on multilane highways. When deciding whether or not to install illumination, consider traffic volumes during the hours of darkness and the availability of power.

The wide shoulders at chain-up and chain-off areas may encourage parking. When parking is undesirable, consider parking restrictions.

Exhibit 1270-13 Chain-Up/Chain-Off Area



Notes:

[1] Where traffic volumes are low and trucks are not a concern, the width may be reduced to 10 ft min, with 15 ft desirable.

[2] 2% desirable. (See Chapter 1250 for traveled way cross slope.)

1270.08 Documentation

Refer to Chapter 300 for design documentation requirements.

1270.09 References

1270.09(1) Federal/State Laws and Codes

Revised Code of Washington (RCW) 46.61, Rules of the road

1270.09(2) Design Guidance

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)

Standard Plans for Road, Bridge, and Municipal Construction (*Standard Plans*), M 21-01, WSDOT

Traffic Manual, M 51 02, WSDOT

1270.09(3) Supporting Information

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO, current edition

Emergency Escape Ramps for Runaway Heavy Vehicles, FHWA-T5-79-201, March 1978

Highway Capacity Manual, latest edition, Transportation Research Board, National Research Council

Truck Escape Ramps, NCHRP Synthesis 178, Transportation Research Board

Chapter 1300 Intersection Control Type

1300.01 General
1300.02 Intersection Control Objectives
1300.03 Common Types of Intersection Control
1300.04 Modal Considerations
1300.05 Procedures
1300.06 Documentation
1300.07 References

1300.01 General

It is WSDOT practice to analyze potential intersection solutions at all intersection improvement locations in accordance with *E 1082 – Business Practices for Moving Washington* and E 1090 – *Moving Washington Forward: Practical Solutions*. The objective is to provide the optimum solution within available resources, with an emphasis on low-cost investments. The analysis can be done for individual intersections, or on a corridor or network basis. This chapter provides guidance on preliminary intersection analysis and selection of control type. Intersection design is completed using Chapter 1310 for the geometrics of intersections, Chapter 1320 for roundabouts, and Chapter 1330 for traffic signals. Use the aforementioned chapters in conjunction with chapters 1106, 1230 series, 1430, 1510, and 1520 to assist with dimensioning design elements.

Consider design users and the balance between modes, safety and mobility performance considerations, context-sensitive/sustainable design, and economics when selecting and evaluating alternatives to meet the needs of the project.

Identification of intersection projects can come from a variety of programs and sources, including those funded by local agencies and developers. The intent of this chapter is that the ICA procedures apply to all types of intersection modifications on the state highway system. Potential safety project locations are identified through the safety priority programming process. Other programs may identify intersection needs through the priority array programming process, but the influence of the type of intersection control with respect to specific performance category needs may not be fully understood until contributing factors analysis is completed (see Chapter 1101).

Complete an Intersection Control Analysis (ICA) as early in the project development process as practicable, taking into account the level of community engagement that may need to occur prior to approval. The ICA (see 1300.05 for procedures) should be initiated no later than the scoping phase. ***Scale the ICA according to the size and complexity of the project***; for example, evaluation of adding a turn lane to an existing intersection control may take less effort than evaluating new intersection control. Consult the region or HQ Traffic offices for assistance with the level of effort required.

It is WSDOT policy to focus on lower cost solutions with the intent to optimize return on investment. Only when all at-grade intersection alternatives are ruled out, including turn restrictions and complete intersection removal, should other more-costly measures be considered, such as grade-separation. Ramp terminal intersections are subject to the analysis requirements of this chapter. See Chapters 1360 and 550 for additional information.

For additional information, see the following chapters:

Chapter	Subject
320	Traffic analysis
321	Sustainable Safety Analysis
530	Limited access control
540	Managed access control
550	Interchange Justification Report
1100	Practical Design
1101	Need Identification
1103	Design Controls
1106	Design Element Dimensioning
1230	Geometric Cross Section Basics; and other 1230 series chapters
1310	Intersections
1320	Roundabouts
1330	Traffic signals
1340	Road Approaches
1360	Interchanges
1510	Pedestrian facilities
1515	Shared-use paths
1520	Bicycle facilities

1300.02 Intersection Control Objectives

Intersections are an important part of highway design. Intersection control choice requires consideration of all potential users of the facility, including drivers of motorcycles, passenger cars, heavy vehicles of different classifications, public transit, and bicyclists and pedestrians.

Design users have varying skills and abilities. Younger and older drivers in particular are subject to a variety of behavioral or human factors that can influence elements of their driving ability. See NCHRP Report 600 – Human Factors Guidelines for Road Systems: Second Edition for additional information (http://www.trb.org/Main/Blurbs/167909.aspx). Bicyclists, from recreational to commuters, also have a variety of skill sets that can influence the effectiveness of bike facilities and intersection operational design (see Chapter 1520 for additional information). Meeting the needs of one user group can directly influence the service that other groups experience. The selection process evaluates these competing needs and results in an optimal balance of tradeoffs for all design users, recognizing the context and priorities of the location.

The intent of an ICA is not to design an intersection, but to evaluate the compatibility of different intersection control types with respect to context, modal priority, intersection design vehicle and the identified balance of performance needs. Four basic intersection design considerations are shown in Exhibit 1300-1 and can affect the intersection control types depending on the situation.

The objectives of the ICA are to:

- Provide a consistent framework to determine the most compatible intersection control type for the location, context, economics, and balance of performance needs.

- Evaluate the operational and safety performance for various appropriate and feasible intersection control types under consideration.
- Evaluate the modal performance considerations between different intersection control types with respect to the identified modal priority and intersection design vehicle (see Chapter 1103). Identify the potential modal treatments that augment the control types.
- Consider the intersection operations and the relationship with adjacent intersections and other access points.
- Evaluate the intersection control types for potential sustainability, cost-effectiveness, and expected maintenance and operations life cycle needs.
- Establish that a roundabout is the preferred intersection control type. When a roundabout is not selected, provide justification to support alternative decisions.
- Consider emerging alternative intersection designs such as displaced left-turn (DLT) and restricted crossing u-turn intersections (RCUT) where appropriate.
- Select the most cost-effective intersection control type for the project based on overall need and context.

Exhibit 1300-1: Intersection Design Considerations

Human Factors	
• Driving habits • Driver workload • Driver expectancy • Driver error • Driver distractions • Perception-reaction time	• Conformance to natural paths of movement • Pedestrian use and habits • Bicycle traffic use and habits • Visual recognition of roadway cues • Compatibility with context characteristics • Demand for alternative mode choices
Traffic Considerations	
• Design users, modal priority, and intersection design vehicle • Design and actual capacities • Design-hour turning movements • Variety of movements (diverging/merging/weaving/crossing)	• Vehicle size and operating characteristics • Vehicle speeds • Transit involvement • Crash Experience • Bicycle movements • Pedestrian movements
Physical Elements	
• Character and use of abutting property • Vertical alignments at the intersection • Sight distance • Angle of the intersection • Conflict areas • Speed-change lanes • Managed lanes (HOV, HOT, shoulder) • Accessible facilities • Parking zones • Geometric design features	• Traffic control devices • Illumination • Roadside design features • Environmental factors • Crosswalks • Transit facilities • Driveways • Streetside design features • Adjacent at-grade rail crossing • Access management treatments including turn restrictions
Economic Factors	
• Cost of improvements, annual maintenance, operations and life cycle costs, and salvage value • Effects of controlling access and right of way on abutting properties where channelization restricts or prohibits vehicular movements • Energy consumption and emissions	

1300.03 Common Types of Intersection Control

1300.03(1) Uncontrolled Intersections



- Uncontrolled intersections do not have signing, and the normal right of way rule (RCW 46.61.180) applies.
- This intersection type is typically found on local roads and streets where the volumes of the intersecting roadways are low and roughly equal, speeds are low, and there is little to no crash history.
- Uncontrolled intersections are not recommended for state routes.

1300.03(2) Yield Control



- Intersections with yield control assign right of way without requiring a stop.
- Mostly used at rural low-volume ramps and wye (Y) intersections.
- Yield control is generally not recommended in urban locations or where pedestrians are expected.

1300.03(3) Two-Way Stop Control

- Intersections with two-way stop control are a common, lower cost control, which require the traffic on the minor roadway to stop and yield to mainline traffic before entering the major roadway.
- Along certain corridors, especially where u-turn opportunities exist, consider limiting access at two-way stops to “right-in, right-out only.”

1300.03(4) Multi-Way Stop Control



- Multi-way stop control normally requires all traffic to stop before entering the intersection.
- Fewer fatal and injury crashes than two-way stop control.
- Multi-way stop control is suited for lower speed facilities with approximately equal volumes on all legs and total entering volumes not exceeding 1,400 vehicles during the peak hour.
- Increased traffic delays, fuel consumption, and air pollution.
- Multi-way stop control is not recommended on multilane state routes or at intersections with unbalanced directional traffic flows because of the delays and queues introduced on the major-volume legs of the intersection.

1300.03(5) Roundabouts

Roundabouts are often circular (or near-circular) at-grade intersections, where traffic on the approaches yield to traffic within the circulating roadway. Roundabouts are an effective intersection type that may offer the following:



- Reduced fatal and injury crashes compared with other at-grade intersection types.
- Fewer conflict points.
- Lower potential for wrong-way driving.
- Reduced traffic delays.
- Traffic-calming and lower speeds.
- More capacity than a two-way or multi-way stop.
- Quickly serves pedestrians needing to cross the intersection and shortens crossing distance for pedestrians by allowing for crossing in stages where needed. Reduces vehicular approach speeds that in turn reduces injury risk to pedestrians.
- Ability to serve high turning volumes with minimal number of approach lanes.
- Improved operations where space for queuing is limited.
- At ramp terminals where left-turn volumes are high, improved capacity without affecting the structure.
- Facilitation of u-turn movements and can be appropriate when combined with access management along a corridor.
- Aesthetic treatments and gateways to communities.
- Roundabouts are scalable and site-specific solutions, with flexibility to fit funding and a variety of site constraints. See Chapter 1320 for more information on roundabout types and design.

1300.03(6) Traffic Control Signals

- Signalized intersections may offer the following:
- Increased capacity of the intersection.
- Allow for improved progression within a coordinated system along a corridor or a grid.
- Can be used to interrupt heavy traffic at intervals to permit other traffic, vehicular or pedestrian, to complete their movement or enter the intersection.
- Can be preempted to provide priority service to railroad, emergency responders, transit and approaches where advance queue loops are used.

However, signalized intersections:

- Require continual maintenance and engineering for optimal operations.

- Cannot adequately balance large traffic flows with pedestrian demands.
- Can be susceptible to power outages and detection failures.

Indiscriminate use of traffic signals can adversely affect the safety performance and operational efficiency of vehicle, bicycle, and pedestrian traffic. Therefore, and as required by the MUTCD, a traffic signal should be considered for installation only after if it is determined to meet specific "warrants" and an engineering study shows that the installation would improve safety and/or operations. Satisfying a signal warrant does not mandate the installation of a traffic signal nor by itself meet the requirements of 1300.05; but failing to satisfy at least one warrant shall remove the signal from consideration.

Not all crashes are correctable with the installation of a traffic signal. Traffic signals may decrease the potential for crashes of one type and increase the potential for another type. For instance, rear-end crashes more frequently occur with signals because of stopping and starting of vehicles. At operating speeds above 40 mph, the severity of these rear-end crashes tend to be higher. This requires careful consideration of the location characteristics, traffic flow, and crash history.

State statutes (RCW 46.61.085) require WSDOT approval for the design and location of all conventional traffic signals and for some types of beacons located on city streets forming parts of state highways. The Traffic Signal Permit (DOT Form 242-014 EF) is the formal record of the department's approval of the installation and type of signal. For traffic signal permit guidance, see Chapter 1330.

1300.03(7) Alternative Intersections

Alternative intersections work mainly by rerouting U and left turns, and/or separating movements. Alternative intersections may have different terminology in different areas, but the most common types include:

- Median u-turn (MUT)
- Jug handle
- Bowtie
- Restricted crossing u-turn (RCUT)
- Displaced left-turn intersection (DLT)
- Continuous green tee
- Split intersection
- Quadrant roadway intersection
- Single quadrant interchange
- Echelon
- Center turn overpass

As alternative intersections may be relatively new to Washington State and its users, more education and community engagement will be necessary to ensure project success. However, extensive experience shows that many of these intersection types can provide better operational and safety performance, often at much less cost than traditional strategies.

Three types of alternative intersections are highlighted in the subsections below: median u-turn (MUT), restricted crossing u-turn (RCUT), and displaced left-turn (DLT) intersections. For more information about these and other intersection design solutions, see the Federal Highway Administration (FHWA) Alternative Intersection Design web page:
http://safety.fhwa.dot.gov/intersection/alter_design/


1300.03(7)(a) Median U-Turn

The median u-turn (MUT) intersection treatment relocates left turn movements downstream from the intersection resulting in lower delays, higher throughput, and reduction in the number and severity of crashes. Left-turning drivers proceed straight through the at-grade intersection, and then execute a u-turn at some distance downstream at a new or existing median opening. The main intersection is typically signalized and can be highly efficient needing only two signal phases. By removing the left turns at the main intersection, the MUT design results in a significant reduction in rear-end, angle, and sideswipe crashes; while reducing the number of conflict points from 32 to 16 when compared to a conventional signalized intersection. The MUT can also have advantages for pedestrians with fewer conflict points and a lower delay. However, the intersection design may reduce bicyclist mobility as they are expected to use the pedestrian crossings in order to perform left turns at the intersection. The MUT intersection design is more likely to be suitable for consideration in situations where:

- The intersection is over capacity.
- There are heavy through volumes and low to moderate left turn volumes.
- The intersection is within a higher-speed, median-divided corridor.
- There are safety concerns at an existing signalized intersection or corridor.

Refer to FHWA's *Median U-Turn Intersection Informational Guide* for geometric design considerations and recommendations. (See Chapter 1310 for geometrics when designing the u-turn movement for the MUT intersection.)

Exhibit 1300-2 Median U-Turn Intersection Example



MUT Intersection from FHWA's Median U-Turn Intersection Informational Guide


1300.03(7)(b) Restricted Crossing U-Turn Intersection

Restricted crossing u-turn (RCUT) intersections, also known as superstreets or J-turns, have similarities with the MUT in that the minor road through and left-turning movements are redirected (see Exhibit 1300-2). This intersection type results in lower delays, improved progression, and a potential reduction in the total number of crashes and fatal and injury crashes.

Drivers on the minor road approaches must turn right onto the major road and then perform a u-turn maneuver at a median opening downstream. However, the major road left turn movements are still allowed at the main intersection. RCUT intersections may or may not warrant signalization due to traffic volumes, and those with signalization require fewer signal phases and shorter cycle lengths than a traditional signalized intersection. The RCUT intersection is more likely suitable for consideration in situations where:

- The intersection is over capacity.
- There is a need to improve travel time and progression for the major road.
- There are crashes at the intersection related to turning movements that can reduced by a RCUT.
- The intersection is within a higher-speed, multilane corridor.
- There are low through and left turn volumes on the minor road.
- Pedestrian volumes are low.
- The major roadway contains sufficient median width, or total right of way width, to support the u-turn movements.

Exhibit 1300-3 Restricted Crossing U-Turn Intersection Example with Stop-control



Example of RCUT Intersection with stop-control from FHWA's Restricted Crossing U-Turn Intersection Informational Guide


The RCUT intersection may be a potential alternative compared to a grade-separated interchange, at locations meeting grade-separated considerations identified in 530.04(3). Refer to FHWA's *Restricted Crossing U-Turn Intersection Informational Guide* for geometric design considerations and recommendations. (See Chapter 1310 for geometrics when designing the u-turn movement for the RCUT.)

1300.03(7)(c) Displaced Left-Turn Intersection

The displaced left-turn (DLT) intersection, also known as a continuous flow intersection, works mainly by relocating one or more left turn movements to the other side of the opposing traffic via an interconnected signalized crossover. This essentially causes the traffic signal system to be more efficient by eliminating the left turn phase at the main intersection allowing for more green time to be allocated to other movements. The DLT can reduce delays by up to 40%, but often can be delivered for just slightly more cost than a typical signalized intersection. Compared with a conventional intersection, the DLT can be more challenging for pedestrians due to longer crossing distances and counter-intuitive left turn vehicular movements. However, the DLT typically has shorter cycle lengths and potentially shorter delays. The DLT intersection design is best applied in situations where:

- There are high left-turn and through volumes.
- Intersection is over capacity.
- There are excessive delays and queuing, especially when left turn queues extend past the available storage bays.
- Pedestrian volumes are low.
- Sufficient right-of-way exists on the leg(s) that need to be widened to accommodate the new lanes.
- Context is urban/suburban.

Exhibit 1300-4 Displaced Left Turn Intersection Example



Example of DLT Intersection from FHWA's Displaced Left Turn Intersection Informational Guide

1300.04 Modal Considerations

When designing a multimodal intersection, consideration needs to be given to all design users at the intersection, the intersection design vehicle and selected modal priority (see Chapter 1103).

It is not appropriate to design for specific modal treatments on the outset of evaluating intersection control types. However, modally oriented intersection treatments may be necessary to enhance specific modal baseline or contextual performance needs (see Chapter 1101), and may influence the control type selection. Include a discussion of the potential modally oriented treatments relevant to the control types being analyzed and modal performance needs. Evaluate the potential effect of modal specific treatments on all design users relevant for the control types evaluated in the ICA.

1300.04(1) Pedestrian Considerations

Consider the intersection type and how it accommodates pedestrians. With each intersection type, there may be specific elements and/or treatments applicable for pedestrians (see, for example chapters 1231 and 1510) to meet modal performance needs identified (see Chapter 1101).

For example, a signalized intersection with a long cycle length, high speeds, or frequent permitted turning movements is generally not appropriate for areas with moderate to high pedestrian demand. However, a responsive signal in an urban downtown core with low speeds is typically well respected with high compliance and short delays.

Often, single-lane roundabouts can be accommodating to pedestrians with high compliance rates, short delays, and minimal disruption to vehicular traffic flow due to short crossing distances and two-stage crossings.

Additional information on emerging practices to address pedestrian performance needs for different intersection control types can be found at the Pedestrian and Bicycle Information Center (http://www.pedbikeinfo.org/)

For signalized intersections, sidewalk and ramp designs have additional requirements to accommodate the pedestrian features of the traffic signal system (see Chapter 1330).

1300.04(2) Bicycle Considerations

For consideration of bicycle needs at intersections and treatments that may have an operational effect on other design users, see chapters 1515 and 1520. Additional emerging practice information to address bicycle performance needs for different intersection control types can be found at the Pedestrian and Bicycle Information Center (http://www.pedbikeinfo.org/) and the NACTO Urban Bikeway Design Guide (https://nacto.org/publication/urban-bikeway-design-guide/).

1300.04(3) Transit Considerations

When transit vehicles are identified as a modal priority, consider treatments to meet the performance needs of the specific transit vehicle types and their effect on the performance of other design users (see Chapter 1103). Transit oriented treatments can vary significantly depending on the proximity of stop locations with respect to the intersection location and origin of the transit movement (see Chapter 1430 for bus stop placement guidelines), and the type of

transit vehicle (such as a fixed guideway vehicle). Discuss treatment options and any operating restrictions the transit provider may have regarding different intersection control types.

1300.04(4) Operational Considerations

Traditional delay analysis focuses on determining the peak-hour letter-graded Level of Service (LOS) of an individual intersection. However, as this approach often does not account for multimodal users and as roughly 80% of the daily traffic volumes occur outside of the peak hours, a more encompassing review of the intersection is needed to provide sufficient multimodal capacity and safety performance at all hours of the day.

Intersection control can have an influence on road user behavior and modal operations, not just at the intersection itself, but also along the corridor or surrounding network, even when the intersection has an acceptable LOS. Delay affects route and mode choice and sometimes whether a user will decide to complete the trip. A user's willingness to accept delay depends on many factors including the user's knowledge of the transportation network, anticipated traffic conditions, and alternative options. The increasing presence of in-vehicle guidance systems and real-time traffic apps further aids the user in selecting the route with shortest travel times. Also, some alternatives that may improve mobility for one mode, such as the addition of turn lanes, may result in a performance degradation or even discourage trips for pedestrians or other modes. Thus, it is important to consider the effects of intersection control on the surrounding network and for all potential users. The following are some factors when selecting and evaluating alternatives:

- Access management strategies can be effective in promoting efficient travel patterns and rerouting traffic to other existing intersections. Check with the WSDOT region Planning Office for future land use plans or comprehensive plans to provide for future growth accommodation.
- Consider the volume to capacity (V/C) ratio, the delay, and the queue length of each approach. Some scenarios may require additional sensitivity analysis to determine the impacts of small changes in volumes.
- Examine the effects of existing conditions. Consider progression through nearby intersections (corridor and network analysis) and known risky or illegal driving maneuvers.
- Consider the possibility that traffic from other intersections with lower LOS will divert to the new/revised intersection.

1300.05 Procedures

For new intersections, determine and document intersection control according to the applicable procedures in this chapter.

For intersection improvement projects involving pavement construction and/or reconstruction, or preservation projects such as signal replacement/rehabilitation, evaluate intersection control in accordance with this chapter unless there is documentation that this analysis has already been completed and is referenced in the Project Summary.

Control for existing intersections that are unaffected by the project (per the contributing factors analysis) or are receiving minor revisions such as signal timing changes or rechannelization of existing pavement are not subject to further evaluation.

1300.05(1) Intersection Control Analysis (ICA)

The Intersection Control Analysis is a 5-step process meant to screen and evaluate alternatives to determine the best possible intersection type and design. Due to the safety and operational performance record, ***a roundabout is the preferred intersection control type and is required to be evaluated in Step 1. If a roundabout is selected and no other feasible alternatives remain after Step 2, contact the Region Traffic Engineer to determine if further analysis is required.***

For each alternative, provide a brief description of the assumed layout. Include the number of lanes on major and minor approaches and any measures necessary to accommodate multi-modal users. For a roundabout, document the assumed inscribed circle diameter. For a signal, document the assumed cycle length and phasing strategy used for the analysis.

Step 1: Background and Project Needs – Describe the existing conditions. Include physical characteristics of the site, posted speed, AADT, channelization and control features, multimodal facilities, context, and modal priority.

Document the project needs and which performance measures will be used for analysis and comparison of project alternatives in Step 3. Identify all project alternatives under consideration. For each alternative, determine if it is expected to meet the basic needs of the project. If an alternative does not pass this initial screening, remove it from consideration. All remaining alternatives are to proceed to Step 2.

Step 2: Feasibility – Develop the alternatives at a sketch level to determine the footprint required to achieve performance measures. Consider right-of-way, environmental, cost, context-sensitive/sustainable design, and geometrics/physical constraints for each remaining alternative. If an alternative is not practicable from any of these perspectives, remove it from consideration. All remaining alternatives are to proceed to Step 3. **If a roundabout is the only remaining viable alternative at this stage, contact the Region Traffic Engineer to determine if further analysis in Steps 3 and 4 is required.**

- Determine the **right of way** requirements and feasibility. Discuss the right of way requirements and the feasibility of acquiring that right of way in the analysis. Include sketches or plan sheets with sufficient detail to identify topography, existing utilities, environmental constraints, drainage, buildings, and other fixed objects. An economic evaluation will be useful if additional right of way is needed. Include the right of way costs in the benefit/cost analysis (Step 4).
- Identify known **environmental** concerns that could influence control type selection. At this stage, are there any red flags or obvious concerns between potential control types? Are there any known environmental risks that may substantially increase the cost of the project or available information that could help in alternatives comparison? Consult with region Environmental staff for support.
- Consider **Context Sensitive/Sustainable Design**. Context sensitive design is a model for transportation project development. A proposed transportation project is to be planned not only for its physical aspects as a facility serving specific transportation objectives, but also for its effects on the aesthetic, social, economic, and environmental values, needs, constraints, and opportunities in a larger community setting. Projects designed using this model:
    - Optimize safety of the facility for both the user and the community.
    - Promote multimodal solutions.

- Are in harmony with the community, and preserve the environmental, scenic, aesthetic, historic, and natural resource values of the area.
- Are designed and built with minimal disruption to the community.
- Involve efficient and effective use of the resources (time, budget, community) of all involved parties.

Step 3: Analysis – Perform and report the results of applicable analyses for all remaining alternatives and the no-build condition for performance measures identified in Step 1. The analysis is scalable, but typically should include the measures below. The level of effort should be based on project complexity, cost of proposed alternatives, context, and impact to the network and other modes. Contact the region Traffic Office early in the process to determine the network area of influence and scope of analysis. Include the following:

- Traffic Analysis – Use the opening year and selected design year for analysis (see Chapter 1103). In some cases, it may also be appropriate to analyze the horizon year as well. Identify and justify any growth rates used and provide turning movements for all scenarios. There are several deterministic and microsimulation tools for analyzing delay and intersection performance. Traffic volumes and the proximity to other access points will dictate the modeling effort required. Contact the region Traffic Office to determine the appropriate approved tool. For more information and guidance on traffic analysis, refer to Chapter 320 and the Traffic Analysis webpage (http://www.wsdot.wa.gov/Design/Traffic/Analysis/).
  - Peak hour(s) – Report the delay for each alternative.
  - Off-Peak – Report the delay for an additional time period representative of off-peak travel. Depending on location, up to 80% of total delay can occur in off-peak hours.
  - If a traffic signal is under consideration, perform and report the findings of the signal warrant analysis.
- Report the expected average crash frequency (total and fatal/all injury) of each alternative. When a safety need has been identified in Step 1, perform a crash analysis and summarize the findings. See Chapter 321 for more information.
- Multimodal safety and operations – Briefly discuss how the design for each alternative is expected to affect multimodal users, when applicable. Potential items to consider include pedestrian delay, number of lanes to cross, protected vs permitted turning movements, motorist approach speed, etc. When applicable, evaluate multimodal treatments that may be necessary for each alternative to meet the performance needs.

Step 4: Benefit/Cost Analysis – When applicable, report the Benefit/Cost (B/C) for mobility (due to change in travel time) and/or the B/C for safety (due to change in crash frequency/severity). Include the following in the analysis:

- Project costs related to design, right of way, and construction.
- Annual maintenance and operations cost. For signals, this should include the cost of signal engineers and technicians to review and implement signal timings and respond to malfunctions and emerging issues. This value can be obtained from the region Traffic Office.

- Travel time savings based on the reduction in delay over the life cycle during identified peak hours and/or off-peak hours.
- Societal cost savings (considered as the Benefit in the analysis) of reduced crash frequency and/or severity using a predictive method as described in Chapter 321. Use the following for WSDOT Societal Costs for crashes:
  - Fatal crash: $2,900,000
  - Serious injury crash: $2,900,000
  - Evident injury crash: $155,000
  - Possible injury crash: $60,000
  - Property damage only crash: $10,000
- Salvage value of right of way, grading and drainage, and structures.

Step 5: Selection – Based on performance tradeoffs and documented project needs, select the recommended alternative.

1300.05(1)(a) Additional Information

Discuss the following in the ICA as needed to further support the selection (is it an item that will have a significant effect on the decision?):

- Review the corridor sketch plans and database with the regional planning office.
- Information from a corridor or planning study.
- Current and future land use and whether or not the intersection control will reasonably accommodate future land use traffic changes.
- Community engagement and local agency coordination and comments.
- Effect on future local agency projects.
- Other elements considered in the selection of the intersection control.

1300.05(2) Community Engagement



Community engagement is a necessary element of project development. Technical, public, and political aspects must be considered. There is often concern from communities regarding control types that may be under consideration, especially the types of intersections that may seem unfamiliar or that break from the traditional approach. Education and outreach efforts, if necessary, are collaborative and are most useful during the analysis and early scoping stages. It is critical that community engagement efforts occur with preparation and well-organized content regarding the performance data associated with different control types to inform communities of the distinct differences between control types with respect to the context, modes, safety and operations desired. Use contextual performance needs (see Chapter 1101) identified by the community to help support the options being considered at a given location.

Follow the guidelines of WSDOT's Community Engagement Plan (www.wsdot.wa.gov/planning/), and document the effort as indicated in Chapter 1100.

1300.05(3) Approval

The ICA shall be prepared by or under the direct supervision of a licensed Professional Engineer. Approval of the ICA (see Chapter 300 for more information) requires the following:

- Region Traffic Engineer Approval
- HQ Traffic Approval

1300.05(4) Local Agency or Developer-Initiated Intersections

Chapter 320 provides guidance for preparation of a Traffic Impact Analysis (TIA). Early in the design process, local agencies and developers should coordinate with the region office to identify specific intersections for further analysis. The project initiator provides an Intersection Control Analysis (ICA) for approaches and intersections with state routes per 1300.05, or references this information in the TIA. The project initiator documents the design considerations and submits the ICA and all documentation to the region for approval (per 1300.05). After the ICA is approved, finalize the intersection design and obtain approval per Chapters 300 (for documentation), 1310 (for intersections), 1320 (for roundabouts), and 1330 (for traffic signals).

1300.06 Documentation

Refer to Chapter 300 for additional design documentation requirements.

1300.07 References

1300.07(1) Federal/State Laws, Codes, and Policies

Revised Code of Washington (RCW) 46.61, Rules of the road

Washington Administrative Code (WAC) 468-52, Highway access management – access control classification system and standards

Secretary's Executive Order: E 1082, *Business Practices for Moving Washington*, August 2012, WSDOT

1300.07(2) Design Guidance

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO Current Edition

Highway Capacity Manual (HCM), latest edition, Transportation Research Board, National Research Council

Local Agency Guidelines (LAG), M 36-63, WSDOT

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT

1300.07(3) Supporting Information

Highway Safety Manual (HSM), AASHTO

Roundabouts: An Informational Guide, FHWA-RD-00-067, USDOT, FHWA

Roundabouts: An Informational Guide, Second Edition, NCHRP Report 672, Transportation Research Board, 2010

A Review of the Signalized Intersections: Informational Guide. FHWA-HRT-04-092, USDOT, FHWA, APRIL 2004. www.fhwa.dot.gov/publications/research/safety/04092/

Choosing Intersection Control, IMSA Journal, Buckholz, Nov/Dec 2002.
www.imsasafety.org/journal/nd02/buckholz.pdf

A Comparison of a Roundabout to Two-way Stop Controlled Intersections with Low and High Traffic Volumes, Luttrell, Greg, Eugene R. Russell, and Margaret Rys, Kansas State University

Guidance for Implementation of the AASHTO Strategic Highway Safety Plan, Volume 5: A Guide for Addressing Unsignalized Intersection Collisions, NCHRP Report 500, Transportation Research Board, 2003

Guidance for Implementation of the AASHTO Strategic Highway Safety Plan Volume 12: A Guide for Reducing Collisions at Signalized Intersections, NCHRP Report 500, Transportation Research Board, 2004

U-turn Based Intersections, FHWA
https://safety.fhwa.dot.gov/intersection/innovative/uturn/

Crossover-Based Intersections, FHWA
https://safety.fhwa.dot.gov/intersection/innovative/crossover/

Synthesis of the Median U-Turn Intersection Treatment, Safety, and Operational Benefits, FHWA-HRT-07-033, USDOT, FHWA

Alternative Intersections/Interchanges: Informational Report (AIIR), FHWA-HRT-09-060, Hughes et al., USDOT, FHWA, 2010

Field Evaluation of a Restricted Crossing U-Turn Intersection, FHWA-HRT-12-037, USDOT, FHWA

Roundabouts and Sustainable Design, Ariniello et al., Green Streets and Highways – ASCE, 2011

Pedestrian and Bicycle Information Center www.pedbikeinfo.org/

Community Engagement Plan, WSDOT http://www.wsdot.wa.gov/planning/default.htm

Chapter 1310 Intersections

1310.01 General
1310.02 Design Considerations
1310.03 Design Elements
1310.04 U-Turns
1310.05 Intersection Sight Distance
1310.06 Signing and Delineation
1310.07 Procedures
1310.08 Documentation
1310.09 References

1310.01 General

Intersections are a critical part of Washington State Department of Transportation (WSDOT) highway design because of increased conflict potential. Traffic and driver characteristics, bicycle and pedestrian needs, physical features, and economics are considered during the scoping and design stages to develop channelization and traffic control to provide multimodal traffic flow through intersections.

See chapters in the 1100 series for instruction on multimodal practical design, including identifying project needs, context, design controls, modal performance, alternatives analysis, and design element dimensioning.

This chapter provides guidance for designing intersections, including ramp terminals. Refer to the following chapters for additional information:

Chapter	Subject
1103	Design controls
1106	Design element dimensions
1230	Geometric cross section
1300	Intersection control type
1320	Roundabouts
1330	Traffic signals
1340	Driveways
1360	Interchanges
1510	Pedestrian facilities
1520	Roadway bicycle facilities

For assistance with intersection design, contact the Headquarters (HQ) Design Office.

1310.02 Design Considerations

Consider all potential users of the facility in the design of an intersection. This involves addressing the needs of a diverse mix of user groups, including passenger cars, heavy vehicles of varying classifications, bicycles, and pedestrians. Often, meeting the needs of one user group results in a compromise in service to others. Intersection design balances these competing needs, resulting in appropriate levels of operation for all users.

In addition to reducing the number of conflicts, minimize the conflict area as much as possible while still providing for the design vehicle (see Chapter 1103). This is done to control the speed of turning vehicles and reduce the area of exposure for vehicles, bicycles, and pedestrians. For additional information on pedestrian needs, see Chapter 1510. For intersections with shared-use paths, see Chapter 1515. For bicycle considerations at intersections, see Chapter 1520.

1310.02(1) Non-Geometric Considerations

Geometric design considerations, such as sight distance and intersection angle, are important. Equally important are perception, contrast, and a driver's age. Perception is a factor in the majority of crashes. Regardless of the type of intersection, the function depends on the driver's ability to perceive what is happening with respect to the surroundings and other vehicles. When choosing an acceptable gap, the driver first identifies the approaching vehicle and then determines its speed. The driver uses visual clues provided by the immediate surroundings in making these decisions. Thus, given equal sight distance, it may be easier for the driver to judge a vehicle's oncoming speed when there are more objects to pass by in the driver's line of sight. Contrast allows drivers to discern one object from another.

1310.02(2) Intersection Angle and Roadway Alignment

An important intersection design characteristic is the intersection angle. The desirable intersection angle is 90°, with 60° to 120° allowed. Do not put angle points on the roadway alignments within intersection areas or on the through roadway alignment within 100 feet of the edge of traveled way of a crossroad. However, angle points within the intersection are allowed at intersections with a minor through movement, such as at a ramp terminal (see Exhibit 1310-2).

When feasible, locate intersections such that curves do not begin or end within the intersection area. It is desirable to locate the PC and PT 250 feet or more from the intersection so that a driver can settle into the curve before the gap in the striping for the intersection area. Do not locate short curves where both the PC and PT are within the intersection area.

1310.02(3) Lane Alignment


It is desirable that entering through traffic is aligned with the exit lanes. However, the entering and exit lanes may be offset up to 6 feet when the following conditions are met:

- Illumination is provided.
- The intersection is not within a horizontal curve, nor is it within a crest vertical curve.
- The taper rates provided in Exhibit 1310-1 are used.
- There is a posted speed of 55 mph or less.

Consider dotted extension lines that continue through the intersection.



Exhibit 1310-1 Lane Alignment Taper Rate



Posted Speed	Taper Rate
55 mph	55:1
50 mph	50:1
45 mph	45:1
40 mph	27:1
35 mph	21:1
30 mph	15:1
25 mph	11:1

1310.02(4) Intersection Spacing

Provide intersection spacing for efficient operation of the highway. The minimum design intersection spacing for highways with limited access control is covered in Chapter 530. For other highways, the minimum design intersection spacing is dependent on the managed access highway class. (See Chapter 540 for minimum intersection spacing on managed access highways.)

As a minimum, provide enough space between intersections for left-turn lanes and storage length. Space signalized intersections and intersections expected to be signalized to maintain efficient signal operation. Space intersections so that queues will not block an adjacent intersection.

Evaluate existing intersections that are spaced less than shown in Chapters 530 and 540. Also, evaluate closing or restricting movements at intersections with operational issues. Document the spacing of existing intersections that will remain in place and the effects of the spacing on operation, capacity, and circulation.

1310.02(5) Accommodating vs. Designing for Vehicles

Accommodating for a vehicle allows encroachment of other lanes, shoulders, or other elements to complete the required maneuver. Designing for a vehicle does not require encroachment on those elements.

There are competing design objectives when considering the crossing needs of pedestrians and the turning needs of larger vehicles. To design for large design vehicles, larger turn radii are used. This results in increased pavement areas, longer pedestrian crossing distances, and longer traffic signal arms. (See Chapter 1103 for design vehicle selection criteria.)

When appropriate, to reduce the intersection area, consider accommodating for large vehicles instead of designing for them. This reduces the potential for vehicle/pedestrian conflicts, decreases pedestrian crossing distance, and controls the speeds of turning vehicles. Use turn simulation software (such as AutoTURN®) to verify the design.

1310.02(6) Sight Distance

For stopping and decision sight distance criteria, see Chapter 1260. Intersection sight distance criteria are discussed in section 1310.05.

1310.02(7) Crossroads

When the crossroad is a city street or county road, design the crossroad beyond the intersection area in cooperation with the local agency.

When the crossroad is a state facility, design the crossroad according to the *Design Manual*. Continue the cross slope of the through roadway shoulder as the grade for the crossroad. Use a vertical curve that is at least 60 feet long to connect to the grade of the crossroad.

Evaluate the profile of the crossroad in the intersection area. The crown slope of the main line might need to be adjusted in the intersection area to improve the profile for the cross traffic.

Design the grade at the crosswalk to meet the requirements for accessibility. (See Chapter 1510 for additional crosswalk information.)

In areas that experience accumulations of snow and ice for all legs that require traffic to stop, design a maximum grade of ±4% for a length equal to the anticipated queue length for stopped vehicles.

1310.02(8) Rural Expressway At-Grade Intersections

Evaluate grade separations at all intersections on rural expressways.

Design high-speed at-grade intersections on rural expressways as indirect left turns, split intersections, or roundabouts.

The State Traffic Engineer's approval is required for any new intersection or signal on a rural expressway.

1310.02(9) Interchange Ramp Terminals

When stop control or traffic signal control is selected, the design to be used or modified is shown in Exhibit 1310-2. Higher-volume intersections with multiple ramp lanes are designed individually. Provide ramp terminal designs consistent with the speed of the crossroad.


Where stop control or signal control is implemented, the intersection configuration criteria for ramp terminals are normally the same as for other intersections. One exception is that an angle point is allowed between an off-ramp and an on-ramp. This is because the through movement of traffic getting off the freeway, going through the intersection, and getting back on the freeway is minor.

Another exception is at ramp terminals where the through movement is eliminated (for example, at a single-point interchange). For ramp terminals that have two wye connections, one for right turns and the other for left turns, and no through movement, the intersection angle has little meaning and does not need to be considered.

Due to the probable development of large traffic generators adjacent to an interchange, width for a median on the local road is desirable whenever such development is expected. This allows for future left-turn channelization. Use median channelization when justified by capacity determination and analysis or by the need to provide a smooth traffic flow.

Adjust the alignment of the intersection legs to fit the traffic movements and to discourage wrong-way movements. Use the allowed intersecting angles of 60° to 120° in designing the best alignment for efficiency and intersection operations.

Exhibit 1310-2 Ramp Terminal Intersection Details



Notes:

[1] For right-turn corner design, see Exhibit 1310-6.

[2] Use turn simulation software to verify that the design vehicle can make the turn.

[3] For taper rates, see Exhibit 1310-10a, Table 1.

1310.02(10) Wrong-Way Movement Countermeasures

Wrong-way crashes, though infrequent, have the potential to be more serious than other types of crashes, especially on high-speed facilities. Crash data show that impaired and older drivers are overrepresented and that a high percentage of these occurrences are at night. Washington State data show approximately equal numbers of crashes on the Interstate and multilane urban principal arterial highways. Discourage wrong-way maneuvers at all stages of design.

1310.02(10)(a) Wrong-Way Driving Countermeasure Categories

There are three categories of countermeasures to discourage wrong-way driving:

- Signing and delineation
- Intelligent transportation systems
- Geometric design

1310.02(10)(a)(1) Signing and Delineation

Signing and delineation countermeasures include:

- DO NOT ENTER and WRONG WAY signs.
- ONE WAY signs.
- Turn restriction signs.
- Red-backed raised pavement markers (RPMs).
- Directional pavement arrows.
- Yellow edge line on left and white edge line on right side of exit ramps.
- Pavement marking extension lines to direct drivers to the correct ramp.

Signing can be a more effective countermeasure when the signs are lowered. At night, lowered signs are better illuminated by low-beam headlights. Other improvements may include a second set of signs, supplemental sign placards, oversized signs, flashing beacons, internal illumination, overhead-mounted signs, red reflective tape on the back of signs, extra overhead lighting, and red-backed guideposts on each side of the ramp up to the WRONG WAY sign.

1310.02(10)(a)(2) Intelligent Transportation Systems (ITS)

Wrong-way ITS countermeasures are wrong-way detection and warning systems. Contact the region Traffic Office for assistance when considering an ITS wrong-way warning system.

1310.02(10)(a)(3) Geometric Design

Geometric countermeasures include separating wrong-way movements from other movements, discouraging wrong-way movements, encouraging right-way movements, and improving the visibility of the right-way movement.


a. Separate On- and Off-Ramp Terminals

Consider the separation of on- and off-ramp terminals, particularly at interchanges where the ramp terminals are closely spaced (for example, partial cloverleaf ramps combined with

other ramps). Wider medians between off- and on-ramp terminals provide room for signing and allow the median end to be shaped to help direct vehicles onto the correct roadway. The minimum width of the raised median is 7 feet, face of curb to face of curb, to accommodate a 36 inch sign.

Extend the raised median on a two-way ramp from the ramp terminal intersection to the split of the on- and off-ramps. The median outside of the intersection area may be reduced to the width of a dual-faced mountable curb. (See Exhibit 1310-3 for an example of the minimum median at the terminal of a two-way ramp.)

Exhibit 1310-3 Median at Two-Way Ramp Terminal



b. Reduced Off-Ramp Terminal Throat Width

Reducing the width of the off-ramp throat has been a successful method of discouraging wrong-way movements. A smaller opening makes the wrong-way entry less inviting, particularly for closely spaced ramps. When off-ramp terminals have right-turn lanes, a raised island will reduce the potential for a wrong-way movement.

c. Increased On-Ramp Terminal Throat Width


Increasing the width of the on-ramp throat can encourage right-way movements. A larger opening for the on-ramp makes it easier to turn into. To increase the throat width of on-ramps, use flat radii for left- and right-turning traffic and remove islands.

d. Intersection Balance

When drivers make a left turn, they are required to leave the intersection in the extreme left-hand lane lawfully available. As a result, left-turning drivers tend to head for a point between 50% and 60% of the way through the intersection.

At a two-way ramp terminal, the desirable throat width for the on-ramp roadway is not less than the off-ramp roadway width to accommodate this behavior (see Exhibit 1310-4). Much of this can be achieved by adjusting the stop bar position on the interchange cross street.

Exhibit 1310-4 Intersection Balance Example



e. Visibility

When drivers can see and recognize the roadway they want to turn onto, they are less likely to make a mistake and turn onto the wrong roadway. For two-way ramps and divided multilane roadways with barrier in the median, end the barrier far enough from the intersection that a left-turning driver can see and recognize the roadway going the correct

direction. Drivers need to see the delineation pavement markings, curbs, or other elements to locate the correct roadway.

f. Angular Corners on the Left of Off-Ramp Terminals

Angular corners on the left side of off-ramp terminals will discourage wrong-way right turns. Provide a corner design as angular as feasible that will provide for the left turn from the off-ramp. Circular curves can look inviting for a wrong-way right turn onto the off-ramp (see Exhibit 1310-2).

1310.02(10)(b) Countermeasure Applications

Following are applications of wrong-way countermeasures for some common locations. For assistance with signing and delineation, contact the region Traffic Office.

1310.02(10)(1) All Ramps

Countermeasures that can be used on almost any ramp or intersection with potential wrong-way concerns include:

- Enlarged warning signs.
- Directional pavement arrows at ramp terminals.
- Redundant signing and pavement arrows.
- Roundabout ramp terminal intersections, where room is available.
- Red-backed RPMs.

1310.02(10)(2) One-Way Diamond Off-Ramp

Diamond interchanges are common, and although drivers are familiar with them, they can still get confused and go the wrong way. In addition to signing and pavement markings for these interchanges, provide:


- Angular corners to discourage wrong-way right turns.

1310.02(10)(3) Diamond Interchange With Advance Storage

Diamond interchanges with advance storage have left-turn storage lanes that extend from the on-ramp past the off-ramp (see Exhibit 1310-5). This allows for a potential early left turn onto the off-ramp. Following are additional countermeasures for interchanges with advanced left-turn storage:

- Provide a raised median to discourage the wrong-way left turn.
- Provide signing and directional arrows to direct traffic to the correct left-turn point.

Exhibit 1310-5 Diamond Interchange With Advance Storage



1310.02(10)(4) Two-Way Ramps

Two-way ramps have the on- and off-ramp adjacent to each other. They are used at partial cloverleaf, trumpet, and button hook interchanges. Because the on and off roadways are close to each other, they are more vulnerable to wrong-way driving. Also, when the separation between on and off traffic is striping only, the ramps are susceptible to drivers entering the correct roadway and inadvertently crossing to the wrong ramp. In addition to signing and delineation, the following are countermeasures for two-way ramps:

- Separate the on- and off-ramp terminals.
- Reduce off-ramp terminal throat width.
- Increase on-ramp terminal throat width.
- Maintain intersection balance.
- Improve on-ramp visibility.
- Provide a raised median or dual-faced curb from the ramp terminal intersection to the gore nose.

1310.02(10)(5) HOV Direct Access Ramps

HOV direct access ramps are two-way ramps in the median; therefore, the ability to provide separation between the on and off traffic is limited by the width of the median. An additional concern is that HOV direct access ramps are left-side ramps. Drivers normally enter the freeway using a right-side ramp and they may mistakenly travel the wrong way on

a left-side ramp. Review existing and proposed signing for inadvertent misdirection. (See Chapter 1420 for HOV direct access and countermeasures for wrong-way driving at HOV direct access ramps.)

1310.02(10)(6) Multilane Divided Roadways

Wrong-way driving can also occur on multilane divided nonfreeway facilities. Wrong-way drivers may enter multilane divided facilities at driveways and at-grade intersections. Countermeasures for wrong-way driving on nonfreeway multilane divided highways include:

- Wrong-way signing and delineation at the intersections.
- Right-in/right-out road approaches.

1310.03 Design Elements

When designing an intersection, identify and address the needs of all intersection users.

If pedestrian facilities are present, the design objective becomes one of reducing the potential for vehicle/pedestrian conflicts. This is done by minimizing pedestrian crossing distances and controlling the speeds of turning vehicles. Pedestrian refuge islands can be beneficial. They minimize the pedestrian crossing distance, reduce the conflict area, and minimize the impacts on vehicular traffic. When designing islands, speeds can be reduced by designing the turning roadway with a taper or large radius curve at the beginning of the turn and a small radius curve at the end. This allows larger islands while forcing the turning traffic to slow down. Use turn simulation software (such as AutoTURN®) to verify the design.

Channelization, the separation or regulation of traffic movements into delineated paths of travel, can facilitate the orderly movement of pedestrians, bicycles, and vehicles. Channelization includes left-turn lanes, right-turn lanes, speed change lanes (both acceleration and deceleration lanes), and islands.


1310.03(1) Right-Turn Corners

Exhibit 1310-6 shows initial ranges for right-turn corner designs using a simple curve with a taper. These are considered approximate pavement areas to accommodate the design vehicles without encroachment on the adjacent lane at either leg of the curve.

Depending on the context of the roadway and right-turn corner (and whether the right-turn corner will be designed for or will accommodate a design vehicle), there may be several design considerations. Consider vehicle-pedestrian conflicts; vehicle encroachment on the shoulder or adjacent same-direction lane at the exit leg; capacity restrictions for right-turning vehicles or other degradation of intersection operations; and the effects on other traffic movements.

Other design considerations may include a combination of simple or compound curves, tapers at the beginning or end of the turn, and so on. Verify the design vehicle can make the turn using turn simulation software (such as AutoTURN®).

Exhibit 1310-6 Initial Ranges for Right-Turn Corner (Simple Curve-Taper)



L_1 = Available roadway width [2] that the vehicle is turning from

L_2 = Available roadway width [2] for the vehicle leaving the intersection

R = Radius to the edge of traveled way

T = Taper rate (length per unit of width of widening)

A = Delta angle of the turning vehicle

Vehicle	*A*	*R*	*L_1 [1]*	*L_2 [2]*	*T*
P	All	30	11	11	25
SU-30 & CITY-BUS	All	50	11	11	25
WB-40	All	55	11	15	7.5
WB-67	All	50-85	11	22-24	7

Notes:

[1] When available roadway width is less than 11 ft, widen at 25:1.

[2] Available roadway width includes the shoulder, less a 2-ft clearance to a curb, and all the same-direction lanes of the exit leg at signalized intersections.

General:

All distances given in feet and angles in degrees

1310.03(2) Left-Turn Lanes and Turn Radii

Left-turn lanes provide storage, separate from the through lanes, for left-turning vehicles waiting for a signal to change or for a gap in opposing traffic. (See 1310.03(4) for a discussion on speed change lanes.)

Design left-turn channelization to provide sufficient operational flexibility to function under peak loads and adverse conditions.

1310.03(2)(a) One-Way Left-Turn Lanes

One-way left-turn lanes are separate storage lanes for vehicles turning left from one roadway onto another. One-way left-turn lanes may be an economical way to lessen delays and crash potential involving left-turning vehicles. In addition, they can allow deceleration clear of the through traffic lanes. Provide a minimum storage length of 100 feet for one-way left-turn lanes. When evaluating left-turn lanes, include impacts to all intersection movements and users.

At signalized intersections, use a traffic signal analysis to determine whether a left-turn lane is needed and the storage length. If the length determined is less than the 100-foot minimum, make it 100 feet (see Chapter 1330).

At unsignalized intersections, use the following as a guide to determine whether or not to provide one-way left-turn lanes:

- A traffic analysis indicates congestion reduction with a left-turn lane. On two-lane highways, use Exhibit 1310-7a, based on total traffic volume (DHV) for both directions and percent left- turn traffic, to determine whether further investigation is needed. On four-lane highways, use Exhibit 1310-7b to determine whether a left-turn lane is recommended.
- A study indicates crash reduction with a left-turn lane.
- Restrictive geometrics require left-turning vehicles to slow greatly below the speed of the through traffic.
- There is less than decision sight distance for traffic approaching a vehicle stopped at the intersection to make a left turn.

A traffic analysis based on the *Highway Capacity Manual* (HCM) may also be used to determine whether left-turn lanes are needed to maintain the desired level of service.

Exhibit 1310-7a Left-Turn Storage Guidelines: Two-Lane, Unsignalized





Exhibit 1310-7b Left-Turn Storage Guidelines: Four-Lane, Unsignalized



Determine the storage length on two-lane highways by using Exhibits 1310-8a through 8c. On four-lane highways, use Exhibit 1310-7b. These lengths do not consider trucks. Use Exhibit 1310-9 for storage length when trucks are present.

Use turn simulation software (such as AutoTURN®) to verify that left-turn movements for the design vehicle(s) do not have conflicts. Design opposing left-turn design vehicle paths with a minimum 4-foot (12-foot desirable) clearance between opposing turning paths.

Where one-way left-turn channelization with curbing is to be provided, evaluate surface water runoff and design additional drainage facilities if needed to control the runoff.

Provide illumination at left-turn lanes in accordance with the guidelines in Chapter 1040.

Exhibit 1310-8a Left-Turn Storage Length: Two-Lane, Unsignalized (40mph)




Exhibit 1310-8b Left-Turn Storage Length: Two-Lane, Unsignalized (50 mph)




Exhibit 1310-8c Left-Turn Storage Length: Two-Lane, Unsignalized (60 mph)




Exhibit 1310-9 Left-Turn Storage With Trucks (ft)

Storage Length* (ft)	% Trucks in Left-Turn Movement				
	10	20	30	40	50
100	125	125	150	150	150
150	175	200	200	200	200
200	225	250	275	300	300
250	275	300	325	350	375
300	350	375	400	400	400
*Length from Exhibits 1310-7b and 1310-8a, 8b, or 8c.					

At signalized intersections with high left-turn volumes, double (or triple) left-turn lanes may be needed to maintain the desired level of service. For a double left-turn, a throat width of 30 to 36 feet is desirable on the exit leg of the turn to offset vehicle offtracking and the difficulty of two vehicles turning abreast. Use turn simulation software (such as AutoTURN®) to verify that the design vehicle can complete the turn. Where the design vehicle is a WB 40 or larger, it is desirable to provide for the design vehicle in the outside lane and an SU-30 vehicle turning abreast rather than two design vehicles turning abreast.

Exhibits 1310-10a through 10f show left-turn lane geometrics, which are described as follows:

1310.03(2)(a)(1) Widening

It is desirable that offsets and pavement widening (see Exhibit 1310-10a) be symmetrical about the centerline or baseline. Where right of way or topographic restrictions, crossroad alignments, or other circumstances preclude symmetrical widening, pavement widening may be on one side only.

1310.03(2)(a)(2) Divided Highways

Widening is not needed for left-turn lane channelization where medians are 11 feet wide or wider (see Exhibits 1310-10b through 10d). For medians between 13 feet and 23 feet or where the acceleration lane is not provided, it is desirable to design the left-turn lane adjacent to the opposing lane (see Exhibit 1310-10b) to improve sight distance and increase opposing left-turn clearances.

A median acceleration lane (see Exhibits 1310-10c and 10d) may be provided where the median is 23 feet or wider. The median acceleration lane might not be needed at a signalized intersection. When a median acceleration lane is to be used, design it in accordance with 1310.03(4), Speed Change Lanes. Where medians have sufficient width, provide a 2-foot shoulder adjacent to a left-turn lane.


1310.03(2)(a)(3) Minimum Protected Left Turn With a Median

At intersections on divided highways where channelized left-turn lanes are not provided, provide the minimum protected storage area (see Exhibit 1310-10e).

1310.03(2)(a)(4) Modifications to Left-Turn Designs

The left-turn lane designs discussed above and given in Exhibits 1310-10a through 10e may be modified when determined by design element dimensioning (see Chapter 1106.) Document the benefits and impacts of the modified design, including changes to vehicle-pedestrian conflicts; vehicle encroachment; deceleration length; capacity restrictions for turning vehicles or other degradation of intersection operations; and the effects on other traffic movements. Provide a modified design that is able to accommodate the design vehicle, and provide for the striping (see the *Standard Plans* and the MUTCD). Verify the design vehicle can make the turn using turn simulation software (such as AutoTURN®); include a plot of the design and verification.

Exhibit 1310-10a Median Channelization: Widening



Notes:

[1] The minimum width of the left-turn storage lane (T1+T2) is 11 ft.

[2] For left-turn storage length, see Exhibits 1310-7b for 4-lane roadways or 1310-8a through 8c for 2-lane roadways.

[3] Use turn simulation software (such as AutoTURN®) to verify the design vehicle can make the turn.

[4] For right-turn corner design, see Exhibit 1310-6.

[5] For desirable taper rates, see Table on this Exhibit. With justification, taper rates from the Table in Exhibit 1310-10c may be used.

[6] For pavement marking details, see the *Standard Plans* and the MUTCD.


[7] Where curb is provided, add the width of the curb and the shoulders to the left-turn lane width. For shoulder widths at curbs, see 1310.03(6) and Chapter 1230.

T_1 = Width of left-turn lane on approach side of centerline

T_2 = Width of left-turn lane on departure side of centerline

Posted Speed	Desirable Taper Rate [6]
55 mph	55:1
50 mph	50:1
45 mph	45:1
40 mph	40:1
35 mph	35:1
30 mph	30:1
25 mph	25:1

Exhibit 1310-10b Median Channelization: Median Width 11 ft or More



Notes:

[1] Where curb is provided, add the width of the curb and the shoulders. For shoulder widths at curbs, see 1310.03(6) and Chapter 1230.

[2] For left-turn storage length, see Exhibits 1310-7b for 4-lane roadways or 1310-8a through 8c for 2-lane roadways.

[3] Verify the design vehicle can make the turn using turn simulation software (such as AutoTURN®).

[4] For right-turn corner design, see Exhibit 1310-6.

[5] For median widths greater than 13 ft, it is desirable to locate the left-turn lane adjacent to the opposing through lane with excess median width between the same-direction through lane and the turn lane.


[6] For increased storage capacity, the left-turn deceleration taper alternate design may be used.

[7] Reduce to lane width for medians less than 13 ft wide.

General:

For pavement marking details, see the *Standard Plans* and the MUTCD.

Exhibit 1310-10c Median Channelization: Median Width 23 ft to 26 ft



Notes:

[1] When curb is provided, add the width of the curb.

[2] For left-turn storage length, see Exhibits 1310 7b for 4-lane roadways or 1310-8a through 8c for 2-lane roadways.

[3] Verify the design vehicle can make the turn using turn simulation software (such as AutoTURN®).

[4] For right-turn corner design, see Exhibit 1310 6.

[5] The minimum total length of the median acceleration lane is shown in Exhibit 1310-14.

[6] For acceleration taper rate, see Table on this exhibit.


[7] For increased storage capacity, the left-turn deceleration taper alternate design may be used.

Posted Speed	Taper Rate
55 mph	55:1
50 mph	50:1
45 mph	45:1
40 mph	27:1
35 mph	21:1
30 mph	15:1
25 mph	11:1

General:

For pavement marking details, see the *Standard Plans* and the MUTCD.

Exhibit 1310-10d Median Channelization: Median Width of More Than 26 ft



Notes:

[1] For left-turn storage length, see Exhibits 1310-7b for 4-lane roadways or 1310-8a through 8c for 2 lane roadways.

[2] Verify the design vehicle can make the turn using turn simulation software (such as AutoTURN®).

[3] For right-turn corner design, see Exhibit 1310-6.


[4] The minimum length of the median acceleration lane is shown in Exhibit 1310-14.

[5] For acceleration taper rate, see the Table on Exhibit 1310-10c.

General:

For pavement marking details, see the *Standard Plans* and the MUTCD.

Exhibit 1310-10e Median Channelization: Minimum Protected Storage



Notes:

[1] Verify the design vehicle can make the turn using turn simulation software (such as AutoTURN®).

[2] For right-turn corner design, see Exhibit 1310-6.

[3] For median width 17 ft or more. For median width less than 17 ft, widen to 17 ft. or use Exhibit 1310-10b.

General:

For pavement marking details, see the *Standard Plans* and the MUTCD.

1310.03(2)(b) Two-Way Left-Turn Lanes (TWLTL)

Two-way left-turn lanes are located between opposing lanes of traffic. They are used by vehicles making left turns from either direction, from or onto the roadway.

Use TWLTLs only on managed access highways where there are no more than two through lanes in each direction. Evaluate installation of TWLTLs where:


- A crash study indicates reduced crashes with a TWLTL.
- There are existing closely spaced access points or minor street intersections.
- There are unacceptable through traffic delays or capacity reductions because of left-turning vehicles.

TWLTLs can reduce delays to through traffic, reduce rear-end crashes, and provide separation between opposing lanes of traffic. However, they do not provide refuge for pedestrians and can encourage strip development with additional closely spaced access points. Evaluate other alternatives (such as prohibiting midblock left turns and providing for U-turns) before using a TWLTL. (See Chapter 540 for additional restrictions on the use of TWLTLs, and Chapter 1230 for discussion of road diets, which commonly employ a center turn lane.)

The basic design for a TWLTL is illustrated in Exhibit 1310-10f. Additional criteria are as follows:

- The desirable length of a TWLTL is not less than 250 feet.
- Provide illumination in accordance with the guidelines in Chapter 1040.
- Pavement markings, signs, and other traffic control devices must be in accordance with the MUTCD and the *Standard Plans*.
- Provide clear channelization when changing from TWLTLs to one-way left-turn lanes at an intersection.

Exhibit 1310-10f Median Channelization: Two-Way Left-Turn Lane



Notes:

[1] Verify the design vehicle can make the turn using turn simulation software (such as AutoTURN®).

[2] For right-turn corner design, see Exhibit 1310-6.

General:


For pavement marking details and signing criteria, see the *Standard Plans* and the MUTCD.

1310.03(3) Right-Turn Lanes

Right-turn movements influence intersection capacity even though there is no conflict between right-turning vehicles and opposing traffic. Right-turn lanes might be needed to maintain efficient intersection operation. Use the following to determine when to consider right-turn lanes at unsignalized intersections:

- For two-lane roadways and for multilane roadways with a posted speed of 45 mph or above, when recommended by Exhibit 1310-11.
- A crash study indicates an overall crash reduction with a right-turn lane.
- The presence of pedestrians requires right-turning vehicles to stop.
- Restrictive geometrics require right-turning vehicles to slow greatly below the speed of the through traffic.
- There is less than decision sight distance for traffic approaching the intersection.
- For unsignalized intersections, see 1310.03(4) for guidance on right-turn lane lengths. For signalized intersections, use a traffic signal analysis to determine whether a right-turn lane is needed and what the length is (see Chapter 1330).
- A capacity analysis may be used to determine whether right-turn lanes are needed to maintain the desired level of service.
- Where adequate right of way exists, providing right-turn lanes is relatively inexpensive and can provide increased operational efficiency.
- The right-turn pocket or the right-turn taper (see Exhibit 1310-12) may be used at any minor intersection where a right-turn lane is not provided. These designs reduce interference and delay to the through movement by offering an earlier exit to right-turning vehicles.
- If the right-turn pocket is used, Exhibit 1310-12 shows taper lengths for various posted speeds.

Exhibit 1310-11 Right-Turn Lane Guidelines



Notes:

[1] For two-lane highways, use the peak hour DDHV (through + right-turn).
For multilane, high-speed highways (posted speed 45 mph or above), use the right-lane peak hour approach volume (through + right-turn).

[2] When all three of the following conditions are met, reduce the right-turn DDHV by 20:


- The posted speed is 45 mph or below
- The right-turn volume is greater than 40 VPH
- The peak hour approach volume (DDHV) is less than 300 VPH

[3] For right-turn corner design, see Exhibit 1310-6.

[4] For right-turn pocket or taper design, see Exhibit 1310-12.

[5] For right-turn lane design, see Exhibit 1310-13.

Exhibit 1310-12 Right-Turn Pocket and Right-Turn Taper



Posted Speed Limit	*L*
Below 40 mph	40 ft
40 mph or above	100 ft

1310.03(4) Speed Change Lanes


A speed change lane is an auxiliary lane primarily for the acceleration or deceleration of vehicles entering or leaving the through traveled way. Speed change lanes are normally provided for at-grade intersections on multilane divided highways with access control. Where roadside conditions and right of way allow, speed change lanes may be provided on other through roadways. Justification for a speed change lane depends on many factors, including speed; traffic volumes; capacity; type of highway; design and frequency of intersections and crash history

When either deceleration or acceleration lanes are to be used, design them in accordance with Exhibits 1310-13 and 1310-14. When the design speed of the turning traffic is greater than 20 mph, design the speed change lane as a ramp in accordance with Chapter 1360. When a deceleration lane is used with a left-turn lane, add the deceleration length to the storage length.

A dedicated deceleration lane (see Exhibit 1310-13) is advantageous because it removes slowing vehicles from the through lane.

An acceleration lane (see Exhibit 1310-14) is not as advantageous because entering drivers can wait for an opportunity to merge without disrupting through traffic. However, acceleration lanes for left-turning vehicles provide a benefit by allowing the turn to be made in two movements.

Exhibit 1310-13 Right-Turn Lane



Highway Design Speed (mph)	Deceleration Lane Length (ft)
30	160 [1]
35	220
40	275
45	350
50	425
55	515
60	605
65	715
70	820

Minimum Deceleration Lane Length (ft)

Grade	Upgrade	Downgrade
3% to less than 5%	0.9	1.2
5% or more	0.8	1.35

Adjustment Multiplier for Grades 3% or Greater

Notes:

[1] When adjusting for grade, do not reduce the deceleration lane to less than 150 ft.


[2] For right-turn corner design, see Exhibit 1310-6.

[3] See 1310.03(6) and Chapter 1230.

General:

For pavement marking details, see the *Standard Plans* and the MUTCD.

Exhibit 1310-14 Acceleration Lane



Highway Design Speed (mph)	Turning Roadway Design Speed (mph)		
	Stop	15	20
30	180	140	
35	280	220	160
40	360	300	270
45	560	490	440
50	720	660	610
55	960	900	810
60	1,200	1,140	1,100
65	1,410	1,350	1,310
70	1,620	1,560	1,520

Minimum Acceleration Length (ft) [1]

Highway Design Speed (mph)	% Grade	Upgrade	Downgrade
40	3% to less than 5%	1.3	0.7
50		1.3	0.65
60		1.4	0.6
70		1.5	0.6
40	5% or more	1.5	0.6
50		1.5	0.55
60		1.7	0.5
70		2.0	0.5

Adjustment Multiplier for Grades 3% or Greater

Notes:

[1] At free right turns (no stop required) and all left turns, the minimum acceleration lane length is not less than 300 ft.

[2] For right-turn corner design, see Exhibit 1310-6.

[3] See 1310.03(6) and Chapter 1230.

[4] Lane width as determined by Chapters 1106 and 1230.

General:

For pavement-marking details, see the *Standard Plans* and the MUTCD.

1310.03(5) Drop Lanes

A lane may be dropped at an intersection with a turn-only lane or beyond the intersection. Do not allow a lane-reduction taper to cross an intersection or end less than 100 feet before an intersection. (See Chapter 1210 for lane reduction pavement transitions.)

When a lane is dropped beyond signalized intersections, provide a lane of sufficient length to allow smooth merging. For facilities with a posted speed of 45 mph or higher, use a minimum length of 1,500 feet. For facilities with a posted speed lower than 45 mph, provide a lane of sufficient length that the advanced lane reduction warning sign can be placed not less than 100 feet beyond the intersection area.

When a lane is dropped beyond unsignalized intersections, provide a lane beyond the intersection not less than the acceleration lane length from Exhibit 1310-14.

1310.03(6) Shoulders

Shoulder width is controlled by its intended functional use and its contribution to achieving the desired safety performance when balanced with other design elements. See Chapter 1230 for functional uses and recommended shoulder widths.

Reducing the shoulder width at intersections facilitates the installation of turn lanes without unduly affecting the overall width of the roadway. A narrower roadway also reduces pedestrian exposure in crosswalks and discourages motorists from using the shoulder to bypass other turning traffic.

1310.03(7) Islands

An island is a defined area within an intersection between traffic lanes for the separation of vehicle movements or for pedestrian refuge. Within an intersection, a median is considered an island. Design islands to clearly delineate the traffic channels to drivers and pedestrians.

Traffic islands perform the following functions:

- Channelization islands control and direct traffic movements.
- Divisional islands separate traffic movements.
- Refuge islands provide refuge for pedestrians and bicyclists crossing the roadway.
- Islands can provide for the placement of traffic control devices and luminaires.
- Islands can provide areas within the roadway for landscaping.

1310.03(7)(a) Size and Shape

Divisional islands are normally elongated and at least 4 feet wide and 20 feet long.

Channelization islands are normally triangular. In rural areas, 75 ft2 is the minimum island area and 100 ft2 is desirable. In urban areas where posted speeds are 25 mph or below, smaller islands are acceptable. Use islands with at least 200 ft2 if pedestrians will be crossing or traffic control devices or luminaires will be installed.

Design triangular-shaped islands as shown in Exhibits 1310-15a through 15c. The shoulder and offset widths illustrated are for islands with vertical curbs 6 inches or higher. Where painted islands are used, such as in rural areas, these widths are desirable but may be omitted. (See Chapter 1240 for desirable turning roadway widths.)


Island markings may be supplemented with reflective raised pavement markers.

Provide barrier-free access at crosswalk locations where raised islands are used. For pedestrian refuge islands and barrier-free access requirements, see Chapter 1510.


1310.03(7)(b) Location

Design the approach ends of islands so they are visible to motorists. Position the island so that a smooth transition in vehicle speed and direction is attained. Begin transverse lane shifts far enough in advance of the intersection to allow gradual transitions. Avoid introducing islands on a horizontal or vertical curve. If the use of an island on a curve cannot be avoided, provide sight distance, illumination, or extension of the island.

Exhibit 1310-15a Traffic Island Designs



Small Traffic Island Design [5]



Large Traffic Island Design [5]

Notes:

[1] Widen shoulders when right-turn radii or roadway width cannot be provided for large trucks. Design widened shoulder pavement the same depth as the right-turn lane.

[2] Use turn simulation software (such as AutoTURN®) for the intersection design vehicle

[3] For turning roadway widths, see Chapter 1240.

[4] For additional details on island placement, see Exhibit 1310-15c.

[5] Small traffic islands have an area of 100 ft2 or less; large traffic islands have an area greater than 100 ft2.


General:

- Provide an accessible route for pedestrians (see Chapter 1510).
- 60° to 90° angle at stop or yield control.
- For right-turn corner design, see Exhibit 1310-6.

1310.03(7)(c) Compound Right-Turn Lane

To design large islands, the common method is to use a large-radius curve for the turning traffic. While this does provide a larger island, it also encourages higher turning speeds. Where pedestrians are a concern, higher turning speeds are undesirable. An alternative is a compound curve with a large radius followed by a small radius (see Exhibit 1310-15b). This design forces the turning traffic to slow down.

Exhibit 1310-15b Traffic Island Designs: Compound Curve



Notes:

[1] Widen shoulders when right-turn radii and roadway width cannot be provided for large trucks. Design widened shoulder pavement the same depth as the right-turn lane.

[2] Use the truck turn simulation software (such as AutoTURN®) for the intersection design vehicle.

[3] For turning roadway widths, see Chapter 1240.

[4] For right-turn corner design, see Exhibit 1310-6.

General:

- Provide an accessible route for pedestrians (see Chapter 1510).
- For additional details on island placement, see Exhibit 1310-15c.

1310.03(7)(d) Curbing

Provide vertical curb 6 inches or higher for:

- Islands with luminaires, signals, or other traffic control devices.
- Pedestrian refuge islands.

Also consider curbing for:


- Divisional and channelizing islands.
- Landscaped islands.
- Stormwater conveyance.

In general, except to meet one of the uses listed above, it is desirable not to use curbs on facilities with a posted speed of 45 mph or above.


Avoid using curbs if the same objective can be attained with pavement markings.

Refer to Chapter 1230 for additional information and design criteria on the use of curbs.

Exhibit 1310-15c Traffic Island Designs



Small Raised Traffic Island [2]



Large Raised Traffic Island [2]

Notes:

[1] For shoulder width at curbs, see Chapter 1230. For additional information on shoulders at turn lanes, see 1310.03(6).

[2] Small traffic islands have an area of 100 ft2 or less; large traffic islands have an area greater than 100 ft2.

General:

Provide an accessible route for pedestrians (see Chapter 1510).

1310.04 U-Turns

For divided multilane highways without full access control that have access points where the median prevents left turns, evaluate the demand for locations that allow U turns. Normally, U turn opportunities are provided at intersections. However, where intersections are spaced far apart, U-turn median openings may be provided between intersections to accommodate U-turns. Use the desirable U-turn spacing (see Exhibit 1310-16) as a guide to determine when to provide U-turn median openings between intersections. Where the U-turning volumes are low, longer spacing may be used.

Locate U-turn median openings where intersection sight distance can be provided.

Exhibit 1310-16 U-Turn Spacing

Urban/Rural	Desirable	Minimum
Urban [1]	1,000 ft	[2]
Suburban	½ mile	¼ mile [3]
Rural	1 mile	½ mile

Notes:


[1] For design speeds higher than 45 mph, use suburban spacing.

[2] The minimum spacing is the acceleration lane length from a stop (see Exhibit 1310-14) plus 300 ft.

[3] For design speeds 60 mph or higher, the minimum spacing is the acceleration lane length from a stop (see Exhibit 1310-14) plus 300 ft.

When designing U-turn median openings, use Exhibit 1310-18 as a guide. Where the median is less than 40 feet wide, with a large design vehicle, provide a U-turn roadway (see Exhibit 1310-17). Design A, with the U-turn roadway after the left-turn, is desirable. Use Design A when the median can accommodate a left-turn lane. Use Design B only where left-turn channelization cannot be built in the median.


Exhibit 1310-17 U-Turn Roadway



Document the need for U-turn locations, the spacing used, and the selected design vehicle. If the design vehicle is smaller than the largest vehicle using the facility, provide an alternate route.

U-turns at signal-controlled intersections do not need the acceleration lanes shown in Exhibit 1310-18. For new U-turn locations at signal-controlled intersections, evaluate conflicts between right-turning vehicles from side streets and U-turning vehicles. Warning signs on the cross street might be appropriate.

Exhibit 1310-18 U-Turn Median Openings



Vehicle	W	R	L	F_1	F_2	T
P	52	14	14	12	12	—
SU-30	87	30	20	13	15	10:1
CITY-BUS	87	28	23	14	18	10:1
WB-40	84	25	27	15	20	6:1
WB-67	94	22	49	15	35	6:1

U-Turn Design Dimensions

Notes:

[1] The minimum length of the acceleration lane is shown in Exhibit 1310-14. Acceleration lane may be eliminated at signal-controlled intersections.

[2] When U-turn uses the shoulder, provide shoulder width sufficient for the intersection design vehicle to make the turn and shoulder pavement designed to the same depth as the through lanes for the acceleration length and taper.

[3] Lane width as determined by Chapters 1106 and 1230.

General:
All dimensions are in feet.

1310.05 Intersection Sight Distance

Providing drivers the ability to see stop signs, traffic signals, and oncoming traffic in time to react accordingly will reduce the probability of conflicts occurring at an intersection. Actually avoiding conflicts is dependent on the judgment, abilities, and actions of all drivers using the intersection.

The driver of a vehicle that is stopped and waiting to cross or enter a through roadway needs obstruction-free sight triangles in order to see enough of the through roadway to complete all legal maneuvers before an approaching vehicle on the through roadway can reach the intersection. Use Exhibit 1310-19a to determine minimum intersection sight distance along the through roadway.

The sight triangle is determined as shown in Exhibit 1310-19b. Within the sight triangle, lay back the cut slopes and remove, lower, or move hedges, trees, signs, utility poles, signal poles, and anything else large enough to be a sight obstruction. Eliminate parking to remove obstructions to sight distance. In order to maintain the sight distance, the sight triangle must be within the right of way or a state maintenance easement (see Chapter 510).

The setback distance for the sight triangle is 18 feet from the edge of traveled way. This is for a vehicle stopped 10 feet from the edge of traveled way. The driver is almost always 8 feet or less from the front of the vehicle; therefore, 8 feet are added to the setback. When the stop bar is placed more than 10 feet from the edge of traveled way, providing the sight triangle to a point 8 feet back of the stop bar is desirable.

Provide a clear sight triangle for a P vehicle at all intersections. In addition, provide a clear sight triangle for the SU-30 vehicle for rural highway conditions. If there is significant combination truck traffic, use the WB-67 rather than the SU-30. In areas where SU-30 or WB vehicles are minimal and right of way restrictions limit sight triangle clearing, only the P vehicle sight distance needs to be provided.

At existing intersections, when sight obstructions within the sight triangle cannot be removed due to limited right of way, the intersection sight distance may be modified. Drivers who do not have the desired sight distance creep out until the sight distance is available; therefore, the setback may be reduced to 10 feet. Document the right of way width and provide a brief analysis of the intersection sight distance clarifying the reasons for reduction. Verify and document that there is no identified crash trend at the intersection. Document the intersection location and the available sight distance as a Design Analysis.

If the intersection sight distance cannot be provided using the reductions in the preceding paragraph, where stopping sight distance is provided for the major roadway, the intersection sight distance, at the 10-foot setback point, may be reduced to the stopping sight distance for the major roadway, with a Design Analysis and HQ Design Office review and concurrence. (See Chapter 1260 for required stopping sight distance.) Document the right of way width and provide a brief analysis of the intersection sight distance clarifying the reasons for reduction. Verify and document that there is no identified crash trend at the intersection. Document the intersection location and the available sight distance as a Design Analysis.

In some instances, intersection sight distance is provided at the time of construction, but subsequent vegetative growth has degraded the sight distance available. The growth may be seasonal or occur over time. In these instances, intersection sight distance can be restored through the periodically scheduled maintenance of vegetation in the sight triangle within the WSDOT right of way or state maintenance easement.


At intersections controlled by traffic signals, provide sight distance for right-turning vehicles. For intersections controlled by the geometry of roundabouts, see Chapter 1320.

Designs for movements that cross divided highways are influenced by median widths. If the median is wide enough to store the design vehicle, with a 3-foot clearance at both ends of the vehicle, sight distances are determined in two steps. The first step is for crossing from a stopped position to the median storage. The second step is for the movement, either across or left into the through roadway.

Design sight distance for ramp terminals as at-grade intersections with only left- and right-turning movements. An added element at ramp terminals is the grade separation structure. Exhibit 1310-19b gives the sight distance guidance in the vicinity of a structure. In addition, when the crossroad is an undercrossing, check the sight distance under the structure graphically using a truck eye height of 6 feet and an object height of 1.5 feet.

Document a brief description of the intersection area, sight distance restrictions, and traffic characteristics to support the design vehicle and sight distances chosen.

Exhibit 1310-19a Sight Distance at Intersections



$$S_i = 1.47Vt_g$$

Where:

S_i = Intersection sight distance (ft)
V = Design speed of the through roadway (mph)
t_g = Time gap for the minor roadway traffic to enter or cross the through roadway (sec)

Intersection Sight Distance Equation
Table 1

Design Vehicle	Time Gap (t_g) in Sec
Passenger car (P)	7.5
Single-unit trucks and buses (SU-30 & CITY-BUS)	9.5
Combination trucks (WB-40 & WB-67)	11.5

Note:
Values are for a stopped vehicle to turn left onto a two-lane two-way roadway with no median and grades 3% or less.

Intersection Sight Distance Time Gaps (t_g)
Table 2

Notes:

Adjust the tg values listed in Table 2 as follows:

Crossing or right-turn maneuvers:

All vehicles subtract 1.0 sec

Multilane roadways:

Left turns, for each lane in excess of one to be crossed, and for medians wider than 4 ft:

Passenger cars add 0.5 sec

All trucks and buses add 0.7 sec

Crossing maneuvers, for each lane in excess of two to be crossed, and for medians wider than 4 ft:

Passenger cars add 0.5 sec

All trucks and buses add 0.7 sec


Where medians are wide enough to store the design vehicle, determine the sight distance as two maneuvers.

Crossroad grade greater than 3%:

All movements upgrade for each percent that exceeds 3%:

All vehicles add 0.2 sec

Exhibit 1310-19b Sight Distance at Intersections



For sight obstruction driver cannot see over:

$$S_i = \frac{(26+b)(X)}{(18+b-n)}$$

Where:

S_i = Available intersection sight distance (ft)
n = Offset from sight obstruction to edge of lane (ft)
b = Distance from near edge of traveled way to near edge of lane approaching from right (ft) (b=0 for sight distance to the left)
X = Distance from centerline of lane to sight obstruction (ft)

For crest vertical curve over a low sight obstruction when S<L:

$$S_i = \sqrt{\frac{100L\left[\sqrt{2(H_1-HC)}+\sqrt{2(H_2-HC)}\right]^2}{A}}$$

$$L = \frac{AS_i^2}{100\left[\sqrt{2(H_1-HC)}+\sqrt{2(H_2-HC)}\right]^2}$$

Where:

Si = Available sight distance (ft)
H_1 = Eye height (3.5 ft for passenger cars; 6 ft for all trucks)
H_2 = Approaching vehicle height (3.5 ft)
HC = Sight obstruction height (ft)
L = Vertical curve length (ft)
A = Algebraic difference in grades (%)

1310.06 Signing and Delineation

Use the MUTCD and the *Standard Plans* for signing and delineation criteria. Provide a route confirmation sign on all state routes shortly after major intersections. (See Chapter 1020 for additional information on signing.)

Painted or plastic pavement markings are normally used to delineate travel paths. For pavement marking details, see the MUTCD, Chapter 1030, and the *Standard Plans*.

Contact the region or HQ Traffic Office for additional information when designing signing and pavement markings.

1310.07 Procedures

Document design decisions and conclusions in accordance with Chapter 300. For highways with limited access control, see Chapter 530.

1310.07(1) Approval

An intersection is approved in accordance with Chapter 300. Complete the following items, as needed, before intersection approval:

- Intersection Control Type Approval (see Chapter 1300)
- Design Analyses approved in accordance with Chapter 300
- Approved Traffic Signal Permit (DOT Form 242-014 EF) (see Chapter 1330)

1310.07(2) Intersection Plans

Provide intersection plans for any increases in capacity (turn lanes) at an intersection, modification of channelization, or change of intersection geometrics. Support the need for intersection or channelization modifications with history; school bus and mail route studies; hazardous materials route studies; pedestrian use; public meeting comments; etc.

For information to be included on the intersection plan for approval, see the Intersection/ Channelization Plan for Approval Checklist on the following website:

www.wsdot.wa.gov/design/projectdev/

1310.07(3) Local Agency or Developer-Initiated Intersections

Intersections in local agency and developer projects on state routes must receive the applicable approvals in section 1310.07(1) as part of the intersection design process.

The project initiator submits an intersection plan and the documentation of design decisions that led to the plan to the region for approval. For those plans requiring a Design Analysis, the Design Analysis must be approved in accordance with Chapter 300 prior to approval of the plan. After the plan approval, the region prepares a construction agreement with the project initiator (see the *Utilities Manual*).

1310.08 Documentation

Refer to Chapter 300 for design documentation requirements.

1310.09 References

1310.09(1) Federal/State Laws and Codes

Americans with Disabilities Act of 1990 (ADA) (28 CFR Part 36, Appendix A)

Revised Code of Washington (RCW) 35.68.075, Curb ramps for persons with disabilities – Required – Standards and requirements

Washington Administrative Code (WAC) 468-18-040, Design standards for rearranged county roads, frontage roads, access roads, intersections, ramps and crossings

WAC 468-52, Highway access management – Access control classification system and standards

1310.09(2) Design Guidance

Local Agency Guidelines (LAG), M 36-63, WSDOT

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT

1310.09(3) Supporting Information

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO

Aspects of Traffic Control Devices, Highway Research Record No. 211, pp 1 18, "Volume Warrants for Left-Turn Storage Lanes at Unsignalized Grade Intersections," Harmelink, M.D.

Guidelines and Recommendations to Accommodate Older Drivers and Pedestrians, FHWA-RD-01-051, USDOT, FHWA, May 2001

Highway Capacity Manual (HCM), Special Report 209, Transportation Research Board, National Research Council

Intersection Channelization Design Guide, NCHRP 279

Chapter 1320 Roundabouts

1320.01 General
1320.02 Roundabout Types
1320.03 Capacity Analysis
1320.04 Geometric Design
1320.05 Pedestrians
1320.06 Bicycles
1320.07 Signing
1320.08 Pavement Marking
1320.09 Illumination
1320.10 Road Approach, Parking, and Transit Facilities
1320.11 Geometric Design Peer Review
1320.12 Documentation and Approvals
1320.13 References

1320.01 General

Modern roundabouts are near-circular intersections at grade. They are an effective intersection type with fewer conflict points and lower speeds, and they provide for easier decision making than other intersection types. They also require less maintenance than traffic signals. Well-designed roundabouts have been found to reduce crashes (especially fatal and severe injury collisions), traffic delays, fuel consumption, and air pollution. They also have a traffic-calming effect by reducing vehicle speeds using geometric design rather than relying solely on traffic control devices.

Roundabout design is an iterative process.

A well-designed roundabout achieves a balance of safety and efficiency.

Good design is a process of creating the smooth curvature, channelization, and deflection required to achieve consistent speeds, well-marked lane paths, and appropriate sight distance.



Roundabout

The decision to install a roundabout is the result of an Intersection Control Analysis (see Chapter 1300) approved by the region Traffic Engineer or other designated authority.

1320.02 Roundabout Types

There are five basic roundabout types: mini, compact, single-lane, multilane, and teardrop described in the following sections.

1320.02(1) Mini-Roundabouts

Mini-roundabouts are small single-lane roundabouts generally used in 25 mph or less urban/suburban environments. Because of this, mini-roundabouts are typically not suitable for use on higher-volume (greater than 6,000 AADT) state routes. In retrofit applications, mini-roundabouts are relatively inexpensive because they normally require minimal additional pavement at the intersecting roads. A 2-inch mountable curb for the splitter islands and the central island is desirable because larger vehicles might be required to cross over it.

A common application is to replace a stop-controlled or uncontrolled intersection with a mini-roundabout to reduce delay and increase capacity. With mini roundabouts, the existing curb and sidewalk at the intersection can sometimes be left in place.

1320.02(2) Compact Roundabouts

Compact roundabouts are a hybrid of attributes found in mini- and single-lane roundabouts. Similar to a mini-roundabout, a compact roundabout may require minimal additional pavement, has a completely mountable center island, and in many cases existing curb or sidewalk can be left in place. As a result, compact roundabouts rarely require the purchase of right of way. Compact roundabouts are similar to single-lane roundabouts regarding design vehicle assumptions, ability to process traffic volumes, and signing.





Compact roundabouts



1320.02(2) Single-Lane Roundabouts

Single-lane roundabouts have single-lane entries at all legs and one circulating lane. They typically have mountable raised splitter islands, a mountable truck apron, and a landscaped central island.



Single-lane roundabout

1320.02(3) Multilane Roundabouts

Multilane roundabouts have at least one entry or exit with two or more lanes and more than one circulating lane. The operational practice for trucks negotiating roundabouts is to straddle adjacent lanes.



Multilane roundabout

1320.02(4) Teardrop Roundabout

Teardrops are usually associated with ramp terminals at interchanges: typically, at diamond interchanges. Teardrop roundabouts allow the "wide node, narrow link" concept. Unlike circular roundabouts, teardrops do not allow for continuous 360° travel resulting in less vehicle conflicts as traffic traveling on the crossroad (link) between ramp terminal intersections (nodes) does not encounter a yield as it enters the teardrop intersections. At higher ADT locations this lack of conflicting vehicles can result in a higher throughput, but can also result in limited gaps for the off ramp approach. Consult HQ or region Traffic Office for guidance.





Teardrop roundabouts

1320.03 Capacity Analysis

Use the capacity analysis completed as part of the Intersection Control Analysis (see Chapter 1300) to verify the number of lanes required for every individual movement in the design year.

1320.04 Geometric Design

1320.04(1) Selecting Shape and Placement

Roundabout shape is an important decision, because the shape can affect design elements that affect safety performance and operation of the roundabout.

1320.04(1)(a) Circular

The circular shape is the most desirable roundabout shape when constraints allow. If a circular shape is not feasible, contact the region Traffic Office to investigate other shapes described below. Sometimes a circular shape
can be used by slightly offsetting the placement of the roundabout.




Circular shape

1320.04(1)(b) Non-Circular

A non-circular roundabout is a good choice when constraints such as right of way, existing roadway alignments, buildings, and/or environmentally sensitive areas influence the shape.


Experiment with different roundabout sizes and radii, and use design vehicle turning software (such as AutoTURN®) to refine the shape to find the best operation while retaining desired speeds.



Non-circular roundabout with example dimensions

1320.04(2) Roundabout Design Elements

This section provides guidance for roundabout design elements. The photo below labels many of them.



Roundabout design elements

1320.04(2)(a) Curbing

All curbing within a roundabout should be rolled. The type of rolled curbing appropriate for a roundabout is shown in the Standard Plan Roundabout Cement Concrete Curbs: F-10.18.

Exception: existing curb untouched as part of a mini or compact roundabout installation may remain.

1320.04(2)(b) Truck Apron

A truck apron is the mountable portion of the central island used to accommodate the turning path of a design vehicle larger than a passenger vehicle or BUS, and helps to minimize the overall footprint of the roundabout. Generally, the truck tractor can traverse the roundabout in the circulating lane while the trailer is allowed to off track onto the apron. The apron is raised above the circulating path to provide guidance for drivers in the circulating lane.

A truck apron's width is based on the needs of the design vehicle. If buses are a consistent vehicle using the intersection try to minimize apron use for all movements, however this is not a requirement. Use turn simulation software (such as AutoTURN®) to fine tune the width of apron needed, so as not to design an apron that won't be used.

The apron color should be easily distinguishable in contrast with the adjacent circulating roadway and pedestrian facilities. Work with the region Landscape Architect (HQ Roadside and Site Development Section for regions without a Landscape Architect) for concrete color and texture.



Roundabout showing colored truck apron at central island and at buffer area between travel lanes and sidewalk

1320.04(2)(c) Central Island

The central island is the portion of the roundabout that is inside of the circulating roadway and typically includes an inside truck apron and a landscaped area (except for mini-roundabouts and compact roundabouts, which have no landscaped area and are entirely mountable).

Central island shape is a function of the site-specific needs of a roundabout intersection. It doesn't have to be an identical shape of the inscribed circle diameter (ICD) dimensions, but

should support the design principles of deflection and low speeds, and the accommodation of the design vehicle.


Roundabouts present opportunities to create community focal points, landscaping, and other gateway features within an intersection. The central island may include enhancements (such as landscaping, sculptures, or fountains), which serve both an aesthetic purpose and provide visual indication of the intersection for approaching motorists (this is particularly important for high speed approaches). Ideal central island treatments fit the context and result in minimal consequence to any vehicle that may encroach on the non-mountable portion of the central island. These treatments should not attract pedestrians to the central island, as pedestrians should never cross the circulating roadway. Work with the region Landscape Architect (HQ Roadside and Site Development Section for regions without a Landscape Architect) for central island features. See Chapter 950 Public Art for policy and guidance.

1320.04(2)(d) Splitter Island

A splitter island is the raised island at each two-way leg between entering and exiting vehicles, designed primarily to control the entry and exit speeds by providing deflection. They also discourage wrong-way movements, and provide pedestrian refuge. Splitter islands can have different shapes based on entry angle requirements and exit design speeds.

Raised channelization, or the appearance of raised curbing, is important, as research shows that drivers will slow down when they perceive that the driving width is narrowing.

The length of the splitter island will vary (typical lengths: 30 ft to 350 ft) based on the terrain, access considerations, site-specific mainline and crossroad operational speeds and the stepdown speeds to the final desired entry speed, which is usually 15–25 mph. (See 1320.04(3)(a) for using chicanes on higher-speed roadways.)



Splitter Island

Try to maximize the splitter island width adjacent to the circulating roadway. The larger achieved width, the better a driver approaching the roundabout can perceive whether a driver in the circulating lane will exit or continue inside the roundabout. This results in better gap acceptance. This may also support a better pedestrian refuge design.

1320.04(2)(e) Inscribed Circle Diameter (ICD)

The Inscribed Circle Diameter (ICD), that is, the overall outside diameter of a roundabout, is determined by the variables design vehicle, design speed, and the number of circulatory lanes.

The ranges of ICD in Exhibit 1320-1 are only suggestions to start a roundabout design. The ICD for noncircular shapes should be defined with dimensions along the X and Y axis.

Exhibit 1320-1 Suggested Initial Design Ranges

Design Element	Mini [1]	Compact	Single-Lane	Multilane
Number of Lanes	1	1+	1	2+
Inscribed Circle Diameter [2]	45’ – 80’	65’ – 120’	80’ – 150’	120’ – 165’
Circulating Roadway Width	N/A	N/A	14’ – 19’	29’
Entry Widths	N/A	N/A	16’ – 18’	25’

Notes:
The “+” symbol used here means that a portion of the circulating roadway may have more than one lane.
[1] Reserved for urban/suburban intersections with a 25 mph or less posted speed.
[2] The given diameters assume a circular roundabout; adjust accordingly for other shapes. Some conditions may require ICDs outside ranges shown here.

1320.04(2)(f) Entry

1. Deflection

Ideal alignment offers an entry design that provides deflection, speed control, and reasonable view angles to drivers while balancing property impacts and costs. While most intersections are at 90º angles and most through movements are straight, deflection contributes to the safety performance of a roundabout. Deflection is primarily achieved with the central island and supporting it with splitter islands on all entries to the roundabout.

2. Alignment Offset

There are three alignment choices for attaching entry legs to the circulatory roadway:

- The offset left alignment is preferred. It constrains the entry, slowing a vehicle's approach speed, and opens up the exit for efficient egress.
- The symmetrical alignment (if needed) is acceptable for lower speed contexts such as 30 mph.
- The offset right alignment tends to allow faster entry speeds and constrains the exit; it is undesirable.




Offset left alignment (preferred)

3. Entry Angle

To achieve the proper amount of deflection for each approach to a roundabout, there is a range of angle values that are desirable. This range is usually between 20 and 40 degrees. The purpose of entry angle is so vehicles don't hit broadside.

4. Entry Width


Entry width is determined by the turning template of the design vehicle turning through the entry curve at the desired entry speed. The ranges of entry widths in Exhibit 1320-1 are only suggestions to start a roundabout design.




Entry angle and width

5. Path Overlap

In a multilane roundabout, if the vehicles in the entry are aligned toward the central island or the truck apron, the vehicle on the right is pointed toward the inside lane and tends to go in that direction, while the vehicle on the left tends to be squeezed to the right toward the vehicle on the right. Avoid path overlap. Avoid a design that aligns an entering vehicle at the incorrect lane in the circulatory roadway. As a vehicle enters the circulating roadway it should be headed directly toward its respective lane within the circulating roadway. For multilane roundabouts, if inside lane is pointing at truck apron this is also considered to be path overlap. If right entry lane is pointing to left circulatory lane, then there is path overlap.



Path overlap conflict




Good path alignment

1320.04(2)(g) Right-Turn Slip Lanes

Right-turn slip lanes are a proven way to increase the "life" of an intersection by removing traffic that would otherwise enter the roundabout and reduce the available capacity to other movements. If a right-turn movement has 250 vehicles/hour or more, or if over 40% of the total approach volume is taking right turns, a slip lane should be considered.

The conflicting volume of vehicles on the merge will influence the length of merge lane prior to termination. Speeds can be very low and vehicles can take turns at these low speeds. Multimodal considerations will influence the length based on crosswalk location and bicycle use.



Right-turn slip lanes showing merge and yield termination

1320.04(3) Speed Control

Roundabout operation performance is dependent on low, consistent vehicle speeds. Low and consistent operating speeds facilitate appropriate gap acceptance by an entering driver. Design for travel path operating speeds between 15 mph and 25 mph (see 1320.04(3)(b)). Design to have low-speed differentials (12 mph or under) between entering and circulating traffic. Multilane roundabouts might have higher speeds along their respective travel paths, but generally 30 mph or less.


The ideal design speed mechanism has the entry and circulating speeds being similar. This varies due to size, shape and context of the roundabout.

The vehicle then moves into and through the circulation lane, being controlled all along by the design speed of the circulating lane. The circulating design speed controls the exit speed; therefore, the exit design speed, as calculated in the Travel Path section below, is not as critical.

Designing geometric entry speed control encourages lower speeds and lower speed differentials at conflict points, which reduces the potential for collisions.

1320.04(3)(a) Chicanes

Chicanes are a type of horizontal deflection used in traffic calming to reduce the speed of vehicles. Research has shown that chicanes have value in slowing down higher approach speeds.




Chicane

Consider chicanes where posted speeds near the roundabout are 45 mph or higher. Design chicane curves with successively smaller radii in order to successively reduce vehicle speeds approaching the roundabout entry. Use Exhibit 1320-2 to determine the radii-speed relationship (the radii are measured using the offsets recommended in the Travel Paths section). The normal cross slope (superelevation in 1320-2) is 2% however, site conditions may require more based on how you tilt the plane of the roundabout for site specific conditions. A minus (-) 2% drains toward the central island.


Also, consider the grade of the roadways that enter the roundabout, because a vehicle can more easily slow down on an upgrade than on a downgrade. Adjust the length of the deceleration based on the "Adjustment Factors for Grades Greater Than 3%" in *Design Manual* Exhibit 1360-10.


1320.04(3)(b) Travel Paths

Travel path calculations can be used on all roundabout designs to get an understanding of speeds for different paths throughout the roundabout. A travel path is the shortest path through the roundabout, no closer than 5 feet from any curb face or lane line as shown. Use Exhibit 1320-2 and R_1 through R_5 to determine Travel Path speeds.




Travel paths





Source: NCHRP

Exhibit 1320-2 Radii-Speed Relationship on Approach Legs and R Value Relationships



1320.04(4) Grades


Do not use grades as a constraint during scoping to rule out a roundabout. Be aware of how the profiles mesh with sight distances and ADA pedestrian requirements.

1320.04(4)(a) Circulatory Roadway

The circulatory roadway grade value should not exceed 4%. Terrain may require benching the roundabout to fit conditions.

1320.04(4)(b) Grade Transitions for Roadway Entry and Exit to the Circulatory Roadway

Consider the grade transitions and make them as long as feasible. When designing for pedestrians see Chapter 1510 and work with region ADA subject matter expert to ensure that grades for ADA compliance at all pedestrian crossing are met.




Grades and preferred cross slope

1320.04(5) Circulatory Roadway Cross Slope

The circulatory roadway cross slope may range from 1.5% to 4.0% (2.0% preferred), away from the central island to promote lower circulating speeds, improve central island visibility, minimize breaks in cross slope of entry and exit lanes, and facilitate drainage of water to the outside of the roundabout.

Sometimes roundabouts have to be built on a titled plane or benched and cross slope conditions will vary by leg or quadrant on the circulating roadway and may fall outside the 1.5% - 4.0% range. However, it is desirable to match existing ground elevation as much as possible.



Drawing shows preferred slopes. Site conditions and drainage may require slopes outside these ranges.

Cross slopes

1320.04(6) Design Tools

During the scoping or preliminary geometric design process, do not to use truck turning paths alone as a constraint to eliminate a roundabout at an intersection. There are several design tools available to aid in the design of a roundabout. It is important to understand how the software works, its default settings, and its application to the design process.

1320.04(6)(a) Design Vehicle Assumptions

While all highway-to-highway movements require accommodating a WB-67, there are certain assumptions that must be made with software programs that replicate truck swept paths. Determine which truck percentage defaults are to be used (recognizing that truck percentages can range from 2% to 20%) so that different segments can be modeled accurately. Recognize that within a set percentage, WB-67s may only represent a small sample of the entire truck volume on any given day. Therefore, consider whether a WB-67 should be designed for, or accommodated (also see Chapter 1103).

1. Designing for a WB 67

A roundabout that is being designed for a WB-67 may result in wider lane widths and a larger Inscribed Circle Diameter. For this situation, rolled curb design is critical to the truck's traversing the roundabout (see *Standard Plan* F-10.18 for curb details). Outside aprons may not be needed in many situations based on AutoTurn® modeling and knowledge of driver turning behavior when encountering geometric features.

2. Accommodating a WB 67

A roundabout that is designed to accommodate a WB-67 assumes that a WB-67 could utilize truck aprons to maneuver through the roundabout, if necessary, which should reduce the overall footprint of the roundabout. For this situation, rolled curb is critical to the truck's traversing the roundabout confidently. Although outside truck aprons are needed infrequently, there may be situations where the design may need to incorporate them. Contact HQ Traffic for guidance.

1320.04(6)(b) Truck Swept Path


In some cases, roundabouts of the perfect circular variety with symmetrical roadway attachments require less specific knowledge of truck-turning software and its applications. However, when looking at a non-circular shaped roundabout where the combination of the truck's speed, its turning angle settings, its rear axle locations, and its alignment are the critical design elements to address, a mastery of the software is required. Designers that are unfamiliar with how to apply the software inputs accurately to model a truck's swept path need to contact HQ Traffic Office for guidance. Poor alignment of a truck swept path can result in unnecessarily large roundabout footprints, higher than desired Travel Path speeds, or uncomfortable driving maneuvers by the freight community.

Assume that a truck will travel much slower through a roundabout than the Travel Path speed calculated for passenger vehicles (see 1320.04(3)(b)). Adjust the software input to allow a slower truck speed in order to make a good engineering judgment about how fast a truck may use a roundabout (for example, for AutoTURN® use 5 mph). Design tool default settings don't necessarily allow the maximization of the tool and can prohibit the designer from getting a good, balanced design between passenger car speeds and truck accommodation.



Single lane roundabout - Truck using the truck apron

When using a truck-turning software tool like AutoTURN® on multilane roundabouts, assume a truck's travel path will occupy (straddle) parts of two adjacent lanes.




Multilane roundabout - truck straddles lanes

1320.04(7) Sight Distance

Sight distance is an important design consideration at roundabouts. Restricting sight distance across the central island with strategic landscaping may enhance the intersection by making the intersection a focal point and encouraging lower speeds. Work with the region Traffic Engineer and Landscape Architect (HQ if there is no region contact) to determine this balance. Provide sight triangle plan sheets for consideration of landscape design.

1320.04(7)(a) Stopping

Use the design stopping sight distance in Chapter 1260. Anticipated speeds throughout the roundabout can be calculated using Exhibit 1320-2, based on the Travel Path radius and direction of the particular curve. The design stopping sight distance is measured along the vehicle's path as it follows the curvature of the roadway; it is not measured as a straight line.




Sight distance – Approach and Exit


1320.04(7)(b) Intersection


Provide minimum intersection sight distance. Longer sight distances can lead to higher vehicle speeds that reduce gap opportunities for entering vehicles. For intersection sight distance at roundabouts, provide entering vehicles a clear view of traffic on the circulating roadway and on the immediate upstream approach in order to aid in judging an acceptable gap.

The intersection sight distance at roundabouts is given in Exhibit 1320-3. The S_1 intersection sight distance is based on the average of the entering and circulating speeds, and the S_2 intersection sight distance is based on the left-turning speed. The sight distance may also be calculated using the intersection sight distance equation given in Chapter 1310 using a time gap (tg) of 4.5 seconds.

Exhibit 1320-3 Intersection Sight Distance







1320.04(8) Railroad Crossings

Although it is undesirable to locate any intersection near an at-grade railroad crossing, this situation exists at many locations on the highway system. Experience shows that a roundabout placed near a crossing has some operational advantages. If there is a railroad crossing near the roundabout contact HQ Traffic Office for further guidance.

1320.05 Pedestrians

As part of the approved Intersection Control Analysis (ICA), it has already been determined whether pedestrians will use the roundabout and, if so, which legs (see Chapter 1300).

With the knowledge of where pedestrian facilities are needed, design the roundabout while keeping in mind the ADA requirements for crosswalks, sidewalks, paths, and other pedestrian facilities.


1320.05(1) Crossing Location

The pedestrian crossing located on the entry side of a roundabout leg should be at least 20 feet from the yield line so that a pedestrian can walk behind a vehicle that is waiting at the yield line. If there is an extremely large truck percentage, consider moving the crossing to accommodate the most common truck.

The crossing located in the exit side of the roundabout leg can be closer to the roundabout, because as the vehicles leave the roundabout, they accelerate and make it harder to find a break in traffic. As speed increases, drivers are less likely and less able to stop. Verify that no significant, large sight obstructions are located within the sight lines.

1320.05(2) Splitter Island Pass Through

Design the splitter island pass through a minimum of 5 feet wide, or the width of the sidewalk, whichever is greater. The length of the pass through (measured back of curb to back of curb of the splitter island) is to be a minimum of 6 feet long measured along the shortest section of the pedestrian path. Consider a "V" shape pass through as shown.



Splitter island pass through

1320.05(3) Buffers

Wherever feasible, separate sidewalks from the curb with a buffer. Landscaping or colored concrete are acceptable for the buffer. See WSDOT *Standard Plan F10-18* for dimension details. Do not compromise required vehicle sight triangle needs.

The buffer discourages pedestrians from crossing to the central island or cutting across the circulatory roadway of the roundabout. It also helps guide pedestrians with vision impairments to the designated crosswalks, and can accommodate the occasional inexperienced truck driver who encroaches up onto a curb while traversing through the roundabout.

1320.05(4) Curb Ramps

Roundabouts with buffers typically have combination-type curb ramps; otherwise, parallel curb ramps are normally used. (See Chapter 1510 and the *Standard Plans* for curb ramp information.)


1320.05(5) Sight Triangles

A vehicle sight triangle specific to pedestrians (see 1320.04(7)) must include the whole curb ramp, including the landing, where pedestrians are likely to wait to cross.

It is also important that pedestrians are also able to see approaching vehicles.

1320.05(6) Pedestrian Beacons

On multilane roundabouts, consider installing pedestrian beacons to warn drivers when a pedestrian wants to cross the roadway. Work with the region Traffic Engineer on types and locations of pedestrian beacons.



Pedestrian beacons


1320.06 Bicycles

Provide bicyclists with similar options to negotiate roundabouts as they have at other intersections. Consider how they navigate either as motor vehicles or pedestrians depending on the size of the intersection, traffic volumes, their experience level, and other factors.

Bicyclists are often comfortable riding through single-lane roundabouts in low-volume environments in the travel lane with motor vehicles, as speeds are comparable and potential conflicts are low.

At larger or busier roundabouts, cyclists may be more comfortable using ramps connecting to a sidewalk around the perimeter of the roundabout as a pedestrian. Where bicycle lanes or shoulders are used on approach roadways, they should end before the geometry changes the approach to the roundabout.

Contact the HQ Design Office for bicycle ramp design options.



Bicycle rider using lane

1320.07 Signing

The graphic shown is an example of potential signing for a single-lane roundabout. For additional information, refer to the MUTCD, Plan Sheet Library, and the *Standard Plans* for details on signing.

A preliminary sign plan is developed to identify existing and proposed signing on state highways. Sign plans on state routes are to be reviewed and approved by the region Traffic Engineer and then furnished to the HQ Traffic Office for review.

The plan provides an easily understood graphic representation of the signing, and it provides statewide uniformity and consistency for regulatory, warning, and guide signs at roundabouts on the state highway system. For roundabouts located near a port, industrial area, or route that accommodates oversize loads, consider using perforated square steel posts.



Signing example

1320.08 Pavement Marking

See *Standard Plan* M-12.10 for roundabout pavement marking details. Consult region Traffic on traffic pavement markings and materials.

1320.09 Illumination

Provide illumination for each of the conflict points between circulating and entering traffic in the roundabout and at the beginning of the raised splitter islands. Illuminate raised channelization or curbing. Position the luminaires on the upstream side of each crosswalk to improve the visibility of pedestrians. Light the roundabout from the outside in toward the center. This improves the visibility of the central island and circulating vehicles to motorists approaching the roundabout. Ground-level lighting within the central island that shines upward toward objects in the central island can also improve their visibility. Consult with the region Traffic office for illumination design. (See Chapter 1040 for additional information on illumination.) On higher-speed approaches, consider internally illuminated bollards (IIB) in lieu of other illumination.

1320.10 Road Approach, Parking, and Transit Facilities

Road approach (road or driveway) connections to the circulating roadway are not allowed at roundabouts unless they are designed as a leg to the roundabout. It is desirable that road approaches not be located on the approach or departure legs within the length of the splitter island. The minimum distance from the circulating roadway to a road approach is controlled by corner clearance using the outside edge of the circulating roadway as the crossroad. When minimum corner clearance cannot be met, document the decision in accordance with Chapters 530 and 540.

If a parcel adjoins two legs of the roundabout, it is acceptable to provide a right-in/right-out driveway within the length of the splitter islands on both legs. This provides for all movements; design both driveways to accommodate their design vehicles.

Roadways between roundabouts may have restrictive medians with left-turn access provided with U-turns at the roundabouts.

Parking is not allowed in the circulating roadway or on the entry or exit roadway within the length of the splitter island.

Transit stops are not allowed in the circulating roadway, in the approach lanes, or in the exit lanes prior to the crosswalk. Locate transit stops on the roadway before or after the roundabout, in a pullout, or where the pavement is wide enough that a stopped bus does not block the through movement of traffic or impede sight distance.



Right in / right out driveways

1320.11 Geometric Design Peer Review

Conduct a peer review of the roundabout design with the following participants.

- Region Traffic Office
- Assistant Sate Traffic Engineer
- Region Project Development Engineer or Engineering Manager
- Assistant State Design Engineer

The intent of this meeting is to review, discuss, evaluate, and provide feedback on the 2-D roundabout layout design in order to finalize the channelization plan.

1320.12 Documentation and Approvals

Refer to Chapter 300 for design documentation and approval requirements.

1320.13 References

1320.13(1) Federal/State Laws and Codes

See Chapter 1510 for Americans with Disabilities Act Policy and references

Revised Code of Washington (RCW) 47.05.021, Functional classification of highways

Washington Administrative Code (WAC) 468-58-080, Guides for control of access on crossroads and interchange ramps

1320.13(2) Design Guidance

Roundabout Cement Concrete Curbs: *Standard Plan F-10.18-00*

Roundabout Pavement Markings: *Standard Plan M-12.10*

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA, as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)

Standard Plans for Road, Bridge, and Municipal Construction (*Standard Plans*), M 21 01, WSDOT

Standard Specifications for Road, Bridge, and Municipal Construction (*Standard Specifications*), M 41-10, WSDOT

1320.13(3) Supporting Information

Roundabouts: An Informational Guide Second Edition, NCHRP Report 672, Transportation Research Board, 2010 http://nacto.org/docs/usdg/nchrprpt672.pdf

Roundabouts: An Informational Guide, FHWA-RD-00-067, USDOT, FHWA http://www.fhwa.dot.gov/publications/research/safety/00067/index.cfm

Highway Capacity Manual 2010 (HCM 2010), Transportation Research Board, National Research Council, Washington D.C., 2000

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO

"Crash Reductions Following Installation of Roundabouts in the United States," Insurance Institute for Highway Safety, March 2000
https://www.dot.ny.gov/main/roundabouts/files/insurance_report.pdf

"Long-Term Trends in Public Opinion Following Construction of Roundabouts," Insurance Institute for Highway Safety, 2007
http://trrjournalonline.trb.org/doi/abs/10.3141/2019-26

Truck and Bus Safety; Roundabouts, Journal of the Transportation Research Board No. 2585, 2016.
http://trrjournalonline.trb.org/toc/trr/2585/

Understanding Flexibility in Transportation Design – Washington, WSDOT, 2005
www.wsdot.wa.gov/research/reports/600/638.1.htm

Chapter 1330 Traffic Control Signals

1330.01 General
1330.02 Procedures
1330.03 Intersection Design Considerations
1330.04 Conventional Traffic Signal Design
1330.05 Preliminary Signal Plan
1330.06 Operational Considerations for Design
1330.07 Documentation
1330.08 References

1330.01 General

Traffic control signals are automated traffic control devices that warn or direct motorists to take a specific action. Traffic control signals are used to control the assignment of right of way at locations where conflicts with motorists, bicyclists, and pedestrians exist or where passive devices such as signs and markings do not provide the necessary flexibility of control to move motorists, bicyclists, and pedestrians in an efficient manner.

The decision to install a traffic signal is the result of an Intersection Control Analysis (ICA) (see Chapter 1300) that is approved by the region Traffic Engineer or other designated authority.

1330.02 Procedures

1330.02(1) Traffic Signal Permit

State statutes (RCWs) require Washington State Department of Transportation (WSDOT) approval for the design and location of all conventional traffic signals and some types of beacons located on city streets forming parts of state highways. Approval by WSDOT for the design, location, installation, and operation of all other traffic control signals installed on state highways is required by department policy.

The Traffic Signal Permit (DOT Form 242-014 EF) is the formal record of the signal warrant analysis required by the MUTCD and the department's approval of the installation and type of signal. Permits are required for the following types of signal installations:

- Conventional traffic signals
- Emergency vehicle signals
- Intersection control beacons
- Lane control signals
- Movable bridge signals
- Ramp meter signals
- Pedestrian signals
- Pedestrian Hybrid Beacon signals ("HAWK" signals)
- Temporary traffic signals (only when not being used in place of a permanent, permitted signal)
- Queue-cutter traffic signals

The Permit and its supporting data must be included in the Design Documentation Package (DDP.) The permit is completed by the requesting agency and submitted, complete with supporting data, through the region Traffic Office to the approving authority for approval. See 1330.02(1)(a) for Signal Warrant information required as part of the supporting documentation.

The approving authority is the Regional Administrator or authorized delegate. The approving authority approves or denies the application and sends it back to the region Traffic Office. The region Traffic Office retains a record of the approved permit and supporting data and forwards a copy of the Permit and the supporting data to the State Traffic Engineer at WSDOT Headquarters (HQ). Preserve the approved permit as required by 1330.07 Documentation.

Emergency vehicle signals require annual permit renewal. The region Traffic Office reviews the installation for compliance with requirements. If satisfactory, the permit is renewed by the Regional Administrator with a letter to the operating agency. A copy of this letter is also sent to the State Traffic Engineer.

Permits are not required for portable traffic signals, speed limit sign beacons, stop sign beacons, or lane assignment signals at toll facilities.

A new permit application is required when the level of control is increased, such as changing from an intersection control beacon to a conventional traffic signal or adding an approach to an existing signal system.

For a reduction in the level of control, such as converting a conventional signal to a flashing intersection beacon or removal of the signal, submit the "Report of Change" portion of the traffic signal permit, complete with supporting data, to the approving authority, with a copy to the region Traffic Office and State Traffic Engineer.

If experimental systems are proposed, region Traffic Engineer review and approval is required. The region Traffic Office will send the approved proposal to the State Traffic Engineer for review and approval. The State Traffic Engineer will forward the approved proposal to FHWA for their approval. A copy of the approval from FHWA will be returned and must be preserved as required by 1330.07 Documentation.

Any signal system requiring a permit, with the exception of Ramp Meter signals, also requires Preliminary Signal Plan approval from the WSDOT HQ Traffic Office (see 1330.05).

1330.02(1)(a) Signal Warrants

A signal warrant is a minimum condition that is to be met before a signal may be considered for installation. Satisfying a warrant does not mandate the installation of a traffic signal. The warranting condition(s) supports the inclusion of a traffic signal for consideration as part of the Intersection Control Analysis performed during the scoping of the project (see Chapter 1300). For a list of the traffic signal warrants and information on how to use them, see the *Manual on Uniform Traffic Control Devices* (MUTCD). Contact the region Traffic Engineer for region specific practices Address all warrants listed in the currently adopted MUTCD as part of the Signal Warrant Analysis. Mark warrants which do not apply as "Not Applicable" and include a basic supporting statement or similar justification. Include the Signal Warrant Analysis in the Signal Permit supporting data.

1330.02(2) Responsibility for Funding, Construction, Maintenance, and Operation

Responsibility for the funding, construction, maintenance, and operation of traffic signals on state highways has been defined by legislative action and Transportation Commission resolutions (see Exhibit 1330-1). Responsibilities vary depending on location, jurisdiction, and whether or not limited access control has been established. Limited access as used in this chapter refers to full, partial, or modified limited access control that has been established as identified in the Access Control Tracking System:
www.wsdot.wa.gov/design/accessandhearings/tracking.htm

Exhibit 1330-1 Responsibility for Facilities

Responsibility for Various Types of Facilities on State Highways				
Area	**Responsibility**	**Emergency Vehicle Signals**	**Traffic Signals, Pedestrian Signals, & Intersection Control Beacons**	**Reversible Lane Signals & Movable Bridge Signals**
Cities with a population of 25,000 or greater	Finance Construct Maintain Operate	ESD [1] ESD [1] ESD [1] ESD [1]	City [2] City [2] City [2] City [2]	City [2] City [2] City [2] City [2]
All other locations	Finance Construct Maintain Operate	ESD [1] ESD [1] ESD [1] ESD [1]	State/County [3] /Other [4] State/County [3] /Other [4] State State	State State State State

Notes:
[1] ESD refers to the applicable Emergency Service Department.
[2] Does not apply to state highways with established limited access control (see 1330.02(2)(c)).
[3] Beyond corporate limits due to county activity (see 1330.02(2)(d)).
[4] Other refers to signals proposed by or required due to third party activity (see 1330.02(2)(g)).

(a) Inside the corporate limits of cities with a population of 25,000 or greater where there is no established limited access control: The city is responsible for the funding, construction, maintenance, and operation of traffic signals. Population figures can be found at:
www.ofm.wa.gov/pop/

(b) Inside the corporate limits of cities with a population of less than 25,000: WSDOT is responsible for funding, construction, maintenance, and operation of traffic signals. Population figures can be found at: www.ofm.wa.gov/pop/

(c) Inside the corporate limits of cities with a population of 25,000 or greater where there is established limited access control: WSDOT is responsible for funding, construction, maintenance, and operation of traffic signals. Population figures can be found at:
www.ofm.wa.gov/pop/

(d) Outside the corporate limits of cities and outside established limited access control areas: WSDOT is responsible for funding, construction, maintenance, and operation of a traffic signal when a new state highway crosses an existing county road. When a new county road intersects an existing state highway, WSDOT is responsible for only the maintenance and operation of a traffic signal. The county is responsible for the construction costs of the traffic signal and associated illumination. When it is necessary to construct a traffic signal at

an existing county road and state highway intersection, the construction cost distribution is based on the volume of traffic entering the intersection from each jurisdiction's roadway. The county's share of the cost, however, is limited to a maximum of 50%. The state is responsible for maintenance and operation (WAC 468-18-040).

(e) Outside the corporate limits of cities and inside established limited access control areas: WSDOT is responsible for funding, construction, maintenance, and operation of traffic signals.

(f) Emergency vehicle signals: The emergency service agency is responsible for all costs associated with emergency vehicle signals.

(g) Third party agreement signals: At those locations where WSDOT is responsible for traffic signals and third party activity justifies the installation of a traffic signal, as determined by an ICA, the following rules apply:


- The third party is responsible for funding the design and construction of the traffic signal system, unless another arrangement is agreed upon with WSDOT.
- The third party obtains a traffic signal permit.
- The third party agrees to design and construct the traffic signal in conformance with WSDOT's guidelines and requirements.
- The third party agrees to submit the design and construction documents to WSDOT for review and approval by the region Traffic Engineer.
- Preserve all third party provided documents and any third party agreement(s) as required by 1330.07 Documentation.

1330.03 Intersection Design Considerations

Signalized intersections require different design considerations than non-signalized intersections. These elements should be considered as early as the ICA process (see Chapters 1300 and 1310 for further guidance.) This Section discusses basic intersections with relatively simple geometry. For more complex or innovative intersection layouts such as Diverging Diamond Interchanges (DDIs), Displaced Left Turns (DLTs), or Single Point Urban Interchanges (SPUIs), contact the WSDOT HQ Traffic Office for support.

Consider providing an unrestricted through lane on the major street of a T intersection (sometimes referred to as a Continuous Green "T" (CGT) intersection). This design allows for one traffic movement to flow without restriction. When this is used on through roadways with a posted speed of 45 MPH or greater, the through lane must be separated by a physical barrier or the through movement must also be signalized. If there is a crosswalk across the through lane, the through lane must be signalized. Exhibit 1330-2 shows an example of a CGT intersection.

Exhibit 1330-2 Example Continuous Green "T" (CGT) Intersection Layout



1330.03(1) Left Turns

It is recommended that a left turn storage lane be provided for all main line roadways where left turns are allowed. This helps to avoid having stopped traffic in a through lane with a green through signal display. This also helps to support potential future changes in left turn operations. See Section 1330.06(1) for additional discussion.

Left-turning traffic can operate more efficiently when the opposing left-turn lanes are directly opposite each other. When a left-turn lane is offset into the path of an opposing through lane, the left-turning driver may assume the opposing vehicles are also in a left-turn lane and fail to yield. To prevent this occurrence, less efficient split phasing may be necessary. (See Chapter 1310 for guidance on lane offsets and opposing left-turn clearance.) Where there are opposing through lanes but no opposing left turn lane, install a striped or raised median area opposite the left turn lane if possible.

Place stop lines so that they are out of the path of conflicting left turns. Check the geometric layout by using turning templates or a computerized vehicle turning path program (such as AutoTURN®) to determine whether the proposed layout and phasing can accommodate the design vehicles. Also, check the turning paths of opposing left-turn movements. In many cases, the phase analysis might recommend allowing opposing left turns to run concurrently, but the intersection geometrics are such that this operation cannot occur. The intersection should be large enough to accommodate opposing left turning vehicle paths with a 4-foot minimum (12-foot desirable) separation between them. Where this separation cannot be achieved, less efficient signal phasing may be required to accommodate opposing left turns.


Some intersections may have multi-lane left turns. At locations with closely spaced intersections, a multi-lane left-turn storage area might be the only solution to reduce the potential for the left-turn volume to back up into an adjacent intersection. As with single left turn lanes, the intersection should be large enough to accommodate opposing left turning vehicle paths with a 4-foot minimum (12-foot desirable) separation between them. Where this separation cannot be achieved, less efficient signal phasing may be required to accommodate opposing left turns.

At smaller intersections, the opposing single-lane left-turn movement might not be able to turn during the two-lane left-turn phase and it might be necessary to reposition this lane. If the opposing left turns cannot time together, the reduction in delay from the two-lane left-turn


phase is likely to be nullified by the requirement for a separate opposing left-turn phase. Exhibit 1330-3 shows two examples of two-lane left turns with opposing single-left arrangements.

Two receiving lanes are required for two-lane left-turn movements. In addition, these receiving lanes are to extend well beyond the intersection before reducing to one lane. A lane reduction immediately beyond the intersection can cause delays and backups into the intersection because the left-turning vehicles usually move in dense platoons, which may make merging and lane changes difficult. (See Chapter 1310 for guidance on lane reductions on intersection exits.)

Exhibit 1330-3 Left-Turn Lane Configuration Examples



Single left turn lane not offset – overlapping left turn paths



Offset single left turn lane – opposing lefts no longer in conflict

1330.03(2) Right Turns

Large right-turn curb radii at intersections sometimes have impacts on traffic signal operation. Larger radii allow faster turning speeds and might move the pedestrian entrance point farther away from the intersection area. Pedestrian crossing times are increased because of the longer crossing, thereby reducing the amount of time available for vehicular traffic. (See Chapter 1310 for guidance on determining these radii.)

At intersections with large right-turn radii, consider installing raised traffic islands. These islands are primarily designed as pedestrian refuge areas. (See Chapter 1510 for pedestrian refuge islands and traffic island designs.) Traffic islands may decrease the required pedestrian clearance intervals; however, large radii and raised traffic islands may make it difficult for pedestrians to navigate the intersection. Where pedestrians are expected to cross a right turn lane to a traffic island, it is recommended to use a compound right turn-lane design as shown in Chapter 1310.


1330.03(3) Pedestrian Features

Additional sidewalk criteria must be met to accommodate pedestrians at signalized intersections. Mobility assistance devices such as wheelchairs and scooters add complexity to the system design. Coordination is required between sidewalk design, curb ramp design and pedestrian pushbutton (PPB) placement. In most cases, an initial sidewalk and curb ramp design should be developed, and then adjustments made as necessary to accommodate the PPBs and ensure that the pedestrian access route is maintained (See Chapter 1510 for more information on accessible pedestrian routes.) The following describe the required level clear space for PPBs (see Exhibit 1330-4):

- The level clear space must be a minimum of 36 inches by 60 inches in size, unobstructed, with the PPB centered along one of the 60 inch sides. Possible obstructions include the pole baseplate and the pushbutton itself.
- 12 inches of additional traversable surface (such as sidewalk) is required at each end of the 60 inch level clear space for a total unobstructed area of 36 inches by 84 inches. Curb ramp slopes are considered traversable for these purposes.
- To be considered level, the level clear space may have a maximum of 2% cross slope and 2% running slope.

  Note: It is recommended that cross slopes and running slopes be designed to be less than the allowed maximum to allow for some tolerance in construction. For example, design the level clear space for a maximum 1.5% cross slope and running slope (rather than 2% maximum).
- The level clear space should be centered relative to the pole with the PPB either facing the level clear space, or with the face of the PPB rotated up to 90 degrees as needed to align the tactile arrow of an APS PPB with the direction of crossing.
- The level clear space should be as close to the PPB as possible, but may be up to 9 inches away from the center of the physical pushbutton (i.e., not the housing or assembly), as measured perpendicular from one of the 60 inch sides. Measuring from the center of the pole upon which the PPB is mounted will normally result in the PPB meeting the 9 inch reach requirement.

Exhibit 1330-4 Basic Level Clear Space for Pedestrian Pushbuttons



PPBs at newly constructed/reconstructed intersection quadrants must meet the above criteria.

The level clear space for the PPB is not required to be concurrent with sidewalk ramp landings, but using one level clear space for both is desirable and does occur frequently. Exhibits 1330-5a and 1330-5b show examples of how the level clear space for the PPB overlays with typical perpendicular and parallel ramp designs. The 48 inch by 48 inch dimensions shown are the typical required level landings for curb ramps.

PPBs at existing intersection quadrants that are not being reconstructed should meet as many of these criteria as possible. If it is not possible to get the level clear space close enough to the pole, an extension may be used to get the PPB itself within 9 inches of the level clear space. Extensions may only be used when no other alternative is physically possible, and are limited to 12 inches in length. See 1330.04(4) for additional requirements.

Exhibit 1330-5a Example Basic Perpendicular Ramp PPB Level Clear Space






Exhibit 1330-5b Example Basic Parallel Ramp PPB Level Clear Space





1330.03(4) Road Approaches and Driveways

If roadway approaches and driveways are located too close to an intersection, the traffic from these facilities can affect signal operations. Consider eliminating the accesses or restricting them to "right in/right out". If a driveway or road approach is directly opposite a leg of the intersection, that approach may be signalized. If the approach is signalized, it must be signalized as if it were a standard intersection leg, and the pedestrian crossing across the approach must also be signalized as if it were a standard crosswalk.

Management of driveways and road approaches should be determined early (preferably no later than scoping) so that they can be considered and addressed in the design. (See Chapters 530 and 540 for further guidance.) Consider shifting the location of advance detection upstream to clear an access point so that vehicles entering from the access point will not affect detection and operation of the signal.

1330.03(5) Skewed Intersections

Skewed intersections, because of their geometry, are challenging to signalize and delineate. Where feasible, modify the skew angle to provide more normal approaches and exits. In many cases, the large paved areas for curb return radii at skewed intersections can be reduced when the skew angle is reduced. (See Chapter 1310 for requirements and design options.) Visibility of pedestrians is of particular concern, and must also be taken into consideration.

1330.03(6) Transit Stops

Transit stop and pullout locations should be located on the far side of the intersection to minimize their impacts on signal operation. (See Chapter 1430 for transit stop and pullout designs.)


1330.03(7) Railroad Crossings

Where railroad preemption is used at a signalized intersection, install left and right turn lanes for the movements leading to the leg of the intersection with the railroad crossing if possible. This greatly improves the efficiency of the signal during railroad preemption when turns are restricted. Also consider providing a left-turn lane for the minor leg opposing the railroad crossing. This will allow for more effective signal operations during long periods of railroad preemption.

Where there is less than 40 feet between the nearest rail and the normal location of the stop line, do not install a stop line between the tracks and the intersection. Use the same stop line for the traffic signal and the rail crossing instead. Exhibit 1330-6 shows recommended intersection features for intersections near rail crossings.

Contact the WSDOT HQ Traffic Office for assistance with standalone queue-cutter signals.

Exhibit 1330-6 Recommended Features for Intersections Near Rail Crossings



1330.04 Conventional Traffic Signal Design

1330.04(1) General

The goal of any traffic signal design is to assign right of way in the most efficient manner possible and still be consistent with traffic volumes, intersection geometrics, and safety.

An advanced signalized intersection warning sign and beacon assembly to warn motorists of a signalized intersection should be installed when either of the two following conditions exists:

(a) The visibility requirements in the MUTCD are not achievable.


(b) The posted speed is 55 mph or higher and the next nearest signalized intersection is more than 2 miles away; this does not apply to freeway off-ramps.

This warning sign and beacon assembly consists of a W3-3 sign with Type IV reflective sheeting and one or two continuously flashing beacons. Where two beacons are used, the beacons should flash alternately instead of simultaneously. Locate the sign in advance of the intersection in accordance with Table 2C-4 (Condition A) of the MUTCD. The warning sign and beacon assembly may be omitted with approval from the region Traffic Engineer.

1330.04(2) Signal Phasing

With some exceptions, the fewer the traffic signal phases, the more efficient the operation of the traffic signal. The number of phases required for efficient operation is related to intersection geometrics, traffic volumes, composition of traffic flow, turning movement demands, and desired level of driver comfort. The traffic movements at an intersection have been standardized to provide consistency in both traffic signal design and driver expectations. (See Exhibit 1330-7 for standard intersection movements, signal head (display) numbering, and standard phase operation.)

Exhibit 1330-7 Standard Intersection Movements, Head Numbers, and Phase Operation



For WSDOT operated signals, the region Signal Operations Engineer will develop the signal phasing plan or review proposed phasing for systems designed by others. For signals operated by other jurisdictions, the operating jurisdiction should be involved in signal phasing development. Phasing development is addressed in 1330.06 Operational Considerations for Design. Phasing development should begin as soon as the decision is made to install a traffic signal and may begin as early as the intersection control analysis. Provide the proposed channelization plans and traffic count data to the region Signal Operations Engineer or phasing designer as early as possible, as phasing information is required to complete the signal system design.

For WSDOT owned and operated signals, vehicle and pedestrian movement phase numbering is standardized to provide uniformity in signal phase numbering, signal display numbering, preemption channel identification, detection numbering, and circuit identification. For signals owned and operated by other jurisdictions, refer to that jurisdiction's guidelines for phase and equipment numbering. The following are general guidelines for the WSDOT numbering system:

1. Phases 2 and 6 are normally assigned to the major street through movements, with phase 2 assigned to the northbound or eastbound direction of the major street. This results in phase 2 being aligned with the direction of increasing mileposts.
2. Phases 1 and 5 are normally assigned to the major street protected left-turn movements.
3. Phases 4 and 8 are normally assigned to the minor street through movements, with phase 4 normally assigned to the approach to the left of the phase 2 approach (as viewed from the phase 2 stop line).
4. Phases 3 and 7 are normally assigned to the minor street protected left-turn movements.
5. Phasing on new signals installed within an already signalized corridor should be assigned to match the existing corridor phasing – even if it doesn't follow the standard phasing conventions listed above.
6. At T intersections, the movement on the stem of the T is normally assigned to either phase 4 or phase 8. Which phase is used will normally depend on the major street phase assignments.
7. At intersections where split phasing is used (opposing directions time separately) assign phases normally but show the split phase phasing diagram, unless otherwise directed by maintenance and operations staff.
8. Signal displays are numbered as follows:

    a. The first number indicates the signal phase and the second number is the number of the signal head, counting from centerline (or left edge line) to the right edge line of the approach. For example, signal displays for phase 2 are numbered, as viewed from left to right, 21, 22, 23, and so on. If the display is an overlap, the designation is the letter assigned to that overlap. For example, signal displays for overlap A are number A1, A2, A3, and so on.

    b. If the display is protected/permissive, the display is numbered with the phase number of the through display followed by the phase number of the left-turn phase. For example, a protected/permissive signal display for phase 1 (the left-turn movement) and phase 6 (the compatible through movement) is numbered 61/11. For overlap right turns, the protected portion may either be an overlap phase, or it may be the same phase as the complementing left turn phase.

With a conventional protected/permissive left-turn display, the circular red, yellow, and green displays are connected to the through phase (phase 6, in this example) controller output and the steady yellow and green arrow displays are connected to the left turn phase (phase 1, in this example) controller output.

When a flashing yellow arrow display is used, coordinate with the Signal Operations Engineer and signal maintenance group to determine appropriate wiring. For new cabinets, always specify an auxiliary output rack when protected/permissive phasing will be used.

9. Pedestrian displays and detectors are numbered with the first number indicating the signal phase and the second number as either an 8 or 9. For example, pedestrian displays and detectors 28 and 29 are assigned to phase 2. If there are more than two displays or detectors for a single pedestrian phase, use letter suffixes for additional displays and detectors (28A / 29A, 28B / 29B, etc.).

10. Vehicle detector numbering depends on the type of detection:

    a. Induction loop detectors use three digit numbers for designation. The first number represents the phase. The second number represents the lane number, starting from the left lane and moving towards the right edge line. The third number represents the loop number counting from the stop line back. For example, detection loops for phase 2 detectors are numbered 211, 212, 213 for lane 1; 221, 222, 223 for lane 2; and so on. For loops tied together in series for a single detection channel, such as a three loop series stop line detector, the individual loops in the series use a letter suffix. For a stop line detector in lane 1 for phase 2, using three loops in series, the loops would be designated 211A, 211B, and 211C.

    b. Video detectors are designated V#, where "#" is the through phase number for that approach, even if it will cover additional phases (such as left turn or overlap) for that approach. If the video detector is for advance detection, the suffix "A" is added. For example, the advance video detector for phase 6 would be V6A.

       Video detection zones may be drawn on the contract plans if desired, but these will normally be field established and adjusted and may not end up as shown in the plans. If used, video detection zones are labeled the same as loop detectors, but with a "V" suffix. For example, the stop line video detection zone for phase 5 would be 511V.


    c. Radar detectors are designated similar to video detectors, but use an "R" prefix in place of the "V". For example, the advance radar detector for phase 4 would be R4A.

    d. Wireless in pavement sensors use the same numbering scheme as induction loops, but add a "W" suffix. For example, the phase 7 stop line sensor would be 711W.

    e. Exhibit 1330-8 shows examples of standard detector numbering.

11. Emergency vehicle detectors use letter designations: Channel A detectors cover phase 2 and phase 5; Channel B detectors cover phase 4 and phase 7; Channel C detectors cover phase 1 and phase 6; and Channel D detectors cover phase 3 and phase 8. When there are multiple detectors for the same channel, the first detector uses the letter, and all other detectors use a number suffix (C, C1, C2, etc.).

Exhibit 1330-8 Detector Numbering Examples



1330.04(3) Vehicle Signal Displays

Signal displays are the devices used to convey right of way assignments and warnings from the signal controller to the motorists and pedestrians. When selecting display configurations and locations, the most important objective is the need to present these assignments and warnings to the motorists and pedestrians in a clear, concise, and uniform manner.

The use of ball, steady arrow, or flashing yellow arrow displays is dependent upon the signal phasing. Use the approved signal phasing diagram to determine which display types can be used for which movements. Typical vehicle signal displays are shown in Exhibits 1330-9a through 9h. In addition to the display requirements contained in the MUTCD, the following also apply:

1. A minimum of two indications for the through movement, if one exists at an intersection, must be provided - even if it is not the primary (predominant) movement. Provide a minimum of two indications for the major signalized turn movement of an intersection if no through movement exists, such as on the stem of a T intersection. These signal faces are to be spaced a minimum of 8 feet apart. At a T intersection, select the higher-volume movement as the primary movement and provide displays accordingly.

   A green left-turn arrow on a primary display and a green ball on the other primary display do not comply with this rule. At an intersection where left turns are prohibited, the leftmost through display may use a green up arrow in place of the green ball display. At an

intersection where right turns are prohibited, the rightmost through display may use a green up arrow in place of the green ball display.

2. All displays for an approach, regardless of phase served, are to be a minimum of 8 feet apart.

3. Locate displays directly overhead and centered over the associated lane of the applicable vehicular traffic as it moves through the intersection. (See Exhibits 1330-9a through 9h for signal head locations.) For intersections with a skew for through traffic, locate signal displays for through traffic in one of the following ways:

    a. Over the center of the outbound (far side) lane

    b. Over a line drawn between the center of the approaching lane and the center of the associated outbound lane, ending at the stop lines

    Left turn displays may either be located relative to the through displays or in line with approaching traffic, dependent on ability to mount the display(s). (See Exhibit 1330-10 for skew placement examples.)

4. Locate displays a minimum of 50 feet and a maximum of 180 feet from the stop line. The preferred location of the signal heads is between 60 and 120 feet from the stop line. When the nearest signal face is located between 150 and 180 feet beyond the stop line, engineering judgment of conditions, including worst-case visibility conditions, is to be used to determine whether the provision of a supplemental or nearside signal face would be beneficial. When it is not physically possible to locate displays at least 50 feet from the stop line, the distance to the displays may be reduced as follows:

    a. 3-section vertical and 5-section cluster (doghouse) displays may be located between 40 and 50 feet from the stop line.

    b. 4-section vertical displays may be located between 41 and 50 feet from the stop line.

    c. 5-section vertical displays may be located between 45 and 50 feet from the stop line.

    The distances listed above are the minimums required to maintain 16.5 feet of clearance over the roadway with a backplate installed.

    Overhead displays should always be located on the far side of the crossing roadway for the best visibility. Locating overhead displays on the near side of the roadway results in issues with visibility and driver compliance with stop lines. When an overhead display is located on the near side of the crossing roadway, the stop line typically has to be pushed back so that the minimum visibility distance is met. However, this also pushes the stop line back too far for drivers to see cross traffic, resulting in drivers creeping past the stop line towards the intersection – especially for turning traffic. This results in both the driver being stopped past the stop line and being unable to see the signal displays.


    For ramp meter signals, place Type RM signal standards and displays at the stop line.

5. Use vertical vehicle-signal display configurations. Horizontal displays are not allowed unless clearance requirements cannot be achieved with vertical displays or unless they are being installed at an intersection to match other displays in the intersection. Approval by the State Traffic Engineer is required for the installation of horizontal displays.


6. Use 12-inch signal sections for all vehicle displays except the lower display for a post mounted ramp meter signal.
7. Provide displays for turning movements with dedicated lanes as follows:
    a. For protected movements, use all arrow displays.
    b. For protected / permissive movements, use four section arrow displays. Alternatively, a shared five section cluster (doghouse) display may be used for both the turn lane and the adjacent through lane. Note: A three section arrow display, with bi-modal flashing yellow arrow / steady green arrow may be used in cases where windload or vertical roadway clearance will not allow for the use of a four-section display. If vertical clearance can be accommodated through adjustments to the signal display mount, such as mounting the Type M mount between different display sections, a four section arrow display should be used.
8. Use steady green arrow indications only when the associated movement is completely protected from conflict with other vehicular and pedestrian movements. This includes conflict with a permissive left-turn movement. At T intersections, steady green arrow displays may not be used for a movement that has a conflicting pedestrian movement.
9. Use either Type M or Type N mountings for vehicle display mountings on mast arms, as directed by the region maintenance staff or owning agency. Provide only one type of mounting for each signal system. Mixing mounting types at an intersection is not acceptable except for supplemental displays mounted on the signal standard shaft.
10. Use backplates for all overhead-mounted displays for new, updated, or rebuilt signal faces. Add backplates to all existing signal displays that do not already have them.
11. Use Type E mountings for pedestrian displays mounted on signal standard shafts unless otherwise approved by region maintenance staff or the owning agency.
12. Include supplemental signal displays when the approach is in a horizontal or vertical curve and the intersection visibility requirements of this section and the MUTCD cannot be met, unless approved otherwise by the region Traffic Engineer.

    Supplemental far side displays are recommended at intersections with higher truck volumes, as the trucks will frequently block visibility of overhead displays for following drivers. Supplemental far side protected left turn displays are recommended for long left turns.

Exhibit 1330-9a Signal Display Placements – Key to Diagrams




Pavement markings are used to represent possible lane lines and vehicular movements. The lane lines shown are typical, but not necessarily required.



All signal mounts must be a minimum of 8 feet apart, measured center to center.

This example shows typical mount locations for a single approach lane.


Exhibit 1330-9b Signal Displays for Single Lane Approach



Single lane approach with permissive (or no left turns).


R10-12 sign optional.

Where left turns are prohibited, install a 30” x 30” R3-2 No Left Turn (Symbol) Sign in place of the R10-12 sign shown here.




Single lane approach with protected / permissive left turns.

R10-12 sign required.



Single lane approach with protected left turns.


Exhibit 1330-9c Signal Display Mounting Locations for Multi-Lane Approaches



Single through lane with left turn lane(s).


Through lane displays arranged the same as for a single lane approach.

Left turn display(s) centered over lane(s).



Multiple through lanes.

Center displays over each lane.




Single through lane with right turn lane(s).

Through lane displays arranged the same as for a single lane approach.


Ensure that the 8-foot spacing requirement is met if a right turn display is installed overhead.

Exhibit 1330-9d Signal Displays for Dedicated Left Turn Lanes




Dedicated left turn lane with permissive left turns.

R10-27 (Modified) sign optional.




Dedicated left turn lane with protected / permissive left turns.

R10-27 (Modified) sign optional.



Dedicated left turn lane with protected left turns.

Exhibit 1330-9e Signal Displays for Shared Through-Left Lanes – Multiple Through Lanes



Shared through-left lane with permissive left turns.


R10-12 sign optional.

Shared through-left lane with protected / permissive left turns.


R10-12 sign required.

Shared through-left lane with protected left turns.


Exhibit 1330-9f Signal Displays for Shared Through-Right Lanes



Single shared through-right lane with permissive right turns.




Shared through-right lane, multiple through lanes, with permissive right turns.



Shared through-right lane, multiple through lanes, with protected right turns.


For protected / permissive right turns, mirror protected / permissive left turn display from Exhibit 1330-9e.

Exhibit 1330-9g Signal Displays for Dedicated Right Turn Lanes




Dedicated right turn lane with permissive right turns.

R10-27 (Modified) sign optional.




Dedicated right turn lane with protected / permissive right turns.

R10-27 (Modified) sign optional.




Dedicated right turn lane with protected right turns.

Exhibit 1330-9h Signal Displays for Multiple Turn Lanes



Multiple left turn lanes.


R3-5L signs optional.



Multiple left turn lanes, with a shared through-left lane.

R3-5L and R3-6 signs optional.


Mirror for right turns.



Multiple right turn lanes.

R3-5R signs optional.

Exhibit 1330-10 Example Signal Display Placement for Skew Intersection



The minimum mounting height for overhead signal displays is 16.5 feet from the roadway surface to the bottom of the signal housing, including the backplate. There is also a maximum height for signal displays allowed by the MUTCD, since the roof of a vehicle can obstruct a motorist's view of a signal display. The maximum heights from the roadway surface to the bottom of the signal display housing with 12-inch displays are shown in Exhibit 1330-11.

Exhibit 1330-11 Signal Display Maximum Heights

Distance to Stop Line (ft)	Signal Display Arrangement	Maximum Height (to bottom of display housing [3])
40 [1]	Vertical 3-section	17.5 ft
42 [1]	Vertical 4-section	17.0 ft
45 [1]	Vertical 5-section [2]	17.0 ft
53 to 180	Vertical 3-section	22.0 ft
	Vertical 4-section	20.8 ft
	Vertical 5-section [2]	19.6 ft

Notes:
[1] Minimum distance required to achieve 16.5 feet of clearance with backplate installed.
[2] For 5-section cluster displays, use the Vertical 3-section heights.
[3] Subtract 0.5 ft for height to bottom of backplate.


At signalized intersections with railroad preemption, install blankout signs for turning movements that do not have a dedicated signal display (3-section arrow display). Blankout signs are 36" x 36" and will display either a No Right Turn symbol (R3-1) or No Left Turn symbol (R3-2) when activated, as appropriate. Blankout signs should be placed the same as equivalent static signs.

1330.04(4) Pedestrian Equipment

Pedestrian equipment consists of pedestrian signal displays and pedestrian detectors (pushbuttons). New signal systems are required to use countdown displays and Accessible Pedestrian Signal (APS) pushbuttons. See 1330.04(4)(a) for pedestrian display and detection requirements for existing signal systems. No intersection may have a mix of APS and non-APS pushbuttons, nor may any intersection have a mix of countdown and non-countdown pedestrian displays.

Pedestrian displays are required to be installed with the bottom of the display housing no less than 7 feet or more than 10 feet above the sidewalk surface. Pedestrian displays are required to be installed to provide maximum visibility at the beginning of the controlled crosswalks. To accomplish this, pedestrian displays should be located no more than 5 feet from the outside edge of the crosswalk, as measured on a line perpendicular to the crosswalk centerline (See Exhibit 1330-12). The offset distance may be offset up to a maximum of 10 feet from the outside edge of the crosswalk if physical constraints prevent the display from being placed no more than 5 feet from the outside edge of the crosswalk.


Exhibit 1330-12 Pedestrian Display Placement Requirements



Pedestrian pushbuttons (PPBs) are required to be located within a certain distance of the crosswalk being served. Pedestrian pushbutton location requirements are as follows:

- The PPB should be between 4 and 10 feet from the face of curb, where sidewalk is present, or the edge line of the roadway where there is no sidewalk. The PPB may be between 1.5 and 4 feet from the curb face or edge line, but this is not recommended due to proximity to the roadway. The PPB may not be closer than 1.5 feet from the curb face or edge line. Contact the HQ Traffic Office if the PPB cannot be placed within 10 feet of the curb face or edge line.
- The PPB should be located as close to the outside edge of the crosswalk line as possible, so that for APS PPBs, the button and sign face towards the core of the intersection, rather than back down the adjacent approaching roadway. The PPB may be located no more than 5 feet outside either edge of the crosswalk line.
- If possible, PPBs should be located on separate poles and be separated by a minimum of 10 feet.
- See Exhibit 1330-13 for recommended and allowed PPB placement locations.

Exhibit 1330-13 PPB Placement Requirements



PPBs are required to be located so that the actual button, not just the assembly, is within 9 inches of a level all-weather surface (generally sidewalk or paved road shoulder) as described in 1330.03(3). To accomplish this, certain criteria must be met depending on the type of pole upon which the pushbutton is installed:

a. For vertical shaft poles (Type PPB, PS, I, FB, or RM), the center of the pole shall be no more than 9 inches from the edge of the level clear space. The pushbutton shall not be oriented more than 90 degrees from facing the level clear space. (See Exhibit 1330-14a.)

b. For larger signal standards (Type II, III, IV, IV, or SD), the button must face the level clear space, with the edge of the pole baseplate no more than 6 inches from the edge of the level clear space. It is recommended that the pole either be in the sidewalk, or the edge of the pole base plate be installed as close to the back of sidewalk as possible. (See Exhibit 1330-14b.) Some minor rotation of the button on the pole is possible, but even smaller angles may quickly exceed the allowed reach limit – particularly on larger poles.

Exhibit 1330-14a PPB Placement on Vertical Shaft Poles





Exhibit 1330-14b PPB Placement on Large Signal Standards



In all cases, it is recommended that the pole be installed in the sidewalk for maximum accessibility. However, the pole and the pushbutton itself are obstructions and must not encroach upon the required minimum pedestrian access route widths (see Chapter 1510).

PPBs are required to be installed at 42 inches above the level clear space, as measured to the center of the actual button. Existing pushbuttons do not require a height adjustment if the center of the actual button is within a range of 36 to 48 inches above the level clear space.

For WSDOT owned systems, pedestrian signal equipment may not be installed on light standards. Do not install pedestrian signal equipment on light standards for systems owned by other jurisdictions unless directed by that jurisdiction.

1330.04(4)(a) Accessible Pedestrian Signals (APS) and Countdown Pedestrian Displays

Accessible Pedestrian Signals (APS) consist of a pedestrian pushbutton with integrated vibro-tactile and audible versions of the visual indications presented by pedestrian signal displays. APS are required at any location with a pedestrian display – *even if there was no pedestrian detection previously*. This is due to the requirement to provide non-visual indication of the pedestrian phase.

Countdown pedestrian displays are displays which use a combination of an overlapping person (walk) and hand (don't walk) indication and an adjacent two digit countdown timer display. The timer counts down the seconds remaining in the pedestrian clearance phase (flashing don't walk).

For existing signalized intersections where pedestrian equipment was not previously installed, the installation of accessible pedestrian signals (APS) and countdown pedestrian displays is required for the entire intersection. This may require new or relocated poles, as well as additional ramp and sidewalk work beyond that necessary for basic sidewalk and ramp ADA compliance.

At signalized intersections with existing pedestrian equipment:

- For any project that qualifies as an "alteration" under ADA guidelines, as part of the ADA work, sidewalk and ramp work shall be coordinated with signal system work to ensure that all poles with pedestrian equipment meet accessibility requirements for APS pushbuttons for the entire traffic signal system at that intersection. This may require new or relocated poles, as well as additional ramp and sidewalk work beyond that necessary for basic sidewalk and ramp ADA compliance.
    - For WSDOT owned signal systems, APS pushbuttons and countdown displays must be installed.
    - For signal systems owned by other agencies, install APS pushbuttons and countdown displays if funded by the owning agency.
- For other projects, where pushbuttons are being relocated on a single corner, including to a new pole, and no other work (including sidewalk or ramp work) is taking place at any other corner, pushbuttons may be relocated or replaced with the same type of pushbutton as currently exists at that intersection. Countdown pedestrian displays are not required to be installed at that intersection. New pole location(s) must meet accessibility requirements for both the existing and APS pushbuttons.
- Where APS pushbuttons are being installed at a signal system in response to a public request, all pushbuttons are required to be replaced with APS pushbuttons and all pedestrian displays are required to be replaced with countdown pedestrian displays at

that intersection. Additional poles may be required and ramp and sidewalk work may be necessary to support access to new APS locations / orientations.

- Where pushbuttons are only being adjusted in height at a signal system, no other revisions are required.
- For all other cases, APS pushbuttons and countdown pedestrian displays shall be installed over the entire intersection. This may require additional ramp and sidewalk work to provide required accessibility to and for APS locations / orientations beyond that already required for other ADA compliance efforts.

1330.04(5) Signal Standards (Supports)

Signal standards consist of five main types of supports: Vertical Steel Shaft, Cantilevered Steel Mast Arm, Steel Strain Pole, Wood Strain Pole, and Signal Bridge. The type of support selected will depend on required placement of vehicle signal displays and the ability of the support to reach that location. The MUTCD states that the preferred location for signal displays is overhead on the far side of the intersection.

Signal displays may also be mounted to bridges where clearance will not allow an alternate signal standard type. Installation on bridges requires approval of both the region Traffic Engineer and the HQ Bridge and Structures Office.

Signal Standards shall be considered in the following order of preference:

1. **Cantilevered Steel Mast Arm**. These are the standard support type for permanent systems, and should be used whenever possible. Mast arm installations are preferred because they generally provide better placement of the signal displays, greater stability for signal displays in high-wind areas, and reduced maintenance costs. Mast arm lengths are limited to 65 feet from center of pole to farthest display mount – if additional length is needed, an alternate support type must be used.
2. **Span Wire System (Steel or Wood Strain Poles).** These systems may be used when displays are needed at a greater distance than a mast arm system can support, or if a system is expected to be in place for less than 5 years. Steel poles are required to be used for permanent signal systems. Temporary signal systems (systems to be removed under the same contract as installation) may use wood poles. The use of wood poles beyond the end of a contract or for longer than 5 years requires the approval of the region Traffic Engineer. Individual spans have a limit of 150 feet – longer spans require design by the HQ Bridge and Structures Office.
3. **Signal Bridge.** Signal bridges shall only be used when no other alternative can physically be installed and support displays in the required locations. Diagonal signal bridges are not recommended as they are extremely difficult to maintain and result in displays being too close to at least one of the two cross streets, resulting in poor display visibility. Diagonal spans in general are not recommended as a failure will result in the loss of the entire signal system, rather than just one or two directions.
4. **Vertical Steel Shaft.** Vertical steel shaft supports should only be used for supplemental vehicle displays or pedestrian equipment. In special cases (such as in a small historic town), vertical steel shaft supports may be used without overhead signal displays if approved by the region Traffic Engineer, as allowed by the MUTCD. This practice is not recommended, as displays are too easily obstructed from view.

When placing signal standards, the primary consideration is the visibility of signal faces. Place the signal supports as far as feasible from the edge of the traveled way without adversely affecting signal visibility. (The MUTCD provides additional guidance on locating signal supports.) Initially, lay out the location for supports for vehicle display systems, pedestrian detection systems, and pedestrian display systems independently to determine the optimal location for each type of support. Consider the need for future right-turn lanes or intersection widening when choosing the final location of the signal standards. Poles should also be located outside of sight triangles for turning traffic.

If conditions allow and optimal locations are not compromised, pedestrian displays and pedestrian detectors can be installed on the vehicular display supports. However, pole placement cannot encroach on pedestrian access route or maneuvering space requirements. Pole mounted appurtenances, such as pushbuttons, terminal cabinets, and displays, need to be taken into consideration in regards to their encroachment into accessible spaces.

Another important consideration that can influence the position of signal standards is the presence of overhead and underground utilities. Verify the location of these lines during the preliminary design stage to avoid costly changes during construction:

a. **Underground Utilities:** Underground utilities must be located, marked, and surveyed. If any underground utility is within 10 feet of any foundation, consider potholing for the utility to find its actual location. Field locates are rarely precise and must be verified if a potential conflict exists.

b. **Overhead Utilities:** Signal standards may be located within close proximity to overhead communications lines (phone, cable, fiber-optic), but the lines should not touch the any part of the signal system and should not pass in front of any displays. Overhead power lines require a minimum 10-foot circumferential clearance for lines rated at 50KV or below, including the neutral. For lines rated over 50KV, the minimum clearance is 10 feet plus 0.4 inches for each KV over 50KV. Overhead utilities may have to be relocated if a suitable location for signal equipment cannot be found.

Once pole locations have been selected, a soils investigation is required to determine the lateral bearing pressure, the friction angle of the soil, and whether groundwater may be encountered. Standard foundations may be used if the soil lateral bearing pressure is at least 1,000 psf, the friction angle is at least 17°, and the ground slope is 2H : 1V or flatter. Standard foundation information is found in the *Standard Plans*, and depends on the type of support system being used.

Special foundation designs are required if the soil lateral bearing pressure is less than 1,000 psf, the friction angle is less than 17°, or the ground slope is steeper than 2H : 1V. The region materials group works with the HQ Materials Laboratory to determine the bearing pressure and friction angle of the soil at the proposed foundation locations. If soils do not meet these minimum values for lateral bearing pressure and friction angle, the signal standard charts and soil conditions report (summary of geotechnical conditions for foundations) must be forwarded to the HQ Bridge and Structures Office with a request for special foundation design. The HQ Bridge and Structures Office designs foundations for the regions and reviews designs submitted by others.

Where poles are installed on structures, the anchorage must be designed by the Bridge designer. Coordinate with the Bridge designer for placement and design of pole anchorages on structures.

Do not place any signal standard in a median area. The sole exception is a Type PS or Type PPB signal standard as required for median refuge areas for pedestrians.

Coordinate with all stakeholders (Maintenance, Signal Operations, Civil Design Engineer, Drainage Engineer, and so on) in the placement of signal equipment to avoid any possible conflicts. Arrange field reviews with the appropriate stakeholders as necessary.

1330.04(5)(a) Mast Arm Signal Standards and Foundation Design

Mast arm signal standards are designated by the following types:

- Type II: Single mast arm with no luminaire mount.
- Type III: Single mast arm with luminaire mount.
- Type SD: Double mast arm, with or without luminaire mount.

Mast arm signal standards are normally located on the far right corner of the intersection from approaching traffic. A typical mast arm signal standard only has one mast arm, however two may be used. If the angle between the two arms is not exactly 90 degrees, the design must be sent to the bridge and structures office. In most cases, two arms at 90 degrees can support the necessary display positioning. Additionally, signal standards on mast arms may be rotated up to 30 degrees from center. Do not allow a mast arm for one direction to cross in front of the mast arm for a different direction if possible, as it results in a visual obstruction of the signal displays. Where two double arm signal standards are installed on opposite corners, the preferred location for the two poles are the far right corners of the mainline roadway. This way, the mast arms for the mainline traffic will not cross in front of each other.

Mast arm signal standards have a typical arm attachment point of 18 to 20 feet in height. This height range needs to be taken into consideration when placing signal displays in order to ensure that the display height requirements shown in 1330.04(3) are met. The attachment point height may be adjusted throughout this range as necessary, but increments of 0.5 feet are recommended for ease of fabrication. Connection points outside of this range are a special design, and require design support from the Bridge and Structures Office.

Mast arm signal standards are designed based on the total wind load moment on the mast arm. The moment is a function of the surface area of each appurtenance (signal display or sign), X * Y, and the distance between the vertical centerline of each appurtenance and the vertical centerline of the signal pole Z. This determines the total wind load moment, referred to as an XYZ value and measured in cubic feet, which is used to select the appropriate mast arm fabrication plan and foundation design. Preapproved mast arm fabrication plans are available at http://www.wsdot.wa.gov/Bridge/Structures/LSS.htm, and will be listed in the Contract Provisions. To determine the XYZ value for a signal standard, the XYZ value of each appurtenance must be calculated. These values are then totaled to determine the overall XYZ value for the signal standard. For signal standards with two mast arms at 90 degrees apart, the larger of the two XYZ values calculated for each mast arm is used for the overall pole XYZ value.

When determining the XYZ values, use the worst-case scenarios for signal display and sign placements. All signal displays and mast arm-mounted signs, including street name signs, must be included in this calculation. Emergency preemption detectors, preemption indicator lights, cameras, and radar detectors are negligible and are not included in determining the XYZ values. For mast arm-mounted signs, use the actual sign area (in square feet) to determine the XYZ value. For poles with luminaire supports, the luminaire and arm is also included in the total XYZ

calculation. Surface areas for vehicle displays are shown in Exhibit 1330-15. Signs are limited in size as follows:

- Street name signs may be a maximum of 36 inches in height and 36 square feet in total area. Design the mast arm to support the widest sign that will fit within these limits (up to 144 inches wide), regardless of the actual sign size needed. This allows for future changes to the street name sign. Street name signs are mounted such that the edge of the pole is no less than 1 foot but no more than 2.5 feet from the vertical pole centerline, as shown in the *Standard Plans*. Use the offset necessary for the largest possible sign in the signal standard chart for the XYZ value, but refer to the *Standard Plans* for actual sign installation requirements using construction notes in the Contract Plans.
- Other mast arm mounted signs may not exceed 36 inches in height and 7.5 square feet in area.
- Signs mounted on the vertical pole may not exceed 36 inches in width and 15 square feet in area. These signs are not included in the XYZ calculation.

After calculating the total XYZ value, round this up to the next standard foundation XYZ value or 2850 ft^3, whichever is lower, to determine the design XYZ value. The design XYZ builds in some flexibility for future modifications. If the total XYZ value exceeds 2850 ft^3, a special design signal support is required. Preserve traffic signal support calculations as required by 1330.07 Documentation.

Exhibit 1330-15 Signal Display Surface Areas

Signal Display	Area
Vertical 3-section	9.2 sq ft
Vertical 4-section	11.6 sq ft
Vertical 5-section	14.1 sq ft
5-section cluster	14.4 sq ft

After the total XYZ value is determined, if a standard foundation may be used, select the correct foundation depths for the XYZ values from the table in the *Standard Plans*, using the next higher total XYZ value. For WSDOT systems, only the 700, 1350, 1900, 2600, and 3000 columns may be used. All five foundation options should be provided unless there is a known constraint preventing the use of one of the options, such as insufficient space for 4 ft diameter foundation or expected loose soil requiring the use of the Alternate 2 foundation construction.

1330.04(5)(b) Span Wire Signal Standards and Foundation Design

Span Wire Systems use poles and aerial wires to support signal displays, signs, and emergency preemption equipment. Cameras, radar detectors, and street name signs are installed on the vertical strain poles. When laying out span wires, the preferred layout is similar to mast arm supports. Displays for an approach should be installed on a span on the far side of the intersection, with poles on the two far corners. Do not use diagonal spans unless absolutely necessary, as they are extremely difficult to maintain and if the wire is broken, the entire signal

system is lost and blocks the entire intersection, rather than the equipment for only one approach.

Span wire signal standards include both steel and timber strain poles. Steel and timber strain poles are designated by pole class, which is based on the horizontal tension load the pole will support. The loads and resultant forces imposed on strain poles are calculated and a pole class greater than that load is specified. Steel Pole Classes and their allowed tension loads are listed in the *Standard Plans*. Exhibit 1330-16 lists the pole classes and tension loading available for timber strain poles.

Headquarters Traffic and Headquarters Bridge and Structures office support is required for determining span tension load and pole classes. Provide the pole and span layout, the locations and sizes of all signal displays and span wire mounted signs, and the soils report. Span wire mounted signs are limited to a maximum of 36 inches in height and 7.5 square feet in area. Emergency preemption equipment locations do not need to be submitted, as they are not included in load calculations. Spans should not exceed 150 feet, if possible, in order to reduce the complexity of the design.

After the pole classes are provided by the Headquarters Bridge and Structures office, select the appropriate foundation information from the *Standard Plans* using the pole classes and soil conditions. If a standard foundation cannot be used, a foundation design will be provided along with the pole class information.

Exhibit 1330-16 Timber Strain Pole Classes

Pole Class	Tension Load Limit (lbs)
4	2400
3	3000
2	3700
1	4500
H1	5400
H2	6400
H3	7500

Pole Classes from ANSI Standard O5.1

1330.04(5)(c) Special Case Signal Supports

Special case signal supports include signal bridges and structure (typically bridge) mounts. These should only be selected if absolutely necessary, as they are difficult to design, construct, and maintain, and they frequently result in signal display locations that are difficult for drivers to see.

Signal bridges function the same as a diagonal span wire system, with the two supports on opposite corners of the intersection. Signal bridges require windload calculations similar to mast

arm signal standards, so display and sign locations and offsets must be provided. Signal bridge foundations must be designed by the Headquarters Bridge and Structures office.

Signal displays and other equipment may be installed on structures when there is insufficient clearance below the structure to allow for a different type of signal support. Coordinate with the Bridge designer to place mounts and determine routing paths for conduit and wiring out of the structure. Structure mounts are not desirable, as they typically cannot be modified without reconstruction of the structure itself, and any equipment embedded in the structure is inaccessible after the structure is complete.

Signal displays may not be installed on sign structures such as cantilever sign structures or sign bridges. Signal displays also may not be installed on railroad cantilever structures unless the signal system and the railroad are owned by the same jurisdiction and maintained by the same staff.

1330.04(5)(d) Vertical Steel Shaft Supports

Vertical steel shaft supports include the following types of signal standards:

(a) Type PPB: Sometimes referred to as a "stub pole", this pole is typically 5 feet tall and 3 inches in diameter. It is used strictly to support pedestrian pushbuttons. Due to the frequency of damage, regardless of location, it is recommended that breakaway bases always be used.

(b) Type PS, I, RM, and FB: These poles are effectively identical, with the difference being the total height to the slipfitter top.

- Type PS are 8 ft tall and may only have pedestrian displays mounted on the top.
- Type I are 10 ft tall and may have vehicle displays mounted on the top and pedestrian displays mounted on the side. Type RM are identical to Type I but are used for ramp meter systems only.
- Type FB are 14 feet tall, and may be used like Type I when additional height is needed for the vehicle display(s).

Placement of vertical steel shaft supports will depend on visibility requirements for displays and accessibility requirements of pedestrian features. Generally, these supports should be located at back of sidewalk, as they are farther from traffic and more likely to be out of both the pedestrian access route and the path of any users. Fixed bases should be used when located at the back of sidewalk, but slip bases may be used if circumstances recommend it. Supports located within sidewalk (includes planter strips) or in locations with only paved shoulders should always use slip bases.

1330.04(6) Vehicle Detection Systems

Vehicle detection systems are necessary for the efficient operation of traffic signals. By responding to the presence of traffic, signal systems do not have to use fixed timing. This improves efficiency by removing unnecessary delay and not providing service to an approach or movement with no traffic.

1330.04(6)(a) Vehicle Detection Zone Placement

The detection system at a traffic-actuated signal installation provides the control unit with information regarding the presence or movement of vehicles, bicycles, and pedestrians. Vehicle detection systems perform two basic functions: queue clearance and the termination of phases. Depending on the specific intersection characteristics, either of these functions can take priority. The merits of each function are considered and a compromise might be necessary.

There are two basic types of detection zones: stop bar and advance. Stop bar detection is a zone that extends from the stop line to a point 30 to 40 feet in advance of that location. Advance detection is a discrete zone (or zones) placed in advance of the stop line at a distance dependent on vehicle speed.

Basic vehicle detection requirements depend upon the speeds of the approaching vehicles:

(a) When the posted speed is below 35 mph, provide stop bar detection or one advance detection zone. See Exhibit 1330-17 for advance detection zone distances.

(b) When the posted speed is at or above 35 MPH, provide stop bar detection and at least two advance detection zones. Multiple advance detection zones are normally required to accommodate decision zone detection.

(c) Side street advance detection is not required for WSDOT owned signal systems, but may be provided through means that do not require equipment to be installed off of WSDOT right of way. For signals owned by other jurisdictions, the use of side street advance detection is at the discretion of the owning jurisdiction.

A decision zone is a location along the intersection approach where a motorist is forced to make a decision between two alternatives. As applied to vehicle detection design, this situation can occur when two vehicles are approaching a traffic signal and the signal indication turns yellow. The motorist in each vehicle must decide whether to continue through the intersection or stop prior to the intersection. If the lead vehicle decides to brake and the following vehicle does not, there may be a rear-end collision.

For posted speeds of 35 MPH or higher, there are two options for placing advance detectors to address the decision zone:

1. Fixed locations based on posted speed, which is generally the 85th percentile speed. Place loops according to the table in Exhibit 1330-17.
2. Calculated locations based on calculated decision zone detection design. This design increases the opportunity for a range of vehicles from the 90th percentile speed vehicle to the 10th percentile speed vehicle to either clear the intersection or decelerate to a complete stop before reaching the intersection. The method of calculating the decision zone and the required detection loops is shown in Exhibit 1330-18.

Although the exhibits reference loops, advance detectors may be of any approved type.

For new intersection construction where there is no existing traffic, the fixed locations based on posted (target design) speed are to be used. Fixed locations based on posted speed use the same methods as the calculated decision zone detection design, but set V90 at 5 MPH above posted speed and V10 at 5 MPH below posted speed. Engineering judgment based on similar intersections (such as geometrics and traffic volumes) may justify modifying the V90 and V10 speeds used in the calculation, with concurrence from the region Signal Operations Engineer.

Both methods require a study of the approach speeds at the intersection. For intersection approaches, conduct the speed study as follows:

- Collect data at the approximate location or just upstream of the decision zone;
- Collect data during off-peak hours in free-flow and favorable weather conditions;
- Collect data during regular commuting hours in a high volume signalized corridor during favorable weather conditions
- Only document the speed of the lead vehicle in each platoon.

It is important that the person conducting the speed study remain inconspicuous so they do not influence drivers to slow down. Normal driving patterns are needed for proper speed studies. Prior speed-study information obtained at this location may be used if it is less than 18 months old and driving conditions have not changed significantly in the area.

Preserve detection zone placements and any supporting calculations as required by 1330.07 Documentation.

Exhibit 1330-17 Fixed Vehicle Detection Placement

Fixed Detection Placement – Below 35 MPH


V_{85} =		V_{90} =		V_{10} =		UDZ_{90}	DDZ_{10}	LC_1	P_{MID}	LC_2	Calculated	Rounded
MPH	ft/s	MPH	ft/s	MPH	ft/s	ft	ft	s	ft	s	Loop 1	Loop 1
25	36.7	30	44.00	20	29.33	165.00	50.84	3.9	107.92	1.9	107.92	105
30	44	35	51.33	25	36.67	216.03	70.28	4	143.15	2	143.15	140

For posted speeds below 35 MPH, only the PMID detection location is used.

Fixed Detection Placement – 35 MPH and Above

V_{85} =		V_{90} =		V_{10} =		UDZ_{90}	DDZ_{10}	LC_1	P_{MID}	LC_2	Calculated		Rounded	
MPH	ft/s	MPH	ft/s	MPH	ft/s	ft	ft	s	ft	s	Loop 1	Loop 2	Loop 1	Loop 2
35	51.33	40	58.67	30	44.00	273.78	92.40	4.1	183.09	2.1	183.09	273.78	180	275
40	58.67	45	66.00	35	51.33	338.25	117.21	4.3	227.73	2.2	227.73	338.25	225	340
45	66	50	73.33	40	58.67	409.44	144.71	4.5	277.08	2.3	277.08	409.44	275	410
50	73.33	55	80.67	45	66.00	487.36	174.90	4.7	331.13	2.4	331.13	487.36	330	490
55	80.67	60	88.00	50	73.33	572.00	207.78	5	389.89	2.5	389.89	572.00	385	575
60	88	65	95.33	55	80.67	663.36	243.34	5.2	453.35	2.6	453.35	663.36	450	665

Exhibit 1330-18 Decision Zone Detection Placement



Single Advanced Loop Design
Use when $LC_1 \leq 3$ seconds

$$LC_1 = \frac{UDZ_{90} - DDZ_{10}}{V_{10}}$$

Decision Zone Endpoint Calculation
(for all loop arrangements)

Where grades are flatter than +/- 4%:


$$UDZ_{90} = \frac{(V_{90})^2}{16} + V_{90}$$

$$DDZ_{10} = \frac{(V_{10})^2}{40} + V_{10}$$

Where grades are +/- 4% or steeper:


$$UDZ_{90} = \frac{(V_{90})^2}{2(8+32.2G)} + V_{90}$$

$$DDZ_{10} = \frac{(V_{10})^2}{2(20+32.2G)} + V_{10}$$



Double Advanced Loop Design
Use when $LC_2 \leq 3$ seconds

$$P_{MID} = \frac{UDZ_{90} + DDZ_{10}}{2} \qquad LC_2 = \frac{UDZ_{90} - P_{MID}}{V_{10}}$$



Triple Advanced Loop Design
Use when $LC_3 \leq 3$ seconds

$$LC_3 = \frac{UDZ_{90} - DDZ_{10}}{3V_{10}} \qquad P_{MID1} = \frac{[2(UDZ_{90}) + DDZ_{10}]}{3} \qquad P_{MID2} = \frac{[UDZ_{90} + 2(DDZ_{10})]}{3}$$

Where:

V_{90} = 90th percentile speed, in feet per second
V_{10} = 10th percentile speed, in feet per second
UDZ_{90} = Upstream end of decision zone, for 90th percentile speed
DDZ_{10} = Downstream end of decision zone, for 10th percentile speed
G = Grade of roadway, in decimal form, including + or – (Example: -4% = -0.04)
LC_1 = V_{10} travel time to DDZ_{10}
LC_2 = V_{10} travel time from UDZ_{90} to P_{MID}
LC_3 = V_{10} travel time from P_{MID2} to DDZ_{10}

1330.04(6)(b) Vehicle Detector Types

There are two basic categories of vehicle detectors:

- **Non-Invasive**: These are detectors installed outside of the roadway, typically overhead in a strategic location. These include camera (optical and infra-red) and radar systems.
- **In-Pavement**: These are detectors which are installed in the road itself. These include induction loops and wireless in-pavement sensors.

Non-invasive detection is generally recommended over in-pavement detection, due to the ability to revise non-invasive detection at any time and the ease of installation, repair, and replacement – particularly when supporting traffic control and impacts are taken into account. Additionally, pavement damage due to regular wear or construction activities will disable in-pavement detection, whereas non-invasive detectors will continue to function, and can even be adjusted to accommodate revised lane configurations.

Stop line detection should use non-invasive systems for detection. Although induction loop detectors are typically the most reliable for detecting cars and trucks, they do not consistently detect bicycles and motorcycles. RCW 47.36.025 specifically requires that vehicle-activated traffic control signals be capable of detecting motorcycles and bicycles.

Advanced detection may be either non-invasive or in-pavement, as these improve efficiency of the signal systems but are not as critical as stop line detection. Non-invasive is recommended for posted speeds of 45 MPH or lower, as they are currently only effective for up to about 600 feet from the location of the detector. The advantage is that advance detection can be installed at the intersection, rather than trenching long distances to place advanced detectors in pavement. For speeds over 45 MPH, non-invasive detection systems may be considered, but in-pavement systems will probably be more effective. Advance detection does not need to detect bicycles.

Selection of detector types will depend on a variety of environmental factors and locations available for placement.

1. Radar Detectors

Radar detectors are located on either the signal mast arms or the signal vertical strain poles, depending on lane configuration, detector type, and location availability. Radar detectors are not affected by weather, and are typically minimally affected by mast arm motion in high wind. Consult the detector manufacturer's installation guidance for placement details. One detector can normally cover all lanes of an approach for that type of detection (stop line or advance).

2. Video Detectors


Placement of video detectors depends on the function of the detector. Exhibit 1330-19 provides placement examples.

Stop line detectors should be installed on the same mast arm as the vehicle displays for that approach. The detector should be placed on an extension of the wide line between the left turn and through lanes, if present; if there is no wide line, the detector should be centered on the through lanes. One detector can cover all lanes of an approach for that type of detection (stop line or advance).

Advance detectors should be installed on a luminaire arm, preferably on the adjacent corner to the approaching lanes, as the effectiveness of the advance detection depends on height. Consider requiring a luminaire arm even if no luminaire is needed, in order to provide an optimal installation site for the detector. Advance detectors may be installed on a mast arm, but will typically have less effective range.

Both infra-red and optical cameras are available, but optical cameras are not recommended due to the adverse effects of rain, snow, fog, sun glare, and sharp shadows on their effectiveness. However, infra-red cameras may still be affected by heavy fog or other major thermal events. All video detection may be affected by mast arm motion due to high winds.

Exhibit 1330-19 Video Detector Placement



3. Induction Loops

Induction Loops are coils of wire in the roadway that use the magnetic properties of vehicles to detect them. Induction loops can last a very long time when undisturbed. However, induction loops require bicycles to be in a very specific location in order to be detected, and may not detect carbon fiber bicycles. Induction loops must be installed with one per lane per detection zone – stop line loops may be larger or series loops. Where induction loops are used, loops need to be numbered in order to keep track of the wiring and lanes they are detecting. See 1330.04(2) for detector numbering requirements.

4. Wireless In-Pavement Sensors

Wireless in-pavement sensors are compact detectors installed in pavement, and use either radar or magnetics to detect vehicles. They use a wireless connection to the signal cabinet. The sensors rely on a battery for operation, and require replacement of the entire unit when they fail. Sensor placement is similar to induction loops – one per lane per detection zone. The magnetic versions are subject to the same difficulties with bicycles as loop detectors. All wireless sensors are also subject to various factors that impact wireless signals such as range, signal obstructions, and possible signal interference from other radios depending on the frequency used.

Non-invasive detectors are preferred with concrete (Portland cement concrete pavement) roadway surfaces. In-pavement detectors installed in concrete panels typically cannot be revised or replaced until all affected concrete panels are replaced. In-pavement detectors installed in bridge decks must be installed when the bridge deck is constructed, and cannot be replaced unless the bridge deck is replaced. Non-invasive detection is also useful for approaches where advance detection is desired, but the approach is outside the jurisdiction of the agency that owns the signal, or for non-standard approaches such as driveways.

Temporary detection should be installed for all stop lines where existing detection will be disabled or ineffective (such as lane shifts) during construction. Temporary advance detection is recommended for high speed (45 MPH or higher) approaches where the decision zone detection will be disconnected for an extended period of time. Consult with the Signal Operations Engineer to determine if temporary advance detection should be used. Temporary advance detection zone placement should take into account any temporary speed limit revisions.

1330.04(7) Preemption Systems

1330.04(7)(a) Emergency Vehicle Preemption

Emergency vehicle preemption (EVP) is required for all traffic signals unless approved otherwise by the region Traffic Engineer. WSDOT is responsible for installing EVP detection equipment at new and rebuilt signalized intersections on state highways. At existing signalized intersections that do not have EVP detection equipment, or where an emergency service agency requests additional equipment beyond the basic required equipment, the emergency service agency is responsible for all material and installation costs. The emergency service agency is responsible for preemption emitters in all cases.

Optically activated EVP systems are used to ensure compatibility with all area emergency service agency emitters. Approval by the State Traffic Engineer is required for the installation of any other type of emergency vehicle preemption system.

Locate optical detectors facing each approach to the intersection – only one detector per approach – with a clear view of the approaching roadway. Detectors have a cone of vision of approximately 8 degrees, and an effective range of 200 to 2500 feet. Detectors should have an unobstructed view of the approach for a minimum of 1800 feet. Primary detectors are normally installed on the same support as the vehicle displays for that approach. Place the detector between the left turn lane and through lane displays on approaches with left turn lanes, or centered on the approaching lanes where left turn lanes are absent.

When the approach is in a horizontal or vertical curve, or there are other sight obstructions, non-standard placement of the primary detector or additional supplemental detectors may be necessary. Primary detectors may be located on other signal display supports (arms or spans) or vertical strain poles, depending on visibility requirements. Supplemental detectors may also be located on separate Type I or Type FB poles in advance of the intersection. On higher speed roadways, supplemental detectors can provide extended detection range – one mile in advance of the intersection is usually sufficient.

Preserve any documentation associated with the EVP system, including system type selected and any associated agreements or approvals, as required by 1330.07 Documentation.

1330.04(7)(b) Railroad Preemption

Railroad preemption is used when a railroad is in close proximity to a signalized intersection. If railroad tracks are within 1/4 mile of a signalized intersection, then a Railroad Crossing Evaluation Team is formed to determine the need (if any) for railroad preemption, interconnection, simultaneous preemption, advanced preemption, and so on. The Railroad Crossing Evaluation Team should consist of region and HQ Signal Design Engineers, region and HQ Signal Operations Engineers, HQ Railroad Liaison, HQ Rail Office representative, region Utilities Engineer, region Traffic Design Engineer, region Maintenance Superintendent, and the affected railroad representative. Where the signal is owned, operated, or maintained by a local agency, a local agency representative should also be included.

The Railroad Crossing Evaluation Team will determine what design considerations are needed at all signalized intersections near railroad crossings. For locations where the railroad tracks are located greater than 500 feet from the signalized intersection, and it can be demonstrated that the 95% maximum queue length(s) will not extend to within 200 feet of the tracks, railroad preemption may be omitted with the approval of the Railroad Crossing Evaluation Team. Include the demonstration and approval in the documentation required by 1330.07 Documentation.

Railroad preemption and interconnection are recommended when any of the following conditions occurs:

- The distance from the stop bar to the nearest rail is less than or equal to 200 feet.
- There is no dedicated left turn lane and the distance from the stop bar to the nearest rail is less than or equal to 500 feet.
- The 95% maximum queue lengths from the intersection stop bar are projected to cross the tracks. (Use a queue arrival/departure study or a traffic analysis “micro-simulation model” to determine 95% maximum queue lengths.)

- The 95% maximum queue lengths from the railroad are projected to affect an upstream traffic signal. (Use a queue arrival/departure study or a traffic analysis "micro-simulation model" to determine 95% maximum queue lengths.)

If it is determined that advanced preemption is needed, the HQ and region Signal Operations Engineers will calculate the amount of railroad preemption time required using the *Guide for Determining Time Requirements for Traffic Signal Preemption at Highway-Rail Grade Crossings (TxDOT Form 2304)*.

The addition of a pre-signal is recommended when any of the following conditions occurs:

- The distance from the stop bar to the nearest rail is less than 88 feet but is at least 40 feet. (For reference, the 88 feet is derived from: the longest design vehicle permitted by statute (75 feet) + front overhang (3 feet) + rear overhang (4 feet) + downstream clear storage (6 feet)).
- The distance from the stop bar to the nearest rail is > 88 feet and < 120 feet and there are no gates for the railroad crossing.
- The sight distance triangle in Chapter 1350, Exhibit 1350-1 (Sight Distance at Railroad Crossing), cannot be met, and the railroad crossing does not have active control (lights or gates).


When pre-signals are used, two stop lines are used: one for the rail crossing, and one for the intersection. The pre-signal displays stop traffic at the rail crossing stop line, and the second set of signal displays stop traffic at the intersection. Use louvers on the intersection displays so that they are not visible from the stop line for the rail crossing. Optically programmed displays may be used in place of louvers, but are not recommended due to the limited benefits, complexity of installation and maintenance, and high cost.

Where the distance between the normal location for the stop bar and the approach is less than 40 feet, the same stop bar should be used for both the traffic signal and the rail crossing. Install vehicle displays on the near side of the intersection, but on the far side of the tracks from the stop line, to improve visibility and discourage drivers from stopping between the tracks and the intersection. Do not install vehicle displays on the far side of the intersection.


Exhibit 1330-20 shows examples of the distances and typical system layouts referenced above.

The Railroad Crossing Evaluation Team has final review and approval authority for all PS&E documents for signal design and operation at all signalized intersections near railroad crossings. All documentation associated with railroad preemption and a memo with each team member's concurrence with the PS&E documents must be preserved as required by 1330.07 Documentation.

Exhibit 1330-20 Signal Display Layout for Rail Crossings



Display Placement
Less than 40 feet between tracks (dynamic envelope marking) and intersection



Display Placement
40 to 88 feet between tracks and intersection

1330.04(7)(c) Transit Priority Preemption

Transit Priority Preemption allows for transit operations to influence signal timing, similar to emergency vehicle preemption. This can be included in mobility projects, but the transit agency assumes all costs for providing, installing, and maintaining this preemption equipment. WSDOT's role is limited to approving preemption operational strategies (phasing, timing, software, and so on) and verifying the compatibility of the transit agency's equipment with the traffic signal control equipment. Preserve all transit priority preemption decisions and agreements as required by 1330.07 Documentation.

1330.04(8) Control Equipment

The standard WSDOT Signal Controller type for traffic signals is the Type 2070 Controller. Some agencies use National Electrical Manufacturers Association (NEMA) controllers (Type TS1 or TS2). Although not normally used for new construction, WSDOT Ramp Meters and some older systems still use Type 170 Controllers. All traffic signal controllers have the following basic functions:

- Dual ring phase operation
- Eight vehicle phases
- Four pedestrian phases
- Four overlap phases
- Four emergency vehicle preemption channels
- Railroad preemption
- Start and end daylight savings time dates
- Transit preemption (some older controllers may not support this)

Type 2070 controllers and newer NEMA controllers are functionally equivalent for basic signal operations. However, Type 2070 controllers and NEMA controllers use different operating software and communications protocols, and therefore cannot be interconnected together. The type of controller should be specified as follows:

1. For WSDOT traffic signals, specify Type 2070 controllers, unless:

    a. The signal is interconnected with other signals. If the other controllers in the interconnected system are not being replaced, specify a controller (2070, NEMA, or other) that matches the rest of the interconnected system.

    b. The signal is operated by another agency. In this case, work with WSDOT and the other agency's maintenance staff to determine the appropriate controller type.

2. For traffic signals owned by other agencies, specify the controller type used by that agency.

The region or operating agency will determine the controller brand and operating software, which are included in the cabinet specifications. Each region or operating agency will provide specifications for their cabinets and the equipment contained therein. For 2070 controllers, double-width cabinets (two racks) should be specified if physically possible to allow for future communications and ITS equipment.

It is often beneficial for one of the agencies to assume responsibility for the operation of the traffic signals. This is accomplished by negotiating an agreement with the other agency. The designer needs to check region policy and make sure someone initiates the process for setting up an operational agreement with the other agency or modifying an existing agreement when applicable. (See the *Agreements Manual* for more information on signal systems and maintenance agreements.) At a new intersection, where the state owns the signal, but WSDOT has agreed to let another agency operate the signal, the controller should be compatible with that agency's system. When installing a new controller in an existing interconnected corridor, the controller should be capable of operating with the existing controllers in the corridor. In situations where it is necessary to coordinate the traffic movements with another agency, it is important that the agencies work together.

Intersections within ½ mile of each other on state highways should be interconnected. Perform an operational analysis to determine need for interconnection where intersections are within 1 mile of each other on state highways with a posted speed of 45 MPH or higher. The preferred method for interconnection is fiber optic cable, but other methods such as IP over copper or wireless interconnect may be considered after discussion with maintenance staff and approval by the region Traffic Engineer. Where fiber optic cable is used, it must be routed through pull boxes and cable vaults – bending fiber optic cable through standard junction boxes typically results in the cable being broken. Consider using a separate pull box or vault for coiling the fiber optic interconnect cable to allow for the large-bend radii. Add a construction note in the plans stating to coil additional cable in the adjacent pull box or vault, not the controller cabinet. This will save on space in the controller cabinet and provides additional cable in case an errant vehicle hits the cabinet.

Coordinate with the operations and maintenance staff to determine the optimum controller cabinet location and the cabinet door orientation. The controller cabinet is positioned to provide the best maintenance access and clearest view of the intersection possible. Preferred visibility allows for as many signal displays and roadway approaches visible as possible from a single location. Cabinets should not be placed where they might block the view of turning traffic (intersection sight triangle). If possible, position the controller where it will not be affected by future highway construction.

Cabinets require a minimum of 36 inches of level space in front of each door, including the concrete pad. Do not place cabinets where flooding might occur or where the cabinet might be hit by errant vehicles. If there is a steep down slope or drop off near the cabinet, personnel fall protection (such as fencing) is required in accordance with standards established by the Department of Labor and Industries. Fall protection may not encroach on the required clear space for the cabinet. The location must also have adequate room for a maintenance vehicle to park near the cabinet. Sufficient space for a bucket truck to park is preferable.

If a telephone line (voice or DSL), fiber optic, wireless, or other connection is desired for remote access to the equipment in the cabinet, provide the appropriate equipment in the controller cabinet and/or nearby junction box or cable vault with separate conduits and junction boxes for the remote communications equipment. Communications connections to outside utilities require their own separate conduit and box/vault system.

Consult with maintenance and operations staff to determine if a backup power source, such as an Uninterruptible Power Supply (UPS) or backup generator, is needed for the signal cabinet. Install the backup power supply on the same concrete pad as the signal cabinet. Service and other cabinets may also be installed on the same concrete pad as the signal cabinet (see the

Standard Plans for concrete cabinet pad layouts). Refer to Chapter 1040 for electrical service types, overcurrent protection, and descriptions and requirements for other components.

1330.04(9) Wiring, Conduit, and Junction Boxes

Consider cost, flexibility, construction requirements, and ease of maintenance when laying out the electrical circuits for the traffic signal system. Consolidate roadway crossings (signal, illumination, ITS conduits, and so on) whenever possible to minimize the number of crossings and take advantage of single crossing construction (joint trenches or consolidated directional boring). Include all electrical design calculations in the Project File.

1330.04(9)(a) System Wiring

Traffic signal systems use multi-conductor cables to connect most of the equipment. Single conductor cable is limited to cabinet power and street lighting circuits.

The following describes typical WSDOT wire type selection:

- 5c cables for signal displays. One 5c per signal phase may connect the signal cabinet to the terminal cabinet on the pole. Separate 5c cables should connect each signal display to the terminal cabinet. Protected / permissive displays may either use one 7c cable or two 5c cables (one for each phase on the shared display).
- 5c cables for pedestrian displays. Consult with region maintenance to determine if the same 5c cable is used for associated pedestrian detection.
- 3cs cables for emergency preemption detectors.
- 2c cables for induction loop detectors. Shielded cable is not required for modern loop detector cards. Older systems may still need shielded cable (2cs), but it is recommended to replace the loop detector cards instead.
- Manufacturer specified cables for video and radar detectors. Video detectors typically use a combined RG9/5c (#18) cable. Radar detectors typically use proprietary 6c and 8c cables. These cables are roughly the size of 7c cables (for calculating conduit fill).
- Use 2c cables for isolated pedestrian detectors (separate pole from associated pedestrian display). For connecting 4-wire APS units, a 7c cable may be used between the PPB post and the signal pole with the pedestrian display (where the APS control unit is located).

To simplify potential repairs for smaller signal standards (Type FB and smaller), consider routing signal display and detection conductors through terminal cabinets on larger signal standards (Type II and larger) before connecting to smaller signal standards. This reduces the amount of wire which may need to be replaced if a smaller signal standard is knocked down and the wiring damaged.

1330.04(9)(b) Conduit

Refer to the Standard Specifications for conduit installation requirements. At existing intersections, where roadway reconstruction is not proposed, conduits are to be placed beyond the paved shoulder or behind existing sidewalks to reduce installation costs. All conduits shall be a minimum of 2 inches in size, with the following exceptions:

1. Conduits entering Type PPB signal standards shall be 1 inch. This may be increased to 1 1/4 inch when two APS PPBs are installed on the same pole.
2. Lighting conduits entering pole foundations (signal or light standards) shall be a minimum of 1 inch. See Chapter 1040 for additional requirements for light standards with slip bases.
3. Conduits entering Type PS, I, RM, and FB poles may be a minimum of 1-inch and a maximum of 2-inch.
4. The conduit for the service grounding electrode conductor may be a minimum of ½-inch.

Install spare conduits at all road crossings. Spare conduits at road crossings should be a minimum of one 3-inch conduit or two 2-inch conduits. Install a minimum 2-inch (preferably 3-inch) spare conduit into the controller cabinet.

It is recommended to use full inch conduit sizes to simplify construction and reduce the different types of conduits required for the system. This helps to provide future capacity and reduce costs through bulk material purchasing. Size all conduits to provide 26% maximum conductor fill for new signal installations. A 40% fill area can be used when installing conductors in existing conduits. (See Exhibit 1330-21 for conduit and signal conductor sizes.)

Exhibit 1330-21 Conduit and Conductor Sizes

Conduit Sizing Table			
Trade Size	**Inside Diam. (inches)**	**Maximum Fill (inch^2)**	
		26%	**40%**
1/2"	0.632	0.08	0.13
3/4"	0.836	0.14	0.22
1”	1.063	0.23	0.35
1 1/4"	1.394	0.40	0.61
1 1/2"	1.624	0.54	0.83
2”	2.083	0.89	1.36
2 1/2"	2.489	1.27	1.95
3”	3.09	1.95	3.00
3 1/2"	3.57	2.60	4.00
4”	4.05	3.35	5.15

Conductor Size Table			
Size (AWG)	**Area (inch^2)**	**Size (AWG)**	**Area (inch^2)**
# 14 USE	0.021	2cs (# 14)	0.090
# 12 USE	0.026	3cs (# 20)	0.070
# 10 USE	0.033	4cs (# 18)	0.060
# 8 USE	0.056	5c (# 14)	0.140
# 6 USE	0.073	7c (# 14)	0.170
# 4 USE	0.097	10c (# 14)	0.290
# 3 USE	0.113	6pcc (# 19)	0.320
# 2 USE	0.133		

Minimize roadway crossings whenever possible. Usually only three crossings are needed (one main line) for a four-leg intersection, and only two roadway crossings are needed for a T intersection. In most cases, the conduit should cross both the main line and side street from the corner where the controller is located.

Directional boring should normally be used when crossing the state route (main line). Open cut trenching may only be used to install conduits under the following circumstances:

1. Existing roadways where the roadway is being resurfaced.
2. Existing roadways where substantial obstacles under the roadway will be encountered.
3. Where there is insufficient room for jacking or boring pits at the edges of the roadway.

Open cut trenching is not permitted across limited access roadways unless the entire pavement surface is being replaced. Sign or signal bridges may not be used for roadway crossings.

1330.04(9)(c) Junction Boxes

Provide junction boxes at the following locations:

- Adjacent to the signal cabinet. A pull box or larger vault may be used in place of multiple junction boxes.
- Adjacent to each signal pole. One box may serve multiple poles. The distance from a pole to the first junction box should not exceed 10 feet without concurrence from maintenance staff. Pole bases may not be used as junction boxes.
- Adjacent to each set of detector loops. These boxes contain the detector loop splices. One box may serve multiple lanes, but the box should be no more than 50 feet from the detector loop.
- At the end of each road crossing.
- In the middle of conduit runs where the number of bends would equal or exceed 360°.

Where possible, locate junction boxes out of paved areas and adjacent to (but not in) sidewalks. New junction boxes may not to be placed in the pedestrian curb ramp or ramp landing of a sidewalk. If a new junction box must be placed within sidewalk, locate it at the edge of the sidewalk and designate it to be slip-resistant. Existing junction boxes located within new or existing sidewalk, including ramps or landings, must be revised as follows:

- Existing junction boxes containing power conductors for the traffic signal (not including street lighting), or wiring for the signal displays, may remain in place, even if they will be within a sidewalk ramp or ramp landing.
- Existing junction boxes containing detector wiring may remain in sidewalks, but must be relocated outside of sidewalk ramps and ramp landings. Designate that the relocation work, including conduit adjustments and rewiring, be completed within a single shift or provide temporary detection using another conduit path.
- All junction boxes which will be within sidewalk, sidewalk ramps, or ramp landings, must be slip-resistant junction boxes. This includes replacing existing junction boxes with slip-resistant junction boxes.
- Under no circumstances may a junction box be located in a grade break for a sidewalk ramp. Either the ramp must be redesigned or additional accommodations made in construction to allow for the box to be relocated.

The fundamental principle is that if relocating a junction box requires shutting down a traffic signal system, the junction box may remain in its existing location but must be replaced with a slip-resistant junction box. See Chapter 1510 for additional ADA requirements.

Do not place junction boxes within the traveled way unless absolutely necessary. Make every effort to locate new junction boxes and to relocate existing junction boxes outside the travel lane or paved shoulder. If there is no way to avoid locating the junction box in the traveled way or paved shoulder, heavy-duty junction boxes must be used. Avoid placing junction boxes in areas of poor drainage. Do not place junction boxes within 2 feet of ditch bottoms or drainage areas, or within vegetative filter strips or similar water treatment features which may be

present. The maximum conduit capacities for various types of junction boxes are shown in the *Standard Plans*.

1330.05 Preliminary Signal Plan

Develop a preliminary signal plan for the Project File. Include a brief discussion of the issue that is being addressed by the project. Provide sufficient level of detail on the preliminary signal plan to describe all aspects of the signal installation, including proposed channelization modifications. Use a plan scale of "1 inch = 20 feet" and include:

(a) Stop lines.

(b) Crosswalks.

(c) Sidewalk locations, including curb ramps.

(d) Guardrail locations.

(e) Drainage items.

(f) Left-turn radii, including beginning and ending points.

(g) Corner radii, including beginning and ending points.

(h) Vehicle detector locations and proposed detector types, including exclusive bicycle detectors.

(i) Pedestrian detector (PPB) locations.

(j) Signal standard types and locations.

(k) Vehicle signal displays.

(l) Pedestrian signal displays.

(m) Phase diagram, including pedestrian movements.

(n) Emergency vehicle preemption requirements.

(o) Railroad preemption requirements.

(p) Illumination treatment, including a calculation summary showing the average light level, average/minimum uniformity ratio, and maximum veiling luminance ratio. (See Chapter 1040 for more information on illumination design requirements.)

(q) Cabinet locations with door orientations.

(r) Traffic counts, including left-turn movements.

(s) Speed study information indicating 90th and 10th percentile speeds for all approaches (if used for detector spacing).

(t) Utilities information.

Submit a copy of the preliminary signal plan to the State Traffic Engineer for review and comment. Allow two to three weeks for review of the preliminary signal plan. After addressing

all review comments, finalize the plan and preserve as required by 1330.07 Documentation. Prepare the contract plans in accordance with the *Plans Preparation Manual*.

If HQ Traffic Design is preparing the contract Plans, Specifications, and Estimate (PS&E) package for the signal system portion of the project, submit the above preliminary signal plan with the following additional items:

(u) Contact person.

(v) Charge numbers.

(w) Critical project schedule dates.

(x) Existing and proposed utilities, both underground and overhead.

(y) Existing intersection layout, if different from the proposed intersection.

(z) Turning movement traffic counts (peak hour for isolated intersections) and a.m., midday, and p.m. peak-hour counts if there is another intersection within 500 feet.

(aa) Electrical service location, source of power, and utility company connection requirements.

After the PS&E is prepared, the entire package is transmitted to the region for incorporation into its contract documents.

1330.06 Operational Considerations for Design

This section describes operational guidance for traffic signals. These operational requirements will directly affect the design of the traffic signal, particularly in regards to signal display types and locations.

All traffic signals should be periodically re-evaluated, to determine if timing or phasing changes would result in more efficient operation of the traffic signal, or in the case of interconnected systems, the corridor or network. Changes in traffic volumes, posted speeds, or other factors may influence turning movement phasing operations (protected, protected/permissive, or permissive), green times, yellow change intervals, and other operational parameters.

1330.06(1) Left-Turn Phasing

Left-turn phasing can either be permissive, protected/permissive, or protected. It is not necessary that the left-turn mode for an approach be the same throughout the day. Varying the left-turn mode on an approach among the permissive only, protected/permissive, and protected-only left-turn modes during different periods of the day is acceptable. Examples are included in the phase diagrams shown in Exhibit 1330-22 and Exhibit 1330-23.

1. Permissive Left-Turn Phasing

Permissive left-turn phasing requires the left-turning vehicle to yield to opposing through traffic and pedestrians. Permissive left-turn phasing is used when the following are true:

a. Turning volume is minor.

b. Adequate gaps occur in the opposing through movement.

c. Adequate sight distance beyond the intersection is provided.

This phasing is more effective on minor streets where providing separate protected turn phasing might cause significant delays to the higher traffic volume on the main street. On single-lane approaches with a posted speed of 45 mph or above, or where sight distance approaching the intersection is limited, channelization should include a separate left-turn storage lane for the permissive movement to reduce the potential for rear-end-type collisions and delay to through movements.

Unless there is a dedicated left-turn lane, do not provide a separate display for permissive left turns. When there is a dedicated left-turn lane, a three-section flashing yellow arrow display (with steady red arrow, steady yellow arrow, and flashing yellow arrow displays) is recommended for the left-turn lane, as this provides a more positive indication of the permissive turning movement.

2. Protected/Permissive Left-Turn Phasing

Protected/permissive left-turn phasing provides both a protected phase and a permissive phase for the same lane, using the same signal display. Where left-turn phasing will be installed and conditions do not warrant protected-only operation, consider protected/permissive left-turn phasing. Protected/permissive left-turn phasing can result in increased efficiency at some types of intersections, particularly "T" intersections, ramp terminal intersections, and intersections of a two-way street with a one-way street where there are no opposing left-turn movements.

Protected/permissive left-turn phasing is NOT allowed under the following conditions:

a. For new signals, on an approach where Warrant 7 is met and there are five or more left-turning collisions on that approach included in the warranting collisions. This condition requires protected left turn phasing.

b. For existing signals, when documentation shows that existing protected left-turn phasing was installed due to left-turn collisions.

c. When sight distance for left-turning vehicles, as outlined in AASHTO's *A Policy on the Geometric Design of Highways and City Streets*, cannot be met.

d. On intersection approaches where the opposing approach has three or more lanes (including right-turn lanes) and either the posted speed limit or 85th percentile speeds for the opposing approach are at or above 45 mph.

e. On intersection approaches that have dual left-turn lanes, including approaches with left only and through-left lanes.

Where there is a separate left-turn lane, protective/permissive displays may use either of the following display arrangements:

- A dedicated four-section arrow display, with steady red arrow, steady yellow arrow, flashing yellow arrow, and steady green arrow displays (four-section FYA). A three-section display with a bi-modal flashing yellow arrow / steady green arrow may only be used if the signal support cannot accommodate a four-section signal display.
- A shared five-section cluster (doghouse) display, placed over the wide line between the left turn lane and the adjacent through lane.

Where there is no separate left-turn lane, only a five-section vertical (recommended) or cluster display may be used. The five-section display is used in place of the left of the two required through displays for that approach.

Protected/permissive displays may run as lead or lag. The display cycle will depend on the display type and whether the protected left leads or lags:

- Leading 4-section FYA: steady green arrow, steady yellow arrow, steady red arrow, flashing yellow arrow, steady yellow arrow, steady red arrow.
- Leading 5-section: green arrow, yellow arrow, red ball, green ball, yellow ball, red ball. Option: green ball may come up with green arrow, but the arrow and ball displays should cycle to yellow and red together (similar to lagging 5-section)
- Lagging 4-section FYA: flashing yellow arrow, steady green arrow, steady yellow arrow, steady red arrow
- Lagging 5-section: green ball, green ball with green arrow, yellow ball with yellow arrow, red.

A permissive left turn phase shall not terminate separately from the conflicting phase(s) (typically, the opposing through phase). This is to prevent placing left turning traffic in a yellow trap.

3. Protected Left-Turn Phasing

Protected left-turn phasing provides the left-turning vehicle a separate phase, and conflicting movements are required to stop.

Use protected left-turn phasing under the following conditions:

a. Multi-lane left turn movements, including left and through-left from the same approach.

b. The left-turn is onto a roadway with a rail crossing.

c. Where Warrant 7 is met and there are five or more left-turning collisions on that approach included in the warranting collisions. Protected left-turn phasing is recommended even when there are as few as three left-turning collisions on that approach. This includes left-turning collisions involving pedestrians.

d. Where the peak-hour turning volume exceeds the storage capacity of the left-turn lane and one or more of the following conditions is present:

   i. The posted speed or the 85th percentile speed of the opposing traffic is 45 mph or higher.

   ii. The sight distance to oncoming traffic is less than 250 feet when the posted or 85th percentile speed is 35 mph or below, or less than 400 feet when the posted or 85th percentile speed is above 35 mph.

   iii. The left-turn movement crosses three or more lanes (including right-turn lanes) of opposing traffic.

   iv. Geometry or channelization is confusing, such as skewed intersections, offset-T intersections, or intersections which require unusual maneuvers to traverse.

There are three typical operational arrangements for protected left turns:

- Leading Lefts: The left turns are served before the associated through movements. This is the most common operational arrangement. Example: Phases 1 and 5 (major street lefts) are served first, then phases 2 and 6 (major street throughs) are served.
- Lagging Lefts: The left turns are served after the associated through movements. Example: Phases 4 and 8 (minor street throughs) are served first, then phases 3 and 7 (minor street lefts) are served.
- Offset (or Lead/Lag) Lefts: One left turn is served before the associated through movements, and the opposing left turn is served after the associated through movements. Example: Phase 1 (one major left turn) is served first (phase 6 may be served at the same time), then phases 2 and 6 (major throughs) are served, and then phase 5 (opposing major left turn) is served (phase 2 may still be served with phase 5).

Check that all turning movements provide turning clearance for opposing turn phases. If the opposing left-turning vehicle paths do not have 4-foot minimum—12-foot desirable—separation between them, split or offset (lead/lag) phasing will have to be used.

1330.06(2) Right-Turn Phasing

Right turns typically do not operate with their own phasing unless there is a dedicated right turn lane. When there is no dedicated right turn lane, right turns are normally a permissive movement from the right most through lane, depending on pedestrian phases in use. When there is a dedicated right turn lane, right-turn phasing effectively operates the same as left-turn phasing.

Dedicated right turn lanes may be operated the same as left turn lanes: permissive, protected/permissive, or protected. However, right turn phase operation needs to take into account any pedestrian crossing on the receiving side of the right turn. If there is a conflicting pedestrian phase – typically a pedestrian phase running concurrent with the through phase from which the right turn is being made – the right turn phase may only be operated as permissive.

Dedicated right turn lanes operated as permissive and protected/permissive are recommended to have their own displays, but may use a shared display with the adjacent through lane. Dedicated right turn lanes operated as protected must use their own display. Right turn displays are arranged and operated the same as those listed for left turns in 1330.06(1).

Separate right turn phasing also needs to consider some additional operational modes and issues:

1. Right-Turn Overlapped Phasing

A right turn overlap is when a protected right turn is allowed at the same time as a complementary protected left turn, and is recommended when the lane and phase configuration will support this operation. When this operation is used, the left turn must be signed that U-turns are prohibited.

When right turn overlaps are used, the wiring of the right turn displays will depend on the operating mode of each display section:

- Permissive: Connect permissive display sections to the same terminals as the associated through phase.
- Protected: Protected display sections may either be:

  (a) Connected to the complementary left turn phase. Use this arrangement when the protected right turn will only be run concurrent with the complementary left turn phase.

  (b) Connected to an overlap phase. Use this arrangement when the protected right turn will be run with both the complementary left turn phase and with the through phase associated with the right turn.


2. Multiple-Lane Right-Turn Phasing


Multiple-lane right turns may be run independent or overlapped as described above. Multiple-lane right turns can cause operational challenges when "right turn on red" is permitted at the intersection. Verify that there is adequate sight distance and adequate receiving lanes are available to minimize the possibility of collisions. In most cases, a single unrestricted "right-turn-only" lane approach with a separate receiving lane (auxiliary lane) will have a similar capacity as the two lane right-turn phasing.

1330.06(3) Typical Signal Phasing Arrangements


The following diagrams show typical phasing diagrams for four-way and three-way intersections.

Exhibit 1330-22 Phase Diagrams: Four-Way Intersections






Basic Four Phase Operation
All permissive left turns




Six Phase Operation
Main Street protected lefts
Minor Street permissive lefts




Split Phase (Six Phase) Operation*
Main Street protected lefts
Minor Street split - protected lefts
with concurrent through


***With modern controllers, split phases can be run from either the through or the left turn phase.**




Split Phase (Six Phase) Operation*
(Alternate Arrangement)
Main Street protected lefts
Minor Street split - protected lefts
with concurrent through




Eight Phase Operation:
Typical
Leading protected left turns



Eight Phase Operation:
Lagging Lefts
Lagging protected left turns




Eight Phase Operation:
Split Lefts
Opposing left turns split between leading and lagging




Eight Phase Operation:
Overlaps
Leading protected left turns with overlapped protected right turns. Right turns may be permissive with associated through phase.

If right turns are protected with concurrent through phase, negative pedestrian overlaps must be used.


Exhibit 1330-23 Phase Diagrams: Three-Way Intersections




Basic Three Phase Operation
All permissive turns




Three Phase Operation: Restricted Peds
Protected left turn from side street by removing conflicting pedestrian phase (and crossing)




Five Phase Operation: Exclusive Peds
All pedestrian crossings run together as separate phase



Six Phase Operation: Typical
Leading protected left turns



Six Phase Operation: Lagging Lefts
Lagging protected left turns



Six Phase Operation: Overlaps
Leading protected left turns with overlapped protected right turns. Right turns may be permissive with associated through phase.

If right turns are protected with concurrent through phase, negative pedestrian overlaps must be used.

LEGEND


- **Protected Vehicle Movement**
- **Overlap (Protected) Vehicle Movement**
- **(A) Overlap Phase Letter**
- **Protected Pedestrian Movement**


1330.06(4) Phasing at Railroad Crossings

Traffic signals near railroad crossings have additional special phasing arrangements. To provide for efficient signal operations during a rail crossing, ensure that there are dedicated turn lanes for movements turning onto the tracks. These turn lanes should be on their own dedicated phases, so that they may be omitted from the signal timing (held in red) during the rail crossing. This allows for as many of the other intersection movements as possible to continue to operate – a timing scheme referred to as "Limited Service Operation" (LSO).


Just prior to LSO, when railroad preemption is used, the traffic signal will shift to a "Track Clearance Green" (TCG) phase. TCG shifts non-conflicting phases to green to allow vehicles to clear the railroad tracks. Examples of a TCG phase and LSO are shown in Exhibit 1330-24. Standalone queue cutter signals do not have a TCG phase – contact the HQ Traffic Office for operational guidance on standalone queue cutter signals.


Exhibit 1330-24 Phasing at Railroad Crossings





Track Clearance Green





Limited Service Operation

1330.07 Documentation

The following original signal design documents shall be included in a Signal System file and provided to the region Traffic Office or owning agency:

1. Signal Permit, including Signal Warrant Analysis and supporting documentation.
2. FHWA Approval for Experimentation.
3. Signal Standard Design Chart, including signal support engineering calculations.
4. Signal Detection Zone Placement. Include calculations if used.
5. Signal Wiring Diagram and Conduit Fill calculations.
6. Railroad preemption calculation and interconnect setup.
7. Any third party documentation provided.
8. Approved Preliminary Signal Plan.
9. Emergency Preemption Equipment selected.
10. Transit Priority Preemption and associated agreements.

Copies of items 1 and 2 are also required to be included in the Design Documentation Package (DDP). Copies of items 3 through 10 are also required to be included in the Project File (PF).

Refer to Chapter 300 for additional design documentation requirements.

1330.08 References

The following references are used in the planning, design, construction, and operation of traffic control signals installed on state highways. The RCWs noted are specific state laws concerning traffic control signals, and conformance to these statutes is required.

1330.08(1) Federal/State Laws and Codes

Americans with Disabilities Act of 1990 (ADA) (28 CFR Part 35)

Revised Code of Washington (RCW) 35.77, Streets – Planning, establishment, construction, and maintenance

RCW 46.04.450, Railroad sign or signal

RCW 46.04.600, Traffic control signal

RCW 46.04.62250, Signal preemption device

RCW 46.61.050, Obedience to and required traffic control devices

RCW 46.61.055, Traffic control signal legend

RCW 46.61.060, Pedestrian control signals

RCW 46.61.065, Flashing signals

RCW 46.61.070, Lane-direction-control signals

RCW 46.61.072, Special traffic control signals – Legend

RCW 46.61.075, Display of unauthorized signs, signals, or markings

RCW 46.61.080, Interference with official traffic-control devices or railroad signs or signals

RCW 46.61.085, Traffic control signals or devices upon city streets forming part of state highways – Approval by department of transportation

RCW 46.61.340, Approaching train signal

RCW 47.24.020(6) and (13), Jurisdiction, control

RCW 47.36.020, Traffic control signals

RCW 47.36.060, Traffic devices on county roads and city streets

Washington Administrative Code (WAC) 468 18-040, Design standards for rearranged county roads, frontage roads, access roads, intersections, ramps and crossings

WAC 468-18-050, Policy on the construction, improvement and maintenance of intersections of state highways and city streets

"City Streets as Part of State Highways: Guidelines Reached by the Washington State Department of Transportation and the Association of Washington Cities on the Interpretation of Selected Topics of RCW 47.24 and Figures of WAC 468-18-050 for the Construction, Operations and Maintenance Responsibilities of WSDOT and Cities for Such Streets," April 30, 1997.

1330.08(2) Design Guidance

A Policy on the Geometric Design of Highways and City Streets (Green Book), AASHTO

Guide for Determining Time Requirements for Traffic Signal Preemption at Highway-Rail Grade Crossings (TxDOT Form 2304) and Instructions for Form 2304 (TxDOT Form 2304-I), Texas Department of Transportation
http://www.txdot.gov/inside-txdot/forms-publications/forms/rail.html

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)

Plans Preparation Manual, M 22-31, WSDOT

Revised Draft Guidelines for Accessible Public Rights-of-Way, (PROWAG), November 23, 2005, United States Access Board

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21 01, WSDOT

Standard Specifications for Road, Bridge, and Municipal Construction (Standard Specifications), M 41-10, WSDOT

WSDOT Traffic Design Resources
www.wsdot.wa.gov/design/traffic/

Chapter 1340 Driveways

1340.01 General
1340.02 References
1340.03 Design Considerations
1340.04 Driveway Design Templates
1340.05 Sidewalks
1340.06 Driveway Sight Distance (Eye height – 3.5 ft., Object height – 3.5 ft.)
1340.07 Stormwater and Drainage
1340.08 Mailboxes
1340.09 Documentation

1340.01 General



For the purpose of this chapter, and to remain consistent with WSDOT's *Standard Plans* and AASHTO terminology, the terms "access" and "approach" will be referred to as "driveway." An access on a managed access highway is defined as an "access connection," while an access on a limited access highway is defined as an "approach."

This chapter describes the design guidelines, including sight distance criteria, for driveway connections on the state highway system. WSDOT controls driveways on all limited access state highways, and regulates driveways on all managed access state highways outside the incorporated limits of a city or town. RCW 47.50.030 states that cities and towns, regardless of population size, are the permitting authority for managed access state highways within their respective incorporated city and town limits. The RCW also requires those cities and towns to adopt standards for access permitting on managed access state highways that meet or exceed WSDOT standards, provided those adopted standards are consistent with WSDOT standards.

Limited access highways are roadways to which WSDOT has acquired the access rights from abutting property owners. Driveways, if they have been allowed, are documented and recorded in a deed. Chapter 530 describes the three levels of limited access highways: full, partial, and modified. Any change to the number, type, and use of a limited access driveway must be approved by Headquarters through the process outlined in Chapter 530. A general permit is required to allow any new construction or repairs for a deeded driveway on a limited access highway. Access connection permits are not issued on limited access highways.

Any roadway that is not a limited access highway is a managed access highway. Chapter 540 describes the five classes of managed access highways: Class 1 (most restrictive) to Class 5 (least restrictive). An access connection permit is required to allow the use, operation, and maintenance of a driveway connection on a managed access highway, outside incorporated cities, where WSDOT is the access permitting authority. Check with Development Services to ascertain where WSDOT has permitting authority (such as tribal lands or National Parks).

1340.02 References

1340.02(1) State Laws and Codes

Revised Code of Washington (RCW) 47.32.150, Approach roads, other appurtenances – Permit

RCW 47.32.160, Approach roads, other appurtenances – Rules – Construction, maintenance of approach roads

RCW 47.32.170, Approach roads, other appurtenances – Removal of installations from right-of-way for default

Chapter 47.50 RCW, Highway access management

Chapter 47.52 RCW, Limited access facilities

Chapter 468-51 Washington Administrative Code (WAC), Highway access management access permits – Administrative process

Chapter 468-52 WAC, Highway access management – Access control classification system and standards

Chapter 468-58 WAC, Limited access highways

1340.02(2) Design Guidance

Right of Way Manual, M 26-01, WSDOT

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT

Development Services Manual, M 3007, WSDOT

Limited Access and Managed Access Master Plan, WSDOT
www.wsdot.wa.gov/design/accessandhearings/tracking.htm

1340.03 Design Considerations

1340.03(1) General

The design of a driveway is based on the usage, design vehicle, and traffic volumes anticipated for the driveway. Generally, the driveway should be designed to accommodate the largest vehicle that will regularly use the driveway. For example, a residential driveway connection will typically have smaller radii and a narrower access width than a higher-volume commercial driveway.

However, if the property owner regularly has larger-wheelbase vehicles using the driveway, such as a home-based work vehicle, recreational vehicle, or truck and boat trailer combination, then a larger driveway may be appropriate.

Conversely, some driveways, such as a rural locked and gated utility, farm, or logging access that larger vehicles sometimes use, may be better served with a smaller and narrower access. This is based on infrequent use and to prevent unauthorized use or dumping of debris on or near the driveway. Other design considerations are:

- Prevent stormwater from flowing onto the roadway from the driveway.
- Properly size culverts under the driveway to adequately accommodate the conveyance of stormwater in the roadway ditches and swales.
- Provide driveway sight distance.
- Accommodate for mailbox placement.
- Ensure surfacing materials and depths are appropriate.
- Generally, extend paving to the right of way line depending on the location/purpose of the driveway. The desirable intersection angle of the driveway is 90°, with 60° to 120° allowed.

1340.03(2) WSDOT Projects

When evaluating access connections or approaches on a project, review existing driveways for possible alterations, relocations, consolidations, or closures. The first step in that process is to determine the legality of the driveway. The region Development Services Office can provide a list of the permitted driveway connections on a managed access highway, noting that, per RCW 47.50.080, Permit removal, "Unpermitted connections to the state highway system in existence on July 1, 1990, shall not require the issuance of a permit and may continue to provide access to the state highway system, unless the permitting authority determines that such a connection does not meet minimum acceptable standards of highway safety." As a result, driveway connections on a managed access state highway can be considered to be permitted, grandfathered, or unpermitted as described below:


- *Permitted* driveways hold a valid permit and shall remain valid until modified or revoked.
- *Grandfathered* driveways that were in existence and in active use consistent with the type of connection on July 1, 1990, may continue to provide connection to the state highway system. They do not require the issuance of a new permit and may continue to provide access to the state highway system, unless the permitting authority determines that such a connection does not meet minimum acceptable standards of highway safety.
- *Unpermitted* driveways are not allowed. The permitting authority may initiate action to close the unpermitted driveway in compliance with the applicable chapters of 47.50 RCW and 468-51 and 468-52 WAC. These are driveways that do not have a permit and were constructed after July 1, 1990.

If a WSDOT project proposes to alter, relocate, consolidate, or close a driveway—regardless of whether the driveway is permitted, grandfathered, or unpermitted—it is required that a new access connection permit be issued for any driveways that are to remain. If a driveway is to be removed, formal notification to the property owner will be provided as specified in WAC 468-51-040. Unless determined otherwise, the affected property owners of driveways that will be altered, relocated, consolidated, or closed will not have the right of an adjudicative proceeding. Additional information regarding this process can be obtained by contacting your region's Development Services Office.


On limited access highways, both the region Development Services and Real Estate Services offices may provide assistance to determine the legality of an existing driveway. Federal Highway Administration approval is required for driveway modifications on Interstate facilities.

1340.04 Driveway Design Templates

There are two design templates for use where there is no adjacent sidewalk. (When a driveway connection has or will have adjacent sidewalk, see 1340.05.) The templates may be used on both limited access and managed access state highways. If an Interstate limited access driveway is allowed, it must be gated. Considering the context of use, Exhibit 1340-1 is generally used for design vehicles of SU-30 and smaller, while Exhibit 1340-2 is generally used for design vehicles of SU-30 and larger.



Driveway Design Template SU-30 and Smaller
Exhibit 1340-1



Driveway Design Template SU-30 and Larger
Exhibit 1340-2

Use the design template that will best accommodate the intended use of the driveway, unless a smaller driveway is appropriate and will not adversely affect the traveled way of the state highway. If necessary, use turn simulation software (such as AutoTURN®) to verify the driveway design will adequately accommodate the largest vehicle that will regularly use the driveway.

1340.05 Sidewalks

If a driveway connection has (or will have) adjacent sidewalk, use the applicable Cement Concrete Driveway Entrance Standard Plan F-80.10 and width issued on the access permit. The design and construction of any sidewalk shall be compliant with Chapter 1510 and Section F of the *Standard Plans*, in addition to the latest Americans with Disabilities Act criteria.


1340.06 Driveway Sight Distance (Eye height – 3.5 ft., Object height – 3.5 ft.)

A driver on the highway needs to see far enough ahead to assess developing situations and take actions appropriate for the conditions, such as when a vehicle is either entering or leaving the highway at a driveway.

In addition, drivers entering the highway from a driveway also need to see enough of the highway, whether to the left or right, so they can take actions appropriate for the conditions to enter the highway in a reasonably safe manner.

Design and locate driveways such that the sight distances meet or exceed the distances shown in Exhibit 1340-3; these distances may require an approaching vehicle to reduce speed or stop to prevent a collision. In addition, provide decision sight distance for through traffic at all utility and special-use driveways on facilities with limited access control (see Chapter 1260).

For road approaches with AWDVTE greater than 1,500, use intersection sight distance criteria (see Chapter 1310). Areas along driveway legs and across their included corners should be clear of obstructions that might block or affect a driver's view of potentially conflicting vehicles.



Posted Speed Limit (mph)	25	30	35	40	45	50	55	60	65	70
Driveway Sight Distance (ft)	155	200	250	305	360	425	495	570	645	730

Notes:

[1] Measured from the edge of through lane. If the desirable 18-foot setback cannot be achieved, obtain as much as practicable, down to a 10-foot minimum.

[2] Not required for driveways restricted to right in/right out.

Driveway Sight Distance
Exhibit 1340-3

1340.07 Stormwater and Drainage

Design a driveway to slope away from the highway for a distance to prevent stormwater runoff and other debris from flowing onto the traveled lanes and shoulders of the highway. If this is not feasible, then other measures may be necessary to divert the stormwater away from the traveled lanes and shoulder of the highway.



If the driveway will in any way interfere with the flow of stormwater in an existing ditch or swale located on the state highway right of way, install a culvert with beveled ends (see Chapter 1600). Choose a culvert size that will adequately handle the stormwater (see the *Highway Runoff Manual*). Contact either the region hydraulic engineer or the applicable region maintenance office for assistance. Consider placing quarry spalls at each end of the open culvert to prevent erosion. If the installation of new culvert requires the installation of a catch basin, it is desirable to locate the catch basin outside the normal traveled way of the driveway.

1340.08 Mailboxes

Refer to Chapter 1600, Roadside Safety, for guidance regarding the placement of mailboxes.

1340.09 Documentation

Refer to Chapter 300 for design documentation requirements.

Chapter 1350 Railroad Grade Crossings

1350.01 General
1350.02 References
1350.03 Plans
1350.04 Traffic Control Systems
1350.05 Nearby Roadway Intersections
1350.06 Pullout Lanes
1350.07 Crossing Surfaces
1350.08 Crossing Closure
1350.09 Traffic Control During Construction and Maintenance
1350.10 Railroad Grade Crossing Petitions and WUTC Orders
1350.11 Grade Crossing Improvement Projects
1350.12 Light Rail
1350.13 Documentation

1350.01 General

Highway-rail grade crossings ("grade crossings") are the intersection of two modes of transportation with very different physical and operational characteristics. Because of the inherent limitations associated with train operations, RCW 46.61.350 gives train traffic the right of way at grade crossings, thereby assigning motorists the primary responsibility to avoid collisions.

There are many variables that influence a motorist's ability to react appropriately at grade crossings, including what information is available to them as they approach the crossing and human factors such as competing decisions, distractions, and impaired driving. Primary factors in the design of grade crossings are roadway and railway geometry; available sight distance; highway and railway speeds; competing decisions or visual distractions; and the types of warning devices at the grade crossing.

Another aspect of grade crossing design is coordination of highway traffic signal operations with grade crossing active warning devices ("railroad preemption") when signalized intersections are located near grade crossings. In such instances, railroad preemption is designed to clear the tracks of any vehicles that may be stopped as a result of the highway traffic signal when a train is approaching the grade crossing. Further guidance on railroad preemption requirements is provided in Chapter 1330.

Grade crossings are also unique due to their multijurisdictional nature. Highway authorities and railroad companies are each legally responsible for different elements at grade crossings. Additionally, the Washington Utilities and Transportation Commission (WUTC) is the state regulatory agency with oversight of public grade crossings in Washington, except within the limits of first class cities in accordance with RCW 81.53.240. Establishing new crossings, altering existing crossings, or closing crossings all require WUTC approval. Therefore, highway projects that include a grade crossing will generally require close coordination with both the railroad company and the WUTC.

Projects that include grade crossings will generally require execution of construction and maintenance agreements between the Washington State Department of Transportation (WSDOT) and the railroad company. These agreements specify the design elements of the crossing, work that the railroad will perform on behalf of the project, payment terms, and legal provisions. It may also be necessary for WSDOT to obtain easements from the railroad company for new grade crossings on railroad property. The Headquarters (HQ) Railroad Liaison is responsible for facilitating highway project coordination with railroad companies, including developing agreements and obtaining WUTC approvals. Obtaining necessary approvals from the railroad company may take several months. Contact the HQ Railroad Liaison early in the design phase so that all necessary design and agreement coordination can be completed according to project schedules.

More information about general railroad coordination and WUTC requirements is provided in Chapter 3 of the *Utilities Manual*.

1350.02 References

(1) Federal/State Laws and Codes

Revised Code of Washington (RCW) 81.53, Railroad crossings
http://apps.leg.wa.gov/rcw/default.aspx?cite=81.53

Washington Administrative Code (WAC) 480-62-150, Grade crossing petitions
http://apps.leg.wa.gov/wac/default.aspx?cite=480-62-150

(2) Design Guidance

Agreements Manual, M 22-99, WSDOT
http://wwwi.wsdot.wa.gov/publications/manuals/m22-99.htm

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)
www.wsdot.wa.gov/publications/manuals/mutcd.htm

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT
www.wsdot.wa.gov/publications/manuals/m21-01.htm

(3) Supporting Information

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO

Guidance On Traffic Control Devices At Highway-Rail Grade Crossings, Highway/Rail Grade Crossing Technical Working Group (TWG), FHWA, November 2002
http://safety.fhwa.dot.gov/xings/collision/twgreport/

Railroad-Highway Grade Crossing Handbook, FHWA, August 2007
http://safety.fhwa.dot.gov/xings/com_roaduser/07010/

Manual on Uniform Traffic Control Devices Part 8. Traffic Control for Railroad and Light Rail Transit Grade Crossings
http://mutcd.fhwa.dot.gov/htm/2009/part8/part8_toc.htm

1350.03 Plans

(1) Proposed Improvements

Include plans for proposed improvements to existing crossings and any new crossings in the Plans, Specifications, and Estimates (PS&E) package. In addition to basic roadway dimensions, signs, and markings, indicate the angle of crossing; number of tracks; location of signals and other railway facilities (such as electrical/communications lines and control boxes); and the limits of property ownership by the railroad company at the crossing location.

For any project proposing to alter the horizontal or vertical alignment at a grade crossing, including grade separations, show the alignment and profile for both the railroad and the roadway for a minimum of 500 feet on all legs of the crossing. Show all other important features that might affect the safety, operation, and design of the crossing, such as nearby crossroads, driveways/entrances, buildings, and highway structures on the plans.

(a) Sight Distance


A railroad grade crossing is comparable to the intersection of two highways where a sight triangle is kept clear of obstructions or it is protected by a traffic control device. The desirable sight distance allows a driver to see an approaching train at a distance that allows the vehicle to stop well in advance of the crossing if signals, or gates and signals, are not present (see Exhibit 1350-1, Case 2). Sight distances of the order shown are desirable at any railroad grade crossing not controlled by railroad flashing light signals or gates (active warning devices). Attainment of optimal sight distances is often difficult and impracticable due to topography and terrain. Even in flat, open terrain, the growth of crops or other seasonal vegetation can create a permanent or seasonal sight distance obstruction. Furthermore, the properties upon which obstructions might exist are commonly owned by the railroad or others. Evaluate installation of active devices at any location where adequate sight distances cannot be provided. Include communication with the railroad and the WUTC in your evaluation.

The driver of a vehicle stopped at a crossing with signal lights but no gates needs to be able to see far enough down the tracks from the stop bar to be able to cross the tracks before a train, approaching at maximum allowable speed, reaches the crossing (see Exhibit 1350-1, Case 1).

(b) Highway Grade and Crossing Angle

Construct highway grades so that low-clearance vehicles do not hang up on tracks or damage them. (See Chapter 1220 for information on vertical alignment at railroad grade crossings.) Whenever possible, design the roadway to cross grade crossings at right angles. If bicycle traffic uses the crossing (this can be assumed for most roads), provide a shoulder through the grade crossing at least as wide as the approach shoulder width. If a skew is unavoidable, wider shoulders may be needed to permit bicycles to maneuver to cross the tracks at right angles. (See Chapter 1520 for information on bikeways crossing railroad tracks.) Consider installation of advance warning signs indicating the presence of a skewed crossing for crossings where engineering judgment suggests a benefit.

Include any engineering studies or sight distance measurements in the Design Documentation Package (DDP).



d_t = Sight distance along railroad tracks (ft)
d_h = Sight distance along highway (ft)
d_e = Distance from driver to front of vehicle (8 ft)
D = Distance from stop line to nearest rail (15 ft)
W = Distance between outer rails (single track W=5 ft)
V_v = Velocity of vehicle (mph)
f = Coefficient of friction
V_t = Velocity of train (mph)
L = Length of vehicle (65 ft)

Notes:

- Adjust for skewed crossings.
- Assume flat highway grades adjacent to and at crossings.

Train Speed (mph) V_t	Case 1: Departure From Stop	Case 2: Moving Vehicle						
		Vehicle Speed (mph) V_v						
		10	20	30	40	50	60	70
		f=0.40	0.40	0.35	0.32	0.30	0.29	0.28
	Distance Along Railroad From Crossing d_t (ft)							
10	240	146	106	99	100	105	111	118
20	480	293	212	198	200	209	222	236
30	721	439	318	297	300	314	333	355
40	961	585	424	396	401	419	444	473
50	1,201	732	530	494	501	524	555	591
60	1,441	878	636	593	601	628	666	706
70	1,681	1,024	742	692	701	733	777	828
80	1,921	1,171	848	791	801	833	888	946
90	2,162	1,317	954	890	901	943	999	1,064
		Distance Along Highway From Crossing dh (ft)						
		69	135	220	324	447	589	751
Design sight distance for a combination of highway and train vehicle speeds and a 65-ft truck crossing a single set of tracks at 90° (AASHTO).								

Source: *A Policy on Geometric Design of Highway and Streets*, 2004, by the American Association of State Highway and Transportation Officials.

Sight Distance at Railroad Crossing

Exhibit 1350-1

1350.04 Traffic Control Systems

(1) Traffic Control System Elements

There are two categories of railroad warning devices: "passive" and "active." Passive devices include all signs and pavement markings. Active devices include flashing light signals, railroad warning gates, and active advance warning systems, all of which are activated by approaching trains.

(a) Passive Elements

1. The following signing elements are shown in the MUTCD, Part 8, Traffic Control for Highway-Rail Grade Crossings:

   - **Highway-Rail Grade Crossing (Crossbuck) sign:** Crossbuck signs identify the location of the grade crossing and convey the same meaning as a yield sign. The railroad is responsible for installation and maintenance of Crossbuck signs.

     Note: Railroads are required to upgrade standard Crossbuck signs at passive grade crossings to "Crossbuck Assemblies" by December 31, 2019. Crossbuck Assemblies are Crossbuck signs mounted in conjunction with STOP or YIELD signs. Any projects that establish new passive crossings or result in reconstruction of passive crossings should include design of Crossbuck Assemblies. (See Chapter 8 of the MUTCD for additional guidance.)

   - **Supplemental Number of Tracks (inverted "T") sign:** This sign is mounted below the Crossbuck sign to indicate the number of tracks when two or more tracks are involved. The railroad is responsible for installation and maintenance of these signs.

   - **Grade Crossing Advance Warning sign (W10 sign series):** The road authority is responsible for installation and maintenance of these signs.

   - **Exempt sign:** This is a supplemental sign that, when authorized by the WUTC, may be mounted below the Crossbuck sign. When this sign is approved, certain classes of vehicles, otherwise required to stop before crossing the tracks, may proceed without stopping, provided no train is approaching. The road authority is responsible for installation and maintenance of these signs.

   - **Do Not Stop on Tracks sign:** This sign is used where it is determined that additional emphasis is needed to remind motorists of this legal requirement, such as where nearby roadway intersections result in queuing back across the tracks. The road authority is responsible for installation and maintenance of these signs.

2. Pavement markings on all paved approaches are the responsibility of the road authority and consist of **RR Crossing** markings in accordance with the *Standard Plans*, **No Passing** markings, and **Pullout Lanes**, as appropriate.

3. Consider the installation of illumination at and adjacent to railroad crossings where an engineering study determines that better nighttime visibility of the train and the grade crossing is needed. For example, where:
   - A substantial number of railroad operations are conducted at night.
   - Grade crossings are blocked for long periods at night by slow-speed trains.
   - Collision history indicates that drivers experience difficulty seeing trains during hours of darkness.

(b) Active Elements

1. **Railroad Flashing Light Signals and Gates:** These are active devices intended to warn motorists of approaching trains and impose a stopping requirement. The railroad is responsible for installation and maintenance of these devices.

2. **Traffic Signal Interconnection (also known as "railroad preemption"):** These provide linkage between the railroad signals and adjacent traffic signals to allow vehicles to clear the tracks at a traffic signal as a train approaches. They are typically funded by the road authority and require cooperation with the railroad for installation. The formation of a Railroad Crossing Evaluation Team is required to determine signal railroad preemption requirements. (See Chapter 1330 for further guidance.)

3. **Pre-Signals:** These are traffic control signal faces that control roadway traffic approaching a grade crossing in conjunction with the traffic control signal faces that control traffic approaching a roadway-roadway intersection beyond the tracks. Pre-signals are typically used where the clear storage distance is insufficient to store one or more design vehicles.

4. **Active Advance Warning Systems:** These are supplemental flashing yellow beacons mounted along with the grade crossing advance warning signs that are interconnected to the railroad active warning devices. Activation of the railroad active warning devices activates the beacons to provide motorists with an advance indication that a train is approaching or occupying the crossing. Active advance warning systems are typically used where roadway geometry prevents a clear view of the grade crossing ahead, or where higher highway speeds may require advance notification of an impending stopping requirement. Use a plaque stating "Train When Flashing" as part of such systems.

5. **Supplemental Safety Devices:** Supplemental safety devices are typically used at locations where it is known that motorists frequently drive around gates, where unique local safety hazards exist, or as part of railroad quiet zones where trains are no longer required to sound the locomotive horn. (For more information about quiet zones, see www.fra.dot.gov/us/content/1318.)

   Typical supplemental safety devices include:

   - Four-Quadrant Gate Systems: These are additional gates placed on the opposite side of the roadway from the primary railroad warning gates that, when lowered, make it impossible for motorists to drive around the lowered gates. (See Chapter 8 of the MUTCD for additional information on four-quadrant gate systems.

- Median Separators: This is a system of raised delineators extending along the roadway centerline back from the tip of a lowered railroad warning gate that prevents motorists from being able to drive around the lowered gates. Make median separators at least 60 feet in length where sufficient space is available.

(c) Selection of Grade Crossing Warning Devices

At a minimum:

- All public grade crossings are required to be equipped with Crossbuck signs, a supplemental plaque indicating the presence of multiple tracks (if applicable), and advance warning signs.
- Railroad pavement markings are required at all crossings where active warning devices are present or the posted legal speed limit is 40 mph or higher.

Passive warning devices notify drivers that they are approaching a grade crossing and to be on the lookout for trains. In general, consider stand-alone passive warning devices at grade crossings with low volumes and speeds on both the highway and railway, and where adequate sight distances exist. Active warning devices are to be considered at all other crossings. No national or state warrants have been developed for installation of traffic control devices at grade crossings. Furthermore, due to the large number of significant variables that need to be considered, there is no single system of active traffic control devices universally applicable for grade crossings. Warning systems at grade crossings should be based on an engineering and traffic investigation, including input from the railroad and the WUTC. Primary factors to consider in selecting warning devices are train and highway volumes and speeds; highway and railway geometry; pedestrian volume; accident history; and available sight distance.

Evaluate railroad signal supports and gate mechanisms as roadside features to be considered for mitigation. Use traffic barrier or impact attenuators as appropriate (see Division 16).

1350.05 Nearby Roadway Intersections

Operations at roadway intersections located near grade crossings can present significant challenges for grade crossing safety. In particular, vehicle queues originating from the roadway intersection and extending back to the grade crossing must be clear of the tracks before the arrival of any trains. While RCW 46.61.570 prohibits motorists from stopping on any railroad tracks, it is not uncommon for motorists to stop on tracks when focusing on the downstream highway intersection rather than the immediate grade crossing.

For signalized highway intersections where vehicle queues result from a red signal indication, clearance of vehicles from the grade crossing is accomplished through traffic signal interconnection with the railroad warning signals (“railroad preemption”). When railroad preemption is in place, an approaching train will initiate a special mode within the highway traffic signal specifically designed to clear any vehicles from the tracks prior to the arrival of the train at the grade crossing. Railroad preemption design involves a specialized analysis that considers the distance between the roadway intersection and grade crossing; queue clearance times; train speeds; the capabilities of the railroad active warning devices; and other traffic signal phases.

Where the distance between the grade crossing and the roadway intersection is not sufficient to store a design vehicle, a pre-signal may be considered to prevent subsequent vehicles from entering the grade crossing limits during the track clearance phases of the downstream highway signal. Additionally, whenever a signalized roadway intersection is located 500 feet from a grade crossing, a Railroad Crossing Evaluation Team, which includes representatives from both WSDOT and the railroad company, will jointly determine the need for and design of railroad preemption systems. (See Chapter 1330 for further guidance on railroad preemption requirements.)


Vehicle queues over the tracks can also result from operations at nonsignalized roadway intersections; for example, where there is a short distance between the grade crossing and a roadway intersection controlled by a STOP or YIELD sign. A "Do Not Stop on Tracks" sign should be installed at locations where the distance between the grade crossing and the roadway intersection is not sufficient to store a design vehicle or it is otherwise determined that vehicle queues originating from the roadway intersection routinely extend back to the grade crossing. To determine whether or not to consider a highway traffic signal in such instances, refer to MUTCD Traffic Signal Warrant 9.

1350. 06 Pullout Lanes

In accordance with RCW 46.61.350, certain vehicles are required to stop at all railroad crossings unless the grade crossing is flagged or an "Exempt" sign is posted. Evaluate the installation of "pullout" lanes when grade crossings have no active protection. Some school districts have a policy that school buses must stop at all grade crossings regardless of the type of control. Consider the installation of pullout lanes at any public grade crossing used regularly by school buses or by trucks transporting flammable cargo or explosives and at which they must stop.

Contact the local school district for school bus information. Contact the Truck Freight Program and Policy Manager at the WSDOT HQ Freight Systems Division about truck freight operations in the project vicinity.

Design pullout lane geometrics in accordance with Exhibit 1350-2. The minimum shoulder width adjacent to the pullout lane is 3 feet.



Ld = Total length of pullout lane, approach
La = Total length of pullout lane, exit

Approach Length of Pullout Lane, L_d		Downstream Length of Pullout Lane, L_a	
Vehicle Speed (mph)	**Length (ft)**	**Vehicle Speed (mph)**	**Length (ft)**
30	235	30	*
40	320	40	360
50	435	50	720
60	530	60	1,200
*Taper length only			

Typical Pullout Lane at Railroad Crossing
Exhibit 1350-2

1350.07 Crossing Surfaces

Railroads are responsible for the maintenance of crossing surfaces up to 12 inches outside the edge of rail (WAC 480-62-225). Crossing surfaces can be constructed of a number of different materials, including asphalt, concrete, steel, timber, rubber, or plastic. The most common surface types used on state highway crossings are asphalt, precast concrete, and rubber. Timbered crossings are frequently used for low-volume roads and temporary construction crossings.

The life of a crossing surface depends on the volume and weight of highway and rail traffic using it. Highway traffic not only dictates the type of crossing surface, but it also has a major influence on the life of the crossing. Rough crossing surfaces impact the motoring public far more than the railroad. Therefore, when a highway project passes through a railroad grade crossing, consider the condition of the crossing surface. While the existing condition might not warrant railroad investment in replacing it, the surface might have deteriorated sufficiently to increase vehicle operating costs and motorist inconvenience. In such cases, it may be effective to partner with the railroad to replace the crossing as part of the highway project. Such partnerships typically consist of the state reimbursing the railroad for all or a portion of the cost of the work.

1350.08 Crossing Closure

The MUTCD states, "Any highway-rail grade crossing that cannot be justified should be eliminated." Coordination with the appropriate railroad and the Washington Utilities and Transportation Commission is required before any grade crossing can be closed. If a state route grade crossing appears unused, consult the HQ Railroad Liaison before taking any action. Close at-grade crossings that are replaced by grade separations.

1350.09 Traffic Control During Construction and Maintenance

Provide work zone traffic control for projects at highway-rail grade crossings, which need protection from train traffic. When highway construction or maintenance activities affect a railroad crossing, the railroad company must be notified at least ten days before performing the work (WAC 480-62-305(4)). Furthermore, whenever highway construction or maintenance crews or equipment are working within 25 feet of an active rail line or grade crossing, consult the railroad to determine whether a railroad flagger is required. Current contact numbers for railroads may be obtained by contacting your region Utilities Engineer or the HQ Railroad Liaison. Railroad flaggers differ from highway flaggers in that they have information on train schedules and can generally communicate with trains by radio. When flaggers are required, the railroad generally sends the road authority a bill for the cost of providing this service.

Do not allow work zone traffic to stop or queue up on a nearby rail-highway grade crossing unless railroad flaggers are present. Without proper protection, vehicles might be trapped on the tracks when a train approaches. (See the MUTCD for more detailed guidance.)

For projects requiring temporary access across a set of railroad tracks, contact the HQ Railroad Liaison early in the design process since a railroad agreement or permit will likely be required.

1350.10 Railroad Grade Crossing Petitions and WUTC Orders

The Washington Utilities and Transportation Commission (WUTC) is authorized by statute (Title 81 RCW) to have regulatory authority over railroad crossings. Establishing new crossings, closing existing crossings, or modifying existing grade crossings must be approved by the WUTC (WAC 480-62-150). WUTC authority does not apply within the limits of first class cities, in accordance with RCW 81.53.240. This is accomplished by submitting a formal petition to the WUTC for a formal order. The HQ Railroad Liaison will assist in the preparation and submittal of this petition. Include a copy of the petition and WUTC findings and order in the Design Documentation Package.

1350.11 Grade Crossing Improvement Projects

The HQ Highways and Local Programs Office (H&LP) administers the federal (Section 130) Grade Crossing Safety Improvement Program. Project proposals are submitted by local agencies, railroads, and WSDOT.

Contact H&LP or the HQ Railroad Liaison in the Utilities, Railroads, and Agreements Section for more information.

1350.12 Light Rail

Light rail transit systems have been implemented and will continue to be developed in some urban areas of the state. For the most part, criteria for light rail transit crossings are very similar to those for freight and passenger rail with the exception of locations where light rail shares a street right of way with motor vehicles. The MUTCD now includes guidance devoted exclusively to light rail transit and can be consulted as the situation warrants.

1350.13 Documentation

For the list of documents required to be preserved in the Design Documentation Package and the Project File, see the Design Documentation Checklist:
www.wsdot.wa.gov/design/projectdev/

Chapter 1360 Interchanges

1360.01 General
1360.02 Interchange Design
1360.03 Ramps
1360.04 Interchange Connections
1360.05 Ramp Terminal Intersections at Crossroads
1360.06 Interchanges on Two-Lane Highways
1360.07 Interchange Plans for Approval
1360.08 Documentation
1360.09 References

1360.01 General

The primary purpose of an interchange is to reduce conflicts caused by vehicle crossings and minimize conflicting left-turn movements. Provide interchanges on all Interstate highways and freeways, and at other locations where traffic cannot be controlled efficiently by intersections at grade.

For additional information, see the following chapters:

Chapter	Subject
520	Access control
530	Limited access
550	Interchange justification report
1103	Design controls
1106	Design element dimensions
1240	Turning widths
1250	Cross Slope and Superelevation
1310	Intersections
1410	HOV lanes
1420	HOV direct access connections

1360.02 Interchange Design

1360.02(1) General

All freeway exits and entrances, except HOV direct access connections, are to connect on the right of through traffic. Variations from this will be considered only for special conditions.

HOV direct access connections may be constructed on the left of through traffic when they are designed in accordance with Chapter 1420.

Provide complete ramp facilities for all directions of travel wherever possible. However, give primary consideration to the basic traffic movement function that the interchange is to fulfill.

Complications are rarely encountered in the design and location of rural interchanges that simply provide a means of exchanging traffic between a limited access freeway and a local

crossroad. Carefully consider the economic and operational effects of locating traffic interchanges along a freeway through a community, particularly with respect to local access, to provide convenient local service without reducing the capacity of the major route(s).

Where freeway-to-freeway interchanges are involved, do not provide ramps for local access unless they can be added conveniently and without detriment to efficient traffic flow or reduction of capacity, either ramp or freeway main line. When exchange of traffic between freeways is the basic function, and local access is prohibited by access control restrictions or traffic volume, separate interchanges for local service may be needed.

1360.02(2) Interchange Patterns

Basic interchange patterns have been established that can be used under certain general conditions and modified or combined to apply to many more. Consider alternatives in the design of a specific facility; however, the conditions in the area and on the highway involved govern the final design of the interchange.

Selection of the final design is based on a study of projected traffic volumes, site conditions, geometric controls, criteria for intersecting legs and turning roadways, driver expectancy, consistent ramp patterns, continuity, and cost.

The patterns most frequently used for interchange design are those commonly described as directional, semidirectional, cloverleaf, partial cloverleaf, diamond, and single point (urban) interchange (see Exhibit 1360-1).

1360.02(2)(a) Directional

A directional interchange is the most effective design for connection of intersecting freeways. The directional pattern has the advantage of reduced travel distance, increased speed of operation, and higher capacity. These designs eliminate weaving and have a further advantage over cloverleaf designs in avoiding the loss of sense of direction drivers experience in traveling a loop. This type of interchange is costly to construct, commonly using a four-level structure.

1360.02(2)(b) Semidirectional

A semidirectional interchange has ramps that loop around the intersection of the highways. This results in multiple single-level structures and more area than the directional interchange.

1360.02(2)(c) Cloverleaf

The full cloverleaf interchange has four loop ramps for the left-turning traffic. Outer ramps provide for the right turns. A full cloverleaf is the minimum type interchange for a freeway-to-freeway interchange. Cloverleaf designs often incorporate a C-D road to minimize signing difficulties and remove weaving conflicts from the main roadway.

The principal advantage of this design is the elimination of all left-turn conflicts with one single-level structure. Because all movements are merging movements, it is adaptable to any grade line arrangement.

The cloverleaf has some major disadvantages. The left-turn movement has a circuitous route on the loop ramp, the speeds are low on the loop ramp, and there are weaving conflicts between the loop ramps. The cloverleaf also needs a large area. The weaving and the radius of the loop ramps are a capacity constraint on the left-turn movements.

1360.02(2)(d) Partial Cloverleaf (PARCLO)

A partial cloverleaf has loop ramps in one, two, or three quadrants that are used to eliminate the major left-turn conflicts. These loops may also serve right turns for interchanges where ramp cannot be built in one or two quadrants. Outer ramps are provided for the remaining turns. Design the grades to provide sight distance between vehicles approaching these ramps.

1360.02(2)(e) Diamond

A diamond interchange has four ramps that are essentially parallel to the major arterial. Each ramp provides for one right-turn and one left-turn movement. Because left turns are made at grade across conflicting traffic on the crossroad, intersection sight distance is a primary consideration.


The diamond design is the most generally applicable and serviceable interchange configuration and usually has a smaller footprint than any other type. Consider this design first unless another design is clearly dictated by traffic, topography, or special conditions.

1360.02(2)(f) Single Point Urban (SPUI)


A single point urban interchange is a modified diamond with all of its ramp terminals on the crossroad combined into one signalized at-grade intersection. This single intersection accommodates all interchange and through movements.

A single point urban interchange can improve the traffic operation on the crossroad with less right of way than a typical diamond interchange, but a larger structure.


Exhibit 1360-1 Basic Interchange Patterns




Directional




Semidirectional




Cloverleaf With C-D Roads



Diamond



Single Point Urban Interchange (SPUI)



Partial Cloverleaf


1360.02(3) Spacing

To avoid excessive interruption of main line traffic, consider each proposed facility in conjunction with adjacent interchanges, intersections, and other points of access along the route as a whole.

The minimum spacing between adjacent interchanges is 1 mile in urban areas, 3 miles on the Interstate in rural areas, and 2 miles on non-Interstate in rural areas (see Exhibit 1360-2). In urban areas, spacing less than 1 mile may be used with C-D roads or grade-separated (braided) ramps. Interchange spacing is measured along the freeway centerline between the centerlines of the crossroads.

The spacing between interchanges may also be dependent on the spacing between ramp connections. The minimum spacing between the gore noses of adjacent ramps is given in Exhibit 1360-3.

Exhibit 1360-2 Interchange Spacing



Notes:

[1] As a minimum, provide length for weaving and signing, but not less than given in Exhibit 1360-3.

[2] 3 miles on the Interstate System.

Consider either frontage roads or C-D roads to facilitate the operation of near-capacity volumes between closely spaced interchanges or ramp terminals. C-D roads may be needed where cloverleaf loop ramps are involved or where a series of interchange ramps have overlapping speed change lanes. Base the distance between successive ramp terminals on capacity. Check the intervening sections by weaving analyses to determine whether capacity, sight distance, and effective signing can be provided without the use of auxiliary lanes or C-D roads.

Provide justifications for existing interchanges with less-than-desirable spacing or ramp connection spacing to remain in place.

1360.02(4) Route Continuity

Route continuity is providing the driver of a through route a path on which lane changes are minimized and other traffic operations occur to the right.

In maintaining route continuity, interchange configuration may not favor the heavy traffic movement, but rather the through route. In this case, design the heavy traffic movements with multilane ramps, flat curves, and reasonably direct alignment.





1360.02(5) Drainage

Avoid interchanges located in proximity to natural drainage courses. These locations often result in complex and unnecessarily costly hydraulic structures. The open areas within an interchange can be used for stormwater detention facilities.

1360.02(6) Uniformity of Exit Pattern

While interchanges are of necessity custom-designed to fit specific conditions, it is desirable that the pattern of exits along a freeway have some degree of uniformity. From the standpoint of driver expectancy, it is desirable that each interchange have only one point of exit, located in advance of the crossroad.

Exhibit 1360-3 Minimum Ramp Connection Spacing

On-On or Off-Off		Off-On		Turning Roadways		On-Off (Weaving)			
									
Freeway	C-D Road	Freeway	C-D Road	System[2] Interchange	Service[3] Interchange	A	B	C	D
1,000	800	500	400	800	600	2000	1600	1600	1000
Gore nose									

L = Minimum distance in feet from gore nose to gore nose.

A = Between two interchanges connected to a freeway: a system interchange[2] and a service interchange.[3]

B = Between two interchanges connected to a C-D road: a system interchange[2] and a service interchange.[3]

C = Between two interchanges connected to a freeway: both service interchanges.[3]

D = Between two interchanges connected to a C-D road: both service interchanges.[3]

Notes:

These values are based on operational experience, need for flexibility, and signing. Check them in accordance with Exhibit 1360-12 and the procedures outlined in the *Highway Capacity Manual*, and use the larger value.

[1] With justification, these values may be reduced for cloverleaf ramps.

[2] A system interchange is a freeway-to-freeway interchange.

[3] A service interchange is a freeway-to-local road interchange.

1360.03 Ramps

1360.03(1) Ramp Design Speed

The design speed for a ramp is based on the design speed for the freeway main line.

It is desirable that the ramp design speed at the connection to the freeway be equal to the free-flow speed of the freeway. Meet or exceed the upper range values from Exhibit 1360-4 for the design speed at the ramp connection to the freeway. Transition the ramp design speed to provide a smooth acceleration or deceleration between the speeds at the ends of the ramp. However, do not reduce the ramp design speed below the lower-range speed of 25 mph. For loop ramps, use a design speed as high as feasible, but not lower than 25 mph.

These design speed guidelines do not apply to the ramp in the area of the ramp terminal at-grade intersection. In the area of the intersection, use a design speed of 15 mph for turning traffic or 0 mph for a stop condition. Use the allowed skew at the ramp terminal at-grade intersection to minimize ramp curvature.

For freeway-to-freeway ramps and C-D roads, the design speed at the connections to both freeways is the upper range values from Exhibit 1360-4; however, with justification, the midrange values from Exhibit 1360-4 may be used for the remainder of the ramp. When the design speed for the two freeways is different, use the higher design speed.

Existing ramps meet design speed criteria if acceleration or deceleration criteria are met (see Exhibit 1360-9 or 1360-10) and superelevation meets the criteria in Chapter 1250.

Exhibit 1360-4 Ramp Design Speed

Main Line Design Speed (mph)		50	55	60	65	70	80
Ramp Design Speed (mph)	Upper Range	45	50	50	55	60	70
	Midrange	30	40	45	45	50	60
	Lower Range	25	25	25	25	25	25

1360.03(2) Sight Distance

Design ramps in accordance with the provisions in Chapter 1260 for stopping sight distances.

1360.03(3) Grade

The maximum grade for ramps for various design speeds is given in Exhibit 1360-5.

Exhibit 1360-5 Maximum Ramp Grade

Ramp Design Speed (mph)		25 – 30	35 – 40	45 and above
Ramp Grade (%)	Desirable	5	4	3
	Maximum *	7	6	5
* On one-way ramps, downgrades may be 2% greater				

1360.03(4) Cross Section

Provide the ramp widths given in Exhibit 1360-6. Ramp traveled ways may need additional width when operational needs exist.

Cross slope and superelevation criteria for ramp traveled ways and shoulders are as given in Chapter 1250 for roadways. At ramp terminals, the intersection lane and shoulder width design guidance shown in Chapter 1310 may be used.

Whenever feasible, make the ramp cross slope at the ramp beginning or ending station equal to the cross slope of the through lane pavement. Where space is limited and superelevation runoff is long, or when parallel connections are used, the superelevation transition may be ended beyond (for on-ramps) or begun in advance of (for off-ramps) the ramp beginning or ending station, provided that the algebraic difference in cross slope at the edge of the through lane and the cross slope of the ramp does not exceed 4%. In such cases, provide smooth transitions for the edge of traveled way.

Exhibit 1360-6 Ramp Widths

Number of Lanes			1	2
Ramp Width (ft)	Traveled Way [1]		11-13 [5]	23-25 [3] [5]
	Shoulders	Right	4-8 [2] [5]	4-8 [2] [5]
		Left	2	2-4
	Medians [4]		6	6-8

Notes:

[1] Evaluate shoulder use to accommodate offtracking, if determined inadequate for operational performance needs, apply turning roadway widths in Chapter 1240.

[2] Provide width necessary to accommodate offtracking by large vehicles.

[3] Add 12 ft for each additional lane.

[4] The minimum two-way ramp median width (including shoulders) is given. Wider medians may be required for signs or other traffic control devices and their respective clearances. When either the on- or off-ramp is single-lane, use the one-lane column. If both directions are two lanes, use the two-lane column.

[5] Use the mode/function/performance approach described in Chapter 1106 to choose between the range of widths given.

Ramp shoulders may be used by large trucks for offtracking and by smaller vehicles cutting to the inside of curves. Evaluate the need to pave shoulders full depth for larger vehicle offtracking using turn simulation software on one-way ramps to accommodate this type of use. If operational performance needs demonstrate that accommodation of offtracking on shoulders is inadequate apply turning roadway widths in Chapter 1240.

1360.03(5) Two-Way Ramps

Two-way ramps are on- and off-ramps on a single roadway. Design two-way ramps as separate one-way ramps. Provide a raised median to physically separate the on- and off- ramps. Wider medians than given in Exhibit 1360-6 may be required for signing or other traffic control devices and their clearances. (For signs, it is sign width plus 4 feet.) Where wider medians are required, provide a 2-foot clearance between the face of curb and the edge of traveled way. Where additional width is not required, the raised median width may be reduced to a double-faced

mountable or extruded curb. Traffic barrier or a depressed median may be provided in place of the raised median.

1360.03(6) Ramp Lane Increases

When off-ramp traffic and left-turn movement volumes at the ramp terminal at-grade intersection cause excessive queue length, it may be desirable to add lanes to the ramp to reduce the queue length caused by congestion and turning conflicts. Make provision for the addition of ramp lanes whenever ramp exit or entrance volumes are expected to result in an undesirable mobility or safety performance. (See Chapter 1210 for width transition design.)

1360.03(7) Ramp Meters

Ramp meters are used to allow a measured or regulated amount of traffic to enter the freeway. When operating in the "measured" mode, they release traffic at a measured rate to keep downstream demand below capacity and improve system travel times. In the "regulated" mode, they break up platoons of vehicles that occur naturally or result from nearby traffic signals. Even when operating at near capacity, a freeway main line can accommodate merging vehicles one or two at a time, while groups of vehicles will cause main line flow to break down.

The location of the ramp meter is a balance between the storage and acceleration criteria. Locate the ramp meter to maximize the available storage and so that the acceleration lane length, from a stop to the freeway main line design speed, is available from the stop bar to the merging point. With justification, the average main line running speed during the hours of meter operation may be used for the highway design speed to determine the minimum acceleration lane length from the ramp meter. (See 1360.04(4) for information on the design of on-connection acceleration lanes and Chapter 1050 for additional information on the design of ramp meters.)

Driver compliance with the signal is required for the ramp meter to have the desired results. Consider enforcement areas with metered ramps.

Consider HOV bypass lanes with ramp meters. (See Chapter 1410 for design data for ramp meter bypass lanes.)

1360.04 Interchange Connections

To the extent practicable, provide uniform geometric design and uniform signing for exits and entrances in the design of a continuous freeway. Do not design an exit ramp as an extension of a main line tangent at the beginning of a main line horizontal curve.


Provide spacing between interchange connections as given in Exhibit 1360-3.

Avoid on-connections on the inside of a main line curve, particularly when the ramp approach angle is accentuated by the main line curve, the ramp approach results in a reverse curve to connect to the main line, or the elevation difference will cause the cross slope to be steep at the nose.

Keep the use of mountable curb at interchange connections to a minimum.

Provide justification when curb is used adjacent to traffic with a design speed of 40 mph or higher.

Exhibit 1360-7a Lane Balance



*Note: Number of lanes (F) may increase by one lane, when the lane is an auxiliary lane between closely spaced entrance and exit ramps.

1360.04(1) Lane Balance

Design interchanges to the following principles of lane balance:

1360.04(1)(a) Entrances

At entrances, make the number of lanes beyond the merging of two traffic streams not less than the sum of all the lanes on the merging roadways less one (see Exhibit 1360-7a).

1360.04(1)(b) Exits


At exits, make the number of approach lanes equal the number of highway lanes beyond the exit plus the number of exit lanes less one (see Exhibit 1360-7a). Exceptions to this are:

- At a cloverleaf.
- At closely spaced interchanges with a continuous auxiliary lane between the entrance and exit.

In these cases, the auxiliary lane may be dropped at a single-lane, one-lane reduction off-connection (Exhibit 1360-14c), with the number of approach lanes being equal to the sum of the highway lanes beyond the exit and the number of exit lanes. Closely spaced interchanges have a distance of less than 2,100 feet between the end of the acceleration lane and the beginning of the deceleration lane.

Maintain the basic number of lanes, as described in Chapter 1210, through interchanges. When a two-lane exit or entrance is used, maintain lane balance with an auxiliary lane (see Exhibit 1360-7b). The exception to this is when the basic number of lanes is changed at an interchange.

Exhibit 1360-7b Lane Balance



1360.04(2) Main Line Lane Reduction


The reduction of a basic lane or an auxiliary lane may be made at a two-lane exit or may be made between interchanges. When a two-lane exit is used, provide a recovery area with a normal acceleration taper. When a lane is dropped between interchanges, drop it 1,500 to 3,000 feet from the end of the acceleration taper of the previous interchange. This allows for signing but will not be so far that the driver becomes accustomed to the number of lanes and will be surprised by the reduction (see Exhibit 1360-8).

Reduce the traveled way width of the freeway by only one lane at a time.


1360.04(3) Sight Distance

Locate off-connections and on-connections on the main line to provide decision sight distance for a speed/path/direction change as described in Chapter 1260.


Exhibit 1360-8 Main Line Lane Reduction Alternatives




Lane dropped at two-lane off-connection




Lane between closely spaced ramps
dropped at single-lane off-connection
(lane imbalance for weaving)



Lane between closely spaced ramps
dropped at single-lane off-connection
(lane balance for weaving)



Lane dropped within intersection



Lane dropped between interchanges

1360.04(4) On-Connections

On-connections are the paved areas at the end of on-ramps that connect them to the main lane of a freeway. They have two parts: an acceleration lane and a taper. The acceleration lane allows entering traffic to accelerate to the freeway speed and evaluate gaps in the freeway traffic. The taper is for the entering vehicle to maneuver into the through lane.

On-connections are either tapered or parallel. The tapered on-connection provides direct entry at a flat angle, reducing the steering control needed. The parallel on-connection adds a lane adjacent to the through lane for acceleration with a taper at the end. Vehicles merge with the through traffic with a reverse curve maneuver similar to a lane change. While less steering control is needed for the taper, the parallel is narrower at the end of the ramp and has a shorter taper at the end of the acceleration lane.

1360.04(4)(a) Acceleration Lane

Provide the minimum acceleration lane length, given in Exhibit 1360-9, for each ramp design speed on all on-ramps. When the average grade of the acceleration lane is 3% or greater, multiply the distance from the Minimum Acceleration Lane Length table by the factor from the Adjustment Factor for Grades table.


For existing ramps that do not have significant crashes in the area of the connection with the freeway, the freeway posted speed may be used to calculate the acceleration lane length for Preservation projects. If corrective action is indicated, use the freeway design speed to determine the length of the acceleration lane.

The acceleration lane is measured from the last point designed at each ramp design speed (usually the PT of the last curve for each design speed) to the last point of the ramp width. Curves designed at higher design speeds may be included as part of the acceleration lane length.


1360.04(4)(b) Gap Acceptance

For parallel on-connections, provide the minimum gap acceptance length (Lg) to allow entering motorists to evaluate gaps in the freeway traffic and position their vehicles to use the gap. The length is measured beginning at the point that the left edge of traveled way for the ramp intersects the right edge of traveled way of the main line to the ending of the acceleration lane (see Exhibits 1360-13b and 13c). The gap acceptance length and the acceleration length overlap, with the ending point controlled by the longer of the two.

Exhibit 1360-9 Acceleration Lane Length



Tapered On-Connection



Parallel On-Connection

Highway Design Speed (mph)	Ramp Design Speed (mph)										
	0	15	20	25	30	35	40	45	50	60	70
30	180	140									
35	280	220	160								
40	360	300	270	210	120						
45	560	490	440	380	280	160					
50	720	660	610	550	450	350	130				
55	960	900	810	780	670	550	320	150			
60	1200	1140	1100	1020	910	800	550	420	180		
65	1410	1350	1310	1220	1120	1000	770	600	370		
70	1620	1560	1520	1420	1350	1230	1000	820	580	210	
80	2000	1950	1890	1830	1730	1610	1380	1200	970	590	210

Minimum Acceleration Lane Length (ft)

Highway Design Speed (mph)	Grade	Upgrade				Downgrade
		Ramp Design Speed				All Ramp Design Speeds
		20	30	40	50	
40	3% to less than 5%	1.3	1.3			0.70
45		1.3	1.35			0.675
50		1.3	1.4	1.4		0.65
55		1.35	1.45	1.45		0.625
60		1.4	1.5	1.5	1.6	0.60
70		1.5	1.6	1.7	1.8	0.60
40	5% or more	1.5	1.5			0.60
45		1.5	1.6			0.575
50		1.5	1.7	1.9		0.55
55		1.6	1.8	2.05		0.525
60		1.7	1.9	2.2	2.5	0.50
70		2.0	2.2	2.6	3.0	0.50

Adjustment Factors for Grades Greater Than 3%

Note: Lane widths are shown for illustrative purposes. Determine lane widths based on Exhibit 1360-6.

1360.04(4)(c) Single-Lane On-Connections

Single-lane on-connections may be either tapered or parallel. The tapered is desirable; however, the parallel may be used with justification. Design single-lane tapered on-connections as shown in Exhibit 1360-13a and single-lane parallel on-connections as shown in Exhibit 1360-13b.

1360.04(4)(d) Two-Lane On-Connections

For two-lane on-connections, the parallel is desirable. Design two-lane parallel on-connections as shown in Exhibit 1360-13c. A capacity analysis will normally be the basis for determining whether a freeway lane or an auxiliary lane is to be provided.

Justify the use of a two-lane tapered on-connection. Design two-lane tapered on connections in accordance with Exhibit 1360-13d.

1360.04(5) Off-Connections

Off-connections are the paved areas at the beginning of an off-ramp, connecting it to a main lane of a freeway. They have two parts: a taper for maneuvering out of the through traffic and a deceleration lane to slow to the speed of the first curve on the ramp. Deceleration is not assumed to take place in the taper.

Off-connections are either tapered or parallel. The tapered is desirable because it fits the normal path for most drivers. When a parallel connection is used, drivers tend to drive directly for the ramp and not use the parallel lane. However, when a ramp is on the outside of a curve, the parallel off-connection is desirable. An advantage of the parallel connection is that it is narrower at the beginning of the ramp.


1360.04(5)(a) Deceleration Lane

Provide the minimum deceleration lane length given in Exhibit 1360-10 for each design speed for all off-ramps. Also, provide deceleration lane length to the end of the anticipated queue at the ramp terminal. When the average grade of the deceleration lane is 3% or greater, multiply the distance from the Minimum Deceleration Lane Length table by the factor from the Adjustment Factor for Grades table.


For existing ramps that do not have significant crashes in the area of the connection with the freeway, the freeway posted speed may be used to calculate the deceleration lane length for Preservation projects. If corrective action is indicated, use the freeway design speed to determine the length of the deceleration lane.

The deceleration lane is measured from the point where the taper reaches the selected ramp lane width to the first point designed at each ramp design speed (usually the PC of the first curve for each design speed). Curves designed at higher design speeds may be included as part of the deceleration lane length.

Exhibit 1360-10 Deceleration Lane Length



Tapered Off-Connection



Parallel Off-Connection

Highway Design Speed (mph)	Ramp Design Speed (mph)										
	0	15	20	25	30	35	40	45	50	60	70
30	235	200	170	140							
35	280	250	210	185	150						
40	320	295	265	235	185	155					
45	385	350	325	295	250	220	155				
50	435	405	385	355	315	285	225	175			
55	480	455	440	410	380	350	285	235	180		
60	530	500	480	460	430	405	350	300	240		
65	570	540	520	500	470	440	390	340	280	185	
70	615	590	570	550	520	490	440	390	340	240	
80	735	710	690	670	640	610	555	510	465	360	265

Minimum Deceleration Lane Length (ft)

Grade	Upgrade	Downgrade
3% to less than 5%	0.9	1.2
5% or more	0.8	1.35

Adjustment Factors for Grades Greater Than 3%

Note: Lane widths are shown for illustrative purposes. Determine lane widths based on Exhibit 1360-6.

1360.04(5)(b) Gores

Gores (see Exhibits 1360-11a and 11b) are decision points. Design them to be clearly seen and understood by approaching drivers. In a series of interchanges along a freeway, it is desirable that the gores be uniform in size, shape, and appearance.

The paved area between the physical nose and the gore nose is the reserve area. It is reserved for the installation of an impact attenuator. The minimum length of the reserve area is controlled by the design speed of the main line (see Exhibits 1360-11a and 11b).

In addition to striping, raised pavement marker rumble strips may be placed for additional warning and delineation at gores. (See the *Standard Plans* for striping and rumble strip details.)

Keep the unpaved area beyond the gore nose as free of obstructions as possible to provide a clear recovery area. Grade this unpaved area as nearly level with the roadways as possible. Avoid placing obstructions such as heavy sign supports, luminaire poles, and structure supports in the gore area.

When an obstruction is placed in a gore area, provide an impact attenuator (see Chapter 1620) and barrier (see Chapter 1610). Place the beginning of the attenuator as far back in the reserve area as possible, desirably after the gore nose.

1360.04(5)(c) Single-Lane Off-Connections

For single-lane off-connections, the tapered is desirable. Use the design shown in Exhibit 1360-14a for tapered single-lane off-connections. Justify the use of a parallel single-lane off-connection, as shown in Exhibit 1360-14b.

1360.04(5)(d) Single-Lane Off-Connection With One Lane Reduction

The single-lane off-connection with one lane reduction, shown in Exhibit 1360-14c, is used when the conditions from lane balance for a single-lane exit, one-lane reduction, are met.


1360.04(5)(e) Tapered Two-Lane Off-Connection

The tapered two-lane off-connection design, shown in Exhibit 1360-14d, is desirable where the number of freeway lanes is reduced or where high-volume traffic operations will be improved by the provision of a parallel auxiliary lane and the number of freeway lanes is unchanged.

1360.04(5)(f) Parallel Two-Lane Off-Connection

The parallel two-lane off-connection, shown in Exhibit 1360-14e, allows less operational flexibility than the taper, requiring more lane changes. Justify the use of a parallel two-lane off-connection.

Exhibit 1360-11a Gore Area Characteristics



Single-Lane Off-Connections: No Lane Reduction

Notes:


[1] The reserve area length (L) is not less than:

Main Line Design Speed (mph)	40	45	50	55	60	65	70	80
L (ft)	25	30	35	40	45	50	55	70

[2] $Z = \frac{\text{Design Speed}}{2}$, design speed is for the main line.

[3] Radius may be reduced, when protected by an impact attenuator.

Exhibit 1360-11b Gore Area Characteristics



Single-Lane, One-Lane Reduction Off-Connections
and All Two-Lane Off-Connections

Notes:

[1] The reserve area length (L) is not less than:

Main Line Design Speed (mph)	40	45	50	55	60	65	70	80
L (ft)	25	30	35	40	45	50	55	70

[2] $Z = \frac{\text{Design Speed}}{2}$, design speed is for the main line.

[3] Radius may be reduced, when protected by an impact attenuator.

1360.04(6) Collector-Distributor (C-D) Roads

A C-D road can be within a single interchange, through two closely spaced interchanges, or continuous through several interchanges. Design C-D roads that connect three or more interchanges to be two lanes wide. Other C-D roads may be one or two lanes in width, depending on capacity. Consider intermediate connections to the main line for long C-D roads.

a. Exhibit 1360-15a shows the designs for collector-distributor outer separations. Use Design A, with concrete barrier, when adjacent traffic in either roadway is expected to exceed 40 mph. Design B, with mountable curb, may be used when adjacent posted speed does not exceed 40 mph.

b. The details shown in Exhibit 1360-15b apply to single-lane C-D road off-connections. Design a two-lane C-D road off-connection, with the reduction of a freeway lane or an auxiliary lane, as a normal two-lane off-connection in accordance with 1360.04(5).

c. Design C-D road on-connections in accordance with Exhibit 1360-15c.

1360.04(7) Loop Ramp Connections

Loop ramp connections at cloverleaf interchanges are distinguished from other ramp connections by a low-speed ramp on-connection, followed closely by an off-connection for another low-speed ramp. The loop ramp connection design is shown in Exhibit 1360-16. The minimum distance between the ramp connections is dependent on a weaving analysis. When the connections are spaced far enough apart that weaving is not a consideration, design the on-connection in accordance with 1360.04(4) and the off-connection in accordance with 1360.04(5).

1360.04(8) Weaving Sections


Weaving sections may occur within an interchange, between closely spaced interchanges, or on segments of overlapping routes. Exhibit 1360-12 gives the length of the weaving section for preliminary design. The total weaving traffic is the sum of the traffic entering from the ramp to the main line and the traffic leaving the main line to the exit ramp in equivalent passenger cars. For trucks, a passenger car equivalent of two may be estimated. Use the Highway Capacity Manual for the final design of weaving sections.

Because weaving sections cause considerable turbulence, interchange designs that eliminate weaving or remove it from the main roadway are desirable. Use C-D roads for weaving between closely spaced ramps when adjacent to high-speed highways. C-D roads are not needed for weaving on low-speed roads.

1360.05 Ramp Terminal Intersections at Crossroads

Design ramp terminal intersections at grade with crossroads as intersections at grade (see Chapter 1300). Whenever possible, design ramp terminals to discourage wrong-way movements. Locate ramp terminal intersections at grade with crossroads to provide signal progression if the intersection becomes signalized in the future. Provide intersection sight distance as described in Chapters 1310 or 1320.

Exhibit 1360-12 Length of Weaving Sections



Note:

To determine whether or not lane balance for weaving exists, see Exhibit 1360-8.

1360.06 Interchanges on Two-Lane Highways

Occasionally, the first stage of a conventional interchange will be built with only one direction of the main roadway and operated as a two-lane two-way roadway until the ultimate roadway is constructed.

The design of interchanges on two-lane two-way highways may vary considerably from traditional concepts due to the following conditions:

- The potential for cross-centerline crashes due to merge conflicts or motorist confusion.
- The potential for wrong-way or U-turn movements.
- Future construction considerations.
- Traffic type and volume.
- The proximity to multilane highway sections that might influence a driver's impression that these roads are also multilane.

Provide the deceleration taper for all interchange exit ramps on two-lane highways. Design the entering connection with either the normal acceleration taper or a "button hook" configuration with a stop condition before entering the main line. Consider the following items:

- Design the stop condition connection in accordance with a tee (T) intersection as shown in Chapter 1310. Use this type of connection when an acceleration lane is not possible. Provide decision sight distance as described in Chapter 1260.
- Since designs may vary from project to project, analyze each project for the most efficient signing placement, such as one-way, two-way, no passing, do not enter, directional arrows, guideposts, and traffic buttons.
- Prohibit passing through the interchange area on two-lane highways by means of signing, pavement marking, or a combination of both. The desirable treatment is a 4 foot median island, highlighted with raised pavement markers and diagonal stripes. When using a 4-foot median system, extend the island 500 feet beyond any merging ramp traffic acceleration taper. The width for the median can be provided by reducing each shoulder 2 feet through the interchange (see Exhibit 1360-17).
- Include signing and pavement markings to inform both the entering and through motorists of the two-lane two-way characteristic of the main line.
- Use as much of the ultimate roadway as possible. Where this is not possible, leave the area for future lanes and roadway ungraded.
- Design and construct temporary ramps as if they were permanent unless second-stage construction is planned to rapidly follow the first stage. Design the connection to meet the needs of the traffic.

1360.07 Interchange Plans for Approval

Exhibit 1360-18 is a sample showing the general format and data for interchange design plans.

Compass directions (W-S Ramp) or crossroad names (E-C Street) may be used for ramp designations.

Include the following, as applicable:

- Design speeds (see Chapter 1103) for main line and crossroads.
- Curve data on main line, ramps, and crossroads.
- Numbers of lanes and widths of lanes and shoulders on main line, crossroads, and ramps.
- Superelevation diagrams for the main line, the crossroad, and all ramps; these may be submitted on separate sheets.
- Channelization.
- Stationing of ramp connections and channelization.
- Proposed right of way and access control treatment (see Chapters 510, 520, and 530).
- Delineation of all crossroads, existing and realigned.
- Traffic data for the proposed design; include all movements.
- For HOV direct access connections on the left, include the statement that the connection will be used solely by HOVs or will be closed.

Prepare a preliminary contour grading plan for each completed interchange. Show the desired contours of the completed interchange, including details of basic land formation, slopes, graded areas, or other special features. Coordinate the contour grading with the drainage design and the roadside development plan.

1360.08 Documentation

Refer to Chapter 300 for design documentation requirements.

1360.09 References

1360.09(1) Design Guidance

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)

Plans Preparation Manual, M 22-31, WSDOT

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21 01, WSDOT

Standard Specifications for Road, Bridge, and Municipal Construction (Standard Specifications), M 41-10, WSDOT

1360.09(2) Supporting Information


A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO, current edition

A Policy on Design Standards – Interstate System, AASHTO, 2005

Highway Capacity Manual (Special Report 209), Transportation Research Board

Procedure for Analysis and Design of Weaving Sections: A User's Guide, Jack E. Leisch, October 1985

Exhibit 1360-13a On-Connection: Single-Lane, Tapered



Notes:

[1] For acceleration lane length L_A, see Exhibit 1360-9.

[2] Point Ⓐ is the point controlling the ramp design speed.

[3] A transition curve with a minimum radius of 3000 ft is desirable. The desirable length is 300 ft. When the main line is on a curve to the left, the transition may vary from a 3000-ft radius to tangent to the main line.


[4] Radius may be reduced when concrete barrier is placed between the ramp and main line.


[5] Lane and shoulder widths are shown for illustrative purposes. For ramp lane and shoulder widths, see Exhibit 1360-6.

[6] Approximate angle to establish ramp alignment.

General: For striping, see the *Standard Plans*.

Exhibit 1360-13b On-Connection: Single-Lane, Parallel





Paving detail

Notes:

[1] For acceleration lane length L_A, see Exhibit 1360-9.

[2] Point Ⓐ is the point controlling the ramp design speed.

[3] A transition curve with a minimum radius of 3000 ft is desirable. The desirable length is 300 ft. When the main line is on a curve to the left, the transition may vary from a 3000-ft radius to tangent to the main line. The transition curve may be replaced by a 50:1 taper with a minimum length of 300 ft.

[4] Radius may be reduced when concrete barrier is placed between the ramp and main line.


[5] Lane and shoulder widths are shown for illustrative purposes. For ramp lane and shoulder widths, see Exhibit 1360-6.

[6] Ramp stationing may be extended to accommodate superelevation transition.

General:

For striping, see the *Standard Plans*.

Exhibit 1360-13c On-Connection: Two-Lane, Parallel



Notes:

[1] For acceleration lane length L_A, see Exhibit 1360-9.

[2] Point Ⓐ is the point controlling the ramp design speed.

[3] A transition curve with a minimum radius of 3000 ft is desirable. The desirable length is 300 ft. When the main line is on a curve to the left, the transition may vary from a 3000-ft radius to tangent to the main line. The transition curve may be replaced by a 50:1 taper with a minimum length of 300 ft.

[4] Radius may be reduced when concrete barrier is placed between the ramp and main line.

[5] Lane and shoulder widths are shown for illustrative purposes. For ramp lane and shoulder widths, see Exhibit 1360-6.


[6] Ramp stationing may be extended to accommodate superelevation transition.

[7] Added lane or 1,500-ft auxiliary lane plus 600-ft taper.

General:

For striping, see the *Standard Plans*.

Exhibit 1360-13d On-Connection: Two-Lane, Tapered



Notes:

[1] For acceleration lane length L_A, see Exhibit 1360-9.

[2] Point Ⓐ is the point controlling the ramp design speed.

[3] A transition curve with a minimum radius of 3000 ft is desirable. The desirable length is 300 ft. When the main line is on a curve to the left, the transition may vary from a 3000-ft radius to tangent to the main line.

[4] Radius may be reduced when concrete barrier is placed between the ramp and main line.

[5] Lane and shoulder widths are shown for illustrative purposes. For ramp lane and shoulder widths, see Exhibit 1360-6.


[6] Approximate angle to establish ramp alignment.

[7] Added lane or 1,500-ft auxiliary lane plus 600-ft taper.

General:

For striping, see the *Standard Plans*

Exhibit 1360-14a Off-Connection: Single-Lane, Tapered



**	T	△ [5]
Desirable	20	92° 52'
Minimum	15	93° 49'

Notes:

[1] For deceleration lane length L_D, see Exhibit 1360-10.

[2] Point Ⓐ is the point controlling the ramp design speed.

[3] For gore details, see Exhibit 1360-11a.


[4] Lane and shoulder widths are shown for illustrative purposes. For ramp lane and shoulder widths, see Exhibit 1360-6.

[5] Approximate angle to establish ramp alignment.

General:

For striping, see the *Standard Plans*.

Exhibit 1360-14b Off-Connection: Single-Lane, Parallel



Notes:

[1] For deceleration lane length L_D, see Exhibit 1360-10.

[2] Point Ⓐ is the point controlling the ramp design speed.

[3] For gore details, see Exhibit 1360-11a.


[4] Lane and shoulder widths are shown for illustrative purposes. For ramp lane and shoulder widths, see Exhibit 1360-6.

[5] Ramp stationing may be extended to accommodate superelevation transition.

General:

For striping, see the *Standard Plans*.

Exhibit 1360-14c Off-Connection: Single-Lane, One-Lane Reduction



**	T	△ [5]
Desirable	20	92° 52'
Minimum	15	93° 49'

Notes:

[1] For deceleration lane length L_D, see Exhibit 1360-10.

[2] Point Ⓐ is the point controlling the ramp design speed.

[3] For gore details, see Exhibit 1360-11b.

[4] Lane and shoulder widths are shown for illustrative purposes. For ramp lane and shoulder widths, see Exhibit 1360-6.


[5] Approximate angle to establish ramp alignment.

[6] Auxiliary lane between closely spaced interchanges to be dropped.

General:

For striping, see the *Standard Plans*.

Exhibit 1360-14d Off-Connection: Two-Lane, Tapered



Notes:

[1] For deceleration lane length L_D, see Exhibit 1360-10.

[2] Point Ⓐ is the point controlling the ramp design speed.

[3] For gore details, see Exhibit 1360-11b.

[4] Lane and shoulder widths are shown for illustrative purposes. For ramp lane and shoulder widths, see Exhibit 1360-6.


[5] Approximate angle to establish ramp alignment.

[6] Lane to be dropped or auxiliary lane with a minimum length of 1,500 ft with a 300-ft taper.

General:

For striping, see the *Standard Plans*.

Exhibit 1360-14e Off-Connection: Two-Lane, Parallel



Notes:

[1] For deceleration lane length L_D, see Exhibit 1360-10.

[2] Point Ⓐ is the point controlling the ramp design speed.

[3] For gore details, see Exhibit 1360-11b.

[4] Lane and shoulder widths are shown for illustrative purposes. For ramp lane and shoulder widths, see Exhibit 1360-6.


[5] Ramp stationing may be extended to accommodate superelevation transition.

[6] Lane to be dropped or auxiliary lane with a minimum length of 1,500 ft with a 300-ft taper.

General:

For striping, see the *Standard Plans*.

Exhibit 1360-15a Collector-Distributor: Outer Separations




Notes:

[1] With justification, the concrete barrier may be placed with 2 ft between the edge of either shoulder and the face of barrier. This reduces the width between the edge of through-lane shoulder and the edge of C-D road shoulder to 6 ft and the radius at the nose to 3 ft.

[2] For collector-distributor road lane and shoulder widths, see ramp lane and shoulder widths, Exhibit 1360-6.

Exhibit 1360-15b Collector Distributor: Off-Connections



Notes:

[1] For deceleration lane length L_D, see Exhibit 1360-10.

[2] Point Ⓐ is the point controlling the C-D road or ramp design speed.

[3] For gore details, see Exhibit 1360-11a.

[4] For C-D road and ramp lane and shoulder widths, see Exhibit 1360-6.

[5] Approximate angle to establish alignment.


[6] May be reduced with justification (see Exhibit 1360-15a).

General:

For striping, see the Standard Plans.

Lane and shoulder widths are shown for illustrative purposes. Determine lane and shoulder widths based on Exhibit 1360-6.

Exhibit 1360-15c Collector Distributor: On-Connections



Notes:

[1] For acceleration lane length L_A, see Exhibit 1360-9.

[2] Point Ⓐ is the point controlling the ramp design speed.

[3] A transition curve with a minimum radius of 3000 ft is desirable. The desirable length is 300 ft. When the C-D road is on a curve to the left, the transition may vary from a 3000-ft radius to tangent to the C-D road.

[4] For C-D road and ramp lane and shoulder widths, see Exhibit 1360-6.

[5] Approximate angle to establish alignment.


[6] May be reduced with justification (see Exhibit 1360-15a).

General:

For striping, see the Standard Plans..

Lane and shoulder widths are shown for illustrative purposes. Determine lane and shoulder widths based on Exhibit 1360-6.

Exhibit 1360-16 Loop Ramp Connections



Notes:

[1] For minimum weaving length, see Exhibit 1360-12.

[2] Lane and shoulder widths are shown for illustrative purposes. For minimum ramp lane and shoulder widths, see Exhibit 1360-6.

[3] For gore details, see Exhibit 1360-11b.

General:

For gore details, see Exhibit 1360-11b.

Exhibit 1360-17 Temporary Ramps





Exhibit 1360-18 Interchange Plan



Chapter 1370 Median Crossovers

1370.01 General
1370.02 Analysis
1370.03 Design
1370.04 Plan Updates and Approvals
1370.05 Documentation

1370.01 General

This chapter provides guidance for locating and designing median crossovers.

Median crossovers are provided at locations on divided highways for crossing by maintenance, traffic service, emergency, and law enforcement vehicles. The use of all median crossovers is restricted to these users.

Crossovers may be provided:

- Where main line safety will not be compromised by providing a crossover.
- Where access through interchanges or intersections is not practical.
- As part of region maintenance operations.
- As necessary for law enforcement and emergency services functions.

For information about median openings to provide turning movements for public access to both sides of the roadway, see Chapter 1310, Intersections at Grade.

1370.02 Analysis

A list of existing median crossovers is available from the Headquarters (HQ) Access and Hearings Section. The Statewide Master Plan for Median Crossovers website is:
www.wsdot.wa.gov/design/accessandhearings/tracking.htm

The general categories of vehicles recognized as legitimate users of median crossovers are law enforcement, emergency services, traffic incident response, and maintenance vehicles.

In urban areas with a high-occupancy vehicle (HOV) lane adjacent to the median, crossovers may be considered for law enforcement (see Chapter 1410).

In areas where there are 3 or more miles between access points, providing an unobtrusive crossover can improve emergency services or improve efficiency for traffic services and maintenance forces.

Maintenance crossovers may be needed at one or both ends of an interchange for the purpose of winter maintenance operations and at other locations to facilitate maintenance operations. In general:

- Existing crossovers may remain at their current locations.

- New crossovers should not be located closer than 1,500 feet to the end of a ramp taper or to any structure. This distance may be decreased to improve winter maintenance efficiency based on an operational analysis. Include an operational analysis in the Design Documentation Package (DDP).
- Crossovers should be located only where stopping sight distance is provided and preferably should not be located on superelevated curves.

1370.03 Design

Use the following design criteria for all median crossovers, taking into consideration the intended vehicle usage. Some of these criteria may not apply to crossovers intended primarily for law enforcement.

- Adequate median width at the crossover location is required to allow the design vehicle to complete a U-turn maneuver without backing. Use of the shoulder area is allowed for the execution of the U-turn maneuver. Typical design vehicles for this determination are a passenger car and a single-unit truck.
- When median barrier is placed in the vicinity of a median crossover, position the barrier to minimize the potential for errant vehicles to cross through the median. (See the *Standard Plans* for typical barrier layout.)
- Consider the types of vehicles using the median crossover.
- The minimum recommended throat width is 30 feet.
- Use grades and radii that are suitable for all authorized user vehicles (see Chapter 1340).
- In most cases, 10-foot inside paved shoulders are adequate for deceleration and acceleration lanes. Consider full 10-foot shoulders for a distance of 450 feet upstream of the crossover area to accommodate deceleration, and extend downstream of the crossover area for a distance of 600 feet to allow acceleration prior to entering the travel lane. In cases where the median width is narrower than the design vehicle turning path, widening shoulders may not provide a benefit. Document decisions to provide inside shoulders of less than 10 feet.
- Provide adequate stopping sight distance for vehicles approaching the crossover area. This is due to the unexpected maneuvers associated with these inside access points and the higher operating speeds commonly experienced in the inside travel lanes (see Chapter 1260).
- Provide adequate intersection sight distance at crossover locations where authorized user vehicles must encroach on the travel lanes (see Chapter 1310).
- For the crossing, use sideslopes no steeper than 10H:1V. Grade for a relatively flat and gently contoured appearance that is inconspicuous to the public.
- Consider impacts to existing drainage.
- Do not use curbs or pavement markings.
- Flexible guideposts may be provided for night reference, as shown in the *Standard Plans*.

- Consider the terrain and locate the crossover to minimize visibility to the public.
- Use vegetation to minimize the visibility of the crossover. Low vegetation with a 3-foot year-round maximum height is recommended for this purpose (see Chapter 900).
- In locations where vegetation cannot be used to minimize visibility by the traveling public, and there is a high incidence of unauthorized use, use appropriate signing such as "No U-Turns" to discourage unauthorized use.
- A stabilized all-weather surface is required. Paving of crossings is determined on a case-by-case basis.

1370.04 Plan Updates and Approvals

All approved crossover locations will be designated on the Statewide Master Plan for Median Crossovers. Contact the HQ Access and Hearings Section for the following:

- Proposed new crossings
- Relocation of previously approved crossings
- Removal of crossings that are no longer required

Plan updates and approvals involve coordination between the Assistant Regional Administrator for Operations or Project Development, the Washington State Patrol (WSP), the HQ Access and Hearings Section, the appropriate Assistant State Design Engineer (ASDE), and the Federal Highway Administration (FHA) Area Engineer (or their designees).

Once locations are identified, the region will send a package to the HQ Access and Hearings Section, which should include: a strip map showing MP locations of, and spacing between, existing and/or planned crossovers and interchanges; a justification for the crossover(s); a copy of any requests for crossovers from the WSP, emergency services, or maintenance; and a red and green marked-up plan sheet showing locations. Approval will be given by the ASDE. Construction may not proceed prior to approval.

After notification of approval, the HQ Right of Way Plans Section sends the region a reproducible revised right of way or limited access plan that includes the approved crossover location.

1370.05 Documentation

For the list of documents required to be preserved in the Design Documentation Package and the Project File, see the Design Documentation Checklist:
www.wsdot.wa.gov/design/projectdev/

Chapter 1410 High-Occupancy Vehicle Facilities

1410.01 General
1410.02 References
1410.03 Definitions
1410.04 Preliminary Design and Planning
1410.05 Operations
1410.06 Design Criteria
1410.07 Documentation

1410.01 General

High-occupancy vehicle (HOV) facilities include separate HOV roadways, HOV lanes, transit lanes, HOV direct access ramps, and flyer stops. The objectives for the HOV facilities are:

- Improve the capability of corridors to move more people by increasing the number of people per vehicle.
- Provide travel time savings and a more reliable trip time to HOV lane users.
- Provide travel options for HOVs without adversely affecting the general-purpose lanes.

Plan, design, and construct HOV facilities that provide intermodal linkages. Give consideration to future highway system capacity needs. Whenever possible, design HOV lanes so that the level of service for the general-purpose lanes is not degraded.

In urban corridors that do not currently have planned or existing HOV lanes, complete an analysis of the need for HOV lanes before proceeding with any projects for additional general-purpose lanes. In corridors where both HOV and general-purpose facilities are planned, construct the HOV lane before or simultaneously with the construction of new general-purpose lanes.

For additional information, see the following chapters:

Chapter	Subject
1230	Geometric cross section
1240	General-purpose turning roadway widths
1420	HOV direct access

1410.02 References

(1) Federal/State Laws and Codes

Revised Code of Washington (RCW) 46.61.165, High-occupancy vehicle lanes

RCW 47.52.025, Additional powers – Controlling use of limited access facilities –High occupancy vehicle lanes

Washington Administrative Code (WAC) 468-510-010, High occupancy vehicles (HOVs)

(2) Design Guidance

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT

Traffic Manual, M 51-02, WSDOT

(3) Supporting Information

Design Features of High-Occupancy Vehicle Lanes, Institute of Traffic Engineers (ITE)

Guide for the Design of High-Occupancy Vehicle Facilities, American Association of State Highway and Transportation Officials (AASHTO)

High-Occupancy Vehicle Facilities, Parsons Brinkerhoff, Inc., 1990

HOV Systems Manual, NCHRP Report 414, 1998

1410.03 Definitions

buffer-separated HOV lane An HOV lane that is separated from the adjacent same direction general-purpose freeway lanes by a designated buffer.

bus rapid transit (BRT) An express rubber tired transit system operating predominantly in roadway managed lanes. It is generally characterized by separate roadway or buffer-separated HOV lanes, HOV direct access ramps, and a high-occupancy designation (3+ or higher).

business access transit (BAT) lanes A transit lane that allows use by other vehicles to access abutting businesses.

enforcement area A place where vehicles may be stopped for ticketing by law enforcement. It also may be used as an observation point and for emergency refuge.

enforcement observation point A place where a law enforcement officer may park and observe traffic.

flyer stop A transit stop inside the limited access boundaries.

high-occupancy toll (HOT) lane A managed lane that combines a high-occupancy vehicle lane and a toll lane.

high-occupancy vehicle (HOV) A vehicle that meets the occupancy requirements of the facility as authorized by WAC 468-510-010.

HOV direct access ramp An on- or off-ramp exclusively for the use of HOVs that provides access between a freeway HOV lane and a street, transit support facility, or another freeway HOV lane without weaving across general-purpose lanes.

HOV facility A priority treatment for HOVs.

level of service A qualitative measure describing operational conditions within a traffic stream, incorporating factors of speed and travel time, freedom to maneuver, traffic interruptions, comfort and convenience, and safety.

managed lane A lane that increases efficiency by packaging various operational and design actions. Lane management operations may be adjusted at any time to better match regional goals.

nonseparated HOV lane An HOV lane that is adjacent to and operates in the same direction as the general-purpose lanes with unrestricted access between the HOV lane and the general-purpose lanes.

occupancy designation The minimum number of occupants required for a vehicle to use the HOV facility.

separated HOV facility An HOV roadway that is physically separated from adjacent general-purpose lanes by a barrier or median, or is on a separate right of way.

single-occupant vehicle (SOV) Any motor vehicle other than a motorcycle carrying one occupant.

transit lane A lane for the exclusive use of transit vehicles.

violation rate The total number of violators divided by the total number of vehicles on an HOV facility.

1410.04 Preliminary Design and Planning

(1) Planning Elements for Design

In order to determine the appropriate design options for an HOV facility, establish the travel demand and capacity, identify suitable corridors, evaluate the HOV facility location and length, and estimate the HOV demand. A viable HOV facility satisfies the following criteria:

- It is part of an overall transportation plan.
- It has the support of the community and public.
- It responds to demonstrated congestion or near-term anticipated congestion: Level of Service E or F for at least one hour of peak period (traffic approaching a capacity of 1700 to 2000 vehicles per hour per lane) or average speeds less than 30 mph during peak periods over an extended distance.
- Except for a bypass of a local bottleneck, it is of sufficient length to provide a travel time saving of at least five minutes during the peak periods.
- It has sufficient numbers of HOV users for a cost-effective facility and avoids the perception of under-utilization (HOV volumes of 400 to 500 vehicles per hour on nonseparated lanes and 600 to 800 on separated facilities).
- It provides a safe, efficient, and enforceable operation.

A queue or bottleneck bypass can be effective without satisfying all of the above. An isolated bypass can be viable when there is localized, recurring traffic congestion, and such treatment can provide a travel time saving to a sufficient number of HOV users.

The efficiency of the HOV facility can be affected by the access provisions. Direct access between park & ride/transit facilities and an HOV lane is the most desirable, but it is also an expensive alternative. Direct access options are discussed in Chapter 1420.

Document the need for the HOV lane and how the proposed lane will meet those needs.

(2) HOV Facility Type

Make a determination as to the type of HOV lane. The three major choices are: separated roadway, buffer-separated lane, and nonseparated HOV lane.

(a) **Separated Roadway**

The separated roadway can be either a one-way reversible or a two-way operation. The directional split in the peak periods, available space, and operating logistics are factors to be considered. A separated HOV roadway may be located in the median of the freeway, next to the freeway, or on an independent alignment. Separated HOV facilities are more effective for:

- Large HOV volumes.
- Large merging and weaving volumes.
- Long-distance HOV travel.

Reversible separated roadways operate effectively where there are major directional splits during peak periods. Consider potential changes in this traffic pattern and design the facility to accommodate possible conversion to a two-way operation. The separated roadway is normally more efficient, provides for the higher level of safety, and is more easily enforced. However, it is generally the most expensive type of HOV facility.

(b) **Buffer-Separated Lane**

A buffer-separated HOV lane is similar to a freeway nonseparated HOV lane on the left, but with a buffer between the HOV lane and the general-purpose lanes. The addition of a buffer provides better delineation between the lanes and controls access between the HOV lane and general-purpose lanes to improve operations.

(c) **Nonseparated Lane**

Nonseparated HOV lanes operate in the same direction and immediately adjacent to the general-purpose lanes. They are located either to the left (desirable) or to the right of the general-purpose lanes. Nonseparated HOV lanes are normally less expensive and easier to implement, and they provide more opportunity for frequent access. However, the ease of access can create more problems for enforcement and a greater potential for conflicts.

(3) Freeway Operational Alternatives

For an HOV lane on a limited access facility, consider the following operational alternatives:

- Inside (desirable) or outside HOV lane
- Lane conversion
- Use of existing shoulder—not recommended for permanent operations
- HOV direct access ramps
- Queue bypasses
- Flyer stops
- Hours of operation

When evaluating alternatives, consider a combination of alternatives to provide the optimum solution for the corridor. Also, incorporate flexibility into the design in order not to preclude potential changes in operation, such as changing an outside lane to an inside lane or a reversible facility to two-way operations. Access, freeway-to-freeway connections, and enforcement will have to be accommodated for such changes. Document the operational alternatives.

(a) **Inside vs. Outside HOV Lane**

System continuity and consistency of HOV lane placement along a corridor are important, and they influence facility development decisions. Other issues include land use, trip patterns, transit vehicle service, HOV volume, ramp volume, congestion levels, enforcement, and direct access to facilities.

The inside (left) HOV lane is most appropriate for a corridor with long-distance trip patterns, such as a freeway providing mobility to and from a large activity center. These trips are characterized by long-distance commuters and express transit service. Maximum capacity for an effective inside HOV lane is approximately 1,500 vehicles per hour. When HOVs weaving across the general-purpose lanes cause severe congestion, consider providing HOV direct access ramps, separated HOV roadways, or a higher-occupancy designation. Inside lanes are preferred for HOV lanes on freeways.

The outside (right) HOV lane is most appropriate for a corridor with shorter, more widely dispersed trip patterns. These trip patterns are characterized by transit vehicle routes that exit and enter at nearly every interchange. The maximum capacity for an effective outside HOV lane is reduced and potential conflicts are increased by heavy main line congestion and large entering and exiting general-purpose volumes.

(b) **Conversion of a General-Purpose Lane**

The use of an existing general-purpose lane for an HOV lane is an undesirable option; however, conversion of a lane to an HOV lane might be justified when the conversion provides greater people-moving capability on the roadway. Use of an existing freeway lane as an HOV lane will be considered only with a Design Analysis.

Given sufficient existing capacity, converting a general-purpose lane to an HOV lane can provide for greater people moving capability in the future without significantly affecting the existing roadway operations. The fastest and least expensive method for providing an HOV lane is through conversion of a general-purpose lane. Restriping and signing are sometimes all that is needed. Converting a general-purpose lane to HOV use will likely have environmental benefits. This method, however, is controversial from a public acceptance standpoint. Public support might be gained through an effective public involvement program (see Chapter 210).

Do not convert a general-purpose lane to an HOV lane unless it enhances the corridor's people-moving capacity. Conduct an analysis that includes:

- Public acceptance of the lane conversion.
- Current and long-term traffic impacts on the adjacent general-purpose lanes and the HOV lane.
- Impacts to the neighboring streets and arterials.
- Legal, environmental, and safety impacts.

(c) **Use of Existing Shoulder**

When considering the alternatives in order to provide additional width for an HOV lane, the use of the existing shoulder is an undesirable option. Use of the shoulder on a freeway or freeway ramp as an HOV lane will be considered only with a Design Analysis.

Consider shoulder conversion to an HOV lane when traffic volumes are heavy and the conversion is a temporary measure. Another alternative is to use the shoulder as a permanent measure to serve as a transit-only or queue bypass lane during peak hours and then revert to a shoulder in off-peak hours.

The use of the shoulder creates special signing, operational, and enforcement issues. An agreement is required with the transit agency to limit transit vehicle use of the shoulder to peak hours. Provide signing that clearly defines the use of the shoulder. Institute special operations to clear the shoulder for the designated hours.

The existing shoulder pavement is often not designed to carry heavy volumes of vehicles, especially transit vehicles. As a result, repaving and reconstruction of the shoulder might be required.

(d) **HOV Direct Access Ramps**

To improve the efficiency of an HOV system, exclusive HOV access connections for an inside HOV lane may be considered. (See Chapter 1420 for information on HOV direct access connections.) Direct access reduces the need for HOVs to cross the general-purpose lanes from right-side ramps. Transit vehicles will be able to use the HOV lane and provide service to park & ride lots, flyer stops, or other transit stops by the HOV direct access ramps.

(e) **Queue Bypass Lanes**

A queue bypass lane allows HOVs to save time by avoiding congestion at an isolated bottleneck. An acceptable time saving for a queue bypass is one minute or more. Typical locations for queue bypasses are at ramp meters, signalized intersections, toll plaza or ferry approaches, and locations with isolated main line congestion. By far the most common use is with ramp metering. Queue bypass lanes can be built along with a corridor HOV facility or independently. In most cases, they are relatively low cost and easily implemented. Where feasible, include HOV bypasses on ramp metering sites, or make provisions for their future accommodation unless specific location conditions dictate otherwise.

(f) **Flyer Stops**

Flyer stops reduce the time required for express transit vehicles to serve intermediate destinations. However, passengers must travel greater distances to reach the loading platform. (See Chapter 1420 for information on flyer stops.)

(g) **Hours of Operation**

An HOV designation on freeway HOV lanes 24 hours a day provides benefits to users during off-peak periods, minimizes potential confusion, makes enforcement easier, and simplifies signing and striping. However, 24-hour operation also might result in a lane not used during off-peak periods, negative public opinion, and the need for full-time enforcement.

(4) Arterial Street Operational Alternatives

Arterial street HOV lanes also have a variety of HOV alternatives to be considered. Some of these alternatives are site-specific or have limited applications. Arterial HOV lanes differ from freeway HOV lanes in slower speeds, little access control (turning traffic can result in right-angle conflicts), and traffic signals. Arterial HOV lanes are occasionally designated for transit vehicles only, especially in cities with a large concentration of transit vehicles. When evaluating alternatives, consider traffic signal queues and managed access highway class. The alternatives include the following:

- Type of lane
- Left-side or right-side HOV lane
- Hours of operation
- Spot treatments
- Bus stops

When evaluating alternatives, consider a combination of alternatives to provide the optimum solution for the corridor. Also, incorporate flexibility into the design in order not to preclude potential changes in operation. Document the operational alternatives.

(a) **Type of Lane**

Lanes can be transit-only or include all HOVs. Transit-only lanes are desirable where bus volumes are high with a high level of congestion. They increase the speed of transit vehicles through congested areas and improve the reliability of the transit service. Lanes that allow use by all HOVs are appropriate on corridors with high volumes of carpools and vanpools. They can collect carpools and vanpools in business and industrial areas and connect them to the freeway system.

(b) **Left-Side or Right-Side HOV Lane**

Continuity of HOV lane location along a corridor is an important consideration when making the decision whether to locate an arterial street HOV lane on the left or right side of the street. Other issues include land use, trip patterns, transit vehicle service, safety, enforcement, and presence of parking.

The right side is desirable for arterial street HOV lanes on transit routes with frequent stops. It is the most convenient for passenger boarding at transit stops. It is also the most common location for HOV lanes on arterial streets. General-purpose traffic must cross the HOV lane to make a right turn at intersections and to access driveways. These turns across the HOV lane can create conflicts. Minimizing access points that create these conflict locations is recommended. Other issues to consider are on-street parking, stopping areas for delivery vehicles, and enforcement areas.

Left-side arterial street HOV lanes are less common than right-side lanes. HOV lanes on the left eliminate the potential conflicts with driveway access, on-street parking, and stopping areas for delivery vehicles. The result is fewer delays and higher speeds, making left-side arterial street HOV lanes appropriate for longer-distance trips. The disadvantages include the difficulty providing transit stops and the need to provide for left-turning general-purpose traffic.

(c) Hours of Operation

An arterial street HOV lane can either operate as an HOV lane 24 hours a day or during peak hours only. Factors to consider in determining which to use include type of HOV lane, level of congestion, continuity, and enforcement.

HOV lanes operating 24 hours a day are desirable when congestion and HOV demand exists for extended periods throughout the day. The 24-hour operation provides benefits to users during off-peak periods, minimizes potential confusion, makes enforcement easier, and simplifies signing and striping. The disadvantages include negative public opinion if the lane is not used during off-peak periods, the need for full-time enforcement, and the loss of on-street parking.

Peak period HOV lanes are appropriate for arterial streets with HOV demand or congestion existing mainly during the peak period. Peak period HOV lanes provide HOV priority at the critical times of the day, lessen negative public perception of the HOV lane, and allow on-street parking or other shoulder uses at other times. The disadvantages include possible confusion to drivers, more difficult enforcement, increased signing, and the need to institute special operations to clear the shoulder or lane for the designated period.

(d) Spot Treatments

An HOV spot treatment is used to give HOVs priority around a bottleneck. It can provide time savings, travel time reliability, and improved access to other facilities. Examples include a short HOV lane to provide access to a freeway on-ramp, one lane of a dual turn lane, a priority lane at ferry terminals, and priority at traffic signals.

Signal priority treatments that alter the sequence or duration of a traffic signal are techniques for providing preferential treatment for transit vehicles. The priority treatments can range from timing and phasing adjustments to signal preemption. Consider the overall impact on traffic. Preemption would normally not be an appropriate treatment where traffic signal timing and coordination are being utilized or where there are high traffic volumes on the cross streets.

(e) Bus Stops

Normally, with arterial HOV lanes, there is not a shoulder suitable for a bus to use while stopped to load and unload passengers without blocking the lane. Therefore, bus stops are either in-lane or in a pullout. In-lane bus stops are the simplest type of bus stop. However, stopped buses will block the HOV lane; therefore, in-lane bus stops are only allowed in transit lanes. Bus pullouts provide an area for buses to stop without blocking the HOV lane. Disadvantages include higher cost, reduced width for the sidewalk or other roadside area, and possible difficulty reentering the HOV lane. (See Chapter 1430 for additional information on bus stop location and design.)

1410.05 Operations

(1) Vehicle Occupancy Designation

Select the vehicle occupancy designation to provide the maximum movement of people in a corridor, provide free-flow HOV operations, reduce the empty lane perception, provide for the ability to accommodate future HOV growth within a corridor, and be consistent with the regional transportation plan and the policies adopted by the Metropolitan Planning Organization (MPO).

Establish an initial occupancy designation. It is Washington State Department of Transportation (WSDOT) policy to use the 2+ designation as the initial occupancy designation. Consider a 3+ occupancy designation if it is anticipated during initial operation that the volumes will be 1,500 vehicles per hour for a left-side HOV lane, or 1,200 vehicles per hour for a right-side HOV lane, or that a 45 mph operating speed cannot be maintained for more than 90% of the peak hour.

(2) Enforcement

Enforcement is necessary for the success of an HOV facility. Coordination with the Washington State Patrol (WSP) is critical when the operational characteristics and design alternatives are being established. This involvement ensures the project is enforceable and will receive their support.

Provide both enforcement areas and observation points for high-speed HOV lanes and ramp facilities.

Barrier-separated facilities, because of the limited access, are the easiest facilities to enforce. Shoulders provided to accommodate breakdowns may also be used for enforcement. Reversible facilities have ramps for the reverse direction that may be used for enforcement. Gaps in the barrier may be needed so emergency vehicles can access barrier-separated HOV lanes.

Buffer-separated and nonseparated HOV lanes allow violators to easily enter and exit the HOV lane. Provide strategically located enforcement areas and observation points.

Consider the impact on safety and visibility for the overall facility during the planning and design of enforcement areas and observation points. Where HOV facilities do not have enforcement areas, or where officers perceive that the enforcement areas are inadequate, enforcement on the facility will be difficult and less effective.

(3) Intelligent Transportation Systems

The objective of Intelligent Transportation Systems (ITS) is to make more efficient use of our transportation network. This is done by collecting data, managing traffic, and relaying information to the motoring public.

It is important that an ITS system be incorporated into the HOV project and that the HOV facility fully utilize the ITS features available. This includes providing a strategy of incident management since vehicle breakdowns and crashes have a significant impact on the efficient operation of the HOV facilities. (For more information on ITS, see Chapter 1050.)

1410.06 Design Criteria

(1) Design Procedures

Refer to chapters in the 1100 series for practical design guidance and procedures.

(2) Design Considerations

HOV lanes are designed to the same criteria as the facilities to which they are attached. Design nonseparated and buffer-separated HOV lanes to match the vertical alignment, horizontal alignment, and cross slope of the adjacent lane.

(3) Adding an HOV Lane

The options for adding an HOV lane are: reconstruction, restriping, combined reconstruction and restriping, and possibly lane conversion.

(a) **Reconstruction**

Reconstruction involves creating roadway width. Additional right of way may be required.

(b) **Restriping**

Restriping involves reallocating the existing paved roadway to create enough space to provide an additional HOV lane.

(c) **Combined Reconstruction and Restriping**

Reconstruction and restriping can be combined to maximize use of the available right of way. For example, a new lane can be created through a combination of median reconstruction, shoulder reconstruction, and lane restriping. Handle each project on a case-by-case basis. Generally, consider the following reductions in order of preference:

- Reduction of the inside shoulder width, provided the enforcement and safety mitigation issues are addressed. (Give consideration to not precluding future HOV direct access ramps by over-reduction of the available median width.)
- Reduction of the interior general-purpose lane width to 11 feet.
- Reduction of the outside general-purpose lane width to 11 feet.
- Reduction of the HOV lane to 11 feet.
- Reduction of the outside shoulder width to 8 feet.

(d) Lane Conversion

If lane width adjustments are made, thoroughly eradicate the old lane markings. It is desirable that longitudinal joints (new or existing) not conflict with tire track lines. If they do, consider overlaying the roadway before restriping.

(4) Design Criteria for Types of HOV Facilities

(a) Separated Roadway HOV Facilities

The separated HOV facility can be single-lane or multilane and directional or reversible (see Exhibit 1410-2).

1. **Lane Widths**

   For traveled way width (WR) on turning roadways, see Exhibit 1410-1.

2. **Shoulder Widths**

   The shoulder width requirements are as follows:

   - The minimum width for the sum of the two shoulders is 12 feet for one-lane facilities and 14 feet for two-lane facilities.
   - Provide a width of at least 10 feet for one of the shoulders for disabled vehicles. The minimum for the other shoulder is 2 feet for one-lane facilities and 4 feet for two-lane facilities.
   - The wider shoulder may be on the left or the right. Maintain the wide shoulder on the same side throughout the facility.

3. **Total Widths**

   To reduce the probability of blocking the HOV facility, make the total width (lane width plus paved shoulders) wide enough to allow an A-BUS to pass a stalled A-BUS. For single-lane facilities, the traveled way widths (WR), given in Exhibit 1410-1, plus the 12-foot total shoulder width will provide for this passing for radii (R) 100 feet or greater. For R of 75 feet, a total roadway width of 33 feet is needed, and for R of 50 feet, a total roadway width of 41 feet is needed to provide for the passing.

R (ft)[1]	W_R (ft)	
	1-Lane	2-Lane
3,001 to Tangent	13[2]	24
3,000	14	24
2,000	14	25
1,000	15	26
500	15	27
300	15	28
200	16	29
150	17	31
100	18	34
75	19	37
50	22	45

Notes:

[1] Radius (R) is on the outside edge of traveled way on 1-lane and centerline on 2-lane roadways.

[2] May be reduced to 12 ft on tangent.

Minimum Traveled Way Widths for Articulated Buses
Exhibit 1410-1

(b) **Nonseparated Freeway HOV Lanes**

For both inside and outside HOV lanes, the minimum lane width is 12 feet and the minimum shoulder width is 10 feet (see Exhibit 1410-2).

When a left shoulder less than 10 feet wide is proposed for distances exceeding 1.5 miles, provide enforcement and observation areas at 1- to 2-mile intervals (see 1410.06(7)).

Where left shoulders less than 8 feet wide are proposed for lengths of roadway exceeding 0.5 mile, provide safety refuge areas at 0.5- to 1-mile intervals. These can be in addition to or in conjunction with the enforcement areas.

Allow general-purpose traffic to cross HOV lanes at on- and off-ramps.

(c) **Buffer-Separated HOV Lanes**

Design buffer-separated HOV lanes the same as for inside nonseparated HOV lanes, except for a buffer 2 to 4 feet in width or 10 feet or greater in width with pavement marking, with supplemental signing, to restrict crossing. For buffer-separated HOV lanes with a buffer at least 4 feet wide, the left shoulder may be reduced to 8 feet. Buffer widths between 4 and 10 feet are undesirable because they may appear to be wide enough for a refuge area, but they are too narrow. Provide gaps in the buffer to allow access to the HOV lane.

(d) **Arterial Street HOV Lanes**

The minimum width for an arterial street HOV lane is 12 feet. Allow general-purpose traffic to cross the HOV lanes to turn at intersections and to access driveways (see Exhibit 1410-2).

For right-side HOV lanes adjacent to curbs, provide a 4-foot shoulder between the HOV lane and the face of curb. The shoulder may be reduced to 2 feet with justification.

For HOV lanes on the left, a 1-foot left shoulder between the HOV lane and the face of curb is required. When concrete barrier is adjacent to the HOV lane, the minimum shoulder is 2 feet.

(e) **HOV Ramp Meter Bypass**

An HOV bypass may be created by widening an existing ramp, constructing a new ramp where right of way is available, or reallocating the existing pavement width (provided the shoulders are full depth).

Ramp meter bypass lanes may be located on the left or right of metered lanes. Typically, bypass lanes are located on the left side of the ramp. Consult with local transit agencies and the region Traffic Office for guidance on which side to place the HOV bypass.

Consider the existing conditions at each location when designing a ramp meter bypass. Design a single-lane ramp with a single metered lane and an HOV bypass as shown in Exhibit 1410-4a. Make the total width of the metered and bypass lanes equal to a 2-lane ramp (see Chapters 1240 and 1360). Design a ramp with two metered lanes and an HOV bypass as shown in Exhibit 1410-4b. Make the width of the two metered lanes equal to a 2-lane ramp (see Chapters 1240 and 1360) and the width of the bypass lane as shown in Exhibit 1410-3. The design shown in Exhibit 1410-4b requires that the ramp operate as a single-lane ramp when the meter is not in operation.

Both Exhibits 1410-4a and 4b show an observation point/enforcement area. Document any other enforcement area designs in the design documentation package. An alternative is to provide a 10 foot outside shoulder from the stop bar to the main line.

(5) HOV Direct Access Ramps

HOV direct access ramps provide access between an HOV lane and another freeway, a local arterial street, a flyer stop, or a park & ride facility. Design HOV direct access ramps in accordance with Chapter 1420.

(6) HOV Lane Termination

Locate the beginning and end of an HOV lane at logical points. Provide decision sight distance, signing, and pavement markings at the termination points.

The desirable method of terminating an inside HOV lane is to provide a straight through move for the HOV traffic, ending the HOV restriction and dropping a general-purpose lane on the right. However, analyze volumes for both the HOV lanes and general-purpose lanes, as well as the geometric conditions, to optimize the overall operational performance of the facility.

(7) Enforcement Areas

Enforcement of the inside HOV lane can be done with a minimum 10-foot inside shoulder. For continuous lengths of barrier exceeding 2 miles, a 12-foot shoulder is recommended for the whole length of the barrier.

For inside shoulders less than 10 feet, locate enforcement and observation areas at 1 to 2-mile intervals or based on the recommendations of the WSP. These areas can also serve as refuge areas for disabled vehicles (see Exhibits 1410-5a and 5b).

Provide observation points approximately 1,300 feet before enforcement areas. They can be designed to serve both patrol cars and motorcycles or motorcycles only. Coordinate with the WSP during the design stage to provide effective placement and utilization of the observation points. Median openings give motorcycle officers the added advantage of being able to quickly respond to emergencies in the opposing lanes (see Exhibit 1410-5b). The ideal observation point places the motorcycle officer 3 feet above the HOV lane and outside the shoulder so the officer can look down into a vehicle.

Locate the enforcement area on the right side for queue bypasses and downstream from the stop bar so the officer can be an effective deterrent (see Exhibits 1410-4a and 4b).

An optional signal status indicator for enforcement may be placed at HOV lane installations that are metered. The indicator faces the enforcement area so that a WSP officer can determine whether vehicles are violating the ramp meter. The indicator allows the WSP officer to simultaneously enforce two areas: the ramp meter and the HOV lane. Consult with the WSP regarding use at all locations.

For additional information on enforcement signal heads, see the *Traffic Manual* regarding HOV metered bypasses.

(8) Signs and Pavement Markings

(a) **Signs**

Provide post-mounted HOV preferential lane signs next to the HOV lane or overhead-mounted signs over the HOV lane. Make the sign wording clear and precise, stating which lane is restricted, the type of HOVs allowed, and the HOV vehicle occupancy designation for that section of road. The sign size, location, and spacing are dependent upon the conditions under which the sign is used. Roadside signs can also be used to convey other HOV information such as the HERO program, carpool information, telephone numbers, and violation fines. Some situations may call for the use of variable message signs.

Place overhead signs directly over the HOV lane to provide maximum visibility. Use a sequence of overhead signs at the beginning and end of freeway HOV facilities. Overhead signs can also be used in conjunction with roadside signs along the roadway.

(b) **Pavement Markings**


Provide pavement markings that conform to the *Traffic Manual* and the *Standard Plans*.

(c) **Interchanges**

In the vicinity of interchange on- and off-connections where merging or exiting traffic crosses an HOV lane, make provisions for general-purpose traffic using the HOV lane. These provisions include signing and striping that clearly show the changes in HOV versus general traffic restrictions. (See the *Standard Plans* for pavement markings and signing.)

1410.07 Documentation

Refer to Chapter 300 for design documentation requirements.



Notes:

[1] The sum of the two shoulders is 12 ft for one-lane and 14 ft for two-lane facilities. Provide one shoulder with a width of at least 10 ft for disabled vehicles. The wider shoulder may be on the left or the right. Maintain the wide shoulder on the same side throughout the facility (see 1410.06(4)(a)2).

[2] 12-ft minimum for single lane, 24-ft minimum for two lanes. Wider width is required on curves (see 1410.06(4)(a)1 and Exhibit 1410-1).

[3] For total width requirements, see 1410.06(4)(a)3.

[4] Width as required, and the number of lanes.

[5] Buffer 2 to 4 ft or 10 ft or more.

[6] When buffer width is 4 ft or more, may be reduced to 8 ft.

[7] 2 ft when adjacent to concrete barrier.

[8] Arterial HOV lanes on the left operate in the same direction as the adjacent general-purpose lane.

[9] May be reduced to 2 ft with justification.


Typical HOV Lane Sections
Exhibit 1410-2

Radius of Two-Lane Ramp R (ft)	Design Width of Third Lane[1] W (ft)
1,000 to Tangent	12
999 to 500	13
499 to 250	14
249 to 200	15
199 to 150	16
149 to 100	17


Notes:

[1] Apply additional width to two-lane ramp widths.

[2] For turning roadway widths, see traveled way width for two-lane one-way turning roadways in Chapter 1240.



Roadway Widths for Two-Lane Ramps With an HOV Lane
Exhibit 1410-3



Notes:

[1] For on-connection details and for acceleration lane length, see Chapter 1360.


[2] For ramp lane and shoulder widths for a 2-lane ramp, see Chapters 1240 and 1360.

[3] A transition curve with a minimum radius of 3,000 ft is desirable. The minimum length is 300 ft. When the main line is on a curve to the left, the transition may vary from a 3,000 ft radius to tangent to the main line.

General:

For striping details, see the *Standard Plans*.

Single-Lane Ramp Meter With HOV Bypass
Exhibit 1410-4a



Notes:

[1] For acceleration lane length, see Chapter 1360.

[2] For 2-lane ramp lane and shoulder widths, see Chapters 1240 and 1360. For 3rd lane width, see Exhibit 1410-3.


[3] A transition curve with a minimum radius of 3000 ft is desirable. The minimum length is 300 ft. When the main line is on a curve to the left, the transition may vary from a 3000 ft radius to tangent to the main line.

General:


For striping details, see the *Standard Plans*.

Two-Lane Ramp Meter With HOV Bypass

Exhibit 1410-4b



Enforcement Area: One Direction Only
Exhibit 1410-5a



Note:

[1] For median width transition, see Chapter 1210.

Enforcement Area: Median

Exhibit 1410-5b

Chapter 1420 HOV Direct Access

1420.01 General
1420.02 HOV Access Types and Locations
1420.03 Direct Access Geometrics
1420.04 Passenger Access
1420.05 Traffic Design Elements
1420.06 Documentation
1420.07 References

1420.01 General

This chapter provides Washington State Department of Transportation (WSDOT) design guidance for left-side direct access facilities for high-occupancy vehicles (HOVs) between freeway HOV lanes and flyer stops within the freeway right of way or facilities outside of the right of way. Design right-side HOV-only access facilities in accordance with Chapter 1360.

Direct access eliminates the need for left-side HOV lane users to cross the general-purpose lanes to right-side general-purpose ramps. Also, transit vehicles can use the HOV lane and provide service to the HOV direct access facility.

Providing the HOV user access to the inside HOV lane without mixing with the general-purpose traffic saves the user additional travel time and aids in safety, enforcement, incident handling, and overall operation of the HOV facility.

Locations for direct access ramps include HOV facilities on intersecting routes, park & ride lots, flyer stops, and locations with a demonstrated demand. Coordinate with the local transit agencies to identify these key locations. Give priority to locations that serve the greatest number of transit vehicles and other HOVs.

1420.01(1) Practical Design

Under WSDOT practical design (see Chapter 1100 and Division 11) an important function of alternative solution formulation is to identify alternatives that address the baseline need while balancing the performance trade-offs identified in the process. Since HOV direct access connections are often added to existing corridors, performance tradeoffs to mainline GP lanes or other elements may be needed and acceptable to provide the new HOV connections. Document performance tradeoffs according to Chapter 1100 and Division 11.

1420.01(2) Reviews, Studies, and Reports

The practical design project development process is to be followed when developing an HOV direct access project (see Chapter 1100). Despite the nature of the projects that are the focus of this chapter, most facets of the project development process remain unchanged. For example, early coordination with others is a vital part of developing a project. There are also environmental considerations, public involvement, and value engineering studies (see Chapter 310). There may also be reviews, studies, and reports required by agreements with regional transit authorities or other agencies.

Provide an interchange justification report (see Chapter 550) when there is a proposal to add, delete, or change an access point. Provide the operational analysis from the report for all flyer stops. For left-side connections, include the commitment that the connection will be used solely by HOVs or will be closed.

Throughout the project development phase, make sure the project:

- Need Statement (see Chapter 1101) and cost estimate are correct.
- Development process is on schedule.
- Documents are biddable.
- Will be constructible.
- Will be maintainable.

Constructability of HOV direct access facilities is an important consideration during the design phase. These facilities will typically be constructed on existing highways with traffic maintained on-site. Key goals are to:

- Provide a project that can be built.
- Plan a construction strategy.
- Provide a safe work zone.
- Minimize construction delays.

Consider access to these facilities by maintenance crews. Avoid items that require a significant maintenance effort and might result in lane closure for routine maintenance or repair.

1420.01(3) Left-Side Connections

Left-side connections are allowed only when they serve HOVs exclusively and connect to an HOV lane. The higher traffic volume associated with general-purpose traffic is not acceptable for left-side connections. If the demand for an HOV direct access decreases to the point that the HOV direct access connection is no longer desirable, the connection must be closed.

1420.02 HOV Access Types and Locations

To provide direct access for high-occupancy vehicles from the HOV lane to a passenger loading facility, there are many options and many constraints. Following are some of the options (selected as being usable on Washington's freeways) and constraints regarding their use.

To select an option, first establish the need, choose possible locations, evaluate site features (such as terrain, existing structures, median widths), and evaluate existing HOV information (such as lanes, park & ride facilities, transit routes and schedules, and origin and destination studies). Choose a location that meets access point spacing requirements and will not degrade traffic operations on the main line.

Important constraints to transit stop designs are:

- Passenger access routes and waiting areas are separated from freeway traffic.
- Passenger access to a bus is on its right side only.
- Passenger access to a loading platform must accommodate the disabled.

1420.02(1) Freeway Ramp Connection Locations

1420.02(1)(a) Spacing

For minimum ramp connection spacing, see Chapter 1360. When evaluating the spacing of left-side direct access ramps, include only left-side connections.

Traffic operations can be degraded by the weaving caused by a left-side on-connection followed closely by a right-side off-connection (or a right-side on-connection followed by a left-side off-connection). As a general rule, if the spacing between the HOV direct access ramp and the general-purpose ramp is less than one gap acceptance length (see 1420.03(6)(c)) per lane, make the HOV lane buffer-separated (see Chapter 1410).

Conduct an analysis to make certain that the new ramp will not degrade traffic operations. (See Chapter 550 for the studies and report required for a new access point.)

When an off-connection follows an on-connection, provide full speed-change lane lengths and tapers or at least sufficient distance for full speed-change lanes that connect at full width with no tapers (see 1420.03(6) and (7)). An auxiliary lane can be used to connect full-width speed-change lanes if there is not sufficient distance for both tapers.

1420.02(1)(b) Sight Distance

Locate both on- and off-connections to the main line where decision sight distance exists on the main line (see Chapter 1260).

1420.02(2) Ramp Terminal Locations

1420.02(2)(a) Local Streets and Roads

Access to the HOV lane can be provided by a ramp that terminates at a local street or road. The local street or road may incorporate HOV lanes, but they are not required. (See 1420.05 for signing and pavement markings.)

Consider traffic operations on the local road. Locate the terminal where:

- It has the least impact on the local road.
- Intersection spacing criteria are satisfied.
- Queues from adjacent intersections do not block the ramp.
- Queues at the ramp do not block adjacent intersections.
- Wrong-way movements are discouraged.

When off-ramps and on-ramps are opposite each other on the local road, consider incorporating a transit stop with the intersection.

1420.02(2)(b) Park & Ride Lots

HOV direct access ramps that connect the HOV lane with a park & ride lot provide easy access for express transit vehicles between the HOV lane and a local service transit stop at the park & ride facility. Other HOV traffic using the access ramp enters through the park & ride lot, which can create operational conflicts.

1420.02(2)(c) Flyer Stops

Median flyer stops do not provide general access to the HOV lane. Access is from the HOV lane to the transit stop and back to the HOV lane. No other vehicle access is provided. Ramps to and from the flyer stops are restricted to transit vehicles only.


1420.02(3) Ramp Types

1420.02(3)(a) Drop Ramps


Drop ramps are generally straight, stay in the median, and connect the HOV lane with a local road or flyer stop. Following is a photo and an example of a drop ramp.



Drop ramp photograph from FHWA/PB HOV Interactive 1.0
High Occupancy Vehicle Data Base from the U.S., Canada, and Europe




Consider this example for gore area characteristics for drop lanes:



1420.02(3)(b) T Ramps

A T ramp is a median ramp that serves all four HOV access movements and comes to a T intersection within the median, usually on a structure. The structure then carries the HOV ramp over the freeway to a local road or directly to a park & ride lot. Through traffic is not permitted at the T ramp; therefore, flyer stops are not allowed. A photo and an example of a T ramp are shown for reference. Also, refer to 1420.03(10) for added design information.






1420.02(3)(c) Flyover Ramps

A flyover ramp is designed to accommodate high-speed traffic by using flat curves as the ramp crosses from the median over one direction of the freeway to a local road, a park & ride lot, or an HOV lane on another freeway. A photo and an example of a flyover ramp are shown.



Flyover ramp photograph from FHWA/PB HOV Interactive 1.0 High Occupancy Vehicle Data Base from the U.S., Canada, and Europe



1420.02(4) Transit Stops

1420.02(4)(a) Flyer Stops

Flyer stops are transit stops inside the limited access boundaries for use by express transit vehicles using the freeway. They may be located in the median at the same grade as the main roadway or on a structure, on a ramp, or on the right side of the main line.

The advantage of a median flyer stop is that it reduces the time for express transit vehicles to serve intermediate destinations. A disadvantage is that passengers travel greater distances to reach the loading platform.

With left-side HOV lanes, flyer stops located on the right side increase the delay to the express transit vehicles by requiring them to cross the general-purpose lanes. However, these stops improve passenger access from that side of the freeway.

For additional design information, see Chapter 1430.


1. Side-Platform Flyer Stops



Side-platform flyer stops are normally located in the median and have two passenger loading platforms: one on each side between the bus loading lane and the through HOV lane. This design provides the most direct movement for the express transit vehicle and is the desirable design for median flyer stops.

This design is relatively wide. Where space is a concern, consider staggering the loading platforms longitudinally.

Consider tall barrier to divide the directions of travel or staggering the loading platforms to discourage unauthorized at-grade movement of passengers from one platform to the other (see 1420.05(1)). The side platform flyer stop with grade-separated access to each platform is the preferred design.




2. At-Grade Passenger Crossings

This design is similar to the side-platform flyer stop, except that passengers are allowed to cross, from one platform to the other, at grade. This design might eliminate the need for passenger access to one of the loading platforms with a ramp or an elevator, and it simplifies transfers. The passenger crossing necessitates providing a gap in the barrier for the crosswalk. Only transit vehicles are allowed. Passenger/ pedestrian accommodations must comply with the ADA.




At-grade passenger crossing photograph from FHWA/PB HOV Interactive 1.0 High Occupancy Vehicle Data Base from the U.S., Canada, and Europe

Consider an at-grade passenger crossing flyer stop only when passenger volumes are expected to be low. Design at-grade passenger crossing flyer stops as the first stage of the stop, with the ultimate design being side-platform flyer stops with grade-separated access to both platforms.



3. Ramp Flyer Stops

When ramp flyer stops are located on an HOV direct access drop ramp, the delay for the express transit vehicle will not be much more than for a median stop, and passenger access and connectivity to local service transit routes, on the local street or road, are improved. A flyer stop on a right-side ramp works well with right-side HOV lanes and diamond interchanges in which express transit vehicles can use the off-ramp to connect with a bus route on the local road and the on-ramp to return to the HOV lane. However, a stop on a general-purpose right-side ramp with a left-side HOV lane will increase the delay by requiring the express transit vehicle to use the general-purpose lanes and possibly degrade main line traffic operations by increasing weaving movements.




1420.02(4)(b) Off-Line Transit Stops

1. Park & Ride Stops

Transit stops located at park & ride lots provide transfer points between the express transit system and the local transit system, and there is convenient passenger access to the park & ride lot. When a direct access ramp is provided, express transit delays from the HOV lane to the stop are reduced. These delays can be reduced more by providing a median flyer stop with passenger access facilities connecting the park & ride lot to the flyer stop; however, this might be more inconvenient for the passengers.

2. Stops at Flyer Stop Passenger Access Points

To minimize the passenger travel distance between express and local service transit stops, locate local system transit stops near passenger access facilities for the flyer stops.



1420.02(5) Enforcement Areas

Enforcing the vehicle occupancy requirement helps the HOV facilities function as intended. Law enforcement officers need areas for observation that are near pull-out areas, where both the violator and the officer can pull safely out of the traffic flow.

Consider locating observation and pull-out areas near any point where violators can enter or exit an HOV direct access facility. Examples of potential locations are:

- Freeway on- and off-connections for HOV direct access ramps.
- HOV direct access ramp terminals at parking lots.

For freeway HOV lanes, locate enforcement areas on the adjacent shoulders so officers and violators are not required to cross several lanes of traffic.

Enforcement area guidance and designs are in Chapter 1410.

1420.03 Direct Access Geometrics

HOV direct access ramps are different than other ramps because they are usually on the left side of the through lanes and they have a high percentage of buses. Design right-side HOV direct access using the procedures given in Chapter 1360. The following procedures are for the design of left-side HOV direct access.

Because left-side ramps are rare and therefore less expected, signing is an important issue. (For signing guidance, see 1420.05(2).)

When the bus percentage is high, there are several considerations:

- When a bus enters the through lanes from the left, the driver has a relatively poor view of the through traffic.
- A bus requires a longer distance to accelerate than other vehicles.
- A bus requires a longer deceleration length for passenger comfort.

1420.03(1) Design Vehicles

Use the following design vehicles for left-side HOV direct access facilities:

- Use AASHTO's A BUS vehicle for horizontal design.
- Use AASHTO's SU-30 vehicle for vertical design.
- Use AASHTO's P vehicle for stopping sight distance.

Refer to Chapters 1300 and 1430, and the AASHTO Green Book for vehicle descriptions and dimensions. Use turn simulation software (such as AutoTURN®) to verify turning movements.

1420.03(2) Design Speeds

Refer to Chapter 1360 for the design speeds for ramps. Use the design speed of the general-purpose lanes for the main line design speed.

1420.03(3) Sight Distance

Provide stopping sight distance in accordance with Chapter 1260. This provides sight distance for an automobile. The longer distance needed for a bus to stop is compensated for by the greater eye height of the driver, with the resulting vertical curve length about equal to that for an automobile.

Sag vertical curves may be shortened where necessary. (See Chapter 1220 for guidance.)

1420.03(4) Grades

Grades for ramps are covered in Chapter 1360. Deviations will be considered for:

- Downgrade on-ramps with grades increased by an additional 1%.
- Upgrade off-ramps with grades increased by an additional 2%.

These increased grades help when geometrics are restricted, and they assist transit vehicles with the acceleration when entering and the deceleration when exiting the freeway.

1420.03(5) Ramp Widths

1420.03(5)(a) Lane Widths

Use widths for separated roadway HOV facilities. (See Minimum Traveled Way Widths for Articulated Buses in Chapter 1410.) On tangents, the minimum lane width may be reduced to 12 feet.

1420.03(5)(b) Shoulder Widths

Ramp shoulder width criteria are modified as follows:

- The minimum width for the sum of the two shoulders is 10 feet for one-lane ramps and 12 feet for two or more lanes.
- The minimum width for one of the shoulders is 8 feet for disabled vehicles. The minimum width for the other shoulder is 2 feet. (See Chapter 1239 for lateral clearance to curb and barrier.)
- The wider shoulder may be on the left or the right. Maintain the wide shoulder on the same side throughout the ramp.

Minimum Ramp Widths for Articulated Buses

R (ft)*	W_R (ft)
Tangent	21
500	23
400	23
300	24
200	26
150	27
100	30
75	34
50	40

*R is to the curve inside edge of traveled way

1420.03(5)(c) Total Ramp Widths

When an A-BUS is the intersection design vehicle at the ramp terminal, make the total width of the ramp (lane width plus shoulders) wide enough to allow an A-BUS to pass a stalled A-BUS. This width has two components:

- The vehicle width (U = 8.5 feet on tangent) for each vehicle
- Lateral clearance (C = 2 feet) for each vehicle

The vehicle width and the lateral clearance are about the width of an A-BUS from edge of mirror to edge of mirror.


The table above gives the minimum ramp width (W_R), including shoulders, at various radii (R) for an articulated bus. For ramp locations on a tangent section or on a curve with a radius greater than 150 feet, consider the W_R width when requesting a reduced lane or shoulder width. For ramp curves with a radius less than 150 feet, check the total ramp width and, if necessary, widen the shoulders to provide the W_R width.

1420.03(6) On-Connections

1420.03(6)(a) Parallel On-Connections

For left-side on-connections, use the parallel on-connection.

A parallel on-connection adds a parallel lane that is long enough for the merging vehicle to accelerate in the lane and then merge with the through traffic. This merge is similar to a lane change and the driver can use side and rear view mirrors to advantage.



Notes:

[1] For acceleration lane length L_A, see 1420.03(6)(b). Check L_A for each ramp design speed.

[2] L_g is the gap acceptance length. Begin L_g at the beginning of the parallel lane, as shown, but not before the end of the acceleration lane L_A. (See 1420.03(6)(c) for the length L_g.)

[3] Point Ⓐ is the point controlling the ramp design speed or the end of the transit stop zone or other stopping point.

[4] For ramp lane and shoulder widths, see 1420.03(5).


[5] A transition curve with a minimum radius of 3,000 ft is desirable. The desirable length is 300 ft. When the main line is on a curve to the right, the transition may vary from a 3,000 ft radius to tangent to the main line. The transition curve may be replaced by a 50:1 taper with a minimum length of 300 ft.

[6] Angle point for width transitions, when required. (See Chapter 1210 for pavement transitions.)

[7] For ramp shoulder width, see 1420.03(5)(b).

[8] The 10 ft left shoulder is the minimum width; 14 ft is desirable. Maintain this shoulder width for at least 500 ft; 1,000 ft is desirable.

[9] Radius may be reduced when concrete barrier is placed between the ramp and main line.



Paving Detail

General:

For striping, see the *Standard Plans*.


Ramp lane width shown for illustrative purposes. Determine lane width according to 1420.03(5). Verify ramp width selection with transit providers that may utilize these connections.

1420.03(6)(b) Acceleration Lanes

The table below gives the minimum acceleration lane length (L_A) for left-side HOV direct access on-connections.

The buses using HOV direct access ramps merge with high-speed traffic. Acceleration lanes that are longer than normally used are needed.

For left-side on-connections, consider at least the normal 10-foot-wide (14-foot desirable) left shoulder for the main line for a minimum length of 500 feet (1,000 feet desirable) beyond the end of the on-connection taper. This gives additional room for enforcement, merging, and erratic maneuvers.



Freeway Speed (mph)	Ramp Design Speed								
	0	15	20	25	30	35	40	45	50
40	555	480	420	340	185				
45	835	760	700	615	470	290			
50	1,230	1,160	1,100	1,020	865	685	310		
55	1,785	1,715	1,655	1,575	1,420	1,235	875	410	
60	2,135	2,085	2,040	1,985	1,875	1,735	1,440	995	460
70	3,045	3,015	2,985	2,945	2,860	2,745	2,465	2,050	1,515
80	4,505	4,465	4,420	4,370	4,250	4,095	3,745	3,315	2,780

Acceleration Length (LA) for Buses (ft)

Notes: For the adjustment factors for grade, see acceleration lane in Chapter 1360.
Ramp lane width shown for illustrative purposes. Determine ramp lane widths according to 1420.03(5). Verify ramp width selection with transit providers that may utilize these connections.

1420.03(6)(c) Gap Acceptance Length

Gap acceptance length is a minimum distance traveled while a merging driver finds a gap in the through traffic and begins the merge. For left-side parallel on-connections, the gap acceptance length is added to the acceleration length. The L_g values are given in the table below. These values are larger than for right-side on-connections to account for drivers' visibility constraints.

Highway Posted Speed (mph)	Gap Acceptance Length, L_g (ft)
45	550
50	625
55	700
60	775
65	850
70	925

1420.03(6)(d) Urban On-Connection Design

Design left-side HOV direct access on-connections in urban areas as follows:

1. Use the parallel design for left-side on-connections.
2. Add the Gap Acceptance Length for Parallel On-Connections (see 1420.03(6)(c)) for a freeway speed of 60 mph to the acceleration length.
3. Use Acceleration Length for Buses (see 1420.03(6)(b)) with a 60 mph freeway speed and the ramp design speed (see 1420.03(2)) for acceleration length.


1420.03(6)(e) Rural On-Connection Design


Design left-side HOV direct access on-connections in rural areas using mainline design speed.

1420.03(7) Off-Connections

1420.03(7)(a) Parallel Off-Connection

The parallel off-connection is desirable for left-side direct access off-connections. For freeway-to freeway off-connections, provide a parallel lane with a length sufficient for signing and deceleration. The desirable minimum length is not less than the gap acceptance length (see 1420.03(6)(c)).





Notes:

[1] For deceleration lane length LD, see 1420.03(7)(c). Check LD for each ramp design speed.

[2] Point Ⓐ is the point controlling the ramp design speed or the end of the transit stop zone or other stopping point.

[3] Ramp lane width shown for illustrative purposes. Determine lane and shoulder widths according to 1420.03(5). Verify ramp width selection with transit providers that may utilize these connections.

[4] For ramp shoulder width, see 1420.03(5)(b).

[5] Angle point for width transitions, when required. (See Chapter 1210 for pavement transitions.)

[6] Gore area characteristics at drop ramp connections are shown on 1420.02(3)(a). (See Chapter 1360 for gore details at other connection types.)

[7] The desirable shoulder width is 10 ft.

General:


For striping, see the *Standard Plans*.

1420.03(7)(b) Tapered Off-Connection

The tapered off-connection may be used, with justification. (See Chapter 1360 for the design of tapered off-connections.)

1420.03(7)(c) Deceleration Lanes

Bus passenger comfort requires longer deceleration lanes. Use the deceleration lane lengths from the table below for HOV direct access facilities.



Freeway Speed (mph)	Ramp Design Speed								
	0	15	20	25	30	35	40	45	50
40	390	330	290	240	170	100			
45	470	420	380	330	260	190	90		
50	570	520	480	430	360	290	190	100	
55	680	620	590	540	470	400	300	210	110
60	800	740	700	660	580	520	420	330	230
70	990	930	900	850	780	710	610	520	420
80	1,210	1,150	1,110	1,060	990	920	830	740	640

Deceleration Length (L_D) for Buses (ft)

Notes: For the adjustment factors for grade, see deceleration lane in Chapter 1360. Ramp lane width shown for illustrative purposes. Determine lane width according to 1420.03(5). Verify ramp width selection with transit providers that may utilize these connections.

1420.03(7)(d) Urban Off-Connection Design

Design left-side HOV direct access off-connections in urban areas as follows:

1. Either the parallel (desirable) or the taper (with justification) design may be used.
2. Use the longer deceleration length of: the Deceleration Length for Buses (see 1420.03(7)(c)) from a 60 mph freeway speed to the ramp design speed (see 1420.03(2)) or the Minimum Deceleration Length given in Chapter 1360 from the freeway design speed to the ramp design speed.

1420.03(7)(e) Rural Off-Connection Design

Design left-side HOV direct access off-connections in rural areas using mainline design speed.

1420.03(8) Vertical Clearance

Vertical clearance for a structure over a road is measured from the lower roadway surface, including the usable shoulders, to the bottom of the overhead structure.

Refer to Chapter 720 for information on vertical clearance.

The minimum vertical clearance for a pedestrian grade separation over any road is 17.5 feet.

1420.03(9) Flyer Stops

Design flyer-stop ramp on-connections as given in 1420.03(6), and design off-connections as given in 1420.03(7). Flyer stop connections are included in the access point spacing discussed in 1420.02(1)(a).

Design the ramp to the flyer stop in accordance with 1420.03(3), 1420.03(4), and 1420.03(5).

The minimum width for the roadway at a flyer stop is 24 feet.


When a flyer stop is in the median, provide enough median width for the flyer stop roadway, passenger facilities, and barrier separation without reducing the width of the through lanes or shoulders (see 1420.04).


The approval of a flyer stop requires the operational analysis portion of the interchange justification report (see Chapter 550).

1420.03(10) Wrong-Way Driving Countermeasures

The following bulleted items and examples are countermeasures for wrong-way driving at HOV direct access ramps:

- Provide a staggered traffic arrow to better describe the left and right turns.
- Provide pavement marking extensions, using wide lines, through intersections.
- Use redundant directional pavement arrows at ramp terminals.
- Paint or use reflective sheeting to highlight barrier terminals.
- Locate the left barrier end to provide good visibility for left-turning traffic for both the barrier terminal and the on-ramp roadway.
- Extend the right barrier as far as feasible while providing a 4-foot clearance for the left-turning exiting design vehicle.
- Provide redundant signing.
- Provide enlarged warning signs.





1420.04 Passenger Access

When designing transit stops, include accessibility (compliance with the ADA), safety, and the comfort of passengers. Minimize pedestrian/vehicle conflict points. Design the whole facility with security in mind by keeping lines of sight as open as possible. Traffic barriers, fencing, illumination, landscaping, seating, windscreens, shelters, enclosed walkways, telephones, and posted schedules are examples of items that contribute to passenger safety and well-being. (See Chapter 1430 for passenger amenities at transit stops.)

1420.04(1) Passengers

To encourage use of the passenger access facility for an express transit stop, provide a route that is the shortest distance to travel from the park & ride lot or local transit stop. Failure to do so might generate the use of undesirable shortcuts. To encourage local use of the passenger access facilities, provide direct access from surrounding neighborhoods.

Provide grade separations for pedestrian access to transit stops in the median. Consider stairways, ramps, elevators, and escalators, but provide at least one access for the disabled at every loading platform, as required by the American with Disabilities Act of 1990. (See Chapter 1510 for guidance when designing pedestrian grade separations.)

The ADA Accessibility Guidelines for Buildings and Facilities states, "Platform edges bordering a drop-off and not protected by platform screens or guard rails shall have a detectable warning … 24 inches wide running the full length of the platform drop-off." (See the *Standard Plans* for the detectable warning pattern.)

At transit stops, at-grade crosswalks are only permitted in the at-grade crossing flyer stop layout described in 1420.02(4)(a)2. Use traffic calming techniques, such as horizontal alignment, textured pavement and crosswalk markings, barrier openings, and other treatments, to channelize pedestrian movements and slow the transit vehicle's movements. Illuminate transit stop crosswalks (see Chapter 1040).

Where at-grade crosswalks are not permitted, take steps to minimize unauthorized at-grade crossings. Fencing, taller concrete traffic barrier, enclosed walkways, and ramps are examples of steps that may be taken.

1420.04(2) Bicycles

Bike lanes on nearby streets and separate trails encourage people to bicycle from surrounding neighborhoods. Provide these bicyclists direct access to passenger access facilities.

Design bicycle access facilities in conjunction with the access for the disabled (see Chapters 1510, 1515, and 1520).

Locate bicycle parking outside of the passenger walkways (see Chapter 1430).

Locations near colleges and universities and locations with good bicycle access, especially near trails, will attract bicyclists. Contact the region Bicycle Coordinator for information on the predicted number of bicycle parking spaces needed and the types of bicycle racks available.

1420.05 Traffic Design Elements

Traffic design elements are critical to the safe and efficient use of HOV direct access facilities. The following discusses the elements of traffic design that might be different for HOV direct access facilities.

1420.05(1) Traffic Barriers

Separate the main line from the HOV direct access facilities with a traffic barrier. Whenever possible, separate opposing traffic lanes in the facility by using traffic barrier (see Chapter 1610). This is especially important in areas where opposing traffic is changing speeds to or from main line speeds. Concrete barrier is generally desirable on these facilities due to lower maintenance requirements.

Provide crashworthy end treatments to the approach ends of traffic barriers (see Chapter 1620).

When the operating speed is 25 mph or lower, and where an at-grade pedestrian crossing transit stop has an opening in a concrete barrier, a sloped-down end as shown in the *Standard Plans* is acceptable.

When providing a break in the barrier for turning maneuvers, consider sight distance (see Chapter 1260) when determining the location for stopping the barrier.

In areas where headlight glare is a concern, consider glare screens such as taller concrete barrier. Other glare screen options that mount on the top of a barrier tend to be high-maintenance items and are discouraged.

Taller barrier might also be desirable in areas where pedestrian access is discouraged, such as between opposing flyer stops or between a flyer stop and the main line.

1420.05(2) Signing

Design and place HOV signing to clearly indicate whether the signs are intended for motorists in the HOV lane or the general-purpose lanes. The purposes of the signs are to:

- Enhance safety.
- Convey the message that HOV lanes are restricted to HOVs.
- Provide clear directions for entrances and exits.
- Define vehicle occupancy requirements or other restrictions.

Because HOV facilities are not found in many regions, the signing not only considers the commuter but also the occasional user of the facility who might be unfamiliar with the HOV facility and its operation.

1420.05(2)(a) Safety

Much of HOV signing relates to enhancing safety for motorists. Not only are geometrics often minimized due to the lack of right of way, but there are unusual operational characteristics such as the differential speed between the HOV vehicle and the adjacent general-purpose traffic. To allow for the lack of passing opportunities in the HOV lane and the necessity for frequent merging and weaving actions, use messages that are clear and concise, and use symbols wherever possible.

Because left-side off-connections are unusual, advance warning signing alerting motorists that an exit is on the left becomes more important.


For T ramps, provide traffic control at the T to assign priority to one of the turn movements and to avert wrong-way movements.

1420.05(2)(b) Diamond Symbols

The diamond symbol is used to designate HOV facilities where carpools are allowed. For all signs, whether regulatory, guide, or warning, the symbol is white on a black background to convey the restrictive nature of the HOV lane and to make the signs more uniformly recognizable. The use of the symbol with all HOV signs also informs drivers that the message is intended for HOVs. The diamond symbol is only for HOV lanes where carpools are allowed; it is not used for bus, taxi, or bicycle preferential lanes.

1420.05(2)(c) Selection and Location

The signing details given throughout this section provide for the HOV geometric configurations used within the right of way. Signing for other types of HOV facilities (such as those used for reversible-flow and for HOV direct access between freeways and temporary HOV lanes used during construction) is designed on a case-by-case basis and requires consultation with the appropriate Headquarters and region traffic personnel. In addition to the normal regulatory signs, include HOV guide signs, both advance and action, in the design of signing for HOV direct access between freeways.




Notes:


- Place signs in accordance with the MUTCD.
- For non-HOV sign details, see the *Sign Fabrication Manual*.

1420.05(2)(d) Regulatory Signs


Regulatory signs for HOV facilities follow the normal regulatory signing principles: black legend with a white reflective background on a rectangular panel. Keep in mind that messages conveyed by the HOV signs (such as signs concerning violations and those indicating the beginning of an HOV lane downstream) are not necessarily intended only for the HOV vehicle. Therefore, it might be prudent to place additional signs on the right side of the freeway when doing so conforms to sound engineering practice.




E1-1 MOD.
BLACK ON WHITE




E6-101 MOD.
BLACK ON WHITE




E6-2 MOD.
BLACK ON WHITE




D1-701 MOD.
BLACK ON WHITE
SHIELD
LEGEND - WHITE (REFL)
TOP - RED (REFL)
BOTTOM - BLUE (REFL)



E5-1 MOD.
BLACK ON WHITE



E12-201 MOD.
BLACK ON WHITE



W13-2 MOD.
WHITE ON BLACK &
BLACK ON YELLOW



Guide striping provided for left-hand turns.



Do Not Enter sign located on the left side at the top of each off-ramp.



Keep Right sign located at the top of the median barrier separating on- and off-ramps.



HOV Entrance sign located on the right side at the beginning of each on-ramp.




Wrong Way signs (30° rotation at potential wrong-way entrance point).



Diamonds and Turn Only pavement markings on off-ramps.

1420.05(2)(e) Guide Signs

Guide signs for HOV facilities are generally used at intermediate on and off locations to inform HOV motorists of upcoming freeway exits and the appropriate location to exit the HOV lane. For HOV direct access to and from arterials, guide signs are used in a fashion similar to normal arterial interchange signing practice. The guide signs for HOV facilities have a black nonreflective legend on a white reflective background. The exception is the diamond, where the white reflective symbol is on a black nonreflective background. For all HOV-related guide signs, the diamond is placed in the upper left-hand corner of the sign.



Notes:

- Sign placement shall be in accordance with the MUTCD.
- For non-HOV sign details, see the *Sign Fabrication Manual*.

1420.05(3) Lighting

Provide illumination of HOV direct access ramps, loading platforms at transit stops, major parking lots, and walkways as defined in Chapter 1040.

1420.05(4) Intelligent Transportation Systems

Intelligent Transportation Systems (ITS) are used to collect traffic data, maintain freeway flow, and disseminate traveler information. Transit information systems for passengers and transit facility surveillance are not normally a part of WSDOT's system, but implementation of these components may be considered for some locations.

Fully utilize available ITS elements in the design of HOV direct access facilities. Need for ITS elements varies depending on project features, such as facility design and operation, and whether the site has existing ITS components.

ITS elements that might be applicable to HOV direct access facilities include: closed circuit television surveillance; ramp metering; data collection; exit queue detection and override; dynamic signing; transit signal priority; and automatic vehicle identification and location.

Guidance on the development of ITS elements is found in Chapter 1050. Include the region Traffic Office, transit operator, and affected local agency in the coordination for the design and implementation of ITS.

1420.06 Documentation

Refer to Chapter 300 for design documentation requirements.

1420.07 References

1420.07(1) Federal/State Laws and Codes

Americans with Disabilities Act of 1990 (ADA) (28 Code of Federal Regulations [CFR] Part 36, Appendix A, as revised July 1, 1994)

Washington Administrative Code (WAC) 468-510-010, High occupancy vehicles (HOV)

1420.07(2) Design Guidance

ADA Field Guide for Accessible Public Rights of Way, WSDOT

ADA Standards for Accessible Design, U.S. Department of Justice (USDOJ), 2010; consists of 28 CFR parts 35 & 36 and the ADA and Architectural Barriers Act (ABA) Accessibility Guidelines for Buildings and Facilities (ADA-ABAAG; also referred to as the 2004 ADAAG), July 23, 2004, U.S.

Access Board. (For buildings and on-site facilities; applies to new construction or alterations as of March 15, 2012.)
www.access-board.gov/guidelines-and-standards

ADA Standards for Transportation Facilities, USDOT, 2006; consists of 49 CFR Parts 37 & 38 and the ADA and ABA Accessibility Guidelines for Buildings and Facilities (ADA-ABAAG; also referred to as the 2004 ADAAG), July 23, 2004, U.S. Access Board as modified by USDOT. (For transit, light rail, and similar public transportation facilities.)
www.access-board.gov/guidelines-and-standards

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)

Revised Draft Guidelines for Accessible Public Rights-of-Way (PROWAG), November 23, 2005, U.S. Access Board. The current best practices for evaluation and design of pedestrian facilities in the public right of way per the following FHWA memoranda:
www.fhwa.dot.gov/environment/bikeped/prwaa.htm
www.fhwa.dot.gov/civilrights/memos/ada_memo_clarificationa.htm
http://www.access-board.gov/guidelines-and-standards

Sign Fabrication Manual, M 55-05, WSDOT

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT

1420.07(3) Supporting Information

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO

FHWA/PB, *HOV Interactive 1.0 High Occupancy Vehicle Data Base from the U.S., Canada and Europe* (CD ROM), USDOT, FHWA and Parsons Brinkerhoff

Bus Use of Highways: Planning and Design Guidelines, NCHRP 155

Guide for the Design of High-Occupancy Vehicle (HOV) Facilities, AASHTO

High-Occupancy Vehicle Facilities: A Planning, Design, and Operation Manual, Parsons Brinckerhoff

HOV Systems Manual, NCHRP 414

"Transit Implications of HOV Facility Design," WA-RD 396.1, September 1996, WSDOT and USDOT, Federal Transit Administration

Chapter 1430 Transit Facilities

1430.01 General
1430.02 Bus Stops and Pullouts
1430.03 Passenger Amenities
1430.04 Park and Ride Lots
1430.05 Transfer/Transit Centers
1430.06 Roadway and Intersection Design
1430.07 Documentation
1430.08 References

1430.01 General

This chapter provides general siting and design information for transit facilities. It is intended for Washington State Department of Transportation (WSDOT) engineering and planning staff, local transit providers, developers, and local agencies engaged in the collaborative development of transit facilities on or adjacent to state highways.

The main points covered in this chapter are:

- **Bus Stop Policy:** WSDOT's policy for developing bus stops on state highways is presented. The policy calls for WSDOT and the transit provider to work together to locate stops on state highways. Bus stop placement considerations are also provided.
- **Park and Ride Lots:** Basic guidelines for development of park and ride lots are presented.
- **Transit/Transfer Centers:** Guidance on these centers is provided. Guidance in the Park and Ride section may apply as well.
- **Universal Access:** The requirements of the Americans with Disabilities Act (ADA) apply to bus stops and shelters, park and ride lots, and transit centers. This information is presented in various sections of the chapter, with additional references provided.
- **Tools and Resources:** Additional guidance and criteria are recommended and referenced, such as: other chapters in the *Design Manual* for designing intersections and road approaches; the *Roadside Manual* for parking lot design; the local transit authority's own standards; and AASHTO.

The design and planning information that follows supports the development of public transit infrastructure and services on state highways.

***Design Manual* topics and chapters commonly used in conjunction with this chapter include:**

- Right of way and access control: Chapters 510 through 560.
- Intersections and road approaches: Chapters 1300 through 1370.
- Americans with Disabilities Act (ADA) and sidewalk design: Chapter 1510.
- High-occupancy vehicle (HOV) facilities: Chapters 1410 and 1420.

1430.02 Bus Stops and Pullouts

WSDOT's Modal Integration Goal seeks to optimize existing system capacity through better interconnectivity of all transportation modes. In support of this goal, WSDOT promotes safe and efficient public transportation services on state highways, including transit routes and stops.

On limited access facilities, bus stops are only allowed at designated locations, such as flyer stops. (See Chapters 520, 530, and 540 for access control policy and guidance.)

Bus stops may be approved on non-limited access facilities at the transit agency's request and upon formal review by WSDOT for sight distance and universal access requirements at the proposed location. At a transit agency's option, a bus stop on these highways may be located either within the travel lane, or outside the travel lane in a pullout. Contact the State Traffic Engineer for information on how to process a transit agency proposal for either an in-lane or pullout bus stop and for more information about the approval process.

Refer to WAC 468-46, Transit Vehicle Stop Zones, for additional details.

The bus stop is the point of contact between the passenger and the transit services. The simplest bus stop is a location by the side of the road. The highest quality bus stop is an area that provides passenger amenities and protection from the weather. Bus stops are typically maintained by the transit agency. The bus boarding and alighting pad, the path to the shelter, and the area within the shelter must meet the requirements for universal access. Coordinate with the local transit agency regarding the location and what type of bus stop to use.

For additional information on bus stop treatments, see *Understanding Flexibility in Transportation Design – Washington* and the transit agency's standards for treatment.

1430.02(1) Bus Stop Placement Guidelines

The information in this section is offered as an example of good practice, and is not intended to be binding by either the transit agency or WSDOT.

Placement of bus stops addresses the needs and convenience of transit providers, riders, and highway or street operations. Basic considerations include:

- The need for safe, secure, and convenient service for patrons
- Access for people with disabilities
- Convenient passenger transfers to other intersecting bus routes or transfer points
- Connection to nearby pedestrian circulation systems
- Presence and width of sidewalks, crosswalks, and curb ramps
- Pedestrian activity through intersections
- Ability of the stop to accommodate transit dwell time and the loading/unloading of wheel chairs and bicycles
- Adequate curb space for the number of buses expected at the stop at one time
- Ease of reentering traffic stream (if a pullout)
- Design characteristics and operational considerations of the highway or street
- Presence of on-street automobile parking and truck delivery zones
- Traffic control devices near the bus stop, such as signals or stop signs
- Volumes and turning movements of other traffic, including bicycles

- Proximity and traffic volumes of nearby driveways
- Street grade
- Proximity to rail crossings
- Accommodating transit priority equipment at signalized intersections
- Transit queue bypass at signalized intersections
- Often stops are paired on each side of a highway or street
- Proximity to intersections

Where blocks are exceptionally long or where bus patrons are concentrated well away from intersections, midblock bus stops and midblock crosswalks may be beneficial. Contact the Region Traffic Engineer when a midblock bus stop is being considered on a multilane roadway to determine crossing design details and treatments that may be required. (See Chapter 1510 and the *Traffic Manual* for more information on midblock crossings.)

It is common to clearly mark the bus stop as a NO PARKING zone or as a BUS ONLY zone with signs and/or curb painting.

The remainder of this section discusses three types of bus stops:

- Far-side, with a stop located just past an intersection
- Near-side, with a stop located just prior to an intersection
- Midblock, with a stop located away from an intersection

Exhibit 1430-1 illustrates these three types of stops and provides some general dimensions. Consult the AASHTO *Guide for Geometric Design of Transit Facilities on Highways and Streets* for additional guidelines on bus stop spacing, including information on these types of stops.

Examine each case separately and determine the most suitable location, giving consideration to service and safety of patrons, efficiency of transit operations, and traffic operation in general.

1430.02(1)(a) Far-Side Bus Stops

Sight distance conditions generally favor far-side bus stops, especially at unsignalized intersections. A driver approaching a cross street on the through lanes can see any vehicles approaching from the right. With near-side stops, the view to the right may be blocked by a stopped bus. Where the intersection is signalized, the bus may block the view of one of the signal heads.

Advantages:

- Right turns can be accommodated with less conflict.
- Minimum interference is caused at locations where traffic is heavier on the approach side of the intersection.
- Stopped buses do not obstruct sight distance for vehicles entering or crossing from a side street.
- At a signalized intersection, buses can often find a gap to enter the traffic stream, except where there are heavy turning movements onto the street with the bus route.
- Waiting passengers assemble at less-crowded sections of the sidewalk away from the intersection corners.
- Buses in the bus stop do not obscure traffic control devices or pedestrian movements at the intersection.

Disadvantages:

- Intersections may be blocked if other vehicles park illegally in the bus stop or if more buses than the stop can accommodate arrive at the same time.
- If signal priority is not used, the bus stops at the red light and again at the far-side stop, interfering with traffic and efficient bus operations.

1430.02(1)(b) Near-Side Bus Stops

Advantages:

- May be considered in cases where a far-side bus stop location does not provide a secure, convenient, or feasible boarding location for passengers.
- Minimum interference is caused where traffic is heavier on the departure side than on the approach side of the intersection.
- Less interference is caused where the cross street is a one-way street from right to left.
- Passengers generally exit the bus close to the crosswalk.
- There is less interference with traffic turning onto the bus route street from a side street.

Disadvantages:

- Can cause conflicts with right-turning traffic.
- Buses often obscure sight distance to stop signs, traffic signals, or other control devices, as well as to pedestrians crossing in front of the bus.
- Where the bus stop is too short to accommodate buses arriving at the same time, the overflow may obstruct the traffic lane.
- If a queue bypass or bus lane is not used at a signalized intersection, then vehicles waiting at a red signal may block buses from accessing the bus stop, which will require the bus to wait through multiple signal cycles to enter and then depart the bus stop.

1430.02(1)(c) Midblock Bus Stops

Midblock stop areas are desirable under the following conditions: where traffic or physical street characteristics prohibit a near- or far-side stop adjacent to an intersection, or where large factories, commercial establishments, or other large bus passenger generators exist. Locate a midblock stop at the far side of a pedestrian crosswalk (if one exists), so that standing buses do not block an approaching motorist's view of pedestrians in the crosswalk.


Advantages:

- Buses cause a minimum of interference with the sight distance of both vehicles and pedestrians.
- Stops can be located adjacent to major bus passenger generators and attractors.
- Allows riders to board buses closest to the crosswalk.

Disadvantages:

- Increases walking distance for passengers crossing at intersections.
- Buses may or may not have difficulty reentering the flow of traffic.
- Driveway access may or may not be negatively impacted.

Exhibit 1430-1 Bus Zone Dimensions



Minimum Lengths for Bus Curb Loading Zones (L)[1]						
Approx. Bus Length	Loading Zone Length (feet)					
	One-Bus Stop			Two-Bus Stop		
	Far-Side[2]	Near-Side[3] [4]	Midblock	Far-Side[2]	Near-Side[3][4]	Midblock
25	65	90	125	90	120	150
30	70	95	130	100	130	160
35	75	100	135	110	140	170
40	80	105	140	120	150	180
60	100	125	160	160	190	220

Notes:

[1] Based on bus 1 ft from curb on 40 ft wide streets. When bus is 0.5 ft from curb, add 20 ft near-side, 15 ft far-side, and 20 ft midblock. Add 15 ft when street is 35 ft wide, and 30 ft when street is 32 ft wide.

[2] Measured from extension of building line or established stop line. Add 15 ft where buses make a right turn.

[3] Add 30 ft where right-turn volume is high for other vehicles.

[4] Measured from head of bus zone as determined by the transit agency (may depend on ADA considerations). Add 15 ft where buses make a right turn.

1430.02(2) Bus Pullouts

When designing a pullout, incorporate a deceleration lane or taper into the pullout, a staging area for all anticipated buses, and a merging lane or taper exiting the pullout. As roadway operating speeds increase, increase the taper length accordingly.




Bus Pullout with Longitudinal Island

Exhibit 1430-2 illustrates general dimensions and design features of a bus pullout located along a road. It could also apply to a pullout integrated at the edge of a park and ride lot or transit center.

Exhibit 1430-3 illustrates the dimensions and design features of bus pullouts associated with near-side, far-side, and midblock bus pullouts.


Exhibit 1430-4 illustrates the dimension and design of far-side bus zones and pullouts where buses stop after making a right turn. Adherence to these designs allows buses to stop with minimal interference to legally parked vehicles.

Exhibit 1430-2 Pullout for Bus Stop along a Road




*On higher-speed facilities, it may be necessary to provide a greater acceleration/deceleration transition. Suggested values shown; coordinate designs with the transit agency.


Exhibit 1430-3 Bus Stop Pullouts: Arterial Streets




A. Far-Side




C. Near-Side Right-Turn Lane and Far-Side Bus Bays[1]




B. Near-Side




D. Midblock Bus Bays



Near-Side Corner Location



Far-Side Corner Location



Midblock Location


Notes:

This exhibit provides some general values; coordinate with transit provider for actual dimensions.


[1] For right-turn lane design, see Chapter 1310.

[2] Based on a 40 ft bus. Add 20 ft for articulated bus. Add 45 ft (65 ft articulated) for each additional bus.


Exhibit 1430-4 Bus Zone and Pullout After Right Turn



Far-Side Bus Stop



Far-Side Bus Pullout
After Right Turn



* Based on 40' bus. Add 20' for articulated bus.

1430.03 Passenger Amenities

1430.03(1) Bus Stop Waiting Areas

Bus passengers desire a comfortable place to wait for the bus. Providing an attractive, pleasant setting for the passenger waiting area is an important factor in attracting bus users.

Important elements of a bus stop include:

- ADA Standards
- Protection from passing traffic
- Lighting
- Security
- Paved surface
- Protection from the environment
- Seating or other street furniture (if the wait may be long)
- Information about routes serving the stop

Providing protection from passing traffic involves locating stops where there is enough space, so passengers can wait away from the edge of the traveled roadway. The buffering distance from the roadway increases with traffic speed and traffic volume. Where vehicle speeds are 30 mph or below, 5 feet is a satisfactory distance. In a heavy-volume arterial with speeds up to 45 mph, a distance of 10 feet provides passenger comfort.

Passengers arriving at bus stops, especially infrequent riders, want information and reassurance. Provide information that includes the numbers or names of routes serving the stop. Other important information may include a system route map, the hours and days of service, schedules, and a phone number for information. Information technology systems are evolving and some transit agencies now provide information about wait time until the next bus and kiosks to purchase the fare before boarding.

Where shelters are not provided, a bus stop sign and passenger bench are desirable, depending on weather conditions. The sign indicates to passengers where to wait and can provide some basic route information. The information provided and format used is typically the responsibility of the local transit agency.

1430.03(2) Passenger Shelters

Passenger shelters provide protection for waiting transit users and create driver awareness of intermodal connections involving vulnerable users. Locate the shelter conveniently for users, without blocking the sidewalk or the drivers' line of sight.

Providing shelters (and footing for shelters) is normally the responsibility of the local transit agency; it provides for shelter design and footing needs. State motor vehicle funds cannot be used for design or construction of shelters, except for the concrete pad.

Lighting can enhance passenger safety and security. Lighting makes the shelter visible to passing traffic and allows waiting passengers to read the information provided. General street lighting is usually sufficient. Where streetlights are not in place, consider streetlights or transit shelter lights. For information on illumination, see Chapter 1040.

A properly drained paved surface is needed so passengers do not traverse puddles and mud in wet weather. Protection from the environment is typically provided by a shelter, which offers shade from the sun, protection from rain and snow, and a wind break.

Shelters can range from simple to elaborate. The latter type may serve as an entrance landmark for a residential development or business complex and be designed to carry through the architectural theme of the complex. If a non-public transportation entity shelter is provided, its design and siting must be approved by the local transit agency. The reasons for this approval include safety, barrier-free design, intermodal connections, and long-term maintenance concerns.


Consider shelters at bus stops in new commercial and office developments and in places where large numbers of elderly and disabled persons wait, such as at hospitals and senior centers. In residential areas, shelters are placed at the highest-volume stops.

In order to use buses that are accessible, bus stops must also be accessible. The nature and condition of streets, sidewalks, passenger loading pads, curb ramps, and other bus stop facilities can constitute major obstacles to mobility and accessibility. State, local, public, and private agencies need to work closely with public transportation officials to provide universal access.

Involve the local transit agency in the bus stop pad design and location so that lifts can actually be deployed at the site.

In order to access a bus stop, it is important that the path to the stop also be accessible. This can be accomplished by the use of sidewalks with curb ramps. For sidewalk design and curb ramp information, see Chapter 1510 and the *Standard Plans*. Exhibit 1430-5 depicts ADA standards for bus stop locations.

Exhibit 1430-5 Bus Stop Accessibility Features



✳ Slope may be the same as the roadway

Design bus shelter clear space to meet the requirements found in *ADA Standards for Transportation Facilities*.



Passenger shelter showing clear space

For more details, see:

Chapter 3, *ADA Standards for Transportation Facilities*, United States Access Board
www.access-board.gov/guidelines-and-standards/transportation/facilities/ada-standards-for-transportation-facilities/chapter-3-building-blocks

Chapter 8, *ADA Standards for Transportation Facilities*, United States Access Board
www.access-board.gov/guidelines-and-standards/transportation/facilities/ada-standards-for-transportation-facilities/chapter-8-special-rooms,-spaces,-and-elements

1430.04 Park and Ride Lots

Park and ride lots provide parking for people who wish to transfer from private vehicles, bicycles, and other modes to public transit or carpools/vanpools. Most park and ride lots located within urban areas are served by transit agencies. Leased lots, such as at churches or shopping centers, or park and rides in rural locations, may have no bus service and only serve carpools and vanpools.

HOV facilities are often considered and included in larger park and ride lots, to improve access for transit and carpools (see Chapter 1410).

Park and ride needs and locations are determined through planning processes typically conducted by transit agencies, WSDOT, and/or RTPOs/MPOs. Once the need is identified, then the project lead should be identified. Early and continual coordination between the project lead and other stakeholders, authorities, and agencies is critical.



Park and ride lot

A **Cooperative Agreement** is written by Headquarters (HQ) Real Estate Services for the purpose of assigning maintenance and/or operational responsibilities for a WSDOT park and ride lot to a transit agency or local governmental agency. (See the *Agreements Manual* and the HQ Real Estate Services Cooperative Agreement form.)

When a memorandum of understanding (MOU) or other formal agreement exists that outlines the design, funding, maintenance, and operation of park and ride lots, it must be reviewed for requirements pertaining to new lots. If the requirements in the MOU or other formal agreement cannot be met, the MOU must be renegotiated.

1430.04(1) Site Selection

In determining the location of a park and ride lot, public input is a valuable tool. Estimated parking demand and other factors determine the size of the lot. Traveler convenience is an important siting factor. Locations that minimize overall trip travel time are most attractive to commuters. Park and rides near freeway access tend to be heavily used because they minimize overall trip travel time for the most people. Freeway proximity makes it easier for transit authorities to provide frequent route service. Other factors that may affect the initial size of the park and ride lot may include available land, the state of the economy, energy availability and cost, perceived congestion, transit service frequency, and environmental controls.

Consider sizing the facility to allow for a conservative first-stage construction with expansion possibilities. As a rule of thumb, 1 acre can accommodate approximately 90 vehicles in a park and ride lot. This allows approximately 40% of the area for borders, landscaping, passenger amenities, bus facilities for larger lots, and future expansion. (See the AASHTO *Guide for Geometric Design of Transit Facilities on Highways and Streets*, Appendix E, for complementary information.)

The local transit authority can give critical input on the need for and design of the park and ride lot. The comprehensive transit plan may already specify a location, and coordination with the transit agency will ensure the site works well for transit vehicle access. Good coordination with the transit agencies through the entire design process is necessary to ensure a well-planned facility that meets the needs of all modal users.

Develop a list of potential sites to identify properties that can be most readily developed for parking and that have suitable access. Sources for selecting sites can include State Route Corridor Sketches and useful tools such as GIS or existing aerial photos, detailed land use maps, or property maps.

Factors influencing site selection and design of a park and ride facility include:

- Local transit authority master plan
- Regional transportation plan
- Local agency codes
- Ability to use existing underutilized paved parking areas within proximity of the desired location
- Local public input
- Proximity to demand
- Local traffic operations, characteristics, parking availability, and roadway geometry
- Local government zoning

- Social and environmental impacts
- Local land use compatibility with current or future development patterns
- Cost and benefit/cost
- Access by all modes of travel
- Security and lighting impacts
- Maintenance
- Stormwater treatment and outfall
- Available utilities
- Existing right of way or sundry site
- Potential for future expansion

Purchasing or leasing property increases costs. Therefore, the first choice is state- or transit-owned right of way, assuming the other selection criteria are favorable. Also, give prime consideration to the use of city- or county-owned right of way. Select a site that complements the current and future land use and highway needs.

Investigate each potential site in the field. The field survey serves to confirm or revise impressions gained from the office review. When conducting the investigation, consider the following:

- Physical characteristics of the site
- Current use and zoning of the area
- Land use surrounding the property (such as residential or commercial use)
- Street network and condition of the roadways
- Visibility from adjacent streets to enhance security
- Potential for additional expansion
- Ability to meet ADA requirements and accessibility for motorists and other modes of travel, including transit
- Proximity of any existing parking facilities (such as church or shopping center parking lots) that are underutilized during the day
- Potential for joint use of facilities with businesses (such as day care centers or dry cleaners) or land uses compatible with park and ride patrons
- Congestion and other design considerations
- Avoiding locations that encourage noncommuter use (such as proximity to a high school)

The desirable location for park and ride lot along one-way couplets is between the two one-way streets, with access from both streets. When this is not achievable, provide additional signing to guide users to and from the facility.

Establish potential sites, with transit agency input, and complete public meetings and environmental procedures prior to finalizing the design. Follow the procedures outlined in Chapter 210.

1430.04(2) Design Guidance

The remainder of this section covers basic design principles and guidance for park and ride lots. Design features are to be in compliance with local requirements. In some cases, variances to local design requirements may be needed to provide for the safety and security of facility users.

Common design components with park and ride lots include:

- Geometric design of access points
- Selection of a design bus type
- Efficient traffic flows, both internal and external circulation, for transit, carpools, vanpools, pedestrians, and bicycles
- ADA-compliant features
- Parking space layout (including accessible stalls)
- Pavements
- Shelters
- Seating or other street furniture
- Exclusive HOV facilities
- Bicycle facilities
- Motorcycle facilities
- Traffic control devices (including signs, signals, and permanent markings)
- Illumination (within the lot and along the streets)
- Stormwater treatment, drainage, and erosion control
- Security for facility users and vehicles (emergency call boxes or telephones)
- Landscape preservation and development
- Environmental mitigation
- Restroom facilities (for transit drivers only or open to the public)
- Trash receptacles
- Artwork (where required by other agencies)

The degree to which the desirable attributes of any component are sacrificed to obtain the benefits of another component can only be determined on a site-specific basis. However, these guidelines present the optimum design elements of each factor.

Large park and ride lots are intended to be transfer points from private automobiles and other modes to transit buses. The same basic principles are used in designing all park and ride lots.

Park and Ride lots that serve a large number of buses and/or routes may also serve as Transfer/Transit Centers; in these cases section 1430.05 would also apply.

1430.04(2)(a) Access

Provide for all modes of transport used to arrive at and depart from transit facilities. The six basic modes are pedestrian, bicycle, motorcycle, automobile, vanpool, and bus.

Coordinate with the local jurisdiction and transit authorities to develop the park and ride lot's ingress and egress locations for transit and for other vehicles. Design the access route, circulation patterns, and return routes to minimize travel time. Exclusive direct connections for buses, vanpools, and carpools may reduce transit costs and save time for riders.

Design transit facility access points on intersecting collector or local streets where possible. Locate the access to avoid the queues from nearby intersections. Provide vehicle storage lanes for entering and exiting vehicles to ensure ease of access and encourage use of the facility. To avoid increasing congestion on the highway or the community that the facility serves, locate entrances and exits where a traffic signal, or other intersection control type (see Chapter 1300), can be reasonably installed at a later time, if needed.

Entrances and exits to park and rides range in scale from full public intersections to driveways, depending on contextual factors such as traffic volumes and remoteness. Design access points using criteria in the 1300 chapter series (Division 13) or other published design guidelines used by the local agency.

When locating access points on a state highway, see chapters in the 500 series (Division 5) for information about access control types (managed or limited access) and standard access spacing and other requirements.

When designing the entrance/exit locations used by buses, start the design using a 15-foot lane width, and then adjust as needed using the bus design vehicle and turn simulation software (such as AutoTURN®) to verify the design.

1430.04(2)(b) Internal Circulation

Provide walkways to minimize pedestrian use of a circulation road or an aisle to minimize pedestrian conflict points with other modes.

Make the pedestrian circulation path from any parking stall to the loading zone as direct as possible. Where pedestrian movement originates from an outlying part of a large parking lot, consider a walkway that extends toward the loading zone in a straight line.

For additional criteria for pedestrian movement, see *Design Manual* Chapter 1510 and Chapter 630 of the *Roadside Manual*.



Pedestrian Access Route

Locate major vehicular circulation routes within a park and ride lot at the periphery of the parking area to minimize vehicle-pedestrian conflicts. Take care that an internal intersection is not placed too close to a street intersection. Consider a separate loading area with priority parking for vanpools. Wherever possible, do not mix buses and auto circulation.

Close coordination with the local transit authority is critical in the design of internal circulation for buses and vanpools. Design bus circulation routes to provide for easy movement, with efficient terminal operations and convenient passenger transfers. Design bus routes within the internal layout, including entrance and exit driveways, to the turning radius of the design bus vehicle.

Additional considerations for internal circulation are:

- Base the general design for the individual user modes on the priority sequence of: pedestrians, bicycles, feeder buses, and park and ride area.
- Design the different traffic flows (auto, pedestrian, bicycle, and bus) circulating within the lot to be understandable to all users, and to minimize conflicting movements between modes.
- Disperse vehicular movements within the parking area by the strategic location of entrances, exits, and aisles.
- Do not confront drivers with more than one decision at a time.
- Provide clear signing for all modes.
- Make the pedestrian circulation routes ADA-compliant (see Chapter 1510).
- Parking stall and access aisle surfaces shall be even and smooth, with surface slopes not exceeding 2%.
- Consider future expansion.
- Align parking aisles to facilitate convenient pedestrian movement toward the bus loading zone.
- Locate the passenger loading zone either in a central location, to minimize the pedestrian walking distance from the parking area to the loading zone, or near the end of the facility, to minimize the transit travel time.
- In large lots, you may need to provide more than one waiting area for multiple buses.

1430.04(2)(c) Parking Area Design

Refer to the *Roadside Manual* for detailed guidance on parking area design. Some general guidelines follow.

Normally, internal circulation is two way with 90° parking. However, one-way aisles with angled parking may be advantageous in a smaller lot due to the limited available space or to promote a specific circulation pattern.

Provide parking for bicycles, motorcycles, and private automobiles, as well as carpools, vanpools, and buses. Locate accessible parking stalls close to the transit loading and unloading area. Two accessible parking stalls may share a common access aisle. For information on the number and design of accessible stalls, see the *Roadside Manual* and the parking space layouts in the *Standard Plans*. Sign accessible parking stalls in accordance with the requirements of RCW 46.61.581. Parking stalls and access aisle surfaces shall be even and smooth, with surface slopes not exceeding 2%.

Locate the bicycle-parking area relatively close to the transit passenger loading area, separated from motor vehicles by curbing or other physical barriers, without landscaping that hides the bike area from view, and with a direct route from the street.

- Design the bike-parking area to discourage pedestrians from inadvertently walking into the area and tripping. Provide lots that are served by public transit, with lockers or with a rack that will support the bicycle frame and allow at least one wheel to be locked.
- Consider providing shelters for bicycle racks. For bicycles, the layout normally consists of stalls 2.5 feet x 6 feet, at 90° to aisles, with a minimum aisle width of 4 feet. Coordinate decisions to provide bicycle lockers, racks, and shelters with the local transit authority and the region subject matter experts.

For more information, see *Understanding Flexibility in Transportation Design – Washington*. It is complementary to the content in this chapter, and provides more insights to modal designs, environment and aesthetics, community engagement, jurisdictional coordination.

1430.04(2)(d) Drainage

Provide sufficient slope for surface drainage, as ponding of water in a lot is undesirable for both vehicles and pedestrians. This is particularly true in cold climates where freezing may create icy spots. The maximum grade is 2%. Install curb, gutter, and surface drains and grates where needed. Coordinate designs for drainage and pedestrian access routes to avoid conflicts. Coordinate drainage design with the local agency to make sure appropriate codes are followed. For additional drainage information, see *Design Manual* Chapter 800 and the *Roadside Manual*.

1430.04(2)(e) Pavement Design

Design pavement to conform to design specifications for each of the different uses and loadings that a particular portion of a lot or roadway is expected to handle. Bus lanes are typically Portland cement concrete pavement. Within the parking area, HMA-type pavements are typically used. Coordinate the pavement designs with the local transit agency and local jurisdiction. Consult with the Region Materials Engineer on pavement section requirements. There may be benefits to permeable pavement if space for stormwater facilities is limited.

1430.04(2)(f) Driver Guidance

Provide a well thought out design for traffic movements within the lot using the proper pavement markings and signage for safe and efficient use by all users of the lot. Typically, reflectorized markings for centerlines, lane lines, channelizing lines, and lane arrows are needed to guide or separate patron and transit traffic. Install park and ride identification signs. For signing and pavement markings, see Chapters 1020 and 1030 and the MUTCD.

1430.04(2)(g) Shelters

Coordinate with the transit agency on the need, location, design, and installation of pedestrian shelters. To satisfy local needs, shelters may be individually designed, provided by the transit agency, or selected from a variety of commercially available designs. These designs must meet ADA accessibility requirements. Consider the following features in shelter design:

- Select open locations with good visibility for user safety.
- Situate enclosed shelters away from edges of driveways and roadways to keep users dry.
- Select materials and locations where the bus driver can see waiting passengers.
- Avoid using doors, for ease of maintenance and to limit vandalism opportunities.
- Allow for a small air space along the bottom of the enclosure panels, to permit air circulation and reduce debris collection.
- Optional features you may provide are: lighting; heat; telephone; static or electronic travel information (schedules); electronic fare collection equipment; commercial advertisements for revenue generation; and trash receptacles.

For additional information on passenger amenities, see 1430.03.

1430.04(2)(h) Illumination, Safety, and Security

Lighting is important from a safety standpoint and as a deterrent to criminal activity in both the parking area and the shelters. For guidance, see *Design Manual* Chapter 1040, Chapter 630 of the *Roadside Manual*, local agency criteria, and AASHTO.

The *Guide for Geometric Design of Transit Facilities on Highways and Streets*, AASHTO, 2014, states: "Security at stations and major stops—both manned and unmanned—should be achieved by closed circuit television monitoring, provision of call boxes, good visibility and lighting, police surveillance, and effective designs. Both the actual security and the passengers' perceptions of security are important for a viable service or operation." (See the Guide for more information.)

1430.04(2)(i) Planting Areas

Selectively preserve existing vegetation and provide new plantings to afford a balanced environment for the park and ride lot user. For guidance and policy, see the *Roadside Manual* and the *Roadside Policy Manual*, respectively.

1430.04(2)(j) Fencing

For fencing guidelines, see Chapter 560 and discuss with the partnering transit agency.

1430.04(2)(k) Maintenance

Maintenance of park and ride lots outside state right of way is the responsibility of the local transit authority. Negotiate maintenance agreements with local transit authorities or other appropriate parties during the design phase, to identify the requirements and responsibilities for the maintenance. A Cooperative Agreement is written by HQ Real Estate Services for the purpose of assigning maintenance and/or operational responsibilities for a WSDOT park and ride lot to a transit agency or local governmental agency. (See the *Agreements Manual* and the HQ Real Estate Services Cooperative Agreement form.)

Consider the following in the maintenance plan:

- Cost estimate
- Periodic inspection
- Pavement repair
- Traffic control devices (signs and pavement markings)
- Lighting
- Mowing
- Cleaning of drainage structures
- Sweeping/trash pickup
- Landscaping
- Shelters
- Snow and ice control

Understanding Flexibility in Transportation Design – Washington, 2005 provides more information on many of the above topics.

For more information, see *Understanding Flexibility in Transportation Design – Washington*. It is complementary to the content in this chapter, and provides more insights to modal designs, environment and aesthetics, community engagement, jurisdictional coordination.

1430.04(2)(d) Drainage

Provide sufficient slope for surface drainage, as ponding of water in a lot is undesirable for both vehicles and pedestrians. This is particularly true in cold climates where freezing may create icy spots. The maximum grade is 2%. Install curb, gutter, and surface drains and grates where needed. Coordinate designs for drainage and pedestrian access routes to avoid conflicts. Coordinate drainage design with the local agency to make sure appropriate codes are followed. For additional drainage information, see *Design Manual* Chapter 800 and the *Roadside Manual*.

1430.04(2)(e) Pavement Design

Design pavement to conform to design specifications for each of the different uses and loadings that a particular portion of a lot or roadway is expected to handle. Bus lanes are typically Portland cement concrete pavement. Within the parking area, HMA-type pavements are typically used. Coordinate the pavement designs with the local transit agency and local jurisdiction. Consult with the Region Materials Engineer on pavement section requirements. There may be benefits to permeable pavement if space for stormwater facilities is limited.

1430.04(2)(f) Driver Guidance

Provide a well thought out design for traffic movements within the lot using the proper pavement markings and signage for safe and efficient use by all users of the lot. Typically, reflectorized markings for centerlines, lane lines, channelizing lines, and lane arrows are needed to guide or separate patron and transit traffic. Install park and ride identification signs. For signing and pavement markings, see Chapters 1020 and 1030 and the MUTCD.

1430.04(2)(g) Shelters

Coordinate with the transit agency on the need, location, design, and installation of pedestrian shelters. To satisfy local needs, shelters may be individually designed, provided by the transit agency, or selected from a variety of commercially available designs. These designs must meet ADA accessibility requirements. Consider the following features in shelter design:

- Select open locations with good visibility for user safety.
- Situate enclosed shelters away from edges of driveways and roadways to keep users dry.
- Select materials and locations where the bus driver can see waiting passengers.
- Avoid using doors, for ease of maintenance and to limit vandalism opportunities.
- Allow for a small air space along the bottom of the enclosure panels, to permit air circulation and reduce debris collection.
- Optional features you may provide are: lighting; heat; telephone; static or electronic travel information (schedules); electronic fare collection equipment; commercial advertisements for revenue generation; and trash receptacles.

For additional information on passenger amenities, see 1430.03.

1430.04(2)(h) Illumination, Safety, and Security

Lighting is important from a safety standpoint and as a deterrent to criminal activity in both the parking area and the shelters. For guidance, see *Design Manual* Chapter 1040, Chapter 630 of the *Roadside Manual*, local agency criteria, and AASHTO.

The *Guide for Geometric Design of Transit Facilities on Highways and Streets*, AASHTO, 2014, states: "Security at stations and major stops—both manned and unmanned—should be achieved by closed circuit television monitoring, provision of call boxes, good visibility and lighting, police surveillance, and effective designs. Both the actual security and the passengers' perceptions of security are important for a viable service or operation." (See the Guide for more information.)

1430.04(2)(i) Planting Areas

Selectively preserve existing vegetation and provide new plantings to afford a balanced environment for the park and ride lot user. For guidance and policy, see the *Roadside Manual* and the *Roadside Policy Manual*, respectively.

1430.04(2)(j) Fencing

For fencing guidelines, see Chapter 560 and discuss with the partnering transit agency.

1430.04(2)(k) Maintenance

Maintenance of park and ride lots outside state right of way is the responsibility of the local transit authority. Negotiate maintenance agreements with local transit authorities or other appropriate parties during the design phase, to identify the requirements and responsibilities for the maintenance. A Cooperative Agreement is written by HQ Real Estate Services for the purpose of assigning maintenance and/or operational responsibilities for a WSDOT park and ride lot to a transit agency or local governmental agency. (See the *Agreements Manual* and the HQ Real Estate Services Cooperative Agreement form.)

Document the agreements in the Design Documentation Package (see Chapter 300).

Consider the following in the maintenance plan:

- Cost estimate
- Periodic inspection
- Pavement repair
- Traffic control devices (signs and pavement markings)
- Lighting
- Mowing
- Cleaning of drainage structures
- Sweeping/trash pickup
- Landscaping
- Shelters
- Snow and ice control

Understanding Flexibility in Transportation Design – Washington, 2005 provides more information on many of the above topics.

1430.05 Transfer/Transit Centers

Transfer/transit centers are large multimodal bus stops where buses on a number of routes converge to allow riders the opportunity to change buses or transfer to other modes.

Transit centers are frequently major activity centers and serve as destination points.

Many factors dictate the particular needs of each transit center. Design of a transit center considers such features as passenger volume; number of buses on the site at one time; local auto and pedestrian traffic levels; and universal access.

Transit agencies generally lead in the development of transfer/transit centers, and their standards apply. Consult the AASHTO *Guide for Geometric Design of Transit Facilities on Highways and Streets* for more comprehensive overviews and design guidelines for these facilities.

1430.05(1) Bus Platforms

At a transit center where several transit routes converge and where buses congregate (lay over), multiple bus berths or spaces are typically needed, along with areas where passengers boarding or alighting the bus can take refuge. Typically, there are several design styles for multi-berth bus platforms (see AASHTO). Parallel and sawtooth types are described below.

An important aspect in multiple bus berthing is proper signing and marking for the bus bays for both operators and passengers. Clearly delineate the route served by each bay. Consider pavement marking to indicate stopping positions. Separate layover bays may be needed for terminating bus routes, or the layover function can be provided at the passenger platform if the platform only serves a single route. Consider future service plans and maximize flexibility in the design of transit center bays and circulation.

Portland cement concrete pavement is desirable for pedestrian walkways on the platform, for ease of cleaning.

Where buses are equipped with a bicycle rack, provide for the loading and unloading of bicycles.

Exhibit 1430-6 shows typical parallel and sawtooth designs for parking 40-foot buses for passengers boarding and alighting at a platform. The sawtooth design does not require buses to arrive or depart in any order.

Exhibit 1430-7 is an example of a platform design that has a combination of parallel and sawtooth bus berths at a platform. The sawtooth design provides more space-efficient berthing, as the parallel design shown may require that buses arrive and/or depart in order. Coordinate the bus berth style and platform design with the local transit authority throughout the design process, and obtain its concurrence for the final design.

In the design of parallel bus berths, additional roadway width is needed for swing-out maneuvers if shorter bus loading platforms are utilized. The roadway width and the amount of lineal space required at the bus platform are directly related where designs allow departing buses to pull out from the platform around a standing bus. The shorter the berth length allowed, the wider the roadway. Use turn simulation software (such as AutoTURN®) to verify the design.


Considerable length is needed in a parallel design to permit a bus to pass and pull into a platform in front of a parked bus. Design the bus aisle so that a bus can by-pass another bus stopped at the platform. The decision to provide a parallel design to accommodate a by-pass maneuver may depend on how many routes service the location, and the frequency of service.

1430.05(2) Flow/Movement Alternatives


Two primary alternatives for vehicle and passenger movement are possible for transfer centers, regardless of the type of bus berths used, as shown in Exhibit 1430-6. Buses may line up along one side of the transfer center. This type of arrangement is generally suitable for a limited number of buses due to the walking distances for transferring passengers. For a larger number of buses, an arrangement similar to Exhibit 1430-7 can minimize transfer time by consolidating the buses in a smaller area.

Consult the AASHTO *Guide for Geometric Design of Transit Facilities on Highways and Streets* for more comprehensive overviews and design guidelines.

Exhibit 1430-6 Bus Berth Design



Parallel Design




Sawtooth Design[2]

Notes:

[1] Dimensions shown are for a 40-ft bus; adjust the length when designing for a longer bus.

[2] Design shown is an example; contact the local transit agency for additional information.

Exhibit 1430-7 Design Alternative for a Combination of Bus Berths at a Platform



Not to Scale

1430.06 Roadway and Intersection Design

Refer to chapters in the 1100, 1200, and 1300 series (Divisions 11, 12, and 13) for guidance on roadway and intersection design controls and design elements. Some brief discussions are provided below.

1430.06(1) Pavement

Coordinate the pavement design (type and thickness) of a transit project, whether initiated by a public transportation agency or a private entity, with WSDOT or the local agency public works department, depending on highway, street, or road jurisdiction. These agencies play a major role in determining the paving section for the particular project.

Consult with the Region Materials Engineer on pavement section requirements.

1430.06(2) Grades

Roadway grades refer to the maximum desirable slope or grade, or the maximum slope based on the minimum design speed that a 40-foot bus can negotiate efficiently. For roadway grade guidance, see Chapter 1220 or the *Local Agency Guidelines*.

Bus speed on grades is directly related to the weight/horsepower ratio. Select grades that permit uniform operation at an affordable cost. In cases where the roadway is steep, a climbing lane for buses and trucks may be needed. For climbing lane guidance, see Chapter 1270. Avoid abrupt changes in grade due to bus overhangs and ground clearance.

1430.06(3) Lane Widths

Guidance on roadway and lane widths is given in Chapter 1230 or the *Local Agency Guidelines*, based on the context, modal users, needs of the highway or road, and jurisdiction.

1430.06(4) Design Vehicle Characteristics

Most transit agencies operate several types of buses within their systems. Vehicle sizes range from articulated buses to passenger vans operated for specialized transportation purposes and vanpooling. Several bus types are listed below. (See Chapter 1103, Design Controls, and Chapter 1300 for design vehicle guidance.)

1430.06(4)(a) City Buses (CITY-BUS)

These traditional urban transit vehicles are typically 40 feet long and have a wheelbase of approximately 25 feet. Many of these vehicles are equipped with either front or rear door wheelchair lifts or a front “kneeling” feature that reduces the step height for mobility-impaired patrons. Installing higher curb can reduce the time it takes to kneel a bus and thus increase reliability.

1430.06(4)(b) Articulated Buses (A-BUS)

Because articulated buses are hinged between two sections, these vehicles can turn within a relatively short radius. Articulated buses are typically 60 feet in length, with a wheelbase of 22 feet from the front axle to the mid axle and 19 feet from the mid axle to the rear axle. If articulated buses are the common bus using a stop, adjust the length of the pullout accordingly to avoid conflicts.

1430.06(4)(c) Small Buses

Some transit agencies operate small buses, which are designed for use in low-volume situations or for driving on lower-class roads. Small buses are also used for transportation of elderly and disabled persons and for shuttle services. Passenger vans are a type of small bus used for specialized transportation and vanpooling. Since the vehicle specifications vary so widely within this category, consult the local transit authority for the specifications of the particular vehicle in question.

1430.06(5) Intersection Radii

A fundamental characteristic of transit-accessible development is convenient access and circulation for transit vehicles. It is important that radii at intersections be designed to accommodate turning buses. Radii that accommodate turning buses reduce conflicts between automobiles and buses, reduce bus travel time, and provide maximum comfort for the passengers.

Refer to Chapters 1300 and 1310 for intersection design guidance, and take the following factors into consideration in designing intersection radii:

- Right of way availability
- Angle of intersection
- Width and number of lanes on the intersecting streets
- Feasibility of channelization adjustments such as set-back stop bar or adjusted center line
- Design vehicle turning radius
- On-street parking and/or curb extensions (see Chapter 1510)
- Allowable bus encroachment
- Operating speed and speed reductions
- Adequate intersection sight distance
- Needs of pedestrians, bicyclists, and other design users (see chapters in the 1100 series (Division 11) for contextual discussions and Chapter 1230 for roadway types.)

Because of space limitations and generally lower operating speeds in urban areas, curve radii for turning movements are typically smaller than those used in rural areas.

1430.07 Documentation

Refer to Chapter 300 for design documentation requirements.

1430.08 References

1430.08(1) Federal/State Laws and Codes

Americans with Disabilities Act of 1990 (ADA) (28 Code of Federal Regulations [CFR] Part 36, Appendix A, as revised July 1, 1994)

Revised Code of Washington (RCW) 46.61.581, Parking spaces for persons with disabilities – Indication, access – Failure, penalty

RCW 70.92.120, Handicap symbol – Display – Signs showing location of entrance for handicapped

Washington Administrative Code (WAC) Chapter 468-46, Transit vehicle stop zones

WAC 468-510-010, High occupancy vehicles (HOVs)

1430.08(2) Design Guidance

ADA Field Guide for Accessible Public Rights of Way, WSDOT
www.wsdot.wa.gov/publications/manuals/fulltext/m0000/ada_field_guide.pdf

ADA Standards for Accessible Design, U.S. Department of Justice (USDOJ), 2010; consists of 28 CFR parts 35 & 36 and the *ADA and Architectural Barriers Act (ABA) Accessibility Guidelines for Buildings and Facilities* (ADA-ABAAG; also referred to as the 2004 ADAAG), July 23, 2004, U.S.

Access Board. (For buildings and on-site facilities; applies to new construction or alterations as of March 15, 2012.)
www.access-board.gov/guidelines-and-standards

ADA Standards for Transportation Facilities, USDOT, 2006; consists of 49 CFR Parts 37 & 38 and the *ADA and ABA Accessibility Guidelines for Buildings and Facilities* (ADA-ABAAG; also referred to as the 2004 ADAAG), July 23, 2004, U.S. Access Board as modified by USDOT. (For transit, light rail, and similar public transportation facilities.)
www.access-board.gov/guidelines-and-standards

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)

Plans Preparation Manual, M 22-31, WSDOT

Roadside Manual, M 25-30, WSDOT

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT

Traffic Manual, M 51-02, WSDOT

Revised Draft Guidelines for Accessible Public Rights-of-Way (PROWAG), November 23, 2005, U.S. Access Board. The current best practices for evaluation and design of pedestrian facilities in the public right of way per the following FHWA memoranda:
http://www.fhwa.dot.gov/environment/bikeped/prwaa.htm
http://www.fhwa.dot.gov/civilrights/memos/ada_memo_clarificationa.htm
www.access-board.gov/guidelines-and-standards

Transit Capacity and Quality of Service Manual, Third Edition (TCRP Report 165), Transportation Research Board.
http://www.trb.org/Main/Blurbs/169437.aspx

1430.08(3) Supporting Information

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO, current edition

ADA Standards for Accessible Design, U.S. Department of Justice
www.ada.gov/stdspdf.htm

Bus Use of Highways: Planning and Design Guidelines, National Cooperative Highway Research Program Report 155, Transportation Research Board, 1975

Guide for Geometric Design of Transit Facilities on Highways and Streets, AASHTO, 2014
The AASHTO Guide provides a comprehensive reference of current practice in the geometric design of transit facilities on streets and highways.

Guidelines for the Location and Design of Bus Stops, Transit Cooperative Research Program (TCRP) Report 19, Transportation Research Board, 1996

Understanding Flexibility in Transportation Design – Washington, WSDOT, 2005
www.wsdot.wa.gov/research/reports/600/638.1.htm

Chapter 1510 Pedestrian Facilities

1510.01 General
1510.02 References
1510.03 Definitions
1510.04 Policy
1510.05 ADA Requirements by Project Type
1510.06 Pedestrian Circulation Paths
1510.07 Pedestrian Access Routes (PARs)
1510.08 Sidewalks
1510.09 Curb Ramps
1510.10 Crosswalks
1510.11 Raised Medians/Traffic Islands
1510.12 Pedestrian Pushbuttons at Signals
1510.13 At-Grade Railroad Crossings
1510.14 Pedestrian Grade Separations (Structures)
1510.15 Other Pedestrian Facilities
1510.16 Illumination and Signing
1510.17 Work Zone Pedestrian Accommodation
1510.18 Documentation

1510.01 General

Pedestrian travel is a vital transportation mode. It is used at some point by nearly everyone and is a critical link to everyday life for many. Designers must be aware of the various physical needs and abilities of pedestrians in order to ensure facilities provide universal access.

Section 504 of the Rehabilitation Act and the Americans with Disabilities Act of 1990 (ADA) require pedestrian facilities to be designed and constructed so they are readily accessible to and usable by persons with disabilities. This chapter provides accessibility criteria for the design of pedestrian facilities that meet applicable state and federal standards.

The pedestrian facilities included in a project are determined during the planning phase based on: access control of the highway; local transportation plans; comprehensive plans and other plans (such as Walk Route Plans developed by schools and school districts); the roadside environment; pedestrian volumes; user age group(s); and the continuity of local walkways along or across the roadway.

When developing pedestrian facilities within a limited amount of right of way, designers can be faced with multiple challenges. It is important that designers become familiar with the ADA accessibility criteria in order to appropriately balance intersection design with the often competing needs of pedestrians and other roadway users.

Similar to the roadway infrastructure, pedestrian facilities (and elements) require periodic maintenance in order to prolong the life of the facility and provide continued usability. Title II of the ADA requires that all necessary features be accessible and maintained in operable working condition for use by individuals with disabilities.

1510.02 References

1510.02(1) Federal/State Laws and Codes

ADA – 28 Code of Federal Regulations (CFR) Part 35, as revised September 15, 2010

23 CFR Part 652, Pedestrians and Bicycle Accommodations and Projects

49 CFR Part 27, Nondiscrimination on the Basis of Disability in Programs or Activities Receiving Federal Financial Assistance (Section 504 of the Rehabilitation Act of 1973 implementing regulations)

Revised Code of Washington (RCW) 35.68, Sidewalks, gutters, curbs and driveways – All cities and towns

RCW 35.68.075, Curb ramps for persons with disabilities – Required – Standards and Requirements

RCW 46.04.160, Crosswalk (definition)

RCW 46.61, Rules of the Road

RCW 47.24.020, City streets as part of state highways – Jurisdiction, control

1510.02(2) Design Guidance

ADA Standards for Accessible Design, U.S. Department of Justice (USDOJ), 2010; consists of 28 CFR parts 35 & 36 and the *ADA and Architectural Barriers Act (ABA) Accessibility Guidelines for Buildings and Facilities* (ADA-ABAAG; also referred to as the 2004 ADAAG), July 23, 2004, U.S. Access Board as modified by USDOT for entities receiving USDOT funding per 49 CFR Part 27. (Applies to new construction or alterations as of November 29, 2006 for entities receiving USDOT funding per 49 CFR Part 27.) https://www.access-board.gov/guidelines-and-standards/transportation/facilities/ada-standards-for-transportation-facilities

ADA Standards for Transportation Facilities, USDOT, 2006; consists of 49 CFR Parts 37, 38, & 39, the *ADA Accessibility Guidelines for Transportation Vehicles, September 6, 1991*, and the *ADA and ABA Accessibility Guidelines for Buildings and Facilities* (ADA-ABAAG; also referred to as the 2004 ADAAG), July 23, 2004, U.S. Access Board as modified by USDOT. (For transit, light rail, and similar public transportation facilities under Federal Transit Administration jurisdiction.)

https://www.access-board.gov/guidelines-and-standards/transportation/facilities/ada-standards-for-transportation-facilities

https://www.access-board.gov/guidelines-and-standards/transportation/vehicles/adaag-for-transportation-vehicles

Department of Justice/Department of Transportation Joint Technical Assistance on the Title II of the Americans with Disabilities Act Requirements to Provide Curb Ramps when Streets, Roads, or Highways are Altered through Resurfacing, USDOJ and USDOT, July 2013

http://www.ada.gov/doj-fhwa-ta.htm

http://www.ada.gov/doj-fhwa-ta-glossary.htm

https://www.ada.gov/doj-fhwa-ta-supplement-2015.html

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD) www.wsdot.wa.gov/publications/manuals/mutcd.htm

Revised Draft Guidelines for Accessible Public Rights-of-Way (PROWAG), November 23, 2005, U.S. Access Board. The current best practices for evaluation and design of pedestrian facilities in the public right of way per the following FHWA Memoranda:

https://www.fhwa.dot.gov/environment/bicycle_pedestrian/resources/prwaa.cfm

http://www.fhwa.dot.gov/civilrights/memos/ada_memo_clarificationa.htm

https://www.access-board.gov/guidelines-and-standards/streets-sidewalks/public-rights-of-way/background/revised-draft-guidelines

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT www.wsdot.wa.gov/publications/manuals/m21-01.htm

1510.02(3) Supporting Information

1991 ADA Standards for Accessible Design, USDOJ; consists of 28 CFR parts 35 & 36 and the *ADA Accessibility Guidelines for Buildings and Facilities* (ADAAG), July 1991, U.S. Access Board. (For buildings and on-site facilities: Expired for new construction and alterations. To be used only for evaluating the adequacy of new construction or alteration that occurred prior to November 29, 2006 for entities receiving USDOT funding per 49 CFR Part 27.)
https://www.access-board.gov/guidelines-and-standards/buildings-and-sites/about-the-ada-standards/background/adaag

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO, Current version adopted by FHWA

Field Guide for Accessible Public Rights of Way, WSDOT, November 1, 2012
http://www.wsdot.wa.gov/publications/fulltext/roadside/ada_field_guide.pdf

Guide for the Planning, Design, and Operation of Pedestrian Facilities, AASHTO, 2004. Provides guidance on the planning, design, and operation of pedestrian facilities along streets and highways. Specifically, the guide focuses on identifying effective measures for accommodating pedestrians on public rights of way. It can be purchased through the AASHTO website.

Highway Capacity Manual, Transportation Research Board (TRB), 2000

Pedestrian Facilities Guidebook: Incorporating Pedestrians Into Washington's Transportation System, OTAK, 1997 www.wsdot.wa.gov/publications/manuals/fulltext/m0000/pedfacgb.pdf

Pedestrian Facilities Users Guide – Providing Safety and Mobility, FHWA, 2002. Provides useful information regarding walkable environments, pedestrian crashes and their countermeasures, and engineering improvements for pedestrians.
http://drusilla.hsrc.unc.edu/cms/downloads/pedfacility_userguide2002.pdf

Proposed Accessibility Guidelines for Pedestrian Facilities in the Public Right-of-Way, July 26, 2011, U.S. Access Board. Federal Notice of Proposed Rule Making that gives a preview of potential future revisions to the PROWAG. https://www.access-board.gov/guidelines-and-standards/streets-sidewalks/public-rights-of-way/proposed-rights-of-way-guidelines

"Special Report: Accessible Public Rights-of-Way – Planning & Design for Alterations," Public Rights-of-Way Access Advisory Committee, July 2007
www.access-board.gov/prowac/alterations/guide.htm

Understanding Flexibility in Transportation Design – Washington, WSDOT, 2005
www.wsdot.wa.gov/research/reports/600/638.1.htm

Washington State Bicycle Facilities and Pedestrian Walkways Plan
www.wsdot.wa.gov/bike/bike_plan.htm

Terminal Design Manual, Chapter 300 Accessibility, WSDOT, Washington State Ferries Division www.wsdot.wa.gov/publications/manuals/m3082.htm

1510.03 Definitions

Refer to the "ADA / Pedestrian Terms" section of the *Design Manual* Glossary for definitions of many of the terms used in this chapter.

1510.04 Policy

1510.04(1) General

It is WSDOT policy to provide appropriate pedestrian facilities along and across sections of state routes as an integral part of the transportation system. Federal Highway Administration (FHWA) and WSDOT policy is that bicycle and pedestrian facilities be given full consideration in the planning and design of new construction and reconstruction highway projects, except where bicycle and pedestrian use is prohibited.

1510.04(2) Jurisdiction

Proposed projects in public rights of way must address ADA compliance as described in this chapter. (See 1510.05 for ADA requirements by project type.) Regardless of which public agency has jurisdiction within the right of way, the public agency that is sponsoring the project is responsible for ensuring ADA compliance is addressed on its project.

On all state routes outside of incorporated cities and on those with limited access (full, partial, and modified) within incorporated cities, jurisdiction remains with the state unless modified by a maintenance agreement. In turnback areas where the turnback agreement has not been completed, the state maintains full jurisdiction (see Chapters 510, 520, and 530).

When project work occurs on a managed access state route inside an incorporated city that has jurisdiction beyond the curbs (RCW 47.24.020), design pedestrian facilities using the city design standards adopted in accordance with RCW 35.78.030 and the most current ADA requirements. Document the coordination with the city in the Design Documentation Package (DDP). Refer to Chapter 300 for information about the DDP.

1510.04(3) Transition Planning

Section 504 of the Rehabilitation Act and the ADA require all public entities to conduct a self-evaluation of their programs and activities, including sidewalks, curb ramps, and other pedestrian facilities and elements within the public right of way, to determine if barriers exist that prevent people with disabilities from being able to access these programs and activities.

If barriers are identified, agencies with 50 or more employees must develop and implement a transition plan that describes the barriers, the modifications needed, and a schedule for when the needed work will be accomplished.

1510.04(4) Maintenance

As noted in 1510.01, Title II of the ADA requires that a public entity maintain in operable working condition those features of facilities and equipment that are required to be readily accessible to and usable by persons with disabilities.

1510.05 ADA Requirements by Project Type

Wherever pedestrian facilities are intended to be a part of the transportation facility, federal regulations (28 CFR Part 35) require that those pedestrian facilities meet ADA guidelines. All new construction or alteration of existing transportation facilities must be designed and constructed to be accessible to and usable by persons with disabilities. FHWA is one of the federal agencies designated by the Department of Justice to ensure compliance with the ADA for transportation projects.

1510.05(1) New Construction Projects

New construction projects address the construction of a new roadway, interchange, or other transportation facility where none existed before. For these projects, pedestrians' needs are assessed and included in the project. All pedestrian facilities included in these projects must fully meet the accessibility criteria when built.

1510.05(2) Alteration Projects

Any project that affects or could affect the usability of a pedestrian facility is classified as an alteration project. Alteration projects include, but are not limited to, renovation; rehabilitation; reconstruction; historic restoration; resurfacing of circulation paths or vehicular ways; and changes or rearrangement of structural parts or elements of a facility. Where existing elements or spaces are altered, each altered element or space within the limits of the project shall comply with the applicable accessibility requirements to the maximum extent feasible.

The following are some examples of project types that are classified as alteration projects and can potentially trigger a variety of ADA requirements:

- HMA overlay or inlay
- Traffic signal installation or retrofit
- Roadway widening
- Realignment of a roadway (vertical or horizontal)
- Sidewalk improvements
- PCCP panel repair/replacement
- Bridge replacement
- Raised channelization

The following are not considered alterations:

- Spot pavement repair
- Liquid-asphalt sealing, chip seal (BST), or crack sealing
- Lane restriping that does not alter the usability of the shoulder

If there is uncertainty as to whether a project meets the definition of an alteration project, consult with the Regional ADA Coordinator.

The following apply to alteration projects:

- All new pedestrian facilities included in an alteration project that are put in place within an existing developed right of way must meet applicable accessibility requirements to the maximum extent feasible.
- All existing pedestrian facilities disturbed by construction of an alteration project must be replaced. The replacement facilities must meet applicable accessibility requirements to the maximum extent feasible.
- An alteration project shall not decrease or have the effect of decreasing the accessibility of a pedestrian facility or an accessible connection to an adjacent building or site below the ADA accessibility requirements in effect at the time of the alteration.
- Within the construction impact zone of an alteration project, any existing connection from a pedestrian access route to a crosswalk (marked or unmarked) that is missing a required curb ramp must have a curb ramp installed that meets applicable accessibility requirements to the maximum extent feasible. (See 1510.09(2) for curb ramp accessibility criteria.)

- A crosswalk served by a curb ramp must also have an existing curb ramp in place on the receiving end unless there is no curb or sidewalk on that end of the crosswalk (RCW 35.68.075). If there is no existing curb ramp in place on the receiving end, an accessible curb ramp must be provided. This requirement must be met regardless of whether the receiving end of the crosswalk is located within the project's limits.
- Within the construction impact zone of an alteration project, evaluate all existing curb ramps to determine whether curb ramp design elements meet the accessibility criteria. (See 1510.09(2) for curb ramp accessibility criteria.) Modify existing curb ramps that do not meet the accessibility criteria to meet applicable accessibility requirements to the maximum extent feasible. This may also trigger modification of other adjacent pedestrian facilities to incorporate transitional segments in order to ensure specific elements of a curb ramp will meet the accessibility criteria.
- Within the construction impact zone of an alteration project that includes hot mix asphalt overlay (or inlay) of an existing roadway and *does not* include reconstruction, realignment, or widening of the roadway, evaluate all existing marked and unmarked crosswalks. (See 1510.10(2) for crosswalk accessibility criteria.) If it is not possible to meet the applicable accessibility requirements for crosswalks, document this in the DDP.
- Within the construction impact zone of an alteration project that includes reconstruction, realignment, or widening of the roadway, evaluate all existing crosswalks (marked or unmarked) to determine whether crosswalk design elements meet the accessibility criteria. (See 1510.10(2) for crosswalk accessibility criteria.) Modify crosswalk slopes to meet the applicable accessibility requirements to the maximum extent feasible.

It may not always be possible to fully meet the applicable accessibility requirements during alterations of existing facilities. If such a situation is encountered, consult with the Regional ADA Coordinator to develop a workable solution to meet the accessibility requirements to the maximum extent feasible. Cost is not to be used as a justification for not meeting the accessibility criteria. Physical terrain or site conditions that would require structural impacts, environmental impacts, or unacceptable impacts to the community in order to achieve full compliance with the accessibility criteria are some of the factors that can be used to determine that the maximum extent feasible is achieved. If it is determined to be virtually impossible to meet the accessibility criteria for an element, document the decision in one of the following ways, as applicable:

- Within the construction impact zone of an alteration project that does not include reconstruction, realignment, or widening of the roadway, document the following deficient elements in the DDP:
    - Perpendicular curb ramp or parallel curb ramp landing cross slope that is constrained by the existing roadway gutter profile and exceeds 2%, but is less than or equal to 5%, that cannot be constructed to fully meet applicable accessibility requirements.
    - Flared side of a perpendicular curb ramp that is constrained by the existing roadway gutter profile and has a slope that exceeds 10%, but is less than or equal to 16.7%, that cannot be constructed to fully meet applicable accessibility requirements.
- For any deficient element that does not match the preceding description, document the decision via a Maximum Extent Feasible (MEF) document. The MEF document will be reviewed by the appropriate Assistant State Design Engineer (ASDE) and the Headquarters (HQ) ADA Compliance Manager. If acceptable, the MEF document will be approved and included in the DDP.


1510.06 Pedestrian Circulation Paths

Pedestrian circulation paths are prepared exterior or interior ways of passage provided for pedestrian travel. They include independent walkways, sidewalks, shared-use paths, and other types of pedestrian facilities. Pedestrian circulation paths can either be immediately adjacent to streets and highways or separated from them by a buffer. Examples of pedestrian circulation paths are shown in Exhibit 1510-1.

When the pedestrian circulation path is located behind guardrail, address protruding bolts. Installing a rub rail or a "W-beam" guardrail on the pedestrian side of the posts can mitigate potential snagging and also serve as a guide for sight-impaired pedestrians.

Provide a smooth finish to vertical surfaces adjacent to a pedestrian circulation path to mitigate potential snagging or abrasive injuries from accidental contact with the surface. Where adjacent walkway segments diverge, such as can occur if a parallel curb ramp does not occupy the entire width of a pedestrian circulation path, any resulting drop-offs must be protected to prevent trips or falls.

When relocation of utility poles and other fixtures is necessary for a project, determine the impact of their new location on all pedestrian circulation paths. Look for opportunities to relocate obstructions, such as existing utility objects, away from the pedestrian circulation path.



Pedestrian Circulation Paths
Exhibit 1510-1

Highway shoulders are an extension of the roadway and are not typically considered pedestrian facilities. Pedestrians are allowed to use many state highways. Although pedestrians are allowed to travel along the shoulder in these cases, its main purpose is to provide an area for disabled vehicles, a recovery area for errant vehicles, and positive drainage away from the roadway.

Shoulders may serve as a pedestrian facility when sidewalks are not provided. If pedestrian generators, such as bus stops, are present and pedestrian usage is evident, a 4-foot-wide paved shoulder is adequate. Note that detectable warning surfaces should not be installed where a sidewalk ends and pedestrians are routed onto a shoulder since the shoulder is not a vehicular traveled way.

Where pedestrian traffic is evident, consider a separate pedestrian circulation path during the planning and programming of the project. Consult with the State Bicycle and Pedestrian Coordinator.

1510.06(1) Accessibility Criteria for Pedestrian Circulation Paths

The following criteria apply across the entire width of the pedestrian circulation path, not just within the pedestrian access route.

1510.06(1)(a) Vertical Clearance

- The minimum vertical clearance for objects that protrude into or overhang a pedestrian circulation path is 80 inches.
- If the minimum vertical clearance cannot be provided, railings or other barriers shall be provided. The leading bottom edge of the railing or barrier shall be located 27 inches maximum above the finished surface for cane detection.

  Note: Per the MUTCD, the vertical clearance to the bottom of signs is 7 feet (84 inches.)

1510.06(1)(b) Horizontal Encroachment

- Protruding objects on pedestrian circulation paths shall not reduce the clear width of the pedestrian access route to less than 4 feet, exclusive of the curb.

  Note: If an object must protrude farther than 4 inches into a pedestrian circulation path at a height that is greater than 27 inches and less than 80 inches above the finished surface, then it must be equipped with a warning device that is detectable by a vision-impaired person who navigates with a cane. The minimum clear width of the pedestrian access route must still be provided.

1510.06(1)(c) Post-Mounted Objects


- Objects mounted on posts, at a height that is greater than 27 inches and less than 80 inches above the finished surface, shall not protrude more than 4 inches into a pedestrian circulation path.

  Note: If an object must protrude farther than 4 inches into a pedestrian circulation path at a height that is greater than 27 inches and less than 80 inches above the finished surface, then it must be equipped with a warning device that is detectable by a vision-impaired person who navigates with a cane. The minimum clear width of the pedestrian access route must still be provided.


- Where a sign or other obstruction on a pedestrian circulation path is mounted on multiple posts, and the clear distance between the posts is greater than 12 inches, the lowest edge of the sign or obstruction shall be either 27 inches maximum or 80 inches minimum above the finished surface.

1510.07 Pedestrian Access Routes (PARs)

All pedestrian circulation paths (PCPs) are required to contain a continuous pedestrian access route (see Exhibit 1510-2) that connects to all adjacent pedestrian facilities, elements, and spaces that are required to be accessible. Pedestrian access routes consist of one or more of the following pedestrian facilities: walkways/sidewalks, crosswalks, curb ramps (excluding flares), landings, pedestrian overpasses/underpasses, access ramps, elevators, and platform lifts.



With Continuous Buffer



Without Continuous Buffer

Relationship Between Pedestrian Circulation Paths and Pedestrian Access Routes

Exhibit 1510-2

1510.07(1) Accessibility Criteria for Pedestrian Access Routes

1510.07(1)(a) Clear Width

- The minimum continuous and unobstructed clear width of a pedestrian access route shall be 4 feet, exclusive of the width of the curb.
- Pedestrian access routes that are less than 5 feet in clear width, exclusive of the width of the curb, shall provide passing spaces at intervals no farther apart than 200 feet. Passing spaces shall be 5 feet wide minimum, for a minimum distance of 5 feet.



Note: Provide wheel stops or a wider sidewalk to remedy the encroachment into the PAR.

Obstructed Pedestrian Access Route
Exhibit 1510-3

1510.07(1)(b) Cross Slope and Grade

- The cross slope of a pedestrian access route shall be 2% maximum.

  Note: It is recommended that cross slopes be designed to be less than the allowed maximum to allow for some tolerance in construction. For example: design for a maximum 1.5% cross slope (rather than 2% maximum).

  Exceptions:

  1. Midblock crosswalks – The cross slope of the crosswalk and any connected curb ramp is permitted to match street or highway grade.
  2. Crosswalks without stop sign control – The cross slope of the crosswalk can be up to 5% maximum.

- Where a pedestrian access route is contained within the highway right of way, its grade shall not exceed the general grade established for the adjacent roadway.


  Exception: The maximum grade in a crosswalk (marked or unmarked) is 5%, measured parallel to the direction of pedestrian travel in the crosswalk.

- Where a pedestrian access route is not contained within the highway right of way, the maximum running slope allowed is 5% unless designed as an access ramp. (See 1510.15(2) for access ramp accessibility criteria.)
- For additional criteria when a pedestrian access route is supported by a structure, see 1510.14.


1510.07(1)(c) Surface

- The surface of the pedestrian access route shall be firm, stable, and slip resistant. Use hard surfaces like cement or asphalt concrete; crushed gravel is not considered to be a stable, firm surface.
- Vertical alignment shall be planar within curb ramps, landings, and gutter areas within the pedestrian access route and within clear spaces for accessible pedestrian signals, street furniture, and operable parts.
- Grade breaks shall be flush.
- Surface discontinuities (see Exhibits 1510-4 and 1510-5) on existing surfaces in the pedestrian access route (such as at the joints of settled or upheaved sidewalk panels) may not exceed ½ inch maximum. Vertical discontinuities between ¼ inch and ½ inch maximum shall be beveled at 2H:1V or flatter. Apply the bevel across the entire level change.

  Exception: No surface discontinuity is allowed at the connection between an existing curb ramp or landing and the gutter. This grade break must be flush.



Beveling Options
Exhibit 1510-4



Surface Discontinuities (Noncompliant)
Exhibit 1510-5

- Gratings, access covers, utility objects, and other appurtenances shall not be located on curb ramps, landings, or gutters within the pedestrian access route.
- Locate gratings, access covers, utility objects, and other appurtenances outside the pedestrian access route on walkways and sidewalks. Where this is not possible, ensure covers, grates, and lids are designed to be slip resistant and are installed flush with the surrounding surface (see the *Standard Plans*).

1510.07(1)(d) Horizontal Openings

- Any sidewalk joints or gratings that are in the pedestrian access route shall not permit passage of a sphere more than ½ inch in diameter.
- Elongated openings shall be placed so that the long dimension is perpendicular to the dominant direction of travel.
- Openings for wheel flanges at pedestrian crossings of nonfreight rail track shall be 2½ inches maximum (3 inches maximum for freight rail track).
- For additional requirements when a pedestrian access route crosses a railroad, see 1510.13.

1510.08 Sidewalks

Sidewalks are one type of pedestrian circulation path. (See 1510.06 for pedestrian circulation path accessibility criteria.) Plan the design of sidewalks carefully to include a pedestrian access route that provides universal access. (See 1510.07 for pedestrian access route accessibility criteria.) Sidewalk design elements are found in Exhibit 1510-7 and details for raised sidewalks are shown in the *Standard Plans*. Wherever appropriate, make sidewalks continuous and provide access to side streets. The most pleasing and comfortable installation for the pedestrian is a sidewalk separated from the traveled way by a planted buffer. This provides a greater separation between vehicles and pedestrians than curb alone.

1510.08(1) Sidewalk and Buffer Widths

The WSDOT minimum sidewalk width is 5 feet (excluding the curb), but providing wider sidewalks is encouraged. Wider sidewalks are desirable on major arterials, in central business districts, and along parks, schools, and other major pedestrian generators. When sidewalks abut storefronts, additional width should be provided to accommodate window-shoppers and to avoid conflicts with opening doors and pedestrians entering or leaving the buildings.


When a buffer (vegetated as well as alternate pavement) is provided, the buffer should be at least 3 feet wide (excluding the curb). Document the decision to reduce a buffer width to less than 3 feet in the DDP.

If trees or shrubs are included in a buffer, coordinate with the region or HQ Landscape Architect. Take into account Design Clear Zone guidelines (see Chapter 1600). Design subsurface infrastructure (such as structural soils) and select plants whose root systems do not cause sidewalks to buckle or heave. Coordinate buffer planting with maintenance personnel.

Where possible, strive to accommodate snow storage while keeping the pedestrian route free of snow accumulation. Make sure maintenance access is not obstructed. Shoulders, bike lanes, and on-street parking are not considered buffers, but they do offer the advantage of further separation between vehicles and pedestrians.



Sidewalks With Buffers
Exhibit 1510-6



Notes:

If vertical drop is within the Design Clear Zone and the posted speed is > 35 mph, then barrier may be needed (see Chapter 1600).

If vertical drop is ≥ 2 feet 6 inches and barrier is not needed, then railing is indicated.

If vertical drop is < 2 feet 6 inches and barrier is not needed, then a 4-inch curb at back of sidewalk is adequate.

General:

See the *Standard Plans* for details on slopes at back of sidewalk.

See Chapter 1230 for slope selection criteria.

Sidewalks may be sloped away from the roadway for stormwater treatment (see the *Highway Runoff Manual*).

Typical Sidewalk Designs

Exhibit 1510-7

1510.08(2) Sidewalks at Driveways

Provide a pedestrian access route where driveways intersect a pedestrian circulation path (see Exhibit 1510-8). The *Standard Plans* shows details of driveway designs that provide a pedestrian access route. (See 1510.06 and 1510.07 for accessibility criteria.) When a driveway is signalized as part of an intersection, contact the Region ADA Coordinator for guidance.



Typical Driveways
Exhibit 1510-8

1510.09 Curb Ramps

Curb ramps provide an accessible connection from a raised sidewalk down to the roadway surface. A curb ramp, or combination of curb ramps, is required to connect pedestrian access routes to crosswalks (marked or unmarked) where curbs and sidewalks are present, except where pedestrian crossing is prohibited. (See 1510.10(2)(c) for guidance on closed crossings and Exhibit 1510-17 for an example.)

For new construction projects, provide a curb ramp oriented in each direction of pedestrian travel within the width of the crosswalk it serves. For alteration projects, a curb ramp oriented in each direction of pedestrian travel within the width of the crosswalk it serves is desirable.

Every curb ramp must have a curb ramp at the other end of the crosswalk it serves unless there is no curb or sidewalk on that side (RCW 35.68.075).

Curb ramps are also required at midblock crossings where curbs and sidewalks are present.

1510.09(1) Types of Curb Ramps

Different types of curb ramps can be used: perpendicular, parallel, and combination. Carefully analyze and take into consideration drainage patterns, especially when designing a parallel or combination curb ramp installation.

1510.09(1)(a) Perpendicular Curb Ramp

Perpendicular curb ramps (see Exhibits 1510-9 and 1510-10) are aligned to cut through the curb and meet the gutter grade break at a right angle. The landing is to be located at the top of the curb ramp.

1. Advantages


- Having the path of travel aligned to cross the gutter grade break at a right angle facilitates usage by individuals with mobility devices.
- The height of the ramp run relative to the gutter elevation may facilitate drainage.
- The height of the ramp run relative to the gutter elevation discourages vehicular traffic from cutting across the corner.
- On small-radius corners, the ramp alignment may be more closely aligned with the alignment of the crosswalk markings, which facilitates direction finding for the visually impaired.

2. Disadvantages

- The ramp run and landing might not fit within available right of way.
- On small-radius corners, the flares may not fit between closely spaced perpendicular curb ramps.
- On larger-radius corners, there will be less facilitation of direction finding for the visually impaired due to the requirement that the path of travel cross the gutter grade break at a right angle.



Perpendicular Curb Ramp
Exhibit 1510-9



Perpendicular Curb Ramp Common Elements
Exhibit 1510-10

1510.09(1)(b) Parallel Curb Ramp

Parallel curb ramps (see Exhibits 1510-11 and 1510-12) are aligned with their running slope in line with the direction of sidewalk travel, parallel to the curb. The landing is located at the bottom of the curb ramp.

1. Advantages


- Requires minimal right of way.
- Allows ramps to be extended to reduce ramp grade within available right of way.
- Provides edges on the side of the ramp that are detectable to vision-impaired pedestrians who navigate with a cane.

2. Disadvantages

- Depending on the style of parallel curb ramp, pedestrian through traffic on the sidewalk may need to negotiate two ramp grades instead of one, possibly making it more difficult to traverse for some.
- The installation of additional drainage features in the upstream gutter line may be necessary to prevent the accumulation of water or debris in the landing at the bottom of the ramp.



Parallel Curb Ramp
Exhibit 1510-11



Note: The pedestrian curb shown on the back of the curb ramp is intended to retain material in a cut section and is not required if there is no material to retain due to the nature of the roadside topography.

Parallel Curb Ramp Common Elements
Exhibit 1510-12

1510.09(1)(c) Combination Curb Ramp

Combination curb ramps (see Exhibit 1510-13) combine the use of perpendicular and parallel types of curb ramps. Landings may be shared by multiple ramps in this application. Buffer areas and pedestrian curbing that define the pedestrian path of travel are inherent design elements for this type of curb ramp.

1. Advantages

- Allows the elevation difference between the sidewalk and the gutter line to be transitioned with multiple ramps. This can help achieve compliant ramp running slopes.
- Provides additional locations in the gutter line along the radius where drainage structures can be placed outside the pedestrian access route due to the well-defined pedestrian paths of travel.
- Can be constructed within available right of way when the right of way boundary is located at the back of the existing sidewalk, provided sufficient buffer width is available on the roadway side of the sidewalk.
- Provides a way to avoid the relocation of existing features such as utility poles, fire hydrants, and signal poles by incorporating those features into the buffer areas.
- The pedestrian curbing that defines the buffer areas and forms the curb returns for the perpendicular ramp connections facilitates direction finding for a vision-impaired person who navigates with a cane.

2. Disadvantages

- Has a higher construction cost than other curb ramp types due to extensive use of curbing and a larger footprint.
- Due to generally flatter ramp grades and multi-tiered ramp elements, inadequate drainage and accumulation of debris can occur.



Combination Curb Ramps
Exhibit 1510-13

1510.09(2) Accessibility Criteria for Curb Ramps

The accessibility criteria for pedestrian circulation paths and pedestrian access routes (see 1510.06 and 1510.07) also apply to curb ramps unless superseded by the following accessibility criteria specifically for curb ramps.

1510.09(2)(a) Clear Width

- The clear width of curb ramps and their landings shall be 4 feet minimum, excluding flares.

1510.09(2)(b) Running Slope

- The running slope of curb ramps shall not exceed 8.3% maximum.

  Note: It is recommended that running slopes be designed to be less than the allowed maximum to allow for some tolerance in construction. For example, design for a maximum 7.5% curb ramp running slope (rather than the 8.3% maximum).

- The running slope of a perpendicular curb ramp shall intersect the gutter grade break at a right angle at the back of curb.
- The curb ramp maximum running slope shall not require the ramp length to exceed 15 feet.

1510.09(2)(c) Cross Slope

- The cross slope of curb ramp shall not be greater than 2%, measured perpendicular to the direction of travel.

  Note: It is recommended that cross slopes be designed to be less than the allowed maximum to allow for some tolerance in construction. For example, design for a maximum 1.5% cross slope (rather than the 2% maximum).

  Exception: The cross slopes of curb ramps at midblock crossings are permitted to match the street or highway grade.

1510.09(2)(d) Landing

A level landing is required either at the top of a perpendicular ramp or the bottom of a parallel curb ramp, as noted in 1510.09(1)(a) and (b) for the type of curb ramp used.

- Provide a landing that is at least 4 feet minimum length by 4 feet minimum width.
- The running and cross slopes of a curb ramp landing shall be 2% maximum.

  Note: It is recommended that cross slopes be designed to be less than the allowed maximum to allow for some tolerance in construction. For example, design for a maximum 1.5% cross slope (rather than 2% maximum).

  Exception: The running and cross slopes of landings for curb ramps at midblock crossings are permitted to match the street or highway grade.

1510.09(2)(e) Flares

- Flared sides are to be used only where a pedestrian circulation path crosses the curb ramp from the side.
- Flared sides are to have a slope of 10% maximum, measured parallel to the back of curb.

1510.09(2)(f) Counter Slope

- The counter slope of the gutter or street at the foot of a curb ramp or landing shall be 5% maximum.

1510.09(2)(g) Detectable Warning Surfaces

- Detectable warning surfaces are required where curb ramps or landings connect to a roadway. (See the *Standard Plans* for placement details and other applications.)
- Detectable warning surfaces shall contrast visually (either light-on-dark or dark-on-light) with the adjacent walkway surface, gutter, street, or highway.

  Note: Federal yellow is the color used to achieve visual contrast on WSDOT projects. Within cities, other contrasting colors may be used if requested by the city.

1510.09(2)(h) Surfaces

- Surfaces of curb ramps shall be firm, stable, and slip resistant.
- Gratings, access covers, utility objects, and other appurtenances shall not be located on curb ramps, landings, or gutters within the pedestrian access route.

1510.09(2)(i) Grade Breaks

- Vertical alignment shall be planar within curb ramp runs, landings, and gutter areas within the pedestrian access route.
- Grade breaks at the top and bottom of curb ramps shall be perpendicular to the direction of travel on the ramp run.
- Surface slopes that meet at grade breaks shall be flush.


1510.09(2)(j) Clear Space

- Beyond the curb face where the bottom of a curb ramp or landing meets the gutter, a clear space of 4 feet minimum by 4 feet minimum shall be provided in the roadway that is contained within the width of the crosswalk and located wholly outside the parallel vehicle travel lane.

  Note: Clear space is easily achieved when a separate curb ramp is provided, oriented in each direction of pedestrian travel within the width of the crosswalk it serves.

1510.09(3) Curb Ramp Drainage

Surface water runoff from the roadway can flood the lower end of a curb ramp. Provide catch basins or inlets to prevent ponding at the base of curb ramps and landings. Exhibit 1510-14 shows examples of drainage structure locations. Verify that drainage structures will not be located in the pedestrian access route.



Typical Curb Ramp Drainage
Exhibit 1510-14

1510.10 Crosswalks

1510.10(1) Designing Crossing Facilities

Evaluate the following for crossing facilities to address the needs of all user modes:

- Minimize turning radii to keep speeds low. (See Chapter 1300 for design vehicle guidance.)
- Place crosswalks so they are visible and connect to the adjacent pedestrian facilities.
- Provide sight distance (driver to pedestrian; pedestrian to driver).
- Use a separate left-turn phase along with a “WALK/DON’T WALK” signal.
- Restrict or prohibit turns.
- Shorten crossing distance.
- Use a raised median/cut-through island for a pedestrian refuge.
- Use accessible pedestrian signals (APS).
- Use signing and delineation as determined by the region Traffic Engineer.
- Place crosswalks as close as practicable to the intersection traveled way.
- Provide pedestrian-level lighting.
- Consider the crosswalk location in relation to transit stops.
- Provide a PAR that meets the accessibility criteria at all pedestrian crossings.

1510.10(2) Crosswalks at Intersections


Provide a pedestrian access route within marked and unmarked pedestrian crossings. (See 1510.07 for accessibility criteria for pedestrian access routes.)

Crosswalks are provided on all legs of an intersection, except in rare cases. There are normally three crosswalks at a "T" intersection and four crosswalks at a "four-leg" intersection. For pedestrian route continuity, the minimum number of crosswalks is two at "T" intersections and three at "four-leg" intersections. One example where crosswalks might not be provided on all interaction legs is a diamond interchange with heavy left-turn movements from the off-ramp approach. (See 1510.10(2)(c) for Closed Crossings policy.)

The *Traffic Manual* provides recommendations for determining pedestrian markings based on lane configuration, vehicular traffic volume, and speed. However, coordinate with the region Traffic Engineer early on with any existing or proposed crosswalks. The Traffic Engineer makes the final determination on appropriate signing and delineation.

1510.10(2)(a) Unmarked Crossings

Legal crosswalks exist at all intersections, whether marked or not, regardless of the number of legs at the intersection. An unmarked crosswalk (see Exhibit 1510-15) is the portion of the roadway behind a prolongation of the curb or edge of the through traffic lane and a prolongation of the farthest sidewalk connection or, in the event there are no sidewalks, between the edge of the through traffic lane and a line 10 feet from there (RCW 46.04.160).




Unmarked Crosswalks
Exhibit 1510-15

1510.10(2)(b) Marked Crossings

Marked crosswalks are used at intersections or midblock crossings. They are not to be used indiscriminately. Maintenance agreements and RCW 47.24.020(30) provide jurisdictional authority for decisions to mark crosswalks based on a population threshold of 25,000 and should be consulted prior to a decision to mark a crosswalk. Consult region Traffic Offices for "best practices" for marking crosswalks based on intersection type. The MUTCD is a good resource to use when evaluating locations for marking consideration.

The desirable width for a marked crosswalk is 10 feet (6 feet minimum, with justification). The preferred type of marked crosswalk is a longitudinal pattern known as a Ladder Bar, which is shown in the *Standard Plans* and Exhibit 1510-16. Stop and yield line dimensions and placement must conform to the MUTCD and are shown in the *Standard Plans*.

Some decorative crosswalk materials (such as colored pavement or bricks) may cause confusion for visually impaired pedestrians and can create discomfort for wheelchair users. Supplement decorative crosswalks with pavement markings to enhance visibility and delineate the crosswalk. Refer to the MUTCD and the Local Agency Crosswalk Options website:
www.wsdot.wa.gov/design/standards/plansheet/pm-2.htm



Marked Pedestrian Crossing
Exhibit 1510-16

1510.10(2)(c) Closed Crossings

Pedestrian crossings shall only be closed for documented potential or observed crash concerns or for essential signal operations. If a crossing has been previously closed as indicated by existing signing and ADA facilities are being evaluated, provide an appropriate treatment that is detectable by people with vision difficulties who navigate with a cane, such as directional pedestrian curbing and removal of ramps at these closed crossing. The region Traffic Engineer is the approval authority for the closing of crossings.

Vacant

Exhibit 1510-17

1510.10(3) Midblock Crosswalks

On roadways with pedestrian crossing traffic caused by nearby pedestrian generators, a midblock crossing may be appropriate. (See 1510.10(2) for crosswalk criteria and the *Traffic Manual* for marked crosswalk recommendations at unsignalized intersections.) The approval authority is the Traffic Engineer.

Engineering judgment of conditions that might increase the value of a midblock crossing includes the following:

- High pedestrian crossing volume present with long block spacing.
- Evidence of pedestrian-vehicular midblock conflicts (site observations, law enforcement reporting, and city traffic engineers).
- Proposed crossing with a realistic opportunity to channel multiple pedestrian crossings to a single location.
- Sight lines that enable sufficient eye contact between motorists and pedestrians.
- Community commitment for a successful outcome.
- Ability to mitigate risks associated with the location using proven countermeasures such as, but not limited to, refuge islands, rectangular rapid flashing beacons, and/or pedestrian hybrid beacons.
- Modal interchange points where high volumes crossing pedestrians occur (e.g., transit stop to apartment complex).


To meet the accessibility criteria, the pedestrian access route in the crosswalk may have a cross slope that matches the grade of the roadway. An example of a midblock crossing is shown in Exhibit 1510-18. (See Chapter 530 for further information on pedestrian access and paths on limited access facilities.)



Midblock Pedestrian Crossing
Exhibit 1510-18

1510.10(4) Sight Distance at Crosswalks

When locating crosswalks at intersections, it is important to evaluate the sight lines between pedestrians and motorists. Shrubbery, signs, parked cars, and other roadside elements can block motorists' and pedestrians' views of one another. Exhibit 1510-19 illustrates these sight distance concerns.




Obstructed Line of Sight at Intersection
Exhibit 1510-19

1510.10(5) Curb Extensions

Curb extensions are traffic calming measures that may improve sight distance and reduce pedestrian crossing times, which limits pedestrian exposure. Installing a curb extension can help reduce the sight distance problem with parked cars that limit driver/pedestrian visibility. Curb extensions may allow for better curb ramp design as well as provide more space for pedestrians. ***Note:*** Curb extensions are not an option on streets with high-speed traffic or without on-street parking because drivers would be confronted with sudden changes in roadway width.

Extend the curb no farther than the width of the parking lane. (See Chapters 1230, and 1520 for shoulder/bike lane width guidance.) Design the approach nose to ensure adequate setback of vehicles to provide visibility of pedestrians. At intersections with traffic signals, the curb extensions can be used to reduce pedestrian signal timing. Examples of sidewalk curb extensions are shown in Exhibits 1510-20 and 1510-21.



Improved Line of Sight at Intersection
Exhibit 1510-20



Curb Extension Examples
Exhibit 1510-21

The right-turn path of the design vehicle is a critical element in determining the size and shape of the curb extension. Sidewalk curb extensions tend to restrict the width of the roadway and can make right turns difficult for large trucks. Ensure the geometry of the curb extension is compatible with the turn path for the design vehicle selected.

Avoid interrupting bicycle traffic with curb extensions.

Do not use curb extensions on state highways when:

- The design vehicle (see Chapter 1300) encroaches on curbs or opposing lanes, and other solutions will not improve the circumstances.
- On-street parking is not provided/allowed.
- The posted speed is above 35 mph.

Site features such as landscaping, cabinets, poles, benches, planters, bollards, newspaper stands, and sandwich boards should be selected and placed so they do not obstruct the vision of pedestrians or drivers within curb extension areas, as shown in Exhibit 1510-21. Take into account motorist and pedestrian visibility and Design Clear Zone guidelines (see Chapter 1600).

1510.11 Raised Medians/Traffic Islands

Wide multilane streets are often difficult for pedestrians to cross, particularly when there are insufficient gaps in vehicular traffic because of heavy volumes. Consider raised medians and traffic islands with a pedestrian refuge area (see Exhibit 1510-22) on roadways with the following conditions:

- Two-way arterial with intermediate to high speeds (greater than 35 mph), moderate to high average daily traffic (ADT), and high pedestrian volumes.
- Significant pedestrian crash history.
- Near a school or other community center.
- Crossing distance exceeds 30 feet.
- Complex or irregularly shaped intersections.

A traffic island used for channelized right-turn slip lanes can provide a pedestrian refuge, but the slip lane may promote faster turning speeds. Minimize the turning radius of the slip lane to keep speeds as low as feasible. To reduce conflicts, keep the slip lane as narrow as practicable and design a crosswalk alignment that is at a right angle to the face of curb. (See Chapters 1310 for turn lanes, 1360 for interchange ramps, and 1320 for pedestrian accommodations in roundabouts.)

The pedestrian access route through a raised median or traffic island can be either raised with curb ramps or a cut-through type (see Exhibit 1510-22). Curb ramps in medians and islands can add difficulty to the crossing for some users. The curbed edges of cut-throughs can be useful cues to the visually impaired in determining the direction of a crossing, especially on an angled route through a median or island.

1510.11(1) Accessibility Criteria for Raised Medians and Traffic Islands

There are many design considerations when deciding whether to ramp up to the median or island grade or create a cut-through median or island matching the roadway grade. These considerations may include the profile grade and cross slope of the road, drainage patterns, and the length or width of the median or island.


The following accessibility criteria apply:

- Each raised median or traffic island shall contain a pedestrian access route connecting to each crosswalk (see 1510.07).
- A passing space shall be provided that is at least 5 feet wide for a distance of at least 5 feet for each pedestrian access route in a raised median or on a traffic island (see Exhibit 1510-22).


  Note: It is recommended that cut-throughs be designed to have a minimum width of 5 feet to ensure a passing space is provided.
- Medians and pedestrian refuge islands shall be 6 feet minimum in length in the direction of pedestrian travel.
- Detectable warning surfaces are to be separated by 2 feet minimum length in the direction of pedestrian travel.
- Detectable warning surfaces are located at each curb ramp or roadway entrance of a pedestrian access route through a raised median or traffic island. The detectable warning surface shall be located at the back of the curb (see Exhibit 1510-22).
- Pedestrian access routes of shared-use paths that go through raised medians or traffic islands shall be the same width as the shared-use path (see Chapter 1515).




Island Cut-Through



Island Cut-Through



Raised Traffic Island With Curb Ramps



Median Island Cut-Through (full width shown)

(See 1510.11(1) for minimum accessibility criteria.)

See the *Standard Plans* for details.

Raised Islands With Curb Ramps and Pedestrian Cut-Throughs

Exhibit 1510-22

1510.12 Pedestrian Pushbuttons at Signals

When designing pedestrian signals, consider the needs of all pedestrians, including older pedestrians and pedestrians with disabilities who might walk at a significantly slower pace than the average pedestrian. Determine whether there are pedestrian generators in the project vicinity that might attract older people and pedestrians with disabilities, and adjust signal timing accordingly. When pedestrian signals are newly installed, replaced, or significantly modified, include accessible pedestrian signal (APS) pushbuttons and countdown pedestrian displays as described in 1510.12(2).



Typical Pedestrian Pushbutton
Exhibit 1510-23


1510.12(1) Accessibility Criteria for All Pedestrian Pushbuttons (including APS)

1510.12(1)(a) Location Requirements

- Not greater than 5 feet from the crosswalk line (extended) that is farthest from the center of the intersection.
- Between 1½ feet and 10 feet from the edge of the curb, shoulder, or pavement.
- Mounting height: 42 inches desirable, 48 inches maximum, 15 inches minimum.

1510.12(1)(b) Clear Space Requirements

- Grade: 2% maximum running and cross slopes.
- Clear space dimensions: 30 inches minimum width by 48 inches minimum length (see Exhibit 1510-24). [Note: These are minimum ADA dimensions. See Chapter 1330 for updated WSDOT policy regarding these dimensions.]
- Clear space is allowed to overlap other PAR elements (i.e., sidewalk/curb ramp landing).
- Clear space must be connected to the crosswalk served by the pedestrian pushbutton with a PAR.
- Additional maneuvering space may be required if the clear space is constrained on three sides (see PROWAG).



Note: A desirable clear space accommodates the full spectrum of wheeled mobility device users approaching the pedestrian pushbutton from multiple directions. Consider providing 36 inches width and up to 84 inches length designed for a parallel approach with the pedestrian pushbutton centered within the length.

Clear Space Parallel and Forward Approach Orientation
Exhibit 1510-24

1510.12(1)(c) Reach Range Requirements

[Minimum ADA criteria. See Chapter 1330 for updated WSDOT policy.]

- The provided clear space must be within reach range of the pedestrian pushbutton.
- For a parallel approach pedestrian pushbutton that has a mounting height greater than 46 inches and not more than 48 inches, the reach range is 10 inches maximum.
- For a parallel approach pedestrian pushbutton that has a mounting height 46 inches or less, the reach range is 24 inches maximum; however, design for 10 inches or less reach range whenever possible.
- For a forward approach pedestrian pushbutton, the reach range is 0 (zero) inches maximum regardless of mounting height. The pushbutton must either be placed at the very edge of the clear space or extend into the clear space while providing knee and toe clearance for a wheeled mobility device user (see PROWAG).

Note: Due to the challenges associated with providing reach range, it is desirable to design clear space for a parallel approach whenever possible.

1510.12(2) Accessible Pedestrian Signals (APS)

At all locations where pedestrian signals are newly installed, replaced, or significantly modified, the installation of accessible pedestrian signals and countdown pedestrian displays is required. ***Note:*** Simply moving existing pedestrian pushbuttons to satellite poles to improve accessibility is not by itself considered a significant modification of the pedestrian signal.

When APS and countdown pedestrian display improvements are made, they shall be made for all locations associated with the system being improved. APS includes audible and vibrotactile indications of the WALK interval. Installation of these devices may require improvements to existing sidewalks and curb ramps to ensure ADA compliance.



Accessible Pedestrian Signal Pushbutton Stations
Exhibit 1510-25

1510.12(3) Accessibility Criteria for Accessible Pedestrian Signals (APS)

In addition to the general pedestrian pushbutton accessibility criteria described in 1510.12(1), the following criteria apply to APS installations:

- APS pushbuttons shall have a locator tone that operates during the DON'T WALK and the flashing DON'T WALK intervals only.
- APS pushbuttons must have both audible and vibrotactile indications of the WALK interval.
- APS pushbutton controls and signs shall be installed facing the intersection and be parallel to the crosswalk served.
- An APS pushbutton shall have a tactile arrow that indicates the crossing direction activated by the pushbutton.
- An APS pushbutton provides high contrast (light-on-dark or dark-on-light) against its background.
- If extended pushbutton press features are available, the APS pushbutton shall be marked with three braille dots forming an equilateral triangle in the center of the pushbutton.
- If additional crossing time is provided by an extended pushbutton press feature, then an R10-32P (MUTCD) plaque shall be mounted adjacent to or integral with the APS pushbutton.
- If the pedestrian clearance time is sufficient only to cross from the curb or shoulder to a median to wait for the next cycle, then an additional APS pushbutton shall be provided in the median.
- The desirable spacing between the APS pushbuttons is 10 feet minimum (5 feet minimum spacing on medians and islands), if feasible.
- If the spacing between the APS pushbuttons is 10 feet or greater, the audible WALK indication shall be a percussive tone.
- If the spacing between the APS pushbuttons is less than 10 feet, the audible WALK indication shall be a speech walk message, and a speech pushbutton information message shall be provided.

Refer to the MUTCD for further design guidance. Also, consult with HQ Traffic Operations and either region or city maintenance personnel (as appropriate) for current equipment specifications and additional maintenance requirements.

1510.13 At-Grade Railroad Crossings

The design of pedestrian facilities that cross railroad tracks (see Exhibit 1510-26) often presents challenges due to the conflicting needs of pedestrians and trains. In particular, the flangeway gap for trains to traverse a crossing surface may create a significant obstacle for a person who uses a wheelchair, crutches, or walking aids for mobility. Whenever practicable, align pedestrian crossings perpendicular to the tracks in order to minimize potential problems related to flangeway gaps. Crossing surfaces may be constructed of timber planking, rubberized materials, or concrete. Concrete materials generally provide the smoothest and most durable crossing surfaces. When detectable warning surfaces are used at railroad crossings, place them according to the MUTCD stop line placement criteria.



Undesirable Recommended

Pedestrian Railroad Crossings
Exhibit 1510-26

There are a number of railroad crossing warning devices (see Exhibit 1510-27) intended specifically for pedestrian facilities (see the MUTCD). When selecting warning devices, factors such as train and pedestrian volumes, train speeds, available sight distance, number of tracks, and other site-specific characteristics should be taken into account. Coordinate with the HQ Design Office Railroad Liaison early in the design process so that all relevant factors are considered and an agreement may be reached regarding the design of warning devices and crossing surfaces.



Pedestrian Railroad Warning Device
Exhibit 1510-27

Except for crossings located within the limits of first-class cities,* the Washington Utilities and Transportation Commission (WUTC) approves proposals for any new railroad at-grade crossings or changes to warning devices or geometry at existing crossings. Additionally, any project that requires the railroad to perform work such as installation of warning devices or crossing surfaces must obtain a railroad construction and maintenance agreement. Contact the HQ Design Office Railroad Liaison to coordinate with both the WUTC and the railroad company.

*RCW 35.22.010: A first class city is a city with a population of ten thousand or more at the time of its organization or reorganization that has a charter adopted under Article XI, section 10, of the state Constitution.

Note: There are very few first-class cities in the state of Washington. Verify with the HQ Design Office Railroad Liaison.

1510.14 Pedestrian Grade Separations (Structures)

On the approach to a bridge that has a raised sidewalk, provide a ramp that transitions to the sidewalk from the paved shoulder. A ramp that transitions from a paved shoulder to a sidewalk on a bridge is to have a slope of 5% maximum and be constructed of asphalt or cement concrete. In addition to aiding pedestrian access, the ramp also serves as a roadside safety feature to mitigate the raised blunt end of the concrete sidewalk. If a pedestrian circulation path (such as a raised sidewalk or shared-use path) is located near the bridge, consider eliminating the gap between the bridge sidewalk and the pedestrian circulation path by extending the bridge sidewalk to match into the nearby pedestrian circulation path.

At underpasses where pedestrians are allowed, it is desirable to provide sidewalks and to maintain the full shoulder width. When bridge columns are placed on either side of the roadway, it is preferred to place the walkway between the roadway and the columns for pedestrian visibility and security. Provide adequate illumination and drainage for pedestrian safety and comfort.

In cases where there is a pedestrian crash history, and the roadway cannot be redesigned to accommodate pedestrians at grade, planners should consider providing a grade-separated pedestrian structure (see Exhibits 1510-28 and 1510-29). When considering a grade-separated pedestrian structure, determine whether the conditions that require the crossing are permanent. If there is likelihood that pedestrians will not use a grade separation, consider less-costly solutions.

Locate the grade-separated crossing where pedestrians are most likely to cross the roadway. A crossing might not be used if the pedestrian is required to deviate significantly from a more direct route.

It is sometimes necessary to install fencing or other physical barriers to channel the pedestrians to the structure and reduce the possibility of undesired at-grade crossings. ***Note:*** The HQ Bridge and Structures Office is responsible for the design of pedestrian structures.

Consider a grade-separated crossing where:

- There is moderate to high pedestrian demand to cross a freeway or expressway.
- There are large numbers of young children, particularly on school routes, who regularly cross high-speed or high-volume roadways.
- The traffic conflicts that would be encountered by pedestrians are considered unacceptable (such as on wide streets with high pedestrian volumes combined with high-speed traffic).
- There are documented crashes or close calls involving pedestrians and vehicles.

- One or more of the conditions stated above exists in conjunction with a well-defined pedestrian origin and destination (such as a residential neighborhood across a busy street from a school).

1510.14(1) Pedestrian Bridges

Pedestrian grade-separation bridges (see Exhibit 1510-28) are more effective when the roadway is below the natural ground line, as in a cut section. Elevated grade separations in cut sections, where pedestrians climb stairs or use long approach ramps, tend to be underused. Pedestrian bridges need adequate right of way to accommodate accessible ramp approaches leading up to and off of the structure. The bridge structure must comply with ADA requirements and meet the accessibility criteria for either a pedestrian circulation path (if the grade is 5% or less) or an access ramp (if the grade is greater than 5% but less than or equal to 8.3%), and must include a pedestrian access route. (See 1510.06 and 1510.07 for pedestrian circulation path and pedestrian access route accessibility criteria; see 1510.15(2) for access ramp accessibility criteria.)

For the minimum vertical clearance from the bottom of the pedestrian structure to the roadway beneath, see Chapter 720. The height of the structure can affect the length of the pedestrian ramp approaches to the structure. When access ramps are not feasible, provide both elevators and stairways.

Provide railings on pedestrian bridges. Protective screening is sometimes desirable to deter pedestrians from throwing objects from an overhead pedestrian structure (see Chapter 720).

The minimum clear width for pedestrian bridges is 8 feet. Consider a clear width of 14 feet where a pedestrian bridge is enclosed or shared with bicyclists, or equestrians, or if maintenance or emergency vehicles will need to access.



Pedestrian Bridges
Exhibit 1510-28

1510.14(2) Pedestrian Tunnels

Tunnels are an effective method of providing crossings for roadways located in embankment sections. Well-designed tunnels can be a desirable crossing for pedestrians. When feasible, design the tunnel with a nearly level profile to provide an unobstructed line of sight from portal to portal (see Exhibit 1510-29). People may be reluctant to enter a tunnel with a depressed profile because they are unable to see whether the tunnel is occupied. Law enforcement also has difficulty patrolling depressed profile tunnels.

Provide vandal-resistant daytime and nighttime illumination within the pedestrian tunnel. Installing gloss-finished tile walls and ceilings can enhance light levels within the tunnel. The minimum overhead clearance for a pedestrian tunnel is 10 feet. The minimum width for a pedestrian tunnel is 12 feet. Consider a tunnel width between 14 and 18 feet depending on usage and the length of the tunnel.



Pedestrian Tunnel
Exhibit 1510-29

Pedestrian tunnels need adequate right of way to accommodate accessible approaches leading to the tunnel structure. The tunnel structure must comply with ADA requirements and meet the accessibility criteria for either a pedestrian circulation path (if the grade is less than or equal to 5%) or an access ramp (if the grade is greater than 5% and less than or equal to 8.3%), and must include a pedestrian access route. (See 1510.06 and 1510.07 for pedestrian circulation path and pedestrian access route accessibility criteria; see 1510.15(2) for access ramp accessibility criteria.)

1510.15 Other Pedestrian Facilities

1510.15(1) Transit Stops and School Bus Stops

The location of transit stops is an important element in providing appropriate pedestrian facilities. (Coordinate with the local transit provider.) Newly constructed transit stops must conform to ADA requirements. Design newly constructed transit stops so that they are accessible from the sidewalk or paved shoulder. A transit stop on one side of a street usually has a counterpart on the opposite side because transit routes normally function in both directions on the same roadway. Provide adequate crossing facilities for pedestrians.

When locating a transit stop (see *Traffic Manual* 7.9), consider transit ridership and land use demand for the stop. Also, take into account compatibility with the following roadway/traffic characteristics:

- ADT
- Traffic speed
- Crossing distance
- Crash history
- Sight distance
- Connectivity to a pedestrian access route
- Traffic generator density

If any of these suggests an undesirable location for a pedestrian crossing, consider a controlled crossing or another location for the transit stop. (See Chapter 530 for further information on bus stops on limited access facilities.)

When analyzing a transit stop location with high pedestrian crash frequency, take into account the presence of nearby transit stops and opportunities for pedestrians to cross the street in a reasonably safe manner. At-grade midblock pedestrian crossings may be effective at transit stop locations on roadways with lower vehicular volumes. Pedestrian grade separations are appropriate at midblock locations when vehicular traffic volumes prohibit pedestrian crossings at grade. (See the *Traffic Manual* for recommendations for marked crosswalks at unsignalized intersections.)

School bus stops are typically adjacent to sidewalks in urban areas and along shoulders in rural areas. Determine the number of children using the stop and provide a waiting area that allows the children to wait for the bus. Coordinate with the local school district. Because of their smaller size, children might be difficult for motorists to see at crossings or stops. Determine whether utility poles, vegetation, and other roadside features interfere with motorists' ability to see the children. When necessary, remove or relocate the obstructions or move the bus stop. Parked vehicles can also block visibility, and parking prohibitions might be advisable near the bus stop. Coordinate transit and school bus stop locations with the region Traffic Office.

1510.15(2) Access Ramps Serving Transit Stops, Park & Ride Lots, Rest Areas, Buildings, and Other Facilities

An access ramp (see Exhibit 1510-30) provides an accessible pedestrian route from a pedestrian circulation path to a facility such as a transit stop, park & ride lot, rest area, pedestrian overcrossing/undercrossing structure, or building. When the running slope is 5% or less, it can be designed as a pedestrian circulation path that includes a pedestrian access route. When the running slope is greater than 5% to a maximum of 8.3%, it must be designed as an access ramp. (See 1510.06 and 1510.07 for pedestrian circulation path and pedestrian access route accessibility criteria; see 1510.15(2)(a) for access ramp accessibility criteria.)

1510.15(2)(a) Accessibility Criteria for Access Ramps

Access ramps are composed of one or more ramp segments interconnected by level landings. Unless superseded by the following specific accessibility requirements for access ramps, the accessibility requirements for pedestrian access routes also apply:

- Ramp segments shall have a maximum running slope of 8.3%.
- The cross slope of ramp segments shall be 2% maximum.
- The minimum clear width of ramps is 4 feet; however, it is desirable to match the width of the connecting pedestrian facility.
- The rise for any ramp segment shall be 30 inches maximum.
- A level landing (2% maximum running and cross slopes) shall be provided at the top and bottom of each access ramp segment.
- An access ramp landing's clear width shall be at least as wide as the widest ramp segment leading to the landing.
- An access ramp landing's length shall be 5 feet minimum.
- Access ramps that change direction between ramp segments at landings shall have a level landing 5 feet minimum width by 5 feet minimum length.
- All access ramp segments with a rise greater than 6 inches shall have ADA-compliant handrails (see 1510.15(3) for handrail accessibility criteria).

Provide edge protection complying with one of the two following options on each side of access ramp segments:

- The surface of the ramp segment and landing shall extend 12 inches minimum beyond the inside face of the handrail.
- A curb or barrier shall be provided that does not allow the passage of a 4-inch-diameter sphere, where any portion of the sphere is within 4 inches of the ramp/landing surface.



Access Ramp With Accessible Handrails
Exhibit 1510-30

1510.15(3) Railings and Handrails for Pedestrian Facilities

Accessible handrails are required on stairs and also on access ramps that have a rise greater than 6 inches (see 1510.15(2)(a) for access ramp accessibility criteria). If the height of a drop-off (typically greater than 30 inches) adjacent to a pedestrian facility necessitates the need to protect pedestrians from falls, then a more robust railing system designed for fall protection should be used. If the drop-off is adjacent to either a stairway or an access ramp with a rise greater than 6 inches, then a combined railing system that meets the requirements for both accessibility and fall protection must be used.

1510.15(3)(a) Fall Protection Railing

Railing designed for fall protection alone is typically placed adjacent to pedestrian facilities other than stairs or access ramps to prevent pedestrians or bicyclists from falls. The minimum railing height for pedestrian fall protection is 42 inches. For facilities where bicycle traffic is anticipated, such as on a grade-separation structure on a shared-use facility (see Chapter 1515), the minimum railing height for bicyclist fall protection is 54 inches.

1510.15(3)(b) Accessible Fall Protection Railing

When fall protection is needed adjacent to stairs or an access ramp that has a rise greater than 6 inches, then a combined railing system that meets both the accessibility criteria for handrail outlined in 1510.15(3)(d) and the requirements for fall protection must be used. The minimum railing height for pedestrian fall protection is 42 inches. For facilities where bicycle traffic is anticipated, such as on the approach to a grade-separation structure on a shared-use facility (see Chapter 1515), the minimum railing height for bicyclist fall protection is 54 inches.

1510.15(3)(c) Accessible Handrail

Accessible handrail meeting the accessibility criteria listed in 1510.15(3)(d) that is not designed to provide fall protection is to be used adjacent to stairs or access ramps that have a rise greater than 6 inches at locations where robust fall protection is not needed.

1510.15(3)(d) Accessibility Criteria for Handrail

The following accessibility criteria apply to all handrail installations provided at stairs and access ramps that have a rise greater than 6 inches.

1. Height

- The top of handrail gripping surfaces shall be 34 inches minimum and 38 inches maximum vertically above walking surfaces, stair nosings, and ramp surfaces.
- The mounting height of the handrail shall also be at a consistent height.

2. Gripping Surface

- Clearance between handrail gripping surfaces and adjacent surfaces shall be 1½ inches minimum.
- Handrail gripping surfaces shall be continuous along their length and shall not be obstructed along their tops or sides.
- The bottoms of handrail gripping surfaces shall not be obstructed for more than 20% of their length.
- Where provided, horizontal projections shall be located 1½ inches minimum below the bottom of the handrail gripping surface.
- Handrail gripping surfaces with a circular cross section shall have an outside diameter between 1¼ inches minimum and 2 inches maximum.
- Handrail gripping surfaces with a noncircular cross section shall have a perimeter dimension between 4 inches minimum and 6¼ inches maximum, and a cross section dimension of 2¼ inches maximum.
- Handrail gripping surfaces and the surfaces adjacent to them shall be free of sharp or abrasive elements and shall have rounded edges.
- Handrails shall not rotate in their fittings.

3. Placement and Continuity

- Handrails shall be provided on both sides of access ramps and stairs.
- Handrails shall be continuous within the full length of each access ramp run or stair flight.
- Inside handrails on switchback or dogleg access ramps and stairs shall be continuous between runs or flights.

4. Extensions

- Access ramp handrails shall extend horizontally above the landing for 12 inches minimum beyond the top and bottom of ramp runs.
- At the top of a stair flight, handrails shall extend horizontally above the landing for 12 inches minimum beginning directly above the first riser nosing.

- At the bottom of a stair flight, handrails shall extend at the slope of the stair flight for a horizontal distance at least equal to one tread depth beyond the last riser nosing.
- Handrail extensions shall return to a wall, guard, or the landing surface, or shall be continuous to the handrail of an adjacent access ramp run or stair flight.

  Exception: Handrail extensions shall not be required for continuous handrails at the inside turn of switchback or dogleg access ramps or stairs.

1510.15(4) Other Pedestrian Facilities, Features, and Elements

This chapter covers the accessibility criteria for the most commonly encountered pedestrian design elements in the public right of way. However, there are ADA requirements that apply to any feature or element for pedestrian use, such as doorways, elevators, stairs, call boxes, and drinking fountains. For accessibility criteria for less commonly encountered pedestrian design elements, consult the applicable federal guidance document(s) listed in 1510.02(2).

1510.16 Illumination and Signing

In Washington State, the highest number of crashes between vehicles and pedestrians tends to occur during November through February, when there is poor visibility and fewer daylight hours. Illumination of pedestrian crossings and other walkways is an important design consideration because lighting has a major impact on a pedestrian's safety and sense of security. Illumination provided solely for vehicular traffic is not always effective in lighting parallel walkways for pedestrians. Consider pedestrian-level (mounted at a lower level) lighting for pedestrian circulation paths, intersections, and other pedestrian crossing areas with high nighttime pedestrian activity, such as shopping districts, transit stops, schools, community centers, and other major pedestrian generators or areas with a history of pedestrian crashes. (See Chapter 1040 for design guidance on illumination, and Chapter 1020 and the MUTCD for pedestrian-related signing.)

1510.17 Work Zone Pedestrian Accommodation

While Title II of the ADA requires that a public entity maintain its pedestrian facilities in operable working condition, including maintenance of their accessibility features, construction and maintenance activities often temporarily disrupt these facilities. When this occurs, provide access and mobility for pedestrians through and around work zones (see Exhibit 1510-31). Address this in the temporary traffic control plans if the project occurs in a location accessible to pedestrians. The designer must determine pedestrian needs in the proposed work zone during the public input process and through field visits.

Detailed guidance on work zone pedestrian accommodation can be found in the WSDOT *Field Guide for Accessible Public Rights of Way*, the MUTCD, and Chapter 1010.

Some work zone considerations include:

- Separate pedestrians from conflicts with work zone equipment and operations.
- Separate pedestrians from traffic moving through or around the work zone.
- Provide pedestrians with alternate routes that have accessible and convenient travel paths that duplicate, as closely as feasible, the characteristics of the existing pedestrian facilities.

Provide walkways that are clearly marked and pedestrian barriers that are continuous, rigid, and detectable to vision-impaired persons who navigate with a cane. Also, keep:

- The pedestrian head space clear.
- Walkways free from pedestrian hazards such as holes, debris, and abrupt changes in grade or terrain.
- Access along sidewalks clear of obstructions such as construction traffic control signs.
- A minimum clear width path throughout: 4 feet for pedestrians or 10 feet for pedestrians and bicyclists.

Temporary pedestrian facilities within the work zone must meet accessibility criteria to the maximum extent feasible. (See 1510.06 and 1510.07 for pedestrian circulation path and pedestrian access route accessibility criteria.)

Consider the use of flaggers if pedestrian generators such as schools are in the work zone vicinity. Consider spotters who are prepared to help pedestrians through the work zone.

Provide for advance public notification of sidewalk closures in the contract special provisions and plans.

Where transit stops are affected or relocated because of work activity, provide an accessible route to temporary transit stops.



Meets ADA requirements



Does not meet ADA requirements

Work Zones and Pedestrian Facilities
Exhibit 1510-31

1510.18 Documentation

Refer to Chapter 300 for design documentation requirements.

Chapter 1515 Shared-Use Paths

1515.01 General
1515.02 References
1515.03 Definitions
1515.04 Shared-Use Path Design – The Basics
1515.05 Intersections and Crossings Design
1515.06 Grade Separation Structures
1515.07 Signing, Pavement Markings, and Illumination
1515.08 Restricted Use Controls
1515.09 Documentation

1515.01 General

Shared-use paths are designed for both transportation and recreation purposes and are used by pedestrians, bicyclists, skaters, equestrians, and other users. Some common locations for shared-use paths are along rivers, streams, ocean beachfronts, canals, utility rights of way, and abandoned railroad rights of way; within college campuses; and within and between parks as well as within existing roadway corridors. A common application is to use shared-use paths to close gaps in bicycle networks. There might also be situations where such facilities can be provided as part of planned developments. Where a shared-use path is designed to parallel a roadway, provide a separation between the path and the vehicular traveled way in accordance with this chapter.

As with any roadway project, shared-use path projects need to fit into the context of a multimodal community. Exhibits are provided throughout this chapter to illustrate possible design solutions, which should be treated with appropriate flexibility as long as doing so complies with corresponding laws, regulations, standards, and guidance. Engage various discipline experts, including landscape architects, soil and pavement engineers, maintenance staff, traffic control experts, ADA and bicycle coordinators, and others. Additionally, when designing such facilities, consider way-finding.

This chapter includes technical provisions for making shared-use paths accessible to persons with disabilities. Design shared-use paths and roadway crossings in consultation with your region's ADA Coordinator, Bicycle Coordinator, and State Bicycle and Pedestrian Coordinator. For additional information on pedestrian and bicycle facilities, see Chapters 1510 and 1520, respectively.

1515.02 References

(1) Federal/State Laws and Codes

Americans with Disabilities Act of 1990 (ADA)

ADA (28 CFR Part 35, as revised September 15, 2010)

23 CFR Part 652, Pedestrian and Bicycle Accommodations and Projects

49 CFR Part 27, Nondiscrimination on the Basis of Disability in Programs or Activities Receiving Federal Financial Assistance (Section 504 of the Rehabilitation Act of 1973 implementing regulations)

(2) Design Guidance

Guide for the Development of Bicycle Facilities, 4th Edition, AASHTO, 2012

Revised Draft Guidelines for Accessible Public Rights-of-Way (PROWAG), November 23, 2005, U.S. Access Board. The current best practices for evaluation and design of pedestrian facilities in the public right of way per the following FHWA Memoranda:
http://www.fhwa.dot.gov/environment/bikeped/prwaa.htm
http://www.fhwa.dot.gov/civilrights/memos/ada_memo_clarificationa.htm
www.access-board.gov/prowac/draft.htm

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA, as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT

ADA Standards for Accessible Design, USDOJ, 2010; consists of 28 CFR parts 35 & 36 and the *ADA and Architectural Barriers Act (ABA) Accessibility Guidelines for Buildings and Facilities* (ADA-ABAAG; also referred to as the 2004 ADAAG), July 23, 2004, U.S. Access Board
http://www.access-board.gov/ada/

(3) Supporting Information

Equestrian Design Guidebook for Trails, Trailheads and Campgrounds, Chapter 3, provides guidance on shared-use paths for equestrian users, FHWA

Pedestrian Bicycle Information Center
http://www.bicyclinginfo.org/engineering/paths-principles.cfm

1515.03 Definitions

rest area An area to the side of a path.

running slope A slope measured in the direction of travel, normally expressed as a percent.

shared-use landing A level (0 to 2% grade cross slope and running slope) paved area within the shared-use path, designed to provide turning and maneuvering space for wheelchair users and as a resting place for pedestrians.

shared-use path A facility physically separated from motorized vehicular traffic within the highway right of way or on an exclusive right of way with minimal crossflow by motor vehicles. Shared-use paths are primarily used by bicyclists and pedestrians, including joggers, skaters, and pedestrians with disabilities, including those who use nonmotorized or motorized wheeled mobility devices. With appropriate design considerations, equestrians may also be accommodated by a shared-use path facility.

1515.04 Shared-Use Path Design – The Basics

When designing shared-use paths, the bicyclist may not be the critical design user for every element of design. For example, the crossing speeds of most intersections between roads and pathways should be designed for pedestrians, as they are the slowest users. Accommodate all intended users, and minimize conflicts. When designing to serve equestrians, it is desirable to provide a separate bridle trail along the shared-use path to minimize conflicts with horses.



Shared-Use Path
Exhibit 1515-1

(1) Design Speed

The design speed for a shared-use path is based on the bicycle user and is dependent on the terrain and the expected conditions of use. Design the shared-use path to encourage bicyclists to operate at speeds compatible with other users. Higher speeds are discouraged in a mixed-use setting. Design shared-use paths to maintain speeds at or below the speeds shown in Exhibit 1515-2 by designing to the horizontal curve radii shown.

Conditions	Design Speed (mph)	Curve Radius (ft)
Long downgrades (steeper than 4% and longer than 500 ft)	30	166
Open country (level or rolling); shared-use paths in urban areas	20	74
Approaching intersections	12	27

Bicycle Design Speeds
Exhibit 1515-2

When minimum radius curves cannot be obtained because of right of way, topographical, or other constraints, consider installing the following mitigation measures for traffic calming to slow bicyclists when approaching curves:

- Intermittent curves to slow or maintain desired speeds.
- Standard curve warning signs and supplemental pavement markings in accordance with the MUTCD.
- Perpendicular stripes painted on the pathway in decreasing intervals to provide the perception of increased speed. This has been shown to slow drivers when applied to roadways.
- Changes in pavement texture to encourage reductions in speed at tight curve approaches.

The negative effects of tight radius curves can also be partially offset by widening the pavement through the curves. Steeper vertical grades affect the running speed of bicycles. A shared-use path should be designed not to exceed 5%. Refer to 1515.04(3) for further guidance.

(2) Widths, Cross Slopes, Side Slopes, and Clearances

(a) Shared-Use Path Widths

The appropriate paved width for a shared-use path is dependent on the context, volume, and mix of users. The desirable paved width of a shared-use path, excluding the shoulders on either side, is 12 feet. The minimum paved width, excluding the shoulders on either side, is 10 feet.

A paved width of more than 12 feet, excluding the shoulders on either side, may be appropriate when substantial use by both pedestrians and bicyclists is expected or maintenance vehicles are anticipated.

Shared-use path shoulders are typically unpaved and 2 feet wide on either side. Exhibits 1515-3 through 1515-5 provide additional information and cross-sectional elements.

On bridges or tunnels, it is common to pave the entire shared-use path, including shoulders. This usable width can be advantageous for emergency, patrol, and maintenance vehicles and allows for maneuvering around pedestrians and bicyclists who may have stopped. It also keeps the structure uncluttered of any loose gravel shoulder material.

1. Exceptions to Minimum Path Widths

A reduced path width of 8 feet may be designed at spot locations that present a physical constraint such as an environmental feature or other obstacle. Refer to the MUTCD for signing and pavement markings for such conditions.

In very rare circumstances, a reduced width of 8 feet may be used where the following conditions prevail:

- Bicycle traffic is expected to be low, even on peak days or during peak hours.
- Pedestrian use of the facility is not expected to be more than occasional.
- Horizontal and vertical alignments provide frequent, well-designed passing and resting opportunities.
- The shared-use path will not be regularly subjected to maintenance vehicle loading conditions that would cause pavement edge damage.
- The share-use path is for a short distance such as a spur connection to a neighborhood.

(b) Existing Shared-Use Paths – Considerations

Some existing shared-use paths were constructed to narrower dimensions, generally providing 8 feet of pavement. Evaluate existing older paths for current needs. Consider widening an existing shared-use path to meet current geometric standards.

(c) Cross Slope

The maximum cross slope on a paved shared-use path is to be 2%. The cross slope of the shoulders can be no steeper than 6H:1V. To accommodate drainage, the entire section, including shoulders, should transition through curves. It is desirable to design the pivot point on the outside edge of one side of the shoulder or the other to avoid a pavement crown (see Exhibits 1515-3 through 1515-5).

It is recommended that cross slopes be designed to be less than the allowed maximum to account for some tolerance in construction. For example, design for a 1.5% cross slope (rather than the 2% maximum).

Sloping the pavement surface to one side is desirable and usually simplifies drainage design and surface construction. Generally, surface drainage from the path is dissipated as it flows down the side slope.

(d) Side Slopes and Pedestrian Rail


Side slopes along shared-use paths are an important design feature. Embankment side slopes of 6H:1V or flatter provide a gently sloping path border.

For shared-use paths with side slopes steeper than 3H:1V, or where obstacles or waterways may exist, evaluate the potential risk and provide mitigation such as:

- A minimum 5-foot separation from the edge of the pavement to the embankment edge. This can be accomplished by providing a 5-foot shoulder as shown in Exhibit 1515-5, Example 2.
- A natural barrier such as dense shrubbery on the side slopes.
- A physical barrier, such as pedestrian rail.
- Where a shared-use path is adjacent to a vertical drop of 2 feet 6 inches or more, a pedestrian rail is needed (see Exhibit 1515-5, Example 4).
- If the vertical drop is less than 2 feet 6 inches, a pedestrian rail, chain link fence, or 4-inch curb at the edge of the shared-use path may be installed to delineate the edge.
- Where a shared-use path is constructed on the side of a hill, drainage facilities may need to be considered.


(e) Clearances

The minimum horizontal clearance from the edge of pavement to an obstruction (such as bridge piers or guardrail) is 2 feet. Provide a minimum vertical clearance of 10 feet from the pavement surface to overhead obstructions to accommodate maintenance vehicles, bicyclists, and equestrians.



Two-Way Shared-Use Path: Independent Alignment

Exhibit 1515-3




Note:

[1] 3 ft minimum. Provide as much separation from the roadway as practicable.

Two-Way Shared-Use Path: Adjacent to Roadway (≤ 35 mph)

Exhibit 1515-4a




Notes:

- A separation greater than 5 feet is required for path user comfort. If separation greater than 5 feet cannot be obtained, provide barrier separation in accordance with Exhibit 1515-4c.
- See Chapter 1600 for roadway clear zone design guidance for fixed objects.

Two-Way Shared-Use Path: Adjacent to Roadway (> 35mph)

Exhibit 1515-4b




Notes:

- It is desirable for the cross slope to slope toward grass areas for drainage.
- See Chapter 1610 for barrier design. Pedestrian rail height minimum is 42 inches.


Two-Way Shared-Use Path: Attached to Roadway (>35mph)

Exhibit 1515-4c




Example 1: Embankment

Based on context, flatter slopes are desirable.




Example 3: Cut section with ditch

Consult with the Region Materials Engineer to determine for appropriate cut slopes.



Example 2: Shoulder widening to 5 feet or more

Used with steeper fill slopes to provide clear space between the hinge point and path. Vegetation can also be used as a buffer on slopes. In lieu of 3 ft additional widening, consider a natural or physical barrier.



Example 4: Railing used at drop off

Apply railing or fencing a minimum of 42 inches high when a drop off is present, such as along a retaining wall. Consult with the Region Materials Engineer to determine if shoulder along wall should be paved.

Note: These drawings depict some common applications for various slope alternatives.

Shared-Use Path Side Slopes and Railing

Exhibit 1515-5

(3) Running Slopes, Landings, and Rest Areas

(a) **Running Slopes**

Design running slopes (grades) on shared-use paths less than or equal to 5% to accommodate all user types, including pedestrians with disabilities.


When the path is within the highway right of way, its running slope can match the general grade established for the adjacent roadway.

(b) Landings

Shared-use path landings provide users a level place to rest on extended grades. Exhibits 1515-6 and 1515-7 show these features.

Design landings to:

- Permit users to stop periodically and rest.
- Not exceed maximum running slopes and cross slopes of 2%.
- Be in line and as wide as the shared-use path. Landings are to be at least 5 feet long.
- Avoid abrupt grade changes or angle points. Design transitions to landings using vertical curves.



Notes:

- Landings are desirable on extended grades.
- Design vertical curves to transition from the grade to the landing.
- Exhibit 1515-7 illustrates a landing and a rest area.


Shared-Use Path Landing Profile
Exhibit 1515-6

(c) Rest Areas

Although not required, rest areas may be provided adjacent to the shared-use path outside of the path travelled way as shown in Exhibit 1515-7.

Requirements for rest areas include:

- The maximum running slope and cross slopes are 2%.
- The minimum size is to be 5 feet by 5 feet.
- If features such as benches are provided, they must meet ADA requirements; consult with the region ADA Coordinator for guidance.



Notes:

- Design inline landings at least 5 feet long and as wide as the shared-use path.
- Design inline landings with a maximum cross slope and running slope of 2%.

Shared-Use Path Landing and Rest Area

Exhibit 1515-7

(4) Pavement Structural Section

Design the pavement structural section of a shared-use path in the same manner as a highway, considering the quality of the subgrade and the anticipated loads on the path. (Design loads are normally maintenance and emergency vehicles.) Provide a firm, stable, slip-resistant pavement surface.

Design the pavement structural section as recommended by the Region Materials Engineer.

Use crushed rock or other suitable material for shoulder graded areas. Consult with the Region Materials Engineer. On bridges or tunnels, it is common to pave the entire shared-use path, including shoulders across the structure.

(5) Stopping Sight Distance

The distance needed to bring a shared-use path user to a complete stop is a function of the user's perception and braking reaction times, the initial speed, the coefficient of friction between the wheels and the pavement, the braking ability of the user's equipment, and the grade. Exhibits 1515-14a and 14b provide a graph and an equation to obtain minimum stopping sight distances for various design speeds and grades.

(a) **Stopping Sight Distance on Crest Vertical Curves**

Exhibit 1515-15 provides a chart or equations to obtain the minimum lengths of crest vertical curves for varying stopping sight distances and algebraic differences in grade. The values are based on a 4.5-foot eye height for the bicyclist and a 0-foot height for the object (path surface).

(b) **Stopping Sight Distance on Horizontal Curves**

Exhibit 1515-16 gives the minimum clearances to line-of-sight obstructions for sight distance on horizontal curves. Provide lateral clearance based on the sum of stopping sight distances from Exhibits 1515-14a and 14b for bicyclists traveling in both directions and the proposed horizontal curve radius. Where this minimum clearance cannot be obtained, provide curve warning signs and use centerline pavement markings in accordance with the MUTCD.

Exhibits 1515-14a, 14b, 15, and 16 are presented at the end of the chapter.

1515.05 Intersections and Crossings Design

This section covers path/roadway intersections and grade-separated crossings. Detectable warning surfaces are required where shared-use paths connect to the roadway.

(1) Intersections With Roadways


Clearly define who has the right of way and provide sight distance for all users at shared-use path and roadway intersections.

The common types of shared-use path/roadway at-grade intersection crossings are midblock and adjacent.

For roadway intersections with roundabouts, see Chapter 1320.

Midblock crossings are located between roadway intersections. When possible, locate the path crossings far enough away from intersections to minimize conflicts between the path users and motor vehicle traffic. It is preferable for midblock path crossings to intersect the roadway at an angle as close to perpendicular as practicable. A minimum 60-degree crossing angle is acceptable to minimize right of way needs. A diagonal midblock crossing can be altered as shown in Exhibit 1515-8.

There are other considerations when designing midblock crossings. They include traffic right of way assignments; traffic control devices; sight distances for both bicyclists and motor vehicle operators; refuge island use; access control; and pavement markings.



Notes:

- For path and highway signing and markings, see the MUTCD and the *Standard Plans*. http://www.wsdot.wa.gov/publications/fulltext/Standards/english/PDF/m09.60-00_e.pdf
- For radii approaching roadway intersections, see Exhibit 1515-2.

Typical Redesign of a Diagonal Midblock Crossing


Exhibit 1515-8

Adjacent path crossings are located at or near public intersection crosswalks and are normally placed with them. These crossings are usually placed with pedestrian crossings, where motorists can be expected to stop. If alternate intersection locations for a shared-use path are available, select the one with the greatest sight distance.

Adjacent path crossings occur where a path crosses an existing intersection of two roadways, a T intersection (including driveways), or a four-way intersection, as shown in Exhibit 1515-9. It is desirable to integrate this type of crossing close to an intersection so that motorists and path users recognize one another as intersecting traffic. The path user faces potential conflicts with motor vehicles turning left (A) and right (B) from the parallel roadway and on the crossed roadway (C, D, and E).

Consider crossing improvements on a case-by-case basis. Suggested improvements include: move the crossing; evaluate existing or proposed intersection control type; change signalization timing; or provide a refuge island and make a two-step crossing for path users.

Important elements that greatly affect the design of these crossings are traffic right of way assignments, traffic control devices, and the separation distance between path and roadway.



Note:
For signing and pavement markings, see the MUTCD and the *Standard Plans*.

Adjacent Shared-Use Path Intersection

Exhibit 1515-9

(a) Additional Roadway/Path Intersection Design Considerations

Additional roadway/path intersection design considerations include the following:

1. Evaluate Intersection Control

Determine the need for traffic control devices at path/roadway intersections by using MUTCD warrants and engineering judgment. Bicycles are considered vehicles in Washington State, and bicycle path traffic can be classified as vehicular traffic for MUTCD warrants. Provide traffic signal timing set for pedestrians.

2. Signal Actuation Mechanisms

Place the manually operated accessible pedestrian pushbutton in a location that complies with ADA requirements. For additional information, see Chapters 1330 and 1510. A detector loop in the path pavement may be provided in addition to the manually operated accessible pedestrian push button.

3. **Signing**

   Provide sign type, size, and location in accordance with the MUTCD. Place path STOP signs as close to the intended stopping point as feasible. Do not place the shared-use path signs where they may confuse motorists or place roadway signs where they may confuse shared-use path users. For additional information on signing, see the MUTCD and Chapter 1020.

4. **Approach Treatments**

   Design shared-use path and roadway intersections with level grades, and provide sight distances. Provide advance warning signs and pavement markings that alert and direct path users that there is a crossing (see the MUTCD). Do not use speed bumps or other similar surface obstructions intended to cause bicyclists to slow down. Consider some slowing features such as horizontal curves (see Exhibits 1515-2 and 1515-8). Avoid locating a crossing where there is a steep downgrade where bike speeds could be high.

5. **Sight Distance**

   Sight distance is a principal element of roadway and path intersection design. At a minimum, provide stopping sight distance for both the roadway and the path at the crossing. Decision sight distance is desirable for the roadway traffic. Refer to Chapter 1260 for stopping sight distance for the roadway and 1515.04(5) for shared-use path stopping sight distance.

6. **Curb Ramp Widths**

   Design curb ramps with a width equal to the shared-use path. Curb ramps and barrier-free passageways are to provide a smooth transition between the shared-use path and the roadway or sidewalk (for pedestrians). Curb ramps at path/roadway intersections must meet the requirements for curb ramps at a crosswalk. For design requirements, see Chapter 1510, and for curb ramp treatments at roundabouts, see Chapter 1320.

7. **Refuge Islands**


   Consider refuge islands where a shared-use path crosses a roadway when one or more of the following applies:

   - High motor vehicle traffic volumes and speeds
   - Wide roadways
   - Use by the elderly, children, the disabled, or other slow-moving users

   The refuge area may either be designed with the storage aligned perpendicularly across the island or be aligned diagonal (as shown in Exhibit 1515-10). The diagonal storage area has the added benefit of directing attention toward oncoming traffic since it is angled toward the direction from which traffic is approaching.

(2) At-Grade Railroad Crossings

Wherever possible, design the crossing at right angles to the rails. For signing and pavement marking for a shared-use path crossing a railroad track, see the MUTCD and the *Standard Plans*. Also, see Chapter 1510 for design of at-grade pedestrian railroad crossings.



Note:
This exhibit shows a case where a path intersects a roadway framed with both a sidewalk and a paved shoulder, for the purpose of showing detectible warning surface placements.

Roadway Crossing Refuge Area
Exhibit 1515-10

1515.06 Grade Separation Structures

Provide the same minimum clear width as the approach paved shared-use path plus the graded clear areas.

Carrying full widths across structures has two advantages:

- The clear width provides a minimum horizontal shy distance from the railing or barrier.
- It provides needed maneuvering room to avoid pedestrians and other bicyclists.

For undercrossings and tunnels, provide a minimum vertical clearance of 10 feet for path users from the path pavement to the structure above. This allows access by emergency, patrol, and maintenance vehicles on the shared-use path.

Consult the region Maintenance Office and the HQ Bridge Preservation Office to verify that the planned path width meets their needs. If not, widen to their specifications.

Use expansion joints that accommodate shared-use path users. Expansion joints should be perpendicular to the path and have a maximum gap of ½ inch or be covered with a slip-resistant plate.

Vertical clearance is the critical height under a structure that will accommodate vehicular and rail traffic based on its design characteristics. (See Chapter 720 for minimum vertical clearance guidance.)

The installation of protective screening is analyzed on a case-by-case basis. Refer to Chapter 720 for guidance.



Note:
On structures, the bridge railing type and height are part of the structure design. Contact the HQ Bridge and Structures Office for additional information.

Shared-Use Path Bridge and Approach Walls
Exhibit 1515-11



Notes:

- The photo above shows a bridge with a shared-use path separating the users from the roadway. Pedestrian rail is used on the outside edge.
- On structures, the bridge railing type and height are part of the structure design. Contact the HQ Bridge and Structures Office for additional information.

Bridge and Pedestrian Rail
Exhibit 1515-12

1515.07 Signing, Pavement Markings, and Illumination

Generally, WSDOT does not provide continuous centerline striping or channelization for user modes on shared-use paths. However, signing and pavement markings can be beneficial to warn shared-use path users of curves, grades, obstructions, and intersections.

Refer to the MUTCD for guidance and directions regarding signing (regulatory, warning, and way finding) and pavement markings.

The *Standard Plans* shows shared-use path pavement markings at obstructions in accordance with the MUTCD and also shows placement of detectible warning surfaces.

For pavement marking around bollards and other obstructions, see Standard Plan M-9.60:
http://www.wsdot.wa.gov/publications/fulltext/standards/english/pdf/m09.60-00_e.pdf

The level of illumination on a shared-use path is dependent on the amount of nighttime use expected and the nature of the area surrounding the facility. If illumination is used, provide illumination in accordance with Chapter 1040.

1515.08 Restricted Use Controls

This section presents considerations on use of fencing and other treatments to restrict roadway and path users to their domains.

(1) Fencing

Limited access highways often require fencing or other forms of controlling access. Shared-use paths constructed within these corridors, such as shown in Exhibit 1515-13, likely require fencing. For guidance on fencing, limited access controls, and right of way, refer to Division 5 of the *Design Manual*. Evaluate the impacts of fencing on sight distances.



Shared-Use Path in Limited Access Corridor

Exhibit 1515-13

(2) Restriction of Motor Vehicle Traffic

Shared-use paths often need some form of physical barrier at roadway intersections to prevent unauthorized motor vehicles from entering.

Bollards have been used by many path owners to prevent unauthorized vehicle access. However, bollards should not be applied indiscriminately, and there are other considerations to bollard installation.

(a) **Landscaped Islands**

A preferred method of restricting entry of motor vehicles is to split the entry way into two sections separated by low landscaping, thereby splitting a path into two channels at roadway intersections. This method essentially creates an island in the middle of the path rather than installing a bollard. Such an island could be planted with low-growing, hardy vegetation capable of withstanding the occasional authorized vehicle traveling over it. When splitting a path, employ MUTCD pavement markings and signing, such as is used for bollards and obstructions.

(b) **Bollard Considerations**

Typically, one bollard located in the center of the path is sufficient to control motor vehicle access to the path. If more than one bollard is needed, the additional bollards should be placed at the edge of the shared-use path.

Install bollards at entrances to shared-use paths to discourage motor vehicles from entering. Do not use bollards to divert or slow path traffic. When locating such installations, stripe an envelope around the bollards and paint and reflectorize them to be visible to path users both day and night. Bollards located on or adjacent to shared-use paths represent an object that needs to be avoided by bicyclists and pedestrians. To increase the potential for appropriate maneuvering to occur, provide designs where the post is clearly visible and recognizable.

When designing bollards, the following apply:


- The desirable design is to provide a single bollard, installed in the middle of the path to reduce confusion.
- When multiple bollard posts are used in wide path sections, use a minimum 5-foot spacing between the edge of concrete footings to permit passage of bicycle-towed trailers, wheelchairs, and adult tricycles, with room for bicycle passage without dismounting.
- Provide 4 feet minimum (5 feet desirable) clear width between the edge of concrete footing and edge of path.
- At a minimum, provide stopping sight distance to bollards. An ideal location for bollard placement is in a relatively straight area of the path where the post placement has the stopping sight distance given in Exhibit 1515-14a and 14b. Do not place bollards in difficult-to-see locations (for example, immediately upon entering a tunnel).
- For cases where multiple posts are used longitudinally along the path, locate them at least 20 feet apart, with the first post in line from each direction having stopping sight distance.
- Use a contrasting striping pattern on the post.
- Use reflective materials on the post, such as a band at the top and at the base.
- Design all bollards along a corridor to be uniform in appearance. Frequent cyclists can become familiar with the posts and recognize them easily.
- Provide pavement markings in accordance with the *Standard Plans* and MUTCD at all bollards on paved paths.
- Use removable bollards (Bollard Type 1) to permit access by emergency and service vehicles.
- Nonremovable bollards (Bollard Type 2) may be used where access is not needed.

Refer to the *Standard Plans* for bollard designs and the *Standard Plans* and MUTCD for pavement markings at bollards.

When bollards need to be placed near the roadway, see Chapter 1600 for clear zone requirements.

1515.09 Documentation

For the list of documents required to be preserved in the Design Documentation Package and the Project File, see the Design Documentation Checklist:
www.wsdot.wa.gov/design/projectdev/



Note:
Shaded area represents grades greater than 5%.


$$S = \frac{V^2}{0.30(f - G)} + 3.67V$$

Where:

S = Stopping sight distance (ft)
V = Speed (mph)
f = Coefficient of friction (use 16)
G = Grade (%)

Stopping Sight Distance for Downgrades

Exhibit 1515-14a



Note:
Shaded area represents grades greater than 5%.

$$S = \frac{V^2}{0.30(f + G)} + 3.67V$$

Where:

S = Stopping sight distance (ft)
V = Speed (mph)
f = Coefficient of friction (use 16)
G = Grade (%)

Stopping Sight Distance for Upgrades

Exhibit 1515-14b

A (%)	Stopping Sight Distance, S (ft)													
	40	**60**	**80**	**100**	**120**	**140**	**160**	**180**	**200**	**220**	**240**	**260**	**280**	
2	3	3	3	3	3	3	3	3	3	3	30	70	110	150
3	3	3	3	3	3	3	20	60	100	140	180	220	260	300
4	3	3	3	3	15	55	95	135	175	215	256	300	348	400
5	3	3	3	20	60	100	140	180	222	269	320	376	436	500
6	3	3	10	50	90	130	171	216	267	323	384	451	523	600
7	3	3	31	71	111	152	199	252	311	376	448	526	610	700
8	3	8	48	88	128	174	228	288	356	430	512	601	697	800
9	3	20	60	100	144	196	256	324	400	484	576	676	784	900
10	3	30	70	111	160	218	284	360	444	538	640	751	871	1,000
11	3	38	78	122	176	240	313	396	489	592	704	826	958	1,100
12	5	45	85	133	192	261	341	432	533	645	768	901	1,045	1,200
13	11	51	92	144	208	283	370	468	578	699	832	976	1,132	1,300
14	16	56	100	156	224	305	398	504	622	753	896	1,052	1,220	1,400
15	20	60	107	167	240	327	427	540	667	807	960	1,127	1,307	1,500
16	24	64	114	178	256	348	455	576	711	860	1,024	1,202	1,394	1,600
17	27	68	121	189	272	370	484	612	756	914	1,088	1,277	1,481	1,700
18	30	72	128	200	288	392	512	648	800	968	1,152	1,352	1,568	1,800
19	33	76	135	211	304	414	540	684	844	1,022	1,216	1,427	1,655	1,900
20	35	80	142	222	320	436	569	720	889	1,076	1,280	1,502	1,742	2,000
21	37	84	149	233	336	457	597	756	933	1,129	1,344	1,577	1,829	2,100
22	39	88	156	244	352	479	626	792	978	1,183	1,408	1,652	1,916	2,200
23	41	92	164	256	368	501	654	828	1,022	1,237	1,472	1,728	2,004	2,300
24	43	96	171	267	384	523	683	864	1,067	1,291	1,536	1,803	2,091	2,400
25	44	100	178	278	400	544	711	900	1,111	1,344	1,600	1,878	2,178	2,500

Minimum Length of Vertical Curve, L (ft)

$$L = \frac{AS^2}{900} \quad \text{when } S < L$$

$$L = 2S - \frac{900}{A} \quad \text{when } S > L$$

Where:

S = Stopping sight distance (ft)

A = Algebraic difference in grade (%)

L = Minimum vertical curve length (ft)

Based on an eye height of 4.5 ft and an object height of 0 ft.

Note:

Below ——— represents $S \leq L$.

Shaded area represents A>10%.

Minimum Lengths for Crest Vertical Curves

Exhibit 1515-15

Height of eye: 4.50 ft

Height of object: 0.0 ft


Line of sight at the M distance is normally 2.3 ft above centerline of inside lane at point of obstruction, provided no vertical curve is present in horizontal curve.

$$M = R\left(1 - \text{COS}\frac{S\,28.65}{R}\right)$$

$$S = \frac{R}{28.65}\left[\text{COS}^{-1}\left(\frac{R-M}{R}\right)\right]$$

S ≤ Length of curve

Angle is expressed in degrees.



Where:

S = Sight distance (ft)

R = Centerline radius of inside lane (ft)

M = Distance from inside lane centerline (ft)

R (ft)	Stopping Sight Distance, S (ft)[1]													
	40	60	80	100	120	140	160	180	200	220	240	260	280	300
25	7.6	15.9												
50	3.9	8.7	15.2	23.0	31.9	41.5								
75	2.7	5.9	10.4	16.1	22.7	30.4	38.8	47.8	57.4	67.2				
95	2.1	4.7	8.3	12.9	18.3	24.6	31.7	39.5	47.9	56.9	66.2	75.9	85.8	
125	1.6	3.6	6.3	9.9	14.1	19.1	24.7	31.0	37.9	45.4	53.3	61.7	70.5	79.7
150	1.3	3.0	5.3	8.3	11.8	16.0	20.8	26.2	32.1	38.6	45.5	52.9	60.7	69.0
175	1.1	2.6	4.6	7.1	10.2	13.8	18.0	22.6	27.8	33.4	39.6	46.1	53.1	60.4
200	1.0	2.2	4.0	6.2	8.9	12.1	15.8	19.9	24.5	29.5	34.9	40.8	47.0	53.7
225	0.9	2.0	3.5	5.5	8.0	10.8	14.1	17.8	21.9	26.4	31.2	36.5	42.2	48.2
250	0.8	1.8	3.2	5.0	7.2	9.7	12.7	16.0	19.7	23.8	28.3	33.0	38.2	43.7
275	0.7	1.6	2.9	4.5	6.5	8.9	11.6	14.6	18.0	21.7	25.8	30.2	34.9	39.9
300	0.7	1.5	2.7	4.2	6.0	8.1	10.6	13.4	16.5	19.9	23.7	27.7	32.1	36.7
350	0.6	1.3	2.3	3.6	5.1	7.0	9.1	11.5	14.2	17.1	20.4	23.9	27.6	31.7
400	0.5	1.1	2.0	3.1	4.5	6.1	8.0	10.1	12.4	15.0	17.9	20.9	24.3	27.8
500	0.4	0.9	1.6	2.5	3.6	4.9	6.4	8.1	10.0	12.1	14.3	16.8	19.5	22.3
600	0.3	0.7	1.3	2.1	3.0	4.1	5.3	6.7	8.3	10.1	12.0	14.0	16.3	18.7
700	0.3	0.6	1.1	1.8	2.6	3.5	4.6	5.8	7.1	8.6	10.3	12.0	14.0	16.0
800	0.2	0.6	1.0	1.6	2.2	3.1	4.0	5.1	6.2	7.6	9.0	10.5	12.2	14.0
900	0.2	0.5	0.9	1.4	2.0	2.7	3.6	4.5	5.5	6.7	8.0	9.4	10.9	12.5
1,000	0.2	0.4	0.8	1.2	1.8	2.4	3.2	4.0	5.0	6.0	7.2	8.4	9.8	11.2

Minimum Lateral Clearance, M (ft)

Note:

[1] S is the sum of the distances (from Exhibits 1515-14a and 14b) for bicyclists traveling in both directions.

Lateral Clearance for Horizontal Curves

Exhibit 1515-16

Chapter 1520 Roadway Bicycle Facilities

1520.01 General
1520.02 Roadway Bicycle Facility Types
1520.03 Bicycle Facility Selection
1520.04 Intersection Design Treatments
1520.05 Additional Bicycle Design Requirements and Considerations
1520.06 Documentation
1520.07 References

1520.01 General

The Washington State Department of Transportation (WSDOT) encourages and relies on bicycle use on and interconnecting with its facilities. Bicycle facilities or improvements for bicycle transportation are included in WSDOT's project development and highway programming processes.

This chapter is a guide for designing bicycle facilities within state highway right of way or between the curb lines on city streets designated as state highways. When designing facilities outside of state highway right of way or beyond the curb on city streets designated as state highways, use the local agency's design guidance. If the bicycle facility will have shared use with pedestrians incorporate ADA requirements in Chapter 1515.

Guidance in this chapter applies to typical situations encountered on state highways, and includes options for intersection and interchange design. Unique design challenges are resolved using expertise and guidance from the regional Bicycle Coordinator or if none exists, the WSDOT headquarters Bicycle Coordinator. Additional concepts to resolve unique bicycle facility design situations can be found in guides referenced (1520.07), but may require additional approvals for signing, pavement markings or bike facility types not presented within this chapter.

The region Traffic Engineer is responsible for determining which sections are inappropriate for bicycle traffic on state highways. The State Traffic Engineer, after consultation with the Bicycle Advisory Committee, prohibits bicycling on sections of state highways through the traffic regulation process. Contact the region Traffic Office for further information.

1520.02 Roadway Bicycle Facility Types

WSDOT has adopted the following six types of bicycle facilities, from most protected to least protected:

- Shared-Use Paths (see Chapter 1515 for guidance)
- Raised and Curb-Separated
- Separated Buffered Bike Lanes
- Buffered Bike Lanes
- Conventional Bike Lanes
- Shared Lane Markings

Shared-use paths (see Chapter 1515) are the most protected type of bike facility because the path is physically separated from motor vehicle traffic most commonly by a wide vegetated outer separation or other physical barrier. Roadway bicycle facilities can range from separated from motor vehicle traffic to physically sharing a lane with motor vehicle traffic. The following subsections discuss five types of roadway bicycle facilities adopted for use on state highways.

All roadway bicycle facility types will be designated by striping, signage, and pavement markings to indicate the preferential or exclusive use for bicycle users. See 1520.05(1) for more information.

1520.02(1) Raised and Curb-Separated


Exhibit 1520-1 shows a raised and curb-separated bicycle facility. These facilities are considered protected because they are vertically separated from motor vehicle traffic. When a raised and curb-separated bicycle facility is applied, it is considered part of the streetside zone (see Chapter 1230); however, it cannot be combined with other zone areas because the intent is also segregation from pedestrians. The raised and curb-separated facility is dedicated for bike users and delineated with pavement markings, signing, and in some cases pavement material.

There are advantages in utilizing streetside zones in conjunction with a raised and curb-separated bike facility. A furnishing zone can be used to help segregate pedestrian and bicycle users or for additional separation between the bike facility and motor vehicle traffic. If a furnishing zone is not used to separate the raised bike facility from the pedestrian zone, consider different pavement types, signs, pavement borders, or striping within the streetside zone to effectively separate pedestrian and bicycle users.

When the raised and curb-separated bike facility is placed adjacent to motor vehicle traffic, consider using a sloped and mountable curb (see Chapter 1230) to enable passing maneuvers between cyclists.

Within incorporated limits, raised and curb-separated bike facilities are located behind the curb and therefore fall under a local agency's jurisdiction. (See Chapters 1230, and 1600 for additional information on jurisdictional boundaries). In these situations, follow the local agency's design guidance for this type of bike facility.

Exhibit 1520-1 Raised and Curb-Separated Bike Facility



1520.02(2) Separated Buffered Bike Lanes


Separated buffered bike lanes are at grade with the roadway, and they include a bike lane, a buffer area, and some type of vertical feature that reduces the likelihood of encroachment into the bike lane by motor vehicles and increases user comfort. Bike markings (see the *Standard Plans*) in the bike lane and signage are employed. The most common type of vertical separator used within the buffer area is a pavement mounted flexible tubular marker or delineator. Use of dual-faced curbing, raised medians, or the parking zone adjoining the buffer area can also accomplish the same task.

If parked vehicles within the parking zone are used as the vertical separator, the parking zone cannot encroach onto the buffer area. When a separated buffered bike lane is positioned between motor vehicle lanes and a parking zone, consider including an additional buffer area between the parking zone and bike lane. Use of the buffer area described in these two configurations facilitates loading and unloading of the parked vehicles, and reduces the risk of a

cyclist being struck when a parked vehicle door opens (aka "dooring"). See NACTO's *Urban Bikeway Design Guide and Urban Street Design Guide* for examples.

Exhibit 1520-2 shows an example of separated buffered bike lane using a flexible tubular marker as the vertical separator. A painted buffer strip with flexible tubular marker helps accentuate the bicycle facility from the motor vehicle lane, when curbing or a raised median (also considered vertical separation) is not used for the buffer strip. Consider a 3-foot-wide buffer strip whenever possible. When utilizing a buffer, the bike lane itself may be 3 feet in width. However, 5 feet is recommended exclusively to the bike lane to enable passing maneuvers between cyclists, and account for the effective width needs of bicyclists when drainage features are present in the bike lane. In space constrained areas where inexperienced bicyclists, such as children, are expected or where there is a steep uphill grade use a 4 foot minimum for the bicycle lane. High bicyclist volume locations should consider more width to facilitate mobility performance for this mode. In constrained spaces where lower volumes of cyclists are anticipated and inexperienced bicyclists are not expected, the minimum total width of both the bike lane and buffer combined is 5 feet.


Exhibit 1520-2 Separated Buffered Bike Lane



1520.02(3) Buffered Bike Lane

Exhibit 1520-3 shows a buffered bike lane. The design is effectively the same as a separated buffered bike lane (see 1520.02(2)) without the use of vertical separators. Consider a 3-foot buffer strip whenever possible. When utilizing a buffer, the bike lane itself may be 3 feet in width, but it is recommended that 5 feet be provided exclusively to the bike lane to enable passing maneuvers between cyclists. High cyclist volume locations should consider more width to facilitate mobility performance for this mode. In locations where the posted speed is 30mph or less and lower volumes of cyclists are anticipated, the minimum total width of both the bike lane and buffer combined is 5 feet. In locations where inexperienced bicyclists, such as children, are expected or when there is a steep uphill grade the minimum total width of both the bike lane and the buffer combined is 6 feet.


Exhibit 1520-3 Buffered Bike Lane



1520.02(4) Conventional Bike Lane

Conventional bike lanes are at grade and adjacent to motor vehicle traffic lane and are designated by a single solid wide stripe between the motor vehicle lane and bike lane. Additional bike markings (see the *Standard Plans*) in the bike lane and signage are employed. A width of 6 feet is recommended for a conventional bike lane when designing for the "Interested, but Concerned" user type. The minimum width for a conventional bike lane is 5 feet when adjacent to curb, or 4 feet when no curb is present. Additional width is considered when higher volumes of cyclists are anticipated or when adjacent to parallel on-street parking. Exhibit 1520-4 shows a conventional bike lane.


Exhibit 1520-4 Bike Lane



1520.02(5) Shared Lane

A shared lane is a combined motor vehicle and bicycle lane, as shown in Exhibit 1520-5. Shared lanes are appropriate for lower-speed and lower-volume streets. Shared lanes employ pavement markings and signage to indicate the combined use. Shared lanes are more common in bicycle boulevards, establishing a complete network for cyclists within an urban or suburban environment. Shared lanes may be used on state highways within the ranges presented in 1520.03; however, it is more likely that shared lanes will interface with state highways through crossing situations. It is important to consider how to configure an intersection or dedicated bicycle crossing location when intersecting with a bicycle boulevard network (see 1520.04(5)).

Exhibit 1520-5 Shared Lane Markings



Shared lane markings (aka "sharrows") are pavement markings specifically used to indicate a shared lane or intersection space. The position of the marking can encourage a desired lateral position within the lane for cyclists, as well as alerting motor vehicle users. Consider the shared lane marking placement with respect to on-street parking and the potential for dooring that will lower safety performance for the cyclist. Shared lane markings must be placed at least 4 feet from the face of curb, or in the center of the shared lane (or at least 11 feet from face of curb) when an adjacent parallel parking zone is present.

Conventionally, wide lanes have been encouraged for shared-lane applications, to allow for motor vehicles to pass cyclists, or for cyclists to pass motor vehicles in a queue. However, wider lanes may also encourage motor vehicle drivers to travel at higher speeds and a detriment for a shared lane application. Permitting in-lane passing between motor vehicles and bicyclists can lower safety performance for cyclists.

The speed of cyclists can vary significantly between users, and depends on the experience, fitness level of the user, bike technology, and roadway grade. If a shared lane is proposed on an hill, consider a conventional bike lane in the upgrade direction of travel.

1520.02(5)(a) Accommodating Bikes on Shoulders

Many rural highways are used by bicyclists for commuting between cities or for recreation. Providing and maintaining paved shoulders can significantly improve convenience and safety for both bicyclists and motorists along such routes.

Accommodating bicycle users on the shoulder is common on state highways, particularly on rural high-speed facilities. Shoulder improvements to facilitate bicycle travel include widening the shoulders to a minimum of 4 feet, improving roadside maintenance (including periodic sweeping), and removing surface obstacles such as drain grates that are not compatible with bicycle tires. If shoulder rumble strips are present, provide for at least 4 feet of usable shoulder between the rumble strip and the outside edge of shoulder. If guardrail or barrier is present, increase the dimension to 5 feet of usable shoulder.

Accommodating bicycle use on shoulders is appropriate at many locations. Note, however, that bike on shoulder accommodations are not dedicated bicycle facilities, and bicycle users do not have the same operating privileges as with designated roadway bike facilities. In rural to suburban/urban transition areas consider converting the shoulder to a protected buffered bike lane, both to encourage speed management of motor vehicle users through the transition and to establish a dedicated special-use lane for cyclists to tie into the local network.

1520.03 Bicycle Facility Selection

Bicycle facilities are desirable in order to provide viable travel alternatives, and for bicycle users to have the ability to access land use destinations along state highways.

Understand how the state highway interfaces with routes identified as local, state, or regional bike routes. If the state highway is the bike route, intersects with an existing route, or if bicycle users are an identified modal priority (See Chapter 1103), account for the bike facility needs within the design. Other projects need to consider a design that does not preclude the future vision for a planned bike route, depending on the context identification selection (See Chapter 1102) and design year selection (See Chapter 1103).

The only instance during planning or design when performance effects on existing or planned bike facilities may not be considered is in locations being designed for the existing context, and the location is prohibits bicycle use. State highways that prohibit bike use can be found here: http://www.wsdot.wa.gov/bike/closed.htm

1520.03(1) Types of Cyclists

Recent research indicates that people have different viewpoints and thresholds that dictate their willingness to utilize bike facilities. Three general types of cyclist users exist:

- *Strong and Fearless* – This cyclist type are confident not only in their abilities as a cyclist but also with their ability to operate intermixed with other modal users.
- *Enthused and Confident* – These cyclists prefer utilizing separated facilities, but are comfortable riding intermixed within other modes in some transportation contexts.
- *Interested, but Concerned* – Cyclists who primarily have safety concerns and who are less skilled or less familiar with the rules of the road, but would like to ride more. These cyclists are frequently dissuaded from cycling, even if bike facilities are present, because of the degree of separation between themselves and other traffic. This category includes children and others new to bicycling.

1520.03(1)(a) Designing for the Interested, but Concerned


The Interested, but Concerned cyclist constitutes the largest segment of cyclist types within suburban, urban and small town populations. Bike facility selection on state routes is based on designing for the "Interested, but Concerned" user type as a starting point. Exhibit 1520-6a shows ranges of applications for the different types of bicycle facilities related to generally accepted safety and mobility performance for this design user.

Other performance needs may increase or decrease the viability of certain types of bike facilities, such as shared-use paths through aesthetic areas or those planned for a mixture of commute and recreational purposes. Further considerations for cyclist perception of comfort are another factor that can affect use of the facility. Designing for a higher level of separation may be more important at locations that serve community activity centers, schools or popular destinations (such as a retail oriented segment of a route) where additional accommodations are appropriate for either the functional uses or less skilled cyclists (including children). In these situations, separated facilities or wider dimensions may provide the level of comfort needed to satisfy user needs and context considerations. Additionally, some suburban, urban, and small town contexts will have more specific bicycle performance needs that will help identify either spot improvements or alteration of the type of existing facility to enhance a specific performance area. Bike facility selection in 1520.03(1)(b) are provided for these reasons.

1520.03(1)(b) Designing for the Confident


In some contexts, it is appropriate to design for the Strong and Fearless, and Enthused and Confident user types. In cases, where right of way is very constrained or where bicycles are not considered the modal priority (see Chapter 1103), it is appropriate to use Exhibit 1520-6b for determining facility selection after input from community engagement efforts. However, understand that the application of Exhibit 1520-6b may result in less mode shift or use of the capacity provided.

Exhibit 1520-6a Bicycle Facility Selection Chart – Interested, but Concerned Cyclists



Note: Adapted from *Montgomery County Bicycle Planning Guidance*, Montgomery County Department of Transportation, 2014.

Exhibit 1520-6b Bicycle Facility Selection Chart – Confident Cyclists



1520.03(2) Speed Considerations

While Exhibits 1560-6a and 1560-6b provide ranges of speeds in which different types of bike facilities may be appropriate, it is critical to understand that motor vehicle speed plays a significant role in crash severity between motor vehicles and cyclists. When designing multimodal facilities, a target speed selection within the low speed design control is encouraged. Safety performance increases as motor vehicle speeds are decreased. The optimum target speed for safety performance of multimodal designs is the lowest statutory speed allowed on state routes, which is 25 mph. See Chapter 1103 for further discussion on target speed and speed management treatments.

1520.04 Intersection Design Treatments

The principle objective when designing intersections for bicycle mobility and safety performance is to provide a visible, distinct, predictable, and clearly designated path leading to and through the intersection while managing potential conflicts between all other users and cyclists. This chapter covers options for intersection design for bicyclists while chapters in the 1300 series provide guidance for intersection control type selection and design.

Intersection design to meet the bicycle safety and mobility performance of the cyclist is unique to each location. The primary emphasis is to create a visible, distinct, predictable and clear path for the cyclist to reduce conflicts between cyclists and other design users. This is most commonly achieved through clear delineation of the bike facility leading up to and through the intersection, along with segregating or prioritizing movements between design users. Several proven state-of-the-practice intersection treatments are presented within this section. However, pavement marking or aspects about the configuration may not currently be supported by the *Manual on Uniform Traffic Control Devices*.

At the time of publication, bike boxes (1520.04(2)) and two-stage left turn lanes (1520.04(3)) are subject to an experimentation request to FHWA. Obtain Headquarters (HQ) Traffic Office approval and assistance with submitting a request for experimentation. Consult, as appropriate, the Federal Highway Administration's (FHWA) MUTCD website for bicycle facilities for a listing of the current status of bicycle-related pavement markings and treatments: http://www.fhwa.dot.gov/environment/bicycle_pedestrian/guidance/mutcd/index.cfm. See 1520.05(1) for additional information on bicycle pavement markings under MUTCD evaluation.

Note: Exhibits 1520-7 through 1520-9 all show colored pavement markings to increase the safety performance of intersection designs. However, colored pavement markings are not required, and may be added at a later stage if the desired safety performance is not met.

1520.04(1) Approach Through Lanes

The approach to intersections needs to balance the bicycle user's safety needs with the mobility needs of other users. Clear delineation of user lanes and potential conflict areas is currently the treatment most commonly used to manage the approach to intersections. Use dotted lines to identify the conflict area. Colored pavement markings can be used to further enhance and delineate the conflict area. Exhibit 1520-7 shows different applications of the approach through lane most likely to be encountered.

1520.04(2) Bike Boxes and Crossing Pavement Markings

Bike boxes are designated areas for bicyclists positioned across and in front of the bike and motor vehicle lanes as shown in Exhibit 1520-8. Bike boxes are used at signalized intersections and increase both mobility and safety performance for the bicycle mode. Applying a bike box assists mobility performance by prioritizing the bicycle movement at an intersection, and enables a cyclist to position for a left-turn movement. Bike boxes have also been found to prevent cyclist and motor vehicle encroachment into the pedestrian crossing, reducing conflicts with pedestrians at intersections. Bicycle safety performance is improved by increasing the visibility of the cyclist, and by reducing conflicts between motor vehicles making a right turn and the bicycle through movement (also known as “right-hook” conflict).

There are several different ways to delineate bike lanes through the intersection. Dotted lines are the most common, but can be combined with sharrows or green pavement markings (see 1520.05(1)) to further enhance the bike facility’s presence and position within an intersection.


1520.04(3) Two-Stage Left Turns

Exhibit 1520-9 shows an example of a two-stage left-turn design for bicycle users. This design utilizes a rectangular bike box to enable cyclist queueing at the crossroad signal phase. The bicyclist passes partway through the intersection to access the bike box, and then waits for the crossroad next signal phase to eliminate the bicyclist left turn movement. This treatment is has best value at intersections with significant volumes of motor vehicle traffic or large volumes of left-turn cyclists, or when separated or buffered roadway bicycle facilities are used on the segment.


This treatment can increase safety performance by reducing conflicts between cyclists and other users, segregating motor vehicle and bicycle users, and separating turning cyclists from through cyclists.

The position of the queue box is a critical aspect of this intersection design. Depending on the size and configuration of the intersection, it may present a modal performance trade-off between bicycle mobility and safety versus motor vehicle mobility performance. Use turn simulation software to verify the queue box is outside the crossroad left-turn path, or restrict left turns at the crossroad to accommodate the queue box. Similarly, right turns may need to be restricted for motor-vehicles approaching the queue box if motor vehicle right-turn lanes or right-turn pockets are not present.


Exhibit 1520-7 Approach Through Lanes



RIght-Turn-Only Lane



Parking Area Becomes Right-Turn-Only Lane




Right Lane Becomes Right-Turn-Only Lane

Notes:

- Not to scale and not all dimensions shown.
- See 1520.05(1)(a) for criteria when considering the use of green colored pavement markings.
- Consider both the speed of motorized vehicles and bicyclists when determining the length of weave and degree of taper for the bike lane.


Exhibit 1520-8 Bike Box and Intersection Crossing Markings



Notes:

- This exhibit is intended to illustrate options for bike facilities through interchange areas, and not intended to represent recommended practice for any other features including ADA criteria (See Chapter 1510 for ADA and pedestrian design).
- See 1520.05(1)(a) for criteria when considering the use of green colored pavement markings.


Exhibit 1520-9 Two-Stage Left-Turn Queue Box



Notes:

- This exhibit is intended to illustrate options for bike facilities through interchange areas, and not intended to represent recommended practice for any other features including ADA criteria (See Chapter 1510 for ADA and pedestrian design).
- Consider both the speed of motorized vehicles and bicyclists when determining the length of weave and degree of taper for the bike lane.
- See 1520.05(1)(a) for criteria when considering the use of green colored pavement markings.

Exhibit 1520-10 Median Refuge Island for Cyclists



1520.04(4) Traffic Signals Considerations

Consider bicycle needs and intersection geometry when timing the traffic signal cycle and when selecting the method of detecting the presence of cyclists. Contact the regional Bicycle Coordinator and region Traffic Engineer for assistance in determining the timing criteria. At a minimum consider safety performance needs, projected bicycle volume, motor vehicle volume, traffic delay, roadway grade and the types of bicyclists using the intersection that may require more time to clear the intersection. Consider the installation of effective loop detectors or other methods of detecting a bicycle within the bike lane (in advance of the intersection) and turn lanes. Select detectors sensitive enough to detect bicycles, and use a bike detector symbol to identify detector presence.

Push button actuators may also be used to facilitate movement of bicyclists through a signalized intersection. However, requiring bicyclists to go out of their way to use push button actuators may create motor vehicle driver confusion of the bicyclists intended path through the intersection, as well as inconveniencing the bicyclist. If pushbutton actuators are used, consider their position relative to the bike facility. Pushbutton actuators are more effective when the bike facility is adjacent to the curb (curb extensions at intersections can create this environment). Consider an additional push button actuator for the exclusive use of cyclists when positioning of the actuator is in conflict with ADA design requirements (see Chapter 1510). For additional guidance on signal design, see Chapter 1330.

1520.04(4)(a) Bike Signals

Intersections with separated bike lanes, other complex multimodal intersection treatments or those with a specific baseline need to increase bicycle user safety performance may incorporate a dedicated bike signal head with detection or actuation systems. Bike signal heads further separate modal user movements at intersections, while also allowing for priority to cyclists at intersections. Contact the region Traffic Engineer for approval for application of this treatment.

At the time of this publication, bike signal faces are subject to requirements of FHWA Interim Approval for this treatment. For current status of the treatment and conditions of the Interim Approval, if still applicable, see
http://www.fhwa.dot.gov/environment/bicycle_pedestrian/guidance/mutcd/index.cfm

1520.04(5) Median Refuge Islands for Cyclists

Layered networks have the benefit of separating modes onto different facilities to either enhance mobility or safety performance of active transportation modes. However, layered networks do intersect and specific median treatments exist to manage the confluence of these networks.

Median refuge islands provide a refuge for bicyclists to cross one direction of traffic at a time while restricting motor-vehicle through movements on crossroads designated as primary bicycle corridors or bike boulevards. The treatment minimizes impacts for bicyclists on the crossroad while prohibiting motor vehicle left turn movements from the cross street to eliminate conflicts.

Consider median refuge islands when one or more of the following occurs:

- Bike facilities cross a roadway with median restricted left turns.
- Bike facilities cross a moderate to high (motor vehicle) volume roadway, with intermediate motor-vehicle speeds
- Bike facilities cross a 4 lane divided highway.
- Separated or buffered bike facilities used on the cross street.
- There is a performance need to restrict motor vehicle through traffic on a bike route.
- Safety or mobility performance need of mainline cyclists exist for left turning movements onto a bike route or shared use pathway

Exhibit 1520-10 shows an example of a median refuge designed for cyclists. Design refuge areas between 4 and 5 feet wide (longitudinally with respect to the median), additional width may be needed if high volumes of cyclists exist or are anticipated at the crossing. Consider the types of cyclists and destinations when determining the median refuge length (lateral dimension with respect to the median) to adequately store the bicycle. Consider what locations may need to accommodate the length of a bicycle and trailer. The refuge area is to be in alignment with the approach and receiving lanes of the crossroad. In other situations the median refuge island may be designed for both pedestrians and bicycle users. When this is the case, design the median refuge predominately for the pedestrian as with midblock crossings (See Chapter 1510), note that additional lateral and longitudinal dimensions will be necessary.

1520.05 Additional Bicycle Design Requirements and Considerations

1520.05(1) Signing and Pavement Markings

Use the MUTCD and the *Standard Plans* for signing and pavement marking criteria. (See Chapter 1020 for additional information on signing and Chapter 1030 for information on pavement markings). Pavement marking and signing options for bicycle facilities are rapidly changing. Situations may exist where unique project concerns may necessitate innovative pavement markings or signage. Consult, as appropriate, the Federal Highway Administration (FHWA) MUTCD website for bicycle facilities for a listing of the current status of bicycle-related pavement markings and treatments:
http://www.fhwa.dot.gov/environment/bicycle_pedestrian/guidance/mutcd/index.cfm

HQ Traffic Office approval is necessary for traffic control devices not currently approved for use through the MUTCD.

1520.05(1)(a) Green Pavement Marking – Criteria for Consideration

Green -colored pavement markings are a traffic control device whose need must be demonstrated before use and documented with a design decision. The highest benefit of applying green colored pavement markings occurs where the potential conflicts exist between cyclists and other design users, or when other design users should yield to cyclists. Green colored pavement markings are only intended as a supplemental treatment for standard striping configurations for bicycle facilities.

The below criteria are provided when evaluating the need to apply green colored pavement markings.

1. Existing Bike Facilities – retrofitting an existing facility with green pavement may be considered when two or more of the following apply:
    a. It is the engineering judgment of the Region Traffic Engineer
    b. There is an existing traffic conflict area, such as bike lane crossing a motor vehicle turn lane, and there are one or more observed motor vehicle and bicyclist crashes in the last 5 years.
    c. The bike mode is a modal priority (see Chapter 1103), and there is a baseline or contextual need identified associated with increasing safety performance of the mode.
    d. When a bike route intersects a multilane highway, and the crossing is neither signalized nor a roundabout.
2. Changing of Bike Facility Type –consider green pavement markings when one or more of the following apply:
    a. It is the engineering judgment of the Region Traffic Engineer.
    b. A transition from a separated facility through a functional intersection or interchange area necessitates additional delineation to create a clear, visible, predictable and distinct travel path for bike users, and a bike signal or actuation device is not used.
    c. The facility type change does not substantively alter the configuration of an existing conflict area, and there are one or more observed motor vehicle and bicyclist crashes in the last 5 years at that conflict area.
3. New Bike Facility – Generally, the immediate application of green colored pavement on a new bike facility is discouraged until the need for increased safety performance is demonstrated. This said, consider green colored pavement when two or more of the following conditions exist:
    a. It is the engineering judgment of the Region Traffic Engineer
    b. The bike mode is a modal priority (see Chapter 1103), and there is a baseline or contextual need in which the application of green colored pavement markings is needed to meet the stated modal safety performance target (see Chapter 1101).
    c. The bike facility nodes and/or crossings are within 1 mile of activity centers, such as schools, libraries, colleges, etc.
    d. The bike facility crosses a motor vehicle free right turn to or from an interchange ramp.
    e. The bike facility is a bike route or bike boulevard (for definition, see NACTO's *Urban Bikeway Design Guide*).
    f. The state route is also a city street, and the city policy or municipal code requires green colored pavement markings as their standard.
    g. The bike facility is raised and curb separated, and the city engineer requests green colored pavement markings at either crossings or conflict areas.

1520.05(1)(b) Green Pavement Marking – Configuration

Use green pavement markings to supplement the conventional white bike lane striping as required by the MUTCD. Apply green colored pavement markings in conflict areas, consistent with what is shown in Exhibits 1520-7 through 1520-9. Preceding the conflict area, apply solid green 25-50 feet in length (see Exhibit 1520-11), use green ladder striping between the required white dotted striping through the extent of the conflict area, and apply solid green after the ladder striping for at least 25 ft but no more than 50 ft. If closely spaced conflict areas exist, it may be appropriate to carry solid green into the next conflict area as determined by the Region Traffic Engineer.

1520-11 Length of Solid Green Pavement Marking Preceding Conflict Area

Motor Vehicle Speed	Length of Solid Green Colored Pavement Marking Preceding Conflict Area
25 mph	25 ft
30 mph	30 ft
35 mph or more	35-50 ft
Interchange Ramps	See 1520.05(6)

Additional configurations or styles exist for the application of green colored pavement and can be used with the approval of HQ Traffic Office. Consider specifically when bike route continuity with a local agency's bike facilities is a concern.

1520.05(2) Drainage Grates and Manhole Covers


Locate drainage inlet grates and manhole covers to avoid bike lanes. When drainage grates or manhole covers are located in a bike lane, minimize the effect on bicyclists. Consider providing 3 feet of lateral clearance between the edge of a drainage inlet grate and the bike lane stripe, when practicable. Install and maintain grates and manhole covers level with the surface of the bike lane.

Provide drainage inlet grates on bicycle facilities that have openings narrow enough and short enough that bicycle tires will not drop into the grates. Replace existing grates that are not designed for bicycles: a WSDOT vanned grate, herringbone grate, or other grate with an opening 4 inches or less center to center and perpendicular to the direction of travel.

1520.05(3) At-Grade Railroad Crossings

Whenever a bike lane crosses railroad tracks, continue the crossing at least as wide as the bike lane. Use special construction and materials to keep the flangeway depth and width to a minimum. Wherever possible, design the crossing at right angles to the rails. Where a skew is unavoidable, widen the shoulder or bike lane, to permit bicyclists to cross at right angles. Exhibit 1520-12 shows options and details to consider for at-grade railroad crossings.

Exhibit 1520-12 At-Grade Railroad Crossings



Notes:


- Provide additional width at railroad crossings to allow bicyclists to choose their own crossing routes.
- When pedestrians are provided for, design as a shared-use path (see Chapters 1510 and 1515).

1520.05(4) Barrier and Railing

When the edge of the bike lane is within 5 feet of a barrier or railing, provide a barrier height a of 42 inches or more to reduce the potential for bicyclists to fall over the barrier (see Exhibit 1520-13). When the bicycle facility is adjacent to barrier, consider single slope barrier to mitigate for pedal movement conflicts other barrier designs.


On structures, the bridge railing type and height are part of the structure design. Contact the HQ Bridge and Structures Office for additional information. (See Chapter 720 for further considerations.)

Exhibit 1520-13 Barrier Adjacent to Bicycle Facilities



Bike Lane

Bike lane between edge of traveled way and barrier



Bike Lane With Sidewalk or Curb

Bike lane between edge of traveled way and sidewalk

Notes:

[1] Height does not apply to bridge railing. On structures, the bridge railing type and height are part of the structure design. (Contact the HQ Bridge and Structures Office for additional information.)

[2] Applies to bike lanes. Additional height is not needed for shared-use roadways.

1520.05(5) Transit Considerations

Transit and bicycle facilities can generate unique conflicts because of their typical position within the geometric cross section of the traveled way zone. Where public transport and cycling facilities meet, an integrated design that does not inconvenience either mode is desirable to meet the performance needs of these modes. Consider the following:

- Route the bike lane behind the transit stop location using a raised bike lane or outer separation for that spot location. Ensure the resulting outer separation provided for the transit stop meets the Americans with Disabilities Act (ADA) requirements (see Chapter 1510). Ensure signing and pavement markings are used to alert cyclists and pedestrians of the conflict area created with this design.
- Provide additional delineation in the bike lane to highlight the pedestrian and cyclist conflict, when separated buffered bike lanes and in-lane transit stops are used. Bus loading and other conflict areas will need to meet ADA requirements (see Chapter 1510) and those of the transit agency.
- Where bus operating speeds are low, consider a bus-bicycle shared lane with the transit agency.

Consider providing bicycle parking facilities near public transportation stops to improve accessibility performance needs.

1520.05(6) Interchange Considerations

Crossing bicycle facilities through an interchange functional area has a greater potential for conflict because of higher travel speeds and lane configurations. Interchange crossings designed in a manner similar to intersection crossings are more compatible to bicyclists. Exhibits 1520-14a through 1520-14d illustrate design options for bike facilities design through an interchange functional area. Interchanges can be special environments to evaluate the safety and mobility needs of the bike mode. The specific challenge is often the inclusion of motor vehicle free right turns to or from interchange ramps. The preferred configuration for bicycle safety performance at an interchange will not provide the motor vehicle free right turn, and will realign ramps to intersect perpendicular with the crossroad (see off ramp terminal in Exhibit 1520-14a). However, given the modal priorities and operational performance needs of those priorities, this configuration may not always be practicable.


In some cases, it is possible to align the bike facility to cross an off ramp with a more direct path for the bike crossing (see Exhibit 1520-14d). Breaking up the work load for the motor vehicle driver is one advantage of this configuration, similar to pedestrian treatments common in roundabout design. Shortening the crossing distance required for the bicyclist is another advantage with this configuration. Consider the inclusion of Rectangular Rapid Flashing Beacons (RRFB) or a refuge island when there are multiple travel lanes. This configuration may also require additional speed management (see Chapter 1103), signing or striping treatments on the ramp.

Other situations may dictate additional delineation parallel to and matching the length of the auxiliary lane provided at the ramp terminal as shown in Exhibit 1520-14b. This configuration can be coupled with additional signing preceding the motor vehicle merge, and additional separation or a buffer between the ramp's auxiliary lane and the through bike lane. The length of the motorized auxiliary lane will vary depending on speed and volume, so the length of green

markings shown in Exhibit 1520-11 may not adequately satisfy the delineation desired at these locations. Consult with the Region Traffic Engineer for determining the length of green pavement markings at interchange locations, when they are provided according to 1520.05(1)(a).

Exhibit 1520-14c provides a design option in which the bike lane merges with the sidewalk, and requires bicyclists to cross an interchange ramp at the pedestrian crossing. This configuration is ideal when bicycle mode is not identified as a modal priority, there is high motor vehicle ADT, there is a large intersection design vehicle, there is intermediate to high motor vehicle speeds, or when there are identification design users (see Chapter 1103) that suggests low experienced bicyclists will be present. Consider inclusion of an RRFB or a median refuge island when there are multiple lanes. Exhibits 1520-14b and 1520-14d also show the option of providing a bike ramp to the sidewalk. Providing options for cyclists at interchanges is encouraged, since the range of comfort among users is known to be diverse. Consult with the local agency regarding any prohibitions against bicyclists using the sidewalk that may negate the ability to implement this configuration.


Exhibit 1520-14a – Bike Facility Crossing On and Off Ramps



Notes:

- Adapted from the Draft *Recommended Design Guidelines to Accommodate Pedestrians and Bicycles at Interchanges*, ITE, unpublished.
- This exhibit is intended to illustrate options for bike facilities through interchange areas, and not intended to represent recommended practice for any other features including ADA criteria (See Chapter 1510 for ADA and pedestrian design).


Exhibit 1520-14b – Bicycle Facility Crossing Single Lane On Ramp



Notes:

- Adapted from the Draft *Recommended Design Guidelines to Accommodate Pedestrians and Bicycles at Interchanges*, ITE, unpublished.
- This exhibit is intended to illustrate options for bike facilities through interchange areas, and not intended to represent recommended practice for any other features including ADA criteria (See Chapter 1510 for ADA and pedestrian design).
- Consider both the speed of motorized vehicles and bicyclists when determining the length of weave and degree of taper for the bike lane.


Exhibit 1520-14c – Bicycle Facility Crossing Option for Dual Lane On-Ramp Configuration



Notes:

- Adapted from the Draft *Recommended Design Guidelines to Accommodate Pedestrians and Bicycles at Interchanges*, ITE, unpublished.
- This exhibit is intended to illustrate options for bike facilities through interchange areas, and not intended to represent recommended practice for any other features including ADA criteria (See Chapter 1510 for ADA and pedestrian design).

Exhibit 1520-14d – Bicycle Facility Crossing Option for Dual Off-Ramp



Notes:

- Adapted from the Draft *Recommended Design Guidelines to Accommodate Pedestrians and Bicycles at Interchanges*, ITE, unpublished
- This exhibit is intended to illustrate options for bike facilities through interchange areas, and not intended to represent recommended practice for any other features including ADA criteria (See Chapter 1510 for ADA and pedestrian design).

1520.05(7) Sight Triangles at Intersections and Conflict Areas

The visibility of all users is to be evaluated at intersections. Identifying sight triangles can help determine the optimal configuration of bicycle and pedestrian crossings. See Chapter 1310 for determining sight distance at an intersection, and Chapter 1340 for sight distance at road approaches near midblock crossings. Visibility is impacted by both speed and the configuration of the intersection. There are multiple benefits in multimodal intersection configurations to proactively manage motorized vehicle speeds (see Chapter 1103 for speed reducing traffic calming treatments) at intersection locations, rather than widening the intersection and/or removing elements from the roadside or streetside zone to obtain the needed sight distance. The primary objective at intersections and interchanges is to create a clear, distinct, and predictable travel path for all users through the intersection.

1520.05(8) Maintenance Considerations

Consult with all maintenance jurisdictions for partnering opportunities and clearly understand which jurisdiction will be responsible for specific elements of the bike facility maintenance. Some maintenance jurisdictions may be better equipped to maintain the bike facility than others. Certain bike facilities, like the raised and curb separated, clearly fall within the jurisdictional authority of an incorporated city (see chapters 1230 and 1600 for more information). For other facility types it may be more advantageous to discuss the capabilities of each maintenance jurisdiction, and develop a maintenance agreement (see Chapter 301).

It is important to obtain information from maintenance regarding the facility type and dimensioning, and discuss methods for maintaining the facility. The Maintenance Owner's Manual (See Chapter 301) is suggested to contain frequency, equipment needs and material types necessary for the continual maintenance of facility features, including but not limited to:

- Sweeping
- Snow removal
- Striping and pavement markings
- Signing

1520.06 Documentation

Document the type of bike facility employed or changed in section 5 of the Basis of Design. Dimensions chosen for the facility are documented on design parameter sheets.

1520.07 References

1520.07(1) Federal/State Laws and Codes

Americans with Disabilities Act of 1990 (ADA)

23 Code of Federal Regulations (CFR) Part 652, Pedestrian and Bicycle Accommodations and Projects

Revised Code of Washington (RCW), Chapter 35.75, Streets – Bicycles – Paths
http://apps.leg.wa.gov/rcw/default.aspx?cite=35.75

RCW 46.04, Definitions
http://apps.leg.wa.gov/rcw/default.aspx?cite=46.04

RCW 46.61, Rules of the road
http://apps.leg.wa.gov/rcw/default.aspx?cite=46.61\

RCW 46.61.710, Mopeds, electric-assisted bicycles – General requirements and operation
http://apps.leg.wa.gov/rcw/default.aspx?cite=46.61.710

RCW 47.26.300, Bicycle routes – Legislative declaration
http://apps.leg.wa.gov/rcw/default.aspx?cite=47.26.300

1520.07(2) Supporting Information

Urban Bikeway Design Guide, NACTO, current edition (WSDOT endorsed)
http://nacto.org/publication/urban-bikeway-design-guide/

Guide for the Development of Bicycle Facilities, AASHTO, current edition
https://bookstore.transportation.org/collection_detail.aspx?ID=116

Separated Bike Lane Planning and Design Guide, FHWA, current edition
http://www.fhwa.dot.gov/environment/bicycle_pedestrian/publications/separated_bikelane_pdg/page00.cfm

Bicycle Parking Guidelines, Association of Pedestrian and Bicycle Professionals, current edition
http://www.apbp.org/?page=Publications

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)
www.wsdot.wa.gov/publications/manuals/mutcd.htm

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT
www.wsdot.wa.gov/publications/manuals/m21-01.htm

Understanding Flexibility in Transportation Design – Washington, WSDOT, 2005
www.wsdot.wa.gov/research/reports/600/638.1.htm

Selecting Roadway Design Treatments to Accommodate Bicycles, USDOT, Federal Highway Administration (FHWA), 1994

NCHRP Report 766: Recommended Bicycle Lane Widths for Various Roadway Characteristics, Transportation Research Board of the National Academies, 2014
http://onlinepubs.trb.org/onlinepubs/nchrp/nchrp_rpt_766.pdf

NCHRP Report 500 Volume 18: A Guide for Reducing Collisions Involving Bicycles, Transportation Research Board of the National Academies, 2006
http://onlinepubs.trb.org/onlinepubs/nchrp/nchrp_rpt_500v18.pdf

Four Types of Cyclists?, Dill, Jennifer, and Nathan McNeil, Transportation Research Record: Journal of the Transportation Research Board 2387.1 (2013): 129-138.

Recommended Design Guidelines to Accommodate Pedestrians and Bicycles at Interchanges, ITE, unpublished.
http://ecommerce.ite.org/IMIS/ItemDetail?iProductCode=RP-039

Montgomery County Bicycle Planning Guidance, Montgomery County Department of Transportation, 2014.
http://www.montgomeryplanning.org/transportation/bikeways/documents/FINALBicyclePlanningGuidance.pdf

Separated Bike Lane Planning and Design Guide, Massachusetts Department of Transportation (MassDOT), 2015
http://www.massdot.state.ma.us/highway/DoingBusinessWithUs/ManualsPublicationsForms/SeparatedBikeLanePlanningDesignGuide.aspx

Chapter 1600 Roadside Safety

1600.01 General
1600.02 Clear Zone
1600.03 Mitigation Guidance
1600.04 Medians
1600.05 Other Roadside Safety Features
1600.06 Documentation
1600.07 References

1600.01 General

Roadside safety addresses the area outside the roadway and is an important component of total highway design. There are numerous reasons why a vehicle leaves the roadway, including driver error and behaviors. Regardless of the reason, a roadside design can reduce the severity and subsequent consequences of a roadside encroachment. From a crash reduction and severity perspective, the ideal highway has roadsides and median areas that are flat and unobstructed by objects. It is also recognized that different facilities have different needs and considerations, and these issues are considered in any final design.

It is not possible to provide a clear zone free of objects at all locations and under all circumstances. The engineer faces many tradeoffs in design decision-making, balancing needs of the environment, right of way, and different modes of transportation. The fact that recommended values for guardrail are presented in this chapter does not require the Washington State Department of Transportation to modify or upgrade locations to meet the specified or new criteria; those locations are addressed as appropriate through the priority array. On some projects, an analysis of roadside crash potential will be needed. See Chapter 321.

Elements such as sideslopes, fixed objects, and water are features that a vehicle might encounter when it leaves the roadway. These features present varying degrees of deceleration to the vehicle and its occupants. Unfortunately, geography and economics do not always allow ideal highway conditions. The mitigative measures to be taken depend on the probability of a crash occurring, the likely severity, and the priority array.

In order of priority, the mitigative measures the Washington State Department of Transportation (WSDOT) uses are:

1. Remove
2. Redesign (a fixed object) so it can be traversable
3. Relocate
4. Reduce impact severity (using breakaway features or making it traversable)
5. Shielding with a traffic barrier; or
6. Delineate (if the previous options are not appropriate or feasible)

Factors for selecting a mitigative measure include, but may not be limited to:

- Cost (initial and life cycle costs)
- Maintenance needs
- Crash severity potential

Use traffic barriers when other measures cannot reasonably be accomplished and conditions are appropriate based on an engineering analysis. See Chapter 1610 for additional information on traffic barriers.

1600.02 Clear Zone

A clear roadside border area is a primary consideration when analyzing potential roadside and median features (as defined in 1600.03). The intent is to provide as much clear, traversable area for a vehicle to recover as practicable given the function and context of the roadway and the potential tradeoffs. The Design Clear Zone is used to evaluate the adequacy of the existing clear area and proposed modifications of the roadside. When considering the placement of new objects along the roadside or median, evaluate the potential for impacts and try to select locations with the least likelihood of an impact by an errant vehicle.

In situations where the Design Clear Zone is beyond WSDOT right of way, evaluate options on a case-by-case basis. Consider the nature of the objects within the Design Clear Zone, the roadway geometry, traffic volume, and crash history. Coordinate with adjacent property owners when proposed options include any work beyond WSDOT right of way. At a minimum, provide clear zone to the limits of the WSDOT right of way.

Clear zone is measured from the edge of the through traveled way. Auxiliary lanes longer than 400 ft generally operate the same as a through lane and should be considered. Any project that changes the relationship between the through lane and the roadside by widening or realignment has changed the clear zone and requires evaluation.

1600.02(1) Design Clear Zone on Limited Access State Highways and Other State Highways Outside Incorporated Cities and Towns

Use the Design Clear Zone Inventory form (Exhibit 1600-3) to identify potential features to be mitigated and propose corrective actions.

Guidance for establishing the Design Clear Zone for highways outside incorporated cities is provided in Exhibit 1600-2. This guidance also applies to limited access facilities within the city limit. Providing a clear recovery area that is consistent with this guidance does not require any additional documentation. However, there might be situations where it is not practicable to provide these recommended distances. In these situations, document the decision as a Design Analysis as discussed in Chapter 300.

There is flexibility in establishing the Design Clear Zone in urbanized areas where operating speeds are 35 mph or less. To achieve this flexibility, use a Design Analysis to establish the Design Clear Zone that presents the tradeoffs associated with the decision. Provide information on the benefits and impacts of the Design Clear Zone selected in the Design Analysis, including safety, aesthetics, the environment, economics, modal needs, and access control. Although not a WSDOT policy document on clear zone, Chapter 10 of the AASHTO *Roadside Design Guide* provides information to consider when performing a Design Analysis in urban areas.


In curbed sections, and where applicable (e.g. parking), provide an 18-inch operational offset beyond the face of curb for lateral clearance to accommodate opening car doors or large side mirrors.

1600.02(2) Design Clear Zone Inside Incorporated Cities and Towns

For managed access state highways within an urban area, it might not be practicable to provide the Design Clear Zone distances shown in Exhibit 1600-2. Roadways within an urban area generally have curbs and sidewalks and might have objects such as trees, poles, benches, trash cans, landscaping, and transit shelters along the roadside.

For projects on city streets as state highways that include work in those areas that are the city's responsibility and jurisdiction (see Exhibit 1600-1), design the project using the city's development/design Standards. The standards adopted by the city must meet the requirements set by the City Design Standards Committee for all arterial projects, bike projects, and federal-aid projects. See the Local Agency Guidelines Chapter 42 for more information on this Committee.

Exhibit 1600-1 City and State Responsibilities and Jurisdictions



Roadway with Raised Median (Landscaped)

1600.02(2)(a) Roadside and Median

For managed access state highways inside incorporated cities, it is the city's responsibility to establish an appropriate Design Clear Zone in accordance with guidance contained in the City and County Design Standards (*Local Agency Guidelines*, Chapter 42.) Exhibit 1600-1 shows an example of state and city responsibilities and jurisdictions. Document the Design Clear Zone established by the city in the Design Documentation Package. Have the responsible transportation official from the city (e.g., City Engineer) document the Design Clear Zone, and their acknowledgement and acceptance of the design and maintenance responsibilities for project roadsides and medians, in a letter addressed to WSDOT, and file this letter as part of the local agency coordination in the Design Documentation Package. Respond to the sender by letter acknowledging receipt.

1600.02(3) Design Clear Zone and Calculations

Use Exhibit 1600-2 to determine the Design Clear Zone for posted speed, sideslope, and traffic volume at any given location. Note that there are no clear zones distances in the table for 3H:1V fill slopes. Although fill slopes between 4H:1V and 3H:1V are considered traversable if free of fixed objects, these slopes are defined as nonrecoverable slopes. A vehicle might be able to begin recovery on the shoulder, but likely will not be able to further this recovery until reaching a flatter area (4H:1V or flatter) at the toe of the slope. Under these conditions, the Design Clear

Zone distance is called a recovery area. The method used to calculate the recovery area and an example are shown in Exhibit 1600-4.

For ditch sections, the following criteria determine the Design Clear Zone:

(a) For ditch sections with foreslopes 4H:1V or flatter (see Exhibit 1600-5, Case 1, for an example), the Design Clear Zone distance is the greater of the following:

- The Design Clear Zone distance for a 10H:1V cut section based on speed and the average daily traffic (ADT); or
- A horizontal distance of 5 feet beyond the beginning of the backslope.

When a backslope steeper than 3H:1V continues for a horizontal distance of 5 feet beyond the beginning of the backslope, it is not necessary to use the 10H:1V cut slope criteria.

(b) For ditch sections with foreslopes steeper than 4H:1V and backslopes steeper than 3H:1V, the Design Clear Zone distance is 10 feet horizontal beyond the beginning of the backslope (see Exhibit 1600-5, Case 2, for an example).

(c) For ditch sections with foreslopes steeper than 4H:1V and backslopes 3H:1V or flatter, the Design Clear Zone distance is the distance established using the recovery area formula (see Exhibit 1600-4; also see Exhibit 1600-5, Case 3, for an example).

1600.03 Mitigation Guidance

There are three general categories of features to be mitigated: sideslopes, fixed objects, and water. This section provides guidance for determining when these objects present a significant risk to an errant motorist. For each case, the following conditions need added consideration:

- Locations with high expected crash frequency.
- Locations with pedestrian and bicycle usage (See Chapters 1510, Pedestrian Facilities, 1515, Shared-Use Paths, and 1520, Roadway Bicycle Facilities).
- Playgrounds, monuments, and other locations with high social or economic value.
- Redirectional landforms, also referred to as earth berms, were installed to mitigate objects located in depressed medians and at roadsides. They were constructed of materials that provided support for a traversing vehicle. With slopes in the range of 2H:1V to 3H:1V, they were intended to redirect errant vehicles. The use of redirectional landforms has been discontinued as a means for mitigating fixed objects. Where redirectional land forms currently exist as mitigation for a fixed object, provide designs where the landforms, and the feature(s) they were intended to mitigate, are removed, relocated, made crashworthy, or shielded with barrier. Landforms may be used to provide a smooth surface at the base of a rock cut slope.

The use of a traffic barrier for features other than those described below requires justification.

1600.03(1) Side Slopes

1600.03(1)(a) Fill Slopes

Fill slopes can present a risk to an errant vehicle with the degree of severity dependent upon the slope and height of the fill. Providing fill slopes that are 4H:1V or flatter can mitigate this condition. If flattening the slope is not feasible or cost-effective, the installation of a barrier might be appropriate. Exhibit 1600-6 represents a selection procedure used to determine whether an existing fill sideslope constitutes a condition for which a barrier is a cost-effective mitigation. The curves are based on the severity indexes and represent the points where total costs associated with a traffic barrier are equal to the predicted cost of crashes over the service life for selected slope heights without traffic barrier. If the ADT and height of fill intersect on the "Barrier Recommended" side of the embankment slope curve, then provide a barrier if flattening the slope is not feasible or cost-effective.

Do not use Exhibit 1600-6 for slope design. Design slopes consistent with guidance in Chapter 1239, evaluating designs with clear, traversable slopes before pursuing a barrier option. Also, if Exhibit 1600-6 indicates that barrier is not recommended at an existing slope, that result is not justification for a Design Analysis. For example, if the ADT is 4,000 and the embankment height is 10 feet, barrier might be cost-effective for a 2H:1V slope, but not for a 2.5H:1V slope. This process only addresses the potential risk of exposure to the slope. Obstacles on the slope can compound the condition. Where barrier is not cost-effective, use the recovery area formula to evaluate fixed objects on critical fill slopes less than 10 feet high.

1600.03(1)(b) Cut Slopes

A traversable cut slope reduces crash potential. The exception is a rock cut with a rough face that might cause vehicle snagging rather than providing relatively smooth redirection.

Analyze the location and evaluate the roadside characteristics, crash potential, and other benefits of treatment of rough rock cuts located within the Design Clear Zone. Conduct an individual investigation for each rock cut or group of rock cuts. A cost-effectiveness analysis that considers the consequences of doing nothing, removal, smoothing of the cut slope, and other viable options to reduce the severity of the condition can be used to determine the appropriate treatment. Some potential options are:

- Graded landform along the base of a rock cut
- Flexible barrier
- More rigid barrier
- Rumble strips

1600.03(2) Fixed Objects

Use engineering judgment when considering the following objects for mitigation:

- Wooden poles or posts with cross-sectional areas greater than 16 square inches that do not have breakaway features.
- Signs, illumination, cameras, weather stations, and other items mounted on nonbreakaway poles, cantilevers, or bridges.
- Trees with a diameter of 4 inches or more, measured at 6 inches above the ground surface.

- Fixed objects extending above the ground surface by more than 4 inches; for example, boulders, concrete bridge rails, signal/electrical/ITS cabinets, piers, and retaining walls.
- Drainage items, such as culvert and pipe ends.

1600.03(2)(a) Trees

When evaluating new plantings or existing trees, consider the maximum allowable diameter of 4 inches, measured at 6 inches above the ground when the tree has matured. When removing trees within the Design Clear Zone, complete removal of stumps is preferred. However, to avoid significant disturbance of the roadside vegetation, larger stumps may be mitigated by grinding or cutting them flush to the ground and grading around them.

Removal of trees may reduce the impacts of roadway departure, and clear zone encroachments. It is recognized that different facilities have different needs and considerations, and these issues are considered in any final design. For instance, removal of trees within the Design Clear Zone may not be desirable in urban areas, or in other land use contexts such as within areas having high level of non-motorized uses, a forest, park, or within a scenic and recreational highway. In these situations, analyze crash reports' contributing factors to determine whether roadside vegetation is contributing to the severity of crashes. If large vegetation is removed, replace with shrubs or groundcover or consult guidance contained in established vegetation management plans or corridor plans. Additional guidance for maintenance of roadside vegetation can be found in the Memorandum of Understanding between the US Forest Service and WSDOT, *Highways Over National Forest Lands*, dated July 2002. In incorporated cities, refer to guidance in 1600.02(2).

1600.03(2)(b) Mailboxes

For mailboxes located within the Design Clear Zone, provide supports and connections as shown in the *Standard Plans*. The height from the ground to the bottom of the mailbox is 3 feet 3 inches. This height may vary from 3 feet 3 inches to 4 feet if requested by the mail carrier. If the desired height is to be different from 3 feet 3 inches, provide the specified height in the contract plans. (See Exhibit 1600-7 for installation guidelines.) Coordinate with homeowners when upgrading mailboxes.

In urban areas where sidewalks are prevalent, contact the postal service to determine the most appropriate mailbox location. Locate mailboxes on limited access highways in accordance with Chapter 530, Limited Access. A turnout, as shown in Exhibit 1600-7, is not needed on limited access highways with shoulders of 6 feet or more where only one mailbox is to be installed. On managed access highways, mailboxes are to be on the right-hand side of the road in the postal carrier's direction of travel. Avoid placing mailboxes along high-speed, high-volume highways. Locate Neighborhood Delivery and Collection Box Units outside the Design Clear Zone.

1600.03(2)(c) Culvert Ends

Provide a traversable end treatment when the culvert end section or opening is on the roadway sideslope and within the Design Clear Zone. This can be accomplished for small culverts by beveling the end to match the sideslope, with a maximum of 4 inches extending out of the sideslope.

Bars might be needed to provide a traversable opening for larger culverts. Place bars in the plane of the culvert opening in accordance with the *Standard Plans* when:

- Single cross-culvert opening exceeds 40 inches, measured parallel to the direction of travel.
- Multiple cross-culvert openings that exceed 30 inches each, measured parallel to the direction of travel.
- Culvert approximately parallel to the roadway that has an opening exceeding 24 inches, measured perpendicular to the direction of travel.

Bars are permitted where they will not significantly affect the stream hydraulics and where debris drift is minor. Consult the region Maintenance Office to verify these conditions. If debris drift is a concern, consider options to reduce the amount of debris that can enter the pipe (see the *Hydraulics Manual*). Other treatments are extending the culvert to move the end outside the Design Clear Zone or installing a traffic barrier.

1600.03(2)(d) Signposts

Whenever possible, locate signs behind the standard run, but not the end terminals, of existing or planned traffic barrier installations to eliminate the need for breakaway posts, and place them such that the sign face is behind the barrier. When barrier is not present, use terrain features where practicable to reduce the likelihood of an errant vehicle striking the signposts. (See Chapter 1020 for additional information regarding the placement of signs.) Use the MUTCD to guide placement of the warning sign.

Signposts with cross-sectional areas greater than 16 square inches that are within the Design Clear Zone and not located behind a barrier are to have breakaway features as shown in the *Standard Plans*.

Sign bridges and cantilever sign supports are designed for placement outside the Design Clear Zone or must be shielded by barrier.

1600.03(2)(e) Traffic Signal Standards/Posts/Supports

Breakaway signal posts generally are not feasible or desirable, and barrier is not generally an option due to constraints that are typically found at intersection locations. To reduce potential for contact with vehicles, or impede the movement of pedestrian or bicycle traffic in the vicinity, locate posts in accordance with Chapter 1330.

For ramp meter systems, single lane ramp meters use breakaway Type RM signal standards. Multilane ramp meters normally use Type II signal standards, which must either be located outside of clear zone for all adjacent roadways or be protected by some type of barrier.

1600.03(2)(f) Fire Hydrants

Fire hydrants are typically allowed on WSDOT right of way by franchise or permit. Fire hydrants that are made of cast iron can be expected to fracture on impact and can therefore be considered a breakaway device. Any portion of the hydrant that will not be breakaway must not extend more than 4 inches above the ground. In addition, the hydrant must have a stem that will shut off water flow in the event of an impact. Provide mitigation to address potential vehicle impact with hydrant types not expected to fracture on impact.

1600.03(2)(g) Utility Poles

Since utilities often share the right of way, utility objects such as poles are often located along the roadside. It is normally undesirable or infeasible to install barrier for all of these objects, so

mitigation is usually in the form of relocation (underground or to the edge of the right of way) or delineation. In some instances where there is a history of impacts with poles and relocation is not possible, a breakaway design might be appropriate.

Evaluate roadway geometry and crash history as an aid in determining locations that exhibit the greatest need. Contact the Headquarters (HQ) Design Office for information on breakaway features. Coordinate with the HQ Utilities Unit when appropriate.

For policy and guidance on locating utility poles along state highways, also see Chapter 9 of the *Utilities Manual*. Document the determination of appropriate mitigative measures and coordination with the region Utilities Office.

1600.03(2)(h) Light Standards

Provide breakaway light standards unless fixed light standards can be justified. Fixed light standards may be appropriate in areas of extensive pedestrian concentrations, such as adjacent to bus shelters. Document the decision to use fixed bases in the Design Documentation Package.

1600.03(3) Water

Water with a depth of 2 feet or more and located with a likelihood of encroachment by an errant vehicle is to be considered for mitigation.

Perform a benefit-cost analysis that considers the consequences of doing nothing versus installing a longitudinal barrier to determine the appropriate treatment (see Chapter 321 for more information). For fencing considerations along water features, see Chapter 560.

1600.04 Medians

Median barriers are normally used on limited access, multilane, high-speed, high-volume highways. These highways generally have posted speeds of 45 mph or higher. Median barrier is not normally placed on collectors or other state highways that do not have limited access control. Providing access through median barrier results in openings, therefore, end treatments are needed.

Provide median barrier on full access control multilane highways with median widths of 50 feet or less and posted speeds of 45 mph or higher. Consider median barrier on highways with wider medians or lower posted speeds when there is a history of cross-median crashes. Contact the HQ Design Office for more information.

Provide a left-side shoulder when installing median barrier using width criteria given in Chapter 1230. Consider a wider shoulder area where the barrier might cast a shadow on the roadway and hinder the melting of ice. (See Chapter 1239 for additional criteria for placement of median barrier, Chapter 1610 for information on the types of barriers that can be used, and Chapter 1260 for lateral clearance on the inside of a curve to provide the needed stopping sight distance.) Consider the need to accommodate drainage as a result of the addition of median barrier treatments.

When median barrier is being placed in an existing median, identify the existing crossovers and enforcement observation points. Provide the needed median crossovers in accordance with Chapter 1370, considering enforcement needs. Chapter 1410 provides guidance on HOV enforcement.

1600.05 Other Roadside Safety Features

1600.05(1) Rumble Strips

Rumble strips are milled grooves or rows of raised pavement markers placed perpendicular to the direction of travel to alert inattentive drivers.

Depending on the pavement condition or type, rumble strips may have an adverse impact on pavement longevity or performance. Consult with the Region Materials Engineer to determine installation procedure and verify that the pavement structure is adequate. Installation should also be avoided in open-graded pavements. In locations where the pavement structure or type would preclude rumble strip installation, mill out a strip of the existing pavement, fill with hot mix asphalt (per Region Materials Engineer specification), and install new rumble strips in this strip. When installing both rumble strips and recessed lane markers, follow the Standard Plan to avoid overlapping the grindings.

Installing rumble strips in bituminous surface treatment (or BST) or other thin surface treatments can expose pavement structure and lead to delamination. In new rumble strip locations where BST will be applied on an HMA pavement, install the rumble strips in the HMA pavement before placing the BST. In existing rumble strip locations, note that a single application of BST on top of an existing rumble strip installation typically results in satisfactory rumble strip depth. Where rumble strips currently exist and an additional BST application is contemplated, evaluate whether the depth of the grooves following paving will support their continuing function to alert drivers. If not, or in the case of an HMA overlay, it may be necessary to remove existing rumble strips and install new ones.

Provide an offset to the longitudinal paving joint so that rumble strips are not ground into the joint where practicable.

For additional guidance on surface preparation and pavement stability, refer to the WSDOT Pavement Policy.

The noise created when vehicle tires contact a rumble strip can result noise in complaints from nearby residents. This commonly is a result from incidental contact where the vehicle might not have been heading toward a crash. For example, left-turning or passing vehicles, along with the off-tracking of large trucks or trailers may result in incidental contact with centerline rumble strips. With some specific attention to details, some of these contacts can be significantly reduced by discontinuing the rumble strip installations through intersections or frequently used road approaches. For roadways with limited passing opportunities, evaluate the frequency and position of neighboring residents and site-specific crash experience to determine if the rumble strip should be discontinued in a potential passing location. Attention to horizontal curvature, curve widening, and large-vehicle usage may help identify locations where the rumble strips may need to be discontinued through a tight radius curve. New rumble strip designs that reduce noise are under investigation. Contact HQ Design for more information.

There are three kinds of rumble strips: roadway, shoulder, and centerline, and each are described in the following sections.

1600.05(1)(a) Roadway Rumble Strips

Roadway rumble strips are placed transversely in the traveled way to alert drivers who are approaching a change of roadway condition or object that requires substantial speed reduction

or other maneuvering. Some locations where advance roadway rumble strips may be placed include:

- Stop-controlled intersections
- Port of entry/customs stations
- Lane reductions where crash history shows a pattern of driver inattention, and
- Horizontal alignment changes where crash history shows a pattern of driver inattention.

They may also be placed at locations where the character of the roadway changes, such as at the end of a freeway.

Contact the HQ Design Office for additional guidance on the design and placement of roadway rumble strips.

Document decisions to use roadway rumble strips in the Design Documentation Package.

1600.05(1)(b) Shoulder Rumble Strips

Shoulder rumble strips (SRS) are placed parallel to the traveled way just beyond the edge line to warn drivers they are entering a part of the roadway not intended for routine traffic use. Shoulder rumble strips are effective in reducing run-off-the-road crashes when the contributing circumstances are human factors related, such as inattention, apparently fatigued, or apparently asleep.

When shoulder rumble strips are used, discontinue them where no edge stripe is present, such as at intersections and where curb and gutter are present. Discontinue shoulder rumble strips where shoulder driving is allowed.

Shoulder rumble strip patterns vary depending on the likelihood of bicyclists being present along the highway shoulder and whether they are placed on divided or undivided highways. Rumble strip patterns for undivided highways are shallower and may be narrower than patterns used on divided highways. They also provide gaps in the pattern, providing opportunities for bicycles to move across the pattern without having to ride across the grooves. There are four shoulder rumble strip patterns. Consult the Standard Plans for the patterns and construction details.

1. Divided Highways

Install shoulder rumble strips on both the right and left shoulders of rural Interstate highways. Consider them on both shoulders of rural divided highways. Use the Shoulder Rumble Strip Type 1 pattern on divided highways.

Shoulder rumble strips on rural Interstate highways may be omitted under any of the following conditions:

- When another project scheduled within two years of the proposed project will overlay or reconstruct the shoulders or will use the shoulders for detours.
- When a pavement analysis determines that installing shoulder rumble strips will result in inadequate shoulder strength.
- When overall shoulder width will be less than 4 feet wide on the left and 6 feet wide on the right.

Document the decision to omit rumble strips in a Design Analysis (see Chapter 300.)

2. Undivided Highways

Consider installing shoulder rumble strips on undivided highways during centerline rumble strip installation or rehabilitation. Apply the following criteria in evaluating whether or not to install shoulder rumble strips.

- Consider the impact on bicycle riders, especially on bike touring routes or other routes where bicycle events are regularly held.
- Use on rural highways only.
- Determine that shoulder pavement is structurally adequate to support milled rumble strips.
- Posted speed is 45 mph or higher.
- Provide for at least 4 feet of usable shoulder between the rumble strip and the outside edge of shoulder. If guardrail or barrier is present, increase the dimension to 5 feet of usable shoulder. Field-verify these dimensions.
- Preliminary evaluation indicates a run-off-the-road crash experience of approximately 0.6 crashes per mile per year. (This value is intended to provide relative comparison of crash experience and is not to be used as absolute guidance on whether rumble strips are appropriate.)
- Do not place shoulder rumble strips on downhill grades exceeding 4% for more than 500 feet in length along routes where bicyclists are frequently present.
- Consider approaches to reducing incidental contact where applicable (see Section 1600.05(1)).
- An engineering analysis indicates a run-off-the-road crash experience considered correctable by shoulder rumble strips.

Consult the region and Headquarters Bicycle and Pedestrian Coordinators to determine bicycle usage along a route, and involve them in the decision-making process when considering rumble strips on bike touring routes. When bicycle traffic on the shoulder is determined to be high, the Shoulder Rumble Strip Type 4 pattern is used. Document decisions to continue or discontinue shoulder rumble strip usage.

Consult the following website for guidance on conducting an engineering analysis:
http://www.wsdot.wa.gov/Design/Policy/RoadsideSafety.htm

1600.05(1)(c) Centerline Rumble Strips

Centerline rumble strips are placed on the centerline of undivided highways to alert drivers that they are entering the opposing lane. They are installed with no differentiation between passing permitted and no passing areas. Refresh pavement markings when removed by centerline rumble strips.

Centerline rumble strips are evaluated using a programmatic approach, starting with a preliminary review of each rural undivided highway as a potential installation site. The HQ Design Office conducts the preliminary review, evaluating cross-centerline crash history and pavement width. A list of sites is generated from this review and periodically updated and distributed to the regions for a more detailed analysis of each site. The presence of a particular site on the preliminary list does not imply that rumble strips must be installed.

The preliminary review conducted in the Design Office does not assess pavement structure; traffic volume and composition; type and volume of nonmotorized users; or proximity to roadside residents. Region project development staff are expected to evaluate these items, and to field-verify roadway widths and appropriate project limits. The final determination about the appropriateness of centerline rumble strips is the responsibility of region project development staff. Although these decisions are made in the region, it is important that they be evaluated in a consistent manner from region to region. Evaluate the following criteria in determining the appropriateness of centerline rumble strips.

Review the crash history to determine the frequency of crashes with human factors contributing circumstances such as inattention, apparently fatigued, apparently asleep, over the centerline, or on the wrong side of the road. These types of cross-centerline crashes are considered to be correctable with centerline rumble strips. Centerline rumble strips are most appropriate on rural roads, but with special consideration, may also be appropriate for urban roads. Some concerns specific to urban areas are more residents impacted by noise in more densely populated areas, the frequent need to interrupt the rumble strip pattern to accommodate left-turning vehicles, and a reduced effectiveness at lower speeds (35 mph and below). Centerline rumble strips are not appropriate where two way left-turn lanes exist.

Do not install centerline rumble strips when the combined lane and shoulder widths in either direction are less than 12 feet. See Chapter 1230 for guidance on lane and shoulder widths.

Where the combined lane and shoulder width is 14 feet or less, consider the level of bicycle and pedestrian use along the route When drivers shift their lane position away from centerline to avoid the rumble strips, they are moving closer to pedestrians and bicyclists on the shoulder. Also consider the roadside characteristics and the potential for a lane position adjustment to result in a run-off-the-road event, evaluating clear zone width along the route. Balance these issues with the frequency and severity of cross-centerline crashes.in the decision to install centerline rumble strips.

Noise for Roadside Residents

Consider approaches to reducing incidental contact where applicable (see 1600.05).

1600.05(2) Headlight Glare Considerations

Headlight glare from opposing traffic is most common between opposing main line traffic. Glare screens can be used to mitigate this condition. Other conditions for which glare screen might be appropriate are:

- Between a highway and an adjacent frontage road or parallel highway, especially where opposing headlights might seem to be on the wrong side of the driver.
- At an interchange where an on-ramp merges with a collector-distributor and the ramp traffic might be unable to distinguish between collector and main line traffic.
- Where headlight glare is a distraction to adjacent property owners. Playgrounds, ball fields, and parks with frequent nighttime activities might benefit from screening if headlight glare interferes with these activities.

Glare screening is normally not justifiable where the median width exceeds 20 feet, and the ADT is less than 20,000 vehicles per day. Document the decision to use glare screening using the following criteria:

- Higher frequency of night crashes compared to similar locations or based on statewide experience.
- Higher than normal ratio of night-to-day crashes.
- Unusual distribution or concentration of nighttime crashes.
- Over-representation of older drivers in night crashes.
- Combination of horizontal and vertical alignment, particularly where the roadway on the inside of a curve is higher than the roadway on the outside of the curve.
- Direct observation of glare.
- Public complaints concerning glare.

There are currently three basic types of glare screen available: chain link (see the *Standard Plans*), vertical blades, and concrete barrier (see Exhibit 1600-8).

When the glare is temporary (due to construction activity), consider traffic volumes, alignment, duration, presence of illumination, and type of construction activity. Glare screen may be used to reduce rubbernecking associated with construction activity, but less expensive methods, such as plywood that seals off the view of the construction area, might be more appropriate.

1600.06 Documentation

Refer to Chapter 300 for design documentation requirements.

1600.07 References

1600.07(1) Federal/State Laws and Codes

Revised Code of Washington (RCW) 47.24.020(2), Jurisdiction, control

RCW 47.32.130, Dangerous objects and structures as nuisances

1600.07(2) Design Guidance

Highway Safety Manual, AASHTO

Local Agency Guidelines (City and County Design Standards), M 36-63, WSDOT

Roadside Design Guide, AASHTO, 2011

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT

1600.07(3) Supporting Information

A Policy on Geometric Design of Highways and Streets (Green Book), AASHTO, 2011

Understanding Design Clear Zone – This e-learning course for WSDOT employees covers how to determine the appropriate Design Clear Zone for recoverable and nonrecoverable slopes as well as ditches. Request this training via the web-based Learning Management System.

Highways Over National Forest Lands, MOU, 2013, US Forest Service and WSDOT, www.wsdot.wa.gov/publications/manuals/m22-50.htm

Utilities Manual, M 22-87, WSDOT. Chapter 9 provides Control Zone guidance for utilities in the WSDOT right of way.

Exhibit 1600-2 Design Clear Zone Distance Table

Posted Speed (mph)	Average Daily Traffic	Cut Section (Backslope) (H:V)						Fill Section (H:V)					
		3:1	4:1	5:1	6:1	8:1	10:1	3:1	4:1	5:1	6:1	8:1	10:1
35 or Less		The Design Clear Zone Distance is 10 ft											
40	Under 250	10	10	10	10	10	10	*	13	12	11	11	10
	251 – 800	11	11	11	11	11	11	*	14	14	13	12	11
	801 – 2,000	12	12	12	12	12	12	*	16	15	14	13	12
	2,001 – 6,000	14	14	14	14	14	14	*	17	17	16	15	14
	Over 6,000	15	15	15	15	15	15	*	19	18	17	16	15
45	Under 250	11	11	11	11	11	11	*	16	14	13	12	11
	251 – 800	12	12	13	13	13	13	*	18	16	14	14	13
	801 – 2,000	13	13	14	14	14	14	*	20	17	16	15	14
	2,001 – 6,000	15	15	16	16	16	16	*	22	19	17	17	16
	Over 6,000	16	16	17	17	17	17	*	24	21	19	18	17
50	Under 250	11	12	13	13	13	13	*	19	16	15	13	13
	251 – 800	13	14	14	15	15	15	*	22	18	17	15	15
	801 – 2,000	14	15	16	17	17	17	*	24	20	18	17	17
	2,001 – 6,000	16	17	17	18	18	18	*	27	22	20	18	18
	Over 6,000	17	18	19	20	20	20	*	29	24	22	20	20
55	Under 250	12	14	15	16	16	17	*	25	21	19	17	17
	251 – 800	14	16	17	18	18	19	*	28	23	21	20	19
	801 – 2,000	15	17	19	20	20	21	*	31	26	23	22	21
	2,001 – 6,000	17	19	21	22	22	23	*	34	29	26	24	23
	Over 6,000	18	21	23	24	24	25	*	37	31	28	26	25
60	Under 250	13	16	17	18	19	19	*	30	25	23	21	20
	251 – 800	15	18	20	20	21	22	*	34	28	26	23	23
	801 – 2,000	17	20	22	22	23	24	*	37	31	28	26	25
	2,001 – 6,000	18	22	24	25	26	27	*	41	34	31	29	28
	Over 6,000	20	24	26	27	28	29	*	45	37	34	31	30
65	Under 250	15	18	19	20	21	21	*	33	27	25	23	22
	251 – 800	17	20	22	22	24	24	*	38	31	29	26	25
	801 – 2,000	19	22	24	25	26	27	*	41	34	31	29	28
	2,001 – 6,000	20	25	27	27	29	30	*	46	37	35	32	31
	Over 6,000	22	27	29	30	31	32	*	50	41	38	34	33
70	Under 250	16	19	21	21	23	23	*	36	29	27	25	24
	251 – 800	18	22	23	24	26	26	*	41	33	31	28	27
	801 – 2,000	20	24	26	27	28	29	*	45	37	34	31	30
	2,001 – 6,000	22	27	29	29	31	32	*	50	40	38	34	33
	Over 6,000	24	29	31	32	34	35	*	54	44	41	37	36

Notes:

This exhibit applies to:

- All state highways outside incorporated cities.
- Limited access state highways within cities.

For Roadside and Median areas on managed access state highways within incorporated cities, see 1600.02 for guidance. Curb is not considered adequate to redirect an errant vehicle.

Design Clear Zone distances are given in feet, measured from the edge of traveled way.

*When the fill section slope is steeper than 4H:1V, but not steeper than 3H:1V, the Design Clear Zone distance is modified by the recovery area formula (see Exhibit 1600-4) and is referred to as the recovery area. The basic philosophy behind the recovery area formula is that the vehicle can traverse these slopes but cannot recover (control steering); therefore, the horizontal distance of these slopes is added to the Design Clear Zone distance to form the recovery area.

Exhibit 1600-3 Design Clear Zone Inventory Form (# 410-026 EF)



Washington State Department of Transportation

Design Clear Zone Inventory


Region	SR	Control Section	MP to MP	Date

Project Number	Project Title	Responsible Unit

Item Number	MP to MP	Distance From Traveled Way L	Distance From Traveled Way R	Description	Corrective Actions Considered (2)	Estimated Cost to Correct	Correction Planned (1) Yes	Correction Planned (1) No

(1) Only one "Yes" or "No" per item number. Corrections not planned must be explained on reverse side.
(2) A list of Location 1 & 2 Utility Objects to be forwarded to the region Utility Office for coordination per Control Zone Guidelines.


DOT Form 410-026 EF
Revised 4/05



Item Number	Reasons for Not Taking Corrective Action

DOT Form 410-026 EF
Revised 4/05

Exhibit 1600-4 Recovery Area



* Recovery area normally applies to slopes steeper than 4H:1V, but not steeper than 3H:1V. For steeper slopes, the recovery area formula may be used as a guide if the embankment height is 10 ft or less.

Formula:

Recovery area = (shld. width) + (horizontal distance) + (Design Clear Zone distance – shld. width)

Example: Fill section (slope 3H:1V or steeper)

Conditions:

Speed = 45 mph
Traffic = 3,000 ADT
Slope = 3H:1V

Criteria:

Slope 3H:1V → Use recovery area formula

Recovery area = (shld. width) + (horizontal distance) + (Design Clear Zone distance – shld. width)

= 8 + 12 + (17-8)

Recovery area = 29 feet




Exhibit 1600-5 Design Clear Zone for Ditch Sections


Case 1: Cut section with ditch (foreslope 4H:1V of flatter)

Conditions:

Speed = 55 mph

Traffic = 4,200 ADT

Slope = 4H:1V



Criteria:

Greater of:

(1) Design Clear Zone for 10H:1V cut section, 23 ft

(2) 5 feet horizontal beyond beginning of back slope, 22 feet


Design Clear Zone = 23 feet

Case 2: Cut section with ditch (foreslope steeper than 4H:1V and backslope steeper than 3H:1V)

Conditions: NA

Criteria: 10 feet horizontal beyond beginning of backslope

Design Clear Zone = 19 feet



Case 3: Cut section with ditch (foreslope 3H:1V or steeper and backslope not steeper than 3H:1V)


Conditions:

Speed = 45 mph

Traffic = 3,000 ADT

Foreslope = 2H:1V

Backslope = 4H:1V




Criteria: Use recovery area formula

Recovery area = (shoulder width) + (horizontal distance) + (Design Clear Zone distance – shoulder width)

= 6 + 6 + (15 – 6) = 21

Recovery Area = 21 feet


Exhibit 1600-6 Guidelines for Embankment Barrier




Note:

Routes with ADTs under 400 may be evaluated on a case-by-case basis.

Exhibit 1600-7 Mailbox Location and Turnout Design




Mailbox Turnout



Mailbox Location: Single Box Design


Detail A




Mailbox Location: Multiple Box Design

Detail B


Exhibit 1600-8 Glare Screens



Chain Link



Vertical Blades



Concrete Barrier

Chapter 1610 Traffic Barriers

1610.01 Introduction
1610.02 Barrier Impacts
1610.03 General Barrier Design Considerations
1610.04 Beam Guardrail
1610.05 High-Tension Cable Barrier
1610.06 Concrete Barrier
1610.07 Bridge Traffic Barriers
1610.08 Other Barriers
1610.09 References

Chapter Organization: The first sections (Introduction and Barrier Impacts) present information to consider when deciding whether to install a barrier. The next section (General Barrier Design Considerations) contains guidance common to ALL barrier types, such as deflection distance, length of need and sight distance. The remaining sections present design information organized by specific barrier type (beam guardrail, cable barrier, etc.).

Refer to the *Design Manual* Glossary for many of the terms used in this chapter.

Refer to Chapter 300 for design documentation requirements.

1610.01 Introduction

The Washington State Department of Transportation (WSDOT) uses traffic barriers to reduce the overall severity of crashes. Consideration is given as to whether a barrier is preferable to the recovery area it may replace. In some cases, installation of a traffic barrier may result in more crashes as it presents an object that can be struck. Barriers are designed so that such encounters might be less severe and not lead to secondary or tertiary crashes. However, traffic barriers are not guaranteed to redirect an impacting vehicle without resulting injury to its occupants or triggering additional crashes. Barrier performance is affected by the characteristics of the vehicles that collide with them. Different vehicles will react differently given the characteristics and dynamics of the crash. Therefore, vehicles will be decelerated and redirected differently given the size, weight and direction of force imparted from the vehicle to the barrier.

Barriers are not placed with the assumption that the system will restrain or redirect all vehicles in all conditions. It is recognized that the designer cannot design a system that will address every potential crash situation. Instead, barriers are placed with the assumption that, under typical crash conditions, they might decrease the potential for excessive vehicular deceleration or excessive vehicle redirection when compared to the location without the barrier.

Traffic barriers do not prevent crashes or injuries from occurring. They often lower the potential severity for crash outcomes. Consequently, barriers should not be used unless a reduced crash severity potential is likely. No matter how well a barrier system is designed, optimal performance is dependent on drivers' proper maintenance and operation of their vehicles and the proper use of passenger restraint systems. The ultimate choice of barrier type and placement should be made by gaining an understanding of site and traffic conditions, having a thorough understanding of and applying the criteria presented in Chapters 1600 and 1610, and using engineering judgment.

Barrier systems and vehicle fleets continue to evolve. The choice of a barrier is based on the characteristics of today's vehicle fleet and testing criteria, not on speculative assumptions of future vehicle designs. This continuum of change does not allow engineers to predict the future with any degree of certainty. Consequently, engineering decisions need to be made based on the most reliable and current information.

Engineers are constantly striving to develop more effective design features to improve highway safety. However, economics, asset management and maintenance needs, and feasibility do not permit the deployment of new designs as soon as they become available on the market or are invented by a manufacturer. Further, most new designs only make marginal changes to systems and do not imply that old designs are unsafe or need modification.

Solutions may consider crash frequency and severity. As discussed previously, performance of the system relies on the interaction of the vehicle, driver, and system design at any given location. Additionally, the ability to safely access, maintain and operate over time is incorporated into the final barrier decision.

When barriers are crash-tested, it is impossible to replicate the innumerable variations in highway conditions under which the barrier applications occur. Therefore, barriers are crash-tested under standardized conditions. These standard conditions were previously documented in National Cooperative Highway Research Program (NCHRP) Reports 230 and 350. These guidelines have been updated and are now presented in the AASHTO publication, *Manual for Assessing Safety Hardware* (MASH).

As roadside safety hardware changes occur on the highway system they will use MASH crash testing criteria instead of NCHRP Report 350. To learn more about WSDOT's plan for implementing MASH-compliant hardware see the following website:
http://www.wsdot.wa.gov/Design/Policy/RoadsideSafety.htm

1610.01(1) Site Constraints

Site constraints play a major role in decisions regarding guardrail selection and placement. Depending on the location, these constraints may include (but are not limited to) environmental considerations, topographic challenges, restricted right-of-way, geologic concerns or conflicts with other infrastructure to name just a few. Document barrier location decisions, including any site constraints encountered that influenced those decisions. A decision to install barrier using criteria outside the guidance provided in this chapter requires a Design Analysis (See Chapter 300).

1610.02 Barrier Impacts

Engineering judgment is required in determining the appropriate placement of barrier systems, therefore consider the location of the system and the possible impacts the barrier may have to other highway objectives.

1610.02(1) Assessing Impacts to Stormwater and Wetlands

The presence of stormwater facilities or wetlands influence the choice and use of barrier systems. For example, the placement of concrete barrier may increase the amount of impervious surface, which could then result in retrofit or reconstruction of the existing retention/detention systems and environmental impact requirements and studies. Assess


whether concrete barrier or beam guardrail placement will cause the need for an evaluation by the HQ Environmental Services Office. Conduct this evaluation early in the project's development process to allow adequate time for discussion of options.

1610.02(2) Assessing Impacts to Wildlife

The placement of concrete barriers in locations where wildlife frequently cross the highway can influence wildlife-vehicle crash potential. When wildlife encounters physical barriers that are difficult to see beyond or cross, such as concrete barriers, they often stop or move parallel to those barriers, increasing their time on the highway and their exposure.

Traffic-related wildlife mortality may play a role in the decline of some species listed under the Endangered Species Act. To address wildlife concerns, see Exhibit 1610-1 to assess whether barrier placement needs to have an evaluation by the HQ Environmental Services Office to determine its effect on wildlife. Conduct this evaluation early in the project development process to allow adequate time for discussion of options.

Exhibit 1610-1 Concrete Barrier Placement Guidance: Assessing Impacts to Wildlife



1610.03 General Barrier Design Considerations

See Chapter 1105 Design Element Selection for guidance regarding required design elements for the various different project types (programs and subprograms).

Chapter 1120 identifies those elements and features to be evaluated and potentially addressed during the course of a Preservation project.

Follow the guidance in this chapter for any project that introduces new barrier onto the roadside (including median section) and follow the guidance in Chapter 1600 for removal of barrier that is not needed. Slope flattening is recommended when the crash reduction benefit justifies the additional cost to eliminate the need for barrier.

When selecting a barrier, consider the barrier system's deflection characteristics, cost, maintainability and impacts to traffic flow during repair. Barriers are categorized as flexible, semi-rigid, or rigid depending on their deflection characteristics. (See Exhibit 1610-3). Barrier types include:

- Beam Guardrail
- Cable Barrier
- Concrete Barrier
- Bridge Traffic Barrier
- Other Barriers

Since non-rigid systems typically sustain more damage during an impact, consider the amount of traffic exposure maintenance crews might incur with the more frequent need for repairs.

The costs for procuring and maintaining the barrier system are important factors when considering what system to install. Considerations may include:

- Consultation with the Area Maintenance Superintendent to identify needs or recommendations.
- Drainage, alignment, and drifting snow or sand are considerations that can influence the selection of barrier type. Beam guardrail and concrete barrier can contribute to snow drifts. Consider long-term maintenance costs associated with snow removal at locations prone to snow drifting. Cable barrier is not an obstruction to drifting snow.
- Analysis of potential reduction of sight distance due to barrier selection and placement.
- Additional widening and earthwork requirements. With some systems, such as concrete barrier and beam guardrail, the need for additional shoulder widening or slope flattening is common. Selection of these types of barriers may require substantial environmental permitting or roadway reconstruction. Permits issued under the SEPA and NEPA processes may lead to the use of a barrier design, such as cable barrier, which has fewer potential environmental impacts and costs.
- For concrete barrier systems:
  - Lower maintenance costs than for other barrier types.
  - Deterioration due to weather and vehicle impacts is less than most other barrier systems.
  - Unanchored precast concrete barrier can usually be realigned or repaired after a vehicle impact. However, heavy equipment may be necessary to reposition or

replace barrier segments. Therefore, in medians, consider the shoulder width and the traffic volume when determining the acceptability of unanchored precast concrete barrier versus rigid concrete barrier. See Exhibit 1610-3 for deflection area requirements.

Consider the following for existing barrier systems:

- Install, replace, or modify transitions as discussed in 1610.04(6) Transitions and Connections.
- When installing new terminals, extend the guardrail to meet the length-of-need criteria found in 1610.03(5).
- When replacing damaged terminals, consider extending the guardrail to meet the length of need criteria in 1610.03(5)
- When the end of a barrier has been terminated with a small mound of earth, remove and replace with a terminal as described in 1610.06(3).
- Special use or aesthetic barriers may be used on designated Scenic Byway and Heritage Tour routes if funding, permits, and approvals can be arranged (see 1610.08).
- Design Manual Chapter 1120 identifies specific requirements to be addressed for a Preservation project. For other projects, address barrier runs that include:
  - W-beam guardrail with 12-foot 6-inch post spacing, or no blockouts, or both.
  - W-beam guardrail on concrete posts.
  - Cable barrier on wood or concrete posts.
  - Half-moon or C-shaped rail elements.

1610.03(1) Barrier Placement Considerations

Proper installation of a barrier system is required for the system to perform similar to the crash tests that resulted in its acceptance for use on our highways. Maximize the distance between the barrier and the travelled way.


See Chapter 1239 for minimum lateral clearance requirements.

1610.03(1)(a) Placement on a Slope

Slopes may affect barrier placement. Considerations for barrier placement on a slope include:

- For slopes that are 10:1 or flatter, concrete barrier, beam guardrail or cable barrier can be installed anywhere beyond the edge of shoulder. See Exhibit 1610-2.
- For additional placement guidance see 1610.05(1) for cable barrier, see 1610.04(2) for beam guardrail, and see 1610.06 for concrete barrier.

Exhibit 1610-2 Traffic Barrier Locations on Slopes



1610.03(1)(b) Placement in Median Locations

Considerations for barrier placement in a median include:

- Address the design deflection characteristics of the barrier to avoid placement of barrier where the design deflection extends into oncoming traffic.
- Narrow medians provide little space for any maintenance activities, including repair or repositioning of the barrier. Installing barriers in medians that provide less than 8 feet from the edge of the traveled way to the face of the barrier will likely require temporarily closing the adjacent lane during maintenance activities. This will impact the travelling public and impact maintenance staff, and maintenance staff should be consulted. See Chapter 301 Design and Maintenance Coordination.
- At locations where the roadways are on independent alignments and there is a difference in elevation between the roadways, the slope from the upper roadway might be steeper than 6H:1V. In these locations, position the median barrier along the upper roadway and provide deflection and offset distance as discussed previously. Barrier is generally not needed along the lower roadway except where there are fixed features in the median.
- In wider medians, the selection and placement of barrier might depend on the slopes in the median. At locations where the median slopes are relatively flat (10H:1V or flatter), unrestrained precast concrete barrier, beam guardrail, and cable barrier can be used depending on the available deflection distance. At these locations, position the barrier as close to the center of the median as possible so that the recovery distance can be maximized for both directions. There may be a need to offset the barrier from the flow line to avoid impacts to the drainage flow.
- In general, cable barrier is recommended with medians that are 30 feet or wider. However, cable barrier may be appropriate for narrower medians if adequate deflection distance exists.
- When W-beam barrier is placed in a median as a countermeasure for cross-median crashes, design the barrier to be struck from either direction of travel. For example, the installation of beam guardrail might be double-sided (Type 31-DS).
- For additional placement guidance see 1610.05(1) for cable barrier, see 1610.04(2) for beam guardrail, and see 1610.06 for concrete barrier.

1610.03(2) Sight Distance

When selecting and placing a barrier system, consider the possible impact the barrier type and height may have on sight distance. In some cases, barriers may restrict the sight distances of road users entering the roadway, such as from road approaches, intersections, and other locations. In these cases, the barrier may need to be adjusted to meet the sight distance requirements at these locations.

1610.03(3) Barrier Deflections

Expect all barriers, except rigid barriers (such as concrete bridge rails, barrier integral to retaining walls, or embedded cast-in-place barriers), to deflect when hit by an errant vehicle. The amount of deflection is primarily dependent on the stiffness of the system. However, vehicle speed, angle of impact, and weight of the vehicle also affect the amount of barrier deflection. For flexible and semi-rigid roadside barriers, the deflection distance is designed to prevent the impacting vehicle from striking the object being shielded. For unrestrained rigid systems (unanchored precast concrete barrier), the deflection distance is designed to help prevent the barrier from being knocked over the side of a drop-off or steep fill slope (2H:1V or steeper).

In median installations, design systems such that the anticipated deflection will not enter the lane of opposing traffic. When evaluating new barrier installations, consider whether impacts would require significant traffic closures to accomplish maintenance. Use a rigid system where deflection cannot be accommodated, such as in narrow medians or at the edge of bridge decks or other vertical drop-off areas. Runs of rigid concrete barrier can be cast in place or extruded with appropriate footings.

In some locations, where deflection distance is limited, anchor precast concrete barrier. Unless the anchoring system has been designed to function as a fully rigid barrier, some movement can be expected and repairs may be more expensive. Use of an anchored or other deflecting barrier on top of a retaining wall without deflection distance provided requires approval from the HQ Design Office. See 1610.06 for more information on concrete barrier.

Refer to Exhibit 1610-3 for barrier deflection design values when selecting a longitudinal barrier. The deflection values for cable and beam guardrail are minimum distances, measured between the face of the barrier to the fixed feature. The deflection values for unanchored concrete barrier are minimum distances, measured from the back edge of the barrier to the fixed feature, drop-off or slope break.

Exhibit 1610-3 Longitudinal Barrier Deflection

Barrier Type	System Type	Deflection
High-tension cable barrier	Flexible	12 ft [1]
Beam guardrail, Types 1, 1a, 2, 10, and 31	Semi-rigid	3 ft (face of barrier to object)
Two-sided W-beam guardrail, Types 3, 4, and 31-DS	Semi-rigid	2 ft (nearest face of barrier to object)
Permanent concrete barrier, unanchored	Rigid Unrestrained	3 ft [2] (back of barrier to object)
Temporary concrete barrier, unanchored	Rigid Unrestrained	2 ft [3] (back of barrier to object)
Precast concrete barrier, anchored	Rigid Anchored	6 inches
Rigid concrete barrier	Rigid	No deflection

Notes:
[1] See 1610.05(2)
[2] When placed in front of a 2H:1V or flatter fill slope, the deflection distance can be reduced to 2 feet.
[3] When used as temporary bridge rail, anchor all barrier within 3 feet of a drop-off.

1610.03(4) Flare Rate

A roadside barrier is considered flared when it is not parallel to the edge of the traveled way.

Flare the ends of longitudinal barriers where site constraints allow (see 1610.01(1)). The four functions of a flare are to:

- Maximize the distance between the barrier (and its terminal) and the travelled way.
- Reduce the length of need.
- Redirect an errant vehicle.
- Minimize a driver's reaction to the introduction of an object near the traveled way.

Keeping flare rates as flat as site constraints allow preserves the barrier's redirectional performance and minimizes the angle of impact. It has also been shown that an object (or barrier) close to the traveled way might cause a driver to shift laterally, slow down, or both. The flare reduces this reaction by gradually introducing the barrier so the driver does not perceive the barrier as an object to be avoided. The flare rates in Exhibit 1610-4 are intended to satisfy the four functions listed above. Flares that are more gradual may be used. Flare rates are offset parallel to the edge of the traveled way. Transition sections are not flared.

Situations exist where hardware installations may have barrier flare rates different than shown in Exhibit 1610-4. If a *Standard Plan* for a barrier installation shows a different flare rate than is shown in Exhibit 1610-4, the flare rate shown on the *Standard Plan* can be used.

Exhibit 1610-4 Longitudinal Barrier Flare Rates

Posted Speed (mph)	Rigid & Rigid Anchored System	Unrestrained Rigid System	Semi-rigid
65–70	20:1	18:1	15:1
60	18:1	16:1	14:1
55	16:1	14:1	12:1
50	14:1	12:1	11:1
45	12:1	11:1	10:1
40 or below	11:1	10:1	9:1

1610.03(5) Length of Need

The length of traffic barrier needed to shield a fixed feature (length of need) is dependent on the location and geometrics of the object, direction(s) of traffic, posted speed, traffic volume, and type and location of traffic barrier. When designing a barrier for a fill slope (see Chapter 1600), the length of need begins at the point where the need for barrier is recommended. For fixed objects and water, Exhibit 1610-5 shows design parameters for determining the needed length of a barrier for both adjacent and opposing traffic on relatively straight sections of highway.


When barrier is to be installed on the outside of a horizontal curve, the length of need can be determined graphically as shown in Exhibit 1610-7. For installations on the inside of a curve, determine the length of need as though it were straight. Also, consider the flare rate, barrier deflection, and barrier end treatment to be used.

When beam guardrail is placed in a median, consider the potential for impact from opposing traffic when conducting a length of need analysis. When guardrail is placed on either side of objects in the median, consider whether the trailing end of each run of guardrail will shield the leading end of the opposing guardrail. Shield the leading end when it is within the Design Clear Zone of opposing traffic (see Exhibit 1610-8). This is also a consideration when objects are placed in the outer separations between the main line and collector-distributors.

Before the actual length of need is determined, establish the lateral distance between the proposed barrier installation and the object shielded. Provide a distance that is greater than or equal to the anticipated deflection of the longitudinal barrier. (See Exhibit 1610-3 for barrier deflections.) Place the barrier as far from the edge of the traveled way as possible while maintaining the deflection distance.

If the end of the length of need is near an adequate cut slope, extend the barrier and embed it in the slope (see 1610.04(5)). Avoid gaps of 300 feet or less. Short gaps are acceptable when the barrier is terminated in a cut slope. If the end of the length of need is near the end of an existing barrier, it is recommended that the barriers be connected to form a continuous barrier. Consider maintenance access issues when determining whether or not to connect barriers.

Exhibit 1610-5 Barrier Length of Need on Tangent Sections



Note: For supporting length of need equation factors, see Exhibit 1610-6

Exhibit 1610-6 Barrier Length of Need

Posted Speed (mph)	Design Parameters						
	ADT				Barrier Type		
	Over 10,000	5,000 to 10,00	1,000 to 4,999	Under 1,000	Rigid & Rigid Anchored Barrier	Rigid Unrestrained Barrier	Semi-rigid Barrier
	LR (ft)	LR (ft)	LR (ft)	LR (ft)	F	F	F
70	360	330	290	250	20	18	15
65	330	290	250	225	20	18	15
60	300	250	210	200	18	16	14
55	265	220	185	175	16	14	12
50	230	190	160	150	14	12	11
45	195	160	135	125	12	11	10
40	160	130	110	100	11	10	9
35	135	110	95	85	11	10	9
30	110	90	80	70	11	10	9
25	110	90	80	70	11	10	9

L1 = Length of barrier parallel to roadway from adjacent-side fixed feature to beginning of barrier flare. This is used if a portion of the barrier cannot be flared (such as a bridge rail and the transition).

L2 = Distance from adjacent edge of traveled way to portion of barrier parallel to roadway.

L4 = Length of barrier parallel to roadway from opposite-side fixed feature to beginning of barrier flare.

L5 = Distance from centerline of roadway to portion of barrier parallel to roadway. ***Note:*** If the fixed feature is outside the Design Clear Zone when measured from the centerline, it may only be necessary to provide a crash-tested end treatment for the barrier.

LH1 = Distance from outside edge of traveled way to back side of adjacent-side fixed feature. ***Note:*** If a fixed feature extends past the Design Clear Zone, the Design Clear Zone can be used as LH1.

LH2 = Distance from centerline of roadway to back side of opposite-side fixed feature. ***Note:*** If a fixed feature extends past the Design Clear Zone, the Design Clear Zone can be used as LH2.

LR = Runout length, measured parallel to roadway.

X1 = Length of need for barrier to shield an adjacent-side fixed feature.

X2 = Length of need for barrier to shield an opposite-side fixed feature.


F = Flare rate value.

Y = Offset distance needed at the beginning of the length of need.

Different end treatments need different offsets:

- For the SRT 350 and FLEAT 350, use Y = 1.8 feet.
- For evaluating existing BCTs, use Y = 1.8 feet.
- For the FLEAT TL-2, use Y = 0.8 feet.
- No offset is needed for the non-flared terminals or impact attenuator systems. Use Y = 0.


Exhibit 1610-7 Barrier Length of Need on Curves



Notes:

- This is a graphical method for determining the length of need for barrier on the outside of a curve.
- On a scale drawing, draw a tangent from the curve to the back of the fixed feature. Compare T to LR from Exhibit 1610-6 and use the shorter value.
- If using LR, follow Exhibits 1610-5 and 6.
- If using T, draw the intersecting barrier run to scale and measure the length of need.

Exhibit 1610-8 W-Beam Guardrail Trailing End Placement for Divided Highways



1610.03(6) Barrier Delineation

Refer to Chapter 1030 for barrier delineation requirements.

1610.04 Beam Guardrail

Strong post W-beam guardrail and thrie beam guardrail are semi-rigid barriers used predominantly on roadsides. They have limited application as median barrier. A strong-post W-beam (commonly referred to as W-Beam) guardrail system is the most common type of guardrail system used. The design uses wood or steel posts, rail, and blockouts to support the rail away from the post. The system resists a vehicle impact through a combination of the tensile and flexural stiffness of the rail and the bending or shearing resistance of the post.

Installed incorrectly, strong post W-beam guardrail can cause vehicle snagging or spearing. This can be avoided by lapping the rail splices in the direction of traffic (as shown in the *Standard Plans*), by using crash-tested end treatments, and by blocking the rail away from the posts.

Beam guardrail systems are shown in the *Standard Plans*.

1610.04(1) Beam Guardrail Systems

1610.04(1)(a) Type 31 Beam Guardrail

Use Type 31 guardrail for new runs. The Type 31 system uses many of the same components as the old WSDOT Type 1 system. The main differences are that the blockouts extend 12 inches from the posts, the rail height is 31 inches from the ground to the top of the rail, and the rail elements are spliced between posts.

Type 31 guardrail offers tolerance for future HMA overlays. The system allows a 3-inch tolerance from 31 inches to 28 inches without adjustment of the rail element.

Type 31 guardrail is available double-sided, which can be used in medians.

1610.04(1)(b) (Old) Type 1 Beam Guardrail

Previous WSDOT standard practice was to install W-beam guardrail at a rail height of 27 to 28 inches, and is referred to as “Type 1” guardrail. WSDOT is phasing out the use of Type 1 guardrail. Do not use Type 1 guardrail for new installations. For more information on (Old) Beam Guardrail Type 1, see: http://www.wsdot.wa.gov/Design/Policy/RoadsideSafety.htm.

Existing runs of Type 1 guardrail are acceptable to leave in place and can be extended up to 50 ft (use Type 1 Alternate where future overlays are anticipated). If an existing run of Type 1 guardrail requires extending more than 50 ft, use the Beam Guardrail Type 31 to Beam Guardrail Type 1 Adaptor shown in the *Standard Plans*, and complete the guardrail extension using Type 31 guardrail.

1610.04(1)(c) Other Guardrail Types

W-beam guardrail Type 2 and Type 3 have a height of 30 inches and utilize a rubrail. A rubrail is a structural steel channel added below the W-beam rail and is used in these specific designs to reduce vehicle snagging on the post. Existing runs of Type 2 or Type 3 guardrail are acceptable to leave in place. If the existing run of Type 2 or 3 requires extending more than 50 ft, contact

WSDOT Design Office to identify appropriate extension methods to transition to the Type 31 double sided system.

Type 4 guardrail is a double-sided version of the Type 1 guardrail system. For new installation, use the Type 31 double-sided w-beam guardrail instead of Type 4 guardrail. Existing runs of Type 4 guardrail are acceptable to leave in place. If the existing run of Type 4 requires extending more than 50 ft, contact WSDOT Design Office to identify appropriate extension methods to transition to the Type 31 double-sided system.

Type 10 and Type 11 are thrie-beam guardrail systems. For new installations, see *Standard Plans*. Existing runs of Type 10 or 11 guardrail are acceptable to leave in place and may be extended as needed.

Weak post W-beam guardrail (Type 20) and thrie beam guardrail (Type 21) are flexible barrier systems primarily used in conjunction with Service Level 1 bridges. These systems use weak steel posts. For information on Type 20 and Type 21 guardrail see:
http://www.wsdot.wa.gov/Design/Policy/RoadsideSafety.htm

1610.04(2) Beam Guardrail Placement

There a number of considerations regarding guardrail placement. These include:

- During the project development processes, consult with maintenance staff to help identify guardrail runs that may need to be modified.
- When guardrail is installed along existing shoulders with a width greater than 4 feet, the shoulder width may be reduced by 4 inches to accommodate the 12-inch blockout. A Design Analysis is not required for the reduced shoulder width. If the remaining shoulder width is 4 feet or less, see Chapter 1030 for barrier delineation guidance.
- Keep the slope of the area between the edge of the shoulder and the face of the guardrail 10H:1V or flatter.
- On fill slopes 10:1 or flatter, beam guardrail can be placed anywhere outside of the shoulder.
- On fill slopes between 6H:1V and 10H:1V, place beam guardrail at the shoulder or at least 12 feet from the slope breakpoint (as shown in Exhibit 1610-9).
- Do not place beam guardrail on a fill slope steeper than 6H:1V
- On the high side of superelevated sections, place beam guardrail at the edge of shoulder prior to the slope breakpoint.
- For W-beam guardrail installed at or near the shoulder, 2 feet of shoulder widening behind the barrier is generally provided from the back of the post to the slope breakpoint of a fill slope (see Exhibit 1610-10, Case 2). If the slope is 2H:1V or flatter, this distance can be 2.5 feet measured from the face of the guardrail rather than the back of the post (see Exhibit 1610-10, Case 1).
- On projects where no roadway widening is proposed and site constraints prevent providing the 2-foot shoulder widening behind the barrier, long post installations are available as shown in Exhibit 1610-10, Cases 3, 4, 5, and 6. When installing guardrail where the roadway is to be widened or along new alignments, the use of Cases 5 and 6 requires a Design Analysis.

Exhibit 1610-9 Beam Guardrail Installation on 6:1 to 10:1 Slopes





Exhibit 1610-10 Beam Guardrail Post Installation



Type 31 Shown

Notes:

- Use Cases 1 and 3 when there is a 2.5-foot or greater shoulder widening from face of guardrail to the slope breakpoint.
- Use Case 2 when there is a 4.0-foot or greater shoulder widening from the face of the guardrail to the slope breakpoint.
- Use Cases 4, 5, and 6 when there is less than a 2.5-foot shoulder widening from face of guardrail to the slope breakpoint.
- Cases shown do not apply to terminals, transition sections or anchors. Install terminals, transition sections and anchors per the *Standard Plans*.

1610.04(3) W-Beam Barrier Height

For existing Type 1 guardrail runs under 26.5 inches, adjust or replace the rail to a height of 28 inches minimum to 30 inches maximum, or replace the run with the 31-inch-high Type 31 beam guardrail.

For HMA Overlay Projects that will reduce the height of W-beam guardrail to less than 26.5 inches from the ground to the top of the rail element, adjust the height to a minimum of 28 inches and a maximum of 30 inches. A rail height of 30 inches is desirable to accommodate future overlays.

If Type 1 Alternative W-beam guardrail is present, raise the rail element after each overlay. If Type 1 Alternative is not present, the blockout and rail element may be raised up to 4 inches. This requires field drilling a new hole in the guardrail post. See the *Standard Plans*.

1610.04(4) Additional Guidance

Additional guidance related to w-beam guardrail:

- Locations where crossroads and driveways cause gaps in the guardrail create situations requiring special consideration. Elimination of the need for the barrier is the preferred solution. At these locations, a barrier flare might be needed to provide sight distance.
- Rail washers on beam guardrail are not normally used. If rail washers are present, removal is not necessary. However, if the rail element is removed for any reason, do not reinstall rail washers. In areas where heavy snow accumulations are expected to cause the bolts to pull out, specify snowload post washers and rail washers in the contract documents. (Snowload post washers are used to help prevent the bolts from pulling through the posts, and snowload rail washers are used to help prevent the bolt head from pulling through the rail). In other installations, it is normal to have the rail pull loose from the bolt head when impacted. Do not use rail washers within the limits of a guardrail terminal except, for some models, at the end post when they are needed for anchorage of the rail.
- The use of curb in conjunction with beam guardrail is discouraged. If a curb is needed, the 3 inch-high curb is preferred. If necessary, the 4-inch-high extruded curb can be used behind the face of rail for any posted speed. The 6-inch-high extruded curb can be used at locations where the posted speed is 50 mph or below. When replacing extruded curb at locations where the posted speed is above 50 mph, use 3 inch-high or 4-inch-high curb. (See the *Standard Plans* for extruded curb designs.)
- When curb is used in conjunction with Type 31 W-beam guardrail, an acceptable option is to place up to a 6-inch-high extruded curb at a maximum 6 inch offset in front of the face of the rail at any posted speed. Contact the WSDOT Design Office for more information.
- The installation of strong post W-beam guardrail posts in rigid surfacing such as asphalt or concrete pavement involves special details that will allow the posts to rotate. Contact the WSDOT Design Office for more information.
- For (Old) Guardrail Types 1, 2, 3,and 4, it is acceptable to use blockouts that extend the rail element from the post for a distance not to exceed 16 inches.

1610.04(5) Terminals and Anchors

A guardrail anchor is required at the end of a run of guardrail to develop tensile strength throughout its length. In addition, when the end of the guardrail is subject to head-on impacts, a crash-tested guardrail terminal is required (see the *Standard Plans*).

Replace guardrail terminals that do not have a crash-tested design with crash-tested guardrail terminals. Common features of systems that do not meet current crash-tested designs include:

- No cable anchor.
- A cable anchored into concrete in front of the first post.

- Second post not breakaway (CRT).
- Design A end section.
- Design C end sections may be left in place if the terminal is otherwise a crash-tested design —see the *Standard Plans* for end section details.
- Terminals with beam guardrail on both sides of the posts (two-sided).
- Buried guardrail terminals that slope down such that the guardrail height is reduced to less than 28 inches (measured in relation to a 10H:1V line extended from the breakpoint at edge of shoulder).

When the height of a terminal, as measured from the ground to the top of the rail element, will be affected by the project, adjust the terminal based upon the following criteria:

- If the height of the adjoining Type 1, 2, 3, or 4 guardrail will be reduced to less than 26.5 inches or increased to greater than 30 inches, adjust the height of the terminal to a minimum of 28 inches and a maximum of 30 inches. A terminal height of 30 inches is desirable to accommodate future overlays.
- If the height of the adjoining Type 31 guardrail will be reduced to less than 28 inches or increased to greater than 32 inches, adjust the height of the terminal to 31 inches.

When adjusting terminals that are equipped with CRT posts, the top-drilled holes in the posts need to remain at the surface of the ground.

One terminal that was used extensively on Washington's highways was the Breakaway Cable Terminal (BCT). This system used a parabolic flare similar to the Slotted Rail Terminal (SRT) and a Type 1 anchor (Type 1 anchor posts are wood set in a steel tube or a concrete foundation). For guidance regarding BCT's on Preservation projects see Chapter 1120. For non-Preservation projects replace BCTs with a currently approved terminal.

Information regarding (Old) Type 1 beam guardrail terminals can be found at:
http://www.wsdot.wa.gov/Design/Policy/RoadsideSafety.htm

1610.04(5)(a) Buried Terminal (BT) for Type 31 Beam Guardrail

A buried terminal is designed to terminate the guardrail by burying the end in a backslope. The BT is the preferred terminal because it eliminates the exposed end of the guardrail.

For new BT installations, use the Buried Terminal Type 2. Previously, another BT option (the Buried Terminal Type 1) was an available choice. For existing installations, it is acceptable to leave this option in service as long as height requirements and other design criteria is met. See the plan sheet at: www.wsdot.wa.gov/design/standards/plansheet.

The BT uses a Type 2 anchor to develop the tensile strength in the guardrail. The backslope needed to install a BT is to be 3H:1V or steeper and at least 4 feet in height above the roadway. The entire BT can be used within the length of need for backslopes of 1H:1V or steeper if the barrier remains at full height in relation to the roadway shoulder to the point where the barrier enters the backslope.

For backslopes between 1H:1V and 3H:1V, design the length of need beginning at the point where the W-beam remains at full height in relation to the roadway shoulder—usually beginning at the point where the barrier crosses the ditch line. If the backslope is flatter than

1H:1V, provide a minimum 20-foot-wide by 75-foot-long distance behind the barrier and between the beginning length of need point at the terminal end to the mitigated object to be protected.

Flare the guardrail to the foreslope/backslope intersection using a flare rate that meets the criteria in 1610.03(4). Provide a 4H:1V or flatter foreslope into the face of the guardrail and maintain the full guardrail height to the foreslope/backslope intersection in relation to a 10H:1V line extending from edge of shoulder breakpoint. (See the *Standard Plans* for details.)

1610.04(5)(b) Non-flared Terminals for Type 31 Beam Guardrail

If a buried terminal cannot be installed as described in 1610.04(5)(a), install a non-flared terminal. These systems use W-beam guardrail with a special end piece that fits over the end of the guardrail. When hit head on, the end piece is pushed over the rail, absorbing the energy of the impacting vehicle in the process. An anchor is included for developing the tensile strength of the guardrail. The length of need does not begin at the impact head, but will vary by system. Non-flared terminals may be provided for two different design levels that are based on the posted speed of the highway. For highways with a posted speed of 50 mph or above, use only a TL-3 (Test Level 3) product. For highways with a posted speed of 45 mph or below, either a TL-2 or a TL-3 product is acceptable. See the *Standard Plans*.

The availability and acceptance of these systems is expected to change rapidly over time. Refer to the Type 31 Beam Guardrail Terminals website for the latest information on availability or acceptance of different systems (see http://www.wsdot.wa.gov/Design/Policy/RoadsideSafety.htm).

Although non-flared terminals do not need to have an offset at the end, a flare is recommended so that the end piece does not protrude into the shoulder. See the *Standard Plans*.

Four feet of widening is needed at the end posts to properly anchor the systems (See the *Standard Plans*). When widening includes an embankment, properly placed and compacted fill material will be necessary for optimum terminal performance (see the *Standard Specifications* for embankment widening for guardrail).

For guardrail runs that are located more than 12 feet from the slope break (as shown in Exhibit 1610-9) no additional embankment widening is required at the terminal.

No snowload rail washers are allowed within the limits of these terminals.

WSDOT does not currently use a flared terminal system for the Type 31 guardrail system.

Note: Approved shop drawings for terminals can be found by accessing the following website: http://www.wsdot.wa.gov/Design/Policy/RoadsideSafety.htm

1610.04(5)(c) Terminal Evolution Considerations

Some currently approved terminals have been in service for a number of years. During this time, there have been minor design changes. However, these minor changes have not changed the devices' approval status. Previous designs for these terminals may remain in place.

Note: If questions arise concerning the current approval status of a device, contact the HQ Design Office for clarification when replacement is being considered.

1610.04(5)(d) Anchors

A guardrail anchor is needed at the end of a run of guardrail to develop tensile strength throughout its length.

- Use the Type 10 anchor to develop the tensile strength of the guardrail on the end of Type 31 guardrail runs where a crash-tested terminal is not needed.
- Anchors for (Old) Beam Guardrail Type 1 include Type 1, Type 3, Type 4, Type 5, and Type 7.

For more information on these anchor types used in run of (Old) Beam Guardrail Type 1, see: http://www.wsdot.wa.gov/Design/Policy/RoadsideSafety.htm.

1610.04(6) Transitions and Connections

When there is an abrupt change from one barrier type to a more rigid barrier type, a vehicle hitting the more flexible barrier may be caught in the deflected barrier pocket and directed into the more rigid barrier. This is commonly referred to as "pocketing." A transition stiffens the more flexible barrier by decreasing the post spacing, increasing the post size, and using stiffer beam elements to reduce the possibility of pocketing.

When connecting beam guardrail to a more rigid barrier or a structure use the transitions and connections that are shown in Exhibits 1610-12 and 1610-13 and detailed in the *Standard Plans*.

When connecting a Type 21 Transition to an existing bridge rail, a special connection plate may be required. Coordinate with the WSDOT Bridge and Structures Office (BSO). The transition pay item includes the connection.

Exhibit 1610-12 Guardrail Connections

Condition	Connection
Unrestrained concrete barrier	A
Rigid, rigid anchored, untapered safety shape bridge rails or barriers [1]	B
Bridge rails with curbs 9 inches or less in width	B
Bridge rails with curbs between 9 and 18 inches wide	C
Vertical walls, single slope, or tapered safety shape barrier [1]	D

Note:

[1] New single slope and safety shape bridge rails are designed with the toe of the barrier tapered so that it does not project past the face of the approach guardrail.

Exhibit 1610-13 Transitions and Connections

Connecting W-Beam Guardrail to:			Transition Type*	Connection
Bridge Rail	New Installation		21	D
	Existing Concrete	Concrete Parapet > (Greater Than) 20 in.	21, 4 [4]	Exh. 1610-12 [6]
		Concrete Parapet < (Less Than) 20 in.	21, 2, 4 [4]	Exh. 1610-12 [6]
		Existing W-Beam Transition	2 [1][5], 4 [4]	[1]
	Thrie Beam at Face of Curb [3]	Approach End	23	n/a
		Trailing End (two-way traffic only)	23	n/a
	Thrie Beam at Bridge Rail (curb exposed) [3]	Approach End	22	n/a
		Trailing End (two-way traffic only)	22	n/a
	Weak Post Intersection Design (see http://www.wsdot.wa.gov/publications/fulltext/design/RoadsideSafety/Type1_Info.pdf Cases 12 & 13)		5	Exhibit 1610-12
Concrete Barrier	Rigid & Rigid Anchored		21	Exhibit 1610-12
	Unrestrained		21, 2, 4 [4]	A
Rigid Structures such as Bridge Piers	New Installation (see Cases 11–31)		21	n/a
	Existing W-Beam Transition		[2]	n/a
Connecting Thrie Beam Guardrail to:			**Transition Type***	**Connection**
Bridge Rail or Concrete Barrier	New Installation (for example: use with thrie beam guardrail bull nose terminal)		1B	Exhibit 1610-12

*Consult Section C of the *Standard Plans* for details on transition types.

Notes:

[1] If work creates the need for reconstruction or resetting of the transition, upgrade as shown above. Raising the guardrail is not considered reconstruction. If the transition is not being reconstructed, the existing connection may remain in place. When Type 3 anchors are encountered, see http://www.wsdot.wa.gov/Design/Policy/RoadsideSafety.htm for guidance.

[2] For new/reconstruction, use Case 11 (thrie beam). For existing modified Case 11 with W-beam, add a second W beam rail element.

[3] For Service Level 1 bridge rail, see http://www.wsdot.wa.gov/publications/fulltext/design/RoadsideSafety/Type1_Info.pdf, Case 14.

[4] Use on highways with posted speeds 45 mph or below.

[5] If an existing transition has the needed guardrail height and includes the three 10" x 10" (nominal) posts and three 6" x 8" (nominal) posts spaced 3'-1.5" apart—it is acceptable if a W-beam element is added to make the element nested.

[6] When connecting a Type 21 Transition to an existing bridge rail, a special connection plate may be required. Contact the WSDOT BSO for details.

1610.04(7) Guardrail Placement Cases

The *Standard Plans* contain placement cases that show beam guardrail elements needed for typical situations. For new installations, use the appropriate Type 31 placement option.

Information regarding placement cases for (old) Type 1 beam guardrail can be found at http://www.wsdot.wa.gov/Design/Policy/RoadsideSafety.htm.

1610.04(7)(a) Beam Guardrail Type 31 Placements

- Case 1-31 is used where there is one-way traffic. It uses a crash-tested terminal on the approach end and a Type 10 anchor on the trailing end.
- Case 2-31 is used where there is two-way traffic. A crash-tested terminal is used on both ends.
- Case 3-31 is used at railroad signal supports on one-way or two-way roadways. A terminal is used on the approach end, but usually cannot be used on the trailing end because of its proximity to the railroad tracks. If there is a history of crossover collisions, consider additional protection such as an impact attenuator.
- Case 4-31 is used where guardrail on the approach to a bridge is to be shifted laterally to connect with the bridge rail. A terminal is used on the approach end and a transition is needed at the bridge end. Curves (bends) are shown in the guardrail to shift it to the bridge rail. However, the length of the curves are not critical. The criterion is to provide smooth curves that are not more abrupt than the allowable flare rate (see Exhibit 1610-4).
- Case 5-31 is a typical bridge approach where a terminal and a transition are needed.
- Case 6 is used on bridge approaches where opposing traffic is separated by a median that is 36 feet or wider. This case is designed so that the end of the guardrail will be outside the Design Clear Zone for the opposing traffic.
- Case 10 (A-31, B-31, and C-31) is used at roadside fixed features (such as bridge piers) when 3 or more feet are available from the face of the guardrail to the feature. The approach end is the same for one-way or two-way traffic. Case 10A-31 is used with two-way traffic; therefore, a terminal is needed on the trailing end. Case 10B-31 is used for one-way traffic when there is no need to extend guardrail past the bridge pier and a Type 10 anchor is used to end the guardrail. Case 10C-31 is used for one-way traffic when the guardrail will extend for a distance past the bridge pier.
- Case 11 (A-31, B-31, and C-31) is used at roadside fixed features (such as bridge piers) when the guardrail is to be placed within 3 feet of the feature. Since there is no room for deflection, the rail in front of the feature is to be considered a rigid system and a transition is needed. The trailing end cases are the same as described for Case 10.
- Beam Guardrail Type 31 (12'6", 18'9", or 25' Span) is used when it is necessary to omit one, two, or three posts. This application is typically used when guardrail is installed over a shallow buried obstruction, such as drainage structures. This design may be used in other situations where there are no above ground objects located behind the guardrail and within the lateral deflection distance. Three CRT posts are provided on each end of the omitted post(s).

- Guardrail Placement Strong Post – Type 31 is the "Strong Post Intersection Design for Type 31 barrier" that provides a more rigid barrier. This design is used at crossroads or road approaches where a barrier is needed and where the length of need cannot be achieved using standard components such as standard longitudinal barrier runs, transitions, and terminals.

1610.05 High-Tension Cable Barrier

Cable barrier is a flexible barrier system that can be used on a roadside or as a median barrier. Early cable barrier designs centered around low-tension cable systems. With research and crash analysis of these systems, the designs evolved into high-tension cable systems. These high-tension cable systems are primarily used in medians and are preferred for many installations due in part to high benefit-to-cost ratios. Read about advantages for selecting a cable barrier system here:
http://www.wsdot.wa.gov/publications/fulltext/design/Policy/CableBarriers.pdf.

There are a number of manufacturers of high-tension cable barrier systems. These systems have been designed using either three or four-cables fixed to metal posts placed at a fixed spacing. Each cable system has specially designed anchors placed at both ends of the barrier run to provide the proper tensioning in the cables. Currently, both three and four-cable high-tension cable barrier systems are installed along WSDOT state routes. See additional information about these approved cable barrier systems here:
http://www.wsdot.wa.gov/publications/fulltext/design/Policy/CableBarriers.pdf.

Use four-cable high-tension cable barrier systems for all new installations.

1610.05(1) High-Tension Cable Barrier Placement

High-tension cable barrier can be placed in a median or along the roadside.

Note: Additional placement cases are shown in the WSDOT *Standard Plans*. For non-typical installations, such as double runs of cable barrier or median ditch cross sections that differ significantly from those shown, contact the HQ Design Office for guidance.


1610.05(1)(a) Median Applications

For typical cable barrier installations in a median, the following apply (see Exhibit 1610-14a):


- Install the cable barrier as far from the edge of traveled way as site constraints allow. Consider a minimum placement distance of 8 feet from the edge of traveled way to allow vehicles to use this area for refuge.
- Install cable barrier on slopes 6H:1V or flatter.
- There are approved high-tension cable barrier systems that can be placed on slopes as steep as 4H:1V. The use of these systems requires special placement considerations, contact the HQ Design Office for guidance.
- Provide an obstruction free zone within the cable barrier system's lateral deflection distance (see 1610.05(2)).
- On tangent sections of a roadway where no ditch is present, consider installing the cable barrier in the middle of the median.

- Along horizontal curves, consider installing the cable barrier along the inside of the curve. Reduce the post spacing per manufacturer's recommendations.
- Where a ditch is present, install cable barrier at the centerline of the ditch or within 1-foot of the ditch centerline.
- Avoid installing cable barrier within the range between 1-foot to 8-foot offset from the ditch centerline to avoid "under-riding" of vehicles that cross the ditch (see Exhibit 1610-14a).
- In some situations, it may be advantageous to terminate a run of cable barrier on one side of the median (to provide maintenance access to a feature, for example) and then begin an adjacent cable barrier run on the opposite side of the median. In this application, it is important to provide adequate cable barrier overlap distance between the two runs. For placement guidance, see Exhibit 1610-15.
- Narrow medians provide little space for maintenance crews to repair or reposition the barrier. Wherever site conditions permit, provide at least 14 feet of clearance from the adjacent lane edge to the face of the cable barrier.

Exhibit 1610-14a Median Cable Barrier Placement



Cable Barrier Placement in Median with Ditch



Cable Barrier Placement in Median with No Ditch

Notes:


1. Cable barrier may be installed in the center of the ditch and from the ditch centerline a maximum of 1 foot (left or right).
2. Avoid installing cable barrier within a range of 1-foot to 8-foot offset from the ditch centerline.
3. Applies to slopes 6H:1V or flatter.
4. Provide an obstruction free zone within the cable barrier's lateral deflection distance, see 1610.05(2)

1610.05(1)(b) Roadside Applications

For typical non-median roadside applications, the following apply (see Exhibit 1610-14b):

- Install the cable barrier as far from the edge of traveled way as site constraints allow.
- Consider a minimum placement distance of 8 feet from the edge of traveled way to allow vehicles to use this area for refuge.
- Install cable barrier on slopes 6H:1V or flatter
- There are approved high-tension cable barrier systems that can be placed on slopes as steep as 4H:1V. The use of these systems requires special placement considerations, contact the HQ Design Office for guidance.
- Along horizontal curves, consider installing along the inside of the curve. Reduce post spacing per manufacturer's recommendations
- Provide an obstruction free zone within the cable barrier system's lateral deflection distance, see 1610.05(2).

Exhibit 1610-14b Roadside Cable Barrier Placement



Notes:

1 Provide an obstruction free zone within the cable barrier's lateral deflection distance, see 1610.05(2)

1610.05(2) High-Tension Cable Barrier Lateral Deflection Distances

Depending on the high-tension cable barrier system, lateral deflection distances for each barrier system vary based upon the length of the barrier run, the spacing of the end anchors, and post spacing. Provide an obstruction free zone within the system's lateral deflection distance for the following situations:

1. In the direction of travel (located in the median or along roadside), locate the cable barrier system so that there are no fixed objects within the limits of the cable barrier lateral deflection distance.

2. For opposing traffic (where present), locate the cable barrier to provide lateral deflection distance to prevent a vehicle's encroachment into the opposite lane of travel.

Provide a minimum 12-feet for cable barrier lateral deflection distance and specify the minimum allowable lateral deflection distance in the contract documents in order for the contractor to select a cable barrier manufacturer that can meet the lateral deflection requirements.

Note: There are new high-tension cable barrier systems under development that may change selection and placement criteria. For example, newer systems may allow placement on steeper slopes or have reduced deflection distances. Contact the HQ Design Office for guidance.

1610.05(3) High-Tension Cable Barrier Height


A high-tension four-cable barrier system shall provide a height to the center of the top cable of not less than 35 inches and a height to the center of the bottom cable not greater than 19 inches. Previous testing of cable barrier systems has shown that providing cables within the ranges specified typically restrains a vehicle traversing the various slopes and reduces the possibility of the vehicle either overriding or under riding the cable barrier.

1610.05(4) High-Tension Cable Barrier Termination

Manufacturers of high-tension four-cable barrier systems provide designed anchors for the ends of cable barrier runs. Other alternatives to end a cable barrier include:

- It is possible to terminate high-tension cable barrier systems by connecting directly to beam guardrail runs (such as transitions to bridge rails) or to a separate cable barrier anchorage system. Review field conditions, check local maintenance personnel needs, and then specify the required connection option in the contract documents. If a separate anchorage system is used, refer to Exhibit 1610-15 for placement guidance.
- When cable barrier is connected to a more rigid barrier, a transition section is typically needed. Contact the HQ Design Office for further details.

Exhibit 1610-15 Cable Barrier Placement for Divided Highways




Cable Barrier Median Overlap

$$BO = \frac{LH1 - L2}{(LH1/LR)}$$ (Direction A shown)

Note:

Calculate barrier overlap (BO) from both directions of travel. Use the greatest value of BO obtained.



Cable Barrier Overlap with Beam Guardrails

Notes:

- The beam guardrail may need to be extended and flared to maintain adequate barrier overlap and shoulder width.
- Typical applications may be at either bridge transitions or where high-tension cable and beam guardrail systems end or begin.
- For supporting length of need equation factors, see Exhibit 1610-6.

1610.05(5) High-Tension Cable Barrier Curb Placement

Avoid the placement of curb in conjunction with high-tension cable barrier systems. Currently, there are no known acceptable cable barrier systems that have been successfully crash tested with this feature present.

1610.06 Concrete Barrier

Concrete barriers are identified as either rigid, rigid anchored, or unrestrained rigid systems. They are commonly used in medians and as shoulder barriers. These systems are stiffer than beam guardrail or cable barrier, and impacts with these barriers tend to be more severe. Consider the following when installing concrete barriers:


- For slopes 10H:1V or flatter, concrete barrier can be used anywhere outside of the shoulder.
- Do not use concrete barrier at locations where the foreslope into the face of the barrier is steeper than 10H:1V.
- Light standards mounted on top of precast concrete median barrier must not have breakaway features. (See the concrete barrier light standard section in the *Standard Plans*.)
- When considering concrete barrier use in areas where drainage and environmental issues (such as stormwater, wildlife, or endangered species) might be adversely impacted, contact the HQ Hydraulics Office and/or the appropriate environmental offices for guidance. Also, refer to 1610.02.

1610.06(1) Concrete Barrier Shapes

Concrete barriers use a single-slope or safety shape (New Jersey or F-Shape) to redirect vehicles while minimizing vehicle vaulting, rolling, and snagging. A comparison of these barrier shapes is shown in Exhibit 1610-16.

The single-slope barrier face is the recommended option for embedded rigid concrete barrier applications.

Exhibit 1610-16 Concrete Barrier Shapes



When the single-slope or F-Shape face is used on structures, and precast barrier is selected for use on the approaches, a cast-in-place transition section is needed so that no vertical edges of the barrier are exposed to oncoming traffic. For details on bridge rail designs, see the *Bridge Design Manual*.

For aesthetic reasons, avoid changes in the shape of the barrier face within a project or corridor.

The New Jersey shape and F-shape barriers are commonly referred to as "safety shapes." The New Jersey shape and F-shape have an initial overall height of 32 inches. This height includes provision for up to a 3-inch future pavement overlay that can reduce the barrier height to 29 inches minimum.

1610.06(1)(a) Safety Shape Barrier

The New Jersey shape face is primarily used on precast concrete barrier.

Concrete Barrier Type 2 (see the *Standard Plans*) is a freestanding precast barrier that has the New Jersey shape on two sides. It can be used for both median and shoulder installations. Unanchored units are connected with steel pins through wire rope loops. For permanent installation, this barrier is placed on a paved surface and a paved surface is provided beyond the barrier for deflection. See Exhibit 1610-3 for deflection requirements.

The cost of precast Type 2 barrier is significantly less than the cost of the cast-in-place barriers. Therefore, consider the length of the barrier run and the deflection needs to determine whether transitioning to precast Type 2 barrier is desirable. If precast Type 2 barrier is used for the majority of a project, use the New Jersey face for small sections that need cast-in-place barrier, such as for a light standard section, see the *Standard Plans* for additional details for transitioning the barrier faces.

Concrete barrier Type 4 is a precast, single-faced New Jersey shape barrier. These units are not freestanding and are to be placed against a rigid structure or anchored to the pavement. If Type 4 barriers are used back to back, fill any gap between them to prevent tipping.

Precast barrier can be anchored where a more rigid barrier is needed. (Anchoring methods are shown in the *Standard Plans*.) Anchors Type 1 and Type 2 are for temporary installations on a rigid pavement. Anchor Type 3 can be used in temporary or permanent installations on an asphalt pavement. Consult the WSDOT BSO for details when anchoring permanent precast concrete barrier to a rigid pavement.

Precast barrier used on the approach to bridge rail is to be connected to the bridge rail by installing wire rope loops embedded 1-foot 3-inches into the bridge rail with epoxy resin and as detailed in the *Standard Plans*.

Place unrestrained (unanchored) precast concrete barrier on slopes of 5% (20H:1V) or flatter where possible. The maximum slope for placement of concrete barrier is 10% (10H:1V).

In the past WSDOT used a Type 5 single-faced New Jersey shape for special applications, such as adjacent to bridge rails with similar shapes. The Type 5 barrier is seldom used by WSDOT. See the Plan Sheet Library for more information on Type 5 barrier:
http://www.wsdot.wa.gov/Design/Standards/PlanSheet/TB-5.htm.

1610.06(1)(b) Single-Slope Barrier

Single-slope barrier is available in various heights, as shown in the *Standard Plans*. Single-slope concrete barrier can be cast in place or precast. A primary benefit of using precast single-slope barrier is that it can be used as temporary barrier during construction and then reset into a permanent location. In temporary applications, the height of the single-slope barrier may also offer the added benefits of reducing headlight glare and providing reduced deflection characteristics over some other barrier types.

Single-slope barrier is considered a rigid system regardless of the construction method used provided the barrier is embedded a minimum of 3-inches in the roadway wearing surface on both sides. When precast single-slope barrier is installed on top of the roadway surface, it is considered a rigid unrestrained system and barrier deflection needs to be provided as shown in Exhibit 1610-3.

For new installations, the minimum height of single-slope barrier above the roadway is 2 feet 10 inches, which allows a 2-inch tolerance for future overlays. The minimum total height of the barrier section is 3 feet 6 inches (including embedment). This allows for use of the 3-foot-6-inch barrier between roadways with grade separations of up to 5 inches. A grade separation of up to 10 inches is allowed when using a 4-foot-6-inch high barrier section, as shown in the *Standard Plans*. The barrier is to have a depth of embedment equal to or greater than the grade separation. Contact the WSDOT BSO for grade separations greater than 10 inches.

1610.06(1)(c) High-Performance Concrete Barrier

High-Performance Concrete Barrier (HP Barrier) is a rigid barrier with a minimum height of 3-foot-6-inch above the roadway surface. This barrier is designed to function more effectively during heavy-vehicle crashes. This taller barrier may also offer the added benefits of reducing headlight glare and reducing noise in surrounding environments. WSDOT HP Barrier utilizes the single-slope shape. (See the *Standard Plans* for barrier details.)

Use HP Barrier in freeway medians of 22 feet or less. Also, use HP Barrier on Interstate or freeway routes where collision history suggests a need or where roadway geometrics increase the possibility of larger trucks hitting the barrier at a high angle (for example, on-ramps for freeway-to-freeway connections with sharp curvature in the alignment).

Consider the use of HP Barrier at other locations such as highways with narrow medians, near highly sensitive environmental areas, near densely populated areas, over or near mass transit facilities, or on vertically divided highways.

1610.06(1)(d) Low-Profile Barrier

Low-profile barrier designs are available for median applications where the posted speed is 45 mph or below. These barriers are normally used in urban areas. They are typically 18 to 20 inches high and offer sight distance benefits. For barrier designs, terminals, and further details, contact the HQ Design Office.

1610.06(2) Concrete Barrier Height

Overlays in front of safety shape concrete barriers can extend to the top of the lower, near-vertical face of the barrier before adjustment is necessary.

- Allow no less than 2-foot 5 inches from the pavement to the top of the safety shape barriers. Allow no less than 2-foot 8-inches from the pavement to the top of the single-slope barrier.

1610.06(3) Concrete Barrier Terminals

Whenever possible, bury the blunt end of a concrete barrier run into the backslope of the roadway. If the end of a concrete barrier run cannot be buried in a backslope or terminated as described below, terminate the barrier using a guardrail terminal and transition or an impact attenuator (see Chapter 1620).

To bury the blunt end of the barrier into a backslope, the following conditions must be met:

- The backslope is 3H:1V or steeper
- The backslope extends minimum of 4 feet in height above the edge of shoulder
- Flare the concrete barrier into the backslope using a flare rate that meets the criteria in 1610.03(4)
- Provide a 10H:1V or flatter foreslope into the face of the barrier and maintain the full barrier height until the barrier intersects with the backslope. This might create the need to fill ditches and install culverts in front of the barrier face.

The 7-foot-long precast concrete barrier Type 2 and the 10- to 12-foot single-slope barrier terminal (precast or cast-in-place) may be used for the following conditions:

- Outside the Design Clear Zone.
- On the trailing end of the barrier when it is outside the Design Clear Zone for opposing traffic.
- On the trailing end of one-way traffic.
- Where the posted speed is 25 mph or below.

See the *Standard Plans* for barrier terminal details.

1610.07 Bridge Traffic Barriers

Bridge traffic barriers redirect errant vehicles and help to keep them from going over the side of the structure. (See the *Bridge Design Manual* for information regarding bridge barrier on new bridges and replacement bridge barrier on existing bridges).

When considering work on a bridge traffic barrier consult the WSDOT BSO.

- For new bridge barrier installations, a 2-foot 10-inch-high single-slope or a 2-foot 8-inch-high safety shape (F Shape) bridge barrier may be required.
- Taller 3-foot 6-inch single-slope or safety shape bridge barriers may be required on Interstate or freeway routes where collision history suggests a need or where taller barrier is required on approaching roadways with narrow medians, as defined in 1610.06(1)(c).
- Also, the taller 3-foot 6-inch barrier may be required when geometrics increase the possibility of larger trucks hitting the barrier at a high angle (such as on-ramps for freeway-to-freeway connections with sharp curvature in the alignment).


Approach barriers, transitions, and connections are usually needed on all four corners of bridges carrying two-way traffic and on both corners of the approach end for one-way traffic. (See 1610.04(6) for guidance on transitions). A transition is available to connect the Type 2 concrete barrier (New Jersey shape) and the bridge barrier (F-Shape.) (See the *Standard Plans* for further details).

Bridge railing attaches to the top of the bridge barrier. When bridge barrier is included in a project, the bridge rails, including crossroad bridge rail, are to be addressed. Consult the WSDOT BSO regarding bridge rail selection and design and for design of the connection to an existing bridge. Consider the following:

- Use an approved, crash-tested concrete bridge rail on new bridges or bridges to be widened. The *Bridge Design Manual* provides examples of typical bridge rails.
- An existing bridge rail on a highway with a posted speed of 30 mph or below may remain in place if it is not located on a bridge over a National Highway System (NHS) highway. When Type 7 bridge rail is present on a bridge over an NHS highway with a posted speed of 30 mph or below, it may remain in place regardless of the type of metal rail installed. Other bridge rails are to be evaluated for strength and geometrics. (See 1610.07(1) for guidance on retrofit techniques.)
- The Type 7 bridge rail is common. Type 7 bridge rails have a curb, a vertical-face parapet, and an aluminum top rail. The curb width and the type of aluminum top rail are factors in determining the adequacy of the Type 7 bridge rail, as shown in Exhibit 1610-17. Consult the WSDOT BSO for assistance in evaluating other bridge rails.

When considering an overlay on a bridge, consult the WSDOT BSO to verify the overlay depth can be placed on the bridge deck based on the type of traffic barrier. There may be instances where the height of the bridge barrier will not allow for the planned overlay depth without removal of existing pavement.

Exhibit 1610-17 Type 7 Bridge Rail Upgrade Criteria



Aluminum Rail Type	Curb Width	
	9 Inches or Less	Greater Than 9 Inches*
Type R, S, or SB	Bridge rail adequate	Bridge rail adequate
Type 1B or 1A	Bridge rail adequate	Upgrade bridge rail
Other	Consult the WSDOT BSO	

*When the curb width is greater than 9 inches, the aluminum be able to withstand a 5 kip load.

1610.07(1) Bridge Barrier Retrofit

If the bridge barrier system does not meet the criteria for strength and geometrics, modifications to improve its redirectional characteristics and its strength may be needed. Consult the WSDOT BSO to determine which retrofit method described below can be completed.

1610.07(1)(a) Concrete Safety Shape

Consult the WSDOT BSO to determine whether the existing bridge deck and other superstructure elements are of sufficient strength to accommodate this bridge barrier system and provide design details for the retrofit. Retrofitting with a new concrete bridge barrier is costly and requires authorization from Program Management when no widening is proposed.

1610.07(1)(b) Thrie Beam Retrofit

Retrofitting the bridge barrier with thrie beam is an economical way to improve the strength and redirectional performance of a bridge barrier. The thrie beam can be mounted to steel posts or the existing bridge barrier, depending on the structural adequacy of the bridge deck, the existing bridge barrier type, the width of curb (if any), and the curb-to-curb roadway width carried across the structure. Exhibit 1610-18 shows typical retrofit criteria.


Consider the Service Level 1 (SL-1) system on bridges with wooden decks and for bridges with concrete decks that do not have the needed strength to accommodate the thrie beam system. Contact the HQ Bridge and Structures Office for information needed for the design of the SL-1 system.

If a thrie beam retrofit results in reduction in sidewalk width ensure ADA compliance is addressed, see Chapter 1510.

The funding source for retrofit of existing bridge rail is dependent on the length of the structure. Bridge rail retrofit for bridges less than 250 feet in length or a total bridge rail length of 500 feet is funded by the project (Guardrail Preservation or Improvement). For longer bridges, the retrofit will be included in the I-2 Bridge Rail upgrades program. Contact the HQ Program Development Office to determine whether funding is available.

Exhibit 1610-18 Thrie Beam Rail Retrofit Criteria

Curb Width	Bridge Width	Concrete Bridge Deck		Wood Bridge Deck or Low- Strength Concrete Deck
		Concrete Bridge Rail (existing)	Steel or Wood Post Bridge Rail (existing)	
<18 inches		Thrie beam mounted to existing bridge rail [2] and blocked out to the face of curb. Height = 32 inches.	Thrie beam mounted to steel posts [2] at the face of curb. Height = 32 inches	• Service Level 1 Bridge Rail. [2] • Height = 32 inches. • Curb or wheel guard needs to be removed.
>18 inches	**> 28 ft (curb to curb)**	Thrie beam mounted to steel posts[2] at the face of curb. [1] Height = 32 inches.		
>18 inches	**< 28 ft (curb to curb)**	Thrie beam mounted to existing bridge rail.[2] Height = 35 inches.	Thrie beam mounted to steel posts [2] in line with existing rail. Height = 35 inches.	



Notes:

[1] To maximize available curb/sidewalk width for pedestrian use, thrie beam may be mounted to the bridge rail at a height of 35 inches.

[2] Contact the WSDOT BSO for design details on bridge rail retrofit projects.

1610.08 Other Barriers

1610.08(1) Redirectional Landform

Redirectional landforms, also referred to as earth berms, were formerly installed to help mitigate crashes with fixed objects located in depressed medians and at roadsides. They were constructed of materials that provided support for a traversing vehicle. With slopes in the range of 2H:1V to 3H:1V, they were intended to redirect errant vehicles. The use of redirectional landforms has been discontinued. Where redirectional landforms currently exist as mitigation for a fixed object, provide alternative means of mitigation of the fixed object, such as remove, relocate, upgrade with crash-tested systems, or shield with barrier. Landforms may be used to provide a smooth surface at the base of a rock cut slope.

1610.08(2) Aesthetic Barrier Treatment

When designing a barrier for use on a Scenic Byway, consider barriers that are consistent with the recommendations in the associated corridor management plan (if one is available). Contact the region or HQ Landscape Architect Office to determine whether the project is on such a designated route. Low-cost options may be feasible, such as weathering agents, stains, colorants, or coatings applied to galvanized steel beam guardrail and its components. Higher-cost options, such as steel-backed timber rail and stone guardwalls, might necessitate a partnering effort to fund the additional costs. Grants might be available for this purpose if the need is identified early in the project definition phase.

1610.08(3) Steel-Backed Timber Guardrail

Steel-backed timber guardrails consist of a timber rail with a steel plate attached to the back to increase its tensile strength. There are several variations of this system that have passed crash tests. The nonproprietary systems use a beam with a rectangular cross section that is supported by either wood or steel posts.

A proprietary (patented) system, called the Ironwood Guardrail, is also available. This system uses a beam with a round cross section and is supported by steel posts with a wood covering to give the appearance of an all-wood system from the roadway. The incorporation of the Ironwood Guardrail will need to be documented. Consult with the Assistant State Design Engineer to determine what justification (proprietary or a public interest finding) will be required.

The most desirable method of terminating the steel-backed timber guardrail is to bury the end in a backslope, as described in 1610.04(5). When this type of terminal is not possible, use of the barrier is limited to highways with a posted speed of 45 mph or below. On these lower-speed highways, the barriers can be flared away from the traveled way as described in 1610.03(4) and terminated in a berm outside the Design Clear Zone.

For details on these systems, contact the HQ Design Office.

1610.08(4) Stone Guardwalls

Stone guardwalls function like rigid concrete barriers but have the appearance of natural stone. These walls can be constructed of stone masonry over a reinforced concrete core wall or of simulated stone concrete. These types of barriers are designed to have a limited textured

projection of the stones to help aid in the redirectional characteristics of the barrier. The most desirable method of terminating this barrier is to bury the end in a backslope, as described in 1610.06(3). When this type of terminal is not possible, use of the barrier is limited to highways with a posted speed of 45 mph or below. On these lower-speed highways, the barrier can be flared away from the traveled way and terminated in a berm outside the Design Clear Zone.

For details on these systems, contact the HQ Design Office.

1610.08(5) Dragnet

The Dragnet Vehicle Arresting Barrier consists of chain link or fiber net that is attached to energy absorbing units. When a vehicle hits the system, the Dragnet brings the vehicle to a controlled stop with limited damage. Possible uses for this device include the following:

- Reversible lane entrances and exits
- Railroad crossings
- Truck escape ramps (instead of arrester beds—see Chapter 1270)
- T-intersections
- Work zones
- Swing span bridges

Coordinate with the HQ Design Office for design details.

1610.09 References

1610.09(1) Design Guidance

WSDOT Roadside Safety site: http://www.wsdot.wa.gov/Design/Policy/RoadsideSafety.htm

Bridge Design Manual LRFD, M 23-50, WSDOT

Roadside Design Guide, AASHTO, 2011 with Errata (July 2015)

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 21-01, WSDOT

Traffic Manual, M 51-02, WSDOT

1610.09(2) Supporting Information

Manual for Assessing Safety Hardware (MASH), AASHTO, 2009

NCHRP 350, TRB, 1993

Determining Length of Need. This e-learning course for WSDOT employees covers the "Length of Need," which is a calculation of how much longitudinal barrier is necessary to shield objects on the roadside. Request this training via the web-based Learning Management System.

Chapter 1620 Impact Attenuator Systems

1620.01 General
1620.02 Design Criteria
1620.03 Selection
1620.04 Impact Attenuator Systems
1620.05 Documentation

1620.01 General

Impact attenuator systems are protective systems that help aid an errant vehicle from impacting an object by either gradually decelerating the vehicle to a stop when hit head-on or by redirecting it away from the feature when struck on the side. These systems are used for rigid objects or other features that cannot be removed, relocated, or made breakaway.

Approved systems are shown in Exhibits 1620-1a and 1620-1b and on the Washington State Department of Transportation (WSDOT) Headquarters (HQ) Design Office web page:
www.wsdot.wa.gov/design/policy/roadsidesafety.htm

Approved systems shall meet standardized testing defined in National Cooperative Highway Research Program (NCHRP) Report 350 or the American Association of State Highway and Transportation Officials (AASHTO) *Manual for Assessing Safety Hardware* (MASH). In addition, these devices shall have an acceptance letter from FHWA that certifies that the device meets the appropriate crash test criteria and is eligible for federal-aid reimbursement.

1620.02 Design Criteria

The following design criteria apply to new, existing, or reset permanent and temporary impact attenuators.

Impact attenuators are placed so that they do not present a feature that needs mitigating in relation to opposing traffic. For median and reversible lane locations, the backup structure or attenuator-to-object connection is designed to help in aiding opposing traffic from being snagged.

Avoid placement of curbs between attenuators and traffic. Refer to the specific attenuator manufacturer's instructions if considering placement of curbing between an attenuator and the travelled way. It is desirable that existing curbing be removed and the surface smoothed with asphalt or cement concrete pavement before an impact attenuator is installed. However, mountable curbs 4 inches or less in height may be retained depending on the feasibility of their removal.

In general, attenuators are aligned parallel to the roadway except the inertial barriers.

Consult with the Area Maintenance Superintendent who will be maintaining the system prior to selecting the attenuator systems to include in a construction contract.

1620.03 Selection

To select an appropriate impact attenuator system, the following factors must be assessed:

- Posted speed
- Operating speed
- Average daily traffic (ADT)
- Repair crew exposure
- Proximity to the roadway
- Anticipated number of yearly impacts
- Available space (length and width)
- Maintenance costs
- Initial cost
- Duration (permanent or temporary use)
- Portion of the impact attenuator that is redirective/nonredirective (see Exhibit 1620-2)
- Width of object to be shielded

It is very important for designers to take into account the portion of an impact attenuator that is designed to redirect vehicles during a side impact of the unit. It is crucial that fixed objects, either permanent or temporary (such as construction equipment), are not located behind the nonredirective portion of these devices.

The posted speed is a factor in the selection of many impact attenuators. Use Exhibits 1620-1a and 1620-1b to select the system and configuration appropriate for the posted speed. In the interest of a cost-effective design, selecting a system applicable for the posted speed is recommended (although using a system tested for a higher speed is acceptable). Where there is evidence that the average operating speed of the facility is higher than the posted speed, consider selecting an attenuator system rated at the facility's operating speed. Manufacturer's product information may indicate that a longer system (than what is in Exhibits 1620-1a and 1620-1b) is required for speeds of 70 mph or greater. These models are generally referred to as "high speed" or "70 mph" systems. Use of these systems on facilities with 70 mph posted speeds is not required, and selection of a system rated for at least 60 mph will typically be appropriate for most sites on these facilities. For permanent installations where unusual conditions warrant consideration of a high-speed device, these systems are available and may be used with justification. Contact the HQ Design Office for guidance when selecting one of these systems.

For a comparison summary of space and initial cost information related to impact attenuator systems, see Exhibits 1620-1a and 1620-1b.

When maintenance costs are considered, anticipate the average annual impact rate. If few impacts are anticipated, lower-cost devices such as inertial barriers might meet the need. (See Chapter 301 for examples of how to determine lifecycle costs for proposed hardware). Inertial barriers have the lowest initial cost and initial site preparation. However, maintenance will be costly and necessary after each impact. Labor and equipment are needed to clean up the debris and install new containers (barrels). Inertial barriers are not be used where flying debris might be a danger to pedestrians.

In selecting a system, one consideration is the anticipated exposure to traffic that the workers making the repairs may encounter. In areas with high traffic exposure, a low-maintenance system that can be repaired quickly is most desirable. Some systems need nearly total replacement or replacement of critical components (such as cartridges or braking mechanisms) after a head-on impact, while others simply need resetting.

It is very important to consider that each application is unique when selecting impact attenuators for use in particular applications. This applies to both permanent and temporary installations. When specifying the system or systems that can be used at a specific location, the list shown in Exhibits 1620-1a and 1620-1b are to be used as a starting point. As the factors discussed previously are analyzed, inappropriate systems may be identified and eliminated from further consideration. Systems that are not eliminated may be appropriate for the project. When the site conditions vary, it might be necessary to have more than one list of acceptable systems within a contract. Systems are not to be eliminated without documented reasons. Also, wording such as "or equivalent" is not to be used when specifying these systems. If only one system is found to be appropriate, then approval from the Assistant State Design Engineer of a public interest finding for the use of a sole source proprietary item is needed.

When a transition to connect with a concrete barrier, fixed object, or beam guardrail is needed (see impact attenuator descriptions in 1620.04), the transition type and connection may need to be specified. In most cases, the transition type and connection required will be a custom design per the manufacturer (these transitions are included in the cost of the impact attenuator). In a few cases, the transition type and connection to use will be as described in Chapter 1610 and the *Standard Plans* (these transition sections are not included in the cost of the impact attenuator and must be included as a separate bid item in the construction contract). Consult with the Area Maintenance Superintendent who will be maintaining the systems before finalizing the list of attenuators to be included in the contract.

1620.03(1) Low-Maintenance Category

The QuadGuard Elite, SCI100GM/SCI70GM, and REACT 350 are considered low-maintenance devices. These devices have a higher initial cost, requiring substantial site preparation, including a backup or anchor wall in some cases and cable anchorage at the front of the installation. However, repair costs are comparatively low, with labor typically being the main expense. Maintenance might not be needed after minor side impacts with these systems.

Installation of a low-maintenance device is desirable at locations that meet at least one of the following criteria:

- Sites with an ADT of 25,000 or greater
- Sites with a history/anticipation of more than one impact-per year
- Sites with unusually challenging conditions, such as limitations on repair time, a likelihood of frequent night repairs, or narrow gore locations

Document the decision in the DDP to use any device other than a low-maintenance device at locations meeting at least one of the criteria above.

Consider upgrading existing ADIEM, G-R-E-A-T, and Hex-Foam Sandwich impact attenuators to low-maintenance devices when the repair history shows one or more impacts per year over a three- to five-year period.

The HQ Design Office conducts an annual review of maintenance records to consider which devices should be included in the Low-Maintenance category. For a description of requirements that need to be met in order to be included in the Low-Maintenance category, see:
www.wsdot.wa.gov/publications/fulltext/design/roadsidesafety/low_maint.pdf


1620.04 Impact Attenuator Systems

1620.04(1) Permanent Installations

For systems used in permanent installations, a description of the system's purpose, parts, and function, as well as transition needs, foundation, and slope requirements are provided as follows and in Exhibits 1620-1a and 1620-1b.

1620.04(1)(a) Brakemaster 350


1. **Purpose:** The Brakemaster 350 system is an end treatment for W-beam guardrail and concrete barrier.
2. **Description:** The system contains an embedded anchor assembly, brake cable, W-beam fender panels, steel posts, tension and transition straps, and diaphragms.
3. **Function:** The system uses a brake and cable device for head-on impacts and for redirection. The cable is embedded in a concrete anchor at the end of the system.
4. **Foundation:** A concrete foundation is not needed for this system, but a paved surface is recommended.
5. **Slope:** 10H:1V or flatter slope between the edge of the traveled way and the near face of the unit.
6. **Transitions:** If used as an end treatment for concrete barrier, the system must be connected to the barrier with a transition section (not included in the cost of the attenuator). See Chapter 1610 and the *Standard Plans* for the type of transition section and connection required.
7. **Manufacturer/Supplier:** Energy Absorption Systems



Brakemaster 350 – Permanent Installations

1620.04(1)(b) Crash Cushion Attenuating Terminal (CAT-350)


1. **Purpose:** The CAT-350 is an end treatment for W-beam guardrail and concrete barrier.
2. **Description:** The system consists of slotted W-beam guardrail mounted on both sides of breakaway timber posts. Steel sleeves with soil plates hold the timber posts in place.
3. **Function:** When hit head-on, the slotted guardrail is forced over a pin that shears the steel between the slots. This shearing helps dissipate the energy of the impact.
4. **Foundation:** A concrete foundation or paved surface is not needed. Can be installed in soil.
5. **Slope:** 10H:1V or flatter slope between the edge of the traveled way and the near face of the unit.
6. **Transitions:** If used as an end treatment for concrete barrier, the system must be connected to the barrier with a transition section (not included in the cost of the attenuator). (See Chapter 1610 and the *Standard Plans* for the type of transition section and connection required.)
7. **Manufacturer/Supplier:** Trinity Industries, Inc.



CAT 350 – Permanent Installations

1620.04(1)(c) QuadTrend 350

1. **Purpose:** The QuadTrend 350 is an end treatment for 2-foot-8-inch-high concrete barriers. The system's short length may allow it to be used at the ends of certain bridges where the installation of a beam guardrail transition and terminal is not feasible and manufacturer's requirements for slope and clear area behind the device can be met.
2. **Description:** This system consists of telescoping quadruple corrugated fender panels mounted on steel posts with slip bases, a tension strap, sand-filled boxes, and a ground-level redirective cable.
3. **Function:** Sand-filled boxes attached to the posts help dissipate a portion of the energy of an impact. In head-on impacts, the anchored ground-level cable installed behind the fender panels directs the vehicle behind and away from the barrier end. Side impacts within the redirective portion of the system, which begins 10.5 ft. from the nose of the system, are redirected toward the roadway.
4. **Foundation:** The system is installed on a concrete foundation to support the steel posts.
5. **Slope:** A 10H:1V or flatter slope is needed on the approaches to the device and to 3 ft. behind the system. A 6H:1V or flatter slope is needed behind the barrier to allow for vehicle recovery.
6. **Transitions:** No transition section is needed for connection to a vertical wall or vertical concrete barrier. A custom transition section per manufacturer's specifications is needed for connection to non-vertical concrete barrier such as New Jersey or F-Shape barrier (included in the cost of the attenuator).
7. **Manufacturer/Supplier:** Energy Absorption Systems



QuadTrend 350 – Permanent Installations

1620.04(1)(d) Universal TAU-II

1. **Purpose:** The Universal TAU-II crash cushion system is an end treatment for concrete barrier, beam guardrail, and fixed objects up to 8 feet wide.
2. **Description:** The system is made up of overlapping thrie beam panels, structural support diaphragms, supported cables, energy absorbing cartridges, and foundation anchors.
3. **Function:** During a head-on hit, energy-absorbing cartridges and structural support diaphragms help dissipate the energy of the impact as they are guided by high strength galvanized steel cables and overlapping thrie beam panels. In a side impact, the thrie beam rail panels redirect the vehicle back toward the roadway.
4. **Foundation:** The system is installed on either a concrete foundation or an asphalt foundation that conforms to the manufacturer's recommendations.
5. **Slope:** 10H:1V or flatter slope between the edge of the traveled way and the near face of the unit.
6. **Transitions:** A transition section is not needed for concrete barrier or fixed objects exposed to traffic from only one direction. A custom transition section per manufacturer's specifications is needed for all connections to beam guardrail and for connection to a concrete barrier or fixed object exposed to bi-directional traffic (included in the cost of the attenuator).
7. **Manufacturer/Supplier:** Barrier Systems, Inc.



Universal TAU-II – Permanent Installations

1620.04(1)(e) QuadGuard and QuadGuard II

1. **Purpose:** The QuadGuard and QuadGuard II provide end treatments for concrete barrier and beam guardrail. The QuadGuard can be used to mitigate fixed objects up to 10 feet wide and the QuadGuard II can be used to mitigate fixed objects up to 7 feet 6 inches wide.
2. **Description:** These systems consist of a series of Hex-Foam cartridges surrounded by a framework of steel diaphragms and quadruple corrugated fender panels. The QuadGuard and QuadGuard II use the same framework, but the QuadGuard II is shorter in length than the QuadGuard for any given posted speed.
3. **Function:** The internal shearing of the cartridges and the crushing of the energy absorption material dissipates impact energy from end-on hits. The fender panels redirect vehicles impacting the attenuator on the side.
4. **Foundation:** The systems are installed on a concrete foundation.
5. **Slope:** If the site has excessive grade or cross slope, additional site preparation or modification to the units in accordance with the manufacturer's literature is needed. "Excessive" is defined as steeper than 8% for the QuadGuard and QuadGuard II.
6. **Transitions:** A transition section is not needed for concrete barrier and fixed objects exposed to traffic from only one direction. A custom transition section per manufacturer's specifications is needed for all connections to beam guardrail and for connection to a concrete barrier or fixed object exposed to bi-directional traffic (included in the cost of the attenuator).
7. **Manufacturer/Supplier:** Energy Absorption Systems



QuadGuard – Permanent and Work Zone Installations

1620.04(1)(f) QuadGuard Elite

1. **Purpose:** The QuadGuard Elite is an end treatment for concrete barrier, beam guardrail, and fixed objects up to 7 feet 6 inches wide.
2. **Description:** The system consists of telescoping quadruple corrugated fender panels mounted on both sides of a series of polyethylene cylinders contained within steel diaphragms.
3. **Function:** The cylinders are compressed during a head-on impact and typically return to their original shape, which may provide continued shielding of the fixed object after the impact. The fender panels redirect vehicles impacting the attenuator on the side. It is anticipated that this system will not need many replacement parts or extensive repair following an impact.
4. **Foundation:** The system is installed on a concrete foundation.
5. **Slope:** If the site has excessive grade or cross slope, additional site preparation or modification to the units in accordance with the manufacturer's literature is needed. "Excessive" is defined as steeper than 8% for the QuadGuard Elite.
6. **Transitions:** A transition section is not needed for concrete barrier and fixed objects exposed to traffic from only one direction. A custom transition section per manufacturer's specifications is needed for all connections to beam guardrail and for connection to a concrete barrier or fixed object exposed to bi-directional traffic (included in the cost of the attenuator).
7. **Manufacturer/Supplier:** Energy Absorption Systems



QuadGuard Elite – Permanent and Work Zone Installations

1620.04(1)(g) QuadGuard M10

1. **Purpose:** The QuadGuard M10 is an end treatment for concrete barrier, beam guardrail, and fixed objects up to 7 feet 6 inches wide.
2. **Description:** The system consists of a series of energy-absorbing cartridges surrounded by a framework of steel diaphragms and quadruple corrugated fender panels.
3. **Function:** The internal shearing of the cartridges and the crushing of the energy absorption material dissipates impact energy from end-on hits. The fender panels redirect vehicles impacting the attenuator on the side.
4. **Foundation:** The system is installed on a concrete foundation.
5. **Slope:** If the site has excessive grade or cross slope, additional site preparation or modification to the unit in accordance with the manufacturer's literature is needed. "Excessive" is defined as steeper than 8% for the QuadGuard M10.
6. **Transitions:** A transition section is not needed for concrete barrier and fixed objects exposed to traffic from only one direction. A custom transition section per manufacturer's specifications is needed for all connections to beam guardrail and for connection to a concrete barrier or fixed object exposed to bi-directional traffic (included in the cost of the attenuator).
7. **Manufacturer/Supplier:** Energy Absorption Systems



QuadGuard M10 – Permanent and Work Zone Installations

1620.04(1)(h) HEART


1. **Purpose:** The HEART is an end treatment for concrete barriers and fixed objects up to 2 feet wide.
2. **Description:** The system consists of High Density Polyethylene (HDPE) side panels and a rounded nose piece connected to steel diaphragms with tensioning cables that are mounted on a tubular steel track.
3. **Function:** During an end-on impact, the side panels and steel diaphragms help dissipate impact energy as they are pushed toward the rear of the system along the track. In a side impact, the side panels and tensioning cables redirect the vehicle.
4. **Foundation:** The system is installed on a concrete foundation or paved surface conforming to the manufacturer's recommendations.
5. **Slope:** 12H:1V or flatter slope between the edge of the traveled way and the near face of the unit.
6. **Transitions:** A transition section is not needed for concrete barrier and fixed objects exposed to traffic from only one direction. A custom transition section per manufacturer's specifications is needed for connection to a concrete barrier or fixed object exposed to bi-directional traffic (included in the cost of the attenuator).
7. **Other:** The HEART should not be installed behind a curb.
8. **Manufacturer/Supplier:** Trinity Industries, Inc.



HEART – Permanent and Work Zone Installations

1620.04(1)(i) Reusable Energy Absorbing Crash Terminal (REACT 350)


1. **Purpose:** The REACT 350 is an end treatment for concrete barriers and fixed objects up to 3 feet wide.
2. **Description:** The system consists of polyethylene cylinders with varying wall thicknesses, redirecting cables, a steel frame base, and a backup structure.
3. **Function:** The redirecting cables are anchored in the concrete foundation at the front of the system and in the backup structure at the rear of the system. When hit head-on, the cylinders compress, absorb the impact energy, and immediately return to much of their original shape, position, and capabilities. For side impacts, the cables restrain the system enough to help prevent penetration and redirect the vehicle. It is anticipated that this system will not need many replacement parts or extensive repairs following an impact.
4. **Foundation:** The system is installed on a concrete foundation.
5. **Slope:** If the site has excessive grade or cross slope, additional site preparation or modification to the units in accordance with the manufacturer's literature is needed. "Excessive" is defined as steeper than 8% for the REACT 350.
6. **Transitions:** Depending on traffic flow directions, the shape of the toe of the concrete barrier, and the ability to offset the system on the site, modifications to the toe of the concrete barrier and/or a custom transition section per manufacturer's specifications may be needed to prevent vehicle snagging (included in the cost of the attenuator).
7. **Manufacturer/Supplier:** Energy Absorption Systems



REACT 350 – Permanent and Work Zone Installations

1620.04(1)(j) REACT 350 Wide


1. **Purpose:** The REACT 350 Wide is a device that can be used to shield fixed objects with widths up to 10 feet wide.
2. **Description:** The system consists of polyethylene cylinders with varying wall thicknesses, internal struts, space frame diaphragms, and a monorail.
3. **Function:** When hit head-on, the cylinders compress, absorb the impact energy, and immediately return to much of their original shape, position, and capabilities. For side impacts, the system is designed to restrain and redirect the vehicle. It is anticipated that this system will not need many replacement parts or extensive repairs following an impact.
4. **Foundation:** The system is installed on a concrete foundation.
5. **Slope:** If the site has excessive grade or cross slope, additional site preparation or modification to the units in accordance with the manufacturer's literature is needed. "Excessive" is defined as steeper than 8% for the REACT 350 Wide.
6. **Transitions:** A transition section is not needed for fixed objects exposed to traffic from only one direction. If the attenuator is exposed to bi-directional traffic, modification to the shielded object or a custom transition section per manufacturer's recommendations may be needed if the width of the attenuator's backstop exceeds the width of the shielded object (included in the cost of the attenuator).
7. **Manufacturer/Supplier:** Energy Absorption Systems



REACT 350 Wide – Permanent and Work Zone Installations

1620.04(1)(k) Compressor

1. **Purpose:** The Compressor is an end treatment for concrete barrier and fixed objects up to 3 feet wide.
2. **Description:** The system consists of High Density Polyethylene (HDPE) modules with varying heights and wall thicknesses, a mounting base, and fender panels.
3. **Function:** When hit head-on, the modules compress, absorb the impact energy, and immediately return to much of their original shape, position, and capabilities. When impacted from the side, the fender panels redirect the vehicle.
4. **Foundation:** The system is installed on a concrete or asphalt foundation.
5. **Slope:** An 8% or flatter slope between the edge of the traveled way and the near face of the unit is required.
6. **Transitions:** A transition section is not needed for concrete barrier and fixed objects exposed to traffic from only one direction. A custom transition section per manufacturer's specifications is needed for connection to a concrete barrier or fixed object exposed to bi-directional traffic (included in the cost of the attenuator).
7. **Manufacturer/Supplier:** Traffix Devices



Compressor – Permanent and Work Zone Installations

1620.04(1)(l) Smart Cushion Innovations SCI100GM / SCI70GM

1. **Purpose:** The SCI100GM and SCI70GM are end treatments that can be used for concrete barrier and beam guardrail with widths up to 2 feet.
2. **Description:** The system for both models consists of a front sled assembly, telescoping steel side panels mounted to collapsing steel frames, a shock arresting cylinder, and a steel cable routed around sheave assemblies. It is mounted on a base with a series of tubular steel side frame assemblies.
3. **Function:** During a head-on impact, the system telescopes backwards and dissipates impact energy with a combination of friction between the steel cable and sheaves as well as variable resistance from the shock arresting cylinder. In a side impact, a vehicle is redirected by the steel side panels. It is anticipated that this system will not need many replacement parts or extensive repairs following an impact.
4. **Foundation:** The system is installed on a concrete foundation (see manufacturer's installation information for details).
5. **Slope:** Longitudinal and cross slopes at the installation site must be 10H:1V or flatter.
6. **Transitions:** A transition section is not needed for concrete barrier and fixed objects exposed to traffic from only one direction. A custom transition section per manufacturer's specifications is needed for connection to a concrete barrier or fixed object exposed to bi-directional traffic (included in the cost of the attenuator). If used as an end treatment for beam guardrail, the system must be connected to a transition section (not included in the cost of the attenuator). (See Chapter 1610 and the *Standard Plans* for the type of transition section required.) Connection of the transition section to the attenuator must be per the manufacturer's specifications using custom connection pieces (included in the cost of the attenuator).
7. **Other:** The SCI100GM and SCI70GM should not be installed behind a curb.
8. **Manufacturer/Supplier:** Work Area Protection Corp.



SCI100GM – Permanent and Work Zone Installations

1620.04(1)(m) Inertial Barrier

Inertial barrier configurations are shown in the *Standard Plans*. If a situation is encountered where the configurations in the Standard Plans are not appropriate, contact the HQ Design Office for further information.

1. **Purpose:** Inertial barrier is an end treatment for concrete barrier and is used to mitigate fixed objects. This system does not provide redirection from a side impact.
2. **Description:** This system consists of an array of plastic containers filled with varying weights of sand.
3. **Function:** The inertial barriers slow an impacting vehicle by the transfer of the momentum of the vehicle to the mass of the barrier. This system is not suitable where space is limited to less than the widths shown in the *Standard Plans*. Whenever possible, align inertial barriers so that an errant vehicle deviating from the roadway by 10° would be on a parallel path with the attenuator alignment (see the *Standard Plans*). In addition, inertial barriers do not provide any redirection and are not appropriate where high-angle impacts are likely.
4. **Foundation:** A concrete or paved surface is recommended.
5. **Slope:** If the site has excessive grade or cross slope, additional site preparation or modification to the units in accordance with the manufacturer's literature is needed. "Excessive" is defined as steeper than 5% for inertial barriers.
6. **Manufacturer/Supplier:** Approved Inertial Barrier systems (sand barrel arrays) are listed in the Qualified Products List.



Inertial Barrier – Permanent and Work Zone Installations

1620.04(2) Work Zone (Temporary) Installation

Several of the impact attenuators previously listed under the heading "Permanent Installations" are also appropriate for use in work zones or other temporary locations. The following is a list of these devices:


- QuadGuard
- QuadGuard II
- QuadGuard Elite
- QuadGuard M10
- HEART
- REACT 350
- REACT 350 Wide
- Compressor
- SCI100GM
- SCI70GM
- Inertial Barriers

The systems described in the following sections are appropriate only in work zones or other temporary installations. However, the TRACC impact attenuator may be considered for permanent use with the concurrence of the WSDOT Area Maintenance Superintendent who will be maintaining the system.

Descriptions of each work zone (or other temporary) system's purpose, parts, and functionality, as well as guidance for transition, foundation, and slope, are provided as follows and in Exhibits 1620-1a and 1620-1b.

1620.04(2)(a) ABSORB 350

1. **Purpose:** The ABSORB 350 is an end treatment limited to temporary installations for both concrete barrier and the Quickchange Moveable Barrier (QMB).
2. **Description:** The system contains water-filled Energy Absorbing Elements. Each element is 2 feet wide, 2 feet 8 inches high, and 3 feet 3½ inches long.
3. **Function:** The low-speed (rated for 45 mph or less) system uses five Energy Absorbing Elements, and the high-speed (rated for 60 mph and above) system uses nine elements. The energy of an impact is dissipated as the elements are crushed.
4. **Foundation:** The system does not need a paved foundation.
5. **Slope:** 12H:1V or flatter slope between the edge of the traveled way and the near face of the unit.
6. **Transitions:** A custom transition section per manufacturer's specifications is needed for all connections to concrete barrier or QMB (included in the cost of the attenuator).
7. **Other:** Although manufacturer's information may show configurations using different numbers of Energy Absorbing Elements, use only the five or nine Energy Absorbing Element configurations. Proper antifreeze agents must be used when the Absorb 350 is used in areas where low temperatures can be anticipated.
8. **Manufacturer/Supplier:** Barrier Systems, Inc.



ABSORB 350 – Work Zone Installations

1620.04(2)(b) Advanced Dynamic Impact Extension Module 350 (ADIEM 350)

1. **Purpose:** The ADIEM 350 is limited to temporary installations where vehicle speeds are 45 mph or lower. It is generally used as an end treatment for concrete barrier. Currently, there are a few existing permanent units in service. It is permissible to reset these existing devices. However, some of these units may exhibit significant deterioration and replacement may be the appropriate option.
2. **Description:** The system is 30 feet long and consists of ten lightweight concrete modules on an inclined base.
3. **Function:** An inclined base provides a track for placement of the modules and provides redirection for side impacts for roughly half the length. The energy of an impact is dissipated as the concrete modules are crushed.
4. **Foundation:** The system does not need a paved foundation.
5. **Slope:** If the site has excessive grade or cross slope, additional site preparation or modification to the units in accordance with the manufacturer's literature is needed. "Excessive" is defined as steeper than 8% for the ADIEM 350.
6. **Transitions:** Custom bracket attachments per manufacturer's specifications that act as transition sections to prevent snagging are needed for all connections to concrete barrier (included in the cost of the attenuator).
7. **Manufacturer/Supplier:** Trinity Industries, Inc.



ADIEM 350 – Work Zone Installations

1620.04(2)(c) QuadGuard CZ

This system is similar to the QuadGuard listed for permanent systems above, except that it is mounted on an integral steel plate for ease of transport and resetting and can be installed on a 6-inch-minimum-depth asphalt concrete surface that has a 6-inch-minimum-depth compacted base.



QuadGuard CZ – Work Zone Installations

1620.04(2)(d) Reusable Energy Absorbing Crash Terminal (REACT 350)

This is the same system listed for permanent systems above except that it can be installed on a 6-inch-minimum-depth asphalt concrete surface that has a 6-inch-minimum-depth compacted base.

1620.04(2)(e) Non-Redirecting Energy Absorbing Terminal (N-E-A-T)

1. **Purpose:** The N-E-A-T system is an end treatment for temporary concrete barrier where vehicle speeds are 45 mph or lower.
2. **Description:** The N-E-A-T system's cartridge weighs about 300 pounds and is 9 feet 8 inches long. The system consists of aluminum cells encased in an aluminum shell with steel backup, attachment hardware, and transition panels. It can be attached to the ends of New Jersey and F-Shaped portable concrete barrier as well as the Quickchange Moveable Barrier.
3. **Function:** The energy of an impact is dissipated as the aluminum cells are crushed.
4. **Foundation:** The system does not need a paved foundation.
5. **Slope:** 10H:1V or flatter slope between the edge of the traveled way and the near face of the unit.
6. **Transitions:** Custom transition panels per manufacturer's specifications that act as transition sections to prevent snagging are needed for all connections to concrete barrier (included in the cost of the attenuator).
7. **Manufacturer/Supplier:** Energy Absorption Systems



N-E-A-T – Work Zone Installations

1620.04(2)(f) Trinity Attenuating Crash Cushion (TRACC)

1. **Purpose:** The TRACC is an end treatment for concrete barriers. It is limited to use in construction or other work zones on a temporary basis.
2. **Description:** The 21.3-foot-long (not including the plastic nosepiece and front end shoes) TRACC includes four major components: a pair of guidance tracks, an impact sled, intermediate steel frames, and 10 gauge W-beam fender panels. The low-speed version (45 mph or less) is called the ShorTRACC and is 14.3 feet long (not including the plastic nosepiece and front end shoes).
3. **Function:** The sled (impact face) is positioned over the upstream end of the guidance tracks and contains a hardened steel blade that cuts the metal plates on the sides of the guidance tracks as it is forced backward when hit head-on, dissipating the impact energy. In a side impact, the fender panels redirect the vehicle.
4. **Foundation:** The system needs a concrete foundation.
5. **Slope:** 10H:1V or flatter slope between the edge of the traveled way and the near face of the unit.
6. **Transitions:** A transition section is not needed for concrete barrier exposed to traffic from only one direction. A custom transition section per manufacturer's specifications is needed for connection to a concrete barrier exposed to bi-directional traffic (included in the cost of the attenuator).
7. **Manufacturer/Supplier:** Trinity Industries, Inc.



TRACC – Work Zone Installations

1620.04(2)(g) Triton CET


1. **Purpose:** The Triton CET is an end treatment limited to temporary concrete barrier installations.
2. **Description:** The system contains water-filled energy absorbing elements.
3. **Function:** The system uses six energy absorbing elements. The energy of an impact is dissipated as the elements are crushed.
4. **Foundation:** The system does not need a paved foundation.
5. **Slope:** Longitudinal and cross slopes at the installation site must be 20H:1V or flatter.
6. **Transitions:** A custom transition connection per manufacturer's specifications that acts as transition section to prevent snagging is needed for all connections to concrete barrier (included in the cost of the attenuator).
7. **Other**: Proper antifreeze agents must be used when the Triton CET is used in areas where low temperatures can be anticipated.
8. **Manufacturer/Supplier:** Energy Absorption, Inc.



Triton CET– Work Zone Installations

1620.04(2)(h) QUEST

1. **Purpose:** The QUEST is an end treatment for concrete barrier, guardrail, or fixed features and is limited to temporary applications. This system is designed to shield features 3 feet or less in width.
2. **Description:** The system consists of two front anchor assemblies; a nose assembly containing an integrated trigger assembly; two shaper rail assemblies; a support rail assembly with two energy-absorbing tube shapers; a diaphragm assembly; a bridge assembly; two rear rails; a freestanding backup assembly; and W-beam fender panels.
3. **Function:** During head-on impacts, the QUEST system telescopes rearward and energy is absorbed through momentum transfer, friction, and deformation. When impacted from the side, the QUEST system restrains lateral movement by dynamic tension developed between the end restraints.
4. **Foundation:** The system is installed on a concrete or asphalt foundation. (See manufacturer's installation information for details.)
5. **Slope:** 12H:1V (8%) or flatter slope between the edge of the traveled way and the near face of the unit is needed.
6. **Transitions:** A transition section is not needed for concrete barrier, guardrail, and fixed objects exposed to traffic from only one direction. A custom transition section per manufacturer's specifications is needed for connection to a concrete barrier or fixed object exposed to bi-directional traffic (included in the cost of the attenuator). If used as an end treatment for beam guardrail exposed to bi-directional traffic, the system must be connected to a transition section (not included in the cost of the attenuator). (See Chapter 1610 and the *Standard Plans* for the type of transition section required.) Connection of the transition section to the attenuator must be per the manufacturer's specifications and may require custom side panels (included in the cost of the attenuator).
7. **Manufacturer/Supplier:** Energy Absorption Systems, Inc.



QUEST – Work Zone Installations

1620.04(2)(i) ACZ 350

1. **Purpose:** The ACZ 350 is an end treatment limited to temporary concrete barrier installations.
2. **Description:** The system consists of water-filled plastic sections and an integrated steel nose section. The low-speed (rated for 45 mph and below) system uses two water-filled sections, and the high-speed (rated for 60 mph and above) system uses four.
3. **Function:** The energy of an impact is dissipated as the water-filled sections are crushed.
4. **Foundation:** The system does not need a paved foundation.
5. **Slope:** If the site has excessive cross slope, additional site preparation in accordance with the manufacturer's literature is needed. Excessive is defined as steeper than 5% for the ACZ 350.
6. **Transitions:** A custom transition connection per manufacturer's specifications that acts as a transition section to prevent snagging is needed for all connections to concrete barrier (included in the cost of the attenuator).
7. **Other**: Proper antifreeze agents must be used when the ACZ 350 is used in areas where low temperatures can be anticipated.
8. **Manufacturer/Supplier:** Energy Absorption Systems, Inc.



ACZ 350 – Work Zone Installations

1620.04(2)(j) Sentry Longitudinal Energy Dissipater (SLED)

1. **Purpose:** The SLED is an end treatment limited to temporary concrete barrier installations.
2. **Description:** The system contains energy absorbing modules, some filled with water. The low-speed (rated for 45 mph and below) system uses three energy absorbing modules, and the high-speed (rated for 60 mph and above) system uses four.
3. **Function:** The energy of an impact is dissipated as the modules are crushed.
4. **Foundation:** The system does not need a paved foundation.
5. **Slope:** 10H:1V or flatter slope between the edge of the traveled way and the near face of the unit.
6. **Transitions:** A custom transition section per manufacturer's specifications is needed for all connections to concrete barrier (included in the cost of the attenuator).
7. **Other**: Proper antifreeze agents must be used when the SLED is used in areas where low temperatures can be anticipated.
8. **Manufacturer/Supplier:** TrafFix Devices Inc.



SLED – Work Zone Installations

1620.04(2)(k) Transportable Attenuators (Truck-Mounted and Trailer-Mounted)


Truck Mounted Attenuators and Trailer-Mounted Attenuators are portable systems mounted on trucks or trailers. They are intended for use in work zones and for temporary applications.

1620.04(3) Older Systems

The following systems are in use on Washington State highways and may be left in place or reset with concurrence of the WSDOT Area Maintenance Superintendent who maintains the system. New installations of these systems need approval from the HQ Design Office.

1620.04(3)(a) Sentre


The Sentre is a guardrail end treatment. Its overall length of 17 feet allowed it to be used where space was not available for a guardrail transition and terminal. The system is very similar to the QuadTrend 350 in both appearance and function except that it uses thrie beam fender panels instead of the quadruple corrugated panels. This system needs a transition when used to terminate rigid barriers.



Sentre

1620.04(3)(b) TREND


The TREND is an end treatment with a built-in transition and was used at the end of rigid barriers including bridge rails. The system is similar to the QuadTrend 350 except that it uses thrie beam fender panels.



TREND

1620.04(3)(c) Guard Rail Energy Absorption Terminal (G-R-E-A-T)


This system was primarily used as an end treatment for concrete barrier. It is similar to the QuadGuard except that it uses thrie beam fender panels.



GREAT

1620.04(3)(d) Low-Maintenance Attenuator System (LMA)


The LMA is an end treatment for concrete barrier and beam guardrail and was used for fixed objects up to 3 feet wide. The system is similar to the QuadGuard Elite except that it uses thrie beam fender panels and rubber cylinders.



LMA

1620.04(3)(e) Hex-Foam Sandwich

The Hex-Foam Sandwich system is an end treatment for beam guardrail and concrete barrier and was also used for fixed objects 3 feet or more in width. This system consists of a number of Hex-Foam cartridges containing an energy absorption material separated by a series of diaphragms and restrained by anchor cables. It is installed on a concrete slab. Impact energy is absorbed by the internal shearing of the cartridges and crushing of the energy absorption material. The lapped panels on the perimeter serve to redirect vehicles for side impacts. If the site has grade or cross slope in excess of 5%, additional site preparation or modification to the units in accordance with the manufacturer's literature is needed.



Hex-Foam Sandwich

Exhibit 1620-1a Impact Attenuator System Comparison

System [1]	Permanent (P), Temporary (T), or Both (B)	Posted Speed (mph) [4]	Approximate Outside Width	Maximum Shielded Object Width	Approximate System Length [10]	Distance Beyond Length of Need (See Exhibit 1620-2)	Initial Cost Category [11]
Brakemaster 350 [2]	P	≥ 60	2.1	2	31.5	15.8	A
CAT 350 [2]	P	≥ 60	2.5	2	31.3	18.8	A
QuadTrend 350 [6]	P	≥ 60	1.3	2	20	10.5	A
Universal Tau-II [7]	P	See Note 7	4.4 to 8.9	3.9 to 8.4	14.5 to 27.1	3	C,D [7]
QuadGuard [7]	B	See Note 7	2.5 to 10.5	2.0 to 10	13.1 to 22.1	3.3	B,C [7]
QuadGuard II [7]	B	See Note7	2.5 to 8.0	2.0 to 7.5	10.0 to 19.1	3.3	B,C [7]
QuadGuard Elite [7]	B	See Note 7	2.5 to 8.0	2.0 to 7.5	18 to 27.1	3.3	C [7]
QuadGuard M10 [7]	B	See Note 7	2.5 to 8.0	2.0 to 7.5	13.1 to 22.1	3.3	C,D [7]
HEART	B	≥ 60	3	2	26	5	D
REACT 350 (9-Bay)	B	≥ 60	4	3	30.5	4.3	D
REACT 350 (6-Bay)	B	≤ 55	4	3	20	4.3	D
REACT 350 (4-Bay)	B	≤ 45	4	3	15.5	4.3	D
REACT 350 Wide TL-3 (60"/96"/120" widths)	B	≥ 60	5.2/8.2/10.2	5.0/8.0/10.0	32.8/36.8/36.8	4.3	D
REACT 350 Wide TL-2 (60"/96" widths)	B	≤ 45	5.2/8.2/10.2	5.0/8.0/10.0	21	4.3	D
Compressor	B	≥ 60	4.1	3.0	21.3	3	D
SCI100GM	B	≥ 60	3.1	2.0/2.5/3.0	21.5/24.4/25.9	3	C
SCI70GM	B	≤ 45	2.8	2.0/2.5/3.1	13.5/15.4/16.9	3	C
INERTIAL BARRIERS	B	See Note 5	See Note 5	See Note 5	See Note 5	See Note3	A
ABSORB 350 TL-3 [8]	T	≥ 60	2	2	32	See Note 3	B
ABSORB 350 TL-2	T	≤ 45	2	2	19.3	See Note 3	B
ADIEM 350	T	≤ 45	2.7	2	30	14.1	B
QuadGuard CZ [7]	T	See Note 7	2.5 to 8.0	2.0 to 7.5	13 to 22.1	3.3	C,D [7]
N-E-A-T	T	≤ 45	1.9	2	10	See Note 3	B
TRACC	T [9]	≥ 60	2.6	2	21.3	8	B
ShorTRACC	T [9]	≤ 45	2.6	2	14.3	8	B
Triton CET TL-3 [8]	T	≥ 60	1.8	2	40	See Note 3	A
Triton CET TL-2	T	≤ 45	1.8	2	40	See Note 3	A
QUEST TL-3 (24"/30"/36" widths)	T	≥ 60	3.0/3.5/4.0	2.0/2.5/3.0	28	3.5	B
QUEST TL-2 (24"/30"/36" widths)	T	≤ 45	3.0/3.5/4.0	2.0/2.5/3.0	22	3.5	B
ACZ-350 TL-3 [8]	T	≥ 60	1.7	2	31.6	See Note 3	A
ACZ-350 TL-2	T	≤ 45	1.7	2	18.4	See Note 3	A
SLED TL-3 [8]	T	≥ 60	2	2	26	See Note 3	B
SLED TL-2	T	≤ 45	2	2	19	See Note 3	B

For table notes, see the following page.

Exhibit 1620-1a Impact Attenuator System Comparison (continued)

Notes:

[1] See system descriptions in 1620.04 for additional information regarding slopes, transitions, and other factors that may influence the appropriateness of an attenuator selection for a specific site.

[2] Generally for use with double-sided beam guardrail

[3] The N-E-A-T, Inertial Barriers, Triton CET, ACZ 350, SLED and ABSORB 350 may only be used beyond the length of need.

[4] It is acceptable to use an attenuator rated for a higher posted speed on a roadway with a lower posted speed. For example: an attenuator rated for $\geq$ 60 mph may be used on a roadway with posted speed of 50 mph (see 1620.03).

[5] Varies; see the *Standard Plans*.

[6] See manufacturer's requirements for slope and clear area behind the device.

[7] Numerous speed, length, and width combinations are available (see Exhibit 1620-1b).

[8] Test Level 3 version on high-speed facilities should be limited to locations where the likelihood of being hit is low.

[9] May be considered for permanent installations with concurrence of the Area Maintenance Superintendent.

[10] The given dimension is the approximate system length. The effective length may vary depending on such factors as the physical design and type of anchorage used. To verify the total length needed, refer to the manufacturer's specifications and drawings.

[11] A ($5,000 to $10,000); B ($10,000 to $15,000); C ($15,000 to $25,000); D ($25,000 to $50,000). These are rough initial cost estimates; verify actual costs through manufacturers/suppliers. Some products are priced very close to the margin between cost categories.

Exhibit 1620-1b Impact Attenuator Systems: Universal TAU II and QuadGuard Configurations

System [1]	Permanent (P), Temporary (T), or Both	Posted Speed (mph) [2]	Approximate Outside Width	Maximum Shielded Object Width	Approximate System Length [3]	Initial Cost Category [4]
Universal Tau-II (8-Bay, 30" width)	P	≥ 60	2.9	2.5	25.4	D
Universal Tau-II (8-Bay, 42"/48"/54"/60" widths)	P	≥ 60	4.4/4.9/5.4/5.9	3.9/4.4/4.9/5.4	27.1	D
Universal Tau-II (7-Bay, 66"/72"/78"/84"/90"/96" widths)	P	≥ 60	6.4/6.9/7.4/7.9/8.4/8.9	5.9/6.4/6.9/7.4/7.9/8.4	24.2	D
Universal Tau-II (7-Bay, 30" width)	P	≤ 55	2.9	2.5	22.7	C
Universal Tau-II (7-Bay, 42"/48"/54"/60" widths)	P	≤ 55	4.4/4.9/5.4/5.9	3.9/4.4/4.9/5.4	24.2	D
Universal Tau-II (5-Bay, 72"/78"/84"/90"/96" widths)	P	≤ 55	6.9/7.4/7.9/8.4/8.9	6.4/6.9/7.4/7.9/8.4	18.6	D
Universal Tau-II (5-Bay, 30" width)	P	≤ 50	2.9	2.5	16.9	C
Universal Tau-II (5-Bay, 42"/48"/54"/60" widths)	P	≤ 50	4.4/4.9/5.4/5.9	3.9/4.4/4.9/5.4	18.6	D
Universal Tau-II (4-Bay, 66"/ 72"/78"/84"/90"/96" widths)	P	≤ 50	6.4/6.9/7.4/7.9/8.4/8.9	5.9/6.4/6.9/7.4/7.9/8.4	16	D
Universal Tau-II (4-Bay, 30" width)	P	≤ 45	2.9	2.5	14.5	C
Universal Tau-II (4-Bay, 42"/48"/54"/60" widths)	P	≤ 45	4.4/4.9/5.4/5.9	3.9/4.4/4.9/5.4	16	C
QuadGuard (6-Bay, 24"/30"/36"/90"/120" widths)	B	≥ 60	2.5/3.0 /3.5/8.0/10.5	2.0/2.5/3.0 /7.5/10	22.1	C
QuadGuard (5-Bay, 24"/30"/36"/90" widths)	B	≤ 55	2.5/3.0 /3.5/8.0	2.0/2.5/3.0 /7.5	19.1	C
QuadGuard (4-Bay, 24"/30"/36"/69"/90" widths)	B	≤ 50	2.5/3.0 /3.5/6.3/8.0	2.0/2.5/3.0 /5.7/7.5	16.1	C
QuadGuard (3-Bay, 24"/30"/36"/69"/90" widths)	B	≤ 45	2.5/3.0 /3.5/6.3/8.0	2.0/2.5/3.0 /5.7/7.5	13.1	B
QuadGuard II (5-Bay, 24"/30"/36"/90" widths)	B	≥ 60	2.5/3.0 /3.5/8.0	2.0/2.5/3.0 /7.5	19.1	C
QuadGuard II (4-Bay, 24"/30"/36"/69"/90" widths)	B	≤ 55	2.5/3.0 /3.5/.6.3/8.0	2.0/2.5/3.0 /5.8/7.5	16.1	C
QuadGuard II (3-Bay, 24"/30"/36"/69"/90" widths)	B	≤ 50	2.5/3.0 /3.5/.6.3/8.0	2.0/2.5/3.0 /5.8/7.5	13.1	B
QuadGuard II (2-Bay, 24"/30"/36" widths)	B	≤ 45	2.5/3.0 /3.5	2.0/2.5/3.0	10	B
QuadGuard Elite (8-Bay, 24"/30"/36"/69"/90" widths)	B	≥ 60	2.5/3.0 /3.5/.6.3/8.0	2.0/2.5/3.0 /5.8/7.5	27.1	C
QuadGuard Elite (5-Bay, 24"/30"/36"/69"/90" widths)	B	≤ 45	2.5/3.0 /3.5/.6.3/8.0	2.0/2.5/3.0 /5.8/7.5	18	C
QuadGuard M10 (6-Bay, 24"/30"/36"/69"/90" widths)	B	≥ 60	2.5/3.0 /3.5/.6.3/8.0	2.0/2.5/3.0 /5.8/7.5	22.1	D
QuadGuard M10 (3-Bay, 24"/30"/36"/69"/90" widths)	B	≤ 45	2.5/3.0 /3.5/.6.3/8.0	2.0/2.5/3.0 /5.8/7.5	13.1	C
QuadGuard CZ (6-Bay, 24"/30"/36" widths)	T	≥ 60	2.5/3.0 /3.5	2.0/2.5/3.0	22.1	D
QuadGuard CZ (5-Bay, 24"/30"/36" widths)	T	≤ 55	2.5/3.0 /3.5	2.0/2.5/3.0	19.1	D
QuadGuard CZ (4-Bay, 24"/30"/36" widths)	T	≤ 50	2.5/3.0 /3.5	2.0/2.5/3.0	16.1	C
QuadGuard CZ (3-Bay, 24"/30"/36" widths)	T	≤ 45	2.5/3.0 /3.5	2.0/2.5/3.0	13.1	C

Notes:


[1] See system descriptions in 1620.04 for additional information regarding slopes, transitions, and other factors that may influence the appropriateness of an attenuator selection for a specific site.

[2] It is acceptable to use an attenuator rated for a higher posted speed on a roadway with a lower posted speed. For example, an attenuator rated for ≥ 60 mph may be used on a roadway with posted speed of 50 mph (see 1620.03).

[3] The given dimension is the approximate system length. The effective length may vary depending on such factors as the physical design and type of anchorage used. To verify the total length needed, refer to the manufacturer's specifications and drawings.

[4] A ($5,000 to $10,000); B ($10,000 to $15,000); C ($15,000 to $25,000); D ($25,000 to $50,000). These are rough initial cost estimates; verify actual costs through manufacturers/suppliers. Some products are priced very close to the margin between cost categories.

Exhibit 1620-2 Impact Attenuator Distance Beyond Length of Need



Notes:

[1] Impact attenuator type and manufacturer varies with application (see Exhibit 1620-1a).

[2] Distance beyond the length of need (see Exhibit 1620-1a). This portion is nonredirective (gating).

[3] This portion is redirective (nongating) and can be included as part of the barrier needed to satisfy length of need.

[4] Concrete barrier shown for illustration purposes only. Type of object varies.

1620.05 Documentation

Refer to Chapter 300 for design documentation requirements.

1710.01 General
1710.02 References
1710.03 Definitions
1710.04 Safety Rest Area Project Team
1710.05 Location, Access, and Site Design
1710.06 Buildings
1710.07 Utilities
1710.08 Documentation

1710.01 General

The Washington State Department of Transportation (WSDOT) has developed a statewide system of traveler stopping opportunities along Interstate highways and state routes. This system includes safety rest areas (see Exhibit 1710-1), roadside parks, and viewpoints. These services provide universal access for rest, traveler information, and restroom facilities. Benefits include improved safety by reducing driver fatigue and the number of vehicles parked on the shoulders of state routes, refuge from adverse driving conditions, and increased tourism promotion.

Safety rest areas (SRAs) are spaced approximately every 60 miles on the National Highway System and on Scenic and Recreational Highways. Use the Safety Rest Area Program Strategic Plan as a guide when selecting a site location. The link to the SRA Strategic Plan can be found in the SRA Section of the Capital Facilities Office internal web page at: http://wwwi.wsdot.wa.gov/operations/facilities/

Safety rest areas are planned and designed by a multidisciplinary team lead through the Facilities Administrator in the Capital Facilities Office, a branch of Maintenance Operations. (See 1710.04 for an expanded discussion on team roles and membership.)



Photo: Keith Anderson, VERG

WSDOT Safety Rest Area

Exhibit 1710-1

1710.02 References

(1) Federal/State Laws and Codes

23 Code of Federal Regulations (CFR) 1.23, Rights-of-way

23 CFR 635, Construction and Maintenance

23 CFR 752, Landscape and roadside development

23 CFR 771, Environmental impact and related procedures

42 United States Code (USC) Chapter 126, Section 12101 et seq., Americans with Disabilities Act of 1990

20 USC Chapter 6A, Section 107, The Randolph-Sheppard Act

Revised Code of Washington (RCW) 46.17.375, Recreational vehicle sanitary disposal fee

RCW 46.68.170, RV account – Use for sanitary disposal systems

RCW 47.01.460, Adjustments to recreational vehicle fees

RCW 47.06.040, Statewide multimodal transportation plan

RCW 47.28.030, Contracts – State forces

RCW 47.38, Roadside areas – Safety rest areas

RCW 47.39, Scenic and Recreational Highway Act of 1967

RCW 47.42, Scenic Vistas Act

Washington Administrative Code (WAC) 246-290, Group A public water supplies

WAC 468-66, Highway Advertising Control Act

(2) Design Guidance

As the lead WSDOT organization for SRA project teams, the Capital Facilities Office coordinates design details and standards for SRA-related items.

ADA Accessibility Guidelines for Buildings and Facilities (ADAAG)
www.access-board.gov/adaag/html/adaag.htm

Manual on Uniform Traffic Control Devices for Streets and Highways, USDOT, FHWA; as adopted and modified by Chapter 468-95 WAC "Manual on uniform traffic control devices for streets and highways" (MUTCD)
www.wsdot.wa.gov/publications/manuals/mutcd.htm

Highway Runoff Manual, M 31-16, WSDOT

Hydraulics Manual, M 23-03, WSDOT

Plans Preparation Manual, M 22-31, WSDOT

Maintenance Manual, M 51-01, WSDOT

Right of Way Manual, M 26-01, WSDOT

Roadside Manual, M 25-30, WSDOT

Roadside Policy Manual, M3110, WSDOT

Standard Plans for Road, Bridge, and Municipal Construction (Standard Plans), M 22-01, WSDOT

Traffic Manual, M 51-02, WSDOT

(3) Supporting Information

Safety Rest Area Strategic Plan, WSDOT Capital Facilities Office
http://wwwi.wsdot.wa.gov/operations/facilities/

Guide for Development of Rest Areas on Major Arterials and Freeways, AASHTO Task Force on Geometric Design

Project Management Online Guide, WSDOT

(4) Agreements

Interpretive Signs and Markers Agreement – Washington State Parks Commission

- (GM 869) 1989 Highways and Local Programs Division

Traveler and Commercial Information Services – Private Vendor (StoreyCo, Inc.)

- (AA-1-12097) 2007 Capital Facilities Office

Vending Machines – Department of Services for the Blind (DSB)

- (GCA 10377) Capital Facilities Office

1710.03 Definitions

ancillary services Those secondary services, also considered amenities, provided at safety rest areas that include, but are not limited to, vending machines, picnic areas, interpretive signing, telephones, recreational vehicle (RV) sanitary disposal facilities, trails, scenic viewpoints, commercial and public information displays, and visitor information centers.

Recreational Vehicle Account In 1980 the RV account was established for use by the department of transportation for the construction, maintenance, and operation of recreational vehicle sanitary disposal systems at safety rest areas (RCW 46.68.170). A recreational vehicle sanitary disposal fee is required for registration of a recreational vehicle (RCW 46.17.375). Adjustments to the recreational vehicle fee by the department of transportation may be implemented after consultation with the citizens' representatives of the recreational vehicle user community (RCW 47.01.460).

roadside park A roadside user facility for safe vehicular parking off the traveled way and separated from the highway by some form of buffer. These sites might be equipped with features or elements such as points of interest, picnic tables, and/or vault toilet buildings. Unlike a safety rest area, a roadside park does not always provide a permanent restroom building.

safety rest area (SRA) A roadside facility equipped with permanent restroom building(s), a parking area, picnic tables, refuse receptacles, illumination, and other ancillary services. SRAs typically include potable water and might include traveler information and telephones.

Safety Rest Area Strategic Plan Developed in 2008 under a stakeholder-coordinated effort of executive and advisory team members, this plan provides guidance for current and future management of the SRA program.

traveler information Commercial and noncommercial information that informs and orients the traveling public. This includes access information for food, gas, lodging, local attractions, regional tourist attractions, roadway conditions, and construction schedules.

universal access Access for all persons regardless of ability or stature.

viewpoint A roadside stopping opportunity with a view of some point of interest or area scenery. This area is not typically separated from the traveled way by some form of highway buffer.

Visitor Information Center (VIC) A staffed or nonstaffed booth or separate building that displays and dispenses free tourist travel maps and brochures. These are typically located at border-entry SRAs to provide travel information to highway users as they enter the state.

1710.04 Safety Rest Area Project Team

The Capital Facilities Office has primary responsibility for program oversight and communication and is the primary point of contact for questions concerning SRAs. Duties include planning and programming for capital Preservation and Improvement projects, maintenance operations oversight and policy development, and project delivery.

Exhibits 1710-2 and 1710-3 outline the many disciplines involved with SRA planning, design, construction, and maintenance. The exhibits outline roles during the different phases of SRA management. Services are provided by internal WSDOT staff, other government agencies, and private consultants.

1710.05 Location, Access, and Site Design

(1) Conformance With the Safety Rest Area Strategic Plan

Regional planners, in coordination with the Capital Facilities Office, will use the Safety Rest Area Strategic Plan as a guide to determine which areas in the state are potential areas of need for a new facility. Verify current locations of SRAs, roadside parks, viewpoints, and undeveloped SRA properties that could be utilized for development of a new SRA. Coordinate all SRA planning and design efforts with the SRA Program located in the Capital Facilities Office.

(2) Highway Spacing Guidelines

It is preferred to space SRAs and roadside parks approximately every 60 miles on the National Highway System and Scenic Byways. Consider the location of other available public facilities when deciding where to locate an SRA. Other public or private facilities may offer stopping opportunities that could mitigate the need for construction of a new SRA. Reference the SRA Strategic Plan for potential areas of need for new stopping opportunities.

WSDOT Office	Planning	Programming & Budget	Design	Construction	Operations & Maintenance[1]	Agreements & Partnerships
Capital Facilities	Lead	Lead	Lead	Lead	Oversight	Lead
Maintenance Operations	Support	N/A	Support	Support	Lead	Lead/Support
Capital Program Development	Approver	Approver	Approver	Approver	N/A	N/A
Budget and Financial Analysis	N/A	Approver	N/A	N/A	N/A	N/A
Highways and Local Programs	Support	N/A	Support	N/A	N/A	Support
Design	Support	N/A	Support	Support	N/A	N/A
Construction	NA	N/A	Support	Support	N/A	N/A
Landscape Architect	Support	N/A	Support	Support	Support	N/A
Utilities	NA	N/A	Support	Support	Support	Support
Environmental	Support	N/A	Support	Support	Support	N/A
Hydraulics	Support	N/A	Support	Support	N/A	N/A
Traffic	Support	N/A	Support	Support	Support	N/A
Public-Private Partnerships	Support	N/A	Support	N/A	N/A	Lead/Support
Freight Systems Division	Support	N/A	Support	N/A	N/A	Support
Statewide Travel and Collision Data	Support	N/A	Support	N/A	N/A	N/A
Real Estate Services	Support	N/A	Support	N/A	Support	Support
Emergency Management	Support	N/A	Support	N/A	Support	N/A

Note:

[1] The SRA section in the WSDOT *Maintenance Manual* provides additional information pertaining to daily operations at the rest areas. Operations policy is outlined for all the ancillary services provided at each rest area site, such as the free coffee program, vending machines, literature distribution and posting, site security, seasonal or temporary closures, and other site activities.

WSDOT's SRA Project and Programming Roles

Exhibit 1710-2

Organization	Planning	Programming & Budget	Design	Construction	Operations & Maintenance	Agreements & Partnerships
Federal Highways Administration	Approver	N/A	Approver	Approver	Support	Approver
Attorney General	N/A	N/A	N/A	N/A	N/A	Support
Washington State Patrol	Support	N/A	Support	Support	Support	Support
Department of Commerce	Support	N/A	N/A	N/A	N/A	Support
Washington State Historical Society	Support	N/A	Support	N/A	N/A	Support
RV Citizens Advisory Committee[1]	Support	Support	Support	N/A	Support	Support
Association of Visitor Information Centers of WA	Support	N/A	N/A	N/A	N/A	Support
Washington State Hotel and Lodging Association	Support	N/A	N/A	N/A	N/A	Support

Note:

[1] **Recreational Vehicle Citizens Advisory Committee:** The department utilizes a volunteer citizen-based group of recreational vehicle users to help define the RV needs at SRAs. This group provides guidance on the expenditure of funds from the RV account and fee adjustments. The fee adjustments must be preceded by an evaluation per RCW 47.01.460.

Additional Safety Rest Area Resources

Exhibit 1710-3

(3) Adjacent Land Use

Consult local planning offices for information about zoning and expected development in the area of a proposed site to ensure compatibility with a new safety rest area or roadside park. Acquire a buffer area or scenic easement on adjacent lands, if possible, to protect scenic views and existing vegetation. Incorporate any cultural, historical, or scenic points of interest into the site design to enhance visitor experience and area education. For Interstate safety rest areas, vehicular ingress and egress will be from the main line only.

(4) Availability of Utilities

Determine the proximity and availability of water, power, and sewer systems prior to site acquisition. Prepare required legal documents such as well agreements, easements, water rights, and acquisition documents. The Capital Facilities Office uses annual traffic data in the area to estimate the number of rest area users and determine the adequacy of potable water supply, power capacity, parking space needs, and sewage disposal system options. New construction should meet the 20-year projected growth rate based on potential traffic increases.

(5) Level of Development

Roadside facilities have different levels of development and require varying site size and amenity levels. Exhibit 1710-4 shows recommended site sizing and amenities for SRAs, roadside parks, and viewpoints.

(6) Site Conditions

SRAs need large parcels of land to provide adequate space for parking passenger vehicles and trucks, on-site sewage treatment, and on-site water systems if provided. Any selected site should consider the terrain to allow for safe ingress and egress from the highway. Other considerations are:

- Grades and slopes to accommodate parking, sewage treatment, and the building site.
- High water level, particularly if the site is in a floodplain.
- Soil conditions and soil type for structural designs and the on-site sewage treatment system.
- Vegetation and natural features to understand potential mitigation costs from impacts to existing wetlands or stormwater drainage, etc.
- Prevailing wind direction and typical wind velocities that can affect building siting/design and visitor experience.

(7) Site Security

Design the facility to maximize line of sight for rest area users. Design vegetation for visibility to avoid hiding places on-site. If electrical power is available on-site, provide lighting around all parking areas, buildings, and other site amenities that are made available to the public.

(8) Site Sustainability

During site development, adhere to the U.S. Green Building Council's Leadership in Energy and Environmental Design standards where practicable. Strive for energy efficiency, water conservation, and low operational costs in building designs. Ensure landscaping features will be durable and easy to maintain. Contact the Capital Facilities Office for minimum requirements and standard details.

(9) Stormwater Management

For stormwater management, particularly in areas covered by the National Pollutant Discharge Elimination System (NPDES) permit, make an effort to minimize the use of storm drainage devices such as catch basins, oil-water separators, and retention vaults. Design the site to accommodate sheet flow off paved surfaces to vegetative areas for on-site infiltration and management of stormwater where practicable. (See the *Highway Runoff Manual* for stormwater design information.)

(10) Traffic Ingress and Egress

Design connections to the main line highway in accordance with *Design Manual* chapters in Division 13. Consult with the HQ Access and Hearings Section for establishing new or modifying existing highway access points.

Site Development	Safety Rest Area	Roadside Park	Viewpoint
Site			
Minimum site size – Professional judgment should be used based on site-specific requirements	Up to 30 acres	Up to 3 acres	Up to 1 acre
ADAAG code compliance	Required	Required	Required
Utilities			
Potable water	Optional	Optional	No
Off-site sewage disposal	Optional	Optional	No
On-site sewage disposal	Optional	Optional	No
RV sanitary disposal systems	Optional	No	No
Electrical power	Optional	Optional	Optional
Electric vehicle charging stations*	Optional	No	No
Restroom Buildings			
Permanent building	Required	Optional	No
Toilets and hand cleaning	Required	Optional	No
Portable toilets: vault, chemical, or composting	Optional	Optional	Optional
ADAAG code compliance	Required	Required	Required
Parking and Pavement			
Impervious	Required	Optional	Optional
Truck parking	Optional	Optional	No
RV parking	Optional	Optional	Optional
Site Amenities			
Pedestrian plaza	Optional	Optional	No
Sidewalks	Optional	Optional	Optional
Picnic tables	Optional	Optional	Optional
Recreation trails	Optional	Optional	Optional
Pet walking area	Optional	Optional	No
Bicycle access and/or racks	Optional	Optional	Optional
Historical or area information display	Required	Optional	Optional
Ancillary Services			
Telephone service	Optional	Optional	No
Refuse receptacles	Required	Optional	Optional
Vending machines*	Optional	No	No
Volunteer refreshment area*	Optional	No	No
Visitor information booth*	Optional	No	No
Travel information kiosk*	Optional	Optional	No
Interpretive displays, markers, or memorial signs	Optional	Optional	Optional
Safety and Security			
Fencing	Optional	Optional	Optional
Site illumination*	Optional	Optional	No
Surveillance cameras*	Optional	No	No

*If provided, electrical power is required.

Roadside Facilities Level of Development

Exhibit 1710-4

(11) ADAAG Compliance

You must comply with the *Americans with Disabilities Act Accessibility Guidelines* (ADAAG) for all site components that are made available to the public. Provide at least one accessible route of travel, defined in ADAAG, from the parking area to each on-site amenity or ancillary service.

(12) Parking Area Design

Consider the parking area layout when generating a site master plan. Include stages of construction if applicable. Provide separate parking areas for trucks/RVs/buses and passenger cars. For new designs, locate large-vehicle parking on the far side of the site away from the highway for improved highway visibility and site security purposes. Provide shade for vehicles where practicable. Exhibit 1710-5 shows an example of a truck parking area layout. AASHTO's *Guide for Development of Rest Areas on Major Arterials and Freeways* provides parking area design considerations. Consider areas for snow storage needs. Refer to the *Hydraulics Manual* for drainage design. Preserve existing landscape features to the greatest extent possible. Design vehicular and pedestrian routes to be safe, simple, direct, and obvious. Meet local building codes and ADAAG requirements for public parking.

(13) Recreational Vehicle (RV) Sanitary Disposal Facilities

Construct RV sanitary disposal facilities (dump stations) only at sites served by municipal sewage disposal systems, or at sites served by sewage lagoons with adequate capacity. On-site septic systems with drainfields are not an option for RV dump stations because of sewage volume, technical/maintenance requirements, and costs. Contact the Capital Facilities Office for details on RV dump station design and operation.

(14) Walkways


Design walkways for direct pedestrian movement to all facilities and comply with ADAAG requirements. Provide sidewalk width a minimum of 48 inches, which exceeds ADAAG requirements.

(15) Vegetation


Vegetation enhances the physical environment by providing shade, shelter from wind, visual screening, wildlife habitat, and other benefits. Landscape Architects engaged in the project employ designs that emphasize low-maintenance practices and obstacle-free lawns, and minimize water usage for irrigation and impacts to existing native vegetation where practicable.

(16) Picnic Tables


Provide one picnic table for every ten passenger car parking stalls, with a minimum of four tables per SRA where practicable. Provide shelters for 50% of the picnic tables on-site. Provide windscreens for picnic tables exposed to frequent high winds. Each SRA is required to provide a minimum of one picnic table that complies with ADAAG requirements. Place picnic tables near walkways but also provide privacy from restroom users.



* If exit ramp is tangent or has curve radii greater than 1,000', this width may be reduced to 14'.



Section A-A



Section A-A
Alternate

Typical Truck Storage
Exhibit 1710-5

(17) Recreation Trails

Provide trails or nature walks where practicable. (See Chapter 1515 for more information about shared-use paths.)

(18) Pet Areas

Provide ADAAG-compliant, well-lit areas for visitors to walk their pets away from kiosks, plaza areas, and moving vehicles. Provide trash receptacles and pet waste bags near pet areas.

(19) Electric Vehicle Charging Stations

Electric vehicle (EV) charging stations are provided at select sites. One ADAAG-compliant parking stall with an accessible route is required when EV charging stations are installed. Because EV charging is not the primary purpose of SRAs, locate the EV parking stalls at the ends of the passenger vehicle parking area.

(20) Bicycle Facilities

Provide bicycle racks where this type of active transportation mode is accessible to an SRA. (See Chapter 1520 for more information about roadway bicycle facilities.)

1710.06 Buildings

(1) Codes

Comply with current versions of the International Building Code, International Plumbing Code, National Electric Code, *Americans with Disabilities Act Accessibility Guidelines*, and all applicable state and local code requirements.

(2) Americans with Disabilities Act Accessibility Guidelines (ADAAG)

You must comply with accessibility guidelines specified in ADAAG for all building components that are available to the public. Design restrooms, ancillary service buildings, picnic benches, and information kiosks to ADAAG standards.

(3) Restroom Capacity

Provide a male/female restroom stall ratio of 40:60, and one unisex restroom that can be opened to allow for daily cleaning operations where practicable. If the unisex restroom is the only ADAAG-compliant toilet stall on-site, it must remain open at all times. Contact the Capital Facilities Office for restroom standards and to verify the number of stalls that should be provided at each site.

(4) Building Security

Design rest area buildings to provide a safe, comfortable experience for the traveling public. Avoid building designs with potential hiding places, and ensure adequate building lighting is provided around the perimeter.

(5) Building Sustainability

Buildings and systems are to adhere to the U.S. Green Building Council's Leadership in Energy and Environmental Design standards where practicable. Design facilities for energy efficiency, water conservation, and low operational costs. Ensure materials are durable and easy to maintain. Contact the Capital Facilities Office for minimum requirements and standard details.

(6) Vandalism Mitigation

Consider vandal-resistant materials as a preferred option for building components such as fixtures, fasteners, and surface coatings.



WSDOT Safety Rest Area Building – Adaptive Reuse Historic Preservation
Exhibit 1710-6

(7) Plaza Areas

Provide paved/concrete plaza areas at all new SRAs, where practicable, to enhance safety, reduce wear and maintenance on heavy-travel areas, and provide unobstructed pedestrian movement. Consider pedestrian movement when designing exterior fixtures such as benches, kiosks, telephones, and vending machines in plaza areas. Avoid creating potential hiding places and ensure appropriate lines of sight for safety.

(8) Building Signage

Ensure building signage meets current standards for rest area signage. Contact the Capital Facilities Office for details.

(9) Kiosks

Install travel information kiosks at all Interstate rest areas and at non-Interstate rest areas as needed. A kiosk is usually equipped with backlit information displays.

(10) Volunteer Refreshment and Coffee Services

Construct volunteer services buildings at all Interstate rest areas and at non-Interstate rest areas as needed. They can usually be incorporated with the travel information kiosks. Wire, plumb, and heat these buildings to meet building codes as an occupied space. Locate these buildings to give volunteers an unobstructed view of restroom entrances and parking areas if feasible.

(11) Rehabilitation and Expansion

Minor renovation projects to address specific building and system deficiencies such as roofs, interior fixtures and partitions, wall and floor surfaces, HVAC, electrical, water, and sewer will extend the usefulness of the building and minimize maintenance and operations costs. When major renovations are needed, consider restroom capacity increases to meet current standards based on expected user volumes.

Other facility components that will eventually need rehabilitation are kiosks, irrigation systems, sidewalks, picnic tables, parking areas, and RV dump stations. All projects must meet current ADAAG building and site requirements. Consider efficiency improvements that can be made to reduce operational costs. Coordinate with the Capital Facilities Office for all renovation or expansion projects.

1710.07 Utilities

Contact the region Utilities Office for acquisition of Utility Service Agreements for any utility needs. Coordinate with the Capital Facilities Office for long-term planning considerations. Telephones are provided at most SRAs and must meet ADAAG requirements. Because of the availability of cellular phones, and due to vandalism and other reasons, public telephone service may be cancelled after coordination between the Capital Facilities Office and region Maintenance.

(1) Power Capacity

A new or upgraded electrical service provided on-site will meet the projected needs of the facility over the next 20 years where practicable. Provide three-phase service where available. Consider building capacity increases, site lighting improvements, electric vehicle charging stations, truck parking electrification, and other potential needs. Contact the Capital Facilities Office for site-specific details or master plans.

(2) Water & Sewer Systems

Refer to the *Hydraulics Manual* for information on water and sewage disposal systems, including reservoirs, long-distance pressure sewers, septic tanks, drainfields, and sewage lagoons. Install separate water meters to quantify irrigation, building, RV dump stations, and source water where practicable. Consider maintenance needs for water and sewer system designs. Coordinate with the Capital Facilities Office for all issues related to water and sewer systems at SRAs.

(3) Stormwater Systems

Stormwater management and treatment systems are to meet the guidelines and requirements of the National Pollutant Discharge Elimination System (NPDES). Ensure runoff from impervious surfaces at SRAs is managed on-site using typical best management practices. Contact the Hydraulics Office for specific design recommendations, and the Maintenance Operations Office for specific site requirements noted in the statewide NPDES permit.

(4) Future Utilities

Provide sleeves and conduits for future utilities in accordance with the site master plan for water, sewer, power, and telephone. Address site-specific agreements by coordinating with region Maintenance, utility companies, the Capital Facilities Office, and others during site design.

1710.08 Documentation

(1) Design Documentation Checklist

For the list of documents required to be preserved in the Design Documentation Package and the Project File, see the Design Documentation Checklist:
www.wsdot.wa.gov/design/projectdev/

Also, coordinate design documentation with the Capital Facilities Office for any SRA design projects.

(2) Environmental Documentation and Permitting

Coordinate with the appropriate environmental support personnel or region Environmental Office during the planning and design stages of the project to determine what environmental, cultural, or historical documentation will be required. Environmental staff will determine applicable exemptions and required environmental permits for project delivery.

(3) Permanent Safety Rest Area Closures

Safety rest areas may be closed permanently or relocated. Federal Highways Administration approval is required for any closure or transfer of such facilities to other federal, state, or local agencies. Detailed closure procedures are stated in 23 CFR 752. Coordinate with the Capital Facilities Office for proposal to close any WSDOT SRA.

Chapter 1720 Weigh Sites

1720.01 General
1720.02 Definitions
1720.03 Planning, Development, and Responsibilities
1720.04 Permanent Facilities
1720.05 Portable Facilities
1720.06 Shoulder Sites
1720.07 Federal Participation
1720.08 Procedures
1720.09 Documentation

1720.01 General

Truck weighing facilities are needed to protect state highways from overweight vehicles, to provide for vehicle safety inspection, and to provide a source of data for planning and research. The development, construction, and maintenance of these facilities is a cooperative effort between the Washington State Department of Transportation (WSDOT) and the Washington State Patrol (WSP).

1720.02 Definitions

Note: For definitions of ***roadway, traveled way***, ***lane***, ***median***, ***outer separation***, ***shoulder***, ***decision sight distance***, ***sight distance***, and ***stopping sight distance***, see the Glossary.

Commercial Vehicle Information Systems and Networks (CVISN) A network that links intelligent transportation systems (ITS) to share information on commercial vehicles. When in operation at a weigh site, it can enable commercial vehicles to clear the facility without stopping.

frontage road An auxiliary road that is a local road or street located beside a highway for service to abutting property and adjacent areas and for control of access.

static scale A scale that requires a vehicle to stop for weighing.

usable shoulder The width of the shoulder that can be used by a vehicle for stopping.

weigh in motion (WIM) A scale facility capable of weighing a vehicle without the vehicle stopping.

1720.03 Planning, Development, and Responsibilities

The WSP works with WSDOT Strategic Planning and Programming to develop a prioritized list of weigh facility needs for each biennium. The list includes:

- New permanent facilities.
- New portable facilities.
- New shoulder sites.
- WIM equipment.

- Vehicle inspection facilities.
- Scale approach slab reconstruction.

The WSP provides the Program Management Office of Strategic Planning and Programming a Project Definition, which includes:

- A statement of need, the purpose of the project, and the type of work.
- The general location of the project.

Program Management sends this information to the region for preparation of a Project Summary. The region works with the WSP to identify the specific location of the facility. The region then prepares a design decision estimate and submits it to Program Management.

The region negotiates and the Regional Administrator executes any formal agreements with the WSP required for the design, construction, or maintenance of vehicle weighing and inspection facilities.

The Memorandum of Understanding Related to Vehicle Weighing and Equipment: Inspection Facilities on State Highways, Exhibit 1720-8, contains details about the various responsibilities of WSDOT and the WSP.

1720.04 Permanent Facilities

Permanent truck weighing facilities have permanent scales and may have buildings. When these facilities are in operation, trucks are required stop. However, when Weigh In Motion (WIM) and Commercial Vehicle Information Systems and Networks (CVISN) capabilities have been installed, the driver may be notified to continue without stopping. The notification to continue may be through the use of signs or transponders.

(1) Site Locations

The exact location of a truck weighing facility is generally controlled by topography, highway alignment, and geometrics. It is also desirable to select a site where adequate right of way is already available. Select the most economical site to minimize site preparation, expense, and impact on the environment. Water, electricity availability, and sewage treatment and disposal are other considerations for site selection. Additionally, use the following criteria:

- Locate the facility such that its operation will not hinder the operation of the highway or other related features such as intersections and interchanges.
- To the extent feasible, eliminate options for truck traffic to bypass the weigh site.
- Base the site selection on the type and volume of trucks using the route.

An interchange justification report is required for weigh sites on multilane divided highways with access control (see Chapter 550).

(2) Design Features

On multilane highways, provide off- and on-connections as shown in Chapter 1360. Exhibit 1720-1 is the minimal design of a weigh site on multilane highways.

Design weigh facilities on two-lane highways to best fit the existing conditions, with particular consideration given to the matter of access to and from the site. Off- and on-connections, as shown in Chapter 1360, are preferred. However, with justification, on-connections may be designed as intersections (see Chapter 1310). Exhibit 1720-2 is a guide for the design of weigh sites on two-lane highways.

The following special design features apply to weigh sites:

- Level cement concrete approach slabs are required at both ends of the scales.
- Hot mix asphalt (HMA) approach slabs will be allowed only when adequate soil conditions exist, projected truck volume is light, and benefit/cost analysis justifies the HMA based on the small percentage of time the scales will be in operation.
- The approach slabs must be level and in the same plane as the scale.
- Provide adequate parking and storage to ensure trucks do not impede the main line through traffic. The WSDOT Regional Administrator and the WSP agree on the area to be provided.
- On multilane divided highways, install illuminated electronically controlled "open" and "closed" message signs that can be operated from the scalehouse or the control cabinet. Provide permanent signing for the facility, as requested by the WSP.
- The need for a vehicle safety inspection facility at any site is identified by the WSP. Exhibit 1720-3 is a guide for a site plan for a single-bay vehicle inspection facility. Additional bays and site adaptation will be on a site-by-site basis. The WSDOT Regional Administrator and the WSP agree on the area to be provided.
- The need for some form of approach protective treatment for the scale house or a protective fence between the scale and roadway is identified by the WSP and agreed upon by the WSDOT Regional Administrator and the WSP. The need for the device is to protect the scale house from errant vehicles. (See Chapter 1600 for additional clear zone considerations.)
- The need for WIM or CVISN capabilities is identified by the WSP. Design the in-place facilities to provide the ability to notify drivers whether to continue on or to stop for further investigation before they reach the exit for the static scale. The design is agreed upon by the WSDOT Regional Administrator and the WSP.
- When WIM and CVISN are not included in the project, provide conduit for their future installation.
- With justification, at locations where space is limited, the depressed outer separation between the weigh facility and the through lanes may be replaced with concrete traffic barrier. (See the Collector-Distributor: Outer Separations exhibit in Chapter 1360.)
- Provide a clear view of the entire weigh site for the facility's operator and the driver of an approaching vehicle.
- Hot mix asphalt is acceptable for use on the ramp and storage areas. Design the depth in accordance with the surfacing report.
- To optimize scale efficiency, make the storage area flat; however, to facilitate drainage, the slope may be up to 2%.
- Provide illumination when requested by the WSP. Illumination is required if the facility is to be operated during the hours of darkness and may be desirable at other locations to deter unauthorized use of the facility. (See Chapter 1040 for additional information on illumination.)

1720.05 Portable Facilities

Portable truck weighing facilities have no permanent scales or buildings. When these facilities are in operation, they operate in the same manner as permanent facilities.

(1) Site Locations

Design portable truck weighing facilities located on two-lane and multilane roadways to best fit the existing conditions. Minor portable scale sites, as shown in Exhibit 1720-4, are used with two-way traffic and on multilane highways with low traffic volumes. Major portable scale sites (see Exhibit 1720-5) are for use on expressways, freeways, and where traffic volumes are high.

Locate the weighing facility such that its operation will not hinder the operation of the highway or other related features such as intersections.

An interchange justification report is required for weigh sites on multilane divided highways with access control (see Chapter 550).

(2) Design Features

The following special design features apply to portable facilities:

- Off- and on-connections, as shown in Exhibits 1720-4 and 1720-5, are preferred; however, with justification on highways with no access control, on-connections may be designed as intersections (see Chapter 1310).
- With justification, at locations where space is limited, the depressed outer separation between the weigh facility and the through lanes may be replaced with concrete traffic barrier. (See the Collector-Distributor: Outer Separation exhibit in Chapter 1360.)
- Provide adequate parking and storage to ensure trucks do not impede the main line through traffic. The WSDOT Regional Administrator and the WSP agree on the area to be provided.
- Hot mix asphalt is acceptable for use on the ramp and storage areas. Design the depth in accordance with the surfacing report.
- To optimize portable scale efficiency, make the storage area flat; however, to facilitate drainage, the slope may be up to 2%.
- Provide permanent signing for the facility, as requested by the WSP.
- Provide illumination when requested by the WSP. Illumination is required if the facility is to be operated during the hours of darkness and may be desirable at other locations to deter unauthorized use of the facility. (See Chapter 1040 for additional information on illumination.)

1720.06 Shoulder Sites

Shoulder sites are used by the WSP to pull a truck over for inspection and weighing with portable scales.

(1) Site Locations

Design shoulder sites to best fit the existing conditions. Small shoulder sites (see Exhibit 1720-6) are for use on lower-volume roadways (ADT 5000 or less) with two-way traffic. Large shoulder sites (see Exhibit 1720-7) are to be used with higher-volume two-way roadways and multilane highways.

Locate the weighing facility so that its operation will not hinder the operation of the highway or other related features such as intersections.

(2) Design Features

Shoulder sites are designed in coordination with the WSP. Input from the local WSP Commercial Vehicle Enforcement personnel will ensure the proposed site will meet their needs without over-building the facility. Obtain written concurrence from the WSP for the length, width, and taper rates before the design is finalized.

When the ADT is 1,500 or less, and with the written approval of the WSP, the tapers at small shoulder sites may be eliminated. The shoulders on either side of the site may be used as acceleration and deceleration lanes, whether or not they were designed for this use. Therefore, provide adequate strength to support truck traffic.

Hot mix asphalt is acceptable for use on all shoulder sites. Design the depth in accordance with the surfacing report. Design the shoulder pavement at this depth for a length not less than the deceleration lane length before, and the acceleration lane length after, the site (see Chapter 1360).

When the shoulders are designed to be used for deceleration and acceleration lanes, the minimum width is 12 feet with full pavement depth for the deceleration/ acceleration lane lengths (see Chapter 1360).

Use a maximum 2% slope in order to optimize portable scale efficiency and facilitate drainage.

1720.07 Federal Participation

Federal funds appropriate to the system being improved may be used for the acquisition of right of way and the construction of truck weighing facilities and vehicle inspection facilities. This includes, but is not limited to, on- and off-ramps, deceleration/acceleration lanes, passing lanes, driveways, parking areas, scale approach slabs, vehicle inspection facilities, roadway illumination, and signing.

1720.08 Procedures


Prepare site plans for all truck weighing facilities that include:

- Class of highway and design speed for main line (see Chapter 1103).
- Curve data on main line and weigh site.
- Number of lanes and width of lanes and shoulders on main line and weigh site.
- Superelevation diagrams for the main line and weigh site.
- Stationing of ramp connections and channelization.
- Illumination.
- Signing.
- Water supply and sewage treatment.
- Roadside development.


Get WSP approval of the site plans before the final plan approval.


1720.09 Documentation


Refer to Chapter 300 for design documentation requirements.




Truck Weigh Site: Multilane Highways
Exhibit 1720-1









Truck Weigh Site: Two-Lane Highways
Exhibit 1720-2




Vehicle Inspection Installation
Exhibit 1720-3




(Not to Scale)




Minor Portable Scale Site
Exhibit 1720-4




(Not to Scale)



Major Portable Scale Site
Exhibit 1720-5



Small Shoulder Site
Exhibit 1720-6



Large Shoulder Site
Exhibit 1720-7

C9904776SC

Memorandum of Understanding

Related to Vehicle Weighing and
Equipment Inspection Facilities on State Highways

This Memorandum of Understanding by and between the Washington State Department of Transportation hereinafter called the "Department of Transportation," and the Washington State Patrol, hereinafter called the "State Patrol," establishes procedures for coordinating and delineating the responsibilities for the location, design, construction, maintenance, signing, and other matters related to vehicle weighing and equipment inspection facilities and the state highway improvements needed as a result of these facilities.

It is mutually recognized that:

The Department of Transportation is responsible for planning, designing, constructing, and perpetuating public highways of the State Highway system for the safety and benefit of the traveling public;

The State Patrol is responsible for enforcement of the laws of the state of Washington regarding vehicle weight enforcement programs and vehicle safety inspection programs;

Nothing in this agreement is to be construed as conflicting with existing laws, regulations, and prescribed responsibilities, and

In recognition of the responsibilities, interest, and limitations set forth above and of the mutual benefits of established procedures to facilitate agreement on specific matters, the Department of Transportation and the State Patrol mutually agree as follows:

I. Planning

A. The State Patrol will work with the Department of Transportation's Planning and Programming Service Center to develop a prioritized list of weigh station needs at each biennium. The list will include:

- New permanent facilities
- New portable facilities
- Weigh-in-Motion (WIM) equipment
- Vehicle inspection facilities
- Scale approach slab construction

B. The State Patrol will provide the Planning and Programming Service Center with a project definition for each project, which will include statement of need, purpose of project, type of work, and general location of the project.

C. The Planning and Programming Center will send the information to the Regional Administrator for preparation of a project summary. The Regional Administrator will work with the State Patrol to identify the specific location of the facility, prepare a design decision estimate, and submit it to the Planning and Programming Service Center for inclusion in the biennial program.

D. The Regional Administrator will negotiate and execute any formal agreements required for design, construction, or maintenance of vehicle weighing and inspection sites.

MOU Related to Vehicle Weighing and Equipment: Inspection Facilities on State Highways
Exhibit 1720-8

C990477GSC

II. Responsibilities

Vehicle weighing and equipment inspection facilities shall meet highway standards for acceleration and deceleration lanes, on and off ramps, illumination, and other related equipment. These facilities will be provided through the cooperative efforts of the State Patrol and Department of Transportation as needed on state highways.

A. The State Patrol will:

1. Initiate the action and submit recommendations for the addition of a new facility or expansion of an existing facility or the relocation of an existing facility, and negotiate agreements, e.g. siting of a new facility, etc. with the Department of Transportation through the appropriate region and the Olympia Service Center.

2. Perform the preliminary engineering and submit the design and PS&E documents for the scale, WIM, scalehouse, and inspection facility to the Department of Transportation for review and processing for approval with the Federal Highway Administration (FHWA), if applicable, at the State Patrol's expense.

3. Construct, operate, and maintain the weigh station scale, WIM, scalehouse, and equipment inspection facility with all related equipment thereto including lighting, water, heat, telephone, and toilet facilities at the State Patrol's expense.

4. For WIM facilities and for facilities deploying Commercial Vehicle Information Systems and Networks (CVISN), select sites in cooperation with DOT that minimize the need for pavement reconstruction, and, at the State Patrol's expense, install, operate, and maintain any weigh-in-motion signs and related equipment, purchase and install all WIM hardware and software, and provide electrical conduit and an equipment storage room within the scale facility.

5. In the event the State Patrol cannot fulfill the responsibilities specified above for preliminary engineering (design and PS&E documents), construction, or maintenance, they may request that the Department of Transportation perform the work on the basis of a written agreement that includes reimbursement to the Department of Transportation for the costs.

6. Construct the CVISN roadside apparatus at the same time as WIM equipment is installed, e.g.; cantilevered mounting poles, guard rail, conduit/raceway installation at DOT expense. All construction in the state or interstate right-of-way will be under the responsibility of a DOT region engineer.

B. The Department of Transportation will:

1. Initiate action for the relocation of an existing installation when necessary because of the relocation of a highway or expansion of an existing highway, and obtain concurrence of the State Patrol.

2. Negotiate agreements with the State Patrol regarding addition, expansion, and relocation of facilities.

MOU Related to Vehicle Weighing and Equipment: Inspection Facilities on State Highways

Exhibit 1720-8 (continued)

C990477GSC

3. On all newly located or existing highways, at Department of Transportation expense, acquire the necessary right of way, construct and maintain the required acceleration and deceleration lanes, on and off ramps, driveways, passing lanes, scale approach slabs, and parking areas, including the surfacing thereof, excavate the scale pit, and construct and maintain the inspection, parking, and roadway illumination and standard signing at approved locations.

4. For WIM facilities and for facilities deploying Commercial Vehicle Information Systems and Networks (CVISN), at Department of Transportation's expense, construct the special approaches, provide maintenance of CVISN hardware and software located within the facility, and provide traffic control for installation of the scale and, when closure of any lane is required, for maintenance of the scale.

5. For facilities deploying Commercial Vehicle Information Systems and Networks (CVISN), at WSDOT's expense install mainline hardware (Automated Vehicle Identification equipment) and software for conformance with CVISN standards and provide maintenance of CVISN hardware and software located within the facility.

6. Upon request of the State Patrol, in accordance with a written agreement and on a reimbursement basis, perform other preliminary engineering, construction, and maintenance, which is the sole responsibility of the State Patrol.

Additionally, the State Patrol and the Department of Transportation agree to follow the Federal Highway Administration's *Guidance for Local Agency Roadway Projects within Interstate Rights-of-Way*, as outlined in Attachment A.

III. Conclusions and Approvals

A. The Regional Administrators for the Department of Transportation and the Commercial Vehicle Division Commander for the State Patrol are encouraged to consult with each other and to agree on such matters that fall within their scope of responsibility.

B. This memorandum may be amended or supplemented by mutual agreement between the signers or their successors.

C. Either party may terminate this MOU upon thirty- (30) days' written notification. If this MOU is so terminated, the terminating party shall be liable only for performance in accordance with the terms of the MOU for performance rendered prior to the effective date of the termination.

D. In the event a dispute arises under this MOU, it shall be resolved as follows: The Secretary of WSDOT and the Chief of the WSP shall each appoint a member, not affiliated with either agency, to a conflict resolution board. Then these two members shall appoint a third member. The decision made by this board shall be final and binding on the parties to the MOU.

E. In the event funding from state, federal, or other sources is withdrawn, reduced, or limited in any way after the effective date of this MOU and prior to normal completion, the WSDOT or WSP may terminate the MOU under the TERMINATION clause, subject to renegotiation under those new funding limitations and conditions.

MOU Related to Vehicle Weighing and Equipment: Inspection Facilities on State Highways
Exhibit 1720-8 (continued)

C990477GSC

F. We have read the foregoing and agree to accept and abide by the procedures herein.

Annette M. Sandberg, Chief
Washington State Patrol

12/16/99
Date

Sid Morrison, Secretary
Washington State
Department of Transportation

3/9/00
Date

APPROVED AS TO FORM:

Assistant Attorney General

9/7/99
Date

Washington State Patrol
Budget and Fiscal Services

12/27/99
Date

MOU Related to Vehicle Weighing and Equipment:
Inspection Facilities on State Highways
Exhibit 1720-8 (continued)

LY9U477GSL

ATTACHMENT A
Guidance for Local Agency Roadway Projects within Interstate Rights-of-Way

Since all projects within the Interstate rights-of-way (ROW) have the potential to impact safety and operations on the Interstate route, they must incorporate Interstate design criteria and construction quality. It is the Federal Highway Administration's (FHWA) policy that the Washington State Department of Transportation (WSDOT) should administer all projects within the Interstate ROW. However, given the scope and extent of non-Interstate projects within the Interstate ROW, it is recognized that local agency administration of some projects may be desirable.

Whenever a local agency proposes a project within the Interstate ROW, they must develop an agreement with WSDOT that clearly outlines their duties and responsibilities to maintain the integrity of the Interstate facility, from both the safety and quality perspectives. The agreement must be executed prior to beginning design and must incorporate the following requirements:

Responsibilities: WSDOT and the local agency must each assign a responsible Project Engineer.

Design: WSDOT must review and approve all highway plans, profiles, deviations structural plans false-work plans, shoring plans, and traffic control plans for any work within the Interstate ROW.

Plans, specification and estimates: WSDOT must review and approve the plans and specifications for any work within Interstate ROW.

Advertising and aware: The local agency must confer with the WSDOT Project Engineer on any pre-aware issues affecting the quality and timing of the contract.

Construction: All construction, materials, and quality control requirements contained in the current editions of the WSDOT Standard Specifications and Construction Manual must be incorporated into the agreement.

Contract changes: All contract changes affecting work within the Interstate ROW must have the prior concurrence of the WSDOT Project Engineer.

Final inspection: The final inspection of the project must be performed by WSDOT Olympia Service Center and must evidence their approval.

Only local agencies with full certification acceptance authority may enter into such an agreement with the WSDOT.

The agreement must be submitted to FHWA for approval. FHWA reserves the right to assume full oversight of the project.

MOU Related to Vehicle Weighing and Equipment:
Inspection Facilities on State Highways
Exhibit 1720-8 (continued)

Glossary

Acronyms

ADA / Pedestrian Terms

Main Glossary of Terms

Acronyms

AADT	Annual average daily traffic
ACT	Alternatives Comparison Table
ADA	Americans with Disabilities Act of 1990
ADT	Annual daily traffic
ALJ	Administrative law judge
AOS	Apparent opening size
APS	Accessible pedestrian signal
AWDVTE	Average weekday vehicle trip ends
BAT	Business access transit
B/C	Benefit / cost
BLM	Bureau of Land Management
BOD	Basis of Design
BRT	Bus rapid transit
BST	Bituminous surface treatment
CAR	Collision Analysis Report
CE	Categorical Exemption (SEPA)
CE	Categorical Exclusion (NEPA)
CFA	Contributing Factors Analysis
CFR	Code of Federal Regulations
CIPP	Capital Improvement and Preservation Program
CLB	Current Law Budget
CMP	Corridor Management Plan
CPMS	Capital Program Management System
CRT	Controlled releasing terminal post
CSS	Context sensitive solutions
CTR	Commute Trip Reduction
CVISN	Commercial Vehicle Inf. System and Networks
DDHV	Directional design hour volume
DDP	Design Documentation Package
DHV	Design hourly volume
DNS	Determination of Nonsignificance (SEPA)
DS	Determination of Significance (SEPA)
EA	Environmental Assessment (NEPA)
E&EP	Environmental & Engineering Programs Division
EIS	Environmental Impact Statement
ERS	Environmental Review Summary
FAST	Freight Action Strategy
FGTS	Freight and Goods Transportation System
FHWA	Federal Highway Administration
FONSI	Finding of No Significant Impact (NEPA)
FTA	Federal Transit Administration
GIS	Geographic Information System
GLO	General Land Office
GMA	Growth Management Act
HCM	Highway Capacity Manual
HCP	Highway Construction Program
HMA	Hot mix asphalt
HOT	High-occupancy toll
HOV	High-occupancy vehicle
HQ	WSDOT's Headquarters in Olympia
HSM	Highway Safety Manual
HSP	Highway System Plan (also SHSP)
HSS	Highways of Statewide Significance
ICA	Intersection Control Analysis
ICD	Inscribed circle diameter
IHSDM	Interactive Highway Safety Design Model
IJR	Interchange Justification Report
ITS	Intelligent transportation systems
L/A	Limited access
LOS	Level of service
MEF	Maximum extent feasible
MOU	Memorandum of Understanding
MPO	Metropolitan Planning Organization
MTIP	Metropolitan Transportation Improvement Program
MUTCD	Manual on Uniform Traffic Control Devices
NEPA	National Environmental Policy Act
NHS	National Highway System
PAR	Pedestrian access route
PATS	Priority Array Tracking System
PC&R	Project Control and Reporting
PCPH	Passenger cars per hour
PDMSG	Project Delivery Method Selection Guidance
PE	Preliminary engineering
PEL	Planning and Environmental Linkage
PF	Project File
PoDI	Project of Division Interest (FHWA)
PPH	Persons per hour
PS	Project Summary
PS&E	Plans, Specifications, and Estimates
RCW	Revised Code of Washington
RFP	Request for Proposal
ROD	Record of Decision
RTIP	Regional Transportation Improvement Program
RTPO	Regional Transportation Planning Organization
RV	Recreational vehicle
R/W	Right of way
SEPA	[Washington] State Environmental Policy Act
SHS	Sustainable Highway Safety
SIMMS	SIgnal Maintenance Management System
SOV	Single-occupant vehicle
SRA	Safety rest area
STIP	Statewide Transportation Improvement Program
STP	Surface Transportation Program
TIP	Transportation Improvement Program
TMA	Transportation Management Area
TMP	Transportation management plan
TRIPS	Transportation Information and Planning Support
TWLTL	Two-way left-turn lane
UPO	[Central Puget Sound] Urban Planning Office
USC	United States Code
VE	Value engineering
VECP	Value Engineering Change Proposal
VIC	Visitor Information Center
VPH	Vehicles per hour
WAC	Washington Administrative Code
WIM	Weigh in motion
WSDOT	Washington State Department of Transportation
WSPMS	Washington State Pavement Management System
WTP	Washington Transportation Plan

ADA / Pedestrian Terms

Note: This grouping of terms is used primarily in Chapters 1510 and 1515.

ADA / Pedestrian Terms	
accessible	Usable by persons with disabilities (ADA compliant).
accessible pedestrian signal (APS)	A device that communicates information about the "WALK" phase in audible and vibrotactile (vibrating surface that communicates information through touch, located on the accessible pedestrian signal button) formats.
accessible route	See *pedestrian access route*.
ADA	An abbreviation for the Americans with Disabilities Act of 1990. The ADA is a civil rights law that identifies and prohibits discrimination based on disability. Title II of the ADA requires public entities to design new pedestrian facilities or alter existing pedestrian facilities to be accessible to and usable by people with disabilities.
alternate pedestrian access route	A temporary accessible route to be used when the existing pedestrian access route is blocked by construction, alteration, maintenance, or other temporary condition(s).
alteration	A change to a facility in the public right of way that affects or could affect access, circulation, or use. Alterations include, but are not limited to: renovation; rehabilitation; reconstruction; historic restoration; resurfacing of circulation paths or vehicular ways; or changes or rearrangement of structural parts or elements of a facility. Alterations *do not* include: Spot pavement repair; liquid-asphalt sealing, chip seal (bituminous surface treatment), or crack sealing; or lane restriping that does not alter the usability of the shoulder.
buffer	A space measured from the back of the curb to the edge of the sidewalk that could be treated with plantings or alternate pavement, or be used for needs such as drainage treatment or utility placement.
clear width	The unobstructed width within a pedestrian circulation path. The clear width within a pedestrian circulation path must meet the accessibility criteria for a pedestrian access route.
construction impact zone	The area in which an alteration to an existing facility takes place (also known as the project footprint). If a crosswalk (marked or unmarked) will be reconstructed, paved (overlay or inlay), or otherwise altered as part of a project, then the curb ramps that serve that crosswalk are within the construction impact zone.
counter slope	The slope of the gutter or roadway at the foot of a curb ramp or landing where it connects to the roadway, measured along the axis of the running slope extended.
cross slope	The slope measured perpendicular to the direction of travel.

ADA / Pedestrian Terms	
crosswalk	A marked or unmarked pedestrian crossing, typically at an intersection, that connects the pedestrian access routes on opposite sides of a roadway. A crosswalk must meet accessibility criteria. A crosswalk is also defined as: • "…the portion of the roadway between the intersection area and a prolongation or connection of the farthest sidewalk line or in the event there are no sidewalks then between the intersection area and a line ten feet therefrom, except as modified by a marked crosswalk" (RCW 46.04.160). • "(a) That part of a roadway at an intersection included within the connections of the lateral lines of the sidewalks on opposite sides of the highway measured from the curbs or in the absence of curbs, from the edges of the traversable roadway, and in the absence of a sidewalk on one side of the roadway, the part of the roadway included within the extension of the lateral lines of the sidewalk at right angles to the center line; (b) any portion of a roadway at an intersection or elsewhere distinctly indicated as a pedestrian crossing by lines on the surface, which might be supplemented by contrasting pavement texture, style, or color" (MUTCD, 2003*; Guide for the Planning, Design, and Operation of Pedestrian Facilities*, AASHTO, 2004).
curb extension	A curb and sidewalk bulge or extension out into the parking lane used to decrease the length of a pedestrian crossing and increase visibility for the pedestrian and driver.
curb ramp	A combined ramp and landing to accomplish a change in level at a curb. This element provides street and sidewalk access to pedestrians with mobility impairments. • **parallel curb ramp** A curb ramp design where the sidewalk slopes down to a landing at road level with the running slope of the ramp in line with the direction of sidewalk travel • **perpendicular curb ramp** A curb ramp design where the ramp path is perpendicular to the curb and meets the gutter grade break at a right angle.
detectable warning surface	A tactile surface feature of truncated dome material built into or applied to the walking surface to alert persons with visual impairments of vehicular ways. Federal yellow is the color used on WSDOT projects to achieve visual contrast. Colors other than federal yellow that meet the light-on-dark/dark-on-light requirement may be used on projects where cities have jurisdiction. (Detectable warning surfaces are detailed in the *Standard Plans*.)
flangeway gap	The gap for the train wheel at a railroad crossing. The space between the inner edge of a rail and the pedestrian crossing surface.
grade break	The intersection of two adjacent surface planes of different grade.
landing	A level paved area, within or at the top and bottom of a stair or ramp, designed to provide turning and maneuvering space for wheelchair users and as a resting place for pedestrians.
maximum extent feasible (MEF)	From the U.S. Department of Justice, 28 CFR Part 36.402, Alterations. The phrase "to the maximum extent feasible" applies to "the occasional case where the nature of an existing facility makes it virtually impossible to comply fully with applicable accessibility standards through a planned alteration." This phrase also refers to a stand-alone piece of design documentation that WSDOT uses to record its reasons for not being able to achieve full ADA compliance in alteration projects (called a Maximum Extent Feasible document).
midblock pedestrian crossing	A marked pedestrian crossing located between intersections.

ADA / Pedestrian Terms	
passenger loading zone	An area provided for pedestrians to board/disembark a vehicle.
pedestrian	Any person afoot or using a wheelchair (manual or motorized) or means of conveyance (other than a bicycle) propelled by human power, such as skates or a skateboard.
pedestrian access route (PAR) (synonymous with *accessible route*)	A continuous, unobstructed walkway within a pedestrian circulation path that provides accessibility. Pedestrian access routes consist of one or more of the following pedestrian facilities: walkways/sidewalks, curb ramps (excluding flares), landings, crosswalks, pedestrian overpasses/underpasses, access ramps, elevators, and platform lifts. Note: Not all transportation facilities need to accommodate pedestrians. However, those that do accommodate pedestrians need to have an accessible route.
pedestrian circulation path	A prepared exterior or interior way of passage provided for pedestrian travel. Includes independent walkways, shared-use paths, sidewalks, and other types of pedestrian facilities. All pedestrian circulation paths are required to contain a continuous pedestrian access route that connects to all adjacent pedestrian facilities, elements, and spaces that are required to be accessible.
pedestrian facilities	Walkways such as sidewalks, walking and hiking trails, shared-use paths, pedestrian grade separations, crosswalks, and other improvements provided for the benefit of pedestrian travel. Pedestrian facilities are intended to be accessible routes.
pedestrian overpass or underpass	A grade-separated pedestrian facility, typically a bridge or tunnel structure over or under a major highway or railroad that allows pedestrians to cross.
pedestrian refuge island	An island in the roadway that physically separates the directional flow of traffic, provides pedestrians with a place of refuge, and reduces the crossing distance. Note: Islands with cut-through paths are more accessible to persons with disabilities than are raised islands with curb ramps.
pedestrian signal	An adaptation of a conventional traffic signal installed at established pedestrian crossings. It is used to provide a protected phase for pedestrians by terminating the conflicting vehicular movements to allow for pedestrian crossings.
person with disability	An individual who has an impairment, including a mobility, sensory, or cognitive impairment, that results in a functional limitation in access to and use of a building or facility.
raised median	A raised island in the center of a road used to restrict vehicle left turns and side street access. Note: Islands with cut-through paths are more accessible to persons with disabilities than are raised islands with curb ramps.
ramp	A walking surface with a running slope steeper than 20H:1V (5%).
running slope	A slope measured in the direction of travel, normally expressed as a percent.
sidewalk	A walkway along a highway, road, or street intended for use by pedestrians.
site	A parcel of land bounded by a property line or a designated portion of a public right of way.
street furniture	Sidewalk equipment or furnishings, including garbage cans, benches, parking meters, and telephone booths.
traffic calming	Design techniques that have been shown to reduce traffic speeds and unsafe maneuvers. These techniques can be stand-alone or used in combination, and they include lane narrowing, curb extensions, surface variations, and visual clues in the vertical plane.

ADA / Pedestrian Terms	
transitional segments	Segments of a pedestrian circulation path that blend between existing undisturbed pedestrian facilities and newly altered pedestrian facilities. Use of transitional segments may permit the work of the alteration to more nearly meet the new construction standards. At a later time, when other segments of the pedestrian circulation path are altered, the noncomplying transitional segments can be removed and replaced with pedestrian facilities that meet the accessibility criteria.
universal access	Access for all persons regardless of ability or stature.
walk interval	That phase of a traffic signal cycle during which the pedestrian is to begin crossing, typically indicated by a WALK message or the walking person symbol and its audible equivalent.
walkway	The continuous portion of the pedestrian access route that is connected to street crossings by curb ramps.

Main Glossary of Terms

A

access A means of entering or leaving a public road, street, or highway with respect to abutting property or another public road, street, or highway.

access break Any point from inside or outside the state limited access right of way limited access hachures that crosses over, under, or physically through the plane of the limited access, is an access break or "break in access," including, but not limited to, locked gates and temporary construction access breaks.

access connection An access point, other than a public road/street, that permits access to or from a managed access highway on the state highway system.

access connection permit A written authorization issued by the permitting authority for a specifically designed access connection to a managed access highway at a specific location; for a specific type and intensity of property use; and for a specific volume of traffic for the access connection based on the final stage of the development of the applicant's property. The actual form used for this authorization is determined by the permitting authority.

access control The limiting and regulating of public and private access to Washington State's highways, as required by state law. A *design control* (see Chapter 1103) – there are two categories of controlling access to state highways *limited access* and *managed access.*

Access Control Tracking System Limited Access and Managed Access Master Plan A database list, related to highway route numbers and mileposts, that identifies either the level of limited access or the class of managed access: www.wsdot.wa.gov/design/accessandhearings

access density the number of access points (driveways) per mile.

access design analysis A design analysis (see Chapter 300) that authorizes deferring or staging acquisition of limited access control, falling short of a 300-foot requirement, or allowing an existing access point to stay within 130 feet of an intersection on a limited access highway. Approval by the Director & State Design Engineer, Development Division, or designee, is required (see Chapter 530).

access hearing plan A limited access plan prepared for presentation at an access hearing.

access management The programmatic control of the location, spacing, design, and operation of driveways, median openings, interchanges, and street connections to a roadway.

access point Any point that allows private or public entrance to or exit from the traveled way of a state highway, including "locked gate" access and maintenance access points.

access point revision A new access point or a revision of an existing interchange/ intersection configuration. Locked gates and temporary construction breaks are also access point revisions.

access point spacing On a managed access highway, the distance between two adjacent access points on one side of the highway, measured along the edge of the traveled way from one access point to the next (see also corner clearance).

access report plan A limited access plan prepared for presentation to local governmental officials at preliminary meetings before preparation of the access hearing plan.

access rights Property rights that allow an abutting property owner to enter and leave the public roadway system.

adaptive lighting system A lighting system with a control system connected, allowing for dimming, on/off operation by time of night, and independent scheduling of individual lights for select hours of operation during nighttime hours.

affidavit of publication A notarized written declaration stating that a notice of hearing (or notice of opportunity for a hearing) was published in the legally prescribed manner.

affidavit of service by mailing A notarized written declaration stating that the limited access hearing packet was mailed at least 15 days prior to the hearing and entered into the record at the hearing.

alternative(s) Possible solutions to accomplish a defined purpose and need. These include local and state transportation system mode and design options, locations, and travel demand management and transportation system management-type improvements such as ramp metering, mass transit, and high-occupancy vehicle (HOV) facilities.

Alternatives Comparison Table (ACT) A table that documents and presents the tradeoffs among those performance metrics identified for each alternative under consideration on a project. The ACT is used to assist in analyzing the baseline and contextual performance tradeoffs and ultimately to select an alternative. It is a supplemental document to the "Alternatives Analysis" section of the *Basis of Design*.

ancillary services Those secondary services, also considered amenities, provided at safety rest areas that include, but are not limited to, vending machines, picnic areas, interpretive signing, telephones, recreational vehicle (RV) sanitary disposal facilities, trails, scenic viewpoints, commercial and public information displays, and visitor information centers.

annual average daily traffic (AADT) The total volume of traffic passing a point or segment of a highway facility in both directions for one year divided by the number of days in the year.

annual daily traffic (ADT) The volume of traffic passing a point or segment of a highway, in both directions, during a period of time, divided by the number of days in the period, and factored to represent an estimate of traffic volume for an average day of the year.

application for an access connection An application provided by the permitting authority to be completed by the applicant for access to a managed access highway.

approach An access point, other than a public road/street, that allows access to or from a limited access highway on the state highway system.

approach and access connection These terms are listed under the specific access section to which they apply. The first section below is for limited access highways and uses the term approach. The second section below is for managed access highways and uses the term access connection. Approaches and access connections include any ability to leave or enter a highway right of way other than at an intersection with another road or street.

(a) ***limited access highways: approach*** An access point, other than a public road/street, that allows access to or from a limited access highway on the state highway system. There are five types of approaches to limited access highways that are allowed:

- ***Type A*** An off and on approach in a legal manner, not to exceed 30 feet in width, for the sole purpose of serving a single-family residence. It may be reserved by the abutting owner for specified use at a point satisfactory to the state at or between designated highway stations. This approach type is allowed on partial and modified control limited access highways.
- ***Type B*** An off and on approach in a legal manner, not to exceed 50 feet in width, for use necessary to the normal operation of a farm, but not for retail marketing. It may be reserved by the abutting owner for specified use at a point satisfactory to the state at or between designated highway stations. This approach type is allowed on partial and modified control limited access highways. This approach type may be used for wind farms when use of the approach is limited to those vehicles necessary to construct and maintain the farm for use in harvesting wind energy.
- ***Type C*** An off and on approach in a legal manner, for a special purpose and width to be agreed upon. It may be specified at a point satisfactory to the state at or between designated highway stations. This approach type is allowed on partial and modified control limited access highways and on full control limited access highways where no other reasonable means of access exists, as solely determined by the department.
- ***Type D*** An off and on approach in a legal manner, not to exceed 50 feet in width, for use necessary to the normal operation of a commercial establishment. It may be specified at a point satisfactory to the state at or between designated highway stations. This approach type is allowed only on modified control limited access highways.
- ***Type E*** This type is no longer allowed to be constructed because of the requirements that there be only one access point per parcel on a limited access state highway.
- ***Type F*** An off and on approach in a legal manner, not to exceed 30 feet in width, for the sole purpose of serving a wireless communication site. It may be specified at a point satisfactory to the state at or between designated highway stations. This approach type is allowed only on partial control limited access highways. (See WAC 468 58 080(vi) for further restrictions.)

(b) ***managed access highways: access connection*** An access point, other than a public road/street, that permits access to or from a managed access highway on the state highway system. There are five types of access connection permits:

- ***conforming access connection*** A connection to a managed access highway that meets current WAC and WSDOT location, spacing, and design criteria.

- ***grandfathered access connection*** Any connection to the state highway system that was in existence and in active use on July 1, 1990, and has not had a significant change in use.
- ***joint-use access connection*** A single connection to a managed access highway that serves two or more properties.
- ***nonconforming access connection*** A connection to a managed access highway that does not meet current WSDOT location, spacing, or design criteria, pending availability of a future conforming access connection.
- ***variance access connection*** A connection to a managed access highway at a location not normally allowed by current WSDOT criteria.

(c) ***managed access connection category*** There are four access connection permit categories for managed access connections to state highways: Category I, Category II, Category III, and Category IV (see Chapter 540).

approach design speed The design speed of the roadway leading into the roundabout.

approach lanes The lane or set of lanes for traffic approaching the roundabout (see Chapter 1320).

area of influence The area that will be directly impacted by the proposed action: freeway main line, ramps, crossroads, immediate off-system intersections, and state and local roadway systems.

articulated bus A two-section bus that is permanently connected at a joint.

auxiliary aids and services (1) Qualified interpreters, notetakers, transcription services, written materials, telephone handset amplifiers, assistive listening devices, assistive listening systems, telephones compatible with hearing aids, open and closed captioning, telecommunications devices for deaf persons (TDDs), videotext displays, or other effective methods for making aurally delivered materials available to individuals with hearing limitations; (2) Qualified readers, taped texts, audio recordings, Brailled materials, large print materials, or other effective methods for making visually delivered materials available to individuals with visual impairments; (3) Acquisition or modification of equipment or devices; (4) Other similar services and actions; and (5) Providing and disseminating information, written materials, and notices in languages other than English, where appropriate.

auxiliary lane The portion of the roadway adjoining the through lanes for parking, speed change, turning, storage for turning, weaving, truck climbing, and other purposes supplementary to through-traffic movement.

average daily traffic (ADT) The total volume during a given time period (in whole days): greater than one day and less than one year, divided by the number of days in that time period.

average light level The average of all light intensities within the design area.

average weekday vehicle trip ends (AWDVTE) The estimated total of all trips entering plus all trips leaving a road approach on a weekday for the final stage of development of the property served by the road approach.

B

backslope A sideslope that goes up as the distance increases from the roadway (cut slopes).

barrier terminal A crash-tested end treatment for longitudinal barriers that is designed to reduce the potential for spearing, vaulting, rolling, or excessive deceleration of impacting vehicles from either direction of travel. Barrier terminals include applicable anchorage.

baseline The approved time phased plan (for a project, a work breakdown structure component, a work package, or a schedule activity), plus or minus approved project scope, cost, schedule, and technical changes. Generally refers to the current baseline, but may refer to the original or some other baseline. Usually used with a modifier (e.g., cost baseline, schedule baseline, performance measurement baseline, technical baseline).

baseline performance metric A description of need in terms that can be measured or assessed in both the existing and proposed (future) state.

baseline performance need The primary reason a project has been proposed. It refers to the threshold determination at the project location resulting from a statewide biennial prioritization and funding process. It may also be the specific issue to be addressed by the project described by a partnering agency that is providing the funding.

basic number of lanes The minimum number of general purpose lanes designated and maintained over a significant length of highway.

Basis of Design (BOD) A document and template used to record information, decisions, and analysis needed in the development of a project design, including all factors leading to the development and selection of a project alternative, and the selection of design elements associated with that alternative.

benefit/cost analysis A method of valuing a proposition by first monetizing all current expenditures to execute—cost—as well as the expected yields into the future—benefit, then dividing the total benefit by the total cost, thus providing a ratio. Alternatives may be rendered and compared in this fashion where, typically, a higher ratio is preferable, indicating a better return on investment.

bicycle Any device propelled solely by human power upon which a person or persons may ride, having two tandem wheels, either of which is 16 inches or more in diameter, or three wheels, any one of which is more than 20 inches in diameter.

bicycle route A system of facilities that is used or has a high potential for use by bicyclists or that is designated as such by the jurisdiction having the authority. A series of bicycle facilities may be combined to establish a continuous route and may consist of any or all types of bicycle facilities.

bike lane A portion of a highway or street identified by signs and pavement markings as reserved for bicycle use.

break See access break.

buffer-separated HOV lane An HOV lane that is separated from the adjacent same direction general-purpose freeway lanes by a designated buffer.

bus A rubber-tired motor vehicle used for transportation, designed to carry more than ten passengers.

business access transit (BAT) lanes A transit lane that allows use by other vehicles to access abutting businesses.

bus pullout A bus stop with parking area designed to allow transit vehicles to stop wholly off the roadway.

bus rapid transit (BRT) An express rubber tired transit system operating predominantly in roadway managed lanes. It is generally characterized by separate roadway or buffer-separated HOV lanes, HOV direct access ramps, and a high-occupancy designation (3+ or higher).

bus shelter A facility that provides seating and protection from the weather for passengers waiting for a bus.

bus stop A place designated for transit vehicles to stop and load or unload passengers.

C

capacity The maximum sustainable flow rate at which vehicles or persons can reasonably be expected to traverse a point or uniform segment of a lane or roadway during a specified time period under given roadway, geometric, traffic, environmental, and control conditions. Capacity is usually expressed as vehicles per hour (vph), passenger cars per hour (pcph), or persons per hour (pph).

Capital Improvement and Preservation Program (CIPP) WSDOT's program of projects developed each biennium that delivers capital investments in highway, marine, and rail facilities that have been funded in part or in whole by the state Legislature. The CIPP is submitted to the Governor and, ultimately, by the Governor to the Legislature.

Capital Program Management System (CPMS) A computer database used to develop and manage the highway and marine construction programs. The CPMS allows users to establish and maintain project data and is used to manage and deliver statewide construction programs.

capture trips Trips that do not enter or leave the traveled ways of a project's boundary within a mixed-use development.

carpool/vanpool A group of people who share the use and cost of a car or van for transportation on a regular basis.

Categorical Exclusion (CE) (NEPA) or ***Categorical Exemption (CE)*** (SEPA) Actions that do not individually or cumulatively have a significant effect on the environment.

central island The area of the roundabout, including the truck apron, surrounded by the circulating roadway.

central island diameter The diameter of the central island, including the truck apron (see Chapter 1320).

circulating lane A lane used by vehicles circulating in the roundabout.

circulating roadway The traveled lane(s) adjacent to the central island and outside the truck apron, including the entire 360° circumference of the circle.

circulating roadway width The total width of the circulating lane(s) measured from inscribed circle to the central island (see Chapter 1320).

clear run-out area The area beyond the toe of a nonrecoverable slope available for use by an errant vehicle.

clear zone The total roadside border area, available for use by errant vehicles, starting at the edge of the traveled way and oriented from the outside or inside shoulder (in median applications) as applicable. This area may consist of a shoulder, a recoverable slope, a nonrecoverable slope, and/or a clear run-out area. The clear zone cannot contain a critical fill slope, fixed objects, or water deeper than 2 feet.

Climate Change Vulnerability The risk a transportation facility will be impacted by the effects of climate change.

climbing lane An auxiliary lane used for the diversion of slow traffic from the through lane.

collector A context description of a roadway intended to provide a mix of access and mobility performance. Typically low speed, collecting traffic from local roads and connecting them with destination points or arterials. This term is used in multiple classification systems, but is most commonly associated with the *Functional Classification* System.

collector-distributor road (C-D road) A parallel roadway designed to remove weaving from the main line and reduce the number of main line entrances and exits.

collector system Routes that primarily serve the more important intercounty, intracounty, and intraurban travel corridors; collect traffic from the system of local access roads and convey it to the arterial system; and on which, regardless of traffic volume, the predominant travel distances are shorter than on arterial routes (RCW 47.05.021).

Commercial Vehicle Information Systems and Networks (CVISN) A network that links intelligent transportation systems (ITS) to share information on commercial vehicles. When in operation at a weigh site, it can enable commercial vehicles to clear the facility without stopping.

complex ramp alignment and grade The exit advisory speed is 35 mph or lower than the posted main line speed, or there is a 6% or greater change in grade from existing main line grade to the ramp grade.

conflict An event involving two or more road users in which the action of one user causes the other user to make an evasive maneuver to avoid a crash.

conflict point A point where traffic paths cross, merge, or diverge.

connection See *approach and access connection*.

consider To think carefully about, especially in order to make a decision. The decision to document a consideration is left to the discretion of the engineer.

context refers to the environmental, economic, and social features that influence livability and travel characteristics. Context characteristics provide insight into the activities, functions, and performance that can be influenced by the roadway design. Context also informs roadway design, including the selection of design controls, such as target speed and modal priority, and other design decisions. See Chapter 1102.

context categories The naming convention used to describe either a land use or transportation context (see Chapter 1102).

context characteristic A distinguishing trait within a context, either land use or transportation. Chapter 1102 lists several common characteristics that help distinguish between one type of context versus another. There may be additional traits not covered in the chapter.

contextual performance metric A restatement of a contextual performance need in terms that can be measured or assessed in both the existing and proposed (future) state.

contextual performance need A statement of nee that applies to a project location which has not been identified as a baseline need.

context sensitive solutions (CSS) A collaborative, interdisciplinary approach that involves all stakeholders to develop a transportation facility that fits its physical setting and preserves scenic, aesthetic, historic, and environmental resources while maintaining safety and mobility. CSS is an approach that considers the total context within which a transportation improvement project will exist.

contiguous parcels Two or more pieces of real property, under the same ownership, with one or more boundaries that touch and have similarity of use.

continuous load The electrical load on a circuit that lasts for a duration of three or more hours on any day.

contributing factors Those operational conditions, human factors, context conditions, design elements, design controls, or actions identified by data, engineering judgment, or the community that contribute to a performance need under evaluation.

controlled releasing terminal (CRT) post A standard-length guardrail post that has two holes drilled through it so it might break away when struck.

conventional traffic signal A permanent or temporary installation providing alternating right of way assignments for conflicting traffic movements. At least two identical displays are required for the predominant movement on each approach.

corner clearance On a managed access highway, the distance from an intersection of a public road or street to the nearest access connection along the same side of the highway. The minimum corner clearance distance (see Chapter 540) is measured from the closest edge of the intersecting road or street to the closest edge of the traveled way of the access connection, measured along one side of the traveled way (through lanes) (see also *access point spacing*).

corridor sketch an information source that describes the attributes of a state highway corridor, its current and future function, as well as its performance expectations. It will ultimately identify cost-effective strategies for future consideration. A completed corridor sketch may have information that is valuable at the project level in determining contextual performance needs, and project alternatives. A corridor sketch is not a substitute for detailed planning and analysis, nor is it a list of investments or projects.

corridor vision The future transportation context from a regional perspective. Practical Design considers and accounts for the contextual needs of the longer section of highway in the development and evaluation of alternatives to ensure a favorable outcome for the greater system.

countermeasure an action taken to counteract an existing or anticipated condition.

court reporter A person with a license to write and issue official accounts of judicial or legislative proceedings.

crash-accepted device A feature that has been proven acceptable for use under specified conditions, either through crash testing or in-service performance.

Crash Analysis Report (CAR) A template that is the basis for all crash analyses for all types of design documentation that need crash analyses, as described in Chapter 321.

critical fill slope A slope on which a vehicle is likely to overturn. Slopes steeper than 3H:1V are considered critical fill slopes.

crossroad The minor roadway at an intersection. At a stop-controlled intersection, the crossroad has the stop.

curb section A roadway cross section with curb and sidewalk.

D

decision sight distance The distance needed for a driver to detect an unexpected or difficult-to-perceive condition, recognize the condition, select an appropriate maneuver, and complete the maneuver based on design conditions and design speed.

deflection (in respect to roundabouts) The change in the path of a vehicle imposed by the geometric features of a roundabout resulting in a slowing of vehicles.

delineation Any method of defining the roadway operating area for the driver.

deliverable Any unique and verifiable product, result or capability to perform a service that must be produced to complete a process, phase, or project.

departure lanes The lane or set of lanes for traffic leaving the roundabout (see Chapter 1320).

Design Analysis a process and tool to record design element changes where the dimensions chosen do not meet the value, or lie within the range of values, provided for that element in the *Design Manual*. (see Chapters 300 and 1106).

Design Approval Documented approval of the design at this early milestone locks in design policy for three years. Design approval becomes part of the Design Documentation Package (see Chapter 300.)

design-bid-build The project delivery method where design and construction are sequential steps in the project development process (23 CFR 636.103).

design-build contract An agreement that provides for design and construction of improvements by a consultant/contractor team. The term encompasses design-build-maintain, design-build-operate, design-build-finance, and other contracts that include services in addition to design and construction. Franchise and concession agreements are included in the term if they provide for the franchisee or concessionaire to develop the project that is the subject of the agreement (23 CFR 636.103).

design-builder The firm, partnership, joint venture, or organization that contracts with WSDOT to perform the work.

design controls key parameters that critically shape design decisions and effect calculated dimensions for some design elements. Design controls are conscientiously selected and work together with the context characteristics to achieve a particular outcome (see Chapter 1103)

Design Clear Zone The minimum clear zone target value used in highway design.

Design Documentation Package (DDP) See *Project File*.

design element Any component or feature associated with roadway design that becomes part of the final product. Examples include lane width, shoulder width, alignment, and clear zone (see Chapter 1105.)

designer This term applies to WSDOT design personnel. Wherever “designer” appears in this manual, design-build personnel shall deem it to mean: Engineer of Record, Design Quality Assurance Manager, design-builder, or any other term used in the design-build contract to indicate design-build personnel responsible for the design elements of a design-build project, depending on the context of information being conveyed.

design hourly volume (DHV) Computed by taking the annual average daily traffic times the K-factor. It can only be accurately determined in locations where there is a permanent traffic recording device active 365 days of the year. It correlates to the peak hour (see *peak hour*), but it is not equivalent. In some circumstances, it is necessary to use the peak hour data instead of DHV because peak hour can be collected using portable traffic recorders.

design speed A design control; the speed used to determine the various geometric design features of the roadway.

design up An approach to developing project alternatives utilizing the smallest dimensions that meet the need by providing the desired performance.

design users A broad term intended to capture all modal users that currently utilize or are legally permitted on a roadway segment or node.

design variance Same as Design Analysis.

design vehicle See *intersection design vehicle*.

design year The forecast year used for design as described in Chapter 1103. See also *horizon year*.

desirable Design criteria that are recommended for inclusion in the design.

Determination of Nonsignificance (DNS) (SEPA) The written decision by the Regional Administrator that a proposal will not have a significant impact and no EIS is required.

Determination of Significance (DS) (SEPA) A written decision by the Regional Administrator that a proposal could have a significant adverse impact and an EIS is required.

directional design hour volume (DDHV) The traffic volume for the design hour in the peak direction of flow, in vehicles per hour. For example, if during the design hour, 60% of the vehicles traveled eastbound and 40% traveled westbound, then the DDHV for the eastbound direction would be the DHV x 0.60.

divided multilane A roadway with two or more through lanes in each direction and a median that physically or legally prohibits left turns, except at designated locations.

document (verb) The act of including a short note to the Design Documentation Package that explains a design decision.

dooring Describes a conflict with a parked vehicle door opening into a roadway bike facility.

double-lane roundabout A roundabout with a two-lane circulating roadway and one or more entry or exit legs with two lanes.

driveway A vehicular access point that provides access to or from a public roadway.

drop and ride An area of a park & ride lot or other multimodal facility where patrons are dropped off or picked up by private auto or taxi.

E

easement A documented right, as a right of way, to use the property of another for designated purposes.

element An architectural or mechanical component or design feature of a space, site, or public right of way.

emergency escape ramp A roadway leaving the main roadway designed for the purpose of slowing and stopping out-of-control vehicles away from the main traffic stream.

emergency vehicle signal A special adaptation of a conventional traffic signal installed to allow for the safe movement of authorized emergency vehicles. Usually, this type of signal is installed on the highway at the entrance into a fire station or other emergency facility. The signal ensures protected entrance onto the highway for the emergency vehicle. When not providing for this movement, the signal either operates continuously (consistent with the requirements for a conventional traffic signal) or displays continuous green, which is allowed at non-intersection locations only. At least two identical displays are required per approach.

enforcement observation point A place where a law enforcement officer may park and observe traffic.

entry angle The angle between the entry roadway and the circulating roadway measured at the yield point (see Chapter 1320).

entry curve The curve of the left edge of the roadway that leads into the circulating roadway (see Chapter 1320).

entry width The width of an entrance leg at the inscribed circle measured perpendicular to travel (see Chapter 1320).

Environmental Assessment (EA) (NEPA) A document prepared for federally funded, permitted, or licensed projects that are not categorical exclusions (CE), but do not appear to be of sufficient magnitude to require an EIS. The EA provides enough analysis to determine whether an EIS or a FONSI should be prepared.

Environmental Impact Statement (EIS) A detailed written statement of a proposed course of action, project alternatives, and possible impacts of the proposal.

Environmental Review Summary (ERS) (see *Project Summary*) Part of the Project Summary document, the ERS identifies environmental permits and approvals. It is prepared in the region and is required for Design Approval.

exit curve The curve of the left edge of the roadway that leads out of the circulating roadway (see Chapter 1320).

exit width The width of an exit leg at the inscribed circle (see Chapter 1320).

expressway A divided highway that has a minimum of two lanes in each direction for the exclusive use of traffic and that may or may not have grade separations at intersections. A transportation context characteristic that is designated for a divided highway with limited access that provides regional mobility.

extrude A procedure for applying marking material to a surface by forcing the material through a die to give it a certain shape.

F

facility All or any portion of buildings, structures, improvements, elements, and pedestrian or vehicular routes located in a public right of way.

feature A component of a pedestrian access route, such as a curb ramp, driveway, crosswalk, or sidewalk.

Federal Highway Administration (FHWA) The division of the U.S. Department of Transportation with jurisdiction over the use of federal transportation funds for state highway and local road and street improvements.

Federal Transit Administration (FTA) The division of the U.S. Department of Transportation with jurisdiction over the use of federal funds for financial assistance to develop new transit systems and improve, maintain, and operate existing systems.

feeder service Bus service that provides connections with other bus or rail services.

final design Any design activities following preliminary design; expressly includes the preparation of final construction plans and detailed specifications for the performance of construction work (23 CFR 636.103). Final design is also defined by the fact that it occurs after NEPA/SEPA approval has been obtained.

Finding of No Significant Impact (FONSI) (NEPA) A federal document indicating that a proposal will not significantly affect the environment and an EIS is not required.

findings and order A document containing the findings and conclusions of a limited access hearing approved by the Assistant Secretary, Engineering & Regional Operations (see Chapter 210).

findings and order plan A limited access plan, prepared after a limited access hearing, which is based on the hearing record.

fixed feature (object to be mitigated) A fixed object, a side slope, or water that, when struck, can result in impact forces on a vehicle's occupants that may result in injury or place the occupants in a situation that has a high likelihood of injury. A fixed feature can be either constructed or natural.

flare The widening of the approach to the roundabout to increase capacity and facilitate natural vehicle paths.

flasher warning assembly Flashing beacons that are used only to supplement an appropriate warning or regulatory sign or marker. The displays consist of two alternating flashing yellow indications.

flyer stop A transit stop inside the limited access boundaries.

footcandle (fc) The illumination of a surface one square foot in area on which a flux of one lumen is uniformly distributed. One footcandle equals one lumen per square foot.

foreslope A sideslope that goes down as the distance increases from the roadway (fill slopes and ditch inslopes).

freight corridor type Designations for a highway facility found in the Freight and Goods Transportation System (FGTS).

freeway A divided highway that has a minimum of two lanes in each direction for the exclusive use of traffic and with full control of access.

frontage road An auxiliary road that is a local road or street located beside a highway for service to abutting property and adjacent areas and for control of access.

functional classification The grouping of streets and highways according to the character of the service they are intended to provide.

G

geocomposites Prefabricated edge drains, wall drains, and sheet drains that typically consist of a cuspated or dimpled polyethylene drainage core wrapped in a geotextile. The geotextile wrap keeps the core clean so that water can freely flow through the drainage core, which acts as a conduit. Prefabricated edge drains are used in place of shallow geotextile-wrapped trench drains at the edges of the roadway to provide subgrade and base drainage. Wall drains and sheet drains are typically placed between the back of the wall and the soil to drain the soil retained by the wall.

Geographic Information System (GIS) A computerized geographic information system used to store, analyze, and map data. Data may be used with GIS if the data includes the Accumulated Route Mile (ARM) or State Route Milepost (SRMP) programs. Global Positioning System (GPS) technology provides a means of collecting data and is an alternative to ARM and SRMP. WSDOT's primary desktop tool to view and analyze GIS data is ArcGIS software. GIS is used to gather and analyze data to support the purpose and need as described in the Project Summary (http://wwwi.wsdot.wa.gov/gis/supportteam/default.asp).

geogrids A polymer grid mat constructed either of coated yarns or a punched and stretched polymer sheet. Geogrids usually have high strength and stiffness and are used primarily for soil reinforcement.

geomembranes Impervious polymer sheets that are typically used to line ponds or landfills. In some cases, geomembranes are placed over moisture-sensitive swelling clays to control moisture.

geonets Similar to geogrids, but typically lighter weight and weaker, with smaller mesh openings. Geonets are used in light reinforcement applications or are combined with drainage geotextiles to form a drainage structure.

geosynthetic erosion control The minimizing of surficial soil particle movement due to the flow of water over the surface of bare soil or due to the disturbance of soil caused by construction activities under or near bodies of water. This is the primary function of geotextiles used as silt fences or placed beneath riprap or other stones on soil slopes. Silt fences keep eroded soil particles on the construction site, whereas geotextiles placed beneath riprap or other stones on soil slopes prevent erosion from

taking place at all. In general, the permanent erosion control methods described in Chapter 630 are only used where more natural means (like the use of biodegradable vegetation mats to establish vegetation to prevent erosion) are not feasible. These functions control some of the geosynthetic properties, such as apparent opening size (AOS) and permittivity, and in some cases load-strain characteristics. The application will also affect the geosynthetic installation conditions. These installation conditions influence the remaining geosynthetic properties needed, based on the survivability level required.

geosynthetic filtration The passage of water through the geosynthetic relatively unimpeded (permeability or permittivity) without allowing passage of soil through the geosynthetic (retention). This is the primary function of geotextiles in underground drainage applications.

geosynthetic survivability The ability of the geosynthetic to resist installation conditions without significant damage, such that the geosynthetic can function as intended. Survivability affects the strength properties of the geosynthetic required.

geotextiles (nonwoven) A sheet of continuous or staple fibers entangled randomly into a felt for needle-punched nonwovens and pressed and melted together at the fiber contact points for heat-bonded nonwovens. Nonwoven geotextiles tend to have low-to-medium strength and stiffness with high elongation at failure and relatively good drainage characteristics. The high elongation characteristic gives them superior ability to deform around stones and sticks.

geotextiles (woven) Slit polymer tapes, monofilament fibers, fibrillated yarns, or multifilament yarns simply woven into a mat. Woven geotextiles generally have relatively high strength and stiffness and, except for the monofilament wovens, relatively poor drainage characteristics.

gore The area downstream from the intersection of the shoulders of the main line and exit ramp. Although generally referring to the area between a main line and an exit ramp, the term may also be used to refer to the area between a main line and an entrance ramp.

gore nose At an exit ramp, the point at the end of the gore area where the paved shoulders of the main line and the ramp separate (see Chapter 1360) or the beginning of traffic barrier, not including any impact attenuator. Also, the similar point at an entrance ramp.

H

hearing An assembly to which the public is invited and at which participation is encouraged. Types of hearings include:

- ***administrative appeal hearing*** A formal process whereby a property owner may appeal WSDOT's implementation of access management legislation. The appeal is heard by an administrative law judge (ALJ), who renders a decision. (See Chapter 540 for administrative appeal hearing procedures.)
- ***combined hearing*** A hearing held when there are public benefits to be gained by combining environmental, corridor, design, and/or limited access subjects.
- ***corridor hearing*** A formal or informal hearing that presents the corridor alternatives to the public for review and comment before a commitment is made to any one route or location. This type of hearing is beneficial for existing corridors with multiple Improvement projects programmed over a long duration.
- ***design hearing*** A formal or informal hearing that presents the design alternatives to the public for review and comment before the selection of a preferred alternative.
- ***environmental hearing*** A formal or informal hearing documenting that social, economic, and environmental impacts have been considered and that public opinion has been solicited.
- ***formal hearing format*** A hearing conducted by a moderator using a formal agenda, overseen by a hearing examiner, and recorded by a court reporter, as required by law. Limited access hearings require the use of the formal hearing format (see Chapter 210).
- ***informal hearing format*** A hearing where oral comments are recorded by a court reporter, as required by law. An informal hearing often uses the "open house" format (see Chapter 210). A formal agenda and participation by a hearing examiner are optional.
- ***limited access hearing*** A formal hearing that gives local public officials, owners of abutting properties, and other interested persons an opportunity to be heard about the limitation of access to the highway system.

hearing agenda An outline of the actual public hearing elements, used with formal hearings. (See Chapter 210 for contents.)

Hearing Coordinator The HQ Access and Hearings Section Manager: (360) 705-7266.

hearing examiner An administrative law judge from the Office of Administrative Hearings, or a WSDOT designee, appointed to moderate a hearing.

hearing script A written document of text to be presented orally by department representatives at a hearing.

hearing summary Documentation prepared by the region and approved by Headquarters that summarizes environmental, corridor, and design hearings. (See Chapter 210 for content requirements.)

hearing transcript A document prepared by the court reporter that transcribes verbatim all oral statements made during the hearing, including public comments. This document becomes part of the official hearing record.

high-occupancy toll (HOT) lane A managed lane that combines a high-occupancy vehicle lane and a toll lane.

high-occupancy vehicle (HOV) A vehicle that meets the occupancy requirements of the facility as authorized by WAC 468-510-010.

high pavement type Portland cement concrete pavement or hot mix asphalt (HMA) pavement on a treated base.

high-speed roadway See *speed*.

highway A general term denoting a street, road, or public way for the purpose of vehicular travel, including the entire area within the right of way.

Highway Construction Program (HCP) A comprehensive multiyear program of highway Improvement and Preservation projects selected by the Legislature.

Highway System Plan (HSP) A WSDOT planning document that addresses the state highway system element of the Washington Transportation Plan (WTP). The HSP defines the service objectives, action strategies, and costs to maintain, operate, preserve, and improve the state highway system for 20 years. The HSP is the starting point for the state highway element of the CIPP and the state Highway Construction Program. It is periodically updated to reflect completed work and changing transportation needs, policies, and revenues. It compares highway needs to revenues, describes the "constrained" costs of the highway programs, and provides details of conceptual solutions and performance in the improvement program.

Highways of Statewide Significance (HSS) Include interstate highways and other principal arterials that are needed to connect major communities in the state. The designation helps assist with the allocation and direction of funding. (http://www.wsdot.wa.gov/planning/HSS)

Horizon year typically considered to be 20 years from the year construction is scheduled to begin, as described in Chapter 1103. See also design year.

HOV direct access ramp An on- or off-ramp exclusively for the use of HOVs that provides access between a freeway HOV lane and a street, transit support facility, or another freeway HOV lane without weaving across general-purpose lanes.

HOV facility A priority treatment for HOVs.

I

impact attenuator system A device that acts primarily to bring an errant vehicle to a stop at a deceleration rate tolerable to the vehicle's occupants or to redirect the vehicle away from a fixed feature.

incorporated city or town A city or town operating under RCW 35 or 35A.

inscribed circle The outer edge of the circulating roadway.

inscribed circle diameter (ICD) The diameter of the inscribed circle (see Chapter 1320).

intelligent transportation systems (ITS) An integrated system of advanced sensor, computer, electronics, and communication technologies and management strategies, used to increase the safety and efficiency of the surface transportation system.

interchange A system of interconnecting roadways, in conjunction with one or more grade separations, providing for the exchange of traffic between two or more intersecting highways or roadways.

Interchange Justification Report (IJR) The document used to propose a revision to limited access freeways.

intermediate pavement type Hot mix asphalt pavement on an untreated base.

Intermediate speed roadway See speed.

intersection An at-grade access point connecting a state highway with a road or street duly established as a public road or public street by the local governmental entity.

intersection angle The angle between any two intersecting legs at the point the centerlines intersect.

intersection area The area of the intersecting roadways bounded by the edge of traveled ways and the area of the adjacent roadways to the farthest point: (a) the end of the corner radii, (b) through any marked crosswalks adjacent to the intersection, (c) to the stop bar, or (d) 10 feet from the edge of shoulder of the intersecting roadway (see Chapter 1310).

intersection at grade The general area where a roadway or ramp terminal is met or crossed at a common grade or elevation by another roadway.

- ***four-leg intersection*** An intersection formed by two crossing roadways.
- ***split tee*** A four-leg intersection with the crossroad intersecting the through roadway at two tee intersections offset by at least the width of the roadway.
- ***tee (T) intersection*** An intersection formed by two roadways where one roadway terminates at the point it meets a through roadway.
- ***wye (Y) intersection*** An intersection formed by three legs in the general form of a "Y" where the angle between two legs is less than 60°.

intersection control beacon (also *flashing beacon*) A secondary control device, generally suspended over the center of an intersection, that supplements intersection warning signs and stop signs. One display per approach may be used; however, two displays per approach are desirable. Intersection control beacons are installed only at intersections that control two or more directions of travel.

intersection leg Any one of the roadways radiating from and forming part of an intersection.

- ***entrance leg*** The lanes of an intersection leg for traffic entering the intersection.
- ***exit leg*** The lanes of an intersection leg for traffic leaving the intersection.

Note: Whether an intersection leg is an entrance leg or an exit leg depends on which movement is being analyzed. For two-way roadways, each leg is an entrance leg for some movements and an exit leg for other movements.

intersection density The ratio of intersections per mile.

intersection design vehicle A specific selection of the vehicle to be used to dimension intersection design elements at an individual intersection.

intersection sight distance The length of roadway visible to the driver of a vehicle entering an intersection.

Interstate System A network of routes designated by the state and the Federal Highway Administration (FHWA) under terms of the federal-aid acts as being the most important to the development of a national system. The Interstate System is part of the principal arterial system.

island A defined area within an intersection, between traffic lanes, for the separation of vehicle movements or for pedestrian refuge.

J

justify Preparing a memo to the DDP identifying the reasons for the decision: a comparison of advantages and disadvantages of all options considered. A more rigorous effort than document.

K

K-factor The proportion of AADT occurring in the analysis hour is referred to as the K-factor, expressed as a decimal fraction (commonly called “K,” “K30,” or “K100”). The K30 is the thirtieth (K100 is the one-hundredth) highest peak hour divided by the annual average daily traffic. Normally, the K30 or K100 will be in the range of 0.09 to 0.10 for urban and rural areas. Average design hour factors are available on the web in the Statewide Travel and Collision Data Office’s Annual Peak Hour Report.

L

lamp lumens The total light output from a lamp, measured in lumens.

lane A strip of roadway used for a single line of vehicles.

lane control signal (reversible lanes) A special overhead signal that permits, prohibits, or warns of impending prohibition of lane use.

lane width The lateral design width for a single lane, striped as shown in the *Standard Plans* and the *Standard Specifications*. The width of an existing lane is measured from the edge of traveled way to the center of the lane line or between the centers of adjacent lane lines.

lateral clearance The distance from the edge of traveled way to a roadside object.

layered networks Roadway network arrangement where the objective is to separate modes onto different facilities with planned interconnection locations.

lead agency The public agency that has the principal responsibility for carrying out or approving a project.

left-cross Describes the intersection conflict between a motor vehicle left-turn and bicycle through movement in the opposing direction.

legal road approach A road approach that complies with the requirements of Chapter 530 for limited access facilities and Chapter 540 for managed access facilities.

length of need The length of a traffic barrier used to shield a fixed feature.

level of service (LOS) LOS is based on peak hour, except where noted. LOS assigns a rank (A – F) to facility sections based on traffic flow concepts like density, delay, and/or corresponding safety performance conditions. (See the Highway Capacity Manual and AASHTO's Geometric Design of Highways and Streets ["Green Book"] for further details.)

life cycle cost The total cost of a project or item over its useful life. This includes all of the relevant costs that occur throughout the life of a project or item, including initial acquisition costs (such as right of way, planning, design, and construction), operation, maintenance, modification, replacement, demolition, financing, taxes, disposal, and salvage value as applicable.

light emitting diode (LED) A two-lead semiconductor light source.

limited access (L/A) Full, partial, or modified access control is planned and established for each corridor and then acquired as the right to limit access to each individual parcel (see Chapter 520).

- ***acquired limited access control*** Access rights have been purchased.
- ***established limited access control*** An access hearing has been held and the Assistant Secretary, Engineering & Regional Operations, has adopted the findings and order, which establishes the limits and level of control.

- ***planned limited access control*** Limited access control is planned for some time in the future; however, no access hearing has been held.

Limited Access and Managed Access Master Plan A map of Washington State that shows established and planned limited access highways: www.wsdot.wa.gov/design/accessandhearings

limited access highway All highways listed as "Established L/A" on the Limited Access and Managed Access Master Plan and where the rights of direct access to or from abutting lands have been acquired from the abutting landowners.

- ***full access control*** This most restrictive level of limited access provides access, using interchanges, for selected public roads/streets only, and prohibits highway intersections at grade.
- ***partial access control*** The second most restrictive level of limited access. At grade intersections with selected public roads are allowed, and there may be some crossings and some driveway approaches at grade. Direct commercial access is not allowed.
- ***modified access control*** The least restrictive level of limited access. Characteristics are the same as for partial access control except that direct commercial access is allowed.

local roads Non-state highways that are publicly owned.

long tunnel A tunnel, lid, or underpass that is greater than 80' in length and has a length to vertical clearance ratio greater than 10:1.

low pavement type Bituminous surface treatment (BST).

low-speed roadway See *speed*

lumen The unit used to measure luminous flux.

luminaire A complete lighting unit comprised of a light bulb or light emitting Diode (LED) module, wiring, and a housing unit.

luminance The quotient of the luminous flux at an element of the surface surrounding the point and propagated in directions defined by an elementary cone containing the given direction, by the product of the solid angle of the cone and area of the orthogonal projection of the element of the surface on a plane perpendicular to the given direction. The luminous flux may be leaving, passing through, and/or arriving at the surface.

luminous flux The time rate of the flow of light.

M

managed access highway Highways where the rights of direct access to or from abutting lands have not been acquired from the abutting landowners.

managed lane A lane that increases efficiency by packaging various operational and design actions. Lane management operations may be adjusted at any time to better match regional goals.

managing project delivery A WSDOT management process for project delivery from team initiation through project closing.

maximum uniformity ratio The average light level within the design area divided by the minimum light level within the design area (see Chapter 1040).

maximum veiling luminance ratio The maximum veiling luminance divided by the average luminance over a given design area for an observer traveling parallel to the roadway centerline (see Chapter 1040).

mcd/m2/lux Pavement marking retroreflectivity is represented by the coefficient of retroreflected luminance (R_L) measured in millicandelas per square meter.

Measures of Effectiveness (MOEs) In the context of Chapter 320, examples are: speed, delay, density, LOS, QOS, person or vehicle throughput, cost vs. benefit, and queue. (See FHWA's MOE List.)

median The portion of a divided highway separating vehicular traffic traveling in opposite directions.

median functions one or more reason(s) for a median as described in Chapter 1239.

median opening An opening in a continuous median for the specific purpose of allowing vehicle movement.

Memorandum of Understanding (MOU) There is one MOU (Highways Over National Forest Lands) between the United States Forest Service (USFS) and WSDOT that requires the USFS to obtain a road approach permit for new access to a state highway that is crossing Forest Service land.

metering signal A signal used to control the predominant flow rate of traffic at an at-grade facility.

Methods and Assumptions Document A mandatory document developed at the beginning of the IJR phase to record IJR assumptions, methodologies, criteria, and decisions (see Chapter 550).

Metropolitan Planning Organization (MPO) A lead agency designated by the Governor to administer the federally required transportation planning process in a metropolitan area with a population over 50,000. The MPO is responsible for the 20 year long-range plan and Transportation Improvement Program (TIP).

minimum average light level The average of all light intensities within the design area, measured just prior to relamping the system (see Chapter 1040).

minimum light level The minimum light intensity of illumination at any single point within the design area measured just prior to relamping the system (see Chapter 1040).

minor arterial system A rural network of arterial routes linking cities and other activity centers that generate long distance travel and, with appropriate extensions into and through urban areas, form an integrated network providing interstate and interregional service (RCW 47.05.021).

minor operational enhancement projects These projects usually originate from the Q2 component of the Q Program and are quick responses to implement low-cost improvements. They are typically narrow in scope and focus on improvements to traffic operations and modifications to traffic control devices. Guidance on the type of work included in the Q subprograms is in the Chart of Accounts.

modal compatibility An assessment to determine which mode(s) need to be considered strictly based on the context characteristics present or planned. The assessment is independent of whether any particular mode is present on the segment, and intended to guide strategic investment opportunities on a segment.

modal priority Mode(s) that will be prioritized when making design decisions for the project, guided by the outcome of the modal compatibility assessment.

mode A specific type or form of transportation. Typically for roadway design the modes are: automobiles, transit, truck freight, pedestrians, skateboards, and bicycles.

monument As defined in Chapter 410, a monument is any physical object or structure that marks or references a survey point. This includes, but is not limited to, a point of curvature (P.C.), a point of tangency (P.T.), a property corner, a section corner, a General Land Office (GLO) survey point, a Bureau of Land Management (BLM) survey point, and any other permanent reference set by a governmental agency or private surveyor.

monument removal or destruction The physical disturbance or covering of a monument such that the survey point is no longer visible or readily accessible.

mounting height – luminaire The vertical distance between the surface of the design area and the center of the light source of the luminaire. Note: This is not to be confused with pole height (H1), but is the actual distance that the luminaire is located above the roadway edge line.

movable bridge signal (also drawbridge signal) A signal installed to notify traffic to stop when the bridge is opened for waterborne traffic. Movable bridge signals display continuous green when the roadway is open to vehicular traffic.

multilane approach An approach that has two or more lanes, regardless of the lane use designation.

multimodal connection The point where multiple types of transportation activities occur; for example, where transit buses and van pools drop off or pick up passengers (including passengers with bicycles).

N

National Highway System (NHS) The NHS was developed by the U.S. Department of Transportation (DOT) in cooperation with the states, local officials, and metropolitan planning organizations (MPOs).

The NHS includes the following subsystems of roadways (note that a specific highway route may be on more than one subsystem):

- ***Interstate*** The Eisenhower Interstate System of highways retains its separate identity within the NHS.
- ***Other Principal Arterials*** These are highways in rural and urban areas that provide access between an arterial and a major port, airport, public transportation facility, or other intermodal transportation facility.
- ***Strategic Highway Network (STRAHNET)*** This is a network of highways that are important to the United States' strategic defense policy and that provide defense access, continuity, and emergency capabilities for defense purposes.
- ***Major Strategic Highway Network Connectors*** These are highways that provide access between major military installations and highways that are part of the Strategic Highway Network.
- ***Intermodal Connectors*** These highways provide access between major intermodal facilities and the other four subsystems making up the National Highway System.

natural vehicle path The natural path that a driver navigates a vehicle given the layout of the intersection and the ultimate destination.

need A statement that identifies the transportation problem(s) or other performance gap

negative illumination Lighting the background and leaving the object dark to contrast with the light behind it as the driver views it.

network connectivity How the various roadways and other transportation facilities within a network interconnect in a defined geographic area.

nighttime The period of time from one-half hour after sunset to one-half hour before sunrise and any other time when persons or objects may not be clearly discernible at a distance of 500 feet (RCW 46.04.200).

no-build condition The baseline, plus state transportation plan and comprehensive plan improvements, expected to exist, as applied to the year of opening or the design year.

nonconforming road approach A road approach that does not meet current requirements for location, quantity, spacing, sight distance, or geometric elements.

nonrecoverable slope A slope on which an errant vehicle might continue until it reaches the bottom, without having the ability to recover control. Fill slopes steeper than 4H:1V, but not steeper than 3H:1V, are considered nonrecoverable.

nonseparated HOV lane An HOV lane that is adjacent to and operates in the same direction as the general-purpose lanes with unrestricted access between the HOV lane and the general-purpose lanes.

notice of appearance A form provided by WSDOT for anyone wanting to receive a copy of the findings and order and the adopted limited access plan (see Chapter 210).

notice of hearing (or hearing notice) A published advertisement that a public hearing will be held.

notice of opportunity for a hearing An advertised offer to hold a public hearing.

O

occupancy designation The minimum number of occupants required for a vehicle to use the HOV facility.

operating speed The speed at which drivers are observed operating their vehicles during free flow conditions.

order of hearing The official establishment of a hearing date by the Director & State Design Engineer, Development Division.

outer separation The area between the outside edge of traveled way for through traffic and the nearest edge of traveled way of a frontage road or collector-distributor (C-D) road.

overlapped displays Overlapped displays allow a traffic movement to operate with one or more nonconflicting phases. Most commonly, a minor street's exclusive right-turn phase is overlapped with the nonconflicting major street's left-turn phase. An overlapped display can be terminated after the parent phase (the main phase the overlap is associated with) terminates. An overlapped display programmed for two or more parent phases continues to display until all of the parent phases have terminated. An overlap is made up of two or more phases—not one phase controlling two movements.

P

painted nose The point where the main line and ramp lanes separate.

"pass-by" trips Pass-by trips are intermediate stops between an origin and a primary trip destination; for example, home to work, home to shopping.

passenger loading zone An area provided for pedestrians to board/disembark a vehicle.

passing lane An auxiliary lane on a two-lane highway used to provide the desired frequency of passing zones.

passing sight distance The distance (on a two-lane highway) needed for a vehicle driver to execute a normal passing maneuver based on design conditions and design speed.

pavement marking A colored marking applied to the pavement by spray, extrusion, adhesives, or glue to provide drivers with guidance and other information.

pavement marking beads ***Glass:*** Small glass spheres used in highway pavement markings to provide retroreflectivity. ***Composite:*** any non-glass bead intended to provide wet weather retroreflectivity.

pavement marking durability A measure of a pavement marking's resistance to wear and deterioration.

peak hour The 60-minute interval that contains the largest volume of traffic during a given time period. If a traffic count covers consecutive days, the peak hour can be an average of the highest hour across all of the days. An a.m. peak is simply the highest hour from the a.m., and the p.m. peak is the highest from the p.m. The peak hour correlates to the DHV, but is not the same. However, it is close enough on items such as intersection plans for approval to be considered equivalent.

performance-based decisions Decisions that are made based on performance, performance metrics, performance targets, and performance gaps. Also, decisions made using performance evaluation tools, such as Highway Safety Manual methodology for evaluating safety performance.

performance category Any broad area of performance important to an organization, project, or place. WSDOT's six performance categories: Economic Vitality, Preservation, Safety, Mobility, Environment, and Stewardship are a product of legislative policy.

performance evaluation tools Quantitative tools used to measure performance. Examples of these tools currently being used by WSDOT are *Highway Safety Manual* methodology (for safety performance) and *Highway Capacity Manual* (for mobility performance).

performance gap The difference between the measured and targeted performance unit for a performance metric. This gap is another way of describing the performance need(s) at a location.

performance metric Any measurable indicator used to assess the achievement of outcomes.

performance need See *baseline performance need* and *contextual performance need*

performance target(s) An outcome or desired state intended for a project. Performance targets are identified as either baseline or contextual (see Chapter 1101).

permit holder The abutting property owner or other legally authorized person to whom an access connection permit is issued by the permitting authority.

permitted access connection A connection for which an access connection permit has been issued by a permitting authority.

permitting authority The agency that has legal authority to issue managed access connection permits. For access connections in unincorporated areas, the permitting authority is WSDOT; for access connections within corporate limits, the permitting authority is a city or town.

physical nose The point, upstream of the gore, with a separation between the roadways of 16 to 22 feet (see Chapter 1360).

planning Transportation planning is a decision-making process required by federal and state law used to solve complex, interrelated transportation and land use problems.

Planning and Environmental Linkage (PEL) A collaborative and integrated approach to transportation decision-making that (1) considers environmental, community, and economic goals early in the planning process, and (2) uses the information, analysis, and products developed during planning to inform the environmental review process.

Plans, Specifications, and Estimates (PS&E) The project development activity that follows Project Definition and culminates in the completion of contract-ready documents and the engineer's cost estimate.

pole height (H1) The vertical distance from the light source to the pole base. This distance is specified in contracts and used by the pole manufacturers to fabricate the light standard.

policy point There are eight policy points addressed in the IJR:

- Need for the Access Point Revision
- Reasonable Alternatives
- Operational & Crash Analyses
- Access Connections & Design
- Land Use & Transportation Plans
- Future Interchanges
- Coordination
- Environmental Processes

portable traffic signal A type of conventional traffic signal used in work zones to control traffic. This signal is most commonly used on two-way two-lane highways where one lane has been closed for roadwork. This signal is most commonly operated in pairs, with one signal at each end of the work zone. This eliminates the need for 24-hour flagger control. The traffic signal provides alternating right of way assignments for conflicting traffic movements. The signal has an adjustable vertical support with two three-section signal displays and is mounted on a mobile trailer with its own power source.

positive illumination Lighting the surface of the object as the driver views it.

posted speed The maximum legal speed as posted on a section of highway using regulatory signs.

Practical Design/Practical Solutions An approach to making project decisions that focuses on the specific problem the project is intended to address. This performance-based approach looks for lower cost solutions that meet outcomes that WSDOT, partnering agencies, communities and stakeholders have identified. Practical design is a fundamental component to the vision, mission, values, goals, and reforms identified in Results WSDOT- WSDOT's Strategic Plan. With practical solutions, decision-making focuses on maximum benefit to the system, rather than maximum benefit to the project. Focusing on the specific project need minimizes the scope of work for each project so that system-wide needs can be optimized.

prehearing packet A concise, organized collection of all necessary prehearing data, prepared by the region and approved by the HQ Access and Hearings Section Manager prior to the hearing (see Chapter 210).

preliminary engineering (PE) A term used to describe the Project Delivery process from project scoping through PS&E review.

principal arterial system A connected network of rural arterial routes with appropriate extensions into and through urban areas, including routes designated as part of the Interstate System, that serves corridor movements with travel characteristics indicative of substantial statewide and interstate travel (RCW 47.05.021).

priority array A collection of similar needs identified in the HSP, prioritized based on the methodology adopted by WSDOT to meet the requirements of RCW 47.05.

Priority Array Tracking System (PATS) A database that allows tracking of highway needs and their solutions. The system is designed to ensure WSDOT addresses the highest-ranked transportation needs. Deficiencies are tracked for each strategy in the HSP.

product or service Any element of a project from concept through maintenance and operation. In all instances, the required function should be achieved at the lowest life cycle cost based on requirements for performance, maintainability, safety, environment, and aesthetics.

project The Project Management Institute defines a project to be "a temporary endeavor undertaken to create a unique product or service."

Project Change Request Form A form used to document and approve revisions to project scope, schedule, or budget from a previously approved Project Definition (see Project Summary). Include copies in the Design Documentation Package.

Project Control and Reporting (PC&R) The Headquarters (HQ) Project Control and Reporting Office is responsible for monitoring, tracking, and reporting delivery of the Highway Construction Program in coordination with the Program Management offices in each of the six WSDOT regions and the Urban Corridors Office.

Project Definition (see *Project Summary*)

Project Development Approval Final approval of all project development documents by the designated representative of the approving organization prior to the advertisement of a capital transportation project (see Chapter 300).

Project Engineer This term applies to WSDOT personnel. Wherever “Project Engineer” appears in this manual, the design-builder shall deem it to mean “Engineer of Record.”

Project File (PF) A file containing all documentation and data for all activities related to a project (see Chapter 300).

- ***Design Documentation Package (DDP)*** The portion of the Project File, including Design Approval and Project Development Approval that will be retained long term in accordance with WSDOT document retention policies. Depending on the scope of the project, it contains the Project Summary and some or all of the other documents discussed in Chapter 300. Technical reports and calculations are part of the Project File, but they are not designated as components of the DDP. Include estimates and justifications for decisions made in the DDP (see Chapter 300). The DDP explains how and why the design was chosen and documents approvals.

project management plan A formal, approved document that defines how the project is executed, monitored, and controlled. It may be in summary or detailed form and may be composed of one or more subsidiary management plans and other work planning documents. For further information, see the Project Management Guide: http://www.wsdot.wa.gov/Projects/ProjectMgmt/OnlineGuide/ProjectManagementOnlineGuide.htm

project need statement A statement identifying the baseline performance need for the project. For each identified project need, there may be one or more performance metrics, targets, and gaps.

Project Scoping See *scoping phase*.

Project Summary A set of documents consisting of the, Environmental Review Summary (ERS), and Project Definition (PD). The Project Summary is part of the design documentation required to obtain Design Approval and is ultimately part of the design documentation required for Project Development Approval (see Chapter 300).

- ***Environmental Review Summary (ERS)*** A document that records the environmental classification (class of action) and considerations (consequences of action) for a specific project.
- ***Project Definition (PD)*** A document that records the purpose and need of the project, along with program level and design constraints.

Projects of Division Interest (PoDIs) A primary set of projects for which FHWA determines the need to exercise oversight and approval authority, as described in Chapter 300.

proposal The combination of projects/actions selected through the study process to meet a specific transportation system need.

public art An enhancement to a functional element, feature, or place within a transportation facility to provide visual interest. The enhancement could be an addition to a functional element, integrated into a design, or for purely aesthetic purposes. An element is considered “public art” if it is beyond WSDOT standard practice for architectural treatment.

public involvement plan A plan to collaboratively involve the public in decision making, tailored to the specific needs and conditions of a project and the people and communities it serves. It is often part of a broader communications plan.

public transportation Passenger transportation services available to the public, including buses, ferries, rideshare, and rail transit.

purpose General project goals such as improve safety, enhance mobility, or enhance economic development.

Q

Quality of Service (QOS) Defined by the *Highway Capacity Manual* or by agreement. Intended to describe how well a facility or service operates or functions from the perspective of the user.

quantitative safety analysis An analysis that relies on science-based modeling associated with safety, and utilizes quantitative tools.

quantitative tools Tools used to measure performance. Examples of tools currently being used by WSDOT are:

- *Highway Safety Manual* methodology (for safety performance)
  - Safety Analyst Toolset
  - ISATe
  - IHSDM
  - HSM Enhanced Spread Sheets
  - See also http://wwwi.wsdot.wa.gov/RiskManagement/SHS/SafetyTools.htm
- *Highway Capacity Manual* (for mobility performance)

queue cutter traffic signal A traffic signal used at highway-rail grade crossings where the queue from a downstream traffic signal is expected to extend within the Minimum Track Clearance Distance. It is used to keep vehicles from an adjacent signalized intersection from queuing on the railroad tracks.

R

ramp connection The pavement at the end of a ramp, connecting to a main lane of a roadway.

ramp (in relation to a *roadway*) A short roadway connecting a main lane of a highway with another facility, such as a road, parking lot, or transit stop, for vehicular use.

ramp meter A traffic signal at a freeway entrance ramp that allows a measured or regulated amount of traffic to enter the freeway.

ramp terminal An intersection at the end of a ramp.

Record of Decision (ROD) Under the National Environmental Policy Act, the Record of Decision accompanies the Final Environmental Impact Statement; explains the reasons for the project decision; discusses alternatives and values considered in selection of the preferred alternative; and summarizes mitigation measures and commitments that will be incorporated in the project.

recoverable slope A slope on which the driver of an errant vehicle can regain control of the vehicle. Slopes of 4H:1V or flatter are considered recoverable.

recovery area The minimum target value used in highway design when a fill slope between 4H:1V and 3H:1V starts within the Design Clear Zone.

Recreational Vehicle Account In 1980 the RV account was established for use by the department of transportation for the construction, maintenance, and operation of recreational vehicle sanitary disposal

systems at safety rest areas (RCW 46.68.170). A recreational vehicle sanitary disposal fee is required for registration of a recreational vehicle (RCW 46.17.375). Adjustments to the recreational vehicle fee by the department of transportation may be implemented after consultation with the citizens' representatives of the recreational vehicle user community (RCW 47.01.460).

Regional Transportation Planning Organization (RTPO) A planning organization authorized by the Legislature in 1990 as part of the Growth Management Act. The RTPO is a voluntary organization with representatives from state and local governments that are responsible for coordinating transportation planning activities within a region.

relocation assistance program A program that establishes uniform procedures for relocation assistance that will ensure legal entitlements and provide fair, equitable, and consistent treatment to persons displaced by WSDOT-administered projects, as defined in the *Right of Way Manual*.

Request for Proposal (RFP) The document package issued by WSDOT requesting submittal of proposals for the project and providing information relevant to the preparation and submittal of proposals, including the instructions to proposers, contract documents, bidding procedures, and reference documents.

rest area An area to the side of a path.

résumé An official notification of action taken by WSDOT following adoption of a findings and order (see Chapter 210).

retroreflection The phenomenon of light rays striking a surface and being returned directly back to the source of light.

Retroreflection, coefficient of (R_L) A measure of retroreflection.

retroreflectometer An instrument used to measure retroreflectivity.

right-hook Potential intersection conflicts between motor vehicles making a right turn and the bicycle through movement.

right of way (R/W) A general term denoting land or interest therein, acquired for or designated for transportation purposes. More specifically, lands that have been dedicated for public transportation purposes or land in which WSDOT, a county, or a municipality owns the fee simple title, has an easement devoted to or required for use as a public road/street and appurtenant facilities, or has established ownership by prescriptive right.

right of way and limited access plan (R/W and L/A plan) A right of way plan that also shows limited access control details.

road approach An access point, other than a public road/street, that allows access to or from a limited access highway on the state highway system.

roadside park A roadside user facility for safe vehicular parking off the traveled way and separated from the highway by some form of buffer. These sites might be equipped with features or elements such

as points of interest, picnic tables, and/or vault toilet buildings. Unlike a safety rest area, a roadside park does not always provide a permanent restroom building.

roadway The portion of a highway, including shoulders.

roadway luminance The light projected from a luminaire that travels toward a given area, represented by a point on the pavement surface, and then back toward the observer, opposite to the direction of travel. The units of roadway luminance are footcandles.

roundabout A circular intersection at grade with yield control of all entering traffic, channelized approaches with raised splitter islands, counter-clockwise circulation, and appropriate geometric curvature to force travel speeds on the circulating roadway generally to less than 25 mph.

rumble strips Rumble strips are grooves or rows of raised pavement markers placed perpendicular to the direction of travel to alert inattentive drivers.

S

Safety Analyst A program developed to implement the *Highway Safety Manual* methodology

safety rest area (SRA) A roadside facility equipped with permanent restroom building(s), a parking area, picnic tables, refuse receptacles, illumination, and other ancillary services. SRAs typically include potable water and might include traveler information and telephones.

Safety Rest Area Strategic Plan Developed in 2008 under a stakeholder-coordinated effort of executive and advisory team members, this plan provides guidance for current and future management of the SRA program.

sawtooth berth A series of bays that are offset from one another by connecting curb lines, constructed at an angle from the bus bays. This configuration minimizes the amount of space needed for vehicle pull in and pull out.

scoping phase An initial phase of project development for a specific project. The scoping phase precedes the design and/or preliminary engineering phase and is intended to support priority programing and budget building scenarios. The *Project Summary* is the documentation developed during this phase.

security lighting A minimal amount of lighting used to illuminate areas for public safety or theft reduction. Security lighting for walkways is the lighting of areas where shadows and horizontal and vertical geometry obstruct a pedestrian's view.

"select zone" analysis A traffic model run, where the related project trips are distributed and assigned along a populated highway network. This analysis isolates the anticipated impact on the state highway network created by the project.

separated HOV facility An HOV roadway that is physically separated from adjacent general-purpose lanes by a barrier or median, or is on a separate right of way.

shared roadway A roadway that is open to both bicycle and motor vehicle travel. This may be a new or existing roadway/highway, a street with wide curb lanes, or a road with paved shoulders.

shared-use landing A level (0 to 2% grade cross slope and running slope) paved area within the shared-use path, designed to provide turning and maneuvering space for wheelchair users and as a resting place for pedestrians.

shared-use path A facility physically separated from motorized vehicular traffic within the highway right of way or on an exclusive right of way with minimal crossflow by motor vehicles. Shared-use paths are primarily used by bicyclists and pedestrians, including joggers, skaters, and pedestrians with disabilities, including those who use nonmotorized or motorized wheeled mobility devices. With appropriate design considerations, equestrians may also be accommodated by a shared-use path facility.

short tunnel A tunnel, lid, or underpass that is shorter than 80' in length and has a length to vertical clearance ratio of 10:1 or less.

shoulder The portion of the roadway contiguous with the traveled way, primarily for accommodation of stopped vehicles, emergency use, lateral support of the traveled way, and where allowed, use by pedestrians and bicycles.

shoulder width The lateral dimension of the shoulder, measured from the edge of traveled way to the edge of roadway or the face of curb.

sight distance The length of highway visible to a driver.

SIgnal Maintenance Management System (SIMMS) A database used for traffic signals, illumination, and Intelligent Transportation Systems (ITS). SIMMS is used to establish an inventory base, enter work reports, print timesheets, and store maintenance records for electrical/electronics systems within WSDOT right of way.

signed shared roadway A shared roadway that has been designated by signing as a route for bicycle use.

single-lane roundabout A roundabout having single-lane entries at all legs and one circulating lane.

single-occupant vehicle (SOV) Any motor vehicle other than a motorcycle carrying one occupant.

site Parcel(s) of land bounded by a property line or a designated portion of a public right of way.

site design Style and configuration of the built environment or parcel(s).

slip base A mechanical base designed to allow the light standard to break away from the fixed foundation when hit by a vehicle traveling at the design speed and traveling at a departure angle less than or equal to the design departure angle.

slip lane A lane that separates heavy right-turn movements from the roundabout circulating traffic (see Chapter 1320).

slip ramp A connection between legs of an intersection that allows right-turning vehicles to bypass the intersection or a connection between an expressway and a parallel frontage road. These are often separated by an island.

slow-moving vehicle turnout A shoulder area widened to provide room for a slow-moving vehicle to pull out of the through traffic, allow vehicles to pass, and then return to the through lane.

speed The operations or target or posted speed of a roadway. There are three classifications of speed established:

- ***Low speed*** is considered 35 mph and below.
- ***Intermediate speed*** is considered 40-45 mph.
- ***High speed*** is considered 50 mph and above.

speed limit sign beacon A beacon installed with a fixed or variable speed limit sign. The preferred display is two flashing yellow indications.

speed management An engineered effort to achieve a targeted speed.

speed transition segment An engineered segment of road intended to lower the operating speed between contexts with different target speeds.

splitter island The raised island at each two-way leg between entering and exiting vehicles, designed primarily to control the entry and exit speeds by providing deflection. They also discourage wrong-way movements, and provide pedestrian refuge.

state highway system All roads, streets, and highways designated as state routes in compliance with RCW 47.17.

Statewide Transportation Improvement Program (STIP) A planning document that includes all federally funded projects and other regionally significant projects for a three-year period.

static scale A scale that requires a vehicle to stop for weighing.

stopping sight distance The distance needed for a driver to stop a vehicle traveling at design speed based on design conditions.

stop sign beacon A beacon installed above a stop sign. The display is a flashing red indication.

streetside The portion of the public right of way dedicated to the pedestrian thoroughfare and supporting the accessibility, activities and functions of the local land use. The streetside is comprised of a frontage zone, pedestrian zone, furnishing zone and parking zone (see Chapter 1238). Note some local agencies may divide the streetside zone.

study area The transportation system area to study in the study process and for an IJR. The study area is a minimum of one interchange upstream and downstream from the proposal. The study area shall also include the intersecting roadway in the area to the extent necessary to ensure its ability to collect and distribute traffic to and from the interchange. The study area should be expanded as necessary to

capture operational impacts of adjacent interchanges in the vicinity that are, or will be, bottlenecks or chokepoints that influence the operations of the study interchange.

study plan A term associated with environmental procedures, this plan proposes an outline or "road map" of the environmental process to be followed during the development of a project that requires complex NEPA documentation (see Chapter 210 and the *Environmental Manual*).

subject matter expert A person who is an authority in a particular area or topic, and understands the data and the limitations on the use and application of the data.

superelevation The rotation of the roadway cross section in such a manner as to overcome part of the centrifugal force that acts on a vehicle traversing a curve.

superelevation runoff The length of highway needed to accomplish the change in cross slope from a section with adverse crown removed (level) to a fully superelevated section, or vice versa.

superelevation transition length The length of highway needed to change the cross slope from normal crown or normal pavement slope to full superelevation.

support team An integral part of the IJR process consisting of an assemblage of people from the regions, FHWA (for Interstates), WSDOT HQ Access and Hearings, and other representatives organized to develop and analyze alternatives to meet the need of a proposal, including approval authorities.

Surface Transportation Program (STP) A federal program established by Congress in 1991 that provides a source of federal funding for highway and bridge projects.

T

tangent runout The length of highway needed to change the cross slope from normal crown to a section with adverse crown removed (level).

target speed A proactive approach to establishing a speed consistent with the context characteristics. Target speed is the design operating speed, which aligns design, posted and operating speed as the same value.

team management The direction of a group of individuals that work as a unit. Effective teams are results-oriented and are committed to project objectives, goals and strategies.

temporary traffic signal A conventional traffic signal used during construction to control traffic at an intersection while a permanent signal system is being constructed. A temporary traffic signal is typically an inexpensive span-wire installation using timber strain poles.

Total Project Costs The costs of all phases of a project, including environmental, design, right of way, utilities, and construction.

tradeoffs analysis An analysis method for balancing factors, performance or outcomes, which are not attainable at the same time.

traffic barrier A longitudinal barrier, including bridge rail or an impact attenuator, used to redirect vehicles from fixed features located within an established Design Clear Zone, help mitigate median crossovers, reduce the potential for errant vehicles to travel over the side of a bridge structure, or (occasionally) protect workers, pedestrians, or bicyclists from vehicular traffic.

traffic barrier/longitudinal barrier A device oriented parallel or nearly parallel to the roadway whose primary function is to contain or safely redirect errant vehicles away from fixed features or to (occasionally) protect workers, pedestrians, or bicyclists from vehicular traffic. Beam guardrail, cable barrier, bridge rail, concrete barrier, and impact attenuators are barriers, and they are categorized as rigid, rigid anchored, unrestrained rigid, semirigid, and flexible. They can be installed as roadside or median barriers.

traffic calming treatments Treatments along the roadway that can be used to reduce speeds through a section of roadway (see Chapter 1103).

Traffic Impact Analysis (TIA) (sometimes called *Traffic Impact Study (TIS)*) If a traffic analysis is not an IJR, it is a TIA. TIAs are used for environmental reviews and developer projects (see Chapter 320).

traffic paint A pavement marking material that consists mainly of a binder and a carrier. The carrier is kept in liquid form, which evaporates upon application to the pavement, leaving the binder to form a hard film.

transit A general term applied to passenger rail and bus service used by the public.

transit facility A capital facility that improves the efficiency of public transportation or encourages the use of public transportation.

transit flyer stop A multimodal connection located within the boundaries of a limited access facility.

transition A section of barrier used to produce the gradual stiffening of a flexible or semirigid barrier as it connects to a more rigid barrier or fixed object.

transit lane A lane for the exclusive use of transit vehicles.

transit stop A facility for loading and unloading passengers that is set aside for the use of transit vehicles only.

transit vehicle A bus or other motor vehicle that provides public transportation (usually operated by a public agency).

Transportation Improvement Program (TIP) A three-year transportation improvement strategy required from MPOs by Congress, which includes all federally funded or regionally significant projects.

Transportation Information and Planning Support (TRIPS) A mainframe computer system designed to provide engineering, maintenance, planning, and accounting staff with highway inventory, traffic, and accident data.

Transportation Management Area (TMA) Urbanized areas with populations of 200,000 or greater are federally designated as Transportation Management Areas.

transportation management plan (TMP) A set of traffic control plans, transportation operations plans, and public information strategies for managing the work zone impacts of a project. A TMP is required for all projects to address work zone safety and mobility impacts.

Transportation Planning Studies These studies identify the current functions of a corridor and forecast future demands on the system. Data collection and public involvement are used to forecast future needs that will improve the function of a state route.

travel demand The demand travelers will make on the system based on the number and types of trips they will take and the mode and routes they will use. Local travel demand represents short trips that should be made on the local transportation system, such as intracity roads and streets. Regional travel demand represents long trips that are made on the regional transportation system, such as Interstate, regional, and/or intercity/interregional roads, streets, or highways.

traveled way The portion of the roadway intended for the movement of vehicles, exclusive of shoulders and lanes for parking, turning, and storage for turning.

traveled way zone The portion of the roadway intended for the movement of people and goods, exclusive of shoulders, roadsides, on-street parking, medians and streetside zones.

traveler information Commercial and noncommercial information that informs and orients the traveling public. This includes access information for food, gas, lodging, local attractions, regional tourist attractions, roadway conditions, and construction schedules.

traveling public Motorists, motorcyclists, bicyclists, pedestrians, and pedestrians with disabilities.

trips Short trips are normally local. Long trips are normally interstate, regional, or interregional.

truck apron The optional mountable portion of the central island of a roundabout between the raised nontraversable area of the central island and the circulating roadway (see Chapter 1320).

turning radius The radius that the front wheel of the intersection design vehicle on the outside of the curve travels while making a turn (see Chapter 1320).

turning roadway A curve on an open highway, a ramp, or the connecting portion of the roadway between two intersecting legs of an intersection.

two-way left-turn lane (TWLTL) A lane, located between opposing lanes of traffic, to be used by vehicles making left turns from either direction, from or onto the roadway.

U

undivided multilane A roadway with two or more through lanes in each direction on which left turns are not controlled.

uniformity ratio The ratio of the minimum average light level on the design area to the minimum light level of the same area (see Chapter 1040).

urban area An area designated by the Washington State Department of Transportation (WSDOT) in cooperation with the Transportation Improvement Board (TIB) and Regional Transportation Planning Organizations (RTPO), subject to the approval of the Federal Highway Administration (FHWA).

urbanized area An urban area with a population of 50,000 or more.

usable shoulder The width of the shoulder that can be used by a vehicle for stopping.

V

validation A process to confirm the reasonableness, accuracy and completeness of estimated costs and quantities.

Value Engineering (VE) Analysis A systematic approach to identifying and removing unnecessary costs which do not contribute to a desired result by analyzing cost versus function.

Value Engineering Change Proposal (VECP) A construction contract change proposal submitted by the construction contractor based on a VECP provision in the contract. The intent of these types of proposals is to (1) improve the project's performance, value, and/or quality, (2) lower construction costs, or (3) shorten the delivery time, while considering their impacts on the project's overall life-cycle cost and other applicable factors.

Value Engineering (VE) Job Plan A systematic and structured action plan (see Chapter 310) for conducting and documenting the results of the VE analysis. While each VE analysis shall address each phase in the VE Job Plan, the level of analysis conducted and effort expended for each phase should be scaled to meet the needs of each individual project. The WSDOT VE analysis uses the Seven-Phase Job Plan shown in Exhibit 310-1.

veiling luminance The stray light produced within the eye by light sources produces a veiling luminance that is superimposed on the retinal image of the objects being observed. This stray light alters the apparent brightness of an object within the visual field and the background against which it is viewed, thereby impairing the ability of the driver to perform visual tasks. Conceptually, veiling luminance is the light that travels directly from the luminaire to the observer’s eye.

viewpoint A roadside stopping opportunity with a view of some point of interest or area scenery. This area is not typically separated from the traveled way by some form of highway buffer.

violation rate The total number of violators divided by the total number of vehicles on an HOV facility.

visioning exercises a process of determining the goals for a facility or place.

Visitor Information Center (VIC) A staffed or nonstaffed booth or separate building that displays and dispenses free tourist travel maps and brochures. These are typically located at border-entry SRAs to provide travel information to highway users as they enter the state.

W

warning beacon A beacon that supplements a warning or regulatory sign or marking. The display is a flashing yellow indication. These beacons are not used with STOP, YIELD, or DO NOT ENTER signs or at intersections that control two or more lanes of travel. A warning identification beacon is energized only during those times when the warning or regulation is in effect.

warrant A minimum condition for which an action is authorized. Meeting a warrant does not attest to the existence of a condition that needs attention. Further justification is required.

Washington State Pavement Management System (WSPMS) A computer system that stores data about the pavement condition of all the highways in the state. Information available includes the latest field review and past contracts for every main line mile of state highway. Calculations are used to determine whether a given section of pavement is a past due, due, or future due preservation need.

Washington Transportation Plan (WTP) A WSDOT planning document developed in coordination with local governments, regional agencies, and private transportation providers. The WTP addresses the future of transportation facilities owned and operated by the state as well as those the state does not own but in which it has an interest. It identifies needed transportation investments, which are defined by service objectives and specific desired outcomes for each transportation mode.

weaving section A length of highway over which one-way traffic streams cross by merging and diverging maneuvers.

weigh in motion (WIM) A scale facility capable of weighing a vehicle without the vehicle stopping.

wet film thickness Thickness of a pavement marking at the time of application without beads.

work zone An area of a highway with construction, maintenance, or utility work activities. A work zone is identified by the placement of temporary traffic control devices that may include signs, channelizing devices, barriers, pavement markings, and/or work vehicles with warning lights. It extends from the first warning sign or high-intensity rotating, flashing, oscillating, or strobe lights on a vehicle to the END ROAD WORK sign or the last temporary traffic control device (MUTCD).

work zone impact Highway construction, maintenance, or utility work operations in the traveled way, adjacent to the traveled way, or within the highway's right of way that creates safety and mobility concerns for workers or the traveling public.

work zone traffic control The planning, design, and preparation of contract documents for the modification of traffic patterns due to work zone impacts.

wye (Y) connection An intersecting one-way roadway, intersecting at an angle less than 60°, in the general form of a "Y."

Y

yield-at-entry The requirement that vehicles on all entry lanes yield to vehicles within the circulating roadway.

yield point The point at which entering traffic must yield to circulating traffic before entering the circulating roadway (see Chapter 1320).