

Chapter 1	General Information	1-1
1.1	Manual Description	1-1
1.1.1	Purpose	1-1
1.1.2	Specifications	1-2
1.1.3	Format	1-2
1.1.4	Revisions	1-4
1.1.5	Design Memorandums	1-4
1.2	Bridge and Structures Office Organization	1-5
1.2.1	General	1-5
1.2.2	Organizational Elements of the Bridge Office	1-5
1.2.3	Unit Responsibilities and Expertise	1-10
1.3	Roles, Responsibilities and Procedures	1-11
1.3.1	General	1-11
1.3.2	General Design Procedures	1-11
1.3.3	Design/Check Calculation File	1-20
1.3.4	PS&E Review Period	1-22
1.3.5	Addenda	1-22
1.3.6	Construction Support	1-23
1.3.7	Vacant	1-27
1.3.8	Archiving Design Calculations, Job Files, and S&E Files	1-28
1.3.9	Public Disclosure Policy Regarding Bridge Plans	1-31
1.3.10	Use of Computer Software	1-31
1.4	Quality Control/Quality Assurance/Quality Verification (QC/QA/QV) Procedures	1-32
1.4.1	General	1-32
1.4.2	WSDOT Prepared Bridge (or Structure) Preliminary Plans	1-32
1.4.3	WSDOT Prepared PS&E	1-33
1.4.4	Consultant Prepared PS&E/Preliminary Plans on WSDOT Right of Way	1-39
1.4.5	Structural Design Work Prepared Under Design-Build Method of Project Delivery	1-40
1.5	Bridge Design Scheduling	1-41
1.5.1	General	1-41
1.5.2	Preliminary Design Schedule	1-42
1.5.3	Final Design Schedule	1-42
1.6	Guidelines for Bridge Site Visits	1-45
1.6.1	Existing Structure Modifications	1-45
1.6.2	New Structures	1-46
1.6.3	Structure Demolition	1-46
1.7	Appendices	1-47
Appendix 1.1-A1	Bridge Design Manual Revision QC/QA Worksheet	1-48
Appendix 1.2-A1	Bridge & Structures Design Office Workflow	1-49
Appendix 1.3-A1	Bridge & Structures Design Calculations	1-50
Appendix 1.4-A1	QC/QA Signature Sheet	1-51
1.99	References	1-52

Chapter 2	Preliminary Design	2-1
2.1	Preliminary Studies	2-1
2.2	Preliminary Plan	2-8
2.2.1	Development of the Preliminary Plan	2-8
2.3	Preliminary Plan Criteria	2-21
2.3.1	Highway Crossings	2-21
2.3.2	Railroad Crossings	2-25
2.3.3	Water Crossings	2-28
2.3.4	Bridge Widening	2-30
2.3.5	Temporary Bridges	2-31
2.3.6	Retaining Walls and Noise Walls	2-32
2.3.7	Bridge Deck Drainage	2-32
2.3.8	Bridge Deck Protection Systems	2-32
2.3.9	Construction Clearances	2-32
2.3.10	Design Guides for Falsework Depth Requirements	2-33
2.3.11	Inspection and Maintenance Access	2-35
2.4	Selection of Structure Type	2-37
2.5	Aesthetic Considerations	2-46
2.6	Miscellaneous	2-49
2.7	WSDOT Standards for Highway Bridges	2-50
2.7.1	Design Elements	2-50
2.7.2	Detailing the Preliminary Plan	2-52
2.8	Bridge Security	2-53
2.8.1	General	2-53
2.8.2	Design	2-53
2.8.3	Design Criteria	2-54
2.9	Bridge Standard Drawings	2-56
2.10	Appendices	2-57
Appendix 2.2-A1	Bridge Site Data General	2-58
Appendix 2.2-A2	Structure Site Data Rehabilitation	2-59
Appendix 2.2-A3	Structure Site Data Stream Crossings	2-60
Appendix 2.2-A4	Preliminary Plan Checklist	2-61
Appendix 2.2-A5	Request For Geotechnical & Hydraulic Information for Bridge Preliminary Plan	2-63
2.99	References	2-64

Chapter 3	Loads	3-1
3.1	Scope	3-1
3.2	Definitions	3-2
3.3	Load Designations	3-3
3.4	Limit States	3-4
3.5	Load Factors and Load Combinations	3-5
3.5.1	Load Factors for Substructure.	3-6
3.6	Loads and Load Factors for Construction	3-7
3.7	Load Factors for Post-tensioning	3-8
3.7.1	Post-tensioning Effects from Superstructure	3-8
3.7.2	Secondary Forces from Post-tensioning, PS	3-8
3.8	Permanent Loads	3-9
3.8.1	Deck Overlay Requirement.	3-9
3.9	Live Loads	3-10
3.9.1	Design Live Load	3-10
3.9.2	Loading for Live Load Deflection Evaluation.	3-10
3.9.3	Distribution to Superstructure	3-10
3.9.4	Bridge Load Rating	3-12
3.10	Pedestrian Loads	3-13
3.11	Wind Loads	3-14
3.11.1	Wind Load to Superstructure	3-14
3.11.2	Wind Load to Substructure.	3-14
3.11.3	Wind on Noise Walls	3-14
3.12	Loads on Buried Structures	3-15
3.13	Earthquake Effects	3-16
3.14	Earth Pressure	3-17
3.15	Force Effects Due to Superimposed Deformations.	3-18
3.16	Other Loads.	3-19
3.16.1	Buoyancy	3-19
3.16.2	Collision Force on Bridge Substructure.	3-19
3.16.3	Collision Force on Traffic Barrier.	3-19
3.16.4	Force from Stream Current, Floating Ice, and Drift.	3-19
3.16.5	Ice Load	3-19
3.16.6	Uniform Temperature Load.	3-19
3.16.7	Vehicular Collision Force: CT	3-19
3.99	References	3-22

Chapter 4	Seismic Design and Retrofit	4-1
4.1	General	4-1
4.1.1	Expected Bridge Seismic Performance	4-2
4.1.2	Expected Post-earthquake Service Levels	4-2
4.1.3	Expected Post-earthquake Damage States	4-3
4.2	WSDOT Additions and Modifications to AASHTO Guide Specifications for LRFD Seismic Bridge Design (SEISMIC)	4-4
4.2.1	Definitions	4-4
4.2.2	Earthquake Resisting Systems (ERS) Requirements for Seismic Design Categories (SDCs) C and D	4-4
4.2.3	Seismic Ground Shaking Hazard	4-9
4.2.4	Selection of Seismic Design Category (SDC)	4-11
4.2.5	Temporary and Staged Construction	4-11
4.2.6	Load and Resistance Factors	4-12
4.2.7	Balanced Stiffness Requirements and Balanced Frame Geometry Recommendation	4-12
4.2.8	Selection of Analysis Procedure to Determine Seismic Demand	4-12
4.2.9	Member Ductility Requirement for SDCs C and D	4-12
4.2.10	Longitudinal Restraints	4-12
4.2.11	Abutments	4-13
4.2.12	Foundation – General	4-18
4.2.13	Foundation – Spread Footing	4-18
4.2.14	Procedure 3: Nonlinear Time History Method	4-18
4.2.15	I_{eff} for Box Girder Superstructure	4-18
4.2.16	Foundation Rocking	4-18
4.2.17	Drilled Shafts	4-18
4.2.18	Longitudinal Direction Requirements	4-19
4.2.19	Liquefaction Design Requirements	4-19
4.2.20	Reinforcing Steel	4-19
4.2.21	Concrete Modeling	4-20
4.2.22	Expected Nominal Moment Capacity	4-20
4.2.23	Interlocking Bar Size	4-20
4.2.24	Splicing of Longitudinal Reinforcement in Columns Subject to Ductility Demands for SDCs C and D	4-20
4.2.25	Development Length for Column Bars Extended into Oversized Pile Shafts for SDCs C and D	4-20
4.2.26	Lateral Confinement for Oversized Pile Shaft for SDCs C and D	4-20
4.2.27	Lateral Confinement for Non-Oversized Strengthened Pile Shaft for SDCs C and D	4-21
4.2.28	Requirements for Capacity Protected Members	4-21
4.2.29	Superstructure Capacity Design for Transverse Direction (Integral Bent Cap) for SDCs C and D	4-21
4.2.30	Superstructure Design for Non Integral Bent Caps for SDCs B, C, and D	4-22
4.2.31	Joint Proportioning	4-22
4.2.32	Cast-in-Place and Precast Concrete Piles	4-22
4.2.33	Seismic Resiliency using Innovative Materials and Construction	4-22

4.3	Seismic Design Requirements for Bridge Modifications and Widening Projects	4-23
4.3.1	General	4-23
4.3.2	Bridge Widening Project Classification	4-23
4.3.3	Seismic Design Requirements Bridge Widening Projects	4-24
4.3.4	Scoping for Bridge Widening and Liquefaction Mitigation	4-26
4.3.5	Design and Detailing Considerations	4-27
4.4	Seismic Retrofitting of Existing Ordinary Bridges	4-29
4.4.1	Seismic Analysis Requirements	4-29
4.4.2	Seismic Retrofit Design	4-30
4.4.3	Computer Analysis Verification	4-30
4.4.4	Earthquake Restrainers	4-30
4.4.5	Isolation Bearings	4-31
4.5	Seismic Design Requirements for Retaining Walls and Buried Structure	4-32
4.5.1	Seismic Design of Retaining Walls	4-32
4.5.2	Seismic Design of Buried Structure	4-32
4.6	Appendices	4-33
Appendix 4-B1	Design Examples of Seismic Retrofits of Ordinary Bridges	4-34
Appendix 4-B2	SAP2000 Seismic Analysis Example	4-39
4.99	References	4-122

Chapter 5	Concrete Structures	5-1
5.0	General	5-1
5.1	Materials	5-2
5.1.1	Concrete	5-2
5.1.2	Reinforcing Steel	5-9
5.1.3	Prestressing Steel	5-16
5.1.4	Prestress Losses	5-24
5.1.5	Prestressing Anchorage Systems	5-28
5.1.6	Post-Tensioning Ducts	5-28
5.2	Design Considerations	5-29
5.2.1	Service and Fatigue Limit States	5-29
5.2.2	Strength-Limit State	5-31
5.2.3	Strut-and-Tie Model	5-35
5.2.4	Deflection and Camber	5-35
5.2.5	Construction Joints	5-38
5.2.6	Inspection Access and Lighting	5-39
5.3	Reinforced Concrete Box Girder Bridges	5-42
5.3.1	Box Girder Basic Geometries	5-42
5.3.2	Reinforcement	5-47
5.3.3	Crossbeam	5-55
5.3.4	End Diaphragm	5-58
5.3.5	Dead Load Deflection and Camber	5-61
5.3.6	Thermal Effects	5-61
5.3.7	Hinges	5-62
5.3.8	Drain Holes	5-62
5.4	Hinges and Inverted T-Beam Pier Caps	5-64
5.5	Bridge Widening	5-66
5.5.1	Review of Existing Structures	5-66
5.5.2	Analysis and Design Criteria	5-67
5.5.3	Removing Portions of the Existing Structure	5-71
5.5.4	Attachment of Widening to Existing Structure	5-72
5.5.5	Expansion Joints	5-84
5.5.6	Possible Future Widening for Current Designs	5-85
5.5.7	Bridge Widening Falsework	5-85
5.5.8	Existing Bridge Widening	5-85
5.6	Prestressed Concrete Girder Superstructures	5-86
5.6.1	WSDOT Standard Prestressed Concrete Girder Types	5-86
5.6.2	Design Criteria	5-89
5.6.3	Fabrication and Handling	5-103
5.6.4	Superstructure Optimization	5-108
5.6.5	Repair of Damaged Prestressed Concrete Girders at Fabrication	5-114
5.6.6	Repair of Damaged Prestressed Concrete Girders in Existing Bridges	5-114
5.6.7	Deck Girders	5-121
5.6.8	Prestressed Concrete Tub Girders	5-124
5.6.9	Prestressed Concrete Girder Checking Requirement	5-125
5.6.10	Review of Shop Plans for Pre-tensioned Girders	5-125

5.7	Bridge Decks	5-126
5.7.1	Bridge Deck Requirements	5-126
5.7.2	Bridge Deck Reinforcement	5-128
5.7.3	Stay-In-Place Deck Panels	5-132
5.7.4	Bridge Deck Protection Systems	5-133
5.7.5	HMA Paving on Bridge Decks	5-140
5.8	Cast-in-place Post-Tensioned Bridges	5-146
5.8.1	Design Parameters	5-146
5.8.2	Analysis	5-154
5.8.3	Post-tensioning	5-156
5.8.4	Shear and Anchorages	5-161
5.8.5	Temperature Effects	5-162
5.8.6	Construction	5-163
5.8.7	Post-tensioning Notes – Cast-in-place Girders	5-166
5.9	Spliced Prestressed Concrete Girders	5-167
5.9.1	Definitions	5-167
5.9.2	WSDOT Criteria for Use of Spliced Girders	5-168
5.9.3	Girder Segment Design	5-168
5.9.4	Joints Between Segments	5-169
5.9.5	Review of Shop Plans for Spliced Prestressed Concrete Girders	5-174
5.9.6	Post-tensioning Notes – Spliced Prestressed Concrete Girders	5-175
5.10	Bridge Standard Drawings	5-177
	Girder Sections	5-177
	Superstructure Construction Sequences	5-177
	W Girders	5-177
	WF Girders	5-177
	Wide Flange Thin Deck Girders	5-178
	Wide Flange Deck Girders	5-178
	Deck Bulb Tee Girders	5-179
	Slabs	5-179
	Tub Girders	5-179
	Stay-In-Place Deck Panel	5-179
	Post Tensioned Spliced Girders	5-180
5.11	Appendices	5-181
Appendix 5.1-A1	Standard Hooks	5-183
Appendix 5.1-A2	Minimum Reinforcement Clearance and Spacing for Beams and Columns	5-184
Appendix 5.1-A3	Reinforcing Bar Properties	5-185
Appendix 5.1-A4	Tension Development Length of Deformed Bars	5-186
Appendix 5.1-A5	Compression Development Length and Minimum Lap Splice of Grade 60 Bars	5-189
Appendix 5.1-A6	Tension Development Length of 90° and 180° Standard Hooks	5-190
Appendix 5.1-A7	Tension Lap Splice Lengths of Grade 60 Bars – Class B	5-192
Appendix 5.1-A8	Prestressing Strand Properties and Development Length	5-195
Appendix 5.2-A1	Working Stress Design	5-196
Appendix 5.2-A2	Working Stress Design	5-197
Appendix 5.2-A3	Working Stress Design	5-198

Appendix 5.3-A1	Positive Moment Reinforcement.....	5-199
Appendix 5.3-A2	Negative Moment Reinforcement.....	5-200
Appendix 5.3-A3	Adjusted Negative Moment Case I (Design for M at Face of Support)	5-201
Appendix 5.3-A4	Adjusted Negative Moment Case II (Design for M at 1/4 Point).....	5-202
Appendix 5.3-A5	Cast-In-Place Deck Slab Design for Positive Moment Regions $f'_c = 4.0$ ksi	5-203
Appendix 5.3-A6	Cast-In-Place Deck Slab Design for Negative Moment Regions $f'_c = 4.0$ ksi	5-204
Appendix 5.3-A7	Slab Overhang Design-Interior Barrier Segment.....	5-205
Appendix 5.3-A8	Slab Overhang Design-End Barrier Segment.....	5-206
Appendix 5.6-A1-1	Span Capability of W Girders.....	5-207
Appendix 5.6-A1-2	Span Capability of WF Girders.....	5-208
Appendix 5.6-A1-3	Span Capability of Deck Bulb Tee Girders	5-210
Appendix 5.6-A1-4	Span Capability of WF Thin Deck Girders	5-211
Appendix 5.6-A1-5	Span Capability of WF Deck Girders.....	5-212
Appendix 5.6-A1-6	Span Capability of Trapezoidal Tub Girders without Top Flange.....	5-213
Appendix 5.6-A1-7	Span Capability of Trapezoidal Tub Girders with Top Flange.....	5-214
Appendix 5.6-A1-8	Span Capability of Post-tensioned Spliced I-Girders	5-215
Appendix 5.6-A1-9	Span Capability of Post-tensioned Spliced Tub Girders.....	5-217
Appendix 5-B1	“A” Dimension for Precast Girder Bridges	5-219
Appendix 5-B2	Vacant	5-230
Appendix 5-B3	Existing Bridge Widening	5-231
Appendix 5-B4	Post-tensioned Box Girder Bridges.....	5-233
Appendix 5-B5	Simple Span Prestressed Girder Design	5-238
Appendix 5-B6	Vacant	5-323
Appendix 5-B7	Precast Concrete Stay-in-place (SIP) Deck Panel	5-324
Appendix 5-B8	Vacant	5-342
Appendix 5-B9	Vacant	5-343
Appendix 5-B10	Positive EQ Reinforcement at Interior Pier of a Prestressed Girder ..	5-344
Appendix 5-B11	LRFD Wingwall Design Vehicle Collision.....	5-347
Appendix 5-B12	Flexural Strength Calculations for Composite T-Beams.....	5-350
Appendix 5-B13	Vacant	5-356
Appendix 5-B14	Shear and Torsion Capacity of a Reinforced Concrete Beam	5-357
Appendix 5-B15	Sound Wall Design – Type D-2k	5-363
5.99	References	5-377

Chapter 6	Structural Steel	6-1
6.0	Structural Steel	6-1
6.0.1	Introduction	6-1
6.0.2	Special Requirements for Steel Bridge Rehabilitation or Modification	6-1
6.0.3	Retrofit of Low Vertical Clearance Truss Portal and Sway Members	6-1
6.1	Design Considerations	6-6
6.1.1	Codes, Specification, and Standards	6-6
6.1.2	WSDOT Steel Bridge Practice	6-7
6.1.3	Preliminary Girder Proportioning	6-8
6.1.4	Estimating Structural Steel Weights	6-9
6.1.5	Bridge Steels	6-10
6.1.6	Plate Sizes	6-11
6.1.7	Girder Segment Sizes	6-11
6.1.8	Computer Programs	6-12
6.1.9	Fasteners	6-12
6.1.10	Bending Steel	6-14
6.2	Girder Bridges	6-15
6.2.1	General	6-15
6.2.2	I-Girders	6-15
6.2.3	Tub or Box Girders	6-16
6.2.4	Fracture Critical Superstructures	6-17
6.3	Design of I-Girders	6-19
6.3.1	Limit States for AASHTO LRFD	6-19
6.3.2	Composite Section	6-19
6.3.3	Flanges	6-20
6.3.4	Webs	6-20
6.3.5	Transverse Stiffeners	6-20
6.3.6	Longitudinal Stiffeners	6-21
6.3.7	Bearing Stiffeners	6-21
6.3.8	Cross Frames	6-21
6.3.9	Bottom Laterals	6-23
6.3.10	Bolted Field Splice for Girders	6-23
6.3.11	Camber	6-24
6.3.12	Bridge Deck Placement Sequence	6-26
6.3.13	Bridge Bearings for Steel Girders	6-27
6.3.14	Surface Roughness and Hardness	6-27
6.3.15	Welding	6-29
6.3.16	Shop Assembly	6-30

6.4	Plan Details	6-31
6.4.1	General.	6-31
6.4.2	Structural Steel Notes.	6-31
6.4.3	Framing Plan.	6-31
6.4.4	Girder Elevation	6-31
6.4.5	Typical Girder Details	6-32
6.4.6	Cross Frame Details	6-32
6.4.7	Camber Diagram and Bearing Stiffener Rotation	6-33
6.4.8	Bridge Deck	6-33
6.4.9	Handrail Details, Inspection Lighting, and Access	6-34
6.4.10	Box Girder Details	6-34
6.5	Shop Plan Review	6-36
6.6	Painting of Existing Steel Bridges	6-37
6.6.1	General.	6-37
6.6.2	Vertical Analysis	6-38
6.6.3	Horizontal Analysis.	6-39
6.6.4	Special Considerations	6-42
6.6.5	Quantities and Estimates	6-44
6.7	Corrosion of Steel Foundations and Buried Structures	6-45
6.7.1	Corrosion of Steel Foundations	6-45
6.7.2	Corrosion and Abrasion of Metal Buried Structures	6-47
6.8	Bridge Standard Drawings	6-54
6.8.1	Structural Steel.	6-54
6.99	References	6-55

Chapter 7	Substructure Design	7-1
7.1	General Substructure Considerations	7-1
7.1.1	Foundation Design Process	7-1
7.1.2	Foundation Design Limit States	7-3
7.1.3	Seismic Design	7-4
7.1.4	Substructure and Foundation Loads	7-4
7.1.5	Concrete Class for Substructure	7-7
7.1.6	Foundation Seals	7-7
7.1.7	Scour Requirements	7-10
7.2	Foundation Modeling for Seismic Loads	7-12
7.2.1	General	7-12
7.2.2	Substructure Elastic Dynamic Analysis Procedure	7-12
7.2.3	Bridge Model Section Properties	7-13
7.2.4	Bridge Model Verification	7-15
7.2.5	Deep Foundation Modeling Methods	7-15
7.2.6	Lateral Analysis of Piles and Shafts	7-20
7.2.7	Spread Footing Modeling	7-25
7.3	Column Design	7-28
7.3.1	General Design Considerations	7-28
7.3.2	Slenderness Effects	7-29
7.3.3	Shear Design	7-31
7.3.4	Column Silos	7-31
7.3.5	Column Reinforcement	7-33
7.3.6	Column and Wall Pier Hinges	7-45
7.3.7	Reduced Column Section	7-47
7.4	Crossbeams	7-51
7.4.1	General Design	7-51
7.5	Abutment Design and Details	7-54
7.5.1	General	7-54
7.5.2	Abutments Supported By Mechanically-Stabilized Earth Walls	7-58
7.5.3	Embankment at Abutments	7-63
7.5.4	Abutment Loading	7-63
7.5.5	Temporary Construction Load Cases	7-64
7.5.6	Abutment Bearings and Girder Stops	7-65
7.5.7	Abutment Expansion Joints	7-67
7.5.8	Open Joint Details	7-67
7.5.9	Construction Joints	7-69
7.5.10	Abutment Wall Design	7-69
7.5.11	Drainage and Backfilling	7-71
7.6	Abutment Wing Walls and Curtain Walls	7-73
7.6.1	Traffic Barrier Loads	7-73
7.6.2	Wing Wall Design	7-73
7.6.3	Wing Wall Detailing	7-73

7.7	Footing Design	7-74
7.7.1	General Footing Criteria	7-74
7.7.2	Loads and Load Factors	7-75
7.7.3	Geotechnical Report Summary	7-76
7.7.4	Spread Footing Design	7-77
7.7.5	Pile-Supported Footing Design	7-82
7.8	Shafts	7-85
7.8.1	Axial Resistance	7-85
7.8.2	Structural Design and Detailing	7-90
7.9	Piles and Piling	7-98
7.9.1	Pile Types	7-98
7.9.2	Single Pile Axial Resistance	7-100
7.9.3	Block Failure	7-100
7.9.4	Pile Uplift	7-100
7.9.5	Pile Spacing	7-100
7.9.6	Structural Design and Detailing of CIP Concrete Piles	7-101
7.9.7	Pile Splices	7-102
7.9.8	Pile Lateral Design	7-102
7.9.9	Battered Piles	7-102
7.9.10	Pile Tip Elevations and Quantities	7-103
7.9.11	Plan Pile Resistance	7-103
7.10	Concrete-Filled Steel Tubes	7-104
7.10.1	Scope	7-104
7.10.2	Design Requirements	7-105
7.10.3	CFST-to-Cap Annular Ring Connections	7-110
7.10.4	CFST-to-Cap Reinforced Concrete Connections	7-115
7.10.5	RCFST-to-Column and CFST-to Column Connections	7-118
7.10.6	Partially-filled CFST	7-120
7.10.7	Construction Requirements	7-121
7.10.8	Notation	7-122
7.11	Bridge Standard Drawings	7-124
7.12	Appendices	7-125
Appendix 7.3-A2	Noncontact Lap Splice Length Column to Shaft Connections	7-126
Appendix 7-B1	Linear Spring Calculation Method II (Technique I)	7-128
Appendix 7-B2	Pile Footing Matrix Example Method II (Technique I)	7-134
Appendix 7-B3	Non-Linear Springs Method III	7-137
Soil Modulus - ES	7-138
Subgrade Modulus - kS	7-138
7.99	References	7-139

Chapter 8	Walls and Buried Structures	8-1
8.1	Retaining Walls	8-1
8.1.1	General	8-1
8.1.2	Common Types of Retaining Walls	8-2
8.1.3	General Design Considerations	8-4
8.1.4	Design of Reinforced Concrete Cantilever Retaining Walls	8-4
8.1.5	Design of Cantilever Soldier Pile and Soldier Pile Tieback Walls	8-9
8.1.6	Design of Structural Earth Walls	8-13
8.1.7	Design of Standard Plan Geosynthetic Walls	8-14
8.1.8	Design of Soil Nail Walls	8-14
8.1.9	Scour of Retaining Walls	8-14
8.1.10	Miscellaneous Items	8-18
8.2	Noise Barrier Walls	8-23
8.2.1	General	8-23
8.2.2	Loads	8-23
8.2.3	Design	8-24
8.3	Buried Structures	8-27
8.3.1	General Policy	8-27
8.3.2	WSDOT Buried Structure Templates	8-28
8.3.3	General Design Requirements	8-28
8.3.4	Materials	8-33
8.3.5	Limit States and Design Methodologies	8-35
8.3.6	Provisions for Structure Type	8-39
8.3.7	Design of Detention Vaults	8-45
8.3.8	Design of Tunnels	8-47
8.4	Bridge Standard Drawings	8-49
8.5	Appendices	8-50
Appendix 8.1-A1	Summary of Design Specification Requirements for Walls	8-51
8.99	References	8-54

Chapter 9	Bearings and Expansion Joints	9-1
9.1	Expansion Joints	9-1
9.1.1	General Considerations	9-1
9.1.2	General Design Criteria	9-3
9.1.3	Small Movement Range Joints	9-6
9.1.4	Medium Movement Range Joints	9-15
9.1.5	Large Movement Range Joints	9-19
9.2	Bearings	9-27
9.2.1	General Considerations	9-27
9.2.2	Force Considerations	9-28
9.2.3	Movement Considerations	9-28
9.2.4	Detailing Considerations	9-29
9.2.5	Bearing Types	9-29
9.2.6	Miscellaneous Details	9-37
9.2.7	Contract Drawing Representation	9-37
9.2.8	Shop Drawing Review	9-38
9.2.9	Bearing Replacement Considerations	9-38
9.3	Seismic Isolation Bearings	9-39
9.3.1	General Considerations	9-39
9.3.2	Suitability and Selection Considerations	9-39
9.3.3	General Design Criteria	9-40
9.3.4	Seismic Isolation Bearing Submittal Requirements	9-41
9.3.5	Seismic Isolation Bearing Review Process	9-42
9.3.6	Seismic Isolation Bearing Inspection	9-43
9.4	Bridge Standard Drawings	9-44
9.4.1	Expansion Joints	9-44

Chapter 10	Signs, Barriers, Approach Slabs, and Utilities	10-1
10.1	Sign and Luminaire Supports	10-1
10.1.1	Loads	10-1
10.1.2	Bridge Mounted Signs	10-3
10.1.3	Monotube Sign Structures Mounted on Bridges	10-7
10.1.4	Monotube Sign Structures	10-8
10.1.5	Foundations	10-12
10.1.6	Truss Sign Bridges: Foundation Sheet Design Guidelines	10-15
10.2	Bridge Traffic Barriers	10-16
10.2.1	General Guidelines	10-16
10.2.2	Bridge Railing Test Levels	10-17
10.2.3	Available WSDOT Designs	10-17
10.2.4	Design Criteria	10-21
10.3	At Grade Concrete Barriers	10-25
10.3.1	Differential Grade Concrete Barriers	10-25
10.3.2	Traffic Barrier Moment Slab	10-26
10.3.3	Precast Concrete Barrier	10-30
10.4	Bridge Traffic Barrier Rehabilitation	10-31
10.4.1	Policy	10-31
10.4.2	Guidelines	10-31
10.4.3	Design Criteria	10-31
10.4.4	WSDOT Bridge Inventory of Bridge Rails	10-32
10.4.5	Available Retrofit Designs	10-33
10.4.6	Available Replacement Designs	10-33
10.5	Bridge Railing	10-34
10.5.1	Design	10-34
10.5.2	Railing Types	10-34
10.6	Bridge Approach Slabs	10-36
10.6.1	Notes to Region for Preliminary Plan	10-37
10.6.2	Bridge Approach Slab Design Criteria	10-37
10.6.3	Bridge Approach Slab Detailing	10-38
10.6.4	Skewed Bridge Approach Slabs	10-39
10.6.5	Approach Anchors and Expansion Joints	10-40
10.6.6	Bridge Approach Slab Addition or Retrofit to Existing Bridges	10-41
10.6.7	Bridge Approach Slab Staging	10-42
10.7	Traffic Barrier on Bridge Approach Slabs	10-43
10.7.1	Bridge Approach Slab over Wing Walls, Cantilever Walls or Geosynthetic Walls	10-43
10.7.2	Bridge Approach Slab over SE Walls	10-45

10.8	Utilities Installation on New and Existing Structures	10-46
10.8.1	General Concepts	10-46
10.8.2	Utility Design Criteria	10-49
10.8.3	Box/Tub Girder Bridges	10-51
10.8.4	Traffic Barrier Conduit	10-52
10.8.5	Conduit Types	10-53
10.8.6	Utility Supports	10-53
10.9	Review Procedure for Utility Installations on Existing Structures	10-55
10.9.1	Utility Review Checklist	10-56
10.10	Anchors for Permanent Attachments	10-58
10.11	Drainage Design	10-59
10.12	Bridge Security	10-60
10.12.1	General	10-60
10.12.2	Design	10-60
10.12.3	Design Criteria	10-61
10.13	Temporary Bridges	10-62
10.13.1	General	10-62
10.13.2	Design	10-62
10.13.3	NBI Requirements	10-64
10.13.4	Submittal Requirements	10-64
10.14	Bridge Standard Drawings	10-65
10.99	References	10-68

Chapter 11 Detailing Practice	11-1
11.1 Detailing Practice	11-1
11.1.1 Standard Office Practices	11-1
11.1.2 Bridge Office Standard Drawings and Office Examples	11-14
11.1.3 Typical Plan Set and Sheets	11-15
11.1.4 Electronic Plan Sharing Policy	11-22
11.1.5 Structural Steel	11-23
11.1.6 Aluminum Section Designations	11-24
11.1.7 Abbreviations	11-25
11.2 Appendices	11-34
Appendix 11.2-A1 Dimensional Callout Example	11-35
Appendix 11.2-A2 Typical Details	11-36
Appendix 11.2-A3 Typical Section Callouts	11-37
Appendix 11.2-A4 Reinforcement Callout Examples	11-38

Chapter 12	Quantities, Costs, and Specifications	12-1
12.1	Quantities - General	12-1
12.1.1	Cost Estimating Quantities	12-1
12.1.2	Not Included in Bridge Quantities List	12-2
12.2	Computation of Quantities	12-3
12.2.1	Responsibilities	12-3
12.2.2	Procedure for Computation	12-3
12.2.3	Data Source	12-4
12.2.4	Accuracy	12-4
12.2.5	Excavation	12-4
12.2.6	Shoring or Extra Excavation, Class A	12-7
12.2.7	Piling	12-9
12.2.8	Conduit Pipe	12-10
12.2.9	Private Utilities Attached To Bridge Structures	12-10
12.2.10	Drilled Shafts	12-11
12.3	Construction Costs	12-12
12.3.1	Introduction	12-12
12.3.2	Factors Affecting Costs	12-12
12.3.3	Development of Cost Estimates	12-13
12.4	Construction Specifications and Estimates	12-16
12.4.1	General	12-16
12.4.2	Definitions	12-16
12.4.3	General Bridge S&E Process	12-17
12.4.4	Reviewing Bridge Plans	12-19
12.4.5	Preparing the Bridge Cost Estimates	12-20
12.4.6	Preparing the Bridge Specifications	12-21
12.4.7	Preparing the Bridge Working Day Schedule	12-22
12.4.8	Reviewing Projects Prepared by Consultants	12-23
12.4.9	Submitting the PS&E Package	12-23
12.4.10	PS&E Review Period and Turn-in for AD Copy	12-24
12.5	Appendices	12-25
Appendix 12.1-A1	Not Included In Bridge Quantities List	12-26
Appendix 12.2-A1	Bridge Quantities	12-27
Appendix 12.3-A1	Structural Estimating Aids Construction Costs	12-32
Appendix 12.3-A2	Structural Estimating Aids Construction Costs	12-34
Appendix 12.3-A3	Structural Estimating Aids Construction Costs	12-36
Appendix 12.3-A4	Structural Estimating Aids Construction Costs	12-38
Appendix 12.3-B1	Cost Estimate Summary	12-39
Appendix 12.4-A1	Special Provisions Checklist	12-40
Appendix 12.4-A2	Structural Estimating Aids Construction Time Rates	12-45
Appendix 12.4-B1	Construction Working Day Schedule	12-47

Chapter 13 Bridge Load Rating	13-1
13.1 General	13-1
13.1.1 LRFR Method per the MBE	13-2
13.1.2 Load Factor Method (LFR)	13-5
13.1.3 Allowable Stress Method (ASD)	13-7
13.1.4 Live Loads	13-8
13.1.5 Rating Trucks	13-8
13.2 Special Rating Criteria	13-11
13.2.1 Dead Loads	13-11
13.2.2 Live Load Distribution Factors	13-12
13.2.3 Reinforced Concrete Structures	13-12
13.2.4 Prestressed Concrete Structures	13-12
13.2.5 Concrete Decks	13-13
13.2.6 Concrete Crossbeams	13-13
13.2.7 In-Span Hinges	13-13
13.2.8 Girder Structures	13-13
13.2.9 Box Girder Structures	13-13
13.2.10 Segmental Concrete Bridges	13-13
13.2.11 Concrete Slab Structures	13-13
13.2.12 Steel Structures	13-14
13.2.13 Steel Floor Systems	13-14
13.2.14 Steel Truss Structures	13-14
13.2.15 Timber Structures	13-14
13.2.16 Widened or Rehabilitated Structures	13-15
13.2.17 Buried Structures	13-15
13.2.18 Overloads	13-15
13.2.19 Specialized Hauling Vehicles (SHVs)	13-16
13.3 Load Rating Software	13-18
13.4 Load Rating Reports	13-19
13.5 Appendices	13-20
Appendix 13.5-A1 LRFR Bridge Rating Summary	13-21
Appendix 13.5-A2 LRFR Bridge Rating Summary	13-22
13.99 References	13-23

Chapter 14 Accelerated and Innovative Bridge Construction	14-1
14.1 Introduction	14-1
14.1.1 General	14-1
14.1.2 ABC Methods	14-2
14.2 Application of ABC	14-3
14.2.1 Economics of ABC	14-3
14.2.2 Practical Applications	14-3
14.2.3 Prefabricated Bridge Elements and Systems	14-4
14.2.5 Project Delivery Methods	14-5
14.2.6 Decision Making Tools	14-5
14.3 Structural Systems	14-8
14.3.1 Precast Bent System Design for High Seismic Regions	14-8
14.3.2 Geosynthetic Reinforced Soil Integrated Bridge System	14-11
14.3.3 Precast Decks	14-11
14.3.4 Link Slabs	14-11
14.4 Innovative Bridge Construction	14-12
14.4.1 Self-Centering Columns	14-12
14.4.2 Shape Memory Alloy	14-13
14.5 Shipping, Handling and Erection	14-15
14.5.1 Lifting Devices	14-15
14.5.2 Handling, Storage and Shipping	14-15
14.5.3 Tolerances	14-16
14.5.4 Assembly Plans	14-16
14.5.5 Element Sizes	14-17
14.6 Installation Method Options	14-18
14.6.1 Lateral Slide Systems	14-18
14.6.2 Self-Propelled Modular Transporter Systems	14-18
14.7 Examples of Accelerated and Innovative Bridge Construction	14-19
14.99 References	14-21

Chapter 15	Structural Design Requirements for Design-Build Contracts	15-1
15.1	Manual Description	15-1
15.1.1	Purpose	15-1
15.1.2	Specifications	15-1
15.2	Bridge Configuration Criteria	15-2
15.2.1	General	15-2
15.2.2	Railroad Crossings	15-3
15.2.3	Temporary Bridges	15-3
15.2.4	Inspection and Maintenance Access	15-3
15.2.5	Bridge Types	15-5
15.2.6	Aesthetic Design Elements	15-5
15.2.7	Architectural Design Standards	15-6
15.2.8	Methods	15-6
15.2.9	Design-Builder Urban Design Team	15-6
15.2.10	Analysis and Design Criteria for Structural Widening and Modifications	15-7
15.2.11	Bridge Security	15-7
15.3	Load Criteria	15-9
15.3.1	Scope	15-9
15.3.2	Load Factors and Load Combinations	15-9
15.3.3	Permanent Loads	15-9
15.3.4	Live Loads	15-10
15.3.5	Noise Barrier Walls	15-11
15.4	Seismic Design and Retrofit	15-12
15.4.1	General	15-12
15.4.2	WSDOT Additions and Modifications to AASHTO Guide Specifications for LRFD Seismic Bridge Design	15-12
15.4.3	Seismic Design Requirements for Bridge Modifications and Widening Projects	15-24
15.4.4	Seismic Retrofitting of Existing Bridges	15-26
15.5	Concrete Structures	15-28
15.5.1	General	15-28
15.5.2	Materials	15-28
15.5.3	Design Considerations	15-31
15.5.4	Superstructures	15-32
15.5.5	Concrete Bridge Decks	15-36
15.6	Steel Structures	15-38
15.6.1	Design Considerations	15-38
15.6.2	Girder Bridges	15-41
15.6.3	Design of I-Girders	15-42
15.6.4	Plan Details	15-47
15.6.5	Painting of Existing Steel Bridges	15-50
15.6.6	Corrosion of Steel Foundations and Buired Structures	15-50

15.7	Substructure Design	15-51
15.7.1	General Substructure Considerations	15-51
15.7.2	Foundation Modeling for Seismic Loads	15-52
15.7.3	Column Design	15-54
15.7.4	Crossbeam	15-56
15.7.5	Abutment Design and Details	15-56
15.7.6	Abutment Wing Walls and Curtain Walls	15-58
15.7.7	Footing Design	15-58
15.7.8	Shafts	15-59
15.7.9	Piles and Piling	15-61
15.7.10	Concrete-Filled Steel Tubes	15-62
15.8	Walls and Buried Structures	15-63
15.8.1	Retaining Walls	15-63
15.8.2	Noise Barrier Walls	15-66
15.8.3	Buried Structures	15-67
15.9	Bearings and Expansion Joints	15-70
15.9.1	Expansion Joints	15-70
15.9.2	Bearings	15-76
15.10	Signs, Barriers, Bridge Approach Slabs, and Utilities	15-82
15.10.1	Sign and Luminaire Supports	15-82
15.10.2	Bridge Traffic Barriers	15-90
15.10.3	At Grade Concrete Barriers	15-92
15.10.4	Bridge Traffic Barrier Rehabilitation	15-94
15.10.5	Bridge Railing	15-95
15.10.6	Bridge Approach Slabs	15-95
15.10.7	Traffic Barrier on Bridge Approach Slabs	15-97
15.10.8	Utilities Installation on New and Existing Structures	15-98
15.10.9	Review Procedure for Utility Installations on Existing Structures	15-101
15.10.10	Anchors for Permanent Attachments	15-101
15.10.11	Drainage Design	15-102
15.11	Detailing Practices	15-103
15.11.1	Standard Practices	15-103
15.11.2	Bridge Office Standard Drawings and Office Examples	15-107
15.11.3	Plan Sheets	15-107
15.11.5	Structural Steel	15-110
15.11.6	Aluminum Section Designations	15-112
15.11.7	Abbreviations	15-112
15.12	Bridge Load Rating	15-113
15.12.1	General	15-113
15.12.2	Load Rating Software	15-113
15.13	Appendices	15-114
	Appendix 15.2-A1 Conceptual Plan Checklist	15-115
15.99	References	15-116