Foreword

This manual has been prepared to provide Washington State Department of Transportation (WSDOT) bridge design engineers with a guide to the design criteria, analysis methods, and detailing procedures for the preparation of highway bridge and structure construction plans, specifications, and estimates.

It is not intended to be a textbook on structural engineering. It is a guide to acceptable WSDOT practice. This manual does not cover all conceivable problems that may arise, but is intended to be sufficiently comprehensive to, along with sound engineering judgment, provide a safe guide for bridge engineering.

A thorough knowledge of the contents of this manual is essential for a high degree of efficiency in the engineering of WSDOT highway structures.

This loose leaf form of this manual facilitates modifications and additions. New provisions and revisions will be issued from time to time to keep this guide current. Suggestions for improvement and updating the manual are always welcome.

All manual modifications must be approved by the Bridge Design Engineer.



Jerry Weigel
Bridge and Structures Engineer
Washington State Department of Transportation

Contents

Chapter 1 General Information

1.1 Manual Description 1-1
- 1.1.1 Purpose ... 1-1
- 1.1.2 Specifications ... 1-1
- 1.1.3 Format ... 1-1
- 1.1.4 Revisions ... 1-2

1.2 Bridge and Structures Office Organization ... 1-4
- 1.2.1 General ... 1-4
- 1.2.2 Organizational Elements of the Bridge Office ... 1-4
- 1.2.3 Design Unit Responsibilities and Expertise ... 1-7

1.3 Quality Control/Quality Assurance (QC/QA) Procedure ... 1-8
- 1.3.0 General ... 1-8
- 1.3.1 Design/Check Procedures ... 1-8
- 1.3.2 Design/Check Calculation File ... 1-17
- 1.3.3 PS&E Review Period ... 1-18
- 1.3.4 Addenda ... 1-18
- 1.3.5 Shop Plans and Permanent Structure Construction Procedures ... 1-18
- 1.3.6 Contract Plan Changes (Change Orders and As-Builts) ... 1-21
- 1.3.7 Archiving Design Calculations, Design Files, and S&E Files ... 1-22
- 1.3.8 Public Disclosure Policy Regarding Bridge Plans ... 1-23
- 1.3.9 Use of Computer Software ... 1-24

1.4 Coordination With Other Divisions and Agencies ... 1-25
- 1.4.1 Preliminary Planning Phase ... 1-25
- 1.4.2 Final Design Phase ... 1-25

1.5 Bridge Design Scheduling ... 1-26
- 1.5.1 General ... 1-26
- 1.5.2 Preliminary Design Schedule ... 1-26
- 1.5.3 Final Design Schedule ... 1-26

1.6 Guidelines for Bridge Site Visits ... 1-29
- 1.6.1 Bridge Rehabilitation Projects ... 1-29
- 1.6.2 Bridge Widening and Seismic Retrofits ... 1-29
- 1.6.3 Rail and Minor Expansion Joint Retrofits ... 1-29
- 1.6.4 New Bridges ... 1-29
- 1.6.5 Bridge Demolition ... 1-30
- 1.6.6 Proximity of Railroads Adjacent to the Bridge Site ... 1-30

1.99 Bibliography ... 1-30

Appendix 1-A
- Figure 1-A-1 Special Provisions Checklist ... 1-A-1
- Figure 1-A-2 Breakdown of Project Manhours Required Form ... 1-A-7
- Figure 1-A-3 Monthly Project Progress Report Form ... 1-A-8

Chapter 2 Preliminary Design

2.1 Preliminary Studies ... 2-1
- 2.1.1 Interdisciplinary Design Studies ... 2-1
- 2.1.2 Value Engineering Studies ... 2-1
- 2.1.3 Preliminary Recommendations for Bridge Rehabilitation Projects ... 2-1
- 2.1.4 Preliminary Recommendations for New Bridge Projects ... 2-2
- 2.1.5 Type, Size, and Location (TS&L) Reports ... 2-2

2.2 Preliminary Plan 2-6
2.2.1 Development of the Preliminary Plan 2-6
2.2.2 Documentation 2-7
2.2.3 General Factors for Consideration 2-8
2.2.4 Permits 2-10
2.2.5 Preliminary Cost Estimate 2-10
2.2.6 Approvals 2-11
2.3 Preliminary Plan Criteria 2-14
2.3.1 Highway Crossings 2-14
2.3.2 Railroad Crossings 2-17
2.3.3 Water Crossings 2-19
2.3.4 Bridge Widenings 2-21
2.3.5 Detour Structures 2-22
2.3.6 Retaining Walls and Noise Walls 2-22
2.3.7 Bridge Deck Drainage 2-22
2.3.8 Bridge Deck Protective Systems 2-22
2.3.9 Construction Clearances 2-23
2.3.10 Design Guides for Falsework Depth Requirements 2-23
2.3.11 Inspection and Maintenance Access 2-24
2.4 Selection of Structure Type 2-26
2.4.1 Bridge Types 2-26
2.4.2 Wall Types 2-31
2.5 Aesthetic Considerations 2-32
2.5.1 General Visual Impact 2-32
2.5.2 End Piers 2-32
2.5.3 Intermediate Piers 2-33
2.5.4 Barrier and Wall Surface Treatments 2-33
2.5.5 Superstructure 2-34
2.6 Miscellaneous 2-35
2.6.1 Structure Costs 2-35
2.6.2 Handling and Shipping Precast Members and Steel Beams 2-35
2.6.3 Salvage of Materials 2-35
2.7 WSDOT Standard Highway Bridge 2-36
2.7.1 Design Elements 2-36
2.7.2 Detailing the Preliminary Plan 2-37
2.99 Bibliography 2-38

Appendix 2-A

Figure 2-A-1 Bridge Site Date General 2-A-1
Figure 2-A-2 Bridge Site Date Rehabilitation 2-A-2
Figure 2-A-3 Bridge Site Date Stream Crossing 2-A-3
Figure 2-A-4 Preliminary Plan Checklist 2-A-4
Figure 2-A-5 Bridge StageConstruction Comparison 2-A-5
Figure 2-A-6 ..... 2-A-6
Figure 2-A-7 ..... 2-A-7
Figure 2-A-8 ..... 2-A-8

Appendix 2-B

Figure 2-B-1 Preliminary Plan Bridge Replacement 2-B-1
Figure 2-B-2 Preliminary Plan Bridge Replacement 2-B-2
Figure 2-B-3 Preliminary Plan Bridge Replacement 2-B-3
Figure 2-B-4 Preliminary Plan Bridge Widening 2-B-4
Figure 2-B-5 Preliminary Plan Bridge Widening 2-B-5

Figure 2-B-6 Preliminary Plan Bridge Widening 2-B-6
Figure 2-B-7 Preliminary Plan Bridge with Staging 2-B-7
Figure 2-B-8 Preliminary Plan Bridge with Staging 2-B-8
Figure 2-B-9 Preliminary Plan Bridge Replacement 2-B-9

Chapter 3 Loads

3.1 Type of Loads 3-1
3.1.1 Dead Loads 3-1
3.1.2 Live Loads 3-1
3.1.3 Earthquake Loads (see Chapter 4) 3-2
3.1.4 Other Loads 3-2
3.2 Application of Loads 3-3
3.2.1 Wind Load 3-3
3.3 Use of Computer Software 3-4
3.3.1 Protection of Intellectual Property 3-4
3.3.2 Policy on Open Source Software 3-4
3.3.3 Approved Software Tools 3-4
3.99 Bibliography 3-4
Appendix 3-B
Appendix 3-B-1 HL 93 Loading for Bridge Piers 3-B-1

Chapter 4 Seismic Design and Retrofit

4.0 Seismic Design and Retrofit 4-1
4.1 General 4-1
4.2 Seismic Design Process 4-2
4.3 WSDOT Practices and Criteria 4-3
4.4 Elastic Dynamic Analysis (EDA) 4-6
4.4.1 Analytical Methods 4-6
4.4.2 Structural System or Global Analyses 4-7
4.4.3 Stand-Alone or Local Analysis 4-8
4.4.4 Model Verification 4-9
4.4.5 Effective Cracked Moment of Inertia for Reinforced Concrete Columns 4-9
4.5 Base Isolation and Energy Dissipation Devices 4-10
4.6 Retrofit Guide 4-12
4.6.1 Vulnerability Study 4-12
4.6.2 Material Properties 4-14
4.6.3 Earthquake Restrainers 4-14
4.6.4 Shear Blocks and Catcher Beams 4-15
4.6.5 Post-tensioning Strengthening 4-16
4.6.6 Column jacketing 4-17
4.6.7 Steel Structures 4-21
4.6.8 Base Isolation and Energy Dissipation Devices 4-22
4.99 Bibliography 4-23
Appendix 4-A
Figure 4-A-1 Earthquake Probability - Poisson Model 4-A-1
Figure 4-A-2 Design Examples of Seismic Retrofits 4-A-2

Chapter 5 Concrete Structures

5.0 General 5-1
5.1 Material Properties 5-1
5.1.1 Concrete Properties 5-1
5.1.2 Reinforcing Steel 5-5
5.1.3 Prestressing Steel 5-12
5.1.4 Prestress Losses 5-17
5.1.5 Prestressing Anchorage Systems 5-20
5.1.6 Ducts 5-21
5.2 Design Consideration 5-22
5.2.1 Design Limit States 5-22
5.2.2 Design Criteria 5-22
5.2.3 Service Limit State 5-23
5.2.4 Strength Limit State 5-24
5.2.5 Strut-and-tie Model 5-32
5.2.6 Deflection and Camber 5-33
5.2.7 Serviceability 5-35
5.2.8 Connections (Joints) 5-36
5.2.9 Revised Provisions for Flexural Design 5-37
5.3 Reinforced Concrete Box Girder Bridges 5-41
5.3.1 Box Girder Basic Geometries 5-41
5.3.2 Reinforcement 5-45
5.3.3 Crossbeam 5-55
5.3.4 End Diaphragm 5-58
5.3.5 Dead Load Deflection and Camber 5-61
5.3.6 Thermal Effects 5-62
5.3.7 Hinges 5-62
5.3.8 Utility Openings 5-62
5.4 Hinges and Inverted T-Beam Pier Caps 5-66
5.5 Bridge Widenings 5-69
5.5.1 Review of Existing Structures 5-69
5.5.2 Analysis and Design Criteria 5-70
5.5.3 Removing Portions of the Existing Structure 5-75
5.5.4 Attachment of Widening to Existing Structure 5-75
5.5.5 Expansion Joints 5-87
5.5.6 Possible Future Widening for Current Designs 5-89
5.5.7 Bridge Widening Falsework 5-89
5.5.8 Existing Bridge Widenings 5-89
5.6 Precast Prestressed Girder Superstructures 5-90
5.6.1 WSDOT Standard Prestressed Girders 5-90
5.6.2 Criteria for Girder Design 5-93
5.6.3 Fabrication and Handling 5-101
5.6.4 Superstructure Optimization 5-106
5.6.5 Repair of Damaged Girders at Fabrication 5-110
5.6.6 Repair of Damaged Bridge Girders 5-110
5.6.7 Short Span Precast Prestressed Bridges 5-112
5.6.8 Precast Tub Girders 5-113
5.6.9 Prestressed Girder Checking Requirement 5-113
5.6.10 Review of shop plans for pretensioned girders 5-113

5.7 Roadway Slab 5-115
5.7.1 Roadway Slab Requirements 5-115
5.7.2 Slab Reinforcement 5-117
5.7.3 Stay-In-Place Deck Panels 5-123
5.7.4 Concrete Bridge Deck Protection Systems 5-124
5.8 Cast-in-Place Bridges 5-129
5.8.1 Design Parameters 5-129
5.8.2 Analysis 5-137
5.8.3 Post-tensioning 5-139
5.8.4 Shear 5-144
5.8.5 Temperature Effects 5-145
5.8.6 Construction 5-146
5.8.7 Post-Tensioning Notes — Cast-in-Place Girders 5-148
5.9 Spliced Precast Girders 5-149
5.9.1 Definitions 5-149
5.9.2 WSDOT Criteria for use of Spliced Girders 5-150
5.9.3 Girder Segment Design 5-150
5.9.4 Joints Between Segments 5-151
5.9.5 Review of shop plans for precast post-tensioned spliced-girders 5-152
5.9.6 Post-Tensioning Notes ~ Precast Post-Tensioning Spliced-Girders 5-153
5.99 Bibliography 5-154

Appendix 5-A

Figure 5-A-1 Standard Hooks 5-A-1
Figure 5-A-2 Minimum Reinforcement Clearance and Spacing for Beams and Columns 5-A-2
Table 5-A-3 Reinforcing Bar Properties 5-A-3
Table 5-A-4 Tension Development Length of Deformed Bars 5-A-4
Table 5-A-5 Compression Development Length and Minimum Lap Splice of Grade 60 Bars 5-A-5
Table 5-A-6 Tension Development Length of 90º and 180º Standard Hooks 5-A-6
Table 5-A-7 Tension Lap Splice Lengths of Grade 60 Uncoated Bars ~ Class B 5-A-7
Table 5-A-8 Prestressing Strand Properties and Development Length 5-A-8
Table 5-A-9 Flexural Reinforcement for Class 4000 Concrete 5-A-9
Table 5-A-10 Flexural Reinforcement for Class 5000 Concrete 5-A-10
Table 5-A-11 Flexural Reinforcement for Class 6000 Concrete 5-A-11
Figure 5-A-12 Positive Moment Reinforcement 5-A-12
Figure 5-A-13 Negative Moment Reinforcement 5-A-13
Figure 5-A-14 Adjusted Negative Moment Case I (Design for M @ Face of Support) 5-A-14
Figure 5-A-15 Adjusted Negative Moment Case II (Design for M @ 1/4 Point) 5-A-15
Figure 5-A-16 Cast-In-Place Deck Slab Design for Positive Moment Regions f'c=4, 0 ksi 5-A-16
Figure 5-A-17 Cast-In-Place Deck Slab Design for Negative Moment Regions f'c=4, 0 ksi 5-A-17
Figure 5-A-18 Slab Overhang Design- Interior Barrier Segment 5-A-18
Figure 5-A-19 Slab Overhang Design- End Barrier Segment 5-A-19
Table 5-A-20 Span Capability of Prestressed I-Girders 5-A-20
Table 5-A-21 Span Capability of Prestressed Wide Flange I-Girders 5-A-21
Table 5-A-22 Span Capability of Thin Flange Bulb-Tee Girders 5-A-22
Table 5-A-23 Span Capability of Trapezoidal Tub Girders without Top Flange 5-A-23
Table 5-A-24 Span Capability of Trapezoidal Tub Girders with Top Flange 5-A-24
Table 5-A-25 Span Capability of Prestressed1’-6” Voided Slabs 5-A-25

Table 5-A-26 Span Capability of Prestressed2'-2" Voided Slabs 5-A-26
Table 5-A-27 Span Capability of Prestressed1'-0" Solid Slabs 5-A-27
Table 5-A-28 Span Capability Precast Prestressed Double Tee Girders 5-A-28
Table 5-A-29 Span Capability Precast Prestressed Ribbed Girders 5-A-29
Table 5-A-30 Span Capability of Deck Bulb Tee Girders 5-A-30
Table 5-A-31 Design Charts for W35DG Deck Bulb Tee Girder 5-A-31
Table 5-A-32 Design Charts for W41DG Deck Bulb Tee Girder 5-A-32
Table 5-A-33 Design Charts for W53DG Deck Bulb Tee Girder 5-A-33
Table 5-A-34 Design Charts for W65DG Deck Bulb Tee Girder 5-A-34
Table 5-A-35 Span Capability of Post-Tensioned Spliced I-Girders 5-A-35
Table 5-A-36 Span Capability of Post-Tensioned Spliced Tub Girders 5-A-37
Figure 5-A-37 I-Girder Sections 5-A-39
Figure 5-A-38 Wide Flange I-Girder Sections 5-A-40
Figure 5-A-39 Bulb Tee Girder Sections 5-A-41
Figure 5-A-40 Wide Flange Bulb Tee Girder Sections 5-A-42
Figure 5-A-41 Trapezodial Tub Girder Sections 5-A-43
Figure 5-A-42 Trapezoidal Tub Girder with Top Flange Sections 5-A-44
Figure 5-A-43 Deck Blub Tee Girder Section 5-A-45
Figure 5-A-44 Precast Prestressed Slab Sections 5-A-46
Figure 5-A-45 Double Tee and Ribbed Deck Girder Sections 5-A-47
Figure 5-A-46 Spliced I-Girders Sections 5-A-48
Figure 5-A-47 Spliced Trapeziodal Tub Girders Sections 5-A-49
Figure 5-A-48 Single Span Prestressed Girder Construction Sequence 5-A-50
Figure 5-A-49 Multiple Span Prestressed Girder Construction Sequence 5-A-51
Figure 5-A-50 Single Span Prestressed Girder Construction Sequence 5-A-52
Figure 5-A-51 W42G Girder Details 1 of 2 ..... 5-A-53
Figure 5-A-52 W42G Girder Details 2 of 2 ..... 5-A-54
Figure 5-A-53 W42G End Diaphragm on Girder Details 5-A-55
Figure 5-A-54 W42G Abutment Type Pier Diaphragm Details 5-A-56
Figure 5-A-55 W42G Fixed Flush-Face Diaphragm at Intermediate Pier Details 5-A-57
Figure 5-A-56 W42G Fixed Recessed-Face Diaphragm at Intermediate Pier Details .. 5-A-58
Figure 5-A-57 W42G Hinged Diaphragm at Intermediate Pier Details 5-A-59
Figure 5-A-58 W42G Intermediate Diaphragm Details 5-A-60
Figure 5-A-59 W42G Miscelleneous Diaphragm Details 5-A-61
Figure 5-A-60 Multiple Simple Spans Intermediate Pier Details 5-A-62
Figure 5-A-61 W50G Girder Details 1 of 2 ..... 5-A-63
Figure 5-A-62 W50G Girder Details 2 of 2 ..... 5-A-64
Figure 5-A-63 W50G End Diaphragm on Girder Details 5-A-65
Figure 5-A-64 W50G Abutment Type Pier Diaphragm Details 5-A-66
Figure 5-A-65 W50G Fixed Flush-Face Diaphragm at Intermediate Pier Details 5-A-67
Figure 5-A-66 W50G Fixed Recessed-Face Diaphragm at Intermediate Pier Details .. 5-A-68
Figure 5-A-67 W50G Hinged Diaphragm at Intermediate Pier Details 5-A-69
Figure 5-A-68 W50G Intermediate Diaphragm Details 5-A-70
Figure 5-A-69 W50G Miscelleneous Diaphragm Details 5-A-71
Figure 5-A-70 W58G Girder Details 1 of 3 ..... 5-A-72
Figure 5-A-71 W58G Girder Details 2 of 3 ..... 5-A-73
Figure 5-A-72 W58G Girder Details 3 of 3 ..... 5-A-74
Figure 5-A-73 W58G End Diaphragm on Girder Details 5-A-75
Figure 5-A-74 W58G Abutment Type Pier Diaphragm Details 5-A-76
Figure 5-A-75 W58G Fixed Flush-Face Diaphragm at Intermediate Pier Details 5-A-77
Figure 5-A-76 W58G Fixed Recessed-Face Diaphragm at Intermediate Pier Details .. 5-A-78

Figure 5-A-77 W58G Hinge Diaphragm at Intermediate Pier Details 5-A-79
Figure 5-A-78 W58G Intermediate Diaphragm Details 5-A-80
Figure 5-A-79 W58G Miscelleneous Diaphragm Details..... 5-A-81
Figure 5-A-80 W74G Girder Details 1 of 3 ..... 5-A-82
Figure 5-A-81 W74G Girder Details 2 of 3 ..... 5-A-83
Figure 5-A-82 W74G Girder Details 3 of 3 ..... 5-A-84
Figure 5-A-83 W74G End Diaphragm on Girder Details..... 5-A-85
Figure 5-A-84 W58G Abutment Type Pier Diaphragm Details..... 5-A-86
Figure 5-A-85 W58G Fixed Flush-Face Diaphragm at Intermediate Pier Details 5-A-87
Figure 5-A-86 W58G Fixed Recessed-Face Diaphragm at Intermediate Pier Details .. 5-A-88
Figure 5-A-87 W58G Hinge Diaphragm at Intermediate Pier Details 5-A-89
Figure 5-A-88 W58G Intermediate Diaphragm Details 5-A-90
Figure 5-A-89 W58G Miscelleneous Diaphragm Details..... 5-A-91
Figure 5-A-90 WF42G GIRDER DETAILS 1 OF 3 ..... 5-A-92
Figure 5-A-91 WF42G GIRDER DETAILS 2 OF 3 ..... 5-A-93
Figure 5-A-92 WF42G GIRDER DETAILS 3 OF 3 ..... 5-A-94
Figure 5-A-93 WF50G GIRDER DETAILS 1 OF 3 ..... 5-A-95
Figure 5-A-94 WF50G GIRDER DETAILS 2 OF 3 ..... 5-A-96
Figure 5-A-95 WF50G GIRDER DETAILS 3 OF 3 ..... 5-A-97
Figure 5-A-96 WF58G GIRDER DETAILS 1 OF 3 ..... 5-A-98
Figure 5-A-97 WF58G GIRDER DETAILS 2 OF 3 ..... 5-A-99
Figure 5-A-98 WF58G GIRDER DETAILS 3 OF 3 ..... 5-A-100
Figure 5-A-99 WF74G GIRDER DETAILS 1 OF 3 ..... 5-A-101
Figure 5-A-100 WF74G GIRDER DETAILS 2 OF 3 ..... 5-A-102
Figure 5-A-101 WF74G GIRDER DETAILS 3 OF 3 ..... 5-A-103
Figure 5-A-102 WF74G End Diaphragm on Girder Details..... 5-A-104
Figure 5-A-103 WF74G Abutment Type Pier Diaphragm Details 5-A-105
Figure 5-A-104 WF74G Fixed Flush-Face Diaphragm at Intermediate Pier Details 5-A-106
Figure 5-A-105 WF74G Fixed Recessed-Face Diaphragm at Intermediate Pier Details..... 5-A-107
Figure 5-A-106 WF74G Hinge Diaphragm at Intermediate Pier Details 5-A-108
Figure 5-A-107 WF74G Intermediate Diaphragm Details 5-A-109
Figure 5-A-108 WF74G Miscelleneous Diaphragm Details 5-A-110
Figure 5-A-109 W83G GIRDER DETAILS 1 OF 3..... 5-A-111
Figure 5-A-110 W83G GIRDER DETAILS 2 OF 3..... 5-A-112
Figure 5-A-111 W83G GIRDER DETAILS 3 OF 3..... 5-A-113
Figure 5-A-112 W83G End Diaphragm on Girder Details..... 5-A-114
Figure 5-A-113 W83G Abutment Type Pier Diaphragm Details..... 5-A-115
Figure 5-A-114 W83G Fixed Flush-Face Diaphragm at Intermediate Pier Details 5-A-116
Figure 5-A-115 W83G Fixed Recessed-Face Diaphragm at Intermediate Pier Details 5-A-117
Figure 5-A-116 W83G Hinge Diaphragm at Intermediate Pier Details 5-A-118
Figure 5-A-117 W83G Intermediate Diaphragm Details 5-A-119
Figure 5-A-118 W83G Miscelleneous Diaphragm Details..... 5-A-120
Figure 5-A-119 W95G GIRDER DETAILS 1 OF 3..... 5-A-121
Figure 5-A-120 W95G GIRDER DETAILS 2 OF 3..... 5-A-122
Figure 5-A-121 W95G GIRDER DETAILS 3 OF 3..... 5-A-123
Figure 5-A-122 W95G End Diaphragm on Girder Details..... 5-A-124
Figure 5-A-123 W95G Abutment Type Pier Diaphragm Details..... 5-A-125
Figure 5-A-124 W95G Fixed Flush-Face Diaphragm at Intermediate Pier Details 5-A-126
Figure 5-A-125 W95G Fixed Recessed-Face Diaphragm at Intermediate Pier Details 5-A-127
Figure 5-A-126 W95G Hinge Diaphragm at Intermediate Pier Details 5-A-128

Figure 5-A-127 W95G Intermediate Diaphragm Details 5-A-129
Figure 5-A-128 W95G Miscelleneous Diaphragm Details..... 5-A-130
Figure 5-A-129 W32BTG GIRDER DETAILS 1 OF 3..... 5-A-131
Figure 5-A-130 W32BTG GIRDER DETAILS 2 OF 3..... 5-A-132
Figure 5-A-131 W32BTG GIRDER DETAILS 3 OF 3..... 5-A-133
Figure 5-A-132 W38BTG GIRDER DETAILS 1 OF 3..... 5-A-134
Figure 5-A-133 W38BTG GIRDER DETAILS 2 OF 3..... 5-A-135
Figure 5-A-134 W38BTG GIRDER DETAILS 3 OF 3..... 5-A-136
Figure 5-A-135 W62BTG GIRDER DETAILS 1 OF 3..... 5-A-137
Figure 5-A-136 W62BTG GIRDER DETAILS 2 OF 3..... 5-A-138
Figure 5-A-137 W62BTG GIRDER DETAILS 3 OF 3..... 5-A-139
Figure 5-A-138 Prestressed Trapezoidal Tub Girder Details 1 of 3 ..... 5-A-140
Figure 5-A-139 Prestressed Trapezoidal Tub Girder Details 2 of 3 ..... 5-A-141
Figure 5-A-140 Prestressed Trapezoidal Tub Girder Details 3 of 3 ..... 5-A-142
Figure 5-A-141 Prestressed Trapezoidal Tub Girder End Diaphragm on Girder Details..... 5-A-143
Figure 5-A-142 Prestressed Trapezoidal Tub Girder Raised Crossbeam Details 5-A-144
Figure 5-A-143 Prestressed Trapezoidal Tub Girder Miscellaneous Details..... 5-A-145
Figure 5-A-144 Trapezoidal Tub S-I-P Deck Panel Girder - Details 1 of 4 ..... 5-A-146
Figure 5-A-145 Trapezoidal Tub S-I-P Deck Panel Girder - Details 2 of 4 ..... 5-A-147
Figure 5-A-146 Trapezoidal Tub S-I-P Deck Panel Girder - Details 3 of 4 ..... 5-A-148
Figure 5-A-147 Trapezoidal Tub S-I-P Deck Panel Girder - Details 4 of 4 ..... 5-A-149
Figure 5-A-148 Trapezoidal Tub S-I-P Deck Panel Girder - End Diaphragm on Girder Details..... 5-A-150
Figure 5-A-149 Trapezoidal Tub S-I-P Deck Panel Girder - Raised Crossbeam Details..... 5-A-151
Figure 5-A-150 Trapezoidal Tub S-I-P Deck Panel Girder - Miscellaneous Diaphragm Details 5-A-152
Figure 5-A-151 Precast Prestressed Stay-in-Place Deck Panel Details..... 5-A-153
Figure 5-A-152 Precast Prestressed 1’-0” Solid Slab Details 1 of 2 ..... 5-A-154
Figure 5-A-153 Precast Prestressed 1’-0” Solid Slab Details 2 of 2 ..... 5-A-155
Figure 5-A-154 Precast Prestressed 1’-6” Voided Slab Details 1 of 3..... 5-A-156
Figure 5-A-155 Precast Prestressed 1’-6” Voided Slab Details 2 of 3..... 5-A-157
Figure 5-A-156 Precast Prestressed 1’-6” Voided Slab Details 3 of 3..... 5-A-158
Figure 5-A-157 Precast Prestressed 2’-2” Voided Slab Details 1 of 3..... 5-A-159
Figure 5-A-158 Precast Prestressed 2’-2” Voided Slab Details 2 of 3..... 5-A-160
Figure 5-A-159 Precast Prestressed 2’-2” Voided Slab Details 3 of 3..... 5-A-161
Figure 5-A-160 Precast Prestressed Slab Layout..... 5-A-162
Figure 5-A-161 Precast Prestressed Slab End Pier Details 1 of 2 ..... 5-A-163
Figure 5-A-162 Precast Prestressed Slab End Pier Details 2 of 2 ..... 5-A-164
Figure 5-A-163 Precast Prestressed Slab Intermediate Piers Details 1 of 2 ..... 5-A-165
Figure 5-A-164 Precast Prestressed Slab Intermediate Piers Details 2 of 2 ..... 5-A-166
Figure 5-A-165 Precast Prestressed Ribbed Girder Details 1 of 2 ..... 5-A-167
Figure 5-A-166 Precast Prestressed Ribbed Girder Details 2 of 2 ..... 5-A-168
Figure 5-A-167 Precast Prestressed Ribbed Girder Pier Details 5-A-169
Figure 5-A-168 Precast Prestressed Double T Details 1 of 2 ..... 5-A-170
Figure 5-A-169 Precast Prestressed Double T Details 2 of 2 ..... 5-A-171
Figure 5-A-170 W35DG Deck Bulb Tee Girder Details 1 of 2 ..... 5-A-172
Figure 5-A-171 W35DG Deck Bulb Tee Girder Details 2 of 2 ..... 5-A-173
Figure 5-A-172 W35DG Deck Bulb Tee Diaphragm Details..... 5-A-174
Figure 5-A-173 W41DG Deck Bulb Tee Girder Details 1 of 2 ..... 5-A-175

Figure 5-A-174 W41DG Deck Bulb Tee Girder Details 2 of 2 ..... 5-A-176
Figure 5-A-175 W41DG Deck Bulb Tee Diaphragm Details 5-A-177
Figure 5-A-176 W53DG Deck Bulb Tee Girder Details 1 of 2 ..... 5-A-178
Figure 5-A-177 W53DG Deck Bulb Tee Girder Details 2 of 2 ..... 5-A-179
Figure 5-A-178 W53DG Deck Bulb Tee Diaphragm Details 5-A-180
Figure 5-A-179 W65DG Deck Bulb Tee Girder Details 1 of 2 ..... 5-A-181
Figure 5-A-180 W65DG Deck Bulb Tee Girder Details 2 of 2 ..... 5-A-182
Figure 5-A-181 W65DG Deck Bulb Tee Girder Diaphragm Details 5-A-183
Figure 5-A-182 W65DG Deck Bulb Tee Girder Misc. Diaphragm Details 5-A-184
Figure 5-A-183 WF74PTG Spliced Girder Details 1 of 5 ..... 5-A-185
Figure 5-A-184 WF74PTG Spliced Girder Details 2 of 5 ..... 5-A-186
Figure 5-A-185 WF74PTG Spliced Girder Details 3 of 5 ..... 5-A-187
Figure 5-A-186 WF74PTG Spliced Girder Details 4 of 5 ..... 5-A-188
Figure 5-A-187 WF74PTG Spliced Girder Details 5 of 5 ..... 5-A-189
Figure 5-A-188 W83PTG Spliced Girder Details 1 of 5 ..... 5-A-190
Figure 5-A-189 W83PTG Spliced Girder Details 2 of 5 ..... 5-A-191
Figure 5-A-190 W83PTG Spliced Girder Details 3 of 5 ..... 5-A-192
Figure 5-A-191 W83PTG Spliced Girder Details 4 of 5 ..... 5-A-193
Figure 5-A-192 W83PTG Spliced Girder Details 5 of 5 ..... 5-A-194
Figure 5-A-193 W95PTG Spliced Girder Details 1 of 5 ..... 5-A-195
Figure 5-A-194 W95PTG Spliced Girder Details 2 of 5 ..... 5-A-196
Figure 5-A-195 W95PTG Spliced Girder Details 3 of 5 ..... 5-A-197
Figure 5-A-196 W95PTG Spliced Girder Details 4 of 5 ..... 5-A-198
Figure 5-A-197 W95PTG Spliced Girder Details 5 of 5 ..... 5-A-199
Figure 5-A-198 Trapezoidal Tub Spliced Girder Details 1 of 5 ..... 5-A-200
Figure 5-A-199 Trapezoidal Tub Spliced Girder Details 2 of 5 ..... 5-A-201
Figure 5-A-200 Trapezoidal Tub Spliced Girder Details 3 of 5 ..... 5-A-202
Figure 5-A-201 Trapezoidal Tub Spliced Girder Details 4 of 5 ..... 5-A-203
Figure 5-A-202 Trapezoidal Tub Spliced Girder Details 5 of 5 ..... 5-A-204
Figure 5-A-203 Trapezoidal Tub Spliced Girder End Diaphragm on Girder Details 5-A-205
Figure 5-A-204 Trapezoidal Tub Spliced Girder Raised Crossbeam Details 5-A-206
Figure 5-A-205 Trapezoidal Tub Spliced Girder Miscellaneous Details 5-A-207
Figure 5-A-206 Trapezoidal Tub S-I-P Deck Panel Spliced Girder - Details 1 of 5 ..... 5-A-208
Figure 5-A-207 Trapezoidal Tub S-I-P Deck Panel Spliced Girder - Details 2 of 5 ..... 5-A-209
Figure 5-A-208 Trapezoidal Tub S-I-P Deck Panel Spliced Girder - Details 3 of 5 ..... 5-A-210
Figure 5-A-209 Trapezoidal Tub S-I-P Deck Panel Spliced Girder - Details 4 of 5 ..... 5-A-211
Figure 5-A-210 Trapezoidal Tub S-I-P Deck Panel Spliced Girder - Details 5 of 5 ..... 5-A-212
Figure 5-A-211 Trapezoidal Tub S-I-P Deck Panel Girder End Diaphragm on Girder Details 5-A-213
Figure 5-A-212 Trapezoidal Tub S-I-P Deck Panel Girder - Raised Crossbeam Details 5-A-214
Figure 5-A-213 Trapezoidal Tub S-I-P Deck Panel Girder - Miscellaneous Diaphragm Details 5-A-215
Figure 5-A-214 Vacant 5-A-216
Figure 5-A-215 Vacant 5-A-217

Appendix B

Appendix 5-B-1 "A" Dimension for Prestressed Girder Bridges 5-B-1
Appendix 5-B-2 Pre-approved Post-Tensioning Anchorages 5-B-3
Appendix 5-B-3 Existing Bridge Widenings 5-B-5
Appendix 5-B-4 P.T. Box Girder Bridges Single Span 5-B-7

Appendix 5-B-5 ..... 5-B-13
Design Example 1 Prestressed Girder Design 5-B-13
Design Example 2 Cast-in-Place Concrete Slab Design 5-B-55
Design Example 3 Precast Slab Design Stay-In-Place (SIP) Deck Panel 5-B-75
Design Example 4 Deck Bulb Tee and Ribbed Girder Design 5-B-95
Design Example 5 Solid and Voided Slab Design 5-B-101
Design Example 6 Positive EQ Reinforcement at Interior Pier of a Prestressed Girder 5-B-139
Design Example 7 Noise Wall Type D-2K (Precast Panel on Shaft) 5-B-143
Design Example 8 Construction Reinforcement in Crossbeam 5-B-157
Design Example 9 Stut and Tie Design 5-B-159
Design Example 10 Crossbeam Shear and Torsion Design 5-B-165
Design Example 11 Torsion and Shear Capacity of Reinforced Concrete Beams 5-B-169
Design Example 12 Strain Compatibility Approach for Flexural Capacity 5-B-173

Chapter 6 Structural Steel

6.0 Structural Steel 6-1
6.0.1 Introduction 6-1
6.1 Design Considerations 6-1
6.1.1 Codes, Specification, and Standards 6-1
6.1.2 Preferred Practice 6-2
6.1.3 Preliminary Girder Proportioning 6-2
6.1.4 Estimating Structural Steel Weights 6-3
6.1.5 Bridge Steels 6-6
6.1.6 Available Plate Sizes 6-7
6.1.7 Girder Segment Sizes 6-7
6.1.8 Computer Programs 6-7
6.1.9 Fasteners 6-8
6.2 Girder Bridges 6-10
6.2.1 General 6-10
6.2.2 I-Girders 6-10
6.2.3 Tub or Box Girders 6-11
6.2.4 Special Live Load Criteria for Curved Girders 6-12
6.3 Design of I-Girders 6-13
6.3.1 Limit States for LRFD 6-13
6.3.2 Composite Section 6-13
6.3.3 Flanges 6-13
6.3.4 Webs 6-14
6.3.5 Transverse Stiffeners 6-14
6.3.6 Longitudinal Stiffeners 6-14
6.3.7 Bearing Stiffeners 6-14
6.3.8 Crossframes 6-15
6.3.9 Bottom Laterals 6-16
6.3.10 Bolted Field Splice for Girders 6-16
6.3.11 Camber 6-17
6.3.12 Roadway Slab Placement Sequence 6-18
6.3.13 Bridge Bearings for Steel Girders 6-19

6.3.14 Surface Roughness and Hardness 6-19
6.3.15 Welding 6-20
6.3.16 Shop Assembly 6-21
6.4 Plan Details 6-23
6.4.1 General 6-23
6.4.2 Structural Steel Notes 6-23
6.4.3 Framing Plan 6-23
6.4.4 Girder Elevation 6-23
6.4.5 Typical Girder Details 6-24
6.4.6 Crossframe Details 6-24
6.4.7 Camber Diagram and Bearing Stiffener Rotation 6-24
6.4.8 Roadway Slab 6-24
6.4.9 Handrail Details and Inspection Access 6-25
6.5 Shop Plan Review 6-26
6.99 References 6-26
Appendix 6-A
Figure 6-A-1 Steel Plate Girder Framing Plan 6-A-1
Figure 6-A-2 Steel Plate Girder Girder Elevation 6-A-2
Figure 6-A-3 Steel Plate Girder Girder Details 6-A-3
Figure 6-A-4 Steel Plate Girder Field Splice 6-A-4
Figure 6-A-5 Steel Plate Girder Crossframes 6-A-5
Figure 6-A-6 Steel Plate Girder Camber Diagram 6-A-6
Figure 6-A-7 Steel Plate Girder Roadway Section 6-A-7
Figure 6-A-8 Steel Plate Girder Slab Plan 6-A-8
Figure 6-A-9 Handrail 6-A-9

Chapter 7 Substructure Design

7.1 General Substructure Considerations 7-1
7.1.1 Foundation Design Process 7-1
7.1.2 Foundation Limit States and Factors 7-4
7.1.3 Substructure and Foundation Loads 7-5
7.1.3 Substructure and Foundation Loads (continued) 7-6
7.1.4 Concrete Class for Substructure 7-8
7.1.5 Foundation Seals 7-9
7.1.5.C.1 Timber Pile Footing Example 7-11
7.2 Foundation Modeling 7-12
7.2.1 General Modeling Concepts 7-12
7.2.2 Substructure Analysis Flow Chart 7-15
7.2.3 Bridge Model Section Properties 7-18
7.2.4 Bridge Model Verification 7-19
7.2.5 Deep Foundation Modeling 7-20
7.2.6 Spread Footing Modeling 7-32
7.3 Column Design 7-36
7.3.1 Preliminary Plan Stage 7-36
7.3.2 General Column Criteria 7-36
7.3.3 Column Design Flow Chart 7-37
7.3.4 Slenderness Effects 7-38
7.3.5 Moment Magnification Method 7-38
7.3.6 Second-Order Analysis 7-38

7.4 Column Reinforcement 7-40
7.4.1 Minimum Longitudinal Reinforcement Ratio 7-40
7.4.2 Longitudinal Splices 7-40
7.4.3 Ties and Spirals 7-42
7.4.4 Longitudinal Development and Confinement Steel 7-45
7.4.5 Column Hinges 7-47
7.5 Abutment Design and Details 7-49
7.5.1 Abutment Types 7-49
7.5.2 Embankment at Abutments 7-52
7.5.3 Abutment Loading 7-52
7.5.4 WSDOT Temporary Construction Load Cases 7-53
7.5.5 Abutment Bearings and Girder Stops 7-53
7.5.6 Abutment Expansion Joints 7-55
7.5.7 Open Joint Details 7-55
7.5.8 Construction Joints 7-57
7.5.9 Abutment Wall Design 7-58
7.5.10 Drainage and Backfilling 7-59
7.6 Wing/Curtain Wall at Abutments 7-61
7.6.1 Traffic Barrier Loads 7-61
7.6.2 Wingwall BDM Design 7-61
7.6.3 Wing wall Detailing 7-61
7.7 Footing Design 7-62
7.7.1 General Footing Criteria 7-62
7.7.2 Loads and Load Factors 7-63
7.7.3 Geotechnical Report Summary 7-64
7.7.4 Spread Footing Structural Design 7-65
7.7.4.A Abutment Spread Footing Force Diagram 7-65
7.7.4.B Bearing Stress 7-66
7.7.4.C Failure By Sliding 7-67
7.7.4.D Overturning Stability 7-68
7.7.4.E Footing Settlement 7-68
7.7.4.F Concrete Design 7-68
7.7.5 Footing Concrete Design on Pile Supports 7-69
7.7.5.A Pile Embedment, Clearance, and Rebar Mat Location 7-70
7.7.5.B Pile Pullout and Details 7-71
7.7.5.C Concrete Design 7-71
7.8 Drilled Shafts 7-72
7.8.1 Drilled Shaft Design 7-72
7.8.2 Lateral Load Analysis 7-73
7.9 Piles and Piling 7-74
7.9.1 Pile Types 7-74
7.9.2 Pile Design Flow Chart 7-76
7.9.3 General Pile Design 7-77
7.9.4 Pile Axial Design 7-78
7.9.5 Pile Lateral Design 7-79
7.9.6 Pile Tip Elevations and Quantities 7-79

Chapter 8 Walls & Buried Structures

8.4 Retaining Walls 8-1
8.4.1 General 8-1
8.4.2 Common Types of Walls 8-1
8.4.3 Design 8-3
8.4.4 Miscellaneous Items 8-6
8.5 Miscellaneous Underground Structures 8-10
8.5.1 General 8-10
8.5.2 Design 8-10
8.5.3 References 8-13

Appendix A-8

Figure 8-A-1 SEW Wall Elevation 8-A-1
Figure 8-A-2 SEW Wall Section 8-A-2
Figure 8-A-3 Soil Nail Layout 8-A-3
Figure 8-A-4 Soil Nail Wall Fascia Panel Details 8-A-4
Figure 8-A-5 Soil Nail Wall Section 8-A-5
Figure 8-A-6 Cable Fence 8-A-6
Figure 8-A-7 Cable Fence - Top Mount 8-A-7
Figure 8-A-8 Soldier Pile/Tieback Wall Elevation 8-A-8
Figure 8-A-9 Soldier Pile/Tieback Wall Details 1 of 2 ..... 8-A-9
Figure 8-A-10 Soldier Pile/Tieback Wall Details 2 of 2 ..... 8-A-10
Figure 8-A-11 Soldier Pile/Tieback Wall Fascia Panel Details 8-A-11
Figure 8-A-12 Soldier Pile/Tieback Wall Permanent Ground Anchor Details 8-A-12
Figure 8-A-13 Pre-approved Proprietary Wall Systems 8-A-13

Chapter 9 Bearings & Expansion Joints

9.1 Expansion Joints 9-1
9.1.1 General Considerations 9-1
9.1.2 General Design Criteria 9-2
9.1.3 Small Movement Range Joints 9-4
9.1.3.1 Compression Seals 9-4
9.1.3.2 Rapid-Cure Silicone Sealants 9-6
9.1.3.3 Asphaltic Plug Joints 9-8
9.1.4 Medium Movement Range Joints 9-8
9.1.4.1 Steel Sliding Plate Joints 9-8
9.1.4.2 Strip Seal Joints 9-9
9.1.4.3 Bolt-down Panel Joints 9-11
9.1.5 Large Movement Range Joints 9-12
9.1.5.1 Steel Finger Joints 9-12
9.1.5.2 Modular Expansion Joints 9-12
9.1.5.2.1 Operational Characteristics 9-13
9.1.5.2.2 Movement Design 9-14
9.1.5.2.3 Review of Shop Drawings and Structural Design Calculations 9-16
9.1.5.2.4 Construction Considerations 9-17
9.2 Bearings 9-18
9.2.1 General Considerations 9-18
9.2.2 Force Considerations 9-18
9.2.3 Movement Considerations 9-18
9.2.4 Detailing Considerations 9-19
9.2.5 Bearing Types 9-19

9.2.5.1 Elastomeric Bearings 9-19
9.2.5.2 Fabric Pad Sliding Bearings 9-21
9.2.5.3 Pin Bearings 9-23
9.2.5.4 Rocker and Roller Type Bearings 9-23
9.2.5.5 Spherical Bearings 9-23
9.2.5.6 Disk Bearings 9-24
9.2.5.7 Seismic Isolation Bearings 9-24
9.2.6 Miscellaneous Details 9-24
9.2.6.1 Temporary Support before Grouting Masonry Plate 9-24
9.2.6.2 Anchor Bolts 9-25
9.2.7 Contract Drawing Representation 9-25
9.2.8 Shop Drawing Review 9-25
9.2.9 Bearing Replacement Considerations 9-25
Appendix 9-A
Figure 9-A-1 Expansion Joint Details Compression Seal 9-A-1
Figure 9-A-2 Expansion Joint Details Strip Seal 9-A-2
Figure 9-A-3 Silicone Seal Expansion Joint Details 9-A-3

Chapter 10 Signs, Barriers, Approach Slabs & Utilities

10.1 Sign and Luminaire Supports 10-1
10.1.1 Loads 10-1
10.1.2 Bridge Mounted Signs 10-3
10.1.3 Sign Bridges Mounted on Bridges 10-7
10.1.4 Monotube Sign Structures 10-7
10.1.5 Foundations 10-11
10.1.6 Truss Sign Bridges: Foundation Sheet Design Guidelines 10-12
10.2 Bridge Traffic Barriers 10-13
10.2.1 General Guidelines 10-13
10.2.2 Bridge Railing Test Levels 10-13
10.2.3 Available WSDOT Designs 10-13
10.2.4 Design Criteria 10-17
10.3 At Grade Cast-in-Place Barriers 10-20
10.3.1 Median Barriers 10-20
10.3.2 Shoulder Barriers 10-20
10.4 Bridge Traffic Barrier Rehabilitation 10-21
10.4.1 Policy 10-21
10.4.2 Guidelines 10-21
10.4.3 Design Criteria 10-21
10.4.4 WSDOT Bridge Inventory of Bridge Rails 10-22
10.4.5 Available Retrofit Designs 10-22
10.4.6 Available Replacement Designs 10-22
10.5 Bridge Railing 10-23
10.5.1 Design 10-23
10.5.2 Railing Types 10-23
10.6 Bridge Approach Slabs 10-24
10.6.1 Notes to Region for Preliminary Plan 10-24
10.6.2 Approach Slab Design and Detailing 10-25
10.6.3 Approach Expansion Joints 10-25
10.6.4 Skewed Approach Slabs 10-26
10.6.5 Bridge Approach Approach Detailing 10-27
10.6.6 Pavement Seats on Existing Bridges 10-27

10.7 Traffic Barrier on Approach Slabs 10-28
10.7.1 Approach Slab over Wing Walls, Cantilever Walls or Geosynthetic Walls 10-29
10.7.2 Approach Slab over SE Walls 10-29
10.8 Utilities Installed with New Construction 10-31
10.8.1 General Concepts 10-31
10.8.2 Utility Design Criteria 10-31
10.8.3 Box Girder Bridges 10-33
10.8.4 Traffic Barrier Conduit 10-34
10.8.5 Conduit Types 10-35
10.8.6 Utility Supports 10-35
10.9 Utility Review Procedure for Installation on Existing Bridges 10-37
10.9.1 Utility Review Checklist 10-37
10.10 Drainage Design 10-39
Appendix 10-A
Figure 10-A-1 Monotube Sign Structures Sign Bridge Layout 10-A-1
Figure 10-A-2 Monotube Sign Structures Cantilever Layout 10-A-2
Figure 10-A-3 Monotube Sign Structures Structural Details 1 ..... 10-A-3
Figure 10-A-4 Monotube Sign Structures Structural Details 2 ..... 10-A-4
Figure 10-A-5 Monotube Sign Structures Foundation Type 1 ..... 10-A-5
Figure 10-A-6 Monotube Sign Structures Foundation Types 2 and 3 ..... 10-A-6
Figure 10-A-7 Monotube Sign Structures Double Faced Barrier Foundation 10-A-7
Figure 10-A-8 Monotube Sign Structures Single Slope Barrier Foundation 10-A-8
Figure 10-A-9 Truss Sign Structures Double Faced Barrier Foundation 10-A-9
Figure 10-A-10 Traffic Barrier – Shape F Details 1 of 3 ..... 10-A-10
Figure 10-A-11 Traffic Barrier - Shape F Details 2 of 3 ..... 10-A-11
Figure 10-A-12 Traffic Barrier - Shape F Details 3 of 3 ..... 10-A-12
Figure 10-A-13 Traffic Barrier - Shape F Flat Slab - Details 1 of 3 ..... 10-A-13
Figure 10-A-14 Traffic Barrier - Shape F Flat Slab - Details 2 of 3 ..... 10-A-14
Figure 10-A-15 Traffic Barrier - Shape F Flat Slab - Details 3 of 3 ..... 10-A-15
Figure 10-A-16 Traffic Barrier - Single Slope Details 1 of 3 ..... 10-A-16
Figure 10-A-17 Traffic Barrier - Single Slope Details 2 of 3 ..... 10-A-17
Figure 10-A-18 Traffic Barrier - Single Slope Details 3 of 3 ..... 10-A-18
Figure 10-A-19 Pedestrian Barrier Details 1 of 3 ..... 10-A-19
Figure 10-A-20 Pedestrian Barrier Details 2 of 3 ..... 10-A-20
Figure 10-A-21 Pedestrian Barrier Details 3 of 3 ..... 10-A-21
Figure 10-A-22 Traffic Barrier - Shape F 42” Details 1 of 3 ..... 10-A-22
Figure 10-A-23 Traffic Barrier - Shape F 42” Details 2 of 3 ..... 10-A-23
Figure 10-A-24 Traffic Barrier - Shape F 42” Details 3 of 3 ..... 10-A-24
Figure 10-A-25 Traffic Barrier - Single Slope 42” Details 1 of 3 ..... 10-A-25
Figure 10-A-26 Traffic Barrier - Single Slope 42” Details 2 of 3 ..... 10-A-26
Figure 10-A-27 Traffic Barrier - Single Slope 42” Details 3 of 3 ..... 10-A-27
Figure 10-A-28 Traffic Barrier - Shape F Luminaire Anchor Details 10-A-28
Figure 10-A-29 Traffic Barrier - Single Slope Lumiaire Anchor Details 10-A-29
Figure 10-A-30 Thrie Beam Retrofit Concrete Balster 10-A-30
Figure 10-A-31 Thrie Beam Retrofit Concrete Railbase 10-A-31
Figure 10-A-32 Thrie Beam Retrofit Concrete Curb 10-A-32
Figure 10-A-33 WP Thrie Beam Retrofit SL1 - Details 1 Of 2 ..... 10-A-33
Figure 10-A-34 WP Thrie Beam Retrofit SL1 - Details 2 Of 3 ..... 10-A-34
Figure 10-A-35 Traffic Barrier - Shape F Rehabilitation Rehabilitation-Details 1 of 3 10-A-35
Figure 10-A-36 Traffic Barrier - Shape F Rehabilitation - Details 2 of 3 ..... 10-A-36
Figure 10-A-37 Traffic Barrier - Shape F Rehabilitation - Details 3 of 3 ..... 10-A-37

Figure 10-A-38 Bridge Railing Type Pedestrain Details 1 of 2 ..... 10-A-38
Figure 10-A-39 Bridge Railing Type Pedestrian Details 2 of 2 ..... 10-A-39
Figure 10-A-40 Bridge Railing Type BP Details 1 of 2 ..... 10-A-40
Figure 10-A-41 Bridge Railing Type BP Details 2 of 2 ..... 10-A-41
Figure 10-A-42 Bridge Railing Type S-BP Details 1 of 2 ..... 10-A-42
Figure 10-A-43 Bridge Railing Type S-BP Details 2 of 2 ..... 10-A-43
Figure 10-A-44 Pedestrian Railing Details 1 of 2 ..... 10-A-44
Figure 10-A-45 Pedestrian Railing Details 2 of 2 ..... 10-A-45
Figure 10-A-46 Bridge Railing Type Chain Link Snow Fence 10-A-46
Figure 10-A-47 Bridge Approach Slab Details 1 of 2 ..... 10-A-47
Figure 10-A-48 Bridge Approach Slab Details 2 of 2 ..... 10-A-48
Figure 10-A-49 Pavement Seat Repair Details 10-A-49
Figure 10-A-50 Section Pavement Seat Repair Details 10-A-50
Figure 10-A-51 Utility Hangers for Prestressed Girders 10-A-51
Figure 10-A-52 Utility Hanger Details for Concrete Box Structures 10-A-52
Figure 10-A-53 Utility Hanger Details 10-A-53
Figure 10-A-54 Bridge Drain Modification 10-A-54
Figure 10-A-55 Bridge Drains Types 2 thru 5 Modification for Overlay 10-A-55

Chapter 11 Detailing Practice

11.1 Detailing Practice 11-1
11.1.1 Standard Office Practices 11-1
11.1.2 Bridge Office Standard Drawings and Office Examples 11-6
11.1.3 Plan Sheets 11-6
11.1.4 Structural Steel 11-9
11.1.5 Abbreviations 11-12

Chapter 12 Quantities, Costs & Specifications

12.1 Quantities - General 12-1
12.1.1 Cost Estimating Quantities 12-1
12.1.2 Not Included in Bridge Quantities List 12-1
12.2 Computation of Quantities 12-2
12.2.1 Responsibilities 12-2
12.2.2 Procedure for Computation 12-2
12.2.3 Data Source 12-3
12.2.4 Accuracy 12-3
12.2.5 Excavation 12-3
12.2.6 Shoring or Extra Excavation, Class A 12-7
12.2.7 Piling 12-9
12.3 Construction Costs 12-9
12.3.1 Introduction 12-9
12.3.2 Factors Affecting Costs 12-9
12.3.2.1 Type of Structure 12-9
12.3.2.2 Location of Project Site 12-9
12.3.2.3 Size of Project Contract 12-10
12.3.2.4 Foundation Requirements 12-10
12.3.2.5 Sequencing of Project 12-10
12.3.3 Development of Cost Estimates 12-10
12.3.3.1 Types 12-10
12.3.3.2 Responsibilities 12-11

12.3.3.3 Documentation 12-11
12.3.3.4 Cost Data 12-11
12.4 Construction Specifications and Estimates 12-12
12.4.1 General 12-12
12.4.2 Definitions 12-12
12.4.3 General Bridge S&E Process 12-13
12.4.4 Reviewing Bridge Plans 12-14
12.4.5 Preparing the Bridge Cost Estimates 12-15
12.4.6 Preparing the Bridge Specifications 12-16
12.4.7 Preparing the Bridge Working Day Schedule 12-17
12.4.8 Reviewing Projects Prepared by Consultants 12-17
12.4.9 Submitting the PS&E Package 12-18
12.4.10 PS&E Review Period and Turn-in for AD Copy 12-19
Appendix 12-A
Figure 12-A-1 Not Included In Bridge Quantities List 12-A-1
Figure 12-A-2 Bridge Quantities (Page 1 of 6) 12-A-2
Figure 12-A-2 Bridge Quantities (Continued Page 2 of 6) 12-A-3
Figure 12-A-2 Bridge Quantities (Continued Page 3 of 6) 12-A-4
Figure 12-A-2 Bridge Quantities (Continued Page 4 of 6) 12-A-5
Figure 12-A-2 Bridge Quantities (Continued Page 5 of 6) 12-A-6
Figure 12-A-2 Bridge Quantities (Continued Page 6 of 6) 12-A-7
Figure 12-A-3 Bridge and Structures 12-A-8
Figure 12-A-3 Bridge and Structures (Continued) 12-A-9
Figure 12-A-4 Substructure 12-A-10
Figure 12-A-5 Superstructre 12-A-11
Figure 12-A-6 Miscellaneous 12-A-12
Figure 12-A-7 Construction Time Rates 12-A-13
Appendix 12-B
Figure 12-B-1 Cost Estimate Summary 12-B-1
Figure 12-B-2 Construction Working Day Schedule 12-B-2

Chapter 13 Bridge Load Rating

13.1 General 13-1
13.1.1 WSDOT Rating (LRFR) 13-1
13.1.1.1 Strength Method (LRFR) 13-2
13.1.1.2 Service Method (LRFR) 13-2
13.1.1.3 Resistance Factors (LRFR) 13-4
13.1.1.4 Load Factors (LRFR) 13-4
13.1.1.5 Impact (LRFR) 13-4
13.1.1.6 Live Load Reduction Factors (LRFR) 13-4
13.1.1.7 Live Loads (LRFR) 13-5
13.1.1.8 Rating Trucks 13-5
13.1.2 NBI Rating (LFR) 13-7
13.1.2.1 Strength Method (LFR) 13-7
13.1.2.2 Service Method (LFR) 13-8
13.1.2.3 Resistance Factors (LFR) 13-8
13.1.2.4 Live Loads 13-8
13.1.2.5 Impact (LFR) 13-9
13.1.2.6 Live Load Reduction Factors (LFR) 13-9

13.2 Special Rating Criteria 13-10
13.2.1 Dead Loads 13-10
13.2.2 Live Load Distribution Factors 13-10
13.2.3 Reinforced Concrete Structures 13-10
13.2.4 Concrete Decks 13-10
13.2.5 Concrete Crossbeams 13-10
13.2.6 In-Span Hinges 13-10
13.2.7 Concrete Box Girder Structures 13-11
13.2.8 Prestressed Concrete Girder Structures 13-11
13.2.9 Concrete Slab Structures 13-11
13.2.10 Steel Structures 13-11
13.2.11 Steel Floor Systems 13-11
13.2.12 Steel Truss Structures 13-11
13.2.13 Timber Structures 13-11
13.2.14 Widened or Rehabilitated Structures 13-12
13.3 Load Rating Software 13-13
13.4 Load Rating Reports 13-14
13.5 Bibliography 13-15
Appendix 13-A
Figure 13-A-1 Bridge Rating Summary 13-A-1

Contents

Chapter 1 General Information

1.1 Manual Description 1-1
- 1.1.1 Purpose ... 1-1
- 1.1.2 Specifications ... 1-1
- 1.1.3 Format ... 1-1
- 1.1.4 Revisions ... 1-2

1.2 Bridge and Structures Office Organization ... 1-4
- 1.2.1 General ... 1-4
- 1.2.2 Organizational Elements of the Bridge Office ... 1-4
- 1.2.3 Design Unit Responsibilities and Expertise ... 1-7

1.3 Quality Control/Quality Assurance (QC/QA) Procedure ... 1-8
- 1.3.0 General ... 1-8
- 1.3.1 Design/Check Procedures ... 1-8
- 1.3.2 Design/Check Calculation File ... 1-17
- 1.3.3 PS&E Review Period ... 1-18
- 1.3.4 Addenda ... 1-18
- 1.3.5 Shop Plans and Permanent Structure Construction Procedures ... 1-18
- 1.3.6 Contract Plan Changes (Change Orders and As-Builts) ... 1-21
- 1.3.7 Archiving Design Calculations, Design Files, and S&E Files ... 1-22
- 1.3.8 Public Disclosure Policy Regarding Bridge Plans ... 1-23
- 1.3.9 Use of Computer Software ... 1-24

1.4 Coordination With Other Divisions and Agencies ... 1-25
- 1.4.1 Preliminary Planning Phase ... 1-25
- 1.4.2 Final Design Phase ... 1-25

1.5 Bridge Design Scheduling ... 1-26
- 1.5.1 General ... 1-26
- 1.5.2 Preliminary Design Schedule ... 1-26
- 1.5.3 Final Design Schedule ... 1-26

1.6 Guidelines for Bridge Site Visits ... 1-29
- 1.6.1 Bridge Rehabilitation Projects ... 1-29
- 1.6.2 Bridge Widening and Seismic Retrofits ... 1-29
- 1.6.3 Rail and Minor Expansion Joint Retrofits ... 1-29
- 1.6.4 New Bridges ... 1-29
- 1.6.5 Bridge Demolition ... 1-30
- 1.6.6 Proximity of Railroads Adjacent to the Bridge Site ... 1-30

1.99 Bibliography ... 1-30

Appendix 1-A
- Figure 1-A-1 Special Provisions Checklist ... 1-A-1
- Figure 1-A-2 Breakdown of Project Manhours Required Form ... 1-A-7
- Figure 1-A-3 Monthly Project Progress Report Form ... 1-A-8

1.1 Manual Description

1.1.1 Purpose

The Bridge Design Manual (BDM) is a guide for those who design bridges for the Washington State Department of Transportation (WSDOT). The BDM supplements the AASHTO LRFD Specifications. It explains differences where it deviates from the AASHTO LRFD Specifications. It contains standardized design details and methods, which are based on years of experience.

The BDM is a dynamic document, which constantly changes because of the creativity and innovative skills of our bridge designers and structural detailers. It is not intended for the design of unusual structures or to inhibit the designer in the exercise of engineering judgment. There is no substitute for experience, good judgment, and common sense.

1.1.2 Specifications

The AASHTO LRFD Bridge Design Specifications and the WSDOT Bridge Design Manual (BDM) are the basic documents used to design highway bridges and structures in Washington State.

The WSDOT BDM supplements the AASHTO Specifications by providing additional direction, design aides, examples, and information on office practice. The BDM takes precedence where conflict exists between the BDM and the AASHTO Specifications. The WSDOT Bridge Design Engineer will provide guidance where a conflict still exists.

The BDM does not duplicate the AASHTO Specifications. References are listed at the end of each chapter.

1.1.3 Format

A. General

The Bridge Design Manual consists of two volumes with each chapter organized as follows:

Criteria or other information

Appendix A (printed on yellow paper) Design Aids

Appendix B (printed on salmon paper) Design Examples

B. Chapters

1. General Information
2. Preliminary Design
3. Loads
4. Seismic Design and Retrofit
5. Concrete Structures
6. Steel Design
7. Substructure
8. Walls and Buried Structures

9. Bearings and Expansion Joints
10. Traffic Barriers, Sign Structures, Approach Slabs, Utility Supports
11. Detailing Practice
12. Quantities, Construction Costs, and Specifications
13. Bridge Rating

C. Numbering System

1. The numbering system for the criteria consists of a set of numbers followed by letters as required to designate individual subjects. This format is similar to that used by AASHTO.

   Example:

   Chapter 5 Concrete Structures (Chapter)

   5.3 Reinforced Concrete Box Girder Bridges (Section)

   5.3.2 Reinforcement (Subsection)

   A. Top Slab Reinforcement

   1. Near Center of Span

   a. Transverse Reinforcement

2. Numbering of Sheets

   Each section starts a new page numbering sequence. The page numbers are located in the lower outside corners and begin with the chapter number, followed by the section number, then a sequential page number.

   Example: 5.3-1, 5.3-2, etc.

3. Appendices are included to provide the designer with design aids (Appendix A) and examples (Appendix B). Design aids are generally standard in nature, whereas examples are modified to meet specific job requirements.

   An appendix is numbered using the chapter followed by section number and then a hyphen and the letter of the appendix followed by consecutive numbers.

   Example: 5.3-A1 (Box Girder Bridges) designates a design aid required or useful to accomplish the work described in Chapter 5, Section 3.

4. Numbering of Tables and Figures

   Tables and figures shall be numbered using the chapter, section, subsection in which they are located, and then a hyphen followed by consecutive numbers.

   Example: Figure 5.3.2-1 is the first figure found in Chapter 5, section 3, subsection 2.

1.1.4 Revisions

A. Manual Updates

The Bridge Design Manual will change as new material is added and as criteria and specifications change.

Designers shall check any for BDM updates issued by the Bridge and Structures Office as Design Memorandums. These are posted on the following website: www.wsdot.wa.gov/eesc/bridge/bdm and are incorporated into the BDM as soon as possible.

Revisions and new material will be issued with a Publications Transmittal Form. The form will have a revision number and remarks or special instructions regarding the sheets. The revision number shall be entered on the Record of Revision sheet in this manual. This allows the user to verify that the manual is up to date.

B. Bridge Design Instruction

Special instructions regarding interpretation of criteria or other policy statements may be issued using a Bridge Design Instruction (BDI). The BDI will be transmitted in the same manner as outlined above for manual revisions. The BDI should be inserted in the appropriate place in the manual and remains in effect until the expiration date shown or until superseded by a revision to the manual.

C. Record of Manual Revisions

In order that a ready means be available to check whether a manual is up to date, each manual holder is requested to keep his copy up to date and to record Bridge Design Instructions or Revisions as material is added or changed. The form below is intended for use in keeping this record. At any time, a manual holder will be able to check his list with the list in the "master" manual.

Revision Number	Entry Date	By (Initial)	Revision Number	Entry Date	By (Initial)	Revision Number	Entry Date	By (Initial)

Record of Manual Revisions
Table 1-1

1.2 Bridge and Structures Office Organization

1.2.1 General

The responsibilities of the Bridge and Structures Office are:

Provides structural engineering services for WSDOT. Provides technical advice and assistance to other governmental agencies on such matters.

The WSDOT Design Manual states the following:

Bridge design is the responsibility of the Bridge and Structures Office in Olympia. Any design authorized at the Region level is subject to review and approval by the Bridge and Structures Office.

1.2.2 Organizational Elements of the Bridge Office

A. Bridge and Structures Engineer

The Bridge and Structures Engineer is responsible for structural engineering services for the department and manages staff and programs for structural design, contract plan preparation, inspections and assessments of existing bridges.

B. Bridge Design Engineer

The Bridge Design Engineer is directly responsible to the Bridge and Structures Engineer for structural design and review, and advises other divisions and agencies on such matters.

1. Structural Design Units

The Structural Design Units are responsible for the final design of bridges and other structures. Final design includes preparation of contract plans. The units provide special design studies, develop design criteria, check shop plans, and review designs submitted by consultants. Frequently, the Bridge Projects Engineer assigns the units the responsibility for preparing preliminary bridge plans and other unscheduled work.

The Bridge Engineer Supervisor (Unit Supervisor) provides day-to-day leadership, project workforce planning, mentoring, and supervision for the design unit. Organization and job assignments within the unit are flexible and depend on projects underway at any particular time as well as the qualifications and experience level of individuals. The primary objective of the design units is to produce contract plans for bridges and structures within scope, schedule and budget. This involves designing, checking, reviewing, and detailing in an efficient and timely manner.

A bridge specialist is assigned to each design unit. Each specialist has a particular area of expertise. The three major areas are: concrete, steel, expansion joints and bearings. The specialists act as a resource for the bridge office in their specialty and are responsible for keeping up-to-date on current AASHTO criteria, new design concepts and products, technical publications, construction and maintenance issues, and are the primary points of contact for industry representatives.

The design units are also responsible for the design and preparation of contract plans for modifications to bridges in service. These include bridge rail replacement, deck repair, seismic retrofits, emergency repairs when bridges are damaged by vehicle or ship collision or natural phenomenon, and expansion joint and drainage retrofits. They review proposed plans of utility attachments to existing bridges.

2. Bridge Projects Unit

The Bridge Projects Engineer directs preliminary design work, specification and cost estimates preparation, falsework review, project scoping, coordinates scheduling of bridge design projects and unscheduled work assignments with the Region Project Development Engineers, Bridge Design Engineer, and the Unit Supervisors.

The Preliminary Plan Engineers are responsible for bridge project planning from initial scoping to design type, size, and location (TSL) studies and reports. They are responsible for preliminary plan preparation of bridge and walls including assembly and analysis of site data, preliminary structural analysis, cost analysis, determination of structure type, and drawing preparation. They also check preliminary plans prepared by others, review highway project environmental documents and design reports, and prepare U. S. Coast Guard Permits.

The Specifications and Estimate (S&E) Engineers develop and maintain construction specifications and cost estimates for bridge projects. They also develop specifications and cost estimates for bridge contracts prepared by consultants and other government agencies, which are administered by WSDOT. They assemble and review the completed bridge PS&E before submittal to the Regions. They also coordinate the PS&E preparation with the Regions and maintain bridge construction cost records.

The Construction Support Unit Engineers are responsible for checking the contractor's falsework, shoring, and forming plans. Shop plan review and approval are coordinated with the design units. Actual check of the shop plans is done in the design unit. Field requests for plan changes come through this office for a recommendation as to approval.

The Bridge Plans Engineer processes as-built plans in this unit. Region Project Engineers are responsible for preparing and submitting as-built plans at the completion of a contract.

The Scheduling Engineer monitors the design work schedule for the Bridge and Structures Office, updates the Bridge Design Schedule (BDS) and maintains records of bridge contract costs. Other duties include coordinating progress reports to Regions by the Unit Supervisors and S&E Engineers through the Project Delivery Information System (PDIS).

In addition, the unit is responsible for updating the Bridge Design Manual. The unit coordinates Standard Plan changes through the Bridge Construction Office, changes to the WSDOT Standard Specifications and design standards, professional activities, and AASHTO reviews.

C. Bridge Preservation Engineer

The Bridge Preservation Engineer directs activities and develops programs to assure the structural and functional integrity of all state bridges in service. The Bridge Preservation Engineer directs emergency response activities when bridges are damaged.

1. Bridge Preservation Office (BPO)

The Bridge Preservation Office is responsible for planning and implementing an inspection program for the more than 3,200 fixed and movable state highway bridges. In addition, BPO provides inspection services on some local agency bridges and on the state's ferry terminals. All inspections are conducted in accordance with the National Bridge Inspection Standards (NBIS).

BPO maintains the computerized Washington State Bridge Inventory System (WSBIS) of current information on more than 7,300 state, county, and city bridges in accordance with the NBIS. This includes load ratings for all bridges. BPO prepares a *Bridge List* of the state's bridges, which is published every two years, maintains the intranet-based Bridge Engineering Information System (BEIST), and prepares the annual Recommended Bridge Repair List (RBRL) based on the latest inspection reports.

BPO is responsible for the bridge load rating and risk reduction (SCOUR) programs. It provides damage assessments and emergency response services when bridges are damaged because of vehicle or ship collision or natural phenomenon such as: floods, wind, or earthquakes.

D. Bridge Management Engineer

The Bridge Management Unit is responsible for the program development, planning and monitoring of all statewide bridge program activities. These include P2 funded bridge replacements and rehabilitation, bridge deck protection, major bridge repair, and bridge painting.

In addition, the Bridge Management Unit manages the bridge deck protection, deck testing and the bridge research programs. It is responsible for the planning, development, coordination, and implementation of new programs (e.g., Seismic Retrofit and Preventative Maintenance), experimental feature projects, new product evaluation, and technology transfer.

The Bridge Management Engineer is the Bridge and Structures Office's official Public Disclosure contact. (See Section 1.3.8 Public Disclosure Policy Regarding Bridge Plans).

E. Computer Support Unit

The Computer Support Unit is responsible for computer resource planning and implementation, computer user support, liaison with Management Information Systems (MIS), computer aided engineer operation support, and software development activities. In addition, the unit works closely with the Bridge Projects Unit in updating the BDM and Standard Plans.

F. Consultant Liaison Engineer

The Consultant Liaison Engineer prepares bridge consultant agreements and coordinates consultant PS&E development activities with those of the Bridge Office. The Consultant Liaison Engineer negotiates bridge design contracts with consultants.

G. State Bridge and Structures Architect

The State Bridge and Structures Architect is responsible for reviewing and approving preliminary plans, preparing renderings, model making, coordinating aesthetic activities with Regions (i.e. suggesting corridor themes), and other duties to improve the aesthetics of our bridges and structures. The State Bridge and Structures Architect works closely with staff and Regions. During the design phase, designers should get the Architect's approval for any changes to architectural details shown on the approved preliminary plan.

H. Staff Support Unit

The Staff Support Unit is responsible for many support functions, such as: typing, timekeeping, payroll, receptionist, vehicle management, mail, inventory management, and other duties requested by the Bridge and Structures Engineer. Other duties include: filing field data, plans for bridges under contract or constructed, and design calculations. This unit also maintains office supplies and provides other services.

I. Office Administrator

The Office Administrator is responsible for coordinating personnel actions, updating the organizational chart, ordering technical materials, and other duties requested by the Bridge and Structures Engineer. Staff development and training are coordinated through the Office Administrator. The Office Administrator also handles logistical support, office and building maintenance issues.

1.2.3 Design Unit Responsibilities and Expertise

The following is an updated summary of design responsibilities/expertise within the Bridge Design Section. Contact the Unit Supervisor for the name of the appropriate staff expert for the needed specialty.

Unit Supervisor	**Responsibility/Expertise**
Karl Kirker	Bearings and Expansion Joints
	Seismic Retrofit
	Retaining Walls (including Structural Earth, Soldier Pile and Tie-Back, and Soil Nail)
	This design unit has primary responsibility for reviewing proposals submitted by retaining wall manufacturers for pre-approval of their wall systems. Once the wall system is preapproved with concurrence from the State Geotechnical Engineer, each design unit is responsible for checking the proprietary retaining wall shop drawings and designs that are submitted on contracts for which they have design responsibility. The Retaining Wall Specialist assigned to this unit handles the preapproval of proprietary retaining walls and is available as a resource for engineers that are performing design checks.
	When proprietary retaining wall shop plans/designs are submitted on unassigned contracts, the Construction Support Unit will assign the shop plan/design review to one of the three design units on a rotating basis.
Mark Anderson	Noise Walls
	Bridge Traffic Barriers
	Standard Plans for Prestressed Concrete
John Van Lund	Coast Guard Permits
	Special Provisions and Cost Estimates
	Falsework, Forming and Temporary Structures
	Standard Plans (other than Prestressed Concrete)
	Bridge Design Manual
Richard Zeldenrust	Sign Supports, Light Standards, Traffic Signal Supports
	Repairs to Damaged Bridges
Patrick Clarke	Floating Bridges
	Special Structures

1.3 Quality Control/Quality Assurance (QC/QA) Procedure

1.3.0 General

A. The purpose of the QC/QA procedure is to improve the quality of the structural designs and plans. The key element to the success of this process is effective communication between all parties. The goals of the QC/QA procedure are:

- Designed structures improve public safety and meet state regulations.
- Designed structures meet the requirements of the WSDOT Bridge Design Manual, AASHTO LRFD Bridge Design Specifications, current structural engineering practices, and geometric criteria provided by the Region.
- Designed structures are aesthetically pleasing, constructible, durable, economical, inspectable, and require little maintenance.
- Design contract documents meet the customer's needs, schedule, budget, and construction staging requirements.
- Structural design costs are minimized.
- An organized and indexed set of design calculations are produced. Design criteria and assumptions are included in the front after the index.
- Plan quality is maximized.
- The QA/QC procedure allows for change, innovation, and continuous improvement.

The goals are listed in order of importance. If there is a conflict between goals, the more important goal takes precedence.

The Unit Supervisor determines project assignments and the QC/QA process to be used in preparation of the structural design. The intent of the QC/QA process is to facilitate plan production efficiency and cost-effectiveness while assuring the structural integrity of the design and maximizing the quality of the structural contract documents.

1.3.1 Design/Check Procedures

A. PS&E Prepared by WSDOT Bridge and Structures Office

1. Design Team

The design team usually consists of the Designer(s), Checker(s), Structural Detailer(s), and a Specification and Estimate Engineer, who are responsible for preparing a set of contract documents on or before the scheduled due date(s) and within the budget allocated for the project. On large projects, the Unit Supervisor may designate a designer to be a Design Team Leader with additional duties, such as: assisting the supervisor in planning, scheduling, coordinating, and monitoring the activities of the design team. In this case, the team leader would also coordinate and communicate with the Region and the Geotechnical Branch.

The QC/QA procedures may vary depending on the type and complexity of the structure being designed, and the experience level of the design team members. More supervision, review, and checking may be required when the design team members are less experienced. In general, it is a good QC/QA practice to have some experienced designers on each design team. All design team members should have the opportunity to provide input to maximize the quality of the design plans.

2. Designer Responsibility

The designer is responsible for the content of the contract plan sheets, including structural analysis, completeness and correctness. Errors and omissions must be discovered and corrected before subsequent checking and review of plans. A good set of example plans, which is representative of the bridge type, is indispensable as an aid to less experienced designers and detailers.

During the design phase of a project, the designer will need to communicate frequently with the Unit Supervisor and other stakeholders. This includes acquiring, finalizing or revising roadway geometrics, soil reports, hydraulics recommendations, and utility requirements. Constructibility issues may also require that the designer communicate with the Region or Construction Office. The designer may have to organize face-to-face meetings to resolve constructibility issues early in the design phase. The bridge plans must be coordinated with the PS&E packages produced concurrently by the Region.

The designer shall advise the Unit Supervisor as soon as possible of any scope and project cost increases and the reasons for the increases. The Unit Supervisor will then notify the Region project office if the delivery schedule will have to be changed. If Region concurs with a change in the delivery date, the Unit Supervisor will notify the Bridge Projects Engineer or the Bridge Scheduling Engineer of the revised delivery dates.

The designer or team leader is responsible for project planning which involves the following:

a. Determines scope of work, identifies tasks, plans order of work, and makes assignments.

b. Prepares a Design Time Estimate. See Section 1.5.3.

c. Prepare design criteria that are included in the front of the design calculations. Compares tasks with BDM office practice and AASHTO bridge design specifications.

   (1) Sufficient guidelines?

   (2) Deviation from BDM/AASHTO?

   (3) Any question on design approach?

   (4) Deviation from office practices regarding design and details?

   (5) Other differences.

d. Meet with the Region design staff and other project stakeholders early in the design process to resolve as many issues as possible before proceeding with final design and detailing.

e. Identify coordination needs with other designers, units, and offices.

f. Early in the project, determine the number and titles of sheets. For projects with multiple bridges, each set of bridge sheets should have a unique set of bridge sheet numbers. The bridge sheet numbering system should be coordinated with the Region design staff.

g. At least monthly or as directed by the design Unit Supervisor:

   (1) Update Project Schedule and List of Sheets.

   (2) Estimate percent complete.

(3) Estimate time to complete.

(4) Work with Unit Supervisor to adjust resources, if necessary.

h. Develop preliminary quantities for 90 percent complete cost estimate.

i. Near end of project:

(1) Keep track of sheets as they are completed.

(2) Develop quantities, *Not Included in Bridge Quantity List*, and *Special Provisions Checklist* that are to be turned in with the plans. (See Figure 1-A-1).

(3) Prepare and check Bar List.

(4) Coordinate all final changes, including review comments from the checker, managers, specialists, the Region, and the Construction Office.

(5) Meet with Region design staff and other project stakeholders at the constructibility meeting to address final project coordination issues.

The designer should inform the Unit Supervisor of any areas of the design, which should receive special attention during checking and review.

The design calculations are prepared by the designer and become a very important record document. Design calculations will be a reference document during the construction of the structure and throughout the life of the structure. It is critical that the design calculations be user friendly. The design calculations shall be well organized, clear, properly referenced, and include numbered pages along with a table of contents. The design calculations shall be archived. Computer files should be archived for use during construction, in the event that changed conditions arise. Archive-ready design and check calculations shall be bound and submitted to the Unit Supervisor within 30 days of submitting the 100 percent PS&E. Calculations shall be stored in the design unit until completion of construction. After construction, they shall be sent to archives. (See Section 1.3.7 Archiving Design Calculations, Design Files, and S&E Files).

The designer is also responsible for resolving construction problems referred to the Bridge Office during the life of the contract. These issues will generally be referred through the Bridge Technical Advisor, the Unit Supervisor, the Construction Support Unit, or the HQ Construction-Bridge.

3. Design Checker Responsibility

The checker is responsible to the Unit Supervisor for "quality assurance" of the structural design, which includes checking the design and plans to assure accuracy and constructibility. The Unit Supervisor works with the checker to establish the level of checking required. The checking procedure for assuring the quality of the design will vary from project to project. Following are some general checking guidelines:

a. Design Calculations

(1) For designs checked by an experienced checker, a review and initialing of the designer's calculations by the checker is acceptable. If it is more efficient, the checker may choose to perform his/her own calculations to check. All the designer and checker calculations shall be placed in one design calculation set.

(2) For designs checked by an inexperienced checker, a more thorough check should be performed by an inexperienced checker to enhance his/her understanding of structural design. In this case, the Unit Supervisor should provide the checker with a design example to be followed.

(3) Revision of design calculations, if required, is the responsibility of the designer.

b. Structural Plans

(1) The checker's plan review comments are recorded on the structural plans, including details and bar lists, and returned to the designer for consideration. If the checker's comments are not incorporated, the designer should provide justification for not doing so. If there is a difference of opinion that cannot be resolved between the designer and checker, the Unit Supervisor shall resolve any issues.

(2) If assigned by the Unit Supervisor, the checker shall perform a complete check of the geometry using CADD, hand calculations, or a geometry program.

(3) Revision of plans, if required, is the responsibility of the designer.

c. Quantities and Barlist

(1) The checker shall provide an independent set of quantity calculations. These together with the designer's quantity calculations shall be placed in the job file.

(2) Resolution of differences between the designer and checker shall be completed before the 100 percent PS&E submittal. The checker shall also check the barlist.

4. Structural Detailer Responsibility

The structural detailer is responsible for the quality and consistency of the contract plan sheets. The structural detailer shall ensure that the Bridge Office drafting standards as explained in BDM Chapter 11 are upheld.

a. Refer to BDM, Chapter 11, for detailing practices.

b. Provide necessary and adequate information to ensure the contract plans are accurate, complete, and readable.

c. Detail plan sheets in a consistent manner and follow accepted detailing practices.

d. Check plans for geometry, reinforcing steel congestion, consistency, and verify control dimensions.

e. Check for proper grammar and spelling.

f. On multiple bridge contracts, the structural detailing of all bridges within the contract shall be coordinated to maximize consistency of detailing from bridge to bridge. Extra effort will be required to ensure uniformity of details, particularly if multiple design units and/or consultants are involved in preparing bridge plans.

g. Maintain an ongoing program of related professional education including an understanding of bridge construction.

5. Specialist Responsibility

   There are currently three specialist positions in the Bridge and Structures Office. The three specialty areas in the Design Section are bearings and expansion joints, concrete (including prestressed concrete), and structural steel.

   The primary responsibility of the specialist is to act as a knowledge resource for the Bridge and Structures Office. The Specialists maintain an active knowledge of their specialty area along with a current file of products and design procedures. The Specialists maintain industry contacts. Specialists also provide training in their area of specialty.

   Specialists are expected to review and initial plans in their specialty area for contract plans prepared by other designers.

   Specialists also assist the Bridge and Structures Engineer in reviewing and voting on amendments to AASHTO specifications. They also are responsible for keeping their respective chapters of the Bridge Design Manual up to date.

   A secondary responsibility of the Specialist is to serve as Unit Supervisor when the supervisor is absent.

6. Design Unit Technical Responsibilities

   In addition to the specialty areas described above, each unit maintains a resource of technical knowledge in several technical areas. The following list describes additional specialty areas:

   - U.S. Coast Guard Permits
   - Cost Estimates
   - Bridge Special Provisions
   - Sign Supports, Light Standards, Traffic Signal Supports
   - Repairs to Damaged Prestressed and Steel Girders
   - Expansion Joint Modifications and Repairs
   - Retaining Walls (Including Structural Earth, Soldier Pile and Tie-Back, and Soil Nail Walls)
   - Seismic Retrofit
   - Noise Walls
   - Traffic Barrier Retrofits/Standards
   - Bridge Standard Plans and BDM
   - Software Development

   The resource/leadership responsibility for these technical areas does not necessarily include responsibility for performing all of the work relating to the technical area. For many of the technical areas, the design unit acts as a resource for the technical area and as a contact for industry and others.

7. Specification and Estimating Engineer Responsibilities

   The S&E Engineer is responsible for compiling the PS&E package for bridge and/or related highway structural components. This PS&E package includes Special Provisions (Bridge Special Provisions or BSPs and General Special Provisions or GSPs as appropriate), construction cost estimate, construction working day schedule, test hole boring logs and other appendices as appropriate, and the design plan package.

For a detailed description of the S&E Engineer's responsibilities, see Section 12.4.

8. Design Unit Supervisor Responsibility

   a. The Unit Supervisor is responsible to the Bridge Design Engineer for the timely completion and quality of the bridge plans.

   b. The Unit Supervisor works closely with the design team (designer, checker, and structural detailer) during the design and plan preparation phases to help avoid major changes late in the design process. Activities during the course of design include:

      (1) Evaluate the complexity of the project and the designer's skill and classification level to deliver the project in a timely manner. Determine both the degree of supervision necessary for the designer and the amount of checking required by the checker.

      (2) Assist the design team in defining the scope of work, identifying the tasks to be accomplished, developing a project work plan and schedule, and assigning resources to achieve delivery of the project on schedule and within budget.

      (3) Review and approve design criteria before start of design.

      (4) Help lead designer conduct face-to-face project meetings, such as: project "kick-off" and "wrap-up" meetings with Region, geotechnical staff, bridge construction, and consultants to resolve outstanding issues.

      (5) Assist the design team with planning, anticipating possible problems, collectively identifying solutions, and facilitating timely delivery of needed information, such as geometrics, hydraulics, foundation information, etc.

      (6) Interact with design team regularly to discuss progress, problems, schedule and budget, analysis techniques, constructibility and design issues. Always encourage forward thinking, innovative ideas and suggestions for quality improvement.

      (7) Arrange for and provide the necessary resources and tools for the design team to do the job right the first time. Offer assistance to help resolve questions or problems.

      (8) Help document and disseminate information on special features and lessons learned for the benefit of others and future projects.

      (9) Mentor and train designers and detailers on state-of-the-art practices and through the assignment of a variety of structure types.

   c. The Unit Supervisor works closely with the design team during the plan review phase. Review efforts should concentrate on reviewing the completed plan details and design calculations for completeness and for agreement with office criteria and office practices. Review the following periodically and at the end of the project:

      (1) Design Criteria

         - Seismic Acceleration Coefficient or "a" value
         - Foundation report recommendations, selection of alternates
         - Deviations from AASHTO, BDM, Documentation

      (2) Design Time and Budget

d. Review designer's estimated time to complete the project. Plan resource allocation for completing the project to meet the scheduled Ad Date and budget. Monitor monthly time spent on the project.

   At the end of each month, estimate time remaining to complete project, percent completed, and whether project is on or behind schedule.

   Plan and assign workforce to ensure a timely delivery of the project within the estimated time and budget. At monthly supervisors' scheduling meetings, notify the Bridge Projects Engineer if a project is behind schedule.

e. Advise Region of any project scope creep and construction cost increases. As a minimum, use quarterly status reports to update Region on project progress.

f. Use appropriate computer scheduling software or other means to monitor time usage, to allocate resources, and to plan projects.

g. Review constructibility issues. Are there any problems unique to the project?

h. Check the final plans for the following:

   (1) Scan the job file for unusual items relating to geometrics, hydraulics, geotechnical, environmental, etc.

   (2) Overall check/review of sheet #1, the bridge layout for:

   - Consistency — especially for multiple bridge project
   - Missing information

   (3) Check footing layout for conformance to Bridge Plan and for adequacy of information given. Generally, the field personnel shall be given enough information to "layout" the footings in the field without referring to any other sheets. Plan details shall be clear, precise, and dimensions tied to base references, such as: a survey line or defined centerline of bridge.

   (4) Check the sequence of the plan sheets. The plan sheets should adhere to the following order: layout, footing layout, substructures, superstructures, miscellaneous details, barriers, and barlist. Also check for appropriateness of the titles.

   (5) Check overall dimensions and elevations, spot check for compatibility. For example, check compatibility between superstructures and substructure. Also spot check bar marks.

   (6) Use common sense and experience to check structural dimensions and reinforcement for structural adequacy. When in doubt, question the designer and checker.

i. Stamp and sign the plans in blue ink.

9. Bridge Design Engineer's Responsibilities

   The Bridge Design Engineer is the coach, mentor, and facilitator for the WSDOT QC/QA Bridge Design Procedure. The leadership and support provided by this position is a major influence in assuring bridge design quality for structural designs performed by both WSDOT and consultants. The following summarizes the key responsibilities of the Bridge Design Engineer related to QC/QA:

a. When the structural contract plans are sealed by the Bridge Design Engineer, a structural/constructibility review of the plans is performed. This is a quality assurance (QA) function as well as meeting the "responsible charge" requirements of state laws relating to Professional Engineers.

b. Review and approve the Preliminary Bridge Plans. The primary focus for this responsibility is to assure that the most cost-effective and appropriate structure type is selected for a particular bridge site.

c. Participate in coordinating, scheduling, and communicating with stakeholders, customers, and outside agencies relating to major structural design issues.

d. Facilitate resolution of major project design issues.

e. Review unique project special provisions and Standard Specification modifications relating to structures.

f. Facilitate partnerships between WSDOT, consultants, and the construction industry stakeholders to facilitate and improve design quality.

g. Encourage designer creativity and innovation through forward thinking.

h. Exercise leadership and direction for maintaining a progressive and up to date Bridge Design Manual.

i. Create an open and supportive office environment in which Design Section staff are empowered to do high quality structural design work.

j. Create professional growth opportunities through an office culture where learning is emphasized.

k. Encourage continuing professional development through training opportunities, attendance at seminars and conferences, formal education opportunities, and technical writing.

10. General Bridge Plan Stamping and Signature Policy

The stamping and signing of bridge plans is the final step in the Bridge QC/QA procedure. It signifies a review of the plans and details by those in responsible charge for the bridge plans. At least one Licensed Structural Engineer shall stamp and sign each contract plan sheet (except the bar list).

For major projects, the Unit Supervisor and the Bridge Design Engineer will review, stamp, and sign the bridge plans. For routine bridge designs and transportation structure designs, the Unit Supervisor with a SE License and the designer with a Civil Engineer License will typically review, stamp, and sign the contract plans except for the barlist, which does not have to be stamped and signed.

B. PS&E Prepared by Consultant — Projects on WSDOT Right of Way

PS&E prepared by consultants will follow a similar QC/QA procedure as that shown above for WSDOT prepared PS&E's and, as a minimum, shall include the following elements:

1. WSDOT Consultant Liaison Engineer's Responsibilities

a. Review scope of work and consultant's QC/QA procedures.

b. Negotiate contract and consultant's Task Assignments.

c. Coordinate/Negotiate Changes to Scope of Work and QC/QA Procedures.

2. WSDOT Design Reviewer's or Coordinator's Responsibilities

    a. Early in the project, review consultant's QC/QA procedures, design criteria, and standard details for consistency with WSDOT practices and other bridge designs in project.

    b. Identify resources needed to complete work.

    c. Agree early on the structural concepts and design methods to be used.

    d. Identify who is responsible for what and when 30 percent, 90 percent, and 100 percent PS&E submittals are to be made.

    e. Monitor progress.

    f. Facilitate communication, including face-to-face meetings.

    g. Review consultant's design.

    h. Resolve differences.

    i. Verify that consultant's QC/QA plan was followed during design.

3. WSDOT Design Unit Supervisor's Responsibilities

    a. Encourage and facilitate communication.

    b. Early involvement to assure that design concepts are appropriate.

    c. Empower Design Reviewer or Coordinator.

    d. Facilitate resolution of issues beyond authority of WSDOT Reviewer or Coordinator.

    e. Facilitate face-to-face meetings.

4. WSDOT S&E Engineer's Responsibilities

    See Section 12.4.8.

5. WSDOT Bridge Design Engineer's Responsibilities

    a. Cursory review of design plans.

    b. Signature approval of S&E bridge contract package.

C. Consultant PS&E — Projects On County and City Right of Way

Counties and cities frequently hire Consultants to design bridges. WSDOT Highways and Local Programs Office determines which projects are to be reviewed by the Bridge and Structures Office.

WSDOT Highways and Local Programs sends the PS&E to the Bridge Projects Engineer for assignment when a review is required. The Bridge and Structures Office's Consultant Liaison Engineer is not involved.

A WSDOT Design Reviewer or Coordinator will be assigned to the project and will review the project as outlined for Consultant PS&E — Projects on WSDOT Right of Way (see Section 1.3.1.B).

Two sets of plans with the reviewers' comments marked in red should be returned to the Bridge Projects Unit. One set of plans will be returned to Highways and Local Programs. The Bridge Scheduling Engineer will file the other set in the Bridge Projects Unit.

The first review should be made of the Preliminary Plan first followed later by review of the PS&E and design calculations. Comments are treated as advisory, although major structural issues must be addressed and corrected. An engineer from the county, city, or consultant may contact the reviewer to discuss the comments.

1.3.2 Design/Check Calculation File

A. File of Calculations

The Bridge and Structures Office maintains a file of all pertinent design/check calculations for documentation and future reference. (See Section 1.3.7 Archiving Design Calculations, Design Files, and S&E Files).

B. Procedures

After an assigned project is completed and the bridge is built, the designer should turn in to the Unit Supervisor a bound file containing the design/check calculations. The front cover should have a label (See Figure 1, Section 1.3.7).

C. File Inclusions

The following items should be included in the file:

1. Index Sheets

   Number all calculation sheets and prepare an index by subject with the corresponding sheet numbers.

   List the name of the project, SR Number, designer/checker initials, date (month, day, and year), and Unit Supervisor's initials.

2. Design Calculations

   The design calculations should include design criteria, design assumptions, loadings, structural analysis, one set of moment and shear diagrams and pertinent computer input and output data (reduced to 8½" by 11" sheet size).

   The design criteria, design assumptions, and special design features should follow in that order behind the index.

3. Special Design Features

   Brief narrative of major design decisions or revisions and the reasons for them.

4. Construction Problems or Revisions

   Not all construction problems can be anticipated during the design of the structure; therefore, construction problems arise during construction, which will require revisions. Calculations for revisions made during construction should be included in the design/check calculation file when construction is completed.

D. File Exclusions

The following items should not be included in the file:

1. Geometric calculations.
2. Irrelevant computer information.
3. Prints of Office Standard Sheets.
4. Irrelevant sketches.
5. Voided sheets.

6. Preliminary design calculations and drawings unless used in the final design.
7. Test hole logs.
8. Quantity calculations.

1.3.3 PS&E Review Period

See BDM Section 12.4.10 for PS&E Review Period activities.

1.3.4 Addenda

Plan or specification revisions during the advertising period require an addendum. The Specifications and Estimate Engineer will evaluate the need for the addendum after consultation with the HQ Construction — Bridge, Region, and the HQ or Region Plans Branch. The Bridge Design Engineer or the Unit Supervisor must initial all addenda.

For addenda to contract plans, obtain the original drawing from the Bridge Projects Unit. Use shading to mark all changes (except deletions) and place a revision note at the bottom of the sheet (Region and HQ Plans Branch jointly determine addendum date) and a description of the change. Return the 11" by 17" signed original and copy to the Specifications and Estimate Engineer who will submit the copy to the HQ Plans Branch for processing. See Chapter 12 for additional information.

For changes to specifications, submit a copy of the page with the change to the Specifications and Estimate Engineer for processing.

1.3.5 Shop Plans and Permanent Structure Construction Procedures

This section pertains to fabrication shop plans, weld procedures, electrical and mechanical items, geotechnical procedures, such as: drilled shafts and tieback walls, and other miscellaneous items related to permanent construction.

The following is a guide for checking shop plans and permanent structure construction procedures.

A. Bridge Shop Plans and Procedures

1. Mark one copy of each sheet with the following, near the title block, in red pen or with a rubber stamp:

   Office Copy

   Contract (number)

   (Checker's initials) (Date)

   Approval Status (A, AAN, RFC or Structurally Acceptable)

2. On the Bridge Office copy, mark with red pen any errors or corrections. Yellow shall be used for highlighting the checked items. The red pen marks will be copied onto the other copies and returned to the Region Project Engineer. Comments made with red pen, especially for 8½" by 11" or 11" by 17" size sheets, shall be clear, neat, and conducive to being reproduced by Xerox. These comments should be "bubbled" so they stand out on a black and white Xerox copy. Use of large sheets should be discouraged because these require extra staff assistance and time to make these copies by hand.
3. Items to be checked are typically as follows: Check against Contract Plans and Addenda, Special Provisions, Previously Approved Changes and Standard Specifications.

a. Material specifications (ASTM specifications, hardness, alloy and temper, etc.).

b. Size of member and fasteners.

c. Length dimensions, if shown on the Contract Plans.

d. Finish (surface finish, galvanizing, anodizing, painting, etc.).

e. Weld size and type and welding procedure if required.

f. Strand or rebar placement, jacking procedure, stress calculations, elongations, etc.

g. Fabrication — reaming, drilling, and assembly procedures.

h. Adequacy of details.

i. Erection procedures.

For prestressed girders and post-tensioning shop plan review see BDM 5.6.3A and 5.8.6C respectively.

4. Items Not Requiring Check:

   a. Quantities in bill of materials.

   b. Length dimensions not shown on Contract Plans except for spot checking and is emphasized by stamping the plans: *Geometry Not Reviewed by the Bridge and Structures Office*.

5. Project Engineer's Copy

   Do not use the Project Engineer's copy (comments or corrections are in green) as the office copy. Transfer the Project Engineer's corrections, if pertinent, to the office copy using red pen. The Project Engineer's comments may also be received by E-mail.

6. Marking Copies

   When finished, mark the office copy with one of five categories in red pen, lower right corner.

   a. "A"

      Approved, No Corrections required.

   b. "AAN"

      Approved As Noted — minor corrections only. Do not place written questions on an approved as noted sheet.

   c. "RFC"

      Returned for Correction — major corrections are required which requires a complete resubmittal.

   d. "Structurally Acceptable"

      This is appropriate for items that are not required to be "Approved" per the contract, such as: work platforms, submittals from various local agencies or developers, and other items that are reviewed as a courtesy.

   e. "Structurally Acceptable But Does Not Conform to the Contract Requirements"

      This is appropriate when a deviation from the contract is found but is determined to be structurally acceptable.

If in doubt between AAN and RFC, check with the Unit Supervisor or Construction Support Engineer. An acceptable detail may be shown in red. Mark the plans *Approved As Noted* provided that the detail is clearly noted *Suggested Correction — Otherwise Revise and Resubmit*.

Do not mark the other copies. The Construction Support Unit will do this.

Notify the Construction Support Engineer if there are any structurally acceptable deviations to the contract plans. The Construction Support Engineer will notify both the Region Project Engineer and HQ Construction-Bridge, who may have to approve a change order and provide justification for the change order.

Notify the Unit Supervisor and the Construction Support Engineer if problems are encountered which may cause a delay in the checking of the shop plans or completion of the contract. Typically, WSDOT administered contracts require reviews to be completed within 30 days. The review time starts when the Project Engineer first receives the submittal from the Contractor and ends when the Contractor has received the submittal back from the Project Engineer. The Bridge Office does not have the entire 30-day review period to complete the review. Therefore, designers should give construction reviews high priority and complete reviews in a timely manner so costly construction delays are avoided. Time is also required for marking, mailing and other processing. It is the goal of the Bridge and Structures Office to return reviewed submittals back to the Project Engineer within 7 to 14 days of their receipt by the Bridge Construction Support Unit.

Return all shop drawings and Contract Plans to the Construction Support Unit when checking is completed. Include a list of any deviations from the Contract Plans that are allowed and a list of any disagreements with the Project Engineer's comments (regardless of how minor they may be).

If deviations from the Contract Plans are to be allowed, a Change Order may be required. Alert the Construction Support Unit so that their transmittal letter may inform the Region and the HQ Construction - Bridge.

Under no circumstances should the reviewer mark on the shop plans that a change order is required or notify the Project Engineer that a change order is required. The authority for determining whether a change order is required rests with HQ Construction - Bridge.

B. Sign Structure, Signal, and Illumination Shop Plans

In addition to the instructions described under Section 1.3.5A Bridge Shop Plans, the following instructions apply:

1. Review the shop plans to ensure that the pole sizes conform to the Contract Plans. Determine if the fabricator has supplied plans for each pole or type of pole called for in the contract.
2. The Project Engineer's copy may show shaft lengths where not shown on Contract Plans or whether a change from Contract Plans is required. Manufacturer's details may vary slightly from contract plan requirements, but must be structurally adequate to be acceptable.

C. Geotechnical Submittals

The Bridge Office and the Geotechnical Services Branch concurrently review these submittals which may include special design proprietary retaining walls, drilled shafts, ground anchors, and soldier piles. HQ Construction Office - Bridge is included for the review of drill shaft installation plans. The Construction Support Unit combines these comments and prepares a unified reply that is returned to the Project Engineer

1.3.6 Contract Plan Changes (Change Orders and As-Builts)

A. Request for Changes

The following is intended as a guide for processing changes to the design plans after a project has been awarded.

For projects which have been assigned a Bridge Technical Advisor (BTA), structural design change orders can be approved at the Project Engineer's level provided the instructions outlined in the *Construction Manual* are followed.

For all other projects, all changes are to be forwarded through the Construction Support Unit, which will inform the HQ Construction Engineer - Bridge. Responses to inquiries should be handled as follows:

1. Request by Contractor or Supplier

   A designer, BTA, or Unit Supervisor contacted directly by a contractor/supplier may discuss a proposed change with the contractor/supplier, but shall clearly tell the contractor/supplier to formally submit the proposed change though the Project Engineer and that the discussion in no way implies approval of the proposed change. Designers are to inform their Unit Supervisor if they are contacted.

2. Request From the Region Project Engineer

   Requests for changes directly from the Project Engineer to designer or the Unit Supervisor should be discouraged. The Project Engineer should contact HQ Construction - Bridge, who in turn will contact the designer or Unit Supervisor if clarification is needed regarding changes. The Construction Support Unit should be informed of any changes.

3. Request From the Region Construction Engineer

   Requests from the Region Construction Engineer are to be handled like requests from the Region Project Engineer.

4. Request From the HQ Construction - Bridge

   Requests for changes from HQ Construction - Bridge are usually made through the Construction Support Unit and not directly to the Design Unit. However, sometimes, it is necessary to work directly with the Design Unit. The Construction Support Unit should be informed of any decisions made involving changes to the Contract Plans.

5. Request From the Design Unit

   Request for changes from the Design Unit due to plan errors or omissions shall be discussed with the Bridge Design Engineer prior to revising and issuing new plan sheets.

B. Processing Contract Revisions

Changes to the Contract Plans or Specifications subsequent to the award of the contract may require a contract plan revision. Revised or additional plan sheets, which clearly identify the change on the plans, may be needed. When a revision or an additional drawing is necessary, request the original plan sheets from the Construction Support Unit's Bridge Plans Engineer and prepare revised or new original plan sheets.

Sign, date, and send the new plan sheets to the Bridge Plans Engineer. Send two paper copies to HQ Construction-Bridge. The Construction Support Unit requires one paper copy. The Design Unit requires one or more paper copies. One paper print, stamped *"As Constructed Plans"*, shall be sent to the Project Engineer, who shall use it to mark construction changes and forward them as *"As-Built Plans"* to the Bridge Plans Engineer upon project completion. The Designer is responsible for making the prints and distributing them.

This process applies to all contracts including HQ Ad and Award, Region Ad and Award, or Local Agency Ad and Award.

Whenever new plan sheets are required as part of a contract revision, the information in the title blocks of these sheets must be identical to the title blocks of the contract they are for (e.g., Job Number, Contract No., Fed. Aid Proj. No., Approved by, and the Project Name). These title blocks shall also be initialed by the Bridge Design Engineer, Unit Supervisor, designer, and reviewer before they are distributed. If the changes are modifications made to an existing sheet, the sheet number will remain the same. A new sheet shall be assigned the same number as the one in the originals that it most closely resembles and shall be given a letter after the number (e.g., if the new sheet applies to the original sheet 25 of 53, then it will have number 25A of 53). The Bridge Plans Engineer in the Construction Support Unit shall store the 11" by 17" original revision sheets.

Every revision will be assigned a number, which shall be enclosed inside a triangle. The assigned number shall be located both at the location of the change on the sheet and in the revision block of the plan sheet along with an explanation of the change.

Any revised sheets shall be sent to HQ Construction-Bridge with a written explanation describing the changes to the contract, justification for the changes, and a list of material quantity additions or deletions.

C. As-Built Plan Process

For more information on the as-built plan process for bridges, see the *As-Built Plans Manual*, prepared by the Bridge and Structures Office, dated August 2003. Copies are available from the Bridge Plans Engineer.

1.3.7 Archiving Design Calculations, Design Files, and S&E Files

A. Upon Award

The Bridge Plans Engineer will collect the Design File (Job File), S&E File and Design Calculations. Files will be placed in a temporary storage space marked as "Design Unit Document Temporary Storage". These cabinets will be locked, and only the Bridge Plans Engineer, the Scheduling Engineer, and the Office Administrator will have keys to them. The Design Files, S&E Files, and Design Calculations are stored under the contract number.

A Bridge and Structures staff member may access the Design Files, S&E Files, or Design Calculations by requesting the files from the Bridge Plans Engineer or the Scheduling Engineer, who will check out the files and note the date and person's name. If a person other than a Bridge and Structures Office staff member requests these documents, the approval of the Bridge Design Engineer or Bridge Projects Engineer will be required for release of the documents.

B. Upon Contract Completion

The designer will place a job file cover label on the file folder (see Figure 1) and update the file with any contract plan changes that have occurred during construction.

Two years after physical completion of the contract, the Bridge Plans Engineer will box and send the documents to the Office of Secretary of State for archive storage, except as otherwise approved by the Bridge Design Engineer.

The Bridge Plans Engineer will maintain a record of the documents location and archive status.

SR # _____ County _____ CS # _____

Bridge Name _____

Bridge # _____ Contract # _____

Contents _____

Designed by _____ Checked by _____

Archive Box # _____ Vol. # _____

Cover Label
Figure 1-2

1.3.8 Public Disclosure Policy Regarding Bridge Plans

The Bridge Management Engineer is the Bridge and Structures Office's official Public Disclosure contact and shall be contacted for clarification and/or direction.

Executive Order, E1023.0 Public Disclosure, which replaced *Directive D 72-21 Release of Public Records*, provides a specific procedure to follow when there is a request for public records. (See http://wwwi.wsdot.wa.gov/docs).

The Bridge and Structures Office is the "owner" of only two types of "official" records:
(1) Design Calculations (until they are turned over to the State Archives Office) and
(2) Bridge Inspection Documents.

No records will be disclosed without a written request. This request is to be specific.

As-built plans available on the Bridge and Structures website are not "official" as-built plans. The Regions are the owners of the "official" as-built plans and the procedure for providing requested copies of these plans is similar to the procedure outlined above with the following modifications:

- If you receive a written or verbal request for a set of plans from a person indirectly working for WSDOT (i.e. contractor, consultant), advise them to contact and request the plans from the WSDOT Project Engineer.
- If the request comes from a person directly working on a Bridge Office project as an on-call consultant, have them contact and request the plans from the Bridge and Structures Office's Consultant Liaison Engineer.

- If the request comes from a person not working for WSDOT, they must submit their written request to the person and address noted below and it will be forwarded to the appropriate Region to provide the requested documents.

  Written requests must be sent to:

  Records and Information Service Office
  Washington State Department of Transportation
  310 Maple Park Avenue P. O. Box 47410
  Olympia, WA 98504-7410
  Attn: Ms. Cathy Downs

1.3.9 Use of Computer Software

A. Protection of Intellectual Property

Many of the software tools used by the Bridge and Structures Office are licensed from commercial software vendors. WSDOT is committed to using these tools only as allowed by law and as permitted by software license. WSDOT employees shall comply with the terms and conditions of all licensing agreements and provisions of the Copyright Act and other applicable laws.

Before using any software tools WSDOT employees shall read and understand Instructional Letter 4032.00, Titled "Computer Software Piracy Prevention, and the Protection of Intellectual Property"[1]

B. Policy on Open Source Software

It is the policy of the Bridge and Structures Office to license its own engineering software as open source, and to prefer and promote the use of open source software, within the bridge engineering community.

To support this policy on open source bridge engineering software, the Bridge and Structures Office is a founding and participating member of the Alternate Route Project. The purpose of the Alternate Route Project is to serve as a focal point for the collaborative and cooperative development of open source bridge engineering software tools.

C. Approved Software Tools

A list of approved software tools available for use by WSDOT bridge design engineers is available at http://wwwi.wsdot.wa.gov/eesc/bridge/software. Note that this list is only available on the WSDOT intranet. WSDOT does not require consulting engineers to use any specific software tools, so long as the use of the tools are in accordance with sound engineering practice, and does not violate software licensing agreements and Copyright law.

When using personal design tools created by others, such as a spreadsheet or MathCAD document, the designer is responsible for thoroughly checking the tool to ensure the integrity of the structural analysis and design.

1.4 Coordination With Other Divisions and Agencies

During the various phases of design, it is necessary to coordinate the elements of the bridge design function with the requirements of other divisions and agencies. E-mail messages, telephone calls, and other direct communication with other offices are necessary and appropriate. Adequate communications are essential but organizational format and lines of responsibility must be recognized. However, a written request sent through proper channels is required before work can be done or design changes made on projects.

1.4.1 Preliminary Planning Phase

See Chapter 2.1 of this manual for coordination required at the preliminary planning phase.

1.4.2 Final Design Phase

A. Coordination With Region

Final coordination of the bridge design with Region requirements must be accomplished during the final design phase. This is normally done with the Region Project Engineer, Region Design Engineer, or Region Plans Engineer. Details such as division of quantity items between the Region PS&E and bridge PS&E are very important to a final contract plan set. The Region PS&E and bridge PS&E are combined by the Region Plans Branch. However, coordination should be accomplished before this time.

During the design of a project for a Region level contract, the Region shall provide a copy of the proposed structural plans (such as retaining walls, barrier, large culverts, etc.) to the Bridge and Structures Office. The Bridge and Structures Office will review these plans and indicate any required changes and then send them back to the Region.

The Region shall incorporate the changes prior to contract advertisement.

After contract advertisement, the Region shall return the original plan sheets to Bridge and Structures Office. These sheets shall be held in temporary storage until the Region completes the "As Constructed Plans" for them.

The Region shall then transmit the "As Constructed Plans" to Bridge and Structures Office where they will be transferred to the original plans for permanent storage. Upon request, the Region will be provided copies of these plans by the Bridge and Structures Office.

B. Technical Design Matters

Technical coordination must be done with the HQ Materials Laboratory Foundation Engineer and with the HQ Hydraulic Engineer for matters pertaining to their responsibilities. A portion of the criteria for a project design may be derived from this coordination; otherwise it shall be developed by the designer and approved by the Bridge Design Engineer.

The designer should ensure uniformity of structural details, bid items, specifications, and other items when two or more structures are to be advertised under the same contract.

1.5 Bridge Design Scheduling

1.5.1 General

The Bridge Projects Engineer is responsible for workforce projections, scheduling, and monitoring progress of projects. The *Bridge Design Schedule (BDS)* is used to track the progress of a project and is updated monthly by the Bridge Scheduling Engineer. A typical project would involve the following steps:

A. Regions advise Bridge and Structures Office of an upcoming project.

B. The Bridge Projects Unit determines the scope of work, estimates design time and cost to prepare preliminary plans, design, and S&E (see Section 1.5.2). The Unit Supervisor may also do this and notify the Bridge Projects Engineer.

C. The project is entered into the BDS with start and due dates for site data preliminary plan, project design, PS&E, and the Ad Date.

D. Bridge site data received.

E. Preliminary design started.

F. Final Design Started — Designer estimates time required for final plans (see Section 1.5.3).

G. Monthly Schedule Update — Each Unit Supervisor is responsible for maintaining a workforce projection, monitoring monthly progress for assigned projects, and reporting progress or any changes to the scope of work or schedule to the Bridge Projects Engineer.

H. Project turned in to S&E unit.

1.5.2 Preliminary Design Schedule

The preliminary design estimate done by the Bridge Projects Unit is based on historical records from past projects taking into consideration the unique features of each project, the efficiencies of designing similar and multiple bridges on the same project, designer's experience, and other appropriate factors.

1.5.3 Final Design Schedule

A. Breakdown of Project Man-Hours Required

Using a spreadsheet, list each item of work required to complete the project and the man-hours required to accomplish them. Certain items of work may have been partially completed during the preliminary design, and this partial completion should be reflected in the columns "% Completed" and "Date Completed." See Figures 1-A-2 and 1-A-3.

The designer or design team leader should research several sources when making the final design time estimate. The following are possible sources that may be used:

The "Bridge Design Summary" contains records of design time and costs for past projects. This summary is kept in the Bridge Projects Unit. The times given include preliminary plan, design, check, drafting, and supervision.

The Bridge Projects Unit has "Bridge Construction Cost Summary" books. These are grouped according to bridge types and have records of design time, number of drawings, and bridge cost.

B. Estimate Design Time Required

The designer or design team leader shall determine an estimate of design time required to complete the project. The use of a spreadsheet, or other means is encouraged to ensure timely completion and adherence to the schedule. Use 150 hours for one man month.

The following percentages should be used for the following activities:

Activity No.	Percentage
1	40
2	20
3	20
4	5
5	5
6	5
7	5
Total	100%

The individual activities include the specific items as follows under each major activity.

Activity No. 1 Design — See Section 1.3.1A2 — Includes:

1. Project coordination and maintaining the Design File.
2. Geometric computations.
3. Design calculations.
4. Complete check of all plan sheets by the designer.
5. Compute quantities and prepare barlist.
6. Preparing special provisions checklist.
7. Assemble backup data covering any unusual feature in the Design File.

Activity No. 2 Design Check — See Section 1.3.1A3 — Includes:

1. Checking design at maximum stress locations.
2. Checking major items on the drawings, including geometrics.
3. Additional checking required.

Activity No. 3 Drawings — See Section 1.3.1A4 — Includes:

1. Preparation of all drawings.

Activity No. 4 Revisions — Includes:

1. Revisions resulting from the checker's check.
2. Revisions resulting from the Unit Supervisor's review.
3. Revisions from S&E Engineer's review.
4. Revisions from Region's review.

Activity No. 5 Quantities — Includes:

1. Compute quantities including barlist.
2. Check quantities and barlist.

Activity No. 6 S&E — See Section 12.4. — Includes:

1. Prepare S&E.
2. Prepare working day schedule.

Activity No. 7 Project Review — Includes:

1. Unit Supervisor and Specialist's review.

C. Monthly Project Progress Report

The designer or design team leader is responsible for determining monthly project progress and reporting the results to the Unit Supervisor. The Unit Supervisor is responsible for monthly progress reports using information from the designer or design team leader. Any discrepancies between actual progress and the project schedule must be addressed. Report any revisions to the workforce assigned to the project, hours assigned to activities, or project schedule revisions to the Bridge Projects Engineer and Region.

The designer may use a computer spreadsheet, to track the progress of the project and as an aid in evaluating the percent complete. Other tools include using an Excel spreadsheet listing bridge sheet plans by title, bridge sheet number, percent design complete, percent design check, percent plan details completed, and percent plan details checked. This data allows the designer or design team leader to rapidly determine percent of project completion and where resources need to be allocated to complete the project on schedule.

1.6 Guidelines for Bridge Site Visits

The following guidelines are established to help all staff in determining the need for visiting bridge sites prior to final design. These guidelines should apply to consultants as well as to our own staff. In all cases, the Region project engineer should be made aware of the site visit so they may have the opportunity to participate. Region participation is very useful prior to preparing the preliminary bridge plans.

1.6.1 Bridge Rehabilitation Projects

This section pertains to major bridge rehabilitation projects and excludes rail and minor expansion joint rehabilitation projects. It is critical that the design team know as much as possible about the bridge which is to be rehabilitated. Recent bridge inspection reports, prepared by inspectors from the Bridge Preservation Office (BPO), contain useful information on the condition of existing bridges. The bridge inspection reports, as well as as-built plans, are available on the Intranet through *Bridge Engineering Information System (BEIST)*. BPO maintains *BEIST*.

As-built drawings and contract documents are also helpful, but may not necessarily be accurate. At least one bridge site visit is necessary for this type of project. In some cases, an in-depth inspection with experienced BPO inspectors is appropriate. The decision to perform an in-depth inspection should include the Unit Supervisor, Region, the Bridge Design Engineer, and the Bridge Preservation Engineer.

It may be necessary to use BPO's Under Bridge Inspection Truck (UBIT) if there is a need to access details and obtain measurements during the field visit. Advance planning and coordination with BPO will be necessary if UBIT equipment is required because of BPO's heavy workload and the need to provide traffic control well in advance of the site visit.

1.6.2 Bridge Widening and Seismic Retrofits

For this type of bridge project, it is important that the design team is familiar with the features and condition of the existing bridge. There is good information regarding the condition of existing bridges on *BEIST* and at the Bridge Preservation Office. As-built drawings and contract documents are also helpful, but may not necessarily be accurate. A site visit is recommended for this type of project if the bridge to be widened has unique features or is other than a standard prestressed girder bridge with elastomeric bearings.

1.6.3 Rail and Minor Expansion Joint Retrofits

Generally, photographs and site information from the Region along with as-built plans and condition survey information are adequate for most of these types of projects. However, if there is any doubt about the adequacy of the available information or concern about accelerated deterioration of the structural elements to be retrofitted, a site visit is recommended.

1.6.4 New Bridges

Generally, photographs and site data from the Region are adequate for most new bridge designs. However, if the new bridge is a replacement for an existing bridge, a site visit is recommended, particularly if the project requires staged removal of the existing bridge and/or staged construction of the new bridge.

1.6.5 Bridge Demolition

If bridge demolition is required as part of a project, a site visit would help the design team determine if there are unique site restrictions that could affect the demolition. If unique site restrictions are observed, they should be documented, included in the job file, and noted on the special provisions checklist.

Before making a site visit, the Bridge Preservation Office and the Region should be contacted to determine if there are any unique site conditions or safety hazards. Proper safety equipment and procedures should always be followed during any site visit.

When making a site visit, it is important to obtain as much information as possible. Digital photographs, video records with spoken commentary, field measurements, and field notes are appropriate forms of field information. A written or pictorial record should be made of any observed problems with an existing bridge or obvious site problems. The site visit data would then be incorporated into the job file. This information will be a valuable asset in preparing constructible and cost-effective structural designs.

It is important to include site visits as part of the consultant's scope of work when negotiating for structural design work.

1.6.6 Proximity of Railroads Adjacent to the Bridge Site

During the site visit, it should be noted if there are railroad tracks or railroad structures adjacent to the proposed bridge site. If there are, this will require that a *Railroad Shoring Plan* be included in the bridge plans for any foundation excavation adjacent to the railroad. The reason for including the *Railroad Shoring Plan* is to obtain advance approval of the shoring plan from the railroad so that waiting for the railroad's approval will not cause a delay during construction. The contractor will have to resubmit a revised *Railroad Shoring Plan* to the railroad for approval if the contractor wishes to change any details of the approved *Railroad Shoring Plan* during construction.

At the PS&E submittal phase, the Specifications and Estimates Engineer will send copies of the *Railroad Shoring Plan* to the WSDOT Railroad Liaison Engineer so it can be sent to the railroad for approval.

1.99 Bibliography

1. *LRFD Bridge Design Specifications*, Latest Edition and Interims. American Association of State Highway and Transportation Officials (AASHTO), Washington, D.C.
2. *Design Manual*, WSDOT M22-01.
3. *Construction Manual*, WSDOT M41-01.
4. *As-Built Plans Manual*, WSDOT Bridge & Structures Office, August 2003.

Washington State Department of Transportation
HIGHWAY DIVISION
BRIDGE AND STRUCTURES BRANCH

SPECIAL PROVISIONS CHECKLIST

SR	JOB NO.	PROJECT TITLE	
DESIGN BY	CHECK BY	DATE	SUPV.
TYPE OF STRUCTURE			

INSTRUCTIONS:
- ☑ Check items pertaining to this structure
- ☒ Cross items not pertaining to this structure
- ☐ _____ Note other items on blank lines.

A. Permits and Regulations
- ☐ Coast Guard
- ☐ _____

B. Railroads
- ☐ Railroad Bridge
- ☐ Railroad in vicinity
- ☐ _____

C. Order of Work
- ☐ Approach embankment settlement period
- ☐ Stage construction sequence
- ☐ _____

D. Traffic Control
- ☐ Reduction in traffic lanes
- ☐ Traffic within _____ feet of new construction
- ☐ Traffic detoured, no traffic on bridge
- ☐ One way traffic on bridge
- ☐ _____

E. Utilities and Existing Pavement
- ☐ Utilities on Bridge, type _____, Utility Agreement No. _____
- ☐ Existing utilities in vicinity of construction
- ☐ Existing pavement in vicinity of construction
- ☐ _____

F. Falsework
- ☐ Falsework opening over existing roadway
- ☐ Falsework opening over railroad
- ☐ Falsework opening over water
- ☐ Protection of falsework
- ☐ Supported from existing structure
- ☐ Not supported from existing structure

DOT FORM 230-037 Page 1 of 6
5/87

Special Provisions Checklist
Figure 1-A-1

F. Falsework (Continued)	☐ Special falsework release sequence required ☐ _____
G. Foundation	☐ Excavation near existing pavement ☐ Excavation near railroad track or facilities ☐ Concrete Seals ☐ Seal construction using a berm ☐ Cofferdams ☐ Pumping water from foundation excavation required ☐ Riprap at piers ☐ Shaft Excavation ☐ Removal of unsuitable material ☐ Rock excavation requiring threshold limit value ☐ Special Excavation ☐ _____
H. Forms	☐ Special forms for architectural treatment ☐ Fractured Fin Finish ☐ Remove forms from cells which have access (Box girder) ☐ _____
I. Piling	☐ Concrete test pile ☐ Concrete piling _____ ton ☐ Steel test pile ☐ Steel piling _____ ☐ Timber test pile ☐ Timber piling ☐ Pile loading test ☐ Pile tip elevations ☐ Pile splice ☐ Pile tip ☐ Preboring for pile ☐ Driving piles in highly developed business or residential areas ☐ Excavation for pile ☐ Driving from existing structure ☐ No driving from existing structure ☐ _____

DOT FORM 230-037 Page 2 of 6
5/87

Special Provisions Checklist (Continued)

Figure 1-A-1

J. Prestressed Concrete Girders

- ☐ Epoxy - coated prestressing steel
- ☐ _____

K. Superstructure

- ☐ Concrete class LS
- ☐ Concrete class PC
- ☐ Prestressed concrete girder
- ☐ Precast prestressed tri beam
- ☐ Precast Prestressed double tee beam
- ☐ Precast segment
- ☐ Post - tensioning tendons
- ☐ Elastomeric bearing pads
- ☐ Fabric pad bearing
- ☐ Pot bearing
- ☐ Disc bearing
- ☐ Spherical bearing
- ☐ Cylindrical bearing
- ☐ Electrical Conduit
- ☐ Expansion joint
- ☐ _____

L. Steel Structure

- ☐ Structural Carbon Steel
- ☐ Structural Low Alloy Steel
- ☐ Structural H.S. Steel
- ☐ Steel Casting
- ☐ A - 307 Fasteners
- ☐ M - 164 Fasteners
- ☐ A - 490 Fasteners
- ☐ Shop Assembling
- ☐ Notch Toughness Requirements
- ☐ Application of Paint - Color No. _____
- ☐ Steel Erection
- ☐ _____

M. Timber Structures

- ☐ Untreated
- ☐ Creosote treated
- ☐ Salt treated
- ☐ Glulam deck panels

DOT FORM 230-037 Page 3 of 6
5/87

Special Provisions Checklist (Continued)

Figure 1-A-1

M. Timber Structures (Continued)

- ☐ Type and grade of Timber
- ☐ Fire prevention requirement needed
- ☐ _____

N. Signing and Lighting

- ☐ Navigation lighting system
- ☐ Temporary navigation light
- ☐ Sign bridge on structure
- ☐ Cantilever sign structure on bridge
- ☐ Bridge Mounted Sign brackets
- ☐ _____

O. Drainage System

- ☐ Special bridge drains
- ☐ Bridge grate inlets
- ☐ Downspout
- ☐ _____

P. Surface Finish

- ☐ Fractured fin finish
- ☐ Sandblast finish
- ☐ Pigmented Sealer
- ☐ _____

Q. Special Classes of Concrete

- ☐ Concrete Class EA
- ☐ Concrete Class HE
- ☐ _____

R. Bridge Widening or Replacement

- ☐ Removing portions of existing structure
- ☐ Salvage Materials, Storage Site _____, Salvage item _____
- ☐ Coating concrete surface with epoxy resin
- ☐ Drilling holes
- ☐ Core drilled holes
- ☐ Grout rebar with grout
- ☐ Grout rebar with epoxy
- ☐ Use of rockbolts or rock anchors
- ☐ Concrete class LS
- ☐ Grout, Comp. strength _____ psi at ____ days, Location _____
- ☐ As built plans of existing structure available for bidder's inspection

DOT FORM 230-037 Page 4 of 6
5/87

Special Provisions Checklist (Continued)

Figure 1-A-1

R. Bridge Widening or Replacement (Continued)

- ☐ ACP overlay
- ☐ LMC overlay
- ☐ Polymer Concrete Overlay
- ☐ Bridge Deck Repair
- ☐ Further Deck Preparation
- ☐ Complete removal of existing structure
- ☐ Explosives prohibited
- ☐ Explosives allowed
- ☐ _____

S. Waterproofing

- ☐ Membrane Waterproofing (Deck Seal)
- ☐ Connection for testing Waterproofing Membrane
- ☐ _____

T. Miscellaneous Items

- ☐ Temporary oak blocks
- ☐ Poured rubber
- ☐ Expanded polystyrene
- ☐ Plastic waterstops
- ☐ Expanded rubber
- ☐ Butyl Rubber Sheeting
- ☐ Grout, Comp. strength _____ psi at ____ days, Location _____
- ☐ Electrical Conduit
- ☐ _____

U. Metal Bridge Railing

- ☐ Bridge Railing Type BP
- ☐ Bridge Railing Type _____
- ☐ _____

V. Repair Work

- ☐ Epoxy Crack Sealing
- ☐ Timber Redecking
- ☐ Concrete Deck Repair
- ☐ _____

W. Other Items

- ☐ Ceramic Tiles
- ☐ Structural Earth Wall
- ☐ Tieback Wall
- ☐ Noise Barrier

DOT FORM 230-037 Page 5 of 6
5/87

Special Provisions Checklist (Continued)

Figure 1-A-1

R. Bridge Widening or Replacement (Continued)

- ☐ ACP overlay
- ☐ LMC overlay
- ☐ Polymer Concrete Overlay
- ☐ Bridge Deck Repair
- ☐ Further Deck Preparation
- ☐ Complete removal of existing structure
- ☐ Explosives prohibited
- ☐ Explosives allowed
- ☐ _____

S. Waterproofing

- ☐ Membrane Waterproofing (Deck Seal)
- ☐ Connection for testing Waterproofing Membrane
- ☐ _____

T. Miscellaneous Items

- ☐ Temporary oak blocks
- ☐ Poured rubber
- ☐ Expanded polystyrene
- ☐ Plastic waterstops
- ☐ Expanded rubber
- ☐ Butyl Rubber Sheeting
- ☐ Grout, Comp. strength _____ psi at ____ days, Location _____
- ☐ Electrical Conduit
- ☐ _____

U. Metal Bridge Railing

- ☐ Bridge Railing Type BP
- ☐ Bridge Railing Type _____
- ☐ _____

V. Repair Work

- ☐ Epoxy Crack Sealing
- ☐ Timber Redecking
- ☐ Concrete Deck Repair
- ☐ _____

W. Other Items

- ☐ Ceramic Tiles
- ☐ Structural Earth Wall
- ☐ Tieback Wall
- ☐ Noise Barrier

DOT FORM 230-037 Page 5 of 6
5/87

Special Provisions Checklist (Continued)

Figure 1-A-1

Washington State Department of Transportation

Breakdown of Project Manhours Required

Job No. _____ SR _____ Project _____ Made By _____ Date _____

No.	Drawing or Item	Design				Check				Draw				Check Drawing				Comments
		By	% Completed	Hours Required	Date Completed	By	% Completed	Hours Required	Date Completed	By	% Completed	Hours Required	Date Completed	By	% Completed	Hours Required	Date Completed	
1																		
2																		
3																		
4																		
5																		
6																		
7																		
8																		
9																		
10																		
11																		
12																		
13																		
14																		
15																		
16																		
17																		
18																		
19																		
20																		
21																		
22																		

DOT 232-002 (formerly C1M5)
Rev 3/91

Breakdown of Project Manhours Required Form
Figure 1-A-2

Washington State Department of Transportation

Monthly Project Progress Report

SR | Job No. | Project

Activity No.	As of / Reference No.	Man Hours Used to Date	% of Total Time Used	% of Activity Complete	% of Total Project Complete	As of / Reference No.	Man Hours Used to Date	% of Total Time Used	% of Activity Complete	% of Total Project Complete	As of / Reference No.	Man Hours Used to Date	% of Total Time Used	% of Activity Complete	% of Total Project Complete
1															
2															
3															
4															
5															
6															
7															
8															
9															
Totals															

DOT 232-004 (formerly C1M4)
Rev 3/91

Monthly Project Progress Report Form
Figure 1-A-3

Washington State Department of Transportation

Bridge Site Data General

Region	Made By	Date

Bridge Information

SR	Bridge Name	Control Section	Project No.

Highway Section	Section, Township & Range	Datum

Structure width between curbs ?

Will the structure be widened in a contract subsequent to this contract ? ☐ Yes ☐ No ☐ N/A

Which side and amount ?

Will the roadway under the structure be widened in the future? ☐ Yes ☐ No ☐ N/A

Stage construction requirements? ☐ Yes ☐ No ☐ N/A

Should the additional clearance for off-track railroad maintenance equipment be provided?

Can a pier be placed in the median? ☐ Yes ☐ No ☐ N/A

What are the required falsework or construction opening dimensions ?

Are there detour or shoofly bridge requirements? (If Yes, attach drawings) ☐ Yes ☐ No ☐ N/A

Can the R/W be adjusted to accommodate toe of approach fills? ☐ Yes ☐ No ☐ N/A

What is the required vertical clearance?

What is the available depth for superstructure?

Are overlays planned for a contract subsequent to this contract? ☐ Yes ☐ No ☐ N/A

Can profile be revised to provide greater or less clearance? ☐ Yes ☐ No ☐ N/A

If Yes, which line and how much?

Will bridge be constructed before, with or after approach fill? ☐ Before ☐ With ☐ After ☐ N/A

What are expected foundation conditions?

When can foundation drilling be accomplished?

Is slope protection or riprap required for the bridge end slopes? ☐ Yes ☐ No ☐ N/A

Are sidewalks to be provided? ☐ Yes ☐ No ☐ N/A

If Yes, which side and width?

Will sidewalks carry bicycle traffic? ☐ Yes ☐ No ☐ N/A

Will signs or illumination be attached to the structure? ☐ Yes ☐ No ☐ N/A

Will utility conduits be incorporated in the bridge? ☐ Yes ☐ No ☐ N/A

What do the bridge barriers transition to?

Furnish type and location of existing features within the limits of this project, such as retaining walls, sign support structures, utilities, buildings, powerlines, etc.

Any other data relative to selection of type, including your recommendations?

Attachments

- ☐ Vicinity Map
- ☐ Bridge Site Contour Map
- ☐ Specific Roadway sections at bridge site and approved roadway sections
- ☐ Vertical Profile Data
- ☐ Horizontal Curve Data
- ☐ Superelevation Transition Diagrams
- ☐ Tabulated field surveyed and measured stations, offsets, and elevations of existing roadways
- ☐ Photographs and video tape of structure site, adjacent existing structures and surrounding terrain
- ☐
- ☐

DOT Form 235-002 EF
Revised 1/2000

Bridge Site Date General
Figure 2-A-1

Washington State Department of Transportation

Bridge Site Data Rehabilitation

Region	Made By	Date

Bridge Information

SR	Bridge Name	Control Section	Project No.

Highway Section	Section, Township & Range	Vertical Datum

Existing roadway width, curb to curb _____ Left of ℄ _____ Right of ℄ _____

Proposed roadway width, curb to curb _____ Left of ℄ _____ Right of ℄ _____

Existing wearing surface *(concrete, HMA, HMA w /membrane, MC, epoxy, other)* _____ Thickness _____

Existing drains to be plugged, modified, moved, other? _____

Proposed overlay *(HMA, HMA w /membrane, MC, epoxy)* _____ Thickness _____

Is bridge rail to be modified? ☐ Yes ☐ No

Existing rail type _____

Proposed rail replacement type _____

Will terminal design "F" be required? ☐ Yes ☐ No

Will utilities be placed in the new barrier? ☐ Yes ☐ No

Will the structure be overlayed with or after rail replacement? ☐ With Rail Replacement ☐ After Rail Replacement

Condition of existing expansion joints _____

Existing expansion joints watertight? ☐ Yes ☐ No

Measure width of existing expansion joint, normal to skew. @ curb line _____ Inch @ ℄ roadway _____ Inch @ curb line _____ Inch

Estimate structure temperature at time of expansion joint measurement _____

Type of existing expansion joint _____

Describe damage, if any, to existing expansion joints _____

Existing Vertical Clearance _____

Proposed Vertical Clearance (at curb lines of traffic barrier) _____

Attachments

☐ Video tape of project

☐ Sketch indicating points at which expansion joint width was measured.

☐ Photographs of existing expansion joints.

☐ Existing deck chloride and delamination data.

☐ Roadway deck elevations at curb lines (10-foot spacing)

DOT Form 235-002A EF
Revised 5/05

Bridge Site Date Rehabilitation
Figure 2-A-2

Washington State
Department of Transportation

Bridge Site Data
Stream Crossings

Region	Made By	Date

Bridge Information

SR	Bridge Name	Control Section	Project No.

Highway Section	Section, Township & Range	Datum

Name of Stream	Tributary of

Elevation of W.S. *(@ date of survey)* _____ Stream Velocity *(fps @ date of survey)* _____ Depth of Flow *(@ date of survey)* _____

Max Highwater Elevation _____ @ Date _____

Normal Highwater Elevation _____ @ Date _____

Normal Stage Elevation _____ @ Date _____

Extreme Low Water Elevation _____ @ Date _____

Amount and Character of Drift _____

Streambed Material _____

Datum *(i.e., USC and GS, USGS, etc.)* _____

Manning's "N" Value *(Est.)* _____

Attachments

- ☐ Site Contour Map *(See Sect. 7.02.00 Highway Hydraulic Manual)*
- ☐ Highway Alignment and Profile *(refer to map and profiles)*
- ☐ Streambed: Profile and Cross Sections *(500 ft. upstream and downstream)*
- ☐ Photographs
- ☐ Character of Stream Banks *(i.e., rock, silt, etc.)* / Location of Solid Rock
- ☐ Other Data Relative to Selection of Type and Design of Bridge, Including your Recommendations *(i.e., requirements of riprap, permission of piers in channel, etc.)*

DOT Form 235-001 EF
Revised 3/97

Bridge Site Date Stream Crossing
Figure 2-A-3

Project_____ SR_____ Prelim. Plan by _____ Check by _____ Date_____

PLAN

___Survey Lines and Station Ticks
___Survey Line Intersection Angles
___Survey Line Intersection Stations
___Survey Line Bearings
___Roadway and Median Widths
___Lane and Shoulder Widths
___Sidewalk Width
___Connection/Widening for Guardrail/Barrier
___Profile Grade and Pivot Point
___Roadway Superelevation Rate (if constant)
___Lane Taper and Channelization Data
___Traffic Arrows
___Mileage to Junctions along Mainline
___Back to Back of Pavement Seats
___Span Lengths
___Lengths of Walls next to/ part of Bridge
___Pier Skew Angle
___Bridge Drains, or Inlets off Bridge
___Existing drainage structures
___Existing utilities Type/Size, and Location
___New utilities - Type, Size, and Location
___Luminaires, Junction Boxes, Conduits
___Bridge mounted Signs and Supports
___Contours
___Top of Cut: Toe of Fill
___Bottom of Ditches
___Test Holes (if available)
___Riprap Limits
___Stream Flow Arrow
___R/W Lines and/or Easement Lines
___Points of Minimum Vertical Clearance
___Horizontal Clearance
___Exist. Bridge No. (to be removed, widened)
___Section, Township, Range
___City or Town
___North Arrow
___SR Number
___Bearing of Piers, or note if radial

MISCELLANEOUS

___Structure Type
___Live Loading
___Undercrossing Alignment Profiles/Elevs.
___Superelevation Diagrams
___Curve Data
___Riprap Detail
___Layout Approval Block
___Notes to Region
___Names and Signatures
___Not Included in Bridge Quantities List
___Inspection and Maintenance Access

ELEVATION

___Full Length Reference Elevation Line
___Existing Ground Line x ft. Rt of Survey Line
___End Slope Rate
___Slope Protection
___Pier Stations and Grade Elevations
___Profile Grade Vertical Curves
___BP/Pedestrian Rail
___Barrier/Wall Face Treatment
___Construction/Falsework Openings
___Minimum Vertical Clearances
___Water Surface Elevations and Flow Data
___Riprap
___Seal Vent Elevation
___Datum
___Grade elevations shown are equal to …
___For Embankment details at bridge ends …
___Indicate F, H, or E at abutments and piers

TYPICAL SECTION

___Bridge Roadway Width
___Lane and Shoulder Widths
___Profile Grade and Pivot Point
___Superelevation Rate
___Survey Line
___Overlay Type and Depth
___Barrier Face Treatment
___Limits of Pigmented Sealer
___BP/Pedestrian Rail dimensions
___Stage Construction Lane Orientations
___Locations of Temporary Concrete Barrier
___Closure Pour
___Structure Depth/Prestressed Girder Type
___Conduits/Utilities in bridge
___Substructure Dimensions

LEFT MARGIN


___Job Number
___Bridge (before/with/after) Approach Fills
___Structure Depth/Prestressed Girder Type
___Deck Protective System
___Coast Guard Permit Status
___Railroad Agreement Status
___Points of Minimum Vertical Clearance
___Cast in Place Concrete Strength

RIGHT MARGIN


___Control Section
___Project Number
___Region
___Highway Section
___SR Number
___Structure Name

Preliminary Plan Checklist
Figure 2-A-4

BRIDGE STAGE CONSTRUCTION COMPARISON



1. NO LANES OPEN: RELATIVE COST FACTOR (RCF) = 1.0




2. TWO LANES OPEN WITH NEW ALIGMENT: RFC = 1.0



3. ONE LANE OPEN WITH NEW ALIGMENT AND STAGE CONSTRUCTION: RCF = 1.2




4. ONE LANE OPEN WITH STAGE CONSTRUCTION: RCF = 1.2



5. ONE LANE OPEN WITH DETOUR: RCF = 1.3



6. TWO LANES OPEN WITH DETOUR AND STAGE CONSTRUCTION: RCF = 1.5




7. TWO LANES OPEN WITH DETOUR: RCF = 1.6

ASSUMPTIONS:
NEW BRIDGE, TWO SPAN PRESTRESSED GIRDER, 200 FT. LONG.
DETOUR BRIDGE, TWO SPAN STEEL GIRDER WITH TIMBER TRESTLES, 200 FT. LONG.
$50/FT WITH 20% PREMIUM WHEN STAGING CONSTRUCTION.


THIS CHART IS INTENDED TO SHOW SOME OF THE MANY OPTIONS AVAILABLE FOR STAGING BRIDGE CONSTRUCTION. THE ACTUAL COST FACTORS FOR A SPECIFIC PROJECT ARE VERY SENSITIVE TO THE FACTORS OUTLINED IN SECTION 2.2.3. ANY COMPARISON MADE FOR A PROJECT SHOULD BE DONE UNDER THE GUIDANCE OF THE PRELIMINARY DESIGN UNIT OF THE BRIDGE AND STRUCTURES OFFICE.

Bridge StageConstruction Comparison
Figure 2-A-5




1 COLUMN MINIMUM

PROVIDE COLLISION PROTECTION
OR DESIGN FOR COLLISION LOADS.




2 COLUMNS MINIMUM

PROVIDE COLLISION PROTECTION
OR DESIGN FOR COLLISION LOADS.




3 COLUMNS MINIMUM

SUBSTRUCTURE DESIGN



3 WEBS MINIMUM



4 WEBS MINIMUM

SUPERSTRUCTURE DESIGN

DESIGN NOTES:

1. USE THE MINIMUM COLUMNS AND WEBS SHOWN TO MEET REDUNDANCY CRITERIA FOR PREVENTING CATASTROPHIC COLLAPSE OF BRIDGES.
2. DRAWINGS ARE SHOWN FOR CONCRETE BOX GIRDERS BRIDGES, BUT THE COLUMN AND WEB REQUIREMENTS ALSO APPLY TO OTHER BRIDGE TYPES.

BRIDGE REDUNDANCY CRITERIA

Figure 2-A-6

	STRUCTURE TYPES	SPAN RANGE, FT.	JULY 2002 COST RANGE $ / FT²
HYDAULIC STRUCTURES	PIPE	1 - 3	15 - 45
	CONCRETE CULVERT	3 - 20	75 - 90
	PLATE ARCH	12 - 20	45 - 60
STRUCTURES FOR CONVENTIONAL SITE CONDITIONS	REINF. CONCRETE SLAB	20 - 60	70 - 110
	REINF. CONCRETE TEE BEAM	30 - 60	70 - 120
	REINF. CONCRETE BOX GIRDER	50 - 140	100 - 150
	POST-TENSIONED CONC. BOX GIRDER	140 - 200	120 - 160
	SEGMENTAL P.T. BOX GIRDER	200 - 700	160 - 200
	PRESTRESSED CONC. SLAB	15 - 80	75 - 95
	PRESTRESSED CONC. DECK BULB TEE	40 - 160	80 - 125
	PRESTRESSED CONC. GIRDER	50 - 180	80 - 140
	PRESTRESSED TRAPEZOIDAL TUB GIRDER	40 - 140	140 - 160
	PRESTRESSED CONCRETE SPLICED GIRDER	140 - 230	100 - 150
	STEEL ROLLED GIRDER	20 - 70	100 - 125
	STEEL PLATE GIRDER	60 - 400	110 - 180
	STEEL BOX GIRDER	60 - 400	150 - 230
	STEEL TRUSS	300 - 1200	200 - 300
	TIMBER	10 - 20	80 - 100
	GLULAM TIMBER	14 - 40	80 - 100
STRUCTURES FOR SPECIAL SITE CONDITIONS	CABLE STAY BRIDGE	600 - 1200	250 - 400
	SUSPENSION BRIDGE	600 - 5000	600 - 850
	FLOATING BRIDGE	600 +	400 - 700
	ARCH BRIDGE	30 - 400	250 - 300
	MOVEABLE SPAN BRIDGE	200 - 350	1100 - 1500
	TUNNEL	30 +	800 - 2000







Figure 2-A-7



ELEVATION
SINGLE SPAN BRIDGE



ELEVATION
TWO SPAN BRIDGE



STANDARD SUPERSTRUCTURE ELEMENTS

Figure 2-A-8

Chapter 2 Preliminary Design

2.1 Preliminary Studies 2-1
2.1.1 Interdisciplinary Design Studies 2-1
2.1.2 Value Engineering Studies 2-1
2.1.3 Preliminary Recommendations for Bridge Rehabilitation Projects 2-1
2.1.4 Preliminary Recommendations for New Bridge Projects 2-2
2.1.5 Type, Size, and Location (TS&L) Reports 2-2
2.2 Preliminary Plan 2-6
2.2.1 Development of the Preliminary Plan 2-6
2.2.2 Documentation 2-7
2.2.3 General Factors for Consideration 2-8
2.2.4 Permits 2-10
2.2.5 Preliminary Cost Estimate 2-10
2.2.6 Approvals 2-11
2.3 Preliminary Plan Criteria 2-14
2.3.1 Highway Crossings 2-14
2.3.2 Railroad Crossings 2-17
2.3.3 Water Crossings 2-19
2.3.4 Bridge Widenings 2-21
2.3.5 Detour Structures 2-22
2.3.6 Retaining Walls and Noise Walls 2-22
2.3.7 Bridge Deck Drainage 2-22
2.3.8 Bridge Deck Protective Systems 2-22
2.3.9 Construction Clearances 2-23
2.3.10 Design Guides for Falsework Depth Requirements 2-23
2.3.11 Inspection and Maintenance Access 2-24
2.4 Selection of Structure Type 2-26
2.4.1 Bridge Types 2-26
2.4.2 Wall Types 2-31
2.5 Aesthetic Considerations 2-32
2.5.1 General Visual Impact 2-32
2.5.2 End Piers 2-32
2.5.3 Intermediate Piers 2-33
2.5.4 Barrier and Wall Surface Treatments 2-33
2.5.5 Superstructure 2-34
2.6 Miscellaneous 2-35
2.6.1 Structure Costs 2-35
2.6.2 Handling and Shipping Precast Members and Steel Beams 2-35
2.6.3 Salvage of Materials 2-35
2.7 WSDOT Standard Highway Bridge 2-36
2.7.1 Design Elements 2-36
2.7.2 Detailing the Preliminary Plan 2-37
2.99 Bibliography 2-38
Appendix 2-A
Figure 2-A-1 Bridge Site Date General 2-A-1
Figure 2-A-2 Bridge Site Date Rehabilitation 2-A-2
Figure 2-A-3 Bridge Site Date Stream Crossing 2-A-3

Figure 2-A-4 Preliminary Plan Checklist..... 2-A-4
Figure 2-A-5 Bridge StageConstruction Comparison..... 2-A-5
Figure 2-A-6 ..... 2-A-6
Figure 2-A-7 ..... 2-A-7
Figure 2-A-8 ..... 2-A-8
Appendix 2-B
Figure 2-B-1 Preliminary Plan Bridge Replacement..... 2-B-1
Figure 2-B-2 Preliminary Plan Bridge Replacement..... 2-B-2
Figure 2-B-3 Preliminary Plan Bridge Replacement..... 2-B-3
Figure 2-B-4 Preliminary Plan Bridge Widening 2-B-4
Figure 2-B-5 Preliminary Plan Bridge Widening 2-B-5
Figure 2-B-6 Preliminary Plan Bridge Widening 2-B-6
Figure 2-B-7 Preliminary Plan Bridge with Staging 2-B-7
Figure 2-B-8 Preliminary Plan Bridge with Staging 2-B-8
Figure 2-B-9 Preliminary Plan Bridge Replacement..... 2-B-9

2.1 Preliminary Studies

2.1.1 Interdisciplinary Design Studies

Region may set up an Interdisciplinary Design Team (IDT) to review the various design alternatives for major projects. The IDT is composed of members from Regions, HQ, outside agencies, and consulting firms. The members have different areas of expertise, contribute ideas, and participate in the selection of design alternatives. This work will often culminate in the publication of an Environmental Impact Statement (EIS).

Bridge designers may be asked to participate either as a support resource or as a member of the IDT.

2.1.2 Value Engineering Studies

Value Engineering (VE) is a review process and analysis of a design project. The VE team seeks to define the most cost-effective means of satisfying the basic function(s) of the project. Usually a VE study takes place before or during the time that the region is working on the design. Occasionally, a VE study examines a project with a completed PS&E. VE studies are normally required for projects with cost overruns.

The VE team is headed by a facilitator and is composed of members with different areas of expertise from Regions, HQ, outside agencies, and consulting firms. The Team Facilitator will lead the team through the VE process. The team will review Region's project as defined by the project's design personnel. The VE team will determine the basic function(s) that are served by the project, brainstorm all possible alternatives to serve the same function(s), evaluate the alternatives for their effectiveness to meet the project's basic functions, determine costs, and prioritize and recommend alternatives. The VE team will prepare a report and present their findings to the region. The Region is then required to investigate and address the VE team's findings in the final design.

Bridge designers may be asked to participate either as a support resource or as a member of the VE team. VE studies usually take place over a three to five day period.

Engineers participating in VE studies and Cost-Risk Assessment meetings shall call the S&E Engineers and double check all costs when providing cost estimates at VE studies and CRA meetings.

2.1.3 Preliminary Recommendations for Bridge Rehabilitation Projects

When the Region starts a bridge rehabilitation project, they will submit a written memo requesting that the Bridge and Structures Office make preliminary project recommendations.

The Bridge and Structures Office will review the as-built plans, load ratings, existing inspection and condition reports prepared by the Bridge Preservation Office (BPO), and schedule a site visit with Region and other stakeholders. Special inspection of certain portions of the structure may be included in the site visit or scheduled later with Region and BPO. The purpose of the inspections is to obtain more detailed information as to the bridge's condition, to obtain dimensions and take photographs of details needed for the project recommendations.

Following the site visit, the next steps are:

- Determine the load capacity of the existing bridge.
- Determine what type of rehabilitation work is needed and time frame required to accomplish the work.
- Determine any special construction staging requirements. Can the bridge be totally shut down for the rehabilitation period? How many lanes will need to be open? Can the work be accomplished during night closures or weekend closures?
- Develop various alternatives and cost estimates for comparison, ranging from "do nothing" to "new replacement".
- Determine what the remaining life expectancies are for the various rehabilitation alternatives.
- Determine the cost of a new replacement bridge.

Note: The FHWA will not participate in funding the bridge rehabilitation project if the rehabilitation costs exceed 50 percent of the cost for a new bridge replacement.

The Bridge and Structures Office will provide Region with a written report with background information. The Region will be given an opportunity to review the draft report and to provide input prior to finalization.

The Bridge Projects Engineer and Specifications & Estimates Engineers provide bridge scoping cost estimates to Regions for their use in determining budgets during Region's project definition phase. The S&E Engineers will check the Bridge Project Engineer's estimate as well as check each other.

2.1.4 Preliminary Recommendations for New Bridge Projects

The Region will seek assistance from the Bridge and Structures Office when they are preparing a design project requiring new bridges. Similar to the procedures outlined above for rehabilitation projects. The Region will submit a written memo requesting that the bridge office make preliminary project recommendations. The Bridge and Structures Office will provide scope of work, cost estimate(s), and a summary of the preferred alternatives with recommendations. Face to face meetings with the Region project staff are recommended prior to sending a written memo.

The Bridge Projects Engineer and Specifications & Estimates Engineers provide bridge scoping cost estimates to Regions for their use in determining budgets during Region's project definition phase. The S&E Engineers will check the Bridge Project Engineer's estimate as well as check each other.

2.1.5 Type, Size, and Location (TS&L) Reports

The Federal Highway Administration (FHWA) requires that major or unusual bridges must have a Type, Size, and Location (TS&L) report prepared. The report will describe the project, proposed structure(s), cost estimates, other design alternatives considered, and recommendations. The report provides justification for the selection of the preferred alternative. Approval by FHWA of the TS&L study is the basis for advancing the project to the design stage.

The FHWA should be contacted as early as possible in the Project Development stage because the FHWA requires a TS&L study for tunnels, movable bridges, unusual structures, and major structures. Smaller bridges that are unusual or bridge projects for Local Agencies may also require a TS&L study. Other projects, such as long viaducts, may not. Check with the Bridge Projects Engineer to see if a TS&L report is necessary.

The preparation of the TS&L report is the responsibility of the Bridge and Structures Office. The TS&L cannot be submitted to FHWA until after the environmental documents have been submitted. However, TS&L preparation need not wait for environmental document approval, but may begin as soon as the bridge site data is available. See Chapter 1110 of the WSDOT *Design Manual* for the type of information required for a bridge site data submittal.

A. TS&L General

The designer should first review the project history in order to become familiar with the project. The environmental and design reports should be reviewed. The bridge site data should be checked so that additional data, maps, or drawings can be requested. A meeting with Region and a site visit should be arranged after reviewing the history of the project.

The Materials Laboratory Geotechnical Services Branch must be contacted early in the TS&L process in order to have foundation information. Specific recommendations on the foundation type must be included in the TS&L report. The Materials Laboratory Geotechnical Services Branch will submit a detailed foundation report for inclusion as an appendix to the TS&L report.

To determine the preferred structural alternative, the designer should:

l. Develop a list of all feasible alternatives. At this stage, the range of alternatives should be kept wide open. Brainstorming with supervisors and other engineers can provide new and innovative solutions.

2. Eliminate the least desirable alternatives by applying the constraints of the project. Question and document the assumptions of any restrictions and constraints. There should be no more than four alternatives at the end of this step.

3. Perform preliminary design calculations for unusual or unique structural problems to verify that the remaining alternatives are feasible.

4. Compare the advantages, disadvantages, and costs of the remaining alternatives to determine the preferred alternative(s).

5. Visit the project site with the Region, Materials Laboratory Geotechnical Services Branch, and HQ Hydraulics staff.

FHWA expects specific information on scour and backwater elevations for the permanent bridge piers, as well as, for any temporary falsework bents placed in the waterway opening.

After the piers have been located, a memo requesting a Hydraulics Report should be sent to the HQ Hydraulics Unit. The HQ Hydraulics Unit will submit a report for inclusion as an appendix to the TS&L report.

The State Bridge and Structures Architect should be consulted early in the TS&L study period. “Notes to the File” should be made documenting the aesthetic requirements and recommendations of the State Bridge and Structures Architect.

Cost backup data is needed for any costs used in the TS&L study. FHWA expects TS&L costs to be based on estimated quantities. This cost data is to be included in an appendix to the TS&L report. The quantities should be compatible with the S&E Engineer’s cost breakdown method. The Specifications & Estimates Engineers will check the designer's estimated costs included in TS&L reports. In the case of consultant prepared TS&L reports, the designer shall have the S&E Engineers check the construction costs.

B. TS&L Outline

The TS&L report should describe the project, the proposed structure, and give reasons why the bridge type, size, and location were selected.

1. Cover, Title Sheet, and Index

   These should identify the project, owner, location and the contents of the TS&L.

2. Photographs

   There should be enough color photographs to provide the look and feel of the bridge site. The prints should be numbered and labeled and the location indicated on a diagram.

3. Introduction

   The introduction describes the report, references, and other reports used to prepare the TS&L study. The following reports should be listed, if used.

   - Design Reports and Supplements
   - Environmental Reports
   - Architectural Visual Assessment or Corridor Theme Reports
   - Hydraulic Report
   - Geotechnical Reports

4. Project Description

   The TS&L report clearly defines the project. A vicinity map should be shown. Care should be taken to describe the project adequately but briefly. The project description summarizes the preferred alternative for the project design.

5. Design Criteria

   The design criteria identify the AASHTO LRFD Bridge Design Specifications and AASHTO guide specifications that will be used in the bridge design. Sometimes other design criteria or special loadings are used. These criteria should be listed in the TS&L. Some examples in this category might be the temperature loading used for segmental bridges or areas defined as wetlands.

6. Structural Studies

   The structural studies section documents how the proposed structure Type, Size, and Location were determined. The following considerations should be addressed.

   - Aesthetics
   - Cost Estimates
   - Geometric constraints
   - Project staging and Stage Construction Requirements
   - Foundations
   - Hydraulics
   - Feasibility of construction
   - Structural constraints
   - Maintenance

This section should describe how each of these factors leads to the preferred alternative. Show how each constraint eliminated or supported the preferred alternatives. Here are some examples. “Prestressed concrete girders could not be used because environmental restrictions required that no permanent piers could be placed in the river. This requires a 230-foot clear span.” “Restrictions on falsework placement forced the use of self supporting precast concrete or steel girders.”

7. Executive Summary

   The executive summary should be able to “stand alone” as a separate document. The project and structure descriptions should be given. Show the recommended alternative(s) with costs and include a summary of considerations used to select preferred alternatives or to eliminate other alternatives.

8. Drawings

   Preliminary plan drawings of the recommended alternative are included in an appendix. The drawings show the plan, elevation, and typical section. For projects where alternative designs are specified as recommended alternatives, preliminary plan drawings for each of the different structure types shall be included. Supplemental drawings showing special features, such as complex piers, are often included to clearly define the project.

C. Reviews and Submittals

   While writing the TS&L report, all major decisions should be discussed with the unit supervisor, who can decide if the Bridge Design Engineer needs to be consulted. A peer review meeting with the Bridge Design Engineer should be scheduled at the 50 percent completion stage. If applicable, the FHWA Bridge Engineer should be invited to provide input.

   The final report must be reviewed, approved, and the Preliminary Plan drawings signed by the State Bridge and Structures Architect, the Bridge Projects Engineer, the Bridge Design Engineer, and the Bridge and Structures Engineer. The TS&L study is submitted with a cover letter to FHWA signed by the Bridge and Structures Engineer.

2.2 Preliminary Plan

The Preliminary Plan preparation stage is the most important phase of bridge design because it is the basis for the final design. The Preliminary Plan should completely define the bridge geometry so the final roadway design by the regions and the structural design by the bridge office can take place with minimal revisions.

During the Region's preparation of the highway design, they also begin work on the bridge site data. Region submits the bridge site data to the Bridge and Structures Office, which initiates the start of the Preliminary Plan stage. Information that must be included as part of the bridge site data submittal is described in Chapter 1110 of the *Design Manual*.

2.2.1 Development of the Preliminary Plan

A. Responsibilities

In general, the responsibilities of the designer, checker, detailer, and unit supervisor are described in Section 1.2.2, Chapter 1, *Bridge Design Manual*. The Preliminary Plan Design Engineer or the assigned designer is responsible for developing a preliminary plan for the bridge. The preliminary plan must be compatible with the geometric, aesthetic, staging, geotechnical, hydraulic, financial, structural requirements and conditions at the bridge site.

Upon receipt of the bridge site data from the Region, the designer shall review it for completeness and verify that what the project calls for is realistic and structurally feasible. Any omissions or corrections are to be immediately brought to the Region's attention so that revised site date, if required, can be resubmitted to avoid jeopardizing the bridge design schedule.

The Unit Supervisor shall be kept informed of progress on the preliminary plan so that the schedule can be monitored. If problems develop, the Unit Supervisor can request adjustments to the schedule or allocate additional manpower to meet the schedule. The designer must keep the job file up-to-date by documenting all conversations, meetings, requests, questions, and approvals concerning the project. Notes-to-the-designer, and details not shown in the preliminary plan shall be documented in the job file.

The checker shall provide an independent review of the plan, verifying that it is in compliance with the site data as provided by the region and as corrected in the job file. The plan shall be compared against the Preliminary Plan checklist (see Appendix A) to ensure that all necessary information is shown. The checker is to review the plan for consistency with office design practice, detailing practice, and for constructibility.

The preliminary plan shall be drawn using current office CAD equipment and software by the designer or detailer.

B. Site Reconnaissance

The site data submitted by the Region will include photographs and a video of the site. Even for minor projects, this may not be enough information for the designer to work from to develop a preliminary plan. For most bridge projects, site visits are necessary.

Site visits with Region project staff and other project stakeholders, such as, Materials Laboratory Geotechnical Services Branch, HQ Hydraulics, and Region Design should be arranged with the knowledge and approval of the Bridge Projects Engineer.

C. Coordination

The designer is responsible for coordinating the design and review process throughout the project. This includes seeking input from various WSDOT units and outside agencies. The designer should consult with Materials Laboratory Geotechnical Services Branch, HQ Hydraulics, Bridge Preservation Office, and Region design and maintenance, and other resources for their input.

D. Consideration of Alternatives

In the process of developing the Preliminary Plan, the designer should brainstorm, develop, and evaluate various design alternatives. See Section 2.2.3 General Factors for Consideration and how they apply to a particular site. See also Section 2.1.5A. Preliminary design calculations shall be done to verify feasibility of girder span and spacing, falsework span capacity, geometry issues, and construction clearances. Generally, the number of alternatives will usually be limited to only a few for most projects. For some smaller projects and most major projects, design alternatives merit development and close evaluation. The job file should contain reasons for considering and rejecting design alternatives. This provides documentation for the preferred alternative.

E. Designer Recommendation

The designer should be able to make a recommendation for the preferred alternative after a thorough analysis of the needs and limitations of the site, studying all information, and developing and evaluating the design alternatives for the project. At this stage, the designer should discuss the recommendation with the Bridge Projects Engineer.

F. Concept Approval

For some projects, the presentation, in "E" above, to the Bridge Projects Engineer will satisfy the need for concept approval. Large complex projects, projects of unique design, or projects where two or more alternatives appear viable, should be presented to the Bridge Design Engineer for his/her concurrence before plan development is completed. For unique or complex projects a presentation to the Region Project Engineer, and Bridge and Structures Office Peer Review Committee may be appropriate.

2.2.2 Documentation

A. Job File

An official job file is created by the Bridge Scheduling Engineer when a memo transmitting site data from the region is received by the Bridge and Structures Office. This job file serves as a depository for all communications and resource information for the job. Scheduling and time estimates are kept in this file, as well as cost estimates, preliminary quantities, and documentation of all approvals. Records of important telephone conversations and copies of E-mails approving decisions are also kept in the job file.

After completing the Preliminary Plan, the job file continues to serve as a depository for useful communications and documentation for all pertinent project related information and decisions during the design process through and including preparation of the Final Bridge PS&E.

B. Bridge Site Data

All Preliminary Plans are developed from site data submitted by the Region. This submittal will consist of a memorandum IDC, and appropriate attachments as specified by Chapter 1110 of the *Design Manual*. When this information is received, it should be reviewed for completeness so that missing or incomplete information can be noted and requested.

C. Request for Preliminary Foundation Data

A request for preliminary foundation data is sent to the Geotechnical Services Branch to solicit any foundation data that is available at the preliminary stage. The Materials Laboratory Geotechnical Services Branch is provided with approximate dimensions for the overall structure length and width, approximate number of intermediate piers (if applicable), and approximate stations for beginning and end of structure on the alignment.

Based on test holes from previous construction in the area, geological maps, and soil surveys. The Materials Laboratory Geotechnical Services Branch responds by memo and a report with an analysis of what foundation conditions are likely to be encountered and what foundation types are best suited for the bridge site.

D. Request for Preliminary Hydraulics Data

A Request for preliminary hydraulics data is sent to the HQ Hydraulics Office to document hydraulic requirements that must be considered in the structure design. The HQ Hydraulics Office is provided a contour plan and other bridge site data.

The Hydraulics Office will send a memo providing the following data: seal vent elevations, normal water, 100-year and 500-year flood elevations and flows (Q), pier configuration, scour depth and minimum footing cover required, ice pressure, minimum waterway channel width, riprap requirements, and minimum clearance required to the 100-year flood elevation.

E. Design Report or Design Summary and Value Engineering Studies

Some bridge construction projects have a Design File Report or Design Summary prepared by the region. This is a document, which includes design considerations and conclusions reached in the development of the project. It defines the scope of work for the project. It serves to document the design standards and applicable deviations for the roadway alignment and geometry. It is also an excellent reference for project history, safety and traffic data, environmental concerns, and other information. If a VE study was done on the bridge, the report will identify alternatives that have been studied and why the recommended alternative was chosen.

F. Other Resources

For some projects, preliminary studies or reports will have been prepared. These resources can provide additional background for the development of the Preliminary Plan.

G. Notes of meetings with Regions and other project stakeholders shall be included in the job file.

2.2.3 General Factors for Consideration

Many factors must be considered in preliminary bridge design. Some of the more common of these are listed in general categories below. These factors will be discussed in appropriate detail in subsequent portions of this manual.

A. Site Requirements

Topography
Alignment (tangent, curved, skewed)
Vertical profile and superelevation
Highway Class and design speed
Proposed or existing utilities

B. Safety

Feasibility of falsework (impaired clearance and sight distance, depth requirements, see BDM 2.3.10)
Density and speed of traffic
Detours or possible elimination of detours by construction staging
Sight distance
Horizontal clearance to piers
Hazards to pedestrians, bicyclists

C. Economic

Funding classification (federal and state funds, state funds only, local developer funds)
Funding level
Bridge preliminary cost estimate

D. Structural

Limitation on structure depth
Requirements for future widening
Foundation and groundwater conditions
Anticipated settlement
Stage construction
Falsework limitations

E. Environmental

Site conditions (wetlands, environmentally sensitive areas)
EIS requirements
Mitigating measures
Construction access

F. Aesthetic

General appearance
Compatibility with surroundings and adjacent structures
Visual exposure and experience for public

G. Construction

Ease of construction
Falsework clearances and requirements
Erection problems
Hauling difficulties and access to site
Construction season
Time limit for construction

H. Hydraulic

Bridge deck drainage
Stream flow conditions and drift
Passage of flood debris
Scour, effect of pier as an obstruction (shape, width, skew, number of columns)
Bank and pier protection
Consideration of a culvert as an alternate solution
Permit requirements for navigation and stream work limitations

I. Maintenance

Concrete vs. Steel
Expansion joints
Bearings
Deck protective systems
Inspection and Maintenance Access (UBIT clearances) (see Figure 2.3.101)

J. Other

Prior commitments made to other agency officials and individuals of the community
Recommendations resulting from preliminary studies

2.2.4 Permits

A. Coast Guard

As outlined in Chapter 240 of the *Design Manual*, the Bridge and Structures Office is responsible for coordinating and applying for Coast Guard permits for bridges over waterways. This is handled by the Coast Guard Liaison Engineer in the Bridge Projects Unit of the Bridge and Structures Office.

A determination of whether a bridge requires a permit is known before the bridge site data is received. Generally, tidal-influenced waterways and waterways used for commercial navigation will require Coast Guard permits.

For all waterway crossings, the Coast Guard Liaison Engineer is required to initial the Preliminary Plan as to whether a Coast Guard permit or exemption is required. This box regarding Coast Guard permit status is located in the center left margin of the plan. If a permit is required, the permit target date will also be noted. The reduced print, signed by the Coast Guard Liaison Engineer, shall be placed in the job file.

The work on developing the permit application should be started so that it is ready to be sent to the Coast Guard eight months prior to the project ad date. The Coast Guard Liaison Engineer should be given a copy of the preliminary plan from which to develop the plan sheets, which are part of the permit.

B. Other

All other permits will be the responsibility of the Region. The Bridge and Structures Office may be asked to provide information to the Region to assist them in making applications for these permits.

2.2.5 Preliminary Cost Estimate

A preliminary cost estimate should be developed when the bridge type, foundation type, deck area and adjacent retaining walls are determined. At the preliminary stage the cost estimate is based on square-foot costs taken from the BDM Chapter 12 and adjusted for structure specifics. Consult with a Specifications and Estimates Engineer. The preliminary cost estimate is based on recent bidding history on similar structures, degree of difficulty of construction, inflation trends, and length of time until Ad Date, and time for completion of construction. It is considered accurate to within 15%, but is should be accurate enough to preclude a surprise increase at the time of the Engineer's estimate, which is based on completed design quantities. The preliminary cost estimate shall be updated frequently as changes are made to the preliminary plan or new data influences the costs.

After a Preliminary Plan has been developed, but before sending to the Bridge Design Engineer for signature, the Preliminary Plan and cost estimate shall be submitted to one of the Bridge Specifications and Estimates Engineers for review and comment for the structures in the Preliminary Plan. The information presented to the S&E Engineer shall include the complete Preliminary Plan and all backup data previously prepared on costs for the structures (such as preliminary quantity calculations, preliminary foundation type selection, etc,). The S&E Engineer will review the Preliminary Plan, prepare, sign, and date a cost estimate summary sheet, and return the package to the designer. When the Preliminary Plan is presented to the Bridge Design Engineer, the submittal shall include the summary sheet prepared by the S&E Engineer. The summary sheet and backup data will then be placed in the job file. Do not send the summary sheet to the Region.

After submittal of the Preliminary Plan to the Region, the Region shall be notified immediately of any increases in the preliminary cost estimate during the structural design.

2.2.6 Approvals

A. State Bridge and Structures Architect/Specialists

For all preliminary plans, the State Bridge and Structures Architect and appropriate specialists should be aware and involved when the designer is first developing the plan. The State Bridge and Structures Architect and specialists should be given a print of the plan by the designer. This is done prior to checking the preliminary plan. The State Bridge and Structures Architect and specialist will review, approve, sign and date the print. This signed print is placed in the job file. If there are any revisions, which affect the aesthetics of the approved preliminary plan, the State Bridge and Structures Architect should be asked to review and approve, by signature, a print showing the revisions, which change elements of aesthetic significance.

For large, multiple bridge projects, the State Bridge and Structures Architect should be contacted for development of a coordinated architectural concept for the project corridor.

The architectural concept for a project corridor is generally developed in draft form and reviewed with the project stakeholders prior to finalizing. When finalized, it should be signed by the Region Administrator or his/her designee.

In order to achieve superstructure type optimization and detailing consistency, the following guidelines shall be used for the preparation of all future Preliminary Plans:

- Preliminary Plans for all steel bridges and structures shall be reviewed by the Steel Specialist.
- Preliminary Plans for all concrete bridges and structures shall be reviewed by the Concrete Specialist.
- Detailing of all Preliminary Plans shall be reviewed by the Preliminary Plans Detailing Specialist.

These individuals shall signify their approval by signing the preliminary plan in the Architect/Specialist block on the first plan sheet, together with the State Bridge and Structures Architect.

B. Bridge Design

The Bridge Projects Engineer signs the preliminary plan after it has been checked and approved by the Architect/Specialists. At this point, it is ready for review, approval, and signing by the Bridge Design Engineer and the Bridge and Structures Engineer.

After the Bridge and Structures Engineer has signed the preliminary plan, it is returned to the designer. The designer places the original signed preliminary plan in the job file and enters the names of the signers in the signature block. This preliminary plan will be sent to region for their review and approval.

The transmittal memo includes the preliminary plan and the WSDOT Form 230-038 "Not Included in Bridge Quantities List" and a brief explanation of the preliminary cost estimate. It is addressed to the Region Administrator/Project Development Engineer from the Bridge and Structures Engineer/Bridge Design Engineer. The memo is reviewed by the Bridge Projects Engineer and is initialed by the Bridge Design Engineer.

The following should be included in the cc distribution list with attachments: FHWA Washington Division Bridge Engineer (when project has Federal Funding), Region Project Engineer, Bridge Projects Engineer, Bridge Design Unit Supervisor, State Geotechnical Engineer, HQ Hydraulics Engineer, Bridge Management Engineer (when it is a replacement) Bridge Preservation Engineer, HQ Bridge Construction Engineer, and Region Traffic Engineer (when ITS is required). The Bridge Scheduling Engineer and the Region and HQ Program Management Engineers should receive a copy of the preliminary plan distribution memo without the attachments.

C. Region

Prior to the completion of the preliminary plan, the designer should meet with the Region to discuss the concept, review the list of items to be included in the "Not Included in Bridge Quantities List" and get their input. (This is a list of non-bridge items that appear on the bridge preliminary plan and eventually on the design plans.)

The Region will review the preliminary plan for compliance and agreement with the original site data. They will work to answer any *"Notes to the Region"* that have been listed on the plan. When this review is complete, the Regional Administrator, or his/her designee, will sign the plan. The Region will send back a print of the signed plan with any comments noted in red (additions) and green (deletions) along with responses to the questions raised in the *"Notes to the Region"*.

D. Railroad

When a railroad is involved with a structure on a Preliminary Plan, the HQ RR Liaison Engineer of the Design Office must be involved during the plan preparation process. A copy of the Preliminary Plan is sent to the HQ RR Liaison Engineer, who then sends a copy to the railroad involved for their comments and approval.

The railroad will respond with approval by letter to the HQ RR Liaison Engineer. A copy of this letter is then routed to the Bridge and Structures Office and then placed in the job file.

For design plans prepared within the Bridge and Structures Office, the Unit Supervisor or lead designer will be responsible for coordinating and providing shoring plans for structures adjacent to railroads. It is recommended that the Construction Support Unit design, prepare, stamp, and sign shoring plans. However, the design unit may elect to design, prepare, stamp, and sign shoring plans.

For consultant prepared design plans, the Unit Supervisor or lead reviewer will be responsible for coordinating and having the consultant design shoring plans for structures adjacent to railroads. The Construction Support Unit has design criteria and sample plan details which can be used by the design units and consultants.

A Construction Support engineer is available to attend design project kick-off meetings if there is a need for railroad shoring plans or other constructability issues associated with the project. Regardless of who prepares the bridge plans, all shoring plans should be reviewed by the Construction Support Unit before they are submitted for railroad review and approval at the 50% Final PS&E stage.

For completed shelf projects, the S&E Engineer will contact the Region Project Engineer and inform the Unit Supervisor or lead reviewer on the need for shoring plans for structures adjacent to railroads. If shoring plans are required, the unit supervisor or lead designer may ask the Construction Support Unit to prepare shoring plans.

At the 50% PS&E plan completion stage or sooner if possible, especially for seismic retrofit project, the S&E Engineer will send four (4) copies of the layout, foundation plan, temporary shoring plans, and appropriate special provision section for structures adjacent to railroads to the HQ RR Liaison Engineer, who will submit this package to the appropriate railroad for review and approval. The shoring plans shall show the pressure loading diagram and calculations to expedite the railroad's review and approval.

2.3 Preliminary Plan Criteria

2.3.1 Highway Crossings

A. General

A highway crossing is defined as a grade separation between two intersecting roadways. Naming convention varies slightly between mainline highway crossings and ramp highway crossings, but essentially, all bridges carry one highway, road, or street over the intersecting highway, road, or street.

1. Mainline highway crossings

   Names for mainline highway crossings are defined by the route designation or name of state highway, county road, or city street being carried over another highway, road, or street.

   For example, a bridge included as part of an interchange involving I-182 and SR 14 and providing for passage of traffic on I-182 under SR 14 would be named SR 14 Over I-182 (followed by the bridge number).

2. Ramp highway crossings

   Names for ramp highway crossings are defined by the state highway route numbers being connected, the directions of travel being connected, and the designation or name of the highway, road, or street being bridged.

   For example, a bridge in the Hewitt Avenue Interchange connecting traffic from westbound US 2 to northbound I-5 and passing over Everett Street would be named 2W-5N Ramp Over Everett Street (followed by the bridge number. A bridge connecting traffic from northbound I-5 to westbound SR 518 and passing over northbound I-405 and a ramp connecting southbound I-405 to northbound I-5 would be named 5N-518W Over 405N,405S-5N (followed by the bridge number).

B. Bridge Width

The bridge roadway channelization (configuration of lanes and shoulders) is provided by the region with the Bridge Site Data. For state highways, the roadway geometrics are controlled by Chapters 430 and 440 of the *Design Manual*. For city and county arterials, the roadway geometrics are controlled by Chapter IV of the *Local Agency Guidelines*.


C. Horizontal Clearances

Safety dictates that fixed objects be placed as far from the edge of the roadway as is economically feasible. Criteria for minimum horizontal clearances to bridge piers and retaining walls are outlined in the *Design Manual*. Chapter 700 of the *Design Manual* outlines clear zone and recovery area requirements for horizontal clearances without guardrail or barrier being required.


Actual horizontal clearances shall be shown in the plan view of the Preliminary Plan (to the nearest 0.1 foot). Minimum horizontal clearances to inclined columns or wall surfaces should be provided at the roadway surface and for a vertical distance of 6 feet above the edge of pavement. When bridge end slopes fall within the recovery area, the minimum horizontal clearance should be provided for a vertical distance of 6 feet above the fill surface. See Figure 2-6.

Bridge piers and abutments ideally should be placed such that the minimum clearances can be satisfied. However, if for structural or economic reasons, the best span arrangement requires a pier to be within clear zone or recovery area, and then guardrail or barrier can be used to mitigate the hazard.

There are instances where it may not be possible to provide the minimum horizontal clearance even with guardrail or barrier. An example would be placement of a bridge pier in a narrow median. The required column size may be such that it would infringe on the shoulder of the roadway. In such cases, the barrier safety shape would be incorporated into the shape of the column. Barrier or guardrail would need to taper into the pier at a flare rate satisfying the criteria in Chapter 710 of the *Design Manual*. See Figure 2-2. The reduced clearance to the pier would need to be approved by the Region. Horizontal clearances, reduced temporarily for construction, are covered in BDM Section 2.3.9.



Horizontal Clearance to Incline Piers
1990
Figure 2-1



Bridge Pier in Narrow Median
1990
Figure 2-2

D. Vertical Clearances

The required minimum vertical clearances are established by the functional classification of the highway and the construction classification of the project. For state highways, this is as outlined in Chapters 430, 440, and 1120 of the *Design Manual*. For city and county arterials, this is as outlined in Chapter IV of the Local Agency Guidelines.

Actual minimum vertical clearances are shown on the Preliminary Plan (to the nearest 0.1 foot). The approximate location of the minimum vertical clearance is noted in the upper left margin of the plan. For structures crossing divided highways, minimum vertical clearances for both directions are noted.

E. End Slopes

The type and rate of end slope used at bridge sites is dependent on several factors. Soil conditions and stability, right of way availability, fill height or depth of cut, roadway alignment and functional classification, and existing site conditions are important.


The region should have made a preliminary determination based on these factors during the preparation of the bridge site data. The side slopes noted on the Roadway Section for the roadway should indicate the type and rate of end slope.

The Materials Laboratory Geotechnical Services Branch will recommend the minimum rate of end slope. This should be compared to the rate recommended in the Roadway Section and to existing site conditions (if applicable). The types of end slopes and bridge slope protection are discussed in Chapters 640 and 1120 of the *Design Manual*. Examples of slope protection are shown on Standard Plan D-9.

F. Determination of Bridge Length

Establishing the location of the end piers for a highway crossing is a function of the profile grade of the overcrossing roadway, the superstructure depth, the minimum vertical and horizontal clearances required for the structure, the profile grade and channelization (including future widening) of the undercrossing roadway, and the type and rate of end slope used.

For the general case of bridges in cut or fill slopes, the control point is where the cut or fill slope plane meets the bottom of roadside ditch or edge of shoulder as applicable. From this point, the fill or cut slope plane is established at the recommended rate up to where the slope plane intersects the grade of the roadway at the shoulder. Following the requirements of Standard Plan H-9, the back of pavement seat, end of wing wall or end of retaining wall can be established at 3 feet behind the slope intersection. See Figure 2-3



Determination of Bridge Length
Figure 2-3

For the general case of bridges on wall type abutments or "closed" abutments, the controlling factors are the required horizontal clearance and the size of the abutment. This situation would most likely occur in an urban setting or where right of way or span length is limited.

G. Pedestrian Crossings

Pedestrian crossings follow the same format as highway crossings. Geometric criteria for bicycle and pedestrian facilities are established in Chapters 1020 and 1025 of the *Design Manual*. Width and clearances would be as established there and as confirmed by region. Minimum vertical clearance over a roadway is given in Chapter 1025 and 1120 of the *Design Manual*. Unique items to be addressed with pedestrian facilities include ADA requirements, the railing to be used, handrail requirements, overhead enclosure requirements, and profile grade requirements for ramps and stairs.

H. Bridge Redundancy

Design bridges to minimize the risk of catastrophic collapse by using redundant supporting elements (columns and girders).

For substructure design use:

One column minimum for roadways 40 feet wide and under.
Two columns minimum for roadways over 40 feet to 60 feet.
Three columns minimum for roadways over 60 feet.
Collision protection or design for collision loads for piers with one or two columns.

For superstructure design use:

Three girders (webs) minimum for roadways 32 feet and under.
Four girders (webs) minimum for roadways over 32 feet.
See Appendix 2.3-A2 for details.

Note: Any deviation from the above guidelines shall have a written approval by the Bridge Design Engineer.

2.3.2 Railroad Crossings

A. General

A railroad crossing is defined as a grade separation between an intersecting highway and a railroad. Names for railroad crossings are defined either as railroad over state highway or state highway over railroad. For example, a bridge carrying BNSF railroad tracks over I-5 would be named BNSF Over I-5 (followed by the bridge number) A bridge carrying I-90 over Union Pacific railroad tracks would be named I-90 Over UPRR (followed by the bridge number).

Requirements for highway/railway grade separations may involve negotiations with the railroad company concerning clearances, geometrics, utilities, and maintenance roads. The railroad's review and approval will be based on the completed Preliminary Plan.

B. Criteria

The initial Preliminary Plan shall be prepared in accordance with the criteria of this section to apply uniformly to all railroads. Variance from these criteria will be negotiated with the railroad, when necessary, after a Preliminary Plan has been provided for their review.

C. Bridge Width

For highway over railway grade separations the provisions of Section 2.3.1 pertaining to bridge width of highway crossings shall apply. Details for railway over highway grade separations will depend on the specific project and the railroad involved.

D. Horizontal Clearances

For railway over highway grade separations, undercrossings, the provisions of BDM Section 2.3.1 pertaining to horizontal clearances for highway crossings shall apply. However, because of the heavy live loading of railroad spans, it is advantageous to reduce the span lengths as much as possible. For railroad undercrossings skewed to the roadway, piers may be placed up to the outside edge of standard shoulders (or 8 feet minimum) if certain conditions are met (known future roadway width requirements, structural requirements, satisfactory aesthetics, satisfactory sight distance, barrier protection requirements, etc.).

For railroad overcrossings, minimum horizontal clearances are as noted below:

	Railroad Alone
Fill Section	14 feet
Cut Section	16 feet

Table 2--4

Horizontal clearance shall be measured from the center of the outside track to the face of pier. When the track is on a curve, the minimum horizontal clearance shall be increased at the rate of 1 $^{1}/_{2}$ inches for each degree of curvature. An additional 8 feet of clearance for off-track equipment shall only be provided when specifically requested by the railroad.

The actual minimum horizontal clearances shall be shown in the Plan view of the Preliminary Plan (to the nearest 0.01 foot).

E. Crash Walls

Crash walls, when required, shall be designed to conform to the criteria of the *AREMA Manual*. To determine when crash walls are required, consult the following:

Union Pacific Railroad, "Guidelines for Design of Highway Separation Structures over Railroad (Overhead Grade Separation)"
AREMA Manual
WSDOT Railroad Liaison Engineer
the Railroad


F. Vertical Clearances

For railway over highway grade separations, the provisions of BDM Section 2.3.1 pertaining to vertical clearances of highway crossings shall apply. For highway over railway grade separations, the minimum vertical clearance shall satisfy the requirements of Chapter 1120 of the *Design Manual*.

The actual minimum vertical clearances shall be shown on the Preliminary Plan (to the nearest 0.1 foot). The approximate location of the minimum vertical clearance is noted in the upper left margin of the plan.

G. Determination of Bridge Length

For railway over highway grade separations, the provisions of BDM Section 2.3.1 pertaining to the determination of bridge length shall apply. For highway over railway grade separations, the minimum bridge length shall satisfy the minimum horizontal clearance requirements. The minimum bridge length shall generally satisfy the requirements of Figure 2-5.



Determination of Bridge Length for for a Highway Over Railway Grade Separation

Figure 2-5

H. Special Considerations

For highway over railway grade separations, the top of footings for bridge piers or retaining walls adjacent to railroad tracks shall be 2 feet or more below the elevation of the top of tie and shall not have less than 2 feet of cover from the finished ground. The footing face shall not be closer than 10 feet to the center of the track. Any cofferdams, footings, excavation, etc., encroaching within 10 feet of the center of the track requires the approval of the railroad.

I. Construction Openings

For railroad clearances, see Section 1120 of the WSDOT Bridge Design Manual. The minimum horizontal construction opening is 9 feet to either side of the centerline of track. The minimum vertical construction opening is 23 feet 6 inches above the top of rail at 6 feet offset from the centerline of track. Falsework openings shall be checked to verify that enough space is available for falsework beams to span the required horizontal distances and still provide the minimum vertical falsework clearance. Minimum vertical openings of less than 23 feet 6 inches shall be coordinated with the HQ Railroad Liaison Engineer.

2.3.3 Water Crossings

A. Bridge Width

The provisions of Section 2.3.1 pertaining to bridge width for highway crossings apply here.

B. Horizontal Clearances

Water crossings over navigable waters requiring clearance for navigation channels shall satisfy the horizontal clearances required by the Coast Guard. Communication with the Coast Guard will be handled through the Coast Guard Liaison Engineer. For bridges over navigable waters, the centerline of the navigation channel and the horizontal clearances (to the nearest 0.1 foot) to the piers or the pier protection shall be shown on the Plan view of the Preliminary Plan. Pier locations shall be reviewed by the HQ Hydraulics unit.

C. Vertical Clearances

Vertical clearances for water crossings must satisfy floodway clearance and, where applicable, navigation clearance.

Bridges over navigable waters must satisfy the vertical clearances required by the Coast Guard. Communication with the Coast Guard will be handled through the Coast Guard Liaison Engineer. The actual minimum vertical clearance (to the nearest 0.1 foot) for the channel span shall be shown on the Preliminary Plan. The approximate location of the minimum vertical clearance shall be noted in the upper left margin of the plan. The clearance shall be shown to the water surface as required by the Coast Guard criteria.

Floodway vertical clearance will need to be discussed with the HQ Hydraulics Office. In accordance with the flood history, nature of the site, character of drift, and other factors, they will determine a minimum vertical clearance for the 100-year flood. The roadway profile and the bridge superstructure depth must accommodate this. The actual minimum vertical clearance to the 100-year flood shall be shown (to the nearest 0.1 foot) on the Preliminary Plan, and the approximate location of the minimum vertical clearance shall be noted in the upper left margin of the plan.

D. End Slopes

The type and rate of end slopes for water crossings is similar to that for highway crossings. Soil conditions and stability, fill height, location of toe of fill, existing channel conditions, flood and scour potential, and environmental concerns are all important.

As with highway crossings, the Region, and Materials Laboratory Geotechnical Services Branch will make preliminary recommendations as to the type and rate of end slope. The HQ Hydraulics Office will also review the Region's recommendation for slope protection.

E. Determination of Bridge Length

Determining the overall length of a water crossing is not as simple and straightforward as for a highway crossing. Floodway requirements and environmental factors have a significant impact on where piers and fill can be placed.

If a water crossing is required to satisfy floodway and environmental concerns, it will be known by the time the Preliminary Plan has been started. Environmental studies and the Design Report prepared by the region will document any restrictions on fill placement, pier arrangement, and overall floodway clearance. The Hydraulics Office will need to review the size, shape, and alignment of all bridge piers in the floodway and the subsequent effect they will have on the base flood elevation. The overall bridge length may need to be increased depending on the span arrangement selected and the change in the flood backwater, or justification will need to be documented.

F. Scour

The HQ Hydraulics Office will indicate the anticipated depth of scour at the bridge piers. They will recommend pier shapes to best streamline flow and reduce the scour forces. They will also recommend measures to protect the piers from scour activity or accumulation of drift (use of deep foundations, minimum cover to top of footing, riprap, pier alignment to stream flow, closure walls between pier columns, etc.).

G. Pier Protection

For bridges over navigable channels, piers adjacent to the channel may require pier protection such as fenders or pile dolphins. The Coast Guard will determine whether pier protection is required. This determination is based on the horizontal clearance provided for the navigation channel and the type of navigation traffic using the channel.

H. Construction Access and Time Restrictions

Water crossings will typically have some sort of construction restrictions associated with them. These must be considered during preliminary plan preparation.

The time period that the Contractor will be allowed to do work within the waterway may be restricted by regulations administered by various agencies. Depending on the time limitations, a bridge with fewer piers or faster pier construction may be more advantageous even if more expensive.

Contractor access to the water may also be restricted. Shore areas supporting certain plant species are sometimes classified as wetlands. A work trestle may be necessary in order to work in or gain access through such areas. Work trestles may also be necessary for bridge removal as well as new bridge construction. Work trestle feasibility, location, staging, deck area and approximate number of piles, and estimated cost need to be determined to inform the Region as part of the bridge preliminary plan.

2.3.4 Bridge Widenings

A. Bridge Width

The provisions of BDM Section 2.3.1 pertaining to bridge width for highway crossings shall apply. In most cases, the width to be provided by the widening will be what is called for by the design standards, unless a deviation is approved.

B. Traffic Restrictions

Bridge widenings involve traffic restrictions on the widened bridge and, if applicable, on the lanes below the bridge. The bridge site data submitted by the region should contain information regarding temporary lane widths and staging configurations. This information should be checked to be certain that the existing bridge width, and the bridge roadway width during the intermediate construction stages of the bridge are sufficient for the lane widths, shy distances, temporary barriers, and construction room for the contractor. These temporary lane widths and shy distances are noted on the Preliminary Plan. The temporary lane widths and shy distances on the roadway beneath the bridge being widened should also be checked to ensure adequate clearance is available for any substructure construction.

C. Construction Sequence

A construction sequence shall be developed using the traffic restriction data in the bridge site data. The construction sequence shall take into account the necessary steps for construction of the bridge widening including both the substructure and superstructure. Placement of equipment is critical because of limited access and working space limitations. Space is required for cranes to construct shafts and erect the girders. Consult the Construction Support Unit for crane information, such as: boom angle, capacities, working loads, working radius, and crane footprint. Construction work off of and adjacent to the structure and the requirements of traffic flow on and below the structure shall be taken into account. Generally, cranes are not allowed to lift loads while supported from the existing structure. Checks shall be made to be certain that girder spacing, closure pours, and removal work are all compatible with the traffic arrangements.

Projects with several bridges being widened at the same time should have sequencing that is compatible with the Region's traffic plans during construction and that allow the Contractor room to work. It is important to meet with the Region project staff to assure that the construction staging and channelization of traffic during construction is feasible and minimizes impact to the traveling public.

2.3.5 Detour Structures

A. Bridge Width

The lane widths, shy distances, and overall roadway widths for detour structures are determined by the Region. Review and approval of detour roadway widths is done by the HQ Traffic Office.

B. Live Load

All detour structures shall be designed for an AASHTO HS 20 live load unless approved otherwise by the Bridge Design Engineer. Construction requirements, such as a year long expected use, and staging are sufficient reasons to justify designing for a higher live load of HL-93. Use of an HL-93 live load shall be approved by the Bridge Design Engineer.

2.3.6 Retaining Walls and Noise Walls

The requirements for Preliminary Plans for retaining walls and noise walls are similar to the requirements for bridges. The plan and elevation views define the overall limits and the geometry of the wall. The section view will show general structural elements that are part of the wall and the surface finish of the wall face.

The most common types of walls are outlined in Section 9.4.2 of the *Bridge Design Manual* and Chapter 1130 of the *Design Manual*. The Bridge and Structures Office is responsible for Preliminary Plans for all nonstandard walls (retaining walls and noise walls) as spelled out in Chapter 1130 of the *Design Manual*.

2.3.7 Bridge Deck Drainage

The HQ Hydraulics Office provides a review of the Preliminary Plan with respect to the requirements for bridge deck drainage. An 11x17 print shall be provided to the HQ Hydraulics Office for their review as soon as the Preliminary Plan has been developed. The length and width of the structure, profile grade, superelevation diagram, and any other pertinent information (such as locations of drainage off the structure) should be shown on the plan. For work with existing structures, the locations of any and all bridge drains shall be noted.

The HQ Hydraulics Office or the Region Hydraulics staff will determine the type of drains necessary (if any), the location, and spacing requirements. They will furnish any details or modifications required for special drains or special situations.

If low points of sag vertical curves or superelevation crossovers occur within the limits of the bridge, the region should be asked to revise their geometrics to place these features outside the limits of the bridge. If such revisions cannot be made, the HQ Hydraulics Office will provide details to handle drainage with bridge drains on the structure.

2.3.8 Bridge Deck Protective Systems

The Preliminary Plan shall note in the lower left margin the type of deck protective system to be utilized on the bridge. The most commonly used systems are described in Section 5.7.4 of the *Bridge Design Manual*.

New construction will generally be System 1 ($2\ ^1/_2$ inch concrete top cover plus epoxy-coated rebars for the top mat). System 2 (MC overlay) and System 3 (HMA overlay) are to be used on new construction that require overlays and on widenings for major structures. The type of overlay to be used should be noted in the bridge site data submitted by the Region. The bridge condition report will indicate the preference of the Deck Systems Specialist in the Bridge and Structures Office.

2.3.9 Construction Clearances

Most projects involve construction in and around traffic. Both traffic and construction must be accommodated. Construction clearances and working room must be reviewed at the preliminary plan stage to verify bridge constructability.

For construction clearances for roadways, the Region shall supply the necessary traffic staging information with the bridge site data. This includes temporary lane widths and shoulder or shy distances, allowable or necessary alignment shifts, and any special minimum vertical clearances. With this information, the designer can establish the falsework opening or construction opening.

The horizontal dimension of the falsework or construction opening shall be measured normal to the alignment of the road which the falsework spans. The horizontal dimension of the falsework or construction opening shall be the sum of the temporary traffic lane widths and shoulder or shy distances, plus two 2-foot widths for the temporary concrete barriers, plus additional 2 feet shy distances behind the temporary barriers. For multi-span falsework openings, a minimum of 2 feet, and preferably 4 feet, shall be used for the interior support width. This interior support shall also have 2 feet shy on both sides to the two 2-foot wide temporary concrete barriers that will flank the interior support.

The minimum vertical clearance of the construction opening shall normally be 14 feet 6 inches or as specified by the Region. The vertical space available for the falsework must be deep to accommodate the falsework stringers, camber strips, deck, and all deflections. If the necessary depth is greater than the space available, either the minimum vertical clearance for the falsework shall be reduced or the horizontal clearance and span for the falsework shall be reduced, or the profile grade of the structure shall be raised. Any of these alternatives shall be approved by the Region.

Once the construction clearances have been determined the designer should meet with the region to review the construction clearances to ensure compatibility with the construction staging. This review should take place prior to finalizing the preliminary bridge plan.

For railroads see BDM Section 2.3.2H.

2.3.10 Design Guides for Falsework Depth Requirements

Where falsework is required to support construction of cast-in-place superstructure or segmental elements, the designer of the Preliminary Plan shall confirm with the Region the minimum construction opening. See BDM Section 2.3.9

The bridge designer shall consult with the Construction Support Engineer on falsework depth requirements outlined below.

Bridge designers shall evaluate falsework depth requirements based on the following guidelines:

A. Falsework Spans < 36 feet and No Skews

No design is necessary. Provide for minimum vertical clearance and a minimum falsework depth of 4 feet to accommodate:

W36X___ steel beam sections
$^{3}/_{4}$-inch camber strip
$^{5}/_{8}$-inch plywood
4x4 joists
6-inch depth for segmental falsework release

B. Falsework Spans > 36 feet or Spans with Skews or Limited Falsework Depth

While the falsework or construction openings are measured normal to the alignment which the falsework spans, the falsework span is measured parallel to the bridge alignment.

The Preliminary Plan designer shall perform preliminary design of the falsework sufficiently to determine its geometric and structural feasibility. Shallow, heavy, close-spaced wide-flange steel beams may be required to meet the span requirements within the available depth. The preliminary design shall be based on design guides in the Standard Specifications 6-02.3(17). Beams shall be designed parallel to the longitudinal axis of the bridge. The falsework span deflection shall be limited according to the Standard Specifications 6-02.3(17)B: generally span/360 for a single concrete placement, such as a slab, and span/500 for successive concrete placement forming a composite structure. This limits the stresses in the new structure from the construction and concrete placement sequences. Beam sizes shall be shown in the final plans (and in the Preliminary Plans as required) with the Contractor having the option of submitting an alternate design. The designer shall verify availability of the beam sizes shown in the plans.

C. Bridge Widenings

For bridge widenings where the available depth for the falsework is fixed, designers shall design falsework using shallower and heavier steel beams to fit within the available depth. Beam sizes and details shall be shown in the final plans (and in the Preliminary Plans as required) with the Contractor having the option of using an alternate design. The designer shall verify availability of the beam sizes shown in the plans.

In some cases it may be appropriate to consider a shallower superstructure widening, but with similar stiffness, in order to accommodate the falsework and vertical clearance.


D. Bridge with Skews

Falsework beams shall be laid out and designed for spans parallel to the bridge centerline or perpendicular to the main axis of bending. The centerline of falsework beams shall be located within 2 feet of the bridge girder stems and preferably directly under the stems or webs in accordance with Standard Specification Section 6-02.3(17)E. Falsework beams placed normal to the skew or splayed complicate camber calculations and shall be avoided.

2.3.11 Inspection and Maintenance Access

A. General

FHWA mandates that bridges be inspected every two years. The BPO inspectors are required to access bridge components to within 3 feet for visual inspection and to access bearings close enough to measure movement. Maintenance personnel need to access damaged members and locations that may collect debris. This is accomplished by using many methods. Safety cables, ladders, bucket trucks, Under Bridge Inspection Truck (UBIT), (see Figure 2-6), and under bridge travelers are just a few of the most common methods. Preliminary Plan designers need to be aware of these requirements and prepare designs that allow access for bridge inspectors and maintenance personnel throughout the Preliminary Plan and TS&L planning phases.



Limits of Under Bridge Inspection Truck
Ubits Can Only Deploy to the Tight Side of Truck
Figure 2-6

B. Safety Cables

Safety cables strung on steel plate girders or trusses allow for walking access. Care must be given to the application and location. Built-up plate girder bridges are detailed with a safety cable for inspectors walking the bottom flange. However, when the girders become more than 8 feet deep, the inspection of the top flange and top lateral connections becomes difficult to access. It is not feasible for the inspectors to stand on the bottom flanges when the girders are less than 5 feet deep. On large trusses, large gusset plates (3 feet or more wide) are difficult to circumvent. Tie-off cables are best located on the interior side of the exterior girder of the bridge except at large gusset plates. At these locations, cables or lanyard anchors should be placed on the inside face of the truss so inspectors can utilize bottom lateral gusset plates to stand on while traversing around the main truss gusset plates.

C. Travelers

Under bridge travelers, placed on rails that remain permanently on the bridge, can be considered on large steel structures. This is an expensive option, but it should be evaluated for large bridges with high ADT because access to the bridge would be limited by traffic windows that specify when a lane can be closed. Some bridges are restricted to weekend UBIT inspection for this reason.

D. Abutment Slopes

Slopes in front of abutments shall provide enough overhead clearance to the bottom of the superstructure to access bearings for inspection and possible replacement (usually 3 feet minimum).

2.4 Selection of Structure Type

2.4.1 Bridge Types

See Appendix sheet 2.4-A1 for a bar graph comparing structure type, span range and cost range.

The required superstructure depth is determined during the preliminary plan development process. The AASHTO LRFD Specifications in BDM Section 2.5.2.6.3 show traditional minimum depths for constant depth superstructures. WSDOT has developed superstructure depth-to-span ratios based on past experience.

The superstructure depth is used to establish the vertical clearance that is available below the superstructure. For preliminary plans, the designer should use the more conservative depth determined from either the AASHTO LRFD criteria or the WSDOT criteria outlined below. In either case, the minimum depth includes the deck thickness. For both simple and continuous spans, the span length is the horizontal distance between centerlines of bearings.

The superstructure depth may be refined during the final design phase. It is assumed that any refinement will result in a reduced superstructure depth so the vertical clearance is not reduced from that shown in the preliminary plan. However, when profile grade limitations restrict superstructure depth, the preliminary plan designer shall investigate and/or work with the structural designer to determine a superstructure type and depth that will fit the requirements.

A. Reinforced Concrete Slab

1. Application

   Used for simple and continuous spans up to 60 feet.

2. Characteristics

   Design details and falsework relatively simple. Shortest construction time for any cast-in-place structure. Correction for anticipated falsework settlement must be included in the dead load camber curve because of the single concrete placement sequence.

3. Depth/Span Ratios

   a. Constant depth

Simple span	$^1/_{22}$
Continuous spans	$^1/_{25}$

   b. Variable depth

      Adjust ratios to account for change in relative stiffness of positive and negative moment sections.

B. Reinforced Concrete Tee-Beam

1. Application

   Used for continuous spans 30 feet to 60 feet. Has been used for longer spans with inclined leg piers.

2. Characteristics

   Forming and falsework is more complicated than for a concrete slab. Construction time is longer than for a concrete slab.

3. Depth/Span Ratios

   a. Constant depth

      Simple spans $^1/_{13}$

      Continuous spans $^1/_{15}$

   b. Variable depth

      Adjust ratios to account for change in relative stiffness of positive and negative moment sections.

C. Reinforced Concrete Box Girder

1. Application

   Used for continuous spans 50 feet to 130 feet. Maximum simple span 110 feet to limit excessive dead load deflections.

2. Characteristics

   Forming and falsework is somewhat complicated. Construction time is approximately the same as for a tee-beam. High torsional resistance makes it desirable for curved alignments.

3. Depth/Span Ratios*

   a. Constant depth

      Simple spans $^1/_{18}$

      Continuous spans $^1/_{20}$

   b. Variable depth

      Adjust ratios to account for change in relative stiffness of positive and negative moment sections.

      *If the configuration of the exterior web is sloped and curved, a larger depth/span ratio may be necessary.

D. Post-Tensioned Concrete Box Girder

1. Application

   Normally used for continuous spans longer than 130 feet or simple spans longer than 110 feet. Should be considered for shorter spans if a shallower structure depth is needed.

2. Characteristics

   Construction time is somewhat longer due to post-tensioning operations. High torsional resistance makes it desirable for curved alignments.

3. Depth/Span Ratios*

   a. Constant depth

      Simple spans $^1/_{20.5}$

      Continuous spans $^1/_{25}$

b. Variable depth

Two span structures

At Center of span	$^1/_{25}$
At Intermediate pier	$^1/_{12.5}$

Multi-span structures

At Center of span	$^1/_{36}$
At Intermediate pier	$^1/_{18}$

*If the configuration of the exterior web is sloped and curved, a larger depth/span ratio may be necessary.

E. Prestressed Concrete Sections

1. Application

Local precast fabricators have several standard forms available for precast concrete sections based on the WSDOT standard girder series. These are versatile enough to cover a wide variety of span lengths.

WSDOT standard girders are:

a. W95G, W83G, WF74G, WF58G, WF50G, WF42G, W74G, W58G, W50G, and W42G precast, prestressed concrete I-girders requiring a cast-in-place concrete roadway deck used for spans less than 180 feet. The number (eq. 95) specifies the girder depth in inches.

W95PTG, W83PTG and WF74PTG post-tensioned, precast segmental I–girders with cast–in–place concrete roadway deck use for simple span up to 225 ft. and continuous span up to 250 ft.

b. U**G* and UF**G* precast, prestressed concrete tub girders requiring a cast–in–place concrete roadway deck are used for spans less than 140 ft. “U” specifies webs without flanges, “UF” specifies webs with flanges, ** specifies the girder depth in inches, and * specifies the bottom flange width in feet. U**G* girders have been precast as shallow as 26 inches.

Post-tensioned, precast, prestressed tub girders with cast–in–place concrete roadway deck are used for simple span up to 200 ft. and continuous span up to 250 ft.

c. W65DG, W53DG, W41DG, and W35DG precast, prestressed concrete decked bulb tee girders requiring an ACP overlay roadway surface used for span less than 150 ft.

d. W62BTG, W50BTG, W38BT6, and W32BTG precast, prestressed concrete bulb tee girders requiring a cast-in-place concrete deck for simple spans up to ____ feet.

e. W74TFG, W62TF6, W50TF6, W38TF6, and W32TFG precast, prestressed concrete thin flange deck bulb tee girders requiring a cast-in-place concrete deck for simple spans up to ___ feet.

f. 12-inch, 18-inch, and 26-inch precast, prestressed slabs requiring an HMA overlay roadway surface used for spans less than 80 ft.

g. 26-inch precast, prestressed ribbed girder, deck double tee, and double tee members requiring an HMA overlay roadway surface used for span less than 40 ft.

2. Characteristics

Superstructure design is quick for pretensioned girders with proven user-friendly software (PGSuper and QConBridge)

Construction details and forming are fairly simple. Construction time is less than for a cast-in-place bridge. Little or no falsework is required. Falsework over traffic is usually not required; construction time over existing traffic is reduced.

Precast girders usually require that the bridge roadway superelevation transitions begin and end at or near piers; location of piers should consider this. The Region may be requested to adjust these transition points if possible.

Fully reinforced, composite 8 inch cast-in-place deck slabs continuous over interior piers or reinforced 5 inch cast-in-place deck slabs continuous over interior piers have been used with f. and g.

F. Composite Steel Plate Girder

1. Application

Used for simple spans up to 260 feet and for continuous spans from 120 to 400 feet. Relatively low dead load when compared to a concrete superstructure makes this bridge type an asset in areas where foundation materials are poor.

2. Characteristics

Construction details and forming are fairly simple Construction time is comparatively short. Shipping and erecting of large sections must be reviewed. Cost of maintenance is higher than for concrete bridges. Current cost information should be considered because of changing steel market conditions.

3. Depth/Span Ratios

a. Constant depth

Simple spans	$^1/_{22}$
Continuous spans	$^1/_{25}$

b. Variable depth

@ Center of span	$^1/_{40}$
@ Intermediate pier	$^1/_{20}$

G. Composite Steel Box Girder

1. Use

Used for simple spans up to 260 feet and for continuous spans from 120 to 400 feet. Relatively low dead load when compared to a concrete superstructure makes this bridge type an asset in areas where foundation materials are poor.

2. Characteristics

Construction details and forming are more difficult than for a steel plate girder. Shipping and erecting of large sections must be reviewed. Current cost information should be considered because of changing steel market conditions.

3. Depth/Span Ratios

   a. Constant depth

      Simple spans $^1/_{22}$

      Continuous spans $^1/_{25}$

   b. Variable depth

      At Center of span $^1/_{40}$

      At Intermediate pier $^1/_{20}$

      Note: Sloping webs are not used on box girders of variable depth.

H. Steel Truss

1. Application

   Used for simple spans up to 300 feet and for continuous spans up to 1,200 feet. Used where vertical clearance requirements dictate a shallow superstructure and long spans or where terrain dictates long spans and construction by cantilever method.

2. Characteristics

   Construction details are numerous and can be complex. Cantilever construction method can facilitate construction over inaccessible areas. Through trusses are discouraged because of the resulting restricted horizontal and vertical clearances for the roadway.

3. Depth/Span Ratios

   a. Simple spans $^1/_{6}$

   b. Continuous spans

      @ Center of span $^1/_{18}$

      @ Intermediate pier $^1/_{9}$

I. Segmental Concrete Box Girder

1. Application

   Used for continuous spans from 200 to 700 feet. Used where site dictates long spans and construction by cantilever method.

2. Characteristics

   Use of travelers for the form apparatus facilitates the cantilever construction method enabling long-span construction without falsework. Precast concrete segments may be used. Tight geometric control is required during construction to ensure proper alignment.

3. Depth/Span Ratios

   Variable depth

   At Center of span $^1/_{50}$

   At Intermediate pier $^1/_{20}$

J. Railroad Bridges

1. Use

   For railway over highway grade separations, most railroad companies prefer simple span steel construction. This is to simplify repair and reconstruction in the event of derailment or some other damage to the structure.

2. Characteristics

   The heavier loads of the railroad live load require deeper and stiffer members than for highway bridges. Through girders can be used to reduce overall structure depth if the railroad concurs. Piers should be normal to the railroad to eliminate skew loading effects.

3. Depth/Span Ratios

   Constant depth

Simple spans	$^1/_{12}$
Continuous two span	$^1/_{14}$
Continuous multi-span	$^1/_{15}$

K. Timber

1. Use

   Generally used for spans under 40 feet. Usually used for detour bridges and other temporary structures.

2. Characteristics

   Excellent for short-term duration as for a detour. Simple design and details.

3. Depth/Span Ratios

   Constant depth

Simple span – Timber beam	$^1/_{10}$
Simple span – Glulam beam	$^1/_{12}$
Continuous spans	$^1/_{14}$

L. Other

Bridge types such as cable-stayed, suspension, arch, tied arch, and floating bridges have special and limited applications. The use of these bridge types is generally dictated by site conditions. Preliminary design studies will generally be done when these types of structures are considered.

2.4.2 Wall Types

Retaining walls, wingwalls, curtain walls, and tall closed abutment walls may be used where required to shorten spans or superstructure length or to reduce the width of approach fills. The process of selecting a type of retaining wall should economically satisfy structural, functional, and aesthetic requirements and other considerations relevant to a specific site. A detailed listing of the common wall types and their characteristics can be found in Chapter 8 of the *Bridge Design Manual.*

2.5 Aesthetic Considerations

2.5.1 General Visual Impact

A bridge has a strong visual impact in any landscape. Steps must be taken to assure that even the most basic structure will complement rather than detract from it's surroundings. The EIS and bridge site data submitted by the Region should each contain a discussion on the aesthetic importance of the project site. This commentary, together with submitted video and photographs, will help the designer determine the appropriate structure type.

The State Bridge and Structures Architect should be contacted early in the preliminary bridge plan process for input on aesthetics. Normally, a visit to the bridge site with the State Bridge and Structures Architect and Region design personnel should be made.

Aesthetics is a very subjective element that must be factored into the design process in the otherwise very quantitative field of structural engineering. Bridges that are well proportioned structurally using the least material possible are generally well proportioned. However, the details such as pier walls, columns, and crossbeams require special attention to ensure a structure that will enhance the general vicinity.

For large projects incorporating several to many bridges and retaining walls, an architectural theme is frequently developed to bring consistency in structure type, details, and architectural appointments. The preliminary plan designer shall work with the State Bridge and Structures Architect to implement the theme.

2.5.2 End Piers

A. Wingwalls

The size and exposure of the wingwall at the end pier should balance, visually, with the depth and type of superstructure used. For example, a prestressed girder structure fits best visually with a 15-foot wingwall (or curtain wall/retaining wall). However, there are instances where a 20-foot wingwall (or curtain wall/retaining wall) may be used with a prestressed girder (maximizing a span in a remote area, for example or with deep girders where they are proportionally better in appearance). The use of a 20-foot wingwall shall be approved by the Bridge Design Engineer and the State Bridge and Structures Architect.

It is less expensive for bridges of greater than 40 feet of overall width to be designed with wingwalls (or curtain wall/retaining wall) than to use a longer superstructure.

B. Retaining Walls

For structures at sites where profile, right of way, and alignment dictate the use of high exposed wall-type abutments for the end piers, retaining walls that flank the approach roadway can be used to retain the roadway fill and reduce the overall structure length. Stepped walls are often used to break up the height, and allow for landscape planting. A curtain wall runs between the bridge abutment and the heel of the abutment footing. In this way, the joint in the retaining wall stem can coincide with the joint between the abutment footing and the retaining wall footing. This simplifies design and provides a convenient breaking point between design responsibilities if the retaining walls happen to be the responsibility of the Region. The length shown for the curtain wall dimension is an estimated dimension based on experience and preliminary foundation assumptions. It can be revised under design to satisfy the intent of having the wall joint coincide with the end of the abutment footing.

C. Slope Protection

The Region is responsible for making initial recommendations regarding slope protection. It should be compatible with the site and should match what has been used at other bridges in the vicinity. The type selected shall be shown on the Preliminary Plan. It shall be noted on the "Not Included in Bridge Quantities" list.

2.5.3 Intermediate Piers

The size, shape, and spacing of the intermediate pier elements must satisfy two criteria. They must be correctly sized and detailed to efficiently handle the structural loads required by the design and shaped to enhance the aesthetics of the structure.

The primary view of the pier must be considered. For structures that cross over another roadway, the primary view will be a section normal to the roadway. This may not always be the same view as shown on the Preliminary Plan as with a skewed structure, for example. This primary view should be the focus of the aesthetic review.

Tapers and flares on columns should be kept simple and structurally functional. Fabrication and constructability of the formwork of the pier must be kept in mind. Crossbeam ends should be carefully reviewed. Skewed bridges and bridges with steep profile grades or those in sharp vertical curves will require special attention to detail.

Column spacing should not be so small as to create a cluttered look. Column spacing should be proportioned to maintain a reasonable crossbeam span balance.

2.5.4 Barrier and Wall Surface Treatments

A. Plain Surface Finish

This finish will normally be used on structures that do not have a high degree of visibility or where existing conditions warrant. A bridge in a remote area or a bridge among several existing bridges all having a plain finish would be examples.

B. Fractured Fin Finish

This finish is the most common and an easy way to add a decorative texture to a structure. Variations on this type of finish can be used for special cases. The specific areas to receive this finish should be reviewed with the State Bridge and Structures Architect.

C. Pigmented Sealer

The use of a pigmented sealer can also be an aesthetic enhancement. The particular hue can be selected to blend with the surrounding terrain. Most commonly, this would be considered in urban areas. The selection should be reviewed with the Bridge Architect and the Region.

D. Architectural Details

Rustication grooves, relief panels, pilasters, and decorative finishes may visually improve appearance at transitions between different structure types such as cast-in-place abutments to structural earth retaining walls. Contact the State Bridge and Structures Architect for guidance.

2.5.5 Superstructure

The horizontal elements of the bridge are perhaps the strongest features. The sizing of the structure depth based on the span/depth ratios in BDM Section 2.4.1, will generally produce a balanced relationship.

Haunches or rounding of girders at the piers can enhance the structure's appearance. The use of such features should be kept within reason considering fabrication of materials and construction of formwork. The amount of haunch should be carefully reviewed for overall balance from the primary viewing perspective. Haunches are not limited to cast-in-place superstructures, but may be used in special cases on precast, prestressed I girders. They require job-specific forms which increase cost, and standard design software is not directly applicable.

The slab overhang dimension should approach that used for the structure depth. This dimension should be balanced between what looks good for aesthetics and what is possible with a reasonable slab thickness and reinforcement.

For box girders, the exterior webs can be sloped, but vertical webs are preferred. The amount of slope should not exceed $1\frac{1}{2}$: 1 for structural reasons, and should be limited to 4:1 if sloped webs are desired. Sloped webs should only be used in locations of high aesthetic impact.

2.6 Miscellaneous

2.6.1 Structure Costs

See BDM Section 12.3 for preparing cost estimates for preliminary bridge design.

2.6.2 Handling and Shipping Precast Members and Steel Beams

Bridges utilizing precast concrete beams or steel beams need to have their access routes checked and sites reviewed to be certain that the beams can be transported to the site. It must also be determined that they can be erected once they reach the site.

Both the size and the weight of the beams must be checked. Likely routes to the site must be adequate to handle the truck and trailer hauling the beams. Avoid narrow roads with sharp turns, steep grades, and/or load-rated bridges, which may prevent the beams from reaching the site. The Bridge Preservation Office should be consulted for limitations on hauling lengths and weights.

Generally 200 kips is the maximum weight of a girder that may be hauled by truck. When the weight of a prestressed concrete girder cast in one piece exceeds 160 kips, it may be required to include a post-tensioned 2-piece option detailed in the contract plans.

The site should be reviewed for adequate space for the contractor to set up the cranes and equipment necessary to pick up and place the girders. The reach and boom angle should be checked and should accommodate standard cranes.

2.6.3 Salvage of Materials

When a bridge is being replaced or widened, the material being removed should be reviewed for anything that WSDOT may want to salvage. Items such as aluminum rail, luminaire poles, sign structures, and steel beams should be identified for possible salvage. The Region should be asked if such items are to be salvaged since they will be responsible for storage and inventory of these items.

2.7 WSDOT Standard Highway Bridge

2.7.1 Design Elements

The following are standard design elements for bridges carrying highway traffic. They are meant to provide a generic base for consistent, clean looking bridges, and to reduce design and construction costs. Modification of some elements may be required, depending on site conditions. This should be determined on a case-by-case basis during the preliminary plan stage of the design process.

A. General

Fractured Fin Finish shall be used on the exterior face of the traffic barrier. All other surfaces shall be Plain Surface Finish.

Exposed faces of wingwalls, columns, and abutments shall be vertical. The exterior face of the traffic barrier and the end of the intermediate pier crossbeam and diaphragm shall have a 1:12 backslope.

B. Substructure

End piers use the following details:

15 ft wingwalls with prestressed girders up to 74 inches in depth or a combination of curtain wall/retaining walls.

Stub abutment wall with vertical face. Footing elevation, pile type (if required), and setback dimension are determined from recommendations in the Materials Laboratory Geotechnical Services Branch Geotechnical Report.

Intermediate piers use the following details:

"Semi-raised" Crossbeams: The crossbeam below the girders is designed for the girder and slab dead load, and construction loads. The crossbeam and the diaphragm together are designed for all live loads and composite dead loads. The minimum depth of the crossbeam shall be 3 feet.

"Raised" Crossbeams: The crossbeam is at the same level as the girders are designed for all dead and live loads. "Raised" crossbeams are only used in conjunction with Prestressed Concrete Tub Girders.

Round Columns: Columns shall be 3 feet or 4 feet in diameter. Dimensions are constant full height with no tapers. Bridges with roadway widths of 40 feet or less will generally be single column piers. Bridges with roadway widths of greater the 40 feet shall have two or more columns, following the criteria established in BDM Section 2.3.1 H.

C. Superstructure

Concrete Slab: 7-inch minimum thickness, with the top mat being epoxy coated steel reinforcing bars.

Prestressed Girders: Girder spacing will vary depending on roadway width and span length. The slab overhang dimension is approximately half of the girder spacing. Girder spacing typically ranges between 6 feet and 12 feet.

W95G	Spans up to about 170 feet
W83G	Spans up to about 180 feet
WF74G	Spans up to about 155 feet
WF74G	Spans up to about 145 feet
W58G	Spans up to about 120 feet
W50	Spans up to about 100 feet
W42	Spans up to about 80 feet

Intermediate Diaphragms: Locate at the midspan for girders up to 80 feet long. Locate at third points for girders between 80 feet and 150 feet long and at quarter points for spans over 150 feet.

End Diaphragms: “End Wall on Girder” type.

Traffic Barrier: “F-shape” or Single-sloped barrier.

Fixed Diaphragm at Inter. Piers: Full width of crossbeam between girders and outside of the exterior girders.

Hinged Diaphragm at Inter. Piers: Partial width of crossbeam between girders. Sloped curtain panel full width of crossbeam outside of exterior girders, fixed to ends of crossbeam.

BP Rail: 3 feet 6 inches overall height for pedestrian traffic. 4 feet 6 inches overall height for bicycle traffic.

Sidewalk: 6-inch height at curb line. Transverse slope of -0.01 feet per foot towards the curb line.

Sidewalk barrier: Inside face is vertical. Outside face slopes 1:12 outward.

D. Examples

Appendices 2.7-A1 and A2 detail the standard design elements of a standard highway bridge.

The following bridges are good examples of a standard highway bridge. However, they do have some modifications to the standard.

SR 17 Undercrossing 395/110	Contract 3785
Mullenix Road Overcrossing 16/203E&W	Contract 4143

2.7.2 Detailing the Preliminary Plan

The Bridge Preliminary Plan is used and reviewed by the Bridge and Structures Office or consultant who will do the structural design, Region designers and managers, Geotechnical engineers, Hydraulics engineers, Program managers, FHWA engineers and local agency designers and managers. It sometimes is used in public presentation of projects. With such visibility it is important that it's detailing is clear, complete, professional, and attractive. The designer, detailer, and checker shall strive for completeness and consistency in information, layout, line style, and fonts. Appendix B contains examples of Preliminary Plans following time-proven format that may be helpful. See also Chapter 11, Detailing Practice.

Typical sheet layout is as follows:

1. Plan and Elevation views. (This sheet ultimately becomes the Layout sheet of the design plan set)

2. Typical Section including details of stage construction.

   Superelevation diagrams, tables of existing elevations, Notes to Region, and other miscellaneous details as required shall go on Sheet 2, 3, or 4, as many as are required. See also the Preliminary Plan Checklist for details, dimensions, and notes typically required. The completed plan sheets shall be reviewed for consistency by the Preliminary Plans Detailing Specialist.

2.99 Bibliography

1. Federal Highway Administration (FHWA) publication *Federal Aid Highway Program Manual*.

   FHWA Order 5520.1 (dated December 24, 1990) contains the criteria pertaining to Type, Size, and Location studies.

   Volume 6, Chapter 6, Section 2, Subsection 1, Attachment 1 (Transmittal 425) contains the criteria pertaining to railroad undercrossings and overcrossings.

2. Washington Utilities and Transportation Commission *Clearance Rules and Regulations Governing Common Carrier Railroads.*


3. American Railway Engineering and Maintenance Association (AREMA) *Manual for Railroad Engineering*. Note: This manual is used as the basic design and geometric criteria by all railroads. Use these criteria unless superseded by FHWA or WSDOT criteria.

4. Washington State Department of Transportation (WSDOT) *Design Manual* (M 22-01).


5. *Local Agency Guidelines* (M 36-63).

6. American Association of State Highway and Transportation Officials *AASHTO LRFD Bridge Design Specification.*


7. The Union Pacific Railroad *"Guidelines for Design of Highway Separation Structures over Railroad (Overhead Grade Separation)"*



Preliminary Plan Bridge Replacement
Figure 2-B-1




Preliminary Plan Bridge Replacement
Figure 2-B-2




TYPICAL SECTION
BRIDGE NO. 12/666 & DETOUR BRIDGE
SHOWN NEAR MID SPAN

Preliminary Plan Bridge Replacement
Figure 2-B-3




Preliminary Plan Bridge Widening

Figure 2-B-4




Preliminary Plan Bridge Widening


Figure 2-B-5




L-LINE
SUPERELEVATION DIAGRAM



Preliminary Plan Bridge Widening
Figure 2-B-6



Preliminary Plan Bridge with Staging
Figure 2-B-7



TYPICAL SECTION ~ EB BRIDGE

SHOWN NEAR INTERMEDIATE PIER 3
SUBSTRUCTURE DIMENSIONS ARE APPROXIMATE
HORIZONTAL DIMENSIONS MEASURED PERPENDICULAR TO A22 LINE (UNLESS OTHERWISE NOTED)

Preliminary Plan Bridge with Staging


Figure 2-B-8

EXISTING EB BRIDGE ELEVATIONS

A22 STA.	LT. OFFSET	ELEVATION	LT. OFFSET	ELEVATION
75+98.05			57.84	343.56
76+00.00			57.85	343.57
76+07.79	17.85	344.40		
76+10.00	17.85	344.41	57.87	343.64
76+20.00	17.88	344.45	57.89	343.70
76+30.00	17.91	344.50	57.87	343.75
76+40.00	17.92	344.55	57.85	343.79
76+50.00	17.91	344.61	57.83	343.84
76+60.00	17.89	344.66	57.84	343.90
76+70.00	17.89	344.72	57.85	343.96
76+80.00	17.90	344.77	57.87	344.02
76+90.00	17.90	344.82	57.85	344.08
77+00.00	17.90	344.88	57.84	344.14
77+10.00	17.91	344.93	57.83	344.20
77+20.00	17.91	344.99	57.83	344.25
77+30.00	17.91	345.04	57.84	344.30
77+40.00	17.90	345.09	57.85	344.35
77+50.00	17.90	345.14	57.85	344.40
77+60.00	17.89	345.19	57.82	344.44
77+70.00	17.89	345.24	57.80	344.48
77+80.00	17.89	345.29	57.79	344.52
77+90.00	17.89	345.33	57.80	344.56
78+00.00	17.89	345.38	57.80	344.60
78+10.00	17.88	345.42	57.81	344.64
78+20.00	17.88	345.47	57.82	344.69
78+30.00	17.88	345.51	57.82	344.74
78+40.00	17.88	345.54	57.83	344.78
78+50.00	17.89	345.58	57.84	344.80
78+60.00	17.89	345.62	57.85	344.82
78+70.00	17.89	345.67	57.86	344.83
78+80.00	17.88	345.71	57.86	344.90
78+90.00	17.87	345.76	57.85	344.96
79+00.00	17.88	345.80	57.84	345.02
79+10.00	17.88	345.85	57.84	345.07
79+20.00	17.89	345.90	57.84	345.11
79+30.00	17.89	345.94	57.83	345.15
79+40.00	17.90	345.97	57.83	345.19
79+50.00	17.90	346.01	57.83	345.23
79+60.00	17.90	346.04	57.84	345.26
79+70.00	17.90	346.07	57.84	345.30
79+80.00	17.90	346.09	57.85	345.32
79+90.00	17.90	346.11	57.86	345.35
80+00.00	17.90	346.12	57.86	345.37
80+10.00	17.90	346.13	57.84	345.39
80+20.00	17.90	346.14	57.82	345.41
80+30.00	17.91	346.13	57.80	345.42
80+40.00	17.91	346.12	57.82	345.42
80+50.00	17.92	346.11	57.83	345.43
80+60.00	17.92	346.11	57.85	345.43
80+70.00	17.91	346.13	57.85	345.42
80+80.00	17.90	346.14	57.84	345.41
80+90.00	17.90	346.14	57.84	345.40
81+00.00	17.90	346.13	57.82	345.38
81+10.00	17.91	346.12	57.80	345.37
81+17.04	17.91	346.11		
81+20.00			57.78	345.36
81+23.91			57.77	345.36

TYLER STREET ROADWAY ELEVATIONS

LT. OFFSET	ELEVATION	RT. OFFSET	ELEVATION	LT. OFFSET	ELEVATION	RT. OFFSET	ELEVATION
27.07	315.03	27.08	315.02	4.93	315.50	4.63	315.54
27.06	314.98	27.09	314.96	4.94	315.44	4.63	315.48
27.05	314.93	27.10	314.90	4.94	315.37	4.63	315.42
27.05	314.88	27.12	314.86	4.94	315.33	4.65	315.38
27.05	314.83	27.13	314.84	4.93	315.32	4.71	315.37
27.04	314.78	27.15	314.82	4.92	315.30	4.76	315.36
27.04	314.74	27.16	314.79	4.91	315.29	4.82	315.35
27.04	314.69	27.18	314.77	4.90	315.27	4.88	315.34
27.04	314.65	27.20	314.75	4.90	315.26	4.93	315.33
27.01	314.52				-	-	-
27.01	314.49				-	-	-
27.15	314.53	27.21	314.73	4.93	315.25	4.97	315.32
27.81	314.61	27.20	314.77	4.98	315.26	4.95	315.35
28.36	314.64	27.22	314.80	4.96	315.29	4.92	315.38
28.91	314.68	27.24	314.83	4.93	315.33	4.90	315.41
29.47	314.71	27.25	314.87	4.90	315.36	4.88	315.44
30.02	314.74	27.27	314.90	4.88	315.40	4.85	315.46
30.58	314.77	27.28	314.93	4.85	315.44	4.83	315.50
31.13	314.80	27.26	314.99	4.82	315.47	4.83	315.54
31.68	314.86	27.23	315.04	4.82	315.52	4.83	315.59
32.22	314.91	27.20	315.10	4.84	315.57	4.83	315.64
32.77	314.97	27.17	315.15	4.85	315.62	4.82	315.69
33.32	315.02	27.15	315.21	4.86	315.67	4.82	315.74
33.86	315.08	27.15	315.26	4.88	315.72	4.82	315.80
34.41	315.13	27.16	315.32	4.89	315.78	4.80	315.88
34.94	315.18	27.16	315.37	4.89	315.85	4.79	315.97



BP2 LINE UNDER EB BRIDGE (16/20W)

Preliminary Plan Bridge Replacement
Figure 2-B-9

Chapter 3 Loads

3.1 Type of Loads 3-1
3.1.1 Dead Loads 3-1
3.1.2 Live Loads 3-1
3.1.3 Earthquake Loads (see Chapter 4) 3-2
3.1.4 Other Loads 3-2
3.2 Application of Loads 3-3
3.2.1 Wind Load 3-3
3.3 Use of Computer Software 3-4
3.3.1 Protection of Intellectual Property 3-4
3.3.2 Policy on Open Source Software 3-4
3.3.3 Approved Software Tools 3-4
3.99 Bibliography 3-4
Appendix 3-B
Appendix 3-B-1 HL 93 Loading for Bridge Piers 3-B-1

AASHTO LRFD loading specifications shall be the minimum design criteria used for all bridges.

For falsework and formwork design loads, see standard specifications 6-02.3(17)A.

3.1 Type of Loads

3.1.1 Dead Loads

Use values in AASHTO except as herein modified:

ITEM	LOAD
Reinforced Concrete	160 lb/ft^3
Stay-in-Place Form for Box Girder (of the cell area)	5 lb/ft^2
Traffic Barrier (32" - F Shape)	470 lb/ft
Traffic Barrier (42" - F Shape)	730 lb/ft
Traffic Barrier (34" - Single Slope)	505 lb/ft
Traffic Barrier (42" – Single Slope)	690 lb/ft
Future Wearing Surface (1.5")	20 lb/ft^2
Soil, Compact	125 lb/ft^3

3.1.2 Live Loads

A. General

Live load design criteria is specified in the lower right corner of the bridge preliminary plan sheet. The Bridge Projects Unit determines the criteria using the following guideline:

- HL93 — New bridges and bridges widening with new substructure designed in accordance to AASHTO LRFD Specifications.
- HS-20 — Detour bridges and widening bridges with no addition of substructure.

B. Load Factor γ_{EQ} for Live Load

The γEQ load factor for the live load in Extreme Event-I Limit State, as specified in the LRFD Table 3.4.1-1 for the majority of bridges, shall be equal to 0.0. For bridges located in urban areas susceptible to daily heavy congestion, γEQ shall be equal to 0.5 unless otherwise directed by the WSDOT Bridge Design Engineer. The γEQ factor should be applied to the live load force effect obtained from the bridge live load analysis. Live load mass is ignored in the dynamic analysis.

C. Distribution to Superstructure

1. Concrete Box Girders

For cast-in-place multicell box girders, the following method is used for the live load distribution for both moment and shear instead of using the AASHTO-LRFD live load distribution factor as specified in tables 4.6.2.2.2b-1, 4.6.2.2.2d-1, 4.6.2.2.3a-1, and 4.6.2.2.3b-1.

The number of design lanes, including fractional lanes, shall be taken as the curb-to-curb roadway width in feet divided by 14, and the multiple presence factors shall not be applied to the live load distribution factor.

The correction factor for skewed bridges as specified in AASHTO LRFD table 4.6.2.2.3c-1 shall be applied to the shear distribution factor.

D. Distribution to Substructure

A reduction factor shall be applied in the substructure design for multiple loadings in accordance with AASHTO.

3.1.3 Earthquake Loads (see Chapter 4)

3.1.4 Other Loads

A. Ice Load

In accordance with WSDOT HQ Hydraulics Office criteria, an ice thickness of 12 inches shall be used for stream flow forces on piers in both Western and Eastern parts of State of Washington.

B. Downdrag

Use load factors for downdrag $\gamma_P = 1.00$ instead of the value in LRFD Table 3.4.1-2, for both maximum and minimum situations.

3.2 Application of Loads

3.2.1 Wind Load

Wind load acting on the superstructure shall be based on the bridge elevation exposed by the wind, the height of which usually consists of the girder depth and traffic barrier height.

3.3 Use of Computer Software

3.3.1 Protection of Intellectual Property

Many of the software tools used by the Bridge and Structures Office are licensed from commercial software vendors. WSDOT is committed to using these tools only as allowed by law and as permitted by software license. WSDOT employees shall comply with the terms and conditions of all licensing agreements and provisions of the Copyright Act and other applicable laws.

Before using any software tools WSDOT employees shall read and understand Instructional Letter 4032.00, Titled "Computer Software Piracy Prevention, and the Protection of Intellectual Property"[1].

3.3.2 Policy on Open Source Software

It is the policy of the Bridge and Structures Office to license its own engineering software as open source, and to prefer and promote the use of open source software, within the bridge engineering community.

To support this policy on open source bridge engineering software, the Bridge and Structures Office is a founding and participating member of the Alternate Route Project. The purpose of the Alternate Route Project is to serve as a focal point for the collaborative and cooperative development of open source bridge engineering software tools.

3.3.3 Approved Software Tools

A list of approved software tools available for use by WSDOT bridge design engineers is available at http://wwwi.wsdot.wa.gov/eesc/bridge/software. Note that this list is only available on the WSDOT intranet. WSDOT does not require consulting engineers to use any specific software tools, so long as the use of the tools are in accordance with sound engineering practice, and does not violate software licensing agreements and Copyright law.

When using personal design tools created by others, such as a spreadsheet or MathCAD document, the designer is responsible for thoroughly checking the tool to ensure the integrity of the structural analysis and design.

3.99 Bibliography


1. California Department of Transportation, *Bridge Design Practice*, 1993.

Appendix 3-B-1 HL 93 Loading for Bridge Piers

1. Introduction

The purpose of this example is to demonstrate a methodology of analyzing a bridge pier for the HL-93 live load on two-dimension plane frame in both longitudinal and transverse directions. First, the longitudinal analysis of the superstructure is analyzed. This analysis produces the live load reactions at the intermediate piers. Then the reactions are applied in the transverse direction, for the crossbeam and column design.

2. Bridge Description



3. Analysis Goals

To determine:

- Maximum axial forces and corresponding moments.
- Maximum moments and corresponding axial forces.
- Maximum shears.

4. Material Properties

4.1 Girders

$$E_c = 33{,}000 w_c^{1.5} \sqrt{f'_c}$$

$w_c = 0.160\ kcf$

$f'_c = 7\ ksi$

$E_c = 33{,}000(0.160)^{1.5}\sqrt{7} = 5588$ ksi

4.2 Slab, Columns, and Cross Beam

$w_c = 0.160\ kcf$

$f'_c = 4\ ksi$

$E_c = 33{,}000(0.160)^{1.5}\sqrt{4} = 4224$ ksi

5. Section Properties

Compute the geometric properties of the girder, columns, and cap beam.

5.1 Girder

The composite girder section properties can be obtained from the Section Properties Calculator in QConBridge program for the longitudinal direction.

$A = 1254.6$ in^2

$I = 1{,}007{,}880$ in^3

5.2 Column

Section properties of an individual column are obtained by simple formula for longitudinal and transverse directions:

$$A = \pi \frac{d^2}{4} = \pi \frac{\left(5\,ft \cdot 12\,\frac{in}{ft}\right)^2}{4} = 2827\ in^2$$

$$I = \pi \frac{d^4}{64} = \pi \frac{\left(5\,ft \cdot 12\,\frac{in}{ft}\right)^4}{64} = 636{,}172\ in^4$$

For the longitudinal analysis we need to proportion the column stiffness to each girder line. For longitudinal analysis the section properties of the each column member are:

$$A = \frac{(2\ columns) * (2827\ in^2\ per\ column)}{4\ girder\ lines} = 1413\ in^2$$

$$I = \frac{(2\ columns) * (636{,}172\ in^4\ per\ column)}{4\ girder\ lines} = 318{,}086\ in^4$$

NOTE

For other column shapes and columns on a skewed bent, the properties of the columns need to be computed in the plane of the longitudinal and transverse frames respectively for analysis in each direction.

5.3 Cap Beam

Cap beam properties are obtained by simple formula in transverse direction:

$$A = w \cdot h = 5\,ft \cdot 9\,ft \cdot 144\,\tfrac{in^2}{ft^2} = 6480\,in^2$$

$$I = \frac{1}{12} w \cdot h^3 = \frac{1}{12} \cdot 5\,ft \cdot (9\,ft)^3 \cdot 20736\,\tfrac{in^4}{ft^4} = 6{,}298{,}560\,in^4$$

6. Longitudinal Analysis

The purpose of this analysis is to determine the maximum live load reactions that will be applied to the bent. The results from this analysis will be scaled by the number of loaded lanes causing maximum responses in the bent and distributed to individual columns, for the transverse analysis.


The longitudinal analysis consists of applying various combinations of design lane and design trucks. The details can be found in AAHSTO LRFD 3.6.


6.1 Loading


In order to produce the maximum moment and reaction at interior piers, two trucks spaced at 50 feet minimum are used in the longitudinal direction per AASHTO LRFD Section 3.6.1.3. The influence lines of the axial force, moment, and shear at the top and bottom column of the live loading show the effect of a two-truck loading.

6.1.1 Influence Lines

Figures below are influence lines for axial force, shear, and moment at the top of Pier 2 for a unit load moving along a girder line. The influence lines for the bottom of the pier will be exactly the same, except the moment influence will be different by an amount equal to the shear times the pier height.


Axial, kips
0.20
0.00
-0.20
-0.40
-0.60
-0.80
-1.00
-1.20
0
50
100
150
200
250
300
350
400


Shear
0.40
0.30
0.20
0.10
0.00
-0.10
-0.20
-0.30
-0.40
-0.50
-0.60
0
50
100
150
200
250
300
350
400


Moment
8.00
6.00
4.00
2.00
0.00
-2.00
-4.00
-6.00
-8.00
-10.00
0
50
100
150
200
250
300
350
400

To achieve the maximum compressive reaction, the lane load needs to be in spans 1 and 2, and the two trucks need to straddle between pier 2 and be as close to each other as possible. That is, the minimum headway spacing of 50 feet will maximize the axial reaction.

Maximum shears and moments occur under two conditions. First, spans 1 and 3 are loaded with the lane load and the two truck loading. The headway spacing that causes the maximum response is in the range of 180 – 200 feet. Then, a span 2 is loaded with the lane load and the two truck train. The headway spacing is at its minimum value of 50 ft.

Analytically finding the exact location and headway spacing of the trucks for the extreme force effects is possible, but hardly worth the effort. Structural analysis tools with a moving load generator, such as GTSTRUDL, can be used to quickly determine the maximum force effects.

6.2 Results

A longitudinal analysis is performed using GTSTRUDL. The details of this analysis are shown.

The result of the longitudinal analysis consists of two-truck train and lane load results. These results need to be combined to produce the complete live load response. The complete response is computed as $Q_{LL+IM} = 0.9[(IM)(\textit{Dual Truck Train}) + \textit{Lane Load}]$.

The dynamic load allowance (impact factor) is given by the LRFD specifications as 33%. Note that the dynamic load allowance need not be applied to foundation components entirely below ground level. This causes us to combine the two truck train and lane responses for cross beams and columns differently than for footings, piles, and shafts.

6.2.1 Combined Live Load Response

The tables below summarize the combined live load response. The controlling load cases are given in parentheses.

Maximum Axial

		Top of Pier	Bottom of Pier
	Axial (kips/lane)	Corresponding Moment (k-ft/lane)	Corresponding Moment (k-ft/lane)
Two-Truck Train	-117.9 (Loading case 1014)	-146.2	103.4
Lane Load	-89.1 (Loading case LS12)	-195.5	141.9
LL+IM (Column)	-221.3	-350.9	251.5
LL (Footing)	-186.3	N/A	220.8

Maximum Moment – Top of Pier

	Moment (k-ft/lane)	Corresponding Axial (kips/lane)
Two-Truck Train	-582.5 (Loading 1018)	-85.8
Lane Load	-364.2 (Loading LS2)	-49.4
LL+IM (Column)	-1025.0	-147.2

Maximum Moment – Bottom of Pier

	Moment (k-ft/lane)	Corresponding Axial (kips/lane)
Two-Truck Train	287.7 (Loading 1018)	-85.8
Lane Load	179.7 (Loading LS2)	-49.4
LL+IM (Column)	506.1	-147.2
LL+IM (Footing)	420.7	-121.7

Maximum Shear

	Shear (kips/lane)
Two-Truck Train	21.8 (Loading 1018)
Lane Load	13.6 (Loading LS2)
LL+IM (Column)	38.3
LL (Footing)	31.9

7. Transverse Analysis

Now that we have the maximum lane reactions from the longitudinal girder line analysis, we need to apply these as loads to the bent frame.

7.1 Loading


Apply the superstructure live load reactions of the longitudinal direction to substructure by placing the wheel line reactions directly to the crossbeam and varying the number and position of design lanes described in chapter 7 of the BDM.

7.2 Results

A transverse analysis is performed using GTSTRUDL. The details of this analysis are shown.

7.2.1 Cap Beam

For this example, we will look at results for three design points, the left and right face of the left-hand column, and at the mid-span of the cap beam. Note that in the analysis, the wheel line reactions were applied from the left hand side of the bent. This does not result in a symmetrical set of loadings. However, because this is a symmetrical frame we expect symmetrical results. The controlling results from the left and right hand points “A” and “B” are used.



For shear design of the crossbeam, LRFD specifications section C5.8.3.4.2 allows determination of the effects for moments and shears on the capacity of a section using the maximum factored moments and shears at the section. Hence, the results below do not show the maximum shears and corresponding moments.

The tables below summarize the results of the transverse analysis for the crossbeam.
The basic results are adjusted with the multiple presence factors per LRFD Table 3.6.1.1.2-1.
The controlling load cases are in parentheses.

Point A

	Shear (kips)	+Moment (k-ft)	-Moment (k-ft)
Force Effect	110.7 (Loading 1009)	0	-484.3 (1029)
Multiple Presence Factor	1.2	1.2	1.2
LL+IM	132.8	0	-581.2

Point B

	Shear (kips)	+Moment (k-ft)	-Moment (k-ft)
Force Effect	155.8 (Loading 2330)	314.3 (Loading 1522)	-650.9 (Loading 1029)
Multiple Presence Factor	1.0	1.2	1.2
LL+IM	155.8	377.2	-781.1

Point C

	Shear (kips)	+Moment (k-ft)	-Moment (k-ft)
Force Effect	87.9 (Loading 2036)	426.4 (Loading 1520)	-400.5 (Loading 1029)
Multiple Presence Factor	1.0	1.2	1.2
LL+IM	87.9	511.7	-480.6

7.2.2 Columns

The tables below show the live load results at the top and bottom of a column. The results are factored with the appropriate multiple presence factors. The controlling load cases are in parentheses.

Maximum Axial – Top and Bottom of Column

		Top of Column	Bottom of Column
	Axial (kips)	Corresponding Moment (k-ft)	Corresponding Moment (k-ft)
Force Effect	-347.6 (Loading 2026)	34.1	28.4
Multiple Presence Factor	1.0	1.0	1.0
LL+IM	-347.6	34.1	28.4

Maximum Moment – Top of Column

	Moment (k-ft)	Corresponding Axial (kips)
Force Effect	59.3 (Loading 1009)	-265.6
Multiple Presence Factor	1.2	1.2
LL+IM	71.2	-318.7

Maximum Moment – Bottom of Column

	Moment (k-ft)	Corresponding Axial (kips)
Force Effect	-53.6 (Loading 1029)	55.6
Multiple Presence Factor	1.2	1.2
LL+IM	-64.3	66.7

Maximum Shear

	Shear (kips)
Force Effect	-1.0 (Loading 1029)
Multiple Presence Factor	1.2
LL+IM	-1.2

7.2.3 Footings

In obtaining the footing forces of the loads from the analysis above, the linear elastic system, the principle of superposition can be used. The footing results are simply the column results scaled by the ratio of the footing load to the column load. For this case, the scale factor is 186.3÷221.3 = 0.84.

Maximum Axial – Top of Footing

	Axial (kips)	Corresponding Moment (k-ft)
LL	-292	23.9

Maximum Moment – Top of Footing

	Moment (k-ft)	Corresponding Axial (kips)
LL	-45.0	46.7

Maximum Shear – Top of Footing

	Shear (kps)
LL	-1.0

8. Combining Longitudinal and Transverse Results

To get the full set of column forces, the results from the longitudinal and transverse analyses need to be combined. Recall that the longitudinal analysis produced moments, shears, and axial load for a single loaded lane whereas the transverse analysis produced column and footing forces for multiple loaded lanes.

Before we can combine the force effects we need to determine the per column force effect from the longitudinal analysis. To do this, we look at the axial force results in transverse model to determine the lane fraction that is applied to each column.

For maximum axial load, 2 lanes at 221.3 kips/lane produce an axial force of 347.6 kips. The lane fraction carried by the column is 347.6/(2*221.3) = 0.785 (78.5%).

Mz = (-350.9 K-FT/LANE)(2 LANES)(0.785)(1.0) = -550.9 K-FT (Top of Column)

Mz = (251.5 K-FT/LANE)(2 LANES)(0.785)(1.0) = 394.9 K-FT (Bottom of Column)

Mz = (220.8 K-FT/LANE)(2 LANES)(0.785)(1.0) = 346.7 K-FT (Footing)

For maximum moment (and shear because the same loading governs) at the top of the column, 1 lane at 221.3 kips/lane produces an axial force of 318.7 kips (318.7/221.3 = 1.44), 144% of the lane reaction is carried by the column.

Mz = (-1025.0)(1.44)(1.2) = -1771.2 k-ft


Vx = (38.3)(1.44)(1.2) = 66.2 K (Column)

Vx = (31.9)(1.44)(1.2) = 55.1 K (Footing)

For maximum moment at the bottom of the column, 1 lane at 221.3 kips/lane produces an axial force of 66.7 kips (66.7/221.3 = 0.30) 30% of the lane reaction is carried by the column.

Mz = (506.1)(0.30)(1.2) = 182.2 k-ft (Column)

Mz = (420.7)(0.30)(1.2) = 151.4 k-ft (Footing)



Vx and Mz determined from Longitudinal Analysis
Py, Vz and Mx determined from Transverse Analysis

Column

	Load Case				
	Maximum Axial Top	Maximum Axial Bottom	Maximum Moment Top	Maximum Moment Bottom	Shear
Axial (kips)	-347.6	-347.6	- 318.7	66.7	
Mx (k-ft)	34.1	28.4	71.2	-64.3	
Mz (k-ft)	-550.9	394.9	-1771.2	182.1	
Vx (kips)					66.2
Vz (kips)					-1.2


Footing

	Load Cases		
	Maximum Axial	Maximum Moment Bottom	Shear
Axial (kips)	-292	46.7	
Mx (k-ft)	23.9	-45.0	
Mz (k-ft)	346.7	151.4	
Vx (k)			72.7
Vz (k)			-1.0

9. Skew Effects

This analysis becomes only slightly more complicated when the pier is skewed with respect to the centerline of the bridge. The results of the longitudinal analysis need to be adjusted for skew before being applied to the transverse model.

The shears and moments produced by the longitudinal analysis are in the plane of the longitudinal model. These force vectors have components that are projected into the plane of the transverse model as show in the figure below. The transverse model loading must include these forces and moments for each wheel line load. Likewise, the skew adjusted results from the longitudinal analysis need to be used when combining results from the transverse analysis.



10. Summary

This example demonstrates a method for analyzing bridge piers subjected to the LRFD HL-93 live load.

11. Longitudinal Analysis Details

The following output shows the longitudinal analysis details. In the live load generation portion of the GTSTRUDL input, you will see multiple trials for live load analysis. Each trial uses a different range of headways spacing for the dual truck train. The first trial varies the headway spacing from 180 to 205 feet. Based on this, a tighter range between 193 and 198 feet was used to get the headway spacing corresponding to the maximum loads correct to within 1 foot.

```
                    Commercial Software Rights Legend

 Any use, duplication or disclosure of this software by or for the U.S.
 Government shall be restricted to the terms of a license agreement in
 accordance with the clause at DFARS 227.7202-3.

 This computer software is an unpublished work containing valuable
 trade secrets owned by the Georgia Tech Research Corporation (GTRC).
 No access, use, transfer, duplication or disclosure thereof may be
 made except under a license agreement executed by GTRC or its
 authorized representatives and no right, title or interest thereto
 is conveyed or granted herein, notwithstanding receipt or possession
 hereof.  Decompilation of the object code is strictly prohibited.

   Georgia Tech Research Corporation
   Georgia Institute of Technology
   Atlanta, Georgia  30332   U.S.A.

         Copyright (c) 2002  GTRC
         ALL RIGHTS RESERVED.

# Wed Nov 19 08:57:01 2003


1GTICES/C-NP 2.5.0 MD-NT 2.0, January 1995.
 Proprietary to Georgia Tech Research Corporation, U.S.A.

Reading password file J:\GTSTRUDL\Gtaccess26.dat
 CI-i-audfile, Command AUDIT file FILE0857.aud has been activated.

 *** G T S T R U D L ***
    RELEASE DATE          VERSION             COMPLETION NO.
    February, 2002        26.0                    4290

 **** ACTIVE UNITS -  LENGTH   WEIGHT   ANGLE    TEMPERATURE   TIME
 **** ASSUMED TO BE     INCH    POUND   RADIAN    FAHRENHEIT   SECOND


 {    1} > $ ------------------------------------------------------------
 {    2} > $ This is the Common Startup Macro; put your company-wide startup commands here.
 {    3} > $ You can edit this file from Tools -- Macros.  Click "Startup" and then "Edit".
 {    4} > $ ------------------------------------------------------------

 {    1} > CINPUT 'C:\Documents and Settings\bricer\My Documents\BDM\HL93 Live Load -
```

```
{    2} >_Analysis of Piers\Longitudinal.gti'
{    3} > $ ------------------------------------------------------------
{    4} > $ Live Load Pier Analysis Example
{    5} > $ Longitudinal Anaysis to determine maximum lane reactions
{    6} > $ ------------------------------------------------------------
{    7} > $
{    8} > STRUDL



 ********************************************************************
 *                                                                  *
 *   ******                              G T S T R U D L            *
 *  ********                                                        *
 *  **    **                                                        *
 *  **                *****  ******  *****   **  **  *****   **     *
 *  **  **********   ******  ******  ******  **  **  ******  **     *
 *  **  **********   **        **    **  **  **  **  **  **  **     *
 *  **    ****       *****     **    ******  **  **  **  **  **     *
 *  **********        *****     **    *****   **  **  **  **  **     *
 *   ****** **          **     **    ** **   **  **  **  **  **     *
 *          **       ******    **    **  **  ******  ******  ******  *
 *          **       *****     **    **  **   ****   *****   ******  *
 *          **                                                      *
 *          **                 OWNED BY AND PROPRIETARY TO THE      *
 *          **                 GEORGIA TECH RESEARCH CORPORATION    *
 *                                                                  *
 *  RELEASE DATE         VERSION             COMPLETION NO.         *
 *  February, 2002       26.0                    4290               *
 *                                                                  *
 ********************************************************************



**** ACTIVE UNITS -  LENGTH   WEIGHT   ANGLE    TEMPERATURE   TIME
**** ASSUMED TO BE     INCH    POUND   RADIAN    FAHRENHEIT   SECOND

{    9} > TYPE PLANE FRAME XY
{   10} > OUTPUT LONG NAME
{   11} > UNITS FEET KIPS
{   12} > $
{   13} > JOINT COORDINATES
{   14} > $      Name            X coord            Y coord
```

```
{   15} > $  --------       -------------       ------------
{   16} >           1             0.00000            0.00000
{   17} >           2           100.00000            0.00000
{   18} >           3           240.00000            0.00000
{   19} >           4           340.00000            0.00000
{   20} >           5           100.00000          -40.00000 S
{   21} >           6           240.00000          -40.00000 S
{   22} > $
{   23} > $
{   24} > $ ------------- Boundary conditions -------
{   25} > $ --- Roller joints: rotation + horiz. translation
{   26} > DEFINE GROUP 'roller' ADD JOINTS 1 4
{   27} > STATUS SUPPORT JOINT GROUP 'roller'
{   28} > JOINT GRP 'roller' RELEASES FORCE X MOM Z
{   29} > $
{   30} > MEMBER INCIDENCES
{   31} > $      Name  Start joint  End joint
{   32} > $  --------     --------   --------
{   33} >           1            1          2
{   34} >           2            2          3
{   35} >           3            3          4
{   36} >           4            5          2
{   37} >           5            6          3
{   38} > $
{   39} > $ ------------- Properties ----------------
{   40} > UNITS INCHES
{   41} > MEMBER PROPERTIES
{   42} >    1 TO 3 AX 1255 IZ 1007880
{   43} >    4 TO 5 AX 1413 IZ 318086
{   44} >
{   45} > CONSTANTS
{   46} >    E 5588 MEMBERS 1 TO 3
{   47} >    E 4224 MEMBERS 4 TO 5
{   48} > $
{   49} > $ ------------- Loadings ------------------
{   50} > UNITS KIP FEET
{   51} > $
{   52} > $ --- Lane Loads ---
{   53} > LOADING 'LS12' 'Load load in span 1 and 2'
{   54} > MEMBER 1 2 LOAD FORCE Y UNIFORM FRAcTIONAL -0.640 LA 0.0 LB 1.0
{   55} >
{   56} > LOADING 'LS13' 'Load load in span 1 and 3'
{   57} > MEMBER 1 3 LOAD FORCE Y UNIFORM FRAcTIONAL -0.640 LA 0.0 LB 1.0
{   58} >
{   59} > LOADING 'LS2' 'Load load in span 2'
```

```
{   60} > MEMBER 2 LOAD FORCE Y UNIFORM FRAcTIONAL -0.640 LA 0.0 LB 1.0
{   61} >
{   62} > LOADING 'LS3' 'Load load in span 3'
{   63} > MEMBER 3 LOAD FORCE Y UNIFORM FRAcTIONAL -0.640 LA 0.0 LB 1.0
{   64} >
{   65} > $ --- Dual Truck Train ---
{   66} >
{   67} > $$ --- TRIAL 1 - (GOAL: Determine approximate headway spacing)
{   68} > $$ --- RESULTS: Maximums occured for headway spacings of 50' and 205'
{   69} > $$ --- Load ID Legend
{   70} > $$ - ID = 1000 TO 1999,  50' Headway Spacing
{   71} > $$ - ID = 2000 TO 2999, 180' Headway Spacing
{   72} > $$ - ID = 3000 TO 3999, 185' Headway Spacing
{   73} > $$ - ID = 4000 TO 4999, 190' Headway Spacing
{   74} > $$ - ID = 5000 TO 5999, 195' Headway Spacing
{   75} > $$ - ID = 6000 TO 6999, 200' Headway Spacing
{   76} > $$ - ID = 7000 TO 7999, 205' Headway Spacing
{   77} > $MOVING LOAD GENERATOR
{   78} > $
{   79} > $SUPERSTRUCTURE FOR MEMBERS 1 TO 3
{   80} > $TRUCK FWD GENERAL TRUCK 32.0 14.0 32.0 14.0 8.0  50.0 32.0 14.0 32.0 14.0 8.0
{   81} > $GENERATE LOAD INITIAL 1000 PRINT OFF
{   82} > $
{   83} > $TRUCK FWD GENERAL TRUCK 32.0 14.0 32.0 14.0 8.0 180.0 32.0 14.0 32.0 14.0 8.0
{   84} > $GENERATE LOAD INITIAL 2000 PRINT OFF
{   85} > $
{   86} > $TRUCK FWD GENERAL TRUCK 32.0 14.0 32.0 14.0 8.0 185.0 32.0 14.0 32.0 14.0 8.0
{   87} > $GENERATE LOAD INITIAL 3000 PRINT OFF
{   88} > $
{   89} > $TRUCK FWD GENERAL TRUCK 32.0 14.0 32.0 14.0 8.0 190.0 32.0 14.0 32.0 14.0 8.0
{   90} > $GENERATE LOAD INITIAL 4000 PRINT OFF
{   91} > $
{   92} > $TRUCK FWD GENERAL TRUCK 32.0 14.0 32.0 14.0 8.0 195.0 32.0 14.0 32.0 14.0 8.0
{   93} > $GENERATE LOAD INITIAL 5000 PRINT OFF
{   94} > $
{   95} > $TRUCK FWD GENERAL TRUCK 32.0 14.0 32.0 14.0 8.0 200.0 32.0 14.0 32.0 14.0 8.0
{   96} > $GENERATE LOAD INITIAL 6000 PRINT OFF
{   97} > $
{   98} > $TRUCK FWD GENERAL TRUCK 32.0 14.0 32.0 14.0 8.0 205.0 32.0 14.0 32.0 14.0 8.0
{   99} > $GENERATE LOAD INITIAL 7000 PRINT OFF
{  100} > $
{  101} > $END LOAD GENERATOR
{  102} >
{  103} > $ --- TRIAL 2 - (GOAL: Determine extreme values using refined headway spacing)
{  104} > $ --- Load ID Legend
```

```
{  105} > $ - ID = 1000 TO 1999,  50' Headway Spacing
{  106} > $ - ID = 2000 TO 2999, 193' Headway Spacing
{  107} > $ - ID = 3000 TO 3999, 194' Headway Spacing
{  108} > $ - ID = 4000 TO 4999, 195' Headway Spacing
{  109} > $ - ID = 5000 TO 5999, 196' Headway Spacing
{  110} > $ - ID = 6000 TO 6999, 197' Headway Spacing
{  111} > $ - ID = 7000 TO 7999, 198' Headway Spacing
{  112} >
{  113} > MOVING LOAD GENERATOR
{  114} >
{  115} > SUPERSTRUCTURE FOR MEMBERS 1 TO 3
{  116} > TRUCK FWD GENERAL TRUCK 32.0 14.0 32.0 14.0 8.0  50.0 32.0 14.0 32.0 14.0 8.0
{  117} > GENERATE LOAD INITIAL 1000 PRINT OFF
{  118} >
{  119} > TRUCK FWD GENERAL TRUCK 32.0 14.0 32.0 14.0 8.0 193.0 32.0 14.0 32.0 14.0 8.0
{  120} > GENERATE LOAD INITIAL 2000 PRINT OFF
{  121} >
{  122} > TRUCK FWD GENERAL TRUCK 32.0 14.0 32.0 14.0 8.0 194.0 32.0 14.0 32.0 14.0 8.0
{  123} > GENERATE LOAD INITIAL 3000 PRINT OFF
{  124} >
{  125} > TRUCK FWD GENERAL TRUCK 32.0 14.0 32.0 14.0 8.0 195.0 32.0 14.0 32.0 14.0 8.0
{  126} > GENERATE LOAD INITIAL 4000 PRINT OFF
{  127} >
{  128} > TRUCK FWD GENERAL TRUCK 32.0 14.0 32.0 14.0 8.0 196.0 32.0 14.0 32.0 14.0 8.0
{  129} > GENERATE LOAD INITIAL 5000 PRINT OFF
{  130} >
{  131} > TRUCK FWD GENERAL TRUCK 32.0 14.0 32.0 14.0 8.0 197.0 32.0 14.0 32.0 14.0 8.0
{  132} > GENERATE LOAD INITIAL 6000 PRINT OFF
{  133} >
{  134} > TRUCK FWD GENERAL TRUCK 32.0 14.0 32.0 14.0 8.0 198.0 32.0 14.0 32.0 14.0 8.0
{  135} > GENERATE LOAD INITIAL 7000 PRINT OFF
{  136} >
{  137} > END LOAD GENERATOR
*** OUT OF MOVING LOAD GENERATOR
{  138} > $
{  139} > $ -------------- Analysis
{  140} > $
{  141} > STIFFNESS ANALYSIS
TIME FOR CONSISTENCY CHECKS FOR      5 MEMBERS      0.06 SECONDS
TIME FOR BANDWIDTH REDUCTION                        0.00 SECONDS
TIME TO GENERATE      5 ELEMENT STIF. MATRICES      0.05 SECONDS
TIME TO PROCESS     1337 MEMBER LOADS               0.05 SECONDS
TIME TO ASSEMBLE THE STIFFNESS MATRIX               0.02 SECONDS
TIME TO PROCESS      6 JOINTS                       0.01 SECONDS
TIME TO SOLVE WITH    1 PARTITIONS                  0.01 SECONDS
```

```
 TIME TO PROCESS      6 JOINT DISPLACEMENTS          0.02 SECONDS
 TIME TO PROCESS      5 ELEMENT DISTORTIONS          0.04 SECONDS
 TIME FOR STATICS CHECK                              0.01 SECONDS
 {  142} > $
 {  143} > $ ------------- Results
 {  144} > $
 {  145} > OUTPUT BY MEMBER
 {  146} >
 {  147} > $ ----------- Dual Truck Results Envelope (top and bottom of pier)
 {  148} > LOAD LIST 1000 TO 7999
 {  149} > LIST FORCE ENVELOPE MEMBER 4 SECTION FRACTIONAL NS 2 1.0 0.0
1

   ****************************
   *RESULTS OF LATEST ANALYSES*
   ****************************


    PROBLEM - NONE      TITLE - NONE GIVEN


    ACTIVE UNITS  FEET KIP  RAD  DEGF SEC


    INTERNAL MEMBER RESULTS
    -----------------------

     MEMBER FORCE ENVELOPE

-------------------------------------------------------------------------------------------------------------------------------
---      MEMBER  4
-------------------------------------------------------------------------------------------------------------------------------

   DISTANCE         /-------------------  FORCE  --------------------//------------------  MOMENT  ------------------/
  FROM START              AXIAL         Y SHEAR         Z SHEAR         TORSION       Y BENDING       Z BENDING

    1.000  FR          5.504462        21.75733                                                       459.4002
                           6047           1018                                                          3024
                      -117.8832       -17.13201                                                      -582.5873
                           1014           3024                                                          1018

    0.000              5.504462        21.75733                                                       287.7058
                           6047           1018                                                          1018
                      -117.8832       -17.13201                                                      -225.8802
                           1014           3024                                                          3024
```

```
{  150} >
{  151} > $ ----------- Lane Load Results Envelope (top and bottom of pier)
{  152} > LOAD LIST 'LS12' 'LS13' 'LS2' 'LS3'
{  153} > LIST FORCE ENVELOPE MEMBER 4 SECTION FRACTIONAL NS 2 1.0 0.0


   ***************************
   *RESULTS OF LATEST ANALYSES*
   ***************************


    PROBLEM - NONE      TITLE - NONE GIVEN


    ACTIVE UNITS  FEET KIP  RAD  DEGF SEC


    INTERNAL MEMBER RESULTS
    -----------------------

     MEMBER FORCE ENVELOPE

-------------------------------------------------------------------------------------------------------------------------------
---      MEMBER  4
-------------------------------------------------------------------------------------------------------------------------------

   DISTANCE         /-------------------  FORCE  --------------------//------------------  MOMENT  ------------------/
  FROM START              AXIAL         Y SHEAR         Z SHEAR         TORSION       Y BENDING       Z BENDING

    1.000  FR          3.302270        13.59967                                                       276.7290
                           LS3             LS2                                                            LS13
                      -89.14960       -10.33223                                                      -364.2411
                           LS12            LS13                                                           LS2

    0.000              3.302270        13.59967                                                       179.7457
                           LS3             LS2                                                            LS2
                      -89.14960       -10.33223                                                      -136.5602
                           LS12            LS13                                                           LS13


{  154} >
{  155} > $ ----------- Corresponding force effects maximum axial, shear, and moment
{  156} > LOAD LIST 1014 1018 'LS12' 'LS2'
```

```
{  157} > LIST SECTION FORCES MEMBER 4 SECTION FRACTIONAL NS 2 1.0 0.0


   ****************************
   *RESULTS OF LATEST ANALYSES*
   ****************************


    PROBLEM - NONE      TITLE - NONE GIVEN


    ACTIVE UNITS  FEET KIP  RAD  DEGF SEC


    INTERNAL MEMBER RESULTS
    -----------------------

     MEMBER SECTION FORCES

-------------------------------------------------------------------------------------------------------------------------------
---      MEMBER  4
-------------------------------------------------------------------------------------------------------------------------------


         LOADING    LS12        Load load in span 1 and 2

   DISTANCE         /-------------------  FORCE  --------------------//------------------  MOMENT  ------------------/
  FROM START              AXIAL         Y SHEAR         Z SHEAR         TORSION       Y BENDING       Z BENDING

    1.000  FR          -89.14960        8.433558                                                      -195.4770
    0.000              -89.14960        8.433558                                                       141.8653


         LOADING    LS2         Load load in span 2

   DISTANCE         /-------------------  FORCE  --------------------//------------------  MOMENT  ------------------/
  FROM START              AXIAL         Y SHEAR         Z SHEAR         TORSION       Y BENDING       Z BENDING

    1.000  FR          -49.40132        13.59967                                                      -364.2411
    0.000              -49.40132        13.59967                                                       179.7458


         LOADING    1014        USERS TRUCK      FORWARD  PIVOT ON SECTION  2    MEMBER 2

   DISTANCE         /-------------------  FORCE  --------------------//------------------  MOMENT  ------------------/
```

FROM START		AXIAL	Y SHEAR	Z SHEAR	TORSION	Y BENDING	Z BENDING
1.000	FR	-117.8832	6.239560				-146.2155
0.000		-117.8832	6.239560				103.3669

LOADING 1018 USERS TRUCK FORWARD PIVOT ON SECTION 6 MEMBER 2

DISTANCE		FORCE			MOMENT		
FROM START		AXIAL	Y SHEAR	Z SHEAR	TORSION	Y BENDING	Z BENDING
1.000	FR	-85.84380	21.75733				-582.5874
0.000		-85.84380	21.75733				287.7058

12. Transverse Analysis Details

The following output shows the details of the transverse analysis. The interesting thing to note about the transverse analysis is the live load truck configuration. A technique of treating the wheel line reactions as a longitudinal live load is used. A two axle “truck” is created. The truck is positioned so that it is on the left edge, center, and right edge of the design lane. In order to keep the axles in the correct position, a dummy axle with a weight of 0.0001 kips was used. This dummy axial is the lead axle of the truck and it is positioned in such a way as to cause the two “real” axles to fall in the correct locations within the design lanes.

The GTSTRUDL live load generator uses partial trucks when it is bring a truck onto or taking it off a bridge. As such, less then the full number of axles are applied to the model. For the transverse analysis, we do not want to consider the situation when only one of the two wheel lines is on the model. As such, several load cases are ignored by way of the LOAD LIST command on line76 of the output.

```
                    Commercial Software Rights Legend

 Any use, duplication or disclosure of this software by or for the U.S.
 Government shall be restricted to the terms of a license agreement in
 accordance with the clause at DFARS 227.7202-3.

 This computer software is an unpublished work containing valuable
 trade secrets owned by the Georgia Tech Research Corporation (GTRC).
 No access, use, transfer, duplication or disclosure thereof may be
 made except under a license agreement executed by GTRC or its
 authorized representatives and no right, title or interest thereto
 is conveyed or granted herein, notwithstanding receipt or possession
 hereof.  Decompilation of the object code is strictly prohibited.

   Georgia Tech Research Corporation
   Georgia Institute of Technology
   Atlanta, Georgia  30332   U.S.A.

         Copyright (c) 2002  GTRC
         ALL RIGHTS RESERVED.

# Wed Nov 19 09:23:01 2003


1GTICES/C-NP 2.5.0 MD-NT 2.0, January 1995.
 Proprietary to Georgia Tech Research Corporation, U.S.A.

Reading password file J:\GTSTRUDL\Gtaccess26.dat
 CI-i-audfile, Command AUDIT file FILE0923.aud has been activated.

 *** G T S T R U D L ***
    RELEASE DATE          VERSION             COMPLETION NO.
    February, 2002        26.0                    4290

 **** ACTIVE UNITS -  LENGTH   WEIGHT   ANGLE    TEMPERATURE   TIME
 **** ASSUMED TO BE     INCH    POUND   RADIAN    FAHRENHEIT   SECOND


 {    1} > $ ------------------------------------------------------------
 {    2} > $ This is the Common Startup Macro; put your company-wide startup commands
here.
 {    3} > $ You can edit this file from Tools -- Macros.  Click "Startup" and then
"Edit".
 {    4} > $ ------------------------------------------------------------
```

```
{    1} > CINPUT 'C:\Documents and Settings\bricer\My Documents\BDM\HL93 Live Load -
{    2} >_Analysis of Piers\Transverse.gti'
{    3} > $ ------------------------------------------------------
{    4} > $ Live Load Pier Analysis Example
{    5} > $ Transverse Anaysis to determine column loads
{    6} > $ ------------------------------------------------------
{    7} > $
{    8} > STRUDL
```

```
 ********************************************************************
 *                                                                  *
 *   ******                            G T S T R U D L              *
 *  ********                                                        *
 *  **    **                                                        *
 *  **               *****  ******  *****   **  **  *****   **      *
 *  **  **********  ******  ******  ******  **  **  ******  **      *
 *  **  **********  **        **    **  **  **  **  **  **  **      *
 *  **    ****      *****     **    ******  **  **  **  **  **      *
 *  **********       *****    **    *****   **  **  **  **  **      *
 *   ****** **         **    **    ** **   **  **  **  **  **      *
 *          **      ******    **    **  **  ******  ******  ******  *
 *          **      *****     **    **  **   ****   *****   ******  *
 *          **                                                      *
 *          **                OWNED BY AND PROPRIETARY TO THE       *
 *          **                GEORGIA TECH RESEARCH CORPORATION     *
 *                                                                  *
 *  RELEASE DATE         VERSION             COMPLETION NO.         *
 *  February, 2002       26.0                    4290               *
 *                                                                  *
 ********************************************************************
```

```
**** ACTIVE UNITS -  LENGTH   WEIGHT   ANGLE    TEMPERATURE   TIME
**** ASSUMED TO BE     INCH    POUND   RADIAN    FAHRENHEIT   SECOND
```

```
{    9} > TYPE PLANE FRAME XY
{   10} > MATERIAL STEEL
{   11} > OUTPUT LONG NAME
{   12} > UNITS FEET KIPS
```

```
{   13} > $
{   14} > JOINT COORDINATES
{   15} > $      Name             X coord           Y coord
{   16} > $  --------       -------------       ------------
{   17} >           1           -14.00000           40.00000
{   18} >           2            -7.00000           40.00000
{   19} >           3             7.00000           40.00000
{   20} >           4            14.00000           40.00000
{   21} >           5            -7.00000            0.00000 S
{   22} >           6             7.00000            0.00000 S
{   23} > $
{   24} > $
{   25} > MEMBER INCIDENCES
{   26} > $      Name  Start joint  End joint
{   27} > $  --------     --------   --------
{   28} >           1            1          2
{   29} >           2            2          3
{   30} >           3            3          4
{   31} >           4            5          2
{   32} >           5            6          3
{   33} > $
{   34} > $ ------------- Properties ----------------
{   35} > UNITS INCHES
{   36} > MEMBER PROPERTIES
{   37} >    1 TO 3  AX 64935 IZ 6283008 $ CAP BEAM
{   38} >    4 TO 5  AX  2827 IZ  636172 $ COLUMNS
{   39} > UNITS FEET
{   40} > $
{   41} > $ ------------- Loadings ------------------
{   42} > $
{   43} > MOVING LOAD GENERATOR
{   44} > SUPERSTRUCTURE FOR MEMBERS 1 TO 3
{   45} >
{   46} > $ One lane loaded - Left Aligned
{   47} > TRUCK FWD GENERAL TRUCK NP 3 110.7 6 110.7 0.875 0.0001
{   48} > GENERATE LOAD INITIAL 1000 PRINT OFF
{   49} >
{   50} > $ One lane loaded - Center Aligned
{   51} > TRUCK FWD GENERAL TRUCK NP 3 110.7 6 110.7 2.125 0.00001
{   52} > GENERATE LOAD INITIAL 1300 PRINT OFF
{   53} >
{   54} > $ One lane loaded - Right Aligned
{   55} > TRUCK FWD GENERAL TRUCK NP 3 110.7 6 110.7 3.125 0.0001
{   56} > GENERATE LOAD INITIAL 1500 PRINT OFF
{   57} >
```

```
{   58} >
{   59} > $ Two lanes loaded - Left Aligned
{   60} > TRUCK FWD GENERAL TRUCK NP 5 110.7 6 110.7 6 110.7 6 110.7 0.875 0.0001
{   61} > GENERATE LOAD INITIAL 2000 PRINT OFF
{   62} >
{   63} > $ Two lanes loaded - Center Aligned
{   64} > TRUCK FWD GENERAL TRUCK NP 5 110.7 6 110.7 6 110.7 6 110.7 2.125 0.00001
{   65} > GENERATE LOAD INITIAL 2300 PRINT OFF
{   66} >
{   67} > $ Two lanes loaded - Right Aligned
{   68} > TRUCK FWD GENERAL TRUCK NP 5 110.7 6 110.7 6 110.7 6 110.7 3.125 0.0001
{   69} > GENERATE LOAD INITIAL 2500 PRINT OFF
{   70} >
{   71} > END LOAD GENERATOR
*** OUT OF MOVING LOAD GENERATOR
{   72} > $
{   73} > $ -------------- Analysis
{   74} > $
{   75} > $ --- Keep active only those loads where all of the "axles" are on the structure
{   76} > LOAD LIST 1009 TO 1029 1311 TO 1330 1513 TO 1531  2026 TO 2037 2328 TO 2338 2530 TO 2539
{   77} > STIFFNESS ANALYSIS
TIME FOR CONSISTENCY CHECKS FOR      5 MEMBERS      0.00 SECONDS
TIME FOR BANDWIDTH REDUCTION                        0.00 SECONDS
TIME TO GENERATE      5 ELEMENT STIF. MATRICES      0.00 SECONDS
TIME TO PROCESS      345 MEMBER LOADS               0.01 SECONDS
TIME TO ASSEMBLE THE STIFFNESS MATRIX               0.00 SECONDS
TIME TO PROCESS      6 JOINTS                       0.00 SECONDS
TIME TO SOLVE WITH    1 PARTITIONS                  0.00 SECONDS
TIME TO PROCESS      6 JOINT DISPLACEMENTS          0.01 SECONDS
TIME TO PROCESS      5 ELEMENT DISTORTIONS          0.00 SECONDS
TIME FOR STATICS CHECK                              0.00 SECONDS
{   78} > $
{   79} > $ ------------- Results
{   80} > $
{   81} > $ CAP BEAM RESULTS (FACE OF COLUMN AND CENTERLINE BEAM)
{   82} > LIST FORCE ENVELOPE MEMBER 1 SECTION NS 1 4.5
1

    ***************************
    *RESULTS OF LATEST ANALYSES*
    ***************************


     PROBLEM - NONE      TITLE - NONE GIVEN
```

```
    ACTIVE UNITS  FEET KIP  RAD  DEGF SEC


    INTERNAL MEMBER RESULTS
    -----------------------

     MEMBER FORCE ENVELOPE

-------------------------------------------------------------------------------------------------------------------------------
---      MEMBER  1                                                                                                            -
-------------------------------------------------------------------------------------------------------------------------------

   DISTANCE          /-------------------  FORCE  --------------------//------------------  MOMENT  ------------------/
  FROM START                AXIAL         Y SHEAR         Z SHEAR         TORSION       Y BENDING       Z BENDING

    4.500              0.0000000E+00    110.7001                                                      0.4612272E-11
                           1009            1009                                                          2539
                       0.0000000E+00  -0.3200976E-11                                                 -401.2880
                           1010            2336                                                          1009


{   83} > LIST FORCE ENVELOPE MEMBER 2 SECTION NS 3 2.5 7 11.5


   ****************************
   *RESULTS OF LATEST ANALYSES*
   ****************************


    PROBLEM - NONE      TITLE - NONE GIVEN


    ACTIVE UNITS  FEET KIP  RAD  DEGF SEC


    INTERNAL MEMBER RESULTS
    -----------------------

     MEMBER FORCE ENVELOPE

-------------------------------------------------------------------------------------------------------------------------------
---      MEMBER  2                                                                                                            -
-------------------------------------------------------------------------------------------------------------------------------
```

```
   DISTANCE         /------------------  FORCE  ------------------//-----------------  MOMENT  -----------------/
  FROM START              AXIAL         Y SHEAR         Z SHEAR         TORSION       Y BENDING       Z BENDING

    2.500              1.064582        55.64646                                                       314.3994
                          1029            1029                                                          1522
                      -0.7828730       -155.8126                                                      -522.0231
                          1021            2330                                                          1009

    7.000              1.064582        87.92229                                                       426.4992
                          1029            2036                                                          1520
                      -0.7828730       -87.92228                                                      -400.5730
                          1021            2328                                                          1029

   11.500              1.064582        155.8126                                                       301.1816
                          1029            2034                                                          1022
                      -0.7828730       -44.21778                                                      -650.9821
                          1021            1009                                                          1029


{   84} > LIST FORCE ENVELOPE MEMBER 3 SECTION NS 1 2.5


   ****************************
   *RESULTS OF LATEST ANALYSES*
   ****************************


    PROBLEM - NONE      TITLE - NONE GIVEN


    ACTIVE UNITS  FEET KIP  RAD  DEGF SEC


    INTERNAL MEMBER RESULTS
    -----------------------

     MEMBER FORCE ENVELOPE

-------------------------------------------------------------------------------------------------------------------------------
---      MEMBER  3
-------------------------------------------------------------------------------------------------------------------------------

   DISTANCE         /------------------  FORCE  ------------------//-----------------  MOMENT  -----------------/
  FROM START              AXIAL         Y SHEAR         Z SHEAR         TORSION       Y BENDING       Z BENDING
```

```
    2.500              0.1944455E-10   0.1574852E-11                                                    0.7038116E-05
                           2037            1526                                                            2533
                       0.0000000E+00   -110.7000                                                        -484.3125
                           1010            1026                                                            1029


{   85} >
{   86} > $ COLUMN TOP AND BOTTOM RESULTS
{   87} > LIST FORCE ENVELOPE MEMBER 4 SECTION FRACTIONAL NS 2 1.0 0.0


   ****************************
   *RESULTS OF LATEST ANALYSES*
   ****************************


    PROBLEM - NONE      TITLE - NONE GIVEN


    ACTIVE UNITS  FEET KIP  RAD  DEGF SEC


    INTERNAL MEMBER RESULTS
    -----------------------

     MEMBER FORCE ENVELOPE

-------------------------------------------------------------------------------------------------------------------------------
---      MEMBER  4
-------------------------------------------------------------------------------------------------------------------------------

   DISTANCE         /-------------------  FORCE  -------------------//------------------  MOMENT  ------------------/
  FROM START              AXIAL         Y SHEAR         Z SHEAR         TORSION       Y BENDING       Z BENDING

    1.000  FR          55.64646       0.7828730                                                        59.30810
                           1029            1021                                                            1009
                      -347.5455       -1.064582                                                       -27.00405
                           2026            1029                                                            2539

    0.000              55.64646       0.7828730                                                        28.35656
                           1029            1021                                                            2026
                      -347.5455       -1.064582                                                       -53.63107
                           2026            1029                                                            1029
```

```
{   88} >
{   89} > $ RESULTS CORRESPONDING TO MIN/MAX VALUES
{   90} > $ Corresponding values not needed for cross beam
{   91} > $ COLUMN TOP AND BOTTOM RESULTS
{   92} > LOAD LIST 1009 1029 2026 2539
{   93} > LIST SECTION FORCES MEMBER 4 SECTION FRACTIONAL NS 2 1.0 0.0


   ****************************
   *RESULTS OF LATEST ANALYSES*
   ****************************


    PROBLEM - NONE      TITLE - NONE GIVEN


    ACTIVE UNITS  FEET KIP  RAD  DEGF SEC


    INTERNAL MEMBER RESULTS
    -----------------------

     MEMBER SECTION FORCES

-------------------------------------------------------------------------------------------------------------------------------
---      MEMBER  4
-------------------------------------------------------------------------------------------------------------------------------


         LOADING    1009        USERS TRUCK      FORWARD  PIVOT ON SECTION  0    MEMBER 1

   DISTANCE         /-------------------  FORCE  -------------------//------------------  MOMENT  ------------------/
  FROM START               AXIAL         Y SHEAR         Z SHEAR         TORSION       Y BENDING       Z BENDING

    1.000  FR          -265.6179      -0.8585348                                                      59.30810
    0.000              -265.6179      -0.8585348                                                      24.96671


         LOADING    1029        USERS TRUCK      FORWARD  PIVOT ON SECTION  0    MEMBER 3

   DISTANCE         /-------------------  FORCE  -------------------//------------------  MOMENT  ------------------/
  FROM START               AXIAL         Y SHEAR         Z SHEAR         TORSION       Y BENDING       Z BENDING

    1.000  FR           55.64647       -1.064582                                                     -11.04779
    0.000               55.64647       -1.064582                                                     -53.63107
```

LOADING 2026 USERS TRUCK FORWARD PIVOT ON SECTION 0 MEMBER 1

DISTANCE FROM START	FORCE AXIAL	FORCE Y SHEAR	FORCE Z SHEAR	MOMENT TORSION	MOMENT Y BENDING	MOMENT Z BENDING
1.000 FR	-347.5455	-0.1425789				34.05972
0.000	-347.5455	-0.1425789				28.35657

LOADING 2539 USERS TRUCK FORWARD PIVOT ON SECTION 9 MEMBER 1

DISTANCE FROM START	FORCE AXIAL	FORCE Y SHEAR	FORCE Z SHEAR	MOMENT TORSION	MOMENT Y BENDING	MOMENT Z BENDING
1.000 FR	-86.08118	-0.2046868				-27.00405
0.000	-86.08118	-0.2046868				-35.19152

Chapter 4 Seismic Design and Retrofit

4.0 Seismic Design and Retrofit 4-1
4.1 General 4-1
4.2 Seismic Design Process 4-2
4.3 WSDOT Practices and Criteria 4-3
4.4 Elastic Dynamic Analysis (EDA) 4-6
4.4.1 Analytical Methods 4-6
4.4.2 Structural System or Global Analyses 4-7
4.4.3 Stand-Alone or Local Analysis 4-8
4.4.4 Model Verification 4-9
4.4.5 Effective Cracked Moment of Inertia for Reinforced Concrete Columns 4-9
4.5 Base Isolation and Energy Dissipation Devices 4-10
4.6 Retrofit Guide 4-12
4.6.1 Vulnerability Study 4-12
4.6.2 Material Properties 4-14
4.6.3 Earthquake Restrainers 4-14
4.6.4 Shear Blocks and Catcher Beams 4-15
4.6.5 Post-tensioning Strengthening 4-16
4.6.6 Column jacketing 4-17
4.6.7 Steel Structures 4-21
4.6.8 Base Isolation and Energy Dissipation Devices 4-22
4.99 Bibliography 4-23
Appendix 4-A
Figure 4-A-1 Earthquake Probability - Poisson Model 4-A-1
Figure 4-A-2 Design Examples of Seismic Retrofits 4-A-2

4.0 Seismic Design and Retrofit

4.1 General

The purpose of this chapter is to provide designers with an outline of the seismic design process and to provide specific WSDOT practices and criteria.


The format and material for this chapter is based on the *Seismic Design Criteria* (2004) developed by the California Department of Transportation (Caltrans). Additional references are: the National Highway Institute (NHI) Course No. 13063 *Seismic Bridge Design Applications* (1996), Publications FHWA-SA-97-006 through -012 (1996), and *Seismic Design and Retrofit of Bridges* (1996).

The latest AASHTO LRFD Bridge Design Specifications and all successive Interim Specifications are used for the seismic design of bridges. All highway bridges in Washington State are classified as "Others" except for special major bridges. Special major bridges fitting the classifications of either "Critical" or "Essential" will be so designated by either the Bridge and Structures Engineer or the Bridge Design Engineer.

MCEER (Multidisciplinary Center for Earthquake Engineering Research) has developed new seismic design criteria for bridge structures. These criteria involve two distinct levels: a Life Safety Level or less severe level with a 108-year return period and an Operational Level or more severe level based on a Maximum Credible Earthquake (MCE) with a 2,500-year return period. At this time, AASHTO has not adopted these new seismic criteria. See Appendix A for calculating the probability based on the return period. WSDOT has implemented the new MCEER seismic design criteria for only the design of specific large projects that involve substantial financial investment, such as the Alaskan Way Viaduct Replacement, using the Life Safety performance level only. It is expected that AASHTO will eventually adopt the new criteria. At that time, WSDOT will then use it for the design of new bridges.

4.2 Seismic Design Process

Figure 4-1 shows the seismic design process.



Seismic Design Process

Figure 4-1

4.3 WSDOT Practices and Criteria

Designers shall use the October 2002 USGS 10% Probability of Exceedance in 50 Year Seismic Hazard Contour Map (Figure 4-2) and the Zonation Map (Figure 4-3) in the seismic design of bridges.

The acceleration coefficients from these maps are used to determine seismic forces, which are applied in the horizontal direction only.

The current WSDOT design philosophy for dealing with seismically induced forces in bridge structures is to preserve life-safety through the prevention of collapse. The formation of plastic hinges in bridge columns, major changes in bridge geometry and even non-serviceability following the design level seismic event are all potential (and acceptable) results, but the structure must not collapse. WSDOT defines bridge collapse as follows:

> Bridge Collapse: Excessive movement or deformation of piers creating unacceptable bridge performance that may result in loss of life or serious injury. Unacceptable bridge performance includes, but is not limited to, partial or complete loss of span(s).

The WSDOT Geotechnical Design Manual, Section 6.1.1.1, further identifies the geologic hazards (liquefaction, lateral spread, downdrag, settlement) that may jeopardize highway bridges or structures during a design seismic event.

Earthquake restrainers shall be used across all expansion joints. The purpose of this is to tie the superstructure spans together, preventing the span from unseating and dropping due to insufficient existing seat length.

Designers shall use 5% damping on the AASHTO curves for the elastic spectral acceleration. The geotechnical engineer may develop special curves for the elastic spectral acceleration with higher damping if energy dissipation devices are installed on the bridge.

The passive resistance of the backfill soil behind the abutments shall not be included in seismic design.



Peak Bedrock Acceleration (%g) with
10% Probability of Exceedance in 50 Years
Acceleration Contour
State Hwy Routes
County Boundaries
State Border
Miles
0 12.5 25 50
N
Seismic Data: 2002, USGS
National Seismic Hazards
Mapping Project
BELLINGHAM
PORT ANGELES
EVERETT
SEATTLE
TACOMA
OLYMPIA
ABERDEEN
SPOKANE
PULLMAN
WENATCHEE
YAKIMA
PASCO
VANCOUVER
Strait of Juan de Fuca
Pacific Ocean
Columbia River

Figure 4-2



Seismic Zones and Peak Bedrock Acceleration (%g)
with 10% Probability of Exceedance in 50 Years
Acceleration Contour
State Hwy Routes
County Boundaries
State Border
Seismic Zones
Zone 1
Zone 2
Zone 3
Zone 4
Miles
0 12.5 25 50
N
Seismic Data: 2002, USGS
National Seismic Hazards
Mapping Project
Zone 1
Zone 2
Zone 3
Zone 4
SPOKANE
PULLMAN
PASCO
WENATCHEE
YAKIMA
BELLINGHAM
EVERETT
SEATTLE
TACOMA
OLYMPIA
ABERDEEN
PORT ANGELES
VANCOUVER
Strait of Juan de Fuca
Pacific Ocean
Columbia River

Figure 4-3

4.4 Elastic Dynamic Analysis (EDA)

4.4.1 Analytical Methods

The analysis methods and computer programs described in this section are based on a linear elastic multi-modal spectral analysis of the bridge and foundation as a structural system. This is defined as an Elastic Dynamic Analysis (EDA).

The EDA will likely produce stresses in some elements that exceed their elastic limit, indicating nonlinear behavior. For example, the stress-strain curve for concrete is nonlinear. Therefore, forces generated by a linear EDA could vary considerably from the actual force demands on the structure because of the non-linear behavior of some elements.

Other sources of nonlinear response are the effects of the surrounding soil, yielding of structural components, opening and closing of expansion joints, and nonlinear restrainer and abutment behavior. Forces and moments shall be combined using the complete quadratic combination (CQC) method.


For straight multi-span bridges, the computer program SEISAB may be used to determine design forces. For more complicated structures, the computer programs GTSTRUDL or SAP2000 should be used. The number of degrees-of-freedom and the number of modes considered in the EDA should capture at least 90 percent of the mass participation in the longitudinal and transverse directions.

For bridges made up of many multi-span frames, the structure can be modeled by considering a portion of the structure. See Figure 4-5. However, a minimum of two boundary frames, or one frame and an abutment beyond the frame under consideration, shall be used for multi-span frame modeling.

Seismic Zone	Single Span Bridges	Multi Span Bridges	
		Other Bridges	
		Regular	Irregular
1	*	*	*
2	*	MM	MM
3	*	MM	MM
4	*	MM	MM

* No seismic Analysis required

Minimum Analysis Requirements For Seismic Effects
Figure 4-4



Frame Modeling Techniques
Figure 4-5

4.4.2 Structural System or Global Analyses

Structural system or global dynamic analyses are required when it is necessary to capture the response of the entire bridge system. Bridges with irregular geometry, curved bridges, skewed bridges, bridges with multiple transverse expansion joints, and massive foundation elements or foundations supported by soft soil, may exhibit dynamic response characteristics that are not necessarily obvious and may not be captured in a simple subsystem analysis.

Two separate global dynamic analyses are normally required to capture the assumed nonlinear response of a bridge because the bridge has two distinct dynamic behaviors: tension and compression.

In the tension model, the superstructure joints including the abutments are released longitudinally with truss or tension elements connecting the joints to model the effects of the restrainers. In the compression model, all of the truss or tension elements are inactivated and the superstructure elements are locked longitudinally to capture structural response modes when the joints close or when the abutment is mobilized.

The geometry of the bridge will dictate if both a tension and compression analysis is required. Bridges with appreciable superstructure curvature may require additional models, which combine the characteristics identified for the tension and compression models.

Long multi-frame bridges shall be analyzed with multiple elastic models. A single multi-frame model may not be realistic since it cannot account for out-of-phase movement between individual frames and may not have enough nodes to capture all of the significant dynamic modes.

Each multi-frame model should be limited to five frames plus a boundary frame or an abutment on each end of the model. Adjacent models shall overlap each other by at least one useable frame. See Figure 4-5 for details.


The boundary frames provide some continuity between adjacent models but are considered redundant and their analytical results are ignored. A massless spring should be attached to the dead end of the boundary frames to represent the stiffness of the remaining structure. Engineering judgment should be exercised when interpreting the deformation results among various sets of frames since the boundary frame method does not fully account for continuity of the structure.

4.4.3 Stand-Alone or Local Analysis


A stand-alone or local analysis is used to model the strength and ductility capacity of an individual frame, bent, or column. A stand-alone analysis shall be performed in both the transverse and longitudinal directions.

A transverse stand-alone frame model assumes lumped masses at the columns. The lumped mass shall include the mass of the upper half of the column and shall be located at the intersection of the superstructure center of gravity and the column centerline. Hinged spans shall be modeled as rigid elements with half of the superstructure mass lumped at the adjacent columns. See Figure 4-6. The transverse analysis of end frames shall include a realistic estimate of the abutment stiffness consistent with the abutment's expected performance. The transverse displacement demand at each bent in a frame shall include the effects of rigid body rotation around the frame's center of rigidity.

Longitudinal stand-alone frame model shall include the short side of hinges with a concentrated dead load, and the entire long side of hinges supported by rollers at their ends, see Figure 4-6. Typically the abutment stiffness is ignored in the stand-alone longitudinal model. This provides conservative forces at the intermediate piers.



TRANSVERSE STAND-ALONE MODEL



LONGITUDINAL STAND-ALONE MODEL

Stand-Alone Analysis
Figure 4-6

4.4.4 Model Verification

The computer results shall be verified to ensure accuracy and correctness. The designer should use the following procedures for model verification:

- Using graphics, check the orientation of all nodes, members, supports, joint and member releases. Make sure that all the structural components and connections correctly model the actual structure.
- Check dead load reactions with hand calculations. The difference should be less than 5 percent.
- Calculate fundamental and subsequent modes by hand and compare results with computer results.
- Check the mode shapes and verify that structure movements are reasonable.
- Increase the number of modes to obtain 90 percent or more mass participation in each direction. SEISAB/GTSTRUDL/SAP2000 directly calculates the percentage of mass participation.
- Check the distribution of lateral forces. Are they consistent with column stiffness? Do small changes in stiffness of certain columns give predictable results?

4.4.5 Effective Cracked Moment of Inertia for Reinforced Concrete Columns

The effective cracked moment of inertia, I_{eff} , should be used when modeling reinforced concrete columns in the seismic analysis. I_{eff} shall be approximately 0.5 I_g , where I_g is the gross section moment of inertia of the concrete section.

More accurate I_{eff} may be determined from the empirical curves, depending on the axial load ratio and A_{st} / A_g ratio. See Figure 85, FHWA, *Seismic Retrofitting Manual for Highway Bridges*, pg. 200.

4.5 Base Isolation and Energy Dissipation Devices

A. Base Isolation

The decision to use base isolation devices must be approved by the Bridge Design Engineer.

For most concrete bridges with two to four spans, the period of vibration for the primary mode is approximately one second or shorter. This short period produces large seismic forces in the superstructure and substructure based on the AASHTO acceleration spectrum. Base isolation should be considered during the design phase if the seismic forces are too high and result in very large column dimensions, very large foundations or very deep foundations.

The use of base isolation may result in more economical foundations because base isolation lengthens the period which reduces the acceleration and lowers the seismic forces. This leads to designs with smaller members and less mass. Some types of base isolation devices dissipate seismic energy through internal friction or re-crystallization to further reduce the seismic forces.

Many types of proprietary isolation devices are available with various dynamic properties and characteristics. Each type may be applicable for only certain types of structures. The devices should be evaluated as to their effectiveness and design results obtained before being presented to the Bridge Design Engineer for approval of use. All devices are required to be tested under contract. Testing requirements shall be included in the Special Provisions.

The design criteria for base isolation devices should follow the AASHTO *Guide Specifications for Seismic Isolation Design* (1999).

B. Energy Dissipation Devices

Energy Dissipation Devices (EDD's) or dampers can shift the period of the structure and dissipate energy through additional damping. The AASHTO acceleration spectrum is based on 5% structural damping.

A higher viscous damping will lower the seismic forces to be resisted by the structure. An increase in the equivalent viscous damping reduces the spectral acceleration and displacements. See Figure 4.5.4a & b.

Damping ratios of 20% to 30% may be achieved using EDD's. The geotechnical engineer shall develop the acceleration spectrum for various potential damping ratios achieved by the EDD's used in the design.


Base isolation devices and dampers may be combined in bridge design to reduce the seismic forces and displacement.

C. Shock Transmission Units (STU's)

A shock transmission unit (STU) is a proprietary lock-up device which provides a compression and tension connection between the superstructure and substructure during an earthquake. STU's are frequently located at the tops of piers with existing sliding bearings. The STU's allow slow movement, such as thermal expansion and contraction without resistance, but lock up as a rigid compression or tension link to redistribute load when activated during a seismic event.


A structural analysis should be performed to determine the locations for the STU's and the forces in the STU and structural elements during an earthquake.

All STU's shall be tested under contract prior to installation and the testing requirements shall be included in the Special Provisions.



Acceleration response spectrum for medium-dense soil as a function of viscous damping (ground acceleration = 0.8g)

Figure 4-7a



Displacement response spectrum for medium-dense soil as a function of viscous damping (ground acceleration = 0.8g)

Figure 4-7b

4.6 Retrofit Guide

4.6.1 Vulnerability Study

A Seismic Vulnerability Study is required prior to beginning a seismic retrofit design project. For bridges in Seismic Categories B, C and D, the study shall identify collapse mechanisms and critical structural components that will be damaged by a design level earthquake (see Section 4.3). The seismic retrofit shall upgrade these structural components so they can resist an earthquake without structural collapse or loss of life.

Seismic retrofit alternatives shall be developed with input from the Bridge and Structures Office Seismic Specialist during the Seismic Vulnerability Study and shall be submitted to the Bridge Design Engineer for approval. The Bridge Design Engineer will consider approval of the seismic retrofit alternatives if a structure warrants a higher protection level because of its importance to the transportation system.

The Seismic Vulnerability Study begins with a complete review of the existing structural details and includes a structural analysis.

Some particular details of the structure, which should be reviewed, are:

- Expansion joints
- In-span hinges and AASHTO seat width requirements (See AASHTO Section 4.7.4.4)
- Adequacy of shear reinforcement, particularly size and spacing for short columns
- Confinement of column reinforcement to include anchorage into the concrete core
- Inadequate lap splices of column longitudinal reinforcement
- Welded end-to-end longitudinal reinforcement
- Transverse shear blocks at abutments or intermediate piers
- Narrow gaps between tall columns and adjacent structure

The purpose of the dynamic structural analysis is to determine the forces in the members. These forces and moments are the demand imposed on the members from the earthquake. Separately, the capacity of the members is calculated. For reinforced concrete columns, the computer program RECOL can be used to calculate the capacity. Next, the Demand/Capacity (D/C) ratio can be calculated. The decision on which members to seismically retrofit can be determined from the D/C ratios. All members with D/C greater than 1.0 are vulnerable and shall be strengthened so that the D/C is equal to or less than 1.0.

Earthquakes are multi-directional. Therefore, the designer should recognize that forces from the dynamic analysis could be reversed. To avoid incorrect results, the designer should watch for the reversal of signs of the seismic forces when superimposing these forces with member dead load.

Geotechnical information is provided by the Geotechnical Services Branch – Materials Laboratory and should contain information to calculate the foundation stiffness for dynamic structural analysis. L-pile Plus, the WSDOT "Design Manual for Foundation Stiffness under Seismic Loadings", and "S-Shaft" are used to calculate the foundation stiffness.

Sometimes, new test borings are needed to obtain up-to-date soil information. The potential for differential settlement and lateral spreading caused by soil liquefaction will also be addressed in the Geotechnical Report and should be reviewed and evaluated to identify foundation vulnerability. Stone columns or other soil liquefaction measures may be occasionally considered, but will require the approval of the Bridge Design Engineer prior to actual use in the design. Retrofitting foundations is very expensive. At this time, the seismic retrofit of foundations is not included in the WSDOT Seismic Retrofit Program.

The designer should notify the Bridge Design Engineer if the foundation components have D/C ratios greater than 1.0. This may have a significant impact on the decision to proceed with the seismic retrofit.

A Linear Analysis

A linear analysis is used to obtain the forces and moments acting on structural components in order to calculate D/C ratios. Seismic retrofit of the bridge will not be necessary if both the flexural and shear D/C ratios of all the structural components of a bridge are equal to or less than 1.0. Seismic retrofit of the bridge is required when the shear or flexural D/C ratio of one or more structural components is larger than 1.0. The computer program GTSTRUDL is commonly used to perform a linear static analysis to determine the demand forces, moments, and deflections of a bridge.

The R-factors are not used to reduce the demand values for the D/C analysis. The demand values from the linear analysis should be used directly in the D/C calculations.

For reinforced concrete columns, the designer should use 50 percent of the gross column moment of inertia in the linear analysis to represent the cracked section of the column. See Section 4.4.5 if a more refined stiffness is warranted.

Soil-structure interaction shall be used in this analysis by including the foundation stiffness matrix.

B. Pushover Analysis

A pushover analysis is used to study the sequence of the formation of plastic hinges and the global instability of a bridge. When one or more plastic hinges form, the seismic forces will be reduced and re-distributed resulting in fewer columns requiring retrofitting. If no plastic hinges result from the pushover analysis, then retrofit of the bridge may not be necessary or the number of columns that require retrofitting may be reduced.

A pushover analysis is a nonlinear static analysis to study the failure mechanism of a structure. Pushover analysis may be done by iterative hand calculations or by computer software. The latest version of GTStrudl and SAP2000 have the capability to perform pushover analyses. Pushover analyses provide a reasonable measure of the nonlinear earthquake behavior of frame-type structures without having to perform a nonlinear time-history dynamic analysis.

The lumped plasticity approach, which assumes that yielding or plastic hinges form only at the ends of a member, is used in pushover analyses. A force-moment interaction yield surface provides the plastic hinge element. Bridge columns designed and built in the 1960's or 1970's with poor structural confining details should be input as having "no confining reinforcement" in the pushover analysis.

The structure shall be "pushed" by force control or displacement control. The structure is pushed in a given pattern until a predefined displacement or force magnitude is reached. When the strength of a structural element degrades to the extent it can no longer support its gravity load, local collapse occurs. When sufficient hinges are formed causing the structure to become unstable, global collapse occurs. Sometimes, the analysis may terminate if a global collapse mechanism develops before the prescribed loading or displacement is reached.

The displacement demand applied during the pushover analysis in the longitudinal direction will be the maximum longitudinal displacement determined from the load cases multiplied by 1.5. For a review of the load cases, see AASHTO Section 3.10.8 Combination of Seismic Force Effects. Simultaneous transverse displacement is neglected. Thus, the pushover analysis is a two dimensional analysis and is conducted separately at each bent in either the longitudinal or transverse direction.

C. Nonlinear Time History Dynamic Analysis

The Nonlinear Time History Dynamic Analysis should only be used to study the vulnerability of major bridges, such as: suspension bridges, cable-stayed bridges, and long-span truss bridges.

At least three records of time history input files, representing deep earthquakes, shallow earthquakes, and long duration subduction earthquakes, should be used in the nonlinear analysis to capture the worst-case scenario.

A Nonlinear Time History Dynamic Analysis is a nonlinear analysis using a recorded earthquake, which is divided into many small time increments. The seismic responses in terms of forces and displacements will be output at each of the time steps. The maximum forces and displacement of the structural components are summarized at the end of the analysis.

4.6.2 Material Properties

A. Concrete

The concrete strength specified for the original design does not reflect the current strength because concrete continues to gain strength over time. A 50 percent increase in concrete compressive strength should be used to calculate the modulus of elasticity and to evaluate the shear and flexural capacity of the column.

For example, a 4500 psi compressive strength may be used to calculate the capacity of the structural component if the concrete compressive strength used in the original design was 3000 psi.

Concrete experiences cracking and deterioration caused by alkali-silica reaction, salt-water intrusion, freeze-thaw and other environmental forces. For concrete bridges experiencing such deterioration, it may be appropriate to take core samples to determine the compressive strength of the cores in order to establish the actual in-situ concrete strength and the cross section losses, if any, of the members.

B. Reinforcing Steel

The mild steel reinforcement used in the 1960's and 1970's was Grade 40 with a yield strength of 40 ksi. A 44 ksi yield strength should be used for member strength analysis and capacity calculations because the actual tested yield strength is assumed to be higher by 10 percent.

4.6.3 Earthquake Restrainers

Span unseating is a common problem for existing bridges when the seat width is not sufficient. As a retroft measure, longitudinal earthquake restrainers are used to tie bridge superstructure sections together at in-span hinges and at locations with expansion joints.

For the design of new bridges located in Zones 2, 3 or 4, longitudinal earthquake restrainers shall be used across all expansion joints.

Longitudinal restrainers are high strength bars with both ends anchored on both sides of the adjacent units. A minimum two-inch gap should be maintained at one end of the restrainer to allow for thermal movement. High strength cable may be utilized if the rod cannot fit because of complex geometry, such as: a curved bridge or the movable portion of a ferry terminal.

Bridge Special provision BSP022604.GB6 specifies the current material requirements for the high strength steel bars.

Transverse restrainers are provided to prevent shear failure of the longitudinal restrainers during an earthquake. If the longitudinal restrainers cross a concrete or steel diaphragm, the holes in the diaphragm should be at least one inch larger than the diameter of the high strength steel bars. The transverse restrainer shall limit the bridge transverse movement to less than 1/2 inch.

Earthquake restrainers shall be designed in accordance with the Caltrans method and checked with AASHTO LRFD Section 3.10.9.5. See the earthquake restrainer design example in the Appendix B.

4.6.4 Shear Blocks and Catcher Beams

A. Shear Blocks

Transverse shear blocks shall be installed at all bearings to resist the seismic lateral forces in the transverse direction.

Occasionally, steel pipes filled with grout are installed at the intermediate piers and the in-span hinges of box girder bridges. The pipes should cross the two adjacent diaphragms, and one end of the pipe should be anchored at one of the diaphragms. A two foot square access hatch at the bottom of the box shall be provided to allow for the installation and inspection of the pipes.

Mild reinforcement dowels are drilled and set into the existing concrete with epoxy bonding agent. The potential sliding surface should be roughened to provide additional shear resistance. A shear strength reduction factor of ϕ equal to 1.0 shall be used when designing shear blocks.

B. Catcher Beams

The purpose of installing catcher beams is to provide additional seat support to prevent loss of the span due to span unseating. Most of the highway bridges built in the 1960's and 1970's do not have adequate seat widths. Many of these bridges have roller bearings, which together with insufficient seat width may cause the span to "roll" off the seat and drop.

Catcher beams are subjected to large forces during an earthquake due to the superstructure dropping and sliding on the catch beam. The catcher beams should be designed to resist the following two loading cases: (1) a vertical load of twice the dead load reaction plus the maximum live load reaction, and (2) a vertical load equal to the dead load reaction together with a horizontal load equal to the dead load reaction times the acceleration coefficient.

Concrete catcher beams shall be designed to transmit loads directly to the foundation if possible. Catcher beams anchored to an existing vertical face of concrete with dowels or anchor bolts are not considered to be reliable because of the large vertical and horizontal forces to which they will be subjected in the event the superstructure falls off its bearing onto the catcher beam. Consideration should be given to post-tensioning the catcher beams when direct load transfer to the foundation is not feasible.

The design of concrete catcher beam should provide for access for inspection and drainage requirements.

Steel wide-flange beams may be used at L-abutments if the required seat extension is not more than two feet. Special attention is needed for attaching the steel catcher beams to the abutment to provide additional support for the overhanging portion of the catcher beam.

All the catcher beams should have a ½-inch gap between the bottom of the superstructure and the top of the catcher beam. Steel shim stacks shall be used to adjust the cross slope and vertical curve for steel catcher beam. Web stiffeners should not be used. Instead, the designer should increase the size of the steel section if necessary to gain a thicker web.

4.6.5 Post-tensioning Strengthening

External post-tensioning is another way to increase the flexural capacity of concrete beams, girders and columns. Post-tensioning can also be used for concrete seat extensions and to provide column confinement for large flat surfaces.

A. Superstructure

Post-tensioning retrofits of reinforced concrete girders or crossbeams shall be designed for the moment demand of the structural component. Post-tensioning tendons shall be installed in the new concrete on both sides of the existing member. The same number of tendons should be used on each side to avoid eccentrically applied moments. Sufficient reinforcing bar dowels shall be provided to ensure adequate shear transfer between the existing and new concrete sections. Post-tensioning ducts shall be filled with grout after the post-tensioning.

Post-retrofit analysis shall be performed to check load re-distributions and structural adequacy on the columns and the adjacent superstructure elements.

B. Columns

Post-tensioning may be used as an alternative to steel jacketing in some special cases. Post-tensioning tendons shall be anchored into the crossbeam or pier cap and the footing.

Structural components that are retrofitted with post-tensioning will perform elastically during earthquakes. Plastic hinges shall not be allowed because stresses beyond yielding may cause collapse of the structure.

The flexural capacity after the retrofit is:

$$\sigma_{flexural} = (P_{axial} + P_{post\text{-}tension})/A +/- M/S$$

where: $P_{axial} = P_{DL} +/- P_{EQ}$

The shear capacity after retrofit is:

$$V_{total} = V_c + V_s + 0.2\ (P_{axial} + P_{post\text{-}tension})$$

C. Concrete Seat Extension

Post-tensioning is an alternative for bearing seat extensions when direct load transfer to the foundation is not feasible.

The bearing load on the seat extension shall be resisted by shear resistance of the concrete, shear reinforcing bars, and if needed, post-tensioned high strength steel bars in core drilled holes. New concrete shall be placed before the high strength steel bars are post-tensioned. The jacking force of the high strength steel bars shall be no more than 90 percent of its yield stress. Holes shall be filled with epoxy bonding agent after post-tensioning.

The total shear capacity of the seat extension is:

$$V_{total} = V_c + V_s + 0.2\ P_{post\text{-}tension}$$

The surface of the existing crossbeam or pier cap should be roughened to increase shear friction between the existing beam and the new concrete extension.

D. Confining a Flat Face of a Column

Steel jackets with large flat surfaces may be used only if circular or oval shaped jackets are not feasible.

High-strength steel bars should be installed perpendicular to the flat surface and anchored on both sides of the column because the flat surface of the steel jacket cannot provide the required "hoop" stress confinement of a circular or oval shaped steel jacket. A stress level of 25 to 50 percent of the yield stress in the high strength steel bars should be sufficient for the retrofit.

4.6.6 Column jacketing

A. General

It has been observed after past earthquakes, as well as during experimental tests, that columns are vulnerable to brittle failure, which could be prevented by adding steel jackets to the outside of the columns.

Column jacketing permits ductile behavior of the bridge during an earthquake by providing additional shear capacity and confinement and allowing for the formation of plastic hinges at one or both ends of the column. Forces and moments from a linear structural analysis shall be used to design the column jackets. See design example in Appendix B.

There are several deficiencies in columns constructed before 1973, which make them vulnerable to brittle failure. Two of these are: a) inadequate length of lap splices of longitudinal reinforcement where laps of $20d_b$ to $35d_b$ were typically used; b) inadequate shear reinforcement and confining reinforcement which consisted of single hoops overlapped 6 to 9 inches at the ends. Not all the structures constructed prior to 1973 have seismically vulnerable details. Designers must review the "as-built" plans to identify the column vulnerabilities and retrofit needs.

The type of connections at both ends of the column must be identified before designing a column retrofit. The superstructure-to-pier connection could be a moment-resisting connection, or a one-directional hinge, or one- or two-directional bearing. The substructure-to-column connection could be moment-resisting connection or one-directional hinge. Column retrofits may not be necessary if shear capacity of the columns are sufficient for columns having moment-resistant connections.

The decision to retrofit columns is based on the Demand/Capacity (D/C) ratio. If the flexural or shear D/C ratio of a column is larger than 1.0, the column should be retrofitted. If the D/C ratio is less than 1.0, the column does not have to be retrofitted.

The column should be retrofitted if the column has inadequate lap-splices of longitudinal reinforcement at one or both ends. The minimum requirement for lap-splices is given in Equation (6-3) of FHWA *Seismic Retrofitting Manual for Highway Bridges* (1995).

B. Plastic Hinge

The plastic hinge region will experience large deformation during earthquake resulting in concrete cracking, spalling and longitudinal reinforcement yielding. Therefore, openings and drilling of holes into and through the steel column jackets are not allowed in plastic hinge regions.

The analytical plastic hinge length is the equivalent length of column over which the plastic curvature is assumed constant for determining the plastic rotation.

$$L_p = 0.08\ L + 0.15\ f_{ye}\ d_{bl} \geq 0.3\ f_{ye}\ d_{bl} \qquad \text{(English units: inches, ksi)}$$

where:

L_p = distance from critical section from the plastic hinge to the point of contraflexure after development of a plastic mechanism

L = distance from transverse or longitudinal seismic force in the superstructure to the plastic hinge at the bottom of the column

d_{bl} = diameter of longitudinal reinforcement

f_{ye} = design yield strength for longitudinal reinforcement in plastic hinge

The plastic hinge region, L_{pr} defines the portion of the column that requires additional lateral confinement. L_{pr} is defined by the larger of:

- 1.5 times the cross sectional dimension in the direction of bending
- The region of column where the moment exceeds 75% of the maximum plastic moment, $M_{p\ col}$

C. Aesthetics Issues and Environmental Concerns

The Principal Architect in the Bridge and Structures Office should be consulted regarding the aesthetic considerations and selection of column retrofit types to match both the existing structure and the environment, especially for retrofit projects in urban areas.

For bridges on the list of federal or state historical records, the designer should discuss the retrofit design ideas with the Region Design Project Engineer's Office and determine if coordination with the State Historical Preservation Office (SHPO) is required before beginning the final design.

Column retrofits in water or wetlands need to be coordinated with the HQ Bridge Construction Engineer, the Region Design Project Engineer's Office, and Region Environmental Office because of the long lead-time to acquire permits. The impact area, construction methods, and duration should be determined and sent to the Region Design Project Engineer's Office and Region Environmental Office when the Region begins work on the Design File.

If the construction of column retrofit has impact on a navigation channel, the US Coast Guard Liaison Engineer in the Bridge and Structures Office should be contacted for advice on how to proceed.

D. Column Retrofit Methods

1. Steel Jacketing

Steel jacketing has proven to be the most cost effective method for retrofitting circular and rectangular reinforced concrete columns in Washington State. The steel jacketing method should be the first choice unless it is not feasible.

Circular, oval and "D" shaped steel jackets may be utilized depending on the structural features and the shape of the cross section of the existing columns. Thick plates or high strength steel bars may be used on the large flat face of the "D" shape jacket to provide adequate confining pressure. Columns with variable cross section along its height or with flairs at the top should be analyzed to study the retrofit needs before designing the steel jacket. The steel jacket with either the variable cross section or uniform cross section steel jacket could be used in those cases in order to gain the most economical solution, if approved by the Principal Architect in the Bridge and Structures Office.

Partial height jacketing may be used to retrofit very tall columns or columns with hinge connections on the top.

The steel jacket should be designed according to FHWA *Seismic Retrofitting Manual for Highway Bridges* (1995) and CALTRANs *Seismic Design References* (1997).

The thickness of the steel jacket is calculated to meet the most severe requirements based on shear force, lap splices of longitudinal reinforcement and confining pressure in plastic hinge zone. The critical case for jacket design is when the lap-splices lose anchorage at the 0.001 radial strain level. The minimum thickness for a steel jacket is ¼-inch.

Typically, a space of two inches is provided at the bottom of the jacket and the top of the footing. A two-inch minimum and four inch maximum gap is provided at the top of the jacket and the crossbeam. The purpose of these gaps is to prevent the jacket from acting in compression and bearing against the supporting member at large drift angles.

Grout is pumped into the gap between the steel jacket and the existing column. The gap between a circular column and the steel jacket is ¾-inch minimum and 1-inch maximum. For square or rectangular columns, the ¾-inch minimum and 1-inch maximum gap should be maintained at the four corners. Spacers shall be installed to ensure the gap prior to pumping grout.

Pumping height should be limited to 20 feet for circular column and 8 feet for square or rectangular or split columns. The pumping holes should be located at the bottom of each of the pumping sections. Multiple pumping holes at each of the pumping sections should be installed for circular columns 6 feet in diameter or larger, or for square or rectangular columns in order to have evenly pumped heights of grout.

The grout, mortar, and epoxy bonding agent used for column seismic retrofit shall be as specified in the Bridge Special Provision BSP022606.GB6.

2. Fiber Reinforced Plastic (FRP) Wrapping

   FRP wrapping may be used for column retrofits in special cases to ease constructability problems. FRP has a high tensile strength and is lightweight. The design concept of FRP wrapping is the same as the steel jacketing. The required thickness of the composite materials depends on the fiber content and the strength of the fiber.

   Glass fiber wrapping is not suitable for column retrofit in Western Washington because of its strength reduction in high humidity or immersion application.

   Carbon FRP wrapping is a good alternative to a steel jacket for circular columns and square or rectangular columns with the maximum dimension of the cross section less than three feet. FRP wrapping should not be used if it will be abraded or rubbed.

3. Pedestals

   Most of the pedestals in Washington State are made of plain unreinforced concrete. Pedestal retrofit is required when: $W - D \leq 1'\text{-}\ 0"$, where W is the width of the pedestal and D is the diameter of the column. If the width of the pedestal is larger, it will not require retrofitting.

   A shallow steel jacket is the most cost effective method for pedestal retrofit. The steel jacket for a pedestal retrofit should be designed using the same column retrofit concepts.

The steel jacket should be installed directly on the top of the footing without any vertical gap, and be 2 inches higher than the top horizontal surface of the pedestal. The horizontal gap between the jacket and the pedestal should be filled with grout. The 2 inches vertical gap should be maintained between the top of the pedestal and the bottom of the column jacket.

4. Split Columns

Split columns were used on highway bridges in Washington State in the 1950's and 1960's to allow for thermal and shrinkage movements in long bridges made up of multiple frames. Generally, there are two split columns supported on a common footing with a 2-inch gap between the two split columns for thermal movement. Split columns may be split for the full length from the bottom of the superstructure to the top of footing or partially split at the top of the column and then joined together monolithically as a single large size column for the lower portion.

According to the research report *Retrofit of Split Bridge Columns* (2000), full height split columns may be retrofitted with two "D"-shaped steel jackets. For a partial height split column, the column shall be retrofitted with two "D"-shaped steel jackets on the split portion and a circular or oval shape steel jacket on the non-split portion. The research report recommends that a six-inch vertical gap be maintained between the bottom of the two "D"-shaped steel jackets and the top of the circular or oval shaped steel jacket for the retrofit of a partial height split column.

5. Underground "Silo"

A "Silo" should be used when the bottom of the steel jacket is buried more than 6 feet under the existing or final ground line, in order to leave room for column lateral deflection during an earthquake. PVC pipes or rigid polystyrene strips or panels may be used depending on the depth of the soil and the lateral deflection.

If a steel jacket is installed in the concrete or asphalt pavement and the buried depth is less than 6 feet, premolded joint filler shall be installed between the jacket and the pavement.

A "Silo" may also be used to change the overall structural performance during an earthquake by more evenly distributing the seismic forces between all the columns of a bridge.

6. Excavation Limit

Horizontal excavation limits should be 4 feet measured from: a) the face of the circular column; b) the corner of the square or rectangular column; c) the face of the circular pedestal; or d) the corner of the square or rectangular pedestal, depending on the scope of the retrofit work. These excavation limts shall be shown in the plans.

The need for excavation beyond these limts should be reviewed during the design phase of the PS&E development.

Deep excavations are very expensive. If the required excavation is 18 feet or deeper, the designers should meet with the geotechnical engineers in order to develop a more practical solution.

7. Drainage Pipe and Utilities

All of the existing drains and utilities (and all other attachments) that may have to be relocated, removed or reattached in the seismic retrofit project shall be shown in the Plans. Structural details should be provided if the drains and utilities require

modifications to existing structural components. Strengthening the opening area with a welded steel doubler plate will be required where drainage pipes exist inside the column and exit through the steel jacket. Openings in and through the steel jacket within the plastic hinge zone are not allowed (See BDM Section 4.6.6B.

4.6.7 Steel Structures

Steel bridges in California and Washington States were severely damaged during recent earthquakes and are just as susceptible to damage from earthquakes as concrete bridges.

A SeismicVulnerability Study is necessary to determine the retrofit needs and method for steel bridges. Particular attention should be paid to the connections, bearings, and structural stability.

The seismic retrofit of steel bridges may include istallation of longitudinal seismic restrainers, and retrofit of in-fill walls and pier walls, bearings, steel superstructure members, and movable bridges.

A. Longitudinal Seismic Restrainers

Longitudinal seismic restrainers shall be installed at all piers with expansion joints, at in-span hinges, and at drop-in span locations. The cross section of the restrainer should be determined in the Seismic Vulnerability Study.

The earthquake restrainers should be anchored to the bottom side of the concrete deck or the main member of the steel structure by bolts or welded anchor plates. The locations of the anchors should be carefully studied to ensure the effectiveness and constructability; particularly, for curved bridges, or bridges with large skews, or bridges with other complicated geometry.

B. In-Fill Walls and Pier Walls

In the past, some steel bridges were built with two exterior columns connected by an in-fill wall or full-length pier walls to minimize snagging of debris.

From past earthquakes and lab tests, these pier walls may be damaged by lateral shear or pull out of the longitudinal pier wall reinforcement from the footing if the lap splices of the longitudinal reinforcement are not sufficient.

It is difficult to provide the required confinement by using steel jackets to form plastic hinge because of the long length of the in-fill wall or pier wall. The seismic retrofit of these pier walls should be by strengthening to keep the stress of the pier wall in the elastic range.

The most effective retrofit strategy is to thicken the in-fill wall, which will provide additional shear resistance, and to ensure elastic behavior.

C. Bearings

Steel rocker bearings were commonly used in the 1960's and earlier for steel bridges. Shear resistance is provided by steel pintles, which could be sheared off causing the span to translate longitudinally and possibly drop. These rocker bearings should be replaced and retrofitted by installing catcher beams or transverse shear stops around the bearings. If elastomeric bearings are used as replacement bearings, the designer shall verify that the elastomeric bearing can accommodate the live load rotation of the superstructure.

Concrete cracking and spalling around the anchor bolts of rocker bearings has been observed following recent moderate earthquakes. In a strong earthquake, the bearings could lose their hold-down capability and lateral shear resistance resulting in the span dropping. FRP wrapping or steel collars should be installed to protect the anchorages of vulnerable bearings. The design of the FRP or steel collar should be similar to the steel jacket for columns.

D. Steel Superstructure Members

Diagonal members of trusses, cross frames, and secondary bottom lateral bracing members have buckled in past earthquakes. If the earthquake was stronger, the structure could be severely damaged.

All steel superstructure members should be studied to identify those with potential buckling failures. All vulnerable members should be replaced or retrofitted to prevent buckling.

E. Movable Bridges

Movable bridges, including lift bridges, have suffered severe damage and have encountered operational difficulties after moderate to strong earthquakes. Some observed damage to structural components included: railings, towers for lift spans, central locking mechanism, support frame for counterweight for bascule bridges, counterweights jumping the tracks for lift span bridges, and displacement or settlement for swing-span bridges.

The effective retrofit for these movable bridges is usually strengthening or replacement. The impact of any proposed retrofit on weight changes and on the mechanical/electrical system should be carefully studied. The proposed retrofit should be reviewed and approved by the Bridge Preservation Office's Mechanical and Electrical Engineers.

4.6.8 Base Isolation and Energy Dissipation Devices

A. Base Isolation

Column jacketing is an efficient and economical way to retrofit substructures. However, some bridges were built on wetlands or areas containing hazardous materials. It will be very expensive to excavate the hazardous materials and dispose of it. The construction access in wetlands has significant impact on the environment and will be very expensive to mitigate. It is very time consuming to obtain environmental permits. In these situations, base isolation may be a viable and economical retrofit option.

A feasibility study and analysis are required to determine the type and size of the isolation devices. Dampers and STU's may also be used in conjunction with base isolation if an analysis shows some of the structural components are still vulnerable when only isolation devices are used.

Isolation devices should be able to resist traffic braking and wind loads without excessive deflection. These isolation devices must also allow thermal expansion to occur in the superstructure without overstressing the substructure, and shall be stable during an earthquake. The devices should maintenance-free.

Larger safety factors should be used in isolation design. All the devices should be tested under contract prior to installation. The design criteria for base isolation devices should follow the AASHTO *Guide Specifications for Seismic Isolation Design* (1999).

Liquefiable soil layers underneath footings or pile foundations act as a natural base isolation device because the shear waves cannot transmit through the liquefied soil layer. A geotechnical engineer will have to develop a special acceleration spectrum based on the liquefiable soil layer.

B. Energy Dissipation Devices and STU's

Energy Dissipation Devices (EDD's) and STU's can be used to reduce the seismic forces and displacement. A structural analysis should be performed to determine the location and sizes required for dampers and STU devices. All dampers and STU devices should be tested under contract prior to installation

4.99 Bibliography

AASHTO LRFD Bridge Design Specifications, 2nd Edition, 1998 and Successive Interims.

Guide Specifications for Seismic Isolation Design, AASHTO, 1999, 71 pp.

Seismic Design Criteria, , Caltrans, Version 1.3, February 2004.

Seismic Design References, Caltrans , March 1997.

Seismic Design of Bridges, Priestley, M.J.N., F. Seibel, and M. Calvi, John Wiley & Sons, New York, 1996, 696 pp.

National Highway Institute (NHI) Course No. 13063 *Seismic Bridge Design Applications*, April 1996.

Seismic Bridge Design Applications Part 1, Publication No. FHWA-SA-97-017, April 1996

Seismic Bridge Design Applications Part 2, Publication No. FHWA-SA-97-017, July 1996

Seismic Design of Bridges, Design Example No. 1 through No. 7, Publication No.'s FHWA-SA-97-006 through -012, October 1996

FHWA *Seismic Retrofitting Manual for Highway Bridges*, Publication No. FHWA-RD-94-052, May 1995

Retrofit of Split Bridge Columns. McLean, David I. et al. Washington State Dept. of Transportation, WA-RD 482.1, October 2001.

Earthquake Probability Example

The probability, P, that an earthquake can occur within a certain time frame, t_L, can be estimated using Poisson's distribution:

$$P = 1 - e^{-\lambda_a t_L}$$

For example, assume the average return time or recurrence of an earthquake is 100 years, estimate the probability that it will occur in the next 100 years.

Let T_a = mean return period in years = $1/N_a$

where: $N_a = \lambda_a$ = average annual probability that the peak ground acceleration will exceed a certain acceleration, "a".

In a typical design situation, the designer is interested in the probability that such a peak exceeds "a" during the life of the structure, t_L.

For the earthquake recurrence example, $T_a = 1/N_a = 1/100 = 0.01$ and $t_L = 100$ years:

$$P = 1 - e^{-\lambda_a t_L} = 1 - e^{-0.01(100)} = 0.63 \text{ or } \underline{63\%}$$

Using the same earthquake, determine the chance that the same earthquake will occur within the next 20 years:

$$P = 1 - e^{-\lambda_a t_L} = 1 - e^{-0.01(20)} = 0.18 \text{ or } \underline{18\%}$$

An earthquake with a peak ground acceleration coefficient map (see Figures 4.3.1 and 4.3.2) with a 10% probability of exceedance in 50 years corresponds to a return period of 475 years.

Proof: $T_a = 475$ years, $N_a = \lambda_a = 1/475$ and $t_L = 50$ years


$$P = 1 - e^{-\lambda_a t_L} = 1 - e^{-(1/475)(50)} = 0.0999 \text{ or } \underline{10\%} \text{ Checks}$$

Earthquake Probability - Poisson Model
Figure 4-A-1

Earthquake Restrainer Example

Bridge Type: Multiple Simple Spans

This Design Example is based on CALTRAN's *Seismic Design References* (1997)




Seismic Data: Acceleration Coeficient, A = 0.3g; Soil Type II, S = 1.2
Dead Load of the Span = 540 kips

Bearings: Roller Bearings with no longitudinal restraint. Shear blocks to be added to provide transverse restraint.

Restrainers: 20 foot long High-Strength steel rods (ASTM F1554 Grade 105)
F_y = 105 ksi and E = 29,000 ksi
2 inch gap at end of High-Strength rod

Design Examples of Seismic Retrofits
Figure 4-A-2



Calculate Available Seat Width: (22"/2) – 4" –1" = 6 inches

Determine Maximum Restrainer Deflection (D_r):

Let D_y = max. elastic deformation of rod when restrainer is stressed to F_y

$D_y = F_yL/E$ = (105 ksi)(20ft)(12in/ft)/(29,000 ksi) = 0.9 inches

D_{gap} 2.0

D_r = Resultant Longitudinal Displacement = $D_y + D_{gap}$ = 2.9 inches < 6 inches

Try four 1 inch diameter rods: $A_g = 4(0.785in^2) = 3.14\ in^2$ Use A_g of plain rod for stiffness/ elongation calculations and use tensile area, A_t, for stress check.

(Note: $A_g = A_t$ if a high strength rod is threaded for its full length):

Calculate the stiffness, K_t ,provided by the restrainer rods:

$$K_t = \frac{F_y(A_g)}{D_r} = \frac{105(3.14)}{2.9} = 114 kips/inch$$

Calculate the period, T:

$$T = 2p\sqrt{\frac{W}{gK_t}} = 0.32\sqrt{\frac{540}{114}} = 0.70\,\text{sec}\,onds$$

where: T = period in seconds
W = Dead Load of the span = 540 kips
g = 32.2 ft/sec^2 x 12in/ft = 386 inches/sec^2
K_t = 114 kips/inch

Design Examples of Seismic Retrofits ***(Continued)***

Figure 4-A-2

Calculate the Elastic Seismic Response Coefficient, C_s, for Multimodal Analysis:

$$Cs = \frac{1.2AS}{T^{2/3}} = \frac{1.2(0.30)(1.2)}{0.70^{0.67}} = 0.55g$$

when A ≥ 0.30g, Cs need not exceed 2.0A

Therefore, C_S = 0.55g < 0.6g, okay

Calculate the seismic force and tensile stress, f_t, to be resisted by the restrainers:

Use tensile area: A_t = 0.606 in^2 per restrainer rod

Seismic Force = C_sW = 0.55(540) = 297 kips

$$f_t = \frac{C_sW}{A_t} = \frac{297}{4(0.606)} = 122.5ksi > 105ksi$$

No Good for Stress

Calculate the elastic elongation in the four 1 inch diameter retrainer rods, D_t:

$$D_t = \frac{C_sW}{K_t} = \frac{297}{114} = 2.6inches < D_r = 2.9inches$$

okay

The elastic elongation of the restrainers is less than the resultant displacement. However, the tensile stress at the threaded ends of the rod exceeds fy. Therefore, it is necessary to increase the number of restrainers or increase the diameter of the restrainers in order to reduce the elastic elongation.

Try four 1-1/8 inch diameter x 8UN threaded rods: $A_g = 4(0.994\ in^2) = 3.98\ in^2$

$$K_t = \frac{F_y(A_g)}{D_r} = \frac{105(3.98)}{2.9} = 144kips/inch$$

$$T = 2p\sqrt{\frac{W}{gK_t}} = 0.32\sqrt{\frac{540}{144}} = 0.62\,\text{seconds}$$

$$Cs = \frac{1.2AS}{T^{2/3}} = \frac{1.2(0.30)(1.2)}{0.62^{0.67}} = 0.60g = 0.6g$$

$$D_t = \frac{C_sW}{K_t} = \frac{0.6(540)}{144} = 2.25inches < D_r = 2.9inches$$

okay for Elongation

$$f_t = \frac{C_sW}{A_t} = \frac{324}{4(0.790)} = 102.5ksi < 105ksi$$

okay for Stress

Use four 1-1/8 inch diameter x 20 ft long ASTM F1554 Grade 105 High-Strength Rods with Fy = 105 ksi. Specify a Charpy V-Notch (CVN) of 25 ft-lbs @ 40°F, or Supplemental Requirement S5 (15 ft-lbs @ -40°F.***BRIDGE DESIGN MANUAL***

Design Examples of Seismic Retrofits ***(Continued)***
Figure 4-A-2

Circular Column Steel Jacket Retrofit Example

Lateral tie reinforcement of #4 bars at 12” centers is inadequate confinement for the longitudinal column reinforcement.

Concrete core is adequate to resist seismic transverse shear force

The column is 3 ft. in diameter. Assume clearance is 1” between column and steel jacket.

Determine thickness of steel jacket.

Using the FHWA Guidelines from *Seismic Retrofitting Manual for Highway Bridges*, (1995):

$$t > \frac{f_{cc} D}{58}$$

where: t = thickness of steel jacket in inches
f_{cc} = confining concrete core pressure in ksi = 0.300 ksi
D = 36” + 2” = 38”

$$\therefore t = \frac{(0.3)(38)}{58} = 0.20'' > 0.25'' \text{ min}$$

Use 1/4” thick steel jacket with Fy = 36 ksi

Lateral tie reinforcement of #4 bars at 12” centers is inadequate confinement for the longitudinal column reinforcement.

Concrete core is adequate to resist seismic transverse shear force

The column is 5 ft. in diameter. Assume clearance is 1” between column and steel jacket.

Determine thickness of steel jacket.

Using the FHWA Guidelines from *Seismic Retrofitting Manual for Highway Bridges*, (1995):

$$t > \frac{f_{cc} D}{58}$$

where: t = thickness of steel jacket in inches
f_{cc} = confining concrete core pressure in ksi = 0.300 ksi
D = 60” + 2” = 62”

$$\therefore t = \frac{(0.3)(62)}{58} = 0.32'' > 0.25'' \text{ min}$$

Use 3/8” thick steel jacket with Fy = 36 ksi

A seismic analysis shows the 4 ft. diameter column is required to undergo a plastic drift angle of 0.045 radians.

The existing lateral confining reinforcement is inadequate.

Longitudinal bars are #11 Grade 40 reinforcement and ρ_l = 0.04 or 4 %.

Design Examples of Seismic Retrofits ***(Continued)***
Figure 4-A-2

The ratio $\frac{P}{f'_{ca} A_g} = 0.2$

where: P = resultant axial force in kips
$f'_{ca} = 1.5(f'_c) \approx$ 5 ksi for an original concrete design strength of 3,000psi
A_g = gross concrete column area in in^2

Determine $\frac{t_j}{D} \geq 0.01$ from Figure 8.5(a) *Seismic Design of Bridges*, Priestley, Seibel, and Calvi (1996), p. 592

$$\therefore t_j = 0.01(48 + 2) = 0.50"$$

Use ½" thick steel jacket with Fy = 36 ksi

Lateral tie reinforcement of #4 bars at 12" centers is inadequate confinement for the longitudinal column reinforcement.

Concrete core is adequate to resist seismic transverse shear force

The size of the rectangular column is 2' x 6'

Check size of ellipse to provide 1" clearance between column and steel jacket.

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$$


After several tries, use an elliptical shape such that:

Long axis = 7'-2" such that $a = 3'-7"$ and

Short axis = 4'-2" $b = 2'-1"$

Design Examples of Seismic Retrofits ***(Continued)***
Figure 4-A-2

Find equivalent diameter, D = 2a = 86”



Using the FHWA Guidelines from *Seismic Retrofitting Manual for Highway Bridges*, (1995):

$$t > \frac{f_{cc} D}{58}$$

$$\therefore t = \frac{(0.3)(86")}{58} = 0.44"$$

Use ½” thick steel jacket with Fy = 36 ksi

Lateral tie reinforcement of #4 bars at 12” centers is inadequate confinement for the longitudinal column reinforcement.

Concrete core is adequate to resist seismic transverse shear force

The size of the rectangular column is 4’ x 6’

Check size of ellipse to provide 1” clearance between column and steel jacket.

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$$


After several tries, use an elliptical shape such that:

Long axis = 8’-2” such that $a = 4' - 1"$ and

Short axis = 6’-2” such that $b = 3' - 1"$

Find equivalent diameter, D = 2a = 98”

Design Examples of Seismic Retrofits ***(Continued)***
Figure 4-A-2



Using the FHWA Guidelines from *Seismic Retrofitting Manual for Highway Bridges*, (1995):


$$\therefore t = \frac{(0.3)(98")}{58} = 0.51"$$


Use ½" thick steel jacket with Fy = 36 ksi

Design Examples of Seismic Retrofits ***(Continued)***
Figure 4-A-2

RECOMMENDED END HOOKS
All Grades
D = Finished bend diameter


Bar Size	D	180° HOOKS		90° HOOKS
		A or G	J	A or G
#3	2¼	5	3	6
#4	3	6	4	8
#5	3¾	7	5	10
#6	4½	8	6	1-0
#7	5¼	10	7	1-2
#8	6	11	8	1-4
#9	9½	1-3	11¾	1-7
#10	10¾	1-5	1-1¼	1-10
#11	12	1-7	1-2¾	2-0
#14	18¼	2-3	1-9¾	2-7
#18	24	3-0	2-4½	3-5





STIRRUP AND TIE HOOK DIMENSIONS
All Grades

Bar Size	D (in.)	135° HOOKS	
		Hook A or G	H Approx.
#3	1½	4¼	3
#4	2	4½	3
#5	2½	5½	3¾
#6	4½	8	4½
#7	5¼	9	5¼
#8	6	10½	6




135° SEISMIC STIRRUP/TIE
HOOK DIMENSIONS
All Grades

Bar Size	D (in.)	135° HOOKS	
		Hook A or G	H Approx.
#3	1½	4¼	3
#4	2	4½	3
#5	2½	5½	3¾
#6	4½	8	4½
#7	5¼	9	5¼
#8	6	10½	6

Standard Hooks
Figure 5-A-1

PREFERED MINIMUM CLEARANCE AND SPACING
FOR BEAMS AND COLUMNS.
(DISTANCES IN INCHES)

Bar Size	A	B	C	D
#4	3¼	4	-	-
5	3½	4¼	-	-
6	3¾	4½	-	-
7	4	4¾	-	-
8	4¼	5	4½	5½
9	4½	5¼	4¾	6
10	4¾	5½	5	6¼
11	5	6	5⅛	6½
14	5½	7	5½	7¼
18	6	8½	6¾	9



Minimum Reinforcement Clearance and Spacing for Beams and Columns
Figure 5-A-2

Bar Size	Weight (lbs/ft)	Nominal Diameter (in)	Outside Diameter (in)	Area (in^2)	Max. Bar Length (Normal Length for Barlist) (ft)
#3	0.376	0.375	0.42	0.11	40 (30)
#4	0.668	0.500	0.56	0.20	40 (40)
#5	1.043	0.625	0.7	0.31	60 (40)
#6	1.502	0.750	0.83	0.44	60 (60)
#7	2.044	0.875	0.96	0.60	60 (60)
#8	2.670	1.000	1.1	0.79	72 (60)
#9	3.400	1.128	1.24	1.00	72 (60)
#10	4.303	1.270	1.4	1.27	72 (60)
#11	5.313	1.410	1.55	1.56	90 (60)
#14	7.65	1.693	1.86	2.25	90 (60)
#18	13.60	2.257	2.48	4.00	90 (60)

Reinforcing Bar Properties
Table 5-A-3

Tension Development Length of Uncoated Deformed Bars								
Bar Size	f'_c = 3000 psi		f'_c = 4000 psi		f'_c = 5000 psi		f'_c = 6000 psi	
	Top Bars	Others	Top Bars	Others	Top Bars	Others	Top Bars	Others
3	1’-5”	1’-0”	1’-5”	1’-0”	1’-5”	1’-0”	1’-5”	1’-0”
4	1’-5”	1’-0”	1’-5”	1’-0”	1’-5”	1’-0”	1’-5”	1’-0”
5	1’-9”	1’-3”	1’-9”	1’-3”	1’-9”	1’-3”	1’-9”	1’-3”
6	2’-3”	1’-8”	2’-2”	1’-6”	2’-2”	1’-6”	2’-2”	1’-6”
7	3’-1”	2’-3”	2’-8”	1’-11”	2’-6”	1’-9”	2’-6”	1’-9”
8	4’-1”	2’-11”	3’-6”	2’-6”	3’-2”	2’-3”	2’-11”	2’-1”
9	5’-2”	3’-8”	4’-6”	3’-2”	4’-0”	2’-10”	3’-8”	2’-7”
10	6’-6”	4’-8”	5’-8”	4’-1”	5’-1”	3’-8”	4’-8”	3’-4”
11	8’-0”	5’-9”	6’-11”	5’-0”	6’-3”	4’-5”	5’-8”	4’-1”
14	10’-11”	7’-10”	9’-5”	6’-9”	8’-5”	6’-1”	7’-9”	5’-6”
18	14’-1”	10’-1”	12’-3”	8’-9”	10’-11”	7’-10”	10’-0”	7’-2”
Tension Development Length of Epoxy Coated Deformed Bars								
Bar Size	f'_c = 3000 psi		f'_c = 4000 psi		f'_c = 5000 psi		f'_c = 6000 psi	
	Top Bars	Others	Top Bars	Others	Top Bars	Others	Top Bars	Others
3	1’-9”	1’-6”	1’-9”	1’-6”	1’-9”	1’-6”	1’-9”	1’-6”
4	1’-9”	1’-6”	1’-9”	1’-6”	1’-9”	1’-6”	1’-9”	1’-6”
5	2’-2”	1’-11”	2’-2”	1’-11”	2’-2”	1’-11”	2’-2”	1’-11”
6	2’-9”	2’-5”	2’-7”	2’-3”	2’-7”	2’-3”	2’-7”	2’-3”
7	3’-9”	3’-4”	3’-3”	2’-11”	3’-0”	2’-8”	3’-0”	2’-8”
8	4’-11”	4’-4”	4’-3”	3’-9”	3’-10”	3’-5”	3’-6”	3’-1”
9	6’-3”	5’-6”	5’-5”	4’-9”	4’-10”	4’-3”	4’-5”	3’-11”
10	7’-11”	7’-0”	6’-10”	6’-1”	6’-2”	5’-5”	5’-7”	4’-11”
11	9’-9”	8’-7”	8’-5”	7’-5”	7’-6”	6’-8”	6’-11”	6’-1”
14	13’-3”	11’-8”	11’-6”	10’-1”	10’-3”	9’-1”	9’-4”	8’-3”
18	17’-1”	15’-1”	14’-10”	13’-1”	13’-3”	11’-8”	12’-1”	10’-8”

Top bars are so placed that more than 12” of concrete is cast below the reinforcement.
Modifications factor for spacing >=6” and side cover>=3” = 0.8.
Modification factor for reinforcements enclosed in spirals = 0.75.
Minimum development length = 12”.

Tension Development Length of Deformed Bars
Table 5-A-4

Compression Development Length and Minimum Lap splice of Uncoated Deformed Bars

Bar Size	Compression Development Length					Min. Lap Splice f'c > 3.0 ksi
	Straight Bars				Hooked Bars	
	f'c = 3 ksi	f'c = 4 ksi	f'c = 5 ksi	f'c = 6 ksi		
3	1'-0"	1'-0"	1'-0"	1'-0"	6"	2'-0"
4	1'-0"	1'-0"	1'-0"	1'-0"	7"	2'-0"
5	1'-2"	1'-0"	1'-0"	1'-0"	9"	2'-0"
6	1'-5"	1'-3"	1'-2"	1'-2"	10"	2'-0"
7	1'-8"	1'-5"	1'-4"	1'-4"	1'-0"	2'-3"
8	1'-10"	1'-7"	1'-6"	1'-6"	1'-2"	2'-6"
9	2'-1"	1'-10"	1'-9"	1'-9"	1'-3"	2'-10"
10	2'-4"	2'-1"	1'-11"	1'-11"	1'-5"	3'-3"
11	2'-7"	2'-3"	2'-2"	2'-2"	1'-7"	3'-7"
14	3'-1"	2'-9"	2'-7"	2'-7"	2'-10	4'-3"
18	4'-2"	3'-7"	3'-5"	3'-5"	3'-7"	5'-8"

Compression Development Length and Minimum Lap splice of Epoxy Coated Deformed Bars

Bar Size	Compression Development Length					Min. Lap Splice f'c > 3.0 ksi
	Straight Bars				Hooked Bars	
	f'c = 3 ksi	f'c = 4 ksi	f'c = 5 ksi	f'c = 6 ksi		
3	1'-0"	1'-0"	1'-0"	1'-0"	6"	2'-0"
4	1'-0"	1'-0"	1'-0"	1'-0"	7"	2'-0"
5	1'-2"	1'-0"	1'-0"	1'-0"	9"	2'-0"
6	1'-5"	1'-3"	1'-2"	1'-2"	10"	2'-0"
7	1'-8"	1'-5"	1'-4"	1'-4"	1'-0"	2'-3"
8	1'-10"	1'-7"	1'-6"	1'-6"	1'-2"	2'-6"
9	2'-1"	1'-10"	1'-9"	1'-9"	1'-3"	2'-10"
10	2'-4"	2'-1"	1'-11"	1'-11"	1'-5"	3'-3"
11	2'-7"	2'-3"	2'-2"	2'-2"	1'-7"	3'-7"
14	3'-1"	2'-9"	2'-7"	2'-7"	2'-10	4'-3"
18	4'-2"	3'-7"	3'-5"	3'-5"	3'-7"	5'-8"

Notes:

1. Where excess bar area is provided, the development length may be reduced by ratio of required area to provided area.
2. When splicing smaller bars to larger bars, the lap splice shall be the larger of the minimum compression lap splice or development length of the larger bar in compression.

Compression Development Length and Minimum Lap Splice of Grade 60 Bars
Table 5-A-5

Bar Size	f'_c = 3000 psi		f'_c = 4000 psi		f'_c = 5000 psi		f'_c = 6000 psi	
	Side Cover < 2½" Cover on Tail < 2"	Side Cover >= 2½" Cover on Tail >= 2"	Side Cover < 2½" Cover on Tail < 2"	Side Cover >= 2½" Cover on Tail >= 2"	Side Cover < 2½" Cover on Tail < 2"	Side Cover >= 2½" Cover on Tail >= 2"	Side Cover < 2½" Cover on Tail < 2"	Side Cover >= 2½" Cover on Tail >= 2"
3	0'-9"	0'-6"	0'-8"	0'-6"	0'-7"	0'-6"	0'-6"	0'-6"
4	0'-11"	0'-8"	0'-10"	0'-7"	0'-9"	0'-7"	0'-8"*	0'-7"
5	1'-2"	0'-10"	1'-0"	0'-9"	0'-11"	0'-8"	0'-10"	0'-7"
6	1'-5"	1'-0"	1'-3"	0'-10"	1'-1"	0'-9"	1'-0"	0'-8"
7	1'-8"	1'-2"	1'-5"	1'-0"	1'-3"	0'-11"	1'-2"	0'-10"
8	1'-10"	1'-4"	1'-7"	1'-2"	1'-5"	1'-0"	1'-4"	0'-11"
9	2'-1"	1'-6"	1'-10"	1'-3"	1'-8"	1'-2"	1'-6"	1'-1"
10	2'-4"	1'-8"	2'-1"	1'-5"	1'-10"	1'-3"	1'-8"	1'-2"
11	2'-7"	1'-10"	2'-3"	1'-7"	2'-0"	1'-5"	1'-10"	1'-4"
14	3'-1"	3'-1"	2'-9"	2'-9"	2'-5"	2'-5"	2'-3"	2'-3"
18	4'-2"	4'-2"	3'-7"	3'-7"	3'-3"	3'-3"	2'-11"	2'-11"

Modification factor for Epoxy coated reinforcement = 1.2.

Tension Development Length of 90º and 180º Standard Hooks

Table 5-A-6

Tension Lap Splice Lengths of Grade 60 Uncoated Bars ~ Class B

Bar Size	f'_c = 3000 psi		f'_c = 4000 psi		f'_c = 5000 psi		f'_c = 6000 psi	
	Top Bars	Others	Top Bars	Others	Top Bars	Others	Top Bars	Others
3	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"
4	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"
5	2'-4"	2'-0"	2'-4"	2'-0"	2'-4"	2'-0"	2'-4"	2'-0"
6	2'-11"	2'-1"	2'-9"	2'-0"	2'-9"	2'-0"	2'-9"	2'-0"
7	4'-0"	2'-11"	3'-6"	2'-6"	3'-3"	2'-4"	3'-3"	2'-4"
8	5'-3"	3'-9"	4'-7"	3'-3"	4'-11"	2'-11"	3'-9"	2'-8"
9	6'-8"	4'-9"	5'-9"	4'-2"	5'-2"	3'-9"	4'-9"	3'-5"
10	8'-6"	6'-1"	7'-4"	5'-3"	6'-7"	4'-8"	6'-0"	4'-4"
11	10'-5"	7'-5"	9'-0"	6'-5"	8'-1"	5'-9"	7'-4"	5'-3"
14	Lap Splices		Lap Splices		Lap Splices		Lap Splices	
18	Not Allowed		Not Allowed		Not Allowed		Not Allowed	

Tension Lap Splice Lengths of Grade 60 Epoxy Coated Bars ~ Class B

Bar Size	f'_c = 3000 psi		f'_c = 4000 psi		f'_c = 5000 psi		f'_c = 6000 psi	
	Top Bars	Others	Top Bars	Others	Top Bars	Others	Top Bars	Others
3	2'-3"	2'-0"	2'-3"	2'-0"	2'-3"	2'-0"	2'-3"	2'-0"
4	2'-3"	2'-0"	2'-3"	2'-0"	2'-3"	2'-0"	2'-3"	2'-0"
5	2'-10"	2'-6"	2'-10"	2'-6"	2'-10"	2'-6"	2'-10"	2'-6"
6	3'-7"	3'-2"	3'-4"	3'-0"	3'-4"	3'-0"	3'-4"	3'-0"
7	4'-11"	4'-4"	4'-3"	3'-9"	3'-11"	3'-5"	3'-11"	3'-5"
8	6'-5"	5'-8"	5'-7"	4'-11"	5'-0"	4'-5"	4'-6"	4'-0"
9	8'-1"	7'-2"	7'-0"	6'-2"	6'-3"	5'-7"	5'-9"	5'-1"
10	10'3"	9'-1"	8'-11"	7'-10"	8'-0"	7'-0"	7'-3"	6'-5"
11	12'-8"	11'-2"	10'-11"	9'-8"	9'-9"	8'-0"	8'-11"	7'-11"
14	Lap Splices		Lap Splices		Lap Splices		Lap Splices	
18	Not Allowed		Not Allowed		Not Allowed		Not Allowed	

Top bars are so placed that more than 12" of concrete is cast below the reinforcement.

Modification factor for spacing >=6" and side cover>=3" = 0.8.

Modification factor for reinforcements enclosed in spirals = 0.75.

Minimum development length = 12".

Definition of splice classes:
- Class A: Low stressed bars ~ 75% or less are spliced
- Class B: Low stressed bars ~ more than 75% are spliced
  High stressed bars ~ 50% or less are spliced
- Class C: High stressed bars ~ more than 50% are spliced

Class B lap splice is the preferred and most commonly used by Bridge Office.

Modification factor for Class A = 0.77

Modification factor for Class C = 1.31

Modification factor for 3-bar bundle = 1.2

Tension Lap Splice Lengths of Grade 60 Uncoated Bars ~ Class B

Table 5-A-7

Uncoated Prestressing Strands Properties and Development Length

Strand Diameter (in)	Weight (lbs/ft)	Nominal Diameter (in)	Area (in^2)	Transfer length (in)	Develop. Length k = 1.0 (ft)	Develop. Length k = 1.6 (ft)
3/8	0.29	0.375	0.085	22.5	5.05	8.09
7/16	0.40	0.438	0.115	26.3	5.90	9.43
½	0.52	0.500	0.153	30.0	6.74	10.78
½ S	0.53	0.500	0.167	30.0	6.74	10.78
9/16	0.65	0.563	0.192	33.8	7.58	12.13
0.60	0.74	0.600	0.217	36.0	8.09	12.94

Epoxy Coated Prestressing Strands Properties and Development Length

Strand Diameter (in)	Weight (lbs/ft)	Nominal Diameter (in)	Area (in^2)	Transfer length (in)	Develop. Length k = 1.0 (ft)	Develop. Length k = 1.6 (ft)
3/8	0.31	0.415	0.085	24.9	5.59	8.95
7/16	0.42	0.478	0.115	28.7	6.44	10.31
½	0.54	0.540	0.153	32.4	7.28	11.64
0.60	0.64	0.648	0.217	38.9	8.73	13.97

Prestressing Strand Properties and Development Length

Table 5-A-8

ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$
0.0010	59.3	0.0053	298.1	0.0097	515.4	0.0141	705.2
0.0011	65.1	0.0054	303.4	0.0098	520.0	0.0142	709.2
0.0012	71.0	0.0055	308.6	0.0099	524.6	0.0143	713.2
0.0013	76.8	0.0056	313.8	0.0100	529.2	0.0144	717.2
0.0014	82.6	0.0057	319.0	0.0101	533.8	0.0145	721.1
0.0015	88.4	0.0058	324.2	0.0102	538.3	0.0146	725.1
0.0016	94.2	0.0059	329.4	0.0103	542.9	0.0147	729.0
0.0017	100.0	0.0060	334.5	0.0104	547.4	0.0148	732.9
0.0018	105.7	0.0061	339.7	0.0105	551.9	0.0149	736.8
0.0019	111.4	0.0062	344.8	0.0106	556.4	0.0150	740.7
0.0020	117.2	0.0063	349.9	0.0107	560.9	0.0151	744.6
0.0021	122.9	0.0064	355.0	0.0108	565.4	0.0152	748.4
0.0022	128.6	0.0065	360.1	0.0109	569.9	0.0153	752.3
0.0023	134.3	0.0066	365.2	0.0110	574.3	0.0154	756.1
0.0024	139.9	0.0067	370.2	0.0111	578.8	0.0155	759.9
0.0025	145.6	0.0068	375.3	0.0112	583.2	0.0156	763.7
0.0026	151.2	0.0069	380.3	0.0113	587.6	0.0157	767.5
0.0027	156.8	0.0070	385.3	0.0114	592.0	0.0158	771.2
0.0028	162.4	0.0071	390.3	0.0115	596.4	0.0159	775.0
0.0029	168.0	0.0072	395.0	0.0116	600.7	0.0160	778.7
0.0030	173.6	0.0073	400.3	0.0117	605.1	ρ_{max} 01601	782.5
0.0031	179.2	0.0074	405.2	0.0118	609.4		
0.0032	184.8	0.0075	410.2	0.0119	613.7		
0.0033	190.3	0.0076	415.1	0.0120	618.0		
0.0034	195.8	0.0077	420.0	0.0121	622.3		
0.0035	201.3	0.0078	424.9	0.0122	626.6		
0.0036	206.8	0.0079	429.8	0.0123	630.9		
0.0037	212.3	0.0080	434.7	0.0124	635.1		
0.0038	217.8	0.0081	439.5	0.0125	639.4		
0.0039	223.2	0.0082	444.4	0.0126	643.6		
0.0040	228.7	0.0083	449.2	0.0127	647.8		
0.0041	234.1	0.0084	454.0	0.0128	652.0		
0.0042	239.5	0.0085	458.8	0.0129	656.2		
0.0043	244.9	0.0086	463.6	0.0130	660.3		
0.0044	250.3	0.0087	468.4	0.0131	664.5		
0.0045	255.7	0.0088	473.2	0.0132	668.6		
0.0046	261.0	0.0089	477.9	0.0133	672.8		
0.0047	266.4	0.0090	482.6	0.0134	676.9		
0.0048	271.7	0.0091	487.4	0.0135	681.0		
0.0049	277.0	0.0092	492.1	0.0136	685.0		
0.0050	282.3	0.0093	496.8	0.0137	689.1		
0.0051	287.6	0.0094	501.4	0.0138	693.2		
0.0052	292.9	0.0095	506.1	0.0139	697.2		
		0.0096	510.7	0.0140	701.2		

Notes:

1. Units of $\frac{Mu}{\Phi bd2}$ are in psi.

2. ρ_{min} Should be based on 1.2 Mcr or 1.33 ρ analysis, whichever is smaller.

3. ρ_{max} =0.75 ρ_b = 0.0161 based on $ß_1$ = 0.85.

Flexural Reinforcement for Class 4000 Concrete

Table 5-A-9

ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$
0.0010	59.5	0.0056	319.3	0.0102	556.7	0.0148	771.7	0.0194	964.1
0.0011	65.4	0.0057	324.7	0.0103	561.7	0.0149	776.1	0.0195	968.1
0.0012	71.2	0.0058	330.1	0.0104	566.6	0.0150	780.5	0.0196	972.0
0.0013	77.1	0.0059	335.5	0.0105	571.5	0.0151	784.9	0.0197	975.9
0.0014	83.0	0.0060	340.9	0.0106	576.3	0.0152	789.3	0.0198	979.8
0.0015	88.8	0.0061	346.2	0.0107	581.2	0.0153	793.7	0.0199	983.7
0.0016	94.6	0.0062	351.6	0.0108	586.1	0.0154	798.1	0.0201	987.6
0.0017	100.5	0.0063	356.9	0.0109	590.9	0.0155	802.4	0.0202	991.5
0.0018	106.3	0.0064	362.2	0.0110	595.7	0.0156	806.8	0.0203	995.3
0.0019	112.1	0.0065	367.6	0.0111	600.06	0.0157	811.1	0.0204	999.2
0.0020	117.9	0.0066	372.9	0.0112	605.4	0.0158	815.4	0.0205	1003.0
0.0021	123.7	0.0067	378.2	0.0113	610.2	0.0159	819.7	0.0206	1006.8
0.0022	129.4	0.0068	383.4	0.0114	615.0	0.0160	824.1	0.0207	1010.7
0.0023	135.2	0.0069	388.7	0.0115	619.8	0.0161	828.3	0.0208	1014.5
0.0024	140.9	0.0070	394.0	0.0116	624.5	0.0162	832.6	0.0209	1018.3
0.0025	146.7	0.0071	399.2	0.0117	629.3	0.0163	836.9	0.0210	1022.0
0.0026	152.4	0.0072	404.5	0.0118	634.1	0.0164	841.2	0.0211	1025.8
0.0027	158.1	0.0073	409.7	0.0119	638.8	0.0165	845.4	0.0212	1029.6
0.0028	163.8	0.0074	414.9	0.0120	643.5	0.0166	849.7	0.0213	1033.3
0.0029	169.5	0.0075	420.1	0.0121	648.2	0.0167	853.9	ρ_{max} 0.0214	1037.1
0.0030	175.2	0.0076	425.3	0.0122	653.0	0.0168	858.1		1040.8
0.0031	180.9	0.0077	430.5	0.0123	657.7	0.0169	862.3		
0.0032	186.6	0.0078	435.7	0.0124	662.3	0.0170	866.5		
0.0033	192.2	0.0079	440.9	0.0125	667.0	0.0171	870.7		
0.0034	197.9	0.0080	446.0	0.0126	671.7	0.0172	874.9		
0.0035	203.5	0.0081	451.2	0.0127	676.3	0.0173	879.1		
0.0036	209.1	0.0082	456.3	0.0128	681.0	0.0174	883.2		
0.0037	214.7	0.0083	461.4	0.0129	685.6	0.0175	887.4		
0.0038	220.3	0.0084	466.5	0.0130	690.3	0.0176	891.5		
0.0039	225.9	0.0085	471.6	0.0131	694.9	0.0177	895.6		
0.0040	231.5	0.0086	476.7	0.0132	699.5	0.0178	899.7		
0.0041	237.1	0.0087	481.8	0.0133	704.1	0.0179	903.9		
0.0042	242.6	0.0088	486.9	0.0134	708.6	0.0180	907.9		
0.0043	248.2	0.0089	491.9	0.0135	713.2	0.0181	912.0		
0.0044	253.7	0.0090	497.0	0.0136	717.8	0.0182	916.1		
0.0045	259.2	0.0091	502.0	0.0137	722.3	0.0183	920.2		
0.0046	264.8	0.0092	507.1	0.0138	726.9	0.0184	924.2		
0.0047	270.3	0.0093	512.1	0.0139	731.4	0.0185	928.3		
0.0048	275.8	0.0094	517.1	0.0140	735.9	0.0186	932.3		
0.0049	281.2	0.0095	522.1	0.0141	740.4	0.0187	936.3		
0.0050	286.7	0.0096	527.1	0.0142	744.9	0.0188	940.3		
0.0051	292.2	0.0097	532.0	0.0143	749.4	0.0189	944.3		
0.0052	297.6	0.0098	537.0	0.0144	753.9	0.0190	948.3		
0.0053	303.1	0.0099	542.0	0.0145	758.3	0.0191	952.3		
0.0054	808.5	0.100	546.9	0.0146	762.8	0.0192	956.2		
0.0055	313.9	0.101	551.8	0.0147	767.2	0.0193	960.2		

Notes:

1. Units of $\frac{Mu}{\Phi bd2}$ are in psi.

2. ρ_{min} Should be based on 1.2 Mcr or 1.33 ρ analysis, whichever is smaller.
3. ρ_{max} =0.75 ρ_b = 0.0161 based on ß$_1$ = 0.85.

Flexural Reinforcement for Class 5000 Concrete

Table 5-A-10

ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$
0.0010	59.6	0.0061	350.2	0.0113	623.8	0.0165	874.3	0.0217	1102.0
0.0011	65.5	0.0062	355.7	0.0114	628.8	0.0166	878.9	0.0218	1106.1
0.0012	71.4	0.0063	361.1	0.0115	633.8	0.0167	883.5	0.0219	1110.3
0.0013	77.3	0.0064	366.6	0.0116	638.8	0.0168	888.1	0.0220	1114.4
0.0014	83.2	0.0065	372.1	0.0117	643.8	0.0169	892.7	0.0221	1118.5
0.0015	89.0	0.0066	377.5	0.0118	648.8	0.0170	897.2	0.0222	1122.6
0.0016	94.9	0.0067	382.9	0.0119	653.8	0.0171	901.8	0.0223	1126.8
0.0017	100.8	0.0068	388.4	0.0120	658.8	0.0172	906.3	0.0224	1130.9
0.0018	106.6	0.0069	393.8	0.0121	663.8	0.0173	910.9	0.0225	1134.9
0.0019	112.5	0.0070	399.2	0.0122	668.8	0.0174	915.4	0.0226	1139.0
0.0020	118.3	0.0071	404.6	0.0123	673.7	0.0175	919.9	0.0227	1143.1
0.0021	124.1	0.0072	410.0	0.0124	678.7	0.0176	924.4	0.0228	1147.2
0.0022	129.9	0.0073	415.4	0.0125	683.6	0.0177	928.9	0.0229	1151.2
0.0023	135.8	0.0074	420.7	0.0126	688.6	0.0178	933.4	0.0230	1155.3
0.0024	141.6	0.0075	426.1	0.0127	693.5	0.0179	937.9	0.0231	1159.3
0.0025	147.3	0.0076	431.5	0.0128	698.4	0.0180	942.4	0.0232	1163.4
0.0026	153.1	0.0077	436.8	0.0129	703.3	0.0181	946.8	0.0233	1167.4
0.0027	158.9	0.0078	442.2	0.0130	708.2	0.0182	951.3	0.0234	1171.4
0.0028	164.7	0.0079	447.5	0.0131	713.1	0.0183	955.7	0.0235	1175.4
0.0029	170.4	0.0080	425.8	0.0132	718.0	0.0184	960.2	0.0236	1179.4
0.0030	176.2	0.0081	458.1	0.0133	722.9	0.0185	964.6	0.0237	1183.4
0.0031	181.9	0.0082	463.4	0.0134	727.7	0.0186	969.0	0.0238	1187.4
0.0032	187.7	0.0083	468.7	0.0135	732.6	0.0187	973.5	0.0239	1191.4
0.0033	193.4	0.0084	474.0	0.0136	737.4	0.0188	977.9	0.0240	1195.3
0.0034	199.1	0.0085	479.3	0.0137	742.3	0.0189	982.3	0.0241	1199.3
0.0035	204.8	0.0086	484.6	0.0138	747.1	0.0190	986.6	0.0242	1203.2
0.0036	210.5	0.0087	489.8	0.0139	751.9	0.0191	991.0	0.0243	1207.2
0.0037	216.2	0.0088	495.1	0.0140	756.7	0.0192	995.4	0.0244	1211.1
0.0038	221.9	0.0089	500.4	0.041	761.5	0.0193	999.8	0.0245	1215.00
0.0039	227.5	0.0090	505.6	0.0142	766.3	0.0194	1004.1	0.0246	1218.9
0.0040	233.2	0.0091	510.8	0.0143	771.1	0.0195	1008.5	0.0247	1222.8
0.0041	238.9	0.0092	516.0	0.0144	775.9	0.0196	1012.8	0.0248	1226.7
0.0042	244.5	0.0093	521.3	0.0145	780.7	0.0197	1017.1	0.0249	1230.6
0.0043	250.1	0.0094	526.5	0.0146	785.4	0.0198	1021.5	0.0250	1234.5
0.0044	255.8	0.0095	531.7	0.0147	790.2	0.0199	1025.8	0.0251	1238.4
0.0045	261.4	0.0096	536.9	0.0148	795.0	0.0200	1030.1	ρ_{max} 0.0252	1242.2
0.0046	267.0	0.0097	542.0	0.0149	799.7	0.0201	1034.4		
0.0047	272.6	0.0098	547.2	0.0150	804.4	0.0202	1038.7		
0.0048	278.2	0.0099	552.4	0.0151	809.1	0.0203	1042.9		
0.0049	283.8	0.0100	557.5	0.0152	813.9	0.0204	1047.2		
0.0050	289.4	0.0101	562.7	0.0153	818.6	0.0205	1051.5		
0.0051	295.0	0.0102	567.8	0.0154	823.3	0.0206	1055.7		
0.0052	300.5	0.0103	572.9	0.0155	827.9	0.0207	1060.0		
0.0053	306.1	0.0104	578.1	0.0156	832.6	0.0208	1064.2		
0.0054	311.6	0.0105	583.2	0.0157	837.3	0.0209	1068.4		
0.0055	317.1	0.0106	588.3	0.0158	842.0	0.0210	1072.7		
0.0056	322.7	0.0107	593.4	0.0159	846.6	0.0211	1076.9		
0.0057	328.2	0.0108	598.5	0.0160	851.3	0.0212	1081.1		
0.0058	333.7	0.0109	603.5	0.0161	855.9	0.0213	1085.3		
0.0059	339.2	0.0110	608.6	0.0162	860.5	0.0214	1089.5		
0.0060	344.7	0.0111	613.7	0.0163	865.1	0.0215	1093.6		
		0.0112	618.7	0.0164	869.7	0.0216	1097.8		

Notes:


1. Units of $\frac{Mu}{\Phi bd2}$ are in psi.

2. ρ_{min} Should be based on 1.2 Mcr or 1.33 ρ analysis, whichever is smaller.


3. ρ_{max} =0.75 ρ_b = 0.0161 based on $ß_1$ = 0.85.

Flexural Reinforcement for Class 6000 Concrete


Table 5-A-11




Positive Moment Reinforcement
Figure 5-A-12



Negative Moment Reinforcement
Figure 5-A-13




Adjusted Negative Moment Case I (Design for M @ Face of Support)
Figure 5-A-14




Adjusted Negative Moment Case II (Design for M @ 1/4 Point)

Figure 5-A-15




Cast-In-Place Deck Slab Design for Positive Moment Regions f'c=4, 0 ksi

Figure 5-A-16




Cast-In-Place Deck Slab Design for Negative Moment Regions f'c=4, 0 ksi

Figure 5-A-17



Slab Overhang Design- Interior Barrier Segment

Figure 5-A-18



Slab Overhang Design- End Barrier Segment
Figure 5-A-19

f'ci = 7.5 ksi, f'c = 8.5 ksi Strand diameter = 0.6" Grade 270 ksi low relaxation									
Girder Type	Girder Spacing (ft)	Span Length (ft)	Straight Strands	Harped Strands	Harped Strand Offset*	Top Temp. Strands	Excess Camber (in)	"A" Dim. (in)	Deck Thickness (in)
W42G	5	85	14	10	7	0	2.613	11.25	7.50
	6	80	14	9	6	0	2.591	11.00	7.50
	7	70	10	10	6	0	1.656	10.25	7.50
	8	60	8	9	7	0	1.045	9.50	7.50
	9	55	6	10	6	0	0.815	9.25	7.50
	10	50	6	9	7	0	0.636	9.50	7.75
	11	50	6	10	7	0	0.629	10.00	8.25
	12	45	6	9	8	0	0.512	10.00	8.50
W50G	5	110	20	12	2	0	3.525	12.00	7.50
	6	105	20	12	2	0	3.427	12.00	7.50
	7	95	18	11	3	0	2.758	11.25	7.50
	8	90	18	12	6	0	2.459	11.00	7.50
	9	85	16	12	5	0	2.106	10.75	7.50
	10	75	12	12	6	0	1.356	10.25	7.75
	11	70	12	12	7	0	1.222	10.25	8.00
	12	65	12	11	8	0	1.033	10.50	8.50
W58G	5	125	18	17	0	2	2.699	11.25	7.50
	6	120	18	17	0	2	2.734	11.25	7.50
	7	115	20	16	1	2	2.901	11.50	7.50
	8	105	18	15	2	2	2.381	11.00	7.50
	9	100	18	14	2	2	2.250	10.25	7.50
	10	95	16	16	2	2	2.029	10.75	7.50
	11	90	16	15	2	2	1.846	11.00	8.00
	12	90	16	17	2	2	1.853	11.50	8.50
W74G	5	150	22	21	2	4	2.765	11.50	7.50
	6	140	22	19	2	4	2.770	11.50	7.50
	7	135	20	22	2	4	2.753	11.50	7.50
	8	130	20	22	2	4	2.760	11.50	7.50
	9	125	20	22	3	4	2.640	11.50	7.50
	10	120	18	22	2	4	2.401	11.25	7.50
	11	115	18	21	1	4	2.332	11.50	7.75
	12	110	18	20	0	4	2.259	11.50	8.00

* Offset at harping point

Design Parameters:

- PGSuper V. 1.4
- WSDOT BDM LRFD design criteria
- Slab f'c = 4.0 ksi
- No vertical or horizontal curve
- 2.0% roadway crown slope
- Interior Girder w/ barrier load (6 girder bridge)
- Standard WSDOT "F" shape barrier
- Simple girder span lengths are CL bearing to CL bearing
- Under normal exposure condition and 75% relative humidity
- Spans reported in 5 ft. increments
- Only flexural service and strength checked; Lifting and ha uling checks not necessarily satisfied

Span Capability of Prestressed I-Girders

Table 5-A-20

f'ci = 7.5 ksi, f'c = 8.5 ksi Strand diameter = 0.6" Grade 270 ksi low relaxation									
Girder Type	Girder Spacing (ft)	Span Length (ft)	Straight Strands	Harped Strands	Harped Strand Offset*	Top Temp. Strands	Excess Camber (in)	"A" Dim. (in)	Deck Thickness (in)
WF42G	5	115	24	24	0	6	2.162	11.00	7.50
	6	110	26	24	2	6	2.227	11.00	7.50
	7	105	24	24	1	6	2.197	11.00	7.50
	8	100	24	24	2	6	2.076	11.00	7.50
	9	95	26	19	0	6	2.316	11.25	7.50
	10	90	22	22	0	6	2.073	11.00	7.50
	11	85	20	22	0	4	2.009	11.00	7.50
	12	80	20	20	0	0	2.185	11.50	8.00
WF50G	5	130	32	20	0	6	2.508	11.50	7.50
	6	125	32	22	3	6	2.336	11.25	7.50
	7	120	30	21	0	6	2.543	11.50	7.50
	8	115	28	23	1	6	2.352	11.25	7.50
	9	110	26	24	0	6	2.386	11.25	7.50
	10	105	26	23	0	6	2.337	11.25	7.50
	11	100	24	24	1	6	2.039	11.00	7.50
	12	95	22	24	0	6	1.871	11.25	8.00
WF58G	5	145	34	21	0	6	2.343	11.25	7.50
	6	135	30	22	0	6	2.225	11.00	7.50
	7	130	32	20	0	6	2.463	11.25	7.50
	8	125	30	22	0	6	2.404	11.25	7.50
	9	120	30	20	0	6	2.333	11.25	7.50
	10	115	28	22	0	6	2.281	11.25	7.50
	11	110	26	22	0	6	2.029	11.00	7.50
	12	105	26	21	0	6	1.915	11.25	8.00
WF74G	5	175	40	23	0	6	2.389	11.25	7.50
	6	170	40	24	0	6	2.666	11.50	7.50
	7	160	38	24	3	6	2.431	11.25	7.50
	8	155	38	24	2	6	2.675	11.50	7.50
	9	145	34	23	0	6	2.500	11.50	7.50
	10	140	34	22	0	6	2.497	11.25	7.50
	11	135	36	22	6	6	2.299	11.25	7.50
	12	130	34	23	2	6	2.425	11.75	8.00
W83G	5	195#	46	24	0	6	2.429	11.25	7.50
	6	185#	46	24	0	6	3.011	12.00	7.50
	7	180	46	24	0	6	3.121	12.00	7.50
	8	170	46	21	0	6	3.217	12.25	7.50
	9	165	46	22	0	6	3.434	12.25	7.50
	10	155	46	17	0	6	3.297	12.25	7.50
	11	150	46	17	0	6	3.339	12.25	7.50
	12	145	46	16	0	6	3.161	12.50	8.00
W95G	5	195#	46	19	0	6	3.778	12.75	7.50
	6	190#	46	21	0	6	4.186	13.00	7.50
	7	185#	46	21	0	6	4.209	13.00	7.50
	8	175#	46	18	0	6	4.001	13.00	7.50
	9	170#	46	17	0	6	3.882	12.75	7.50
	10	165	46	18	0	6	4.011	13.00	7.50
	11	160	46	18	0	6	3.997	13.00	7.50
	12	155	46	16	0	6	3.686	13.00	8.00

* Offset at harping point

Span capability exceeds maximum shipping weight of 200 kips

Design Parameters:

- Interior Girder w/ barrier load (6 girder bridge)
- PGSuper V. 1.4
- Standard WSDOT "F" shape barrier
- WSDOT BDM LRFD design criteria
- Simple girder span lengths are CL bearing to CL bearing
- Slab f'c = 4.0 ksi
- Under normal exposure condition and 75% relative humidity
- No vertical or horizontal curve
- Spans reported in 5 ft. increments
- 2.0% roadway crown slope
- Only flexural service and strength checked; Lifting and hauling checks not necessarily satisfied

Span Capability of Prestressed Wide Flange I-Girders

Table 5-A-21

f'ci = 7.5 ksi, f'c = 8.5 ksi Strand diameter = 0.6" Grade 270 ksi low relaxation									
Girder Type	Girder Spacing (ft)	Span Length (ft)	Straight Strands	Harped Strands	Harped Strand Offset*	Top Temp. Strands	Excess Camber (in)	"A" Dim. (in)	Deck Thickness (in)
WBT32G	5	75	20	5	0	6	2.895	11.75	7.50
	6	75	18	10	3	6	2.924	11.75	7.50
	7	70	18	8	0	6	2.839	11.75	7.50
	8	65	18	6	0	6	2.380	11.25	7.50
	9	65	18	8	2	6	2.427	11.25	7.50
	10	60	16	8	0	6	2.123	11.00	7.50
	11	60	18	7	0	6	2.240	11.00	7.50
	12	55	16	7	0	6	1.763	11.25	8.00
WBT38G	5	90	22	8	2	6	3.308	12.25	7.50
	6	85	22	7	0	6	3.245	12.00	7.50
	7	80	22	6	0	6	2.956	11.75	7.50
	8	75	20	7	2	6	2.537	11.50	7.50
	9	75	20	8	0	6	2.742	11.50	7.50
	10	70	18	9	1	6	2.372	11.25	7.50
	11	65	20	5	1	6	2.029	11.00	7.50
	12	65	20	6	0	6	2.087	11.50	8.00
WBT62G	5	130	26	12	0	6	3.415	12.25	7.50
	6	125	26	13	0	6	3.536	12.50	7.50
	7	120	26	12	0	6	3.364	12.25	7.50
	8	115	26	12	0	6	3.354	12.25	7.50
	9	110	26	11	0	6	3.161	12.00	7.50
	10	105	26	10	0	6	2.967	11.75	7.50
	11	100	26	9	0	6	2.763	11.75	7.50
	12	95	26	8	0	6	2.513	12.00	8.00

* Offset at harping point

Design Parameters:

- PGSuper V. 1.4
- WSDOT BDM LRFD design criteria
- Slab f'c = 4.0 ksi
- No vertical or horizontal curve
- 2.0% roadway crown slope
- Interior Girder w/ barrier load (6 girder bridge)
- Standard WSDOT "F" shape barrier
- Simple girder span lengths are CL bearing to CL bearing
- Under normal exposure condition and 75% relative humidity
- Spans reported in 5 ft. increments
- Only flexural service and strength checked; Lifting and hauling checks not necessarily satisfied

Span Capability of Thin Flange Bulb-Tee Girders
Table 5-A-22

f'ci = 7.5 ksi, f'c = 8.5 ksi Strand diameter = 0.6" Grade 270 ksi low relaxation									
Girder Type	Girder Spacing (ft)	Span Length (ft)	Straight Strands	Harped Strands	Harped Strand Offset*	Top Temp. Strands	Excess Camber (in)	"A" Dim. (in)	Deck Thickness (in)
U54G4	8	130	32	26	4	0	0.083	9.00	7.5
	10	125	32	28	0	0	0.164	9.00	7.5
	12	120	32	30	2	0	0.691	9.25	7.5
	14	115	32	30	0	0	0.757	9.25	7.5
U54G5	9	130	46	18	0	0	0.284	9.00	7.5
	11	125	46	20	0	0	0.671	9.00	7.5
	13	120	46	20	0	0	0.874	9.25	7.5
	15	115	46	20	0	0	1.082	9.50	7.5
U54G6	10	120	52	10	0	0	0.000	9.00	7.5
	12	115	52	10	0	0	0.268	9.00	7.5
	14	110	52	10	0	0	0.518	9.00	7.5
	16	105	52	10	0	0	0.740	9.25	7.5
U66G4	8	155#	32	38	8	0	0.581	9.00	7.5
	10	145	32	36	6	0	0.058	9.00	7.5
	12	140	32	38	4	0	0.326	9.00	7.5
	14	135	32	40	4	0	0.717	9.25	7.5
U66G5	9	150#	46	24	4	0	0.000	9.00	7.5
	11	145#	46	26	0	0	0.012	9.00	7.5
	13	140#	46	28	0	0	0.386	9.00	7.5
	15	135	46	28	0	0	0.608	9.25	7.5
U66G6	10	145#	52	24	8	0	0.000	9.00	7.5
	12	140#	52	22	4	0	0.000	9.00	7.5
	14	135#	52	24	4	0	0.000	9.00	7.5
	16	130#	52	24	0	0	0.036	9.00	7.5
U78G4	8	170#	32	42	8	0	0.000	9.00	7.5
	10	165#	32	46	8	0	0.000	9.00	7.5
	12	160#	32	48	8	0	0.150	9.00	7.5
	14	150#	32	44	4	0	0.354	9.00	7.5
	16	145#	32	48	4	0	0.715	9.50	8.0
U78G5	9	170#	46	34	8	0	0.000	9.00	7.5
	11	165#	46	36	4	0	0.000	9.00	7.5
	13	160#	46	38	4	0	0.037	9.00	7.5
	15	155#	46	40	4	0	0.439	9.00	7.5
	17	150#	46	42	6	0	0.699	9.50	8.0
U78G6	10	165#	52	32	8	0	0.000	9.00	7.5
	12	160#	52	34	8	0	0.000	9.00	7.5
	14	155#	52	34	4	0	0.000	9.00	7.5
	16	150#	52	34	4	0	0.000	9.00	7.5
	18	145#	52	36	4	0	0.000	9.00	8.0

Note: Adding bottom flange width does not necessarily increase the span capabilities

* Offset at girder end

Span capability exceeds maximum shipping weight of 200 kips

Design Parameters:

- PGSuper V. 1.4
- WSDOT BDM LRFD design criteria
- Slab f'c = 4.0 ksi
- No vertical or horizontal curve
- 2.0% roadway crown slope
- Interior Girder w/ barrier load (6 girder bridge)
- Standard WSDOT "F" shape barrier
- Simple girder span lengths are CL bearing to CL bearing
- Under normal exposure condition and 75% relative humidity
- Spans reported in 5 ft. increments
- Only flexural service and strength checked; Lifting and hauling checks not necessarily satisfied

Span Capability of Trapezoidal Tub Girders without Top Flange

Table 5-A-23

f'ci = 7.5 ksi, f'c = 8.5 ksi Strand diameter = 0.6" Grade 270 ksi low relaxation									
Girder Type	Girder Spacing (ft)	Span Length (ft)	Straight Strands	Harped Strands	Harped Strand Offset*	Top Temp. Strands	Excess Camber (in)	"A" Dim. (in)	Deck Thickness (in)
UF60G4	9	150#	32	42	4	0	0.000	9.00	7.5
	11	145	32	46	6	0	1.086	9.75	7.5
	13	140	32	48	2	0	1.123	9.75	7.5
	15	130	32	42	0	0	1.174	9.75	7.5
UF60G5	10	150#	46	34	4	0	0.465	9.00	7.5
	12	145#	46	36	4	0	0.830	9.50	7.5
	14	140#	46	38	4	0	1.225	9.75	7.5
	16	135	46	38	4	0	1.419	10.00	7.5
UF60G6	15	135#	52	32	4	0	0.154	9.00	7.5
	17	130#	52	32	4	0	0.453	9.00	7.5
UF72G4	9	165#	32	46	0	0	0.000	9.00	7.5
	11	160#	32	48	0	0	0.000	9.00	7.5
	13	150#	32	46	0	0	0.657	9.25	7.5
	15	145#	32	46	0	0	0.828	9.50	7.5
UF72G5	10	170#	46	42	4	0	0.000	9.00	7.5
	12	165#	46	44	4	0	0.186	9.00	7.5
	14	160#	46	46	4	0	0.604	9.25	7.5
	16	150#	46	42	0	0	0.903	9.50	7.5
UF72G6	13	160#	52	40	8	0	0.000	9.00	7.5
	15	155#	52	42	4	0	0.000	9.00	7.5
	17	150#	52	42	4	0	0.000	9.00	7.5
UF84G4	10	190#	32	66	12	0	0.000	9.00	7.5
	12	185#	32	70	16	0	0.938	9.50	7.5
	14	180#	32	72	16	0	1.310	10.00	7.5
	16	170#	32	68	8	0	1.074	9.50	7.5
UF84G5	11	185#	46	52	8	0	0.000	9.00	7.5
	13	180#	46	54	8	0	0.269	9.00	7.5
	15	175#	46	56	8	0	0.657	9.25	7.5
	17	170#	46	58	8	0	1.038	9.50	7.5
UF84G6	16	170#	52	50	8	0	0.000	9.00	7.5
	18	165#	52	50	8	0	0.000	9.00	7.5

Note: Adding bottom flange width does not necessarily increase the span capabilities

* Offset at girder end

Span capability exceeds maximum shipping weight of 200 kips

Design Parameters:

- PGSuper V. 1.4
- WSDOT BDM LRFD design criteria
- Slab f'c = 4.0 ksi
- No vertical or horizontal curve
- 2.0% roadway crown slope
- Interior Girder w/ barrier load (6 girder bridge)
- Standard WSDOT "F" shape barrier
- Simple girder span lengths are CL bearing to CL bearing
- Under normal exposure condition and 75% relative humidity
- Spans reported in 5 ft. increments
- Only flexural service and strength checked; Lifting and hauling checks not necessarily satisfied

Span Capability of Trapezoidal Tub Girders with Top Flange

Table 5-A-24

Concrete Strength:		f'_{ci} = 6.0 ksi			f'_c = 7.0 ksi				
Prestressing Strands:		½" diameter			f_{pu} = 270 ksi, Low Relaxation				
Span Length (ft)	Strand Layout				Total Jacking Force (kip)	Location of C.G. of Strand, E (in)	Camber (in)		
	3" Top	2" Bot. bonded	2" Bot. unbonded	*Total			C_i	C_{final}	C_{f+sidl}
26	2	8	2	12	377	4.83	0.11	0.24	0.22
29	2	10	2	14	440	5.14	0.18	0.38	0.34
32	2	10	4	16	502	5.38	0.25	0.53	0.47
34	2	12	4	18	565	5.56	0.33	0.72	0.64
36	4	14	4	22	691	4.64	0.36	0.77	0.68
38	4	14	4	24	753	4.67	0.44	0.94	0.82
40	4	14	4	26	816	4.69	0.53	1.13	0.98
42	4	14	4	28	879	4.71	0.62	1.33	1.14
44	4	14	4	30	942	4.73	0.72	1.54	1.32
46	4	14	4	34	1067	4.76	0.92	1.98	1.70
48	4	14	4	38	1193	4.58	1.06	2.28	1.92
50	4	14	47	40	1255	4.50	1.15	2.46	2.04

Concrete Strength:		f'_{ci} = 7.0 ksi			f'_c = 8.0 ksi				
Prestressing Strands:		0.6" diameter			f_{pu} = 270 ksi, Low Relaxation				
Span Length (ft)	Strand Layout				Total Jacking Force (kip)	Location of C.G. of Strand, E (in)	Camber (in)		
	3" Top	2" Bot. bonded	2" Bot. unbonded	*Total			C_i	C_{final}	C_{f+sidl}
32	2	8	2	12	534	4.83	0.22	0.44	0.39
36	2	10	2	14	623	5.14	0.34	0.70	0.62
39	2	10	4	16	712	5.38	0.47	0.96	0.84
42	4	14	4	20	890	4.40	0.53	1.10	0.88
45	4	14	4	22	979	4.64	0.69	1.41	1.19
47	4	14	4	24	1068	4.67	0.82	1.69	1.43
49	4	14	4	26	1157	4.69	0.97	2.01	1.68
52	4	12	6	30	1335	4.73	1.26	2.61	2.16
54	4	12	6	32	1424	4.75	1.45	2.99	2.44
56	4	12	6	34	1513	4.76	1.65	3.39	2.76
58	4	12	6	38	1691	4.58	1.88	3.88	3.12
60	4	12	6	40	1780	4.50	2.02	4.17	3.27

* Total strands include all bottom strands and top strands

Design Parameters:

- LRFD Voided Slab Excel Spreadsheet (office design)
- WSDOT BDM LRFD design criteria
- No vertical or horizontal curve or skew
- Only flexural service and strength checked; Lifting and hauling checks not necessarily satisfied
- Span length is CL bearing to CL bearing
- 80% relative humidity under normal exposure
- Location of C.G. of strands is summation of all strands (top and bottom, bonded and unbonded)
- Jacking forces listed are for the entire system; top and bottom strands
- Top strands will be: 2 min. up to 4 max.
- LL distribution factors used case "g" connected only enough to prevent relative vertical displ.
- Anchor is designed 5" from end of voided slab
- Bridge width of 44' with 3 lanes on the structure

Span Capability of Prestressed1'-6" Voided Slabs

Table 5-A-25

Concrete Strength:	f'_{ci} = 6.0 ksi			f'_c = 7.0 ksi				
Prestressing Strands:	½" diameter			f_{pu} = 270 ksi, Low Relaxation				
Span Length (ft)	Strand Layout				Total Jacking Force (kip)	Location of C.G. of Strand, E (in)	Camber (in)		
	3" Top	2" Bot. bonded	2" Bot. unbonded	*Total			C_i	C_{final}	C_{f+sidl}
43	2	14	2	18	565	8.67	0.25	0.54	0..47
46	2	14	4	20	628	8.90	0.32	0.68	0.59
48	4	14	4	24	753	7.33	0.31	0.66	0.56
50	4	14	4	26	816	7.46	0.38	0.81	0.68
52	4	14	4	28	879	7.57	0.46	0.96	0.82
54	4	14	4	30	942	7.67	0.54	1.13	0.97
56	4	14	4	32	1004	7.75	0.62	1.32	1.11
58	4	12	6	34	1067	7.82	0.70	1.48	1.24
60	4	12	6	36	1130	7.89	0.79	1.68	1.41
62	6	12	6	40	1255	7.05	0.77	1.64	1.33
64	6	12	6	42	1318	7.14	0.87	1.85	1.49
66	6	12	6	46	1443	7.13	1.04	2.21	1.79
68	6	12	6	48	1506	7.13	1.13	2.39	1.91

Concrete Strength:	f'_{ci} = 7.0 ksi			f'_c = 8.0 ksi				
Prestressing Strands:	0.6" diameter			f_{pu} = 270 ksi, Low Relaxation				
Span Length (ft)	Strand Layout				Total Jacking Force (kip)	Location of C.G. of Strand, E (in)	Camber (in)		
	3" Top	2" Bot. bonded	2" Bot. unbonded	*Total			C_i	C_{final}	C_{f+sidl}
55	4	16	2	22	979	7.18	0.47	0.97	0.81
58	4	16	2	24	1068	7.33	0.59	1.20	1.00
61	4	14	4	26	1157	7.46	0.46	1.41	1.16
63	4	14	4	28	1246	7.57	0.83	1.69	1.39
66	4	14	4	30	1335	7.67	0.97	1.98	1.61
68	6	14	4	34	1513	6.71	0.93	1.90	1.48
70	6	14	4	36	1602	6.83	1.09	2.21	1.72
72	6	14	4	38	1691	6.95	1.25	2.55	2.00
74	6	14	4	40	1780	7.05	1.42	2.90	2.26
76	6	12	6	42	1869	7.14	1.57	3.21	2.49
78	6	12	6	44	1958	7.14	1.71	3.49	2.68
80	6	12	6	46	2047	7.13	1.86	3.79	2.84
82	6	12	6	48	2136	7.13	2.01	4.09	3.04

* Total strands include all bottom strands and top strands

Design Parameters:

- LRFD Voided Slab Excel Spreadsheet (office design)
- WSDOT BDM LRFD design criteria
- No vertical or horizontal curve or skew was used
- Only flexural service and strength checked; Lifting and hauling checks not necessarily satisfied
- Span length is CL bearing to CL bearing
- 80% relative humidity under normal exposure
- Location of C.G. of strands is summation of all strands (top and bottom, bonded and unbonded)
- Jacking forces and Eccentricity listed is for the entire system; top and bottom strands
- Top strands will be: 2 min. up to 6 max.
- LL distribution factors used method "g" connected only enough to prevent relative vertical displ.
- Anchor is designed 5" from end of voided slab
- Bridge width of 44' with 3 lanes on the structure

Span Capability of Prestressed2'-2" Voided Slabs

Table 5-A-26

Concrete Strength: f'ci = 6.0 ksi				f'c = 7.0 ksi				
Prestressing Strands: 1/2" diameter				fpu = 270 ksi, Low Relaxation				
Span Length (ft)	Strand Layout			Total Jacking Force (kip)	Location of C.G. of Strand, E (in)	Camber (in)		
	Top Strands (3" from top)	Bottom Debonded Strands	*Total Number of Strands			Ci	Cfinal	Cf+sidl
** 16	2	2	10	314	2.60	0.06	0.14	0.13
** 18	2	2	12	377	2.83	0.12	0.25	0.23
20	4	2	16	502	2.25	0.15	0.31	0.29
22	4	2	18	565	2.44	0.22	0.48	0.44
24	4	2	20	628	2.60	0.32	0.68	0.62
26	4	4	22	691	2.73	0.41	0.87	0.80
28	4	4	26	816	2.62	0.54	1.15	1.03
30	4	4	28	879	2.57	0.63	1.34	1.19
32	4	4	32	1004	2.50	0.78	1.67	1.47

Concrete Strength: f'ci = 7.0 ksi				f'c = 8.0 ksi				
Prestressing Strands: 0.6" diameter				fpu = 270 ksi, Low Relaxation				
Span Length (ft)	Strand Layout			Total Jacking Force (kip)	Location of C.G. of Strand, E (in)	Camber (in)		
	Top Strands (3" from top)	Bottom Debonded Strands	*Total Number of Strands			Ci	Cfinal	Cf+sidl
** 16	2	2	8	356	2.25	0.05	0.10	0.19
** 20	2	2	10	445	2.60	0.13	0.27	0.25
23	2	2	12	534	2.83	0.24	0.49	0.45
25	4	2	16	712	2.25	0.29	0.59	0.53
28	4	2	18	801	2.44	0.44	0.91	0.81
30	4	4	20	890	2.60	0.58	1.20	1.06
35	4	6	26	1157	2.62	0.98	2.02	1.73

* Total strands include all bottom strands and top strands

** Strands are not developed fully, designer should check capacities and span lengths

Design Parameters:

- WSDOT BDM LRFD design criteria
- No vertical or horizontal curve or skew
- Only flexural service and strength checked; Lifting and hauling checks not necessarily satisfied
- Span length is CL bearing to CL bearing
- 80% relative humidity under normal exposure
- Live load truck is not applicable on spans shorter than 22'-0", but the Tandem truck controls before then
- Location of C.G. of strands is summation of all strands (top and bottom, bonded and unbonded)
- Jacking forces listed are for the entire system; top and bottom strands
- Top strands will be: 2 min. up to 4 max.
- LL distribution factors used case "g" connected only enough to prevent relative vertical displ.
- Anchor is designed 5" from end of solid slab
- Bridge width of 44' with 3 lanes on the structure
- Distribution factors are applicable from span 22'-0" or longer based on research; used for shorter spans in these tables

Span Capability of Prestressed1'-0" Solid Slabs

5-A-27

Concrete Strength:		f'_{ci} = 6.5 ksi		f'_c = 8.0 ksi			
Prestressing Strands:		0.6” diameter		f_{pu} = 270 ksi, Low Relaxation			
Section		Span	Strands		Strand Layout		Camber
h (in)	b_f (ft)	L (ft)	#	F_{jack} (kips)	E (in)*	F_o (in)**	C_{final} (in)
20	9	25	12	527	7.0	14	6/16
	10	25	14	615	7.3	14	5/16
	11	25	14	615	7.5	14	5/16
24	9	35	18	791	7.6	16	13/16
	10	35	20	879	8.3	16	14/16
	11	30	16	703	8.0	16	8/16
28	9	40	20	879	8.0	18	1
	10	40	22	967	8.4	18	1 2/16
	11	35	18	791	8.4	18	11/16
32	9	50	24	1055	8.3	20	1 9/16
	10	45	22	967	8.5	20	1 2/16
	11	45	24	1055	8.8	20	1 5/16
36	9	55	24	1055	7.9	24	1 11/16
	10	50	24	1055	8.6	24	1.46
	11	45	20	879	8.5	24	0.99

* Offset for all strands at midpoint

** Offset for harped strands at endblock

Design Parameters:

WSDOT BDM LRFD Design Criteria

Flexural design of interior girder

Simple span on expansion bearings

Shape F traffic barriers on 6 girder bridge

0.25’ overlay

One straight strand in each web

Span capability of Double-Tee Decked Girders

Span Capability Precast Prestressed Double Tee Girders

Table 5-A-28

Concrete Strength:		f'_{ci} = 6.5 ksi		f'_c = 8.0 ksi			
Prestressing Strands:		f_{pu} = 270 ksi, Low Relaxation					
Section		Span	0.5” Diameter Strands		Strand Layout		Camber
h (in)	b_f (ft)	L (ft)	#	F_{jack} (kips)	E (in)*	F_o (in)**	C_{final} (in)
27	4	60	21	923	5.0	10	1 7/16
	5	55	21	923	5.6	10	1 6/16
	6	50	20	879	5.9	10	1 3/16

Section		Span	0.6” Diameter Strands		Strand Layout		Camber
h (in)	b_f (ft)	L (ft)	#	F_{jack} (kips)	E (in)*	F_o (in)**	C_{final} (in)
27	4	60	30	929	5.0	12	1 7/16
	5	55	30	929	5.6	12	1 7/16
	6	45	23	713	5.8	12	13/16

* Offset for all strands at midpoint

** Offset for harped strands at endblock

Design Parameters:

WSDOT BDM LRFD Design Criteria

Flexural design of interior girder

Simple span on expansion bearings

Shape F traffic barriers on 6 girder bridge

0.25’ overlay

One straight strand in each web

Span Capability Precast Prestressed Ribbed Girders

Table 5-A-29

	f'ci = 4.0 ksi f'c = 5.0 ksi, 0.6"ø Strands					f'ci = 5.0 ksi f'c = 6.0 ksi, 0.6"ø Strands				
Girder Type	Girder Width (ft)	Span Length (ft)	Straight	Harped	Temp.	Girder Width (ft)	Span Length (ft)	Straight	Harped	Temp.
W35DG	4	85	18	15	2	4	95	18	10	2
	5	70	22	7	2	5	80	18	8	2
	6	60	22	5	4	6	70	18	6	4
W41DG	4	95	22	12	2	4	105	20	8	2
	5	80	24	7	2	5	95	18	11	2
	6	70	22	7	4	6	80	20	6	4
W53DG	4	115	26	11	2	4	125	22	8	2
	5	105	26	12	2	5	120	22	12	2
	6	90	26	8	4	6	105	22	10	4
W65DG	4	135	26	16	2	4	145	24	9	2
	5	125	26	18	2	5	140	24	14	2
	6	110	26	14	4	6	125	24	12	4

Span Capability of Deck Bulb Tee Girders
Table 5-A-30

Concrete Strength:	f'_c=	8.0	ksi	f'_{ci} = 6.0 ksi
Prestressing Strands:	f_{pu}=	270	ksi	0.6” diameter

W35DG4

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
40	4	174	2	87	6	2.0	4.0	4.0	8.0	2/16	3/16
45	4	174	3	131	7	2.0	4.0	4.0	8.0	3/16	3/16
50	6	261	3	131	9	2.0	4.0	4.0	8.0	4/16	5/16
55	8	348	2	87	10	2.0	4.0	4.0	8.0	7/16	10/16
60	8	348	4	174	12	2.0	4.0	4.0	8.0	9/16	12/16
65	10	435	4	174	14	2.0	4.0	4.0	8.0	13/16	1 2/16
70	12	522	4	174	16	2.3	4.0	4.0	8.0	1 1/16	1 7/16
75	14	610	4	174	18	2.6	4.0	4.0	8.0	1 6/16	1 12/16
80	14	610	6	261	20	2.6	4.0	4.0	8.0	1 10/16	1 14/16
85	16	697	7	305	23	2.8	4.0	4.0	8.0	2 1/16	2 8/16
90	16	697	10	435	26	2.8	4.0	4.0	10.0	2 9/16	3 1/16

W35DG5

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
40	4	174	3	131	7	2.0	4.0	4.0	8.0	3/16	4/16
45	6	261	2	87	8	2.0	4.0	4.0	8.0	4/16	6/16
50	8	348	2	87	10	2.0	4.0	4.0	8.0	6/16	10/16
55	8	348	4	174	12	2.0	4.0	4.0	8.0	8/16	13/16
60	10	435	4	174	14	2.0	4.0	4.0	8.0	12/16	1 2/16
65	12	522	4	174	16	2.3	4.0	4.0	8.0	1	1 7/16
70	14	610	4	174	18	2.6	4.0	4.0	8.0	1 4/16	1 13/16
75	16	697	5	218	21	2.8	4.0	4.0	8.0	1 11/16	2 7/16
80	16	697	8	348	24	2.8	4.0	4.0	8.0	2 1/16	2 14/16

W35DG6

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
40	6	261	2	87	8	2.0	4.0	4.0	8.0	3/16	6/16
45	6	261	4	174	10	2.0	4.0	4.0	8.0	5/16	8/16
50	8	348	4	174	12	2.0	4.0	4.0	8.0	7/16	12/16
55	10	435	4	174	14	2.0	4.0	4.0	8.0	11/16	1 1/16
60	12	522	4	174	16	2.3	4.0	4.0	8.0	14/16	1 7/16
65	14	610	5	218	19	2.6	4.0	4.0	8.0	1 4/16	1 15/16
70	14	610	7	305	21	2.6	4.0	4.0	8.0	1 8/16	2 4/16
75	16	697	8	348	24	2.8	4.0	4.0	8.0	1 14/16	2 14/16

Design Charts for W35DG Deck Bulb Tee Girder

Table 5-A-31

Concrete Strength: f'_c= 8.0 ksi f'_{ci} = 6.0 ksi
Prestressing Strands: f_{pu}= 270 ksi 0.6” diameter

W41DG4

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
50	6	261	2	87	8	2.0	4.0	4.0	8.0	4/16	6/16
55	6	261	3	131	9	2.0	4.0	4.0	8.0	5/16	11/16
60	8	348	2	87	10	2.0	4.0	4.0	8.0	6/16	9/16
65	8	348	4	174	12	2.0	4.0	4.0	8.0	8/16	11/16
70	10	435	3	131	13	2.0	4.0	4.0	8.0	11/16	14/16
75	10	435	5	218	15	2.0	4.0	4.0	8.0	13/16	1
80	12	522	5	218	17	2.3	4.0	4.0	8.0	1 1/16	1 5/16
85	14	610	5	218	19	2.6	4.0	4.0	8.0	1 6/16	1 10/16
90	16	697	5	218	21	2.8	4.0	4.0	8.0	1 11/16	1 15/16
95	16	697	8	348	24	2.8	4.0	4.0	8.0	2 1/16	2 5/16
100	16	697	10	435	26	2.8	4.0	4.0	9.0	2 5/16	2 6/16
105	18	784	11	479	29	2.9	5.0	5.0	9.0	2 12/16	2 14/16

W41DG5

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
50	6	261	3	131	9	2.0	4.0	4.0	8.0	4/16	6/16
55	6	261	4	174	10	2.0	4.0	4.0	8.0	5/16	7/16
60	8	348	4	174	12	2.0	4.0	4.0	8.0	8/16	11/16
65	10	435	4	174	14	2.0	4.0	4.0	8.0	11/16	1
70	10	435	5	218	15	2.0	4.0	4.0	8.0	12/16	1 1/16
75	12	522	6	261	18	2.3	4.0	4.0	8.0	1 1/16	1 8/16
80	14	610	6	261	20	2.6	4.0	4.0	8.0	1 6/16	1 13/16
85	16	697	6	261	22	2.8	4.0	4.0	8.0	1 11/16	2 3/16
90	18	784	7	305	25	2.9	4.0	4.0	8.0	2 2/16	2 12/16
95	16	697	12	522	28	2.8	5.2	5.2	10.0	2 6/16	2 15/16

W41DG6

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
50	8	348	2	87	10	2.0	4.0	4.0	8.0	5/16	8/16
55	8	348	4	174	12	2.0	4.0	4.0	8.0	7/16	11/16
60	10	435	4	174	14	2.0	4.0	4.0	8.0	10/16	1
65	12	522	4	174	16	2.3	4.0	4.0	8.0	13/16	1 4/16
70	12	522	6	261	18	2.3	4.0	4.0	8.0	1	1 8/16
75	12	522	8	348	20	2.3	4.0	4.0	8.0	1 3/16	1 12/16
80	14	610	9	392	23	2.6	4.0	4.0	8.0	1 9/16	2 4/16
85	14	610	12	522	26	2.6	4.0	4.0	10.0	1 15/16	2 12/16

Design Charts for W41DG Deck Bulb Tee Girder

Table 5-A-32

Concrete Strength: f'_c= 8.0 ksi f'_{ci} = 6.0 ksi

Prestressing Strands: f_{pu}= 270 ksi 0.6” diameter

W53DG4

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
60	6	261	2	87	8	2.0	4.0	4.0	8.0	3/16	4/16
65	8	348	1	44	9	2.0	4.0	4.0	8.0	5/16	6/16
70	8	348	3	131	11	2.0	4.0	4.0	8.0	6/16	8/16
75	8	348	4	174	12	2.0	4.0	4.0	8.0	7/16	8/16
80	10	435	3	131	13	2.0	4.0	4.0	8.0	9/16	10/16
85	10	435	5	218	15	2.0	4.0	4.0	8.0	11/16	11/16
90	12	522	5	218	17	2.3	4.0	4.0	8.0	14/16	15/16
95	14	610	4	174	18	2.6	4.0	4.0	8.0	1 1/16	1 1/16
100	14	610	6	261	20	2.6	4.0	4.0	8.0	1 3/16	1 3/16
105	16	697	6	261	22	2.8	4.0	4.0	8.0	1 8/16	1 7/16
110	16	697	8	348	24	2.8	4.0	4.0	8.0	1 11/16	1 8/16
115	18	784	8	348	26	2.9	4.0	4.0	8.0	2	1 12/16
120	18	784	11	479	29	2.9	4.0	4.0	10.0	2 5/16	2
125	20	871	11	479	31	3.2	4.0	4.0	10.0	2 11/16	2 3/16

W53DG5

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
60	8	348	1	44	9	2.0	4.0	4.0	8.0	4/16	6/16
65	8	348	3	131	11	2.0	4.0	4.0	8.0	6/16	8/16
70	10	435	2	87	12	2.0	4.0	4.0	8.0	7/16	10/16
75	10	435	4	174	14	2.0	4.0	4.0	8.0	9/16	13/16
80	12	522	3	131	15	2.3	4.0	4.0	8.0	11/16	14/16
85	12	522	5	218	17	2.3	4.0	4.0	8.0	13/16	1
90	14	610	5	218	19	2.6	4.0	4.0	8.0	1 1/16	1 5/16
95	16	697	5	218	21	2.8	4.0	4.0	8.0	1 5/16	1 10/16
100	16	697	7	305	23	2.8	4.0	4.0	8.0	1 8/16	1 12/16
105	18	784	8	348	26	2.9	4.0	4.0	8.0	1 14/16	2 5/16
110	20	871	8	348	28	3.2	4.0	4.0	8.0	2 3/16	2 9/16
115	20	871	11	479	31	3.2	4.0	4.0	8.0	2 9/16	2 15/16
120	20	871	13	566	33	3.2	4.5	4.5	10.0	2 13/16	3 1/16

W53DG6

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
60	8	348	3	131	11	2.0	4.0	4.0	8.0	5/16	8/16
65	10	435	2	87	12	2.0	4.0	4.0	8.0	7/16	10/16
70	10	435	4	174	14	2.0	4.0	4.0	8.0	8/16	13/16
75	12	522	4	174	16	2.3	4.0	4.0	8.0	11/16	1 1/16
80	14	610	4	174	18	2.6	4.0	4.0	8.0	14/16	1 5/16
85	14	610	6	261	20	2.6	4.0	4.0	8.0	1 1/16	1 8/16
90	16	697	6	261	22	2.8	4.0	4.0	8.0	1 5/16	1 13/16
95	18	784	6	261	24	2.9	4.0	4.0	8.0	1 9/16	2 2/16
100	18	784	9	392	27	2.9	4.0	4.0	8.0	1 14/16	2 8/16
105	20	871	9	392	29	3.2	4.0	4.0	8.0	2 3/16	2 14/16
110	20	871	12	522	32	3.2	5.5	5.5	10.0	2 8/16	3 3/16

Design Charts for W53DG Deck Bulb Tee Girder

Table 5-A-33

Concrete Strength: f'_c= 8.0 ksi f'_{ci} = 6.0 ksi
Prestressing Strands: f_{pu}= 270 ksi 0.6" diameter

W65DG4

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
70	8	348	1	44	9	2.0	4.0	4.0	8.0	4/16	5/16
75	8	348	2	87	10	2.0	4.0	4.0	8.0	4/16	5/16
80	8	348	3	131	11	2.0	4.0	4.0	8.0	5/16	5/16
85	10	435	3	131	13	2.0	4.0	4.0	8.0	7/16	8/16
90	10	435	4	174	14	2.0	4.0	4.0	8.0	8/16	8/16
95	12	522	3	131	15	2.3	4.0	4.0	8.0	10/16	9/16
100	12	522	5	218	17	2.3	4.0	4.0	8.0	12/16	11/16
105	14	610	4	174	18	2.6	4.0	4.0	8.0	14/16	11/16
110	16	697	4	174	20	2.8	4.0	4.0	8.0	1 1/16	15/16
115	16	697	6	261	22	2.8	4.0	4.0	8.0	1 4/16	1
120	18	784	6	261	24	2.9	4.0	4.0	8.0	1 8/16	1 4/16
125	18	784	8	348	26	2.9	4.0	4.0	8.0	1 10/16	1 5/16
130	20	871	8	348	28	3.2	4.0	4.0	8.0	1 15/16	1 8/16
135	22	958	8	348	30	3.5	4.0	4.0	8.0	2 3/16	1 11/16
140	22	958	10	435	32	3.5	4.0	4.0	8.0	2 6/16	1 11/16
145	22	958	14	610	36	3.5	6.0	5.5	10.0	2 12/16	2

W65DG5

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
70	8	348	2	87	10	2.0	4.0	4.0	8.0	4/16	6/16
75	10	435	1	44	11	2.0	4.0	4.0	8.0	6/16	7/16
80	10	435	3	131	13	2.0	4.0	4.0	8.0	7/16	9/16
85	10	435	4	174	14	2.0	4.0	4.0	8.0	8/16	9/16
90	12	522	4	174	16	2.3	4.0	4.0	8.0	10/16	12/16
95	14	610	4	174	18	2.6	4.0	4.0	8.0	13/16	1
100	14	610	5	218	19	2.6	4.0	4.0	8.0	14/16	1
105	16	697	5	218	21	2.8	4.0	4.0	8.0	1 2/16	1 4/16
110	18	784	5	218	23	2.9	4.0	4.0	8.0	1 5/16	1 8/16
115	20	871	5	218	25	3.2	4.0	4.0	8.0	1 9/16	1 13/16
120	20	871	8	348	28	3.2	4.0	4.0	8.0	1 14/16	2 1/16
125	22	958	8	348	30	3.5	4.0	4.0	8.0	2 2/16	2 5/16
130	22	958	10	435	32	3.5	4.0	4.0	8.0	2 6/16	2 6/16
135	22	958	12	522	34	3.5	4.0	4.0	9.0	2 10/16	2 7/16
140	22	958	15	653	37	3.5	5.1	4.5	10.0	2 14/16	2 10/16

W65DG6

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
70	10	435	2	87	12	2.0	4.0	4.0	8.0	6/16	9/16
75	10	435	3	131	13	2.0	4.0	4.0	8.0	6/16	9/16
80	12	522	3	131	15	2.3	4.0	4.0	8.0	9/16	12/16
85	12	522	4	174	16	2.3	4.0	4.0	8.0	10/16	13/16
90	14	610	4	174	18	2.6	4.0	4.0	8.0	12/16	1
95	16	697	4	174	20	2.8	4.0	4.0	8.0	15/16	1 5/16
100	18	784	4	174	22	2.9	4.0	4.0	8.0	1 3/16	1 9/16
105	18	784	6	261	24	2.9	4.0	4.0	8.0	1 5/16	1 12/16
110	20	871	6	261	26	3.2	4.0	4.0	8.0	1 9/16	2
115	20	871	9	392	29	3.2	4.0	4.0	8.0	1 14/16	2 6/16
120	22	958	9	392	31	3.5	4.0	4.0	8.0	2 2/16	2 9/16
125	22	958	12	522	34	3.5	4.0	4.0	8.0	2 7/16	2 15/16
130	22	958	14	610	36	3.5	5.4	5.0	10.0	2 11/16	3

Design Charts for W65DG Deck Bulb Tee Girder

Table 5-A-34

f'ci = 6.0 ksi, f'c = 9 ksi Strand diameter = 0.6" Grade 270 ksi low relaxation												
Girder Type	Girder Spacing (ft)	Span Length (ft)	Cast-in-Place Closures f'ci = 6.0 ksi f'c = 9.0 ksi	Spliced Post-Tensioned Girder								
				PT Ducts ~ Strands/Duct (Duct#4 @ Bottom)				Jacking Force** (kips)	Tendon Force after Seating** (kips)	Tendon Loss* (kips)	E1 (in)	E3 (in)
			Length (ft)	1	2	3	4					
WF74PTG Post-tensioned Before Slab Casting	6	170	2	-	22	22	22	2970	2680	730	36.4	12.7
	8	155	2	-	22	22	22	2970	2670	740	36.4	12.7
	10	140	2	-	22	22	22	2970	2650	760	36.4	12.7
	12	120	2	-	22	22	22	2970	2630	780	36.4	12.7
	14	100	2	-	22	22	22	2970	2590	815	36.4	12.7
WF74PTG Post-tensioned After Slab Casting	6	195	2	-	22	22	22	2960	2690	680	36.4	12.7
	8	185	2	-	22	22	22	2960	2710	680	36.4	12.7
	10	175	2	-	22	22	22	2960	2690	690	36.4	12.7
	12	165	2	-	22	22	22	2990	2720	700	36.4	12.7
	14	155	2	-	22	22	22	3020	2750	710	36.4	12.7
W83PTG Post-tensioned Before Slab Casting	6	185	2	11	22	22	22	3500	3160	850	33.8	14.5
	8	165	2	-	22	22	22	2985	2710	720	36.4	12.7
	10	155	2	-	22	22	22	2985	2700	730	36.4	12.7
	12	135	2	-	22	22	22	2985	2680	740	36.4	12.7
	14	115	2	-	22	22	22	2985	2620	810	36.4	12.7
W83PTG Post-tensioned After Slab Casting	6	*205	2	11	22	22	22	3500	3200	810	33.8	14.5
	8	200	2	11	22	22	22	3500	3210	800	33.8	14.5
	10	195	2	22	22	22	22	4000	3640	940	37.6	15.7
	12	185	2	22	22	22	22	4000	3640	940	37.6	15.7
	14	175	2	22	22	22	22	4000	3640	940	37.6	15.7
W95PTG Post-tensioned Before Slab Casting	6	200	2	11	22	22	22	3500	3150	860	46.1	14.5
	8	185	2	11	22	22	22	3500	3110	980	46.1	14.5
	10	175	2	11	22	22	22	3500	3130	880	46.1	14.5
	12	155	2	8	22	22	22	3360	2990	860	44.9	14.1
	14	135	2	-	22	22	22	3000	2630	810	59.0	12.7
W95PTG Post-tensioned After Slab Casting	6	235	2	11	22	22	22	3500	3210	800	46.1	14.5
	8	230	2	22	22	22	22	4000	3650	930	37.6	15.7
	10	215	2	22	22	22	22	4000	3640	940	37.6	15.7
	12	205	2	22	22	22	22	4000	3640	950	37.6	15.7
	14	190	2	22	22	22	22	4000	3630	960	37.6	15.7

Span Capability of Post-Tensioned Spliced I-Girders

Table 5-A-35

* Controlled by over-reinforced section (see LRFD Sec. 5.7.3.3)

** Total force calculated at jacking end of post-tensioned girder (rounded to the nearest 10)

Design Parameters:

- PGSplice V. 0.3
- WSDOT BDM LRFD design criteria
- No vertical or horizontal curve
- 2.0% roadway crown slope
- Interior Girder w/ barrier load (6 girder bridge)
- Only flexural service and strength checked; Lifting and hauling checks not necessarily satisfied
- Simple girder span lengths are CL bearing to CL bearing
- Slab f'c = 4.0 ksi
- Standard WSDOT "F" shape barrier
- Under normal exposure condition and 75% relative humidity
- Spans reported in 5'-0" increments
- Designs based on "normally" reinforced sections (c/de < 0.42 LRFD 5.7.3.3)
- Designs based on 22 strands/duct
- For 6'-10' girder spacing -- 7.5" slab
- For 12' girder spacing -- 8.0" slab
- For 14' girder spacing -- 8.75" slab
- Girders PT'd before slab pour are assumed to be PT'd adjacent to structure
- All spec checks at wet joints have been ignored. It isassumed that the designer can modify the wet joints to reach the required span as shown in the table. These modifications are outside the scope of this table.

Span Capability of Post-Tensioned Spliced I-Girders

Table 5-A-35 (Continued)

Girder Type	Girder Spacing (ft)	Span Length (ft)	End Segments	Middle Segment	Spliced Post-Tensioned Girder								
			No. of Straight Strands	No. of Straight Strands	PT Ducts ~ Strands/Duct (Duct #4 @ Bottom)				Jacking Force* (kips)	Tendon Force after Seating* (kips)	Tendon Loss* (kips)	E1 (in)	E3 (in)
					1	2	3	4					
U54PTG4	8	135	4	6	-	-	11	22	2904	2636	570	20.0	8.9
	14	150	4	14	-	2	22	22	4048	3708	760	31.5	10.1
U54PTG5	9	135	4	8	-	-	12	22	2992	2764	578	19.7	9.0
	15	150	4	14	-	6	22	22	4400	4032	826	29.8	10.9
U54PTG6	10	135	4	6	-	-	18	22	3520	3200	684	18.3	9.5
	16	145	4	14	-	8	22	22	4576	4196	852	29.0	11.2
U66PTG4	8	155	4	8	-	-	15	22	3256	2944	648	18.9	9.3
	14	170	4	16	-	7	22	22	4488	4088	864	29.4	11.0
U66PTG5	9	155	4	8	-	-	17	22	3432	3110	678	18.5	9.4
	15	170	4	16	-	10	22	22	4752	4334	910	29.3	11.3
U66PTG6	10	155	4	8	-	-	21	22	3784	3434	742	17.7	9.7
	16	165	4	14	-	12	22	22	4928	4500	940	27.7	11.7
U78PTG4	8	175	4	10	-	-	19	22	3608	3262	722	18.1	9.6
	16	190	4	20	-	15	22	22	5192	4718	1014	26.8	12.1
U78PTG5	9	180	4	10	-	2	22	22	4048	3692	776	31.5	10.1
	17	195	4	22	-	21	22	22	5720	5202	1110	25.2	12.6
U78PTG6	10	180	4	10	-	6	22	22	4400	4018	840	29.8	10.9
	18	190#	4	20	2	22	22	22	5896	5400	1104	395.0	12.9

Span Capability of Post-Tensioned Spliced Tub Girders
Table 5-A-36


* Total force calculated at jacking end of post-tensioned girder

Span capability exceeds maximum shipping weight of 200 kips

Design Parameters:


- PGSplice V. 0.3
- WSDOT BDM LRFD design criteria
- No vertical or horizontal curve
- 2.0% roadway crown slope
- Interior Girder w/ barrier load (6 girder bridge)
- Only flexural service and strength checked; Lifting and hauling checks not necessarily satisfied
- Simple girder span lengths are CL bearing to CL bearing
- Standard WSDOT “F” shape barrier
- Under normal exposure condition and 75% humidity
- Spans reported in 5’-0” increments
- ”A” dimension = deck thickness + 2”
- Closure Pour for spliced girders is 2 ft,
  f’ci = 6.0 ksi, f’c = 9 ksi
- Girder f’ci = 6.0 ksi, f’c = 9.0 ksi, slab f’c = 4.0 ksi
- Girders are spliced in-place after slab is cast
- Prestressing and post-tensioning steel is 0.6” diameter, Grade 270
- End segments are 25% of total length, center segment is 50% of total length
- Range of applicability requirements in LRFD ignored; span lengths may be longer than allowed by LRFD
- Designs are based on a 22 diameter strand limit per 4” duct for high pressure grout
- All spec checks at wet joints have been ignored. It is assumed that the designer can modify the wet joints to reach the required span as shown in the table. These modifications are outside the scope of this table.

Span Capability of Post-tensioned Spliced Tub Girders
Table 5-A-36 (Continued)



PRECAST PRESTRESSED I-GIRDERS


I-Girder Sections
Figure 5-A-37




PRECAST PRESTRESSED WIDE FLANGE GIRDERS

Wide Flange I-Girder Sections


Figure 5-A-38



WBT32G




WBT38G




WBT62G


Bulb Tee Girder Sections
Figure 5-A-39




WFBT32G



WFBT38G




WFBT50G




WFBT62G

Wide Flange Bulb Tee Girder Sections

Figure 5-A-40




Trapezodial Tub Girder Sections
Figure 5-A-41




Trapezoidal Tub Girder with Top Flange Sections


Figure 5-A-42




W35DG



W41DG




W53DG




W65DG


Deck Blub Tee Girder Section
Figure 5-A-43



1'-0" DEEP SLAB




1'-6" DEEP SLAB




2'-2" DEEP SLAB

Precast Prestressed Slab Sections
Figure 5-A-44



DOUBLE-TEE GIRDERS



RIBBED GIRDERS

W	NOMINAL WIDTH *
4'-0"	9'-0"
5'-0"	10'-0"
6'-0"	11'-0"

D (IN)	W1 (IN)
20	7½
24	7¼
28	7
32	6¾
36	6½


* COULD BE VARIED TO MEET SUPERSTRUCTURE WIDTH

NOMINAL WIDTH*	B*
4'-0"	1⅛"
5'-0"	7⅛"
6'-0"	1'-1⅛"


* COULD BE VARIED TO MEET SUPERSTRUCTURE WIDTH

PRECAST PRESTRESSED DOUBLE-TEE AND RIBBED DECK GIRDERS


Double Tee and Ribbed Deck Girder Sections
Figure 5-A-45



WF74PTG




W83PTG




W95PTG

PRECAST POST-TENSIONED SPLICED I-GIRDERS

Spliced I-Girders Sections
Figure 5-A-46



POST-TENSIONED TRAPEZOIDAL TUB SECTION




POST-TENSIONED TRAPEZOIDAL TUB SECTION
FOR S-I-P DECK PANEL

* 1'-0" FOR BOTTOM FLANGE WIDTH LESS THAN 5'-6"
2'-0" FOR BOTTOM FLANGE WIDTH EQUAL OR GREATER THAN 5'-6"

PRECAST POST-TENSIONED SPLICE TUB GIRDERS

Spliced Trapeziodal Tub Girders Sections
Figure 5-A-47




NOTE TO DESIGNER

THIS STANDARD IS APPLICABLE TO SINGLE SPAN PRESTRESSED CONC. GIRDERS ONLY

CONSTRUCTION SEQUENCE ~ SUPERSTRUCTURE

Single Span Prestressed Girder Construction Sequence

Figure 5-A-48




CONSTRUCTION SEQUENCE ~ PRECAST SUPERSTRUCTURE

NOTE TO DESIGNER

THIS STANDARD IS APPLICABLE TO MULTIPLE SPAN PRESTRESSED CONCRETE GIRDERS ONLY

Multiple Span Prestressed Girder Construction Sequence

Figure 5-A-49




NOTE TO DESIGNER

THIS STANDARD IS APPLICABLE TO MULTIPLE SPAN PRESTRESSED CONCRETE TUB GIRDERS ONLY


Single Span Prestressed Girder Construction Sequence

Figure 5-A-50



FOR STUB ABUTMENT PIER WITH END DIAPHRAGMS CAST ON GIRDER END

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE INSERT OR APPROVED EQUAL. (TYP.)




OPEN HOLE

BOTTOM HOLE AT END TYPE "B" ONLY


NOTES

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING ALL GIRDERS.
4. THE GIRDERS MAY NEED TO BE BRACED LATERALLY DURING SHIPPING TO PREVENT TIPPING OR BUCKLING.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
6. IF THE LIFTING LOOPS EXTEND WITHIN 3" OF THE TOP OF THE ROADWAY SLAB, THEY SHALL BE CUT OFF PRIOR TO PLACING THE ROADWAY SLAB. ALL LIFTING STRANDS SHALL BE OF THE SAME MATERIAL AND STRENGTH AS THE PRESTRESSING STRANDS. WRAP THE LIFTING LOOPS SO THAT EACH STRAND WILL CARRY ITS SHARE OF THE TOTAL LOAD. EXTEND LIFTING LOOPS ENDING WITH A 9" LONG 90° HOOK TO WITHIN 3" CLEAR OF THE BOTTOM OF THE GIRDER.
7. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
9. ALL STRANDS SHALL BE ½ " OR 0.6" ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
10. FOR SAWTOOTH DETAIL SEE W42G GIRDER DETAILS 2 OF 2.




TYPICAL END ELEVATION

END TYPE C SHOWN, OTHER END TYPES SIMILAR.



VIEW B

SAWTEETH SHOWN BY SHADED AREA



SECTION C

DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0"	0"	0"	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO

TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE


ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	4	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	#
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	4	STR.

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)

NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"

* = VARIES FOR SKEWED SPANS




hash marks

\# #3 OR #4 MAY BE SUBSTITUTED. FIELD BEND IS OPTIONAL.

** SHALL BE CHECK FOR THE EFFECT OF RDWY VERTICAL CURVE


W42G Girder Details 1 of 2

Figure 5-A-51




STRAND PATTERN AT GIRDER END


HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1) , (2) ETC.



STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1) , (2) ETC.






SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - W42G GIRDER DETAILS 1 OF 2

GIRDER SCHEDULE


DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C KSI	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI KSI	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS E	LOCATION OF C.G. STRANDS F℄	LOCATION OF C.G. STRANDS Fb	LOCATION OF C.G. STRANDS Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




TRANSVERSE REINFORCING SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN




ELEVATION



PLAN - BEARING RECESS & BOTTOM FLANGE SPALL PROTECTION



ALTERNATE #1



ALTERNATE #2


STRAND EXTENSION DETAIL

NOTES TO DESIGNER:


This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.

W42G Girder Details 2 of 2

Figure 5-A-52




TYPICAL END DIAPHRAGM




SECTION F

NOTE TO DESIGNER


If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.




ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS





END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.

NOTE:


GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.

W42G End Diaphragm on Girder Details

Figure 5-A-53




TYPICAL END TYPE "B" DIAPHRAGM AT END PIERS




SECTION A


** DISTANCE FROM TOP OF GIRDER TO BOTTOM OF DIAPHRAGM + "A"



ANCHOR DETAIL

A.S.T.M. A-307





ROADWAY EXPANSION JOINT AT END PIERS


LONGITIDINAL DIMENSIONS ARE NORMAL TO SKEW

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".


W42G Abutment Type Pier Diaphragm Details

Figure 5-A-54



PLAN - FIXED FLUSH-FACE DIAPHRAGM

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET




NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.


CONSTRUCTION SEQUENCE

1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



TYPICAL FIXED FLUSH-FACE DIAPHRAGM






OAK BLOCK DETAIL


W42G Fixed Flush-Face Diaphragm at Intermediate Pier Details

Figure 5-A-55



PLAN - FIXED RECESSED-FACE DIAPHRAGM

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET



SECTION A


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



TYPICAL FIXED RECESSED-FACE DIAPHRAGM




DETAIL B



OAK BLOCK DETAIL


W42G Fixed Recessed-Face Diaphragm at Intermediate Pier Details

Figure 5-A-56




PLAN - HINGE DIAPHRAGM


10° MAX. SKEW FOR HINGE DIAPHRAGM.
* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET



HINGE BAR PLAN




SECTION A



TYPICAL HINGE SECTION

** FOR SAWTOOTH SHEAR KEY DETAILS, SEE GIRDER SHEETS.



TYP. END VIEW
HINGE DIAPHRAGM


NOTES TO DESIGNER

Hinge bar plan is shown for designer. The actual hinge bars shall be located along the ℄ pier on the crossbeam details sheet, for final contract plans. The hinge bars shall be deleted from this sheet prior to the award copy of the contract plans.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by the oak block location.

W42G Hinged Diaphragm at Intermediate Pier Details


Figure 5-A-57



TYPICAL INTERMEDIATE DIAPHRAGM



SECTION B



ANCHOR DETAIL


A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".

W42G Intermediate Diaphragm Details


Figure 5-A-58




SECTION G

NOTE:

1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.




GROUT PAD ELEVATION



ELASTOMERIC STOP PAD


DUROMETER HARDNESS = 60



BEARING PAD

LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60


(30 DEG. SKEW ANGLE SHOWN)




GROUT PAD DETAIL

W42G Miscelleneous Diaphragm Details

Figure 5-A-59




TYPICAL END TYPE "B" DIAPHRAGM AT END PIERS




ANCHOR DETAIL

A.S.T.M. A-307




BEARING PAD DETAILS AT INTERMEDIATE PIERS




SECTION A

** DISTANCE FROM TOP OF GIRDER TO BOTTOM OF DIAPHRAGM + "A"



SECT. THRU END DIAPH. EXTERIOR GIRDER AT INTERMEDIATE PIERS

LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.
NOT TO BE USED WITH SERIES W83G & W95G GIRDERS.
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A."



≠ INCREASE THIS DIMENSION FOR BRIDGES ON SAG VERTICAL CURVES TO MAINTAIN 1½" BETWEEN GIRDER ENDS

SECT. THRU END DIAPH. INTERIOR GIRDER AT INTERMEDIATE PIERS


LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.
NOT TO BE USED WITH SERIES W83G & W95G GIRDERS.
SEE "GIRDER DETAILS" FOR DIMENSION "A."

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".


Multiple Simple Spans Intermediate Pier Details

Figure 5-A-60



GIRDER ELEVATION

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅛") FERRULE OR APPROVED EQUAL. (TYP.)




OPEN HOLE

BOTTOM HOLE AT END TYPE "B" ONLY


NOTES

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING ALL GIRDERS.
4. THE GIRDERS MAY NEED TO BE BRACED LATERALLY DURING SHIPPING TO PREVENT TIPPING OR BUCKLING.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
6. IF THE LIFTING LOOPS EXTEND WITHIN 3" OF THE TOP OF THE ROADWAY SLAB, THEY SHALL BE CUT OFF PRIOR TO PLACING THE ROADWAY SLAB. ALL LIFTING STRANDS SHALL BE OF THE SAME MATERIAL AND STRENGTH AS THE PRESTRESSING STRANDS. WRAP THE LIFTING LOOPS SO THAT EACH STRAND WILL CARRY ITS SHARE OF THE TOTAL LOAD. EXTEND LIFTING LOOPS ENDING WITH A 9" LONG 90° HOOK TO WITHIN 3" CLEAR OF THE BOTTOM OF THE GIRDER.
7. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
9. ALL STRANDS SHALL BE ½ " OR 0.6" ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
10. FOR SAWTOOTH DETAIL SEE W50G GIRDER DETAILS 2 OF 2.




TYPICAL END ELEVATION

END OF TYPE C SHOWN, OTHER END TYPES SIMILAR



VIEW B

SAWTEETH SHOWN BY SHADED AREA



SECTION C

DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0"	0"	0"	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULT. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO


TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	4	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	≠
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	4	STR.

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)

NOTE: FOR DIM. "A", SEE GIRDER SCHEDULE




≠ #3 OR #4 MAY BE SUBSTITUTED. FIELD BEND IS OPTIONAL.

** SHALL BE CHECKED FOR THE EFFECT OF RDWY VERTICAL CURVE


W50G Girder Details 1 of 2

Figure 5-A-61




STRAND PATTERN AT GIRDER END


HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.






SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - W50G GIRDER DETAILS 1 OF 2

GIRDER SCHEDULE


DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C KSI	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI KSI	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS E	LOCATION OF C.G. STRANDS F℄	LOCATION OF C.G. STRANDS Fb	LOCATION OF C.G. STRANDS Fo	C (IN.)	D (IN.)	La (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




TRANSVERSE REINFORCING SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN




ELEVATION



PLAN - BEARING RECESS AND BOTTOM FLANGE SPALL PROTECTION



ALTERNATE #1



ALTERNATE #2


STRAND EXTENSION DETAIL

NOTES TO DESIGNER:


This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.

W50G Girder Details 2 of 2

Figure 5-A-62




TYPICAL END DIAPHRAGM




SECTION F

 # NOTE TO DESIGNER


If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.



ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS



END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.

NOTE:


GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.

W50G End Diaphragm on Girder Details

Figure 5-A-63



TYPICAL END TYPE "B" DIAPHRAGM AT END PIERS





ANCHOR DETAIL


A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".








ROADWAY EXPANSION JOINT AT END PIERS

LONGITIDINAL DIMENSIONS ARE NORMAL TO SKEW


W50G Abutment Type Pier Diaphragm Details

Figure 5-A-64



PLAN - FIXED FLUSH-FACE DIAPHRAGM

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET



SECTION A


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



TYPICAL FIXED FLUSH-FACE DIAPHRAGM




DETAIL B



OAK BLOCK DETAIL


W50G Fixed Flush-Face Diaphragm at Intermediate Pier Details

Figure 5-A-65



PLAN - FIXED RECESSED-FACE DIAPHRAGM


* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET




SECTION A

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



TYPICAL FIXED RECESSED-FACE DIAPHRAGM



DETAIL B



OAK BLOCK DETAIL


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.

Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.


W50G Fixed Recessed-Face Diaphragm at Intermediate Pier Details

Figure 5-A-66





PLAN - HINGE DIAPHRAGM

10° MAX. SKEW FOR HINGE DIAPHRAGM.
* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET




HINGE BAR PLAN





TYPICAL HINGE SECTION

** FOR SAWTOOTH SHEAR KEY DETAILS, SEE GIRDER SHEETS.



TYP. END VIEW
HINGE DIAPHRAGM


NOTES TO DESIGNER

Hinge bar plan is shown for designer. The actual hinge bars shall be located along the ℄ pier on the crossbeam details sheet, for final contract plans. The hinge bars shall be deleted from this sheet prior to the award copy of the contract plans.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by the oak block location.

W50G Hinged Diaphragm at Intermediate Pier Details


Figure 5-A-67



TYPICAL INTERMEDIATE DIAPHRAGM



SECTION B



ANCHOR DETAIL


A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".


W50G Intermediate Diaphragm Details

Figure 5-A-68




NOTE:

1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.




GROUT PAD ELEVATION



ELASTOMERIC STOP PAD


DUROMETER HARDNESS = 60



BEARING PAD

LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60

(SKEW ANGLE SHOWN @ 30°)




GROUT PAD DETAIL

(SKEW ANGLE SHOWN @ 30°)

W50G Miscelleneous Diaphragm Details


Figure 5-A-69



GIRDER ELEVATION

NOTES:


1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING ALL GIRDERS
4. THE GIRDERS MAY NEED TO BE BRACED LATERALLY DURING SHIPPING TO PREVENT TIPPING OR BUCKLING.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
6. IF THE LIFTING LOOPS EXTEND WITHIN 3" OF THE TOP OF THE ROADWAY SLAB, THEY SHALL BE CUT OFF PRIOR TO PLACING THE ROADWAY SLAB. ALL LIFTING STRANDS SHALL BE OF THE SAME MATERIAL AND STRENGTH AS THE PRESTRESSING STRANDS. WRAP THE LIFTING LOOPS SO THAT EACH STRAND WILL CARRY ITS SHARE OF THE TOTAL LOAD. EXTEND LIFTING LOOPS ENDING WITH A 9" LONG 90° HOOK TO WITHIN 3" CLEAR OF THE BOTTOM OF THE GIRDER.
7. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
9. ALL STRANDS SHALL BE ½ " OR 0.6" ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
10. FOR SAWTOOTH DETAIL SEE W58G GIRDER DETAILS 2 OF 3.
11. TEMPORARY STRANDS ARE PRETENSIONED OR POST-TENSIONED. IF PRETENSIONED, THESE TEMPORARY STRANDS SHALL BE UNBONDED OVER ALL BUT THE END 10'-0" OF THE GIRDER LENGTH. AS AN ALTERNATE, TEMPORARY STRANDS MAY BE POST-TENSIONED BEFORE THE GIRDER IS LIFTED FROM THE FORM. TEMPORARY STRANDS SHALL BE CUT BEFORE INTERMEDIATE DIAPHRAGMS ARE CAST.



TYPICAL END ELEVATION


END TYPE C SHOWN, OTHER END TYPES SIMILAR

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE OR APPROVED EQUAL. (TYP.)



VIEW B

SAWTEETH SHOWN BY SHADED AREA.



SECTION C

DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" Abutment	B	YES	0"	0"	0"	NO
HINGE DIAPH. @ INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO

TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE


ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G4)
B2 = 3" (G5)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	4	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	≠
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	5	STR.

≠ #3 OR #4 MAY BE SUBSTITUTED. FIELD BENDING IS OPTIONAL.

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)


NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"



** SHALL BE CHECKED FOR THE EFFECT OF RDWY VERTICAL CURVE


W58G Girder Details 1 of 3

Figure 5-A-70




STRAND PATTERN AT GIRDER END

HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



ELEVATION




SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - W58G GIRDER DETAILS 1 OF 3

GIRDER SCHEDULE


DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ_1	θ_2	P_1	P_2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	LOCATION OF C.G. STRANDS (IN.) F℄	LOCATION OF C.G. STRANDS (IN.) Fb	LOCATION OF C.G. STRANDS (IN.) Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




TRANSVERSE REINFORCING SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN




ELEVATION




PLAN - BEARING RECESS & BOTTOM

W58G Girder Details 2 of 3
Figure 5-A-71




ALTERNATE #1



ALTERNATE #2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS



ALTERNATE #3

NOTES TO DESIGNER:

1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.


2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.

3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor. The total number of extended strands shall not be less than:


$$Nps = 12(Mc + Vc \times h - M_{SIDL}) \times Nc \times \frac{K}{Ng} \quad \frac{}{(0.9 \; Aps \times fps \times d)}$$

where:

Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = nember of girders
Aps = area of each extended strand, in^2
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2



TEMPORARY STRAND BLOCKOUT DETAIL




ANCHOR PLATE DETAIL


(MOVE NOTE TO SLAB SECTION SHEET)

TEMPORARY STRAND CUTTING SEQUENCE

1. ERECT AND BRACE GIRDERS.
2. REMOVE EXPANDED POLYSTYRENE IN 2" X 2" RECESSES IN TOP FLANGE OF GIRDERS.
3. CUT STRAND AND PLASTIC SLEEVE IN 2" X 2" RECESS.
4. REMOVE ALL MOISTURE IN RECESS PRIOR TO FILLING RECESS WITH GROUT.
5. CAST INTERMEDIATE & END DIAPHRAGMS.
6. PLACE DECK CONCRETE.




STRAND PATTERN AT GIRDER END



PLAN VIEW OF TEMPORARY STRANDS

W58G Girder Details 3 of 3


Figure 5-A-72




NOTE TO DESIGNER

If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.


TYPICAL END DIAPHRAGM




SECTION F



ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS




END DIAPHRAGM GEOMETRY

SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.


NOTE:


GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.

W58G End Diaphragm on Girder Details
Figure 5-A-73




TYPICAL END TYPE "B" DIAPHRAGM AT END PIERS






ANCHOR DETAIL

A.S.T.M. A-307





ROADWAY EXPANSION JOINT AT END PIERS


LONGITIDINAL DIMENSIONS ARE NORMAL TO SKEW

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".


W58G Abutment Type Pier Diaphragm Details

Figure 5-A-74



PLAN - FIXED FLUSH-FACE DIAPHRAGM

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET



SECTION A


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



TYPICAL FIXED FLUSH-FACE DIAPHRAGM




DETAIL B



OAK BLOCK DETAIL


W58G Fixed Flush-Face Diaphragm at Intermediate Pier Details

Figure 5-A-75



PLAN - FIXED RECESSED-FACE DIAPHRAGM

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET



SECTION A


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



TYPICAL FIXED RECESSED-FACE DIAPHRAGM




DETAIL B



OAK BLOCK DETAIL


W58G Fixed Recessed-Face Diaphragm at Intermediate Pier Details


Figure 5-A-76




PLAN - HINGE DIAPHRAGM

10° MAX. SKEW FOR HINGE DIAPHRAGM.
* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET






HINGE BAR PLAN




SECTION A



TYPICAL HINGE SECTION

** FOR SAWTOOTH SHEAR KEY DETAILS, SEE GIRDER SHEETS.



TYP. END VIEW HINGE DIAPHRAGM


NOTES TO DESIGNER

Hinge bar plan is shown for designer. The actual hinge bars shall be located along the ℄ pier on the crossbeam details sheet, for final contract plans. The hinge bars shall be deleted from this sheet prior to the award copy of the contract plans.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated

W58G Hinge Diaphragm at Intermediate Pier Details


Figure 5-A-77



TYPICAL INTERMEDIATE DIAPHRAGM



SECTION B



ANCHOR DETAIL


A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".

W58G Intermediate Diaphragm Details


Figure 5-A-78




SECTION G

NOTE:

1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.




GROUT PAD ELEVATION



ELASTOMERIC STOP PAD


DUROMETER HARDNESS = 60



BEARING PAD

LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60

(SKEW ANGLE SHOWN @ 30°)




GROUT PAD DETAIL

(SKEW ANGLE SHOWN @ 30°)
(SHOWN FOR END DIAPHRAGM ON GIRDER)


W58G Miscelleneous Diaphragm Details


Figure 5-A-79




NOTES

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING ALL GIRDERS.
4. THE GIRDERS MAY NEED TO BE BRACED LATERALLY DURING SHIPPING TO PREVENT TIPPING OR BUCKLING.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
6. IF THE LIFTING LOOPS EXTEND WITHIN 3" OF THE TOP OF THE ROADWAY SLAB, THEY SHALL BE CUT OFF PRIOR TO PLACING THE ROADWAY SLAB. ALL LIFTING STRANDS SHALL BE OF THE SAME MATERIAL AND STRENGTH AS THE PRESTRESSING STRANDS. WRAP THE LIFTING LOOPS SO THAT EACH STRAND WILL CARRY ITS SHARE OF THE TOTAL LOAD. EXTEND LIFTING LOOPS ENDING WITH A 9" LONG 90° HOOK TO WITHIN 3" CLEAR OF THE BOTTOM OF THE GIRDER.
7. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN. EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
9. ALL STRANDS SHALL BE ½ " OR 0.6" ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
10. FOR SAWTOOTH DETAIL SEE W74G GIRDER DETAILS 2 OF 3.
11. TEMPORARY STRANDS ARE PRETENSIONED OR POST-TENSIONED. IF PRETENSIONED, THESE TEMPORARY STRANDS SHALL BE UNBONDED OVER ALL BUT THE END 10'-0" OF THE GIRDER LENGTH. AS AN ALTERNATE, TEMPORARY STRANDS MAY BE POST-TENSIONED BEFORE THE GIRDER IS LIFTED FROM THE FORM. TEMPORARY STRANDS SHALL BE CUT BEFORE INTERMEDIATE DIAPHRAGMS ARE CAST.







TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0"	0"	0"	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULT. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO


MARK	LOCATION	SIZE	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
G1	GIRDER STIRRUPS	5	NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5 STR.	
G4	GIRDER LONGIT., FULL LENGTH	5 STR.	
G5	GIRDER END LONGIT.	7 STR.	
G6	GIRDER END TIES	W12 #	
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6 STR.	

\# #3 OR #4 MAY BE SUBSTITUTED. FIELD BENDING IS OPTIONAL.

** SHALL BE CHECKED FOR THE EFFECT OF RDWY VERTICAL CURVE


W74G Girder Details 1 of 3

Figure 5-A-80




STRAND PATTERN AT GIRDER END


HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



STRAND PATTERN AT ℄ SPAN


STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.





SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - W74G GIRDER DETAILS 1 OF 3




TRANSVERSE REINFORCING SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN

GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS =				BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)																				
SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ 1	θ 2	P 1	P 2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH		HARPED		STRAIGHT		TEMPORARY		LOCATION OF C.G. STRANDS (IN.)				C (IN.)	D (IN.)	Ld (IN.)
										@ FINAL F'C (KSI)	@ RELEASE F'CI (KSI)	NO. OF STRANDS	JACKING FORCE (KIPS)	NO. OF STRANDS	JACKING FORCE (KIPS)	NO. OF STRANDS	JACKING FORCE (KIPS)	E	F℄	Fb	Fo			
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




ELEVATION




PLAN - BEARING RECESS & BOTTOM FLANGE SPALL PROTECTION

W74G Girder Details 2 of 3


Figure 5-A-81



ALTERNATE #1



ALTERNATE #2



ALTERNATE #3

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS

NOTES TO DESIGNER:

1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.

3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor. The total number of extended strands shall not be less than:


$$Nps = 12(Mc + Vc \times h - M_{SIDL}) \times \frac{Nc}{Ng} \times \frac{K}{(0.9\ Aps \times fps \times d)}$$

where:
Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = nember of girders
Aps = area of each extended strand, in ^{2}
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2


(MOVE NOTE TO SLAB SECTION SHEET)

TEMPORARY STRAND CUTTING SEQUENCE


1. ERECT AND BRACE GIRDERS.
2. REMOVE EXPANDED POLYSTYRENE IN 2" X 2" RECESSES IN TOP FLANGE OF GIRDERS.
3. CUT STRAND AND PLASTIC SLEEVE IN 2" X 2" RECESS.
4. REMOVE ALL MOISTURE IN RECESS PRIOR TO FILLING RECESS WITH GROUT.
5. CAST INTERMEDIATE & END DIAPHRAGMS.
6. PLACE DECK CONCRETE.




TEMPORARY STRAND BLOCKOUT DETAILS



ANCHOR PLATE DETAIL




STRAND PATTERN AT GIRDER END




PLAN VIEW OF TEMPORARY STRANDS

W74G Girder Details 3 of 3

Figure 5-A-82






SECTION F


TYPICAL END DIAPHRAGM

NOTE TO DESIGNER


If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.




ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS





END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.

NOTE:


GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.


W74G End Diaphragm on Girder Details

Figure 5-A-83



TYPICAL END TYPE "B" DIAPHRAGM AT END PIERS






ANCHOR DETAIL

A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".




ROADWAY EXPANSION JOINT AT END PIERS

LONGITIDINAL DIMENSIONS ARE NORMAL TO SKEW


W58G Abutment Type Pier Diaphragm Details

Figure 5-A-84



PLAN - FIXED FLUSH-FACE DIAPHRAGM

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET



SECTION A


NOTES TO DESIGNER

FIXED BAR PLAN IS SHOWN FOR DESIGNER. THE ACTUAL FIXED BARS SHALL BE LOCATED ALONG THE ℄ PIER ON THE CROSSBEAM DETAILS SHEET FOR FINAL CONTRACT PLANS.


OAK BLOCK WEDGES SHALL BE SHOWN ON CROSSBEAM PLAN SHEET, PARALLEL TO THE ℄ PIER IF SKEWED. CROSSBEAM WIDTH IS DICTATED BY OAK BLOCK LOCATION.

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



DETAIL B




TYPICAL FIXED FLUSH-FACE DIAPHRAGM



OAK BLOCK DETAIL


W58G Fixed Flush-Face Diaphragm at Intermediate Pier Details

Figure 5-A-85



PLAN - FIXED RECESSED-FACE DIAPHRAGM


* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET




SECTION A

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



TYPICAL FIXED RECESSED-FACE DIAPHRAGM



DETAIL B



OAK BLOCK DETAIL


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.

Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.


W58G Fixed Recessed-Face Diaphragm at Intermediate Pier Details


Figure 5-A-86




PLAN - HINGE DIAPHRAGM

10° MAX. SKEW FOR HINGE DIAPHRAGM.
* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET






HINGE BAR PLAN




SECTION A



* MIN. LENGTH OF EXTENDED STRANDS = 2'-0" (BEND EXCESS)

TYPICAL HINGE SECTION

** FOR SAWTOOTH SHEAR KEY DETAILS, SEE GIRDER SHEETS.



TYP. END VIEW HINGE DIAPHRAGM


NOTES TO DESIGNER

Hinge bar plan is shown for designer. The actual hinge bars shall be located along the ℄ pier on the crossbeam details sheet, for final contract plans. The hinge bars shall be deleted from this sheet prior to the award copy of the contract plans.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by the oak block location.


W58G Hinge Diaphragm at Intermediate Pier Details

Figure 5-A-87



TYPICAL INTERMEDIATE DIAPHRAGM





ANCHOR DETAIL


A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".

W58G Intermediate Diaphragm Details


Figure 5-A-88




SECTION G

NOTE:

1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.




GROUT PAD ELEVATION



ELASTOMERIC STOP PAD


DUROMETER HARDNESS = 60



BEARING PAD

LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60

(SKEW ANGLE SHOWN @ 30°)




GROUT PAD DETAIL

(SKEW ANGLE SHOWN @ 30°)
(SHOWN FOR END DIAPHRAGM ON GIRDER)


W58G Miscelleneous Diaphragm Details

Figure 5-A-89



GIRDER ELEVATION

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE INSERT OR APPROVED EQUAL. (TYP.)




OPEN HOLE

BOTTOM HOLE AT END TYPE "B" ONLY


NOTES:

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6"ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6.02.3(25)H OF THE STANDARD SPECIFICATIONS
6. LIFTING BARS SHALL BE 1⅜"ø HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM.) LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGRESS OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING. ONCE ERECTED, ALL GIRDERS SHALL BE BRACED TO PREVENT TIPPING UNTIL THE INTERMEDIATE DIAPHRAGMS ARE CAST AND CURED.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
9. FOR SAWTOOTH DETAILS SEE WF42G GIRDER DETAILS 2 OF 3.
10. TEMPORARY STRANDS ARE PRETENSIONED OR POST-TENSIONED. IF PRETENSIONED, THESE TEMPORARY STRANDS SHALL BE UNBONDED OVER ALL BUT THE END 10'-0" OF THE GIRDER LENGTH. AS AN ALTERNATE, TEMPORARY STRANDS MAY BE POST-TENSIONED BEFORE THE GIRDER IS LIFTED FROM THE FORM. TEMPORARY STRANDS SHALL BE CUT AFTER ALL GIRDERS ARE ERECTED, BUT BEFORE INTERMEDIATE DIAPHRAGMS ARE CAST.




TYPICAL END ELEVATION

END TYPE C SHOWN, OTHER END TYPES SIMILAR.



VIEW B

SAWTEETH SHOWN BY SHADED AREA.



SECTION C


DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0"	0"	0"	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO

TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½" (G4 , G9)
B2 = 3" (G5)

MARK	LOCATION	SIZE	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	#
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6	STR.


NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"



# indicates #3 OR #4 MAY BE SUBSTITUTED. FIELD BENDING IS OPTIONAL. ** SHALL BE CHECKED FOR EFFECT OF RDWY VERTICAL CURVE


WF42G GIRDER DETAILS 1 OF 3

Figure 5-A-90




STRAND PATTERN AT GIRDER END


HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



STRAND PATTERN AT ℄ SPAN


STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.





SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - WF74G GIRDER DETAILS 1 OF 3




TRANSVERSE REINFORCING SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN


GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE FCI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	F℄	Fb	Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




ELEVATION




PLAN - BEARING RECESS AND BOTTOM FLANGE SPALL PROTECTION DETAIL

WF42G GIRDER DETAILS 2 OF 3

Figure 5-A-91




ALTERNATE #1



ALTERNATE #2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS



ALTERNATE #3

NOTES TO DESIGNER:


1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.


3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor. The total number of extended strands shall not be less than:

$$Nps = 12(Mc + Vc \times h - M_{SIDL}) \times Nc \times \frac{K}{Ng} \quad \frac{}{(0.9\ Aps \times fps \times d)}$$


where:
Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = nember of girders
Aps = area of each extended strand, in²
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2



TEMPORARY STRAND BLOCKOUT DETAIL



ANCHOR PLATE DETAIL




STRAND PATTERN AT GIRDER END

(MOVE NOTE TO SLAB SECTION SHEET)

TEMPORARY STRAND CUTTING SEQUENCE


1. ERECT AND BRACE GIRDERS.
2. REMOVE EXPANDED POLYSTYRENE IN 2" X 2" RECESSES IN TOP FLANGE OF GIRDERS.
3. CUT STRAND AND PLASTIC SLEEVE IN 2" X 2" RECESS.
4. REMOVE ALL MOISTURE IN RECESS PRIOR TO FILLING RECESS WITH GROUT.
5. CAST INTERMEDIATE & END DIAPHRAGMS.
6. PLACE DECK CONCRETE.



PLAN VIEW OF TEMPORARY STRANDS


WF42G GIRDER DETAILS 3 OF 3

Figure 5-A-92



GIRDER ELEVATION

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE OR APPROVED EQUAL. (TYP.)




OPEN HOLE

BOTTOM HOLE AT END TYPE "B" ONLY


NOTES:

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6"ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6.02.3(25)H OF THE STANDARD SPECIFICATIONS
6. LIFTING BARS SHALL BE 1⅜"ø HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM.) LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGRESS OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING. ONCE ERECTED, ALL GIRDERS SHALL BE BRACED TO PREVENT TIPPING UNTIL THE INTERMEDIATE DIAPHRAGMS ARE CAST AND CURED.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
9. FOR SAWTOOTH DETAILS SEE WF50G GIRDER DETAILS 2 OF 3.
10. TEMPORARY STRANDS ARE PRETENSIONED OR POST-TENSIONED. IF PRETENSIONED, THESE TEMPORARY STRANDS SHALL BE UNBONDED OVER ALL BUT THE END 10'-0" OF THE GIRDER LENGTH. AS AN ALTERNATE, TEMPORARY STRANDS MAY BE POST-TENSIONED BEFORE THE GIRDER IS LIFTED FROM THE FORM. TEMPORARY STRANDS SHALL BE CUT AFTER ALL GIRDERS ARE ERECTED, BUT BEFORE INTERMEDIATE DIAPHRAGMS ARE CAST.




TYPICAL END ELEVATION

END OF TYPE C SHOWN, OTHER END TYPES SIMILAR



VIEW B

SAWTEETH SHOWN BY SHADED AREA.



SECTION C

DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0"	0"	0"	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO


TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	≠
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6	STR.
G10	GIRDER STIRRUPS	4	STR.

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)


NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"



≠ #3 OR #4 MAY BE SUBSTITUTED. FIELD BENDING IS OPTIONAL. ** SHALL BE CHECKED FOR EFFECT OF RDWY VERTICAL CURVE


WF50G GIRDER DETAILS 1 OF 3

Figure 5-A-93




STRAND PATTERN AT GIRDER END


HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



STRAND PATTERN AT ℄ SPAN

STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.






SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - WF74G GIRDER DETAILS 1 OF 3

GIRDER SCHEDULE


DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	F℄	Fb	Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




TRANSVERSE REINFORCING SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN




ELEVATION




PLAN - BEARING RECESS AND BOTTOM FLANGE SPALL PROTECTION DETAIL

WF50G GIRDER DETAILS 2 OF 3

Figure 5-A-94




ALTERNATE #1



ALTERNATE #2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS



ALTERNATE #3

NOTES TO DESIGNER:


1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.


3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor. The total number of extended strands shall not be less than:

$$Nps = 12\left(Mc + Vc \times h - M_{SIDL}\right) \times \frac{Nc \times K}{Ng\ (0.9\ Aps \times fps \times d)}$$


where:
Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = nember of girders
Aps = area of each extended strand, in^2
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2



TEMPORARY STRAND BLOCKOUT DETAIL



ANCHOR PLATE DETAIL




STRAND PATTERN AT GIRDER END

(MOVE NOTE TO SLAB SECTION SHEET)

TEMPORARY STRAND CUTTING SEQUENCE


1. ERECT AND BRACE GIRDERS.
2. REMOVE EXPANDED POLYSTYRENE IN 2" X 2" RECESSES IN TOP FLANGE OF GIRDERS.
3. CUT STRAND AND PLASTIC SLEEVE IN 2" X 2" RECESS.
4. REMOVE ALL MOISTURE IN RECESS PRIOR TO FILLING RECESS WITH GROUT.
5. CAST INTERMEDIATE & END DIAPHRAGMS.
6. PLACE DECK CONCRETE.




PLAN VIEW OF TEMPORARY STRANDS

WF50G GIRDER DETAILS 3 OF 3

Figure 5-A-95



GIRDER ELEVATION




OPEN HOLE

BOTTOM HOLE AT END TYPE "B" ONLY

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE OR APPROVED EQUAL. (TYP.)


NOTES:

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6"ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6.02.3(25)H OF THE STANDARD SPECIFICATIONS
6. LIFTING BARS SHALL BE 1⅜"ø HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM,) LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGRESS OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING. ONCE ERECTED, ALL GIRDERS SHALL BE BRACED TO PREVENT TIPPING UNTIL THE INTERMEDIATE DIAPHRAGMS ARE CAST AND CURED.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
9. FOR SAWTOOTH DETAILS SEE WF58G GIRDER DETAILS 2 OF 3.
10. TEMPORARY STRANDS ARE PRETENSIONED OR POST-TENSIONED. IF PRETENSIONED, THESE TEMPORARY STRANDS SHALL BE UNBONDED OVER ALL BUT THE END 10'-0" OF THE GIRDER LENGTH. AS AN ALTERNATE, TEMPORARY STRANDS MAY BE POST-TENSIONED BEFORE THE GIRDER IS LIFTED FROM THE FORM. TEMPORARY STRANDS SHALL BE CUT AFTER ALL GIRDERS ARE ERECTED, BUT BEFORE INTERMEDIATE DIAPHRAGMS ARE CAST.




TYPICAL END ELEVATION

END TYPE C SHOWN, OTHER END TYPES SIMILAR



VIEW B

SAWTEETH SHOWN BY SHADED AREA.



SECTION C

DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0"	0"	0"	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO


TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	#
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6	STR.

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)


NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"



#3 OR #4 MAY BE SUBSTITUTED.FIELD BENDING IS OPTIONAL. ** SHALL BE CHECKED FOR EFFECT OF RDWY VERTICAL CURVE


WF58G GIRDER DETAILS 1 OF 3

Figure 5-A-96




STRAND PATTERN AT GIRDER END


HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



STRAND PATTERN AT ℄ SPAN


STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.





SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - WF74G GIRDER DETAILS 1 OF 3




TRANSVERSE REINFORCING SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN


GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	F℄	Fb	Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




ELEVATION




PLAN - BEARING RECESS AND BOTTOM FLANGE SPALL PROTECTION DETAIL

WF58G GIRDER DETAILS 2 OF 3

Figure 5-A-97




ALTERNATE #1



ALTERNATE #2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS



ALTERNATE #3

NOTES TO DESIGNER:


1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.


3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor. The total number of extended strands shall not be less than:

$$Nps = 12(Mc + Vc \times h - M_{SIDL}) \times \frac{Nc}{Ng} \times \frac{K}{(0.9\ Aps \times fps \times d)}$$

where:
Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = nember of girders
Aps = area of each extended strand, in ^{2}
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2



ANCHOR PLATE DETAIL




TEMPORARY STRAND BLOCKOUT DETAIL


(MOVE NOTE TO SLAB SECTION SHEET)

TEMPORARY STRAND CUTTING SEQUENCE

1. ERECT AND BRACE GIRDERS.
2. REMOVE EXPANDED POLYSTYRENE IN 2" X 2" RECESSES IN TOP FLANGE OF GIRDERS.
3. CUT STRAND AND PLASTIC SLEEVE IN 2" X 2" RECESS.
4. REMOVE ALL MOISTURE IN RECESS PRIOR TO FILLING RECESS WITH GROUT.
5. CAST INTERMEDIATE & END DIAPHRAGMS.
6. PLACE DECK CONCRETE.




STRAND PATTERN AT GIRDER END



PLAN VIEW OF TEMPORARY STRANDS


WF58G GIRDER DETAILS 3 OF 3

Figure 5-A-98



* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE INSERT OR APPROVED EQUAL. (TYP.)


* *6 : 1 FOR ½"ø STRANDS & 8 : 1 FOR 0.6"ø STRANDS




OPEN HOLE
BOTTOM HOLE AT END TYPE "B" ONLY


NOTES:

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6"ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6.02.3(25)H OF THE STANDARD SPECIFICATIONS
6. LIFTING BARS SHALL BE 1⅜"ø HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM.) LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGREES OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING. ONCE ERECTED, ALL GIRDERS SHALL BE BRACED TO PREVENT TIPPING UNTIL THE INTERMEDIATE DIAPHRAGMS ARE CAST AND CURED.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
9. FOR SAWTOOTH DETAILS SEE WF74G GIRDER DETAILS 2 OF 3.
10. TEMPORARY STRANDS ARE PRETENSIONED OR POST-TENSIONED. IF PRETENSIONED, THESE TEMPORARY STRANDS SHALL BE UNBONDED OVER ALL BUT THE END 10'-0" OF THE GIRDER LENGTH. AS AN ALTERNATE, TEMPORARY STRANDS MAY BE POST-TENSIONED BEFORE THE GIRDER IS LIFTED FROM THE FORM. TEMPORARY STRANDS SHALL BE CUT AFTER ALL GIRDERS ARE ERECTED, BUT BEFORE INTERMEDIATE DIAPHRAGMS ARE CAST.



TYPICAL END ELEVATION
END TYPE C SHOWN, OTHER END TYPES SIMILAR.





DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0"	0"	0"	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO


TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	≠
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6	STR.

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)


NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"



≠ #3 OR #4 MAY BE SUBSTITUTED.FIELD BENDING IS OPTIONAL. ** SHALL BE CHECKED FOR EFFECT OF RDWY VERTICAL CURVE


WF74G GIRDER DETAILS 1 OF 3

Figure 5-A-99




STRAND PATTERN AT GIRDER END


HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



STRAND PATTERN AT ℄ SPAN


STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.





SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - WF74G GIRDER DETAILS 1 OF 3




TRANSVERSE REINFORCING SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN


GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'c (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'ci (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	LOCATION OF C.G. STRANDS (IN.) F℄	LOCATION OF C.G. STRANDS (IN.) Fb	LOCATION OF C.G. STRANDS (IN.) Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




ELEVATION




PLAN - BEARING RECESS AND BOTTOM FLANGE SPALL PROTECTION DETAIL

WF74G GIRDER DETAILS 2 OF 3

Figure 5-A-100




ALTERNATE #1



ALTERNATE #2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS



ALTERNATE #3

NOTES TO DESIGNER:


1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.


3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor. The total number of extended strands shall not be less than:

$$Nps = 12(Mc + Vc \times h - M_{SIDL}) \times \frac{Nc}{Ng} \times \frac{K}{(0.9\ Aps \times fps \times d)}$$

where:
Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips
h = distance from top of column to c.g. of superestructure, Ft
Nc = number of columns
Ng = nember of girders
Aps = area of each extended strand, in ^{2}
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2



TEMPORARY STRAND BLOCKOUT DETAIL




ANCHOR PLATE DETAIL


(MOVE NOTE TO SLAB SECTION SHEET)

TEMPORARY STRAND CUTTING SEQUENCE

1. ERECT AND BRACE GIRDERS.
2. REMOVE EXPANDED POLYSTYRENE IN 2" X 2" RECESSES IN TOP FLANGE OF GIRDERS.
3. CUT STRAND AND PLASTIC SLEEVE IN 2" X 2" RECESS.
4. REMOVE ALL MOISTURE IN RECESS PRIOR TO FILLING RECESS WITH GROUT.
5. CAST INTERMEDIATE & END DIAPHRAGMS.
6. PLACE DECK CONCRETE.




STRAND PATTERN AT GIRDER END




PLAN VIEW OF TEMPORARY STRANDS

WF74G GIRDER DETAILS 3 OF 3

Figure 5-A-101




TYPICAL END DIAPHRAGM




SECTION F

NOTE TO DESIGNER


If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.




ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS





END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.

NOTE:


GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.


WF74G End Diaphragm on Girder Details

Figure 5-A-102



TYPICAL END TYPE "B" DIAPHRAGM AT END PIERS






ANCHOR DETAIL

A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".




ROADWAY EXPANSION JOINT AT END PIERS

LONGITIDINAL DIMENSIONS ARE NORMAL TO SKEW


WF74G Abutment Type Pier Diaphragm Details

Figure 5-A-103



PLAN - FIXED FLUSH-FACE DIAPHRAGM


* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET




SECTION A

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



TYPICAL FIXED FLUSH-FACE DIAPHRAGM



DETAIL B



OAK BLOCK DETAIL


NOTES TO DESIGNER

FIXED BAR PLAN IS SHOWN FOR DESIGNER. THE ACTUAL FIXED BARS SHALL BE LOCATED ALONG THE ℄ PIER ON THE CROSSBEAM DETAILS SHEET FOR FINAL CONTRACT PLANS.

OAK BLOCK WEDGES SHALL BE SHOWN ON CROSSBEAM PLAN SHEET, PARALLEL TO THE ℄ PIER IF SKEWED. CROSSBEAM WIDTH IS DICTATED BY OAK BLOCK LOCATION.


WF74G Fixed Flush-Face Diaphragm at Intermediate Pier Details

Figure 5-A-104



PLAN - FIXED RECESSED-FACE DIAPHRAGM


* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET




SECTION A

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



DETAIL B



TYPICAL FIXED RECESSED-FACE DIAPHRAGM



OAK BLOCK DETAIL


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.

Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.


WF74G Fixed Recessed-Face Diaphragm at Intermediate Pier Details


Figure 5-A-105




PLAN - HINGE DIAPHRAGM

10° MAX. SKEW FOR HINGE DIAPHRAGM.
* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET






HINGE BAR PLAN




SECTION A



TYPICAL HINGE SECTION

** FOR SAWTOOTH SHEAR KEY DETAILS, SEE GIRDER SHEETS.



TYP. END VIEW HINGE DIAPHRAGM


NOTES TO DESIGNER

Hinge bar plan is shown for designer. The actual hinge bars shall be located along the ℄ pier on the crossbeam details sheet, for final contract plans. The hinge bars shall be deleted from this sheet prior to the award copy of the contract plans.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by the oak block location.


WF74G Hinge Diaphragm at Intermediate Pier Details

Figure 5-A-106



TYPICAL INTERMEDIATE DIAPHRAGM






ANCHOR DETAIL
A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".

WF74G Intermediate Diaphragm Details


Figure 5-A-107




SECTION G

NOTE:

1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.




GROUT PAD ELEVATION



ELASTOMERIC STOP PAD


DUROMETER HARDNESS = 60



BEARING PAD

LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60

(SKEW ANGLE SHOWN @ 30°)




GROUT PAD DETAIL

(SKEW ANGLE SHOWN @ 30°)

WF74G Miscelleneous Diaphragm Details

Figure 5-A-108



GIRDER ELEVATION


* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE INSERT OR APPROVED EQUAL. (TYP.)

OPEN HOLE


BOTTOM HOLE AT END TYPE "B" ONLY

NOTES:

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6" ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHAL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-023(25)H OF THE STANDARD SPECIFICATIONS.
6. LIFTING BARS SHALL BE 1⅜ INCH DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM,) LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGRESS OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING. ONCE ERECTED, ALL GIRDERS SHALL BE BRACED TO PREVENT TIPPING UNTIL THE INTERMEDIATE DIAPHRAGMS ARE CAST AND CURED.
8. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
9. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
10. FOR SAWTOOTH DETAILS SEE WF83G GIRDER DETAILS 2 OF 3.
11. TEMPORARY STRANDS ARE PRETENSIONED OR POST-TENSIONED. IF PRETENSIONED, THESE TEMPORARY STRANDS SHALL BE UNBONDED OVER ALL BUT THE END 10'-0" OF THE GIRDER LENGTH. AS AN ALTERNATE, TEMPORARY STRANDS MAY BE POST TENSIONED BEFORE THE GIRDER IS LIFTED FROM THE FORM. TEMPORARY STRANDS SHALL BE CUT AFTER ALL GIRDERS ARE ERECTED, BUT BEFORE INTERMEDIATE DIAPHRAGMS ARE CAST.




TYPICAL END ELEVATION



VIEW B

SAWTEETH SHOWN BY SHADED AREA.



SECTION C


DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0"	0"	0"	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO


TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE


ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	≠
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6	STR.








≠ #3 OR #4 MAY BE SUBSTITUTED.FIELD BENDING IS OPTIONAL.
NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"

** SHALL BE CHECKED FOR EFFECT OF RDWY VERTICAL CURVE

≠ DESIGNER TO REMOVE AND / OR REPLACE WITH APPROPRIATE PIER LOCATION
≠ ≠ DESIGNER TO OMIT IF NOT APPLICABLE
≠ ≠ ≠ END TYPE "C" SHOWN - END TYPES "D" SIMILAR EXCEPT STRAND EXTENSION DETAIL SEE W83G GIRDER DETAILS 3 OF 4.
END TYPE "C" FOR CONTINUOUS SPAN WITH HINGED CONNECTION TO COLUMN
END TYPE "D" FOR CONTINUOUS SPAN FULLY FIXED TO COLUMN


W83G GIRDER DETAILS 1 OF 3

Figure 5-A-109




STRAND PATTERN AT GIRDER END


HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



STRAND PATTERN AT ℄ SPAN


STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.





SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN view B - W83G GIRDER DETAILS 1 OF 3




TRANSVERSE REINFORCING SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN


GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'c (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'ci (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	F℄	Fb	Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




ELEVATION




PLAN - BEARING RECESS AND BOTTOM FLANGE SPALL PROTECTION DETAIL

W83G GIRDER DETAILS 2 OF 3


Figure 5-A-110



ALTERNATE #1



ALTERNATE #2



ALTERNATE #3

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS

NOTES TO DESIGNER:


1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.


3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor. The total number of extended strands shall not be less than:

$$Nps = 12(Mc + Vc \times h - M_{SIDL}) \times \frac{Nc}{Ng} \times \frac{K}{(0.9 \times Aps \times fps \times d)}$$


where:
Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = nember of girders
Aps = area of each extended strand, in^2
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2



ALTERNATE STIRRUP DETAIL



TEMPORARY STRAND BLOCKOUT DETAIL




ANCHOR PLATE DETAIL


(MOVE NOTE TO SLAB SECTION SHEET)

TEMPORARY STRAND CUTTING SEQUENCE

1. ERECT AND BRACE GIRDERS.
2. REMOVE EXPANDED POLYSTYRENE IN 2" X 2" RECESSES IN TOP FLANGE OF GIRDERS.
3. CUT STRAND AND PLASTIC SLEEVE IN 2" X 2" RECESS.
4. REMOVE ALL MOISTURE IN RECESS PRIOR TO FILLING RECESS WITH GROUT.
5. CAST INTERMEDIATE & END DIAPHRAGMS.
6. PLACE DECK CONCRETE.
7. SEE SHEET W83G GIRDER DETAILS 3 OF 3 FOR 2" RECESS BLOCKOUT DETAILS.




STRAND PATTERN AT GIRDER END




PLAN VIEW OF TEMPORARY STRANDS

W83G GIRDER DETAILS 3 OF 3

Figure 5-A-111




TYPICAL END DIAPHRAGM




SECTION F

 # NOTE TO DESIGNER


If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.




ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS





END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.

NOTE:


GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.


W83G End Diaphragm on Girder Details

Figure 5-A-112



TYPICAL END TYPE "B" DIAPHRAGM AT END PIERS






ANCHOR DETAIL

A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".




ROADWAY EXPANSION JOINT AT END PIERS

LONGITIDINAL DIMENSIONS ARE NORMAL TO SKEW


W83G Abutment Type Pier Diaphragm Details

Figure 5-A-113



PLAN - FIXED FLUSH-FACE DIAPHRAGM

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET



SECTION A


NOTES TO DESIGNER

FIXED BAR PLAN IS SHOWN FOR DESIGNER. THE ACTUAL FIXED BARS SHALL BE LOCATED ALONG THE ℄ PIER ON THE CROSSBEAM DETAILS SHEET FOR FINAL CONTRACT PLANS.


OAK BLOCK WEDGES SHALL BE SHOWN ON CROSSBEAM PLAN SHEET, PARALLEL TO THE ℄ PIER IF SKEWED. CROSSBEAM WIDTH IS DICTATED BY OAK BLOCK LOCATION.

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



TYPICAL FIXED FLUSH-FACE DIAPHRAGM




DETAIL B



OAK BLOCK DETAIL


W83G Fixed Flush-Face Diaphragm at Intermediate Pier Details

Figure 5-A-114



PLAN - FIXED RECESSED-FACE DIAPHRAGM


* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET




SECTION A

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



DETAIL B



TYPICAL FIXED RECESSED-FACE DIAPHRAGM



OAK BLOCK DETAIL


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.

Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.


W83G Fixed Recessed-Face Diaphragm at Intermediate Pier Details


Figure 5-A-115




PLAN - HINGE DIAPHRAGM


10° MAX. SKEW FOR HINGE DIAPHRAGM.
* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET






HINGE BAR PLAN





TYPICAL HINGE SECTION



TYP. END VIEW HINGE DIAPHRAGM


NOTES TO DESIGNER

Hinge bar plan is shown for designer. The actual hinge bars shall be located along the ℄ pier on the crossbeam details sheet, for final contract plans. The hinge bars shall be deleted from this sheet prior to the award copy of the contract plans.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by the oak block location.

W83G Hinge Diaphragm at Intermediate Pier Details


Figure 5-A-116



TYPICAL INTERMEDIATE DIAPHRAGM



SECTION B



ANCHOR DETAIL


A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".

W83G Intermediate Diaphragm Details


Figure 5-A-117




SECTION G

NOTE:

1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE CEMENTED TO GIRDER STOPS WITH APPROVED RUBBER CEMENT.




GROUT PAD ELEVATION



ELASTOMERIC STOP PAD


DUROMETER HARDNESS = 60



BEARING PAD

LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60

(SKEW ANGLE SHOWN @ 30°)




GROUT PAD DETAIL

(SKEW ANGLE SHOWN @ 30°)

W83G Miscelleneous Diaphragm Details

Figure 5-A-118




GIRDER ELEVATION

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE INSERT OR APPROVED EQUAL. (TYP.)


OPEN HOLE
BOTTOM HOLE AT END TYPE "B" ONLY

NOTES:


1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6" ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-023(25)H OF THE STANDARD SPECIFICATIONS.
6. LIFTING BARS SHALL BE 1⅜ INCH DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM.) LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGRESS OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING. ONCE ERECTED, ALL GIRDERS SHALL BE BRACED TO PREVENT TIPPING UNTIL THE INTERMEDIATE DIAPHRAGMS ARE CAST AND CURED.
8. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
9. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
10. FOR SAWTEETH DETAILS SEE WF95G GIRDER DETAILS 2 OF 3.
11. TEMPORARY STRANDS ARE PRETENSIONED OR POST-TENSIONED. IF PRETENSIONED, THESE TEMPORARY STRANDS SHALL BE UNBONDED OVER ALL BUT THE END 10'-0" OF THE GIRDER LENGTH. AS AN ALTERNATE, TEMPORARY STRANDS MAY BE POST TENSIONED BEFORE THE GIRDER IS LIFTED FROM THE FORM. TEMPORARY STRANDS SHALL BE CUT AFTER ALL GIRDERS ARE ERECTED, BUT BEFORE INTERMEDIATE DIAPHRAGMS ARE CAST.



TYPICAL END ELEVATION
END TYPE C SHOWN, OTHER END TYPES SIMILAR



VIEW B
SAWTEETH SHOWN BY SHADED AREA.



SECTION C


DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0"	0"	0"	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIX DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULT. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO

TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)


MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	#
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6	STR.



** SHALL BE CHECKED FOR EFFECT OF RDWY VERTICAL CURVE


W95G GIRDER DETAILS 1 OF 3

Figure 5-A-119




STRAND PATTERN AT GIRDER END


HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



STRAND PATTERN AT ℄ SPAN

STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), 2) ETC.






SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - W95G GIRDER DETAILS 1 OF 3

GIRDER SCHEDULE


DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	F℄	Fb	Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




TRANSVERSE REINFORCING SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN




ELEVATION




PLAN - BEARING RECESS AND BOTTOM FLANGE SPALL PROTECTION DETAIL

W95G GIRDER DETAILS 2 OF 3

Figure 5-A-120




ALTERNATE #1



ALTERNATE #2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS



ALTERNATE #3

NOTES TO DESIGNER:


1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.


3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor. The total number of extended strands shall not be less than:

$$Nps = 12(Mc + Vc \times h - M_{SIDL}) \times \frac{Nc}{Ng} \times \frac{K}{(0.9\ Aps \times fps \times d)}$$


where:
Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = nember of girders
Aps = area of each extended strand, in ^{2}
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2



ALTERNATE STIRRUP DETAIL



TEMPORARY STRAND BLOCKOUT DETAIL




ANCHOR PLATE DETAIL


(MOVE NOTE TO SLAB SECTION SHEET)

TEMPORARY STRAND CUTTING SEQUENCE

1. ERECT AND BRACE GIRDERS.
2. REMOVE EXPANDED POLYSTYRENE IN 2" X 2" RECESSES IN TOP FLANGE OF GIRDERS.
3. CUT STRAND AND PLASTIC SLEEVE IN 2" X 2" RECESS.
4. REMOVE ALL MOISTURE IN RECESS PRIOR TO FILLING RECESS WITH GROUT.
5. CAST INTERMEDIATE & END DIAPHRAGMS.
6. PLACE DECK CONCRETE.




STRAND PATTERN AT GIRDER END




PLAN VIEW OF TEMPORARY STRANDS

W95G GIRDER DETAILS 3 OF 3

Figure 5-A-121




TYPICAL END DIAPHRAGM




SECTION F

 # NOTE TO DESIGNER


If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.




ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS





END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A". ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.

NOTE:


GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.

W95G End Diaphragm on Girder Details

Figure 5-A-122



TYPICAL END TYPE "B" DIAPHRAGM AT END PIERS




ANCHOR DETAIL

A.S.T.M. A-307


NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".



SECTION A

** DISTANCE FROM TOP OF GIRDER TO BOTTOM OF DIAPHRAGM + "A"




ROADWAY EXPANSION JOINT AT END PIERS

LONGITIDINAL DIMENSIONS ARE NORMAL TO SKEW


W95G Abutment Type Pier Diaphragm Details

Figure 5-A-123



PLAN - FIXED FLUSH-FACE DIAPHRAGM

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET



SECTION A


NOTES TO DESIGNER

FIXED BAR PLAN IS SHOWN FOR DESIGNER. THE ACTUAL FIXED BARS SHALL BE LOCATED ALONG THE ℄ PIER ON THE CROSSBEAM DETAILS SHEET FOR FINAL CONTRACT PLANS.


OAK BLOCK WEDGES SHALL BE SHOWN ON CROSSBEAM PLAN SHEET, PARALLEL TO THE ℄ PIER IF SKEWED. CROSSBEAM WIDTH IS DICTATED BY OAK BLOCK LOCATION.

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



DETAIL B




TYPICAL FIXED FLUSH-FACE DIAPHRAGM



OAK BLOCK DETAIL


W95G Fixed Flush-Face Diaphragm at Intermediate Pier Details

Figure 5-A-124



PLAN - FIXED RECESSED-FACE DIAPHRAGM

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET



SECTION A


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



DETAIL B




TYPICAL FIXED RECESSED-FACE DIAPHRAGM



OAK BLOCK DETAIL


W95G Fixed Recessed-Face Diaphragm at Intermediate Pier Details


Figure 5-A-125




PLAN - HINGE DIAPHRAGM

10° MAX. SKEW FOR HINGE DIAPHRAGM.
* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET





HINGE BAR PLAN




SECTION A


NOTES TO DESIGNER

Hinge bar plan is shown for designer. The actual hinge bars shall be located along the ℄ pier on the crossbeam details sheet, for final contract plans. The hinge bars shall be deleted from this sheet prior to the award copy of the contract plans.

Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by the oak block location.




TYPICAL HINGE SECTION




TYP. END VIEW HINGE DIAPHRAGM

W95G Hinge Diaphragm at Intermediate Pier Details

Figure 5-A-126



TYPICAL INTERMEDIATE DIAPHRAGM




ANCHOR DETAIL

A.S.T.M. A-307

NOTE:


GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".



SECTION B

W95G Intermediate Diaphragm Details


Figure 5-A-127




SECTION G

NOTE:

1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.




GROUT PAD ELEVATION



ELASTOMERIC STOP PAD


DUROMETER HARDNESS = 60



BEARING PAD

LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60

(SKEW ANGLE SHOWN @ 30°)




GROUT PAD DETAIL

(SKEW ANGLE SHOWN @ 30°)

W95G Miscelleneous Diaphragm Details

Figure 5-A-128



GIRDER ELEVATION


OPEN HOLE

≠ ≠ BOTTOM HOLE AT END TYPE "B" ONLY

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE OR APPROVED EQUAL. (TYP.)


NOTES:

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6" ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6.02.3(25)H OF THE STANDARD SPECIFICATIONS.
6. LIFTING BARS SHALL BE 1⅜ INCH DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM.) LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGRESS OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING. ONCE ERECTED, ALL GIRDERS SHALL BE BRACED TO PREVENT TIPPING UNTIL THE INTERMEDIATE DIAPHRAGMS ARE CAST AND CURED.
8. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
9. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
10. FOR SAWTEETH DETAILS SEE WF74G GIRDER DETAILS 2 OF 3.




TYPICAL END ELEVATION

END TYPE C SHOWN, OTHER END TYPES SIMILAR



VIEW B

SAWTEETH SHOWN BY SHADED AREA.



SECTION C


DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0	0	0	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SUMPLE SPANS @ INTERM. PIER	E	YES	0	0	0	NO

TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0 (G4 , G9)
B2 = 0 (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

MARK	LOCATION	SIZE	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	≠
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6	STR.


NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"



≠ #3 OR #4 MAY BE SUBSTITUTED. FIELD BENDING IS OPTIONAL. ** SHALL BE CHECKED FOR EFFECT OF RDWY VERTICAL CURVE


W32BTG GIRDER DETAILS 1 OF 3


Figure 5-A-129



SAWTOOTH DETAILS


SAWTEETH ARE FULL WIDTH - USE SAWTEETH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - WF74G GIRDER DETAILS 1 OF 3






STRAND PATTERN AT GIRDER END

HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



TRANSVERSE REINFORCING SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN




PLAN

BOTTOM FLANGE SPALL PROTECTION


END TYPES "C" INTERMEDIATE HINGE DIAPHRAGM AND END TYPE "D" INTEREMEDIATE FIXED DIAPHRAGM



SECTION A



ELEVATION



PLAN

BEARING RECESS DETAIL


GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)


SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	F℄	Fb	Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

W32BTG GIRDER DETAILS 2 OF 3

Figure 5-A-130



ALTERNATE #1



ALTERNATE #2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS

NOTES TO DESIGNER:

1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.

3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.

The total number of extended strands shall not be less than:

$$Nps = 12(Mc + Vc \times h - M_{SIDL} - M_{TD}) \times \frac{Nc}{Ng} \times \frac{K}{(0.9 \times Aps \times fps \times d)}$$

where:

Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips

h = distance from top of column to c.g. of superstructure, Ft

Nc = number of columns

Ng = nember of girders

Aps = area of each extended strand, in^2

fps = ultimate strength of strands, ksi

d = distance from top of slab to c.g. of extended strands, in

M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)


K = 0.5 for L1 = L2

0.67 for L1 = 2L2

M_{TD} = Time dependent restraint moment at piers.

W32BTG GIRDER DETAILS 3 OF 3

Figure 5-A-131




GIRDER ELEVATION

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE OR APPROVED EQUAL. (TYP.)


NOTES:

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6" ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-023(25)H OF THE STANDARD SPECIFICATIONS.
6. LIFTING BARS SHALL BE 1⅜ INCH DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM.) LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGRESS OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING. ONCE ERECTED, ALL GIRDERS SHALL BE BRACED TO PREVENT TIPPING UNTIL THE INTERMEDIATE DIAPHRAGMS ARE CAST AND CURED.
8. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
9. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
10. FOR SAWTEETH DETAILS SEE WF74G GIRDER DETAILS 2 OF 3.




TYPICAL END ELEVATION

END TYPE C SHOWN, OTHER END TYPES SIMILAR



VIEW B

SAWTEETH SHOWN BY SHADED AREA.




SECTION C

DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0	0	0	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SUMPLE SPANS @ INTERM. PIER	E	YES	0	0	0	NO

TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0 (G4 , G9)
B2 = 0 (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)


MARK	LOCATION	SIZE	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
G1	GIRDER STIRRUPS	5	NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5 STR.	
G4	GIRDER LONGIT. FULL LENGTH	5 STR.	
G5	GIRDER END LONGIT.	7 STR.	
G6	GIRDER END TIES	W12 #	
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6 STR.	



≠ #3 OR #4 MAY BE SUBSTITUTED,FIELD BENDING IS OPTIONAL. ** SHALL BE CHECKED FOR EFFECT OF RDWY VERTICAL CURVE


W38BTG GIRDER DETAILS 1 OF 3

Figure 5-A-132




SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTEETH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - WF74G GIRDER DETAILS 1 OF 3




END 1 END 2




STRAND PATTERN AT GIRDER END

HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



TRANSVERSE REINFORCING SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN



PLAN

BOTTOM FLANGE SPALL PROTECTION

END TYPES "C" INTERMEDIATE HINGE DIAPHRAGM AND END TYPE "D" INTEREMEDIATE FIXED DIAPHRAGM




SECTION A


GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	F℄	Fb	Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-



ELEVATION




PLAN


BEARING RECESS DETAIL

W38BTG GIRDER DETAILS 2 OF 3

Figure 5-A-133



ALTERNATE #1



ALTERNATE #2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS

NOTES TO DESIGNER:

1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.

3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.

The total number of extended strands shall not be less than:

$$Nps = 12(Mc + Vc \times h - M_{SIDL} - M_{TD}) \times \frac{}{Ng} \times Nc \times \frac{K}{(0.9\ Aps \times fps \times d)}$$

where:

Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips

h = distance from top of column to c.g. of superstructure, Ft

Nc = number of columns

Ng = nember of girders

Aps = area of each extended strand, in^2

fps = ultimate strength of strands, ksi

d = distance from top of slab to c.g. of extended strands, in

M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)


K = 0.5 for L1 = L2

0.67 for L1 = 2L2

M_{TD} = Time dependent restraint moment at piers.

W38BTG GIRDER DETAILS 3 OF 3

Figure 5-A-134



GIRDER ELEVATION


OPEN HOLE

≠ ≠ BOTTOM HOLE AT END TYPE "B" ONLY

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE OR APPROVED EQUAL. (TYP.)


NOTES:

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6" ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-023(25)H OF THE STANDARD SPECIFICATIONS.
6. LIFTING BARS SHALL BE 1⅜ INCH DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM.) LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGRESS OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING. ONCE ERECTED, ALL GIRDERS SHALL BE BRACED TO PREVENT TIPPING UNTIL THE INTERMEDIATE DIAPHRAGMS ARE CAST AND CURED.
8. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
9. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
10. FOR SAWTEETH DETAILS SEE WF74G GIRDER DETAILS 2 OF 3.




TYPICAL END ELEVATION

END TYPE C SHOWN, OTHER END TYPES SIMILAR



VIEW B

SAWTEETH SHOWN BY SHADED AREA.



SECTION C


DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0	0	0	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SUMPLE SPANS @ INTERM. PIER	E	YES	0	0	0	NO

TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0 (G4 , G9)
B2 = 0 (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

MARK	LOCATION	SIZE	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	≠
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6	STR.


NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"



≠ #3 OR #4 MAY BE SUBSTITUTED.FIELD BENDING IS OPTIONAL. ** SHALL BE CHECKED FOR EFFECT OF RDWY VERTICAL CURVE


W62BTG GIRDER DETAILS 1 OF 3


Figure 5-A-135



SAWTOOTH DETAILS


SAWTEETH ARE FULL WIDTH - USE SAWTEETH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - WF74G GIRDER DETAILS 1 OF 3






STRAND PATTERN AT GIRDER END

HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



TRANSVERSE REINFORCING SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN



PLAN

BOTTOM FLANGE SPALL PROTECTION

END TYPES "C" INTERMEDIATE HINGE DIAPHRAGM AND END TYPE "D" INTEREMEDIATE FIXED DIAPHRAGM




SECTION A


GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	F℄	Fb	Fo	C (IN.)	D (IN.)	Pt (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-



ELEVATION




PLAN


BEARING RECESS DETAIL

W62BTG GIRDER DETAILS 2 OF 3

Figure 5-A-136



ALTERNATE #1



ALTERNATE #2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS

NOTES TO DESIGNER:

1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.

3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.
   The total number of extended strands shall not be less than:


$$Nps = 12(Mc + Vc \times h - M_{SIDL} \times M_{TD}) \times \frac{Nc}{Ng} \times \frac{K}{(0.9 \times Aps \times fps \times d)}$$

where:

Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = nember of girders
Aps = area of each extended strand, in^2
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
$K = 0.5$ for L1 = L2
0.67 for L1 = 2L2
M_{TD} = Time dependent restraint moment at piers.


W62BTG GIRDER DETAILS 3 OF 3

Figure 5-A-137




GIRDER ELEVATION

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅜") FERRULE OR APPROVED EQUAL. (TYP.)




BOTTOM SLAB DRAIN HOLE DETAIL




OPEN HOLE DETAIL

BOTTOM HOLE AT END TYPE "B" ONLY



TYPICAL END ELEVATION

END TYPE "C" SHOWN, OTHER END TYPES SIMILAR



TYPICAL SECTION


NOTES:


1. THESE SHEETS ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6"ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. EXTENDED STRANDS AND BARS ARE PARALLEL TO GIRDER.
6. LIFTING BARS SHALL BE 1⅜" ø HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM.) IF THE LIFTING BARS EXTEND WITHIN 3" OF THE TOP OF THE ROADWAY SLAB, THEY SHALL BE CUT OFF PRIOR TO PLACING THE ROADWAY SLAB. LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGREES OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING.
8. THE TOP SURFACE OF THE GIRDER WEBS SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H.
9. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
10. FOR SAWTOOTH DETAILS SEE GIRDER DETAILS 2 OF 3.

Notes to designer						
DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
End diaph. on girder	A	YES	1'-10"	1'-6"	9"	YES
"L" Abutment	B	YES	0	0	0	NO
Hinge diaph.on interm. pier	C	NO	1'-10"	1'-6"	9"	YES
Fixed diaph.@ interm. pier	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
Mult. simple spans @ interm. pier	E	YES	0	0	0	NO

Prestressed Trapezoidal Tub Girder Details 1 of 3


Figure 5-A-138






TYPICAL END ELEVATION

EXTENDED STRANDS NOT SHOWN.
USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE
TO BOTTOM OF LOWEST HARPED STRANDS.



P.C. SECTION



PLAN

BOTTOM FLANGE SPALL PROTECTION

END TYPE "C" INTERMEDIATE HINGE DIAPHRAGM
AND END TYPE "D" INTEREMEDIATE FIXED DIAPHRAGM


BENDING DIAGRAM

MARK	LOCATION	SIZE	U	W	X	
G1	STIRRUPS, OUTSIDE WEB	5				
G2	STIRRUPS, INSIDE WEB	5				
G3	LONGITUDINAL BOTTOM FLANGE	4				STR.
G4	LONGITUDINAL TOP	6				STR.
G5	LONGITUDINAL WEB	6				STR.
G6	WEB TIE	W12				# #4 MAY BE SUBSTITUTED FOR W12, FIELD BENDING IS OPTIONAL
G7	BOTTOM FLANGE	5				
G8	STIRRUP, OUTSIDE WEB	4				
G9	STIRRUP, INSIDE WEB	4				
G10	LONGITUDINAL BOTTOM	4				STR.


ALL DIMENSIONS ARE OUT TO OUT

* = VARIES FOR SKEWED SPANS

NOTE:
FOR DIMENSION "A", SEE "GIRDER SCHEDULE"




SECTION A




TRANSVERSE REINFORCING AT SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN





SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTEETH
FULL HEIGHT ON END SECTIONS.









Prestressed Trapezoidal Tub Girder Details 2 of 3

Figure 5-A-139

NOTES TO DESIGNER:


1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only.This detail is not applicable to continuous spans using hinge diaphragms.
2. Designer shall calculate the exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.
   The total number of extended strands shall not be less than:
3. $Nps = 12(Mc + Vc \times h - M_{SIDL}) \times Nc \frac{X}{Ng} \frac{K}{(0.9\ Aps \times fps \times d)}$

where:
Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear capacity of column Ft-kips, kips respectively,
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = number of girders
Aps = area of each extended strand, in
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2

GIRDER SCHEDULE


DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ_1	θ_2	P_1	P_2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	F℄	Fb	Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




STRAND PATTERN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



ALTERNATE # 1




ALTERNATE # 2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS

Prestressed Trapezoidal Tub Girder Details 3 of 3


Figure 5-A-140




NOTE TO DESIGNER

If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.


TYPICAL END TYPE "A" DIAPHRAGM AT END PIERS




SECTION F




ELEVATION BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW BUTYL RUBBER @ VERTICAL JOINTS





END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.

NOTE:

1. GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.
2. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
3. END DIAPHRAGM MAY BE CAST ON GRADE. IF SO, THE UPPER LEG OF THE JOINT FILLER SHALL FORM THE BOTTOM FACE FULL WIDTH.
4. JOINT FILLER TYPE 1 SHALL BE USED TO COVER ALL VERTICAL END DIAPHRAGM JOINTS. EITHER JOINT FILLER TYPE 1 OR JOINT FILLER TYPE 2 SHALL BE USED TO COVER ALL HORIZONTAL END DIAPHRAGM JOINTS.


Prestressed Trapezoidal Tub Girder End Diaphragm on Girder Details

Figure 5-A-141




PLAN


FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET 3.




SECTION A



TEMPORARY SUPPORT DETAIL




DETAIL C



ELEVATION

CONSTRUCTION SEQUENCE


1. COLUMN & TEMP. SUPPORT
2. PLACE GIRDER ON TEMPORARY SUPPORT
3. CAST DIAPHRAGM STAGE 1
4. CAST ROADWAY SLAB
5. COMPLETE DIAPHRAGM
6. REMOVE TEMPORARY SUPPORT



SECTION B

Prestressed Trapezoidal Tub Girder Raised Crossbeam Details

Figure 5-A-142




DETAIL G

NOTE TO DESIGNER:

This detail to be used on bridges with end piers and no wing walls, and located within and west of the Cascade Mountain range.


NOTE:

1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE COATED WITH RUBBER CEMENT PRIOR TO INSTATLLATION.




EXPANSION JOINT DETAILS

JOINT AT INTERMEDIATE PIER SHOWN




ANCHOR DETAIL

A.S.T.M. A-307




DETAIL E




DETAIL F

DRILL ⅛"ø HOLES THROUGH SEAL WITH STANDARD TWIST DRILL MAKING SURE THE TOP MEMBRANE IS NOT DAMAGED. CUT HOLE WITH SHARP LONG BLADE KNIFE.



BEARING PAD


LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60



GROUT PAD DETAIL


Prestressed Trapezoidal Tub Girder Miscellaneous Details

Figure 5-A-143



GIRDER ELEVATION

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR WEB OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE OR APPROVED EQUAL. (TYP.)




OPEN HOLE DETAIL

BOTTOM HOLE AT END TYPE "B" ONLY


NOTES:

1. THESE SHEETS ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE 0.6"ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. EXTENDED STRANDS AND BARS ARE PARALLEL TO GIRDER.
6. LIFTING BARS SHALL BE 1⅜" ø HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM.) IF THE LIFTING BARS EXTEND WITHIN 3" OF THE TOP OF THE ROADWAY SLAB, THEY SHALL BE CUT OFF PRIOR TO PLACING THE ROADWAY SLAB. LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGRESS OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING.
8. THE TOP SURFACE OF THE GIRDER WEBS SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H.
9. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
10. FOR SAWTOOTH DETAILS SEE GIRDER DETAILS 2 OF 4.
11. TEMPORARY STRANDS ARE PRETENSIONED OR POST-TENSIONED. IF PRETENSIONED, THESE TEMPORARY STRANDS SHALL BE DEBONDED OVER ALL BUT THE END 10'-0" OF THE GIRDER LENGTH. AS AN ALTERNATE, TEMPORARY STRANDS MAY BE POST-TENSIONED BEFORE THE GIRDER IS LIFTED FROM THE FORM. TEMPORARY STRANDS SHALL BE CUT BEFORE THE INTERMEDIATE DIAPHRAGMS ARE CAST. PATCH RECESS WITH CEMENTITIOUS GROUT; DO NOT ALLOW MOISTURE IN RECESS PRIOR TO GROUTING.
12. P.C. GIRDER ENDS SHALL BE PLUMB IN THE FINAL GIRDER'S ERECTED POSITION.



TYPICAL END ELEVATION

END TYPE C SHOWN - OTHER END TYPES SIMILAR.




SECTION ~ REINFORCEMENT

FOR DRAIN HOLE LOCATIONS SEE "FRAMING PLAN" SHEET.

Notes to designer						
DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
End diaph. on girder	A	YES	1'-10"	1'-6"	9"	YES
"L" Abutment	B	YES	0	0	0	NO
Hinge diaph.on interm. pier	C	NO	1'-10"	1'-6"	9"	YES
Fixed diaph.@ interm. pier	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
Mult. simple spans @ interm. pier	E	YES	0	0	0	NO


Trapezoidal Tub S-I-P Deck Panel Girder - Details 1 of 4

Figure 5-A-144



TYPICAL END ELEVATION


EXTENDED STRANDS AND REINF. NOT SHOWN.




SECTION ~ P.C. GIRDER

* SMOOTH FINISH ON TOP OF GIRDER.

*** 1'-0" FOR BOTTOM FLANGE WIDTH 4'-0" & 5'-0"
2'-0" FOR BOTTOM FLANGE WIDTH 6'-0"




SECTION~EXTERIOR P.C. GIRDER




BEARING RECESS DETAIL


RECESS DEPTH SHALL BE ½" AT ℄ BEARING. RECESS SURFACE SHALL BE LEVEL LONGITUDINALLY AND TRANSVERSELY IN FINAL POSITION OF THE P.C. GIRDER. SEE "FABRIC PAD BEARING PIERS 1 AND 3" SHEET FOR OTHER DETAILS.



END 1 PLAN ~ GIRDER END 2




BOTTOM SLAB DRAIN HOLE DETAIL



TRANSVERSE REINFORCING AT SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN



SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH.
USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRANDS AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN ON "TYPICAL END ELEVATION" THIS SHEET.


BENDING DIAGRAM

MARK	LOCATION	SIZE	U	W	X	ALL DIMENSIONS ARE OUT TO OUT
G1	STIRRUPS, OUTSIDE WEB	5				
G2	STIRRUPS, INSIDE WEB	5				
G3	LONGITUDINAL BOTTOM FLANGE	4			STR.	
G4	TOP WEB TIE	4				
G5	LONGITUDINAL WEB	6			STR.	
G6	WEB TIE	W12			#	
G7	TRANSVERSE TIE	5				
G8	STIRRUPS, OUTSIDE WEB	4				
G9	STIRRUPS, INSIDE WEB	4				
G10	LONGITUDINAL TOP FLANGE	4			STR.	

* = VARIES FOR SKEWED SPANS

NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"

#3 OR #4 MAY BE SUBSTITUTED FOR W12, FIELD BENDING IS OPTIONAL



Trapezoidal Tub S-I-P Deck Panel Girder - Details 2 of 4

Figure 5-A-145

NOTES TO DESIGNER:


1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only.This detail is not applicable to continuous spans using hinge diaphragms.
2. Designer shall calculate the exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.
   The total number of extended strands shall not be less than:
3. $Nps = 12(Mc + Vc \times h - M_{SIDL}) \times Nc \times \frac{1}{Ng} \quad \frac{K}{(0.9\ Aps \times fps \times d)}$

where:

Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear capacity of column Ft-kips, kips respectively,
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = number of girders
Aps = area of each extended strand, in
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2

TEMPORARY STRAND CUTTING SEQUENCE

1. ERECT AND BRACE GIRDERS.
2. REMOVE EXPANDED POLYSTYRENE IN 2" X 2" RECESSES IN TOP FLANGE OF GIRDERS.
3. CUT STRAND AND PLASTIC SLEEVE IN 2" X 2" RECESS.
4. REMOVE ALL MOISTURE IN RECESS PRIOR TO FILLING RECESS WITH GROUT.
5. CAST INTERMEDIATE & END DIAPHRAGMS.
6. PLACE DECK CONCRETE.
7. SEE SHEET W83G GIRDER DETAILS 3 OF 3 FOR 2" RECESS BLOCKOUT DETAILS.




PLAN VIEW OF TEMPORARY STRANDS

Trapezoidal Tub S-I-P Deck Panel Girder - Details 3 of 4
Figure 5-A-146


GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS = 10"				BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)																		
SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ_1	θ_2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH		HARPED		STRAIGHT		TEMPORARY		LOCATION OF C.G. STRANDS (IN.)				C (IN.)	D (IN.)	Ld (IN.)
								@ FINAL F'C (KSI)	@ RELEASE F'CI (KSI)	NO. OF STRANDS	JACKING FORCE (KIPS)	NO. OF STRANDS	JACKING FORCE (KIPS)	NO. OF STRANDS	JACKING FORCE (KIPS)	E	F℄	Fb	Fo			
-	-	-	-	-	-°	-°	--'- -"	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




STRAND PATTERN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



ALTERNATE # 1




ALTERNATE # 2

STRAND EXTENSION DETAIL FOR END TYPE D

NOT ALL EXTENDED STRANDS ARE SHOWN

Trapezoidal Tub S-I-P Deck Panel Girder - Details 4 of 4


Figure 5-A-147




NOTE TO DESIGNER

If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.


TYPICAL END TYPE "A" DIAPHRAGM AT END PIERS




SECTION F




ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS





END DIAPHRAGM GEOMETRY

SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.


* TO BE INCREASED AS NECESSARY

NOTE:

1. GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.
2. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
3. END DIAPHRAGM MAY BE CAST ON GRADE. IF SO, THE UPPER LEG OF THE JOINT FILLER SHALL FORM THE BOTTOM FACE FULL WIDTH.
4. JOINT FILLER TYPE 1 SHALL BE USED TO COVER ALL VERTICAL END DIAPHRAGM JOINTS. EITHER JOINT FILLER TYPE 1 OR JOINT FILLER TYPE 2 SHALL BE USED TO COVER ALL HORIZONTAL END DIAPHRAGM JOINTS.


Trapezoidal Tub S-I-P Deck Panel Girder - End Diaphragm on Girder Details


Figure 5-A-148




PLAN

FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET 3.






TEMPORARY SUPPORT DETAIL




DETAIL C



ELEVATION


CONSTRUCTION SEQUENCE

1. COLUMN & TEMP. SUPPORT
2. PLACE GIRDER ON TEMPORARY SUPPORT
3. CAST DIAPHRAGM STAGE 1
4. CAST ROADWAY SLAB
5. COMPLETE DIAPHRAGM
6. REMOVE TEMPORARY SUPPORT



Trapezoidal Tub S-I-P Deck Panel Girder - Raised Crossbeam Details


Figure 5-A-149



DETAIL G


NOTE TO DESIGNER:
This detail to be used on bridges with end piers and no wing walls, and located within and west of the Cascade Mountain range.

NOTE:
1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.



EXPANSION JOINT DETAILS


JOINT AT INTERMEDIATE PIER SHOWN




TOP ANCHOR BOTTOM ANCHOR

ANCHOR DETAIL

A.S.T.M. A-307




DETAIL E




DETAIL F

DRILL ½"ø HOLES THROUGH SEAL WITH STANDARD TWIST DRILL MAKING SURE THE TOP MEMBRANE IS NOT DAMAGED. CUT HOLE WITH SHARP LONG BLADE KNIFE.



BEARING PAD


LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60




GROUT PAD DETAIL

Trapezoidal Tub S-I-P Deck Panel Girder - Miscellaneous Diaphragm Details


Figure 5-A-150



TYPICAL SECTION - PRESTRESSED PANEL




DETAIL B



DETAIL A

NOTE:

THE FIRST INSERT SHALL BE PLACED WITHIN 2'-0" OF THE END DIAPHRAGMS.
FOR INSERT LOCATIONS, SEE "UTILITIES HANGER DETAILS" SHEET.




PLAN VIEW ~ PRESTRESSED PANEL

NOTES:


1. CONCRETE IN THE PRESTRESSED PRECAST DECK PANELS SHALL BE CLASS 5000.
   THE CONCRETE SHALL ATTAIN A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI BEFORE RELEASING THE PRETENSIONING STRANDS.
2. THE PRETENSION STRANDS SHALL BE 7 WIRE ⅜"ø (As = 0.085 IN²) LOW RELAXATION STRANDS (AASHTO M203 GRADE 270)
   THE JACKING FORCE SHALL BE 17.4 KIP PER STRAND.
3. GROUT BED FOR PRESTRESSED PRECAST DECK PANELS SHALL CONFORM TO THE SPECIAL PROVISIONS.
4. LOOSEN THE LEVELING BOLT BY TWO TURN AFTER THE GROUT HAS REACHED THE DESIGN STRENGTH PER STANDARD SPECIFICATION.
5. FOR SKEW END PANELS, ADJUST THE LEVELING BOLT LOCATIONS LONGITUDINALLY ALONG THE ℄ OF GIRDER, SUCH THAT EACH PANEL WILL HAVE 4 BOLTS AFTER THE SAWCUT.

BAR LIST		
MARK #	BAR SIZE	BEND TYPE
P1	5	STRAIGHT
*P2	4 ▽	AS SHOWN
P3	4	AS SHOWN
P4	4	STRAIGHT

▽ = EPOXY COATED
ALL REINFORCEMENT SHALL BE AASHTO M31. GR. 60.
* VARIES



DETAIL D




ELEVATION ~ PRESTRESSED PANEL

(DIMENSIONS SHOWN NORMAL TO ℄ TUB GIRDER)

Precast Prestressed Stay-in-Place Deck Panel Details

Figure 5-A-151




PLAN

SHOWN FOR SKEW ANGLE GREATER THAN OR EQUAL TO 20° (30° MAX.)

NOTES

1. ALL PRESTRESSING STEEL SHALL BE ½"ø OR 0.6"ø LOW-RELAXATION 7-WIRE STRANDS AASHTO M203 GRADE 270. STRANDS SHALL BE TENSIONED INITIALLY TO 0.75 F'S.
2. ALL REINFORCING STEEL SHALL CONFORM TO AASHTO M31, GRADE 60. ALL REINFORCING STEEL SPLICES SHALL BE TWO FEET MINIMUM, UNLESS SHOWN OTHERWISE.
3. ALL REINFORCING BARS SHALL BE PLACED 2 INCHES FROM NEAREST FACE OF CONCRETE UNLESS SHOWN OTHERWISE.
4. CONCRETE SHALL BE WITH MINIMUM COMPRESSIVE STRENGTH AT TRANSFER AND FINAL AS SHOWN IN THE DESIGN TABLE.
5. THE DEFLECTION VALUES LISTED IN THE DESIGN TABLE ARE COMPUTED DEFLECTIONS AT MID-SPAN BASED ON THE FOLLOWING TIME ELAPSE ASSUMPTIONS:
   - INITIAL CONCRETE COMPRESSIVE STRENGTH AT RELEASE WILL BE ATTAINED IN ONE (1) DAY.
   - FINAL CONCRETE COMPRESSIVE STRENGTH AT 28 DAYS WILL BE ATTAINED IN SEVEN (7) DAYS.
   - THE FINAL DEFLECTION IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS.
   - THE FINAL DEFLECTION DUE TO 85 PSF SUPERIMPOSED LOAD (ASPHALT OVERLAY, NOT INCLUDING TRAFFIC BARRIERS) IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS WITH THE LOAD ASSUMED TO BE PLACED ONE HUNDRED TEWENTY (120) DAYS AFTER SLABS ARE CAST. IF THE ACTUAL CONDITIONS VARY SUBSTANTIALLY FROM THOSE ASSUMED ABOVE, THE DEFLECTION SHALL BE MODIFIED AND SUBMITTED TO THE ENGINEER FOR APPROVAL. THE TIME ASSUMPTION MAY VARY BY ± 30%
6. IT IS INTENDED THAT MEMBRANE WATERPROOFING AND ASPHALT OVERLAY BE INSTALLED ON THE IN-PLACE SLABS. THE ASPHALT SHALL BE VARIED TO PARTIALLY COMPENSATE FOR THE TWO THOUSAND (2000) DAY SLAB DEFLECTION. THE THICKNESS OF ASPHALT SHALL BE A MINIMUM OF 1½ INCHES AT MIDSPAN.
7. NO TRAFFIC SHALL BE ALLOWED ON A BEAM ADJACENT TO A GROUTED JOINT UNTIL THE GROUT HAS ATTAINED A MINIMUM STRENTH OF 4000 PSI.



ELEVATION

NOTES TO DESIGNER


STRAND SEQUENCE

1	3	4	2
17 27 21 1 9 3	25 29 19 23 31 11 5 13 7 15	32 24 20 30 26 16 8 14 6 12	22 28 18 4 10 2

WHEN DEBONDED STANDS ARE REQUIRED, PLACE AT INTERIOR STRAND LOCATION (WITHIN SECOND ROW IF POSSIBLE). PLACE DIAMONDS WHERE DEBONDED STRANDS ARE REQUIRED & INDICATE DEBONDED LENGTH.

* ○ = BONDED STRANDS
◇ = DEBONDED STRANDS

* TOP 2" OF SLAB SHALL BE AIR-ENTRAINED CONCRETE.




SECTION A
EXTERIOR SLAB


CUT ALL STRANDS FLUSH WITH SLAB ENDS AND PAINT WITH AN APPROVED EPOXY RESIN

Precast Prestressed 1'-0" Solid Slab Details 1 of 2


Figure 5-A-152




SECTION C
WELD TIE ALTERNATE #1




SECTION C
WELD TIE ALTERNATE #2



SECTION B
KEYWAY DETAIL



END VIEW
EXTERIOR SLAB




CAMBER DETAIL

C_I = CAMBER AT TRANSFER DUE TO PRESTRESSING AND GIRDER SELF WEIGHT.

C_{FINAL} = CAMBER AT 2000 DAYS.


C_{SIDL} = DEFLECTION DUE TO WEIGHT OF ACP OVERLAY AND TRAFFIC BARRIER.

$C_{F+SIDL} = C_{FINAL} + C_{SIDL}$



DEVELOPED ELEVATION
LIFTING LOOP

½"ø OR 0.6"ø 7-WIRE STRANDS (AASHTO M203 GRADE 270) FOR LIFTING SLAB; MINIMUM OF 4 STRANDS PER SLAB. AFTER SLAB IS IN PLACE CUT STRAND 1¼" (MIN.) CLEAR OF TOP SLAB AND FILL HOLE WITH GROUT



PART SECTION
EXTERIOR SLAB

FOR DETAILS NOT SHOWN SEE TRAFFIC BARRIER SHEETS

BARLIST


ALL REINFORCING SHALL BE AASHTO M31 (GRADE 60)

MARK	LOCATION	SIZE	NO. REQ'D	BARLIST DIMENSION TABLE				BENDING DIAGRAM
G1	SLAB LONGIT. - TOP	#4	4 β	STR.	SLAB DEPTH	W	REQUIRED EMBEDMENT	
G2	SLAB LONGIT. - BOT.	4	4	STR.	1'-0"	11"	1'-6"	
G3	END OF SLAB - TIE	#4	8					
G4	END OF SLAB - TIE	4	4					
G5	END OF SLAB - TIE	3	4 δ					
G6	END OF SLAB - TIE	#4	AS REQ'D BY SKEW					
G7	SLAB TRANSV. - TIE	#4	VARIES WITH SPAN					
G8	SLAB TRANSV. - STIRRUP	4	VARIES WITH SPAN					
S1	T.B. TO DECK TIE	4						
S2	T.B. TO DECK TIE	#5						

= EPOXY COATED

δ 2 BARS BUNDLED

β ADDITIONAL BARS WILL BE REQUIRED ON VOIDED SLABS W/BARRIERS, IF OPTION 1 ANCHOR PLATE DETAIL IS SELECTED.




DESIGN TABLE

STRENGTH OF CONCRETE: TRANSFER, F'ci = 5.5 kSI FINAL, F'c = 7.0 kSI
PRESTRESSING STRANDS, 0.60"ø, 270 kSI
* COMBINATION OF TOP AND BOTTOM STRANDS

SPAN NUMBER	SPAN LENGTH ℄/℄ BRG. FT.	TOTAL NO. OF STRANDS	BOTTOM		TOP	* JACKING FORCE KIPS	LOCATION OF C.G. OF STRAND "E" IN. *	CAMBER (IN.)		
			BONDED	DE-BONDED				C_I	C_{FINAL}	C_{F+SIDL}

Precast Prestressed 1'-0" Solid Slab Details 2 of 2

Figure 5-A-153




PLAN


SHOWN FOR SKEW ANGLE GREATER THAN OR EQUAL TO 20° (30° MAX.)

NOTES

1. ALL PRESTRESSING STEEL SHALL BE ½"ø OR 0.6"ø LOW-RELAXATION 7-WIRE STRANDS AASHTO M203 GRADE 270. STRANDS SHALL BE TENSIONED INITIALLY TO 0.75 F'S.
2. ALL REINFORCING STEEL SHALL CONFORM TO AASHTO M31, GRADE 60. ALL REINFORCING STEEL SPLICES SHALL BE TWO FEET MINIMUM, UNLESS SHOWN OTHERWISE.
3. ALL REINFORCING BARS SHALL BE PLACED 2 INCHES FROM NEAREST FACE OF CONCRETE UNLESS SHOWN OTHERWISE.
4. CONCRETE SHALL BE WITH MINIMUM COMPRESSIVE STRENGTH AT TRANSFER AND FINAL AS SHOWN IN THE DESIGN TABLE.
5. THE DEFLECTION VALUES LISTED IN THE DESIGN TABLE ARE COMPUTED DEFLECTIONS AT MID-SPAN BASED ON THE FOLLOWING TIME ELAPSE ASSUMPTIONS:
   - INITIAL CONCRETE COMPRESSIVE STRENGTH AT RELEASE WILL BE ATTAINED IN ONE (1) DAY.
   - FINAL CONCRETE COMPRESSIVE STRENGTH AT 28 DAYS WILL BE ATTAINED IN SEVEN (7) DAYS.
   - THE FINAL DEFLECTION IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS.
   - THE FINAL DEFLECTION DUE TO 85 PSF SUPERIMPOSED LOAD (ASPHALT OVERLAY, NOT INCLUDING TRAFFIC BARRIERS) IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS WITH THE LOAD ASSUMED TO BE PLACED ONE HUNDRED TWENTY (120) DAYS AFTER SLABS ARE CAST. IF THE ACTUAL CONDITIONS VARY SUBSTANTIALLY FROM THOSE ASSUMED ABOVE, THE DEFLECTION SHALL BE MODIFIED AND SUBMITTED TO THE ENGINEER FOR APPROVAL. THE TIME ASSUMPTION MAY VARY BY ± 30%
6. IT IS INTENDED THAT MEMBRANE WATERPROOFING AND ASPHALT OVERLAY BE INSTALLED ON THE IN-PLACE SLABS. THE ASPHALT SHALL BE VARIED TO PARTIALLY COMPENSATE FOR THE TWO THOUSAND (2000) DAY SLAB DEFLECTION. THE THICKNESS OF ASPHALT SHALL BE A MINIMUM OF 1½ INCHES AT MIDSPAN.
7. NO TRAFFIC SHALL BE ALLOWED ON A BEAM ADJACENT TO A GROUTED JOINT UNTIL THE GROUT HAS ATTAINED A MINIMUM STRENTH OF 4000 PSI.




ELEVATION



WHEN DEBONDED STANDS ARE REQUIRED, PLACE AT INTERIOR STRAND LOCATION (WITHIN SECOND ROW IF POSSIBLE). PLACE DIAMONDS WHERE DEBONDED STRANDS ARE REQUIRED & INDICATE DEBONDED LENGTH.

* TOP 2" OF SLAB SHALL BE AIR-ENTRAINED CONCRETE.




SECTION A
EXTERIOR SLAB

CUT ALL STRANDS FLUSH WITH SLAB ENDS AND PAINT WITH AN APPROVED EPOXY RESIN


Precast Prestressed 1'-6" Voided Slab Details 1 of 3

Figure 5-A-154




CAMBER DETAIL


C_I = CAMBER AT TRANSFER DUE TO PRESTRESSING AND GIRDER SELF WEIGHT.
C_{FINAL} = CAMBER AT 2000 DAYS.
C_{SIDL} = DEFLECTION DUE TO WEIGHT OF ACP OVERLAY AND TRAFFIC BARRIER.
$C_{F+SIDL} = C_{FINAL} + C_{SIDL}$




END VIEW EXTERIOR SLAB




SECTION C
WELD TIE ALTERNATE #1



SECTION C
WELD TIE ALTERNATE #2



SECTION B
KEYWAY DETAIL



DEVELOPED ELEVATION LIFTING LOOP

½"ø OR 0.6"ø 7-WIRE STRANDS (AASHTO M203 GRADE 270) FOR LIFTING SLAB; MINIMUM OF 4 STRANDS PER SLAB. AFTER SLAB IS IN PLACE CUT STRAND 1¼" (MIN.) CLEAR OF TOP SLAB AND FILL HOLE WITH GROUT

BARLIST

ALL REINFORCING SHALL BE AASHTO M31 (GRADE 60)


MARK	LOCATION	SIZE	NO. REQ'D	BARLIST DIMENSION TABLE			BENDING DIAGRAM
				STR.	SLAB DEPTH	W	REQUIRED EMBEDMENT
G1	SLAB LONGIT. - TOP	▽4	4 β	STR.	1'-6"	1'-5"	1'-9"
G2	SLAB LONGIT. - BOT.	4	4				
G3	END OF SLAB - TIE	▽4	8				
G4	END OF SLAB - TIE	4	4				
G5	END OF SLAB - TIE	3	4 δ				
G6	END OF SLAB - TIE	▽4	AS REQ'D BY SKEW				
G7	SLAB TRANSV. - TIE	▽4	VARIES WITH SPAN				
G8	SLAB TRANSV. - STIRRUP	4	VARIES WITH SPAN				
S1	T.B. TO DECK TIE	4					
S2	T.B. TO DECK TIE	▽5					

▽ = EPOXY COATED

δ 2 BARS BUNDLED

β ADDITIONAL BARS WILL BE REQUIRED ON VOIDED SLABS W/BARRIERS, IF OPTION 1 ANCHOR PLATE DETAIL IS SELECTED.

VARIABLE LENGTH TO ANCHOR PROVIDED BY VOIDED SLAB MANUFACTURER (BASED ON ANCHOR PLACEMENT.




DESIGN TABLE

STRENGTH OF CONCRETE: TRANSFER, F'ci = 5.5 kSI FINAL, F'c = 7.0 kSI
PRESTRESSING STRANDS, 0.60"ø, 270 kSI
* COMBINATION OF TOP AND BOTTOM STRANDS

SPAN NUMBER	SPAN LENGTH ℄/℄ BRG. FT.	TOTAL NO. OF STRANDS	BOTTOM		TOP	* JACKING FORCE KIPS	LOCATION * OF C.G. OF STRAND "E" IN.	CAMBER (IN.)		
			BONDED	DE-BONDED				C_I	C_{FINAL}	C_{F+SIDL}

Precast Prestressed 1'-6" Voided Slab Details 2 of 3
Figure 5-A-155



PART SECTION
EXTERIOR SLAB


γ SPACING WILL BE DEVELOPED BY S1 & S2 LAYOUT.

β WELD SHALL BE SIZED TO DEVELOP 125% OF THE REBAR YIELD STRENGTH AND TESTED IN ACCORDANCE W/ 6-02.3 (24)E (L IS DEPENDANT ON COUPLER SELECTED)


σ PLACED ALONG ℄ WHEN VOIDED SLAB LONGITUDINAL REINFORCING OR STRANDS ARE NOT IN CONTACT W/ ℄

L LENGTH IS DEPENDENT ON COUPLER SELECTED


WELDED COUPLER TABLE	
BAR SPLICE	BPI BARSPLICER STRUCTURAL CONNECTOR
ERICO	LENTON WELDABLE COUPLER C2/C3J
BAR LOCK	STRUCTURAL STEEL CONNECTORS (WELDABLE HALF COUPLER) SCA




ANCHOR PLATE DETAIL




VIEW A
INSERT 1



VIEW B
INSERT 2




SECTION C




SECTION D

Precast Prestressed 1'-6" Voided Slab Details 3 of 3
Figure 5-A-156



PLAN


SHOWN FOR SKEW ANGLE GREATER THAN OR EQUAL TO 20° (30° MAX.)



ELEVATION

NOTES

1. ALL PRESTRESSING STEEL SHALL BE ½"ø OR 0.6"ø LOW-RELAXATION 7-WIRE STRANDS AASHTO M203 GRADE 270. STRANDS SHALL BE TENSIONED INITIALLY TO 0.75 fpu.
2. ALL REINFORCING STEEL SHALL CONFORM TO AASHTO M31, GRADE 60. ALL REINFORCING STEEL SPLICES SHALL BE TWO FEET MINIMUM, UNLESS SHOWN OTHERWISE.
3. ALL REINFORCING BARS SHALL BE PLACED 2 INCHES FROM NEAREST FACE OF CONCRETE UNLESS SHOWN OTHERWISE.
4. CONCRETE MINIMUM COMPRESSIVE STRENGTH AT TRANSFER AND FINAL SHALL BE AS SHOWN IN THE DESIGN TABLE.
5. THE DEFLECTION VALUES LISTED IN THE DESIGN TABLE ARE COMPUTED DEFLECTIONS AT MID-SPAN BASED ON THE FOLLOWING TIME ELAPSE ASSUMPTIONS:
   - INITIAL CONCRETE COMPRESSIVE STRENGTH AT RELEASE WILL BE ATTAINED IN ONE (1) DAY.
   - FINAL CONCRETE COMPRESSIVE STRENGTH AT 28 DAYS WILL BE ATTAINED IN SEVEN (7) DAYS.
   - THE FINAL DEFLECTION IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS.
   - THE FINAL DEFLECTION DUE TO 85 PSF SUPERIMPOSED LOAD (ASPHALT OVERLAY, NOT INCLUDING TRAFFIC BARRIERS) IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS WITH THE LOAD ASSUMED TO BE PLACED ONE HUNDRED TWENTY (120) DAYS AFTER SLABS ARE CAST. IF THE ACTUAL CONDITIONS VARY SUBSTANTIALLY FROM THOSE ASSUMED ABOVE, THE DEFLECTION SHALL BE MODIFIED AND SUBMITTED TO THE ENGINEER FOR APPROVAL. THE TIME ASSUMPTION MAY VARY BY ± 30%
6. IT IS INTENDED THAT MEMBRANE WATERPROOFING AND ASPHALT OVERLAY BE INSTALLED ON THE IN-PLACE SLABS. THE ASPHALT SHALL BE VARIED TO PARTIALLY COMPENSATE FOR THE TWO THOUSAND (2000) DAY SLAB DEFLECTION. THE THICKNESS OF ASPHALT SHALL BE A MINIMUM OF 1½ INCHES AT MIDSPAN.
7. NO TRAFFIC SHALL BE ALLOWED ON A BEAM ADJACENT TO A GROUTED JOINT UNTIL THE GROUT HAS ATTAINED A MINIMUM STRENTH OF 4000 PSI.



* TOP 2" OF THE SLAB SHALL BE AIR-ENTRAINED CONCRETE.

= ○ = BONDED STRANDS
◇ = DEBONDED STRANDS


\# DISTANCE INDICATES LENGTH THAT EACH END OF CIRCLED STRANDS IS TO BE SLEEVED TO PREVENT BOND.

** NOTE PROJECT SPECIFIC TENSIONING SEQUENCE AND STRAND PATTERN

NOTES TO DESIGNER

STRAND SEQUENCE

| | | |




CAMBER DETAIL

C_I = CAMBER AT TRANSFER DUE TO PRESTRESSING AND GIRDER SELF WEIGHT.


C_{FINAL} = CAMBER AT 2000 DAYS.

C_{SIDL} = DEFLECTION DUE TO WEIGHT OF ACP OVERLAY AND TRAFFIC BARRIER.


$C_{F+SIDL} = C_{FINAL} + C_{SIDL}$




SECTION C
WELD TIE ALTERNATE #1




SECTION C
WELD TIE ALTERNATE #2



SECTION B
KEYWAY DETAIL



END VIEW
EXTERIOR SLAB



DEVELOPED ELEVATION
LIFTING LOOP

0.6"ø 7-WIRE STRANDS (AASHTO M203 GRADE 270) FOR LIFTING SLAB; MINIMUM OF 8 STRANDS PER SLAB. AFTER SLAB IS IN PLACE CUT STRAND 1¼" (MIN.) CLEAR OF TOP SLAB AND FILL HOLE WITH GROUT

BARLIST

ALL REINFORCING SHALL BE AASHTO M31 (GRADE 60)


MARK	LOCATION	SIZE	NO. REQ'D	BARLIST DIMENSION TABLE				BENDING DIAGRAM
G1	SLAB LONGIT. - TOP	#4	4 β	STR.				
G2	SLAB LONGIT. - BOT.		4	STR.	SLAB DEPTH	W	REQUIRED EMBEDMENT	
G3	END OF SLAB - TIE	#4	8		2'-2"	2'-1"	2'-3"	
G4	END OF SLAB - TIE		4					
G5	END OF SLAB - TIE	3	4 δ					
G7	SLAB TRANSV. - TIE	#4	VARIES WITH SPAN					
G8	SLAB TRANSV. - STIRRUP		4	VARIES WITH SPAN				
G7S	END OF SLAB - TIE	#4	AS REQ'D BY SKEW					
G8S	END OF SLAB - TIE		4	AS REQ'D BY SKEW				
S1	T.B. TO DECK TIE	#5	VARIES WITH SPAN					
S2	T.B. TO DECK TIE		4	VARIES WITH SPAN				

= EPOXY COATED

δ 2 BARS BUNDLED

β ADDITIONAL BARS WILL BE REQUIRED ON VOIDED SLABS W/BARRIERS, IF OPTION 1 ANCHOR PLATE DETAIL IS SELECTED.

* VARIABLE LENGTH TO ANCHOR PROVIDED BY VOIDED SLAB MANUFACTURER (BASED ON ANCHOR PLACEMENT.




DESIGN TABLE

STRENGTH OF CONCRETE: TRANSFER, F'ci = 5.5 kSI FINAL, F'c = 7.0 kSI
PRESTRESSING STRANDS, 0.60"ø, 270 kSI
* COMBINATION OF TOP AND BOTTOM STRANDS.

SPAN NUMBER	SPAN LENGTH ℄/℄ BRG. FT.	TOTAL NO. OF STRANDS	BOTTOM		TOP	* JACKING FORCE KIPS	* LOCATION OF C.G. OF STRAND "E" IN.	CAMBER (IN.)		
			BONDED	DE-BONDED				C_I	C_{FINAL}	C_{F+SIDL}

Precast Prestressed 2'-2" Voided Slab Details 2 of 3

Figure 5-A-158



PART SECTION
EXTERIOR SLAB


γ SPACING WILL BE DEVELOPED BY S1 & S2 LAYOUT.

β WELD SHALL BE SIZED TO DEVELOP 125% OF THE REBAR YIELD STRENGTH AND TESTED IN ACCORDANCE W/ 6-02.3 (24)E (L IS DEPENDANT ON COUPLER SELECTED)


σ PLACED ALONG ℄ WHEN VOIDED SLAB LONGITUDINAL REINFORCING OR STRANDS ARE NOT IN CONTACT W/ ℄

L LENGTH IS DEPENDENT ON COUPLER SELECTED


WELDED COUPLER TABLE	
BAR SPLICE	BPI BARSPLICER STRUCTURAL CONNECTOR
ERICO	LENTON WELDABLE COUPLER C2/C3J
BAR LOCK	STRUCTURAL STEEL CONNECTORS (WELDABLE HALF COUPLER) SCA




ANCHOR PLATE DETAIL




VIEW A
INSERT 1



VIEW B
INSERT 2




SECTION C




SECTION D

Precast Prestressed 2'-2" Voided Slab Details 3 of 3
Figure 5-A-159




Precast Prestressed Slab Layout

Figure 5-A-160




TYPICAL PIER ELEVATION

ELEVATION NORMAL TO ℄ ROADWAY



END VIEW

END BLOCK - BOTH ENDS OF PIER



** FOR DETAILS SEE INTERMEDIATE PIER SHEET.

DESIGN NOTES

1. PILE SPACING LISTED IN THE TABLES ARE THE MAXIMUM ALLOWED FOR EACH SPAN LENGTH FOR PILING (TIMBER, CONCRETE OR STEEL) NORMAL OR SKEWED TO THE CENTERLINE OF THE ROADWAY. THE LARGER OF THE TWO PILE SPACING VALUES LISTED FOR SPAN LENGHTS OF TEN (10) FOOT INCREMENTS MAY BE USED.
2. PILE SPACINGS ARE BASED ON 40 TON LOADING FOR TIMBER PILING AND 55 TON LOADING FOR CONCRETE AND STEEL PILING.
3. CONCRETE OR STEEL PILE SPACING LESS THAN 4'-0" MUST BE APPROVED BY THE SOILS ENGINEER. IF PILE SPACING LESS THAN FOUR FEET (4'-0") IS NOT ALLOWED THEN A DOUBLE ROW OF PILES MAY BE REQUIRED AT THE INTERMEDIATE PIER.
4. THIS STANDARD PILE SUBSTRUCTURE IS DESIGNED TO RESIST A SEISMIC LATERAL LOAD EQUIVALENT TO TEN PERCENT (10%) OF THE DEAD LOAD. THE TRANSVERS LATERAL LOAD IS RESISTED BY ALL THE PIERS (END AND INTERMEDIATE.) THE LONGITUDINAL LATERAL LOAD IS RESISTED BY ONE END PIER. THE RESISTANCE CAPACITY IS THE COMBINATION OF 6K/PILE LATERAL RESISTANCE AND PASSIVE SOIL PRESSURE AGAINST THE END PIER. THE PRESSURE WAS CALCULATED APPLYING THE FOLLOWING VALUES:
   - WEIGHT OF SOIL - W = 120 LBS/FT.
   - PASSIVE PRESSURE COEFFICIENT - KP = 3.5.
5. SINCE THE MAJORITY OF THE PIER'S LONGITUDINAL RESISTANCE CAPACITY IS DEVELOPED FROM PASSIVE SOIL PRESSURE, THE DEPTH OF THE END PIER DETERMINES THE MAXIMUM ALLOWABLE STRUCTURE LENGTH. THE TABLE BELOW GIVES THE TOTAL ALLOWABLE STRUCTURE LENGTH FOR A 3'-0" DEEP PIER CAP. FOR EXAMPLE, IF 8 - 32 FOOT SPANS OF 18 INCH SLABS WERE USED FOR A TOTAL STRUCTURE LENGTH OF 256 FEET, THE END PIER CAP WOULD HAVE TO BE DEEPENED BECAUSE THE ALLOWABLE STRUCTURE LENGTH IS ONLY 225 FEET. THE PIER CAP WOULD HAVE TO BE INCREASED TO 3'-6" WHICH ALLOWS FOR A STRUCTURE LENGTH OF 265 FEET FOR THIS SLAB DEPTH.

CONSTRUCTION NOTES

1. EXPOSED SMOOTH DOWELS SHALL BE PAINTED WITH 2 COATS OF STATE FORMULA A-9-73.
2. MECHANICAL BUTT SPLICES ARE REQUIRED FOR P5 #5 REINF. BARS WHEN STAGE CONSTRUCTION INTERFERES WITH THE REBAR CAGE EXTENDING ABOVE THE CONCRETE CAP. WHERE THE MECHANICAL BUTT SPLICE IS USED SEE ALTERNATE REBAR DETAIL.
3. DIMENSIONS SHOWN ARE NORMAL TO ℄ PIER.
4. SEE STANDARD PLAN E-4 FOR DETAILS OF 13 INCH PRECAST AND P.S. PILES. SEE STANDARD PLAN E-4a FOR DETAILS OF 16 INCH PILES.
5. ALL CAST-IN-PLACE PILES REQUIRE SPIRAL AND SPECIAL MAIN REINFORCEMENT WHEN USED FOR INTERIOR PILE BENTS. THE SPIRAL REINFORCEMENT SHALL BE W5 GAGE SPIRAL HOOPING AT 6 INCH CENTERS THE FULL LENGTH OF THE MAIN REINFORCEMENT AS CAST-IN-PLACE PILINGS. THE REINFORCEMENT SHALL EXTEND TO 25 FEET BELOW THE GROUNDLINE OR TO AN ELEVATION SHOWN IN THE PLANS. MINIMUM EXTENSION OF 9 - #8 REBAR INTO THE PILE CAPS 1'-9" UNLESS OTHERWISE SHOWN.
6. MAIN REINFORCEMENT SHALL BE AASHTO M 31. SPIRAL HOOPING SHALL CONFORM TO AASHTO M 32. GALVANIZE SMOOTH DOWELS PER AASHTO M 111.


BAR LIST


ALL REINFORCING SHALL BE AASHTO M 31, GR. 60.

MARK	LOCATION	SIZE	NO. REQ'D. PER PIER	BENDING DIAGRAM
P1	LONGIT - TOP & BOT.	11	4	STR
P2	STIRRUPS	4	VARIES W/PIER LENGTH	
P3	STIRRUPS	4	VARIES W/PIER LENGTH	
P4	END BLOCK REINF.	4	8	STR
P5	END BLOCK STIRR.	5	10	
P6	CORNER DOWELS	5	10	
	END BLOCK W/O APPROACH SLAB			
E1	LONGIT.	4	4	STR
E2	END BLOCK STIRR.	4	VARIES W/PIER LENGTH	
	ADDITIONAL APPROACH SLAB STEEL			
A1	DOWELS	6	VARIES W/PIER LENGTH	
A2	LONGIT.	▽6	3	STR
A3	STIRRUPS	▽5	VARIES W/PIER LENGTH	

SLAB	X	Y	Z
1'-0"	3'-10"	2'-6"	11"
1'-6"	4'-4"	3'-0"	1'-5"
2'-2"	5'-0"	3'-8"	2'-1"

▽ Epoxy Coated






HINGE DETAIL

ALL DIMENSIONS SHOWN ARE NORMAL TO ℄ BRG.

Precast Prestressed Slab End Pier Details 1 of 2

Figure 5-A-161




SECTION A

WITHOUT APPROACH SLAB

NOTE: THIS DETAIL IS TO BE USED BEYOND THE LIMITS OF THE APPROACH SLAB.
ALL DIMENSIONS SHOWN ARE NORMAL TO ℄ BRG.

** 3'-0" MINIMUM - SEE INTERMEDIATE PIER SHEET.




SECTION A
WITH CONCRETE PILES

WITH APPROACH SLAB

NOTE: END ANCHORS NOT REQUIRED PER STD. PLAN A-2
ALL DIMENSIONS SHOWN ARE NORMAL TO ℄ BRG.


δ - DEFLECTION DUE TO VOIDED SLAB CAMBER, MAINTAINING ASPHALT OVERLAY REQUIREMENTS AT MIDSPAN.



JOINT DETAIL


JOINT DETAIL TAKEN @ EXTERIOR PIER

* 1" MIN. GAP SHALL BE MAINTAINED PRIOR TO PLACEMENT OF GROUT AND JOINT FILLER.



SECTION C

NOTE:
FULL BEARING OF SLAB UNIT IS REQUIRED AT EACH ELASTOMERIC BEARING




BEARING DETAILS

BEARING PAD TABLE	
SLAB DEPTH	WIDTH x LENGTH
1'-0"	5" x 10"
1'-6"	5" x 15"
2'-2"	5" x 16"

MAXIMUM CONCRETE/STEEL PILE SPACING TABLE
FOS SLAB DEPTHS SHOWN BELOW


	W/O APPROACH SLABS			W/ APPROACH SLABS			INTERIOR PIER		
SPAN (FT.)	12"	18"	26"	12"	18"	26"	12"	18"	26"
0 to 10	10'-0"	—	—	10'-0"	—	—	8'-3"	—	—
10 to 20	10'-0"	—	—	9'-6"	—	—	6'-6"	—	—
20 to 30	10'-0"	10'-0"	—	8'-4"	8'-3"	—	5'-6"	5'-4"	—
30 to 40	9'-3"	9'-0"	8'-4"	7'-6"	7'-4"	6'-11"	4'-9"	4'-7"	4'-3"
40 to 50	—	7'-11"	7'-4"	—	6'-8"	6'-2"	4'-3"	4'-2"	3'-9"
50 to 60	—	—	6'-6"	—	—	5'-8"	—	3'-9"	3'-5"
60 to 70	—	—	6'-0"	—	—	5'-2"	—		3'-1"

Precast Prestressed Slab End Pier Details 2 of 2
Figure 5-A-162



TYPICAL PIER ELEVATION

ELEVATION NORMAL TO ℄ ROADWAY



SECTION A
WITH STEEL PILES

SECTION A
WITH CONCRETE PILES

DESIGN NOTES

1. PILE SPACING LISTED IN THE TABLES ARE THE MAXIMUM ALLOWED FOR EACH SPAN LENGTH FOR PILING (TIMBER, CONCRETE OR STEEL) NORMAL OR SKEWED TO THE CENTERLINE OF THE ROADWAY. THE LARGER OF THE TWO PILE SPACING VALUES LISTED FOR SPAN LENGHTS OF TEN (10) FOOT INCREMENTS MAY BE USED.
2. PILE SPACINGS ARE BASED ON 40 TON LOADING FOR TIMBER PILING AND 55 TON LOADING FOR CONCRETE AND STEEL PILING.
3. CONCRETE OR STEEL PILE SPACING LESS THAN 4'-0" MUST BE APPROVED BY THE SOILS ENGINEER. IF PILE SPACING LESS THAN FOUR FEET (4'-0") IS NOT ALLOWED THEN A DOUBLE ROW OF PILES MAY BE REQUIRED AT THE INTERMEDIATE PIER.
4. THIS STANDARD PILE SUBSTRUCTURE IS DESIGNED TO RESIST A SEISMIC LATERAL LOAD EQUIVALENT TO TEN PERCENT (10%) OF THE DEAD LOAD. THE TRANSVERS LATERAL LOAD IS RESISTED BY ALL THE PIERS (END AND INTERMEDIATE.) THE LONGITUDINAL LATERAL LOAD IS RESISTED BY ONE END PIER. THE RESISTANCE CAPACITY IS THE COMBINATION OF 6K/PILE LATERAL RESISTANCE AND PASSIVE SOIL PRESSURE AGAINST THE END PIER. THE PRESSURE WAS CALCULATED APPLYING THE FOLLOWING VALUES:
   - WEIGHT OF SOIL - W = 120 LBS/FT.
   - PASSIVE PRESSURE COEFFICIENT - KP = 3.5.
5. SINCE THE MAJORITY OF THE PIER'S LONGITUDINAL RESISTANCE CAPACITY IS DEVELOPED FROM PASSIVE SOIL PRESSURE, THE DEPTH OF THE END PIER DETERMINES THE MAXIMUM ALLOWABLE STRUCTURE LENGTH. THE TABLE BELOW GIVES THE TOTAL ALLOWABLE STRUCTURE LENGTH FOR A 3'-0" DEEP PIER CAP. FOR EXAMPLE, IF 8 - 32 FOOT SPANS OF 18 INCH SLABS WERE USED FOR A TOTAL STRUCTURE LENGTH OF 256 FEET, THE END PIER CAP WOULD HAVE TO BE DEEPENED BECAUSE THE ALLOWABLE STRUCTURE LENGTH IS ONLY 225 FEET. THE PIER CAP WOULD HAVE TO BE INCREASED TO 3'-6" WHICH ALLOWS FOR A STRUCTURE LENGTH OF 265 FEET FOR THIS SLAB DEPTH.


CONSTRUCTION NOTES

1. EXPOSED SMOOTH DOWELS SHALL BE PAINTED WITH 2 COATS OF STATE FORMULA A-9-73.
2. MECHANICAL BUTT SPLICES ARE REQUIRED FOR P5 #5 REINF. BARS WHEN STAGE CONSTRUCTION INTERFERES WITH THE REBAR CAGE EXTENDING ABOVE THE CONCRETE CAP. WHERE THE MECHANICAL BUTT SPLICE IS USED SEE ALTERNATE REBAR DETAIL.
3. DIMENSIONS SHOWN ARE NORMAL TO ℄ PIER.
4. SEE STANDARD PLAN E-4 FOR DETAILS OF 13 INCH PRECAST AND P.S. PILES. SEE STANDARD PLAN E-4a FOR DETAILS OF 16 INCH PILES.
5. ALL CAST-IN-PLACE PILES REQUIRE SPIRAL AND SPECIAL MAIN REINFORCEMENT WHEN USED FOR INTERIOR PILE BENTS. THE SPIRAL REINFORCEMENT SHALL BE W5 GAGE SPIRAL HOOPING AT 6 INCH CENTERS THE FULL LENGTH OF THE MAIN REINFORCEMENT AS CAST-IN-PLACE PILINGS. THE REINFORCEMENT SHALL EXTEND TO 25 FEET BELOW THE GROUNDLINE OR TO AN ELEVATION SHOWN IN THE PLANS. MINIMUM EXTENSION OF 9 - #8 REBAR INTO THE PILE CAPS 1'-9" UNLESS OTHERWISE SHOWN.
6. MAIN REINFORCEMENT SHALL BE AASHTO M 31. SPIRAL HOOPING SHALL CONFORM TO AASHTO M 32. GALVANIZE SMOOTH DOWELS PER AASHTO M 111.

BAR LIST

ALL REINFORCING SHALL BE AASHTO M 31, GR 60


MARK	LOCATION	SIZE	NO. REQUIRED PER PIER	BENDING DIAGRAM
	WEBWALL STEEL			
W1	HORIZ. BARS	4	VARIES W/ PIER HEIGHT	
W2	HORIZ. END BARS	4	VARIES W/ PIER HEIGHT	
W3	VERTICAL	4	VARIES W/ PIER HEIGHT	STR.
W4	HORIZ. TIE BARS	4	VARIES W/ PIER HEIGHT & LENGTH	



HEIGHT TABLE

	CASED	NOT CASED
1'-0" C.I.P. & 1'-1" P.C.	20'-0"	7'-0"
1'-2" C.I.P. & 1'-4" P.C.	20'-0"	15'-0"
HP 12 x 53 STEEL	20'-0"	—

NOTE:
FOR STIRRUP SPACING AND OTHER ADDITIONAL PIER DETAILS REFER TO THE "TYPICAL PIER ELEVATION." SEE STANDARD PILE END PIER SHEET. SEE NOTE AT TOP RIGHT FOR PILE REINFORCEMENT REQUIREMENTS.




TOTAL ALLOWABLE STRUCTURE LENGTH

≠ PIER CAP DEPTH	3'-0"		3'-6"		4'-0"	
SLAB DEPTH	TOTAL LENGTH	W	TOTAL LENGTH	W	TOTAL LENGTH	W
1'-0"	200'	2'-8"	240'	3'-2"	280'	3'-8"
1'-6"	225'	2'-8"	265'	3'-2"	310'	3'-8"
2'-2"	235'	2'-8"	275'	3'-2"	320'	3'-8"

** FOR THE DIMENSIONS OF BARS WHEN A PIER CAP DEPTH OTHER THAN 3'-0" IS USED SEE THE VALUE FOR W SHOWN IN TABLE ABOVE


Precast Prestressed Slab Intermediate Piers Details 1 of 2

Figure 5-A-163




SECTION B / 1

NOTE:
FOR REINFORCING DETAILS FOR P1 THRU P6
SEE BARLIST ON STANDARD PILE END PIER SHEET




BEARING DETAILS



JOINT DETAIL

JOINT DETAIL TAKEN @ INTERIOR PIER

BEARING PAD TABLE	
SLAB DEPTH	WIDTH x LENGTH
1'-0"	5" x 10"
1'-6"	5" x 16"
2'-2"	5" x 16"




SECTION C

NOTE:
FULL BEARING OF SLAB UNIT IS REQUIRED AT EACH ELASTOMERIC BEARING

Precast Prestressed Slab Intermediate Piers Details 2 of 2

Figure 5-A-164



END DIAPHRAGM DETAIL


DIAPHRAGM DIMENSIONS ARE NORMAL TO SKEW.
ALL OTHERS ARE PARALELL TO ℄ GIRDER

ELEVATION

END DIAPHRAGM NOT SHOWN

NOTES

1. CONCRETE SHALL BE WITH A MINIMUM COMPRESSIVE STRENGTH AT TRANSFER AND FINAL AS SHOWN IN THE DESIGN TABLE. ALL PRESTRESSING STEEL SHALL BE ½"ø OR 0.6"ø LOW RELAXATION 7-WIRE STRANDS (AASHTO M 203, GRADE 270.) STRANDS SHALL BE TENSIONED INITIALLY TO 0.75 Fpu. PLATES AND ANGLES SHALL CONFORM TO AASHTO M183 AND SHALL BE PAINTED WITH 2 COATS OF STATE FORMULA A-9-73.
2. ALL REINFORCING STEEL SHALL CONFORM TO AASHTO M31, GRADE 60. ALL REINFORCING STEEL SPLICES SHALL BE 2'-0" MINIMUM UNLESS SHOWN OTHERWISE. ALL DEFORMED WIRE SHALL BE PER ASTM A 496.
3. ALL REINFORCING BARS SHALL BE PLACED 2" CLEAR OF THE NEAREST FACE OF CONCRETE UNLESS SHOWN OTHERWISE.
4. NO TRAFFIC SHAL BE ALLOWED ON A BEAM ADJACENT TO A GROUTED JOINT UNTIL THE GROUT HAS ATTAINED A MINIMUM STRENGTH OF 4,000 PSI.
5. THE DEFLECTION VALUES LISTED IN THE DESIGN TABLE ARE COMPUTED DEFLECTIONS AT MID-SPAN BASED ON THE FOLLOWING TIME ELAPSE ASSUMPTIONS:
   - INITIAL CONCRETE COMPRESSIVE STRENGTH AT RELEASE WILL BE ATTAINED IN ONE (1) DAY.
   - FINAL CONCRETE COMPRESSIVE STRENGTH AT 28 DAYS WILL BE ATTAINED IN SEVEN (7) DAYS.
   - THE FINAL DEFLECTION IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS.
   - THE FINAL DEFLECTION DUE TO SUPERIMPOSED LOAD (ASPHALT OVERLAY PLUS TRAFFIC BARRIERS) IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS WITH THE LOAD ASSUMED TO BE PLACED SIXTY (60) DAYS AFTER BEAMS ARE CAST.
6. IF THE ACTUAL CONDITIONS VARY SUBSTANTIALLY FROM THOSE ASSUMED ABOVE, THE DEFLECTIONS SHOULD BE MODIFIED AND SUBMITTED TO THE DESIGN ENGINEER FOR APPROVAL. THE TIME ASSUMPTIONS MAY VARY BY ± 30%.
7. IT IS INTENDED THAT A MEMBRANE WATERPROOFING AND ASPHALT OVERLAY WILL BE INSTALLED ON THE IN-PLACE SECTION. THE ASPHALT SHALL BE VARIED TO PARTIALLY COMPENSATE FOR THE TWO THOUSAND (2000) DAY SLAB DEFLECTION. THE THICKNESS OF ASPHALT SHALL BE A MINIMUM OF 0.15 FEET AT THE MIDSPAN.





GIRDER PLAN

OMIT WELD TIES ON EXTERIOR EDGE OF EXTERIOR GIRDER.
* LONGITUDINAL WELD TIES ARE REQUIRED AT END PIER WHEN APPROACH SLAB IS USED

▽ EPOXY COATED


MARK	LOCATION	SIZE	NO. REQ'D.	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
G1	STEM - LONGIT.	▽5	6	
G2	DIAPH. - TRANSV.	▽5	6	STR.
G3	TRANSV.	▽4	VARIES	STR.
G4	TRANSV.	4	VARIES	STR.
G5	LONGITUDINAL	▽4	VARIES	
S1	T.B. TO DECK TIE.	▽5	VARIES	
S2	T.B. TO DECK TIE	4	VARIES	





EXTERIOR GIRDER REINFORCING

* ALTERNATIVELY THE TOP 2 INCHES OF THE GIRDER FLANGE MAY BE AIR-ENTRAINED CONCRETE.



** STIRRUP SPACING TO BE DETERMINED BY ANALYSIS


SYMM. ABOUT ℄ OF SECTION UNLESS SHOWN OTHERWISE

TYPICAL SECTION


SECTION SHOWN NEAR MIDSPAN

Precast Prestressed Ribbed Girder Details 1 of 2

Figure 5-A-165



STRAND PATTERN AT GIRDER END




CAMBER DETAIL

C_I = CAMBER AT TRANSFER DUE TO PRESTRESSING AND GIRDER SELF WEIGHT.


C_{FINAL} = CAMBER AT 2000 DAYS.

C_{SIDL} = DEFLECTION DUE TO WEIGHT OF ACP OVERLAY AND TRAFFIC BARRIER.


$C_{F+SIDL} = C_{FINAL} + C_{SIDL}$




LONGITUDINAL WELD TIE DETAIL




SECTION A 1
KEYWAY ALTERNATE 1




SECTION B 1
WELD TIE ALTERNATE #1




SECTION B 1
WELD TIE ALTERNATE #2




SECTION B 1
WELD TIE ALTERNATE #3



SECTION A 1
KEYWAY ALTENATE 2



PLAN



ELEVATION


STEM RECESS DETAIL

DESIGN TABLE

PLAN LENGTH (FT.)	NOMINAL SPAN CTR. TO CTR. BEARING (FT.)	HARP POINT (: × PLAN LENGTH)	NO. STRANDS	DIMENSION "W"	F ℄ (IN.)	DISTANCE "E" TO C.G.S. AT END BLOCK (IN.)	CONCRETE COMPRESSIVE STRENGTH		ESTIMATED DEFLECTION AT MIDSPAN (IN.)		
							INITIAL AT RELEASE (KSI)	FINAL AT 28 DAYS (KSI)	UPWARD AT TRANSFER OF PRESTRESS (Δ1)	FINAL UPWARD FOR RIBBED GIRDER ONLY (Δ 2000)	FINAL DOWNWARD DUE TO SUPER IMPOSED DEAD LOAD/(Δ SDL)


Precast Prestressed Ribbed Girder Details 2 of 2

Figure 5-A-166




END PIER WITHOUT APPROACH SLAB

NOTE: ALL DIMENSIONS SHOWN ARE NORMAL TO ℄ BRG.




END PIER WITH APPROACH SLAB


NOTE: END ANCHORS NOT REQUIRED PER STD. PLAN A-2
ALL DIMENSIONS SHOWN ARE NORMAL TO BRG.



INTERIOR PIER




END PIER W/O APPROACH SLAB




END VIEW

END BLOCK - BOTH ENDS OF PIER




SHEAR BLOCK DETAIL


POUR AFTER TRI-BEAMS HAVE BEEN PLACED AND GROUTED




SECTION - TRAFFIC BARRIER



END PIER W/APPROACH SLAB



BEARING DETAILS



JOINT DETAIL

JOINT DETAIL TAKEN @ INTERIOR PIER AND PIER WITH APPROACH SLAB


NOTE: FULL BEARING OF TRI-BEAM UNIT IS REQUIRED AT EACH ELASTOMERIC BEARING.

BAR LIST

▽ Epoxy Coated


BENDING DIAGRAM
ALL REINFORCING SHALL BE AASHTO M 31, GR. 60

MARK	LOCATION	SIZE	NO. REQ'D. PER PIER	
P1	LONGIT - TOP & BOT.	11	4	STR
P2	STIRRUPS	4	VARIES W/PIER LENGTH	
P3	STIRRUPS	4	VARIES W/PIER LENGTH	
P4	END BLOCK REINF.	4	8	STR
P5	END BLOCK STIRR.	5	10	
P6	CORNER DOWELS	5	10	
	END BLOCK W/O APPROACH SLAB			
E1	LONGIT.	4	4	STR
E2	END BLOCK STIRR.	4	VARIES W/PIER LENGTH	
	ADDITIONAL APPROACH SLAB STEEL			
A1	DOWELS	6	VARIES W/PIER LENGTH	
A2	LONGIT.	▽6	3	STR
A3	STIRRUPS	▽5	VARIES W/PIER LENGTH	




Precast Prestressed Ribbed Girder Pier Details

Figure 5-A-167



END DIAPHRAGM DETAIL

DIAPHRAGM DIMENSIONS ARE NORMAL TO SKEW. ALL OTHERS ARE PARALELL TO ℄ GIRDER




ELEVATION

END DIAPHRAGM NOT SHOWN


NOTES


1. CONCRETE SHALL BE WITH A MINIMUM COMPRESSIVE STRENGTH AT TRANSFER AND FINAL AS SHOWN IN THE DESIGN TABLE. ALL PRESTRESSING STEEL SHALL BE ½"ø OR 0.6"ø LOW RELAXATION 7-WIRE STRANDS (AASHTO M 203, GRADE 270.) STRANDS SHALL BE TENSIONED INITIALLY TO 0.75 Fpu. PLATES AND ANGLES SHALL CONFORM TO AASHTO M183 AND SHALL BE PAINTED WITH 2 COATS OF STATE FORMULA A-9-73.
2. ALL REINFORCING STEEL SHALL CONFORM TO AASHTO M31, GRADE 60. ALL REINFORCING STEEL SPLICES SHALL BE 2'-0" MINIMUM UNLESS SHOWN OTHERWISE. ALL DEFORMED WIRE SHALL BE PER ASTM A 496.
3. ALL REINFORCING BARS SHALL BE PLACED 2" CLEAR OF THE NEAREST FACE OF CONCRETE UNLESS SHOWN OTHERWISE.
4. NO TRAFFIC SHAL BE ALLOWED ON A BEAM ADJACENT TO A GROUTED JOINT UNTIL THE GROUT HAS ATTAINED A MINIMUM STRENGTH OF 4,000 PSI.
5. THE DEFLECTION VALUES LISTED IN THE DESIGN TABLE ARE COMPUTED DEFLECTIONS AT MID-SPAN BASED ON THE FOLLOWING TIME ELAPSE ASSUMPTIONS:
   - INITIAL CONCRETE COMPRESSIVE STRENGTH AT RELEASE WILL BE ATTAINED IN ONE (1) DAY.
   - FINAL CONCRETE COMPRESSIVE STRENGTH AT 28 DAYS WILL BE ATTAINED IN SEVEN (7) DAYS.
   - THE FINAL DEFLECTION IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS.
   - THE FINAL DEFLECTION DUE TO SUPERIMPOSED LOAD (ASPHALT OVERLAY PLUS TRAFFIC BARRIERS) IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS WITH THE LOAD ASSUMED TO BE PLACED SIXTY (60) DAYS AFTER BEAMS ARE CAST.
6. IF THE ACTUAL CONDITIONS VARY SUBSTANTIALLY FROM THOSE ASSUMED ABOVE, THE DEFLECTIONS SHOULD BE MODIFIED AND SUBMITTED TO THE DESIGN ENGINEER FOR APPROVAL. THE TIME ASSUMPTIONS MAY VARY BY ± 30%.
7. IT IS INTENDED THAT A MEMBRANE WATERPROOFING AND ASPHALT OVERLAY WILL BE INSTALLED ON THE IN-PLACE SECTION. THE ASPHALT SHALL BE VARIED TO PARTIALLY COMPENSATE FOR THE TWO THOUSAND (2000) DAY SLAB DEFLECTION. THE THICKNESS OF ASPHALT SHALL BE A MINIMUM OF 0.15 FEET AT THE MIDSPAN.



GIRDER PLAN

OMIT WELD TIES ON EXTERIOR EDGE OF EXTERIOR GIRDER.
* LONGITUDINAL WELD TIES ARE REQUIRED AT END PIER WHEN APPROACH SLAB IS USED






TYPICAL SECTION

SECTION SHOWN NEAR MIDSPAN

▽ EPOXY COATED

MARK	LOCATION	SIZE	NO. REQ'D.	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
G1	STEM - LONGIT.	▽5	6	
G2	DIAPH. - TRANSV.	▽5	6	STR.
G3	TRANSV.	▽4	VARIES	VARIES
G4	TRANSV.	4	VARIES	STR.
G5	LONGITUDINAL	▽4	VARIES	
S1	T.B. TO DECK TIE.	▽5	VARIES	
S2	T.B. TO DECK TIE	4	VARIES	




EXTERIOR GIRDER REINFORCING

* ALTERNATIVELY THE TOP 2 INCHES OF THE GIRDER FLANGE MAY BE AIR-ENTRAINED CONCRETE.


** STIRRUP SPACING TO BE DETERMINED BY ANALYSIS

Precast Prestressed Double T Details 1 of 2

Figure 5-A-168



STRAND PATTERN AT GIRDER END




CAMBER DETAIL

C_I = CAMBER AT TRANSFER DUE TO PRESTRESSING AND GIRDER SELF WEIGHT.


C_{FINAL} = CAMBER AT 2000 DAYS.

C_{SIDL} = DEFLECTION DUE TO WEIGHT OF ACP OVERLAY AND TRAFFIC BARRIER.


$C_{F+SIDL} = C_{FINAL} + C_{SIDL}$




LONGITUDINAL WELD TIE DETAIL




SECTION A 1
KEYWAY ALTERNATE 1




SECTION B 1
WELD TIE ALTERNATE #1




SECTION B 1
WELD TIE ALTERNATE #2




SECTION B 1
WELD TIE ALTERNATE #3



SECTION A 1
KEYWAY ALTENATE 2



PLAN



ELEVATION


STEM RECESS DETAIL

DESIGN TABLE

PLAN LENGTH (FT.)	NOMINAL SPAN CTR. TO CTR. BEARING (FT.)	HARP POINT (☐ : x PLAN LENGTH)	NO. STRANDS	DIMENSION "W"	F ℄ (IN.)	DISTANCE "E" TO C.G.S. AT END BLOCK (IN.)	CONCRETE COMPRESSIVE STRENGTH		ESTIMATED DEFLECTION AT MIDSPAN (IN.)		
							INITIAL AT RELEASE (KSI)	FINAL AT 28 DAYS (KSI)	UPWARD AT TRANSFER OF PRESTRESS (△ 1)	FINAL UPWARD FOR RIBBED GIRDER ONLY (△ 2000)	FINAL DOWNWARD DUE TO SUPER IMPOSED DEAD LOAD(△ SDL)

Precast Prestressed Double T Details 2 of 2

Figure 5-A-169



GIRDER ELEVATION


\# MIDPOINT OF SPAN FOR SPAN LENGTHS 40'-0" to 80'-0". NO INTERMEDIATE DIAPHRAGM FOR SPAN LENGTHS 40'-0" OR LESS

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE INSERT OR APPROVED EQUAL. (TYP.)

** ⅛ : 1 FOR ½"ø STRANDS & ⅙ : 1 FOR 0.6"ø STRANDS


GENERAL NOTES


1. ALL DETAILS SHOWN PERTAIN ONLY TO THE 35 INCH DEEP GIRDER WITH THE 6'-0" GIRDER WIDTH SHOWN.
2. FORMS FOR THE BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER SO AS TO NOT CAUSE DAMAGE TO THE GIRDERS DURING THE STRAND RELEASE OPERATION.
3. SPAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE
4. ALL PRESTRESSING STRANDS SHALL BE ½ INCH OR 0.6 INCH ø LOW RELAXATION SEVEN WIRE STRAND, AASHTO M203 GR. 270. ALL MILD STEEL REINFORCING SHALL BE AASHTO M31 GR. 60. ALL STUDS SHALL CONFORM TO STD. SPEC. SECTION 9-06.15. ALL OTHER STEEL SHALL BE AASHTO M183 AND SHALL BE PAINTED WITH 2 COATS OF STATE FORMULA A-9-73.
5. CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS EXCEPT FOR THOSE SHOWN TO BE EXTENDED, AND PAINT ENDS OF FLUSH STRANDS WITH AN APPROVED EPOXY RESIN.
6. AFTER ERECTION, CUT OFF LIFTING LOOPS 1 INCH BELOW THE TOP OF THE FLANGE AND FILL WITH AN APPROVED GROUT PRIOR TO PLACING OF THE OVERLAY. ALL LIFTING STRANDS ARE TO BE OF THE SAME MATERIAL AND STRENGTH AS THE PRESTRESSING STRANDS. WRAP LIFTING LOOPS SO THAT EACH STRAND WILL CARRY IT'S SHARE OF THE TOTAL LOAD. EXTEND LIFTING LOOPS WITH 9 INCH LONG 90° HOOKS TO WITHIN 3 INCHES CLEAR OF THE BOTTOM OF THE GIRDER.
7. TOP 2 INCHES OF THE GIRDER FLANGE SHALL BE AIR-ENTRAINED CONCRETE.



GIRDER PLAN


OMIT WELD TIES ON EXTERIOR EDGE OF EXTERIOR GIRDER. (STRANDS AND LONGITUDINAL BARS NOT SHOWN)






EXTERIOR GIRDER REINFORCING NEAR GIRDER END

FOR DETAILS NOT SHOWN, SEE INTERIOR GIRDER



INTERIOR GIRDER REINFORCING NEAR MIDSPAN

*** THICKEN FLANGE TO COMPENSATE FOR SUPERELEVATION.




PLAN SECTION THROUGH GIRDER WEB

▽ DENOTES EPOXY COATED

△△ #3 OR #4 BARS MAY BE USED IN LIEU OF W12. FIELD BEND IS OPTIONAL.


MARK	LOCATION	SIZE
G1	GIRDER STIRRUPS	4
G2	GIRDER END STIRRUPS	5
G3	BOTTOM FLANGE	3
G4	TOP OF TOP FLANGE - LONGIT.	▽4 STR.
G5	BOT. OF TOP FLANGE - TRANSV.	4
G6	TOP TRANSV. - EXT. GIRDER	▽6
G7	TOP TRANSV. - INT. GIRDER	▽6 STR.
G8	BOT. OF TOP FLANGE - LONGIT.	4 STR.
G10	GIRDER END TIES	W12 △△
G11	GIRDER LONGIT.	6 STR.
S1	T.B. TO DECK TIE	▽5
S2	T.B. TO DECK TIE	4

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)




W35DG Deck Bulb Tee Girder Details 1 of 2

Figure 5-A-170




STRAND PATTERN AT GIRDER END

HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




TIE SPACING DETAIL




SAWTEETH DETAILS


SAWTEETH ARE FULL WIDTH - USE SAWTEETH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND




SECTION A 1
KEYWAY




SECTION B 1
WELD TIE ALTERNATE #1




SECTION B 1
WELD TIE ALTERNATE #2




SECTION B 1
WELD TIE ALTERNATE #3



GIRDER FLANGE THICKENING**



GIRDER END
AT END PIERS




* ALTERNATIVELY THE TOP 2 INCHES OF THE GIRDER FLANGE MAY BE AIR-ENTRAINED CONCRETE.

** THICKEN FLANGE TO COMPENSATE FOR CAMBER DUE TO PRESTRESS. FLANGE THICKNESS SHOWN IS @ ℄ OF SPAN. FOR FLANGE THINCKNESS ALONG GIRDER SEE GIRDER FLANGE THICKENING DETAILS ON BR. SHEET ____. GIRDERS WITH ULTIMATE CAMBER VALUES SMALLER THAN ¾" ARE EXEMPT FROM THIS REQUIREMENT. FLANGE THICKENING SHALL BE USED ONLY IF NEEDED BY DESIGN.

GIRDER SCHEDULE


W35DG Deck Bulb Tee Girder Details 2 of 2

Figure 5-A-171




ELEVATION - TYPICAL END DIAPHRAGM AT INTERMEDIATE PIERS

CONCRETE CLASS 4000, CAST IN PLACE




SECTION A

LONGIT. DIMENSIONS ARE NORMAL TO SKEW




END DIAPHRAGMS AT INTERMEDIATE PIER

LONGITUDINAL DIMENSIONS ARE NORMAL TO PIER




ELEVATION - TYPICAL INTERMEDIATE DIAPHRAGM

CONCRETE CLASS 4000, CAST IN PLACE




SECTION B



MISC. DECK BULB TEE DIAPHRAGM DETAILS SHEET


ELEVATION - TYPICAL END DIAPHRAGM AT END PIERS

CONCRETE CLASS 4000, CAST IN PLACE



ANCHOR DETAIL

A.S.T.M. A-307




SECTION C

ALL LONGITUDINAL DIMENSIONS SHOWN ARE NORMAL TO ℄ BRG.

W35DG Deck Bulb Tee Diaphragm Details

Figure 5-A-172




GIRDER ELEVATION

*OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE INSERT OR APPROVED EQUAL. (TYP.)


GENERAL NOTES

1. ALL DETAILS SHOWN PERTAIN ONLY TO THE 41 INCH DEEP GIRDER WITH THE 6'-0" GIRDER WIDTH SHOWN.
2. FORMS FOR THE BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER SO AS TO NOT CAUSE DAMAGE TO THE GIRDERS DURING THE STRAND RELEASE OPERATION.
3. SPAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE
4. ALL PRESTRESSING STRANDS SHALL BE ½ INCH OR 0.6 INCH ø LOW RELAXATION SEVEN WIRE STRAND, AASHTO M203 GR. 270. ALL MILD STEEL REINFORCING SHALL BE AASHTO M31 GR. 60. ALL STUDS SHALL CONFORM TO STD. SPEC. SECTION 9-06.15. ALL OTHER STEEL SHALL BE AASHTO M183 AND SHALL BE PAINTED WITH 2 COATS OF STATE FORMULA A-9-73.
5. CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS EXCEPT FOR THOSE SHOWN TO BE EXTENDED, AND PAINT ENDS OF FLUSH STRANDS WITH AN APPROVED EPOXY RESIN.
6. AFTER ERECTION, CUT OFF LIFTING LOOPS 1 INCH BELOW THE TOP OF THE FLANGE AND FILLWITH AN APPROVED GROUT PRIOR TO PLACING OF THE OVERLAY. ALL LIFTING STRANDS ARE TO BE OF THE SAME MATERIAL AND STRENGTH AS THE PRESTRESSING STRANDS. WRAP LIFTING LOOPS SO THAT EACH STRAND WILL CARRY IT'S SHARE OF THE TOTAL LOAD. EXTEND LIFTING LOOPS WITH 9 INCH LONG 90° HOOKS TO WITHIN 3 INCHES CLEAR OF THE BOTTOM OF THE GIRDER.
7. TOP 2 INCHES OF THE GIRDER FLANGE SHALL BE AIR-ENTRAINED CONCRETE.




GIRDER PLAN

OMIT WELD TIES ON EXTERIOR EDGE OF EXTERIOR GIRDER. (STRANDS AND LONGITUDINAL BARS NOT SHOWN)




PLAN SECTION THROUGH GIRDER WEB



EXTERIOR GIRDER REINFORCING NEAR GIRDER END

FOR DETAILS NOT SHOWN, SEE INTERIOR GIRDER



INTERIOR GIRDER REINFORCING NEAR MIDSPAN


*** THICKEN FLANGE TO COMPENSATE FOR SUPERELEVATION.

▽ DENOTES EPOXY COATED

△△ #3 OR #4 BARS MAY BE USED IN LIEU OF W12. FIELD BEND IS OPTIONAL.


MARK	LOCATION	SIZE
G1	GIRDER STIRRUPS	4
G2	GIRDER END STIRRUPS	5
G3	BOTTOM FLANGE	3
G4	TOP OF TOP FLANGE - LONGIT.	▽4 STR.
G5	BOT. OF TOP FLANGE - TRANSV.	4
G6	TOP TRANSV. - EXT. GIRDER	▽6
G7	TOP TRANSV. - INT. GIRDER	▽6 STR.
G8	BOT. OF TOP FLANGE - LONGIT.	4 STR.
G10	GIRDER END TIES	W12 △△
G11	GIRDER LONGIT.	6 STR.
S1	T.B. TO DECK TIE	▽5
S2	T.B. TO DECK TIE	4

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)




W41DG Deck Bulb Tee Girder Details 1 of 2

Figure 5-A-173




STRAND PATTERN AT GIRDER END

HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




TIE SPACING DETAIL




SAWTEETH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTEETH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND




GIRDER END


AT END PIERS




SECTION (B) (1) WELD TIE ALTERNATE #1



SECTION (B) (1) WELD TIE ALTERNATE #2




SECTION (B) (1) WELD TIE ALTERNATE #3




BEARING RECESS

BEARING RECESS IS NORMAL TO ℄ GIRDER



SECTION (A) (1) KEYWAY




GIRDER FLANGE THICKENING**

* ALTERNATIVELY THE TOP 2 INCHES OF THE GIRDER FLANGE MAY BE AIR-ENTRAINED CONCRETE.

** THICKEN FLANGE TO COMPENSATE FOR CAMBER DUE TO PRESTRESS. FLANGE THICKNESS SHOWN IS @ ℄ OF SPAN. FOR FLANGE THINCKNESS ALONG GIRDER SEE GIRDER FLANGE THICKENING DETAILS ON BR. SHEET ☐. GIRDERS WITH ULTIMATE CAMBER VALUES SMALLER THAN ¾" ARE EXEMPT FROM THIS REQUIREMENT. FLANGE THICKENING SHALL BE USED ONLY IF NEEDED BY DESIGN.


GIRDER SCHEDULE

SPAN	GIRDER	END 1	END 2	S	LS	θ_1	θ_2	P_1	P_2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'c KSI	MIN. CONC. COMPR. STRENGTH @ RELEASE F'ci KSI	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS E	LOCATION OF C.G. STRANDS F℄	LOCATION OF C.G. STRANDS Fb	LOCATION OF C.G. STRANDS Fo	CAMBER (IN) RELEASE △	CAMBER (IN) 2000 △	CAMBER (IN)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-



W41DG Deck Bulb Tee Diaphragm Details

Figure 5-A-175




GIRDER ELEVATION

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE INSERT OR APPROVED EQUAL. (TYP.)


GENERAL NOTES

1. ALL DETAILS SHOWN PERTAIN ONLY TO THE 53 INCH DEEP GIRDER WITH THE 6'-0" GIRDER WIDTH SHOWN.
2. FORMS FOR THE BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER SO AS TO NOT CAUSE DAMAGE TO THE GIRDERS DURING THE STRAND RELEASE OPERATION.
3. SPAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE
4. ALL PRESTRESSING STRANDS SHALL BE ½ INCH OR 0.6 INCH ø LOW RELAXATION SEVEN WIRE STRAND, AASHTO M203 GR. 270. ALL MILD STEEL REINFORCING SHALL BE AASHTO M31 GR. 60. ALL STUDS SHALL CONFORM TO STD. SPEC. SECTION 9-06.15. ALL OTHER STEEL SHALL BE AASHTO M183 AND SHALL BE PAINTED WITH 2 COATS OF STATE FORMULA A-9-73.
5. CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS EXCEPT FOR THOSE SHOWN TO BE EXTENDED, AND PAINT ENDS OF FLUSH STRANDS WITH AN APPROVED EPOXY RESIN.
6. AFTER ERECTION, CUT OFF LIFTING LOOPS 1 INCH BELOW THE TOP OF THE FLANGE AND FILL WITH AN APPROVED GROUT PRIOR TO PLACING OF THE OVERLAY. ALL LIFTING STRANDS ARE TO BE OF THE SAME MATERIAL AND STRENGTH AS THE PRESTRESSING STRANDS. WRAP LIFTING LOOPS SO THAT EACH STRAND WILL CARRY IT'S SHARE OF THE TOTAL LOAD. EXTEND LIFTING LOOPS WITH 9 INCH LONG 90° HOOKS TO WITHIN 3 INCHES CLEAR OF THE BOTTOM OF THE GIRDER.
7. TOP 2 INCHES OF THE GIRDER FLANGE SHALL BE AIR-ENTRAINED CONCRETE.




GIRDER PLAN

OMIT WELD TIES ON EXTERIOR EDGE OF EXTERIOR GIRDER. (STRANDS AND LONGITUDINAL BARS NOT SHOWN)




PLAN SECTION THROUGH GIRDER WEB



EXTERIOR GIRDER REINFORCING NEAR GIRDER END

FOR DETAILS NOT SHOWN, SEE INTERIOR GIRDER




INTERIOR GIRDER REINFORCING NEAR MIDSPAN

*** THICKEN FLANGE TO COMPENSATE FOR SUPERELEVATION.


MARK	LOCATION	SIZE
G1	GIRDER STIRRUPS	4
G2	GIRDER END STIRRUPS	5
G3	BOTTOM FLANGE	3
G4	TOP OF TOP FLANGE - LONGIT.	▽4 STR.
G5	BOT. OF TOP FLANGE - TRANSV.	4
G6	TOP TRANSV. - EXT. GIRDER	▽6
G7	TOP TRANSV. - INT. GIRDER	▽6 STR.
G8	BOT. OF TOP FLANGE - LONGIT.	4 STR.
G10	GIRDER END TIES	W12 △△
G11	GIRDER LONGIT.	6 STR.
S1	T.B. TO DECK TIE	▽5
S2	T.B. TO DECK TIE	4

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)

△△ #3 OR #4 BARS MAY BE USED IN LIEU OF W12. FIELD BEND IS OPTIONAL.




▽ DENOTES EPOXY COATED




W53DG Deck Bulb Tee Girder Details 1 of 2

Figure 5-A-176




STRAND PATTERN AT GIRDER END

HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




TIE SPACING DETAIL




SAWTEETH DETAILS


SAWTEETH ARE FULL WIDTH - USE SAWTEETH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND




SECTION A KEYWAY




SECTION B WELD TIE ALTERNATE #1



SECTION B WELD TIE ALTERNATE #2




SECTION B WELD TIE ALTERNATE #3



GIRDER END


AT END PIERS



GIRDER FLANGE THICKENING**

* ALTERNATIVELY THE TOP 2 INCHES OF THE GIRDER FLANGE MAY BE AIR-ENTRAINED CONCRETE.

** THICKEN FLANGE TO COMPENSATE FOR CAMBER DUE TO PRESTRESS. FLANGE THICKNESS SHOWN IS @ ℄ OF SPAN. FOR FLANGE THINCKNESS ALONG GIRDER SEE GIRDER FLANGE THICKENING DETAILS ON BR. SHEET ____. GIRDERS WITH ULTIMATE CAMBER VALUES SMALLER THAN ¾" ARE EXEMPT FROM THIS REQUIREMENT. FLANGE THICKENING SHALL BE USED ONLY IF NEEDED BY DESIGN.



BEARING RECESS


BEARING RECESS IS NORMAL TO ℄ GIRDER

GIRDER SCHEDULE

SPAN	GIRDER	END 1	END 2	S	LS	θ_1	θ_2	P_1	P_2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C KSI	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI KSI	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS E	LOCATION OF C.G. STRANDS F℄	LOCATION OF C.G. STRANDS Fb	LOCATION OF C.G. STRANDS Fo	CAMBER (IN) RELEASE △	CAMBER (IN) 2000 △	
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-


W53DG Deck Bulb Tee Girder Details 2 of 2

Figure 5-A-177




ELEVATION - TYPICAL END DIAPHRAGM AT INTERMEDIATE PIERS

CONCRETE CLASS 4000, CAST IN PLACE




ELEVATION - TYPICAL INTERMEDIATE DIAPHRAGM

CONCRETE CLASS 4000, CAST IN PLACE




ELEVATION - TYPICAL END DIAPHRAGM AT END PIERS




SECTION A

LONGIT. DIMENSIONS ARE NORMAL TO SKEW




SECTION B




ANCHOR DETAIL

A.S.T.M. A-307



END DIAPHRAGMS AT INTERMEDIATE PIER

LONGITUDINAL DIMENSIONS ARE NORMAL TO PIER




SECTION C

ALL LONGIT. DIMENSIONS SHOWN ARE NORMAL TO ℄ BRG.

W53DG Deck Bulb Tee Diaphragm Details


Figure 5-A-178



GIRDER ELEVATION


GENERAL NOTES

1. ALL DETAILS SHOWN PERTAIN ONLY TO THE 65 INCH DEEP GIRDER WITH THE 6'-0" GIRDER WIDTH SHOWN.
2. FORMS FOR THE BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER SO AS TO NOT CAUSE DAMAGE TO THE GIRDERS DURING THE STRAND RELEASE OPERATION.
3. SPAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE
4. ALL PRESTRESSING STRANDS SHALL BE ½ INCH OR 0.6 INCH ø LOW RELAXATION SEVEN WIRE STRAND, AASHTO M203 GR. 270. ALL MILD STEEL REINFORCING SHALL BE AASHTO M31 GR. 60. ALL STUDS SHALL CONFORM TO STD. SPEC. SECTION 9-06.15. ALL OTHER STEEL SHALL BE AASHTO M183 AND SHALL BE PAINTED WITH 2 COATS OF STATE FORMULA A-9-73.
5. CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS EXCEPT FOR THOSE SHOWN TO BE EXTENDED, AND PAINT ENDS OF FLUSH STRANDS WITH AN APPROVED EPOXY RESIN.
6. AFTER ERECTION, CUT OFF LIFTING LOOPS 1 INCH BELOW THE TOP OF THE FLANGE AND FILL WITH AN APPROVED GROUT PRIOR TO PLACING OF THE OVERLAY. ALL LIFTING STRANDS ARE TO BE OF THE SAME MATERIAL AND STRENGTH AS THE PRESTRESSING STRANDS. WRAP LIFTING LOOPS SO THAT EACH STRAND WILL CARRY IT'S SHARE OF THE TOTAL LOAD. EXTEND LIFTING LOOPS WITH 9 INCH LONG 90° HOOKS TO WITHIN 3 INCHES CLEAR OF THE BOTTOM OF THE GIRDER.
7. TOP 2 INCHES OF GIRDER FLANGE SHALL BE AIR-ENTRAINED CONCRETE.




GIRDER PLAN

OMIT WELD TIES ON EXTERIOR EDGE OF EXTERIOR GIRDER.
(STRANDS AND LONGITUDINAL BARS NOT SHOWN)




EXTERIOR GIRDER REINFORCING NEAR GIRDER END

FOR DETAILS NOT SHOWN, SEE INTERIOR GIRDER



INTERIOR GIRDER REINFORCING NEAR MIDSPAN


*** THICKEN FLANGE TO COMPENSATE FOR SUPERELEVATION



PLAN SECTION THROUGH GIRDER WEB


MARK	LOCATION	SIZE	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
G1	GIRDER STIRRUPS	4	△△ #3 OR #4 BARS MAY BE USED IN LIEU OF W12. FIELD BEND IS OPTIONAL.
G2	GIRDER END STIRRUPS	5	
G3	BOTTOM FLANGE	3	
G4	TOP OF TOP FLANGE - LONGIT.	▽ 4 STR.	
G5	BOT. OF TOP FLANGE - TRANSV.	4	
G6	TOP TRANSV. - EXT. GIRDER	▽ 6	
G7	TOP TRANSV. - INT. GIRDER	▽ 6 STR.	
G8	BOT. OF TOP FLANGE - LONGIT.	4 STR.	
G10	GIRDER END TIES	W12 △△	
G11	GIRDER LONGIT.	6 STR.	
S1	T.B. TO DECK TIE	▽ 5	
S2	T.B. TO DECK TIE	4	

▽ DENOTES EPOXY COATED




W65DG Deck Bulb Tee Girder Details 1 of 2

Figure 5-A-179




STRAND PATTERN AT GIRDER END

HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




TIE SPACING DETAIL




SAWTEETH DETAILS


SAWTEETH ARE FULL WIDTH - USE SAWTEETH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND




SECTION B / 1 WELD TIE ALTERNATE #2



SECTION B / 1 WELD TIE ALTERNATE #3



GIRDER FLANGE THICKENING**




GIRDER END


AT END PIERS

* ALTERNATIVELY THE TOP 2 INCHES OF THE GIRDER FLANGE MAY BE AIR-ENTRAINED CONCRETE.

** THICKEN FLANGE TO COMPENSATE FOR CAMBER DUE TO PRESTRESS. FLANGE THICKNESS SHOWN IS @ ℄ OF SPAN. FOR FLANGE THINCKNESS ALONG GIRDER SEE GIRDER FLANGE THICKENING DETAILS ON BR. SHEET [ ]. GIRDERS WITH ULTIMATE CAMBER VALUES SMALLER THAN ¾" ARE EXEMPT FROM THIS REQUIREMENT. FLANGE THICKENING SHALL BE USED ONLY IF NEEDED BY DESIGN.




SECTION B / 1 WELD TIE ALTERNATE #1



BEARING RECESS

BEARING RECESS IS NORMAL TO ℄ GIRDER




SECTION A / 1 KEYWAY

GIRDER SCHEDULE

SPAN	GIRDER	END 1	END 2	S	LS	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C KSI	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI KSI	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS E	LOCATION OF C.G. STRANDS F℄	LOCATION OF C.G. STRANDS Fb	LOCATION OF C.G. STRANDS Fo	CAMBER (IN) RELEASE △	CAMBER (IN) 2000 △	
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-


W65DG Deck Bulb Tee Girder Details 2 of 2

Figure 5-A-180




W65DG Deck Bulb Tee Girder Diaphragm Details

Figure 5-A-181




GIRDER STOP DETAIL



GROUT PAD GEOMETRY

NOTE:


1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.



BEARING PAD

LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60

(SKEW ANGLE SHOWN @ 30°)




GROUT PAD DETAIL

(SKEW ANGLE SHOWN @ 30°)
(SHOWN FOR END DIAPHRAGM ON GIRDER)


W65DG Deck Bulb Tee Girder Misc. Diaphragm Details

Figure 5-A-182




PRECAST LONGITUDINAL HALF-SECTION

SHOWING POST-TENSIONING CABLE PATHS
* MEASURED BEFORE POST-TENSIONING.




DETAIL A



TENDON IN SAG CURVE


STRAND LOCATION DETAIL



DUCT SPLICE DETAIL

POST-TENSIONING TABLE

SPAN	GIRDER	MIN. CONC. COMPRESIVE STRENGTH, KSI		NUMBER OF STRANDS	PRESTRESSING LOAD KIPS		PRESTRESS LOSS KSI	E_1 (IN.)	E_2 (IN.)	E_3 (IN.)
		GIRDER	WET JOINT		JACKING	AFTER SEATING				




STRAND PATTERN AT ℄ SPAN

STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.

POST-TENSIONING NOTES

1. THE CAST-IN-PLACE CONCRETE IN DECK SLAB SHALL BE CLASS 4000D. THE MINIMUM COMPRESSIVE STRENGTH OF THE CAST-IN-PLACE CONCRETE AT THE WET JOINT AT THE TIME OF POST-TENSIONING SHALL BE ??? ksi.
2. THE MINIUM PRESTRESSING LOAD AFTER SEATING AND THE MINIMUM NUMBER OF PRESTRESSING STRANDS FOR EACH GIRDER SHALL BE AS SHOWN IN POST-TENSIONING TABLE.
3. THE DESIGN IS BASED ON ?? INCH DIAMETER LOW RELAXATION STRANDS WITH A JACKING LOAD FOR EACH GIRDER AS SHOWN IN POST-TENSIONING TABLE, AN ANCHOR SET OF ⅜ INCH OF CURVATURE FRICTION COEFFICIENT, μ = 0.20 AND A WOBBLE FRICTION COEFFICIENT, k = 0.0002/ft. THE ACTUAL ANCHOR SET USED BY THE CONTRACTOR SHALL BE SPECIFIED IN THE SHOP PLANS AND INCLUDED IN THE TRANSFER FORCE CALCULATIONS.
4. THE DESIGN IS BASED ON THE ESTIMATED PRESTRESS LOSS OF POST-TENSIONING STRANDS SHOWN IN POST-TENSIONING TABLE DUE TO STEEL RELAXATION, ELASTIC SHORTENING CREEP AND SHRINKAGE OF CONCRETE.
5. THE CONTRACTOR SHALL SUBMIT THE STRESSING SEQUENCE AND ELONGATION CALCULATIONS TO THE ENGINEER FOR APPROVAL. ALL LOSSES DUE TO TENDON VERTICAL AND HORIZONTAL CURVATURE MUST BE INCLUDED IN ELONGATION CALCULATIONS.
   A. THE PRESTRESSING FORCE SHALL BE DISTRIBUTED WITH AN APPROXIMATELY EQUAL AMOUNT IN EACH WEB.
   B. NO MORE THAN ONE-HALF OF THE PRESTRESSING FORCE IN ANY WEB MAY BE STRESSED BEFORE AN EQUAL FORCE IS STRESSED IN THE ADJACENT WEBS.
6. THE MAXIMUM OUTSIDE DIAMETER OF THE DUCT SHALL BE ??? INCHES. THE AREA OF THE DUCT SHALL BE AT LEAST 2.5 TIMES THE NET AREA OF THE PRESTRESSING STEEL IN THE DUCT.
7. ALL TENDONS SHALL BE STRESSED FROM PIER ??.

WF74PTG Spliced Girder Details 1 of 5
Figure 5-A-183




TYPICAL END ELEVATION AT END DIAPHRAGMS


TYPICAL END ELEVATION AT CLOSURE PLACEMENT

PRE-TENSIONING NOTES:

1. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
2. ALL STRAND FOR PRETENSIONING SHALL BE ??? DIAMETER LOW RELAXATION STRANDS (AASHTO M203, GRADE 270).
3. EXCEPT FOR ??? EXTENDED STRANDS AS SHOWN, CUT ALL REMAINING STRANDS 1" BELOW SURFACE OF THE GIRDER ENDS AND GROUT WITH ANY APPROVED EPOXY GROUT.
4. THE GIRDERS MAY NEED TO BE BRACED LATERALLY DURING SHIPPING TO PREVENT TIPPING OR BUCKLING.
5. LIFTING BARS SHALL BE 1⅜" DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275, GRADE 150 MINIMUM). LIFTING HARDWARE THAT CONNECTS TO THREADED BARS SHALL BE DESIGNED AND DETAILED BY THE CONTRACTOR. LIFTING FORCES ON THREAD BARS SHALL BE VERTICAL ONLY AND WITHIN 10 DEGREES OF PERPENDICULAR TO A LINE BETWEEN PICK POINTS. CONTRACTOR SHALL SUBMIT CALCULATIONS FOR APPROVAL BY THE ENGINEER IF LIFTING FORCES ARE TO BE OTHERWISE.
6. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING ALL GIRDERS. ALL GIRDERS SHALL BE CHECKED TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING.
7. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS NOT TO CAUSE DAMAGE TO THE GIRDER DURING STRAND RELEASE OPERATION.
9. FOR SAWTEETH DETAILS SEE WPT83G GIRDER DETAILS 5 OF 5.




SECTION A



TRANSVERSE REINFORCING AT SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN

END SEGMENT DETAILS



VIEW B

REINFORCING NOT SHOWN FOR CLARITY. SAWTEETH SHOWN BY SHADED AREA.

VIEW B

FOR "B1" & "B2" SEE WPT83G GIRDER DETAILS 3 OF 5


SECTION C

VIEW D


SAWTEETH SHOWN BY SHADED AREA.

WF74PTG Spliced Girder Details 2 of 5

Figure 5-A-184




ALTERNATE STIRRUP DETAIL




STRAND EXTENSION DETAIL

NOTES TO DESIGNER:


This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms. Designer shall calculate the exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.




SECTION A



ELEVATION




PLAN



PLAN

BOTTOM FLANGE SPALL PROTECTION



ELEVATION

TEMPORARY STRAND PATTERN AT TOP FLANGE GIRDER END


Notes to designer	#, # # DESIGNER TO MODIFY FOR SPECIFIC PROJECT					
DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
End diaph. on girder	A	YES	1'-10"	1'-6"	9"	YES
"L" Abutment	B	YES	0	0	0	NO
Hinge diaph.on interm. pier	C	NO	1'-10"	1'-6"	9"	YES
Fixed diaph.@ interm. pier	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
Mult. simple spans @ interm. pier	E	YES	0	0	0	NO
Spliced girder closure pour	F	YES	1'-10"	1'-6"	9"	YES

TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0 (G4)
B2 = 0 (G5 , G9)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4)
B2 = 3" (G5 , G9)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	#
G8	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	4	STR.
G10	GIRDER STIRRUPS	4	
G10	GIRDER STIRRUPS	5	


BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)



#3 OR #4 MAY BE SUBSTITUTED. FIELD BENDING IS OPTIONAL.


WF74PTG Spliced Girder Details 3 of 5

Figure 5-A-185




GIRDER ELEVATION ~ MID-SEGMENT

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1"ø ROCKET/KOHLER, BURKE HI-TENSILE, LANCASTER MALLEABLE OR APPROVED EQUAL.




TYPICAL MID-SEGMENT ELEVATION




SECTION C

WF74PTG Spliced Girder Details 4 of 5

Figure 5-A-186




GIRDER PLAN



STRAND PATTERN
PRECAST END SEGMENTS

STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1),(2),(3), ... ETC.


INDICATES DEBOND STRAND




STRAND PATTERN
PRECAST MID-SEGMENT

STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1),(2),(3) , ... ETC.

INDICATES DEBOND STRAND.




STRAND DEBONDING DETAIL



SAWTEETH DETAIL


SAWTEETHS ARE FULL WIDTH ~ USE SAWTEETH KEYS, IN AREA OUTSIDE OF PT. DUCTS AS SHOWN IN SECTION D/2 D/2

| DIMENSION "A" AT ℄ BEARINGS = SEE "A" DIMENSION TABLE | | |




PRECAST LONGITUDINAL HALF-SECTION

SHOWING POST-TENSIONING CABLE PATHS
* MEASURED BEFORE POST-TENSIONING.
** CONTRACTOR MAY ELECT TO CAST THE GIRDER IN ONE PIECE IF THE SHIPPING WEIGHT IS LESS THAN 200 KIPS & THE SHIPPING ROUTE ALLOWS THE SHIPMENT OF LONG GIRDERS.




DETAIL A



TENDON IN SAG CURVE


STRAND LOCATION DETAIL



DUCT SPLICE DETAIL

POST-TENSIONING TABLE

SPAN	GIRDER	MIN. CONC. COMPRESIVE STRENGTH, KSI		NUMBER OF STRANDS	PRESTRESSING LOAD KIPS		PRESTRESS LOSS KSI	E_1 (IN.)	E_2 (IN.)	E_3 (IN.)
		GIRDER	WET JOINT		JACKING	AFTER SEATING				



STRAND PATTERN AT ℄ SPAN


STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.

POST-TENSIONING NOTES

1. THE CAST-IN-PLACE CONCRETE IN DECK SLAB SHALL BE CLASS 4000D. THE MINIMUM COMPRESSIVE STRENGTH OF THE CAST-IN-PLACE CONCRETE AT THE WET JOINT AT THE TIME OF POST-TENSIONING SHALL BE ??? ksi.
2. THE MINIUM PRESTRESSING LOAD AFTER SEATING AND THE MINIMUM NUMBER OF PRESTRESSING STRANDS FOR EACH GIRDER SHALL BE AS SHOWN IN POST-TENSIONING TABLE.
3. THE DESIGN IS BASED ON ?? INCH DIAMETER LOW RELAXATION STRANDS WITH A JACKING LOAD FOR EACH GIRDER AS SHOWN IN POST-TENSIONING TABLE, AN ANCHOR SET OF ⅜ INCH OF CURVATURE FRICTION COEFFICIENT, μ = 0.20 AND A WOBBLE FRICTION COEFFICIENT, k = 0.0002/ft. THE ACTUAL ANCHOR SET USED BY THE CONTRACTOR SHALL BE SPECIFIED IN THE SHOP PLANS AND INCLUDED IN THE TRANSFER FORCE CALCULATIONS.
4. THE DESIGN IS BASED ON THE ESTIMATED PRESTRESS LOSS OF POST-TENSIONING STRANDS SHOWN IN POST-TENSIONING TABLE DUE TO STEEL RELAXATION, ELASTIC SHORTENING CREEP AND SHRINKAGE OF CONCRETE.
5. THE CONTRACTOR SHALL SUBMIT THE STRESSING SEQUENCE AND ELONGATION CALCULATIONS TO THE ENGINEER FOR APPROVAL. ALL LOSSES DUE TO TENDON VERTICAL AND HORIZONTAL CURVATURE MUST BE INCLUDED IN ELONGATION CALCULATIONS.
   A. THE PRESTRESSING FORCE SHALL BE DISTRIBUTED WITH AN APPROXIMATELY EQUAL AMOUNT IN EACH WEB.
   B. NO MORE THAN ONE-HALF OF THE PRESTRESSING FORCE IN ANY WEB MAY BE STRESSED BEFORE AN EQUAL FORCE IS STRESSED IN THE ADJACENT WEBS.
6. THE MAXIMUM OUTSIDE DIAMETER OF THE DUCT SHALL BE ??? INCHES. THE AREA OF THE DUCT SHALL BE AT LEAST 2.5 TIMES THE NET AREA OF THE PRESTRESSING STEEL IN THE DUCT.
7. ALL TENDONS SHALL BE STRESSED FROM PIER ??.

W83PTG Spliced Girder Details 1 of 5

Figure 5-A-188




TYPICAL END ELEVATION AT END DIAPHRAGMS


TYPICAL END ELEVATION AT CLOSURE PLACEMENT

PRE-TENSIONING NOTES:

1. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
2. ALL STRAND FOR PRETENSIONING SHALL BE ??? DIAMETER LOW RELAXATION STRANDS (AASHTO M203, GRADE 270).
3. EXCEPT FOR ??? EXTENDED STRANDS AS SHOWN, CUT ALL REMAINING STRANDS 1" BELOW SURFACE OF THE GIRDER ENDS AND GROUT WITH ANY APPROVED EPOXY GROUT.
4. THE GIRDERS MAY NEED TO BE BRACED LATERALLY DURING SHIPPING TO PREVENT TIPPING OR BUCKLING.
5. LIFTING BARS SHALL BE 1 ⅜" DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275, GRADE 150 MINIMUM). LIFTING HARDWARE THAT CONNECTS TO THREADED BARS SHALL BE DESIGNED AND DETAILED BY THE CONTRACTOR. LIFTING FORCES ON THREAD BARS SHALL BE VERTICAL ONLY AND WITHIN 10 DEGREES OF PERPENDICULAR TO A LINE BETWEEN PICK POINTS. CONTRACTOR SHALL SUBMIT CALCULATIONS FOR APPROVAL BY THE ENGINEER IF LIFTING FORCES ARE TO BE OTHERWISE.
6. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING ALL GIRDERS. ALL GIRDERS SHALL BE CHECKED TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING.
7. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS NOT TO CAUSE DAMAGE TO THE GIRDER DURING STRAND RELEASE OPERATION.
9. FOR SAWTEETH DETAILS SEE WPT83G GIRDER DETAILS 5 OF 5.




SECTION A



TRANSVERSE REINFORCING AT SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN

END SEGMENT DETAILS




VIEW B

REINFORCING NOT SHOWN FOR CLARITY. SAWTEETH SHOWN BY SHADED AREA.




VIEW B

FOR "B1" & "B2" SEE WPT83G GIRDER DETAILS 3 OF 5



SECTION C




VIEW D


SAWTEETH SHOWN BY SHADED AREA.

W83PTG Spliced Girder Details 2 of 5

Figure 5-A-189




ALTERNATE STIRRUP DETAIL




STRAND EXTENSION DETAIL

NOTES TO DESIGNER:


This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms. Designer shall calculate the exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.




SECTION A



ELEVATION




PLAN



ELEVATION

TEMPORARY STRAND PATTERN AT TOP FLANGE GIRDER END

Notes to designer	#, # # DESIGNER TO MODIFY FOR SPECIFIC PROJECT					
DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
End diaph. on girder	A	YES	1'-10"	1'-6"	9"	YES
"L" Abutment	B	YES	0	0	0	NO
Hinge diaph.on interm. pier	C	NO	1'-10"	1'-6"	9"	YES
Fixed diaph.@ interm. pier	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
Mult. simple spans @ interm. pier	E	YES	0	0	0	NO
Spliced girder closure pour	F	YES	1'-10"	1'-6"	9"	YES



PLAN

BOTTOM FLANGE SPALL PROTECTION


TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0 (G4)
B2 = 0 (G5 , G9)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4)
B2 = 3" (G5 , G9)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	#
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	4	STR.
G10	GIRDER STIRRUPS	4	
G11	GIRDER STIRRUPS	5	


#3 OR #4 MAY BE SUBSTITUTED. FIELD BENDING IS OPTIONAL

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)




W83PTG Spliced Girder Details 3 of 5

Figure 5-A-190




GIRDER ELEVATION ~ MID-SEGMENT

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1"ø ROCKET/KOHLER, BURKE HI-TENSILE, LANCASTER MALLEABLE OR APPROVED EQUAL.




TYPICAL MID-SEGMENT ELEVATION




SECTION C

W83PTG Spliced Girder Details 4 of 5

Figure 5-A-191




GIRDER PLAN



STRAND PATTERN
PRECAST END SEGMENTS

STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1),(2),(3), ... ETC.


INDICATES DEBOND STRAND




STRAND PATTERN
PRECAST MID-SEGMENT

STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1),(2),(3) , ... ETC.

INDICATES DEBOND STRAND



STRAND DEBONDING DETAIL



SAWTEETH DETAIL

SAWTEETH ARE FULL WIDTH ~ USE SAWTEETH KEYS, IN AREA OUTSIDE OF PT. DUCTS AS SHOWN IN SECTION

DIMENSION "A" AT ℄ BEARINGS SEE "A" DIMENSION TABLE

SPAN	GIRDER	MIN. CONC. COMPR. STRENGTH @ 28 DAYS F'C MPa	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI MPa	END SEGMENT 1 END 1 TYPE	END SEGMENT 1 END 2 TYPE	END SEGMENT 1 L	END SEGMENT 1 θ1	END SEGMENT 1 θ2	END SEGMENT 1 P1	END SEGMENT 1 PLAN LENGTH (ALONG ℄ GIRDER GRADE)	END SEGMENT 1 STRAIGHT NO. OF STRANDS	END SEGMENT 1 STRAIGHT JACKING FORCE (LBS)	END SEGMENT 1 C.G. STRANDS (IN.) E	END SEGMENT 1 D (30 DAYS) (IN.)	END SEGMENT 1 C (IN.)	MID-SEGMENT END 1 TYPE	MID-SEGMENT END 2 TYPE	MID-SEGMENT L	MID-SEGMENT θ1	MID-SEGMENT θ2	MID-SEGMENT PLAN LENGTH (ALONG ℄ GIRDER GRADE)	MID-SEGMENT STRAIGHT NO. OF STRANDS	MID-SEGMENT STRAIGHT JACKING FORCE (LBS)	MID-SEGMENT C.G. STRANDS (IN.) E	MID-SEGMENT D (30 DAYS) (IN.)	MID-SEGMENT C (IN.)	END SEGMENT 2 END 1 TYPE	END SEGMENT 2 END 2 TYPE	END SEGMENT 2 L	END SEGMENT 2 θ1	END SEGMENT 2 θ2	END SEGMENT 2 P2	END SEGMENT 2 PLAN LENGTH (ALONG ℄ GIRDER GRADE)	END SEGMENT 2 STRAIGHT NO. OF STRANDS	END SEGMENT 2 STRAIGHT JACKING FORCE (LBS)	END SEGMENT 2 C.G. STRANDS (IN.) E	END SEGMENT 2 D (30 DAYS) (IN.)	END SEGMENT 2 C (IN.)

"A" DIMENSION TABLE

PIER	"A" (40 DAYS) (IN)	"A" (120 DAYS) (IN)

BENDING DIAGRAM

≠ ≠ ≠ DESIGNER TO MODIFY FOR SPECIFIC PROJECT


MARK	LOCATION	SIZE	
G2		5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER LONGIT.	7	STR.
G6	GIRDER END TIES	W12	≠
G7	GIRDER BOTTOM FLANGE TIES	3	
G9	GIRDER LONGIT. FULL LENGTH	4	STR.
G10	GIRDER TOP FLANGE STIRRUPS	4	

ALL DIMENSIONS ARE OUT TO OUT

* = VARIES FOR SKEWED SPANS


NOTE:
FOR DIMENSION "A", SEE "A" DIMENSION TABLE

≠ #3 OR #4 MAY BE SUBSTITUTED FOR FOR W12, FIELD BENDING IS OPTIONAL.



W83PTG Spliced Girder Details 5 of 5

Figure 5-A-192




PRECAST END SEGEMENT


PRECAST MID-SEGEMENT

PRECAST LONGITUDINAL HALF-SECTION

SHOWING POST-TENSIONING CABLE PATHS
* MEASURED BEFORE POST-TENSIONING.
** CONTRACTOR MAY ELECT TO CAST THE GIRDER IN ONE PIECE IF THE SHIPPING WEIGHT IS LESS THAN 200 KIPS & THE SHIPPING ROUTE ALLOWS THE SHIPMENT OF LONG GIRDERS.




DETAIL A



TENDON IN SAG CURVE


STRAND LOCATION DETAIL



DUCT SPLICE DETAIL

POST-TENSIONING TABLE

SPAN	GIRDER	MIN. CONC. COMPRESIVE STRENGTH, KSI		NUMBER OF STRANDS	PRESTRESSING LOAD KIPS		PRESTRESS LOSS KSI	E_1 (IN.)	E_2 (IN.)	E_3 (IN.)
		GIRDER	WET JOINT		JACKING	AFTER SEATING				



STRAND PATTERN AT ℄ SPAN


STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1),(2) ETC.

POST-TENSIONING NOTES

1. THE CAST-IN-PLACE CONCRETE IN DECK SLAB SHALL BE CLASS 4000D. THE MINIMUM COMPRESSIVE STRENGTH OF THE CAST-IN-PLACE CONCRETE AT THE WET JOINT AT THE TIME OF POST-TENSIONING SHALL BE ??? ksi.
2. THE MINIUM PRESTRESSING LOAD AFTER SEATING AND THE MINIMUM NUMBER OF PRESTRESSING STRANDS FOR EACH GIRDER SHALL BE AS SHOWN IN POST-TENSIONING TABLE.
3. THE DESIGN IS BASED ON ?? INCH DIAMETER LOW RELAXATION STRANDS WITH A JACKING LOAD FOR EACH GIRDER AS SHOWN IN POST-TENSIONING TABLE, AN ANCHOR SET OF ⅜ INCH OF CURVATURE FRICTION COEFFICIENT, μ = 0.20 AND A WOBBLE FRICTION COEFFICIENT, k = 0.0002/ft. THE ACTUAL ANCHOR SET USED BY THE CONTRACTOR SHALL BE SPECIFIED IN THE SHOP PLANS AND INCLUDED IN THE TRANSFER FORCE CALCULATIONS.
4. THE DESIGN IS BASED ON THE ESTIMATED PRESTRESS LOSS OF POST-TENSIONING STRANDS SHOWN IN POST-TENSIONING TABLE DUE TO STEEL RELAXATION, ELASTIC SHORTENING CREEP AND SHRINKAGE OF CONCRETE.
5. THE CONTRACTOR SHALL SUBMIT THE STRESSING SEQUENCE AND ELONGATION CALCULATIONS TO THE ENGINEER FOR APPROVAL. ALL LOSSES DUE TO TENDON VERTICAL AND HORIZONTAL CURVATURE MUST BE INCLUDED IN ELONGATION CALCULATIONS.
   A. THE PRESTRESSING FORCE SHALL BE DISTRIBUTED WITH AN APPROXIMATELY EQUAL AMOUNT IN EACH WEB.
   B. NO MORE THAN ONE-HALF OF THE PRESTRESSING FORCE IN ANY WEB MAY BE STRESSED BEFORE AN EQUAL FORCE IS STRESSED IN THE ADJACENT WEBS.
6. THE MAXIMUM OUTSIDE DIAMETER OF THE DUCT SHALL BE ??? INCHES. THE AREA OF THE DUCT SHALL BE AT LEAST 2.5 TIMES THE NET AREA OF THE PRESTRESSING STEEL IN THE DUCT.
7. ALL TENDONS SHALL BE STRESSED FROM PIER ??.

W95PTG Spliced Girder Details 1 of 5

Figure 5-A-193




TYPICAL END ELEVATION AT END DIAPHRAGMS

TYPICAL END ELEVATION AT CLOSURE PLACEMENT

PRE-TENSIONING NOTES:

1. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
2. ALL STRAND FOR PRETENSIONING SHALL BE ??? DIAMETER LOW RELAXATION STRANDS (AASHTO M203, GRADE 270).
3. EXCEPT FOR ??? EXTENDED STRANDS AS SHOWN, CUT ALL REMAINING STRANDS 1" BELOW SURFACE OF THE GIRDER ENDS AND GROUT WITH ANY APPROVED EPOXY GROUT.
4. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
5. LIFTING BARS SHALL BE 1 ⅜" DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275, GRADE 150 MINIMUM). LIFTING HARDWARE THAT CONNECTS TO THREADED BARS SHALL BE DESIGNED AND DETAILED BY THE CONTRACTOR. LIFTING FORCES ON THREAD BARS SHALL BE VERTICAL ONLY AND WITHIN 10 DEGREES OF PERPENDICULAR TO A LINE BETWEEN PICK POINTS. CONTRACTOR SHALL SUBMIT CALCULATIONS FOR APPROVAL BY THE ENGINEER IF LIFTING FORCES ARE TO BE OTHERWISE.
6. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING ALL GIRDERS. ALL GIRDERS SHALL BE CHECKED TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING.
7. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS NOT TO CAUSE DAMAGE TO THE GIRDER DURING STRAND RELEASE OPERATION.
9. FOR SAWTEETH DETAILS SEE WPT83G GIRDER DETAILS 5 OF 5.




SECTION A

TRANSVERSE REINFORCING AT SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN

END SEGMENT DETAILS




VIEW B

REINFORCING NOT SHOWN FOR CLARITY. SAWTEETH SHOWN BY SHADED AREA.




VIEW B

FOR "B1" & "B2" SEE WPT83G GIRDER DETAILS 3 OF 5



SECTION C




VIEW D


SAWTEETH SHOWN BY SHADED AREA.

W95PTG Spliced Girder Details 2 of 5

Figure 5-A-194




ALTERNATE STIRRUP DETAIL




STRAND EXTENSION DETAIL

NOTES TO DESIGNER:


This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms. Designer shall calculate the exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.




SECTION A



ELEVATION




PLAN



ELEVATION

TEMPORARY STRAND PATTERN AT TOP FLANGE GIRDER END



PLAN

BOTTOM FLANGE SPALL PROTECTION


Notes to designer	#, ## DESIGNER TO MODIFY FOR SPECIFIC PROJECT					
DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
End diaph. on girder	A	YES	1'-10"	1'-6"	9"	YES
"L" Abutment	B	YES	0	0	0	NO
Hinge diaph.on interm. pier	C	NO	1'-10"	1'-6"	9"	YES
Fixed diaph.@ interm. pier	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
Mult. simple spans @ interm. pier	E	YES	0	0	0	NO
Spliced girder closure pour	F	YES	1'-10"	1'-6"	9"	YES

TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0 (G4)
B2 = 0 (G5 , G9)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4)
B2 = 3" (G5 , G9)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	#
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	4	STR.
G10	GIRDER STIRRUPS	4	


BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)



is #3 OR #4 MAY BE SUBSTITUTED. FIELD BENDING IS OPTIONAL.


W95PTG Spliced Girder Details 3 of 5

Figure 5-A-195




GIRDER ELEVATION ~ MID-SEGMENT

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1"ø ROCKET/KOHLER, BURKE HI-TENSILE, LANCASTER MALLEABLE OR APPROVED EQUAL.




TYPICAL MID-SEGMENT ELEVATION




SECTION C

W95PTG Spliced Girder Details 4 of 5

Figure 5-A-196




GIRDER PLAN



STRAND PATTERN
PRESCAST END SEGMENTS

STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1),(2),(3) , ... ETC.


INDICATES DEBOND STRAND FOR A TOTAL OF 6'-0" FROM END OF GIRDER.




STRAND PATTERN
PRECAST MID-SEGMENT

STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1),(2), (3) , ... ETC.

INDICATES DEBOND STRAND IF NEEDED FOR A TOTAL OF 6'-0" FROM END OF GIRDER.



STRAND DEBONDING DETAIL



SAWTEETH DETAIL

SAWTEETH ARE FULL WIDTH ~ USE SAWTEETH KEYS, IN AREA OUTSIDE OF PT. DUCTS AS SHOWN IN SECTION

DIMENSION "A" AT ℄ BEARINGS = SEE "A" DIMENSION TABLE

SPAN	GIRDER	MIN. CONC. COMPR. STRENGTH @ 28 DAYS F'C MPa	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI MPa	END SEGMENT 1											MID-SEGMENT												END SEGMENT 2													
				END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	PLAN LENGTH (ALONG ℄ GIRDER GRADE)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (LBS)	C.G. STRANDS (IN.) E	D (30 DAYS) (IN)	C (IN)	END 1 TYPE	END 2 TYPE	L	θ1	θ2	PLAN LENGTH (ALONG ℄ GIRDER GRADE)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (LBS)	C.G. STRANDS (IN.) E	D (IN)	C (IN)	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P2	PLAN LENGTH (ALONG ℄ GIRDER GRADE)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (LBS)	C.G. STRANDS (IN.) E	Ld (IN.)	D (IN)	C (IN)

"A" DIMENSION TABLE

PIER	"A" (40 DAYS) (IN)	"A" (120 DAYS) (IN)

BENDING DIAGRAM

≠ ≠ ≠ DESIGNER TO MODIFY FOR SPECIFIC PROJECT


MARK	LOCATION	SIZE	
G2	GIRDER STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER LONGIT.	7	STR.
G6	GIRDER END TIES	W12	≠
G7	GIRDER BOTTOM FLANGE TIES	3	
G9	GIRDER LONGIT. FULL LENGTH	4	STR.
G10	GIRDER TOP FLANGE STIRRUPS	4	

ALL DIMENSIONS ARE OUT TO OUT

* = VARIES FOR SKEWED SPANS


NOTE:
FOR DIMENSION "A", SEE TABLE

≠ #3 OR #4 MAY BE SUBSTITUTED FOR FOR W12, FIELD BENDING IS OPTIONAL.




W95PTG Spliced Girder Details 5 of 5

Figure 5-A-197




PRECAST LONGITUDINAL HALF-SECTION


SHOWING POST-TENSIONING CABLE PATHS
* MEASURED BEFORE POST-TENSIONING.
** CONTRACTOR MAY ELECT TO CAST THE PT GIRDER IN ONE PIECE IF THE SHIPPING WEIGHT IS LESS THAN 182 KIPS & THE SHIPPING ROUTE ALLOWS THE SHIPMENT OF LONG GIRDERS.




BOTTOM SLAB DRAIN HOLE




DUCT SPLICE DETAIL



STRAND LOCATION DETAIL




STRAND PATTERN @ ℄ SPAN



OPEN HOLE DETAIL

BOTTOM HOLE AT END TYPE "B" ONLY



DETAIL A

POST-TENSIONING TABLE


SPAN	GIRDER	STRAND DIAMETER IN.	PRESSING LOAD PER WEB TOTAL KIPS		PRESTRESS LOSS KSI (TD+ES+FR+AS)	E_1 (IN.)	E_2 (IN.)	E_3 (IN.)
			JACKING	AFTER SEATING				

POST-TENSIONING NOTES

1. THE CAST-IN-PLACE CONCRETE IN DECK SLAB SHALL BE CLASS 4000D. THE MINIMUM COMPRESSIVE STRENGTH OF THE CAST-IN-PLACE CONCRETE AT THE WET JOINT AT THE TIME OF POST-TENSIONING SHALL BE ??? ksi.
2. THE MINIUM PRESTRESSING LOAD AFTER SEATING AND THE MINIMUM NUMBER OF PRESTRESSING STRANDS FOR EACH GIRDER SHALL BE AS SHOWN IN POST-TENSIONING TABLE.
3. THE DESIGN IS BASED ON ?? INCH DIAMETER LOW RELAXATION STRANDS WITH A JACKING LOAD FOR EACH GIRDER AS SHOWN IN POST-TENSIONING TABLE, AN ANCHOR SET OF ⅜ INCH OF CURVATURE FRICTION COEFFICIENT, μ = 0.20 AND A WOBBLE FRICTION COEFFICIENT, k = 0.0002/ft. THE ACTUAL ANCHOR SET USED BY THE CONTRACTOR SHALL BE SPECIFIED IN THE SHOP PLANS AND INCLUDED IN THE TRANSFER FORCE CALCULATIONS.
4. THE DESIGN IS BASED ON THE ESTIMATED PRESTRESS LOSS OF POST-TENSIONING STRANDS SHOWN IN POST-TENSIONING TABLE DUE TO STEEL RELAXATION, ELASTIC SHORTENING CREEP AND SHRINKAGE OF CONCRETE.
5. THE CONTRACTOR SHALL SUBMIT THE STRESSING SEQUENCE AND ELONGATION CALCULATIONS TO THE ENGINEER FOR APPROVAL. ALL LOSSES DUE TO TENDON VERTICAL AND HORIZONTAL CURVATURE MUST BE INCLUDED IN ELONGATION CALCULATIONS.
   A. THE PRESTRESSING FORCE SHALL BE DISTRIBUTED WITH AN APPROXIMATELY EQUAL AMOUNT IN EACH WEB AND SHALL BE PLACED SYMMETRICALLY ABOUT THE CENTERLINE OF THE TUB.
   B. NO MORE THAN ONE-HALF OF THE PRESTRESSING FORCE IN ANY WEB MAY BE STRESSED BEFORE AN EQUAL FORCE IS STRESSED IN THE ADJACENT WEBS. AT NO TIME DURING STRESSING OPERATION WILL MORE THAN ONE-SIXTH OF THE TOTAL PRESTRESSING FORCE IS APPLIED ECCENTRICALLY ABOUT THE CENTERLINE OF BRIDGE.
6. THE MAXIMUM OUTSIDE DIAMETER OF THE DUCT SHALL BE ??? INCHES. THE AREA OF THE DUCT SHALL BE AT LEAST 2.5 TIMES THE NET AREA OF THE PRESTRESSING STEEL IN THE DUCT.
7. ALL TENDONS SHALL BE STRESSED FROM PIER ??.

Trapezoidal Tub Spliced Girder Details 1 of 5

Figure 5-A-198




TYPICAL END ELEVATION AT END DIAPHRAGMS


TYPICAL END ELEVATION AT CLOSURE PLACEMENT

PRE-TENSIONING NOTES:

1. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
2. ALL STRAND FOR PRETENSIONING SHALL BE ??? DIAMETER LOW RELAXATION STRANDS (AASHTO M203, GRADE 270).
3. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
4. EXTENDED STRANDS AND BARS ARE PARALLEL TO GIRDER.
5. LIFTING BARS SHALL BE 1 ⅜" DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275, GRADE 150 MINIMUM). LIFTING HARDWARE THAT CONNECTS TO THREADED BARS SHALL BE DESIGNED AND DETAILED BY THE CONTRACTOR. LIFTING FORCES ON THREAD BARS SHALL BE VERTICAL ONLY AND WITHIN 10 DEGREES OF PERPENDICULAR TO A LINE BETWEEN PICK POINTS. CONTRACTOR SHALL SUBMIT CALCULATIONS FOR APPROVAL BY THE ENGINEER IF LIFTING FORCES ARE TO BE OTHERWISE.
6. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING ALL GIRDERS. ALL GIRDERS SHALL BE CHECKED TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING.
7. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SHOP A MANNER AS NOT TO CAUSE DAMAGE TO THE GIRDER DURING STRAND RELEASE OPERATION.



SECTION A (ONE WEB SHOWN)





VIEW B — SECTION C — VIEW D

*** 1'-0" FOR BOTTOM FLANGE WIDTH LESS THAN 5'-6"
2'-0" FOR BOTTOM FLANGE WIDTH EQUAL OR GREATER THAN 5'-6"

Trapezoidal Tub Spliced Girder Details 2 of 5


Figure 5-A-199






TYPICAL END ELEVATION

EXTENDED STRANDS NOT SHOWN.
USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRANDS.



P.C. SECTION



PLAN

BOTTOM FLANGE SPALL PROTECTION


END TYPE "C" INTERMEDIATE HINGE DIAPHRAGM
AND END TYPE "D" INTEREMEDIATE FIXED DIAPHRAGM

BENDING DIAGRAM


MARK	LOCATION	SIZE	U	W	X	ALL DIMENSIONS ARE OUT TO OUT
G1	STIRRUPS, OUTSIDE WEB	5				
G2	STIRRUPS, INSIDE WEB	5				
G3	LONGITUDINAL BOTTOM FLANGE	4				STR.
G4	TOP WEB LONGIT.	6				STR.
G5	LONGITUDINAL WEB	5				STR.
G6	WEB TIE	W12				≠ #4 MAY BE SUBSTITUTED FOR W12, FIELD BENDING IS OPTIONAL
G7	WEB	4				

* = VARIES FOR SKEWED SPANS

NOTE:
FOR DIMENSION "A", SEE "GIRDER SCHEDULE"




SECTION A




TRANSVERSE REINFORCING AT SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN




SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTEETH FULL HEIGHT ON END SECTIONS.




Trapezoidal Tub Spliced Girder Details 3 of 5

Figure 5-A-200



GIRDER ELEVATION ~ MID-SEGMENT

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR WEB. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" ø ROCKET/KOHLER, BURKE HI-TENSILE, LANCASTER MALLEABLE OR APPROVED EQUAL.



TYPICAL MID-SEGMENT ELEVATION

Trapezoidal Tub Spliced Girder Details 4 of 5

Figure 5-A-201


DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB POUR (120 DAYS)

SPAN	GIRDER	END SEGMENT 1												MID-SEGMENT										END SEGMENT 2										
		MIN. CONC. COMPR. STRENGTH		END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	PLAN LENGTH (ALONG GIRDER GRADE)	STRAIGHT		C.G. STRANDS (IN.)	Ld (IN.)	END 1 TYPE	END 2 TYPE	L	θ1	θ2	PLAN LENGTH (ALONG GIRDER GRADE)	STRAIGHT		C.G. STRANDS (IN.)	Ld (IN.)	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P2	PLAN LENGTH (ALONG GIRDER GRADE)	STRAIGHT		C.G. STRANDS (IN.)	Ld (IN.)
		@ 28 DAYS F'C MPa	@ RELEASE F'CI MPa								NO. OF STRANDS	JACKING FORCE (LBS)	E								NO. OF STRANDS	JACKING FORCE (LBS)	E									NO. OF STRANDS	JACKING FORCE (LBS)	E	

NOTES TO DESIGNER:

1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only.This detail is not applicable to continuous spans using hinge diaphragms.
2. Designer shall calculate the exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.
   The total number of extended strands shall not be less than:
3. $Nps = 12(Mc + Vc \times h - M_{SIDL}) \times Nc \frac{X}{Ng} \frac{K}{(0.9 \times Aps \times fps \times d)}$


where:
Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear capacity of column Ft-kips, kips respectively,
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = number of girders
Aps = area of each extended strand, in
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2




STRAND DEBONDING DETAIL

STRAND PATTERN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



ALTERNATE # 1




ALTERNATE # 2


STRAND EXTENSION DETAIL FOR END TYPE D

NOT ALL EXTENDED STRANDS ARE SHOWN

Trapezoidal Tub Spliced Girder Details 5 of 5

Figure 5-A-202






SECTION F


NOTE TO DESIGNER

If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.


TYPICAL END TYPE "A" DIAPHRAGM AT END PIERS




ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS





END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.

NOTE:

1. GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.
2. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
3. END DIAPHRAGM MAY BE CAST ON GRADE. IF SO, THE UPPER LEG OF THE JOINT FILLER SHALL FORM THE BOTTOM FACE FULL WIDTH.
4. JOINT FILLER TYPE 1 SHALL BE USED TO COVER ALL VERTICAL END DIAPHRAGM JOINTS. EITHER JOINT FILLER TYPE 1 OR JOINT FILLER TYPE 2 SHALL BE USED TO COVER ALL HORIZONTAL END DIAPHRAGM JOINTS.


Trapezoidal Tub Spliced Girder End Diaphragm on Girder Details

Figure 5-A-203




PLAN


FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET 3.




SECTION A



TEMPORARY SUPPORT DETAIL




DETAIL C



ELEVATION

CONSTRUCTION SEQUENCE


1. COLUMN & TEMP. SUPPORT
2. PLACE GIRDER ON TEMPORARY SUPPORT
3. CAST DIAPHRAGM STAGE 1
4. CAST ROADWAY SLAB
5. COMPLETE DIAPHRAGM
6. REMOVE TEMPORARY SUPPORT



SECTION B

Trapezoidal Tub Spliced Girder Raised Crossbeam Details

Figure 5-A-204




DETAIL G

NOTE TO DESIGNER:

This detail to be used on bridges with end piers and no wing walls, and located within and west of the Cascade Mountain range.


NOTE:

1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.



BEARING PAD


LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60



TOP ANCHOR BOTTOM ANCHOR

ANCHOR DETAIL


A.S.T.M. A-307



GROUT PAD DETAIL

Trapezoidal Tub Spliced Girder Miscellaneous Details


Figure 5-A-205




PRECAST LONGITUDINAL HALF-SECTION

SHOWING POST-TENSIONING CABLE PATHS
* MEASURED BEFORE POST-TENSIONING.


** CONTRACTOR MAY ELECT TO CAST THE PT GIRDER IN ONE PIECE IF THE SHIPPING WEIGHT IS LESS THAN 182 KIPS & THE SHIPPING ROUTE ALLOWS THE SHIPMENT OF LONG GIRDERS.




BOTTOM SLAB DRAIN HOLE




DUCT SPLICE DETAIL



STRAND LOCATION DETAIL




STRAND PATTERN @ ℄ SPAN



OPEN HOLE DETAIL

BOTTOM HOLE AT END TYPE "B" ONLY



DETAIL A

POST-TENSIONING TABLE

SPAN	GIRDER	STRAND DIAMETER IN.	PRESSING LOAD PER WEB KIPS		TOTAL PRESTRESS LOSS KSI (DT+ES+FR+AS)	E_1 (IN.)	E_2 (IN.)	E_3 (IN.)
			JACKING	AFTER SEATING				


PRESSING LOAD PER WEB KIPS

POST-TENSIONING NOTES

1. THE CAST-IN-PLACE CONCRETE IN DECK SLAB SHALL BE CLASS 4000D. THE MINIMUM COMPRESSIVE STRENGTH OF THE CAST-IN-PLACE CONCRETE AT THE WET JOINT AT THE TIME OF POST-TENSIONING SHALL BE ??? ksi.
2. THE MINIUM PRESTRESSING LOAD AFTER SEATING AND THE MINIMUM NUMBER OF PRESTRESSING STRANDS FOR EACH GIRDER SHALL BE AS SHOWN IN POST-TENSIONING TABLE.
3. THE DESIGN IS BASED ON ?? INCH DIAMETER LOW RELAXATION STRANDS WITH A JACKING LOAD FOR EACH GIRDER AS SHOWN IN POST-TENSIONING TABLE, AN ANCHOR SET OF ⅜ INCH OF CURVATURE FRICTION COEFFICIENT, μ = 0.20 AND A WOBBLE FRICTION COEFFICIENT, k = 0.0002/ft. THE ACTUAL ANCHOR SET USED BY THE CONTRACTOR SHALL BE SPECIFIED IN THE SHOP PLANS AND INCLUDED IN THE TRANSFER FORCE CALCULATIONS.
4. THE DESIGN IS BASED ON THE ESTIMATED PRESTRESS LOSS OF POST-TENSIONING STRANDS SHOWN IN POST-TENSIONING TABLE DUE TO STEEL RELAXATION, ELASTIC SHORTENING CREEP AND SHRINKAGE OF CONCRETE.
5. THE CONTRACTOR SHALL SUBMIT THE STRESSING SEQUENCE AND ELONGATION CALCULATIONS TO THE ENGINEER FOR APPROVAL. ALL LOSSES DUE TO TENDON VERTICAL AND HORIZONTAL CURVATURE MUST BE INCLUDED IN ELONGATION CALCULATIONS.
   A. THE PRESTRESSING FORCE SHALL BE DISTRIBUTED WITH AN APPROXIMATELY EQUAL AMOUNT IN EACH WEB AND SHALL BE PLACED SYMMETRICALLY ABOUT THE CENTERLINE OF THE TUB.
   B. NO MORE THAN ONE-HALF OF THE PRESTRESSING FORCE IN ANY WEB MAY BE STRESSED BEFORE AN EQUAL FORCE IS STRESSED IN THE ADJACENT WEBS. AT NO TIME DURING STRESSING OPERATION WILL MORE THAN ONE-SIXTH OF THE TOTAL PRESTRESSING FORCE IS APPLIED ECCENTRICALLY ABOUT THE CENTERLINE OF BRIDGE.
6. THE MAXIMUM OUTSIDE DIAMETER OF THE DUCT SHALL BE ??? INCHES. THE AREA OF THE DUCT SHALL BE AT LEAST 2.5 TIMES THE NET AREA OF THE PRESTRESSING STEEL IN THE DUCT.
7. ALL TENDONS SHALL BE STRESSED FROM PIER ??.

Trapezoidal Tub S-I-P Deck Panel Spliced Girder - Details 1 of 5

Figure 5-A-206




TYPICAL END ELEVATION AT END DIAPHRAGMS


TYPICAL END ELEVATION AT CLOSURE PLACEMENT

PRE-TENSIONING NOTES:

1. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
2. ALL STRAND FOR PRETENSIONING SHALL BE ??? DIAMETER LOW RELAXATION STRANDS (AASHTO M203, GRADE 270).
3. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
4. EXTENDED STRANDS AND BARS ARE PARALLEL TO GIRDER.
5. LIFTING BARS SHALL BE 1 ⅜" DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275, GRADE 150 MINIMUM). LIFTING HARDWARE THAT CONNECTS TO THREADED BARS SHALL BE DESIGNED AND DETAILED BY THE CONTRACTOR. LIFTING FORCES ON THREAD BARS SHALL BE VERTICAL ONLY AND WITHIN 10 DEGREES OF PERPENDICULAR TO A LINE BETWEEN PICK POINTS. CONTRACTOR SHALL SUBMIT CALCULATIONS FOR APPROVAL BY THE ENGINEER IF LIFTING FORCES ARE TO BE OTHERWISE.
6. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING ALL GIRDERS. ALL GIRDERS SHALL BE CHECKED TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING.
7. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SHAPE A MANNER AS NOT TO CAUSE DAMAGE TO THE GIRDER DURING STRAND RELEASE OPERATION.



SECTION A
(ONE WEB SHOWN)



VIEW B


SECTION C


VIEW D

*** 1'-0" FOR BOTTOM FLANGE WIDTH LESS THAN 5'-6"
2'-0" FOR BOTTOM FLANGE WIDTH EQUAL OR GREATER THAN 5'-6"

Trapezoidal Tub S-I-P Deck Panel Spliced Girder - Details 2 of 5

Figure 5-A-207







PLAN

BOTTOM FLANGE SPALL PROTECTION

END TYPE "C" INTERMEDIATE HINGE DIAPHRAGM
AND END TYPE "D" INTEREMEDIATE FIXED DIAPHRAGM




SECTION A



TRANSVERSE REINFORCING AT SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN



SAWTOOTH DETAILS


SAWTEETH ARE FULL WIDTH - USE SAWTEETH FULL HEIGHT ON END SECTIONS.

***THE NUMBER OF LIFTING BARS SHALL BE BASED ON 54 KIPS PER EACH 1⅜" ø BAR.



TYPICAL END ELEVATION

EXTENDED STRANDS NOT SHOWN.
USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRANDS.




P.C. SECTION

* SMOOTH FINISH ON TOP OF GIRDER


BENDING DIAGRAM

MARK	LOCATION	SIZE	U	W	X	ALL DIMENSIONS ARE OUT TO OUT
G1	STIRRUPS, OUTSIDE WEB	5				* = VARIES FOR SKEWED SPANS
G2	STIRRUPS, INSIDE WEB	5				
G3	LONGITUDINAL BOTTOM FLANGE	4			STR.	
G4	TOP WEB LONGITUDINAL	6			STR.	NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"
G5	LONGITUDINAL WEB	5			STR.	
G6	WEB TIE	W12				≠ #4 MAY BE SUBSTITUTED FOR W12, FIELD BENDING IS OPTIONAL
G7	WEB	4				
G8	TOP TRANS. TIE	4				




Trapezoidal Tub S-I-P Deck Panel Spliced Girder - Details 3 of 5

Figure 5-A-208



GIRDER ELEVATION ~ MID-SEGMENT

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR WEB. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" ø ROCKET/KOHLER, BURKE HI-TENSILE, LANCASTER MALLEABLE OR APPROVED EQUAL.





TYPICAL MID-SEGMENT ELEVATION

Trapezoidal Tub S-I-P Deck Panel Spliced Girder - Details 4 of 5

Figure 5-A-209

| DIMENSION "A" AT ℄ BEARINGS = | | | | BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB POUR (120 DAYS) | | | |






SECTION F


NOTE TO DESIGNER

If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.


TYPICAL END TYPE "A" DIAPHRAGM AT END PIERS




ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS





END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.

NOTE:


1. GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.
2. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
3. END DIAPHRAGM MAY BE CAST ON GRADE. IF SO, THE UPPER LEG OF THE JOINT FILLER SHALL FORM THE BOTTOM FACE FULL WIDTH.
4. JOINT FILLER TYPE 1 SHALL BE USED TO COVER ALL VERTICAL END DIAPHRAGM JOINTS. EITHER JOINT FILLER TYPE 1 OR JOINT FILLER TYPE 2 SHALL BE USED TO COVER ALL HORIZONTAL END DIAPHRAGM JOINTS.


Trapezoidal Tub S-I-P Deck Panel Girder End Diaphragm on Girder Details

Figure 5-A-211





FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET 3.





TEMPORARY SUPPORT DETAIL






ELEVATION


CONSTRUCTION SEQUENCE

1. COLUMN & TEMP. SUPPORT
2. PLACE GIRDER ON TEMPORARY SUPPORT
3. CAST DIAPHRAGM STAGE 1
4. CAST ROADWAY SLAB
5. COMPLETE DIAPHRAGM
6. REMOVE TEMPORARY SUPPORT



Trapezoidal Tub S-I-P Deck Panel Girder - Raised Crossbeam Details


Figure 5-A-212




DETAIL G

NOTE TO DESIGNER:
This detail to be used on bridges with end piers and no wing walls, and located within and west of the Cascade Mountain range.


NOTE:
1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.




GROUT PAD DETAIL



EXPANSION JOINT DETAILS
JOINT AT INTERMEDIATE PIER SHOWN




DETAIL E




DETAIL F

DRILL ½"ø HOLES THROUGH SEAL WITH STANDARD TWIST DRILL MAKING SURE THE TOP MEMBRANE IS NOT DAMAGED. CUT HOLE WITH SHARP LONG BLADE KNIFE.



BEARING PAD
LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60



TOP ANCHOR BOTTOM ANCHOR

ANCHOR DETAIL
A.S.T.M. A-307

Trapezoidal Tub S-I-P Deck Panel Girder - Miscellaneous Diaphragm Details

Figure 5-A-213

Vacant

Figure 5-A-214

Vacant

Figure 5-A-215

Chapter 5 Concrete Structures

5.0 General 5-1
5.1 Material Properties 5-1
5.1.1 Concrete Properties 5-1
5.1.2 Reinforcing Steel 5-5
5.1.3 Prestressing Steel 5-12
5.1.4 Prestress Losses 5-17
5.1.5 Prestressing Anchorage Systems 5-20
5.1.6 Ducts 5-21
5.2 Design Consideration 5-22
5.2.1 Design Limit States 5-22
5.2.2 Design Criteria 5-22
5.2.3 Service Limit State 5-23
5.2.4 Strength Limit State 5-24
5.2.5 Strut-and-tie Model 5-32
5.2.6 Deflection and Camber 5-33
5.2.7 Serviceability 5-35
5.2.8 Connections (Joints) 5-36
5.2.9 Revised Provisions for Flexural Design 5-37
5.3 Reinforced Concrete Box Girder Bridges 5-41
5.3.1 Box Girder Basic Geometries 5-41
5.3.2 Reinforcement 5-45
5.3.3 Crossbeam 5-55
5.3.4 End Diaphragm 5-58
5.3.5 Dead Load Deflection and Camber 5-61
5.3.6 Thermal Effects 5-62
5.3.7 Hinges 5-62
5.3.8 Utility Openings 5-62
5.4 Hinges and Inverted T-Beam Pier Caps 5-66
5.5 Bridge Widenings 5-69
5.5.1 Review of Existing Structures 5-69
5.5.2 Analysis and Design Criteria 5-70
5.5.3 Removing Portions of the Existing Structure 5-75
5.5.4 Attachment of Widening to Existing Structure 5-75
5.5.5 Expansion Joints 5-87
5.5.6 Possible Future Widening for Current Designs 5-89
5.5.7 Bridge Widening Falsework 5-89
5.5.8 Existing Bridge Widenings 5-89
5.6 Precast Prestressed Girder Superstructures 5-90
5.6.1 WSDOT Standard Prestressed Girders 5-90
5.6.2 Criteria for Girder Design 5-93
5.6.3 Fabrication and Handling 5-101
5.6.4 Superstructure Optimization 5-106
5.6.5 Repair of Damaged Girders at Fabrication 5-110
5.6.6 Repair of Damaged Bridge Girders 5-110
5.6.7 Short Span Precast Prestressed Bridges 5-112
5.6.8 Precast Tub Girders 5-113

5.6.9 Prestressed Girder Checking Requirement 5-113
5.6.10 Review of shop plans for pretensioned girders 5-113
5.7 Roadway Slab 5-115
5.7.1 Roadway Slab Requirements 5-115
5.7.2 Slab Reinforcement 5-117
5.7.3 Stay-In-Place Deck Panels 5-123
5.7.4 Concrete Bridge Deck Protection Systems 5-124
5.8 Cast-in-Place Bridges 5-129
5.8.1 Design Parameters 5-129
5.8.2 Analysis 5-137
5.8.3 Post-tensioning 5-139
5.8.4 Shear 5-144
5.8.5 Temperature Effects 5-145
5.8.6 Construction 5-146
5.8.7 Post-Tensioning Notes — Cast-in-Place Girders 5-148
5.9 Spliced Precast Girders 5-149
5.9.1 Definitions 5-149
5.9.2 WSDOT Criteria for use of Spliced Girders 5-150
5.9.3 Girder Segment Design 5-150
5.9.4 Joints Between Segments 5-151
5.9.5 Review of shop plans for precast post-tensioned spliced-girders 5-152
5.9.6 Post-Tensioning Notes ~ Precast Post-Tensioning Spliced-Girders 5-153
5.99 Bibliography 5-154

Appendix 5-A

Figure 5-A-1 Standard Hooks 5-A-1
Figure 5-A-2 Minimum Reinforcement Clearance and Spacing for Beams and Columns 5-A-2
Table 5-A-3 Reinforcing Bar Properties 5-A-3
Table 5-A-4 Tension Development Length of Deformed Bars 5-A-4
Table 5-A-5 Compression Development Length and Minimum Lap Splice of Grade 60 Bars 5-A-5
Table 5-A-6 Tension Development Length of 90º and 180º Standard Hooks 5-A-6
Table 5-A-7 Tension Lap Splice Lengths of Grade 60 Uncoated Bars ~ Class B 5-A-7
Table 5-A-8 Prestressing Strand Properties and Development Length 5-A-8
Table 5-A-9 Flexural Reinforcement for Class 4000 Concrete 5-A-9
Table 5-A-10 Flexural Reinforcement for Class 5000 Concrete 5-A-10
Table 5-A-11 Flexural Reinforcement for Class 6000 Concrete 5-A-11
Figure 5-A-12 Positive Moment Reinforcement 5-A-12
Figure 5-A-13 Negative Moment Reinforcement 5-A-13
Figure 5-A-14 Adjusted Negative Moment Case I (Design for M @ Face of Support) 5-A-14
Figure 5-A-15 Adjusted Negative Moment Case II (Design for M @ 1/4 Point) 5-A-15
Figure 5-A-16 Cast-In-Place Deck Slab Design for Positive Moment Regions f'c=4, 0 ksi 5-A-16
Figure 5-A-17 Cast-In-Place Deck Slab Design for Negative Moment Regions f'c=4, 0 ksi 5-A-17
Figure 5-A-18 Slab Overhang Design- Interior Barrier Segment 5-A-18
Figure 5-A-19 Slab Overhang Design- End Barrier Segment 5-A-19
Table 5-A-20 Span Capability of Prestressed I-Girders 5-A-20
Table 5-A-21 Span Capability of Prestressed Wide Flange I-Girders 5-A-21
Table 5-A-22 Span Capability of Thin Flange Bulb-Tee Girders 5-A-22
Table 5-A-23 Span Capability of Trapezoidal Tub Girders without Top Flange 5-A-23

Table 5-A-24 Span Capability of Trapezoidal Tub Girders with Top Flange 5-A-24
Table 5-A-25 Span Capability of Prestressed1'-6" Voided Slabs 5-A-25
Table 5-A-26 Span Capability of Prestressed2'-2" Voided Slabs 5-A-26
Table 5-A-27 Span Capability of Prestressed1'-0" Solid Slabs 5-A-27
Table 5-A-28 Span Capability Precast Prestressed Double Tee Girders 5-A-28
Table 5-A-29 Span Capability Precast Prestressed Ribbed Girders 5-A-29
Table 5-A-30 Span Capability of Deck Bulb Tee Girders 5-A-30
Table 5-A-31 Design Charts for W35DG Deck Bulb Tee Girder 5-A-31
Table 5-A-32 Design Charts for W41DG Deck Bulb Tee Girder 5-A-32
Table 5-A-33 Design Charts for W53DG Deck Bulb Tee Girder 5-A-33
Table 5-A-34 Design Charts for W65DG Deck Bulb Tee Girder 5-A-34
Table 5-A-35 Span Capability of Post-Tensioned Spliced I-Girders 5-A-35
Table 5-A-36 Span Capability of Post-Tensioned Spliced Tub Girders 5-A-37
Figure 5-A-37 I-Girder Sections 5-A-39
Figure 5-A-38 Wide Flange I-Girder Sections 5-A-40
Figure 5-A-39 Bulb Tee Girder Sections 5-A-41
Figure 5-A-40 Wide Flange Bulb Tee Girder Sections 5-A-42
Figure 5-A-41 Trapezodial Tub Girder Sections 5-A-43
Figure 5-A-42 Trapezoidal Tub Girder with Top Flange Sections 5-A-44
Figure 5-A-43 Deck Blub Tee Girder Section 5-A-45
Figure 5-A-44 Precast Prestressed Slab Sections 5-A-46
Figure 5-A-45 Double Tee and Ribbed Deck Girder Sections 5-A-47
Figure 5-A-46 Spliced I-Girders Sections 5-A-48
Figure 5-A-47 Spliced Trapeziodal Tub Girders Sections 5-A-49
Figure 5-A-48 Single Span Prestressed Girder Construction Sequence 5-A-50
Figure 5-A-49 Multiple Span Prestressed Girder Construction Sequence 5-A-51
Figure 5-A-50 Single Span Prestressed Girder Construction Sequence 5-A-52
Figure 5-A-51 W42G Girder Details 1 of 2 ..... 5-A-53
Figure 5-A-52 W42G Girder Details 2 of 2 ..... 5-A-54
Figure 5-A-53 W42G End Diaphragm on Girder Details 5-A-55
Figure 5-A-54 W42G Abutment Type Pier Diaphragm Details 5-A-56
Figure 5-A-55 W42G Fixed Flush-Face Diaphragm at Intermediate Pier Details 5-A-57
Figure 5-A-56 W42G Fixed Recessed-Face Diaphragm at Intermediate Pier Details .. 5-A-58
Figure 5-A-57 W42G Hinged Diaphragm at Intermediate Pier Details 5-A-59
Figure 5-A-58 W42G Intermediate Diaphragm Details 5-A-60
Figure 5-A-59 W42G Miscelleneous Diaphragm Details 5-A-61
Figure 5-A-60 Multiple Simple Spans Intermediate Pier Details 5-A-62
Figure 5-A-61 W50G Girder Details 1 of 2 ..... 5-A-63
Figure 5-A-62 W50G Girder Details 2 of 2 ..... 5-A-64
Figure 5-A-63 W50G End Diaphragm on Girder Details 5-A-65
Figure 5-A-64 W50G Abutment Type Pier Diaphragm Details 5-A-66
Figure 5-A-65 W50G Fixed Flush-Face Diaphragm at Intermediate Pier Details 5-A-67
Figure 5-A-66 W50G Fixed Recessed-Face Diaphragm at Intermediate Pier Details .. 5-A-68
Figure 5-A-67 W50G Hinged Diaphragm at Intermediate Pier Details 5-A-69
Figure 5-A-68 W50G Intermediate Diaphragm Details 5-A-70
Figure 5-A-69 W50G Miscelleneous Diaphragm Details 5-A-71
Figure 5-A-70 W58G Girder Details 1 of 3 ..... 5-A-72
Figure 5-A-71 W58G Girder Details 2 of 3 ..... 5-A-73
Figure 5-A-72 W58G Girder Details 3 of 3 ..... 5-A-74
Figure 5-A-73 W58G End Diaphragm on Girder Details 5-A-75
Figure 5-A-74 W58G Abutment Type Pier Diaphragm Details 5-A-76

Figure 5-A-75 W58G Fixed Flush-Face Diaphragm at Intermediate Pier Details 5-A-77
Figure 5-A-76 W58G Fixed Recessed-Face Diaphragm at Intermediate Pier Details .. 5-A-78
Figure 5-A-77 W58G Hinge Diaphragm at Intermediate Pier Details 5-A-79
Figure 5-A-78 W58G Intermediate Diaphragm Details 5-A-80
Figure 5-A-79 W58G Miscelleneous Diaphragm Details..... 5-A-81
Figure 5-A-80 W74G Girder Details 1 of 3 ..... 5-A-82
Figure 5-A-81 W74G Girder Details 2 of 3 ..... 5-A-83
Figure 5-A-82 W74G Girder Details 3 of 3 ..... 5-A-84
Figure 5-A-83 W74G End Diaphragm on Girder Details..... 5-A-85
Figure 5-A-84 W58G Abutment Type Pier Diaphragm Details..... 5-A-86
Figure 5-A-85 W58G Fixed Flush-Face Diaphragm at Intermediate Pier Details 5-A-87
Figure 5-A-86 W58G Fixed Recessed-Face Diaphragm at Intermediate Pier Details .. 5-A-88
Figure 5-A-87 W58G Hinge Diaphragm at Intermediate Pier Details 5-A-89
Figure 5-A-88 W58G Intermediate Diaphragm Details 5-A-90
Figure 5-A-89 W58G Miscelleneous Diaphragm Details..... 5-A-91
Figure 5-A-90 WF42G GIRDER DETAILS 1 OF 3 ..... 5-A-92
Figure 5-A-91 WF42G GIRDER DETAILS 2 OF 3 ..... 5-A-93
Figure 5-A-92 WF42G GIRDER DETAILS 3 OF 3 ..... 5-A-94
Figure 5-A-93 WF50G GIRDER DETAILS 1 OF 3 ..... 5-A-95
Figure 5-A-94 WF50G GIRDER DETAILS 2 OF 3 ..... 5-A-96
Figure 5-A-95 WF50G GIRDER DETAILS 3 OF 3 ..... 5-A-97
Figure 5-A-96 WF58G GIRDER DETAILS 1 OF 3 ..... 5-A-98
Figure 5-A-97 WF58G GIRDER DETAILS 2 OF 3 ..... 5-A-99
Figure 5-A-98 WF58G GIRDER DETAILS 3 OF 3 ..... 5-A-100
Figure 5-A-99 WF74G GIRDER DETAILS 1 OF 3 ..... 5-A-101
Figure 5-A-100 WF74G GIRDER DETAILS 2 OF 3 ..... 5-A-102
Figure 5-A-101 WF74G GIRDER DETAILS 3 OF 3 ..... 5-A-103
Figure 5-A-102 WF74G End Diaphragm on Girder Details..... 5-A-104
Figure 5-A-103 WF74G Abutment Type Pier Diaphragm Details 5-A-105
Figure 5-A-104 WF74G Fixed Flush-Face Diaphragm at Intermediate Pier Details 5-A-106
Figure 5-A-105 WF74G Fixed Recessed-Face Diaphragm at Intermediate Pier Details 5-A-107
Figure 5-A-106 WF74G Hinge Diaphragm at Intermediate Pier Details 5-A-108
Figure 5-A-107 WF74G Intermediate Diaphragm Details 5-A-109
Figure 5-A-108 WF74G Miscelleneous Diaphragm Details 5-A-110
Figure 5-A-109 W83G GIRDER DETAILS 1 OF 3..... 5-A-111
Figure 5-A-110 W83G GIRDER DETAILS 2 OF 3..... 5-A-112
Figure 5-A-111 W83G GIRDER DETAILS 3 OF 3..... 5-A-113
Figure 5-A-112 W83G End Diaphragm on Girder Details..... 5-A-114
Figure 5-A-113 W83G Abutment Type Pier Diaphragm Details..... 5-A-115
Figure 5-A-114 W83G Fixed Flush-Face Diaphragm at Intermediate Pier Details 5-A-116
Figure 5-A-115 W83G Fixed Recessed-Face Diaphragm at Intermediate Pier Details 5-A-117
Figure 5-A-116 W83G Hinge Diaphragm at Intermediate Pier Details 5-A-118
Figure 5-A-117 W83G Intermediate Diaphragm Details 5-A-119
Figure 5-A-118 W83G Miscelleneous Diaphragm Details..... 5-A-120
Figure 5-A-119 W95G GIRDER DETAILS 1 OF 3..... 5-A-121
Figure 5-A-120 W95G GIRDER DETAILS 2 OF 3..... 5-A-122
Figure 5-A-121 W95G GIRDER DETAILS 3 OF 3..... 5-A-123
Figure 5-A-122 W95G End Diaphragm on Girder Details..... 5-A-124
Figure 5-A-123 W95G Abutment Type Pier Diaphragm Details..... 5-A-125
Figure 5-A-124 W95G Fixed Flush-Face Diaphragm at Intermediate Pier Details 5-A-126

Figure 5-A-125 W95G Fixed Recessed-Face Diaphragm at Intermediate Pier Details 5-A-127
Figure 5-A-126 W95G Hinge Diaphragm at Intermediate Pier Details 5-A-128
Figure 5-A-127 W95G Intermediate Diaphragm Details 5-A-129
Figure 5-A-128 W95G Miscelleneous Diaphragm Details..... 5-A-130
Figure 5-A-129 W32BTG GIRDER DETAILS 1 OF 3..... 5-A-131
Figure 5-A-130 W32BTG GIRDER DETAILS 2 OF 3..... 5-A-132
Figure 5-A-131 W32BTG GIRDER DETAILS 3 OF 3..... 5-A-133
Figure 5-A-132 W38BTG GIRDER DETAILS 1 OF 3..... 5-A-134
Figure 5-A-133 W38BTG GIRDER DETAILS 2 OF 3..... 5-A-135
Figure 5-A-134 W38BTG GIRDER DETAILS 3 OF 3..... 5-A-136
Figure 5-A-135 W62BTG GIRDER DETAILS 1 OF 3..... 5-A-137
Figure 5-A-136 W62BTG GIRDER DETAILS 2 OF 3..... 5-A-138
Figure 5-A-137 W62BTG GIRDER DETAILS 3 OF 3..... 5-A-139
Figure 5-A-138 Prestressed Trapezoidal Tub Girder Details 1 of 3 ..... 5-A-140
Figure 5-A-139 Prestressed Trapezoidal Tub Girder Details 2 of 3 ..... 5-A-141
Figure 5-A-140 Prestressed Trapezoidal Tub Girder Details 3 of 3 ..... 5-A-142
Figure 5-A-141 Prestressed Trapezoidal Tub Girder End Diaphragm on Girder Details..... 5-A-143
Figure 5-A-142 Prestressed Trapezoidal Tub Girder Raised Crossbeam Details 5-A-144
Figure 5-A-143 Prestressed Trapezoidal Tub Girder Miscellaneous Details..... 5-A-145
Figure 5-A-144 Trapezoidal Tub S-I-P Deck Panel Girder - Details 1 of 4 ..... 5-A-146
Figure 5-A-145 Trapezoidal Tub S-I-P Deck Panel Girder - Details 2 of 4 ..... 5-A-147
Figure 5-A-146 Trapezoidal Tub S-I-P Deck Panel Girder - Details 3 of 4 ..... 5-A-148
Figure 5-A-147 Trapezoidal Tub S-I-P Deck Panel Girder - Details 4 of 4 ..... 5-A-149
Figure 5-A-148 Trapezoidal Tub S-I-P Deck Panel Girder - End Diaphragm on Girder Details..... 5-A-150
Figure 5-A-149 Trapezoidal Tub S-I-P Deck Panel Girder - Raised Crossbeam Details..... 5-A-151
Figure 5-A-150 Trapezoidal Tub S-I-P Deck Panel Girder - Miscellaneous Diaphragm Details 5-A-152
Figure 5-A-151 Precast Prestressed Stay-in-Place Deck Panel Details..... 5-A-153
Figure 5-A-152 Precast Prestressed 1’-0” Solid Slab Details 1 of 2 ..... 5-A-154
Figure 5-A-153 Precast Prestressed 1’-0” Solid Slab Details 2 of 2 ..... 5-A-155
Figure 5-A-154 Precast Prestressed 1’-6” Voided Slab Details 1 of 3..... 5-A-156
Figure 5-A-155 Precast Prestressed 1’-6” Voided Slab Details 2 of 3..... 5-A-157
Figure 5-A-156 Precast Prestressed 1’-6” Voided Slab Details 3 of 3..... 5-A-158
Figure 5-A-157 Precast Prestressed 2’-2” Voided Slab Details 1 of 3..... 5-A-159
Figure 5-A-158 Precast Prestressed 2’-2” Voided Slab Details 2 of 3..... 5-A-160
Figure 5-A-159 Precast Prestressed 2’-2” Voided Slab Details 3 of 3..... 5-A-161
Figure 5-A-160 Precast Prestressed Slab Layout..... 5-A-162
Figure 5-A-161 Precast Prestressed Slab End Pier Details 1 of 2 ..... 5-A-163
Figure 5-A-162 Precast Prestressed Slab End Pier Details 2 of 2 ..... 5-A-164
Figure 5-A-163 Precast Prestressed Slab Intermediate Piers Details 1 of 2 ..... 5-A-165
Figure 5-A-164 Precast Prestressed Slab Intermediate Piers Details 2 of 2 ..... 5-A-166
Figure 5-A-165 Precast Prestressed Ribbed Girder Details 1 of 2 ..... 5-A-167
Figure 5-A-166 Precast Prestressed Ribbed Girder Details 2 of 2 ..... 5-A-168
Figure 5-A-167 Precast Prestressed Ribbed Girder Pier Details 5-A-169
Figure 5-A-168 Precast Prestressed Double T Details 1 of 2 ..... 5-A-170
Figure 5-A-169 Precast Prestressed Double T Details 2 of 2 ..... 5-A-171
Figure 5-A-170 W35DG Deck Bulb Tee Girder Details 1 of 2 ..... 5-A-172
Figure 5-A-171 W35DG Deck Bulb Tee Girder Details 2 of 2 ..... 5-A-173

Figure 5-A-172 W35DG Deck Bulb Tee Diaphragm Details 5-A-174
Figure 5-A-173 W41DG Deck Bulb Tee Girder Details 1 of 2 ..... 5-A-175
Figure 5-A-174 W41DG Deck Bulb Tee Girder Details 2 of 2 ..... 5-A-176
Figure 5-A-175 W41DG Deck Bulb Tee Diaphragm Details 5-A-177
Figure 5-A-176 W53DG Deck Bulb Tee Girder Details 1 of 2 ..... 5-A-178
Figure 5-A-177 W53DG Deck Bulb Tee Girder Details 2 of 2 ..... 5-A-179
Figure 5-A-178 W53DG Deck Bulb Tee Diaphragm Details 5-A-180
Figure 5-A-179 W65DG Deck Bulb Tee Girder Details 1 of 2 ..... 5-A-181
Figure 5-A-180 W65DG Deck Bulb Tee Girder Details 2 of 2 ..... 5-A-182
Figure 5-A-181 W65DG Deck Bulb Tee Girder Diaphragm Details..... 5-A-183
Figure 5-A-182 W65DG Deck Bulb Tee Girder Misc. Diaphragm Details..... 5-A-184
Figure 5-A-183 WF74PTG Spliced Girder Details 1 of 5 ..... 5-A-185
Figure 5-A-184 WF74PTG Spliced Girder Details 2 of 5 ..... 5-A-186
Figure 5-A-185 WF74PTG Spliced Girder Details 3 of 5 ..... 5-A-187
Figure 5-A-186 WF74PTG Spliced Girder Details 4 of 5 ..... 5-A-188
Figure 5-A-187 WF74PTG Spliced Girder Details 5 of 5 ..... 5-A-189
Figure 5-A-188 W83PTG Spliced Girder Details 1 of 5 ..... 5-A-190
Figure 5-A-189 W83PTG Spliced Girder Details 2 of 5 ..... 5-A-191
Figure 5-A-190 W83PTG Spliced Girder Details 3 of 5 ..... 5-A-192
Figure 5-A-191 W83PTG Spliced Girder Details 4 of 5 ..... 5-A-193
Figure 5-A-192 W83PTG Spliced Girder Details 5 of 5 ..... 5-A-194
Figure 5-A-193 W95PTG Spliced Girder Details 1 of 5 ..... 5-A-195
Figure 5-A-194 W95PTG Spliced Girder Details 2 of 5 ..... 5-A-196
Figure 5-A-195 W95PTG Spliced Girder Details 3 of 5 ..... 5-A-197
Figure 5-A-196 W95PTG Spliced Girder Details 4 of 5 ..... 5-A-198
Figure 5-A-197 W95PTG Spliced Girder Details 5 of 5 ..... 5-A-199
Figure 5-A-198 Trapezoidal Tub Spliced Girder Details 1 of 5 ..... 5-A-200
Figure 5-A-199 Trapezoidal Tub Spliced Girder Details 2 of 5 ..... 5-A-201
Figure 5-A-200 Trapezoidal Tub Spliced Girder Details 3 of 5 ..... 5-A-202
Figure 5-A-201 Trapezoidal Tub Spliced Girder Details 4 of 5 ..... 5-A-203
Figure 5-A-202 Trapezoidal Tub Spliced Girder Details 5 of 5 ..... 5-A-204
Figure 5-A-203 Trapezoidal Tub Spliced Girder End Diaphragm on Girder Details.... 5-A-205
Figure 5-A-204 Trapezoidal Tub Spliced Girder Raised Crossbeam Details 5-A-206
Figure 5-A-205 Trapezoidal Tub Spliced Girder Miscellaneous Details..... 5-A-207
Figure 5-A-206 Trapezoidal Tub S-I-P Deck Panel Spliced Girder - Details 1 of 5 ..... 5-A-208
Figure 5-A-207 Trapezoidal Tub S-I-P Deck Panel Spliced Girder - Details 2 of 5 ..... 5-A-209
Figure 5-A-208 Trapezoidal Tub S-I-P Deck Panel Spliced Girder - Details 3 of 5 ..... 5-A-210
Figure 5-A-209 Trapezoidal Tub S-I-P Deck Panel Spliced Girder - Details 4 of 5 ..... 5-A-211
Figure 5-A-210 Trapezoidal Tub S-I-P Deck Panel Spliced Girder - Details 5 of 5 ..... 5-A-212
Figure 5-A-211 Trapezoidal Tub S-I-P Deck Panel Girder End Diaphragm on Girder Details 5-A-213
Figure 5-A-212 Trapezoidal Tub S-I-P Deck Panel Girder - Raised Crossbeam Details..... 5-A-214
Figure 5-A-213 Trapezoidal Tub S-I-P Deck Panel Girder - Miscellaneous Diaphragm Details 5-A-215
Figure 5-A-214 Vacant..... 5-A-216
Figure 5-A-215 Vacant..... 5-A-217

Appendix B

Appendix 5-B-1 "A" Dimension for Prestressed Girder Bridges 5-B-1
Appendix 5-B-2 Pre-approved Post-Tensioning Anchorages 5-B-3
Appendix 5-B-3 Existing Bridge Widenings 5-B-5
Appendix 5-B-4 P.T. Box Girder Bridges Single Span 5-B-7
Appendix 5-B-5 ..... 5-B-13
Design Example 1 Prestressed Girder Design 5-B-13
Design Example 2 Cast-in-Place Concrete Slab Design 5-B-55
Design Example 3 Precast Slab Design Stay-In-Place (SIP) Deck Panel 5-B-75
Design Example 4 Deck Bulb Tee and Ribbed Girder Design 5-B-95
Design Example 5 Solid and Voided Slab Design 5-B-101
Design Example 6 Positive EQ Reinforcement at Interior Pier of a Prestressed Girder 5-B-139
Design Example 7 Noise Wall Type D-2K (Precast Panel on Shaft) 5-B-143
Design Example 8 Construction Reinforcement in Crossbeam 5-B-157
Design Example 9 Stut and Tie Design 5-B-159
Design Example 10 Crossbeam Shear and Torsion Design 5-B-165
Design Example 11 Torsion and Shear Capacity of Reinforced Concrete Beams 5-B-169
Design Example 12 Strain Compatibility Approach for Flexural Capacity 5-B-173

5.0 General

The provisions in this section apply to the design of Cast-in-Place (CIP) an precast bridges constructed of normal density concrete and reinforced with mild reinforcing steel and/or prestressing strands or bars. The provisions are based on concrete ultimate compressive strengths of 10.0 ksi or less.

Prior to precast pretensioned and post-tensioned concrete members introduced in the early 1960s, all short and medium span bridges were built as cast-in-place and reinforced concrete superstructures. Examples of reinforced concrete superstructures are: flat slabs, T-beams, arches, and box girders. Many of the bridges built before 1960 are still functional, durable, and structurally sound. The service life of some of these early bridges can be extended by widening their decks to accommodate increased traffic demand or to improve safety.

5.1 Material Properties

Design of concrete structures shall be based on the on the material properties cited herein and on the use of material properties that conform to the current AASHTO LRFD Bridge Design Specifications[1], AASHTO LRFD Bridge Construction Specifications[2], and the WSDOT Standard Specifications for Road, Bridge, and municipal Construction[3].

5.1.1 Concrete Properties

A. Strength of Concrete

Pacific NW aggregates have consistently resulted in excellent concrete strengths, to as much as 10,000 psi in 28 days. The following strengths are normally used for design.

1. Cast-in-Place Concrete Bridges

Since conditions for placing and curing concrete on cast-in-place bridges are not as controlled, as they are for precast bridge sections, a lower concrete strength is used. Class 4000 concrete is typically used for all cast-in-place concrete bridges. Where significant economy can be gained and structural requirements dictate, the structure could be designed for class 5000 concrete. Use of CLASS 5000 or higher requires approval of the Bridge Design Engineer, Bridge Construction Office, and Materials Lab.

2. Precast Girders

Nominal 28-day concrete strength (f'_c) for precast girders with a cast-in-place deck is 7,000 psi. Where higher strengths would eliminate a line of girders, this strength can be specified, preferably at 8,500 psi up to a maximum of 10,000 psi. The final strength of concrete shall be specified as required by design and shown on the plans.

The minimum concrete compressive strength at release (f'_{ci}) for each prestressed girder in a bridge is to be calculated and shown in the plans. For a 28-day concrete compressive strength of 7,000 psi, a concrete compressive strength (at release) of between 3,500 and 6,000 psi shall be specified. For high strength concrete, the compressive strength at release shall be limited to 7,500 psi. Release strengths of up to 8,500 psi can be achieved with extended curing for special circumstances. The specified concrete strength at release should be rounded to the next highest 100 psi.

B. Classes of Concrete

1. CLASS 3000

   Used in large sections with light to nominal reinforcement, mass pours, sidewalks, curbs, gutters, and nonstructural concrete guardrail anchors, luminaire bases.

2. CLASS 4000

   Used in cast-in-place post-tensioned or conventionally reinforced concrete box girders, slabs, traffic and pedestrian barriers, approach slabs, footings, box culverts, wing walls, curtain walls, retaining walls, columns, and crossbeams.

3. CLASS 4000D

   Concrete class 4000D shall be used for all cast-in-place bridge decks unless otherwise approved by the Bridge Design Engineer. WSDOT requires two coats of curing compound and a continuous wet curing for 14 days.

4. CLASS 4000P

   Used for cast-in-place pile and shaft.

5. CLASS 4000W

   Used underwater in seals.

6. CLASS 5000 or Higher. Used in cast-in-place post-tensioned concrete box girder construction or in other special structural applications situations if significant economy can be gained.

   The 28-day compressive design strengths (f'_c) in pounds per square inch (psi) are shown in Table 5-1.

Classes of Concrete	f'_c, (psi)
COMMERCIAL	2300
3000	3000
4000, 4000D	4000
4000W	2400*
5000	5000**
6000	6000
4000P	3400***

* 40 percent reduction from CLASS 4000.

** Class 5000 concrete is available within a 30-mile radius of Seattle, Spokane, and Vancouver. Outside this 30-mile radius, concrete suppliers do not have the quality control procedures and expertise to supply control Class 5000 concrete.

*** 15 percent reduction from CLASS 4000 for all drilled shafts.

28-day Compressive Design Strength

Table 5-1

C. Relative Compressive Concrete Strength

a. During design or construction of a bridge, it is necessary to determine the strength of concrete at various stages of construction. For instance, Section 6-02.3(17)J of the WSDOT Standards Specifications discusses the time at which falsework and forms can be removed to various percentages of the concrete design strength. Occasionally, construction problems will arise which require a knowledge of the relative strengths of concrete at various ages. Table 5-2 shows the approximate values of the minimum compressive strengths of different classes of concrete at various ages. If the concrete has been cured under continuous moist curing at an average temperature, it can be assumed that these values have been developed.

b. Curing of the concrete (especially in the first 24 hours) have a very important influence on the strength development of concrete at all ages. Temperature affects the rate at which the chemical reaction between cement and water takes place. Loss of moisture can seriously impair the concrete strength.

c. If test strength is above or below that shown in Table 5-2, the age at which the design strength will be reached can be determined by direct proportion.

For example, if the relative strength at 10 days is 64 percent instead of the minimum 70 percent shown in Table 5-2, the time it takes to reach the design strength can be determined as follows:

Let x = relative strength to determine the age at which the concrete will reach the design strength

$\frac{x}{70} = \frac{100}{64}$ Therefore, x = 110%

From Table 5-2, the design strength should be reached in 40 days.

Age	Relative Strength	Class 5000	Class 4000	Class 3000	Age	Relative Strength	Class 5000	Class 4000	Class 3000
Days	%	ksi	ksi	ksi	Days	%	ksi	ksi	ksi
3	35	1.75	1.40	1.05	20	91	4.55	3.64	2.73
4	43	2.15	1.72	1.29	21	93	4.65	3.72	2.79
5	50	2.50	2.00	1.50	22	94	4.70	3.76	2.82
6	55	2.75	2.20	1.65	23	95	4.75	3.80	2.85
7	59	2.95	2.36	1.77	24	96	4.80	3.84	2.88
8	63	3.15	2.52	1.89	25	97	4.85	3.88	2.91
9	67	3.35	2.68	2.01	26	98	4.90	3.92	2.94
10	70	3.5	2.80	2.10	27	99	4.95	3.96	2.97
11	73	3.65	2.92	2.19	28	100	5.00	4.00	3.00
12	75	3.75	3.00	2.25	30	102	5.10	4.08	3.06
13	77	3.85	3.08	2.31	40	110	5.50	4.40	3.30
14	79	3.95	3.16	2.37	50	115	5.75	4.60	3.45
15	81	4.05	3.24	2.43	60	120	6.00	4.80	3.60
16	83	4.15	3.32	2.49	70	125	6.25	5.00	3.75
17	85	4.25	3.34	2.55	80	129	6.45	5.16	3.87
18	87	4.35	3.48	2.61	90	131	6.55	5.24	3.93
19	89	4.45	3.56	2.67	100	133	6.70	5.40	4.00

Relative and Compressive Strength of Concrete

Table 5-2

D. Modulus of Elasticity

The modulus of elasticity for concrete strength up to 10 ksi is normally taken:

$$E = 33000w^{3/2}\sqrt{f'_c} \qquad (5.1.1\text{-}1)$$

where:

w = Unit weight of concrete in kip/ft^3. (Normal unit weight concretes used in Washington generally have weights close to 0.155 kip/ft^3)

f'_c = Design compressive strength of concrete in ksi

E. Creep

The creep coefficient for standard conditions may be taken as follows:

Standard conditions are:

- Relative humidity ≤40 percent and
- Average thickness of section 6 inches

1. Cast-in-Place Girders

For most designs, the creep coefficient for loading at 7 days for moist-cured concrete and 1-3 days for steam-cured concrete is:

$$Ct = \frac{22}{6 + f'c} \cdot \frac{t^{0.6}}{10 + t^{0.6}} \qquad (5.1.1\text{-}2)$$

The final deflection is a combination of the elastic deflection and the creep effect associated with given loads shown by the equation below.

$$\Delta_{total} = \Delta_{elastic}\,(1 + C_t) \qquad (5.1.1\text{-}3)$$

For other factors affecting this equation, and methods for calculating creep effects see AASHTO LRFD Specifications section 5.4.2.3.

2. Standard Prestressed Girders

The creep coefficient for standard prestressed girders may be taken as:

$$Ct = \frac{3.95}{6 + f'c} Ln(t+1) \qquad (5.1.1\text{-}4)$$

C_t = creep coefficient

t = time in days

$f'c$ = ultimate strength of concrete in ksi

F. Shrinkage

To compute the variation of shrinkage with time, use the following equations:

For moist cured concrete after 7 days:

$$(\varepsilon_{SH})_t = \left(\frac{t}{35+t}\right) 0.51x10^{-3} \qquad (5.1.1\text{-}5)$$

For steam cured concrete after 1 to 3 days:

$$(\varepsilon_{SH})_t = \left(\frac{t}{55+t}\right) 0.56x10^{-3} \qquad (5.1.1\text{-}6)$$

Where: $(\varepsilon_{SH})_t$ shrinkage strain at any point in time

t = drying time

For corrections to the shrinkage rate values including correction for initial shrinkage, see AASHTO LRFD Specifications Section 5.4.2.3.

G. Grout

Grout is usually a prepackaged cement based grout or nonshrink grout that is mixed, placed, and cured as recommended by the manufacturer. It is used under steel base plates for both bridge bearings and luminaries or sign bridge bases. Should the grout pad thickness exceed 4 inches, steel reinforcement shall be used. For design purposes, the strength of the grout, if properly cured, can be assumed to be equal to or greater than that of the adjacent concrete but not greater than 4000 psi. Nonshrink grout is used in keyways between precast prestressed deck slabs, tri-beams, double-Tees, and deck bulb-tees.

5.1.2 Reinforcing Steel

A. Grades

Steel reinforcing bars are manufactured as plain or deformed bars (which have ribbed projections that grip the concrete in order to provide better bond between steel and concrete). In Washington State, the main reinforcing bars are always deformed. Plain bars are used for spirals and ties.

Reinforcing bars conform to either the requirements of AASHTO M31, Grade 60 (ASTM A-615 Grade 60) with a 60,000 psi yield strength or in the case of bars in portions of concrete members where plastic hanging can occur during an earthquake or which are to be spliced by welding, ASTM A 706 Specifications for Low-Alloy Steel deformed Bars for Concrete Reinforcement.

B. Sizes

Reinforcing bars are referred to in the contract plans and specifications by number and vary in size from #3 to #18. For bars up to and including #8, the number of the bar coincides with the bar diameter in eighths of an inch. The #9, #10, and #11 bars have diameters that provide areas equal to 1" x 1" square bars, $1\frac{1}{8}$" x $1\frac{1}{8}$" square bars and 1¼" x 1 ¼" square bars respectively. Similarly, the #14 and #18 bars correspond to 1½" x 1½" and 2" x 2" square bars, respectively. Table 5.1-A1 in Appendix A, shows the sizes, number, and various properties of the types of bars used in Washington State.

C. Development

1. Tension Development Length

Development length or anchorage of reinforcement is required on both sides of a point of maximum stress at any section of a reinforced concrete member.

Development of bars in tension involves calculating the basic development length, l_d, which is modified by factors to reflect bar spacing, cover, enclosing transverse reinforcement, top bar effect, type of aggregate, epoxy coating, and ratio of required area to provided area of reinforcement to be developed.

The development length, l_d (including all applicable modification factors) must not be less than 12 inches.

Table 5.1-A2 in Appendix A, show the tension development length for both uncoated and epoxy coated Grade 60 bars for normal weight concrete with specified strengths of 3,000 to 6,000 psi.

2. Compression Development Length


   The basic development lengths for deformed bars in compression are shown in Table 5.1-A3, Appendix A. These values may be modified for ratio of required area vs. provided area of reinforcement, or for bars enclosed in a ¼ inch diameter spiral at 4 inch maximum pitch. However, the minimum development length per WSDOT office practice is 1'-0".

3. Tension Development Length of Standard End Hook


   Standard end hooks, utilizing 90o and 180o end hooks, are used to develop bars in tension where space limitations restrict the use of straight bars. Figure 5-4 and 5-5 and Table 5-3 show the minimum embedment lengths necessary to provide 2 inches of cover on the tails of 90 and 180 degree end hooks. Epoxy coating does not affect the tension development lengths, ldh, of standard 90oand 180o end hooks. Tension development Length of 90o & 180o Standard Hooks are shown in Table 5.1-A4 of Appendix A.

Bar Size	Embedment
#3	6″
#4	7″
#5	9″
#6	10″
#7	1′−0″
#8	1′−2″
#9	1′−3″
#10	1′−5″
#11	1′−7″
#14	2′−10″
#18	3′−7″

Minimum Embedment Lengths of Standard 180° End Hooks
Table 5-3



Standard 180° and 90° End Hooks
Figure 5-4




Special Confinement for 180° and 90° End Hooks

Figure 5-5

Cantilever Retaining Wall

The footing near the corner, at the junction between the stem and the footing, with reinforcing as shown will fully develop the resisting moment as long as the toe of the footing is long enough for anchorage, and stress at “A” (bottom) is not critical.




Cantilever Retaining Wall ReinforcingDetails

Figure 5-6a

T-Joint

The forces from a tension crack at 45º . Reinforcement as shown is more than twice as effective in developing the strength of the corner than if the reinforcement was turned 180º.




T-Joint Reinforcing Details

Figure ***5-6b***

"Normal" Right Corners

Corners subjected to bending as shown will crack radially in the corner outside of the main reinforcing steel. Smaller size reinforcing steel shall be provided in the corner to distribute the radial cracking.




"Normal" Right Corner Reinforcing Details

Figure ***5-6c***

Right or obtuse angle corners


Corners subjected to bending as shown in figure (a) tend to crack at the reentrant corner and fail in tension across the corner. If not properly reinforced, the resisting corner moment may be less than the applied moment.



Right or Obtuse Angle Corner

Figure ***5-6d***


Reinforced as shown in figure (b), the section will develop 85% of the ultimate moment capacity of the wall. If the bends were rotated 180º , only 30% of the wall capacity would be developed.



Right or Obtuse Angle Corner Reinforcing Details

Figure ***5-6e***

Adding diagonal reinforcing steel across the corner as shown in figure (c), approximately equal to 50% of the main reinforcing steel, will develop the corner strength to fully resist the applied moment. Extend the diagonal reinforcement past the corner each direction for anchorage. Since this bar arrangement will fully develop the resisting moment, a fillet in the corner is normally unnecessary.



Right or Obtuse Angle Corner Reinforcing Details

*Figure **5-6f***

D. Splices

Three methods are used to splice reinforcing bars; lap splices, mechanical splices, and welded splices. Lap splicing of reinforcing bars is the most common method. The Contract Plans should clearly show the locations and lengths of lap splice. Lap splices are not permitted for bars larger than #11.

No lap splices, for either tension or compression bars, shall be less than 2'-0" per WSDOT office practice. See Section 5.11.5 of the LRFD Specifications for additional splice requirements.

1. Tension Lap Splices

Many of the same factors which affect development length affect splices. Consequently, tension lap splices are a function of the bar's development length, l_d. There are three classes of tension lap splices: Class A, B, and C. Designers are encouraged to splice bars at points of minimum stress and to stagger lap splices along the length of the bars.

Table 5.1-A5 in Appendix A, shows tension lap splices for both uncoated and epoxy coated Grade 60 bars for normal weight concrete with specified strengths of 3,000 to 6,000 psi. For additional requirements, see AASHTO LRFD Specifications Section 5.11.5.

For Seismic Performance Categories C and D, AASHTO LRFD Specifications Section 5.10.11.4.1, the lap splices for longitudinal column bars are permitted only within the center half of the column height and shall not be less than the lap splices given in Table 5.1-A5 in Appendix A, or 60 bar diameters, whichever is greater.

Note that the maximum spacing of the transverse reinforcement (i.e., column ties) over the length of the splice shall not exceed the smaller of 6 inches or ¼ of the minimum column plan dimension.

2. Compression Lap Splices

   The compression lap splices shown in Table 5.1-A6 in Appendix A, are for concrete strengths greater than 3,000 psi. If the concrete strength is less than 3,000 psi, the compression lap splices should be increased by one third. Note that when two bars of different diameters are lap spliced, the length of the lap splice shall be the larger of the lap splice for the smaller bar or the development length of the larger bar.

3. Mechanical Splices

   A second method of splicing is by mechanical splices, which are proprietary splicing mechanisms. The requirements for mechanical splices are found in AASHTO LRFD Specifications Sections 5.5.3.4 and 5.11.5.2.2.

4. Welded Splices

   Welding of reinforcing bars is the third acceptable method of splicing reinforcing bars. AASHTO LRFD Specifications Section 5.11.5.2.3 describes the requirements for welding reinforcing steel. On modifications to existing structures, welding of reinforcing bars may not be possible because of the non-weldability of some steels.

E. Bends

Standard hooks and bend radii for grade 60 reinforcing bars are shown in Figure 5.1-A1 of Appendix A. Note that the tail lengths are greater for the 135° seismic tie hook than for the regular or nonseismic 135° tie hook. For field bending requirements, see AASHTO LRFD Specifications Section 5.11.2.4.

F. Fabrication Lengths

Because of placement considerations, the overall lengths of bar size #3 has been limited to 30 feet and bar sizes #4 and #5 to 40 feet. To use longer lengths, the designer should make sure that the bars can be placed and transported by truck. The maximum overall bar lengths shall be specified as shown in Table 5-7.

Bar Size	Maximum Length
#3	30’-0”
#4, #5	40’-0”
#6, #7	60’-0”
#8, #9, #10	60’-0”
#11, #14, #18	60’-0”

Maximum Bar Lengths
Table 5-7

G. Placement

Placement of reinforcing bars can be a problem during construction. Reinforcing bars are more than just lines on the drawing, they have size, weight, and volume. In confined areas, the designer should ensure that reinforcing bars can be placed. Sometimes it may be necessary to make a large scale drawing of reinforcement to look for interference and placement problems. If interference is expected, additional details may be required in the contract plans showing how to handle the interference and placement problems. Figure 5.1-A2 of Appendix A shows the minimum clearance and spacing of reinforcement for beams and columns.

H. Percentage Requirements

There are several AASHTO LRFD requirements to ensure that minimum reinforcement is provided in reinforced concrete members.

1. Flexure

The reinforcement provided at any section should be adequate to develop a moment at least 1.2 times the cracking moment calculated on the basis of the modulus of rupture for normal weight concrete. The modulus of rupture for normal weight concrete is $7.5\sqrt{f'c}$. This requirement may be waived if the area of reinforcement provided is at least one-third greater than that required by analysis. For additional minimum reinforcement required, see AASHTO LRFD Specifications Section 5.7.3.3.2.

2. Compression

For columns, the area of longitudinal reinforcement shall not exceed 0.08 nor be less than 0.01 of the gross area, Ag, of the section. Preferably, the ratio of longitudinal reinforcement should not exceed 0.04 of the gross area, Ag, to ensure constructability and placement of concrete. If a ratio greater than 0.04 is used, the designer should verify that concrete can be placed. If for architectural purposes the cross section is larger than that required by the loading, a reduced effective area may be used. The reduced effective area shall not be less than that which would require 1% of the longitudinal area to carry the loading. Additional lateral reinforcement requirements are given in Section 5.7.4.3 of AASHTO LRFD Specifications, and for plastic hinge zones, see AASHTO LRFD Specifications Section 5.10.11.4.1. For column reinforcing, ASTM A 706 reinforcing may be specified upon Bridge Engineer's approval to improve ductility.

3. Other Minimum Reinforcement Requirements

For minimum shear reinforcement requirements, see AASHTO LRFD Specifications Section 5.8.2.5 and for minimum temperature and shrinkage reinforcement, see AASHTO LRFD Specifications Section 5.10.8.

5.1.3 Prestressing Steel

A. General

Three types of high-tensile steel used for prestressing steel are:

1. Strands: AASHTO M 203 Grade 270, low relaxation or stress relieved.
2. Bars: AASHTO M 275 Type II
3. Parallel wires: AASHTO M 204 Type WA

All WSDOT designs are based on low relaxation strands using either 0.5” or 0.6”diameter strands for girders, and 3/8” or 7/16” for stay-in-place precast deck panels. Properties of uncoated and epoxy coated prestressing stands are shown in Appendix A Table 5.1-A7.

B. Allowable Stresses

Allowable stresses for prestressing steel are as listed in AASHTO LRFD specifications Section 5.9.3-1.

C. Prestressing Strands

Standard strand pattern for all types of WSDOT prestressed girders are shown throughout the Appendix A.

1. Straight Strands

   The position of the straight strands in the bottom flange and temporary strands for shipping and handling in top flange has been standardized for each size of flange. Those strand positions and the girder flange sizes are summarized in Appendix G.

2. Harped Strands

   The harped strands are bundled at the 0.4 and 0.6 points of the girder length or at the 0.33 and 0.67 points of the girder length depending on the girder type. The harped strands are bundled at the harping points. Bundles are limited to 12 strands each. Twelve (12) and fewer harped strands are placed in a single bundle with the centroid normally 3 inches above the bottom of the girder. Strands in excess of 12 are bundled in a second bundle with the centroid 6 inches above the bottom of the girder. At the girder ends, the strands are splayed to a normal pattern. The centroid of strands at both the girder end and the harping point may be varied to suit girder stress requirements.

   Temporary strands in the top flange of the girder may be required for shipping (see section on girder shipping). These strands may be pretensioned and bonded only for the end 10 feet of the girder, or may be post-tensioned prior to lifting the girder from the form. These strands shall be considered in the design to reduce the required transfer strength, to provide stability during shipping, and to reduce the "A" dimension. These strands must be cut before the cast-in-place intermediate diaphragms are placed.

   The slope of the harped strands shall not be steeper than 8 horizontal to 1 vertical for W83G and W95G, and 6 horizontal to 1 vertical for all other prestressed girders.

   The harped strand exit location at the girder ends shall be held as low as possible while maintaining the concrete stresses within allowable limits.

D. Development of Prestressing Strand

1. General

   In determining the resistance of pretensioned concrete components in their end zones, the gradual buildup of the strand force in the transfer and development lengths shall be taken into account.

   The prestress force may be assumed to vary linearly from 0.0 at the point where bonding commences to a maximum at the transfer length.

   Between the transfer length and the development length, the strand force may be assumed to increase in a parabolic manner, reaching the tensile strength of the strand at the end of development length.

   For the purpose of this article, the transfer length may be taken as 60 strand diameters and the development length shall be taken as specified in AASHTO LRFD Section 5.11.4.2.

   The effects of debonding shall be considered as specified in AASHTO LRFD Section 5.1.3D-4.

2. Bonded Strand

   Pretensioning strand shall be bonded beyond the critical section for development length, in inches, taken as:

$$l_d \geq k\left(f_{ps} - \frac{2}{3} f_{pe} \right) d_b \qquad (5.1.3\text{-}1)$$

where:

d_b = Nominal strand diameter (in)

f_{pe} = Effective stress in prestressing steel after all losses (ksi)

f_{ps} = Stress in prestressing steel at nominal strength (ksi)

k = 1.6 prestressed girders

k = 1.0 for precast slabs and deck panels

The development length of uncoated & coated prestressing strands are shown in Appendix A table 5.1-A7.

3. Partially Debonded Strands

Where it is necessary to prevent a strand from actively supplying prestress force near the end of a girder, it may be debonded. This can be accomplished by taping a close fitting pvc tube to the stressed strand from the end of the girder to some point where the strand can be allowed to develop its load. Since this is not a common procedure, it should be carefully detailed on the plans. It is important when this method is used in construction that the taping of the tube be done in such a manner that concrete cannot leak into the tube and provide an undesirable bond of the strand.

The number of partially debonded strands should not exceed 25 percent of the total number of strands, and the number of debonded strands in any horizontal row shall not exceed 40 percent of the strands in that row.

Debonded strands shall be symmetrically distributed about the centerline of the member. Debonded lengths of pairs of strands that are symmetrically positioned about the centerline of the member shall be equal.

Exterior strands in each horizontal row shall be fully bonded.

Where a portion or portions of a pretensioning strand are not bonded and where tension exists in the precompressed tensile zone, the development length specified in AASHTO LRFD section 5.11.4.2 shall be doubled.

4. Strand Development Outside of Girder

For girders made continuous for live load, extended bottom prestress strands are used to carry positive live load, creep, and other moments from one span to another. WSDOT standard drawings for prestressed girders provide guidance to calculate required number of extended strands. Strands used for this purpose must be developed in the short distance between the two girder ends. This is normally accomplished by requiring strand chucks and anchors as shown in Figure 5-8. The nominal development length is normally 1'-9". At back walls which are connected to the superstructure, the extended strands may be used to withstand earthquake forces and, in this case, should be developed accordingly. The number of strands to be extended cannot exceed the number of straight strands available in the girder.

Designer shall calculate the exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stress imposed to the anchor, and concrete bearing against the projected area of the anchor. The total number of extended strands at each end of girder shall not be less than four or as specified herein.

$$Nps = 12(Mc + Vc \times h - M_{SIDL}) \times \frac{Nc}{Ng} \times \frac{K}{(0.9Aps \times fps \times d)} \qquad (5.1.3\text{-}2)$$

Where:

Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips

h = distance from top of column to c.g. of superstructure, ft

Nc = number of columns

Ng = number of girders

Aps = area of each extended strand, in^2

fps = ultimate strength of strands, ksi

d = distance from top of slab to c.g. of extended strands, in

M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)

K = 0.5 for L1 = L2
0.67 for L1 =2L2

The appropriate strand stress available to resist ultimate load f_{ps} shall not be taken greater than:

$$f_{ps} = \left(\frac{l_x}{d_b} - \frac{2}{3} f_{pe} \right) \qquad (5.1.3\text{-}3)$$


where:

L_x = Available developed length

d_b = Nominal strand diameter (in)

f_{pe} = Effective stress in prestressing steel after all losses (ksi)

f_{ps} = Available strand stress to resist ultimate load




Strand Development
Figure ***5-8***

5. Stress variation at free end of strand

Pretensioning strand shall be bonded beyond the section required to develop f_{ps} for a development length, 1_d. The stress in the pretensioning strand varies linearly from 0.0 at the point where bonding commences to the effective stress after losses, f_{pe}, at the end of the transfer length. Between the end of the transfer length and development length, the strand stress grows from the effective stress in the prestressing steel after losses to the stress in the strand at nominal resistance of the member. Between the end of the transfer length and the development length, the strand stress may be assumed to increase linearly, reaching the stress at nominal resistance, f_{ps}, at the development length.

The correlation between strand stress and the distance over which the strand is bonded to the concrete can be idealized by the relationship shown in Figure 5-9. This idealized variation of strand stress may be used for analyzing sections within the transfer and development length at the end of pretensioned members. In calculating the tensile stress in the longitudinal reinforcement, a variation of design stress with the distance from the free end of strand as specified in Figure 5-9 may be assumed.



Idealized relationship between steel stress and distance from the free end of strand.

Figure 5-9

5.1.4 Prestress Losses

AASHTO LRFD Specifications outline the method of predicting prestress losses for usual prestressed concrete bridges which may be used in design except as noted below.

The following sources of prestress loss can influence the effective stress in the strand.

A. Instantaneous Losses

1. Elastic shortening of concrete.

Transfer of prestress forces into the girder ends results in an instantaneous elastic loss. Prestress losses due to elastic shortening shall be added to the time dependent losses to determine the total losses. The loss due to elastic shortening in pretensioned members shall be taken as:

$$PL_{ES} = \frac{Ep}{Eci} f_{cgp} \qquad (5.1.4\text{-}1)$$

The loss due to elastic shortening in cast-in-place post-tensioned members and precast spliced-girders shall be taken as:

$$PL_{ES} = \frac{N-1}{N} \cdot \frac{Ep}{Eci} f_{cgp} \qquad (5.1.4\text{-}2)$$

where:

E_p = Modulus of elasticity of prestressing steel, ksi

E_{ci} = Modulus of elasticity of concrete at transfer, ksi

N = Number of identical prestressing tendons

f_{cgp} = Sum of concrete stresses at the center of gravity of prestressing tendons due to the prestressing force at transfer (after jacking for post-tensioned members) and the self-weight of the member at the section of maximum moment, ksi

$$f_{cgp} = \frac{P}{A_g} + \frac{Pe^2}{I_g} + \frac{M_g e}{I_g} \qquad (5.1.4\text{-}3)$$

For pretensioned member and low-relaxation strands, f_{cgp} may be calculated based on 0.7fpu. For post-tensioned members with bonded tendons, f_{cgp} may be calculated based on prestressing force after jacking at the section of maximum moment.

For final conditions, the designer shall assume the prestress acting on the section to be NA_S (0.70 f_{pu}-PL) for stress relieved strands and NA_s (0.75 f_{pu}-PL) for low relaxation strands.

Where:

N = number of stressed strands passing through the section

A_s = area of one strand, in^2

f_{pu} = ultimate strength in ksi


PL = total prestress losses in ksi in pretensioned members.

2. Anchorage Set Loss

The anchor set loss shall be based on 3/8"slippage for design purposes. Anchor set loss and the length affected by anchor set loss is shown in Figure 5-10.

$$x = \sqrt{\frac{\Delta_{set} A_{PT} E_P L}{P_{J-Left} - P_{J-Right}}} \qquad (5.1.4\text{-}4$$

$$\Delta f_{PA} = \frac{2x(P_{J-Left} - P_{J-Right})}{A_{PT} L} \qquad (5.1.4\text{-}5)$$



Anchor set loss
Figure 5-10

3. Friction losses.

Friction losses occurring during jacking and prior to anchoring depend on the system and materials used. For purposes of design, this office has specified a rigid spiral galvanized ferrous metal duct system for which μ shall be 0.20 and K = 0.0002. This system is at present available from several large suppliers. To avoid the substantial friction loss caused by sharp tendon curvature in the end regions where the tendons flare out from a stacked arrangement towards the bearing plates, use 0.10 times the span length or 20 feet as the minimum flare zone length. The recommended minimum radius (horizontal or vertical) of flared tendons is 200 feet. In the special cases where sharp curvature cannot be avoided, extra horizontal and vertical ties should be added along the concave side of the curve to resist the tendency to break through the web.

$$\Delta f_{PF} = f_{PJ}(1 - e^{-(kx+\mu\alpha)}) \qquad (5.1.4\text{-}6)$$

Where:

$$\alpha = \sqrt{(\alpha_H)^2 + (\alpha_V)^2}$$

$$\alpha_V = \frac{2\delta}{L}$$


$$\alpha_H = \frac{S}{R}$$

When summing the α angles for total friction loss along the structure, horizontal curvature of the tendons as well as horizontal and vertical roadway curvature should be included in the summation. Losses due to shrinkage, elastic shortening, creep, and relaxation of steel shall be as indicated in Subsection 5.2.4. The α angles for horizontally and vertically curved tendons are shown in Figure 5-11.

$$\alpha = \sqrt{(\alpha_H)^2 + (\alpha_V)^2}$$

$$\text{where: } \alpha_V = \frac{2\delta}{L}$$

$$\alpha_H = \frac{S}{R}$$



(5.1.4-7)

The α angles for Curved PT Tendons
Figure ***5-11***

B. Approximate Lump Sum Estimate of Time-dependent Losses

Time-depended losses include:

1. Creep of concrete.
2. Shrinkage of concrete.
3. Steel relaxation.

For normal design in lieu of more accurate methods, time dependent losses may be taken as shown in Table 5-12.

Type of Section	Low-relaxation Strands	Bars
Rectangular Beam	33 ksi	25 ksi
Box Girder	21 ksi	15 ksi
I-Girder	$33\left[1-\frac{0.15(f'c-6)}{6}\right]$	19 ksi
Single/Double T, Hollow Core Voided Slab	$37\left[1-\frac{0.15(f'c-6)}{6}\right]$	$29\left[1-\frac{0.15(f'c-6)}{6}\right]$

Time Dependent Prestress Losses
Table 5-12

C. Approximate Lump Sum Estimate of Time-Dependent Losses (Alternate Method)

For standard precast, pretensioned members subject to normal loading and environmental conditions and pretensioned with low relaxation strands, the long-term prestress loss, Δf_{pLT}, due to creep of concrete, shrinkage of concrete, and relaxation of steel may be estimated using the following formula:

$$\Delta f_{pLT} = 10.0\frac{f_{pi}A_{ps}}{A_g}\gamma_h\gamma_{st} + 12.0\gamma_h\gamma_{st} + 2.5 \qquad (5.1.4.8)$$

for which:

$$\gamma_h = 1.7 - 0.01H$$

$$\gamma_{st} = \frac{5}{(1 + f'_{ci})}$$

where:

f_{pi} = prestressing steel stress just before transfer to the concrete member (KSI)

A_{ps} = area of prestressing steel (IN^2)

A_g = gross area of concrete member (IN^2)

γ_h = correction factor for relative humidity of the ambient air

γ_{st} = correction factor for specified concrete strength at time of prestress transfer to the concrete member

For members of unusual dimensions, level of prestressing, construction schedule, or concrete constituent materials and for post-tensioned members, the Refined Method of AASHTO LRFD Specifications Section 5.9.5.4 or computer time-step methods should be used.

Equation 5.1.4.5 does not include any elastic shortening loss at time of prestress transfer or elastic elongation gain due to application of deck weight, superimposed dead loads, or live loads. These elastic losses and gains are automatically accounted for if transformed section properties are used in stress analysis.

D. Temporary Losses

For checking of stresses during release, lifting, transportation, and erection of prestressed girders, the elastic and time-dependent prestress losses may be taken as shown in Table 5-13.

Release — 1 day (lifting of girders from casting beds)	computed losses
1 month — 4 months (transportation and erection of girders)	0.75 x computed losses
After 4 months	computed losses

Temporary Prestress Losses

Table 5-13

5.1.5 Prestressing Anchorage Systems

There are numerous prestressing systems. Most systems combine a method of stressing the prestressing strands with a method of anchoring it to concrete.

WSDOT requires approval of all multi-strand and/or bar anchorages used in prestressed concrete bridges by testing or by a certified report, stating that the anchorage assembly will develop the yield strength of post-tensioning steel. WSDOT approved anchorages are listed in Appendix 5-B2.

5.1.6 Ducts

Ducts for longitudinal post-tensioning tendons shall be round and made of rigid galvanized ferrous metal, except for transverse post-tensioning in deck slab where rectangular or oval shape polyethylene ducts may be used. Ducts for transverse post-tensioning of bridge deck slabs may be rectangular.

A. Ducts for Internal Post-tensioning

For longitudinal tendons, prestressing stands shall be encased in a galvanized, ferrous metal duct that is rigid and spiral. For transverse tendons in deck slab, prestressing strands shall be encased a rigid plastic duct. Post-tensioning ducts shall maintain the required profile within a placement tolerance of plus or minus ¼ inch for longitudinal tendons and plus or minus 1/8 inch for transverse slab tendons during construction.

Vents at high points and drains at low points of the tendon profile shall be specified. Vents and drains shall be ½ inch minimum diameter standard steel or polyethylene pipe. Vents are not required for transverse post-tensioning ducts in the roadway slab unless specified in the Plans.

Strand tendon duct shall have an inside cross-sectional area large enough to accomplish strand installation and grouting. The area of the duct shall be at least 2.5 times the net area of prestressing steel in the duct. The maximum duct diameter shall be 4-½ inches.

The inside diameter of bar tendon duct shall at least be ¼ inch larger than the bar diameter. At coupler locations the duct diameter shall at least be ¼ inch larger than the coupler diameter.

Ducts installed and cast into concrete prior to prestressing steel installation, shall be capable of withstanding at least 10 feet of concrete fluid pressure.

Ducts shall have adequate longitudinal bending stiffness for smooth, wobble free placement. When the duct must be bent in a tight radius, more flexible duct may be used, subject to the Bridge Design Engineer's approval. The radius of curvature of tendon ducts shall not be less than 20 ft except in anchorage areas where 12 ft may be permitted.

B. Ducts for External Post-tensioning

Duct shall be high-density polyethylene (HDPE) conforming to ASTM D 3350, including the property values specified in Table X1 for pipe materials PE 3406 and PE 3408.

Duct for external tendons, including their splices, shall be water tight, seamless or welded, and be capable of resisting at least 150-psi grout pressure.

Transition couplers between ducts shall conform to either the standard pressure ratings of ASTM D 3505 or the hydrostatic design stresses of ASTM F 714 at 73F. The inside diameter through the coupled length shall not be less than that produced by the dimensional tolerances specified in ASTM D 3505.

Workers performing HDPE pipe welding shall have satisfactorily completed a certified HDPE pipe welding course and shall have a minimum of five years experience in welding HDPE pipe.

C. Transitions

Transitions between ducts and wedge plates shall have adequate length to reduce the angle change effect on the performance of strand-wedge connection, friction loss at the anchorage, and fatigue strength of the post-tensioning reinforcement.

5.2 Design Consideration

5.2.1 Design Limit States

Concrete bridge components shall be designed to satisfy the requirements of service, strength, and extreme-event limit states for load combinations specified in AASHTO LRFD Specifications Table 3.4.1-1.

A. Service Limit State

Concrete stresses, deformations, and cracking , distribution of reinforcement, deflection and camber shall be investigated at service limit state.

B. Strength Limit State

Axilal, Flexural, Shear strength and stability of concrete components shall be investigated at strength limit state. Resistance factors shall be based on AASHTO LRFD Specifications Section 5.5.4.2.

C. Extreme Event Limit State

Concrete Bridge components, and connections shall resist extreme event loads due to earthquakes and collision forces.

D. Fatigue Limit State

Fatigue of the reinforcement need not be checked for fully prestressed concrete satisfying requirements of service limit state. Fatigue need not be investigated for concrete deck slab on multi-girder bridges. For fatigue requirements, refer to AASHTO LRFD Specifications Section 5.5.3.

5.2.2 Design Criteria

AASHTO LRFD Specifications shall be used to design concrete bridges, except as modified in this section. Prestressed concrete bridges shall be designed for allowable stresses and checked for ultimate load capacity.

A. Design Assumptions and Requirements

The WSDOT design criteria for prestressed girders is given in Table 5-14. These design assumptions and requirements apply to pretensioned girders only. Deck thickness of 7½″ minimum including ½" wearing surface is to be assumed unless a thinner deck can be justified by analysis or by the space necessary to place the deck reinforcement with the required clearances and cover.

Bridge end skew angle is often controlled by the roadway geometry. For common practices this skew angle shall be limited to 45 degrees for all prestressed girders. Skew angle for precast slab and trapezoidal tubs shall be limited to 30 degrees. Deviation from these limits needs Bridge Engineers approval.

Design Specifications	AASHTO LRFD Specifications and WSDOT Bridge Design Manual
Design Method	Prestressed members are designed for service limit state for allowable stresses and checked for strength limit state for ultimate capacity. All other members shall be designed in accordance with the requirements of strength limit state.
Design Assumption	Prestressed girders are designed as simple span for all transient and permanent loads for both simple and continuous spans. Continuity reinforcement are provided at intermediate piers for negative transient loads and super imposed dead loads.
Load and Load factors	Service, Strength, and Extreme Event Limit State load and load combinations per LRFD Specifications
Allowable Stresses	BDM Table 5-15
Prestress Losses	BDM Article 5.2.4 and Table 5.2.4-1
Shear Design	AASHTO LRFD article 5.8 and BDM 5.2.4C
Shipping and Handling	BDM Article 5.6.3C

Design Criteria for prestressed Girders

Table 5-14

5.2.3 Service Limit State

A. General

Service limit state is used to satisfy allowable stresses, deflection, and cracking requirements. Design aid for tensile stress, f_S, and cracking moment, M_{cr}, which are used to check crack control and minimum flexural reinforcement respectively are provided in Appendix A. Figure 5.2-A1 and Tables 5.2-A4 and 5.

B. Allowable Stresses

WSDOT requires that under service limit state the tensile stresses in the precompressed tensile zone shall be limited to zero. This prevents cracking of the concrete during service life of the structure and provides additional stress and strength capacity for overloads. Allowable concrete stresses are shown in Table 5-15.

Condition	Stress	Location	Allowable Stress
Temporary Stress at Transfer and at Lifting from Casting Bed	Tensile	In areas other than Precompressed Tensile Zone and without bonded reinforcement	$0.0948\sqrt{f'_{ci}} \le 0.2(ksi)$
		In areas with bonded reinforcement other than Precompressed Tensile Zone	$0.19\sqrt{f'_{ci}}(ksi)$
	Compression	All Locations	0.6 f'_{ci}
Temporary Stress at Shipping	Tensile	In areas other than Precompressed Tensile Zone and without bonded reinforcement	$0.0948\sqrt{f'_{c}} \le 0.2(ksi)$
		In areas with bonded reinforcement other than Precompressed Tensile Zone	$0.19\sqrt{f'_{c}}(ksi)$
	Compression	All Locations	0.6 $f'c$
Final Stresses at Service Load	Tensile	Precompressed Tensile Zone	0.0
	Compression	All Locations due to:	
		Permanent Loads and effective prestress loads	0.45 f'_c
		Live load plus one-half permanent loads and effective prestress load	0.4 f'_c
		All load combinations	0.6 f'_c

Allowable Stresses in Prestressed Concrete Members Before Losses
Table 5-15

5.2.4 Strength Limit State

A. Design Philosophy

In the strength limit state or previously referred as ultimate strength method, the service loads are increased by load factors to obtain the ultimate design load. The structural members are then proportioned to provide the design ultimate strength.

For flexural strength, it has been determined that AASHTO LRFD Specifications Section 5.7.3 underestimates the strength of the composite deck-girder system[5]. The strain compatibility method given in Section 8.2.2.5 of the PCI Bridge Design Manual 6 is recommended for this analysis. In addition to the effective area of the deck, the top flange of the girder and the mild reinforcement in the deck and the top flange of the girder should be included in the analysis. The typical section for computation of composite section properties is shown in Figure 5-16

B. Flexure

The basic strength design requirement can be expressed as follows:

Design Strength, $\phi M_n \ge M_u$ (5.2.4-1)

For design purposes, the area of reinforcement for a singly reinforced beam or slab can be determined by letting:

$$M_u = \varphi M_n = \varphi\left[A_s f_y (d - \frac{a}{2}) \right] \quad (5.2.4\text{-}2)$$

However, if $a = \frac{A_S f_y}{0.85 b f'_c}$ and $\rho = \frac{A_S}{bd}$ (5.2.4-3)

Equation (2) can be expressed as:

$$\frac{M_U}{\varphi b d^2} = \rho f_y \left(1 - 0.59 \frac{\rho f_y}{f'_c} \right) \quad (5.2.4\text{-}4)$$

Tables 5.2-A1 through 5.2-A3 in Appendix A were prepared based on Equation (4) to quickly determine the amount of required reinforcing steel ($A_{S\ required}$), when M_u, f'_c, f_y, b, and d are known.

An alternate approach is to solve directly for $A_{S\ required}$ from:

$$A_{S.\mathrm{Required}} = \frac{0.85 f'_c (b)}{f_y} \left(d - \sqrt{d^2 - \frac{31.3725 M_u}{f'_c (b)}} \right) \quad (5.2.4\text{-}5)$$

Similarly, substituting 1.2Mcr for M_u, $A_{S\ min}$ can be found from:

$$A_{S.Min} = \frac{0.85 f'_c (b)}{f_y} \left(d - \sqrt{d^2 - \frac{0.124 h^2}{\sqrt{f'_c}}} \right) \quad (5.2.4\text{-}6)$$

where:

h = slab thickness, in.

M_u = ultimate flexural moment, ft-kips

f'_c = ultimate compressive strength of concrete, ksi

From AASHTO LRFD 5.7.3.3-1 $A_{S\ max}$ can be found from:


$$A_{s.\max} = 0.6375 \beta_1 (b)(d) \frac{f'_c}{f_y} \left(\frac{87}{87 + f_y} \right) \quad (5.2.4\text{-}7)$$

where: $\beta_1 = 0.85$ if $f'_c \leq 4$ ksi and
$\beta_1 = 0.85 - 0.05 (f'_c - 4)$ if $f'_c > 4$ ksi, but not less than 0.65


Tension reinforcement should be designed in the following order:

1. From Eq (5) or Tables 5.2-A1 through 5.2-A3 in Appendix A, determine $A_{S\ required}$.
2. From Eq (6) determine $A_{S\ min}$.
3. From Eq (7) or Tables 5.2-A1 through 5.2-A3 in Appendix A, determine $A_{S\ max}$.
4. If $A_{S\ required} > A_{S\ max}$, increase the member's dimensions.
   If $A_{S\ max} > A_{S\ required} > A_{S\ min}$, use $A_S \geq A_{S\ required}$.
   If $A_{S\ required} < A_{S\ min} < 1.33\ A_{S\ required}$, use $A_S \geq A_{S\ min}$.
   If $1.33\ A_{S\ required} < A_{S\ min}$, use $A_S \geq 1.33\ A_{S\ required}$.
   Note: Always use $A_S \leq A_{S\ max}$.

See Appendix B for design examples.



SECTION AS DETAILED



SECTION FOR COMPUTATION OF COMPOSITE SECTION PROPERTIES

Typical Section for Computation of Composite Section Properties

Figure ***5-16***

C. Shear

The AASHTO LRFD Specifications Section 5.8.3 addresses shear design of concrete members.

The shear design for deep beams is addressed in Section 5.2.5G, and Section 11.8, ACI 318-02 of Building Code Requirements for Reinforced Concrete and Commentary, and ACI-ASCE Committee 343 Analysis and design of reinforced concrete bridge structures[7,8,9].

Shear in webs of prestressed bridges shall be in accordance with AASHTO LRFD specifications. For special considerations used for design of Washington State standard prestressed girders, see Subsection 5.2.4D.


D. Interface Shear

Shear friction provisions discussed in AASHTO LRFD Specifications Section 5.8.3 are applied to transfer shear across a plane, such as: an existing or potential crack, an interface between dissimilar materials, or at a construction joint between two sections of concrete placed at different times.

Interface shear in prestressed girder bridge design is critical at the interface connection between slab and girder, and at the end connection of the girder to the crossbeam in continuous bridges. Shear in these areas will normally be resisted by reinforcement extending from the girder.

1. Interface Shear Between Slab and Girder

   This shear represents a rate of change of compression load in the flange of simple span girders or a rate of change of tension load in the flange near the piers of continuous girders. For a simple span girder as represented by Figure 5-17, the top flange stress is the factored centerline moment divided by the section modulus of the composite girder at the centerline of the slab. The horizontal force in slab is this stress times the area of the slab. The factored centerline moment can be taken as total factored moment less 1.0 times dead load applied to girder.




Shear Design for a Simple Span Girder
Figure 5-17

This shear is resisted by the girder stirrups which extend up through the interface between the girder and the slab. The top surface of the girder top flange must be roughened. The force may be assumed to be carried uniformly over the entire girder top surface from centerline of bearing to centerline of span.

For continuous girders, the span, shear, and moment relationships are shown in Figure 5-18. Similar methods are used to analyze slab to girder shear. For positive moment resistance, only those stirrups within length L_c are considered effective in resisting the slab force due to moment. Likewise, only those stirrups within one continuous length L_e are used to resist the negative moment slab force (tension) in that area.

For illustrative purposes, a single concentrated load has been shown. In actual practice, the point of factored maximum moment of the actual moment diagram would be used.

Other flange shear problems are described in Section 5.4. These problems also need to be considered for prestressed girder bridges.




Shear Design for Continuous Span Girder

*Figure 5-**18***

2. Shear at Girder End

   A continuous prestressed girder will nearly always be required to carry end reaction shears at the surface of the end of the girder. An exception to this is girders with notched crossbeams where loads must be carried across the connections which act as hinges.



End Connection for a Continuous Span Prestressed Girder

Figure 5-19

The usual end condition is similar to that shown in Figure 5-19. The shear which must be carried along the interface A-A is the actual factored dead load and live load shear acting on the section. The girder end is required by the plans to be roughened. The saw-toothed shear key shown on the office standard girder plans may be assumed to provide a friction factor of 1.0. Shear resistance must be developed using shear friction theory assuming the longitudinal bars and the extended strands are actively participating. The main longitudinal slab reinforcement is already fully stressed by girder bending moments and thus cannot be considered for shear requirements. All bars, including the extended strands, must be properly anchored in order to be considered effective. This anchorage requirement must be clearly shown on the plans.

The factored shear at the end of prestressed girders shall be transferred to diaphragm. The design for saw tooth shear keys at girder ends for shear transfer to cast-in-place pier diaphragm shall be based on AASHTO LRFD Specifications Section 5.8.4.1.

$$V_n = c\,A_{cv} + \mu\,(A_{uf}f_y + P_c) < 0.2\,F'_c\,A_{cv} < 0.8\,A_{cv} \qquad (5.2.4\text{-}1)$$

Wherer:

$c = 0.10$ ksi, and $\mu = 1.0\,\lambda$, with $\lambda = 1.0$ for normal weight concrete

Note that similar requirements exist for connecting the end diaphragm at bridge ends where the diaphragm is cast on the girders. In this case, however, loads consist only of the factored diaphragm dead load, approach slab dead load, and those wheel loads which can distribute to the interface. Longitudinal reinforcement provided at girder ends shall be identical in both ends of the girder for construction simplicity.

3. Stirrups

Shear for computation of stirrup requirements is computed at d_v from the end of the girder and at the harping point. Ultimate shear is computed at these points based on 1.25 DC + 1.75 (LL + IM). The portion of this shear which is carried by the concrete is given in Section 5.8.4 of AASHTO LRFD Specifications. The stirrup spacing is then calculated using the formula:

$$S = \frac{A_v . f_y . d}{V_s} \qquad (5.2.4\text{-}2)$$

where : $V_s = \frac{V_u}{0.9} - V_c$

d_v = Distance from the extreme compressive fiber to the centroid of the prestressing force.

For precast girders made continuous for live load, d shall be the distance from the extreme compressive fiber to the centroid of the negative moment reinforcement, i.e., d = h + A - 4.5”,

where:

h = height of the girder

A = as defined in Appendix B.

If the stirrup spacing at the point of critical section for shear, d_v from the end of the girder, is smaller than about 1’-2”, further interpolation may be done to obtain a multiple step increment of stirrup spacing.

4. End Section Reinforcement

The Washington State Standard Prestressed Concrete Girders are not provided with a thickened end block section, but have constant thickness webs. The end section reinforcement is detailed on the Office Standard Plans. This reinforcement is based on the requirement to resist bursting forces due to strand force development in this area. If the stirrup spacing required at the end of the girder is less than shown on the Office Standard Plans, end section stirrups spacing on the Standard Plans should be altered to show this spacing. For a distance of 1.5d from the end of the girder, reinforcement shall be placed to confine the prestressing steel in bottom flange. The spacing of confinement reinforcement shall not exceed 6 inch and shall be shaped to enclose the strands.

E. Shear Reinforcement in End Region

1. The end region is considered to be about 1.5 times the depth of the girder, h, from the end of the girder.

2. The vertical reinforcement shown on the standard plans provides for the maximum bursting (splitting) demand at the end of the girder for the maximum number of straight and harped strands plus six temporary strands in the top flange of the girder. This need not be changed unless the number of strands is increased. Generally the maximum number of strands is limited to 68 plus 6 temporary by the maximum concrete transfer strength of 7.50 ksi. The vertical bursting (splitting) reinforcement is located within approximately h/4 from the end of the girder and closely approximates 4 percent of the applied prestressing force at transfer. See AASHTO LRFD Specifications Section 5.10.10.

3. Other reinforcement shown in the end region accounts for vertical shear for the span configurations above and four (4) support conditions,

    1. Lifting with no reaction at the end region, i.e. lifting devices located interior from the end of the girder,

    2. Girder plus three intermediate diaphragms plus 20 psf supported on oak bunking block,

3. Bridge reactions on elastomeric bearings introducing compression into the end region, and

4. Bridge reactions at the end face of the girder (End Types C and D).

The designer shall investigate any additional vertical reinforcement for reaction forces, in the direction of the applied shear, along the vertical end face of the girder. This applies to girder end types A, C and D, where all loads are eventually transferred to the face of the hinge diaphragm or crossbeam. Adequate vertical shear reinforcing is required to take the reaction back up to the top of the girder near the diaphragm interface.

F. Shear Reinforcement Beyond End Region

1. Shear reinforcement size and spacing beyond the end region of the girder shall be determined by the designer. The variation in reinforcing demand for the entire range of span and spacing configurations is considerable. The shear reinforcement is likely to be light, or nominal, for the longest single piece spans with a narrow girder spacing, whereas the demand will be significant well out into the span for shorter spans with wide girder spacing.

2. The minimum angle theta, θ, for calculating shear reinforcement should be 25 degrees to avoid excessive horizontal tension demand through the bottom corner of the girder by the AASHTO LRFD modified compression field theory.

G. Shear and Torsion

The design for shear and torsion is based on ACI 318-02 Building Code[7] Requirements for Structural Concrete and Commentary (318F-02) and is satisfactory for bridge members with dimensions similar to those normally used in buildings. The AASHTO LRFD Specifications Section 5.8.3.6 may also be used for design of sections subjected to shear and torsion.

According to Hsu[10], utilizing ACI 318-02 for members is awkward and overly conservative when applied to large-size hollow members. Collins and Mitchell[11] propose a rational design method for shear and torsion based on the compression field theory or strut and tie method for both prestressed and non-prestressed concrete beams. These methods assume that diagonal compressive stresses can be transmitted through cracked concrete. In addition to transmitting these diagonal compressive stresses, shear stresses are transmitted from one face of the crack to the other by a combination of aggregate interlock and dowel action of the stirrups.

For recommendations and design examples for beams in shear and torsion, the designer can refer to the paper by M.P. Collins and D. Mitchell, Shear and Torsion Design of Prestressed and Non-Prestressed Concrete Beams, PCI Journal, September-October 1980, pp. 32-100[11].

5.2.5 Strut-and-tie Model

A. General

Strut-and-tie models may be used to determine internal force effects near supports and the points of application of concentrated loads[1].

The strut-and-tie model should be considered for the design of deep beams and pile caps or other situations in which the distance between the centers of applied load and supporting reaction is less than twice the member thickness. Design and detailing considerations for strut-and-tie modeling is covered in AASHTO LRFD Section 5.6.3. The resistance factors applicable to strut-and-tie design is covered in AASHTO LRFD Section 5.5.4.2. See Appendix 5-B for a strut and tie design example for a pier cap.

5.2.6 Deflection and Camber

A. General

Flexural members are designed to have adequate stiffness to limit deflections or any deformations which may adversely affect the strength or serviceability of the structure at service load plus impact. The minimum superstructure depths are specified in AASHTO LRFD Table 2.5.2.6.3-1 and deflections shall be computed in accordance with AASHTO LRFD Specifications Section 5.7.3.6.2.

B. Camber Multiplier

Deflections of prestressed concrete beams can be predicted with greater accuracy than those for reinforced concrete beams. Since prestressed concrete is more or less homogeneous and obeys ordinary laws of flexure and shear, the deflection can be computed using elementary methods. However, accurate predictions of the deflections are difficult to determine, since modulus of elasticity of concrete, Ec, varies with stress and age of concrete. Also, the effects of creep on deflections are difficult to estimate. For practical purposes, an accuracy of 10 to 20 percent is often sufficient. Prestressing can be used advantageously to control deflections, however, there are cases where excessive camber due to prestress have caused problems. For normal design, in lieu of more accurate methods, the deflection and camber of prestressed members may be estimated by the multipliers as given in Table 5.2.6-1.

	Normal Strength Concrete $f'_C \leq 7.0ksi$		High Strength Concrete $f'_C \succ 7.0ksi$	
	Non-Composite	Composite	Non-Composite	Composite
Deflection at Erection				
Apply to the elastic deflection due to the member weight at release of prestress	1.85	1.85	1.75	1.75
Apply to the elastic deflection due to prestressing at release of prestress	1.80	1.80	1.70	1.70
Deflection at Final				
Apply to the elastic deflection due to the member weight at release of prestress	2.70	2.40	2.50	2.20
Apply to the elastic deflection due to prestressing at release of prestress	2.45	2.20	2.25	2.10
Apply to the elastic deflection due to the Super Imposed Dead Loads	3.00	3.00	2.75	2.75
Apply to the elastic deflection due to weight of slab	----	2.30	----	2.15

Multipliers for Estimating Long-term Deflection of Prestressed Concrete Girders

Table 5-20

The computer program 'PGSUPER' is used to determine the amount of girder camber for prestressed girder bridges. This program computes the deflections due to prestress, girder dead load, slab dead load, and live load.

C. Deflection Calculation

Figure 5-21 shows a typical pattern of girder deflection with time at centerline span. Portions of this characteristic curve are described below. The subparagraph numbers correspond with circled numbers on the curve.

1. Elastic Deflection Due to Prestress Force

   The prestress force produces moments in the girder tending to bow the girder upward. Resisting these moments are girder section dead load moments. The result is a net upward deflection. In addition, a shortening of the girder occurs due to axial prestress loading.

2. Creep Deflection

   The girder continues to deflect upward due to the effect of creep. This effect is computed using the equation stated in Subsection 5.1.1E-2.

3. Deflection Due to Removal of Temporary Strands

   Removal of temporary strands results in an elastic upward deflection.

4. Diaphragm Load Deflection


   The load of diaphragm is applied to the girder section resulting in an elastic downward deflection.

5. Slab Load Deflection

   The load of the slab is applied to the girder section resulting in an elastic downward deflection. It is this deflection which is offset by the screed camber that is to be applied to the bridge deck during construction.

6. Final Camber

   It might be expected that the above slab dead load deflection would be accompanied by a continuing downward deflection due to creep. Many measurements of actual structure deflections have shown, however, that once the slab is poured, the girder tends to act as though it is locked in position. To obtain a smooth riding surface on the deck, the deflection indicated on Figure 5-21 as “Screed Camber” is added to the profile grade elevation of the deck screeds. The actual position of the girder at the time of the slab pour has no effect on the screed camber.



Prestressed Girder Camber

Figure 5-21

5.2.7 Serviceability

In addition to the deflection control requirements described above, service load stresses shall be limited to satisfy fatigue and for distribution of tension reinforcement when f_y for tension reinforcement exceeds 40,000 psi.

A. Serviceability Requirements

The cracking control of the concrete, tension reinforcement at maximum positive and negative moment sections shall be chosen so that the calculated service load stress, f_s (ksi), shall be less than the value computed by:

$$f_s = \frac{Z}{\sqrt[3]{d_c.A}} \le 0.6 f_y \qquad (5.2.6\text{-}1)$$

The requirements for control of cracking apply to superstructure elements only.

Service load stresses are calculated utilizing service limit state. The values of dc and A are defined in AASHTO LRFD Specifications Section 5.7.3.4. The value Z shall be 130 kips per inch for girder and crossbeam reinforcing bars in negative moment regions, and all deck reinforcing bars. A value of 170 kips per inch shall be used for all other positive moment regions. Note that this check is for distribution of flexural reinforcement to control cracking. See Figure 5-77 which shows the flexural reinforcement at a pier location placed equally in top and bottom layers. When this is done, the total slab thickness can be used in computing A.

B. Modified Serviceability Requirement

To control flexural cracking under Service Limit State the spacing of reinforcement on the tension face shall not exceed the following:

$$s \le \frac{20}{C_f}\left(\frac{36}{f_{sa}}\right)^3 \le 18IN \qquad (5.2.6\text{-}2)$$

where:

$C_f = 1$ moderate exposure and culverts with 8" minimum stab depth

$C_f = 2$ moderate exposure where more restrictive crack control may be required or culverts with less than 8" slab depth and other buried structures.

$C_f = 4$ transverse segmental box girder design or members in severe exposure conditions.

$C_f = 8$ culverts with acidic flows and members located in a constant wet/dry condition and in a saltwater environment.

When computing, f_{sa} , the effects of TU, CR, SH and SE may be computed using a value of E_c equal to one-half that computed by Equation 5.1.1-1.

5.2.8 Connections (Joints)

The connections or joints must divide the structure into a logical pattern of separate elements which also permit ease of manufacture and assembly.

The connection or joint surfaces should be oriented perpendicular to the centroidal axis of the precast element.

A. Types of Connections (Joints):

Connections or joints are either wide or match cast. Depending on their width, they may be filled with cast-in-place concrete or grout. Match cast joints are normally bonded with an epoxy bonding agent. Dry match cast joints are not recommended.

B. Shear and Alignment Keys:

In order to assist shear transmission in wide joints, use a suitable system of keys. The shape of the keys may be chosen to suit a particular application and they can be either single keys or multiple keys. Single keys are generally large and localized whereas multiple keys generally cover as much of the joint surface area as is practical.

Single keys provide an excellent guide for erection of elements. Single keys are preferred for all match cast joints.

For all types of joints, the surfaces must be clean, free from grease and oil, etc. When using epoxy for bonding, the joints should be lightly sandblasted to remove laitance. For cast-in-place or other types of wide joints, the adjacent concrete surfaces should be roughened and kept thoroughly wet, prior to construction of the joint. Cast-in-place joints are generally preferred.

5.2.9 Revised Provisions for Flexural Design

A. Introduction

This section introduces the necessary revisions to AASHTO LRFD specifications for more accurate flexural resistance calculations. The provisions described herein are adapted to WSDOT PGSuper program for the design of prestressed members.

B. Necessary Revisions to LRFD Specification

The AASHTO LRFD Specifications contain provisions for calculating the flexural strength of T-beams that are not consistent with the original derivation of the effective rectangular stress block as applied to beams where the neutral axis drops into the web. The proposed revisions revert to the calculation methods of the ACI 318 and the Standard Specifications, with the exception that the LRFD method of calculating the stress in the prestressing steel at nominal flexural strength is retained. Research[31, 32, 33, 34] has shown that the LRFD equations provide a more realistic estimate of the stress in the prestressing steel at nominal flexural strength if T-beam behavior is assumed to begin when "a" becomes greater than hf.

To implement these revisions, the current LRFD Equations 5.7.3.1.1-3 and 5.7.3.1.2-3 for T-beam behavior shall be modified by deleting β1 from the last term of the numerator as shown below:

For sections with bonded tendons:

$$c = \frac{A_{ps} f_{pu} + A_s f_y - A'_s f'_y - 0.85 f'_c (b - b_w) h_f}{0.85 f'_c \beta_1 b_w + k A_{ps} \frac{f_{pu}}{d_p}} \qquad (5.2.9\text{-}1)$$

For sections with unbonded tendons:

$$c = \frac{A_{ps} f_{ps} + A_s f_y - A'_s f'_y - 0.85 f'_c (b - b_w) h_f}{0.85 f'_c \beta_1 b_w} \qquad (5.2.9\text{-}2)$$

Consequently, the nominal flexural resistance of LRFD Equation 5.7.3.2.2-1 shall be modified by deleting β_1 from the last term as shown below:

$$M_n = A_{ps} f_{ps} \left(d_p - \frac{a}{2} \right) + A_s f_y \left(d_s - \frac{a}{2} \right) - A'_s f'_y \left(d'_s - \frac{a}{2} \right) + 0.85 f'_c (b - b_w) h_f \left(\frac{a}{2} - \frac{h_f}{2} \right) \qquad (5.2.9\text{-}3)$$

C. Nominal Flexural Resistance

1. Theoretical Background

These provisions could be considered a philosophical change to traditional flexural resistance calculations of reinforced and prestressed concrete members. In these provisions sections are considered either tension –controlled, transition or - compression controlled. Classifying sections as tension-controlled, transition or compression-controlled, and linearly varying the resistance factor in the transition zone between values for the two extremes, provides a rational approach for determining ϕ and limiting the capacity of over-reinforced sections.

Sections are compression-controlled when the net tensile strain in the extreme tension steel is equal to or less than the compression-controlled strain limit at the time the concrete in compression reaches its assumed strain limit of 0.003. The compression-controlled strain limit is the net tensile strain in the reinforcement at balanced strain conditions. For Grade 60 reinforcement, and for all prestressed reinforcement, the compression-controlled strain limit may be set equal to 0.002.


Sections are tension-controlled when the net tensile strain in the extreme tension steel is equal to or greater than 0.005 just as the concrete in compression reaches its assumed strain limit of 0.003. Sections with net tensile strain in the extreme tension steel between the compression-controlled strain limit and 0.005 constitute a transition region between compression-controlled and tension-controlled sections.

Balanced strain conditions exist at a cross section when tension reinforcement reaches the strain corresponding to its specified yield strength f_y just as the concrete in compression reaches its assumed ultimate strain of 0.003.

For beams with compression reinforcement, or T-beams, the effects of compression reinforcement and flanges are automatically accounted for in the computation of net tensile strain ε_t. The use of compression reinforcement in conjunction with additional tension reinforcement is permitted to increase the strength of flexural members.

2. Nominal Flexural Resistance

The nominal flexural resistance of a member is reached when the strain in the extreme compression fiber reaches the assumed strain limit of 0.003. The net tensile strain εt is the tensile strain in the extreme tension steel at nominal strength, exclusive of strains due to prestress, creep, shrinkage and temperature. The net tensile strain in the extreme tension steel is determined from a linear strain distribution at nominal strength, as shown in Figure 5-22, using similar triangles.



Strain distribution and net tensile strain

Figure 5-22

When the net tensile strain in the extreme tension steel is sufficiently large (equal to or greater than 0.005), the section is defined as tension-controlled where ample warning of failure with excessive deflection and cracking may be expected. When the net tensile strain in the extreme tension steel is small (less than or equal to the compression-controlled strain limit), a brittle failure condition may be expected, with little warning of impending failure. Flexural members are usually tension-controlled, while compression members are usually compression-controlled. Some sections, such as those with small axial load and large bending moment, will have net tensile strain in the extreme tension steel between the above limits. These sections are in a transition region between compression- and tension-controlled sections.

3. Resistance Factors

The resistance factors for tension-controlled and compression-controlled sections, and for intermediate cases in the transition region shall be taken as follows:

For tension-controlled reinforced concrete sections ……...0.90

For tension-controlled prestressed concrete sections ……..1.00

For compression-controlled sections with spirals or ties,……0.75

For sections in which the net tensile strain in the extreme tension steel at nominal strength is between the limits for compression-controlled and tension-controlled sections, ϕ may be linearly increased from 0.75 to that for tension-controlled sections as the net tensile strain in the extreme tension steel increases from the compression-controlled strain limit to 0.005.

This variation in, ϕ, may be computed for prestressed members as follows:

$$\phi = 0.583 + 0.25\left(\frac{d_t}{c} - 1\right) \qquad (5.2.9\text{-}4)$$

and for non-prestressed members as follows:

$$\phi = 0.65 + 0.15\left(\frac{d_t}{c} - 1\right) \qquad (5.2.9\text{-}5)$$

where:


d_t = distance from extreme compression fiber to centroid of extreme tension steel

ε_t = net tensile strain in extreme tension steel at nominal strength

In applying the resistance factors for tension-controlled and compression-controlled sections, the axial tensions and compressions to be considered are those caused by external forces. Effects of prestressing forces are not included.

A lower ϕ-factor is used for compression-controlled sections than is used for tension-controlled sections because compression-controlled sections have less ductility, are more sensitive to variations in concrete strength, and generally occur in members that support larger loaded areas than members with tension-controlled sections.

For sections subjected to axial load with flexure, factored resistances are determined by multiplying both P_n and M_n by the appropriate single value of ϕ. Compression-controlled and tension-controlled sections are defined as those that have net tensile strain in the extreme tension steel at nominal strength less than or equal to the compression-controlled strain limit, and equal to or greater than 0.005, respectively. For sections with net tensile strain ε_t in the extreme tension steel at nominal strength between the above limits, the value of ϕ may be determined by linear interpolation, as shown in Figure 5-23.



Variation of ϕ with net tensile strain ε_t and d_t/c

Figure 5-23

D. Limit of Reinforcement

The LRFD Specifications do not handle maximum reinforcement limits for prestressed and non-prestressed flexural members in a consistent manner. While over-reinforced non-prestressed flexural members are not allowed, over-reinforced prestressed flexural members are allowed if sufficient ductility of the structure can be achieved.

LRFD specifications limit the tension reinforcement quantity to a maximum amount such that the ratio c/d_e did not exceed 0.42. Sections with $c/d_e > 0.42$ were considered over-reinforced. Over-reinforced nonprestressed members were not allowed, whereas prestressed and partially prestressed members with PPR greater than 50 percent were if "it is shown by analysis and experimentation that sufficient ductility of the structure can be achieved." No guidance was given for what "sufficient ductility" should be, and it was not clear what value of ϕ should be used for such over-reinforced members. These provisions eliminate this limit and unify the design of prestressed and nonprestressed tension- and compression-controlled members. The background and basis for these provisions are given in references 31, 32, 33 and 34.

E. Moment Redistribution

In lieu of more refined analysis, where bonded reinforcement is provided at the internal supports of continuous reinforced concrete beams, negative moments determined by elastic theory at strength limit states may be increased or decreased by not more than 1000 ε_t percent, with a maximum of 20 percent. Redistribution of negative moments shall be made only when ε_t is equal to or greater than 0.0075 at the section at which moment is reduced.

Unless unusual amounts of ductility are required, the 0.005 limits will provide ductile behavior for most designs. One condition where greater ductile behavior is required is in design for redistribution of moments in continuous members and frames. Since moment redistribution is dependent on adequate ductility in hinge regions, moment redistribution is limited to sections that have a net tensile strain of at least 0.0075.

5.3 Reinforced Concrete Box Girder Bridges

A typical box girder bridge is comprised of top and bottom concrete slabs connected by a series of vertical girder stems. This section is a guide for designing top slab, bottom slab, and girder web. For design criteria not covered, see BDM Section 2.4.1.C.

5.3.1 Box Girder Basic Geometries

A. Web Spacing

The most economical web spacing for ordinary box girder bridges varies from about 8 to 12 feet. Greater girder spacing requires some increase in both top and bottom slab thickness, but the cost of the additional concrete can be offset by decreasing the total number of girder stems. Fewer girder stems reduces the amount of form work required and a lower cost.

The number of girder stems can be reduced by cantilevering the top slab beyond the exterior girders. A deck overhang of approximately one-half the girder spacing generally gives satisfactory results. This procedure usually results in a more aesthetic as well as a more economical bridge.

For girder stem spacing in excess of 12 feet or cantilever overhang in excess of 6 feet, transverse post-tensioning shall be used.

B. Basic Dimensions

The basic dimensions for concrete box girders with vertical web is shown in Figure 5-24 and the basic dimensions for box girders with sloped exterior webs is shown in Figure 5-25.

1. Top Slab Thickness, T1

   (includes ½″ wearing surface)

   $T_1 = \dfrac{12(S+10)}{30}$ but not less than 7” with overlay or 7.5” without overlay.

2. Bottom Slab Thickness, T2

   a. Near center span

      $T_2 = \dfrac{12(S_{clr})}{16}$ but not less than 5.5” (normally 6.0″ is used).

   b. Near intermediate piers

      Thickening of the bottom slab is often used in negative moment regions to control compressive stresses that are significant.

      Transition slope = 24:1 (see T2′ in Figure 5-24).

3. Girder Stem (Web) Thickness, T3

   a. Near center span

      Minimum T3 = 9.0″ — vertical

      Minimum T3 = 10.0″ — if sloped

   b. Near supports


      Thickening of girder stems is used in areas adjacent to supports to control shear requirements.

Changes in girder web thickness shall be tapered for a minimum distance of 12 times the difference in web thickness.

Maximum T3 = T3+4.0″ maximum

Transition length = 12 x (T3) in inches

≠ 6" x 6" FILLET FOR #4 AND #5 STIRRUPS
7.5" x 7.5" FILLET FOR #6 STIRRUP
9" x 9" FILLET FOR #7 STIRRUP



Basic Dimensions— Vertical Webs

Figure 5-24

4. Intermediate Diaphragm Thickness, T4 and Diaphragm Spacing

   a. For tangent and curved bridge with R > 800 feet

      T4 = 0″ (Diaphragms are not required.)

   b. For curved bridge with R < 800 feet

      T4 = 8.0″

      Diaphragm spacing shall be as follows:

      For 600′ < R < 800′at ½ pt. of span.


      For 400′ < R < 600′ at 1/3 pt. of span.

      For R < 400′ at ¼ pt. of span.


C. Construction Considerations

Review the following construction considerations to minimize constructability problems:

1. Construction joints at slab/stem interface or fillet/stem interface at top slab are appropriate.
2. All construction joints to have roughened surfaces.
3. Bottom slab is parallel to top slab (constant depth).
4. Girder stems are vertical.
5. Dead load deflection and camber to nearest 1/8″.
6. Skew and curvature effects have been considered.
7. Thermal effects have been considered.
8. The potential for falsework settlement is acceptable. This always requires added stirrup reinforcement in sloped outer webs.



a - 2% CROWN



b - 8% SUPERELEVATION

BASIC DIMENSIONS
SLOPED WEBS

Dimensions are shown for demonstraion only

Basic Dimensions-Sloped Webs

Figure 5-25

D. Load Distribution

1. Unit Design

According to the AASHTO LRFD Specifications, the entire slab width shall be assumed effective for compression. It is both economical and desirable to design the entire superstructure as a unit rather than as individual girders. When a reinforced box girder bridge is designed as an individual girder with a deck overhang, the positive reinforcement is congested in the exterior cells. The unit design method permits distributing all girder reinforcement uniformly throughout the width of the structure.

2. Dead Loads

a. Box dead loads.

b. D.L. of top deck forms:

5 lbs. per sq. ft. of the area.

10 lbs. per sq. ft. if web spacing > 10′–0″.

c. Traffic barrier.

d. Overlay, intermediate diaphragm, and utility weight if applicable.

3. Live Load

a. Superstructure

No. of lanes = slab width (curb to curb) / 14

Fractional lane width will be used

For example, 58 roadway / 14 = 4.14, then No. of lanes = 4.14

b. Substructure

No. of lanes = slab width (curb to curb) / 12

Fractional lane width will be ignored

For example, 58 roadway / 12 = 4.83, then No. of lanes = 4.0

c. Overload if applicable.

5.3.2 Reinforcement

This section discusses Flexural and Shear reinforcement for top slab, bottom slab, wbes, and intermediate diaphragms in box girders.

A. Top Slab Reinforcement

1. Near Center of Span

Figure 5-26 shows the reinforcement required near the center of the span and Figure 5-27 shows the overhang reinforcement.

a. Transverse reinforcing in the top and bottom layers to transfer the load to the main girder stems.

b. Bottom longitudinal “distribution reinforcement” in the middle half of the deck span S_{eff} is provided to aid in distributing the wheel loads.

c. Top longitudinal “temperature and shrinkage reinforcement.”

2. Near Intermediate Piers

Figure 5-28 illustrates the reinforcement requirement near intermediate piers.

a. Transverse reinforcing same as center of span.

b. Longitudinal reinforcement to resist negative moment (see Figure 5-28).

c. "Distribution of flexure reinforcement" to limit cracking (see Figure 5-28).

Allowable stress in tensile reinforcement shall satisfy


where: Z = 130 kips per inch

3. Bar Patterns

a. Transverse Reinforcement

It is preferable to place the transverse reinforcement parallel to the crossbeam and end diaphragm on skew angles up to 25 degrees or less as shown in Figure 5-29. Where skew angles exceed 25 degrees, the transverse bars are normal to bridge center line and the areas near the expansion joint and bridge ends are reinforcement by partial length bars.


b. Longitudinal Reinforcement



$$P = \frac{220}{\sqrt{S}} \qquad (MAX. = .67)$$


Partial Section Near Center of Span

Figure 5-26



Overhang Detail

*Figure 5-**27***




* TOP MAT REBARS SHALL BE EPOXY COATED, BEND STIRRUPS 135 DEGREES. DO NOT EPOXY COAT STIRRUPS.

** SEE TABLE 6.3.3.B2-1 FOR REQUIRED MINIMUM SLAB THICKNESS

Top Slab Flexural Reinforcing Near Intermediate Pier

*Figure 5-**28***



Partial Plans at Abutments
Figure 5-29

B. Bottom Slab Reinforcement

1. Near Center of Span

Figure 5-30 shows the reinforcement required near the center of the span.

a. Minimum transverse "distributed reinforcement."

As=0.005 x flange area with ½ A_S distributed equally to each surface.

b. Longitudinal "main reinforcement" to resist positive moment.

c. Check "distribution of flexure reinforcement" to limit cracking (see Figure 5-30).

Allowable stress in tensile reinforcement shall satisfy

$$f_s = \frac{Z}{\sqrt[3]{d_c.A}} \le 0.6 f_y \quad (5.3.2\text{-}1)$$

where z = 170 kips per inch.

d. Add steel for construction load (sloped outer webs).

2. Near Intermediate Piers

Figure 5-31 shows the reinforcement required near intermediate piers.

a. Minimum transverse reinforcement same as center of span.

b. Minimum longitudinal "temperature and shrinkage reinforcement."

As=0.004 x flange area with ½ A_S distributed equally to each face.

c. Add steel for construction load (sloped outer webs).

3. Bar Patterns

a. Transverse Reinforcement

See top slab bar patterns, Figures 5-26, 5-27, and 5-28.

All bottom slab transverse bars shall be bent at the outside face of the exterior web. For a vertical web, the tail splice will be 1′–0″ and for sloping exterior web 2′–0″ minimum splice with the outside web stirrups. See Figure 5-32. The bottom transverse slab reinforcement is discontinued at the crossbeam (see Figure 5-29).

b. Longitudinal Reinforcement

For longitudinal reinforcing bar patterns, see subsection 5.3.2-6.

C. Web Reinforcement

1. Vertical Stirrups

Vertical stirrups for a reinforced concrete box section is shown in Figure5-32.

The web reinforcement should be designed for the following requirements:

Vertical shear requirements.

- Out of plane bending on outside web due to live load on cantilever overhang.
- Horizontal shear requirements for composite flexural members.
- Minimum stirrups shall be:

$$\frac{A_v}{s} = 50\frac{b_w}{f_y} \qquad (5.3.2\text{-}2)$$

but not less than#5 bars @ 1′–6″,

Where: b_W is the number of girder webs x T3

2. Web Longitudinal Reinforcement

Web longitudinal reinforcement for reinforced concrete box girders is shown in Figure 5-34. If the depth of the side face of a member exceeds 3 feet, longitudinal skin reinforcement shall be uniformly distributed along both side faces of the member for a distance d/2 nearest the flexural tension reinforcement. The area of skin reinforcement A_{sk} per foot of height on each side face shall be:


$$A_{sk} \geq 0.012\ (d - 30) \qquad (5.3.2\text{-}3)$$

Where A_s = Total required area of longitudinal reinforcement, and

Reinforcing steel spacing < Web Thickness (T3) or 12″.


The maximum spacing of skin reinforcement shall not exceed the lesser of d/6 and 12 inches. Such reinforcement may be included in strength computations if a strain compatibility analysis is made to determine stresses in the individual bars or wires. The total area of longitudinal skin reinforcement in both faces need not exceed one half of the flexural tensile reinforcement.

For cast-in-place sloped outer webs, increase inside stirrup reinforcement and bottom slab top transverse reinforcement as required for the web moment locked-in during construction of the top slab. This moment about the bottom corner of the web is due to tributary load from the top slab concrete placement plus 10 psf form dead load. See Figure 5-35 for typical top slab forming.




Bottom Slab Reinforcement Near Center of Span

Figure 5-30




Bottom Slab Reinforcement Near Intermediate Pier

Figure 5-31




SLOPED WEB



VERTICAL WEB

Web Reinforcement
Figure 5-32



PARTIAL LONGITUDINAL GIRDER SECTION


Use 2 #10 (2 #8 & 2 #6 for 10" or less webs) at negative moment region near piers. The length of shall be extended 35 diameters beyond the dead load point of inflecton. Do not splice the #10 (#8) bars near the pier. The #6 bars may be spliced at center pier. Use 2 #8 only for the positive moment region.

Web Reinforcement Details

Figure 5-33

D. Intermediate Diaphragm

Intermediate diaphragms are not required for bridges on tangent alignment or curved bridges with an inside radius of 800 feet or greater.




Notes:

1. If the bar is not spliced, the horizontal dimension should be 4″ shorter than the slab width.
2. Stirrup hanger must be placed above longitudinal steel when diaphragm is skewed and slab reinforcement is placed normal to center of roadway. (Caution: Watch for the clearance with longitudinal steel).
3. The reinforcement should have at least one splice to facilitate proper bar placement.

Web Reinforcement Details

*Figure 5-**34***



Notes:

1. The diagonal brace supports web forms during web pour. After cure, the web is stiffer than the brace, and the web attracts load from subsequent concrete placements.
2. The tributary load includes half the overhang because the outer web form remains tied to and transfers load to the web which is considerably stiffer than the formwork.
3. Increase web reinforcement for Locked-in Construction Load due to top slab forming for sloped web box girders.

Typical Top Slab Forming for Sloped Web Box Girder

Figure 5-35


5.3.3 Crossbeam

A. General

Crossbeam shall be designed in accordance with the requirements of strength limit state design of AASHTO LRFD Specifications and shall satisfy the serviceability requirements for crack control.


B. Basic Geometry

For aesthetic purposes, it is preferable to keep the crossbeam within the superstructure so that the bottom slab of the entire bridge is a continuous plane surface interrupted only by the columns. Although the depth of the crossbeam may be limited, the width can be made as wide as necessary to satisfy design requirements. Normally, it varies from 3 feet to the depth of box but is not less than the column size plus 1'-0" to allow placement of the column reinforcement as shown in see Figures 5-36 and 5-37.



Crossbeam Top Reinforcement for Skew Angle ≤ 25°

Figure 5-36



Crossbeam Top Reinforcement for Skew Angle > 25°

Figure 5-37

Crossbeams on box girder type of construction shall be designed as a T beam utilizing the flange in compression, assuming the deck slab acts as a flange for positive moment and bottom slab a flange for negative moment. The effective overhang of the flange on a cantilever beam shall be limited to six times the flange thickness.

The bottom slab thickness is frequently increased near the crossbeam in order to keep the main box girder compressive stresses to a desirable level for negative girder moments as shown in Figures 5-36 and 5-37. This bottom slab flare also helps resist negative crossbeam moments. Consideration should be given to flaring the bottom slab at the crossbeam for designing the cap even if it is not required for resisting main girder moments.

C. Loads


For concrete box girders the superstructure dead load shall be considered as uniformly distributed over the crossbeam. For concrete box girders the live load shall be considered as the truck load directly to the crossbeam from the wheel axles. Truck axles shall be moved transversely over the crossbeam to obtain the maximum design forces for the crossbeam and supporting columns.

D. Reinforcement Design and Details

The crossbeam section consists of rectangular section with overhanging deck and bottom slab if applicable. The effective width of the crossbeam flange overhang shall be taken as the lesser of:

- 6 times slab thickness,
- 1/10 of column spacing, or
- 1/20 of crossbeam cantilever as shown in Figure 5-38.

The rectangular section of the crossbeam shall have a minimum width of column dimension plus 6 inches.



Effective Width of Crossbeam

Figure 5-38

Crossbeam is usually cast to the fillet below the top slab. To avoid cracking of concrete on top of the crossbeam, construction reinforcement shall be provided at approximately 3 inches below the construction joint. The design moment for construction reinforcement shall be the factored negative dead load moment due to the weight of crossbeam and adjacent 10 feet of superstructure each side. The total amount of construction reinforcement shall be adequate to develop an ultimate moment at the critical section at least 1.2 times the cracking moment M_{cr}.

Special attention should be given to the details to ensure that the column and crossbeam reinforcement will not interfere with each other. This can be a problem especially when round columns with a great number of vertical bars must be meshed with a considerable amount of positive crossbeam reinforcement passing over the columns.

1. Top Reinforcement

   Provide negative moment reinforcement at the ¼ point of the square or equivalent square columns.

a. When Skew Angle < 25º

If the bridge is tangent or slightly skewed and the deck reinforcement is parallel to the cross beam, the negative cap reinforcement can be placed either in contact with top deck negative reinforcement or directly under the main deck reinforcement (see Figure 5-36). Reinforcement must be epoxy coated if the location of reinforcement is less than 4″ below top of deck.

b. When Skewed Angle > 25º

When the structure is on a greater skew and the deck steel is normal or radial to the longitudinal centerline of the bridge, the negative cap reinforcement should be lowered to below the main deck reinforcement (see Figure 5-37).

c. To avoid cracking of concrete, interim reinforcements are required below the construction joint in diaphragms and crossbeams.

The interim reinforcements shall develop a moment capacity of 1.2 Mcr where Mcr may be given as:

$$M_{cr} = \frac{f_r I_g}{y_t} \qquad (5.3.3\text{-}1)$$

$$f_r = 7.5\sqrt{f'_c} \qquad (5.3.3\text{-}2)$$

$$M_{cr} = 1.25bh^2\sqrt{f'_c} \qquad (5.3.3\text{-}3)$$

$$M_n = 1.2M_{cr} = 1.5bh^2\sqrt{f'_c} \qquad (5.3.3\text{-}4)$$

$$A_S = \frac{0.85f'c(b)}{fy}\left(d - \sqrt{d^2 - \frac{31.3725M_u}{f'c(b)}}\right) \qquad (5.3.3\text{-}5)$$

2. Skin Reinforcement

If the depth of crossbeam exceeds 3 feet, longitudinal skin reinforcement shall be provided on both sides of the member for a distance of d/2 nearest the flexural reinforcement. The area of skin reinforcement per foot of height on each side shall be: $A_{sk} >= 0.012$ (d-30)

The maximum spacing of skin reinforcement shall not exceed d/6 or 12 inches whichever is less.


5.3.4 End Diaphragm

A. Basic Geometry

Bearings at the end diaphragms are usually located under the girder stems and transfer loads directly to the pier as shown in Figure 5-39. In this case, the diaphragm width should be equal to or greater than bearing grout pads as shown Figure 5-40.


Designer should provide access space for maintenance and inspection of bearings.

Allowance should be provided to remove and replace the bearings. Lift point locations, jack capacity, number of jacks, and maximum permitted lift should be shown in the plan details.



Bearing Locations, Lift Points, Jack Capacity, and Maximum Lift Permitted at End Diaphragm

Figure 5-39




OUT TO OUT LENGTH
OF BRIDGE > 400FT.
(NO REINFORCEMENT SHOWN)

L-shape Abutment End Diaphragm

Figure 5-40

The end diaphragms should be wide enough to provide adequate reinforcing embedment length. When the structure is on a skew greater than 25 degrees and the deck steel is normal or radial to the center of the bridge, the width should be enough to accommodate the embedment length of the reinforcement.


The most commonly used type of end diaphragm is shown in Figure 5-41. The dimensions shown here are used as a guideline and should be modified if necessary. This end diaphragm is used with a stub abutment and overhangs the stub abutment. It is used on bridges with an overall or out-to-out length less than 400 feet. If the overall length exceeds 400 feet, an L-shape abutment should be used.



End Diaphragm With Stub Abutment
Figure 5-41

B. Reinforcing Steel Details

Typical reinforcement details for an end diaphragm are shown in Figure 5-42.



Typical End Diaphragm Reinforcement
Figure 5-42

5.3.5 Dead Load Deflection and Camber

Camber is the adjustment made to the vertical alignment to compensate for the anticipated dead load deflection and the long-term deflection caused by shrinkage and creep. Estimating long-term deflection and camber for reinforced concrete flexural members should be based on the creep coefficient given in section 5.1.1E. See table 5.3.5-1 for long-term camber multipliers.

	Multiplier Coefficient
Girder Adjacent to Existing/Stage Construction	
Deflection (downward) — apply to the elastic deflection due to the weight of member	1.90
Deflection (downward) — apply to the elastic deflection due to superimposed dead load only	2.20
Girder Away From Existing/Stage Construction	
Deflection (downward) — apply to the elastic deflection due to the weight of member	2.70
Deflection (downward) — apply to the elastic deflection due to superimposed dead load only	3.00

Long-term Camber Multipliers
Table 5-43

In addition to dead load deflection, forms and falsework tend to settle and compress under the weight of freshly placed concrete. The amount of this take-up is dependent upon the type and design of the falsework, workmanship, type and quality of materials and support conditions. The camber should be modified to account for anticipated take-up in the falsework.

5.3.6 Thermal Effects

Concrete box girder bridges are subjected to stresses and/or movements resulting from temperature variation. Temperature effects result from time-dependent variations in the effective bridge temperature and from temperature differentials within the bridge superstructure.

A. Effective Bridge Temperature and Movement

Fluctuation in effective bridge temperature causes expansion and contraction of the structure. Proper temperature expansion provisions are essential in order to ensure that the structure will not be damaged by thermal movements. These movements, in turn, induce stresses in supporting elements such as columns or piers, and result in horizontal movement of the expansion joints and bearings. For more details, see Chapter 8 this manual.

B. Differential Temperature

Although time-dependent variations in the effective temperature have caused problems in both reinforced and prestressed concrete bridges, detrimental effects caused by temperature differential within the superstructure have occurred only in prestressed bridges. Therefore, computation of stresses and movements resulting from the vertical temperature gradients is not included in this chapter. For more details, see AASHTO Guide Specifications, Thermal Effects on Concrete Bridge Superstructures dated 1989.

5.3.7 Hinges

Hinges are one of the weakest links of box girder bridges subject to earthquake forces and it is desirable to eliminate hinges or reduce the number of hinges. For more details on the design of hinges, see Section 5.4.

Designer should provide access space or pockets for maintenance and inspection of bearings.

Allowance should be provided to remove and replace the bearings. Lift point locations, maximum lift permitted, jack capacity, and number of jacks should be shown in the hinge plan details.

5.3.8 Utility Openings


A. Confined Spaces

A confined space is any place having a limited means of exit which is subject to the accumulation of toxic or flammable contaminants or an oxygen deficient environment. Confined spaces include but are not limited to pontoons, box girder bridges, storage tanks, ventilation or exhaust ducts, utility vaults, tunnels, pipelines, and open-topped spaces more than 4 feet in depth such as pits, tubes, vaults, and vessels. The designer should provide for the following:


- A sign with “Confined Space Authorized Personnel Only.”
- In the “Special Provisions Check List,” alert and/or indicate that a special provision might be needed to cover confined spaces.

B. Drain Holes


Drain holes should be placed in the bottom slab at the low point of each cell to drain curing water during construction and any rain water that leaks through the deck slab. Additional drains shall be provided as a safeguard against water accumulation in the cell (especially when waterlines are carried by the bridge). In some instances, drainage through the bottom slab is difficult and other means shall be provided (i.e., cells over large piers and where a sloping exterior web intersects a vertical web). In this case, a horizontal drain should be provided through the vertical web. Figure 5-44 shows drainage details for the bottom slab of concrete box girder bridges with steel wire screen.



DRAIN HOLES SHOWN ON FRAMING PLAN



BOTTOM SLAB DRAIN HOLE DETAIL




WEB DRAIN HOLE DETAIL

Drain Hole Details

Figure 5-44


C. Access Hatch and Air Vent Holes

Access hatches with doors should be placed in the bottom slab if necessary to inspect utilities inside cells (i.e., waterline, conduits, E.Q. restrainers, etc.). Figure 5-45 and 5-46 shows Access hatch details and Air Vent details respectively. Air vents are required when access holes are used.



Access Hatch Details

*Figure 5-**45***




Air Vent Opening Detail
Figure 5-46

5.4 Hinges and Inverted T-Beam Pier Caps


Hinges and inverted T-beam pier caps require special design and detailing considerations. Continuous hinge shelves (both top and bottom projecting shelves) and continuous ledges of inverted T-beam pier caps, which support girders, is shown in Figure 5-47 respectively. In each case, vertical tensile forces (hanger tension) act at the intersection of the web and the horizontal hinge shelf or ledge. In the ledges of inverted T-beam pier caps, passage of live loads may also cause reversing torsional stresses which together with conventional longitudinal shear and bending produce complex stress distributions in the ledges[12, 13].

Figure 5-48 provide minimum shelf or ledge support lengths (N, L_1, and L_2) and provide positive longitudinal linkage (e.g., earthquake restrainers) in accordance with the current AASHTO LRFD Specifications for seismic design requirements. Design considerations for Beam Ledges, Inverted T0beam and Hinges is given in AASHTO LRFD Section 5.13.2-5.



Hinge and Inverted T-beam pier Cap

Figure 5-47



In-Span Hinge

Figure 5-48

5.5 Bridge Widenings

This section provides general guidance for the design of bridge widenings. Included are additions to the substructure and the superstructure of reinforced concrete box girder, flat slab, T-beam, and precast prestressed girder bridges. For additional information, see ACI Committee Report, Guide for Widening Highway Bridges[15].

5.5.1 Review of Existing Structures

A. General

Obtain the following documents from existing records for preliminary review, design, and plan preparation:

1. Reduced copy of "As-Built" contract plans from our microfilm records in Bridge Records, Office of Bridges and Structures.
2. Reduced copy of original contract plans and special provisions, which can be obtained from Engineering Records (Plans Vault), Records Control. These will not include the "As-Built" plans, since they are made prior to receiving the "As-Built" plans from the Project Engineer. Backup microfilm records are also maintained by Engineering Records (Plans Vault), Records Control, but the "As-Built" plans may not be current.
3. Check with the Bridge Preservation Unit for records of any unusual movements/ rotations and other structural information.
4. Original design calculations, which are stored in State Archives and can be retrieved by Bridge Records personnel.
5. Current field data on Supplemental Site Data Form (including current deck elevations at interface of widening and existing deck, as well as cross slopes), are obtained from District. Current field measurements of existing pier crossbeam locations are recommended so that new prestressed girders are not fabricated too short or too long. This is particularly important if piers have been constructed with different skews. This information may not be available in any existing plans, so field trips may be necessary to determine actual details.
6. Original and current Foundation Reports from the Materials Lab or from the Plans Vault.
7. Change Order files to the original bridge contract in Records Control Unit.

B. Original Contract Plans and Special Provisions

Location and size of reinforcement, member sizes and geometry, location of construction joints, details, allowable design soil pressure, and test hole data are given on the plans. Original contract plans can be more legible than the microfilm copies.

The special provisions may include pertinent information that is not covered on the plans or in the LRFD Specifications.

C. Original Calculations

The original calculations should be reviewed for any "special assumptions" or office criteria used in the original design. The actual stresses in the structural members, which will be affected by the widening, should be reviewed. This may affect the structure type selected for the widening.

D. Final Records

For major widening/renovation projects, the Final Records should be reviewed particularly for information about the existing foundations and piles. Sometimes the piles indicated on the original plans were omitted, revised, or required preboring. Final Records are available from Records Control or Bridge Records (Final Records on some older bridges may be in storage at the Materials Lab).

5.5.2 Analysis and Design Criteria

A. General

Each widening represents a unique situation and construction operations may vary between widening projects. The guidelines in this section are based on years of WSDOT design experience with bridge widenings.

1. Appearance

   The widening of a structure should be accomplished in such a manner that the existing structure does not look "added on to." When this is not possible, consideration should be given to enclosure walls, cover panels, paint, or other aesthetic treatments. Where possible and appropriate, the structure's appearance should be improved by the widening.

2. Materials

   Preferably, materials used in the construction of the widening shall have the same thermal and elastic properties as the materials used in the construction of the original structure.

3. Load Distribution and Construction Sequence

   The members of the widening should be proportioned to provide similar longitudinal and transverse load distribution characteristics as the existing structure. Normally this can be achieved by using the same cross sections and member lengths that were used in the existing structure.

   The construction sequence and degree of interaction between the widening and the existing structure, after completion, shall be fully considered in determining the distribution of the dead load for design of the widening and stress checks for the existing structure. The distribution of live load shall be in accordance with the AASHTO LRFD specifications. Where precast-prestressed girders are used to widen an existing cast-in-place concrete box girder or T-beam bridge, the live load distribution factor for interior girder(s) shall be per AASHTO LRFD Specifications.

   The construction sequence or stage construction should be clearly shown in the plans to avoid confusion and misinterpretation during construction. A typical construction sequence may involve placing the deck concrete, removing the falsework, placing the concrete for the closure strip, and placing the concrete for the traffic barrier. Indicate in the plans a suggested stage construction plan to avoid misinterpretation.

4. Specifications

   The design of the widening shall conform to the current AASHTO LRFD Specifications and the state of Washington's STD Specifications for Road, Bridge, and Municipal Construction.

   The method of design for the widening shall be by strength design even though the original design may have been by service load design.

5. Geometrical Constraints

   The overall appearance and geometrical dimensions of the superstructure and columns of the widening should be the same or as close as possible to those of the existing structure. This is to ensure that the widening will have the same appearance and similar structural stiffness as the original structure.

6. Strength of Concrete

   The allowable stresses shown in Table 5-15 are to be used. For concrete structures located in rural areas or where the volume of concrete is less than 30 cubic yards, use Class 4000 (f'_c = 4.0 ksi) and Grade 60 reinforcement. For projects located in urban areas and having a volume of concrete greater than 30 cubic yards, Class 5000 may be specified only if necessary to meet structural requirements and if facilities are available. Concrete with a greater strength may be used, if needed, with consultation and approval of the Bridge Design Engineer.

7. Overlay

   It should be established at the preliminary plan stage if an overlay is required as part of the widening.

8. Strength of the Existing Structure

   A review of the strength of the main members of the existing structure shall be made for construction conditions utilizing AASHTO LRFD Load Factors.

   A check of the existing main members after attachment of the widening shall be made for the final design loading condition.

   If the existing structural elements do not have adequate strength, consult your supervisor or in the case of consultants, contact the Consultant Liaison Engineer for appropriate guidance.

   If significant demolition is required on the existing bridge, consideration should be given to requesting concrete strength testing for the existing bridge and including this information in the contract documents.

9. Special Considerations

   a. For structures that were originally designed for HS-20 loading, HL-93 shall be used to design the widening. For structures that were originally designed for less than HS-20, consideration should be given to replacing the structure instead of widening it.

   b. Where large cambers are expected, a longitudinal joint between the existing structure and the widening may be considered. Longitudinal joints, if used, should be located out of traveled lanes or beneath median barriers to eliminate potentially hazardous vehicle control problems.

   c. The WSDOT STD Specifications do not permit falsework to be supported from the existing structure unless the Plans and Specifications state otherwise. This requirement eliminates the transmission of vibration from the existing structure to the widening during construction. The existing structure may still be in service.

   d. For narrow widenings where the Plans and Specifications require that the falsework be supported from the original structure (e.g., there are no additional girders, columns, crossbeams, or closure strips), there should be no external rigid supports such as posts or falsework from the ground. Supports from the ground do not permit the widening to deflect with the existing structure when traffic is

on the existing structure. This causes the uncured concrete of the widening to crack where it joins the existing structure. Differential dead load deflection during construction should be given consideration.

e. Precast members may be used to widen existing cast-in-place structures. This method is useful when the horizontal or vertical clearances during construction are insufficient to build cast-in-place members.

f. The alignment for diaphragms for the widening shall generally coincide with the existing diaphragms.

g. When using battered piles, estimate the pile tip elevations and ensure that they will have ample clearance from all existing piles, utilities, or other obstructions. Also check that there is sufficient clearance between the existing structure and the pile driving equipment.

B. Seismic Design Criteria for Bridge Widenings

1. Adequacy of Existing Structure

Early in the project, determine whether earthquake loading poses any problems for the structural adequacy of the existing structure (e.g., original unwidened structure). The amount of reinforcement and structural detailing of older structures may not meet the current AASHTO LRFD seismic design requirements. It is important that these deficiencies be determined as soon as possible so that remedial/retrofitting measures can be evaluated. It should be noted that for some structures, because of deterioration and/or inadequate details, the widening may not be structurally or economically feasible. In this case, the Bridge Design Engineer should be consulted for possible structure replacement instead of proceeding with widening the structure.

2. Superstructure Widening Without Adding Substructure

No seismic analysis is necessary for this condition. Check the support shelf length required at all piers. Check the need for longitudinal earthquake restrainers and transverse earthquake stops.

3. Superstructure Widening by Adding Column(s) and Substructure

Use the AASHTO LRFD/BDM seismic design criteria with appropriate R factors to design and detail the new columns and footings for the maximum required capacity.

Analyze the widening and the existing structure as a combined unit.

If the existing structure is supported by single column piers, and is located in seismic zones 2, 3 or 4, the existing column should be retrofitted if it does not have adequate ductility to meet the current standards.

a. For existing bridges in Zone 2, 3, or 4 that are widened with additional columns and substructure, existing columns should be considered for retrofitting unless calculations or column details indicate that the existing columns have adequate ductility. Nonductile existing columns will likely not be able to carry vertical load if they experience the inelastic deflection that a new (ductile) column can tolerate.

b. Only the columns should be retrofitted. Retrofitting the foundations supporting existing columns is generally too expensive to consider for a widening project. Experience in past earthquakes in California has shown that bridges with columns (only) retrofitted have performed quite well.

c. Approval for retrofitting existing multiple column piers is subject to available funding and approval of the Bridge Design Engineer.

4. Other Criteria

   a. If recommended in the foundation report, the superstructure widening with new substructure shall also be checked for differential settlement between the existing structure and the new widened structure. All elements of the structure shall be analyzed and detailed to account for this differential settlement especially on spread footing foundations.

      Refer to Section 6.2.1.1.1 of the WSDOT Geotechnical Design Manual for further information on seismically-induced geologic hazards.

   b. Check support width requirements; if there is a need for earthquake restrainers on the existing structure as well as the widened portion, they shall be included in the widening design.

   c. The current AASHTO LRFD seismic design criteria may result in columns with more reinforcement and larger footings for the widened portion than those on the existing structure. If it is not possible to use larger footings because of limited space, an alternate design concept such as drilled shafts may be necessary.

   d. When modifications are made near or on the existing bridge, be careful to isolate any added potential stiffening elements (such as traffic barrier against columns).

   e. The relative stiffness of the new columns compared to the existing columns should be considered in the combined analysis. The typical column retrofit is steel jacketing with grouted annular space (between the existing column and the steel jacket).

   f. When strutted columns (horizontal strut between existing columns) are encountered, remove the strut and analyze the existing columns for the new unbraced length and retrofit, if necessary.

C. Substructure

1. Selection of Foundation

   a. The type of foundation to be used to support the widening should generally be the same as that of the existing structure unless otherwise recommended by the Geotechnical Engineer. The effects of possible differential settlement between the new and the existing foundations shall be considered.

   b. Consider present bridge site conditions when determining new foundation locations. The conditions include: overhead clearance for pile driving equipment, horizontal clearance requirements, working room, pile batters, channel changes, utility locations, existing embankments, and other similar conditions.

2. Scour and Drift

   Added piles and columns for widenings at water crossings may alter stream flow characteristics at the bridge site. This may result in pier scouring to a greater depth than experienced with the existing configuration. Added substructure elements may also increase the possibility of trapping drift. The Hydraulics Engineer should be consulted concerning potential problems related to scour and drift on all widenings at water crossings.

D. Superstructure

1. Camber

Accurate prediction of dead load deflection is more important for widenings than for new bridges, since it is essential that the deck grades match[12].

To obtain a smooth transition in transverse direction of the bridge deck, the camber of the girder adjacent to the existing structure shall be adjusted for the difference in camber between new and existing structure. A linear interpolation may be used to adjust the camber of the girders located away from the existing structure. The multipliers for estimating camber of new structure may be taken as shown in Table 5.3.5-1.

2. Closure Strip

Except for narrow deck slab widenings a closure strip is required for all cast-in-place widenings. The width shall be the minimum required to accommodate the necessary reinforcement and for form removal. Reinforcement, which extends through the closure strip shall be investigated. Shear shall be transferred across the closure strip by shear friction and/or shear keys.

All falsework supporting the widening shall be released and formwork supporting the closure strip shall be supported from the existing and newly widened structures prior to placing concrete in the closure strip. Because of deck slab cracking experienced in widened concrete decks, closure strips are required unless the mid-span dead load camber is ½ inch or less.

3. Stress Levels and Deflections in Existing Structures

Caution is necessary in determining the cumulative stress levels, deflections, and the need for shoring in existing structural members during rehabilitation projects.

For example, a T-beam bridge was originally constructed on falsework and the falsework was released after the slab concrete gained strength. As part of a major rehabilitation project, the bridge was closed to traffic and the entire slab was removed and replaced without shoring. Without the slab, the stems behave as rectangular sections with a reduced depth and width. The existing stem reinforcement was not originally designed to support the weight of the slab without shoring. After the new slab was placed, wide cracks from the bottom of the stem opened, indicating that the reinforcement was overstressed. This overstress resulted in a lower load rating for the newly rehabilitated bridge. This example shows the need to shore up the remaining T-beam stems prior to placing the new slab so that excessive deflections do not occur and overstress in the existing reinforcing steel is prevented.

It is necessary to understand how the original structure was constructed, how the rehabilitated structure is to be constructed, and the cumulative stress levels and deflections in the structure from the time of original construction through rehabilitation.

E. Stability of Widening

For relatively narrow box girder and T-beam widenings, symmetry about the vertical axis should be maintained because lateral loads are critical during construction. When symmetry is not possible, use pile cap connections, lateral connections, or special falsework. A minimum of two webs is generally recommended for box girder widenings. For T-beam widenings that require only one additional web, the web should be centered at the axis of symmetry of the slab. Often the width of the closure strip can be adjusted to accomplish this.

5.5.3 Removing Portions of the Existing Structure

Portions of the existing structure to be removed shall be clearly indicated on the plans. Where a clean break line is required, a ¾″ deep saw cut shall be specified for a slab with normal wear and a ½″ deep saw cut for worn roadway slabs. In no case, however, shall the saw blade cut or nick the main transverse top slab reinforcement. The special provisions shall state that care will be taken not to damage any reinforcement which is to be saved. Hydromilling is preferred where reinforcing bar cover is shallow and can effectively remove delaminated decks because of the good depth control it offers. When greater depths of slab are to be removed, special consideration should be given to securing exposed reinforcing bars to prevent undue vibration and subsequent fatigue cracks from occurring in the reinforcing bars.

The current General Special Provisions should be reviewed for other specific requirements on slab removal.

Removal of any portion of the main structural members should be held to a minimum. Careful consideration shall be given to the construction conditions, particularly when the removal affects the existing frame system. In extreme situations, preloading by jacking is acceptable to control stresses and deflections during the various stages of removal and construction. Removal of the main longitudinal slab reinforcement should be kept to a minimum. See "Slab Removal Detail" Figure 5-51 for the limiting case for the maximum allowable removal.

The plans should include a note that critical dimensions and elevations are to be verified in the field prior to the fabrication of precast units or expansion joint assemblies.

In cases where an existing sidewalk is to be removed but the supporting slab under the sidewalk is to be retained, district personnel should check the feasibility of removing the sidewalk. Prior to design, district personnel should make recommendations on acceptable removal methods and required construction equipment. The plans and specifications should then be prepared to accommodate these recommendations. This will ensure the constructibility of plan details and the adequacy of the specifications.

5.5.4 Attachment of Widening to Existing Structure

A. General

1. Lap and Mechanical Splices

   To attach a widening to an existing structure, the first choice is to utilize existing reinforcing bars by splicing new bars to existing. Lap splices or mechanical splices should be used. However, it may not always be possible to splice to existing reinforcing bars and spacing limitations may make it difficult to use mechanical splices.

2. Welding Reinforcement

   Existing reinforcing steel may not be readily weldable. Mechanical splices should be used wherever possible. If welding is the only feasible means, the chemistry of the reinforcing steel must be analyzed and acceptable welding procedures developed.

3. Drilling Into Existing Structure

   It may be necessary to drill holes and set dowels in epoxy resin in order to attach the widening to the existing structure.

   When drilling into heavily reinforced areas, chipping should be specified to expose the main reinforcing bars. If it is necessary to drill through reinforcing bars or if the holes are within 4 inches of an existing concrete edge, core drilling should be specified. Core drilled holes shall be roughened before resin is applied. If this is not done, a dried

residue, which acts as a bond breaker and reduces the load capacity of the dowel, will remain. Generally, the drilled holes are $^1/_8$ inch in diameter larger than the dowel diameter for #5 and smaller dowels and ¼ inch in diameter larger than the dowel diameter for #6 and larger dowels.

In special applications requiring drilled holes greater than 1½ inch diameter or deeper than 2 feet, core drilling shall be specified. These holes should also be intentionally roughened prior to applying epoxy resin.

Core drilled holes should have a minimum clearance of 3 inches from the edge of the concrete and 1-inch clearance from existing reinforcing bars in the existing structure. These clearances should be noted in the plans.

4. Dowelling Reinforcing Bars Into the Existing Structure

   a. Dowel bars shall be set with an approved epoxy resin. The existing structural element shall be checked for its adequacy to transmit the load transferred to it from the dowel bars.

   b. Dowel spacing and edge distance affect the allowable tensile dowel loads. Allowable tensile loads, dowel bar embedment, and drilled hole sizes for reinforcing bars (Grade 60) used as dowels and set with an approved epoxy resin are shown in Table 5-49. These values are based on an edge clearance greater than 3 inch, a dowel spacing greater than 6 inch, and are shown for both uncoated and epoxy coated dowels. Table 5-50 lists dowel embedment lengths when the dowel spacing is less than 6 inch. Note that in Table 5-50 the edge clearance is equal to or greater than 3 inch, because this is the minimum edge clearance for a drilled hole from a concrete edge.

      If it is not possible to obtain these embedment, such as for traffic railing dowels into existing deck slabs, the allowable load on the dowel shall be reduced by the ratio of the actual embedment divided by the required embedment.

   c. The embedment shown in Table 5-49 and -2 are based on dowels embedded in concrete with f'_c=4,000 psi.

Bar Size	Allowable Design Tensile Load, T*	Drill Hole Size	Required Embedment, Le**	
			Uncoated	Epoxy Coated
	(kips)	(in)	(in)	(in)
4	12.0	5/8	7	8
5	18.6	¾	8	9
6	26.4	1	9	10
7	36.0	1 1/8	11	12
8	47.4	1¼	13	14.5
9	60.0	1 3/8	16	17½
10	73.6	1½	20	22
11	89.0	1 5/8	25	28

*Allowable Tensile Load (Strength Design) = $(f_y)(A_S)$.

**Based on removed cover. In cases where concrete cover is not removed, the designer should add the cover thickness to the required embedment.

Allowable Tensile Load for Dowels Set With Epoxy Resin f'c=4,000 psi, Grade 60 Reinforcing Bars, Edge Clearance ≥ 3 in., and Spacing ≥ 6 in.

Table 5-49

Bar Size	Allowable Design Tensile Load, T*	Drill Hole Size	Required Embedment, Le**	
			Uncoated	Epoxy Coated
	(kips)	(in)	(in)	(in)
4	12.0	5/8	9½	10½
5	18.6	¾	10½	11½
6	26.4	1	11½	12½
7	36.0	1 1/8	13½	15
8	47.4	1¼	16½	18
9	60.0	1 3/8	20	22
10	73.6	1½	24	27
11	89.0	1 5/8	30	33

*Allowable Tensile Load (Strength Design) = $(f_y)(A_S)$.
**Based on removed cover. In cases where concrete cover is not removed, the designer should add the cover thickness to the required embedment.

Allowable Tensile Load for Dowels Set With Epoxy Resin f'c=4,000 psi, Grade 60 Reinforcing Bars, Edge Clearance ≥ 3 in., and Spacing < 6 in.

Table 5-50

5. Shear Transfer Across a Dowelled Joint

   Shear should be carried across the joint by shear friction on an intentionally roughened surface instead of depending on the dowels to transmit the shear force. Chipping shear keys in the existing concrete can also be used to transfer shear across a dowelled joint, but is expensive.

6. Preparation of Existing Surfaces for Concreting

   See "Removing Portions of Existing Structure" in the General Special Provisions for requirements. Unsound, damaged, dirty, porous, or otherwise undesirable old concrete should be removed, and the remaining concrete surface should be clean, free of laitance, and intentionally roughened to ensure proper bond between the old and new concrete surfaces.

7. Control of Shrinkage and Deflection on Connecting Reinforcement

   Dowels that are fixed in the existing structure may be subject to shear as a result of longitudinal shrinkage and vertical deflection when the falsework is removed. These shear forces may result in a reduced tensile capacity of the connection. When connecting the transverse reinforcing bars across the closure strip is unavoidable, the interaction between shear and tension in the dowel or reinforcing bar should be checked. The use of wire rope or sleeved reinforcement may be acceptable, subject to approval by your supervisor.

   Where possible, transverse reinforcing bars should be spliced to the existing reinforcing bars in a blocked-out area which can be included in the closure strip. Nominal, shear friction, temperature and shrinkage, and distribution reinforcing bars should be bent into the closure strip.

   Rock bolts may be used to transfer connection loads deep into the existing structure, subject to the approval of your supervisor.

8. Post-Tensioning

   Post-tensioning of existing crossbeams may be utilized to increase the moment capacity and to eliminate the need for additional substructure. Generally, an existing crossbeam can be core drilled for post-tensioning if it is less than 30 feet long. The amount of drift in the holes alignment may be approximately 1 inch in 20 feet. For crossbeams longer than 30 feet, external post-tensioning should be considered.

   For an example of this application, refer to Contract 3846, Bellevue Transit Access — Stage 1.


B. Connection Details

The details on the following sheets are samples of details which have been used for widening bridges. They are informational and are not intended to restrict the designer's judgment.

1. Box Girder Bridges


   Figures 5-51 through 5-56 show typical details for widening box girder bridges.

   Welding or mechanical butt splice are preferred over dowelling for the main reinforcement in crossbeams and columns when it can be done in the horizontal or flat position. It shall be allowed only when the bars to be welded are free from restraint at one end during the welding process. If bars are to be dowelled, provide a sufficient embedment depth for moment connection bars into existing structure that will provide the required moment capacity in the existing structure. See Table 5-49 or 5-50.



Slab Removal Detail

*Figure 5-**51***




STAY IN PLACE FORM DETAIL FOR BOX GIRDER STAGED CONSTRUCTION OR WIDENING

* STAY IN PLACE FORMS SHALL BE SOLID GALVANIZED SHEET METAL. FORMS MUST BE VERTICALLY BRACED AS NECCESSARY TO PREVENT BOWING DURING CONCRETE PLACEMENT. TIMBER BRACING MUST BE REMOVED. IF STEEL WALES OR TIES ARE USED, THEY MAY BE LEFT IN PLACE. THE CONTRACTOR SHALL SUBMIT DESIGN CALCULATIONS IN ACCORDANCE WITH STANDARD SPECIFICATIONS 6-02.3(16) AND 6-02.3(17).


Box Girder Section in Span

Figure 5-52




Box Girder Section Through X-Beam

Figure 5-53



SEE "BOX GIRDER - SECTION IN SPAN" FOR ADDITIONAL DETAILS.


Box Girder Section in Span at Diaphragm Alternate I
*Figure 5-**54***



* IF LAP SPLICE EXCEEDS 2'-0", INCREASE WIDTH OF CLOSURE STRIP TO ACCOMMODATE INCREASED LAP SPLICE.

Box Girder Section in Span at Diaphragm Alternate II

Figure 5-55



Narrow Box Girder Widening Details


Figure 5-56

2. Flat Slab Bridges

It is not necessary to remove any portion of the existing slab to expose the existing transverse reinforcing bars for splicing purposes, because the transverse slab reinforcement is only distribution reinforcement. The transverse slab reinforcement for the widening may be dowelled directly into the existing structure without meeting the normal splice requirements.

For the moment connection details, see Figure 5-57 for "Flat Slab — Section through X-Beam."

Note: Falsework shall be maintained under pier crossbeams until closure pour is made and cured for 10 days.




Flat Slab Section through Cross Beam

Figure 5-57

3. T-Beam Bridges

Use details similar to those for box girder bridges for crossbeam connections. See Figure 5-58 for slab connection detail.




T-Beam — Section in Span

Figure 5-58

4. Prestress Concrete Girder Bridges

Use details similar to those for box girder bridges for crossbeam moment connections and use details similar to those in Figure 5-59 for connecting to the slab.



Prestressed Girder — Section in Span


Figure 5-59

5.5.5 Expansion Joints


The designer should determine if existing expansion joints can be eliminated. It will be necessary to determine what modifications to the structure are required to provide an adequate functional system when existing joints are eliminated.

For expansion joint design, see Section 8.4.1 “Expansion Joints.” Very often on widening projects it is necessary to chip out the existing concrete deck and rebuild the joint. Figures 5-60 and 5-61 show details for rebuilding joint openings for compression seal expansion joints.

If a widening project includes an overlay, the expansion joint may have to be raised, modified or replaced. See the Joint Specialist for plan details that are currently being used to modify or retrofit existing expansion joints.



Expansion Joint Detail Shown for Compression Seal —
Existing Reinforcing Steel Saved



Expansion Joint Detail shown for compression seal
with new reinforcing steel added

Figure 5-61

5.5.6 Possible Future Widening for Current Designs

For current projects that include sidewalks (and where it is anticipated that the structure may be modified or widened in the future), provide a smooth rather than a rough construction joint between the sidewalk and the slab. This will normally pertain to flat slab bridges or where the sidewalk width exceeds the slab cantilever overhang.

5.5.7 Bridge Widening Falsework

For widenings which do not have additional girders, columns, crossbeams, or closure pours, falsework should be supported by the existing bridge. There should be an external support from the ground. The reason is that the ground support will not allow the widening to deflect the existing bridge when traffic is on the bridge. This will cause the "green" concrete to crack where it joins the existing bridge. Designer should contact the bridge construction support unit regarding falsework associated with widenings.

5.5.8 Existing Bridge Widenings

Appendix B lists bridge widenings projects that may be used as design aids for the designers. These should not be construed as the only acceptable methods of widening; there is no substitute for the designer's creativity or ingenuity in solving the challenges posed by bridge widenings.

5.6 Precast Prestressed Girder Superstructures

The precast prestressed girder bridge is an economical and rapid type of bridge construction and often preferred for WSDOT bridges. This section discusses the essential of design, detailing, fabrication, and handling of precast prestressed girder bridges.

Precast sections are generally fabricated in plant or somewhere near the construction site and then erected. Precasting permits better material quality control and is often more economical than cast-in-place concrete.

Pre-tensioning is accomplished by stressing high strength steel strands to a predetermined tension and then placing concrete around the strands, while the stress is maintained. After the concrete has hardened, the strands are released and the concrete, which has become bonded to the tendon, is prestressed as a result of the strands attempting to relax to their original length. The strand stress is maintained during placing and curing of the concrete by anchoring the ends of strands to abutments that may be as much as 500 feet apart. The abutments and appurtenances used in the prestressing procedure are referred to as a pre-tensioning bed or bench.

5.6.1 WSDOT Standard Prestressed Girders

Washington State Standard girders were adopted in the mid-1950s. These girder shapes proved to be very efficient due to their thin webs and small flange fillets. These are still the most efficient shapes available and variations of these girders have been adopted by other states. The original series was graduated in 10-foot increments from 30 feet to 100 feet.

In 1990, revisions were made to the prestressed concrete girder standards incorporating the results of the research done at Washington State University on girders without end blocks. The new standards incorporate three major changes. They have a thicker web, the end blocks are eliminated, and have increased distance between strands. The new standard designations are W74G, W58G, W50G, W42G, and deck bulb tee standards W53DG and W35DG. The numbers refer to the depth of the section.

In 1999, deeper girders, commonly called “Supergirders” were added to the WSDOT prestressed concrete girder standards. These new supergirders may be pretensioned or post-tensioned. The pretensioned standards are designated as WF74G, W83G and W95G and the post-tensioned standards are designated as WF74PIG, W83PTG and W95PTG.

In 2004 WF42G, WF50G, WF58G, W32BTG, W38TG and W62BTG were added to WSDOT prestressed girder standards. In 2004 Pretensioned trapezoidal tub girders were also added to WSDOT Standard girders. The standard tub girders are 4’-0”, 5’-0” and 6’-0” bottom Flange width and 4’-6”, 5’6” and 6’-6” deep. A Sub Flange could be added to tub girders to improve Structural efficiency and to accommodate placement of stay-in-place precast deck panels.

All WSDOT prestressed girders are high performance high strength concrete girders. They generally rely on high strength concrete to be effective for the spans expected as a single piece. Maximum girder length is based on a single piece weight not to exceed 200 kips. The approximate range of maximum span lengths for practical minimum and maximum girder spacing are as shown in Table 5.6.1-1.

Standard drawings for WSDOT prestressed girders are shown in Appendix A. Table 5.6.1-2 shows the list of WSDOT prestressed girders.

Type	Depth (in)	Area (in^2)	I_z (in^4)	Y_b (in)	Wt (k/ft)	Girder Spacing ft	Max. Span Capability (ft)	Max. Length (200 kips Limit) (ft)
W42G	42.00	381.3	77467	18.67	0.424	6.0	85	-
W50G	50.00	526.5	165462	22.77	0.585	6.0	110	-
W58G	58.00	604.5	265374	27.96	0.672	6.0	125	-
W74G	73.50	747.7	547533	38.03	0.831	6.0	150	-
WF42G	41.38	725.3	177505	20.05	0.806	6.0	115	-
WF50G	49.26	773.5	273110	23.78	0.859	6.0	130	-
WF58G	57.13	821.7	392639	27.53	0.913	6.0	145	-
WF74G	72.88	918.2	709492	35.10	1.020	6.0	175	-
W83G	82.62	977.9	961875	39.81	1.087	6.0	165	184
W95G	94.49	1050.7	1332264	45.58	1.167	6.0	160	171
W32BTG	32.00	538.0	74039	17.88	0.598	6.0	75	-
W38BTG	38.00	574.0	114540	21.08	0.638	6.0	90	-
W65BTG	62.00	718.0	385995	33.68	0.798	6.0	130	-
U54G4	54.00	1038.8	292423	20.97	1.154	8.0	130	-
U54G5	54.00	1110.8	314382	19.81	1.234	9.0	130	-
U54G6	54.00	1254.8	341728	18.16	1.394	10.0	120	-
U66G4	66.00	1208.5	516677	26.45	1.343	8.0	155	148
U66G5	66.00	1280.5	554262	25.13	1.423	9.0	150	140
U66G6	66.00	1424.5	605412	23.15	1.583	10.0	145	126
U78G4	78.00	1378.2	827453	32.06	1.531	8.0	170	130
U78G5	78.00	1450.2	885451	30.62	1.611	9.0	170	124
U78G6	78.00	1594.2	969347	28.35	1.771	10.0	165	112
UF60G4	60.00	1207.7	483298	26.03	1.342	9.0	150	149
UF60G5	60.00	1279.7	519561	24.74	1.422	10.0	150	140
UF60G6	60.00	1423.7	568717	22.79	1.582	11.0	135	126
UF72G4	72.00	1377.4	787605	31.69	1.530	9.0	165	130
UF72G5	72.00	1449.4	844135	30.26	1.610	10.0	170	124
UF72G6	72.00	1593.4	925720	28.03	1.770	13.0	160	113
UF84G4	84.00	1547.1	1190828	37.42	1.719	10.0	190	116
UF84G5	84.00	1619.1	1272553	35.89	1.799	11.0	185	111
UF84G6	84.00	1763.1	1395939	33.41	1.959	16.0	170	102

Section Properties of WSDOT Standard Precast Pretensioned Girders
Table 5-62

Standard Drawing	Drawing Number
I-Girder Sections	5.6-A1.1
Wide Flange Girder Sections	5.6-A1.2
Bulb-Tee Girder Sections	5.6-A1.3
Wide Flange Bulb-Tee Girder Section	5.6-A1.4
Trapezoidal Tub Girder Sections	5.6-A1.5
Trapezoidal Tub Girder Sections with Flange	5.6-A1.6
Decked Bulb-Tee Girder Sections	5.6-A1.7
Precast Prestressed Slab Sections	5.6-A1.8
Double-Tee and Ribbed Decked Girder Sections	5.6-A1.9
Spliced I-Girder Sections	5.6-A1.10
Spliced Trapezoidal Tub Girder Sections	5.6-A1.11
Prestressed Girder Construction Sequence	5.6-A2.1 through 3
W42G	5.6-A3.1 through 10
W50G	5.6-A4.1 through 9
W58G	5.6-A5.1 through 10
W74G	5.6-A6.1 through 10
WF42G	5.6-A7.1 through 3
WF50G	5.6-A8.1 through 3
WF58G	5.6-A9.1 through 3
WF74G	5.6-A10.1 through 11
W83G	5.6-A11.1 through 10
W95G	5.6-A12.1 through 10
W32BTG	5.6-A13.1 through 3
W38BTG	5.6-A14.1 through 3
W62BTG	5.6-A15.1 through 3
Trapezoidal Tub Girders without Top Flange	5.6-A16.1 through 6
Trapezoidal Tub Girders with Top Flange	5.6-A17.1 through 7
Stay-in-place Deck Panel	5.6-A18.1
Precast Prestressed 1’-0” Solid Slabs	5.6-A19.1 through 3
Precast Prestressed 1’-6” Voided Slabs	5.6-A20.1 through 3
Precast Prestressed 2’-2” Voided Slabs	5.6-A21.1 through 4
Precast Prestressed Ribbed Girders	5.6-A22.1 through 3
Precast Prestressed Double-Tee Girders	5.6-A23.1 through 2
W35DG Decked Bulb-Tee	5.6-A24.1 through 3
W41DG Decked Bulb-Tee	5.6-A25.1 through 3
W53DG Decked Bulb-Tee	5.6-A26.1 through 3
W65DG Decked Bulb-Tee	5.6-A27.1 through 4
WF74PTG Spliced I-Girder	5.9-A1.1 through 5
WF83PTG Spliced I-Girder	5.9-A2.1 through 5
WF95PTG Spliced I-Girder	5.9-A3.1 through 5
Spliced Trapezoidal Tub-Girder without Top Flange	5.9-A4.1 through 8
Spliced Trapezoidal Tub-Girder With Top Flange	5.9-A5.1 through 8

List of WSDOT Standard Drawings


Table 5-63

5.6.2 Criteria for Girder Design

The present WSDOT criteria is to design prestressed girder bridges as simple span for all simple span and continuous spans. Effects of creep and shrinkage are not considered. This is a somewhat conservative procedure, but it minimizes engineering time. For continuous structures consisting of a large number of girders, a more exact analysis could be used, as directed by the design supervisor. Additional comments concerning special problems in design of continuous bridges are added below. The design criteria for prestressed girders is summarized in Table 5-14.


A. Support Conditions

The prestressed girders are assumed to be supported on rigid permanent simple supports. These supports can be either bearing seats or elastomeric pads. The design span length is the distance center to center of bearings for simple spans. For continuous spans erected on falsework (raised crossbeam), the effective point of support for girder design is assumed to be the face of the crossbeam. For continuous spans on crossbeams (dropped or semi-dropped crossbeam), the design span length is usually the distance center to center of temporary bearings as shown in Figure 5-64.



Typical Prestressed Girder Span

Figure 5-64



Typical Section for Computation of Composite Section Properties

Figure 5-65

B. Composite Action

1. General

   The sequence of construction and loading is extremely important in the design of prestressed girders. The composite section has a much larger capacity than the basic girder section but it cannot take loads until the slab has obtained adequate strength. Assumptions used in computing composite section properties are shown in Figure 5-65.

2. Load Application

   The following sequence and method of applying loads is used in girder analysis:

   a. Girder Dead Load is applied to the girder section.

   b. Diaphragm Dead Load is applied to the girder section.

   c. Slab Dead Load is applied to the girder section.

   d. Barrier, Overlay Dead Load, and Live Load are applied to the composite section.

      Dead load of one traffic barrier is divided among a maximum of three girders and this uniform load is applied to the composite section. The dead load of any overlay and live load plus impact is applied to the composite section.

3. Composite Section Properties

   Minimum deck slab thickness is specified as 7 ½ inches by office practice, but may be thicker if girder spacing dictates. This slab forms the top flange of the composite girder in prestressed girder bridge construction. The properties of this slab-girder composite section are affected by specification and by physical considerations.

a. Flange Width

The effective width of slab on each side of the girder centerline which can be considered to act as a compressive flange shall not exceed any of the following:

1. One-eighth of the span length.
2. Six times the thickness of slab plus one-fourth of the girder flange width.
3. One-half the distance to the next girder.
4. The actual distance to the edge of slab.

For effective tension flange widths, see AASHTO LRFD Specifications Section 5.7.3.4.

b. Flange Position

For purposes of calculating composite section properties, the bottom of the slab shall be assumed to be directly on the top of the girder. This assumption may prove to be true at center of span when excess girder camber occurs.

For dimensioning the plans, an increased dimension from top of girder to top of slab is used at centerline of bearing. This is called the "A" dimension. This dimension accounts for the effects of girder camber, vertical curve, slab cross slope, etc. See Appendix B for method of computing.

c. Flange Thickness

For purposes of computing composite section properties, the slab thickness shall be reduced by ½ inch to account for wearing. Where it is known that a bridge will have an asphalt overlay applied prior to traffic being allowed on the bridge, the full slab thickness can be used as effective slab thickness. The effective slab width shall be reduced by the ratio E_s/E_g. The effective modulus of composite section is then E_g.

d. Section Dead Load

The slab dead load to be applied to the girder shall be based on full thickness plus any overhang. The full effective pad ("A"-t) weight shall be added to that load. This assumed pad weight is applied over the full length of the girder.

C. Design Procedure

1. General


The WSDOT Prestressed Girder Design computer program PGSuper uses a trial and error method to arrive at solution for stress requirement and is the preferred method for final design of length and spacing. Some publications suggest various direct means for determining stress and position, but the procedures are generally quite complex.

2. Stress Conditions

The stress limits as described in Table 5-15 must be met for prestressed girder. One or more of the conditions described below may govern design. Each condition is the result of the summation of stresses with each load acting on its appropriate section (such as girder only, composite section). Precast girders shall also be checked during lifting, transportation, and erection stages by the designer to assure that girder delivery is feasible. Impact during the lifting stage shall be 0 percent and during transportation shall be 20 percent of the dead load of the girder. Impact shall be applied either upward or downward to produce maximum stresses.

D. Basic Assumptions

The following basic assumptions are used in the design of these standard girders. Figure 5-64 illustrates some of the factors which are constant in the WSDOT Prestressed Girder Design computer program, PGSuper. Figure 5-65 shows variations from those assumptions for a typical backwall design. Strand location at end and midspan of typical prestressed girder is shown in Figure 5-65b. Appendix A shows the standard strand positions in these girders.






Figure 5-65B

E. Girder End Types


There are four end types shown on the girder sheets. Due to the extreme depth of the W83G and W95G girders, and possible end of girder tilt at the piers for profile grades, the designer will need to pay particular attention to details to assure the girders will fit and perform as intended. The four end types are identified with pertinent detailing dimensions as follows:

1. End Type A

   End Type A as shown in Figure 5-66 is for cantilever end piers with an end diaphragm cast on the end of the girders. End Type A has a recess at the bottom of the girder near the end for an elastomeric bearing pad. The maximum bearing pad size expected for wide Flange I-girders is 18 inches long x 35 inches wide. The recess at the centerline of bearing is ¾ inch deep to accommodate an elastomeric pad length of 18 inches. This recess is to be used for profile grades up to and including 4 percent. The recess is to be replaced by an embedded steel plate flush with the bottom of the girder for grades over 4 percent. A tapered bearing plate, with stops at the edges to contain the elastomeric pad, can be welded or bolted to the embedded plate to provide a level bearing surface.

   Reinforcing bars and pretensioned strands project from the end of the girder. The designer shall assure that these bars and strands fit into the end diaphragm. Embedment of the girder end into the end diaphragm shall be a minimum of 3 inches and a maximum of 6 inches. For girder ends where the tilt would exceed 6 inches of embedment, the girder ends shall be tilted to attain a plumb surface when the girder is erected to the profile grade. Embedment into the end wall shall be 3 inches.

   The gap between the end diaphragm and the stem wall shall be a minimum of 2½ inches or ½ inch greater than required for longitudinal bridge movement.




End Type A (End Diaphragm on Girder)

Figure 5-66

2. End Type B

   End Type B as shown in Figure 5-67 is for "L" type abutments. End Type B also has a recess at the bottom of the girder for an elastomeric bearing pad. Notes regarding the bearing recess on End Type A also apply to End Type B. End Type B is the only end type that does not have reinforcing or strand projecting from the girder end.

   Note that the centerline of the bearing is not coincident with the centerline of the diaphragm. For girders on a grade, dimensions for each bearing, P1 and P2, from the ends of the girder will be different. Typically the centerline of bearing will be 1′–3″ minimum from the end of the girder to fit the bearing and provide adequate edge distance. The designer may want to locate the diaphragm such that it is equal distance from the centerline of the bearing, and the centerline of the bearing is equal distance from the face of the back wall of both abutments. This should create consistency in dimensions and make it easier to calculate girder lengths.



End Type B (L-Shape End Pier)
Figure 5-67

3. End Type C

   End Type C as shown in Figure 5-68 is for continuous spans and an intermediate hinge diaphragm at an intermediate pier. There is no bearing recess and the girder is temporarily supported on oak bunking blocks. This detail is generally used only in low seismic areas. This end type is generally used for bridges east of the Cascade Mountains.

   The designer shall check the edge distance and provide a dimension that prevents edge failure, or spalling, at the top corner of the supporting cross beam for load from the oak block including dead loads from girder, slab, and construction loads.


   Notes to Designer for Prestressed Girders Intermediate Hinge Diaphragms

   a. All girders in each bridge shall be of the same depth.

   b. Design girders as simple span (do not deduct negative moments from maximum simple beam positive moments).

   c. Provide reinforcement for negative moments at intermediate piers in the deck due to live loads and superimposed dead loads from traffic barrier, pedestrian walkway, utilities, etc.

   d. Check hinge bars size and minimum embedment in crossbeam.




End Type C (Intermediate Hinge Diaphragm)

Figure 5-68

4. End Type D

   End Type D as shown in Figure 5-69 is for continuous spans fully fixed to columns at intermediate piers. There is no bearing recess and the girder is temporarily supported on oak bunking blocks.

   The designer shall check the edge distance and provide a dimension that prevents edge failure, or spalling, at the top corner of the supporting cross beam for load from the oak block including dead loads from girder, slab, and construction loads.



End Type D
Figure 5-69

F. Minimum Crossbeam Width

In order to have room for placing oak blocks with required clearances on cross-beams, the cross-beams must be designed with a minimum width of 5′−0″ for W95G and W83G, WF74G, W74G, and 4′−6″ for all other girders. Designer is to check edge distance of oak blocks to top outside corner of cross-beam for reaction from girder weight + diaphragms + (20 psf) construction load. Adjust minimum width of cross-beam as necessary to prevent corner support failure.

5.6.3 Fabrication and Handling

A. Shop Plans

Fabricators of prestressed girders are required to submit shop plans which show specific details for each girder that they construct. These shop plans are checked and approved by the Project Engineer's office for conformance with the Contract Plans and specifications.

B. Special Problems for Fabricators

1. Strand Tensioning

The method selected for strand tensioning may affect the design of the girders. The strand arrangements shown in the office standard plans and included in the Prestressed Girder Design computer program are satisfactory for tensioning methods used by fabricators in this state. Harped strands are normally tensioned by pulling them as straight strands to a partial tension. The strands are then deflected vertically

as necessary to give the required harping angle and strand stress. In order to avoid overtensioning the harped strands by this procedure, the slope of the strands is limited to a maximum of 6:1 for 0.5″ ϕ strands and 8:1 for 0.6″ ϕ strands. The straight strands are tensioned by straight jacking.

2. Hold Down Forces

Forces on the hold-down units are developed as the harped strands are raised. The hold-down device provided by the fabricator must be able to hold the vertical component of the harping forces. Normally a two or more hold-down unit is required. Standard commercial hold-down units have been preapproved for use with particular strand groups.

3. Numbers of Strands

Since the prestressing beds used by the girder fabricators can carry several girders in a line, it is desirable that girders have the same number of strands where practical. This allows several girders to be set up and cast at one time and saves both time and strand material.

C. Handling and Hauling of Long Prestressed Girders

1. General

The designer shall specify the lifting device locations and the corresponding concrete transfer strength that provides an adequate factor of safety for lateral stability. The calculations shall conform to Article 5.2.9 of the PCI Design Handbook, Precast and Prestressed Concrete, Fifth Edition 17, or other approved methods. Other references 5, 6, 18, 19, 20 provide the derivation of the theory and design examples. Temporary top strands may be used to improve the stability of the girder during handling, and to reduce the required concrete transfer strength.

Considerations for handling and shipping long prestressed girders relate primarily to weight, length, height, and lateral stability. The effect of each variable differs considerably depending on where the handling is taking place: in the plant, on the road, or at the jobsite.

2. In-Plant Handling

The primary considerations for in-plant handling are weight and lateral stability. The maximum weight that can be handled by precasting plants in the Pacific Northwest is 200 kips. Pretensioning lines are normally long enough so that the weight of a girder governs capacity, rather than its length. Headroom is also not generally a concern for the deeper sections.

Lateral stability can be a concern when handling long, slender girders. When the girder forms are stripped from the girder, the prestressing level is higher and the concrete strength is lower than at any other point in the life of the member.

The WSDOT prestressed girder sections are relatively wide and stiff about their weak axes and, as a result, exhibit good stability, even at their longer pretentioned lengths. The simplest method of improving stability is to move the lifting devices away from the ends. This invariably increases the required concrete release strength, because decreasing the distance between lifting devices increases the concrete stresses at the harp point. Stresses at the support may also govern, depending on the exit location of the harped strands.

Alternatively, the girder sections may be braced to provide adequate stability. Temporary prestressing in the top flange can also be used to provide a larger factor of safety against cracking.

Other types of bracing have also been used successfully for many years. These systems are generally based on experience rather than theory. Other methods of improving lateral stability, such as raising the roll axis of the girder, are also an option.

For stability analysis of prestressed girder during in-plant handling in absence of more accurate information, the following parameters shall be used:

1. Height of pick point above top of girder = 0.0 in
2. Lifting loop or lifting bars placement tolerance = 0.25 in
3. Maximum girder sweep tolerance = 0.00052 in/in

3. Pick Up Points

The office standard plans show pick-up points for the girders. These points are critical since the girder is in its most highly stressed condition just after strand release. In some cases, fabricators may request to move the pick-up points toward the center of the girder. The request must be reviewed carefully since a decrease in girder dead load moment near centerline span may cause overstressing of the girder. Similarly, the girders must never be supported at any point other than the centerline of bearing during storage. The girders are also very sensitive to lateral loads and accordingly must be stored in a true vertical position.

4. Girder Lateral Bending

Long prestressed girders are very flexible and highly susceptible to lateral bending. Lateral bending failures are sudden, catastrophic, costly, pose a serious threat to workers and surroundings, and therefore must be guarded against. The office standard plans state that girders over certain given lengths must be laterally braced and that all girders must be handled carefully. It is the fabricator's responsibility to provide adequate bracing and provide suitable handling facilities. On unusually long girders, however, the designer should give this matter additional consideration. Published material on girder lateral bending should be consulted and used to assure the constructability of the girder design chosen 5,18,19,20.

D. Shipping

1. General

The designer shall assure that the girders can be reasonably delivered to the site as part of the preliminary design. The girder weight shall not exceed 200 kips. Vertical and horizontal clearances along the selected delivery route shall be verified.

The designer shall check the lateral stability of the girder during shipping 5,6,18,19,20. Temporary top strands shall be used to provide a minimum factor of safety against cracking of 1.0. In the absence of more accurate information on the properties of the truck, the following may be used:

1) the truck rotational spring stiffness K_q = 41,000 kip-in./radian,
2) the height of the roll center above the road h_r = 24 in.,
3) the height of the top of the truck support above the road = 6 ft,
4) the distance from the center of truck to the center of dual tires z_{max} = 36 in. and,
5) the maximum distance between truck supports = 130 ft.

The maximum superelevation along the selected route shall be used in the analysis.

The ability to ship deep girder sections can be influenced by a large number of variables, including mode of transportation, weight, length, height, and lateral stability. Some variables have more influence than others. As such, the feasibility of shipping

deep girders is strongly site-dependent. It is recommended that routes to the site be investigated during the preliminary design phase. To this end, on projects using long, heavy girders, WSDOT can place an advisory in their special provisions including shipping routes, estimated permit fees, escort vehicle requirements, Washington State Patrol requirements, and permit approval time.

2. Mode of Transportation

   Three modes of transportation are commonly used in the industry: truck, rail, and barge. In Washington State, an overwhelming percentage of girders are transported by truck, so discussion in subsequent sections will be confined to this mode. However, on specific projects, it may be appropriate to consider rail or barge transportation.

   Standard rail cars can usually accommodate larger loads than a standard truck. Rail cars range in capacity from approximately 120 to 200 kips. However, unless the rail system runs directly from the precasting plant to the jobsite, members must be trucked for at least some of the route, and weight may be restricted by the trucking limitations.

   For a project where a large number of girders are required, barge transportation is usually the most economical. Product weights and dimensions are generally not limited by barge delivery, but by the handling equipment on either end. In most cases, if a product can be made and handled in the plant, it can be shipped by barge. Of course, this applies only if both the plant and jobsite are fully accessible by barge.

3. Weight Limitations

   Girders shipped in some states have weighed in excess of 200 kips. The net weight limitation with trucking equipment currently available in Washington State is approximately 180 kips, if a reasonable delivery rate (number of pieces per day) is to be maintained. Product weights of up to 200 kips can be hauled with currently available equipment at a limited rate.

   Local carriers should be consulted on the feasibility of shipping heavy girders on specific projects. Some girders can be fabricated and shipped in two or more segments to reduce the weight and assembled and post-tensioned at the bridge site. However, it is more economical to fabricate and ship a single-piece pretensioned girder whenever possible.

4. Length Limitations

   Length limitations are generally governed by turning radii on the route to the jobsite. Potential problems can be circumvented by moving the support points closer together (away from the ends of the girder), or by selecting alternate routes. A rule of thumb of 130 feet between supports is commonly used. The support points can be moved away from the ends while still maintaining the concrete stresses within allowable limits. Length limitations are not expected to be the governing factor for most project locations.

5. Height Limitations

   The height of a deep girder section sitting on a jeep and steerable trailer is of concern when considering overhead obstructions on the route to the jobsite. The height of the support is approximately 6 feet above the roadway surface. When adding the depth of the girder, including camber, the overall height from the roadway surface to the top of concrete can rapidly approach 14 feet. Overhead obstructions along the route should be investigated for adequate clearance in the preliminary design phase. Obstructions without adequate clearance must be bypassed by selecting alternate routes.

Expectations are that, in some cases, overhead clearance will not accommodate the vertical stirrup projection on deeper WSDOT standard girder sections. Alternate stirrup configurations can be used to attain adequate clearance, depending on the route from the plant to the jobsite.

6. Lateral Stability During Shipping

Long, slender members can become unstable when supported near the ends. However, the stability of girders sitting on flexible supports is governed by the rotational stiffness of the support rather than the girder. Recommended factors of safety 1.0 against cracking, and 1.5 against failure (rollover of the truck) should be used.

The control against cracking the top flange is obtained by introducing the number of temporary top strands, jacked to the same load as the permanent strands, required to provide a factor of safety of 1.0. This variable depends on the combination of girder dead load, pre-stressing, and tension in the top flange induced by the girder tilt. The calculated tilt includes both the superelevation and its magnification based on the truck's rotational stiffness.

For stability analysis of prestressed girders during shipping, in absence of more accurate information, the following parameters shall be used:

a. Roll stiffness of truck/trailer = 40500 kip-in/rad

b. Height of girder bottom above roadway = 72 in

c. Height of truck roll center above road = 24 in

d. Center to center distance between truck tires = 72 in

e. Maximum expected roadway superelevation = 0.06

f. Maximum girder sweep tolerance = 0.001042 in/in

g. Support placement lateral tolerance = 1 in

h. Increase girder C.G. height for camber by 2%

E. Erection

A variety of methods are used to erect precast concrete girders, depending on the weight, length, available crane capacity, and site access. Lifting long girders during erection is not as critical as when they are stripped from the forms, particularly when the same lifting devices are used for both. However, if a separate set of erection devices are used, the girder should be checked for stresses and lateral stability. In addition, once the girder is set in place, the free span between supports is usually increased. Wind can also pose a problem. Consequently, when long girders are erected, they should immediately be braced at the ends. Generally, the temporary support of the girders is the contractor's responsibility.

F. Construction Sequence for Multi-Span Prestressed Girder Bridges

For multi-span prestressed girder bridges, the sequence and timing of the superstructure construction has a significant impact on the performance and durability of the bridge. In order to maximize the performance and durability, the "construction sequence" details shown on the attached sheets shall be followed for all new WSDOT multi-span prestressed girder bridges. Particular attention shall be paid to the timing of casting the lower portion of the pier diaphragms/crossbeams (30 days minimum after release of prestress) and the upper portion of the diaphragms/crossbeams (10 days minimum after placement of the roadway slab). The requirements apply to multi-span prestressed girder bridges with monolithic and hinge diaphragms/crossbeams.

5.6.4 Superstructure Optimization

A. Girder Selection

Cost of the girders is a major portion of the cost of prestressed girder bridges. Much care is therefore warranted in the selection of girders and in optimizing their position within the structure. The following general guidelines should be considered.

1. Girder Series Selection

All girders in a bridge will normally be of the same series. If vertical clearance is no problem, a larger girder series, utilizing fewer girder lines, may be a desirable solution. This must be balanced with considerations such as appearance. The relative girder series cost factors shown in Table 5-70 may be used as a guide for this decision:

Type	Depth (in)	Wt (k/ft)	Max. Span Capability (ft)	Relative Cost Factor
W42G	42.00	0.424	85	0.89
W50G	50.00	0.585	110	0.93
W58G	58.00	0.672	125	0.96
W74G	73.50	0.831	150	1.00*
WF42G	41.38	0.806	115	1.10
WF50G	49.26	0.859	130	1.15
WF58G	57.13	0.913	145	1.20
WF74G	72.88	1.020	175	1.25
W83G	82.62	1.087	165	1.30
W95G	94.49	1.167	160	1.40
WBT32G	32.00	0.598	75	0.80
WBT38G	38.00	0.638	90	0.90
WBT62G	62.00	0.798	130	1.00
U54G4	54.00	1.154	130	1.50
U54G5	54.00	1.234	130	1.60
U54G6	54.00	1.394	120	1.70
U66G4	66.00	1.343	155	1.80
U66G5	66.00	1.423	150	1.90
U66G6	66.00	1.583	145	2.00
U78G4	78.00	1.531	170	2.00
U78G5	78.00	1.611	170	2.10
U78G6	78.00	1.771	165	2.20
UF60G4	60.00	1.342	150	1.70
UF60G5	60.00	1.422	150	1.80
UF60G6	60.00	1.582	135	1.90
UF72G4	72.00	1.530	165	1.90
UF72G5	72.00	1.610	170	2.00
UF72G6	72.00	1.770	160	2.10
UF84G4	84.00	1.719	190	2.10
UF84G5	84.00	1.799	185	2.20
UF84G6	84.00	1.959	170	2.30

*W74G is used as basis for relative cost analysis

Approximate Prestressed Girder Cost Factor

Table 5-70

The wider spacing expected when using larger series girders may result in extra reinforcement and concrete but less forming cost. These items must also be considered.

2. Girder Concrete Strength

   Higher girder concrete strengths should be specified where that strength can be effectively used to reduce the number of girder lines. See Subsection 5.1.1A-1. When the bridge consists of a large number of spans, consideration should be given to using a more exact analysis than the usual design program in an attempt to reduce the number of girder lines. This analysis should take into account actual live load, creep, and shrinkage stresses in the girders.

3. Girder Spacing

   Consideration must be given to the slab cantilever length to determine the most economical girder spacing. This matter is discussed in Subsection 5.6.4B. The slab cantilever length should be made a maximum if a line of girders can be saved. The spacing of the interior girders must be considered at the same time. Once the positions of the exterior girders have been set, the positions and lengths of interior girders can be established. The following guidance is suggested.

   a. Straight Spans

      On straight constant width roadways, all girders should be parallel to bridge centerline and girder spacing should be equal.

   b. Tapered Spans

      On tapered roadways, the minimum number of girder lines should be determined as if all girder spaces were to be equally flared. As many girders as possible, within the limitations of girder capacity should be placed. Slab thickness may have to be increased in some locations in order to accomplish this.

   c. Curved Spans

      On curved roadways, normally all girders will be parallel to each other. It is critical that the exterior girders are positioned properly in this case, as described in Subsection 5.6.4B.

   d. Geometrically Complex Spans

      Spans which are combinations of taper and curves will require especially careful consideration in order to develop the most effective and economical girder arrangement. Where possible, girder lengths and numbers of straight and harped strands should be made the same for as many girders as possible in each span.

   e. Number of Girders in a Span

      Usually all spans will have the same number of girders. Where aesthetics of the underside of the bridge is not a factor and where a girder can be saved in a short side span, consideration should be given to using unequal numbers of girders. It should be noted that this will complicate crossbeam design by introducing torsion effects and that additional reinforcement will be required in the crossbeam.

B. Slab Cantilevers

The selection of the location of the exterior girders with respect to the curb line of a bridge is a critical factor in the development of the framing plan. This location is established by setting the curb distance, which is that dimension from centerline of the exterior girder to the adjacent curb line. For straight bridges, the distance between the girder and the edge of slab will normally be no less than 2′–6″ for W42G, W50G, and W58G; 3′–0″ for W74G; and 3′–6″ for WF74G, W83G, and W95G. Some considerations which affect this are noted below.

1. Appearance

   In the past, some prestressed girder bridges have been designed by placing the exterior girders directly under the curb (traffic barrier). This gives a very poor bridge appearance and is uneconomical. Normally, for best appearance, the largest slab overhang which is practical should be used.

2. Economy

   Fortunately, the condition tending toward best appearance is also that which will normally give maximum economy. Larger curb distances may mean that a line of girders can be eliminated, especially when combined with higher girder concrete strengths.

3. Slab Strength

   This is one of the governing conditions which limits the maximum practical curb distance. It must be noted that for larger overhangs, the slab section between the exterior and the first interior girder may be critical and may require thickening. In some cases, live load moments which produce transverse bending in the exterior girder should be considered.

4. Drainage

   Where drainage for the bridge is required, water from bridge drains is normally piped across the top of the girder and dropped inside of the exterior girder line. A large slab cantilever length may severely affect this arrangement and it must be considered when determining exterior girder location.

5. Bridge Curvature

   When straight prestressed girders are used to support curved roadways, the curb distance must vary. Normally, the maximum slab overhang at the centerline of the long span will be made approximately equal to the overhang at the piers on the inside of the curve. At the point of minimum curb distance, however, the edge of the girder top surface should be no closer than 1’-0” from the slab edge. Where curvature is extreme and the difference between maximum and minimum curb distance becomes large, other types of bridges should be considered. Straight girder bridges on highly curved alignments have a poor appearance and also tend to become structurally less efficient.

C. Diaphragm Requirements

1. General

   Diaphragms used with prestressed girder bridges serve two purposes. During the construction stage, the diaphragms provide girder stability for pouring the slab. During the life of the bridge, the diaphragms act as load distributing elements, and are particularly advantageous for distribution of large overloads. Standard diaphragms and diaphragm spacings are given in the office standards for prestressed girder bridges.

Diaphragms that fall within the limitations stated on the office standards need not be analyzed. Where large girder spacings are to be used or other unusual conditions exist, special diaphragm designs should be performed.

2. Design

Diaphragms shall be designed as transverse beam elements carrying both dead load and live load. Wheel loads for design shall be placed in positions so as to develop maximum moments and maximum shears.

3. Geometry

Diaphragms shall normally be oriented parallel to skew (as opposed to normal to girder centerlines). This procedure has the following advantages:

a. The build-up of higher stresses at the obtuse corners of a skewed span is minimized. This build-up has often been ignored in design.

b. Skewed diaphragms are connected at points of approximately equal girder deflections and thus tend to distribute load to the girders in a manner which more closely duplicates design assumptions.

On curved bridges, diaphragms shall normally be placed on radial lines.

D. Skew Effects

Skew in prestressed girder bridges affects structural behavior and member analysis and complicates construction.

1. Analysis

Normally, the effect of skew on girder analysis is ignored. It is assumed that skew has little structural effect on normal spans and normal skews. For short, wide spans and for extreme skews (values over 50 degrees), the effect of the skew on structural action should be investigated. All short span prestressed slabs, tri-beams, and bulb-tee girders have a skew restriction of 30 degrees.

2. Detailing

To minimize labor costs and to avoid stress problems in prestressed girder construction, the ends of girders for continuous spans shall normally be made skewed. When girder ends are skewed, the angle of the girder end should be rounded to the nearest 5 degrees. If this causes problems where the girder extends into the crossbeam, the angle can be specified to the nearest degree. Skew ends of prestressed girders shall always match the piers they rest on at either end.

E. Grade and Cross Slope Effects

Large cross slopes require an increased amount of the girder pad dimension (‘A’ dimension) necessary to ensure that the structure can be built. This effect is especially pronounced if the bridge is on a horizontal or vertical curve. Care must be taken that deck drainage details reflect the cross slope effect. Girder lengths may need to be modified to correct for added length along slope. Remember that the girder is a rectangle in elevation; thus, the position of the girder top corner is affected by grade, girder camber, and tolerances. Details must account for this.

F. Curve Effect and Flare Effect

Curves and tapered roadways each tend to complicate the design of straight girders. The designer must determine what girder spacing to use for dead load and live load design and whether or not a refined analysis, that considers actual load application, is warranted. Normally, the girder spacing at centerline of span can be used for girder design, especially in view of the conservative assumptions made for the design of continuous girders.

5.6.5 Repair of Damaged Girders at Fabrication

This section pertains only to girders which have been damaged before becoming part of a final structure. Repair of damaged girders in existing bridges is covered in Section 5.6.6.

A. Repairs to Girders Prior to Strand Release

When girders suffer defects during casting or damage prior to strand release, the repair procedures are documented in reference 21. Normally, no designer action is required. In prescribing repairs for unusual situations not covered in reference 21, the designer must ensure that the required strength and appearance of the girder can be maintained. Since stressing will occur after the repair is made, normally no test loading is required; however, such a test should be considered.

5.6.6 Repair of Damaged Bridge Girders

A. General

This section is intended to cover repair of damaged girders on existing bridges. For repair of newly constructed girders, see Section 5.6.5. Overheight loads are a fairly common source of damage to prestressed girder bridges. The damage may range from spalling and minor cracking of the lower flange of the girder to loss of a major portion of a girder section. Occasionally, one or more strands may be broken. The damage is most often inflicted on the exterior or first interior girder.

B. Repair Procedure

The determination of the degree of damage to a prestressed girder is largely a matter of judgment. Where the flange area has been reduced or strands lost, calculations can aid in making this judgment decision. The following are general categories of damage and suggested repair procedures[22,23].

1. Minor Damage

If the damage is slight and concerns only spalling of small areas of the outside surface of the concrete, repair may be accomplished by replacing damaged concrete areas with concrete grout. The area where new concrete is to be applied shall first be thoroughly cleaned of loose material, dried, and then coated with epoxy.

2. Moderate Damage

If damage is moderate, consisting of loss of a substantial portion of the flange and possibly loss of one or more strands, a repair procedure must be developed using the following guidelines. It is probable that some prestress will have been lost in the damaged area due to reduction in section and consequent strand shortening or through loss of strands. The following repair procedure is recommended to assure that as much of the original girder strength as possible is retained:

a. Determine Condition

Sketch the remaining cross section of the girder and compute its reduced section properties. Determine the stress in the damaged girder due to the remaining prestress and loads in the damaged state. If severe overstresses are found, action must be taken to restrict loads on the structure until the repair has been completed. If the strand loss is so great that AASHTO prestress requirements cannot be met with the remaining strands, consideration should be given to replacing the girder.

b. Restore Prestress If Needed

If it is determined that prestress must be restored, determine the stress in the bottom fiber of the girder as originally designed due to DL + LL + I + Prestress. (This will normally be about zero psi). Determine the additional load (P) that, when applied to the damaged girder in its existing condition, will result in this same stress. Take into account the reduced girder section, the effective composite section, and any reduced prestress due to strand loss. Should the damage occur outside of the middle one-third of the span length, the shear stress with the load (P) applied should also be computed. Where strands are broken, consideration should be given to coupling and jacking them to restore their prestress.

c. Prepare a Repair Plan

Draw a sketch to show how the above load is to be applied and specify that the damaged area is to be thoroughly prepared, coated with epoxy, and repaired with grout equal in strength to the original concrete. Specify that this load is to remain in place until the grout has obtained sufficient strength. The effect of this load is to restore lost prestress to the strands which have been exposed.

d. Test Load

Consideration should be given to testing the repaired girder with a load equivalent to 1.0DL + 1.5(LL+IM). The LL Live Load for test load is HL-93.

3. Severe Damage

Where the damage to the girder is considered to be irreparable due to loss of many strands, extreme cracking, etc., the girder may need to be replaced. This has been done several times, but involves some care in determining a proper repair sequence.

In general, the procedure consists of cutting through the existing slab and diaphragms and removing the damaged girder. Adequate exposed reinforcement steel must remain to allow splicing of the new bars. The new girder and new reinforcement is placed and previously cut concrete surfaces are cleaned and coated with epoxy. New slab and diaphragm portions are then poured.

It is important that the camber of the new girder be matched with that in the old girders. Excessive camber in the new girder can result in inadequate slab thickness. Girder camber can be controlled by prestress, curing time, or dimensional changes.

Pouring the new slab and diaphragms simultaneously in order to avoid overloading the existing girders in the structure should be considered. Extra bracing of the girder at the time of slab pour should be required.

Methods of construction should be specified in the plans that will minimize inconvenience and dangers to the public while achieving a satisfactory structural result. High early strength grouts and concretes should be considered.

C. Miscellaneous References

Some of the girder replacement contracts which have been completed are:

C-9593 Columbia Center 1C Brs. 12/432 Repair (Simple Span)

C-9593 16th Avenue IC Br. 12/344 Repair (Continuous Span)

C-9446 Mae Valley U Xing (Simple Span)

KD-2488 13th Street O Xing 5/220 (Northwest Region)

KD-2488 SR 506 U Xing 506/108 (Northwest Region)

SR 12 U Xing 12/118 (Northwest Region)

C-5328 Bridge 5/411 NCD (Continuous Span)

KD-2976 Chamber of Commerce Way Bridge 5/227

KD-20080 Golder Givens Road Bridge 512/10

KD-2154 Anderson Hill Road Bridge 3/130W

These and other similar jobs should be used for guidance.

5.6.7 Short Span Precast Prestressed Bridges

A. General

To expedite scheduling and promote economy in building short span bridges, the WSDOT's Bridge Design Office developed standards for short span bridges (range 12 to 70 feet for length of spans). A small bridge program was developed in 1983. A National Cooperative Highway Research Program Report (NCHRP) No. 287, entitled Load Distribution and Connection Design for Precast Stemmed Multibeam Bridge Superstructures was utilized to obtain the most effective keyway geometry between adjacent beam for shear transfer and live load distribution to the girders. These type of bridges are used only for low ADT roads.

B. Precast Prestressed Slabs

The slab sections utilize low relaxation prestressing strands and are connected together permanently with transverse weld tie and keyway. The following are recommendations for the type of precast slab sections to be used for various span lengths:

1. 12-inch depth precast section. This section is capable of spanning between 15 to 35 feet.
2. 18-inch depth voided precast section. This section is capable of spanning between 30 to 50 feet.
3. 26-inch depth voided precast section. This section is capable of spanning between 40 to 70 feet.

Layout, end abutment, and Intermediate Pier standards have been developed for use with the slab sections noted above.

C. Precast Prestressed Tri-Beam and Double-Tee girders

Tri-Beam and double-Tee sections are available as an option to the slab spans. Low relaxation prestressing strands are utilized which enable these sections to span 25 to 70 feet.

D. Precast Prestressed Deck Bulb-Tee Girders

Deck bulb-tee girders are also available as an option to the slab sections. Precast fabricators often prefer deck bulb-tee girders because voided slabs are less efficient sections. We have developed four standard sections while working closely with local fabricator requirements or constraints. 65-inch, 53-inch, 41 inch, and a 35-inch deep bulb-tee girders are used by the state of Washington 4-foot, 5-foot, and 6-foot wide or variable width deck.

5.6.8 Precast Tub Girders

For moderate bridge spans of up to 160 feet, and where girder depth is critical, precast box girders are generally used. These are in the form of U-sections called bath-tubs and joined together with wet joint and post-tensioning. Pretensioned tub girders may be used for spans up to 140 feet.

5.6.9 Prestressed Girder Checking Requirement

1. Shear reinforcing size and spacing beyond the end region of the girder shall be determined by the designer. It is uneconomical to provide a standard pattern to cover all span and girder spacing arrangements.
2. Determine lifting location and required concrete transfer strength to provide adequate stability during handling. The lifting bar location, concrete release strength, and "A" dimension should be checked if temporary strands are used. Generally the temporary strands provide additional stability for lifting and transportation, and reduce the camber. Less camber allows for less "A" dimension and concrete pad dead weight on the structure. Temporary strands are assumed to be cut after all intermediate diaphragms are cast and cured, but before the cast-in-place deck is placed.
3. Due to the extreme depth of the W83G and W95G girders, and possible tilt at the piers for profile grades, the designer will need to pay particular attention to details to assure the girders will fit and perform as intended. Girder data required to be placed in the table on Girder Detail plans include the girder identifiers, "A" dimension, end types, girder geometric data, and strand forces and pattern required.
4. Check edge distance of supporting cross beam.
5. For continuous bridges, design girders as simple spans for live load (Do not deduct negative moments from maximum simple beam positive moments).
6. Provide reinforcement in the deck for negative moments at intermediate piers due to live loads and superimposed dead loads from traffic barrier, pedestrian walkway, utilities, etc.

5.6.10 Review of shop plans for pretensioned girders

Pretensioning shop drawings should be reviewed by the designer if necessary. Shop drawings, after reviewed by the design engineer should be stamped with the official rubber seal and returned to the bridge construction support office. Review of shop drawing must include:

1. All prestressing strands should be of ½" or 0.6" diameter grade 270 low relaxation uncoated strands.
2. Number of strands per girder shall be specified in the shop drawings and should conform to the contract plans.
3. Stresses Prestressing strands shall not exceed $0.75f_{pu}$.
4. Strand placement patterns and harping points should be verified per contract plans.

5. Temporary Strand pattern, bonded length, location and size of blockouts for cutting strands should be verified per contract plans.
6. Procedure for cutting temporary strands and patching the blockouts should be specified.
7. Number and length of extended strands and rebars at girder ends shall be verified per contract plans.
8. Location of holes and shear keys for intermediate and end diaphragms shall be verified per contract plans.
9. Location and size of bearing recesses shall be verified per contract plans.
10. Saw tooth at girder ends shall be verified per contract plans.
11. Location and size of lifting loops or lifting bars shall be verified per contract plans.
12. All horizontal and vertical reinforcement shall be verified per contract plans.
13. Girder length and end skew shall be verified per contract plans.

5.7 Roadway Slab

The following information is intended to provide guidance for slab thickness and transverse and longitudinal reinforcement of roadway slab. Information on deck deterioration prevention systems is section 5.7.4.

5.7.1 Roadway Slab Requirements

A. Slab Thickness

Slab thickness for prestressed girder bridges shall be taken as shown in Table 5-76.

The minimum slab thickness is established in order to ensure that overloads on the bridge will not result in premature slab cracking.


B. Computation of Slab Strength

The thickness and reinforcement requirements for usual slabs are shown in Figure 5-71 and 5-72. the slab design span is defined Figure 5-72 for Composite Prestressed Girder Section.

The thickness of the slab and reinforcement in the area of the cantilever may be governed by traffic barrier loading. Wheel loads plus dead load shall be resisted by the sections shown in Figure 5-71.


Cantilever loads may govern the slab thickness just inside the exterior girder as shown by “Z” in Figure 5-72.

Design of the cantilever is normally based on the expected depth of slab at centerline of girder span. This is less than the dimensions at the girder ends.



Depths for Slab Design at Centerline of Girder Span

Figure 5-71



Depths for Slab Design at Deck Overhang

Figure 5-72

C. Computation of "A" Dimension

The distance from the top of the slab to the top of the girder at centerline bearing (A dimension) is calculated in accordance with the guidance of Appendix B. This ensures that adequate allowance will be made for effects of excess camber, superelevation vertical curve, and horizontal curvature. Ideally the section at centerline of span will have the final geometry shown in Figure 5-71. This must be modified to account for excess camber which may be present in the girders when the slab is poured. Where temporary prestressing strands at top of girder are used to control the girder stresses due to shipping and handling, the "A" dimension shall be adjusted accordingly.

5.7.2 Slab Reinforcement


A. Transverse Reinforcement

The size and spacing of transverse reinforcement may be governed by interior slab span design, cantilever design, or the requirements of traffic barrier load. Where traffic barrier load governs, short hooked bars may be added at the slab edge to increase the reinforcement available in that area. Top transverse reinforcement is always hooked at the slab edge unless a traffic barrier is not used. Top transverse reinforcement is preferably spliced at some point between girders in order to allow the clearance of the hooks to the slab edge forms to be properly adjusted in the field. Usually, the slab edge hooks will need to be tilted in order to place them. On larger bars, the clearance for the longitudinal bar through the hooks should be checked. Bottom transverse slab reinforcement is normally carried far enough to splice with the traffic barrier main reinforcement. Appendix A can be used to aid in selection of bar size and spacing.

For skewed spans, the transverse slab reinforcement is placed parallel to the skew for skew angles of 10 degrees or less. Where skew angles exceed 10 degrees, the transverse bars are placed normal to bridge centerline and the areas near the expansion joints and bridge ends are reinforced by partial length bars. For raised crossbeam bridges, the bottom transverse slab reinforcement is discontinued at the crossbeam.

The spacing of bars over the crossbeam must be detailed to be open enough to allow concrete to be poured into the crossbeam. For typical requirements, see Subsection 5.3.3D.

For slabs with a crowned roadway, the bottom surface and rebar of the slab should be flat, as shown in Figure 5-75.




Bottom of Top Slab at Crown Point
Figure 5-73

B. Longitudinal Reinforcement

This section discusses reinforcement requirements for resistance of longitudinal moments in continuous multi-span precast girder bridges and is limited to reinforcement in the top slab since capacity for resisting positive moment is provided by the prestressing of the girders.

1. Simple Spans

For simple span bridges, longitudinal slab reinforcement is not required to resist negative moments and therefore the reinforcement requirements are nominal. Figure 5-76 defines longitudinal reinforcement requirements for these slabs. The bottom longitudinal reinforcement is defined by AASHTO requirements for distribution reinforcement. The top longitudinal reinforcement is based on current office practice. The requirements of Distribution of Flexural Reinforcement do not apply to these bars.



* TOP MAT REBARS SHALL BE EPOXY COATED. STIRRUPS NEED NOT BE EPOXY COATED AND SHALL BE BENT AT 135°.

** THESE CLEARANCE REQUIREMENTS APPLY IRRESPECTIVE OF WHETHER THE REBARS IN THE TOP MAT ARE EPOXY COATED OR NOT.

Nominal Longitudinal Slab Reinforcement
Figure 5-74

2. Continuous Spans

   Longitudinal reinforcement of continuous spans at intermediate support is dominated by the moment requirement. Where these bars are cut off, they are lapped by the nominal top longitudinal reinforcement described in Subsection 5.7.2D. Typical arrangement of transverse and longitudinal reinforcement is shown in Figure 5-75.

C. Distribution of Flexural Reinforcement

The provision of AASHTO specifications dealing with this subject is provided to limit crack width. At service load, the value of "z" for the equation ,shall be taken as 130 k/inch regardless of whether or not a deck seal or overlay is used. Figure 5-76 shows the area to be used for computing "A." For unevenly spaced bars, this area can be computed as: Total Flange Area/Number of Bars. "Distribution reinforcement" shall be accounted for in the bottom longitudinal layer as follows

1. Prestressed Girders Designed as Simple Spans

   For bridges designed using the "Prestressed Girder Design" program, "distribution reinforcement" need not be added to the area of steel required to resist the negative moments. The bars in the bottom layer, however, shall provide an area not less than that required for distribution reinforcement.

2. Other Prestressed Girder Bridges

On bridges where the effect of continuity is taken into account to reduce moments for girder design, additional longitudinal steel shall be provided as "distribution reinforcement." The sum of the areas in both layers of longitudinal bars shall be equal to the area required to resist negative moments plus the area required by the AASHTO specification for "distribution reinforcement." Equal area of reinforcement shall be used in the top and bottom layers throughout the negative moment region. The total area of steel required in the bottom longitudinal layer shall not be less than that required for "distribution reinforcement."

The minimum clearance between top and bottom bars should be 1-inch . Table 5-73 shows required slab thickness for various bar combinations. Table 5-76 shows the minimum slab thickness for different types of prestresses girders.

Minimum Slab Thickness = 7 Inches	Slab Thickness (Inches)		
	Transverse Bar		
Longitudinal Bar	#5	#6	#7
#4	7½	--	--
5	7½	7½	7¾
6	7½	7¾	8
7	7¾	8	8¼
8	8	8½	8¾
9	8½	8¾	9
10	8¾	--	--

Note: Deduct ½-inch from slab thickness shown in table when asphalt overlay is used and 1 inch when concrete overlay is used. However, the minimum slab thickness shall be 7 inches when overlay is used.

Minimum Slab Thickness for Various Bar Sizes (Slab Without Overlay)
Table 5-75


Girder Type	Web Spacing ft	Width of Top Flange ft	Web Thickness in	Effective Girder Spacing ft	Minimum Slab Thickness in	Design Minimum Slab Thickness in
W42G	5	1.250	6	4.125	7.50	7.50
	6	1.250	6	5.125	7.50	7.50
	7	1.250	6	6.125	7.50	7.50
	8	1.250	6	7.125	7.50	7.50
	9	1.250	6	8.125	7.50	7.50
	10	1.250	6	9.125	7.65	7.75
	11	1.250	6	10.125	8.05	8.25
	12	1.250	6	11.125	8.45	8.50
W50G	5	1.667	6	3.917	7.50	7.50
	6	1.667	6	4.917	7.50	7.50
	7	1.667	6	5.917	7.50	7.50
	8	1.667	6	6.917	7.50	7.50
	9	1.667	6	7.917	7.50	7.50
	10	1.667	6	8.917	7.57	7.75
	11	1.667	6	9.917	7.97	8.00
	12	1.667	6	10.917	8.37	8.50
W58G	5	2.083	6	3.709	7.50	7.50
	6	2.083	6	4.709	7.50	7.50
	7	2.083	6	5.709	7.50	7.50
	8	2.083	6	6.709	7.50	7.50
	9	2.083	6	7.709	7.50	7.50
	10	2.083	6	8.709	7.50	7.50
	11	2.083	6	9.709	7.88	8.00
	12	2.083	6	10.709	8.28	8.50
W74G	5	3.583	6	2.958	7.50	7.50
	6	3.583	6	3.958	7.50	7.50
	7	3.583	6	4.958	7.50	7.50
	8	3.583	6	5.958	7.50	7.50
	9	3.583	6	6.958	7.50	7.50
	10	3.583	6	7.958	7.50	7.50
	11	3.583	6	8.958	7.58	7.75
	12	3.583	6	9.958	7.98	8.00
WF42G, WF50G, WF58G, WF74G, W83G, & W95G	6	4.083	6.125	3.703	7.50	7.50
	7	4.083	6.125	4.703	7.50	7.50
	8	4.083	6.125	5.703	7.50	7.50
	9	4.083	6.125	6.703	7.50	7.50
	10	4.083	6.125	7.703	7.50	7.50
	11	4.083	6.125	8.703	7.50	7.50
	12	4.083	6.125	9.703	7.88	8.00
W32BTG, W38BTG, & W62BTG	5	4.083	6	2.708	7.50	7.50
	6	4.083	6	3.708	7.50	7.50
	7	4.083	6	4.708	7.50	7.50
	8	4.083	6	5.708	7.50	7.50
	9	4.083	6	6.708	7.50	7.50
	10	4.083	6	7.708	7.50	7.50
	11	4.083	6	8.708	7.50	7.50
	12	4.083	6	9.708	7.88	8.00
WF74PTG, W83PTG, & W95PTG	6	4.229	7.875	3.557	7.50	7.50
	8	4.229	7.875	5.557	7.50	7.50
	10	4.229	7.875	7.557	7.50	7.50
	12	4.229	7.875	9.557	7.82	8.00
	14	4.229	7.875	11.557	8.62	8.75
UF60G, UF72G, & UF84G	6	1.256	7	5.080	7.50	7.50
	7	1.256	7	6.080	7.50	7.50
	8	1.256	7	7.080	7.50	7.50
	9	1.256	7	8.080	7.50	7.50
	10	1.256	7	9.080	7.63	7.75
	11	1.256	7	10.080	8.03	8.25
	12	1.256	7	11.080	8.43	8.50

Minimum Slab Thickness for Prestressed Girder Bridges

Table 5-76


D. Bar Patterns

Figure 5-77 shows two typical top longitudinal reinforcing bar patterns. Care must be taken that bar lengths conform to the requirements of Table 5.1.2-4. Note that the reinforcement is distributed over a width equal to the girder spacing according to office practice and does not conform to AASHTO LRFD Specifications Section 9.7.3.2.



Staggered Bar Pattern
Figure 5-77

The symmetrical bar pattern shown should normally not be used when required bar lengths exceed 60 feet. If the staggered bar pattern will not result in bar lengths within the limits specified in Table 5-7, the method shown in Figure 5-78 may be used to provide an adequate splice. All bars shall be extended development length beyond the point where the bar is required.



Bar Splice Within Moment Envelope

Figure 5-78

In all bar patterns, the reinforcement shall be well distributed between webs. Where this cannot be done without exceeding the 1-foot 0-inch maximum spacing requirement, the nominal longitudinal bars may be extended through to provide the 1-foot 0-inch maximum.

Normally, no more than 20 percent of the main reinforcing bars shall be cut off at one point. Where limiting this value to 20 percent leads to severe restrictions on the reinforcement pattern, an increase in figure may be considered. Two main reinforcement bars shall be carried through the positive moment area as stirrup hangers.

E. Recommendations for Concrete Deck Slab Detailing

These recommendations are primarily for beam-slab bridges with main reinforcement perpendicular to traffic.

- The minimum slab thickness including 0.5 in. wearing surface shall be 7.5 in. for concrete bridges 8.0 in. for steel bridges, and 8.5 in. for concrete decks with SIP deck panels.
- Minimum cover over the top layer of reinforcements shall be 2.5 in. including 0.5 in. wearing surface. The minimum cover over the bottom layer reinforcement shall be 1.0 in..
- Maximum bare size of #5 is preferred for all longitudinal and transverse reinforcements in deck slab except maximum bar size of #7 may be used for longitudinal reinforcements at intermediate piers.
- The minimum amount of reinforcement shall be 0.18 $in.^2$/ft of steel for top layer and 0.27 $in.^2$/ft of steel for bottom layer.
- Top and bottom reinforcement in both longitudinal and transverse direction of deck slab shall be staggered to allow better flow of concrete between bars. Reversing lying transverse and longitudinal rebars in the top mat and staggering top and bottom rebars so as not to create significant plane of weakness and using higher percentage of longitudinal steel.

- For bridges with skew angle less than 25 degrees, the primary reinforcement shall be placed parallel to the skew direction.
- For bridges with skew angle exceeding 25 degrees, the primary reinforcement shall be placed perpendicular to the girder direction.
- For bridges with skew angle exceeding 25 degrees, the amount of reinforcement in both primary and secondary direction shall be increased in the end zones.
- The construction joint with roughened surface in the slab at the intermediate pier diaphragm shall be specified instead of construction joint with shear key.
- Both, top and bottom layer reinforcement shall be considered when designing for negative moment at the intermediate piers.
- Using reinforcement ratio of 0.002 for top mat longitudinal steel and using the same for bottom mat and trying to use No. 4 bars
- Reduce lap splices if possible. Use staggered lap splices for both top and bottom in longitudinal and transverse directions

5.7.3 Stay-In-Place Deck Panels

A. General

The use of stay-in-place (SIP) deck panels for bridge decks shall be investigated at the preliminary design stage. A minimum slab thickness of 8 ½", including 3 ½" inch precast deck panel and 5.0 inch cast-in-place concrete topping, shall be specified for design if SIP deck panels are considered for the bridge deck. The acceptance evaluation will consider such items as extra weight for seismic design and the resulting substructure impacts.

The composite deck system consisting of precast prestressed concrete deck panels with a cast-in-place topping has advantages in minimizing traffic disruption, speeding up construction and solving constructability issues on certain projects. Contractors, in most cases, prefer this composite deck panel system for bridge decks in traffic congested areas and other specific cases.

Composite deck slab system consisting of SIP precast concrete deck panels combined with cast-in-place concrete topping may be used on WSDOT bridges upon Region's request and Bridge and Structures Office approval. Details for SIP deck panels are shown in Appendix A Drawing 5.6-A18-1.

B. Design Criteria

The design of SIP deck panels follows the AASHTO LRFD Bridge Design Specifications and the PCI Bridge Design Manual. The design philosophy of SIP deck panels is identical to simple span prestressed girders. They are designed for Service Limit State and checked for Strength Limit State. The precast panels support the dead load of deck panels and CIP topping, and the composite SIP deck panel and CIP cross-section resists the live load. The tensile stress at the bottom of the panel is limited to zero per WSDOT design practice.

C. Limitation on SIP Deck Panels

The conventional full-depth cast-in-place deck slab continuous to be preferred by the Bridge and Structures Office for most applications. However, WSDOT allows the use of S-I-P Deck Panels upon Regions request and Bridge & Structures Office approval with the following limitations:

1. S-I-P Deck Panels shall not be used in Negative moment region of continuous conventionally reinforced bridges. S-I-P Deck Panels may be used in post-tensioned continuous bridges.

2. Bridge widening. S-I-P Deck Panels are not allowed in the bay adjacent to the existing structure because it is difficult to set the panels properly on the existing structure, and the requirement for C-I-P closure. S-I-P Deck Panels can be used on the other girders when the widening involves multiple girders.

3. Phased construction. S-I-P Deck Panels are not allowed in the bay adjacent to the previously placed deck because of the requirement for C-I-P closure.

4. Prestressed girders with narrow flanges. Placement of S-I-P Deck Panels on girders with flanges less than 12 inches wide is difficult. The use of S-I-P Deck Panel shall be investigated at the preliminary design stage and proper flange width shall be considered.

5. A minimum slab thickness of 8.5 inches, including 3.5 inch precast deck panel and 5 inches C-I-P concrete topping shall be specified for design if S-I-P Deck Panels are considered for bridge deck.

6. S-I-P Deck Panels are not allowed for steel girder bridges. WSDOT's Bridge Design Engineer prefers to have a cast-in-place deck on steel girders.

5.7.4 Concrete Bridge Deck Protection Systems

A deck protection system shall be used in all projects involving concrete bridge deck construction or rehabilitation. For new bridge construction and widening projects, the type of system shall be determined by the Bridge Office Preliminary Plan and Bridge Management units during the preliminary plan stage and shall be shown on the preliminary plan in the left margin. For bridge deck rehabilitation and overlay projects, the Bridge Management Unit shall determine the type of system.

A. System Selection for New Structures

1. System 1 will be used for most New Bridges and Concrete Deck Replacements.

2. System 2 will be used on bridges with transverse post-tensioning in the deck. This system provides double protection to the post-tensioning system since restoration due to premature deck deterioration would be very costly. This system has been used on approximately 36 bridges to date that are located primarily on Interstate Routes.

3. System 3 will normally be used on bridges with precast bulb "T" girders and prestressed slabs. The ACP with membrane provides a wearing surface and some protection to the connections between the girder or slab units.

   A cast-in-place reinforced concrete overlay may be substituted for the asphalt overlay on bulb "T" or slab bridges located on routes with an ADT in excess of 20,000. The Bridge Design Engineer and the Bridge Management Unit shall be consulted to determine the best type of overlay to be used in this case.

B. Deck Overlay Selection for Bridge Widening and Existing Deck Rehabilitation

The Bridge Management Unit will recommend the type of overlay to be used on a bridge deck overlay project following discussions with the Region.

1. Epoxy-coated reinforcing will be specified in the new widened portion of the bridge.

2. The type of overlay on a deck widening shall be the same as the type used on the existing bridge. System 1 will be used on a deck widening if the existing deck does not have an overlay and no overlay is required.

3. There may be bridge widening cases when a modified concrete overlay is used on the existing bridge deck. The concrete deck profile in the widening may be constructed to match the profile of the modified concrete overlay. Contact the Bridge Preliminary Plan unit to determine if this detail applies for a bridge deck widening.
4. A modified concrete overlay will normally be used when one or both of the following criteria is met:
   a. Delaminated and patched areas of the existing concrete deck exceed 2% of the total deck area.
   b. Exposed reinforcing steel is visible. This condition can exist on older bridges with significant traffic related wear.
5. An ACP with membrane overlay provides a short term wearing surface and low level of deck protection. This system may be used on bridges with existing ACP overlays that are to be removed and replaced.
6. Other Overlay types, such as a ¾ inch Polyester or 1 ½ inch Rapid Set LMC, are available in special cases on high ADT routes if rapid construction is needed.

C. Deck Protection Systems - New Bridges / Bridge Widenings / Bridge Deck Replacements

System 1: 2½ inches of concrete cover over epoxy-coated top mat of deck reinforcing.

The concrete deck is cast-in-place with no overlay. The 2½ inches of concrete cover includes a nominal depth for traction striations in the roadway surface and ¼ inch tolerance for the placement of the reinforcing steel.




Figure 5-79

Only the bridge deck top steel reinforcing mat and traffic barrier S1 bars are epoxy coated. Indicate the epoxy-coated reinforcing on the plan sheets and with an "E" in the "Epoxy Coated" column of the bar list. Add a note to the traffic barrier sheet to epoxy coat the S1 bars.

System 2: 1¾ inches of concrete cover over epoxy-coated top mat of deck reinforcing and a 1½ inch Modified Concrete Overlay.

The concrete deck is cast-in-place. The top surface is built with 1¾ " clear, then ¼ " of the concrete deck surface is scarified prior to the placement of the 1½" Modified Concrete Overlay. The final nominal concrete cover over the top mat reinforcing is 3 inches. The type of modified concrete overlay will be specified in the contract special provisions. Generally, the contractor will be allowed to choose between Latex, Microsilica, or Fly Ash modified concrete.




Figure 5-80

Only the bridge deck top steel reinforcing mat and traffic barrier S1 bars are epoxy coated. Indicate the epoxy-coated reinforcing on the plan sheets and with an "E" in the "Epoxy Coated" column of the bar list. Add a note to the traffic barrier sheet to epoxy coat the S1 bars.

System 3:—2-inches of concrete cover over epoxy-coated top mat of deck reinforcing with a 0.15' - 0.25' asphalt with waterproofing membrane overlay.

The 2-inches of concrete cover is used for precast prestressed deck members due to the use of high quality concrete and better control of reinforcing placement. The 2 inches of concrete cover includes a ¼-inch tolerance for the placement of the reinforcing steel.

The total asphalt thickness will be determined during the preliminary plan development by contacting Region Design Office. The 0.25' ACP overlay thickness is preferred if the additional deadload can be accommodated. The 0.25' of ACP will allow future overlays to remove and replace 0.15' without damaging the original membrane.




Figure 5-81

Other Systems: There may be special conditions (i.e. a widening) where it may be desirable to use a different overlay or rebar cover thickness than those shown in the typical previous Systems. For example, there have been some System 3 cases that decreased the amount of rebar cover and used a concrete overlay in order to minimize the total dead load and improve long-term performance on a high ADT route.

The Bridge Design Engineer and the Bridge Management Unit shall be consulted before one of these "Other Systems" is considered for use.

D. Deck Protection Systems – Existing Bridge Rehabilitation / Overlay

The Bridge Management unit will determine the type of overlay on deck overlay projects.

Modified Concrete Overlay – 1½ inches

A 1½ inch Modified Concrete Overlay is the preferred overlay system for providing long-term deck protection and a durable wearing surface. The Modified Concrete Overlay special provision allows a contractor to choose between a Latex, Microsilica or Fly Ash mix design. This overlay requires a deck temperature between 45 - 75 degrees and a wind speed less than 10 mph during construction. The time to construct and cure (42 hours) this overlay along with the traffic control cost can be significant. This type of overlay was first used on a WSDOT bridge in 1979 and has an expected life between 20-30 years.

The bridge deck is scarified prior to application of the modified concrete overlay. The depth of scarification varies between ¼ to ½ inch. There are three types of machines used to scarify namely; Rottomill, Hydromill or a Super shot blaster. There are advantages and disadvantages for each machine. In some cases the Bridge Management unit will request only one of these machines be used in a project.

ACP with Membrane Overlay – 0.15 to 0.25 ft

An ACP with membrane overlay provides a low level of deck protection. This type of overlay is generally used when an overlay is needed but the deck conditions do not warrant the use of a modified concrete overlay. This type of overlay was first used on a WSDOT bridge in 1971 and has an expected life between 8-10 years depending on the ADT. The depth of overlay can vary between 0.15 ft (1.8") and 0.25 ft (3"). The Region should be contacted to determine the depth of ACP.

Polyester Modified Concrete Overlay – ¾ inches

This type of overlay uses specialized equipment and materials. A Polyester overlay requires dry weather with temperatures above 50 degrees during construction and normally cures in 4 hours. A Polyester overlay has been used on 12 bridges (most in the early 1990's) and has an expected life between 20-30 years depending on the ADT. Three bridges on Interstate 5 were overlaid with polyester successfully during nighttime closures in the summer of 2002 under contract 6403. A polyester concrete overlay may be used in special cases when rapid construction is needed.

Rapid Set Latex Modified Concrete Overlay – 1½ inches

A Rapid Set LMC overlay is considered experimental. This overlay uses special cement manufactured by the CTS company based in California. A Rapid Set LMC overlay is mixed in a mobil mixing truck and is applied like a regular LMC overlay. This overlay generally cures in 4 hours (verses 42 hours for a modified concrete overlay). The first Rapid Set LMC was applied to bridge 162/20 South Prairie Creek in the summer of 2002 under contract 6395. This overlay should be used on a limited basis until more is known about its long-term performance.

Thin Polymer Overlay – ½ inches

The use of Thin Polymer Overlays has generally been discontinued due to poor performance. This system has been used on movable bridges and bridges with low vertical clearances.

5.8 Cast-in-Place Bridges

5.8.1 Design Parameters

A. General

Post-tensioning is generally used for cast-in-place construction and spliced precast girders since pretensioning is generally practical only for fabricator-produced structural members. The Post-Tensioned Box Girder Bridge Manual[24] published by the Post-Tensioning Institute in 1978 is recommended as the guide for design. This manual discusses longitudinal post-tensioning of box girder webs and transverse post-tensioning of box girder slabs, but the methods apply equally well to other types of bridges. The following recommendations are intended to augment the PTI Manual and the AASHTO Code and point out where current WSDOT practice departs from practices followed elsewhere.

The AASHTO criteria for reinforced concrete apply equally to bridges with or without post- tensioning steel. However, designers should note certain requirements unique to prestressed concrete such as special ϕ-factors, load factors and shear provisions.

Post-tensioning consists of installing steel tendons into a hollow tight ferrous also referred as sheath duct in a structure after the concrete sections are cast. These tendons are usually anchored at each end of the structure and stressed to a design strength using a hydraulic jacking system. After the tendon has been stressed, the duct is filled with grout which bonds the tendon to the concrete section and prevents corrosion of the strand. The anchor heads are then encased in concrete to provide corrosion protection.

B. Bridge Types

Post-tensioning has been used in various types of cast-in-place bridges in Washington State with box girders predominating. See Appendix B for a comprehensive list of box girder designs. The following are some examples of other bridge types:

Kitsap County, Contract C-9788, Multi-Span Slab

Peninsula Drive, Contract C-5898, Two- Span Box Girder

Covington Way to 180th Avenue SE, Contract C-4919, Two-Span Box Girder Longitudinal Post-Tensioning

Snohomish River Bridge, Contract C-4444, Multi-Span Box Girder Longitudinal Post-Tensioning

See BDM Section 2.4.1 for structure type comparison of post-tensioned concrete box girder bridges to other structures. In general, a post-tensioned cast-in-place bridge can have a smaller depth-to-span ratio than the same bridge with conventional reinforcement. This is an important advantage where minimum structure depth is desirable.

1. Slab Bridge

Structure depth can be quite shallow in the positive moment region when post-tensioning is combined with haunching in the negative moment region. However, post-tensioned cast-in-place slabs are usually more expensive than when reinforced conventionally. Designers should proceed with caution when considering post-tensioned slab bridges because severe cracking in the decks of bridges of this type has occurred[31,32,33].

The Olalla Bridge (Contract 9202) could be reviewed as an example. This bridge has spans of 41.5 feet - 50 feet - 41.5 feet, a midspan structure depth of 15 inches, and some haunching at the piers.

2. T-Beam Bridge

   This type of bridge, combined with slope-leg columns, can be structurally efficient and aesthetically pleasing, particularly when the spacing of the beams and the columns are the same. A T-Beam bridge can also be a good choice for a single-span simply-supported structure.

   When equally spaced beams and columns are used in the design, the width of beam webs should generally be equal to the width of the supporting columns. See SR 16, Union Avenue O'Xings, for an example. Since longitudinal structural frame action predominates in this type of design, crossbeams at intermediate piers can be relatively small and the post-tensioning tendons can be placed side-by-side in the webs, resulting in an efficient center of gravity of steel line throughout. For other types of T-Beam bridges, the preferred solution may be smaller, more closely spaced beams and fewer, but larger pier elements. If this type of construction is used in a multispan, continuous bridge, the beam cross-section properties in the negative moment regions need to be considerably larger than the properties in the positive moment regions to resist compression.

   Larger section properties can be obtained by gradually increasing the web thickness in the vicinity of intermediate piers or, if possible, by adding a fillet or haunch. The slab overhang over exterior webs should be roughly half the web spacing.

3. Box Girder Bridge

   This type of bridge has been a popular choice in this state. The cost of a prestressed box girder bridge is practically the same as a conventionally-reinforced box girder bridge, however, longer spans and shallower depths are possible with prestressing.

4. Box Girders

   The superstructure of multi-cell box girders shall be designed as a unit. The entire superstructure section (traffic barrier excluded) shall be considered when computing the section properties.

   Web spacing should normally be 8 to 11 feet and the slab overhang over exterior girders should be approximately half the girder spacing unless transverse post-tensioning is used. The apparent visual depth of box girder bridges can be reduced by sloping all or the lower portion of the exterior web. If the latter is done, the overall structure depth may have to be increased. Web thickness should be 12 inches minimum, but not less than required for shear and for concrete placing clearance. Providing 2½-inches of clear cover expedites concrete placement and consolidation in the heavily congested regions adjacent to the post-tensioning ducts. Webs should be flared at anchorages. Top and bottom slab thickness should normally meet the requirements of Subsection 5.3.1B, but not less than required by stress and specifications. Generally, the bottom slab would require thickening at the interior piers of continuous spans. This thickening should be accomplished by raising the top surface of the bottom slab at the maximum rate of ½-inch per foot.

   For criteria on distribution of live loads, see Subsection 4.1.2 B. All slender members subjected to compression must satisfy buckling criteria.


C. Strand and Tendon Arrangements

The total number of strands selected should be the minimum required to carry the service loads at all points. Duct sizes and the number of strands they contain vary slightly, depending on the supplier. Chapter 2 of the PTI Post-Tensioned Box Girder Bridge Manual, and shop drawings of the recent post-tensioned bridges kept on file in the Construction Plans Section offer guidance to strand selection. In general, a supplier will offer several duct sizes and associated end anchors, each of which will accommodate a range of strand numbers up to a maximum in the range. Present WSDOT practice is to indicate only the design force and cable path on the contract plans and allow the post-tensioning supplier to satisfy these requirements with tendons and anchors. The most economical tendon selection will generally be the maximum size within the range. Commonly-stocked tendons include 9, 12, 19, 27, 31, and 37 - ½-inch diameter strands, and the design should utilize a combination of these commonly-stocked items. For example, a design requiring 72 strands per web would be most economically satisfied by two standard 37-strand tendons. A less economical choice would be three standard 27-strand tendons containing 24 strands each. Tendons should not be larger than (37) ½-inch strand units or (27) 0.6-inch strand units, unless specifically approved by the Bridge Design Engineer and the Design Unit Supervisor. The duct area should be at least 2.5 times the net area of the prestressing steel. In the regions away from the end anchorages, the duct placement patterns indicated in Figure 5-82 through 5-84 should be used.

Although post-tensioning steel normally takes precedence in a member, sufficient room must be provided for other essential mild steel and placement of concrete, in particular near diaphragms and cross-beams.


More prestress may be needed in certain portions of a continuous superstructure than elsewhere, and the designer may consider using separate short tendons in those portions of the spans only. However, the savings on prestressing steel possible with such an arrangement should be balanced against the difficulty involved in providing suitable anchoring points and sufficient room for jacking equipment at intermediate locations in the structure. For example, torsion in continuous, multigirder bridges on a curve can be counter-balanced by applying more prestress in the girders on the outside of the curve than in those on the inside of the curve.

Some systems offer couplers which make possible stage construction of long bridges. With such systems, forms can be constructed and concrete cast and stressed in a number of spans during stage 1, as determined by the designer. After stage 1 stressing, couplers can be added, steel installed, concrete cast and stressed in additional spans. To avoid local crushing of concrete and/or grout, the stress existing in the steel at the coupled end after stage 1 stressing should not be exceeded during stage 2 stressing.




Tendon Placement Pattern for Box Girder Bridges

Figure 5-82




DUCTS 2 " O.D. TO 3" O.D.



DUCTS OVER 3" O.D.

Tendon Placement Pattern for Different Duct Sizes

Figure 5-83



Tendon Placement Pattern for Flat Slab Bridges


Figure 5-84

D. Layout of Anchorages and End Blocks

Consult industry brochures and shop plans for recent bridges before laying out end blocks. To encourage bids from a wider range of suppliers, try to accommodate the large square bearing plate sizes common to several systems.

Sufficient room must be allowed inside the member for mild steel and concrete placement and outside the member for jacking equipment. The size of the anchorage block in the plane of the anchor plates should be large enough to provide a minimum of 1-inch clearance from the plates to any free edge.

In general, the end block dimensions must meet the requirements of the AASHTO Code. Note that in long-span box girder superstructures requiring large bearing pads, the end block should be somewhat wider than the bearing pad beneath to avoid subjecting the relatively thin bottom slab to high bearing stresses. When the piers of box girder or T-beam bridges are severely skewed, the layout of end blocks, bearing pads, and curtain walls at exterior girders become extremely difficult as shown in Figure 5-85. Note that if the exterior face of the exterior girder is in the same plane throughout its entire length, all the end block widening must be on the inside. To lessen the risk of tendon break-out through the side of a thin web, the end block should be long enough to accommodate a horizontal tendon curve of 200 feet minimum radius. The radial component of force in a curved cable is discussed in LRFD section 5.10.4.3.



Layout of Anchorages and End Blocks

Figure 5-85

E. Superstructure Shortening

Whenever members such as columns, crossbeams, and diaphragms in bridges without prestressing steel are appreciably affected by post-tensioning of the main girders, those effects should be included in the design. This will generally be true in structures containing rigid frame elements. For further discussion, see Chapter 2.6 of reference 6.99.24 and Subsection 9.3.2.

Past practice in the state of Washington regarding control of superstructure shortening in post-tensioned bridges with rigid piers can be illustrated by a few examples. Single-span bridges have been provided with a hinge at one pier and longitudinal slide bearings at the other pier. Two-span bridges have been detailed with longitudinal slide bearings at the end piers and a monolithic middle pier. On the six-span Evergreen Parkway Undercrossing structure, the center pier (pier 4) was built monolithic with the superstructure, and all the other piers were constructed with slide bearings. After post- tensioning, the bearings at piers 3 and 5 were converted into fixed bearings to help resist large horizontal loads such as earthquakes.

Superstructures which are allowed to move longitudinally at certain piers are typically restrained against motion in the transverse direction at those piers. This can be accomplished with suitable transverse shear corbels or bearings allowing motion parallel to the bridge only. The casting length for box girder bridges shall be slightly longer than the actual bridge layout length to account for the elastic shortening of the concrete due to prestress.

F. Effects of Curved Tendons

Curved tendons induce deviation forces that are radial to the tendon in the plane of tendon curvature. Curved tendons with multiple strands also induce out-of-plane forces that are perpendicular to the plane of the tendon curvature. Resistance to curved tendon induced forces may be provided by increasing the concrete cover over the duct, by adding confinement reinforcement or by combination of both.

Confinement reinforcement shall be proportioned to ensure that steel stress at service limit state does not exceed 0.6fy for grade 60 reinforcement. Spacing of the confinement reinforcement shall not exceed 3.0 times the outside diameter of the duct or 18.0 in.

The in-plane deviation force effects due to the change in direction of tendons shall be taken as:

$$F_{u-in} = \frac{P_u}{R}$$

The out-of-plane force effect due to the wedging action of strands against the duct wall may be taken as:

$$F_{u-out} = \frac{P_u}{\pi R}$$

The shear resistance of the concrete cover against deviation force, Vr shall be taken as:

$$V_r = 0.125 \varphi d_c \sqrt{f'_c}$$

where:

$F_{u\text{-}in}$ = the in-plane deviation force effect per unit length of girder. k/ft

$F_{u\text{-}out}$ = the out-of-plane deviation force effect per unit length of girder. k/ft

P_u = Factored tendon force, kips

R = radius of tendon curvature at the considered location, ft

F = resistance factor

dc = minimum concrete cover over the tendon duct plus one-half of the duct diameter, in.

f'c = compressive strength of concrete at time of initial loading, ksi

If the above shear resistance is not adequate, local confinement reinforcement shall be provided throughout the curved tendon segments to resist all of the out-of-plane forces, preferably in form of spiral reinforcement.

H. Edge Tension Forces

If the centroid of all tendons is located outside of the kern of the section, longitudinal edge tension force is induced. The longitudinal edge tension force may be determined from an analysis of a section located at one-half the depth of the section away from the loaded surface taken as a beam subjected to combined flexural and axial load.

5.8.2 Analysis

A. General

The procedures outlined in Section 2.1 through 2.5 of reference 24 for computation of stress in single and multispan box girders can be followed for the analysis of T-beams and slab bridges, as well.

The BDS program available on the WSDOT system will quickly perform a complete stress analysis of a box girder, T-beam, or slab bridge, provided the structure can be idealized as a plane frame. For further information, see the program user instructions.

The STRUDL program is recommended for complex structures which are more accurately idealized as space frames. Examples are bridges with sharp curvature, varying superstructure width, severe skew, or slope-leg intermediate piers. An analysis method in Chapter 10 of reference .25 for continuous prestressed beams is particularly well adapted to the loading input format in STRUDL. In the method, the forces exerted by cables of parabolic or other configurations are converted into equivalent vertical linear or concentrated loads applied to members and joints of the superstructure. The vertical loads are considered positive when acting up toward the center of tendon curvature and negative when acting down toward the center of tendon curvature. Forces exerted by anchor plates at the cable ends are coded in as axial and vertical concentrated forces combined with a concentrated moment if the anchor plate group is eccentric. Since the prestress force varies along the spans due to the effects of friction, the difference between the external forces applied at the end anchors at opposite ends of the bridge must be coded in at various points along the spans in order for the summation of horizontal forces to equal zero. With correct input (check thoroughly before submitting for computation), the effects of elastic shortening and secondary moments are properly reflected in all output listings, and the prestress moments printed out are the actual resultant (total) moments acting on the structure. For examples of the application of STRUDL to post-tensioning design, see the calculations for SR 90 West Sunset Way Ramp (simple), SR 5 Nalley Valley Viaduct (complex), and the STRUDL manuals.

B. Section Properties

As in other types of bridges, the design normally begins with a preliminary estimate of the superstructure cross-section and the amount of prestress needed at points of maximum stress and at points of cross-section change. For box girders, See Figure 2-0 through 2-5 of Reference 24. For T-beam and slab bridges, previous designs are a useful guide in making a good first choice.

For frame analysis, use the properties of the entire superstructure regardless of the type of bridge being designed. For stress analysis of slab bridges, calculate loads and steel requirements for a 1-foot wide strip. For stress analysis of T-beam bridges, use the procedures outlined in the AASHTO specifications.

Note that when different concrete strengths are used in different portions of the same member, the equivalent section properties should be calculated in terms of either the stronger or weaker material. In general, the concrete strength should be limited to the values indicated in Subsection 5.1.1 of this manual.


C. Preliminary Stress Check

In accordance with AASHTO, flexural stresses in prestressed members are calculated at service load levels. Shear stresses, stirrups, moment capacities vs. applied moments are calculated at ultimate load levels.

During preliminary design, the first objective should be to satisfy the allowable flexural stresses in the concrete at the critical points in the structure with the chosen cross-section and amount of prestressing steel, then the requirements for shear stress, stirrups, and ultimate moment capacity can be readily met with minor or no modifications in the cross-section. For example, girder webs can be thickened locally near piers to reduce excessive shear stress.

In the AASHTO formulas for allowable tensile stress in concrete, bonded reinforcement should be interpreted to mean bonded auxiliary (nonprestressed) reinforcement in conformity with Article 8.6 of the 2002 ACI Code for Analysis and Design of Reinforced Concrete Bridge Structures. Normal practice is to use the time-dependent prestress loss from Table 5-12. The long-hand formulas for computing time-dependent losses in steel stress given in the code should be used only when a more thorough investigation is deemed necessary. To minimize concrete cracking and protect reinforcing steel against corrosion for bridges, the allowable concrete stress under final conditions in the precompressed tensile zone should be limited to zero in the top and bottom fibers as shown in Figure 5-86.

In all cases where tension is allowed in the concrete under initial or final conditions, extra mild steel (auxiliary reinforcement) should be added to carry the total tension present. This steel can be computed as described in Chapter 9-5 of Reference 25.



Box Girder Stresses
Figure 5-86

In case of overstress, try one or more of the following remedies: Adjust tendon profiles, add or subtract prestress steel, thicken slabs, revise strength of concrete of top slab, add more short tendons locally, etc. Then repeat calculations as necessary.

D. Camber

The camber to be shown on the plans should include the effect of both dead load and final prestress and may be taken as given in Table 5-20.

E. Expansion Bearing Offsets

Figure 5-85 indicates expansion bearing offsets for the partial effects of elastic shortening, creep, and shrinkage. The initial offset shown is intended to result in minimal bearing eccentricity for the majority of the life of the structure. The bearing should be designed for the full range of anticipated movements: ES+CR+SH+TEMP.

5.8.3 Post-tensioning

A. Tendon Layout

After a preliminary estimate has been made of the concrete section and the amount of prestressing needed at points of maximum applied load, it may be advantageous in multispan bridges to draw a tendon profile to a convenient scale superimposed on a plot of the center of gravity of concrete (c.g.c.) line. The most efficient tendon profile from the standpoint of steel stress loss will normally be a series of rather long interconnected parabolas, but other configurations are possible. For continuous bridges with unequal span lengths, the tendon profile (eccentricity) shall be based on the span requirement. This results in an efficient post-tensioning design. The tendon profile and c.g.c. line plot is strongly recommended for superstructures of variable cross-section and/or multiple unsymmetrical span arrangements, but is not necessary for superstructures having constant cross- section and symmetrical spans. The main advantages of the tendon profile and c.g.c. plot are:

1. The primary prestress moment curves (prestress force times distance from c.g.c. line to center of gravity of steel (c.g.s.) lines) at all points throughout all spans are quickly obtained from this plot and will be used to develop the secondary moment curves (if present) and, ultimately, to develop the resultant total prestress moment curve.
2. Possible conflicts between prestressing steel and mild steel near end regions, crossbeams, and diaphragms may become apparent.
3. Possible design revisions may be indicated. For example, camber in bridges with unequal spans can be balanced by adjusting tendon profiles.

   The tendon profile and c.g.c. line diagram should also contain a sketch of how the end bearing plates or anchors are to be arranged at the ends of the bridge. Such a sketch can be useful in determining how large the end block in a girder bridge will have to be and how much space will be required for mild steel in the end region. In general, the arrangement of anchor plates should be the same as the arrangement of the ducts to which they belong to avoid problems with duct cross-overs and to keep end blocks of reasonable width.

B. Prestress Losses

Friction losses occurring during jacking and prior to anchoring, depend on the system and materials used. For purposes of design, this office has specified a rigid spiral galvanized ferrous metal duct system for which μ shall be 0.20 and $K = 0.0002$. This system is at present available from several large suppliers. To avoid the substantial friction loss caused by sharp tendon curvature in the end regions where the tendons flare out from a stacked arrangement towards the bearing plates, use 0.10 times the span length or 20 feet as the minimum flare zone length. The recommended minimum radius (horizontal or vertical) of flared tendons is 200 feet. In the special cases where sharp curvature cannot be avoided, extra horizontal and vertical ties should be added along the concave side of the curve to resist the tendency to break through the web. See stirrup calculations for SR 2, EU-Line O'Xing, for a suggested method of calculating this additional steel.

All other losses (those due to shrinkage, elastic shortening, creep, and relaxation of steel) shall be as indicated in Subsection 6.1.5.

For bridges with horizontal curvature the total friction losses calculation shall be based on the equation:

$$T_x = T_o e^{-(\mu X + KL)}$$


C. Steel Stress Curve

Steel stresses may be plotted either as the actual values or as a percentage of the jacking stresses. A steel stress diagram for a typical two-span bridge is shown below. Spans are symmetrical about pier 2 and the bridge is jacked from both ends. All values are in ksi and pertain to 270 ksi either stress relieved or low relaxation strands. f_{pu} denotes ultimate strength of strands in ksi. All WSDOT post-tensioning designs are based on low relaxation strands.

Losses due to creep, shrinkage, and relaxation of prestressing steel are given in Table 5-12 for structures of usual design and normal weight concrete.

Yield Stress for Stress-Releive Strands = 0.85 f_{pu}


Yield Stress for Low-Relaxation Strands = 0.90 f_{pu}



Stress Diagram for a 2-span PT Bridge
Figure 5-87

Accurate plotting of steel stress variation due to local curvature is normally not necessary, and straight lines between intersection points on the diagram as shown in Figure 5-87 are usually sufficient. When tendons are continuous through the length of the bridge, the stress for design purposes at the jacked end should be limited to $0.75f_{pu}$ or 202 ksi for 270 ksi stress relieved strands or $0.79f_{pu}$ or 213 ksi for 270 ksi low relaxation strands. This would permit the post-tensioning contractor to jack to the slightly higher value of $0.77f_{pu}$ for stress relieved strands or $0.81f_{pu}$ for low relaxation strands as allowed by the AASHTO Code in case friction values encountered in the field turn out somewhat greater than the standard values used in design. Stress loss at jacked end should be calculated from the assumed anchor set of $^3/_8$ inch, the normal slippage during anchoring in most systems. At the high points on the initial stress curve, the stress should not exceed $0.70f_{pu}$ for stress relieved strands or $0.75f_{pu}$ low relaxation strands after sealing of anchorage. If these values are exceeded, the jacking stress can be lowered or alternately the specified amount of anchor set can be increased.

When the total tendon length (L) is less than the length of cable influenced by anchor set (x) and the friction loss is small, as in short straight tendons, the $0.70f_{pu}$ value governs. In these cases, the maximum allowable jacking stress value of $0.75f_{pu}$ for stress relieved or $0.78f_{pu}$ for low relaxation strands cannot be used and a slightly lower value should be specified as shown in Figure 5-88.



Stress Diagram at Jacking End

Figure 5-88

In single-span, simply supported superstructures friction losses are so small that jacking from both ends is normally not warranted. In the longer multispan bridges where the tendons experience greater friction losses, jacking from both ends will usually be necessary. Jacking at both ends need not be done simultaneously, since final results are virtually the same whether or not the jacking is simultaneous. If unsymmetrical two-span structures are to be jacked from one end only, the jacking must be done from the end of the longest span.

D. Flexural Stress in Concrete

Stress at service load levels in the top and bottom fibers of prestressed members should be checked for at least two conditions that will occur in the lifetime of the members. The initial condition occurs just after the transfer of prestress when the concrete is relatively fresh and the member is carrying its own dead load. The final condition occurs after all the prestress losses when the concrete has gained its full ultimate strength and the member is carrying dead load and live load. For certain bridges, other intermediate loading conditions may have to be checked, such as when prestressing and falsework release are done in stages and when special construction loads have to be carried, etc. The concrete stresses shall be within the AASHTO allowable except as amended in Subsection 5.2.3B of this manual.

In single-span simply supported superstructures with parabolic tendon paths, flexural stresses at service load levels need to be investigated at the span midpoint where moments are maximum, at points where the cross-section changes, and near the span ends where shear stress is likely to be maximum (see Subsection 5.8.4 Shear). For tendon paths other than parabolic, flexural stress should be investigated at other points in the span as well.

In multispan continuous superstructures, investigate flexural stress at service load should be at points of maximum moment (in the negative moment region of box girders, check at the quarter point of the crossbeam), at points where the cross section changes, and at points where shear is likely to be maximum. At points of maximum moment, the ultimate moment capacity of the section should exceed or equal the applied ultimate moment. Normally, mild steel should not be used to supplement the ultimate moment capacity. It may be necessary, however, to determine the partial temperature and shrinkage stresses that occur prior to post-tensioning and supply mild steel reinforcing for this condition.

In addition, maximum and minimum steel percentages and cracking moment should be checked. See Subsection 2.3.8 of Reference .24.

E. Prestress Moment Curves

1. Single-Span Bridges, Simply Supported

The primary prestress moment curve is developed by multiplying the initial steel stress curve ordinates by the area of prestressing steel times the eccentricity of steel from the center of gravity of the concrete section at every tenth point in the span. The primary prestress moment curve is not necessary for calculating concrete stresses in single-span simply supported bridges. Since there is no secondary prestress moment developed in the span of a single span, simply supported bridge which is free to shorten, the primary prestress moment curve is equal to the total prestress moment curve in the span. However, if the single span is rigidly framed to supporting piers, the effect of elastic shortening should be calculated. The same would be true when unexpected high friction is developed in bearings during or after construction.

2. Multispan Continuous Bridges

With the exception of T.Y. Lin's equivalent vertical load method used in conjunction with the STRUDL program, none of the methods described in the following section take into account the elastic shortening of the superstructure due to prestressing. To obtain the total prestress moment curve used to check concrete stresses, the primary and secondary prestress moment curves must be added algebraically at all points in the spans. As the secondary moment can have a large absolute value in some structures, it is very important to obtain the proper sign for this moment, or a serious error could result.

A discussion of methods for calculating secondary prestress moments follows:

3. WSDOT BEAMDEF Program

If the primary prestress moment values at tenth points are coded into this program, span stiffness factors, carry-overs, and fixed-end moments will be obtained. Distribution of the fixed-end moments in all spans will yield the secondary moments at all piers. The secondary moments will be zero at simply supported span ends and cantilevers.

a. Equivalent Vertical Load

See discussion in Subsection 5.8.2 of this manual.

b. Table of Influence Lines

See Appendix A.1 of Reference .24 for a discussion. This method is similar to T. Y. Lin's equivalent vertical load method and is a relatively quick way to manually compute prestress moments in bridges of up to five spans. Since the secondary moment effect due to vertical support reactions is included in the coefficients listed in the tables, the support moment computed is the total moment at that point.

c. Slope Deflection

See Section 2.5 of Reference .24 for a discussion. The method, though straightforward, is time consuming.

5.8.4 Shear

A. Shear Capacity

Concrete box girder and T-beam bridges with horizontal construction joints (which result from webs and slabs being cast at different times) should be checked for both vertical and horizontal shear capacity. Generally, horizontal shear requirements will control the stirrup design.

Vertical concrete shear capacity for prestressed or post-tensioned structural members is calculated in AASHTO LRFD Specifications Section 5.8.3. Minimum stirrup area, maximum stirrup spacing, and maximum stirrup capacity, Vs, are further subject to the limitations presented in AASHTO LRFD Specifications Section 5.8.2.5 and 5.8.2.7. For further explanation, refer to Section 11.4 of the ACI 318-02 Building Code Requirements for Reinforced Concrete and Commentary. Chapter 27 of Notes on ACI 318-02 Building Code Requirements for Reinforced Concrete with Design Applications presents two excellent example problems for vertical shear design. The use of an electronic spreadsheet simplifies the repetitive and detailed nature of these calculations.

B. Horizontal Shear

Horizontal shear stress acts over the contact area, of width b_v, between two interconnected surfaces of a composite structural member.

Horizontal shear design is relatively straightforward. The AASHTO LRFD section 5.8.4 shall be used for shear-friction design.

For cast-in-place sloped outer webs, increase inside stirrup reinforcement and bottom slab top transverse reinforcement as required for the web moment locked-in during construction of the top slab. This moment about the bottom corner of the web is due to tributary load from the top slab concrete placement plus 10 psf form dead load.

For precast tub outer webs, increase the stirrup and bottom slab steel as required by moment induced by falsework overhang brackets supporting concrete plus 10 psf overhang deck load.

C. End Block Stresses

The highly concentrated forces at the end anchorages cause bursting and spalling stresses in the concrete which must be resisted by vertical and horizontal reinforcement. For a better understanding of this subject, see Chapter 7 of Reference 25 and 26, and Section 2.82 of Reference 24.

Note that the procedures for computing horizontal bursting and spalling steel in the slabs of box girders and T-beams are similar to those required for computing vertical steel in girder webs, except that the slab steel is figured in a horizontal instead of a vertical plane. In box girders, this slab steel should be placed half in the top slab and half in the bottom slab. See Appendix A for typical box girder end block reinforcement details. The anchorage zones of slab bridges will require vertical stirrups as well as additional horizontal transverse bars extending across the width of the bridge. The horizontal spalling and bursting steel in slab bridges shall be placed half in a top layer and half in a bottom layer.

D. Anchorage Stresses

The average bearing stress on the concrete behind the anchor plate and the bending stress in the plate material should satisfy the requirements of the AASHTO Code. In all sizes up to the 31-strand tendons, the square anchor plates used by three suppliers (DSI, VSL, AVAR, Stronghold) meet the AASHTO requirements, and detailing end blocks to

accommodate these plates is the recommended procedure. In the cases where nonstandard (rectangular) anchor plates must be specified because of space limitations, assume that the trumpet associated with the equivalent size square plate will be used. In order to calculate the net bearing plate area pressing on the concrete behind it, the trumpet size can be scaled from photos in supplier brochures. Assume for simplicity that the concrete bearing stress is uniform. Bending stress in the steel should be checked assuming bending can occur across a corner of the plate or across a line parallel to its narrow edge. See Appendix B for preapproved anchorages for post-tensioning.

5.8.5 Temperature Effects

Most specifications for massive bridges call for a verification of stresses under uniform temperature changes of the total bridge superstructure. Stresses due to temperature unevenly distributed within the cross-section are not generally verified. In reality, however, considerable temperature gradients are set up within the cross-section of superstructures. Such temperature differences are mostly of a very complex nature, depending on the type of cross-section and direction of solar radiation[27].

Solar radiation produces uniform heating of the upper surface of a bridge superstructure which is greater than that of the lower surface. An inverse temperature gradient with higher temperatures at the lower surface occurs rarely and involves much smaller temperature differences. In statically indeterminate continuous bridge beams, a temperature rise at the upper surface produces positive flexural moments which cause tensile stresses in the bottom fibers. When the temperature gradient is constant over the entire length of a continuous beam superstructure, positive flexural moments are induced in all spans. These moments are of equal constant magnitude in the interior spans and decrease linearly to zero in the end spans. The most critical zones are those which have the lowest compressive stress reserve in the bottom fibers under prestress plus dead load. Normally, these are the zones near the interior supports where additional tensile stresses develop in the bottom fibers due to

- A concentrated support reaction, and
- Insufficient curvature of prestressed reinforcement.

Studies have shown that temperature is the most important tension-producing factor, especially in two-span continuous beams in the vicinity of intermediate supports, even when the temperature difference is only 10°C between the deck and bottom of the beam. In practice, a box girder can exhibit a ΔT=30°C. The zone at a distance of about 0.3 to 2.0d on either side of the intermediate support proved to be particularly crack-prone.

Computation of stresses induced by vertical temperature gradients within prestressed concrete bridges can become quite complex and are ignored in typical designs done by WSDOT. It is assumed that movements at the expansion devices will generally relieve any induced stresses. However, such stresses can be substantial in massive, deep bridge members in localities with large temperature fluctuations. If the structure being designed falls within this category, a thermal stress investigation should be considered. See Reference .24 and the following temperature criteria for further guidance.

1. A Mean temperature 50°F with Rise 45°F and Fall 45°F for longitudinal analysis using one-half of the Modulus of Elasticity. (Maximum Seasonal Variation.)
2. The superstructure box girder shall be designed transversely for a temperature differential between inside and outside surfaces of ±15°F with no reduction in Modulus of Elasticity (Maximum Daily Variation).

3. The superstructure box girder shall be designed longitudinally for a top slab temperature increase of 20°F with no reduction in modulus of elasticity. (In accordance with Post-Tensioning Institute Manual, Precast Segmental Box Girder Bridge Manual, Subsection 3.3.4.)

   The coefficient of thermal expansion used is 0.000006.

   Modulus of Elasticity $E_c = 33000 w_c^{1.5} \sqrt{f'_c}$

   Where:

   W = weight of concrete in kip. per cubic foot

   f'c = Concrete compressive strength, ksi

5.8.6 Construction

A. General

Construction plans for conventional post-tensioned box girder bridges include two different sets of drawings. The first set (contract) is prepared by the design engineer (WSDOT or contracting agency) and the second set (shop) is prepared by the post-tensioning materials supplier (contractor).

B. Contract Plans

The plans should be prepared to accommodate any post-tensioning system, so only prestressing forces and eccentricity should be detailed. The concrete sections should be detailed so that available systems can be installed. Design the thickness of webs and flanges to facilitate concrete placement. Generally, web thickness for post-tensioned bridges shall be at least 12 inches.

C. Shop Plans

The shop plans are used to detail, install, and stress the post-tensioning system selected by the Contractor. These plans must contain sufficient information to allow the engineer to check their compliance with the contract plans. These plans must also contain the location of anchorages, stressing data, and arrangement of tendons.

D. Review of Shop Plans for Post-tensioned girder

Post-tensioning shop drawings should be reviewed by the designer (or Bridge Technical Advisor for non bridge office projects) and consulted with the concrete specialist if needed. Shop drawings, after reviewed by the design engineer should be stamped with the official rubber seal and returned to the bridge construction support office. Review of shop drawing must include:

1. All post-tensioning strands should be of ½" or 0.6" diameter grade 270 low relaxation uncoated strands.
2. Tendon profile and tendon placement patterns should be verified per contract plans.
3. Duct size should be based on the duct area at least 2.5 times the total area of prestressing strands.
4. Anchor set should conform to the contract plans. The post-tensioning design is typically based on an anchor set of 3/8".
5. Maximum number of strands per tendon should not exceed 37 - ½" diameter strands or 27 - 0.6" diameter strands per Standard Specifications 6-02.3(26) D.

6. Jacking force per web should be verified per contract plans.
7. Prestress force after anchor set (lift-off force) should conform to contract plans.
8. Number of strands per web shall be specified in the shop drawings and should conform to the contract plans.
9. Anchorage system should conform to pre-approved list of post-tensioning system per BDM Appendix B. The anchorage assembly dimensions and reinforcement detailing should conform to the corresponding post-tensioning catalog.
10. The curvature friction coefficient and wobble friction coefficient should conform to the contract plans. The curvature friction coefficient of $\mu = 0.15$ for bridges less than 400 feet, $\mu = 0.2$ for bridges between 400 feet and 800 feet, and $\mu = 0.25$ for bridges longer than 800 feet. The wobble friction coefficient of $k = 0.0002$ /ft is often used. These coefficients may be revised by the post-tensioning supplier if approved by the design engineer and conform to the Standard Specifications 6.02.3(26) E.
11. Post-tensioning stressing sequence should be in accordance with the contract plan post-tensioning Notes.
12. Tendon stresses shall not exceed as specified per BDM figure 6.4.2-2:
    1. $0.80f_{pu}$ at anchor ends immediately before seating.
    2. $0.70f_{pu}$ at anchor ends immediately after seating.
    3. $0.74f_{pu}$ at the end point of length influenced by anchor set.
13. Elongation calculations for each jacking operation should be verified. If the difference in tendon elongation exceeds 2%, the elongation calculations should be separated for each tendon per Standard Specification 6-02.3(26) A.
14. Vent points should be provided at all high points along tendon.
15. Drain holes should be provided at all low points along tendon.
16. The concrete strength at the time of post-tensioning, f'ci should not be less than 4000 psi per standard specifications 6-02.3(26) E-1. Different concrete strength may be used if specified in the contract plans.
17. Concrete stresses at the anchorage should be checked per Standard specifications 6-02.3(26) B-1 for bearing type anchorage. For other type of anchorage assemblies, if not covered in the BDM Appendix B for pre-approved list of post-tensioning system, testing per Standard Specifications 6-02.3(26) B-2 is required.

E. During Construction

1. If the measured elongation of each strand tendon is within +/- 7% of the approved calculated elongation, the stressed tendon is acceptable.
2. If the measured elongation is greater than 7%, force verification after seating (lift-off force) is required. The lift-off force should not be less than 99% of the approved calculated force or more 70% f_{pu} As.
3. If the measured elongation is less than 7%, the bridge construction office will instruct the force verification.
4. One broken strand per tendon is usually acceptable. (Post-tensioning design should preferably allow one broken strand). If more than one strand per tendon is broken, the group of tendon per web should be considered. If a group of tendons in a web is under-stressed, then the adequacy of the entire structure should be investigated by the designer and consulted with the bridge construction office.

5. Failed anchorage is usually taken care by the bridge construction office.
6. Over or under elongation is usually taken care by the bridge construction office.
7. In case of low concrete strength the design engineer should investigate the adequacy of design with lower strength.
8. Other problems such as unbalanced and out of sequence post-tensioning, strands surface condition, strand subjected to corrosion and exposure, delayed post-tensioning due to mechanical problems, Jack calibration, etc. should be evaluated per case-by-case basis and are usually taken care by bridge construction office.

5.8.7 Post-Tensioning Notes — Cast-in-Place Girders

A. General

The design plans shall contain the following information for use by the post-tensioned and state inspector: Strength of concrete in superstructure, tendon jacking sequence, friction coefficients, duct type, elastic and time-dependent losses, anchor set, prestress forces, strand elongations, deviation of ±7 percent between measured and theoretical elongations, false work construction and removal. If jacking is done at both ends of the bridge, the minimum strand elongation due to the specified jacking load for the end jacked first as well as the end jacked last should be indicated. When calculating strand elongation, use Es = 28,000 ksi. The calculated strand elongations at the ends of the bridge are compared with the measured field values to ensure that the friction coefficients (and hence the levels of prestressing throughout the structure) agree with the values assumed by the designer.

The tendons shall be jacked in a sequence that avoids causing overstress or tension in the bridge.

The following post-tensioning notes for the sequence of stressing of longitudinal tendons should be shown in the Contract Plans:

B. Post-Tensioning Notes ~ Cast-in-Place Post-tensioned Girders

1. The cast-in-place concrete in superstructure shall be Class ….. The minimum compressive strength of the cast-in-place concrete at the time of post-tensioning shall be … ksi.
2. The minimum prestressing load after seating for each web shall be …. kips. Each web shall have a minimum of …. strands.
3. The design is based on …. inch diameter low relaxation strands, a jacking load of …. kips each web, an anchor set of 3/8 inch, a curvature friction coefficient, μ= 0.20, and a wobble friction coefficient, k = 0.0002 /ft. The actual anchor set and jacking force used by the contractor shall be specified in the shop plans and included in the transfer force calculations.
4. The design is based on the estimated prestress loss of post-tensioned prestressing strands of …. ksi due to steel relaxation, elastic shortening, creep and shrinkage of concrete.
5. The contractor shall submit the stressing sequence and elongation calculations to the engineer for approval. All losses due to tendon vertical and horizontal curvature must be included in elongation calculations. The stressing sequence shall meet the following criteria:

a) The prestressing force shall be distributed with an approximately equal amount in each web and shall be placed symmetrically about the centerline of the bridge.

b) No more than one-half of the prestressing force in any web may be stressed before an equal force is stressed in the adjacent webs. At no time during stressing operation will more than one-sixth of the total prestressing force is applied eccentrically about the centerline of bridge.

6. The maximum outside diameter of the duct shall be …. inches. The area of the duct shall be at least 2.5 times the net area of the prestressing steel in the duct.

7. All tendons shall be stressed from pier … .

5.9 Spliced Precast Girders

5.9.1 Definitions

The provisions herein apply to precast girders fabricated in segments that are spliced longitudinally to form the girders in the final structure. The cross-section for this type of bridges is typically comprised of bulb tee girders or trapezoidal tub girders with a composite cast-in-place deck. WSDOT Standard drawings for Spliced I-girders are shown in Appendix A Drawings 5.9-A1 through A5-A3, and for Spliced-Tub girders are shown in Appendix A Drawings 5.9-A4 and 5 span capability of precast spliced girders are shown in Appendix A Tables 5.9-A1-1 for I-girders and A5.9-A1-2 for Trapezoidal Tub girders.

Precast deck bulb tee girder bridges may also be fabricated in segments and spliced longitudinally for final structure. Splicing in this type of girder because of the significant weight of the cross-section, which is comprised of both a girder and deck, may exceed usual limits for handling and transportation may be beneficial. Spliced structures of this type, which have longitudinal joints in the deck between each deck girder, shall comply with the additional requirements of AASTO LRFD Specifications Section 5.14.4.3.

Spliced precast girder bridges may be distinguished from what is referred to as “segmental construction” in Bridge Specifications by several features which typically include:

- The lengths of some or all segments in a bridge are a significant fraction of the span length rather than having a number of segments in each span.
- Design of joints between girder segments at the service limit state does not typically govern the design for the entire length of the bridge for either construction or for the completed structure.
- Wet-cast closure joints are usually used to join girder segments rather than match-cast joints.
- The bridge cross-section is comprised of several individual girders with a cast-in-place concrete composite deck rather than precasting the full width and depth of the superstructure as one piece. In some cases, the deck may be divided into pieces that are integrally cast with each girder. Connecting the girders across the longitudinal joints completes a bridge of this type.
- Girder sections are used, such as bulb tee, deck bulb tee or trapezoidal tub girders, rather than closed cell boxes with wide monolithic flanges.
- Provisional ducts are required for segmental construction to provide for possible adjustment of prestress force during construction. Similar requirements are not given for spliced precast girder bridges because of the redundancy provided by a greater number of webs and tendons, and typically lower friction losses because of fewer joint locations.

- The method of construction and any required temporary support is of paramount importance in the design of spliced precast girder bridges. Such considerations often govern final conditions in the selection of section dimensions and reinforcing and/or prestressing.

All supports required prior to the splicing of the girder shall be shown on the contract documents, including elevations and reactions. The stage of construction during which the temporary supports are removed shall also be shown on the contract documents. Stresses due to changes in the structural system, in particular, the effects of the application of load to one structural system and its removal from a different structural system, shall be accounted for. Redistribution of such stresses by creep shall be taken into account and allowance shall be made for possible variations in the creep rate and magnitude.

Prestress losses in spliced precast girder bridges may be estimated using the provisions of BDM Section 5.1.4. The effects of combined pretensioning and post tensioning and staged post tensioning shall be considered. When required, the effects of creep and shrinkage in spliced precast girder bridges may be estimated using the provisions of BDM Section 5.1.1.

5.9.2 WSDOT Criteria for use of Spliced Girders

Long span prestressed girder bridges may result in increased cost due to fabrication, shipping and erection of girders. Providing alterative design to long span prestressed girders based on the limitations in shipping weight and prestressing may eliminate the excessive cost through competitive biding. The following procedure for alternative design to prestressed girders in the contract plans shall be considered

- All prestressed girders with shipping weight less than 155 kips (144 ft for W83G and 134 ft for W95G) shall be pre-tensioned only (no alternative design).
- All prestressed girders with shipping weight between 156 and 200 kips shall include both pre-tensioned and post-tensioned spliced-girder alternatives with post-tensioning applied after slab casting.
- All prestressed girders with shipping weight exceeding 200 kips shall be post-tensioned spliced-girder with post-tensioning applied after slab casting.

When spliced-girder alternative is considered in the contract plans, the substructure shall be designed and detailed for the maximum force effect case only (no alternative design for substructure).

5.9.3 Girder Segment Design

A. Design Considerations

Stress limits for temporary concrete stresses in girder segments before losses and stress limits for concrete stresses in girder segments at the service limit state after losses specified in BDM Section 5.1.3 shall apply at each stage of pretensioning or post tensioning with due consideration for all applicable loads during construction. The concrete strength at the time the stage of prestressing is applied shall be substituted for f'_{ci} in the stress limits.

The designer shall consider requirements for bracing of the girder segments once they have been erected on the substructure. Any requirements for temporary or permanent bracing during subsequent stages of construction, along with the contractor's responsibilities for designing and placing them, shall be specified in the contract documents.

B. Post tensioning

Post tensioning may be applied either before and/or after placement of deck concrete. Part of the post tensioning may be applied prior to placement of the deck concrete, with the remainder placed after deck concrete placement. In the case of multistage post tensioning, ducts for tendons to be tensioned before the slab concrete shall not be located in the slab.

All post tensioning tendons shall be fully grouted after stressing. Prior to grouting of post tensioning ducts, gross cross-section properties shall be reduced by deducting the area of ducts and void areas around tendon couplers.

Where some or all post tensioning is applied after the deck concrete is placed, fewer post tensioning tendons and a lower concrete strength in the closure joint may be required. However, deck replacement, if necessary, is difficult to accommodate with this construction sequence. Where all of the post tensioning is applied before the deck concrete is placed, a greater number of post tensioning tendons and a higher concrete strength in the closure joint may be required. However, in this case, the deck can be replaced if necessary.

5.9.4 Joints Between Segments

A. General

Cast-in-place closure joints are typically used in spliced girder construction. The sequence of placing concrete for the closure joints and deck shall be specified in the contract documents. Match-cast joints shall not be specified for spliced girder bridges unless approved by the Bridge Design Engineer. Prestress, dead load and creep effects may cause rotation of the faces of the match-cast joints prior to splicing. If match cast joint is specified, the procedures for splicing the girder segments that overcome this rotation to close the match-cast joint should be shown on the contract plans.

B. Location of Closure Joints

The location of intermediate diaphragms shall be offset by at least 2’-0” from the edge of cast-in-place closure joints. The intent of the joint width requirement is to allow proper compaction of concrete in the cast-in-place closure joint. A wider closure joint may be used to provide more room to accommodate tolerances for potential misalignment of ducts within girder segments and misalignment of girder segments at erection.

In horizontally curved spliced girder bridges, intermediate diaphragms could be located at the cast-in-place closure joints if straight segments are spliced with deflection points at closures. In this case, diaphragm could be extended beyond the face of exterior girder for improved development of diaphragm reinforcement.

C. Details of Closure Joints

The width of a closure joint between precast concrete segments shall allow for the splicing of steel whose continuity is required by design considerations and the accommodation of the splicing of post tensioning ducts. The width of a closure joint shall not be less than 24.0 in.

Web reinforcement, A_v/s within the joint shall be the larger of that in the adjacent girders. The face of the precast segments at closure joints shall be specified as intentionally roughened surface.

D. Joint Design

Stress limits for temporary concrete stresses in joints before losses specified in BDM Section 5.1.3 for shall apply at each stage of prestressing post tensioning. The concrete strength at the time the stage of prestressing is applied shall be substituted for f'_{ci} in the stress limits.

Stress limits for concrete stresses in joints at the service limit state after losses specified in BDM Section 5.1.3 for shall apply. These stress limits shall also apply for intermediate load stages, with the concrete strength at the time of loading substituted for f'_c in the stress limits. The compressive strength of the closure joint concrete at a specified age shall be compatible with design stress limitations. Resistance factors for cast-in-place closure joints shall be 0.95 for flexure and 0.9 for shear.

5.9.5 Review of shop plans for precast post-tensioned spliced-girders

Shop drawings for precast post-tensioned spliced-girders should be reviewed by the designer (or Bridge Technical Advisor for non bridge office projects) and consulted with the concrete specialist if needed. Shop drawings, after reviewed by the design engineer should be stamped with the official rubber seal and returned to the bridge construction support office. Review of shop drawing must include:

1. All prestressing strands shall be of ½" or 0.6" diameter grade 270 low relaxation uncoated strands.
2. Number of strands per segment shall be specified in the shop drawings and shall conform to the contract plans.
3. Pretensioning strands jacking stresses shall not exceed $0.75f_{pu}$.
4. Strand placement patterns shall be verified per contract plans.
5. Temporary Strand placement patterns, location and size of blockouts for cutting strands shall be verified per contract plans.
6. Procedure for cutting temporary strands and patching the blockouts shall be specified.
7. Number and length of extended strands and rebars at girder ends shall be verified per contract plans.
8. Location of holes and shear keys for intermediate and end diaphragms shall be verified per contract plans.
9. Location and size of bearing recesses shall be verified per contract plans.
10. Saw tooth at girder ends shall be verified per contract plans.
11. Location and size of lifting loops or lifting bars shall be verified per contract plans.
12. Number and size of horizontal and vertical reinforcement shall be verified per contract plans.
13. Segment length and end skew shall be verified per contract plans.
14. Tendon profile and tendon placement pattern shall be verified per contract plans.
15. Duct size shall be based on the duct area at least 2.5 times the total area of prestressing strands.

16. Anchor set shall conform to the contract plans. The post-tensioning design is typically based on an anchor set of 3/8".

17. Maximum number of strands per tendon shall not exceed 31 - ½" diameter strands or 22 - 0.6" diameter strands per Standard Specifications 6-02.3(26) D.

18. Jacking force per girder shall be verified per contract plans.

19. Prestress force after anchor set (lift-off force) shall conform to contract plans.

20. Number of strands per web shall be specified in the shop drawings and shall conform to the contract plans.

21. Anchorage system shall conform to pre-approved list of post-tensioning system per BDM Appendix B. The anchorage assembly dimensions and reinforcement detailing shall conform to the corresponding post-tensioning catalog.

22. The curvature friction coefficient and wobble friction coefficient shall conform to the contract plans. The curvature friction coefficient of μ= 0.15 for bridges less than 400 feet, μ= 0.2 for bridges between 400 feet and 800 feet, and μ= 0.25 for bridges longer than 800 feet. The wobble friction coefficient of k = 0.0002 /ft is often used. These coefficients may be revised by the post-tensioning supplier if approved by the design engineer and conform to the Standard Specifications 6.02.3(26) E.

23. Post-tensioning stressing sequence shall be in accordance with the contract plan post-tensioning Notes.

24. Tendon stresses shall not exceed as specified per BDM figure 6.4.2-2:
$0.80f_{pu}$ at anchor ends immediately before seating.
$0.70f_{pu}$ at anchor ends immediately after seating.
$0.74f_{pu}$ at the end point of length influenced by anchor set.

25. Elongation calculations for each jacking operation shall be verified. If the difference in tendon elongation exceeds 2%, the elongation calculations shall be separated for each tendon per Standard Specification 6-02.3(26) A.

26. Vent points shall be provided at all high points along tendon.

27. Drain holes shall be provided at all low points along tendon.

28. The concrete strength at the time of post-tensioning, f'ci shall not be less than 4000 psi per standard specifications 6-02.3(26) E-1. Different concrete strength may be used if specified in the contract plans.

29. Concrete stresses at the anchorage shall be checked per Standard specifications 6-02.3(26) B-1 for bearing type anchorage. For other type of anchorage assemblies, if not covered in the BDM Appendix B for pre-approved list of post-tensioning system, testing per Standard Specifications 6-02.3(26) B-2 is required.

30. Concrete stresses at cast-in-place closures shall conform to allowable stresses of Table 5-15.

5.9.6 Post-Tensioning Notes ~ Precast Post-Tensioning Spliced-Girders

1. The cast-in-place concrete in deck slab shall be Class 4000D. The minimum compressive strength of the cast-in-place concrete at the wet joint at the time of post-tensioning shall be …. ksi.

2. The minimum prestressing load after seating and the minimum number of prestressing strands for each girder shall be as shown in post-tensioning table.

3. The design is based on ….. inch diameter low relaxation strands with a jacking load for each girder as shown in post-tensioning table, an anchor set of 3/8 inch a curvature friction coefficient, μ= 0.20 and a wobble friction coefficient, k = 0.0002 /ft. The actual anchor set used by the contractor shall be specified in the shop plans and included in the transfer force calculations.

4. The design is based on the estimated prestress loss of post-tensioned prestressing strands as shown in post-tensioning table due to steel relaxation, elastic shortening, creep and shrinkage of concrete.

5. The contractor shall submit the stressing sequence and elongation calculations to the engineer for approval. All losses due to tendon vertical and horizontal curvature must be included in elongation calculations. The stressing sequence shall meet the following criteria:

6. The prestressing force shall be distributed with an approximately equal amount in each web and shall be placed symmetrically about the centerline of the bridge.

7. No more than one-half of the prestressing force in any web may be stressed before an equal force is stressed in the adjacent webs. At no time during stressing operation will more than one-sixth of the total prestressing force is applied eccentrically about the centerline of bridge.

8. The maximum outside diameter of the duct shall be …. inches. The area of the duct shall be at least 2.5 times the net area of the prestressing steel in the duct.

9. All tendons shall be stressed from pier …. .

5.99 Bibliography

1. AASHTO, LRFD Bridge Design Specifications, 2nd Edition, American Association of State Highway and Transportation Officials, Washington, D.C.

2. AASHTO LRFD Bridge Construction Specifications, 1st Edition 1998, AASHTO, Washington, D.C., 1998.

3. WSDOT Standard Specifications for Highway Bridges and Municipal Construction, Olympia, Washington 98501.

4. ACI Committee 317, Reinforced Concrete Design Handbook — Working Stress Method, Publication SP-3, American Concrete Institute, 3rd Ed., 1965, 271 pp.

5. Seguirant, S.J., "New Deep WSDOT Standard Sections Extend Spans of Prestressed Concrete Girders," PCI JOURNAL, V. 43, No. 4, July-August 1998, pp. 92-119.

6. PCI Bridge Design Manual, Precast/Prestressed Concrete Institute, Chicago, IL, 1997.

7. ACI 318-02, Building Code Requirements for Reinforced Concrete and Commentary, American Concrete Institute, 1989, pp.353.

8. Ghosh, S. K. and Rabbat, B. G., Editors, Notes on ACI 318-89, Building Code Requirements for Reinforced Concrete with Design Applications, Portland Cement Association, 5th ed., 1990.

9. ACI-ASCE Committee 343, Analysis and Design of Reinforced Concrete Bridge Structures, American Concrete Institute, 1988, 162 pp.

10. Hsu, T. T. C., Torsion of Reinforced Concrete, Van Nostrand Reinhold Co., New York, 1st Ed., 1984, 516 pp.

11. Collins, M. P. and Mitchell, D., Shear and Torsion Design of Prestressed and Non-Prestressed Concrete Beams, PCI Journal, September-October, 1980, pp. 32-100.

12. Mirza, S.A., and Furlong, R.W., Design of Reinforced and Prestressed Concrete Inverted T Beams for Bridge Structures, PCI Journal, Vol. 30, No. 4, July-August 1985, pp. 112-136.

13. Rabbat, B.G., Reader Comments Design of Reinforced and Prestressed Concrete inverted T Beams for Bridge Structures, PCI Journal, Vol. 31, No. 3, May-June 1986, pp. 157-163.

14. AASHTO Standard Specifications for Highway Bridges, 16th Edition, AASHTO, Washington, D.C., 1996.

15. ACI Committee 345, Guide for Widening Highway Bridges, ACI Structural Journal, July/August, 1992, pp. 451-466.

16. Babaei, K. and Hawkins, N. M., Bending/Straightening and Grouting Concrete Reinforcing Steel: Review of WSDOT's Specifications and Proposed Modifications, Final Report WA-RD 168.1, Washington State Transportation Center (TRAC), December 1988, 75 pp.

17. PCI Design Handbook, Precast and Prestressed Concrete, Fifth Edition, Precast/Prestressed Concrete Institute, Chicago, IL, 1999.

18. Mast, R.F., "Lateral Stability of Long Prestressed Concrete Beams, Part 1," PCI JOURNAL, V. 34, No. 1, January-February 1989, pp. 34-53.

19. Mast, R.F., "Lateral Stability of Long Prestressed Concrete Beams, Part 2," PCI JOURNAL, V. 38, No. 1, January-February 1993, pp. 70-88.

20. Imper, R.R., and Laszlo, G., "Handling and Shipping of Long Span Bridge Beams," PCI JOURNAL, V. 32, No. 6, November-December 1987, pp. 86-101.

21. Preapproved Repair Procedures, WSDOT Manual for Repair of Concrete.

22. Transportation Research Board Report No. 226 titled, Damage Evaluation and Repair Methods for Prestressed Concrete Bridge Members.

23. Transportation Research Board Report No. 280 titled, Guidelines for Evaluation and Repair of Prestressed Concrete Bridge Members.

24. Post-Tensioned Box Girder Bridge Manual, Post-Tensioning Institute, 301 West Osborn, Phoenix, Arizona.

25. Prestressed Concrete Structures T. Y. Lin, Wiley.

26. Prestressed Concrete Vol. I and II, Guyon, Wiley

27. Design of Concrete Bridges for Temperature Gradients, ACI Journal, May 1978.

28. Cracking of Voided Post-Tensioned Concrete Bridge Decks, Ministry of Transportation and Communications, Toronto, Ontario, Canada

29. Post-Tensioned Bridges - Design & Construction Manual of WCRSI, 1499 Bayshore Highway, Burlingame, California, Copyright 1969.

30. Analysis & Design of Reinforced Concrete Bridge Structures, ACI Committee 443 Report 71-14 ACI Journal, April 1974.

31. Mast, R. F., "Unified Design Provisions for Reinforced and Prestressed Concrete Flexural and Compression Members", ACI Structural Journal, V. 89, No. 2, March-April 1992, pp. 185-199. See also discussions by R.K. Devalapura and M.K. Tadros, C.W. Dolan and J.V. Loscheider and closure to discussions in V. 89, No. 5, September-October 1992, pp. 591-593.


32. Weigel, J.A., Seguirant, S.J., Brice, R., and Khaleghi, B., “High Performance Precast, Prestressed Concrete Girder Bridges in Washington State,” PCI JOURNAL, V. 48, No. 2, March-April 2003, pp. 28-52.


33. Seguirant, S. J., Brice, R., and Khaleghi, B., “Flexural Strength of Reinforced and Prestressed Concrete T-Beams,” ,” PCI JOURNAL, V. 50, No. 1, January-February 2005, pp 44-73.

34. Baran, E., Schultz, A. E., and French, C. E., “Analysis of the Flexural Strength of Prestressed Concrete Flanged Sections”, PCI JOURNAL, V. 50, No. 1, January-February 2005, pp. 74-93.

RECOMMENDED END HOOKS
All Grades
D = Finished bend diameter


Bar Size	D	180° HOOKS		90° HOOKS
		A or G	J	A or G
#3	2¼	5	3	6
#4	3	6	4	8
#5	3¾	7	5	10
#6	4½	8	6	1-0
#7	5¼	10	7	1-2
#8	6	11	8	1-4
#9	9½	1-3	11¾	1-7
#10	10¾	1-5	1-1¼	1-10
#11	12	1-7	1-2¾	2-0
#14	18¼	2-3	1-9¾	2-7
#18	24	3-0	2-4½	3-5





STIRRUP AND TIE HOOK DIMENSIONS
All Grades

Bar Size	D (in.)	135° HOOKS	
		Hook A or G	H Approx.
#3	1½	4¼	3
#4	2	4½	3
#5	2½	5½	3¾
#6	4½	8	4½
#7	5¼	9	5¼
#8	6	10½	6




135° SEISMIC STIRRUP/TIE
HOOK DIMENSIONS
All Grades

Bar Size	D (in.)	135° HOOKS	
		Hook A or G	H Approx.
#3	1½	4¼	3
#4	2	4½	3
#5	2½	5½	3¾
#6	4½	8	4½
#7	5¼	9	5¼
#8	6	10½	6

Standard Hooks
Figure 5-A-1

PREFERED MINIMUM CLEARANCE AND SPACING
FOR BEAMS AND COLUMNS.
(DISTANCES IN INCHES)

Bar Size	A	B	C	D
#4	3¼	4	-	-
5	3½	4¼	-	-
6	3¾	4½	-	-
7	4	4¾	-	-
8	4¼	5	4½	5½
9	4½	5¼	4¾	6
10	4¾	5½	5	6¼
11	5	6	5⅛	6½
14	5½	7	5½	7¼
18	6	8½	6¾	9



Minimum Reinforcement Clearance and Spacing for Beams and Columns
Figure 5-A-2

Bar Size	Weight (lbs/ft)	Nominal Diameter (in)	Outside Diameter (in)	Area (in^2)	Max. Bar Length (Normal Length for Barlist) (ft)
#3	0.376	0.375	0.42	0.11	40 (30)
#4	0.668	0.500	0.56	0.20	40 (40)
#5	1.043	0.625	0.7	0.31	60 (40)
#6	1.502	0.750	0.83	0.44	60 (60)
#7	2.044	0.875	0.96	0.60	60 (60)
#8	2.670	1.000	1.1	0.79	72 (60)
#9	3.400	1.128	1.24	1.00	72 (60)
#10	4.303	1.270	1.4	1.27	72 (60)
#11	5.313	1.410	1.55	1.56	90 (60)
#14	7.65	1.693	1.86	2.25	90 (60)
#18	13.60	2.257	2.48	4.00	90 (60)

Reinforcing Bar Properties
Table 5-A-3

Tension Development Length of Uncoated Deformed Bars								
Bar Size	f'_c = 3000 psi		f'_c = 4000 psi		f'_c = 5000 psi		f'_c = 6000 psi	
	Top Bars	Others	Top Bars	Others	Top Bars	Others	Top Bars	Others
3	1’-5”	1’-0”	1’-5”	1’-0”	1’-5”	1’-0”	1’-5”	1’-0”
4	1’-5”	1’-0”	1’-5”	1’-0”	1’-5”	1’-0”	1’-5”	1’-0”
5	1’-9”	1’-3”	1’-9”	1’-3”	1’-9”	1’-3”	1’-9”	1’-3”
6	2’-3”	1’-8”	2’-2”	1’-6”	2’-2”	1’-6”	2’-2”	1’-6”
7	3’-1”	2’-3”	2’-8”	1’-11”	2’-6”	1’-9”	2’-6”	1’-9”
8	4’-1”	2’-11”	3’-6”	2’-6”	3’-2”	2’-3”	2’-11”	2’-1”
9	5’-2”	3’-8”	4’-6”	3’-2”	4’-0”	2’-10”	3’-8”	2’-7”
10	6’-6”	4’-8”	5’-8”	4’-1”	5’-1”	3’-8”	4’-8”	3’-4”
11	8’-0”	5’-9”	6’-11”	5’-0”	6’-3”	4’-5”	5’-8”	4’-1”
14	10’-11”	7’-10”	9’-5”	6’-9”	8’-5”	6’-1”	7’-9”	5’-6”
18	14’-1”	10’-1”	12’-3”	8’-9”	10’-11”	7’-10”	10’-0”	7’-2”
Tension Development Length of Epoxy Coated Deformed Bars								
Bar Size	f'_c = 3000 psi		f'_c = 4000 psi		f'_c = 5000 psi		f'_c = 6000 psi	
	Top Bars	Others	Top Bars	Others	Top Bars	Others	Top Bars	Others
3	1’-9”	1’-6”	1’-9”	1’-6”	1’-9”	1’-6”	1’-9”	1’-6”
4	1’-9”	1’-6”	1’-9”	1’-6”	1’-9”	1’-6”	1’-9”	1’-6”
5	2’-2”	1’-11”	2’-2”	1’-11”	2’-2”	1’-11”	2’-2”	1’-11”
6	2’-9”	2’-5”	2’-7”	2’-3”	2’-7”	2’-3”	2’-7”	2’-3”
7	3’-9”	3’-4”	3’-3”	2’-11”	3’-0”	2’-8”	3’-0”	2’-8”
8	4’-11”	4’-4”	4’-3”	3’-9”	3’-10”	3’-5”	3’-6”	3’-1”
9	6’-3”	5’-6”	5’-5”	4’-9”	4’-10”	4’-3”	4’-5”	3’-11”
10	7’-11”	7’-0”	6’-10”	6’-1”	6’-2”	5’-5”	5’-7”	4’-11”
11	9’-9”	8’-7”	8’-5”	7’-5”	7’-6”	6’-8”	6’-11”	6’-1”
14	13’-3”	11’-8”	11’-6”	10’-1”	10’-3”	9’-1”	9’-4”	8’-3”
18	17’-1”	15’-1”	14’-10”	13’-1”	13’-3”	11’-8”	12’-1”	10’-8”

Top bars are so placed that more than 12” of concrete is cast below the reinforcement.
Modifications factor for spacing >=6” and side cover>=3” = 0.8.
Modification factor for reinforcements enclosed in spirals = 0.75.
Minimum development length = 12”.

Tension Development Length of Deformed Bars
Table 5-A-4

Compression Development Length and Minimum Lap splice of Uncoated Deformed Bars

Bar Size	Compression Development Length					Min. Lap Splice f'c > 3.0 ksi
	Straight Bars				Hooked Bars	
	f'c = 3 ksi	f'c = 4 ksi	f'c = 5 ksi	f'c = 6 ksi		
3	1'-0"	1'-0"	1'-0"	1'-0"	6"	2'-0"
4	1'-0"	1'-0"	1'-0"	1'-0"	7"	2'-0"
5	1'-2"	1'-0"	1'-0"	1'-0"	9"	2'-0"
6	1'-5"	1'-3"	1'-2"	1'-2"	10"	2'-0"
7	1'-8"	1'-5"	1'-4"	1'-4"	1'-0"	2'-3"
8	1'-10"	1'-7"	1'-6"	1'-6"	1'-2"	2'-6"
9	2'-1"	1'-10"	1'-9"	1'-9"	1'-3"	2'-10"
10	2'-4"	2'-1"	1'-11"	1'-11"	1'-5"	3'-3"
11	2'-7"	2'-3"	2'-2"	2'-2"	1'-7"	3'-7"
14	3'-1"	2'-9"	2'-7"	2'-7"	2'-10	4'-3"
18	4'-2"	3'-7"	3'-5"	3'-5"	3'-7"	5'-8"

Compression Development Length and Minimum Lap splice of Epoxy Coated Deformed Bars

Bar Size	Compression Development Length					Min. Lap Splice f'c > 3.0 ksi
	Straight Bars				Hooked Bars	
	f'c = 3 ksi	f'c = 4 ksi	f'c = 5 ksi	f'c = 6 ksi		
3	1'-0"	1'-0"	1'-0"	1'-0"	6"	2'-0"
4	1'-0"	1'-0"	1'-0"	1'-0"	7"	2'-0"
5	1'-2"	1'-0"	1'-0"	1'-0"	9"	2'-0"
6	1'-5"	1'-3"	1'-2"	1'-2"	10"	2'-0"
7	1'-8"	1'-5"	1'-4"	1'-4"	1'-0"	2'-3"
8	1'-10"	1'-7"	1'-6"	1'-6"	1'-2"	2'-6"
9	2'-1"	1'-10"	1'-9"	1'-9"	1'-3"	2'-10"
10	2'-4"	2'-1"	1'-11"	1'-11"	1'-5"	3'-3"
11	2'-7"	2'-3"	2'-2"	2'-2"	1'-7"	3'-7"
14	3'-1"	2'-9"	2'-7"	2'-7"	2'-10	4'-3"
18	4'-2"	3'-7"	3'-5"	3'-5"	3'-7"	5'-8"

Notes:

1. Where excess bar area is provided, the development length may be reduced by ratio of required area to provided area.
2. When splicing smaller bars to larger bars, the lap splice shall be the larger of the minimum compression lap splice or development length of the larger bar in compression.

Compression Development Length and Minimum Lap Splice of Grade 60 Bars
Table 5-A-5

Bar Size	f'_c = 3000 psi		f'_c = 4000 psi		f'_c = 5000 psi		f'_c = 6000 psi	
	Side Cover < 2½" Cover on Tail < 2"	Side Cover >= 2½" Cover on Tail >= 2"	Side Cover < 2½" Cover on Tail < 2"	Side Cover >= 2½" Cover on Tail >= 2"	Side Cover < 2½" Cover on Tail < 2"	Side Cover >= 2½" Cover on Tail >= 2"	Side Cover < 2½" Cover on Tail < 2"	Side Cover >= 2½" Cover on Tail >= 2"
3	0'-9"	0'-6"	0'-8"	0'-6"	0'-7"	0'-6"	0'-6"	0'-6"
4	0'-11"	0'-8"	0'-10"	0'-7"	0'-9"	0'-7"	0'-8"*	0'-7"
5	1'-2"	0'-10"	1'-0"	0'-9"	0'-11"	0'-8"	0'-10"	0'-7"
6	1'-5"	1'-0"	1'-3"	0'-10"	1'-1"	0'-9"	1'-0"	0'-8"
7	1'-8"	1'-2"	1'-5"	1'-0"	1'-3"	0'-11"	1'-2"	0'-10"
8	1'-10"	1'-4"	1'-7"	1'-2"	1'-5"	1'-0"	1'-4"	0'-11"
9	2'-1"	1'-6"	1'-10"	1'-3"	1'-8"	1'-2"	1'-6"	1'-1"
10	2'-4"	1'-8"	2'-1"	1'-5"	1'-10"	1'-3"	1'-8"	1'-2"
11	2'-7"	1'-10"	2'-3"	1'-7"	2'-0"	1'-5"	1'-10"	1'-4"
14	3'-1"	3'-1"	2'-9"	2'-9"	2'-5"	2'-5"	2'-3"	2'-3"
18	4'-2"	4'-2"	3'-7"	3'-7"	3'-3"	3'-3"	2'-11"	2'-11"

Modification factor for Epoxy coated reinforcement = 1.2.

Tension Development Length of 90º and 180º Standard Hooks

Table 5-A-6

Tension Lap Splice Lengths of Grade 60 Uncoated Bars ~ Class B

Bar Size	f'_c = 3000 psi		f'_c = 4000 psi		f'_c = 5000 psi		f'_c = 6000 psi	
	Top Bars	Others	Top Bars	Others	Top Bars	Others	Top Bars	Others
3	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"
4	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"	2'-0"
5	2'-4"	2'-0"	2'-4"	2'-0"	2'-4"	2'-0"	2'-4"	2'-0"
6	2'-11"	2'-1"	2'-9"	2'-0"	2'-9"	2'-0"	2'-9"	2'-0"
7	4'-0"	2'-11"	3'-6"	2'-6"	3'-3"	2'-4"	3'-3"	2'-4"
8	5'-3"	3'-9"	4'-7"	3'-3"	4'-11"	2'-11"	3'-9"	2'-8"
9	6'-8"	4'-9"	5'-9"	4'-2"	5'-2"	3'-9"	4'-9"	3'-5"
10	8'-6"	6'-1"	7'-4"	5'-3"	6'-7"	4'-8"	6'-0"	4'-4"
11	10'-5"	7'-5"	9'-0"	6'-5"	8'-1"	5'-9"	7'-4"	5'-3"
14	Lap Splices		Lap Splices		Lap Splices		Lap Splices	
18	Not Allowed		Not Allowed		Not Allowed		Not Allowed	

Tension Lap Splice Lengths of Grade 60 Epoxy Coated Bars ~ Class B

Bar Size	f'_c = 3000 psi		f'_c = 4000 psi		f'_c = 5000 psi		f'_c = 6000 psi	
	Top Bars	Others	Top Bars	Others	Top Bars	Others	Top Bars	Others
3	2'-3"	2'-0"	2'-3"	2'-0"	2'-3"	2'-0"	2'-3"	2'-0"
4	2'-3"	2'-0"	2'-3"	2'-0"	2'-3"	2'-0"	2'-3"	2'-0"
5	2'-10"	2'-6"	2'-10"	2'-6"	2'-10"	2'-6"	2'-10"	2'-6"
6	3'-7"	3'-2"	3'-4"	3'-0"	3'-4"	3'-0"	3'-4"	3'-0"
7	4'-11"	4'-4"	4'-3"	3'-9"	3'-11"	3'-5"	3'-11"	3'-5"
8	6'-5"	5'-8"	5'-7"	4'-11"	5'-0"	4'-5"	4'-6"	4'-0"
9	8'-1"	7'-2"	7'-0"	6'-2"	6'-3"	5'-7"	5'-9"	5'-1"
10	10'3"	9'-1"	8'-11"	7'-10"	8'-0"	7'-0"	7'-3"	6'-5"
11	12'-8"	11'-2"	10'-11"	9'-8"	9'-9"	8'-0"	8'-11"	7'-11"
14	Lap Splices		Lap Splices		Lap Splices		Lap Splices	
18	Not Allowed		Not Allowed		Not Allowed		Not Allowed	

Top bars are so placed that more than 12" of concrete is cast below the reinforcement.

Modification factor for spacing >=6" and side cover>=3" = 0.8.

Modification factor for reinforcements enclosed in spirals = 0.75.

Minimum development length = 12".

Definition of splice classes:
- Class A: Low stressed bars ~ 75% or less are spliced
- Class B: Low stressed bars ~ more than 75% are spliced
  High stressed bars ~ 50% or less are spliced
- Class C: High stressed bars ~ more than 50% are spliced

Class B lap splice is the preferred and most commonly used by Bridge Office.

Modification factor for Class A = 0.77

Modification factor for Class C = 1.31

Modification factor for 3-bar bundle = 1.2

Tension Lap Splice Lengths of Grade 60 Uncoated Bars ~ Class B

Table 5-A-7

Uncoated Prestressing Strands Properties and Development Length

Strand Diameter (in)	Weight (lbs/ft)	Nominal Diameter (in)	Area (in^2)	Transfer length (in)	Develop. Length k = 1.0 (ft)	Develop. Length k = 1.6 (ft)
3/8	0.29	0.375	0.085	22.5	5.05	8.09
7/16	0.40	0.438	0.115	26.3	5.90	9.43
½	0.52	0.500	0.153	30.0	6.74	10.78
½ S	0.53	0.500	0.167	30.0	6.74	10.78
9/16	0.65	0.563	0.192	33.8	7.58	12.13
0.60	0.74	0.600	0.217	36.0	8.09	12.94

Epoxy Coated Prestressing Strands Properties and Development Length

Strand Diameter (in)	Weight (lbs/ft)	Nominal Diameter (in)	Area (in^2)	Transfer length (in)	Develop. Length k = 1.0 (ft)	Develop. Length k = 1.6 (ft)
3/8	0.31	0.415	0.085	24.9	5.59	8.95
7/16	0.42	0.478	0.115	28.7	6.44	10.31
½	0.54	0.540	0.153	32.4	7.28	11.64
0.60	0.64	0.648	0.217	38.9	8.73	13.97

Prestressing Strand Properties and Development Length

Table 5-A-8

ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$
0.0010	59.3	0.0053	298.1	0.0097	515.4	0.0141	705.2
0.0011	65.1	0.0054	303.4	0.0098	520.0	0.0142	709.2
0.0012	71.0	0.0055	308.6	0.0099	524.6	0.0143	713.2
0.0013	76.8	0.0056	313.8	0.0100	529.2	0.0144	717.2
0.0014	82.6	0.0057	319.0	0.0101	533.8	0.0145	721.1
0.0015	88.4	0.0058	324.2	0.0102	538.3	0.0146	725.1
0.0016	94.2	0.0059	329.4	0.0103	542.9	0.0147	729.0
0.0017	100.0	0.0060	334.5	0.0104	547.4	0.0148	732.9
0.0018	105.7	0.0061	339.7	0.0105	551.9	0.0149	736.8
0.0019	111.4	0.0062	344.8	0.0106	556.4	0.0150	740.7
0.0020	117.2	0.0063	349.9	0.0107	560.9	0.0151	744.6
0.0021	122.9	0.0064	355.0	0.0108	565.4	0.0152	748.4
0.0022	128.6	0.0065	360.1	0.0109	569.9	0.0153	752.3
0.0023	134.3	0.0066	365.2	0.0110	574.3	0.0154	756.1
0.0024	139.9	0.0067	370.2	0.0111	578.8	0.0155	759.9
0.0025	145.6	0.0068	375.3	0.0112	583.2	0.0156	763.7
0.0026	151.2	0.0069	380.3	0.0113	587.6	0.0157	767.5
0.0027	156.8	0.0070	385.3	0.0114	592.0	0.0158	771.2
0.0028	162.4	0.0071	390.3	0.0115	596.4	0.0159	775.0
0.0029	168.0	0.0072	395.0	0.0116	600.7	0.0160	778.7
0.0030	173.6	0.0073	400.3	0.0117	605.1	ρ_{max} 01601	782.5
0.0031	179.2	0.0074	405.2	0.0118	609.4		
0.0032	184.8	0.0075	410.2	0.0119	613.7		
0.0033	190.3	0.0076	415.1	0.0120	618.0		
0.0034	195.8	0.0077	420.0	0.0121	622.3		
0.0035	201.3	0.0078	424.9	0.0122	626.6		
0.0036	206.8	0.0079	429.8	0.0123	630.9		
0.0037	212.3	0.0080	434.7	0.0124	635.1		
0.0038	217.8	0.0081	439.5	0.0125	639.4		
0.0039	223.2	0.0082	444.4	0.0126	643.6		
0.0040	228.7	0.0083	449.2	0.0127	647.8		
0.0041	234.1	0.0084	454.0	0.0128	652.0		
0.0042	239.5	0.0085	458.8	0.0129	656.2		
0.0043	244.9	0.0086	463.6	0.0130	660.3		
0.0044	250.3	0.0087	468.4	0.0131	664.5		
0.0045	255.7	0.0088	473.2	0.0132	668.6		
0.0046	261.0	0.0089	477.9	0.0133	672.8		
0.0047	266.4	0.0090	482.6	0.0134	676.9		
0.0048	271.7	0.0091	487.4	0.0135	681.0		
0.0049	277.0	0.0092	492.1	0.0136	685.0		
0.0050	282.3	0.0093	496.8	0.0137	689.1		
0.0051	287.6	0.0094	501.4	0.0138	693.2		
0.0052	292.9	0.0095	506.1	0.0139	697.2		
		0.0096	510.7	0.0140	701.2		

Notes:

1. Units of $\frac{Mu}{\Phi bd2}$ are in psi.

2. ρ_{min} Should be based on 1.2 Mcr or 1.33 ρ analysis, whichever is smaller.

3. ρ_{max} =0.75 ρ_b = 0.0161 based on $ß_1$ = 0.85.

Flexural Reinforcement for Class 4000 Concrete

Table 5-A-9

ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$
0.0010	59.5	0.0056	319.3	0.0102	556.7	0.0148	771.7	0.0194	964.1
0.0011	65.4	0.0057	324.7	0.0103	561.7	0.0149	776.1	0.0195	968.1
0.0012	71.2	0.0058	330.1	0.0104	566.6	0.0150	780.5	0.0196	972.0
0.0013	77.1	0.0059	335.5	0.0105	571.5	0.0151	784.9	0.0197	975.9
0.0014	83.0	0.0060	340.9	0.0106	576.3	0.0152	789.3	0.0198	979.8
0.0015	88.8	0.0061	346.2	0.0107	581.2	0.0153	793.7	0.0199	983.7
0.0016	94.6	0.0062	351.6	0.0108	586.1	0.0154	798.1	0.0201	987.6
0.0017	100.5	0.0063	356.9	0.0109	590.9	0.0155	802.4	0.0202	991.5
0.0018	106.3	0.0064	362.2	0.0110	595.7	0.0156	806.8	0.0203	995.3
0.0019	112.1	0.0065	367.6	0.0111	600.06	0.0157	811.1	0.0204	999.2
0.0020	117.9	0.0066	372.9	0.0112	605.4	0.0158	815.4	0.0205	1003.0
0.0021	123.7	0.0067	378.2	0.0113	610.2	0.0159	819.7	0.0206	1006.8
0.0022	129.4	0.0068	383.4	0.0114	615.0	0.0160	824.1	0.0207	1010.7
0.0023	135.2	0.0069	388.7	0.0115	619.8	0.0161	828.3	0.0208	1014.5
0.0024	140.9	0.0070	394.0	0.0116	624.5	0.0162	832.6	0.0209	1018.3
0.0025	146.7	0.0071	399.2	0.0117	629.3	0.0163	836.9	0.0210	1022.0
0.0026	152.4	0.0072	404.5	0.0118	634.1	0.0164	841.2	0.0211	1025.8
0.0027	158.1	0.0073	409.7	0.0119	638.8	0.0165	845.4	0.0212	1029.6
0.0028	163.8	0.0074	414.9	0.0120	643.5	0.0166	849.7	0.0213	1033.3
0.0029	169.5	0.0075	420.1	0.0121	648.2	0.0167	853.9	ρ_{max} 0.0214	1037.1
0.0030	175.2	0.0076	425.3	0.0122	653.0	0.0168	858.1		1040.8
0.0031	180.9	0.0077	430.5	0.0123	657.7	0.0169	862.3		
0.0032	186.6	0.0078	435.7	0.0124	662.3	0.0170	866.5		
0.0033	192.2	0.0079	440.9	0.0125	667.0	0.0171	870.7		
0.0034	197.9	0.0080	446.0	0.0126	671.7	0.0172	874.9		
0.0035	203.5	0.0081	451.2	0.0127	676.3	0.0173	879.1		
0.0036	209.1	0.0082	456.3	0.0128	681.0	0.0174	883.2		
0.0037	214.7	0.0083	461.4	0.0129	685.6	0.0175	887.4		
0.0038	220.3	0.0084	466.5	0.0130	690.3	0.0176	891.5		
0.0039	225.9	0.0085	471.6	0.0131	694.9	0.0177	895.6		
0.0040	231.5	0.0086	476.7	0.0132	699.5	0.0178	899.7		
0.0041	237.1	0.0087	481.8	0.0133	704.1	0.0179	903.9		
0.0042	242.6	0.0088	486.9	0.0134	708.6	0.0180	907.9		
0.0043	248.2	0.0089	491.9	0.0135	713.2	0.0181	912.0		
0.0044	253.7	0.0090	497.0	0.0136	717.8	0.0182	916.1		
0.0045	259.2	0.0091	502.0	0.0137	722.3	0.0183	920.2		
0.0046	264.8	0.0092	507.1	0.0138	726.9	0.0184	924.2		
0.0047	270.3	0.0093	512.1	0.0139	731.4	0.0185	928.3		
0.0048	275.8	0.0094	517.1	0.0140	735.9	0.0186	932.3		
0.0049	281.2	0.0095	522.1	0.0141	740.4	0.0187	936.3		
0.0050	286.7	0.0096	527.1	0.0142	744.9	0.0188	940.3		
0.0051	292.2	0.0097	532.0	0.0143	749.4	0.0189	944.3		
0.0052	297.6	0.0098	537.0	0.0144	753.9	0.0190	948.3		
0.0053	303.1	0.0099	542.0	0.0145	758.3	0.0191	952.3		
0.0054	808.5	0.100	546.9	0.0146	762.8	0.0192	956.2		
0.0055	313.9	0.101	551.8	0.0147	767.2	0.0193	960.2		

Notes:

1. Units of $\frac{Mu}{\Phi bd2}$ are in psi.

2. ρ_{min} Should be based on 1.2 Mcr or 1.33 ρ analysis, whichever is smaller.
3. ρ_{max} =0.75 ρ_b = 0.0161 based on ß$_1$ = 0.85.

Flexural Reinforcement for Class 5000 Concrete

Table 5-A-10

ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$	ρ	$\frac{Mu}{\Phi bd2}$
0.0010	59.6	0.0061	350.2	0.0113	623.8	0.0165	874.3	0.0217	1102.0
0.0011	65.5	0.0062	355.7	0.0114	628.8	0.0166	878.9	0.0218	1106.1
0.0012	71.4	0.0063	361.1	0.0115	633.8	0.0167	883.5	0.0219	1110.3
0.0013	77.3	0.0064	366.6	0.0116	638.8	0.0168	888.1	0.0220	1114.4
0.0014	83.2	0.0065	372.1	0.0117	643.8	0.0169	892.7	0.0221	1118.5
0.0015	89.0	0.0066	377.5	0.0118	648.8	0.0170	897.2	0.0222	1122.6
0.0016	94.9	0.0067	382.9	0.0119	653.8	0.0171	901.8	0.0223	1126.8
0.0017	100.8	0.0068	388.4	0.0120	658.8	0.0172	906.3	0.0224	1130.9
0.0018	106.6	0.0069	393.8	0.0121	663.8	0.0173	910.9	0.0225	1134.9
0.0019	112.5	0.0070	399.2	0.0122	668.8	0.0174	915.4	0.0226	1139.0
0.0020	118.3	0.0071	404.6	0.0123	673.7	0.0175	919.9	0.0227	1143.1
0.0021	124.1	0.0072	410.0	0.0124	678.7	0.0176	924.4	0.0228	1147.2
0.0022	129.9	0.0073	415.4	0.0125	683.6	0.0177	928.9	0.0229	1151.2
0.0023	135.8	0.0074	420.7	0.0126	688.6	0.0178	933.4	0.0230	1155.3
0.0024	141.6	0.0075	426.1	0.0127	693.5	0.0179	937.9	0.0231	1159.3
0.0025	147.3	0.0076	431.5	0.0128	698.4	0.0180	942.4	0.0232	1163.4
0.0026	153.1	0.0077	436.8	0.0129	703.3	0.0181	946.8	0.0233	1167.4
0.0027	158.9	0.0078	442.2	0.0130	708.2	0.0182	951.3	0.0234	1171.4
0.0028	164.7	0.0079	447.5	0.0131	713.1	0.0183	955.7	0.0235	1175.4
0.0029	170.4	0.0080	425.8	0.0132	718.0	0.0184	960.2	0.0236	1179.4
0.0030	176.2	0.0081	458.1	0.0133	722.9	0.0185	964.6	0.0237	1183.4
0.0031	181.9	0.0082	463.4	0.0134	727.7	0.0186	969.0	0.0238	1187.4
0.0032	187.7	0.0083	468.7	0.0135	732.6	0.0187	973.5	0.0239	1191.4
0.0033	193.4	0.0084	474.0	0.0136	737.4	0.0188	977.9	0.0240	1195.3
0.0034	199.1	0.0085	479.3	0.0137	742.3	0.0189	982.3	0.0241	1199.3
0.0035	204.8	0.0086	484.6	0.0138	747.1	0.0190	986.6	0.0242	1203.2
0.0036	210.5	0.0087	489.8	0.0139	751.9	0.0191	991.0	0.0243	1207.2
0.0037	216.2	0.0088	495.1	0.0140	756.7	0.0192	995.4	0.0244	1211.1
0.0038	221.9	0.0089	500.4	0.041	761.5	0.0193	999.8	0.0245	1215.00
0.0039	227.5	0.0090	505.6	0.0142	766.3	0.0194	1004.1	0.0246	1218.9
0.0040	233.2	0.0091	510.8	0.0143	771.1	0.0195	1008.5	0.0247	1222.8
0.0041	238.9	0.0092	516.0	0.0144	775.9	0.0196	1012.8	0.0248	1226.7
0.0042	244.5	0.0093	521.3	0.0145	780.7	0.0197	1017.1	0.0249	1230.6
0.0043	250.1	0.0094	526.5	0.0146	785.4	0.0198	1021.5	0.0250	1234.5
0.0044	255.8	0.0095	531.7	0.0147	790.2	0.0199	1025.8	0.0251	1238.4
0.0045	261.4	0.0096	536.9	0.0148	795.0	0.0200	1030.1	ρ_{max} 0.0252	1242.2
0.0046	267.0	0.0097	542.0	0.0149	799.7	0.0201	1034.4		
0.0047	272.6	0.0098	547.2	0.0150	804.4	0.0202	1038.7		
0.0048	278.2	0.0099	552.4	0.0151	809.1	0.0203	1042.9		
0.0049	283.8	0.0100	557.5	0.0152	813.9	0.0204	1047.2		
0.0050	289.4	0.0101	562.7	0.0153	818.6	0.0205	1051.5		
0.0051	295.0	0.0102	567.8	0.0154	823.3	0.0206	1055.7		
0.0052	300.5	0.0103	572.9	0.0155	827.9	0.0207	1060.0		
0.0053	306.1	0.0104	578.1	0.0156	832.6	0.0208	1064.2		
0.0054	311.6	0.0105	583.2	0.0157	837.3	0.0209	1068.4		
0.0055	317.1	0.0106	588.3	0.0158	842.0	0.0210	1072.7		
0.0056	322.7	0.0107	593.4	0.0159	846.6	0.0211	1076.9		
0.0057	328.2	0.0108	598.5	0.0160	851.3	0.0212	1081.1		
0.0058	333.7	0.0109	603.5	0.0161	855.9	0.0213	1085.3		
0.0059	339.2	0.0110	608.6	0.0162	860.5	0.0214	1089.5		
0.0060	344.7	0.0111	613.7	0.0163	865.1	0.0215	1093.6		
		0.0112	618.7	0.0164	869.7	0.0216	1097.8		

Notes:


1. Units of $\frac{Mu}{\Phi bd2}$ are in psi.

2. ρ_{min} Should be based on 1.2 Mcr or 1.33 ρ analysis, whichever is smaller.


3. ρ_{max} =0.75 ρ_b = 0.0161 based on $ß_1$ = 0.85.

Flexural Reinforcement for Class 6000 Concrete


Table 5-A-11




Positive Moment Reinforcement
Figure 5-A-12



Negative Moment Reinforcement
Figure 5-A-13




Adjusted Negative Moment Case I (Design for M @ Face of Support)
Figure 5-A-14




Adjusted Negative Moment Case II (Design for M @ 1/4 Point)

Figure 5-A-15




Cast-In-Place Deck Slab Design for Positive Moment Regions f'c=4, 0 ksi

Figure 5-A-16




Cast-In-Place Deck Slab Design for Negative Moment Regions f'c=4, 0 ksi

Figure 5-A-17



Slab Overhang Design- Interior Barrier Segment

Figure 5-A-18



Slab Overhang Design- End Barrier Segment
Figure 5-A-19

f'ci = 7.5 ksi, f'c = 8.5 ksi Strand diameter = 0.6" Grade 270 ksi low relaxation									
Girder Type	Girder Spacing (ft)	Span Length (ft)	Straight Strands	Harped Strands	Harped Strand Offset*	Top Temp. Strands	Excess Camber (in)	"A" Dim. (in)	Deck Thickness (in)
W42G	5	85	14	10	7	0	2.613	11.25	7.50
	6	80	14	9	6	0	2.591	11.00	7.50
	7	70	10	10	6	0	1.656	10.25	7.50
	8	60	8	9	7	0	1.045	9.50	7.50
	9	55	6	10	6	0	0.815	9.25	7.50
	10	50	6	9	7	0	0.636	9.50	7.75
	11	50	6	10	7	0	0.629	10.00	8.25
	12	45	6	9	8	0	0.512	10.00	8.50
W50G	5	110	20	12	2	0	3.525	12.00	7.50
	6	105	20	12	2	0	3.427	12.00	7.50
	7	95	18	11	3	0	2.758	11.25	7.50
	8	90	18	12	6	0	2.459	11.00	7.50
	9	85	16	12	5	0	2.106	10.75	7.50
	10	75	12	12	6	0	1.356	10.25	7.75
	11	70	12	12	7	0	1.222	10.25	8.00
	12	65	12	11	8	0	1.033	10.50	8.50
W58G	5	125	18	17	0	2	2.699	11.25	7.50
	6	120	18	17	0	2	2.734	11.25	7.50
	7	115	20	16	1	2	2.901	11.50	7.50
	8	105	18	15	2	2	2.381	11.00	7.50
	9	100	18	14	2	2	2.250	10.25	7.50
	10	95	16	16	2	2	2.029	10.75	7.50
	11	90	16	15	2	2	1.846	11.00	8.00
	12	90	16	17	2	2	1.853	11.50	8.50
W74G	5	150	22	21	2	4	2.765	11.50	7.50
	6	140	22	19	2	4	2.770	11.50	7.50
	7	135	20	22	2	4	2.753	11.50	7.50
	8	130	20	22	2	4	2.760	11.50	7.50
	9	125	20	22	3	4	2.640	11.50	7.50
	10	120	18	22	2	4	2.401	11.25	7.50
	11	115	18	21	1	4	2.332	11.50	7.75
	12	110	18	20	0	4	2.259	11.50	8.00

* Offset at harping point

Design Parameters:

- PGSuper V. 1.4
- WSDOT BDM LRFD design criteria
- Slab f'c = 4.0 ksi
- No vertical or horizontal curve
- 2.0% roadway crown slope
- Interior Girder w/ barrier load (6 girder bridge)
- Standard WSDOT "F" shape barrier
- Simple girder span lengths are CL bearing to CL bearing
- Under normal exposure condition and 75% relative humidity
- Spans reported in 5 ft. increments
- Only flexural service and strength checked; Lifting and ha uling checks not necessarily satisfied

Span Capability of Prestressed I-Girders

Table 5-A-20

f'ci = 7.5 ksi, f'c = 8.5 ksi Strand diameter = 0.6" Grade 270 ksi low relaxation									
Girder Type	Girder Spacing (ft)	Span Length (ft)	Straight Strands	Harped Strands	Harped Strand Offset*	Top Temp. Strands	Excess Camber (in)	"A" Dim. (in)	Deck Thickness (in)
WF42G	5	115	24	24	0	6	2.162	11.00	7.50
	6	110	26	24	2	6	2.227	11.00	7.50
	7	105	24	24	1	6	2.197	11.00	7.50
	8	100	24	24	2	6	2.076	11.00	7.50
	9	95	26	19	0	6	2.316	11.25	7.50
	10	90	22	22	0	6	2.073	11.00	7.50
	11	85	20	22	0	4	2.009	11.00	7.50
	12	80	20	20	0	0	2.185	11.50	8.00
WF50G	5	130	32	20	0	6	2.508	11.50	7.50
	6	125	32	22	3	6	2.336	11.25	7.50
	7	120	30	21	0	6	2.543	11.50	7.50
	8	115	28	23	1	6	2.352	11.25	7.50
	9	110	26	24	0	6	2.386	11.25	7.50
	10	105	26	23	0	6	2.337	11.25	7.50
	11	100	24	24	1	6	2.039	11.00	7.50
	12	95	22	24	0	6	1.871	11.25	8.00
WF58G	5	145	34	21	0	6	2.343	11.25	7.50
	6	135	30	22	0	6	2.225	11.00	7.50
	7	130	32	20	0	6	2.463	11.25	7.50
	8	125	30	22	0	6	2.404	11.25	7.50
	9	120	30	20	0	6	2.333	11.25	7.50
	10	115	28	22	0	6	2.281	11.25	7.50
	11	110	26	22	0	6	2.029	11.00	7.50
	12	105	26	21	0	6	1.915	11.25	8.00
WF74G	5	175	40	23	0	6	2.389	11.25	7.50
	6	170	40	24	0	6	2.666	11.50	7.50
	7	160	38	24	3	6	2.431	11.25	7.50
	8	155	38	24	2	6	2.675	11.50	7.50
	9	145	34	23	0	6	2.500	11.50	7.50
	10	140	34	22	0	6	2.497	11.25	7.50
	11	135	36	22	6	6	2.299	11.25	7.50
	12	130	34	23	2	6	2.425	11.75	8.00
W83G	5	195#	46	24	0	6	2.429	11.25	7.50
	6	185#	46	24	0	6	3.011	12.00	7.50
	7	180	46	24	0	6	3.121	12.00	7.50
	8	170	46	21	0	6	3.217	12.25	7.50
	9	165	46	22	0	6	3.434	12.25	7.50
	10	155	46	17	0	6	3.297	12.25	7.50
	11	150	46	17	0	6	3.339	12.25	7.50
	12	145	46	16	0	6	3.161	12.50	8.00
W95G	5	195#	46	19	0	6	3.778	12.75	7.50
	6	190#	46	21	0	6	4.186	13.00	7.50
	7	185#	46	21	0	6	4.209	13.00	7.50
	8	175#	46	18	0	6	4.001	13.00	7.50
	9	170#	46	17	0	6	3.882	12.75	7.50
	10	165	46	18	0	6	4.011	13.00	7.50
	11	160	46	18	0	6	3.997	13.00	7.50
	12	155	46	16	0	6	3.686	13.00	8.00

* Offset at harping point

Span capability exceeds maximum shipping weight of 200 kips

Design Parameters:

- Interior Girder w/ barrier load (6 girder bridge)
- PGSuper V. 1.4
- Standard WSDOT "F" shape barrier
- WSDOT BDM LRFD design criteria
- Simple girder span lengths are CL bearing to CL bearing
- Slab f'c = 4.0 ksi
- Under normal exposure condition and 75% relative humidity
- No vertical or horizontal curve
- Spans reported in 5 ft. increments
- 2.0% roadway crown slope
- Only flexural service and strength checked; Lifting and hauling checks not necessarily satisfied

Span Capability of Prestressed Wide Flange I-Girders

Table 5-A-21

f'ci = 7.5 ksi, f'c = 8.5 ksi Strand diameter = 0.6" Grade 270 ksi low relaxation									
Girder Type	Girder Spacing (ft)	Span Length (ft)	Straight Strands	Harped Strands	Harped Strand Offset*	Top Temp. Strands	Excess Camber (in)	"A" Dim. (in)	Deck Thickness (in)
WBT32G	5	75	20	5	0	6	2.895	11.75	7.50
	6	75	18	10	3	6	2.924	11.75	7.50
	7	70	18	8	0	6	2.839	11.75	7.50
	8	65	18	6	0	6	2.380	11.25	7.50
	9	65	18	8	2	6	2.427	11.25	7.50
	10	60	16	8	0	6	2.123	11.00	7.50
	11	60	18	7	0	6	2.240	11.00	7.50
	12	55	16	7	0	6	1.763	11.25	8.00
WBT38G	5	90	22	8	2	6	3.308	12.25	7.50
	6	85	22	7	0	6	3.245	12.00	7.50
	7	80	22	6	0	6	2.956	11.75	7.50
	8	75	20	7	2	6	2.537	11.50	7.50
	9	75	20	8	0	6	2.742	11.50	7.50
	10	70	18	9	1	6	2.372	11.25	7.50
	11	65	20	5	1	6	2.029	11.00	7.50
	12	65	20	6	0	6	2.087	11.50	8.00
WBT62G	5	130	26	12	0	6	3.415	12.25	7.50
	6	125	26	13	0	6	3.536	12.50	7.50
	7	120	26	12	0	6	3.364	12.25	7.50
	8	115	26	12	0	6	3.354	12.25	7.50
	9	110	26	11	0	6	3.161	12.00	7.50
	10	105	26	10	0	6	2.967	11.75	7.50
	11	100	26	9	0	6	2.763	11.75	7.50
	12	95	26	8	0	6	2.513	12.00	8.00

* Offset at harping point

Design Parameters:

- PGSuper V. 1.4
- WSDOT BDM LRFD design criteria
- Slab f'c = 4.0 ksi
- No vertical or horizontal curve
- 2.0% roadway crown slope
- Interior Girder w/ barrier load (6 girder bridge)
- Standard WSDOT "F" shape barrier
- Simple girder span lengths are CL bearing to CL bearing
- Under normal exposure condition and 75% relative humidity
- Spans reported in 5 ft. increments
- Only flexural service and strength checked; Lifting and hauling checks not necessarily satisfied

Span Capability of Thin Flange Bulb-Tee Girders
Table 5-A-22

f'ci = 7.5 ksi, f'c = 8.5 ksi Strand diameter = 0.6" Grade 270 ksi low relaxation									
Girder Type	Girder Spacing (ft)	Span Length (ft)	Straight Strands	Harped Strands	Harped Strand Offset*	Top Temp. Strands	Excess Camber (in)	"A" Dim. (in)	Deck Thickness (in)
U54G4	8	130	32	26	4	0	0.083	9.00	7.5
	10	125	32	28	0	0	0.164	9.00	7.5
	12	120	32	30	2	0	0.691	9.25	7.5
	14	115	32	30	0	0	0.757	9.25	7.5
U54G5	9	130	46	18	0	0	0.284	9.00	7.5
	11	125	46	20	0	0	0.671	9.00	7.5
	13	120	46	20	0	0	0.874	9.25	7.5
	15	115	46	20	0	0	1.082	9.50	7.5
U54G6	10	120	52	10	0	0	0.000	9.00	7.5
	12	115	52	10	0	0	0.268	9.00	7.5
	14	110	52	10	0	0	0.518	9.00	7.5
	16	105	52	10	0	0	0.740	9.25	7.5
U66G4	8	155#	32	38	8	0	0.581	9.00	7.5
	10	145	32	36	6	0	0.058	9.00	7.5
	12	140	32	38	4	0	0.326	9.00	7.5
	14	135	32	40	4	0	0.717	9.25	7.5
U66G5	9	150#	46	24	4	0	0.000	9.00	7.5
	11	145#	46	26	0	0	0.012	9.00	7.5
	13	140#	46	28	0	0	0.386	9.00	7.5
	15	135	46	28	0	0	0.608	9.25	7.5
U66G6	10	145#	52	24	8	0	0.000	9.00	7.5
	12	140#	52	22	4	0	0.000	9.00	7.5
	14	135#	52	24	4	0	0.000	9.00	7.5
	16	130#	52	24	0	0	0.036	9.00	7.5
U78G4	8	170#	32	42	8	0	0.000	9.00	7.5
	10	165#	32	46	8	0	0.000	9.00	7.5
	12	160#	32	48	8	0	0.150	9.00	7.5
	14	150#	32	44	4	0	0.354	9.00	7.5
	16	145#	32	48	4	0	0.715	9.50	8.0
U78G5	9	170#	46	34	8	0	0.000	9.00	7.5
	11	165#	46	36	4	0	0.000	9.00	7.5
	13	160#	46	38	4	0	0.037	9.00	7.5
	15	155#	46	40	4	0	0.439	9.00	7.5
	17	150#	46	42	6	0	0.699	9.50	8.0
U78G6	10	165#	52	32	8	0	0.000	9.00	7.5
	12	160#	52	34	8	0	0.000	9.00	7.5
	14	155#	52	34	4	0	0.000	9.00	7.5
	16	150#	52	34	4	0	0.000	9.00	7.5
	18	145#	52	36	4	0	0.000	9.00	8.0

Note: Adding bottom flange width does not necessarily increase the span capabilities

* Offset at girder end

Span capability exceeds maximum shipping weight of 200 kips

Design Parameters:

- PGSuper V. 1.4
- WSDOT BDM LRFD design criteria
- Slab f'c = 4.0 ksi
- No vertical or horizontal curve
- 2.0% roadway crown slope
- Interior Girder w/ barrier load (6 girder bridge)
- Standard WSDOT "F" shape barrier
- Simple girder span lengths are CL bearing to CL bearing
- Under normal exposure condition and 75% relative humidity
- Spans reported in 5 ft. increments
- Only flexural service and strength checked; Lifting and hauling checks not necessarily satisfied

Span Capability of Trapezoidal Tub Girders without Top Flange

Table 5-A-23

f'ci = 7.5 ksi, f'c = 8.5 ksi Strand diameter = 0.6" Grade 270 ksi low relaxation									
Girder Type	Girder Spacing (ft)	Span Length (ft)	Straight Strands	Harped Strands	Harped Strand Offset*	Top Temp. Strands	Excess Camber (in)	"A" Dim. (in)	Deck Thickness (in)
UF60G4	9	150#	32	42	4	0	0.000	9.00	7.5
	11	145	32	46	6	0	1.086	9.75	7.5
	13	140	32	48	2	0	1.123	9.75	7.5
	15	130	32	42	0	0	1.174	9.75	7.5
UF60G5	10	150#	46	34	4	0	0.465	9.00	7.5
	12	145#	46	36	4	0	0.830	9.50	7.5
	14	140#	46	38	4	0	1.225	9.75	7.5
	16	135	46	38	4	0	1.419	10.00	7.5
UF60G6	15	135#	52	32	4	0	0.154	9.00	7.5
	17	130#	52	32	4	0	0.453	9.00	7.5
UF72G4	9	165#	32	46	0	0	0.000	9.00	7.5
	11	160#	32	48	0	0	0.000	9.00	7.5
	13	150#	32	46	0	0	0.657	9.25	7.5
	15	145#	32	46	0	0	0.828	9.50	7.5
UF72G5	10	170#	46	42	4	0	0.000	9.00	7.5
	12	165#	46	44	4	0	0.186	9.00	7.5
	14	160#	46	46	4	0	0.604	9.25	7.5
	16	150#	46	42	0	0	0.903	9.50	7.5
UF72G6	13	160#	52	40	8	0	0.000	9.00	7.5
	15	155#	52	42	4	0	0.000	9.00	7.5
	17	150#	52	42	4	0	0.000	9.00	7.5
UF84G4	10	190#	32	66	12	0	0.000	9.00	7.5
	12	185#	32	70	16	0	0.938	9.50	7.5
	14	180#	32	72	16	0	1.310	10.00	7.5
	16	170#	32	68	8	0	1.074	9.50	7.5
UF84G5	11	185#	46	52	8	0	0.000	9.00	7.5
	13	180#	46	54	8	0	0.269	9.00	7.5
	15	175#	46	56	8	0	0.657	9.25	7.5
	17	170#	46	58	8	0	1.038	9.50	7.5
UF84G6	16	170#	52	50	8	0	0.000	9.00	7.5
	18	165#	52	50	8	0	0.000	9.00	7.5

Note: Adding bottom flange width does not necessarily increase the span capabilities

* Offset at girder end

Span capability exceeds maximum shipping weight of 200 kips

Design Parameters:

- PGSuper V. 1.4
- WSDOT BDM LRFD design criteria
- Slab f'c = 4.0 ksi
- No vertical or horizontal curve
- 2.0% roadway crown slope
- Interior Girder w/ barrier load (6 girder bridge)
- Standard WSDOT "F" shape barrier
- Simple girder span lengths are CL bearing to CL bearing
- Under normal exposure condition and 75% relative humidity
- Spans reported in 5 ft. increments
- Only flexural service and strength checked; Lifting and hauling checks not necessarily satisfied

Span Capability of Trapezoidal Tub Girders with Top Flange

Table 5-A-24

Concrete Strength:		f'_{ci} = 6.0 ksi			f'_c = 7.0 ksi				
Prestressing Strands:		½" diameter			f_{pu} = 270 ksi, Low Relaxation				
Span Length (ft)	Strand Layout				Total Jacking Force (kip)	Location of C.G. of Strand, E (in)	Camber (in)		
	3" Top	2" Bot. bonded	2" Bot. unbonded	*Total			C_i	C_{final}	C_{f+sidl}
26	2	8	2	12	377	4.83	0.11	0.24	0.22
29	2	10	2	14	440	5.14	0.18	0.38	0.34
32	2	10	4	16	502	5.38	0.25	0.53	0.47
34	2	12	4	18	565	5.56	0.33	0.72	0.64
36	4	14	4	22	691	4.64	0.36	0.77	0.68
38	4	14	4	24	753	4.67	0.44	0.94	0.82
40	4	14	4	26	816	4.69	0.53	1.13	0.98
42	4	14	4	28	879	4.71	0.62	1.33	1.14
44	4	14	4	30	942	4.73	0.72	1.54	1.32
46	4	14	4	34	1067	4.76	0.92	1.98	1.70
48	4	14	4	38	1193	4.58	1.06	2.28	1.92
50	4	14	47	40	1255	4.50	1.15	2.46	2.04

Concrete Strength:		f'_{ci} = 7.0 ksi			f'_c = 8.0 ksi				
Prestressing Strands:		0.6" diameter			f_{pu} = 270 ksi, Low Relaxation				
Span Length (ft)	Strand Layout				Total Jacking Force (kip)	Location of C.G. of Strand, E (in)	Camber (in)		
	3" Top	2" Bot. bonded	2" Bot. unbonded	*Total			C_i	C_{final}	C_{f+sidl}
32	2	8	2	12	534	4.83	0.22	0.44	0.39
36	2	10	2	14	623	5.14	0.34	0.70	0.62
39	2	10	4	16	712	5.38	0.47	0.96	0.84
42	4	14	4	20	890	4.40	0.53	1.10	0.88
45	4	14	4	22	979	4.64	0.69	1.41	1.19
47	4	14	4	24	1068	4.67	0.82	1.69	1.43
49	4	14	4	26	1157	4.69	0.97	2.01	1.68
52	4	12	6	30	1335	4.73	1.26	2.61	2.16
54	4	12	6	32	1424	4.75	1.45	2.99	2.44
56	4	12	6	34	1513	4.76	1.65	3.39	2.76
58	4	12	6	38	1691	4.58	1.88	3.88	3.12
60	4	12	6	40	1780	4.50	2.02	4.17	3.27

* Total strands include all bottom strands and top strands

Design Parameters:

- LRFD Voided Slab Excel Spreadsheet (office design)
- WSDOT BDM LRFD design criteria
- No vertical or horizontal curve or skew
- Only flexural service and strength checked; Lifting and hauling checks not necessarily satisfied
- Span length is CL bearing to CL bearing
- 80% relative humidity under normal exposure
- Location of C.G. of strands is summation of all strands (top and bottom, bonded and unbonded)
- Jacking forces listed are for the entire system; top and bottom strands
- Top strands will be: 2 min. up to 4 max.
- LL distribution factors used case "g" connected only enough to prevent relative vertical displ.
- Anchor is designed 5" from end of voided slab
- Bridge width of 44' with 3 lanes on the structure

Span Capability of Prestressed1'-6" Voided Slabs

Table 5-A-25

Concrete Strength:	f'_{ci} = 6.0 ksi			f'_c = 7.0 ksi				
Prestressing Strands:	½" diameter			f_{pu} = 270 ksi, Low Relaxation				
Span Length (ft)	Strand Layout				Total Jacking Force (kip)	Location of C.G. of Strand, E (in)	Camber (in)		
	3" Top	2" Bot. bonded	2" Bot. unbonded	*Total			C_i	C_{final}	C_{f+sidl}
43	2	14	2	18	565	8.67	0.25	0.54	0..47
46	2	14	4	20	628	8.90	0.32	0.68	0.59
48	4	14	4	24	753	7.33	0.31	0.66	0.56
50	4	14	4	26	816	7.46	0.38	0.81	0.68
52	4	14	4	28	879	7.57	0.46	0.96	0.82
54	4	14	4	30	942	7.67	0.54	1.13	0.97
56	4	14	4	32	1004	7.75	0.62	1.32	1.11
58	4	12	6	34	1067	7.82	0.70	1.48	1.24
60	4	12	6	36	1130	7.89	0.79	1.68	1.41
62	6	12	6	40	1255	7.05	0.77	1.64	1.33
64	6	12	6	42	1318	7.14	0.87	1.85	1.49
66	6	12	6	46	1443	7.13	1.04	2.21	1.79
68	6	12	6	48	1506	7.13	1.13	2.39	1.91

Concrete Strength:	f'_{ci} = 7.0 ksi			f'_c = 8.0 ksi				
Prestressing Strands:	0.6" diameter			f_{pu} = 270 ksi, Low Relaxation				
Span Length (ft)	Strand Layout				Total Jacking Force (kip)	Location of C.G. of Strand, E (in)	Camber (in)		
	3" Top	2" Bot. bonded	2" Bot. unbonded	*Total			C_i	C_{final}	C_{f+sidl}
55	4	16	2	22	979	7.18	0.47	0.97	0.81
58	4	16	2	24	1068	7.33	0.59	1.20	1.00
61	4	14	4	26	1157	7.46	0.46	1.41	1.16
63	4	14	4	28	1246	7.57	0.83	1.69	1.39
66	4	14	4	30	1335	7.67	0.97	1.98	1.61
68	6	14	4	34	1513	6.71	0.93	1.90	1.48
70	6	14	4	36	1602	6.83	1.09	2.21	1.72
72	6	14	4	38	1691	6.95	1.25	2.55	2.00
74	6	14	4	40	1780	7.05	1.42	2.90	2.26
76	6	12	6	42	1869	7.14	1.57	3.21	2.49
78	6	12	6	44	1958	7.14	1.71	3.49	2.68
80	6	12	6	46	2047	7.13	1.86	3.79	2.84
82	6	12	6	48	2136	7.13	2.01	4.09	3.04

* Total strands include all bottom strands and top strands

Design Parameters:

- LRFD Voided Slab Excel Spreadsheet (office design)
- WSDOT BDM LRFD design criteria
- No vertical or horizontal curve or skew was used
- Only flexural service and strength checked; Lifting and hauling checks not necessarily satisfied
- Span length is CL bearing to CL bearing
- 80% relative humidity under normal exposure
- Location of C.G. of strands is summation of all strands (top and bottom, bonded and unbonded)
- Jacking forces and Eccentricity listed is for the entire system; top and bottom strands
- Top strands will be: 2 min. up to 6 max.
- LL distribution factors used method "g" connected only enough to prevent relative vertical displ.
- Anchor is designed 5" from end of voided slab
- Bridge width of 44' with 3 lanes on the structure

Span Capability of Prestressed2'-2" Voided Slabs

Table 5-A-26

Concrete Strength: f'ci = 6.0 ksi				f'c = 7.0 ksi				
Prestressing Strands: 1/2" diameter				fpu = 270 ksi, Low Relaxation				
Span Length (ft)	Strand Layout			Total Jacking Force (kip)	Location of C.G. of Strand, E (in)	Camber (in)		
	Top Strands (3" from top)	Bottom Debonded Strands	*Total Number of Strands			Ci	Cfinal	Cf+sidl
** 16	2	2	10	314	2.60	0.06	0.14	0.13
** 18	2	2	12	377	2.83	0.12	0.25	0.23
20	4	2	16	502	2.25	0.15	0.31	0.29
22	4	2	18	565	2.44	0.22	0.48	0.44
24	4	2	20	628	2.60	0.32	0.68	0.62
26	4	4	22	691	2.73	0.41	0.87	0.80
28	4	4	26	816	2.62	0.54	1.15	1.03
30	4	4	28	879	2.57	0.63	1.34	1.19
32	4	4	32	1004	2.50	0.78	1.67	1.47

Concrete Strength: f'ci = 7.0 ksi				f'c = 8.0 ksi				
Prestressing Strands: 0.6" diameter				fpu = 270 ksi, Low Relaxation				
Span Length (ft)	Strand Layout			Total Jacking Force (kip)	Location of C.G. of Strand, E (in)	Camber (in)		
	Top Strands (3" from top)	Bottom Debonded Strands	*Total Number of Strands			Ci	Cfinal	Cf+sidl
** 16	2	2	8	356	2.25	0.05	0.10	0.19
** 20	2	2	10	445	2.60	0.13	0.27	0.25
23	2	2	12	534	2.83	0.24	0.49	0.45
25	4	2	16	712	2.25	0.29	0.59	0.53
28	4	2	18	801	2.44	0.44	0.91	0.81
30	4	4	20	890	2.60	0.58	1.20	1.06
35	4	6	26	1157	2.62	0.98	2.02	1.73

* Total strands include all bottom strands and top strands

** Strands are not developed fully, designer should check capacities and span lengths

Design Parameters:

- WSDOT BDM LRFD design criteria
- No vertical or horizontal curve or skew
- Only flexural service and strength checked; Lifting and hauling checks not necessarily satisfied
- Span length is CL bearing to CL bearing
- 80% relative humidity under normal exposure
- Live load truck is not applicable on spans shorter than 22'-0", but the Tandem truck controls before then
- Location of C.G. of strands is summation of all strands (top and bottom, bonded and unbonded)
- Jacking forces listed are for the entire system; top and bottom strands
- Top strands will be: 2 min. up to 4 max.
- LL distribution factors used case "g" connected only enough to prevent relative vertical displ.
- Anchor is designed 5" from end of solid slab
- Bridge width of 44' with 3 lanes on the structure
- Distribution factors are applicable from span 22'-0" or longer based on research; used for shorter spans in these tables

Span Capability of Prestressed1'-0" Solid Slabs

5-A-27

Concrete Strength:		f'_{ci} = 6.5 ksi		f'_c = 8.0 ksi			
Prestressing Strands:		0.6” diameter		f_{pu} = 270 ksi, Low Relaxation			
Section		Span	Strands		Strand Layout		Camber
h (in)	b_f (ft)	L (ft)	#	F_{jack} (kips)	E (in)*	F_o (in)**	C_{final} (in)
20	9	25	12	527	7.0	14	6/16
	10	25	14	615	7.3	14	5/16
	11	25	14	615	7.5	14	5/16
24	9	35	18	791	7.6	16	13/16
	10	35	20	879	8.3	16	14/16
	11	30	16	703	8.0	16	8/16
28	9	40	20	879	8.0	18	1
	10	40	22	967	8.4	18	1 2/16
	11	35	18	791	8.4	18	11/16
32	9	50	24	1055	8.3	20	1 9/16
	10	45	22	967	8.5	20	1 2/16
	11	45	24	1055	8.8	20	1 5/16
36	9	55	24	1055	7.9	24	1 11/16
	10	50	24	1055	8.6	24	1.46
	11	45	20	879	8.5	24	0.99

* Offset for all strands at midpoint

** Offset for harped strands at endblock

Design Parameters:

WSDOT BDM LRFD Design Criteria

Flexural design of interior girder

Simple span on expansion bearings

Shape F traffic barriers on 6 girder bridge

0.25’ overlay

One straight strand in each web

Span capability of Double-Tee Decked Girders

Span Capability Precast Prestressed Double Tee Girders

Table 5-A-28

Concrete Strength:		f'_{ci} = 6.5 ksi		f'_c = 8.0 ksi			
Prestressing Strands:		f_{pu} = 270 ksi, Low Relaxation					
Section		Span	0.5” Diameter Strands		Strand Layout		Camber
h (in)	b_f (ft)	L (ft)	#	F_{jack} (kips)	E (in)*	F_o (in)**	C_{final} (in)
27	4	60	21	923	5.0	10	1 7/16
	5	55	21	923	5.6	10	1 6/16
	6	50	20	879	5.9	10	1 3/16

Section		Span	0.6” Diameter Strands		Strand Layout		Camber
h (in)	b_f (ft)	L (ft)	#	F_{jack} (kips)	E (in)*	F_o (in)**	C_{final} (in)
27	4	60	30	929	5.0	12	1 7/16
	5	55	30	929	5.6	12	1 7/16
	6	45	23	713	5.8	12	13/16

* Offset for all strands at midpoint

** Offset for harped strands at endblock

Design Parameters:

WSDOT BDM LRFD Design Criteria

Flexural design of interior girder

Simple span on expansion bearings

Shape F traffic barriers on 6 girder bridge

0.25’ overlay

One straight strand in each web

Span Capability Precast Prestressed Ribbed Girders

Table 5-A-29

	f'ci = 4.0 ksi f'c = 5.0 ksi, 0.6"ø Strands					f'ci = 5.0 ksi f'c = 6.0 ksi, 0.6"ø Strands				
Girder Type	Girder Width (ft)	Span Length (ft)	Straight	Harped	Temp.	Girder Width (ft)	Span Length (ft)	Straight	Harped	Temp.
W35DG	4	85	18	15	2	4	95	18	10	2
	5	70	22	7	2	5	80	18	8	2
	6	60	22	5	4	6	70	18	6	4
W41DG	4	95	22	12	2	4	105	20	8	2
	5	80	24	7	2	5	95	18	11	2
	6	70	22	7	4	6	80	20	6	4
W53DG	4	115	26	11	2	4	125	22	8	2
	5	105	26	12	2	5	120	22	12	2
	6	90	26	8	4	6	105	22	10	4
W65DG	4	135	26	16	2	4	145	24	9	2
	5	125	26	18	2	5	140	24	14	2
	6	110	26	14	4	6	125	24	12	4

Span Capability of Deck Bulb Tee Girders
Table 5-A-30

Concrete Strength:	f'_c=	8.0	ksi	f'_{ci} = 6.0 ksi
Prestressing Strands:	f_{pu}=	270	ksi	0.6” diameter

W35DG4

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
40	4	174	2	87	6	2.0	4.0	4.0	8.0	2/16	3/16
45	4	174	3	131	7	2.0	4.0	4.0	8.0	3/16	3/16
50	6	261	3	131	9	2.0	4.0	4.0	8.0	4/16	5/16
55	8	348	2	87	10	2.0	4.0	4.0	8.0	7/16	10/16
60	8	348	4	174	12	2.0	4.0	4.0	8.0	9/16	12/16
65	10	435	4	174	14	2.0	4.0	4.0	8.0	13/16	1 2/16
70	12	522	4	174	16	2.3	4.0	4.0	8.0	1 1/16	1 7/16
75	14	610	4	174	18	2.6	4.0	4.0	8.0	1 6/16	1 12/16
80	14	610	6	261	20	2.6	4.0	4.0	8.0	1 10/16	1 14/16
85	16	697	7	305	23	2.8	4.0	4.0	8.0	2 1/16	2 8/16
90	16	697	10	435	26	2.8	4.0	4.0	10.0	2 9/16	3 1/16

W35DG5

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
40	4	174	3	131	7	2.0	4.0	4.0	8.0	3/16	4/16
45	6	261	2	87	8	2.0	4.0	4.0	8.0	4/16	6/16
50	8	348	2	87	10	2.0	4.0	4.0	8.0	6/16	10/16
55	8	348	4	174	12	2.0	4.0	4.0	8.0	8/16	13/16
60	10	435	4	174	14	2.0	4.0	4.0	8.0	12/16	1 2/16
65	12	522	4	174	16	2.3	4.0	4.0	8.0	1	1 7/16
70	14	610	4	174	18	2.6	4.0	4.0	8.0	1 4/16	1 13/16
75	16	697	5	218	21	2.8	4.0	4.0	8.0	1 11/16	2 7/16
80	16	697	8	348	24	2.8	4.0	4.0	8.0	2 1/16	2 14/16

W35DG6

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
40	6	261	2	87	8	2.0	4.0	4.0	8.0	3/16	6/16
45	6	261	4	174	10	2.0	4.0	4.0	8.0	5/16	8/16
50	8	348	4	174	12	2.0	4.0	4.0	8.0	7/16	12/16
55	10	435	4	174	14	2.0	4.0	4.0	8.0	11/16	1 1/16
60	12	522	4	174	16	2.3	4.0	4.0	8.0	14/16	1 7/16
65	14	610	5	218	19	2.6	4.0	4.0	8.0	1 4/16	1 15/16
70	14	610	7	305	21	2.6	4.0	4.0	8.0	1 8/16	2 4/16
75	16	697	8	348	24	2.8	4.0	4.0	8.0	1 14/16	2 14/16

Design Charts for W35DG Deck Bulb Tee Girder

Table 5-A-31

Concrete Strength: f'_c= 8.0 ksi f'_{ci} = 6.0 ksi
Prestressing Strands: f_{pu}= 270 ksi 0.6” diameter

W41DG4

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
50	6	261	2	87	8	2.0	4.0	4.0	8.0	4/16	6/16
55	6	261	3	131	9	2.0	4.0	4.0	8.0	5/16	11/16
60	8	348	2	87	10	2.0	4.0	4.0	8.0	6/16	9/16
65	8	348	4	174	12	2.0	4.0	4.0	8.0	8/16	11/16
70	10	435	3	131	13	2.0	4.0	4.0	8.0	11/16	14/16
75	10	435	5	218	15	2.0	4.0	4.0	8.0	13/16	1
80	12	522	5	218	17	2.3	4.0	4.0	8.0	1 1/16	1 5/16
85	14	610	5	218	19	2.6	4.0	4.0	8.0	1 6/16	1 10/16
90	16	697	5	218	21	2.8	4.0	4.0	8.0	1 11/16	1 15/16
95	16	697	8	348	24	2.8	4.0	4.0	8.0	2 1/16	2 5/16
100	16	697	10	435	26	2.8	4.0	4.0	9.0	2 5/16	2 6/16
105	18	784	11	479	29	2.9	5.0	5.0	9.0	2 12/16	2 14/16

W41DG5

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
50	6	261	3	131	9	2.0	4.0	4.0	8.0	4/16	6/16
55	6	261	4	174	10	2.0	4.0	4.0	8.0	5/16	7/16
60	8	348	4	174	12	2.0	4.0	4.0	8.0	8/16	11/16
65	10	435	4	174	14	2.0	4.0	4.0	8.0	11/16	1
70	10	435	5	218	15	2.0	4.0	4.0	8.0	12/16	1 1/16
75	12	522	6	261	18	2.3	4.0	4.0	8.0	1 1/16	1 8/16
80	14	610	6	261	20	2.6	4.0	4.0	8.0	1 6/16	1 13/16
85	16	697	6	261	22	2.8	4.0	4.0	8.0	1 11/16	2 3/16
90	18	784	7	305	25	2.9	4.0	4.0	8.0	2 2/16	2 12/16
95	16	697	12	522	28	2.8	5.2	5.2	10.0	2 6/16	2 15/16

W41DG6

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
50	8	348	2	87	10	2.0	4.0	4.0	8.0	5/16	8/16
55	8	348	4	174	12	2.0	4.0	4.0	8.0	7/16	11/16
60	10	435	4	174	14	2.0	4.0	4.0	8.0	10/16	1
65	12	522	4	174	16	2.3	4.0	4.0	8.0	13/16	1 4/16
70	12	522	6	261	18	2.3	4.0	4.0	8.0	1	1 8/16
75	12	522	8	348	20	2.3	4.0	4.0	8.0	1 3/16	1 12/16
80	14	610	9	392	23	2.6	4.0	4.0	8.0	1 9/16	2 4/16
85	14	610	12	522	26	2.6	4.0	4.0	10.0	1 15/16	2 12/16

Design Charts for W41DG Deck Bulb Tee Girder

Table 5-A-32

Concrete Strength: f'_c= 8.0 ksi f'_{ci} = 6.0 ksi

Prestressing Strands: f_{pu}= 270 ksi 0.6” diameter

W53DG4

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
60	6	261	2	87	8	2.0	4.0	4.0	8.0	3/16	4/16
65	8	348	1	44	9	2.0	4.0	4.0	8.0	5/16	6/16
70	8	348	3	131	11	2.0	4.0	4.0	8.0	6/16	8/16
75	8	348	4	174	12	2.0	4.0	4.0	8.0	7/16	8/16
80	10	435	3	131	13	2.0	4.0	4.0	8.0	9/16	10/16
85	10	435	5	218	15	2.0	4.0	4.0	8.0	11/16	11/16
90	12	522	5	218	17	2.3	4.0	4.0	8.0	14/16	15/16
95	14	610	4	174	18	2.6	4.0	4.0	8.0	1 1/16	1 1/16
100	14	610	6	261	20	2.6	4.0	4.0	8.0	1 3/16	1 3/16
105	16	697	6	261	22	2.8	4.0	4.0	8.0	1 8/16	1 7/16
110	16	697	8	348	24	2.8	4.0	4.0	8.0	1 11/16	1 8/16
115	18	784	8	348	26	2.9	4.0	4.0	8.0	2	1 12/16
120	18	784	11	479	29	2.9	4.0	4.0	10.0	2 5/16	2
125	20	871	11	479	31	3.2	4.0	4.0	10.0	2 11/16	2 3/16

W53DG5

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
60	8	348	1	44	9	2.0	4.0	4.0	8.0	4/16	6/16
65	8	348	3	131	11	2.0	4.0	4.0	8.0	6/16	8/16
70	10	435	2	87	12	2.0	4.0	4.0	8.0	7/16	10/16
75	10	435	4	174	14	2.0	4.0	4.0	8.0	9/16	13/16
80	12	522	3	131	15	2.3	4.0	4.0	8.0	11/16	14/16
85	12	522	5	218	17	2.3	4.0	4.0	8.0	13/16	1
90	14	610	5	218	19	2.6	4.0	4.0	8.0	1 1/16	1 5/16
95	16	697	5	218	21	2.8	4.0	4.0	8.0	1 5/16	1 10/16
100	16	697	7	305	23	2.8	4.0	4.0	8.0	1 8/16	1 12/16
105	18	784	8	348	26	2.9	4.0	4.0	8.0	1 14/16	2 5/16
110	20	871	8	348	28	3.2	4.0	4.0	8.0	2 3/16	2 9/16
115	20	871	11	479	31	3.2	4.0	4.0	8.0	2 9/16	2 15/16
120	20	871	13	566	33	3.2	4.5	4.5	10.0	2 13/16	3 1/16

W53DG6

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
60	8	348	3	131	11	2.0	4.0	4.0	8.0	5/16	8/16
65	10	435	2	87	12	2.0	4.0	4.0	8.0	7/16	10/16
70	10	435	4	174	14	2.0	4.0	4.0	8.0	8/16	13/16
75	12	522	4	174	16	2.3	4.0	4.0	8.0	11/16	1 1/16
80	14	610	4	174	18	2.6	4.0	4.0	8.0	14/16	1 5/16
85	14	610	6	261	20	2.6	4.0	4.0	8.0	1 1/16	1 8/16
90	16	697	6	261	22	2.8	4.0	4.0	8.0	1 5/16	1 13/16
95	18	784	6	261	24	2.9	4.0	4.0	8.0	1 9/16	2 2/16
100	18	784	9	392	27	2.9	4.0	4.0	8.0	1 14/16	2 8/16
105	20	871	9	392	29	3.2	4.0	4.0	8.0	2 3/16	2 14/16
110	20	871	12	522	32	3.2	5.5	5.5	10.0	2 8/16	3 3/16

Design Charts for W53DG Deck Bulb Tee Girder

Table 5-A-33

Concrete Strength: f'_c= 8.0 ksi f'_{ci} = 6.0 ksi
Prestressing Strands: f_{pu}= 270 ksi 0.6" diameter

W65DG4

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
70	8	348	1	44	9	2.0	4.0	4.0	8.0	4/16	5/16
75	8	348	2	87	10	2.0	4.0	4.0	8.0	4/16	5/16
80	8	348	3	131	11	2.0	4.0	4.0	8.0	5/16	5/16
85	10	435	3	131	13	2.0	4.0	4.0	8.0	7/16	8/16
90	10	435	4	174	14	2.0	4.0	4.0	8.0	8/16	8/16
95	12	522	3	131	15	2.3	4.0	4.0	8.0	10/16	9/16
100	12	522	5	218	17	2.3	4.0	4.0	8.0	12/16	11/16
105	14	610	4	174	18	2.6	4.0	4.0	8.0	14/16	11/16
110	16	697	4	174	20	2.8	4.0	4.0	8.0	1 1/16	15/16
115	16	697	6	261	22	2.8	4.0	4.0	8.0	1 4/16	1
120	18	784	6	261	24	2.9	4.0	4.0	8.0	1 8/16	1 4/16
125	18	784	8	348	26	2.9	4.0	4.0	8.0	1 10/16	1 5/16
130	20	871	8	348	28	3.2	4.0	4.0	8.0	1 15/16	1 8/16
135	22	958	8	348	30	3.5	4.0	4.0	8.0	2 3/16	1 11/16
140	22	958	10	435	32	3.5	4.0	4.0	8.0	2 6/16	1 11/16
145	22	958	14	610	36	3.5	6.0	5.5	10.0	2 12/16	2

W65DG5

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
70	8	348	2	87	10	2.0	4.0	4.0	8.0	4/16	6/16
75	10	435	1	44	11	2.0	4.0	4.0	8.0	6/16	7/16
80	10	435	3	131	13	2.0	4.0	4.0	8.0	7/16	9/16
85	10	435	4	174	14	2.0	4.0	4.0	8.0	8/16	9/16
90	12	522	4	174	16	2.3	4.0	4.0	8.0	10/16	12/16
95	14	610	4	174	18	2.6	4.0	4.0	8.0	13/16	1
100	14	610	5	218	19	2.6	4.0	4.0	8.0	14/16	1
105	16	697	5	218	21	2.8	4.0	4.0	8.0	1 2/16	1 4/16
110	18	784	5	218	23	2.9	4.0	4.0	8.0	1 5/16	1 8/16
115	20	871	5	218	25	3.2	4.0	4.0	8.0	1 9/16	1 13/16
120	20	871	8	348	28	3.2	4.0	4.0	8.0	1 14/16	2 1/16
125	22	958	8	348	30	3.5	4.0	4.0	8.0	2 2/16	2 5/16
130	22	958	10	435	32	3.5	4.0	4.0	8.0	2 6/16	2 6/16
135	22	958	12	522	34	3.5	4.0	4.0	9.0	2 10/16	2 7/16
140	22	958	15	653	37	3.5	5.1	4.5	10.0	2 14/16	2 10/16

W65DG6

Span Length	Straight Strands		Harped Strands		Total Strands	Strand Patterns C.G. (in)				Camber (in)	
ft	#	Jacking (kips)	#	Jacking (kips)	#	E	F_{cl}	F_b	F_o	C_i	C_{final}
70	10	435	2	87	12	2.0	4.0	4.0	8.0	6/16	9/16
75	10	435	3	131	13	2.0	4.0	4.0	8.0	6/16	9/16
80	12	522	3	131	15	2.3	4.0	4.0	8.0	9/16	12/16
85	12	522	4	174	16	2.3	4.0	4.0	8.0	10/16	13/16
90	14	610	4	174	18	2.6	4.0	4.0	8.0	12/16	1
95	16	697	4	174	20	2.8	4.0	4.0	8.0	15/16	1 5/16
100	18	784	4	174	22	2.9	4.0	4.0	8.0	1 3/16	1 9/16
105	18	784	6	261	24	2.9	4.0	4.0	8.0	1 5/16	1 12/16
110	20	871	6	261	26	3.2	4.0	4.0	8.0	1 9/16	2
115	20	871	9	392	29	3.2	4.0	4.0	8.0	1 14/16	2 6/16
120	22	958	9	392	31	3.5	4.0	4.0	8.0	2 2/16	2 9/16
125	22	958	12	522	34	3.5	4.0	4.0	8.0	2 7/16	2 15/16
130	22	958	14	610	36	3.5	5.4	5.0	10.0	2 11/16	3

Design Charts for W65DG Deck Bulb Tee Girder

Table 5-A-34

f'ci = 6.0 ksi, f'c = 9 ksi Strand diameter = 0.6" Grade 270 ksi low relaxation												
Girder Type	Girder Spacing (ft)	Span Length (ft)	Cast-in-Place Closures f'ci = 6.0 ksi f'c = 9.0 ksi	Spliced Post-Tensioned Girder								
				PT Ducts ~ Strands/Duct (Duct#4 @ Bottom)				Jacking Force** (kips)	Tendon Force after Seating** (kips)	Tendon Loss* (kips)	E1 (in)	E3 (in)
			Length (ft)	1	2	3	4					
WF74PTG Post-tensioned Before Slab Casting	6	170	2	-	22	22	22	2970	2680	730	36.4	12.7
	8	155	2	-	22	22	22	2970	2670	740	36.4	12.7
	10	140	2	-	22	22	22	2970	2650	760	36.4	12.7
	12	120	2	-	22	22	22	2970	2630	780	36.4	12.7
	14	100	2	-	22	22	22	2970	2590	815	36.4	12.7
WF74PTG Post-tensioned After Slab Casting	6	195	2	-	22	22	22	2960	2690	680	36.4	12.7
	8	185	2	-	22	22	22	2960	2710	680	36.4	12.7
	10	175	2	-	22	22	22	2960	2690	690	36.4	12.7
	12	165	2	-	22	22	22	2990	2720	700	36.4	12.7
	14	155	2	-	22	22	22	3020	2750	710	36.4	12.7
W83PTG Post-tensioned Before Slab Casting	6	185	2	11	22	22	22	3500	3160	850	33.8	14.5
	8	165	2	-	22	22	22	2985	2710	720	36.4	12.7
	10	155	2	-	22	22	22	2985	2700	730	36.4	12.7
	12	135	2	-	22	22	22	2985	2680	740	36.4	12.7
	14	115	2	-	22	22	22	2985	2620	810	36.4	12.7
W83PTG Post-tensioned After Slab Casting	6	*205	2	11	22	22	22	3500	3200	810	33.8	14.5
	8	200	2	11	22	22	22	3500	3210	800	33.8	14.5
	10	195	2	22	22	22	22	4000	3640	940	37.6	15.7
	12	185	2	22	22	22	22	4000	3640	940	37.6	15.7
	14	175	2	22	22	22	22	4000	3640	940	37.6	15.7
W95PTG Post-tensioned Before Slab Casting	6	200	2	11	22	22	22	3500	3150	860	46.1	14.5
	8	185	2	11	22	22	22	3500	3110	980	46.1	14.5
	10	175	2	11	22	22	22	3500	3130	880	46.1	14.5
	12	155	2	8	22	22	22	3360	2990	860	44.9	14.1
	14	135	2	-	22	22	22	3000	2630	810	59.0	12.7
W95PTG Post-tensioned After Slab Casting	6	235	2	11	22	22	22	3500	3210	800	46.1	14.5
	8	230	2	22	22	22	22	4000	3650	930	37.6	15.7
	10	215	2	22	22	22	22	4000	3640	940	37.6	15.7
	12	205	2	22	22	22	22	4000	3640	950	37.6	15.7
	14	190	2	22	22	22	22	4000	3630	960	37.6	15.7

Span Capability of Post-Tensioned Spliced I-Girders

Table 5-A-35

* Controlled by over-reinforced section (see LRFD Sec. 5.7.3.3)

** Total force calculated at jacking end of post-tensioned girder (rounded to the nearest 10)

Design Parameters:

- PGSplice V. 0.3
- WSDOT BDM LRFD design criteria
- No vertical or horizontal curve
- 2.0% roadway crown slope
- Interior Girder w/ barrier load (6 girder bridge)
- Only flexural service and strength checked; Lifting and hauling checks not necessarily satisfied
- Simple girder span lengths are CL bearing to CL bearing
- Slab f'c = 4.0 ksi
- Standard WSDOT "F" shape barrier
- Under normal exposure condition and 75% relative humidity
- Spans reported in 5'-0" increments
- Designs based on "normally" reinforced sections (c/de < 0.42 LRFD 5.7.3.3)
- Designs based on 22 strands/duct
- For 6'-10' girder spacing -- 7.5" slab
- For 12' girder spacing -- 8.0" slab
- For 14' girder spacing -- 8.75" slab
- Girders PT'd before slab pour are assumed to be PT'd adjacent to structure
- All spec checks at wet joints have been ignored. It isassumed that the designer can modify the wet joints to reach the required span as shown in the table. These modifications are outside the scope of this table.

Span Capability of Post-Tensioned Spliced I-Girders

Table 5-A-35 (Continued)

Girder Type	Girder Spacing (ft)	Span Length (ft)	End Segments	Middle Segment	Spliced Post-Tensioned Girder								
			No. of Straight Strands	No. of Straight Strands	PT Ducts ~ Strands/Duct (Duct #4 @ Bottom)				Jacking Force* (kips)	Tendon Force after Seating* (kips)	Tendon Loss* (kips)	E1 (in)	E3 (in)
					1	2	3	4					
U54PTG4	8	135	4	6	-	-	11	22	2904	2636	570	20.0	8.9
	14	150	4	14	-	2	22	22	4048	3708	760	31.5	10.1
U54PTG5	9	135	4	8	-	-	12	22	2992	2764	578	19.7	9.0
	15	150	4	14	-	6	22	22	4400	4032	826	29.8	10.9
U54PTG6	10	135	4	6	-	-	18	22	3520	3200	684	18.3	9.5
	16	145	4	14	-	8	22	22	4576	4196	852	29.0	11.2
U66PTG4	8	155	4	8	-	-	15	22	3256	2944	648	18.9	9.3
	14	170	4	16	-	7	22	22	4488	4088	864	29.4	11.0
U66PTG5	9	155	4	8	-	-	17	22	3432	3110	678	18.5	9.4
	15	170	4	16	-	10	22	22	4752	4334	910	29.3	11.3
U66PTG6	10	155	4	8	-	-	21	22	3784	3434	742	17.7	9.7
	16	165	4	14	-	12	22	22	4928	4500	940	27.7	11.7
U78PTG4	8	175	4	10	-	-	19	22	3608	3262	722	18.1	9.6
	16	190	4	20	-	15	22	22	5192	4718	1014	26.8	12.1
U78PTG5	9	180	4	10	-	2	22	22	4048	3692	776	31.5	10.1
	17	195	4	22	-	21	22	22	5720	5202	1110	25.2	12.6
U78PTG6	10	180	4	10	-	6	22	22	4400	4018	840	29.8	10.9
	18	190#	4	20	2	22	22	22	5896	5400	1104	395.0	12.9

Span Capability of Post-Tensioned Spliced Tub Girders
Table 5-A-36


* Total force calculated at jacking end of post-tensioned girder

Span capability exceeds maximum shipping weight of 200 kips

Design Parameters:


- PGSplice V. 0.3
- WSDOT BDM LRFD design criteria
- No vertical or horizontal curve
- 2.0% roadway crown slope
- Interior Girder w/ barrier load (6 girder bridge)
- Only flexural service and strength checked; Lifting and hauling checks not necessarily satisfied
- Simple girder span lengths are CL bearing to CL bearing
- Standard WSDOT “F” shape barrier
- Under normal exposure condition and 75% humidity
- Spans reported in 5’-0” increments
- ”A” dimension = deck thickness + 2”
- Closure Pour for spliced girders is 2 ft,
  f’ci = 6.0 ksi, f’c = 9 ksi
- Girder f’ci = 6.0 ksi, f’c = 9.0 ksi, slab f’c = 4.0 ksi
- Girders are spliced in-place after slab is cast
- Prestressing and post-tensioning steel is 0.6” diameter, Grade 270
- End segments are 25% of total length, center segment is 50% of total length
- Range of applicability requirements in LRFD ignored; span lengths may be longer than allowed by LRFD
- Designs are based on a 22 diameter strand limit per 4” duct for high pressure grout
- All spec checks at wet joints have been ignored. It is assumed that the designer can modify the wet joints to reach the required span as shown in the table. These modifications are outside the scope of this table.

Span Capability of Post-tensioned Spliced Tub Girders
Table 5-A-36 (Continued)



PRECAST PRESTRESSED I-GIRDERS


I-Girder Sections
Figure 5-A-37




PRECAST PRESTRESSED WIDE FLANGE GIRDERS

Wide Flange I-Girder Sections


Figure 5-A-38



WBT32G




WBT38G




WBT62G


Bulb Tee Girder Sections
Figure 5-A-39




WFBT32G



WFBT38G




WFBT50G




WFBT62G

Wide Flange Bulb Tee Girder Sections

Figure 5-A-40




Trapezodial Tub Girder Sections
Figure 5-A-41




Trapezoidal Tub Girder with Top Flange Sections


Figure 5-A-42




W35DG



W41DG




W53DG




W65DG


Deck Blub Tee Girder Section
Figure 5-A-43



1'-0" DEEP SLAB




1'-6" DEEP SLAB




2'-2" DEEP SLAB

Precast Prestressed Slab Sections
Figure 5-A-44



DOUBLE-TEE GIRDERS



RIBBED GIRDERS

W	NOMINAL WIDTH *
4'-0"	9'-0"
5'-0"	10'-0"
6'-0"	11'-0"

D (IN)	W1 (IN)
20	7½
24	7¼
28	7
32	6¾
36	6½


* COULD BE VARIED TO MEET SUPERSTRUCTURE WIDTH

NOMINAL WIDTH*	B*
4'-0"	1⅛"
5'-0"	7⅛"
6'-0"	1'-1⅛"


* COULD BE VARIED TO MEET SUPERSTRUCTURE WIDTH

PRECAST PRESTRESSED DOUBLE-TEE AND RIBBED DECK GIRDERS


Double Tee and Ribbed Deck Girder Sections
Figure 5-A-45



WF74PTG




W83PTG




W95PTG

PRECAST POST-TENSIONED SPLICED I-GIRDERS

Spliced I-Girders Sections
Figure 5-A-46



POST-TENSIONED TRAPEZOIDAL TUB SECTION




POST-TENSIONED TRAPEZOIDAL TUB SECTION
FOR S-I-P DECK PANEL

* 1'-0" FOR BOTTOM FLANGE WIDTH LESS THAN 5'-6"
2'-0" FOR BOTTOM FLANGE WIDTH EQUAL OR GREATER THAN 5'-6"

PRECAST POST-TENSIONED SPLICE TUB GIRDERS

Spliced Trapeziodal Tub Girders Sections
Figure 5-A-47




NOTE TO DESIGNER

THIS STANDARD IS APPLICABLE TO SINGLE SPAN PRESTRESSED CONC. GIRDERS ONLY

CONSTRUCTION SEQUENCE ~ SUPERSTRUCTURE

Single Span Prestressed Girder Construction Sequence

Figure 5-A-48




NOTE TO DESIGNER

THIS STANDARD IS APPLICABLE TO MULTIPLE SPAN PRESTRESSED CONCRETE GIRDERS ONLY

Multiple Span Prestressed Girder Construction Sequence

Figure 5-A-49




NOTE TO DESIGNER

THIS STANDARD IS APPLICABLE TO MULTIPLE SPAN PRESTRESSED CONCRETE TUB GIRDERS ONLY


Single Span Prestressed Girder Construction Sequence

Figure 5-A-50



FOR STUB ABUTMENT PIER WITH END DIAPHRAGMS CAST ON GIRDER END

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE INSERT OR APPROVED EQUAL. (TYP.)




OPEN HOLE

BOTTOM HOLE AT END TYPE "B" ONLY


NOTES

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING ALL GIRDERS.
4. THE GIRDERS MAY NEED TO BE BRACED LATERALLY DURING SHIPPING TO PREVENT TIPPING OR BUCKLING.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
6. IF THE LIFTING LOOPS EXTEND WITHIN 3" OF THE TOP OF THE ROADWAY SLAB, THEY SHALL BE CUT OFF PRIOR TO PLACING THE ROADWAY SLAB. ALL LIFTING STRANDS SHALL BE OF THE SAME MATERIAL AND STRENGTH AS THE PRESTRESSING STRANDS. WRAP THE LIFTING LOOPS SO THAT EACH STRAND WILL CARRY ITS SHARE OF THE TOTAL LOAD. EXTEND LIFTING LOOPS ENDING WITH A 9" LONG 90° HOOK TO WITHIN 3" CLEAR OF THE BOTTOM OF THE GIRDER.
7. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
9. ALL STRANDS SHALL BE ½ " OR 0.6" ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
10. FOR SAWTOOTH DETAIL SEE W42G GIRDER DETAILS 2 OF 2.




TYPICAL END ELEVATION

END TYPE C SHOWN, OTHER END TYPES SIMILAR.



VIEW B

SAWTEETH SHOWN BY SHADED AREA



SECTION C

DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0"	0"	0"	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO

TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE


ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	4	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	#
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	4	STR.

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)

NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"

* = VARIES FOR SKEWED SPANS




** SHALL BE CHECK FOR THE EFFECT OF RDWY VERTICAL CURVE

#3 OR #4 MAY BE SUBSTITUTED. FIELD BEND IS OPTIONAL.


W42G Girder Details 1 of 2

Figure 5-A-51




STRAND PATTERN AT GIRDER END


HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1) , (2) ETC.



STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1) , (2) ETC.






SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - W42G GIRDER DETAILS 1 OF 2

GIRDER SCHEDULE


DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C KSI	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI KSI	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS E	LOCATION OF C.G. STRANDS F℄	LOCATION OF C.G. STRANDS Fb	LOCATION OF C.G. STRANDS Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




TRANSVERSE REINFORCING SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN




ELEVATION



PLAN - BEARING RECESS & BOTTOM FLANGE SPALL PROTECTION



ALTERNATE #1



ALTERNATE #2


STRAND EXTENSION DETAIL

NOTES TO DESIGNER:


This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.

W42G Girder Details 2 of 2

Figure 5-A-52




TYPICAL END DIAPHRAGM




SECTION F

NOTE TO DESIGNER


If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.




ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS





END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.

NOTE:


GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.

W42G End Diaphragm on Girder Details


Figure 5-A-53




TYPICAL END TYPE "B" DIAPHRAGM AT END PIERS




** DISTANCE FROM TOP OF GIRDER TO BOTTOM OF DIAPHRAGM + "A"



ANCHOR DETAIL
A.S.T.M. A-307





ROADWAY EXPANSION JOINT AT END PIERS


LONGITIDINAL DIMENSIONS ARE NORMAL TO SKEW

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".


W42G Abutment Type Pier Diaphragm Details

Figure 5-A-54




PLAN - FIXED FLUSH-FACE DIAPHRAGM

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET





CONSTRUCTION SEQUENCE

1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



TYPICAL FIXED FLUSH-FACE DIAPHRAGM





OAK BLOCK DETAIL


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.

Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.


W42G Fixed Flush-Face Diaphragm at Intermediate Pier Details

Figure 5-A-55



PLAN - FIXED RECESSED-FACE DIAPHRAGM

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET



SECTION A


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



TYPICAL FIXED RECESSED-FACE DIAPHRAGM




DETAIL B



OAK BLOCK DETAIL

W42G Fixed Recessed-Face Diaphragm at Intermediate Pier Details


Figure 5-A-56




PLAN - HINGE DIAPHRAGM


10° MAX. SKEW FOR HINGE DIAPHRAGM.

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET






HINGE BAR PLAN




SECTION A



TYPICAL HINGE SECTION

** FOR SAWTOOTH SHEAR KEY DETAILS, SEE GIRDER SHEETS.



TYP. END VIEW HINGE DIAPHRAGM


NOTES TO DESIGNER

Hinge bar plan is shown for designer. The actual hinge bars shall be located along the ℄ pier on the crossbeam details sheet, for final contract plans. The hinge bars shall be deleted from this sheet prior to the award copy of the contract plans.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by the oak block location.

W42G Hinged Diaphragm at Intermediate Pier Details


Figure 5-A-57



TYPICAL INTERMEDIATE DIAPHRAGM



SECTION B



ANCHOR DETAIL


A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".

W42G Intermediate Diaphragm Details


Figure 5-A-58




SECTION G

NOTE:

1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.




GROUT PAD ELEVATION



ELASTOMERIC STOP PAD


DUROMETER HARDNESS = 60



BEARING PAD

LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60


(30 DEG. SKEW ANGLE SHOWN)




GROUT PAD DETAIL

W42G Miscelleneous Diaphragm Details

Figure 5-A-59




TYPICAL END TYPE "B" DIAPHRAGM AT END PIERS




TOP ANCHOR BOTTOM ANCHOR

ANCHOR DETAIL

A.S.T.M. A-307




BEARING PAD DETAILS AT INTERMEDIATE PIERS




SECTION A

** DISTANCE FROM TOP OF GIRDER TO BOTTOM OF DIAPHRAGM + "A"



SECT. THRU END DIAPH. EXTERIOR GIRDER AT INTERMEDIATE PIERS

LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.
NOT TO BE USED WITH SERIES W83G & W95G GIRDERS.
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A."



≠ INCREASE THIS DIMENSION FOR BRIDGES ON SAG VERTICAL CURVES TO MAINTAIN 1½" BETWEEN GIRDER ENDS

SECT. THRU END DIAPH. INTERIOR GIRDER AT INTERMEDIATE PIERS


LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.
NOT TO BE USED WITH SERIES W83G & W95G GIRDERS.
SEE "GIRDER DETAILS" FOR DIMENSION "A."

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".

Multiple Simple Spans Intermediate Pier Details

Figure 5-A-60




GIRDER ELEVATION

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅛") FERRULE OR APPROVED EQUAL. (TYP.)

OPEN HOLE
BOTTOM HOLE AT END TYPE "B" ONLY


NOTES

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING ALL GIRDERS.
4. THE GIRDERS MAY NEED TO BE BRACED LATERALLY DURING SHIPPING TO PREVENT TIPPING OR BUCKLING.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
6. IF THE LIFTING LOOPS EXTEND WITHIN 3" OF THE TOP OF THE ROADWAY SLAB, THEY SHALL BE CUT OFF PRIOR TO PLACING THE ROADWAY SLAB. ALL LIFTING STRANDS SHALL BE OF THE SAME MATERIAL AND STRENGTH AS THE PRESTRESSING STRANDS. WRAP THE LIFTING LOOPS SO THAT EACH STRAND WILL CARRY ITS SHARE OF THE TOTAL LOAD. EXTEND LIFTING LOOPS ENDING WITH A 9" LONG 90° HOOK TO WITHIN 3" CLEAR OF THE BOTTOM OF THE GIRDER.
7. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
9. ALL STRANDS SHALL BE ½ " OR 0.6" ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
10. FOR SAWTOOTH DETAIL SEE W50G GIRDER DETAILS 2 OF 2.




TYPICAL END ELEVATION

END OF TYPE C SHOWN, OTHER END TYPES SIMILAR



VIEW B

SAWTEETH SHOWN BY SHADED AREA



SECTION C

DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0"	0"	0"	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULT. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO


TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	4	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	≠
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	4	STR.

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)

NOTE: FOR DIM. "A", SEE GIRDER SCHEDULE




≠ #3 OR #4 MAY BE SUBSTITUTED. FIELD BEND IS OPTIONAL.

** SHALL BE CHECKED FOR THE EFFECT OF RDWY VERTICAL CURVE


W50G Girder Details 1 of 2

Figure 5-A-61




STRAND PATTERN AT GIRDER END


HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.






SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - W50G GIRDER DETAILS 1 OF 2

GIRDER SCHEDULE


DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ_1	θ_2	P_1	P_2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C KSI	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI KSI	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS E	LOCATION OF C.G. STRANDS F℄	LOCATION OF C.G. STRANDS Fb	LOCATION OF C.G. STRANDS Fo	C (IN.)	D (IN.)	La (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




TRANSVERSE REINFORCING SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN




ELEVATION



PLAN - BEARING RECESS AND BOTTOM FLANGE SPALL PROTECTION



ALTERNATE #1



ALTERNATE #2


STRAND EXTENSION DETAIL

NOTES TO DESIGNER:


This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.

W50G Girder Details 2 of 2

Figure 5-A-62




TYPICAL END DIAPHRAGM




SECTION F

 # NOTE TO DESIGNER


If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.



ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS



END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.

NOTE:


GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.


W50G End Diaphragm on Girder Details

Figure 5-A-63




TYPICAL END TYPE "B" DIAPHRAGM AT END PIERS






ANCHOR DETAIL

A.S.T.M. A-307





ROADWAY EXPANSION JOINT AT END PIERS


LONGITIDINAL DIMENSIONS ARE NORMAL TO SKEW

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".


W50G Abutment Type Pier Diaphragm Details

Figure 5-A-64



PLAN - FIXED FLUSH-FACE DIAPHRAGM

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET



SECTION A


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



TYPICAL FIXED FLUSH-FACE DIAPHRAGM




DETAIL B



OAK BLOCK DETAIL


W50G Fixed Flush-Face Diaphragm at Intermediate Pier Details

Figure 5-A-65



PLAN - FIXED RECESSED-FACE DIAPHRAGM


* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET




SECTION A

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



TYPICAL FIXED RECESSED-FACE DIAPHRAGM



DETAIL B



OAK BLOCK DETAIL


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.

Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.


W50G Fixed Recessed-Face Diaphragm at Intermediate Pier Details

Figure 5-A-66




PLAN - HINGE DIAPHRAGM


10° MAX. SKEW FOR HINGE DIAPHRAGM.
* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET



HINGE BAR PLAN




SECTION A



TYPICAL HINGE SECTION

** FOR SAWTOOTH SHEAR KEY DETAILS, SEE GIRDER SHEETS.



TYP. END VIEW HINGE DIAPHRAGM


NOTES TO DESIGNER

Hinge bar plan is shown for designer. The actual hinge bars shall be located along the ℄ pier on the crossbeam details sheet, for final contract plans. The hinge bars shall be deleted from this sheet prior to the award copy of the contract plans.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by the oak block location.

W50G Hinged Diaphragm at Intermediate Pier Details


Figure 5-A-67



TYPICAL INTERMEDIATE DIAPHRAGM



SECTION B



ANCHOR DETAIL


A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".


W50G Intermediate Diaphragm Details

Figure 5-A-68




NOTE:

1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.




GROUT PAD ELEVATION



ELASTOMERIC STOP PAD


DUROMETER HARDNESS = 60



BEARING PAD

LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60

(SKEW ANGLE SHOWN @ 30°)




GROUT PAD DETAIL


(SKEW ANGLE SHOWN @ 30°)

W50G Miscelleneous Diaphragm Details

Figure 5-A-69



GIRDER ELEVATION



TYPICAL END ELEVATION

END TYPE C SHOWN, OTHER END TYPES SIMILAR

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE OR APPROVED EQUAL. (TYP.)

DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" Abutment	B	YES	0"	0"	0"	NO
HINGE DIAPH. @ INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO


TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G8)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G4)
B2 = 3" (G5)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	4	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	*
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	5	STR.

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)

NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"



* #3 OR #4 MAY BE SUBSTITUTED. FIELD BENDING IS OPTIONAL.


** SHALL BE CHECKED FOR THE EFFECT OF RDWY VERTICAL CURVE

NOTES:

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING ALL GIRDERS
4. THE GIRDERS MAY NEED TO BE BRACED LATERALLY DURING SHIPPING TO PREVENT TIPPING OR BUCKLING.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
6. IF THE LIFTING LOOPS EXTEND WITHIN 3" OF THE TOP OF THE ROADWAY SLAB, THEY SHALL BE CUT OFF PRIOR TO PLACING THE ROADWAY SLAB. ALL LIFTING STRANDS SHALL BE OF THE SAME MATERIAL AND STRENGTH AS THE PRESTRESSING STRANDS. WRAP THE LIFTING LOOPS SO THAT EACH STRAND WILL CARRY ITS SHARE OF THE TOTAL LOAD. EXTEND LIFTING LOOPS ENDING WITH A 9" LONG 90° HOOK TO WITHIN 3" CLEAR OF THE BOTTOM OF THE GIRDER.
7. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
9. ALL STRANDS SHALL BE ½ " OR 0.6" ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
10. FOR SAWTOOTH DETAIL SEE W58G GIRDER DETAILS 2 OF 3.
11. TEMPORARY STRANDS ARE PRETENSIONED OR POST-TENSIONED. IF PRETENSIONED, THESE TEMPORARY STRANDS SHALL BE UNBONDED OVER ALL BUT THE END 10'-0" OF THE GIRDER LENGTH. AS AN ALTERNATE, TEMPORARY STRANDS MAY BE POST-TENSIONED BEFORE THE GIRDER IS LIFTED FROM THE FORM. TEMPORARY STRANDS SHALL BE CUT BEFORE INTERMEDIATE DIAPHRAGMS ARE CAST.


W58G Girder Details 1 of 3

Figure 5-A-70




STRAND PATTERN AT GIRDER END

HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



ELEVATION




SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - W58G GIRDER DETAILS 1 OF 3

GIRDER SCHEDULE


DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ_1	θ_2	P_1	P_2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	LOCATION OF C.G. STRANDS (IN.) F℄	LOCATION OF C.G. STRANDS (IN.) Fb	LOCATION OF C.G. STRANDS (IN.) Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




TRANSVERSE REINFORCING SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN




ELEVATION




PLAN - BEARING RECESS & BOTTOM

W58G Girder Details 2 of 3
Figure 5-A-71




ALTERNATE #1



ALTERNATE #2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS



ALTERNATE #3

NOTES TO DESIGNER:

1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.


2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.

3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor. The total number of extended strands shall not be less than:


$$Nps = 12(Mc + Vc \times h - M_{SIDL}) \times Nc \times \frac{K}{Ng} \times \frac{}{(0.9\ Aps \times fps \times d)}$$

where:

Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = nember of girders
Aps = area of each extended strand, in^2
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2



TEMPORARY STRAND BLOCKOUT DETAIL




ANCHOR PLATE DETAIL


(MOVE NOTE TO SLAB SECTION SHEET)

TEMPORARY STRAND CUTTING SEQUENCE

1. ERECT AND BRACE GIRDERS.
2. REMOVE EXPANDED POLYSTYRENE IN 2" X 2" RECESSES IN TOP FLANGE OF GIRDERS.
3. CUT STRAND AND PLASTIC SLEEVE IN 2" X 2" RECESS.
4. REMOVE ALL MOISTURE IN RECESS PRIOR TO FILLING RECESS WITH GROUT.
5. CAST INTERMEDIATE & END DIAPHRAGMS.
6. PLACE DECK CONCRETE.




STRAND PATTERN AT GIRDER END



PLAN VIEW OF TEMPORARY STRANDS

W58G Girder Details 3 of 3


Figure 5-A-72




NOTE TO DESIGNER

If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.


TYPICAL END DIAPHRAGM




SECTION F



ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS




END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.


NOTE:
GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.

W58G End Diaphragm on Girder Details
Figure 5-A-73



TYPICAL END TYPE "B" DIAPHRAGM AT END PIERS






ANCHOR DETAIL

A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".




ROADWAY EXPANSION JOINT AT END PIERS

LONGITIDINAL DIMENSIONS ARE NORMAL TO SKEW


W58G Abutment Type Pier Diaphragm Details

Figure 5-A-74



PLAN - FIXED FLUSH-FACE DIAPHRAGM

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET



SECTION A


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



TYPICAL FIXED FLUSH-FACE DIAPHRAGM




DETAIL B



OAK BLOCK DETAIL


W58G Fixed Flush-Face Diaphragm at Intermediate Pier Details

Figure 5-A-75



PLAN - FIXED RECESSED-FACE DIAPHRAGM

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET



SECTION A


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



TYPICAL FIXED RECESSED-FACE DIAPHRAGM




DETAIL B



OAK BLOCK DETAIL


W58G Fixed Recessed-Face Diaphragm at Intermediate Pier Details


Figure 5-A-76




PLAN - HINGE DIAPHRAGM

10° MAX. SKEW FOR HINGE DIAPHRAGM.
* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET






HINGE BAR PLAN




SECTION A



TYPICAL HINGE SECTION

** FOR SAWTOOTH SHEAR KEY DETAILS, SEE GIRDER SHEETS.



TYP. END VIEW HINGE DIAPHRAGM


NOTES TO DESIGNER

Hinge bar plan is shown for designer. The actual hinge bars shall be located along the ℄ pier on the crossbeam details sheet, for final contract plans. The hinge bars shall be deleted from this sheet prior to the award copy of the contract plans.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated

W58G Hinge Diaphragm at Intermediate Pier Details


Figure 5-A-77



TYPICAL INTERMEDIATE DIAPHRAGM



SECTION B



ANCHOR DETAIL


A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".

W58G Intermediate Diaphragm Details


Figure 5-A-78




SECTION G

NOTE:

1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.




GROUT PAD ELEVATION



ELASTOMERIC STOP PAD


DUROMETER HARDNESS = 60



BEARING PAD

LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60

(SKEW ANGLE SHOWN @ 30°)




GROUT PAD DETAIL

(SKEW ANGLE SHOWN @ 30°)

(SHOWN FOR END DIAPHRAGM ON GIRDER)

W58G Miscelleneous Diaphragm Details


Figure 5-A-79




NOTES

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING ALL GIRDERS.
4. THE GIRDERS MAY NEED TO BE BRACED LATERALLY DURING SHIPPING TO PREVENT TIPPING OR BUCKLING.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
6. IF THE LIFTING LOOPS EXTEND WITHIN 3" OF THE TOP OF THE ROADWAY SLAB, THEY SHALL BE CUT OFF PRIOR TO PLACING THE ROADWAY SLAB. ALL LIFTING STRANDS SHALL BE OF THE SAME MATERIAL AND STRENGTH AS THE PRESTRESSING STRANDS. WRAP THE LIFTING LOOPS SO THAT EACH STRAND WILL CARRY ITS SHARE OF THE TOTAL LOAD. EXTEND LIFTING LOOPS ENDING WITH A 9" LONG 90° HOOK TO WITHIN 3" CLEAR OF THE BOTTOM OF THE GIRDER.
7. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN. EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
9. ALL STRANDS SHALL BE ½ " OR 0.6" ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
10. FOR SAWTOOTH DETAIL SEE W74G GIRDER DETAILS 2 OF 3.
11. TEMPORARY STRANDS ARE PRETENSIONED OR POST-TENSIONED. IF PRETENSIONED, THESE TEMPORARY STRANDS SHALL BE UNBONDED OVER ALL BUT THE END 10'-0" OF THE GIRDER LENGTH. AS AN ALTERNATE, TEMPORARY STRANDS MAY BE POST-TENSIONED BEFORE THE GIRDER IS LIFTED FROM THE FORM. TEMPORARY STRANDS SHALL BE CUT BEFORE INTERMEDIATE DIAPHRAGMS ARE CAST.


* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅞") FERRULE INSERT OR APPROVED EQUAL. (TYP.)




OPEN HOLE
BOTTOM HOLE AT END TYPE "B" ONLY



TYPICAL END ELEVATION
END TYPE C SHOWN, OTHER END TYPES SIMILAR.



VIEW B
SAWTEETH SHOWN BY SHADED AREA



SECTION C


DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0"	0"	0"	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULT. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO

TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

MARK	LOCATION	SIZE		BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
G1	GIRDER STIRRUPS	5		NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"
G2	GIRDER END STIRRUPS	5		
G3	GIRDER TOP FLANGE	5	STR.	
G4	GIRDER LONGIT., FULL LENGTH	5	STR.	
G5	GIRDER END LONGIT.	7	STR.	
G6	GIRDER END TIES	W12	#	
G7	GIRDER BOT. FLANGE TIES	3		
G9	GIRDER END LONGIT.	6	STR.	


\# #3 OR #4 MAY BE SUBSTITUTED. FIELD BENDING IS OPTIONAL.



** SHALL BE CHECKED FOR THE EFFECT OF RDWY VERTICAL CURVE


W74G Girder Details 1 of 3

Figure 5-A-80




STRAND PATTERN AT GIRDER END


HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



STRAND PATTERN AT ℄ SPAN


STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.





SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - W74G GIRDER DETAILS 1 OF 3




TRANSVERSE REINFORCING SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN


GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	LOCATION OF C.G. STRANDS (IN.) F℄	LOCATION OF C.G. STRANDS (IN.) Fb	LOCATION OF C.G. STRANDS (IN.) Fo	C (IN.)	D (IN.)	L4 (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




ELEVATION




PLAN - BEARING RECESS & BOTTOM FLANGE SPALL PROTECTION

W74G Girder Details 2 of 3


Figure 5-A-81



ALTERNATE #1



ALTERNATE #2



ALTERNATE #3

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS

NOTES TO DESIGNER:

1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.

3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor. The total number of extended strands shall not be less than:


$$Nps = 12(Mc + Vc \times h - M_{SIDL}) \times \frac{Nc}{Ng} \times \frac{K}{(0.9\ Aps \times fps \times d)}$$

where:
Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = nember of girders
Aps = area of each extended strand, in^2
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2


(MOVE NOTE TO SLAB SECTION SHEET)

TEMPORARY STRAND CUTTING SEQUENCE


1. ERECT AND BRACE GIRDERS.
2. REMOVE EXPANDED POLYSTYRENE IN 2" X 2" RECESSES IN TOP FLANGE OF GIRDERS.
3. CUT STRAND AND PLASTIC SLEEVE IN 2" X 2" RECESS.
4. REMOVE ALL MOISTURE IN RECESS PRIOR TO FILLING RECESS WITH GROUT.
5. CAST INTERMEDIATE & END DIAPHRAGMS.
6. PLACE DECK CONCRETE.




TEMPORARY STRAND BLOCKOUT DETAILS



ANCHOR PLATE DETAIL




STRAND PATTERN AT GIRDER END




PLAN VIEW OF TEMPORARY STRANDS

W74G Girder Details 3 of 3

Figure 5-A-82




TYPICAL END DIAPHRAGM




SECTION F

NOTE TO DESIGNER


If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.




ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS





END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.

NOTE:


GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.


W74G End Diaphragm on Girder Details

Figure 5-A-83



TYPICAL END TYPE "B" DIAPHRAGM AT END PIERS






ANCHOR DETAIL

A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".




ROADWAY EXPANSION JOINT AT END PIERS

LONGITIDINAL DIMENSIONS ARE NORMAL TO SKEW


W58G Abutment Type Pier Diaphragm Details

Figure 5-A-84



PLAN - FIXED FLUSH-FACE DIAPHRAGM

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET



SECTION A


NOTES TO DESIGNER

FIXED BAR PLAN IS SHOWN FOR DESIGNER. THE ACTUAL FIXED BARS SHALL BE LOCATED ALONG THE ℄ PIER ON THE CROSSBEAM DETAILS SHEET FOR FINAL CONTRACT PLANS.


OAK BLOCK WEDGES SHALL BE SHOWN ON CROSSBEAM PLAN SHEET, PARALLEL TO THE ℄ PIER IF SKEWED. CROSSBEAM WIDTH IS DICTATED BY OAK BLOCK LOCATION.

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



DETAIL B




TYPICAL FIXED FLUSH-FACE DIAPHRAGM



OAK BLOCK DETAIL


W58G Fixed Flush-Face Diaphragm at Intermediate Pier Details

Figure 5-A-85



PLAN - FIXED RECESSED-FACE DIAPHRAGM


* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET




SECTION A

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



TYPICAL FIXED RECESSED-FACE DIAPHRAGM



DETAIL B



OAK BLOCK DETAIL


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.

Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.


W58G Fixed Recessed-Face Diaphragm at Intermediate Pier Details


Figure 5-A-86




PLAN - HINGE DIAPHRAGM

10° MAX. SKEW FOR HINGE DIAPHRAGM.
* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET






HINGE BAR PLAN




SECTION A



TYPICAL HINGE SECTION

** FOR SAWTOOTH SHEAR KEY DETAILS, SEE GIRDER SHEETS.



TYP. END VIEW HINGE DIAPHRAGM


NOTES TO DESIGNER

Hinge bar plan is shown for designer. The actual hinge bars shall be located along the ℄ pier on the crossbeam details sheet, for final contract plans. The hinge bars shall be deleted from this sheet prior to the award copy of the contract plans.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by the oak block location.


W58G Hinge Diaphragm at Intermediate Pier Details

Figure 5-A-87



TYPICAL INTERMEDIATE DIAPHRAGM





ANCHOR DETAIL


A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".

W58G Intermediate Diaphragm Details


Figure 5-A-88




SECTION G

NOTE:

1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.




GROUT PAD ELEVATION



ELASTOMERIC STOP PAD


DUROMETER HARDNESS = 60



BEARING PAD

LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60

(SKEW ANGLE SHOWN @ 30°)




GROUT PAD DETAIL

(SKEW ANGLE SHOWN @ 30°)

(SHOWN FOR END DIAPHRAGM ON GIRDER)


W58G Miscelleneous Diaphragm Details

Figure 5-A-89



FOR STUB ABUTMENT PIER WITH END DIAPHRAGMS CAST ON GIRDER END

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE INSERT OR APPROVED EQUAL. (TYP.)




OPEN HOLE

BOTTOM HOLE AT END TYPE "B" ONLY


NOTES:

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6"ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6.02.3(25)H OF THE STANDARD SPECIFICATIONS
6. LIFTING BARS SHALL BE 1⅜"ø HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM.) LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGRESS OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING. ONCE ERECTED, ALL GIRDERS SHALL BE BRACED TO PREVENT TIPPING UNTIL THE INTERMEDIATE DIAPHRAGMS ARE CAST AND CURED.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
9. FOR SAWTOOTH DETAILS SEE WF42G GIRDER DETAILS 2 OF 3.
10. TEMPORARY STRANDS ARE PRETENSIONED OR POST-TENSIONED. IF PRETENSIONED, THESE TEMPORARY STRANDS SHALL BE UNBONDED OVER ALL BUT THE END 10'-0" OF THE GIRDER LENGTH. AS AN ALTERNATE, TEMPORARY STRANDS MAY BE POST-TENSIONED BEFORE THE GIRDER IS LIFTED FROM THE FORM. TEMPORARY STRANDS SHALL BE CUT AFTER ALL GIRDERS ARE ERECTED, BUT BEFORE INTERMEDIATE DIAPHRAGMS ARE CAST.




TYPICAL END ELEVATION

END TYPE C SHOWN, OTHER END TYPES SIMILAR.



VIEW B

SAWTEETH SHOWN BY SHADED AREA.



SECTION C


DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0"	0"	0"	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO

TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½" (G4 , G9)
B2 = 3" (G5)

MARK	LOCATION	SIZE	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	#
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6	STR.


NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"



# indicates #3 OR #4 MAY BE SUBSTITUTED. FIELD BENDING IS OPTIONAL. ** SHALL BE CHECKED FOR EFFECT OF RDWY VERTICAL CURVE


WF42G GIRDER DETAILS 1 OF 3

Figure 5-A-90




STRAND PATTERN AT GIRDER END


HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



STRAND PATTERN AT ℄ SPAN


STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.





SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - WF74G GIRDER DETAILS 1 OF 3




TRANSVERSE REINFORCING SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN


GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE FCI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	F℄	Fb	Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




ELEVATION




PLAN - BEARING RECESS AND BOTTOM FLANGE SPALL PROTECTION DETAIL

WF42G GIRDER DETAILS 2 OF 3

Figure 5-A-91




ALTERNATE #1



ALTERNATE #2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS



ALTERNATE #3

NOTES TO DESIGNER:


1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.


3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor. The total number of extended strands shall not be less than:

$$Nps = 12(Mc + Vc \times h - M_{SIDL}) \times Nc \times \frac{K}{Ng\ (0.9\ Aps \times fps \times d)}$$


where:
Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = nember of girders
Aps = area of each extended strand, in²
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2



TEMPORARY STRAND BLOCKOUT DETAIL



ANCHOR PLATE DETAIL




STRAND PATTERN AT GIRDER END

(MOVE NOTE TO SLAB SECTION SHEET)

TEMPORARY STRAND CUTTING SEQUENCE


1. ERECT AND BRACE GIRDERS.
2. REMOVE EXPANDED POLYSTYRENE IN 2" X 2" RECESSES IN TOP FLANGE OF GIRDERS.
3. CUT STRAND AND PLASTIC SLEEVE IN 2" X 2" RECESS.
4. REMOVE ALL MOISTURE IN RECESS PRIOR TO FILLING RECESS WITH GROUT.
5. CAST INTERMEDIATE & END DIAPHRAGMS.
6. PLACE DECK CONCRETE.



PLAN VIEW OF TEMPORARY STRANDS


WF42G GIRDER DETAILS 3 OF 3

Figure 5-A-92



GIRDER ELEVATION

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE OR APPROVED EQUAL. (TYP.)




OPEN HOLE

BOTTOM HOLE AT END TYPE "B" ONLY


NOTES:

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6"ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6.02.3(25)H OF THE STANDARD SPECIFICATIONS
6. LIFTING BARS SHALL BE 1⅜"ø HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM.) LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGRESS OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING. ONCE ERECTED, ALL GIRDERS SHALL BE BRACED TO PREVENT TIPPING UNTIL THE INTERMEDIATE DIAPHRAGMS ARE CAST AND CURED.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
9. FOR SAWTOOTH DETAILS SEE WF50G GIRDER DETAILS 2 OF 3.
10. TEMPORARY STRANDS ARE PRETENSIONED OR POST-TENSIONED. IF PRETENSIONED, THESE TEMPORARY STRANDS SHALL BE UNBONDED OVER ALL BUT THE END 10'-0" OF THE GIRDER LENGTH. AS AN ALTERNATE, TEMPORARY STRANDS MAY BE POST-TENSIONED BEFORE THE GIRDER IS LIFTED FROM THE FORM. TEMPORARY STRANDS SHALL BE CUT AFTER ALL GIRDERS ARE ERECTED, BUT BEFORE INTERMEDIATE DIAPHRAGMS ARE CAST.




TYPICAL END ELEVATION

END OF TYPE C SHOWN, OTHER END TYPES SIMILAR



VIEW B

SAWTEETH SHOWN BY SHADED AREA.



SECTION C


DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0"	0"	0"	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO

TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	≠
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6	STR.
G10	GIRDER STIRRUPS	4	STR.


BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)



≠ #3 OR #4 MAY BE SUBSTITUTED. FIELD BENDING IS OPTIONAL. ** SHALL BE CHECKED FOR EFFECT OF RDWY VERTICAL CURVE


WF50G GIRDER DETAILS 1 OF 3

Figure 5-A-93




STRAND PATTERN AT GIRDER END


HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



STRAND PATTERN AT ℄ SPAN


STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.





SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - WF74G GIRDER DETAILS 1 OF 3




TRANSVERSE REINFORCING SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN


GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	F℄	Fb	Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




ELEVATION




PLAN - BEARING RECESS AND BOTTOM FLANGE SPALL PROTECTION DETAIL

WF50G GIRDER DETAILS 2 OF 3

Figure 5-A-94




ALTERNATE #1



ALTERNATE #2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS



ALTERNATE #3

NOTES TO DESIGNER:


1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.


3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor. The total number of extended strands shall not be less than:

$$Nps = 12(Mc + Vc \times h - M_{SIDL}) \times Nc \times \frac{K}{Ng} \quad (0.9\ Aps \times fps \times d)$$

where:
Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = nember of girders
Aps = area of each extended strand, in^2
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2



ANCHOR PLATE DETAIL




TEMPORARY STRAND BLOCKOUT DETAIL


(MOVE NOTE TO SLAB SECTION SHEET)

TEMPORARY STRAND CUTTING SEQUENCE

1. ERECT AND BRACE GIRDERS.
2. REMOVE EXPANDED POLYSTYRENE IN 2" X 2" RECESSES IN TOP FLANGE OF GIRDERS.
3. CUT STRAND AND PLASTIC SLEEVE IN 2" X 2" RECESS.
4. REMOVE ALL MOISTURE IN RECESS PRIOR TO FILLING RECESS WITH GROUT.
5. CAST INTERMEDIATE & END DIAPHRAGMS.
6. PLACE DECK CONCRETE.




STRAND PATTERN AT GIRDER END




PLAN VIEW OF TEMPORARY STRANDS

WF50G GIRDER DETAILS 3 OF 3

Figure 5-A-95



GIRDER ELEVATION




OPEN HOLE

BOTTOM HOLE AT END TYPE "B" ONLY

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅜") FERRULE OR APPROVED EQUAL. (TYP.)


NOTES:

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6"ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6.02.3(25)H OF THE STANDARD SPECIFICATIONS
6. LIFTING BARS SHALL BE 1⅜"ø HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM,) LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGRESS OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING. ONCE ERECTED, ALL GIRDERS SHALL BE BRACED TO PREVENT TIPPING UNTIL THE INTERMEDIATE DIAPHRAGMS ARE CAST AND CURED.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
9. FOR SAWTOOTH DETAILS SEE WF58G GIRDER DETAILS 2 OF 3.
10. TEMPORARY STRANDS ARE PRETENSIONED OR POST-TENSIONED. IF PRETENSIONED, THESE TEMPORARY STRANDS SHALL BE UNBONDED OVER ALL BUT THE END 10'-0" OF THE GIRDER LENGTH. AS AN ALTERNATE, TEMPORARY STRANDS MAY BE POST-TENSIONED BEFORE THE GIRDER IS LIFTED FROM THE FORM. TEMPORARY STRANDS SHALL BE CUT AFTER ALL GIRDERS ARE ERECTED, BUT BEFORE INTERMEDIATE DIAPHRAGMS ARE CAST.




TYPICAL END ELEVATION

END TYPE C SHOWN, OTHER END TYPES SIMILAR



VIEW B

SAWTEETH SHOWN BY SHADED AREA.



SECTION C

DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0"	0"	0"	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO


TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	#
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6	STR.

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)


NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"



* #3 OR #4 MAY BE SUBSTITUTED.FIELD BENDING IS OPTIONAL. ** SHALL BE CHECKED FOR EFFECT OF RDWY VERTICAL CURVE


WF58G GIRDER DETAILS 1 OF 3

Figure 5-A-96




STRAND PATTERN AT GIRDER END


HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



STRAND PATTERN AT ℄ SPAN


STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.





SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - WF74G GIRDER DETAILS 1 OF 3




TRANSVERSE REINFORCING SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN


GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	F℄	Fb	Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




ELEVATION




PLAN - BEARING RECESS AND BOTTOM FLANGE SPALL PROTECTION DETAIL

WF58G GIRDER DETAILS 2 OF 3

Figure 5-A-97




ALTERNATE #1



ALTERNATE #2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS



ALTERNATE #3

NOTES TO DESIGNER:


1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.


3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor. The total number of extended strands shall not be less than:

$$Nps = 12(Mc + Vc \times h - M_{SIDL}) \times \frac{Nc}{Ng} \times \frac{K}{(0.9\ Aps \times fps \times d)}$$

where:
Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = nember of girders
Aps = area of each extended strand, in ^{2}
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2



ANCHOR PLATE DETAIL




TEMPORARY STRAND BLOCKOUT DETAIL


(MOVE NOTE TO SLAB SECTION SHEET)

TEMPORARY STRAND CUTTING SEQUENCE

1. ERECT AND BRACE GIRDERS.
2. REMOVE EXPANDED POLYSTYRENE IN 2" X 2" RECESSES IN TOP FLANGE OF GIRDERS.
3. CUT STRAND AND PLASTIC SLEEVE IN 2" X 2" RECESS.
4. REMOVE ALL MOISTURE IN RECESS PRIOR TO FILLING RECESS WITH GROUT.
5. CAST INTERMEDIATE & END DIAPHRAGMS.
6. PLACE DECK CONCRETE.




STRAND PATTERN AT GIRDER END



PLAN VIEW OF TEMPORARY STRANDS


WF58G GIRDER DETAILS 3 OF 3

Figure 5-A-98



* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE INSERT OR APPROVED EQUAL. (TYP.)


* *6 : 1 FOR ½"ø STRANDS & 8 : 1 FOR 0.6"ø STRANDS




OPEN HOLE
BOTTOM HOLE AT END TYPE "B" ONLY

NOTES:


1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6"ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6.02.3(25)H OF THE STANDARD SPECIFICATIONS
6. LIFTING BARS SHALL BE 1⅜"ø HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM.) LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGREES OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING. ONCE ERECTED, ALL GIRDERS SHALL BE BRACED TO PREVENT TIPPING UNTIL THE INTERMEDIATE DIAPHRAGMS ARE CAST AND CURED.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
9. FOR SAWTOOTH DETAILS SEE WF74G GIRDER DETAILS 2 OF 3.
10. TEMPORARY STRANDS ARE PRETENSIONED OR POST-TENSIONED. IF PRETENSIONED, THESE TEMPORARY STRANDS SHALL BE UNBONDED OVER ALL BUT THE END 10'-0" OF THE GIRDER LENGTH. AS AN ALTERNATE, TEMPORARY STRANDS MAY BE POST-TENSIONED BEFORE THE GIRDER IS LIFTED FROM THE FORM. TEMPORARY STRANDS SHALL BE CUT AFTER ALL GIRDERS ARE ERECTED, BUT BEFORE INTERMEDIATE DIAPHRAGMS ARE CAST.



TYPICAL END ELEVATION
END TYPE C SHOWN, OTHER END TYPES SIMILAR.



VIEW B



SECTION C

DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0"	0"	0"	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO


TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	≠
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6	STR.

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)


NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"



≠ #3 OR #4 MAY BE SUBSTITUTED.FIELD BENDING IS OPTIONAL. ** SHALL BE CHECKED FOR EFFECT OF RDWY VERTICAL CURVE


WF74G GIRDER DETAILS 1 OF 3

Figure 5-A-99




STRAND PATTERN AT GIRDER END


HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



STRAND PATTERN AT ℄ SPAN


STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.





SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - WF74G GIRDER DETAILS 1 OF 3




TRANSVERSE REINFORCING SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN


GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	LOCATION OF C.G. STRANDS (IN.) F℄	LOCATION OF C.G. STRANDS (IN.) Fb	LOCATION OF C.G. STRANDS (IN.) Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




ELEVATION




PLAN - BEARING RECESS AND BOTTOM FLANGE SPALL PROTECTION DETAIL

WF74G GIRDER DETAILS 2 OF 3

Figure 5-A-100




ALTERNATE #1



ALTERNATE #2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS



ALTERNATE #3

NOTES TO DESIGNER:


1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.


3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor. The total number of extended strands shall not be less than:

$$Nps = 12(Mc + Vc \times h - M_{SIDL}) \times \frac{Nc}{Ng} \times \frac{K}{(0.9 \times Aps \times fps \times d)}$$

where:
Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips
h = distance from top of column to c.g. of superestructure, Ft
Nc = number of columns
Ng = nember of girders
Aps = area of each extended strand, in ^{2}
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2



TEMPORARY STRAND BLOCKOUT DETAIL




ANCHOR PLATE DETAIL


(MOVE NOTE TO SLAB SECTION SHEET)

TEMPORARY STRAND CUTTING SEQUENCE

1. ERECT AND BRACE GIRDERS.
2. REMOVE EXPANDED POLYSTYRENE IN 2" X 2" RECESSES IN TOP FLANGE OF GIRDERS.
3. CUT STRAND AND PLASTIC SLEEVE IN 2" X 2" RECESS.
4. REMOVE ALL MOISTURE IN RECESS PRIOR TO FILLING RECESS WITH GROUT.
5. CAST INTERMEDIATE & END DIAPHRAGMS.
6. PLACE DECK CONCRETE.




STRAND PATTERN AT GIRDER END




PLAN VIEW OF TEMPORARY STRANDS

WF74G GIRDER DETAILS 3 OF 3

Figure 5-A-101




TYPICAL END DIAPHRAGM




SECTION F

NOTE TO DESIGNER


If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.




ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS





END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.

NOTE:


GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.

WF74G End Diaphragm on Girder Details

Figure 5-A-102



TYPICAL END TYPE "B" DIAPHRAGM AT END PIERS




ANCHOR DETAIL

A.S.T.M. A-307


NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".



SECTION A

** DISTANCE FROM TOP OF GIRDER TO BOTTOM OF DIAPHRAGM + "A"




ROADWAY EXPANSION JOINT AT END PIERS

LONGITIDINAL DIMENSIONS ARE NORMAL TO SKEW


WF74G Abutment Type Pier Diaphragm Details

Figure 5-A-103



PLAN - FIXED FLUSH-FACE DIAPHRAGM


* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET




SECTION A

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



TYPICAL FIXED FLUSH-FACE DIAPHRAGM



DETAIL B



OAK BLOCK DETAIL


NOTES TO DESIGNER

FIXED BAR PLAN IS SHOWN FOR DESIGNER. THE ACTUAL FIXED BARS SHALL BE LOCATED ALONG THE ℄ PIER ON THE CROSSBEAM DETAILS SHEET FOR FINAL CONTRACT PLANS.

OAK BLOCK WEDGES SHALL BE SHOWN ON CROSSBEAM PLAN SHEET, PARALLEL TO THE ℄ PIER IF SKEWED. CROSSBEAM WIDTH IS DICTATED BY OAK BLOCK LOCATION.


WF74G Fixed Flush-Face Diaphragm at Intermediate Pier Details

Figure 5-A-104



PLAN - FIXED RECESSED-FACE DIAPHRAGM


* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET




SECTION A

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



DETAIL B



TYPICAL FIXED RECESSED-FACE DIAPHRAGM



OAK BLOCK DETAIL


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.

Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.


WF74G Fixed Recessed-Face Diaphragm at Intermediate Pier Details


Figure 5-A-105




PLAN - HINGE DIAPHRAGM

10° MAX. SKEW FOR HINGE DIAPHRAGM.
* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET






HINGE BAR PLAN




SECTION A



TYPICAL HINGE SECTION

** FOR SAWTOOTH SHEAR KEY DETAILS, SEE GIRDER SHEETS.



TYP. END VIEW HINGE DIAPHRAGM


NOTES TO DESIGNER

Hinge bar plan is shown for designer. The actual hinge bars shall be located along the ℄ pier on the crossbeam details sheet, for final contract plans. The hinge bars shall be deleted from this sheet prior to the award copy of the contract plans.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by the oak block location.


WF74G Hinge Diaphragm at Intermediate Pier Details

Figure 5-A-106



TYPICAL INTERMEDIATE DIAPHRAGM






ANCHOR DETAIL
A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".

WF74G Intermediate Diaphragm Details


Figure 5-A-107




SECTION G

NOTE:

1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.




GROUT PAD ELEVATION



ELASTOMERIC STOP PAD


DUROMETER HARDNESS = 60



BEARING PAD

LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60

(SKEW ANGLE SHOWN @ 30°)




GROUT PAD DETAIL

(SKEW ANGLE SHOWN @ 30°)

WF74G Miscelleneous Diaphragm Details

Figure 5-A-108



GIRDER ELEVATION


* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE INSERT OR APPROVED EQUAL. (TYP.)

OPEN HOLE


BOTTOM HOLE AT END TYPE "B" ONLY

NOTES:

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6" ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHAL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-023(25)H OF THE STANDARD SPECIFICATIONS.
6. LIFTING BARS SHALL BE 1⅜ INCH DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM,) LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGRESS OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING. ONCE ERECTED, ALL GIRDERS SHALL BE BRACED TO PREVENT TIPPING UNTIL THE INTERMEDIATE DIAPHRAGMS ARE CAST AND CURED.
8. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
9. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
10. FOR SAWTOOTH DETAILS SEE WF83G GIRDER DETAILS 2 OF 3.
11. TEMPORARY STRANDS ARE PRETENSIONED OR POST-TENSIONED. IF PRETENSIONED, THESE TEMPORARY STRANDS SHALL BE UNBONDED OVER ALL BUT THE END 10'-0" OF THE GIRDER LENGTH. AS AN ALTERNATE, TEMPORARY STRANDS MAY BE POST TENSIONED BEFORE THE GIRDER IS LIFTED FROM THE FORM. TEMPORARY STRANDS SHALL BE CUT AFTER ALL GIRDERS ARE ERECTED, BUT BEFORE INTERMEDIATE DIAPHRAGMS ARE CAST.




TYPICAL END ELEVATION



VIEW B

SAWTEETH SHOWN BY SHADED AREA.



SECTION C


DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0"	0"	0"	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO


TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE


ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	≠
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6	STR.








≠ #3 OR #4 MAY BE SUBSTITUTED.FIELD BENDING IS OPTIONAL.
NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"

** SHALL BE CHECKED FOR EFFECT OF RDWY VERTICAL CURVE

≠ DESIGNER TO REMOVE AND / OR REPLACE WITH APPROPRIATE PIER LOCATION
≠ ≠ DESIGNER TO OMIT IF NOT APPLICABLE
≠ ≠ ≠ END TYPE "C" SHOWN - END TYPES "D" SIMILAR EXCEPT STRAND EXTENSION DETAIL SEE W83G GIRDER DETAILS 3 OF 4.
END TYPE "C" FOR CONTINUOUS SPAN WITH HINGED CONNECTION TO COLUMN
END TYPE "D" FOR CONTINUOUS SPAN FULLY FIXED TO COLUMN


W83G GIRDER DETAILS 1 OF 3

Figure 5-A-109




STRAND PATTERN AT GIRDER END


HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



STRAND PATTERN AT ℄ SPAN


STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.





SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN view B - W83G GIRDER DETAILS 1 OF 3




TRANSVERSE REINFORCING SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN


GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'c (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'ci (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	F℄	Fb	Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




ELEVATION




PLAN - BEARING RECESS AND BOTTOM FLANGE SPALL PROTECTION DETAIL

W83G GIRDER DETAILS 2 OF 3


Figure 5-A-110



ALTERNATE #1



ALTERNATE #2



ALTERNATE #3

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS

NOTES TO DESIGNER:


1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.


3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor. The total number of extended strands shall not be less than:

$$Nps = 12(Mc + Vc \times h - M_{SIDL}) \times \frac{Nc}{Ng} \times \frac{K}{(0.9 \times Aps \times fps \times d)}$$


where:
Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = nember of girders
Aps = area of each extended strand, in^2
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2



ALTERNATE STIRRUP DETAIL



TEMPORARY STRAND BLOCKOUT DETAIL




ANCHOR PLATE DETAIL


(MOVE NOTE TO SLAB SECTION SHEET)

TEMPORARY STRAND CUTTING SEQUENCE

1. ERECT AND BRACE GIRDERS.
2. REMOVE EXPANDED POLYSTYRENE IN 2" X 2" RECESSES IN TOP FLANGE OF GIRDERS.
3. CUT STRAND AND PLASTIC SLEEVE IN 2" X 2" RECESS.
4. REMOVE ALL MOISTURE IN RECESS PRIOR TO FILLING RECESS WITH GROUT.
5. CAST INTERMEDIATE & END DIAPHRAGMS.
6. PLACE DECK CONCRETE.
7. SEE SHEET W83G GIRDER DETAILS 3 OF 3 FOR 2" RECESS BLOCKOUT DETAILS.




STRAND PATTERN AT GIRDER END




PLAN VIEW OF TEMPORARY STRANDS

W83G GIRDER DETAILS 3 OF 3

Figure 5-A-111




TYPICAL END DIAPHRAGM




SECTION F

 # NOTE TO DESIGNER


If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.




ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS





END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.

NOTE:


GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.


W83G End Diaphragm on Girder Details

Figure 5-A-112



TYPICAL END TYPE "B" DIAPHRAGM AT END PIERS






ANCHOR DETAIL

A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".




ROADWAY EXPANSION JOINT AT END PIERS

LONGITIDINAL DIMENSIONS ARE NORMAL TO SKEW


W83G Abutment Type Pier Diaphragm Details

Figure 5-A-113



PLAN - FIXED FLUSH-FACE DIAPHRAGM

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET



SECTION A


NOTES TO DESIGNER

FIXED BAR PLAN IS SHOWN FOR DESIGNER. THE ACTUAL FIXED BARS SHALL BE LOCATED ALONG THE ℄ PIER ON THE CROSSBEAM DETAILS SHEET FOR FINAL CONTRACT PLANS.


OAK BLOCK WEDGES SHALL BE SHOWN ON CROSSBEAM PLAN SHEET, PARALLEL TO THE ℄ PIER IF SKEWED. CROSSBEAM WIDTH IS DICTATED BY OAK BLOCK LOCATION.

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



TYPICAL FIXED FLUSH-FACE DIAPHRAGM




DETAIL B



OAK BLOCK DETAIL


W83G Fixed Flush-Face Diaphragm at Intermediate Pier Details

Figure 5-A-114



PLAN - FIXED RECESSED-FACE DIAPHRAGM


* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET




SECTION A

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



DETAIL B



TYPICAL FIXED RECESSED-FACE DIAPHRAGM



OAK BLOCK DETAIL


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.

Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.


W83G Fixed Recessed-Face Diaphragm at Intermediate Pier Details


Figure 5-A-115




PLAN - HINGE DIAPHRAGM


10° MAX. SKEW FOR HINGE DIAPHRAGM.
* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET






HINGE BAR PLAN





TYPICAL HINGE SECTION



TYP. END VIEW HINGE DIAPHRAGM


NOTES TO DESIGNER

Hinge bar plan is shown for designer. The actual hinge bars shall be located along the ℄ pier on the crossbeam details sheet, for final contract plans. The hinge bars shall be deleted from this sheet prior to the award copy of the contract plans.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by the oak block location.

W83G Hinge Diaphragm at Intermediate Pier Details


Figure 5-A-116



TYPICAL INTERMEDIATE DIAPHRAGM



SECTION B



ANCHOR DETAIL


A.S.T.M. A-307

NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".

W83G Intermediate Diaphragm Details


Figure 5-A-117




SECTION G

NOTE:

1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE CEMENTED TO GIRDER STOPS WITH APPROVED RUBBER CEMENT.




GROUT PAD ELEVATION



ELASTOMERIC STOP PAD


DUROMETER HARDNESS = 60



BEARING PAD

LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60

(SKEW ANGLE SHOWN @ 30°)




GROUT PAD DETAIL

(SKEW ANGLE SHOWN @ 30°)

W83G Miscelleneous Diaphragm Details

Figure 5-A-118




GIRDER ELEVATION

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE INSERT OR APPROVED EQUAL. (TYP.)


OPEN HOLE
BOTTOM HOLE AT END TYPE "B" ONLY

NOTES:


1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6" ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-023(25)H OF THE STANDARD SPECIFICATIONS.
6. LIFTING BARS SHALL BE 1⅜ INCH DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM.) LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGRESS OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING. ONCE ERECTED, ALL GIRDERS SHALL BE BRACED TO PREVENT TIPPING UNTIL THE INTERMEDIATE DIAPHRAGMS ARE CAST AND CURED.
8. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
9. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
10. FOR SAWTEETH DETAILS SEE WF95G GIRDER DETAILS 2 OF 3.
11. TEMPORARY STRANDS ARE PRETENSIONED OR POST-TENSIONED. IF PRETENSIONED, THESE TEMPORARY STRANDS SHALL BE UNBONDED OVER ALL BUT THE END 10'-0" OF THE GIRDER LENGTH. AS AN ALTERNATE, TEMPORARY STRANDS MAY BE POST TENSIONED BEFORE THE GIRDER IS LIFTED FROM THE FORM. TEMPORARY STRANDS SHALL BE CUT AFTER ALL GIRDERS ARE ERECTED, BUT BEFORE INTERMEDIATE DIAPHRAGMS ARE CAST.



TYPICAL END ELEVATION
END TYPE C SHOWN, OTHER END TYPES SIMILAR



VIEW B
SAWTEETH SHOWN BY SHADED AREA.



SECTION C


DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0"	0"	0"	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIX DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULT. SIMPLE SPANS @ INTERM. PIER	E	YES	0"	0"	0"	NO


TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE


ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0" (G4 , G9)
B2 = 0" (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	#
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6	STR.








= #3 OR #4 MAY BE SUBSTITUTED.FIELD BENDING IS OPTIONAL.
NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"

** SHALL BE CHECKED FOR EFFECT OF RDWY VERTICAL CURVE


W95G GIRDER DETAILS 1 OF 3

Figure 5-A-119




STRAND PATTERN AT GIRDER END


HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



STRAND PATTERN AT ℄ SPAN

STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), 2) ETC.






SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - W95G GIRDER DETAILS 1 OF 3

GIRDER SCHEDULE


DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	F℄	Fb	Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




TRANSVERSE REINFORCING SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN




ELEVATION




PLAN - BEARING RECESS AND BOTTOM FLANGE SPALL PROTECTION DETAIL

W95G GIRDER DETAILS 2 OF 3

Figure 5-A-120




ALTERNATE #1



ALTERNATE #2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS



ALTERNATE #3

NOTES TO DESIGNER:


1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.


3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor. The total number of extended strands shall not be less than:

$$Nps = 12(Mc + Vc \times h - M_{SIDL}) \times \frac{Nc}{Ng} \times \frac{K}{(0.9\ Aps \times fps \times d)}$$


where:
Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = nember of girders
Aps = area of each extended strand, in ^{2}
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2



ALTERNATE STIRRUP DETAIL



TEMPORARY STRAND BLOCKOUT DETAIL




ANCHOR PLATE DETAIL


(MOVE NOTE TO SLAB SECTION SHEET)

TEMPORARY STRAND CUTTING SEQUENCE

1. ERECT AND BRACE GIRDERS.
2. REMOVE EXPANDED POLYSTYRENE IN 2" X 2" RECESSES IN TOP FLANGE OF GIRDERS.
3. CUT STRAND AND PLASTIC SLEEVE IN 2" X 2" RECESS.
4. REMOVE ALL MOISTURE IN RECESS PRIOR TO FILLING RECESS WITH GROUT.
5. CAST INTERMEDIATE & END DIAPHRAGMS.
6. PLACE DECK CONCRETE.




STRAND PATTERN AT GIRDER END




PLAN VIEW OF TEMPORARY STRANDS

W95G GIRDER DETAILS 3 OF 3

Figure 5-A-121




TYPICAL END DIAPHRAGM




SECTION F

 # NOTE TO DESIGNER


If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.




ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS





END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A". ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.

NOTE:


GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.

W95G End Diaphragm on Girder Details

Figure 5-A-122



TYPICAL END TYPE "B" DIAPHRAGM AT END PIERS




ANCHOR DETAIL

A.S.T.M. A-307


NOTE:

GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".



SECTION A

** DISTANCE FROM TOP OF GIRDER TO BOTTOM OF DIAPHRAGM + "A"




ROADWAY EXPANSION JOINT AT END PIERS

LONGITIDINAL DIMENSIONS ARE NORMAL TO SKEW


W95G Abutment Type Pier Diaphragm Details

Figure 5-A-123



PLAN - FIXED FLUSH-FACE DIAPHRAGM

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET



SECTION A


NOTES TO DESIGNER

FIXED BAR PLAN IS SHOWN FOR DESIGNER. THE ACTUAL FIXED BARS SHALL BE LOCATED ALONG THE ℄ PIER ON THE CROSSBEAM DETAILS SHEET FOR FINAL CONTRACT PLANS.


OAK BLOCK WEDGES SHALL BE SHOWN ON CROSSBEAM PLAN SHEET, PARALLEL TO THE ℄ PIER IF SKEWED. CROSSBEAM WIDTH IS DICTATED BY OAK BLOCK LOCATION.

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



DETAIL B




TYPICAL FIXED FLUSH-FACE DIAPHRAGM



OAK BLOCK DETAIL


W95G Fixed Flush-Face Diaphragm at Intermediate Pier Details

Figure 5-A-124



PLAN - FIXED RECESSED-FACE DIAPHRAGM

* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET



SECTION A


NOTES TO DESIGNER

Fixed bar plan is shown for Designer. The actual bar spacing shall be determined by the Designer.


Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by oak block location.

CONSTRUCTION SEQUENCE


1. CROSSBEAM
2. PLACE GIRDER ON BLOCKS
3. DIAPHRAGM STAGE 2
4. ROADWAY SLAB
5. COMPLETE DIAPHRAGM



DETAIL B




TYPICAL FIXED RECESSED-FACE DIAPHRAGM



OAK BLOCK DETAIL


W95G Fixed Recessed-Face Diaphragm at Intermediate Pier Details


Figure 5-A-125




PLAN - HINGE DIAPHRAGM

10° MAX. SKEW FOR HINGE DIAPHRAGM.
* FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET





HINGE BAR PLAN




SECTION A


NOTES TO DESIGNER

Hinge bar plan is shown for designer. The actual hinge bars shall be located along the ℄ pier on the crossbeam details sheet, for final contract plans. The hinge bars shall be deleted from this sheet prior to the award copy of the contract plans.

Oak block wedges shall be shown on crossbeam plan sheet, parallel to the ℄ pier if skewed. Crossbeam width is dictated by the oak block location.




TYPICAL HINGE SECTION




TYP. END VIEW HINGE DIAPHRAGM

W95G Hinge Diaphragm at Intermediate Pier Details

Figure 5-A-126



TYPICAL INTERMEDIATE DIAPHRAGM




ANCHOR DETAIL

A.S.T.M. A-307

NOTE:


GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".



SECTION B

W95G Intermediate Diaphragm Details


Figure 5-A-127




SECTION G

NOTE:

1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.




GROUT PAD ELEVATION



ELASTOMERIC STOP PAD


DUROMETER HARDNESS = 60



BEARING PAD

LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60

(SKEW ANGLE SHOWN @ 30°)




GROUT PAD DETAIL

(SKEW ANGLE SHOWN @ 30°)

W95G Miscelleneous Diaphragm Details

Figure 5-A-128



GIRDER ELEVATION


OPEN HOLE

≠ ≠ BOTTOM HOLE AT END TYPE "B" ONLY

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE OR APPROVED EQUAL. (TYP.)


NOTES:

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6" ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6.02.3(25)H OF THE STANDARD SPECIFICATIONS.
6. LIFTING BARS SHALL BE 1⅜ INCH DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM.) LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGRESS OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING. ONCE ERECTED, ALL GIRDERS SHALL BE BRACED TO PREVENT TIPPING UNTIL THE INTERMEDIATE DIAPHRAGMS ARE CAST AND CURED.
8. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
9. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
10. FOR SAWTEETH DETAILS SEE WF74G GIRDER DETAILS 2 OF 3.




TYPICAL END ELEVATION

END TYPE C SHOWN, OTHER END TYPES SIMILAR



VIEW B

SAWTEETH SHOWN BY SHADED AREA.



SECTION C


DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0	0	0	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SUMPLE SPANS @ INTERM. PIER	E	YES	0	0	0	NO

TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0 (G4 , G9)
B2 = 0 (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

MARK	LOCATION	SIZE	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	≠
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6	STR.


NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"



≠ #3 OR #4 MAY BE SUBSTITUTED. FIELD BENDING IS OPTIONAL. ** SHALL BE CHECKED FOR EFFECT OF RDWY VERTICAL CURVE


W32BTG GIRDER DETAILS 1 OF 3


Figure 5-A-129



SAWTOOTH DETAILS


SAWTEETH ARE FULL WIDTH - USE SAWTEETH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - WF74G GIRDER DETAILS 1 OF 3






STRAND PATTERN AT GIRDER END

HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



TRANSVERSE REINFORCING SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN




PLAN

BOTTOM FLANGE SPALL PROTECTION


END TYPES "C" INTERMEDIATE HINGE DIAPHRAGM AND END TYPE "D" INTEREMEDIATE FIXED DIAPHRAGM



SECTION A



ELEVATION



PLAN

BEARING RECESS DETAIL


GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)


SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	F℄	Fb	Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-

W32BTG GIRDER DETAILS 2 OF 3

Figure 5-A-130



ALTERNATE #1



ALTERNATE #2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS

NOTES TO DESIGNER:

1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.

3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.

The total number of extended strands shall not be less than:

$$Nps = 12(Mc + Vc \times h - M_{SIDL} - M_{TD}) \times \frac{Nc}{Ng} \times \frac{K}{(0.9 \times Aps \times fps \times d)}$$

where:

Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips

h = distance from top of column to c.g. of superstructure, Ft

Nc = number of columns

Ng = nember of girders

Aps = area of each extended strand, in^2

fps = ultimate strength of strands, ksi

d = distance from top of slab to c.g. of extended strands, in

M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)


K = 0.5 for L1 = L2

0.67 for L1 = 2L2

M_{TD} = Time dependent restraint moment at piers.

W32BTG GIRDER DETAILS 3 OF 3

Figure 5-A-131




GIRDER ELEVATION

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE OR APPROVED EQUAL. (TYP.)


NOTES:

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6" ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-023(25)H OF THE STANDARD SPECIFICATIONS.
6. LIFTING BARS SHALL BE 1⅜ INCH DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM.) LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGRESS OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING. ONCE ERECTED, ALL GIRDERS SHALL BE BRACED TO PREVENT TIPPING UNTIL THE INTERMEDIATE DIAPHRAGMS ARE CAST AND CURED.
8. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
9. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
10. FOR SAWTEETH DETAILS SEE WF74G GIRDER DETAILS 2 OF 3.




TYPICAL END ELEVATION

END TYPE C SHOWN, OTHER END TYPES SIMILAR



VIEW B

SAWTEETH SHOWN BY SHADED AREA.



SECTION C


DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0	0	0	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SUMPLE SPANS @ INTERM. PIER	E	YES	0	0	0	NO

TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0 (G4 , G9)
B2 = 0 (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

MARK	LOCATION	SIZE	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	#
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6	STR.

NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"




shALL BE CHECKED FOR EFFECT OF RDWY VERTICAL CURVE

3 OR #4 MAY BE SUBSTITUTED,FIELD BENDING IS OPTIONAL.


W38BTG GIRDER DETAILS 1 OF 3

Figure 5-A-132




SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTEETH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - WF74G GIRDER DETAILS 1 OF 3




END 1 END 2




STRAND PATTERN AT GIRDER END

HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



TRANSVERSE REINFORCING SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN



PLAN

BOTTOM FLANGE SPALL PROTECTION

END TYPES "C" INTERMEDIATE HINGE DIAPHRAGM AND END TYPE "D" INTEREMEDIATE FIXED DIAPHRAGM




SECTION A


GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	F℄	Fb	Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-



ELEVATION




PLAN


BEARING RECESS DETAIL

W38BTG GIRDER DETAILS 2 OF 3

Figure 5-A-133



ALTERNATE #1



ALTERNATE #2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS

NOTES TO DESIGNER:

1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.

3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.

The total number of extended strands shall not be less than:

$$Nps = 12(Mc + Vc \times h - M_{SIDL} - M_{TD}) \times \frac{}{Ng} \times Nc \times \frac{K}{(0.9\ Aps \times fps \times d)}$$

where:

Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips

h = distance from top of column to c.g. of superstructure, Ft

Nc = number of columns

Ng = nember of girders

Aps = area of each extended strand, in^2

fps = ultimate strength of strands, ksi

d = distance from top of slab to c.g. of extended strands, in

M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)


K = 0.5 for L1 = L2

0.67 for L1 = 2L2

M_{TD} = Time dependent restraint moment at piers.

W38BTG GIRDER DETAILS 3 OF 3

Figure 5-A-134



GIRDER ELEVATION


OPEN HOLE

≠ ≠ BOTTOM HOLE AT END TYPE "B" ONLY

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE OR APPROVED EQUAL. (TYP.)


NOTES:

1. ALL DETAILS ON THIS SHEET ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6" ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-023(25)H OF THE STANDARD SPECIFICATIONS.
6. LIFTING BARS SHALL BE 1⅜ INCH DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM.) LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGRESS OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING. ONCE ERECTED, ALL GIRDERS SHALL BE BRACED TO PREVENT TIPPING UNTIL THE INTERMEDIATE DIAPHRAGMS ARE CAST AND CURED.
8. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
9. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
10. FOR SAWTEETH DETAILS SEE WF74G GIRDER DETAILS 2 OF 3.




TYPICAL END ELEVATION

END TYPE C SHOWN, OTHER END TYPES SIMILAR



VIEW B

SAWTEETH SHOWN BY SHADED AREA.



SECTION C


DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
END DIAPH. ON GIRDER	A	YES	1'-10"	1'-6"	9"	YES
"L" ABUTMENT	B	YES	0	0	0	NO
HINGE DIAPH. ON INTERM. PIER	C	NO	1'-10"	1'-6"	9"	YES
FIXED DIAPH. @ INTERM. PIER	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
MULTI. SUMPLE SPANS @ INTERM. PIER	E	YES	0	0	0	NO

TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0 (G4 , G9)
B2 = 0 (G5)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4 , G9)
B2 = 3" (G5)

MARK	LOCATION	SIZE	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	≠
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	6	STR.


NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"



≠ #3 OR #4 MAY BE SUBSTITUTED.FIELD BENDING IS OPTIONAL. ** SHALL BE CHECKED FOR EFFECT OF RDWY VERTICAL CURVE


W62BTG GIRDER DETAILS 1 OF 3


Figure 5-A-135



SAWTOOTH DETAILS


SAWTEETH ARE FULL WIDTH - USE SAWTEETH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN IN VIEW B - WF74G GIRDER DETAILS 1 OF 3






STRAND PATTERN AT GIRDER END

HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



TRANSVERSE REINFORCING SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN



PLAN

BOTTOM FLANGE SPALL PROTECTION

END TYPES "C" INTERMEDIATE HINGE DIAPHRAGM AND END TYPE "D" INTEREMEDIATE FIXED DIAPHRAGM




SECTION A


GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	TEMPORARY NO. OF STRANDS	TEMPORARY JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	F℄	Fb	Fo	C (IN.)	D (IN.)	Pt (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-



ELEVATION




PLAN


BEARING RECESS DETAIL

W62BTG GIRDER DETAILS 2 OF 3

Figure 5-A-136



ALTERNATE #1



ALTERNATE #2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS

NOTES TO DESIGNER:

1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms.

2. Alternate 3 may be used if additional strands beyond the ones shown in alternates 1 & 2 are required.

3. Designer shall calculatethe exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.
   The total number of extended strands shall not be less than:


$$Nps = 12(Mc + Vc \times h - M_{SIDL} \times M_{TD}) \times \frac{Nc}{Ng} \times \frac{K}{(0.9 \times Aps \times fps \times d)}$$

where:

Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear of column respectively, Ft-kips, kips
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = nember of girders
Aps = area of each extended strand, in^2
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M_{SIDL} = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
$K = 0.5$ for L1 = L2
0.67 for L1 = 2L2
M_{TD} = Time dependent restraint moment at piers.


W62BTG GIRDER DETAILS 3 OF 3

Figure 5-A-137




GIRDER ELEVATION

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅜") FERRULE OR APPROVED EQUAL. (TYP.)




BOTTOM SLAB DRAIN HOLE DETAIL




OPEN HOLE DETAIL

BOTTOM HOLE AT END TYPE "B" ONLY



TYPICAL END ELEVATION

END TYPE "C" SHOWN, OTHER END TYPES SIMILAR



TYPICAL SECTION


NOTES:


1. THESE SHEETS ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE ½" OR 0.6"ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. EXTENDED STRANDS AND BARS ARE PARALLEL TO GIRDER.
6. LIFTING BARS SHALL BE 1⅜" ø HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM.) IF THE LIFTING BARS EXTEND WITHIN 3" OF THE TOP OF THE ROADWAY SLAB, THEY SHALL BE CUT OFF PRIOR TO PLACING THE ROADWAY SLAB. LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGREES OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING.
8. THE TOP SURFACE OF THE GIRDER WEBS SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H.
9. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
10. FOR SAWTOOTH DETAILS SEE GIRDER DETAILS 2 OF 3.

Notes to designer						
DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
End diaph. on girder	A	YES	1'-10"	1'-6"	9"	YES
"L" Abutment	B	YES	0	0	0	NO
Hinge diaph.on interm. pier	C	NO	1'-10"	1'-6"	9"	YES
Fixed diaph.@ interm. pier	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
Mult. simple spans @ interm. pier	E	YES	0	0	0	NO

Prestressed Trapezoidal Tub Girder Details 1 of 3


Figure 5-A-138






TYPICAL END ELEVATION

EXTENDED STRANDS NOT SHOWN.
USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE
TO BOTTOM OF LOWEST HARPED STRANDS.



P.C. SECTION



PLAN

BOTTOM FLANGE SPALL PROTECTION

END TYPE "C" INTERMEDIATE HINGE DIAPHRAGM
AND END TYPE "D" INTEREMEDIATE FIXED DIAPHRAGM


BENDING DIAGRAM

MARK	LOCATION	SIZE	U	W	X	
G1	STIRRUPS, OUTSIDE WEB	5				
G2	STIRRUPS, INSIDE WEB	5				
G3	LONGITUDINAL BOTTOM FLANGE	4				STR.
G4	LONGITUDINAL TOP	6				STR.
G5	LONGITUDINAL WEB	6				STR.
G6	WEB TIE	W12				# #4 MAY BE SUBSTITUTED FOR W12, FIELD BENDING IS OPTIONAL
G7	BOTTOM FLANGE	5				
G8	STIRRUP, OUTSIDE WEB	4				
G9	STIRRUP, INSIDE WEB	4				
G10	LONGITUDINAL BOTTOM	4				STR.


ALL DIMENSIONS ARE OUT TO OUT

* = VARIES FOR SKEWED SPANS

NOTE:
FOR DIMENSION "A", SEE "GIRDER SCHEDULE"




SECTION A




TRANSVERSE REINFORCING AT SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN





SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTEETH
FULL HEIGHT ON END SECTIONS.









Prestressed Trapezoidal Tub Girder Details 2 of 3

Figure 5-A-139

NOTES TO DESIGNER:


1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only.This detail is not applicable to continuous spans using hinge diaphragms.
2. Designer shall calculate the exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.
   The total number of extended strands shall not be less than:
3. $Nps = 12(Mc + Vc \times h - M_{SIDL}) \times Nc \frac{X}{Ng} \frac{K}{(0.9\ Aps \times fps \times d)}$

where:
Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear capacity of column Ft-kips, kips respectively,
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = number of girders
Aps = area of each extended strand, in
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2

GIRDER SCHEDULE


DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)

SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ_1	θ_2	P_1	P_2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C (KSI)	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI (KSI)	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS (IN.) E	F℄	Fb	Fo	C (IN.)	D (IN.)	Ld (IN.)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




STRAND PATTERN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



ALTERNATE # 1




ALTERNATE # 2

STRAND EXTENSION DETAIL

n = ? TOTAL NUMBER OF EXTENDED STRANDS

Prestressed Trapezoidal Tub Girder Details 3 of 3


Figure 5-A-140




NOTE TO DESIGNER

If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.


TYPICAL END TYPE "A" DIAPHRAGM AT END PIERS




SECTION F




ELEVATION BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW BUTYL RUBBER @ VERTICAL JOINTS





END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.

NOTE:

1. GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.
2. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
3. END DIAPHRAGM MAY BE CAST ON GRADE. IF SO, THE UPPER LEG OF THE JOINT FILLER SHALL FORM THE BOTTOM FACE FULL WIDTH.
4. JOINT FILLER TYPE 1 SHALL BE USED TO COVER ALL VERTICAL END DIAPHRAGM JOINTS. EITHER JOINT FILLER TYPE 1 OR JOINT FILLER TYPE 2 SHALL BE USED TO COVER ALL HORIZONTAL END DIAPHRAGM JOINTS.


Prestressed Trapezoidal Tub Girder End Diaphragm on Girder Details

Figure 5-A-141




PLAN


FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET 3.




SECTION A



TEMPORARY SUPPORT DETAIL




DETAIL C



ELEVATION

CONSTRUCTION SEQUENCE


1. COLUMN & TEMP. SUPPORT
2. PLACE GIRDER ON TEMPORARY SUPPORT
3. CAST DIAPHRAGM STAGE 1
4. CAST ROADWAY SLAB
5. COMPLETE DIAPHRAGM
6. REMOVE TEMPORARY SUPPORT



SECTION B

Prestressed Trapezoidal Tub Girder Raised Crossbeam Details

Figure 5-A-142




DETAIL G

NOTE TO DESIGNER:

This detail to be used on bridges with end piers and no wing walls, and located within and west of the Cascade Mountain range.


NOTE:

1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE COATED WITH RUBBER CEMENT PRIOR TO INSTATLLATION.




EXPANSION JOINT DETAILS

JOINT AT INTERMEDIATE PIER SHOWN




ANCHOR DETAIL

A.S.T.M. A-307




DETAIL E




DETAIL F

DRILL ⅛"ø HOLES THROUGH SEAL WITH STANDARD TWIST DRILL MAKING SURE THE TOP MEMBRANE IS NOT DAMAGED. CUT HOLE WITH SHARP LONG BLADE KNIFE.



BEARING PAD


LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60



GROUT PAD DETAIL


Prestressed Trapezoidal Tub Girder Miscellaneous Details

Figure 5-A-143



GIRDER ELEVATION

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR WEB OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE OR APPROVED EQUAL. (TYP.)




OPEN HOLE DETAIL

BOTTOM HOLE AT END TYPE "B" ONLY


NOTES:

1. THESE SHEETS ARE FOR PRETENSIONED DESIGN ONLY.
2. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
3. ALL STRANDS SHALL BE 0.6"ø LOW RELAXATION STRANDS (AASHTO M203 GRADE 270.)
4. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
5. EXTENDED STRANDS AND BARS ARE PARALLEL TO GIRDER.
6. LIFTING BARS SHALL BE 1⅜" ø HIGH STRENGTH THREADED BARS (AASHTO M275 GRADE 150 MINIMUM.) IF THE LIFTING BARS EXTEND WITHIN 3" OF THE TOP OF THE ROADWAY SLAB, THEY SHALL BE CUT OFF PRIOR TO PLACING THE ROADWAY SLAB. LIFTING HARDWARE THAT CONNECTS TO THE THREADED BARS SHALL BE DESIGNED, DETAILED AND FURNISHED BY THE CONTRACTOR. LIFTING FORCES ON THREADED BARS SHALL BE WITHIN 10 DEGRESS OF PERPENDICULAR TO THE TOP OF THE GIRDER. ALTERNATE LIFTING CONFIGURATIONS MAY BE SUBMITTED BY THE CONTRACTOR IN ACCORDANCE WITH SECTION 6-02.3(25)L OF THE STANDARD SPECIFICATIONS.
7. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING GIRDERS. ALL GIRDERS SHALL BE CHECKED BY THE CONTRACTOR TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING.
8. THE TOP SURFACE OF THE GIRDER WEBS SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H.
9. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS TO NOT CAUSE DAMAGE TO THE GIRDER DURING THE STRAND RELEASE OPERATION.
10. FOR SAWTOOTH DETAILS SEE GIRDER DETAILS 2 OF 4.
11. TEMPORARY STRANDS ARE PRETENSIONED OR POST-TENSIONED. IF PRETENSIONED, THESE TEMPORARY STRANDS SHALL BE DEBONDED OVER ALL BUT THE END 10'-0" OF THE GIRDER LENGTH. AS AN ALTERNATE, TEMPORARY STRANDS MAY BE POST-TENSIONED BEFORE THE GIRDER IS LIFTED FROM THE FORM. TEMPORARY STRANDS SHALL BE CUT BEFORE THE INTERMEDIATE DIAPHRAGMS ARE CAST. PATCH RECESS WITH CEMENTITIOUS GROUT; DO NOT ALLOW MOISTURE IN RECESS PRIOR TO GROUTING.
12. P.C. GIRDER ENDS SHALL BE PLUMB IN THE FINAL GIRDER'S ERECTED POSITION.



TYPICAL END ELEVATION

END TYPE C SHOWN - OTHER END TYPES SIMILAR.




SECTION ~ REINFORCEMENT

FOR DRAIN HOLE LOCATIONS SEE "FRAMING PLAN" SHEET.

Notes to designer						
DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
End diaph. on girder	A	YES	1'-10"	1'-6"	9"	YES
"L" Abutment	B	YES	0	0	0	NO
Hinge diaph.on interm. pier	C	NO	1'-10"	1'-6"	9"	YES
Fixed diaph.@ interm. pier	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
Mult. simple spans @ interm. pier	E	YES	0	0	0	NO


Trapezoidal Tub S-I-P Deck Panel Girder - Details 1 of 4

Figure 5-A-144



TYPICAL END ELEVATION


EXTENDED STRANDS AND REINF. NOT SHOWN.




SECTION ~ P.C. GIRDER

* SMOOTH FINISH ON TOP OF GIRDER.

*** 1'-0" FOR BOTTOM FLANGE WIDTH 4'-0" & 5'-0"
2'-0" FOR BOTTOM FLANGE WIDTH 6'-0"




SECTION~EXTERIOR P.C. GIRDER




BEARING RECESS DETAIL


RECESS DEPTH SHALL BE ½" AT ℄ BEARING. RECESS SURFACE SHALL BE LEVEL LONGITUDINALLY AND TRANSVERSELY IN FINAL POSITION OF THE P.C. GIRDER. SEE "FABRIC PAD BEARING PIERS 1 AND 3" SHEET FOR OTHER DETAILS.



END 1 PLAN ~ GIRDER END 2




BOTTOM SLAB DRAIN HOLE DETAIL



TRANSVERSE REINFORCING AT SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN



SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH.
USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRANDS AS WELL AS TOP FLANGE ADJACENT TO HARPED STRANDS AS SHOWN ON "TYPICAL END ELEVATION" THIS SHEET.


BENDING DIAGRAM

MARK	LOCATION	SIZE	U	W	X	ALL DIMENSIONS ARE OUT TO OUT
G1	STIRRUPS, OUTSIDE WEB	5				
G2	STIRRUPS, INSIDE WEB	5				
G3	LONGITUDINAL BOTTOM FLANGE	4			STR.	
G4	TOP WEB TIE	4				
G5	LONGITUDINAL WEB	6			STR.	
G6	WEB TIE	W12			#	
G7	TRANSVERSE TIE	5				
G8	STIRRUPS, OUTSIDE WEB	4				
G9	STIRRUPS, INSIDE WEB	4				
G10	LONGITUDINAL TOP FLANGE	4			STR.	

* = VARIES FOR SKEWED SPANS

NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"

#3 OR #4 MAY BE SUBSTITUTED FOR W12, FIELD BENDING IS OPTIONAL



Trapezoidal Tub S-I-P Deck Panel Girder - Details 2 of 4

Figure 5-A-145

NOTES TO DESIGNER:


1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only.This detail is not applicable to continuous spans using hinge diaphragms.
2. Designer shall calculate the exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.
   The total number of extended strands shall not be less than:
3. $Nps = 12(Mc + Vc \times h - M_{SIDL}) \times Nc \times \frac{1}{Ng} \quad \frac{K}{(0.9\ Aps \times fps \times d)}$

where:

Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear capacity of column Ft-kips, kips respectively,
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = number of girders
Aps = area of each extended strand, in
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2

TEMPORARY STRAND CUTTING SEQUENCE

1. ERECT AND BRACE GIRDERS.
2. REMOVE EXPANDED POLYSTYRENE IN 2" X 2" RECESSES IN TOP FLANGE OF GIRDERS.
3. CUT STRAND AND PLASTIC SLEEVE IN 2" X 2" RECESS.
4. REMOVE ALL MOISTURE IN RECESS PRIOR TO FILLING RECESS WITH GROUT.
5. CAST INTERMEDIATE & END DIAPHRAGMS.
6. PLACE DECK CONCRETE.
7. SEE SHEET W83G GIRDER DETAILS 3 OF 3 FOR 2" RECESS BLOCKOUT DETAILS.




PLAN VIEW OF TEMPORARY STRANDS

Trapezoidal Tub S-I-P Deck Panel Girder - Details 3 of 4
Figure 5-A-146


GIRDER SCHEDULE

DIMENSION "A" AT ℄ BEARINGS = 10"				BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB PLACEMENT (120 DAYS)																		
SPAN	GIRDER	END 1 TYPE	END 2 TYPE	L	θ_1	θ_2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH		HARPED		STRAIGHT		TEMPORARY		LOCATION OF C.G. STRANDS (IN.)				C (IN.)	D (IN.)	Ld (IN.)
								@ FINAL F'C (KSI)	@ RELEASE F'CI (KSI)	NO. OF STRANDS	JACKING FORCE (KIPS)	NO. OF STRANDS	JACKING FORCE (KIPS)	NO. OF STRANDS	JACKING FORCE (KIPS)	E	F℄	Fb	Fo			
-	-	-	-	-	-°	-°	--'- -"	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-




STRAND PATTERN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



ALTERNATE # 1




ALTERNATE # 2

STRAND EXTENSION DETAIL FOR END TYPE D

NOT ALL EXTENDED STRANDS ARE SHOWN

Trapezoidal Tub S-I-P Deck Panel Girder - Details 4 of 4


Figure 5-A-147




NOTE TO DESIGNER

If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.


TYPICAL END TYPE "A" DIAPHRAGM AT END PIERS




SECTION F




ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS





END DIAPHRAGM GEOMETRY

SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.


* TO BE INCREASED AS NECESSARY

NOTE:

1. GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.
2. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
3. END DIAPHRAGM MAY BE CAST ON GRADE. IF SO, THE UPPER LEG OF THE JOINT FILLER SHALL FORM THE BOTTOM FACE FULL WIDTH.
4. JOINT FILLER TYPE 1 SHALL BE USED TO COVER ALL VERTICAL END DIAPHRAGM JOINTS. EITHER JOINT FILLER TYPE 1 OR JOINT FILLER TYPE 2 SHALL BE USED TO COVER ALL HORIZONTAL END DIAPHRAGM JOINTS.


Trapezoidal Tub S-I-P Deck Panel Girder - End Diaphragm on Girder Details


Figure 5-A-148




PLAN

FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET 3.






TEMPORARY SUPPORT DETAIL




DETAIL C



ELEVATION


CONSTRUCTION SEQUENCE

1. COLUMN & TEMP. SUPPORT
2. PLACE GIRDER ON TEMPORARY SUPPORT
3. CAST DIAPHRAGM STAGE 1
4. CAST ROADWAY SLAB
5. COMPLETE DIAPHRAGM
6. REMOVE TEMPORARY SUPPORT



Trapezoidal Tub S-I-P Deck Panel Girder - Raised Crossbeam Details


Figure 5-A-149



DETAIL G


NOTE TO DESIGNER:
This detail to be used on bridges with end piers and no wing walls, and located within and west of the Cascade Mountain range.

NOTE:
1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.



EXPANSION JOINT DETAILS


JOINT AT INTERMEDIATE PIER SHOWN




TOP ANCHOR BOTTOM ANCHOR

ANCHOR DETAIL

A.S.T.M. A-307




DETAIL E




DETAIL F

DRILL ½"ø HOLES THROUGH SEAL WITH STANDARD TWIST DRILL MAKING SURE THE TOP MEMBRANE IS NOT DAMAGED. CUT HOLE WITH SHARP LONG BLADE KNIFE.



BEARING PAD


LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60




GROUT PAD DETAIL

Trapezoidal Tub S-I-P Deck Panel Girder - Miscellaneous Diaphragm Details


Figure 5-A-150



TYPICAL SECTION - PRESTRESSED PANEL




DETAIL B



DETAIL A

NOTE:

THE FIRST INSERT SHALL BE PLACED WITHIN 2'-0" OF THE END DIAPHRAGMS.
FOR INSERT LOCATIONS, SEE "UTILITIES HANGER DETAILS" SHEET.




PLAN VIEW ~ PRESTRESSED PANEL

NOTES:


1. CONCRETE IN THE PRESTRESSED PRECAST DECK PANELS SHALL BE CLASS 5000.
   THE CONCRETE SHALL ATTAIN A MINIMUM COMPRESSIVE STRENGTH OF 4000 PSI BEFORE RELEASING THE PRETENSIONING STRANDS.
2. THE PRETENSION STRANDS SHALL BE 7 WIRE ⅜"ø (As = 0.085 IN²) LOW RELAXATION STRANDS (AASHTO M203 GRADE 270)
   THE JACKING FORCE SHALL BE 17.4 KIP PER STRAND.
3. GROUT BED FOR PRESTRESSED PRECAST DECK PANELS SHALL CONFORM TO THE SPECIAL PROVISIONS.
4. LOOSEN THE LEVELING BOLT BY TWO TURN AFTER THE GROUT HAS REACHED THE DESIGN STRENGTH PER STANDARD SPECIFICATION.
5. FOR SKEW END PANELS, ADJUST THE LEVELING BOLT LOCATIONS LONGITUDINALLY ALONG THE ℄ OF GIRDER, SUCH THAT EACH PANEL WILL HAVE 4 BOLTS AFTER THE SAWCUT.

BAR LIST		
MARK #	BAR SIZE	BEND TYPE
P1	5	STRAIGHT
*P2	4 ▽	AS SHOWN
P3	4	AS SHOWN
P4	4	STRAIGHT

▽ = EPOXY COATED
ALL REINFORCEMENT SHALL BE AASHTO M31. GR. 60.
* VARIES



DETAIL D




ELEVATION ~ PRESTRESSED PANEL

(DIMENSIONS SHOWN NORMAL TO ℄ TUB GIRDER)

Precast Prestressed Stay-in-Place Deck Panel Details

Figure 5-A-151




PLAN

SHOWN FOR SKEW ANGLE GREATER THAN OR EQUAL TO 20° (30° MAX.)

NOTES

1. ALL PRESTRESSING STEEL SHALL BE ½"ø OR 0.6"ø LOW-RELAXATION 7-WIRE STRANDS AASHTO M203 GRADE 270. STRANDS SHALL BE TENSIONED INITIALLY TO 0.75 F'S.
2. ALL REINFORCING STEEL SHALL CONFORM TO AASHTO M31, GRADE 60. ALL REINFORCING STEEL SPLICES SHALL BE TWO FEET MINIMUM, UNLESS SHOWN OTHERWISE.
3. ALL REINFORCING BARS SHALL BE PLACED 2 INCHES FROM NEAREST FACE OF CONCRETE UNLESS SHOWN OTHERWISE.
4. CONCRETE SHALL BE WITH MINIMUM COMPRESSIVE STRENGTH AT TRANSFER AND FINAL AS SHOWN IN THE DESIGN TABLE.
5. THE DEFLECTION VALUES LISTED IN THE DESIGN TABLE ARE COMPUTED DEFLECTIONS AT MID-SPAN BASED ON THE FOLLOWING TIME ELAPSE ASSUMPTIONS:
   - INITIAL CONCRETE COMPRESSIVE STRENGTH AT RELEASE WILL BE ATTAINED IN ONE (1) DAY.
   - FINAL CONCRETE COMPRESSIVE STRENGTH AT 28 DAYS WILL BE ATTAINED IN SEVEN (7) DAYS.
   - THE FINAL DEFLECTION IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS.
   - THE FINAL DEFLECTION DUE TO 85 PSF SUPERIMPOSED LOAD (ASPHALT OVERLAY, NOT INCLUDING TRAFFIC BARRIERS) IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS WITH THE LOAD ASSUMED TO BE PLACED ONE HUNDRED TEWENTY (120) DAYS AFTER SLABS ARE CAST. IF THE ACTUAL CONDITIONS VARY SUBSTANTIALLY FROM THOSE ASSUMED ABOVE, THE DEFLECTION SHALL BE MODIFIED AND SUBMITTED TO THE ENGINEER FOR APPROVAL. THE TIME ASSUMPTION MAY VARY BY ± 30%
6. IT IS INTENDED THAT MEMBRANE WATERPROOFING AND ASPHALT OVERLAY BE INSTALLED ON THE IN-PLACE SLABS. THE ASPHALT SHALL BE VARIED TO PARTIALLY COMPENSATE FOR THE TWO THOUSAND (2000) DAY SLAB DEFLECTION. THE THICKNESS OF ASPHALT SHALL BE A MINIMUM OF 1½ INCHES AT MIDSPAN.
7. NO TRAFFIC SHALL BE ALLOWED ON A BEAM ADJACENT TO A GROUTED JOINT UNTIL THE GROUT HAS ATTAINED A MINIMUM STRENTH OF 4000 PSI.



ELEVATION

NOTES TO DESIGNER


STRAND SEQUENCE

1	3	4	2
17 27 21 1 9 3	25 29 19 23 31 11 5 13 7 15	32 24 20 30 26 16 8 14 6 12	22 28 18 4 10 2

WHEN DEBONDED STANDS ARE REQUIRED, PLACE AT INTERIOR STRAND LOCATION (WITHIN SECOND ROW IF POSSIBLE). PLACE DIAMONDS WHERE DEBONDED STRANDS ARE REQUIRED & INDICATE DEBONDED LENGTH.

* ○ = BONDED STRANDS
◇ = DEBONDED STRANDS

* TOP 2" OF SLAB SHALL BE AIR-ENTRAINED CONCRETE.




SECTION A
EXTERIOR SLAB


CUT ALL STRANDS FLUSH WITH SLAB ENDS AND PAINT WITH AN APPROVED EPOXY RESIN

Precast Prestressed 1'-0" Solid Slab Details 1 of 2


Figure 5-A-152




SECTION C
WELD TIE ALTERNATE #1




SECTION C
WELD TIE ALTERNATE #2



SECTION B
KEYWAY DETAIL



END VIEW
EXTERIOR SLAB




CAMBER DETAIL

C_I = CAMBER AT TRANSFER DUE TO PRESTRESSING AND GIRDER SELF WEIGHT.

C_{FINAL} = CAMBER AT 2000 DAYS.


C_{SIDL} = DEFLECTION DUE TO WEIGHT OF ACP OVERLAY AND TRAFFIC BARRIER.

$C_{F+SIDL} = C_{FINAL} + C_{SIDL}$



DEVELOPED ELEVATION
LIFTING LOOP

½"ø OR 0.6"ø 7-WIRE STRANDS (AASHTO M203 GRADE 270) FOR LIFTING SLAB; MINIMUM OF 4 STRANDS PER SLAB. AFTER SLAB IS IN PLACE CUT STRAND 1¼" (MIN.) CLEAR OF TOP SLAB AND FILL HOLE WITH GROUT



PART SECTION
EXTERIOR SLAB

FOR DETAILS NOT SHOWN SEE TRAFFIC BARRIER SHEETS

BARLIST


ALL REINFORCING SHALL BE AASHTO M31 (GRADE 60)

MARK	LOCATION	SIZE	NO. REQ'D	BARLIST DIMENSION TABLE				BENDING DIAGRAM
G1	SLAB LONGIT. - TOP	#4	4 β	STR.	SLAB DEPTH	W	REQUIRED EMBEDMENT	
G2	SLAB LONGIT. - BOT.	4	4	STR.	1'-0"	11"	1'-6"	
G3	END OF SLAB - TIE	#4	8					
G4	END OF SLAB - TIE	4	4					
G5	END OF SLAB - TIE	3	4 δ					
G6	END OF SLAB - TIE	#4	AS REQ'D BY SKEW					
G7	SLAB TRANSV. - TIE	#4	VARIES WITH SPAN					
G8	SLAB TRANSV. - STIRRUP	4	VARIES WITH SPAN					
S1	T.B. TO DECK TIE	4						
S2	T.B. TO DECK TIE	#5						

= EPOXY COATED

δ 2 BARS BUNDLED

β ADDITIONAL BARS WILL BE REQUIRED ON VOIDED SLABS W/BARRIERS, IF OPTION 1 ANCHOR PLATE DETAIL IS SELECTED.




DESIGN TABLE

STRENGTH OF CONCRETE: TRANSFER, F'ci = 5.5 kSI FINAL, F'c = 7.0 kSI
PRESTRESSING STRANDS, 0.60"ø, 270 kSI
* COMBINATION OF TOP AND BOTTOM STRANDS

SPAN NUMBER	SPAN LENGTH ℄/℄ BRG. FT.	TOTAL NO. OF STRANDS	BOTTOM		TOP	* JACKING FORCE KIPS	LOCATION OF C.G. OF STRAND "E" IN. *	CAMBER (IN.)		
			BONDED	DE-BONDED				C_I	C_{FINAL}	C_{F+SIDL}

Precast Prestressed 1'-0" Solid Slab Details 2 of 2

Figure 5-A-153




PLAN


SHOWN FOR SKEW ANGLE GREATER THAN OR EQUAL TO 20° (30° MAX.)

NOTES

1. ALL PRESTRESSING STEEL SHALL BE ½"ø OR 0.6"ø LOW-RELAXATION 7-WIRE STRANDS AASHTO M203 GRADE 270. STRANDS SHALL BE TENSIONED INITIALLY TO 0.75 F'S.
2. ALL REINFORCING STEEL SHALL CONFORM TO AASHTO M31, GRADE 60. ALL REINFORCING STEEL SPLICES SHALL BE TWO FEET MINIMUM, UNLESS SHOWN OTHERWISE.
3. ALL REINFORCING BARS SHALL BE PLACED 2 INCHES FROM NEAREST FACE OF CONCRETE UNLESS SHOWN OTHERWISE.
4. CONCRETE SHALL BE WITH MINIMUM COMPRESSIVE STRENGTH AT TRANSFER AND FINAL AS SHOWN IN THE DESIGN TABLE.
5. THE DEFLECTION VALUES LISTED IN THE DESIGN TABLE ARE COMPUTED DEFLECTIONS AT MID-SPAN BASED ON THE FOLLOWING TIME ELAPSE ASSUMPTIONS:
   - INITIAL CONCRETE COMPRESSIVE STRENGTH AT RELEASE WILL BE ATTAINED IN ONE (1) DAY.
   - FINAL CONCRETE COMPRESSIVE STRENGTH AT 28 DAYS WILL BE ATTAINED IN SEVEN (7) DAYS.
   - THE FINAL DEFLECTION IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS.
   - THE FINAL DEFLECTION DUE TO 85 PSF SUPERIMPOSED LOAD (ASPHALT OVERLAY, NOT INCLUDING TRAFFIC BARRIERS) IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS WITH THE LOAD ASSUMED TO BE PLACED ONE HUNDRED TWENTY (120) DAYS AFTER SLABS ARE CAST. IF THE ACTUAL CONDITIONS VARY SUBSTANTIALLY FROM THOSE ASSUMED ABOVE, THE DEFLECTION SHALL BE MODIFIED AND SUBMITTED TO THE ENGINEER FOR APPROVAL. THE TIME ASSUMPTION MAY VARY BY ± 30%
6. IT IS INTENDED THAT MEMBRANE WATERPROOFING AND ASPHALT OVERLAY BE INSTALLED ON THE IN-PLACE SLABS. THE ASPHALT SHALL BE VARIED TO PARTIALLY COMPENSATE FOR THE TWO THOUSAND (2000) DAY SLAB DEFLECTION. THE THICKNESS OF ASPHALT SHALL BE A MINIMUM OF 1½ INCHES AT MIDSPAN.
7. NO TRAFFIC SHALL BE ALLOWED ON A BEAM ADJACENT TO A GROUTED JOINT UNTIL THE GROUT HAS ATTAINED A MINIMUM STRENTH OF 4000 PSI.




ELEVATION



WHEN DEBONDED STANDS ARE REQUIRED, PLACE AT INTERIOR STRAND LOCATION (WITHIN SECOND ROW IF POSSIBLE). PLACE DIAMONDS WHERE DEBONDED STRANDS ARE REQUIRED & INDICATE DEBONDED LENGTH.

* TOP 2" OF SLAB SHALL BE AIR-ENTRAINED CONCRETE.




SECTION A
EXTERIOR SLAB

CUT ALL STRANDS FLUSH WITH SLAB ENDS AND PAINT WITH AN APPROVED EPOXY RESIN


Precast Prestressed 1'-6" Voided Slab Details 1 of 3

Figure 5-A-154




CAMBER DETAIL


C_I = CAMBER AT TRANSFER DUE TO PRESTRESSING AND GIRDER SELF WEIGHT.
C_{FINAL} = CAMBER AT 2000 DAYS.
C_{SIDL} = DEFLECTION DUE TO WEIGHT OF ACP OVERLAY AND TRAFFIC BARRIER.
$C_{F+SIDL} = C_{FINAL} + C_{SIDL}$




END VIEW EXTERIOR SLAB




SECTION C
WELD TIE ALTERNATE #1



SECTION C
WELD TIE ALTERNATE #2



SECTION B
KEYWAY DETAIL



DEVELOPED ELEVATION LIFTING LOOP

½"ø OR 0.6"ø 7-WIRE STRANDS (AASHTO M203 GRADE 270) FOR LIFTING SLAB; MINIMUM OF 4 STRANDS PER SLAB. AFTER SLAB IS IN PLACE CUT STRAND 1¼" (MIN.) CLEAR OF TOP SLAB AND FILL HOLE WITH GROUT

BARLIST

ALL REINFORCING SHALL BE AASHTO M31 (GRADE 60)


MARK	LOCATION	SIZE	NO. REQ'D	BARLIST DIMENSION TABLE			BENDING DIAGRAM
				STR.	SLAB DEPTH	W	REQUIRED EMBEDMENT
G1	SLAB LONGIT. - TOP	▽4	4 β	STR.	1'-6"	1'-5"	1'-9"
G2	SLAB LONGIT. - BOT.	4	4				
G3	END OF SLAB - TIE	▽4	8				
G4	END OF SLAB - TIE	4	4				
G5	END OF SLAB - TIE	3	4 δ				
G6	END OF SLAB - TIE	▽4	AS REQ'D BY SKEW				
G7	SLAB TRANSV. - TIE	▽4	VARIES WITH SPAN				
G8	SLAB TRANSV. - STIRRUP	4	VARIES WITH SPAN				
S1	T.B. TO DECK TIE	4					
S2	T.B. TO DECK TIE	▽5					

▽ = EPOXY COATED

δ 2 BARS BUNDLED

β ADDITIONAL BARS WILL BE REQUIRED ON VOIDED SLABS W/BARRIERS, IF OPTION 1 ANCHOR PLATE DETAIL IS SELECTED.

VARIABLE LENGTH TO ANCHOR PROVIDED BY VOIDED SLAB MANUFACTURER (BASED ON ANCHOR PLACEMENT.




DESIGN TABLE

STRENGTH OF CONCRETE: TRANSFER, F'ci = 5.5 kSI FINAL, F'c = 7.0 kSI
PRESTRESSING STRANDS, 0.60"ø, 270 kSI
* COMBINATION OF TOP AND BOTTOM STRANDS

SPAN NUMBER	SPAN LENGTH ℄/℄ BRG. FT.	TOTAL NO. OF STRANDS	BOTTOM		TOP	* JACKING FORCE KIPS	LOCATION * OF C.G. OF STRAND "E" IN.	CAMBER (IN.)		
			BONDED	DE-BONDED				C_I	C_{FINAL}	C_{F+SIDL}

Precast Prestressed 1'-6" Voided Slab Details 2 of 3
Figure 5-A-155



PART SECTION
EXTERIOR SLAB


γ SPACING WILL BE DEVELOPED BY S1 & S2 LAYOUT.

β WELD SHALL BE SIZED TO DEVELOP 125% OF THE REBAR YIELD STRENGTH AND TESTED IN ACCORDANCE W/ 6-02.3 (24)E (L IS DEPENDANT ON COUPLER SELECTED)


σ PLACED ALONG ℄ WHEN VOIDED SLAB LONGITUDINAL REINFORCING OR STRANDS ARE NOT IN CONTACT W/ ℄

L LENGTH IS DEPENDENT ON COUPLER SELECTED


WELDED COUPLER TABLE	
BAR SPLICE	BPI BARSPLICER STRUCTURAL CONNECTOR
ERICO	LENTON WELDABLE COUPLER C2/C3J
BAR LOCK	STRUCTURAL STEEL CONNECTORS (WELDABLE HALF COUPLER) SCA




ANCHOR PLATE DETAIL




VIEW A
INSERT 1



VIEW B
INSERT 2




SECTION C




SECTION D

Precast Prestressed 1'-6" Voided Slab Details 3 of 3
Figure 5-A-156



PLAN


SHOWN FOR SKEW ANGLE GREATER THAN OR EQUAL TO 20° (30° MAX.)



ELEVATION

NOTES

1. ALL PRESTRESSING STEEL SHALL BE ½"ø OR 0.6"ø LOW-RELAXATION 7-WIRE STRANDS AASHTO M203 GRADE 270. STRANDS SHALL BE TENSIONED INITIALLY TO 0.75 fpu.
2. ALL REINFORCING STEEL SHALL CONFORM TO AASHTO M31, GRADE 60. ALL REINFORCING STEEL SPLICES SHALL BE TWO FEET MINIMUM, UNLESS SHOWN OTHERWISE.
3. ALL REINFORCING BARS SHALL BE PLACED 2 INCHES FROM NEAREST FACE OF CONCRETE UNLESS SHOWN OTHERWISE.
4. CONCRETE MINIMUM COMPRESSIVE STRENGTH AT TRANSFER AND FINAL SHALL BE AS SHOWN IN THE DESIGN TABLE.
5. THE DEFLECTION VALUES LISTED IN THE DESIGN TABLE ARE COMPUTED DEFLECTIONS AT MID-SPAN BASED ON THE FOLLOWING TIME ELAPSE ASSUMPTIONS:
   - INITIAL CONCRETE COMPRESSIVE STRENGTH AT RELEASE WILL BE ATTAINED IN ONE (1) DAY.
   - FINAL CONCRETE COMPRESSIVE STRENGTH AT 28 DAYS WILL BE ATTAINED IN SEVEN (7) DAYS.
   - THE FINAL DEFLECTION IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS.
   - THE FINAL DEFLECTION DUE TO 85 PSF SUPERIMPOSED LOAD (ASPHALT OVERLAY, NOT INCLUDING TRAFFIC BARRIERS) IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS WITH THE LOAD ASSUMED TO BE PLACED ONE HUNDRED TWENTY (120) DAYS AFTER SLABS ARE CAST. IF THE ACTUAL CONDITIONS VARY SUBSTANTIALLY FROM THOSE ASSUMED ABOVE, THE DEFLECTION SHALL BE MODIFIED AND SUBMITTED TO THE ENGINEER FOR APPROVAL. THE TIME ASSUMPTION MAY VARY BY ± 30%
6. IT IS INTENDED THAT MEMBRANE WATERPROOFING AND ASPHALT OVERLAY BE INSTALLED ON THE IN-PLACE SLABS. THE ASPHALT SHALL BE VARIED TO PARTIALLY COMPENSATE FOR THE TWO THOUSAND (2000) DAY SLAB DEFLECTION. THE THICKNESS OF ASPHALT SHALL BE A MINIMUM OF 1½ INCHES AT MIDSPAN.
7. NO TRAFFIC SHALL BE ALLOWED ON A BEAM ADJACENT TO A GROUTED JOINT UNTIL THE GROUT HAS ATTAINED A MINIMUM STRENTH OF 4000 PSI.



* TOP 2" OF THE SLAB SHALL BE AIR-ENTRAINED CONCRETE.

= ○ = BONDED STRANDS
◇ = DEBONDED STRANDS


\# DISTANCE INDICATES LENGTH THAT EACH END OF CIRCLED STRANDS IS TO BE SLEEVED TO PREVENT BOND.

** NOTE PROJECT SPECIFIC TENSIONING SEQUENCE AND STRAND PATTERN

NOTES TO DESIGNER

STRAND SEQUENCE

| | | |




CAMBER DETAIL

C_I = CAMBER AT TRANSFER DUE TO PRESTRESSING AND GIRDER SELF WEIGHT.


C_{FINAL} = CAMBER AT 2000 DAYS.

C_{SIDL} = DEFLECTION DUE TO WEIGHT OF ACP OVERLAY AND TRAFFIC BARRIER.


$C_{F+SIDL} = C_{FINAL} + C_{SIDL}$




SECTION C
WELD TIE ALTERNATE #1




SECTION C
WELD TIE ALTERNATE #2



SECTION B
KEYWAY DETAIL



END VIEW
EXTERIOR SLAB



DEVELOPED ELEVATION
LIFTING LOOP

0.6"ø 7-WIRE STRANDS (AASHTO M203 GRADE 270) FOR LIFTING SLAB; MINIMUM OF 8 STRANDS PER SLAB. AFTER SLAB IS IN PLACE CUT STRAND 1¼" (MIN.) CLEAR OF TOP SLAB AND FILL HOLE WITH GROUT

BARLIST

ALL REINFORCING SHALL BE AASHTO M31 (GRADE 60)


MARK	LOCATION	SIZE	NO. REQ'D	BARLIST DIMENSION TABLE				BENDING DIAGRAM
G1	SLAB LONGIT. - TOP	#4	4 β	STR.				
G2	SLAB LONGIT. - BOT.		4	STR.	SLAB DEPTH	W	REQUIRED EMBEDMENT	
G3	END OF SLAB - TIE	#4	8		2'-2"	2'-1"	2'-3"	
G4	END OF SLAB - TIE		4					
G5	END OF SLAB - TIE	3	4 δ					
G7	SLAB TRANSV. - TIE	#4	VARIES WITH SPAN					
G8	SLAB TRANSV. - STIRRUP		4	VARIES WITH SPAN				
G7S	END OF SLAB - TIE	#4	AS REQ'D BY SKEW					
G8S	END OF SLAB - TIE		4	AS REQ'D BY SKEW				
S1	T.B. TO DECK TIE	#5	VARIES WITH SPAN					
S2	T.B. TO DECK TIE		4	VARIES WITH SPAN				

= EPOXY COATED

δ 2 BARS BUNDLED

β ADDITIONAL BARS WILL BE REQUIRED ON VOIDED SLABS W/BARRIERS, IF OPTION 1 ANCHOR PLATE DETAIL IS SELECTED.

* VARIABLE LENGTH TO ANCHOR PROVIDED BY VOIDED SLAB MANUFACTURER (BASED ON ANCHOR PLACEMENT.




DESIGN TABLE

STRENGTH OF CONCRETE: TRANSFER, F'ci = 5.5 kSI FINAL, F'c = 7.0 kSI
PRESTRESSING STRANDS, 0.60"ø, 270 kSI
* COMBINATION OF TOP AND BOTTOM STRANDS.

SPAN NUMBER	SPAN LENGTH ℄/℄ BRG. FT.	TOTAL NO. OF STRANDS	BOTTOM		TOP	* JACKING FORCE KIPS	* LOCATION OF C.G. OF STRAND "E" IN.	CAMBER (IN.)		
			BONDED	DE-BONDED				C_I	C_{FINAL}	C_{F+SIDL}

Precast Prestressed 2'-2" Voided Slab Details 2 of 3

Figure 5-A-158



PART SECTION
EXTERIOR SLAB


γ SPACING WILL BE DEVELOPED BY S1 & S2 LAYOUT.

β WELD SHALL BE SIZED TO DEVELOP 125% OF THE REBAR YIELD STRENGTH AND TESTED IN ACCORDANCE W/ 6-02.3 (24)E (L IS DEPENDANT ON COUPLER SELECTED)


σ PLACED ALONG ℄ WHEN VOIDED SLAB LONGITUDINAL REINFORCING OR STRANDS ARE NOT IN CONTACT W/ ℄

L LENGTH IS DEPENDENT ON COUPLER SELECTED


WELDED COUPLER TABLE	
BAR SPLICE	BPI BARSPLICER STRUCTURAL CONNECTOR
ERICO	LENTON WELDABLE COUPLER C2/C3J
BAR LOCK	STRUCTURAL STEEL CONNECTORS (WELDABLE HALF COUPLER) SCA




ANCHOR PLATE DETAIL




VIEW A
INSERT 1



VIEW B
INSERT 2




SECTION C




SECTION D

Precast Prestressed 2'-2" Voided Slab Details 3 of 3
Figure 5-A-159




Precast Prestressed Slab Layout

Figure 5-A-160




TYPICAL PIER ELEVATION

ELEVATION NORMAL TO ℄ ROADWAY



END VIEW

END BLOCK - BOTH ENDS OF PIER



** FOR DETAILS SEE INTERMEDIATE PIER SHEET.

DESIGN NOTES

1. PILE SPACING LISTED IN THE TABLES ARE THE MAXIMUM ALLOWED FOR EACH SPAN LENGTH FOR PILING (TIMBER, CONCRETE OR STEEL) NORMAL OR SKEWED TO THE CENTERLINE OF THE ROADWAY. THE LARGER OF THE TWO PILE SPACING VALUES LISTED FOR SPAN LENGHTS OF TEN (10) FOOT INCREMENTS MAY BE USED.
2. PILE SPACINGS ARE BASED ON 40 TON LOADING FOR TIMBER PILING AND 55 TON LOADING FOR CONCRETE AND STEEL PILING.
3. CONCRETE OR STEEL PILE SPACING LESS THAN 4'-0" MUST BE APPROVED BY THE SOILS ENGINEER. IF PILE SPACING LESS THAN FOUR FEET (4'-0") IS NOT ALLOWED THEN A DOUBLE ROW OF PILES MAY BE REQUIRED AT THE INTERMEDIATE PIER.
4. THIS STANDARD PILE SUBSTRUCTURE IS DESIGNED TO RESIST A SEISMIC LATERAL LOAD EQUIVALENT TO TEN PERCENT (10%) OF THE DEAD LOAD. THE TRANSVERS LATERAL LOAD IS RESISTED BY ALL THE PIERS (END AND INTERMEDIATE.) THE LONGITUDINAL LATERAL LOAD IS RESISTED BY ONE END PIER. THE RESISTANCE CAPACITY IS THE COMBINATION OF 6K/PILE LATERAL RESISTANCE AND PASSIVE SOIL PRESSURE AGAINST THE END PIER. THE PRESSURE WAS CALCULATED APPLYING THE FOLLOWING VALUES:
   - WEIGHT OF SOIL - W = 120 LBS/FT.
   - PASSIVE PRESSURE COEFFICIENT - KP = 3.5.
5. SINCE THE MAJORITY OF THE PIER'S LONGITUDINAL RESISTANCE CAPACITY IS DEVELOPED FROM PASSIVE SOIL PRESSURE, THE DEPTH OF THE END PIER DETERMINES THE MAXIMUM ALLOWABLE STRUCTURE LENGTH. THE TABLE BELOW GIVES THE TOTAL ALLOWABLE STRUCTURE LENGTH FOR A 3'-0" DEEP PIER CAP. FOR EXAMPLE, IF 8 - 32 FOOT SPANS OF 18 INCH SLABS WERE USED FOR A TOTAL STRUCTURE LENGTH OF 256 FEET, THE END PIER CAP WOULD HAVE TO BE DEEPENED BECAUSE THE ALLOWABLE STRUCTURE LENGTH IS ONLY 225 FEET. THE PIER CAP WOULD HAVE TO BE INCREASED TO 3'-6" WHICH ALLOWS FOR A STRUCTURE LENGTH OF 265 FEET FOR THIS SLAB DEPTH.

CONSTRUCTION NOTES

1. EXPOSED SMOOTH DOWELS SHALL BE PAINTED WITH 2 COATS OF STATE FORMULA A-9-73.
2. MECHANICAL BUTT SPLICES ARE REQUIRED FOR P5 #5 REINF. BARS WHEN STAGE CONSTRUCTION INTERFERES WITH THE REBAR CAGE EXTENDING ABOVE THE CONCRETE CAP. WHERE THE MECHANICAL BUTT SPLICE IS USED SEE ALTERNATE REBAR DETAIL.
3. DIMENSIONS SHOWN ARE NORMAL TO ℄ PIER.
4. SEE STANDARD PLAN E-4 FOR DETAILS OF 13 INCH PRECAST AND P.S. PILES. SEE STANDARD PLAN E-4a FOR DETAILS OF 16 INCH PILES.
5. ALL CAST-IN-PLACE PILES REQUIRE SPIRAL AND SPECIAL MAIN REINFORCEMENT WHEN USED FOR INTERIOR PILE BENTS. THE SPIRAL REINFORCEMENT SHALL BE W5 GAGE SPIRAL HOOPING AT 6 INCH CENTERS THE FULL LENGTH OF THE MAIN REINFORCEMENT AS CAST-IN-PLACE PILINGS. THE REINFORCEMENT SHALL EXTEND TO 25 FEET BELOW THE GROUNDLINE OR TO AN ELEVATION SHOWN IN THE PLANS. MINIMUM EXTENSION OF 9 - #8 REBAR INTO THE PILE CAPS 1'-9" UNLESS OTHERWISE SHOWN.
6. MAIN REINFORCEMENT SHALL BE AASHTO M 31. SPIRAL HOOPING SHALL CONFORM TO AASHTO M 32. GALVANIZE SMOOTH DOWELS PER AASHTO M 111.


BAR LIST


ALL REINFORCING SHALL BE AASHTO M 31, GR. 60.

MARK	LOCATION	SIZE	NO. REQ'D. PER PIER	BENDING DIAGRAM
P1	LONGIT - TOP & BOT.	11	4	STR
P2	STIRRUPS	4	VARIES W/PIER LENGTH	
P3	STIRRUPS	4	VARIES W/PIER LENGTH	
P4	END BLOCK REINF.	4	8	STR
P5	END BLOCK STIRR.	5	10	
P6	CORNER DOWELS	5	10	
	END BLOCK W/O APPROACH SLAB			
E1	LONGIT.	4	4	STR
E2	END BLOCK STIRR.	4	VARIES W/PIER LENGTH	
	ADDITIONAL APPROACH SLAB STEEL			
A1	DOWELS	6	VARIES W/PIER LENGTH	
A2	LONGIT.	▽6	3	STR
A3	STIRRUPS	▽5	VARIES W/PIER LENGTH	

SLAB	X	Y	Z
1'-0"	3'-10"	2'-6"	11"
1'-6"	4'-4"	3'-0"	1'-5"
2'-2"	5'-0"	3'-8"	2'-1"

▽ Epoxy Coated






HINGE DETAIL

ALL DIMENSIONS SHOWN ARE NORMAL TO ℄ BRG.

Precast Prestressed Slab End Pier Details 1 of 2

Figure 5-A-161




SECTION A

WITHOUT APPROACH SLAB

NOTE: THIS DETAIL IS TO BE USED BEYOND THE LIMITS OF THE APPROACH SLAB.
ALL DIMENSIONS SHOWN ARE NORMAL TO ℄ BRG.

** 3'-0" MINIMUM - SEE INTERMEDIATE PIER SHEET.




SECTION A
WITH CONCRETE PILES

WITH APPROACH SLAB

NOTE: END ANCHORS NOT REQUIRED PER STD. PLAN A-2
ALL DIMENSIONS SHOWN ARE NORMAL TO ℄ BRG.


δ - DEFLECTION DUE TO VOIDED SLAB CAMBER, MAINTAINING ASPHALT OVERLAY REQUIREMENTS AT MIDSPAN.



JOINT DETAIL


JOINT DETAIL TAKEN @ EXTERIOR PIER

* 1" MIN. GAP SHALL BE MAINTAINED PRIOR TO PLACEMENT OF GROUT AND JOINT FILLER.



SECTION C

NOTE:
FULL BEARING OF SLAB UNIT IS REQUIRED AT EACH ELASTOMERIC BEARING




BEARING DETAILS

BEARING PAD TABLE	
SLAB DEPTH	WIDTH x LENGTH
1'-0"	5" x 10"
1'-6"	5" x 15"
2'-2"	5" x 16"

MAXIMUM CONCRETE/STEEL PILE SPACING TABLE
FOS SLAB DEPTHS SHOWN BELOW


	W/O APPROACH SLABS			W/ APPROACH SLABS			INTERIOR PIER		
SPAN (FT.)	12"	18"	26"	12"	18"	26"	12"	18"	26"
0 to 10	10'-0"	—	—	10'-0"	—	—	8'-3"	—	—
10 to 20	10'-0"	—	—	9'-6"	—	—	6'-6"	—	—
20 to 30	10'-0"	10'-0"	—	8'-4"	8'-3"	—	5'-6"	5'-4"	—
30 to 40	9'-3"	9'-0"	8'-4"	7'-6"	7'-4"	6'-11"	4'-9"	4'-7"	4'-3"
40 to 50	—	7'-11"	7'-4"	—	6'-8"	6'-2"	4'-3"	4'-2"	3'-9"
50 to 60	—	—	6'-6"	—	—	5'-8"	—	3'-9"	3'-5"
60 to 70	—	—	6'-0"	—	—	5'-2"	—		3'-1"

Precast Prestressed Slab End Pier Details 2 of 2
Figure 5-A-162



TYPICAL PIER ELEVATION

ELEVATION NORMAL TO ℄ ROADWAY



SECTION A
WITH STEEL PILES

SECTION A
WITH CONCRETE PILES

DESIGN NOTES

1. PILE SPACING LISTED IN THE TABLES ARE THE MAXIMUM ALLOWED FOR EACH SPAN LENGTH FOR PILING (TIMBER, CONCRETE OR STEEL) NORMAL OR SKEWED TO THE CENTERLINE OF THE ROADWAY. THE LARGER OF THE TWO PILE SPACING VALUES LISTED FOR SPAN LENGHTS OF TEN (10) FOOT INCREMENTS MAY BE USED.
2. PILE SPACINGS ARE BASED ON 40 TON LOADING FOR TIMBER PILING AND 55 TON LOADING FOR CONCRETE AND STEEL PILING.
3. CONCRETE OR STEEL PILE SPACING LESS THAN 4'-0" MUST BE APPROVED BY THE SOILS ENGINEER. IF PILE SPACING LESS THAN FOUR FEET (4'-0") IS NOT ALLOWED THEN A DOUBLE ROW OF PILES MAY BE REQUIRED AT THE INTERMEDIATE PIER.
4. THIS STANDARD PILE SUBSTRUCTURE IS DESIGNED TO RESIST A SEISMIC LATERAL LOAD EQUIVALENT TO TEN PERCENT (10%) OF THE DEAD LOAD. THE TRANSVERS LATERAL LOAD IS RESISTED BY ALL THE PIERS (END AND INTERMEDIATE.) THE LONGITUDINAL LATERAL LOAD IS RESISTED BY ONE END PIER. THE RESISTANCE CAPACITY IS THE COMBINATION OF 6K/PILE LATERAL RESISTANCE AND PASSIVE SOIL PRESSURE AGAINST THE END PIER. THE PRESSURE WAS CALCULATED APPLYING THE FOLLOWING VALUES:
   - WEIGHT OF SOIL - W = 120 LBS/FT.
   - PASSIVE PRESSURE COEFFICIENT - KP = 3.5.
5. SINCE THE MAJORITY OF THE PIER'S LONGITUDINAL RESISTANCE CAPACITY IS DEVELOPED FROM PASSIVE SOIL PRESSURE, THE DEPTH OF THE END PIER DETERMINES THE MAXIMUM ALLOWABLE STRUCTURE LENGTH. THE TABLE BELOW GIVES THE TOTAL ALLOWABLE STRUCTURE LENGTH FOR A 3'-0" DEEP PIER CAP. FOR EXAMPLE, IF 8 - 32 FOOT SPANS OF 18 INCH SLABS WERE USED FOR A TOTAL STRUCTURE LENGTH OF 256 FEET, THE END PIER CAP WOULD HAVE TO BE DEEPENED BECAUSE THE ALLOWABLE STRUCTURE LENGTH IS ONLY 225 FEET. THE PIER CAP WOULD HAVE TO BE INCREASED TO 3'-6" WHICH ALLOWS FOR A STRUCTURE LENGTH OF 265 FEET FOR THIS SLAB DEPTH.


CONSTRUCTION NOTES

1. EXPOSED SMOOTH DOWELS SHALL BE PAINTED WITH 2 COATS OF STATE FORMULA A-9-73.
2. MECHANICAL BUTT SPLICES ARE REQUIRED FOR P5 #5 REINF. BARS WHEN STAGE CONSTRUCTION INTERFERES WITH THE REBAR CAGE EXTENDING ABOVE THE CONCRETE CAP. WHERE THE MECHANICAL BUTT SPLICE IS USED SEE ALTERNATE REBAR DETAIL.
3. DIMENSIONS SHOWN ARE NORMAL TO ℄ PIER.
4. SEE STANDARD PLAN E-4 FOR DETAILS OF 13 INCH PRECAST AND P.S. PILES. SEE STANDARD PLAN E-4a FOR DETAILS OF 16 INCH PILES.
5. ALL CAST-IN-PLACE PILES REQUIRE SPIRAL AND SPECIAL MAIN REINFORCEMENT WHEN USED FOR INTERIOR PILE BENTS. THE SPIRAL REINFORCEMENT SHALL BE W5 GAGE SPIRAL HOOPING AT 6 INCH CENTERS THE FULL LENGTH OF THE MAIN REINFORCEMENT AS CAST-IN-PLACE PILINGS. THE REINFORCEMENT SHALL EXTEND TO 25 FEET BELOW THE GROUNDLINE OR TO AN ELEVATION SHOWN IN THE PLANS. MINIMUM EXTENSION OF 9 - #8 REBAR INTO THE PILE CAPS 1'-9" UNLESS OTHERWISE SHOWN.
6. MAIN REINFORCEMENT SHALL BE AASHTO M 31. SPIRAL HOOPING SHALL CONFORM TO AASHTO M 32. GALVANIZE SMOOTH DOWELS PER AASHTO M 111.

BAR LIST

ALL REINFORCING SHALL BE AASHTO M 31, GR 60


MARK	LOCATION	SIZE	NO. REQUIRED PER PIER	BENDING DIAGRAM
	WEBWALL STEEL			
W1	HORIZ. BARS	4	VARIES W/ PIER HEIGHT	
W2	HORIZ. END BARS	4	VARIES W/ PIER HEIGHT	
W3	VERTICAL	4	VARIES W/ PIER HEIGHT	STR.
W4	HORIZ. TIE BARS	4	VARIES W/ PIER HEIGHT & LENGTH	



HEIGHT TABLE

	CASED	NOT CASED
1'-0" C.I.P. & 1'-1" P.C.	20'-0"	7'-0"
1'-2" C.I.P. & 1'-4" P.C.	20'-0"	15'-0"
HP 12 x 53 STEEL	20'-0"	—

NOTE:
FOR STIRRUP SPACING AND OTHER ADDITIONAL PIER DETAILS REFER TO THE "TYPICAL PIER ELEVATION." SEE STANDARD PILE END PIER SHEET. SEE NOTE AT TOP RIGHT FOR PILE REINFORCEMENT REQUIREMENTS.




TOTAL ALLOWABLE STRUCTURE LENGTH

≠ PIER CAP DEPTH	3'-0"		3'-6"		4'-0"	
SLAB DEPTH	TOTAL LENGTH	W	TOTAL LENGTH	W	TOTAL LENGTH	W
1'-0"	200'	2'-8"	240'	3'-2"	280'	3'-8"
1'-6"	225'	2'-8"	265'	3'-2"	310'	3'-8"
2'-2"	235'	2'-8"	275'	3'-2"	320'	3'-8"

** FOR THE DIMENSIONS OF BARS WHEN A PIER CAP DEPTH OTHER THAN 3'-0" IS USED SEE THE VALUE FOR W SHOWN IN TABLE ABOVE


Precast Prestressed Slab Intermediate Piers Details 1 of 2

Figure 5-A-163




SECTION B / 1

NOTE:
FOR REINFORCING DETAILS FOR P1 THRU P6
SEE BARLIST ON STANDARD PILE END PIER SHEET




BEARING DETAILS



JOINT DETAIL

JOINT DETAIL TAKEN @ INTERIOR PIER

BEARING PAD TABLE	
SLAB DEPTH	WIDTH x LENGTH
1'-0"	5" x 10"
1'-6"	5" x 16"
2'-2"	5" x 16"




SECTION C

NOTE:
FULL BEARING OF SLAB UNIT IS REQUIRED AT EACH ELASTOMERIC BEARING

Precast Prestressed Slab Intermediate Piers Details 2 of 2

Figure 5-A-164



END DIAPHRAGM DETAIL


DIAPHRAGM DIMENSIONS ARE NORMAL TO SKEW.
ALL OTHERS ARE PARALELL TO ℄ GIRDER

ELEVATION

END DIAPHRAGM NOT SHOWN

NOTES

1. CONCRETE SHALL BE WITH A MINIMUM COMPRESSIVE STRENGTH AT TRANSFER AND FINAL AS SHOWN IN THE DESIGN TABLE. ALL PRESTRESSING STEEL SHALL BE ½"ø OR 0.6"ø LOW RELAXATION 7-WIRE STRANDS (AASHTO M 203, GRADE 270.) STRANDS SHALL BE TENSIONED INITIALLY TO 0.75 Fpu. PLATES AND ANGLES SHALL CONFORM TO AASHTO M183 AND SHALL BE PAINTED WITH 2 COATS OF STATE FORMULA A-9-73.
2. ALL REINFORCING STEEL SHALL CONFORM TO AASHTO M31, GRADE 60. ALL REINFORCING STEEL SPLICES SHALL BE 2'-0" MINIMUM UNLESS SHOWN OTHERWISE. ALL DEFORMED WIRE SHALL BE PER ASTM A 496.
3. ALL REINFORCING BARS SHALL BE PLACED 2" CLEAR OF THE NEAREST FACE OF CONCRETE UNLESS SHOWN OTHERWISE.
4. NO TRAFFIC SHAL BE ALLOWED ON A BEAM ADJACENT TO A GROUTED JOINT UNTIL THE GROUT HAS ATTAINED A MINIMUM STRENGTH OF 4,000 PSI.
5. THE DEFLECTION VALUES LISTED IN THE DESIGN TABLE ARE COMPUTED DEFLECTIONS AT MID-SPAN BASED ON THE FOLLOWING TIME ELAPSE ASSUMPTIONS:
   - INITIAL CONCRETE COMPRESSIVE STRENGTH AT RELEASE WILL BE ATTAINED IN ONE (1) DAY.
   - FINAL CONCRETE COMPRESSIVE STRENGTH AT 28 DAYS WILL BE ATTAINED IN SEVEN (7) DAYS.
   - THE FINAL DEFLECTION IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS.
   - THE FINAL DEFLECTION DUE TO SUPERIMPOSED LOAD (ASPHALT OVERLAY PLUS TRAFFIC BARRIERS) IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS WITH THE LOAD ASSUMED TO BE PLACED SIXTY (60) DAYS AFTER BEAMS ARE CAST.
6. IF THE ACTUAL CONDITIONS VARY SUBSTANTIALLY FROM THOSE ASSUMED ABOVE, THE DEFLECTIONS SHOULD BE MODIFIED AND SUBMITTED TO THE DESIGN ENGINEER FOR APPROVAL. THE TIME ASSUMPTIONS MAY VARY BY ± 30%.
7. IT IS INTENDED THAT A MEMBRANE WATERPROOFING AND ASPHALT OVERLAY WILL BE INSTALLED ON THE IN-PLACE SECTION. THE ASPHALT SHALL BE VARIED TO PARTIALLY COMPENSATE FOR THE TWO THOUSAND (2000) DAY SLAB DEFLECTION. THE THICKNESS OF ASPHALT SHALL BE A MINIMUM OF 0.15 FEET AT THE MIDSPAN.





GIRDER PLAN

OMIT WELD TIES ON EXTERIOR EDGE OF EXTERIOR GIRDER.
* LONGITUDINAL WELD TIES ARE REQUIRED AT END PIER WHEN APPROACH SLAB IS USED

▽ EPOXY COATED


MARK	LOCATION	SIZE	NO. REQ'D.	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
G1	STEM - LONGIT.	▽5	6	
G2	DIAPH. - TRANSV.	▽5	6	STR.
G3	TRANSV.	▽4	VARIES	STR.
G4	TRANSV.	4	VARIES	STR.
G5	LONGITUDINAL	▽4	VARIES	
S1	T.B. TO DECK TIE.	▽5	VARIES	
S2	T.B. TO DECK TIE	4	VARIES	





EXTERIOR GIRDER REINFORCING

* ALTERNATIVELY THE TOP 2 INCHES OF THE GIRDER FLANGE MAY BE AIR-ENTRAINED CONCRETE.



** STIRRUP SPACING TO BE DETERMINED BY ANALYSIS


SYMM. ABOUT ℄ OF SECTION UNLESS SHOWN OTHERWISE

TYPICAL SECTION


SECTION SHOWN NEAR MIDSPAN

Precast Prestressed Ribbed Girder Details 1 of 2

Figure 5-A-165



STRAND PATTERN AT GIRDER END




CAMBER DETAIL

C_I = CAMBER AT TRANSFER DUE TO PRESTRESSING AND GIRDER SELF WEIGHT.


C_{FINAL} = CAMBER AT 2000 DAYS.

C_{SIDL} = DEFLECTION DUE TO WEIGHT OF ACP OVERLAY AND TRAFFIC BARRIER.


$C_{F+SIDL} = C_{FINAL} + C_{SIDL}$




LONGITUDINAL WELD TIE DETAIL




SECTION A 1
KEYWAY ALTERNATE 1




SECTION B 1
WELD TIE ALTERNATE #1




SECTION B 1
WELD TIE ALTERNATE #2




SECTION B 1
WELD TIE ALTERNATE #3



SECTION A 1
KEYWAY ALTENATE 2



PLAN



ELEVATION


STEM RECESS DETAIL

DESIGN TABLE

PLAN LENGTH (FT.)	NOMINAL SPAN CTR. TO CTR. BEARING (FT.)	HARP POINT (: × PLAN LENGTH)	NO. STRANDS	DIMENSION "W"	F ℄ (IN.)	DISTANCE "E" TO C.G.S. AT END BLOCK (IN.)	CONCRETE COMPRESSIVE STRENGTH		ESTIMATED DEFLECTION AT MIDSPAN (IN.)		
							INITIAL AT RELEASE (KSI)	FINAL AT 28 DAYS (KSI)	UPWARD AT TRANSFER OF PRESTRESS (Δ1)	FINAL UPWARD FOR RIBBED GIRDER ONLY (Δ 2000)	FINAL DOWNWARD DUE TO SUPER IMPOSED DEAD LOAD/(Δ SDL)


Precast Prestressed Ribbed Girder Details 2 of 2

Figure 5-A-166




END PIER WITHOUT APPROACH SLAB

NOTE: ALL DIMENSIONS SHOWN ARE NORMAL TO ℄ BRG.




END PIER WITH APPROACH SLAB


NOTE: END ANCHORS NOT REQUIRED PER STD. PLAN A-2
ALL DIMENSIONS SHOWN ARE NORMAL TO BRG.



INTERIOR PIER




END PIER W/O APPROACH SLAB




END VIEW

END BLOCK - BOTH ENDS OF PIER




SHEAR BLOCK DETAIL


POUR AFTER TRI-BEAMS HAVE BEEN PLACED AND GROUTED




SECTION - TRAFFIC BARRIER



END PIER W/APPROACH SLAB



BEARING DETAILS



JOINT DETAIL

JOINT DETAIL TAKEN @ INTERIOR PIER AND PIER WITH APPROACH SLAB


NOTE: FULL BEARING OF TRI-BEAM UNIT IS REQUIRED AT EACH ELASTOMERIC BEARING.

BAR LIST

▽ Epoxy Coated


BENDING DIAGRAM
ALL REINFORCING SHALL BE AASHTO M 31, GR. 60

MARK	LOCATION	SIZE	NO. REQ'D. PER PIER	
P1	LONGIT - TOP & BOT.	11	4	STR
P2	STIRRUPS	4	VARIES W/PIER LENGTH	
P3	STIRRUPS	4	VARIES W/PIER LENGTH	
P4	END BLOCK REINF.	4	8	STR
P5	END BLOCK STIRR.	5	10	
P6	CORNER DOWELS	5	10	
	END BLOCK W/O APPROACH SLAB			
E1	LONGIT.	4	4	STR
E2	END BLOCK STIRR.	4	VARIES W/PIER LENGTH	
	ADDITIONAL APPROACH SLAB STEEL			
A1	DOWELS	6	VARIES W/PIER LENGTH	
A2	LONGIT.	▽6	3	STR
A3	STIRRUPS	▽5	VARIES W/PIER LENGTH	




Precast Prestressed Ribbed Girder Pier Details

Figure 5-A-167



END DIAPHRAGM DETAIL

DIAPHRAGM DIMENSIONS ARE NORMAL TO SKEW. ALL OTHERS ARE PARALELL TO ℄ GIRDER




ELEVATION

END DIAPHRAGM NOT SHOWN


NOTES


1. CONCRETE SHALL BE WITH A MINIMUM COMPRESSIVE STRENGTH AT TRANSFER AND FINAL AS SHOWN IN THE DESIGN TABLE. ALL PRESTRESSING STEEL SHALL BE ½"ø OR 0.6"ø LOW RELAXATION 7-WIRE STRANDS (AASHTO M 203, GRADE 270.) STRANDS SHALL BE TENSIONED INITIALLY TO 0.75 Fpu. PLATES AND ANGLES SHALL CONFORM TO AASHTO M183 AND SHALL BE PAINTED WITH 2 COATS OF STATE FORMULA A-9-73.
2. ALL REINFORCING STEEL SHALL CONFORM TO AASHTO M31, GRADE 60. ALL REINFORCING STEEL SPLICES SHALL BE 2'-0" MINIMUM UNLESS SHOWN OTHERWISE. ALL DEFORMED WIRE SHALL BE PER ASTM A 496.
3. ALL REINFORCING BARS SHALL BE PLACED 2" CLEAR OF THE NEAREST FACE OF CONCRETE UNLESS SHOWN OTHERWISE.
4. NO TRAFFIC SHAL BE ALLOWED ON A BEAM ADJACENT TO A GROUTED JOINT UNTIL THE GROUT HAS ATTAINED A MINIMUM STRENGTH OF 4,000 PSI.
5. THE DEFLECTION VALUES LISTED IN THE DESIGN TABLE ARE COMPUTED DEFLECTIONS AT MID-SPAN BASED ON THE FOLLOWING TIME ELAPSE ASSUMPTIONS:
   - INITIAL CONCRETE COMPRESSIVE STRENGTH AT RELEASE WILL BE ATTAINED IN ONE (1) DAY.
   - FINAL CONCRETE COMPRESSIVE STRENGTH AT 28 DAYS WILL BE ATTAINED IN SEVEN (7) DAYS.
   - THE FINAL DEFLECTION IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS.
   - THE FINAL DEFLECTION DUE TO SUPERIMPOSED LOAD (ASPHALT OVERLAY PLUS TRAFFIC BARRIERS) IS BASED ON A CONCRETE AGE OF TWO THOUSAND (2000) DAYS WITH THE LOAD ASSUMED TO BE PLACED SIXTY (60) DAYS AFTER BEAMS ARE CAST.
6. IF THE ACTUAL CONDITIONS VARY SUBSTANTIALLY FROM THOSE ASSUMED ABOVE, THE DEFLECTIONS SHOULD BE MODIFIED AND SUBMITTED TO THE DESIGN ENGINEER FOR APPROVAL. THE TIME ASSUMPTIONS MAY VARY BY ± 30%.
7. IT IS INTENDED THAT A MEMBRANE WATERPROOFING AND ASPHALT OVERLAY WILL BE INSTALLED ON THE IN-PLACE SECTION. THE ASPHALT SHALL BE VARIED TO PARTIALLY COMPENSATE FOR THE TWO THOUSAND (2000) DAY SLAB DEFLECTION. THE THICKNESS OF ASPHALT SHALL BE A MINIMUM OF 0.15 FEET AT THE MIDSPAN.



GIRDER PLAN

OMIT WELD TIES ON EXTERIOR EDGE OF EXTERIOR GIRDER.
* LONGITUDINAL WELD TIES ARE REQUIRED AT END PIER WHEN APPROACH SLAB IS USED






TYPICAL SECTION

SECTION SHOWN NEAR MIDSPAN

▽ EPOXY COATED

MARK	LOCATION	SIZE	NO. REQ'D.	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
G1	STEM - LONGIT.	▽5	6	
G2	DIAPH. - TRANSV.	▽5	6	STR.
G3	TRANSV.	▽4	VARIES	VARIES
G4	TRANSV.	4	VARIES	STR.
G5	LONGITUDINAL	▽4	VARIES	
S1	T.B. TO DECK TIE.	▽5	VARIES	
S2	T.B. TO DECK TIE	4	VARIES	




EXTERIOR GIRDER REINFORCING

* ALTERNATIVELY THE TOP 2 INCHES OF THE GIRDER FLANGE MAY BE AIR-ENTRAINED CONCRETE.


** STIRRUP SPACING TO BE DETERMINED BY ANALYSIS

Precast Prestressed Double T Details 1 of 2

Figure 5-A-168



STRAND PATTERN AT GIRDER END




CAMBER DETAIL

C_I = CAMBER AT TRANSFER DUE TO PRESTRESSING AND GIRDER SELF WEIGHT.


C_{FINAL} = CAMBER AT 2000 DAYS.

C_{SIDL} = DEFLECTION DUE TO WEIGHT OF ACP OVERLAY AND TRAFFIC BARRIER.


$C_{F+SIDL} = C_{FINAL} + C_{SIDL}$




LONGITUDINAL WELD TIE DETAIL




SECTION A 1
KEYWAY ALTERNATE 1




SECTION B 1
WELD TIE ALTERNATE #1




SECTION B 1
WELD TIE ALTERNATE #2




SECTION B 1
WELD TIE ALTERNATE #3



SECTION A 1
KEYWAY ALTENATE 2



PLAN



ELEVATION


STEM RECESS DETAIL

DESIGN TABLE

PLAN LENGTH (FT.)	NOMINAL SPAN CTR. TO CTR. BEARING (FT.)	HARP POINT (☐ : x PLAN LENGTH)	NO. STRANDS	DIMENSION "W"	F ℄ (IN.)	DISTANCE "E" TO C.G.S. AT END BLOCK (IN.)	CONCRETE COMPRESSIVE STRENGTH		ESTIMATED DEFLECTION AT MIDSPAN (IN.)		
							INITIAL AT RELEASE (KSI)	FINAL AT 28 DAYS (KSI)	UPWARD AT TRANSFER OF PRESTRESS (△ 1)	FINAL UPWARD FOR RIBBED GIRDER ONLY (△ 2000)	FINAL DOWNWARD DUE TO SUPER IMPOSED DEAD LOAD(△ SDL)

Precast Prestressed Double T Details 2 of 2

Figure 5-A-169



GIRDER ELEVATION


\# MIDPOINT OF SPAN FOR SPAN LENGTHS 40'-0" to 80'-0". NO INTERMEDIATE DIAPHRAGM FOR SPAN LENGTHS 40'-0" OR LESS

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE INSERT OR APPROVED EQUAL. (TYP.)

** ⅛ : 1 FOR ½"ø STRANDS & ⅙ : 1 FOR 0.6"ø STRANDS


GENERAL NOTES


1. ALL DETAILS SHOWN PERTAIN ONLY TO THE 35 INCH DEEP GIRDER WITH THE 6'-0" GIRDER WIDTH SHOWN.
2. FORMS FOR THE BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER SO AS TO NOT CAUSE DAMAGE TO THE GIRDERS DURING THE STRAND RELEASE OPERATION.
3. SPAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE
4. ALL PRESTRESSING STRANDS SHALL BE ½ INCH OR 0.6 INCH ø LOW RELAXATION SEVEN WIRE STRAND, AASHTO M203 GR. 270. ALL MILD STEEL REINFORCING SHALL BE AASHTO M31 GR. 60. ALL STUDS SHALL CONFORM TO STD. SPEC. SECTION 9-06.15. ALL OTHER STEEL SHALL BE AASHTO M183 AND SHALL BE PAINTED WITH 2 COATS OF STATE FORMULA A-9-73.
5. CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS EXCEPT FOR THOSE SHOWN TO BE EXTENDED, AND PAINT ENDS OF FLUSH STRANDS WITH AN APPROVED EPOXY RESIN.
6. AFTER ERECTION, CUT OFF LIFTING LOOPS 1 INCH BELOW THE TOP OF THE FLANGE AND FILL WITH AN APPROVED GROUT PRIOR TO PLACING OF THE OVERLAY. ALL LIFTING STRANDS ARE TO BE OF THE SAME MATERIAL AND STRENGTH AS THE PRESTRESSING STRANDS. WRAP LIFTING LOOPS SO THAT EACH STRAND WILL CARRY IT'S SHARE OF THE TOTAL LOAD. EXTEND LIFTING LOOPS WITH 9 INCH LONG 90° HOOKS TO WITHIN 3 INCHES CLEAR OF THE BOTTOM OF THE GIRDER.
7. TOP 2 INCHES OF THE GIRDER FLANGE SHALL BE AIR-ENTRAINED CONCRETE.



GIRDER PLAN


OMIT WELD TIES ON EXTERIOR EDGE OF EXTERIOR GIRDER. (STRANDS AND LONGITUDINAL BARS NOT SHOWN)






EXTERIOR GIRDER REINFORCING NEAR GIRDER END

FOR DETAILS NOT SHOWN, SEE INTERIOR GIRDER



INTERIOR GIRDER REINFORCING NEAR MIDSPAN

*** THICKEN FLANGE TO COMPENSATE FOR SUPERELEVATION.




PLAN SECTION THROUGH GIRDER WEB

▽ DENOTES EPOXY COATED

△△ #3 OR #4 BARS MAY BE USED IN LIEU OF W12. FIELD BEND IS OPTIONAL.


MARK	LOCATION	SIZE
G1	GIRDER STIRRUPS	4
G2	GIRDER END STIRRUPS	5
G3	BOTTOM FLANGE	3
G4	TOP OF TOP FLANGE - LONGIT.	▽4 STR.
G5	BOT. OF TOP FLANGE - TRANSV.	4
G6	TOP TRANSV. - EXT. GIRDER	▽6
G7	TOP TRANSV. - INT. GIRDER	▽6 STR.
G8	BOT. OF TOP FLANGE - LONGIT.	4 STR.
G10	GIRDER END TIES	W12 △△
G11	GIRDER LONGIT.	6 STR.
S1	T.B. TO DECK TIE	▽5
S2	T.B. TO DECK TIE	4

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)




W35DG Deck Bulb Tee Girder Details 1 of 2

Figure 5-A-170




STRAND PATTERN AT GIRDER END

HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




TIE SPACING DETAIL




SAWTEETH DETAILS


SAWTEETH ARE FULL WIDTH - USE SAWTEETH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND




SECTION A 1
KEYWAY




SECTION B 1
WELD TIE ALTERNATE #1




SECTION B 1
WELD TIE ALTERNATE #2




SECTION B 1
WELD TIE ALTERNATE #3



GIRDER FLANGE THICKENING**



GIRDER END
AT END PIERS




* ALTERNATIVELY THE TOP 2 INCHES OF THE GIRDER FLANGE MAY BE AIR-ENTRAINED CONCRETE.

** THICKEN FLANGE TO COMPENSATE FOR CAMBER DUE TO PRESTRESS. FLANGE THICKNESS SHOWN IS @ ℄ OF SPAN. FOR FLANGE THINCKNESS ALONG GIRDER SEE GIRDER FLANGE THICKENING DETAILS ON BR. SHEET ____. GIRDERS WITH ULTIMATE CAMBER VALUES SMALLER THAN ¾" ARE EXEMPT FROM THIS REQUIREMENT. FLANGE THICKENING SHALL BE USED ONLY IF NEEDED BY DESIGN.

GIRDER SCHEDULE


W35DG Deck Bulb Tee Girder Details 2 of 2

Figure 5-A-171




ELEVATION - TYPICAL END DIAPHRAGM AT INTERMEDIATE PIERS

CONCRETE CLASS 4000, CAST IN PLACE




SECTION A

LONGIT. DIMENSIONS ARE NORMAL TO SKEW




END DIAPHRAGMS AT INTERMEDIATE PIER

LONGITUDINAL DIMENSIONS ARE NORMAL TO PIER




ELEVATION - TYPICAL INTERMEDIATE DIAPHRAGM

CONCRETE CLASS 4000, CAST IN PLACE




SECTION B



MISC. DECK BULB TEE DIAPHRAGM DETAILS SHEET


ELEVATION - TYPICAL END DIAPHRAGM AT END PIERS

CONCRETE CLASS 4000, CAST IN PLACE



ANCHOR DETAIL

A.S.T.M. A-307




SECTION C

ALL LONGITUDINAL DIMENSIONS SHOWN ARE NORMAL TO ℄ BRG.

W35DG Deck Bulb Tee Diaphragm Details

Figure 5-A-172




GIRDER ELEVATION

*OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE INSERT OR APPROVED EQUAL. (TYP.)


GENERAL NOTES

1. ALL DETAILS SHOWN PERTAIN ONLY TO THE 41 INCH DEEP GIRDER WITH THE 6'-0" GIRDER WIDTH SHOWN.
2. FORMS FOR THE BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER SO AS TO NOT CAUSE DAMAGE TO THE GIRDERS DURING THE STRAND RELEASE OPERATION.
3. SPAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE
4. ALL PRESTRESSING STRANDS SHALL BE ½ INCH OR 0.6 INCH ø LOW RELAXATION SEVEN WIRE STRAND, AASHTO M203 GR. 270. ALL MILD STEEL REINFORCING SHALL BE AASHTO M31 GR. 60. ALL STUDS SHALL CONFORM TO STD. SPEC. SECTION 9-06.15. ALL OTHER STEEL SHALL BE AASHTO M183 AND SHALL BE PAINTED WITH 2 COATS OF STATE FORMULA A-9-73.
5. CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS EXCEPT FOR THOSE SHOWN TO BE EXTENDED, AND PAINT ENDS OF FLUSH STRANDS WITH AN APPROVED EPOXY RESIN.
6. AFTER ERECTION, CUT OFF LIFTING LOOPS 1 INCH BELOW THE TOP OF THE FLANGE AND FILLWITH AN APPROVED GROUT PRIOR TO PLACING OF THE OVERLAY. ALL LIFTING STRANDS ARE TO BE OF THE SAME MATERIAL AND STRENGTH AS THE PRESTRESSING STRANDS. WRAP LIFTING LOOPS SO THAT EACH STRAND WILL CARRY IT'S SHARE OF THE TOTAL LOAD. EXTEND LIFTING LOOPS WITH 9 INCH LONG 90° HOOKS TO WITHIN 3 INCHES CLEAR OF THE BOTTOM OF THE GIRDER.
7. TOP 2 INCHES OF THE GIRDER FLANGE SHALL BE AIR-ENTRAINED CONCRETE.




GIRDER PLAN

OMIT WELD TIES ON EXTERIOR EDGE OF EXTERIOR GIRDER. (STRANDS AND LONGITUDINAL BARS NOT SHOWN)




PLAN SECTION THROUGH GIRDER WEB



EXTERIOR GIRDER REINFORCING NEAR GIRDER END

FOR DETAILS NOT SHOWN, SEE INTERIOR GIRDER



INTERIOR GIRDER REINFORCING NEAR MIDSPAN


*** THICKEN FLANGE TO COMPENSATE FOR SUPERELEVATION.

▽ DENOTES EPOXY COATED

△△ #3 OR #4 BARS MAY BE USED IN LIEU OF W12. FIELD BEND IS OPTIONAL.


MARK	LOCATION	SIZE
G1	GIRDER STIRRUPS	4
G2	GIRDER END STIRRUPS	5
G3	BOTTOM FLANGE	3
G4	TOP OF TOP FLANGE - LONGIT.	▽4 STR.
G5	BOT. OF TOP FLANGE - TRANSV.	4
G6	TOP TRANSV. - EXT. GIRDER	▽6
G7	TOP TRANSV. - INT. GIRDER	▽6 STR.
G8	BOT. OF TOP FLANGE - LONGIT.	4 STR.
G10	GIRDER END TIES	W12 △△
G11	GIRDER LONGIT.	6 STR.
S1	T.B. TO DECK TIE	▽5
S2	T.B. TO DECK TIE	4

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)




W41DG Deck Bulb Tee Girder Details 1 of 2

Figure 5-A-173




STRAND PATTERN AT GIRDER END

HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




TIE SPACING DETAIL




SAWTEETH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTEETH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND




GIRDER END


AT END PIERS




SECTION (B) (1) WELD TIE ALTERNATE #1



SECTION (B) (1) WELD TIE ALTERNATE #2




SECTION (B) (1) WELD TIE ALTERNATE #3




BEARING RECESS

BEARING RECESS IS NORMAL TO ℄ GIRDER



SECTION (A) (1) KEYWAY




GIRDER FLANGE THICKENING**

* ALTERNATIVELY THE TOP 2 INCHES OF THE GIRDER FLANGE MAY BE AIR-ENTRAINED CONCRETE.

** THICKEN FLANGE TO COMPENSATE FOR CAMBER DUE TO PRESTRESS. FLANGE THICKNESS SHOWN IS @ ℄ OF SPAN. FOR FLANGE THINCKNESS ALONG GIRDER SEE GIRDER FLANGE THICKENING DETAILS ON BR. SHEET ☐. GIRDERS WITH ULTIMATE CAMBER VALUES SMALLER THAN ¾" ARE EXEMPT FROM THIS REQUIREMENT. FLANGE THICKENING SHALL BE USED ONLY IF NEEDED BY DESIGN.


GIRDER SCHEDULE

SPAN	GIRDER	END 1	END 2	S	LS	θ_1	θ_2	P_1	P_2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'c KSI	MIN. CONC. COMPR. STRENGTH @ RELEASE F'ci KSI	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS E	LOCATION OF C.G. STRANDS F℄	LOCATION OF C.G. STRANDS Fb	LOCATION OF C.G. STRANDS Fo	CAMBER (IN) RELEASE △	CAMBER (IN) 2000 △	CAMBER (IN)
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-



W41DG Deck Bulb Tee Diaphragm Details

Figure 5-A-175




GIRDER ELEVATION

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" BURKE HI-TENSILE, LANCASTER MALLEABLE, DAYTON-SUPERIOR F-62 FLARED THIN SLAB (1" x 4⅝") FERRULE INSERT OR APPROVED EQUAL. (TYP.)


GENERAL NOTES

1. ALL DETAILS SHOWN PERTAIN ONLY TO THE 53 INCH DEEP GIRDER WITH THE 6'-0" GIRDER WIDTH SHOWN.
2. FORMS FOR THE BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER SO AS TO NOT CAUSE DAMAGE TO THE GIRDERS DURING THE STRAND RELEASE OPERATION.
3. SPAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE
4. ALL PRESTRESSING STRANDS SHALL BE ½ INCH OR 0.6 INCH ø LOW RELAXATION SEVEN WIRE STRAND, AASHTO M203 GR. 270. ALL MILD STEEL REINFORCING SHALL BE AASHTO M31 GR. 60. ALL STUDS SHALL CONFORM TO STD. SPEC. SECTION 9-06.15. ALL OTHER STEEL SHALL BE AASHTO M183 AND SHALL BE PAINTED WITH 2 COATS OF STATE FORMULA A-9-73.
5. CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS EXCEPT FOR THOSE SHOWN TO BE EXTENDED, AND PAINT ENDS OF FLUSH STRANDS WITH AN APPROVED EPOXY RESIN.
6. AFTER ERECTION, CUT OFF LIFTING LOOPS 1 INCH BELOW THE TOP OF THE FLANGE AND FILL WITH AN APPROVED GROUT PRIOR TO PLACING OF THE OVERLAY. ALL LIFTING STRANDS ARE TO BE OF THE SAME MATERIAL AND STRENGTH AS THE PRESTRESSING STRANDS. WRAP LIFTING LOOPS SO THAT EACH STRAND WILL CARRY IT'S SHARE OF THE TOTAL LOAD. EXTEND LIFTING LOOPS WITH 9 INCH LONG 90° HOOKS TO WITHIN 3 INCHES CLEAR OF THE BOTTOM OF THE GIRDER.
7. TOP 2 INCHES OF THE GIRDER FLANGE SHALL BE AIR-ENTRAINED CONCRETE.




GIRDER PLAN

OMIT WELD TIES ON EXTERIOR EDGE OF EXTERIOR GIRDER. (STRANDS AND LONGITUDINAL BARS NOT SHOWN)




PLAN SECTION THROUGH GIRDER WEB



EXTERIOR GIRDER REINFORCING NEAR GIRDER END

FOR DETAILS NOT SHOWN, SEE INTERIOR GIRDER




INTERIOR GIRDER REINFORCING NEAR MIDSPAN

*** THICKEN FLANGE TO COMPENSATE FOR SUPERELEVATION.


MARK	LOCATION	SIZE
G1	GIRDER STIRRUPS	4
G2	GIRDER END STIRRUPS	5
G3	BOTTOM FLANGE	3
G4	TOP OF TOP FLANGE - LONGIT.	▽4 STR.
G5	BOT. OF TOP FLANGE - TRANSV.	4
G6	TOP TRANSV. - EXT. GIRDER	▽6
G7	TOP TRANSV. - INT. GIRDER	▽6 STR.
G8	BOT. OF TOP FLANGE - LONGIT.	4 STR.
G10	GIRDER END TIES	W12 △△
G11	GIRDER LONGIT.	6 STR.
S1	T.B. TO DECK TIE	▽5
S2	T.B. TO DECK TIE	4

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)

△△ #3 OR #4 BARS MAY BE USED IN LIEU OF W12. FIELD BEND IS OPTIONAL.




▽ DENOTES EPOXY COATED




W53DG Deck Bulb Tee Girder Details 1 of 2

Figure 5-A-176




STRAND PATTERN AT GIRDER END

HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




TIE SPACING DETAIL




SAWTEETH DETAILS


SAWTEETH ARE FULL WIDTH - USE SAWTEETH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND




SECTION A KEYWAY




SECTION B WELD TIE ALTERNATE #1



SECTION B WELD TIE ALTERNATE #2




SECTION B WELD TIE ALTERNATE #3



GIRDER END


AT END PIERS



GIRDER FLANGE THICKENING**

* ALTERNATIVELY THE TOP 2 INCHES OF THE GIRDER FLANGE MAY BE AIR-ENTRAINED CONCRETE.

** THICKEN FLANGE TO COMPENSATE FOR CAMBER DUE TO PRESTRESS. FLANGE THICKNESS SHOWN IS @ ℄ OF SPAN. FOR FLANGE THINCKNESS ALONG GIRDER SEE GIRDER FLANGE THICKENING DETAILS ON BR. SHEET ____. GIRDERS WITH ULTIMATE CAMBER VALUES SMALLER THAN ¾" ARE EXEMPT FROM THIS REQUIREMENT. FLANGE THICKENING SHALL BE USED ONLY IF NEEDED BY DESIGN.



BEARING RECESS


BEARING RECESS IS NORMAL TO ℄ GIRDER

GIRDER SCHEDULE

SPAN	GIRDER	END 1	END 2	S	LS	θ_1	θ_2	P_1	P_2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C KSI	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI KSI	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS E	LOCATION OF C.G. STRANDS F℄	LOCATION OF C.G. STRANDS Fb	LOCATION OF C.G. STRANDS Fo	CAMBER (IN) RELEASE △	CAMBER (IN) 2000 △	
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-


W53DG Deck Bulb Tee Girder Details 2 of 2

Figure 5-A-177




ELEVATION - TYPICAL END DIAPHRAGM AT INTERMEDIATE PIERS

CONCRETE CLASS 4000, CAST IN PLACE




ELEVATION - TYPICAL INTERMEDIATE DIAPHRAGM

CONCRETE CLASS 4000, CAST IN PLACE




ELEVATION - TYPICAL END DIAPHRAGM AT END PIERS




SECTION A

LONGIT. DIMENSIONS ARE NORMAL TO SKEW




SECTION B




ANCHOR DETAIL

A.S.T.M. A-307



END DIAPHRAGMS AT INTERMEDIATE PIER

LONGITUDINAL DIMENSIONS ARE NORMAL TO PIER




SECTION C

ALL LONGIT. DIMENSIONS SHOWN ARE NORMAL TO ℄ BRG.

W53DG Deck Bulb Tee Diaphragm Details


Figure 5-A-178



GIRDER ELEVATION


GENERAL NOTES

1. ALL DETAILS SHOWN PERTAIN ONLY TO THE 65 INCH DEEP GIRDER WITH THE 6'-0" GIRDER WIDTH SHOWN.
2. FORMS FOR THE BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER SO AS TO NOT CAUSE DAMAGE TO THE GIRDERS DURING THE STRAND RELEASE OPERATION.
3. SPAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE
4. ALL PRESTRESSING STRANDS SHALL BE ½ INCH OR 0.6 INCH ø LOW RELAXATION SEVEN WIRE STRAND, AASHTO M203 GR. 270. ALL MILD STEEL REINFORCING SHALL BE AASHTO M31 GR. 60. ALL STUDS SHALL CONFORM TO STD. SPEC. SECTION 9-06.15. ALL OTHER STEEL SHALL BE AASHTO M183 AND SHALL BE PAINTED WITH 2 COATS OF STATE FORMULA A-9-73.
5. CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS EXCEPT FOR THOSE SHOWN TO BE EXTENDED, AND PAINT ENDS OF FLUSH STRANDS WITH AN APPROVED EPOXY RESIN.
6. AFTER ERECTION, CUT OFF LIFTING LOOPS 1 INCH BELOW THE TOP OF THE FLANGE AND FILL WITH AN APPROVED GROUT PRIOR TO PLACING OF THE OVERLAY. ALL LIFTING STRANDS ARE TO BE OF THE SAME MATERIAL AND STRENGTH AS THE PRESTRESSING STRANDS. WRAP LIFTING LOOPS SO THAT EACH STRAND WILL CARRY IT'S SHARE OF THE TOTAL LOAD. EXTEND LIFTING LOOPS WITH 9 INCH LONG 90° HOOKS TO WITHIN 3 INCHES CLEAR OF THE BOTTOM OF THE GIRDER.
7. TOP 2 INCHES OF GIRDER FLANGE SHALL BE AIR-ENTRAINED CONCRETE.




GIRDER PLAN

OMIT WELD TIES ON EXTERIOR EDGE OF EXTERIOR GIRDER.
(STRANDS AND LONGITUDINAL BARS NOT SHOWN)




EXTERIOR GIRDER REINFORCING NEAR GIRDER END

FOR DETAILS NOT SHOWN, SEE INTERIOR GIRDER



INTERIOR GIRDER REINFORCING NEAR MIDSPAN


*** THICKEN FLANGE TO COMPENSATE FOR SUPERELEVATION



PLAN SECTION THROUGH GIRDER WEB


MARK	LOCATION	SIZE	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
G1	GIRDER STIRRUPS	4	△△ #3 OR #4 BARS MAY BE USED IN LIEU OF W12. FIELD BEND IS OPTIONAL.
G2	GIRDER END STIRRUPS	5	
G3	BOTTOM FLANGE	3	
G4	TOP OF TOP FLANGE - LONGIT.	▽ 4 STR.	
G5	BOT. OF TOP FLANGE - TRANSV.	4	
G6	TOP TRANSV. - EXT. GIRDER	▽ 6	
G7	TOP TRANSV. - INT. GIRDER	▽ 6 STR.	
G8	BOT. OF TOP FLANGE - LONGIT.	4 STR.	
G10	GIRDER END TIES	W12 △△	
G11	GIRDER LONGIT.	6 STR.	
S1	T.B. TO DECK TIE	▽ 5	
S2	T.B. TO DECK TIE	4	

▽ DENOTES EPOXY COATED




W65DG Deck Bulb Tee Girder Details 1 of 2

Figure 5-A-179




STRAND PATTERN AT GIRDER END

HARPED STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




STRAND PATTERN AT ℄ SPAN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.




TIE SPACING DETAIL




SAWTEETH DETAILS


SAWTEETH ARE FULL WIDTH - USE SAWTEETH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRAND




SECTION B / 1 WELD TIE ALTERNATE #2



SECTION B / 1 WELD TIE ALTERNATE #3



GIRDER FLANGE THICKENING**




GIRDER END


AT END PIERS

* ALTERNATIVELY THE TOP 2 INCHES OF THE GIRDER FLANGE MAY BE AIR-ENTRAINED CONCRETE.

** THICKEN FLANGE TO COMPENSATE FOR CAMBER DUE TO PRESTRESS. FLANGE THICKNESS SHOWN IS @ ℄ OF SPAN. FOR FLANGE THINCKNESS ALONG GIRDER SEE GIRDER FLANGE THICKENING DETAILS ON BR. SHEET [ ]. GIRDERS WITH ULTIMATE CAMBER VALUES SMALLER THAN ¾" ARE EXEMPT FROM THIS REQUIREMENT. FLANGE THICKENING SHALL BE USED ONLY IF NEEDED BY DESIGN.




SECTION B / 1 WELD TIE ALTERNATE #1



BEARING RECESS

BEARING RECESS IS NORMAL TO ℄ GIRDER




SECTION A / 1 KEYWAY

GIRDER SCHEDULE

SPAN	GIRDER	END 1	END 2	S	LS	θ1	θ2	P1	P2	PLAN LENGTH (ALONG GIRDER GRADE)	MIN. CONC. COMPR. STRENGTH @ FINAL F'C KSI	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI KSI	HARPED NO. OF STRANDS	HARPED JACKING FORCE (KIPS)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (KIPS)	LOCATION OF C.G. STRANDS E	LOCATION OF C.G. STRANDS F℄	LOCATION OF C.G. STRANDS Fb	LOCATION OF C.G. STRANDS Fo	CAMBER (IN) RELEASE △	CAMBER (IN) 2000 △	
-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-


W65DG Deck Bulb Tee Girder Details 2 of 2

Figure 5-A-180




W65DG Deck Bulb Tee Girder Diaphragm Details

Figure 5-A-181




GIRDER STOP DETAIL



GROUT PAD GEOMETRY

NOTE:


1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.



BEARING PAD

LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60

(SKEW ANGLE SHOWN @ 30°)




GROUT PAD DETAIL

(SKEW ANGLE SHOWN @ 30°)
(SHOWN FOR END DIAPHRAGM ON GIRDER)


W65DG Deck Bulb Tee Girder Misc. Diaphragm Details

Figure 5-A-182




PRECAST LONGITUDINAL HALF-SECTION

SHOWING POST-TENSIONING CABLE PATHS
* MEASURED BEFORE POST-TENSIONING.




DETAIL A



TENDON IN SAG CURVE


STRAND LOCATION DETAIL



DUCT SPLICE DETAIL

POST-TENSIONING TABLE

SPAN	GIRDER	MIN. CONC. COMPRESIVE STRENGTH, KSI		NUMBER OF STRANDS	PRESTRESSING LOAD KIPS		PRESTRESS LOSS KSI	E_1 (IN.)	E_2 (IN.)	E_3 (IN.)
		GIRDER	WET JOINT		JACKING	AFTER SEATING				




STRAND PATTERN AT ℄ SPAN

STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.

POST-TENSIONING NOTES

1. THE CAST-IN-PLACE CONCRETE IN DECK SLAB SHALL BE CLASS 4000D. THE MINIMUM COMPRESSIVE STRENGTH OF THE CAST-IN-PLACE CONCRETE AT THE WET JOINT AT THE TIME OF POST-TENSIONING SHALL BE ??? ksi.
2. THE MINIUM PRESTRESSING LOAD AFTER SEATING AND THE MINIMUM NUMBER OF PRESTRESSING STRANDS FOR EACH GIRDER SHALL BE AS SHOWN IN POST-TENSIONING TABLE.
3. THE DESIGN IS BASED ON ?? INCH DIAMETER LOW RELAXATION STRANDS WITH A JACKING LOAD FOR EACH GIRDER AS SHOWN IN POST-TENSIONING TABLE, AN ANCHOR SET OF ⅜ INCH OF CURVATURE FRICTION COEFFICIENT, μ = 0.20 AND A WOBBLE FRICTION COEFFICIENT, k = 0.0002/ft. THE ACTUAL ANCHOR SET USED BY THE CONTRACTOR SHALL BE SPECIFIED IN THE SHOP PLANS AND INCLUDED IN THE TRANSFER FORCE CALCULATIONS.
4. THE DESIGN IS BASED ON THE ESTIMATED PRESTRESS LOSS OF POST-TENSIONING STRANDS SHOWN IN POST-TENSIONING TABLE DUE TO STEEL RELAXATION, ELASTIC SHORTENING CREEP AND SHRINKAGE OF CONCRETE.
5. THE CONTRACTOR SHALL SUBMIT THE STRESSING SEQUENCE AND ELONGATION CALCULATIONS TO THE ENGINEER FOR APPROVAL. ALL LOSSES DUE TO TENDON VERTICAL AND HORIZONTAL CURVATURE MUST BE INCLUDED IN ELONGATION CALCULATIONS.
   A. THE PRESTRESSING FORCE SHALL BE DISTRIBUTED WITH AN APPROXIMATELY EQUAL AMOUNT IN EACH WEB.
   B. NO MORE THAN ONE-HALF OF THE PRESTRESSING FORCE IN ANY WEB MAY BE STRESSED BEFORE AN EQUAL FORCE IS STRESSED IN THE ADJACENT WEBS.
6. THE MAXIMUM OUTSIDE DIAMETER OF THE DUCT SHALL BE ??? INCHES. THE AREA OF THE DUCT SHALL BE AT LEAST 2.5 TIMES THE NET AREA OF THE PRESTRESSING STEEL IN THE DUCT.
7. ALL TENDONS SHALL BE STRESSED FROM PIER ??.

WF74PTG Spliced Girder Details 1 of 5
Figure 5-A-183




TYPICAL END ELEVATION AT END DIAPHRAGMS


TYPICAL END ELEVATION AT CLOSURE PLACEMENT

PRE-TENSIONING NOTES:

1. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
2. ALL STRAND FOR PRETENSIONING SHALL BE ??? DIAMETER LOW RELAXATION STRANDS (AASHTO M203, GRADE 270).
3. EXCEPT FOR ??? EXTENDED STRANDS AS SHOWN, CUT ALL REMAINING STRANDS 1" BELOW SURFACE OF THE GIRDER ENDS AND GROUT WITH ANY APPROVED EPOXY GROUT.
4. THE GIRDERS MAY NEED TO BE BRACED LATERALLY DURING SHIPPING TO PREVENT TIPPING OR BUCKLING.
5. LIFTING BARS SHALL BE 1⅜" DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275, GRADE 150 MINIMUM). LIFTING HARDWARE THAT CONNECTS TO THREADED BARS SHALL BE DESIGNED AND DETAILED BY THE CONTRACTOR. LIFTING FORCES ON THREAD BARS SHALL BE VERTICAL ONLY AND WITHIN 10 DEGREES OF PERPENDICULAR TO A LINE BETWEEN PICK POINTS. CONTRACTOR SHALL SUBMIT CALCULATIONS FOR APPROVAL BY THE ENGINEER IF LIFTING FORCES ARE TO BE OTHERWISE.
6. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING ALL GIRDERS. ALL GIRDERS SHALL BE CHECKED TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING.
7. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS NOT TO CAUSE DAMAGE TO THE GIRDER DURING STRAND RELEASE OPERATION.
9. FOR SAWTEETH DETAILS SEE WPT83G GIRDER DETAILS 5 OF 5.




SECTION A



TRANSVERSE REINFORCING AT SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN

END SEGMENT DETAILS



VIEW B

REINFORCING NOT SHOWN FOR CLARITY. SAWTEETH SHOWN BY SHADED AREA.

VIEW B

FOR "B1" & "B2" SEE WPT83G GIRDER DETAILS 3 OF 5


SECTION C

VIEW D


SAWTEETH SHOWN BY SHADED AREA.

WF74PTG Spliced Girder Details 2 of 5

Figure 5-A-184




ALTERNATE STIRRUP DETAIL




STRAND EXTENSION DETAIL

NOTES TO DESIGNER:


This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms. Designer shall calculate the exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.




SECTION A



ELEVATION




PLAN



PLAN

BOTTOM FLANGE SPALL PROTECTION



ELEVATION

TEMPORARY STRAND PATTERN AT TOP FLANGE GIRDER END


Notes to designer	#, # # DESIGNER TO MODIFY FOR SPECIFIC PROJECT					
DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
End diaph. on girder	A	YES	1'-10"	1'-6"	9"	YES
"L" Abutment	B	YES	0	0	0	NO
Hinge diaph.on interm. pier	C	NO	1'-10"	1'-6"	9"	YES
Fixed diaph.@ interm. pier	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
Mult. simple spans @ interm. pier	E	YES	0	0	0	NO
Spliced girder closure pour	F	YES	1'-10"	1'-6"	9"	YES

TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0 (G4)
B2 = 0 (G5 , G9)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4)
B2 = 3" (G5 , G9)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	#
G8	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	4	STR.
G10	GIRDER STIRRUPS	4	
G10	GIRDER STIRRUPS	5	


BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)



#3 OR #4 MAY BE SUBSTITUTED. FIELD BENDING IS OPTIONAL.


WF74PTG Spliced Girder Details 3 of 5

Figure 5-A-185




GIRDER ELEVATION ~ MID-SEGMENT

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1"ø ROCKET/KOHLER, BURKE HI-TENSILE, LANCASTER MALLEABLE OR APPROVED EQUAL.




TYPICAL MID-SEGMENT ELEVATION




SECTION C

WF74PTG Spliced Girder Details 4 of 5

Figure 5-A-186




GIRDER PLAN



STRAND PATTERN
PRECAST END SEGMENTS

STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1),(2),(3), ... ETC.


INDICATES DEBOND STRAND




STRAND PATTERN
PRECAST MID-SEGMENT

STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1),(2),(3) , ... ETC.

INDICATES DEBOND STRAND.




STRAND DEBONDING DETAIL



SAWTEETH DETAIL


SAWTEETHS ARE FULL WIDTH ~ USE SAWTEETH KEYS, IN AREA OUTSIDE OF PT. DUCTS AS SHOWN IN SECTION D/2 D/2

| DIMENSION "A" AT ℄ BEARINGS = SEE "A" DIMENSION TABLE | | |




PRECAST LONGITUDINAL HALF-SECTION

SHOWING POST-TENSIONING CABLE PATHS
* MEASURED BEFORE POST-TENSIONING.
** CONTRACTOR MAY ELECT TO CAST THE GIRDER IN ONE PIECE IF THE SHIPPING WEIGHT IS LESS THAN 200 KIPS & THE SHIPPING ROUTE ALLOWS THE SHIPMENT OF LONG GIRDERS.




DETAIL A



TENDON IN SAG CURVE


STRAND LOCATION DETAIL



DUCT SPLICE DETAIL

POST-TENSIONING TABLE

SPAN	GIRDER	MIN. CONC. COMPRESIVE STRENGTH, KSI		NUMBER OF STRANDS	PRESTRESSING LOAD KIPS		PRESTRESS LOSS KSI	E_1 (IN.)	E_2 (IN.)	E_3 (IN.)
		GIRDER	WET JOINT		JACKING	AFTER SEATING				



STRAND PATTERN AT ℄ SPAN


STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.

POST-TENSIONING NOTES

1. THE CAST-IN-PLACE CONCRETE IN DECK SLAB SHALL BE CLASS 4000D. THE MINIMUM COMPRESSIVE STRENGTH OF THE CAST-IN-PLACE CONCRETE AT THE WET JOINT AT THE TIME OF POST-TENSIONING SHALL BE ??? ksi.
2. THE MINIUM PRESTRESSING LOAD AFTER SEATING AND THE MINIMUM NUMBER OF PRESTRESSING STRANDS FOR EACH GIRDER SHALL BE AS SHOWN IN POST-TENSIONING TABLE.
3. THE DESIGN IS BASED ON ?? INCH DIAMETER LOW RELAXATION STRANDS WITH A JACKING LOAD FOR EACH GIRDER AS SHOWN IN POST-TENSIONING TABLE, AN ANCHOR SET OF ⅜ INCH OF CURVATURE FRICTION COEFFICIENT, μ = 0.20 AND A WOBBLE FRICTION COEFFICIENT, k = 0.0002/ft. THE ACTUAL ANCHOR SET USED BY THE CONTRACTOR SHALL BE SPECIFIED IN THE SHOP PLANS AND INCLUDED IN THE TRANSFER FORCE CALCULATIONS.
4. THE DESIGN IS BASED ON THE ESTIMATED PRESTRESS LOSS OF POST-TENSIONING STRANDS SHOWN IN POST-TENSIONING TABLE DUE TO STEEL RELAXATION, ELASTIC SHORTENING CREEP AND SHRINKAGE OF CONCRETE.
5. THE CONTRACTOR SHALL SUBMIT THE STRESSING SEQUENCE AND ELONGATION CALCULATIONS TO THE ENGINEER FOR APPROVAL. ALL LOSSES DUE TO TENDON VERTICAL AND HORIZONTAL CURVATURE MUST BE INCLUDED IN ELONGATION CALCULATIONS.
   A. THE PRESTRESSING FORCE SHALL BE DISTRIBUTED WITH AN APPROXIMATELY EQUAL AMOUNT IN EACH WEB.
   B. NO MORE THAN ONE-HALF OF THE PRESTRESSING FORCE IN ANY WEB MAY BE STRESSED BEFORE AN EQUAL FORCE IS STRESSED IN THE ADJACENT WEBS.
6. THE MAXIMUM OUTSIDE DIAMETER OF THE DUCT SHALL BE ??? INCHES. THE AREA OF THE DUCT SHALL BE AT LEAST 2.5 TIMES THE NET AREA OF THE PRESTRESSING STEEL IN THE DUCT.
7. ALL TENDONS SHALL BE STRESSED FROM PIER ??.

W83PTG Spliced Girder Details 1 of 5

Figure 5-A-188




TYPICAL END ELEVATION AT END DIAPHRAGMS


TYPICAL END ELEVATION AT CLOSURE PLACEMENT

PRE-TENSIONING NOTES:

1. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
2. ALL STRAND FOR PRETENSIONING SHALL BE ??? DIAMETER LOW RELAXATION STRANDS (AASHTO M203, GRADE 270).
3. EXCEPT FOR ??? EXTENDED STRANDS AS SHOWN, CUT ALL REMAINING STRANDS 1" BELOW SURFACE OF THE GIRDER ENDS AND GROUT WITH ANY APPROVED EPOXY GROUT.
4. THE GIRDERS MAY NEED TO BE BRACED LATERALLY DURING SHIPPING TO PREVENT TIPPING OR BUCKLING.
5. LIFTING BARS SHALL BE 1 ⅜" DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275, GRADE 150 MINIMUM). LIFTING HARDWARE THAT CONNECTS TO THREADED BARS SHALL BE DESIGNED AND DETAILED BY THE CONTRACTOR. LIFTING FORCES ON THREAD BARS SHALL BE VERTICAL ONLY AND WITHIN 10 DEGREES OF PERPENDICULAR TO A LINE BETWEEN PICK POINTS. CONTRACTOR SHALL SUBMIT CALCULATIONS FOR APPROVAL BY THE ENGINEER IF LIFTING FORCES ARE TO BE OTHERWISE.
6. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING ALL GIRDERS. ALL GIRDERS SHALL BE CHECKED TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING.
7. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS NOT TO CAUSE DAMAGE TO THE GIRDER DURING STRAND RELEASE OPERATION.
9. FOR SAWTEETH DETAILS SEE WPT83G GIRDER DETAILS 5 OF 5.




SECTION A



TRANSVERSE REINFORCING AT SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN

END SEGMENT DETAILS




VIEW B

REINFORCING NOT SHOWN FOR CLARITY. SAWTEETH SHOWN BY SHADED AREA.




VIEW B

FOR "B1" & "B2" SEE WPT83G GIRDER DETAILS 3 OF 5



SECTION C




VIEW D


SAWTEETH SHOWN BY SHADED AREA.

W83PTG Spliced Girder Details 2 of 5

Figure 5-A-189




ALTERNATE STIRRUP DETAIL




STRAND EXTENSION DETAIL

NOTES TO DESIGNER:


This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms. Designer shall calculate the exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.




SECTION A



ELEVATION




PLAN



ELEVATION

TEMPORARY STRAND PATTERN AT TOP FLANGE GIRDER END

Notes to designer	#, # # DESIGNER TO MODIFY FOR SPECIFIC PROJECT					
DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
End diaph. on girder	A	YES	1'-10"	1'-6"	9"	YES
"L" Abutment	B	YES	0	0	0	NO
Hinge diaph.on interm. pier	C	NO	1'-10"	1'-6"	9"	YES
Fixed diaph.@ interm. pier	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
Mult. simple spans @ interm. pier	E	YES	0	0	0	NO
Spliced girder closure pour	F	YES	1'-10"	1'-6"	9"	YES



PLAN

BOTTOM FLANGE SPALL PROTECTION


TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0 (G4)
B2 = 0 (G5 , G9)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4)
B2 = 3" (G5 , G9)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	#
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	4	STR.
G10	GIRDER STIRRUPS	4	
G11	GIRDER STIRRUPS	5	


#3 OR #4 MAY BE SUBSTITUTED. FIELD BENDING IS OPTIONAL

BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)




W83PTG Spliced Girder Details 3 of 5

Figure 5-A-190




GIRDER ELEVATION ~ MID-SEGMENT

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1"ø ROCKET/KOHLER, BURKE HI-TENSILE, LANCASTER MALLEABLE OR APPROVED EQUAL.




TYPICAL MID-SEGMENT ELEVATION




SECTION C

W83PTG Spliced Girder Details 4 of 5

Figure 5-A-191




GIRDER PLAN



STRAND PATTERN
PRECAST END SEGMENTS

STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1),(2),(3), ... ETC.


INDICATES DEBOND STRAND




STRAND PATTERN
PRECAST MID-SEGMENT

STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1),(2),(3) , ... ETC.

INDICATES DEBOND STRAND



STRAND DEBONDING DETAIL



SAWTEETH DETAIL

SAWTEETH ARE FULL WIDTH ~ USE SAWTEETH KEYS, IN AREA OUTSIDE OF PT. DUCTS AS SHOWN IN SECTION

DIMENSION "A" AT ℄ BEARINGS SEE "A" DIMENSION TABLE

SPAN	GIRDER	MIN. CONC. COMPR. STRENGTH @ 28 DAYS F'C MPa	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI MPa	END SEGMENT 1 END 1 TYPE	END SEGMENT 1 END 2 TYPE	END SEGMENT 1 L	END SEGMENT 1 θ1	END SEGMENT 1 θ2	END SEGMENT 1 P1	END SEGMENT 1 PLAN LENGTH (ALONG ℄ GIRDER GRADE)	END SEGMENT 1 STRAIGHT NO. OF STRANDS	END SEGMENT 1 STRAIGHT JACKING FORCE (LBS)	END SEGMENT 1 C.G. STRANDS (IN.) E	END SEGMENT 1 D (30 DAYS) (IN.)	END SEGMENT 1 C (IN.)	MID-SEGMENT END 1 TYPE	MID-SEGMENT END 2 TYPE	MID-SEGMENT L	MID-SEGMENT θ1	MID-SEGMENT θ2	MID-SEGMENT PLAN LENGTH (ALONG ℄ GIRDER GRADE)	MID-SEGMENT STRAIGHT NO. OF STRANDS	MID-SEGMENT STRAIGHT JACKING FORCE (LBS)	MID-SEGMENT C.G. STRANDS (IN.) E	MID-SEGMENT D (30 DAYS) (IN.)	MID-SEGMENT C (IN.)	END SEGMENT 2 END 1 TYPE	END SEGMENT 2 END 2 TYPE	END SEGMENT 2 L	END SEGMENT 2 θ1	END SEGMENT 2 θ2	END SEGMENT 2 P2	END SEGMENT 2 PLAN LENGTH (ALONG ℄ GIRDER GRADE)	END SEGMENT 2 STRAIGHT NO. OF STRANDS	END SEGMENT 2 STRAIGHT JACKING FORCE (LBS)	END SEGMENT 2 C.G. STRANDS (IN.) E	END SEGMENT 2 D (30 DAYS) (IN.)	END SEGMENT 2 C (IN.)

"A" DIMENSION TABLE

PIER	"A" (40 DAYS) (IN)	"A" (120 DAYS) (IN)

BENDING DIAGRAM

≠ ≠ ≠ DESIGNER TO MODIFY FOR SPECIFIC PROJECT


MARK	LOCATION	SIZE	
G2		5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER LONGIT.	7	STR.
G6	GIRDER END TIES	W12	≠
G7	GIRDER BOTTOM FLANGE TIES	3	
G9	GIRDER LONGIT. FULL LENGTH	4	STR.
G10	GIRDER TOP FLANGE STIRRUPS	4	

ALL DIMENSIONS ARE OUT TO OUT

* = VARIES FOR SKEWED SPANS


NOTE:
FOR DIMENSION "A", SEE "A" DIMENSION TABLE

≠ #3 OR #4 MAY BE SUBSTITUTED FOR FOR W12, FIELD BENDING IS OPTIONAL.



W83PTG Spliced Girder Details 5 of 5

Figure 5-A-192




PRECAST END SEGEMENT


PRECAST MID-SEGEMENT

PRECAST LONGITUDINAL HALF-SECTION

SHOWING POST-TENSIONING CABLE PATHS
* MEASURED BEFORE POST-TENSIONING.
** CONTRACTOR MAY ELECT TO CAST THE GIRDER IN ONE PIECE IF THE SHIPPING WEIGHT IS LESS THAN 200 KIPS & THE SHIPPING ROUTE ALLOWS THE SHIPMENT OF LONG GIRDERS.




DETAIL A



TENDON IN SAG CURVE


STRAND LOCATION DETAIL



DUCT SPLICE DETAIL

POST-TENSIONING TABLE

SPAN	GIRDER	MIN. CONC. COMPRESIVE STRENGTH, KSI		NUMBER OF STRANDS	PRESTRESSING LOAD KIPS		PRESTRESS LOSS KSI	E_1 (IN.)	E_2 (IN.)	E_3 (IN.)
		GIRDER	WET JOINT		JACKING	AFTER SEATING				



STRAND PATTERN AT ℄ SPAN


STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1),(2) ETC.

POST-TENSIONING NOTES

1. THE CAST-IN-PLACE CONCRETE IN DECK SLAB SHALL BE CLASS 4000D. THE MINIMUM COMPRESSIVE STRENGTH OF THE CAST-IN-PLACE CONCRETE AT THE WET JOINT AT THE TIME OF POST-TENSIONING SHALL BE ??? ksi.
2. THE MINIUM PRESTRESSING LOAD AFTER SEATING AND THE MINIMUM NUMBER OF PRESTRESSING STRANDS FOR EACH GIRDER SHALL BE AS SHOWN IN POST-TENSIONING TABLE.
3. THE DESIGN IS BASED ON ?? INCH DIAMETER LOW RELAXATION STRANDS WITH A JACKING LOAD FOR EACH GIRDER AS SHOWN IN POST-TENSIONING TABLE, AN ANCHOR SET OF ⅜ INCH OF CURVATURE FRICTION COEFFICIENT, μ = 0.20 AND A WOBBLE FRICTION COEFFICIENT, k = 0.0002/ft. THE ACTUAL ANCHOR SET USED BY THE CONTRACTOR SHALL BE SPECIFIED IN THE SHOP PLANS AND INCLUDED IN THE TRANSFER FORCE CALCULATIONS.
4. THE DESIGN IS BASED ON THE ESTIMATED PRESTRESS LOSS OF POST-TENSIONING STRANDS SHOWN IN POST-TENSIONING TABLE DUE TO STEEL RELAXATION, ELASTIC SHORTENING CREEP AND SHRINKAGE OF CONCRETE.
5. THE CONTRACTOR SHALL SUBMIT THE STRESSING SEQUENCE AND ELONGATION CALCULATIONS TO THE ENGINEER FOR APPROVAL. ALL LOSSES DUE TO TENDON VERTICAL AND HORIZONTAL CURVATURE MUST BE INCLUDED IN ELONGATION CALCULATIONS.
   A. THE PRESTRESSING FORCE SHALL BE DISTRIBUTED WITH AN APPROXIMATELY EQUAL AMOUNT IN EACH WEB.
   B. NO MORE THAN ONE-HALF OF THE PRESTRESSING FORCE IN ANY WEB MAY BE STRESSED BEFORE AN EQUAL FORCE IS STRESSED IN THE ADJACENT WEBS.
6. THE MAXIMUM OUTSIDE DIAMETER OF THE DUCT SHALL BE ??? INCHES. THE AREA OF THE DUCT SHALL BE AT LEAST 2.5 TIMES THE NET AREA OF THE PRESTRESSING STEEL IN THE DUCT.
7. ALL TENDONS SHALL BE STRESSED FROM PIER ??.

W95PTG Spliced Girder Details 1 of 5

Figure 5-A-193




TYPICAL END ELEVATION AT END DIAPHRAGMS

TYPICAL END ELEVATION AT CLOSURE PLACEMENT

PRE-TENSIONING NOTES:

1. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
2. ALL STRAND FOR PRETENSIONING SHALL BE ??? DIAMETER LOW RELAXATION STRANDS (AASHTO M203, GRADE 270).
3. EXCEPT FOR ??? EXTENDED STRANDS AS SHOWN, CUT ALL REMAINING STRANDS 1" BELOW SURFACE OF THE GIRDER ENDS AND GROUT WITH ANY APPROVED EPOXY GROUT.
4. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H OF THE STANDARD SPECIFICATIONS.
5. LIFTING BARS SHALL BE 1 ⅜" DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275, GRADE 150 MINIMUM). LIFTING HARDWARE THAT CONNECTS TO THREADED BARS SHALL BE DESIGNED AND DETAILED BY THE CONTRACTOR. LIFTING FORCES ON THREAD BARS SHALL BE VERTICAL ONLY AND WITHIN 10 DEGREES OF PERPENDICULAR TO A LINE BETWEEN PICK POINTS. CONTRACTOR SHALL SUBMIT CALCULATIONS FOR APPROVAL BY THE ENGINEER IF LIFTING FORCES ARE TO BE OTHERWISE.
6. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING ALL GIRDERS. ALL GIRDERS SHALL BE CHECKED TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING.
7. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SUCH A MANNER AS NOT TO CAUSE DAMAGE TO THE GIRDER DURING STRAND RELEASE OPERATION.
9. FOR SAWTEETH DETAILS SEE WPT83G GIRDER DETAILS 5 OF 5.




SECTION A

TRANSVERSE REINFORCING AT SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN

END SEGMENT DETAILS




VIEW B

REINFORCING NOT SHOWN FOR CLARITY. SAWTEETH SHOWN BY SHADED AREA.




VIEW B

FOR "B1" & "B2" SEE WPT83G GIRDER DETAILS 3 OF 5



SECTION C




VIEW D


SAWTEETH SHOWN BY SHADED AREA.

W95PTG Spliced Girder Details 2 of 5

Figure 5-A-194




ALTERNATE STIRRUP DETAIL




STRAND EXTENSION DETAIL

NOTES TO DESIGNER:


This strand extension detail is to be used for continuous spans at moment resisting diaphragms only. This detail is not applicable to continuous spans using hinge diaphragms. Designer shall calculate the exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.




SECTION A



ELEVATION




PLAN



ELEVATION

TEMPORARY STRAND PATTERN AT TOP FLANGE GIRDER END



PLAN

BOTTOM FLANGE SPALL PROTECTION


Notes to designer	#, ## DESIGNER TO MODIFY FOR SPECIFIC PROJECT					
DIAPHRAGM TYPE	END TYPE	BEARING RECESS	X	Y	Z	SAWTEETH
End diaph. on girder	A	YES	1'-10"	1'-6"	9"	YES
"L" Abutment	B	YES	0	0	0	NO
Hinge diaph.on interm. pier	C	NO	1'-10"	1'-6"	9"	YES
Fixed diaph.@ interm. pier	D	NO	1'-10"	ALT. 1 OR ALT. 2 STRAND EXTEN.		YES
Mult. simple spans @ interm. pier	E	YES	0	0	0	NO
Spliced girder closure pour	F	YES	1'-10"	1'-6"	9"	YES

TO BE USED @ INTERMEDIATE PIER ON MULTIPLE SPAN BRIDGE

ENDS AHEAD ON STATION
G5 BARS LEFT OF ℄
B1 = 0 (G4)
B2 = 0 (G5 , G9)
ENDS BACK ON STATION
G5 BARS RIGHT OF ℄
B1 = 1½"(G4)
B2 = 3" (G5 , G9)

MARK	LOCATION	SIZE	
G1	GIRDER STIRRUPS	5	
G2	GIRDER END STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER END LONGIT.	7	STR.
G6	GIRDER END TIES	W12	#
G7	GIRDER BOT. FLANGE TIES	3	
G9	GIRDER END LONGIT.	4	STR.
G10	GIRDER STIRRUPS	4	


BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)



is #3 OR #4 MAY BE SUBSTITUTED. FIELD BENDING IS OPTIONAL.


W95PTG Spliced Girder Details 3 of 5

Figure 5-A-195




GIRDER ELEVATION ~ MID-SEGMENT

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR GIRDERS. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1"ø ROCKET/KOHLER, BURKE HI-TENSILE, LANCASTER MALLEABLE OR APPROVED EQUAL.




TYPICAL MID-SEGMENT ELEVATION




SECTION C

W95PTG Spliced Girder Details 4 of 5

Figure 5-A-196




GIRDER PLAN



STRAND PATTERN
PRESCAST END SEGMENTS

STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1),(2),(3) , ... ETC.


INDICATES DEBOND STRAND FOR A TOTAL OF 6'-0" FROM END OF GIRDER.




STRAND PATTERN
PRECAST MID-SEGMENT

STRAIGHT STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1),(2), (3) , ... ETC.

INDICATES DEBOND STRAND IF NEEDED FOR A TOTAL OF 6'-0" FROM END OF GIRDER.



STRAND DEBONDING DETAIL



SAWTEETH DETAIL

SAWTEETH ARE FULL WIDTH ~ USE SAWTEETH KEYS, IN AREA OUTSIDE OF PT. DUCTS AS SHOWN IN SECTION

DIMENSION "A" AT ℄ BEARINGS = SEE "A" DIMENSION TABLE

SPAN	GIRDER	MIN. CONC. COMPR. STRENGTH @ 28 DAYS F'C MPa	MIN. CONC. COMPR. STRENGTH @ RELEASE F'CI MPa	END SEGMENT 1											MID-SEGMENT												END SEGMENT 2													
				END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	PLAN LENGTH (ALONG ℄ GIRDER GRADE)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (LBS)	C.G. STRANDS (IN.) E	D (30 DAYS) (IN)	C (IN)	END 1 TYPE	END 2 TYPE	L	θ1	θ2	PLAN LENGTH (ALONG ℄ GIRDER GRADE)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (LBS)	C.G. STRANDS (IN.) E	D (IN)	C (IN)	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P2	PLAN LENGTH (ALONG ℄ GIRDER GRADE)	STRAIGHT NO. OF STRANDS	STRAIGHT JACKING FORCE (LBS)	C.G. STRANDS (IN.) E	Ld (IN.)	D (IN)	C (IN)

"A" DIMENSION TABLE

PIER	"A" (40 DAYS) (IN)	"A" (120 DAYS) (IN)

BENDING DIAGRAM

≠ ≠ ≠ DESIGNER TO MODIFY FOR SPECIFIC PROJECT


MARK	LOCATION	SIZE	
G2	GIRDER STIRRUPS	5	
G3	GIRDER TOP FLANGE	5	STR.
G4	GIRDER LONGIT. FULL LENGTH	5	STR.
G5	GIRDER LONGIT.	7	STR.
G6	GIRDER END TIES	W12	≠
G7	GIRDER BOTTOM FLANGE TIES	3	
G9	GIRDER LONGIT. FULL LENGTH	4	STR.
G10	GIRDER TOP FLANGE STIRRUPS	4	

ALL DIMENSIONS ARE OUT TO OUT

* = VARIES FOR SKEWED SPANS


NOTE:
FOR DIMENSION "A", SEE TABLE

≠ #3 OR #4 MAY BE SUBSTITUTED FOR FOR W12, FIELD BENDING IS OPTIONAL.




W95PTG Spliced Girder Details 5 of 5

Figure 5-A-197




PRECAST LONGITUDINAL HALF-SECTION


SHOWING POST-TENSIONING CABLE PATHS
* MEASURED BEFORE POST-TENSIONING.
** CONTRACTOR MAY ELECT TO CAST THE PT GIRDER IN ONE PIECE IF THE SHIPPING WEIGHT IS LESS THAN 182 KIPS & THE SHIPPING ROUTE ALLOWS THE SHIPMENT OF LONG GIRDERS.




BOTTOM SLAB DRAIN HOLE




DUCT SPLICE DETAIL



STRAND LOCATION DETAIL




STRAND PATTERN @ ℄ SPAN



OPEN HOLE DETAIL

BOTTOM HOLE AT END TYPE "B" ONLY



DETAIL A

POST-TENSIONING TABLE


SPAN	GIRDER	STRAND DIAMETER IN.	PRESSING LOAD PER WEB TOTAL KIPS		PRESTRESS LOSS KSI (TD+ES+FR+AS)	E_1 (IN.)	E_2 (IN.)	E_3 (IN.)
			JACKING	AFTER SEATING				

POST-TENSIONING NOTES

1. THE CAST-IN-PLACE CONCRETE IN DECK SLAB SHALL BE CLASS 4000D. THE MINIMUM COMPRESSIVE STRENGTH OF THE CAST-IN-PLACE CONCRETE AT THE WET JOINT AT THE TIME OF POST-TENSIONING SHALL BE ??? ksi.
2. THE MINIUM PRESTRESSING LOAD AFTER SEATING AND THE MINIMUM NUMBER OF PRESTRESSING STRANDS FOR EACH GIRDER SHALL BE AS SHOWN IN POST-TENSIONING TABLE.
3. THE DESIGN IS BASED ON ?? INCH DIAMETER LOW RELAXATION STRANDS WITH A JACKING LOAD FOR EACH GIRDER AS SHOWN IN POST-TENSIONING TABLE, AN ANCHOR SET OF ⅜ INCH OF CURVATURE FRICTION COEFFICIENT, μ = 0.20 AND A WOBBLE FRICTION COEFFICIENT, k = 0.0002/ft. THE ACTUAL ANCHOR SET USED BY THE CONTRACTOR SHALL BE SPECIFIED IN THE SHOP PLANS AND INCLUDED IN THE TRANSFER FORCE CALCULATIONS.
4. THE DESIGN IS BASED ON THE ESTIMATED PRESTRESS LOSS OF POST-TENSIONING STRANDS SHOWN IN POST-TENSIONING TABLE DUE TO STEEL RELAXATION, ELASTIC SHORTENING CREEP AND SHRINKAGE OF CONCRETE.
5. THE CONTRACTOR SHALL SUBMIT THE STRESSING SEQUENCE AND ELONGATION CALCULATIONS TO THE ENGINEER FOR APPROVAL. ALL LOSSES DUE TO TENDON VERTICAL AND HORIZONTAL CURVATURE MUST BE INCLUDED IN ELONGATION CALCULATIONS.
   A. THE PRESTRESSING FORCE SHALL BE DISTRIBUTED WITH AN APPROXIMATELY EQUAL AMOUNT IN EACH WEB AND SHALL BE PLACED SYMMETRICALLY ABOUT THE CENTERLINE OF THE TUB.
   B. NO MORE THAN ONE-HALF OF THE PRESTRESSING FORCE IN ANY WEB MAY BE STRESSED BEFORE AN EQUAL FORCE IS STRESSED IN THE ADJACENT WEBS. AT NO TIME DURING STRESSING OPERATION WILL MORE THAN ONE-SIXTH OF THE TOTAL PRESTRESSING FORCE IS APPLIED ECCENTRICALLY ABOUT THE CENTERLINE OF BRIDGE.
6. THE MAXIMUM OUTSIDE DIAMETER OF THE DUCT SHALL BE ??? INCHES. THE AREA OF THE DUCT SHALL BE AT LEAST 2.5 TIMES THE NET AREA OF THE PRESTRESSING STEEL IN THE DUCT.
7. ALL TENDONS SHALL BE STRESSED FROM PIER ??.

Trapezoidal Tub Spliced Girder Details 1 of 5

Figure 5-A-198




TYPICAL END ELEVATION AT END DIAPHRAGMS


TYPICAL END ELEVATION AT CLOSURE PLACEMENT

PRE-TENSIONING NOTES:

1. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
2. ALL STRAND FOR PRETENSIONING SHALL BE ??? DIAMETER LOW RELAXATION STRANDS (AASHTO M203, GRADE 270).
3. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
4. EXTENDED STRANDS AND BARS ARE PARALLEL TO GIRDER.
5. LIFTING BARS SHALL BE 1 ⅜" DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275, GRADE 150 MINIMUM). LIFTING HARDWARE THAT CONNECTS TO THREADED BARS SHALL BE DESIGNED AND DETAILED BY THE CONTRACTOR. LIFTING FORCES ON THREAD BARS SHALL BE VERTICAL ONLY AND WITHIN 10 DEGREES OF PERPENDICULAR TO A LINE BETWEEN PICK POINTS. CONTRACTOR SHALL SUBMIT CALCULATIONS FOR APPROVAL BY THE ENGINEER IF LIFTING FORCES ARE TO BE OTHERWISE.
6. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING ALL GIRDERS. ALL GIRDERS SHALL BE CHECKED TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING.
7. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SHOP A MANNER AS NOT TO CAUSE DAMAGE TO THE GIRDER DURING STRAND RELEASE OPERATION.



SECTION A (ONE WEB SHOWN)





VIEW B — SECTION C — VIEW D

*** 1'-0" FOR BOTTOM FLANGE WIDTH LESS THAN 5'-6"
2'-0" FOR BOTTOM FLANGE WIDTH EQUAL OR GREATER THAN 5'-6"

Trapezoidal Tub Spliced Girder Details 2 of 5


Figure 5-A-199






TYPICAL END ELEVATION

EXTENDED STRANDS NOT SHOWN.
USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRANDS.



P.C. SECTION



PLAN

BOTTOM FLANGE SPALL PROTECTION


END TYPE "C" INTERMEDIATE HINGE DIAPHRAGM
AND END TYPE "D" INTEREMEDIATE FIXED DIAPHRAGM

BENDING DIAGRAM


MARK	LOCATION	SIZE	U	W	X	ALL DIMENSIONS ARE OUT TO OUT
G1	STIRRUPS, OUTSIDE WEB	5				
G2	STIRRUPS, INSIDE WEB	5				
G3	LONGITUDINAL BOTTOM FLANGE	4				STR.
G4	TOP WEB LONGIT.	6				STR.
G5	LONGITUDINAL WEB	5				STR.
G6	WEB TIE	W12				≠ #4 MAY BE SUBSTITUTED FOR W12, FIELD BENDING IS OPTIONAL
G7	WEB	4				

* = VARIES FOR SKEWED SPANS

NOTE:
FOR DIMENSION "A", SEE "GIRDER SCHEDULE"




SECTION A




TRANSVERSE REINFORCING AT SKEWED ENDS

ONLY TRANSVERSE REINF. SHOWN




SAWTOOTH DETAILS

SAWTEETH ARE FULL WIDTH - USE SAWTEETH FULL HEIGHT ON END SECTIONS.




Trapezoidal Tub Spliced Girder Details 3 of 5

Figure 5-A-200



GIRDER ELEVATION ~ MID-SEGMENT

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR WEB. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" ø ROCKET/KOHLER, BURKE HI-TENSILE, LANCASTER MALLEABLE OR APPROVED EQUAL.



TYPICAL MID-SEGMENT ELEVATION

Trapezoidal Tub Spliced Girder Details 4 of 5

Figure 5-A-201


DIMENSION "A" AT ℄ BEARINGS = BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB POUR (120 DAYS)

SPAN	GIRDER	END SEGMENT 1												MID-SEGMENT										END SEGMENT 2										
		MIN. CONC. COMPR. STRENGTH		END 1 TYPE	END 2 TYPE	L	θ1	θ2	P1	PLAN LENGTH (ALONG GIRDER GRADE)	STRAIGHT		C.G. STRANDS (IN.)	Ld (IN.)	END 1 TYPE	END 2 TYPE	L	θ1	θ2	PLAN LENGTH (ALONG GIRDER GRADE)	STRAIGHT		C.G. STRANDS (IN.)	Ld (IN.)	END 1 TYPE	END 2 TYPE	L	θ1	θ2	P2	PLAN LENGTH (ALONG GIRDER GRADE)	STRAIGHT		C.G. STRANDS (IN.)	Ld (IN.)
		@ 28 DAYS F'C MPa	@ RELEASE F'CI MPa								NO. OF STRANDS	JACKING FORCE (LBS)	E								NO. OF STRANDS	JACKING FORCE (LBS)	E									NO. OF STRANDS	JACKING FORCE (LBS)	E	

NOTES TO DESIGNER:

1. This strand extension detail is to be used for continuous spans at moment resisting diaphragms only.This detail is not applicable to continuous spans using hinge diaphragms.
2. Designer shall calculate the exact number of extended straight strands needed to develop the required moment capacity at the end of the girder. This calculation shall be based on the tensile strength of the strands, the stresses imposed on the anchor, and concrete bearing against the projected area of the anchor.
   The total number of extended strands shall not be less than:
3. $Nps = 12(Mc + Vc \times h - M_{SIDL}) \times Nc \frac{X}{Ng} \frac{K}{(0.9 \times Aps \times fps \times d)}$


where:
Mc, Vc = The lesser of Elastic or Plastic hinging moment & shear capacity of column Ft-kips, kips respectively,
h = distance from top of column to c.g. of superstructure, Ft
Nc = number of columns
Ng = number of girders
Aps = area of each extended strand, in
fps = ultimate strength of strands, ksi
d = distance from top of slab to c.g. of extended strands, in
M = Moment due to SIDL (Traffic barrier, sidewalk, etc.)
K = 0.5 for L1 = L2
0.67 for L1 = 2L2




STRAND DEBONDING DETAIL

STRAND PATTERN

STRAND LOCATION SEQUENCE SHALL BE AS SHOWN (1), (2) ETC.



ALTERNATE # 1




ALTERNATE # 2


STRAND EXTENSION DETAIL FOR END TYPE D

NOT ALL EXTENDED STRANDS ARE SHOWN

Trapezoidal Tub Spliced Girder Details 5 of 5

Figure 5-A-202






SECTION F


NOTE TO DESIGNER

If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.


TYPICAL END TYPE "A" DIAPHRAGM AT END PIERS




ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS





END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.

NOTE:

1. GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.
2. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
3. END DIAPHRAGM MAY BE CAST ON GRADE. IF SO, THE UPPER LEG OF THE JOINT FILLER SHALL FORM THE BOTTOM FACE FULL WIDTH.
4. JOINT FILLER TYPE 1 SHALL BE USED TO COVER ALL VERTICAL END DIAPHRAGM JOINTS. EITHER JOINT FILLER TYPE 1 OR JOINT FILLER TYPE 2 SHALL BE USED TO COVER ALL HORIZONTAL END DIAPHRAGM JOINTS.


Trapezoidal Tub Spliced Girder End Diaphragm on Girder Details

Figure 5-A-203




PLAN


FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET 3.




SECTION A



TEMPORARY SUPPORT DETAIL




DETAIL C



ELEVATION

CONSTRUCTION SEQUENCE


1. COLUMN & TEMP. SUPPORT
2. PLACE GIRDER ON TEMPORARY SUPPORT
3. CAST DIAPHRAGM STAGE 1
4. CAST ROADWAY SLAB
5. COMPLETE DIAPHRAGM
6. REMOVE TEMPORARY SUPPORT



SECTION B

Trapezoidal Tub Spliced Girder Raised Crossbeam Details

Figure 5-A-204




DETAIL G

NOTE TO DESIGNER:

This detail to be used on bridges with end piers and no wing walls, and located within and west of the Cascade Mountain range.


NOTE:

1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.



BEARING PAD


LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60



TOP ANCHOR BOTTOM ANCHOR

ANCHOR DETAIL


A.S.T.M. A-307



GROUT PAD DETAIL

Trapezoidal Tub Spliced Girder Miscellaneous Details


Figure 5-A-205




PRECAST LONGITUDINAL HALF-SECTION

SHOWING POST-TENSIONING CABLE PATHS
* MEASURED BEFORE POST-TENSIONING.


** CONTRACTOR MAY ELECT TO CAST THE PT GIRDER IN ONE PIECE IF THE SHIPPING WEIGHT IS LESS THAN 182 KIPS & THE SHIPPING ROUTE ALLOWS THE SHIPMENT OF LONG GIRDERS.




BOTTOM SLAB DRAIN HOLE




DUCT SPLICE DETAIL



STRAND LOCATION DETAIL




STRAND PATTERN @ ℄ SPAN



OPEN HOLE DETAIL

BOTTOM HOLE AT END TYPE "B" ONLY



DETAIL A

POST-TENSIONING TABLE

SPAN	GIRDER	STRAND DIAMETER IN.	PRESSING LOAD PER WEB KIPS		TOTAL PRESTRESS LOSS KSI (DT+ES+FR+AS)	E_1 (IN.)	E_2 (IN.)	E_3 (IN.)
			JACKING	AFTER SEATING				


PRESSING LOAD PER WEB KIPS

POST-TENSIONING NOTES

1. THE CAST-IN-PLACE CONCRETE IN DECK SLAB SHALL BE CLASS 4000D. THE MINIMUM COMPRESSIVE STRENGTH OF THE CAST-IN-PLACE CONCRETE AT THE WET JOINT AT THE TIME OF POST-TENSIONING SHALL BE ??? ksi.
2. THE MINIUM PRESTRESSING LOAD AFTER SEATING AND THE MINIMUM NUMBER OF PRESTRESSING STRANDS FOR EACH GIRDER SHALL BE AS SHOWN IN POST-TENSIONING TABLE.
3. THE DESIGN IS BASED ON ?? INCH DIAMETER LOW RELAXATION STRANDS WITH A JACKING LOAD FOR EACH GIRDER AS SHOWN IN POST-TENSIONING TABLE, AN ANCHOR SET OF ⅜ INCH OF CURVATURE FRICTION COEFFICIENT, μ = 0.20 AND A WOBBLE FRICTION COEFFICIENT, k = 0.0002/ft. THE ACTUAL ANCHOR SET USED BY THE CONTRACTOR SHALL BE SPECIFIED IN THE SHOP PLANS AND INCLUDED IN THE TRANSFER FORCE CALCULATIONS.
4. THE DESIGN IS BASED ON THE ESTIMATED PRESTRESS LOSS OF POST-TENSIONING STRANDS SHOWN IN POST-TENSIONING TABLE DUE TO STEEL RELAXATION, ELASTIC SHORTENING CREEP AND SHRINKAGE OF CONCRETE.
5. THE CONTRACTOR SHALL SUBMIT THE STRESSING SEQUENCE AND ELONGATION CALCULATIONS TO THE ENGINEER FOR APPROVAL. ALL LOSSES DUE TO TENDON VERTICAL AND HORIZONTAL CURVATURE MUST BE INCLUDED IN ELONGATION CALCULATIONS.
   A. THE PRESTRESSING FORCE SHALL BE DISTRIBUTED WITH AN APPROXIMATELY EQUAL AMOUNT IN EACH WEB AND SHALL BE PLACED SYMMETRICALLY ABOUT THE CENTERLINE OF THE TUB.
   B. NO MORE THAN ONE-HALF OF THE PRESTRESSING FORCE IN ANY WEB MAY BE STRESSED BEFORE AN EQUAL FORCE IS STRESSED IN THE ADJACENT WEBS. AT NO TIME DURING STRESSING OPERATION WILL MORE THAN ONE-SIXTH OF THE TOTAL PRESTRESSING FORCE IS APPLIED ECCENTRICALLY ABOUT THE CENTERLINE OF BRIDGE.
6. THE MAXIMUM OUTSIDE DIAMETER OF THE DUCT SHALL BE ??? INCHES. THE AREA OF THE DUCT SHALL BE AT LEAST 2.5 TIMES THE NET AREA OF THE PRESTRESSING STEEL IN THE DUCT.
7. ALL TENDONS SHALL BE STRESSED FROM PIER ??.

Trapezoidal Tub S-I-P Deck Panel Spliced Girder - Details 1 of 5

Figure 5-A-206




TYPICAL END ELEVATION AT END DIAPHRAGMS


TYPICAL END ELEVATION AT CLOSURE PLACEMENT

PRE-TENSIONING NOTES:

1. PLAN LENGTH SHALL BE INCREASED AS NECESSARY TO COMPENSATE FOR SHORTENING DUE TO PRESTRESS AND SHRINKAGE.
2. ALL STRAND FOR PRETENSIONING SHALL BE ??? DIAMETER LOW RELAXATION STRANDS (AASHTO M203, GRADE 270).
3. FOR END TYPES A, C AND D, CUT ALL STRANDS FLUSH WITH THE GIRDER ENDS AND PAINT WITH AN APPROVED EPOXY RESIN, EXCEPT FOR EXTENDED STRANDS AS SHOWN. FOR END TYPES B AND E CUT ALL STRANDS 1" BELOW CONCRETE SURFACE AND GROUT WITH AN APPROVED EPOXY GROUT.
4. EXTENDED STRANDS AND BARS ARE PARALLEL TO GIRDER.
5. LIFTING BARS SHALL BE 1 ⅜" DIAMETER HIGH STRENGTH THREADED BARS (AASHTO M275, GRADE 150 MINIMUM). LIFTING HARDWARE THAT CONNECTS TO THREADED BARS SHALL BE DESIGNED AND DETAILED BY THE CONTRACTOR. LIFTING FORCES ON THREAD BARS SHALL BE VERTICAL ONLY AND WITHIN 10 DEGREES OF PERPENDICULAR TO A LINE BETWEEN PICK POINTS. CONTRACTOR SHALL SUBMIT CALCULATIONS FOR APPROVAL BY THE ENGINEER IF LIFTING FORCES ARE TO BE OTHERWISE.
6. EXTRA CAUTION MUST BE EXERCISED IN HANDLING AND PLACING ALL GIRDERS. ALL GIRDERS SHALL BE CHECKED TO ENSURE THAT THEY ARE BRACED ADEQUATELY TO PREVENT TIPPING AND TO CONTROL LATERAL BENDING DURING SHIPPING.
7. THE TOP SURFACE OF THE GIRDER FLANGE SHALL BE ROUGHENED IN ACCORDANCE WITH SECTION 6-02.3(25)H.
8. FORMS FOR BEARING PAD RECESSES SHALL BE CONSTRUCTED AND FASTENED IN SHAPE A MANNER AS NOT TO CAUSE DAMAGE TO THE GIRDER DURING STRAND RELEASE OPERATION.



SECTION A
(ONE WEB SHOWN)



VIEW B


SECTION C


VIEW D

*** 1'-0" FOR BOTTOM FLANGE WIDTH LESS THAN 5'-6"
2'-0" FOR BOTTOM FLANGE WIDTH EQUAL OR GREATER THAN 5'-6"

Trapezoidal Tub S-I-P Deck Panel Spliced Girder - Details 2 of 5

Figure 5-A-207







PLAN

BOTTOM FLANGE SPALL PROTECTION

END TYPE "C" INTERMEDIATE HINGE DIAPHRAGM
AND END TYPE "D" INTEREMEDIATE FIXED DIAPHRAGM




SECTION A



TRANSVERSE REINFORCING AT SKEWED ENDS


ONLY TRANSVERSE REINF. SHOWN



SAWTOOTH DETAILS


SAWTEETH ARE FULL WIDTH - USE SAWTEETH FULL HEIGHT ON END SECTIONS.

***THE NUMBER OF LIFTING BARS SHALL BE BASED ON 54 KIPS PER EACH 1⅜" ø BAR.



TYPICAL END ELEVATION

EXTENDED STRANDS NOT SHOWN.
USE SAWTOOTH KEYS FROM BOTTOM OF BOTTOM FLANGE TO BOTTOM OF LOWEST HARPED STRANDS.




P.C. SECTION

* SMOOTH FINISH ON TOP OF GIRDER


BENDING DIAGRAM

MARK	LOCATION	SIZE	U	W	X	ALL DIMENSIONS ARE OUT TO OUT
G1	STIRRUPS, OUTSIDE WEB	5				* = VARIES FOR SKEWED SPANS
G2	STIRRUPS, INSIDE WEB	5				
G3	LONGITUDINAL BOTTOM FLANGE	4			STR.	
G4	TOP WEB LONGITUDINAL	6			STR.	NOTE: FOR DIMENSION "A", SEE "GIRDER SCHEDULE"
G5	LONGITUDINAL WEB	5			STR.	
G6	WEB TIE	W12				≠ #4 MAY BE SUBSTITUTED FOR W12, FIELD BENDING IS OPTIONAL
G7	WEB	4				
G8	TOP TRANS. TIE	4				




Trapezoidal Tub S-I-P Deck Panel Spliced Girder - Details 3 of 5

Figure 5-A-208



GIRDER ELEVATION ~ MID-SEGMENT

* OMIT HOLES AND PLACE INSERTS ON THE INTERIOR FACE OF EXTERIOR WEB. PLACE HOLES AND INSERTS PARALLEL TO SKEW. INSERTS SHALL BE 1" ø ROCKET/KOHLER, BURKE HI-TENSILE, LANCASTER MALLEABLE OR APPROVED EQUAL.





TYPICAL MID-SEGMENT ELEVATION

Trapezoidal Tub S-I-P Deck Panel Spliced Girder - Details 4 of 5

Figure 5-A-209

| DIMENSION "A" AT ℄ BEARINGS = | | | | BASED ON GIRDER DEFLECTION = "D" AT TIME OF SLAB POUR (120 DAYS) | | | |






SECTION F


NOTE TO DESIGNER

If ground line is less than 2'-0" minimum below the bottom of girder at front face of abutment a curtain wall shall be provided.


TYPICAL END TYPE "A" DIAPHRAGM AT END PIERS




ELEVATION
BUTYL RUBBER @ DIAPHRAGM



PLAN VIEW
BUTYL RUBBER @ VERTICAL JOINTS





END DIAPHRAGM GEOMETRY


SECTIONS THROUGH END DIAPHRAGMS AT END PIERS
SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
ALL LONGITUDINAL DIMENSIONS ARE NORMAL TO SKEW.

NOTE:


1. GIRDERS SHALL BE HELD RIGIDLY IN PLACE WHEN DIAPHRAGMS ARE PLACED.
2. REINFORCING BAR SHALL BE THREADED THROUGH HOLES IN GIRDERS PRIOR TO PLACING OF EXTERIOR GIRDERS. SEE PLANS FOR "TRAFFIC BARRIER" DIMENSIONS AND LOCATION. SEE "GIRDER DETAILS" SHEET FOR DIMENSION "A".
3. END DIAPHRAGM MAY BE CAST ON GRADE. IF SO, THE UPPER LEG OF THE JOINT FILLER SHALL FORM THE BOTTOM FACE FULL WIDTH.
4. JOINT FILLER TYPE 1 SHALL BE USED TO COVER ALL VERTICAL END DIAPHRAGM JOINTS. EITHER JOINT FILLER TYPE 1 OR JOINT FILLER TYPE 2 SHALL BE USED TO COVER ALL HORIZONTAL END DIAPHRAGM JOINTS.


Trapezoidal Tub S-I-P Deck Panel Girder End Diaphragm on Girder Details

Figure 5-A-211





FOR EXTENDED STRAND DETAIL SEE GIRDER SHEET 3.





TEMPORARY SUPPORT DETAIL






ELEVATION


CONSTRUCTION SEQUENCE

1. COLUMN & TEMP. SUPPORT
2. PLACE GIRDER ON TEMPORARY SUPPORT
3. CAST DIAPHRAGM STAGE 1
4. CAST ROADWAY SLAB
5. COMPLETE DIAPHRAGM
6. REMOVE TEMPORARY SUPPORT



Trapezoidal Tub S-I-P Deck Panel Girder - Raised Crossbeam Details


Figure 5-A-212




DETAIL G

NOTE TO DESIGNER:
This detail to be used on bridges with end piers and no wing walls, and located within and west of the Cascade Mountain range.


NOTE:
1. GIRDER STOPS SHALL BE CONSTRUCTED AFTER PLACEMENT OF PRESTRESSED GIRDERS.
2. ELASTOMERIC PADS BETWEEN GIRDER AND GIRDER STOPS SHALL BE PLACED AFTER CONSTRUCTING THE GIRDER STOPS. THE PADS SHALL BE COATED WITH APPROVED CEMENTITIOUS ADHESIVE PRIOR TO INSTALLATION.




GROUT PAD DETAIL



EXPANSION JOINT DETAILS
JOINT AT INTERMEDIATE PIER SHOWN




DETAIL E




DETAIL F

DRILL ½"ø HOLES THROUGH SEAL WITH STANDARD TWIST DRILL MAKING SURE THE TOP MEMBRANE IS NOT DAMAGED. CUT HOLE WITH SHARP LONG BLADE KNIFE.



BEARING PAD
LAMINATED ELASTOMERIC BRIDGE PAD ☐ THICK (☐ SHIMS)
DUROMETER HARDNESS = 60



TOP ANCHOR BOTTOM ANCHOR

ANCHOR DETAIL
A.S.T.M. A-307

Trapezoidal Tub S-I-P Deck Panel Girder - Miscellaneous Diaphragm Details

Figure 5-A-213

Vacant

Figure 5-A-214

Vacant

Figure 5-A-215

Appendix 5-B-1 "A" Dimension for Prestressed Girder Bridges

(For Simple Span or Continuous P.S. Bridges)

Definitions:

S = Span length (ft.)
L = Vertical curve length (ft.)
G = Algebraic diff. in profile tangent grades (%)
R = Horizontal curve radius to girder per next sheet (ft.)
W = Girder top flange width (inches)
m = Deck crown or super slope (ft./ft.)

Note: The following assumes that sag breaks in curb line profiles due to super transitions will occur @ Piers so as not to require any increase "A."

"A" Dimension (At Piers only)

(Slab Thickness + $^3/_4$″) fillet = + (Normally $8^1/_4$″)
① Excess Girder Camber Allowance = + ⊛

Top Flange Width Effect = $W \times \frac{m}{2}$ = +

Horiz. Curve Effect = $\frac{1.5\ S^2 m}{R}$ = +

Vert. Curve Effect = $\frac{1.5\ GS^2}{100L}$ = {+ for Sag Vert. or - for Crown Vert.)

Round "A" to nearest $^1/_4$″ ⟷ Total "A"

(See minimums below) May make shorter span critical.

{ Use "A" = (Slab thickness + $^3/_4$″) + Top Flange Width Effect) Min.
Use "A" = 9″ Min. where Drain Type 5 crosses girder.


The basic attempt is to have the top of girder not higher than $^3/_4$″ below the bottom of slab at the center of the span. This provides that the actual girder camber could exceed the calculated value by $1^3/_4$″ before the top of the girder would start interfering with the slab steel.

① Allowance for the amount the girder camber, at time of slab casting,"D" dimension from Girder Schedule Table.

⊛ Use 2.50 @ preliminary plan stage to determine vertical clearance. Note in left margin of Layout: "A" Dimen. = "X" (not for design).

Use value from deflection program results to determine "A" Dimen. to use for design.

Horizontal Curve Effect:



$$\phi = \frac{5{,}730}{R} \times \frac{S}{400} \times m$$

$$\tan \phi = \frac{5{,}730Sm}{400R} \times 0.01746 \quad \text{(approx.)} \qquad \tan 1°$$

$$H = \frac{573Sm}{4R} \times 0.01746 \times \frac{S}{2} \times 12$$


$$H \frac{1.5 \times S^2}{R} \times m \text{ (inches)} \quad \text{(approx.)}$$


Vertical Curve Effect:

Algebraic difference in profile tangent grades = G (%)

Vertical curve length = L (ft)

Span Length = S (ft)





$$K = \frac{100G}{2L} \qquad a = K \times \frac{S^2}{40{,}000} \times 12 = \frac{G}{} \times \frac{S^2}{400} \times 12$$

$$a = 1.5 \times \frac{G}{100\,L} \times S^2 \text{ (inches)}$$

Check for excess pad at ℄ span

For bridges which are on sharp crowned vertical curves, the pad at ℄ span can become excessive to the point where the girder and diaphragm stirrups (based on the "A" dimension) are too short to bend into the proper position. This is a problem on bridges with spans in excess of 100 feet and a total grade change of 10 percent on a 900-foot vertical curve. The effect of girder cambers which are less than the calculated values tends to add to this error. The "A" dimension @ ℄ centerline span shall not be less than:

"A" ℄ = "A" pier ± Vertical Curve effect + Excess Camber — (D) Screed Camber (C)

A value for "D" of 1 inch less than that shown on the Girder Schedule Table should be used to accommodate the worst case of camber variation.

A correction should be made to the stirrup lengths if the value of A ℄ exceeds A by more than 2 inches.

Preapproved Post-Tensioning Anchorages

The following are the anchorages approved by the Washington State Department of Transportation. The majority of these anchorages have been approved and accepted by WSDOT on the bases of tests done by suppliers for various state and local jurisdictions outside the state of Washington.

VSL Corporation (Owned by DYWIDAG Systems International)		
Anchorage	Type	Maximum Number of Strands
E5-12	Bearing Plate	12 ½-inch strands
E5-19	Bearing Plate	19 ½-inch strands
E5-22	Bearing Plate	22 ½-inch strands
E5-31	Bearing Plate	31 ½-inch strands
E5-37	Bearing Plate	37 ½-inch strands
E6-12	Bearing Plate	12 0.6-inch strands
E6-19	Bearing Plate	19 0.6-inch strands
E6-22	Bearing Plate	22 0.6-inch strands
E6-31	Bearing Plate	22.06-inch strands
EC5-31	Casting With External and Intermediate	31 ½-inch strands
EC5-27	Casting With External and Intermediate	27 ½-inch strands
EC5-19	Casting With External and Intermediate	19 ½-inch strands
EC5-12	Casting With External and Intermediate	12 ½-inch strands
SO6-4	Casting With External Flange (for Bearing)	4 0.6-inch strands used for dock (or slab) post-tensioning
ACS-28.5	Bearing Plate	28 ½-inch strands
ACS-24.5	Bearing Plate	24 ½-inch strands
ACS-22.5	Bearing Plate	22 ½-inch strands
C-22.5	Casting With External and Intermediate	22 ½-inch strands
ES5-12	Single Plane Anchorage	12 ½-inch strands
ES5-19	Single Plane Anchorage	19 ½-inch strands
ES5-31	Single Plane Anchorage	31 ½-inch strands
ES6-7	Single Plane Anchorage	7 0.6 inch strands
ES6-12	Single Plane Anchorage	16 0.6 inch strands
ES6-19	Single Plane Anchorage	19 0.6 inch strands
ES6-22	Single Plane Anchorage	22 0.6 inch strands

AVAR Post-tensioning Systems		
Anchorage	Type	Maximum Number of Strands
SP 12.5	Single Plane System	12 ½-inch strands
SP 19.5	Single Plane System	19 ½-inch strands
SP 27.5	Single Plane System	27 ½-inch strands
SP 37.5	Single Plane System	37 ½-inch strands
MP 12.5	Multiple Plane System	12 ½-inch strands
MP 22.5	Multiple Plane System	22 ½-inch strands
MP 34.5	Multiple Plane System	34 ½-inch strands
C 12.5	Single Plane System	12 ½-inch strands
C 19.5	Single Plane System	19 ½-inch strands
C 27.5	Single Plane System	27 ½-inch strands
DYWIDAG Systems International		
Anchorage	Type	Maximum Number of Strands
MA12-0.5”	Mutiplane Anchorage	12 ½-inch strands
MA 9-.06”	Mutiplane Anchorage	9.6-inch strands
MA 15-.05”	Mutiplane Anchorage	15 ½-inch strands
MA 120-0.6”	Mutiplane Anchorage	12.6-inch strands
MA 20-.05”	Mutiplane Anchorage	20 ½-inch strands
MA 15-.6”	Mutiplane Anchorage	15.6-inch strands
MA 27-0.5”	Mutiplane Anchorage	27 ½-inch strands
MA 19-.06”	Mutiplane Anchorage	19.6-inch strands
MA 37-0.5”	Mutiplane Anchorage	37 ½-inch strands
MA 27-.06”	Mutiplane Anchorage	27.6-inch strands
MA 15-.5”	Mutiplane Anchorage	27 ½-inch strands
MA 15-.5”	Mutiplane Anchorage	27 ½-inch strands
Bar Anchorages 1-inch thread bars through $1\frac{3}{8}$ at fu of 150 ksi only.		

* Total strands include all bottom strands and top strands

** Strands are not developed fully, designer should check capacities and span lengths

Appendix 5-B-3 Existing Bridge Widenings

The following listed bridge widenings are included as aid to the designer. These should not be construed as the only acceptable methods of widening; there is no substitute for the designer's creativity or ingenuity in solving the challenges posed by bridge widenings.

Bridge	SR	Contract No.	Type of Bridge	Unusual Features
NE 8th Street U'Xing	405	9267	Ps. Gir.	Pier replacements
Higgins Slough	536	9353	Flat Slab	
ER17 and AR17 O-Xing	5	9478	Box Girder	Middle and outside widening.
SR 538 O-Xing	5	9548	T-Beam	Unbalanced widening section support at diaphragms until completion of closure pour.
B-N O'Xing	5	9566	Box Girder	Widened with P.S. Girders, X-beams, and diaphragms not in line with existing jacking required to manipulate stresses, added enclusure walls.
Blakeslee Jct. E/W	5	9638	T-Beam and Box Girder	Post-tensioned X-beam, single web.
B-N O'Xing	18	9688	Box Girder	
SR 536		9696	T-Beam	Similar to Contract 9548.
LE Line over Yakima River	90	9806	Box Girder	Pier shaft.
SR 18 O-Xing	90	9823	P.S. Girder	Lightweight concrete.
Hamilton Road O-Xing	5	9894	T-Beam	Precast girder in one span.
Dillenbauch Creek	5		Flat Slab	
Longview Wye SR 432 U-Xing	5		P.S. Girder	Bridge lengthening.
Klickitat River Bridge	142		P.S. Girder	Bridge replacement.
Skagit River Bridge	5		Steel Truss	Rail modification.
B-N O-Xing at Chehalis	5			Replacement of thru steel girder span with stringer span.
Bellevue Access EBCD Widening and Pier 16 Modification	90	3846	Flat Slab and Box Girder	Deep, soft soil. Stradle best replacing single column.
Totem Lake/NE 124th I/C	405	3716	T-Beam	Skew = 55 degrees.
Pacific Avenue I/C	5	3087	Box Girder	Complex parallel skewed structures.
SR 705/SR 5 SB Added Lane	5	3345	Box Girder	Multiple widen structures.
Mercer Slough Bridge 90/43S		3846	CIP Conc. Flat Slab	Tapered widening of flat slab outrigger pier, combined footings.
Spring Street O-Xing No. 5/545SCD		3845	CIP Conc. Box Girder	Tapered widening of box girder with hingers, shafts.
Fishtrap Creek Bridge 546/8		3661	P.C. Units	Widening of existing P.C. Units. Tight constraints on substructure.
Columbia Drive O-Xing 395/16		3379	Steel Girder	Widening/Deck replacement using standard rolled sections.

Bridge	SR	Contract No.	Type of Bridge	Unusual Features
S 74th-72nd St. O-Xing No. 5/426		3207	CIP Haunched Con. Box Girder	Haunched P.C. P.T. Bath Tub girder sections.
Pacific Avenue O-Xing No. 5/332		3087	CIP Conc. Box Girder	Longitudinal joint between new and existing.
Tye River Bridges 2/126 and 2/127		3565	CIP Conc. Tee Beam	Stage construction with crown shift.
SR 20 and BNRR O-Xing No. 5/714		9220	CIP Conc. Tee Beam	Widened with prestressed girders raised crossbeam.
NE 8th St. U'Xing No. 405/43		9267	Prestressed Girders	Pier replacement — widening.
So. 212th St. U'Xing SR 167		3967	Prestressed Girders	Widening constructed as stand alone structure. Widening column designed as strong column for retrofit.
SE 232nd St. SR 18		5801	CIP Conc. Post-tensioned Box	Skew = 50 degree. Longitudinal "link pin" deck joint between new and existing to accommodate new creep.
Obdashian Bridge 2/275		N/A 1999	CIP Post-tensioned Box	Sidewalk widening with pipe struts.

Contract No.	Name	County	Award Date	Span	Width Curb Curb (ft.)	Span/ Depth	Skew Deg.	Remarks
8759	Kalama River Bridge	Cowlitz		40	Varies			6′ sidewalk
	SB		2/70	200	46-53		0	on one side.
				200				
				40				
				40				
	NB		2/70	200	Varies	Varies	0	6′ sidewalk
				200	46.5			on one side.
				40				
				88				
8761	Valley View Road O'xing	Snohomish	2/70	170	38	25.2	0	
				88				
				190				
9102	Columbia River Bridge	Chelan &	7/71	260	74	Varies	0	
	at Olds**	Douglas		190				
				100.5				
				145				
9749	Evergreen Parkway	Thurston		145	26	Varies	47	Hourglass columns.
				114				
				114				
				87.5				
				160				
9840	W Sunset Way Ramp U'xing	King	12/74	159	26	22.9	Curved	
				100			500′R &	
							600′R	
				129				
1193	24F Over MD Line	Clark	8/78	201	26	Varies	0	
				129				
				126				
3794	Sen. Sam C. Guess Memorial		5/90	182	77	Varies	12	Replaced arch, built
	(Division St. 2/644)			126				in two stages.

**Middle 3 spans of 7-span bridge are post-tensioned.

Contract No.	Name	County	Award Date	Span	Width Curb Curb (ft.)	Span/ Depth	Skew Deg.	Remarks
8569	Brickyard Road U'xing	King	2/69	137 155	38	22.2	45	
9122	NE 50th Avenue U'xing	Clark	7/71	124 124	44	24.8	12	
9122	NE 69th Avenue U'xing	Clark	7/71	130 130	84	23.6	0	
9289	SE 232nd Street U'xing	King	3/72	141 133	55	23.5	51	
9448	NE 18th Street U'xing	Clark	1/73	138 138	44	22.8	17	6' sidewalk on each side.
9737	Mill Plain Road I/C U'xing	Clark	5/74	167 172	84	22.2	8	5' sidewalk on each side.
0862	East Zillah I/C U'xing	Yakima	10/77	178 158	40	23.0	44	
0862	Hudson Road U'xing	Yakima	10/77	151 151	30	22.6	37	
1219	Johnson Road U'xing	Yakima & Benton	8/78	156 161	34	22.7	45	
1366	Donald Road U'xing	Yakima	12/78	142 155	55	23.8	45	
1764	148th Avenue NE U'xing	King	12/79	168 157	60	21.9	41	
1788	Gap Road U'xing	Yakima	1/80	131 131	30	22.1	37	

Contract No.	Name	County	Award Date	Span	Width Curb Curb (ft.)	Span/ Depth	Skew Deg.	Remarks
2156	14-H Line U'xing	Clark	11/81	114 114	60	22.8	0	
2156	14-D Line U'xing (North)	Clark	11/81	196 196	26	21.8	Curved 600'R	
2217	SR 12 U'xing	Benton	2/82	147 147	55	23.3	0	
2217	Keene Road U'xing	Benton	2/82	150 150	34	21.4	Curved 11,459'R	25' counterweighted cantilever spans at each end. Transv. P.T.
2207	G Line U'xing	Benton	4/82	162.4 180.6	Varies 78.6-84.6	20.5	0	30' counterweighted cantilever spans at each end. Transv. P.T.
2207	N-S Line U'xing	Benton	4/82	155 155	38	22.1	0	
2207	SR 240 Connection U'xing (R-Line)	Benton	4/82	163.5 163.5	72	20.4	0	25' counterweighted cantilever spans at each end. Transv. P.T.
2236	Road 68 I/C U'xing	Franklin	4/82	191 191	64	23.2	35	
2236	Road 100 I/C U'xing	Franklin	4/82	183 167	55	21.5	15	
2236	SR 14 I/C U'xing (Eastbound)	Franklin	4/82	170 156	26	22.4	Curved 1600'R	
2236	SR 14 I/C U'xing (Westbound)	Franklin	4/82	159 148	38	21.8	Curved 1500'R	

Contract No.	Name	County	Award Date	Span	Width Curb Curb (ft.)	Span/ Depth	Skew Deg.	Remarks
8759	Kalama River Bridge	Cowlitz		40	Varies			6′ sidewalk
	SB		2/70	200	46-53		0	on one side.
				200				
				40				
				40				
	NB		2/70	200	Varies	Varies	0	6′ sidewalk
				200	46.5			on one side.
				40				
				88				
8761	Valley View Road O'xing	Snohomish	2/70	170	38	25.2	0	
				88				
				190				
9102	Columbia River Bridge	Chelan &	7/71	260	74	Varies	0	
	at Olds**	Douglas		190				
				100.5				
				145				
9749	Evergreen Parkway	Thurston		145	26	Varies	47	Hourglass columns.
				114				
				114				
				87.5				
				160				
9840	W Sunset Way Ramp U'xing	King	12/74	159	26	22.9	Curved	
				100			500′R &	
							600′R	
				129				
1193	24F Over MD Line	Clark	8/78	201	26	Varies	0	
				129				
				126				
3794	Sen. Sam C. Guess Memorial		5/90	182	77	Varies	12	Replaced arch, built
	(Division St. 2/644)			126				in two stages.

**Middle 3 spans of 7-span bridge are post-tensioned.

Contract No.	Name	County	Award Date	Span	Width Curb Curb (ft.)	Span/ Depth	Skew Deg.	Remarks
1439	SR 516 O'xing	King	3/79	63.5 133 63.5	42	24.2	40	
1580	Ahtanum Creek O'xing SB	Yakima	8/79	167 5@172 167	26	25.1	Curved 1200'R	
	NB		8/79	137 6@172 166	38	25.1	Curved 1200'R	
1950	Yakima River Bridges North Bridge	Benton	10/80	140+ 161 161 215 147	Varies 48'-100'	Varies	Curved 6000'R	Transverse post-tentioning.
	South Bridge			140+ 161 161 215 147	38	Varies	Curved 5900'R	Transverse post-tensioning. 10' bicycle and pedestrian path on one side.
2156	14-I Line	Clark	11/81	163 145 82	38	22.2	Curved 600'R	
2156	14 D Line (South)	Clark	11/81	128 171 128	26	24.4	Curved 625'R	
2207	GE Line Over G Line	Benton	4/82	90 188 90	38	23.5	Curved 1400'R	

Contract No.	Name	County	Award Date	Span	Width Curb Curb (ft.)	Span/ Depth	Skew Deg.	Remarks
2207	RA Line Over ER Line	Benton	4/82	47 104 47	55	17.3	20	Transverse post-tentioning.
2245	Pearl Street O'xing	Pierce	4/82	49 159 49	54	22.7	Curved 1400'R	
2245	6th Avenue O'xing	Pierce	4/82	43 125 43	Varies 87.4-102	22.7	Curved 1400'R & 400'R	
2327	Spokane River Bridge Stage 1	Spokane	6/82	175 255 175	76	Varies	0	Transverse post-tentioning.
***	Green River Bridge	King		118 150 99	74	Varies	22	
3794	Sen. Sam C. Guess Memorial (Division St. 2/644)		5/90	126 182 126	77	Varies (depth 5.5 to 8.5 at piers)	12	Replaced arch, built in two stages.

***Not yet to contract.

Design Example 1 Prestressed Girder Design

Prestressed Girder Design (LRFD)

girder := "interior"

Design Criteria

Loading: HL-93

Concrete:

prestressed girder, $f'_{ci} := 7.5 \cdot ksi$

$f'_c := 8.5 \cdot ksi$ (f'ci + 1 ksi)

slab, $f'_{cs} := 4 \cdot ksi$

Reinforcing Steel: (§5.4.3)

AASHTO M-31, Grade 60, $f_y := 60 \cdot ksi$

$E_s := 29000 \cdot ksi$

Prestressing Steel:

AASHTO M-203, uncoated 0.6"ϕ, 7 wire, low-relaxation strands (§5.4.4.1)

$f_{pu} := 270 \cdot ksi$

$f_{py} := 0.90 \cdot f_{pu}$ $f_{py} = 243\ ksi$

$E_p := 28500 \cdot ksi$

Nominal strand diameter, $d_b := 0.6 \cdot in$

$A_p := 0.217 \cdot in^2$

Design Method: LRFD

1. Structure

Simple span design

Bridge width, $BW := 38 \cdot ft$ curb to curb

Girder spacing, $S := 8 \cdot ft$

Number of girder lines, $N_b := 5$

Skew angle, $\theta_{sk} := 40.37 \cdot deg$

Design span, CL of brg. to CL of brg., $L := 131.75 \cdot ft$

Girder length (see girder schedule), $GL := 133.07 \cdot ft$

Distance from end of girder to CL Brg. (see girder schedule), $P2 := \frac{3 \cdot in}{\cos(\theta_{sk})}$

Curb width on deck, $cw := 10.5 \cdot in$

Deck overhang (from CL of exterior girder to end of deck, see slab design),

$$overhang := \frac{BW - (N_b - 1) \cdot S}{2} + cw \qquad overhang = 3.875\,ft$$

Prestressing,

harping strands $N_h := 16$

straight strands $N_s := 26$

temporary strands $N_t := 2$

2. Live Load

Loading : HL-93, consisted of a combination of the (§3.6.1.2.1)

- Design truck (HS20) or design tandem (2-25 kip axles @ 4'-0" apart), and
- Design lane load (no dynamic load allowance) $w_{lane} := 0.64 \cdot \frac{kip}{ft}$

No. of design lanes (§3.6.1.1.1)

$$N_L := \begin{cases} floor\left(\frac{BW}{12 \cdot ft}\right) & \text{if } BW > 24 \cdot ft \\ 2 & \text{if } 24 \cdot ft \geq BW \geq 20 \cdot ft \\ 1 & \text{otherwise} \end{cases} \qquad N_L = 3$$

3. Concrete Properties

3.1 Precast Prestressed Girder

$w_c := 0.160 \cdot kcf$

$$E_c := 33000 \cdot \left(\frac{w_c}{kcf}\right)^{1.5} \cdot \sqrt{\frac{f'_c}{ksi}} \cdot ksi \qquad E_c = 6157\,ksi \qquad (§5.4.2.4)$$

$$E_{ci} := 33000 \cdot \left(\frac{w_c}{kcf}\right)^{1.5} \cdot \sqrt{\frac{f'_{ci}}{ksi}} \cdot ksi \qquad E_{ci} = 5784\,ksi$$

$$f_r := 0.24 \cdot \sqrt{\frac{f'_c}{ksi}} \cdot ksi \qquad f_r = 0.7\,ksi \qquad (§5.4.2.6)$$

4 Concrete Deck Slab Requirement

4.1 Determination of slab thickness and effective width

use slab depth (see slab design)

for design, $t_{s1} := 7.0 \cdot in$

for D.L. calculation, $t_{s2} := 7.5 \cdot in$

5. Computation of Section Properties

5.1 Stiffness Assumptions
Dead loads to non-composite section.
Live load and S.I.D.L. to composite section.

5.2 Prestressed Girder Section Properties
W74G Washington standard prestressed girder

$d_g := 73.5 \cdot in$ $A_g := 747.7 \cdot in^2$ $I_g := 547384 \cdot in^4$ $Y_{bg} := 38.02 \cdot in$ $b_w := 6 \cdot in$

$Y_{tg} := d_g - Y_{bg}$ $S_{tg} := \frac{I_g}{Y_{tg}}$ $S_{bg} := \frac{I_g}{Y_{bg}}$ $b_f := 43 \cdot in$ (top flange width)

$Y_{tg} = 35.48\,in$ $S_{tg} = 15428\,in^3$ $S_{bg} = 14397\,in^3$

"A" dimension (from top of slab to top of girder) (BDM 6.1-A1-1), set $A := 11.25 \cdot in$

Optional criteria for span-to depth ratio (§2.5.2.6.3) - for continuous prestressed girder, the min. depth (including deck) is $0.040 \cdot L = 5.27\,ft$ **OK**

5.3 Composite Section Properties (§4.6.2.6)

Assume effective span (for simple span analysis), $L_e := L$

Let $tem := \max\left(\left(b_w \quad \frac{1}{2} \cdot b_f\right)\right)$

The effective flange width b shall be taken as the least of

$b_i := \min\left(\begin{pmatrix} \frac{1}{4}\cdot L_e \\ 12\cdot t_{s1} + tem \\ S \end{pmatrix}\right)$ $b_i = 96\,in$

$b = 8\,ft$

$$b := \begin{cases} b_i & \text{if girder = "interior"} \\ \frac{b_i}{2} + \min\left(\begin{pmatrix} \frac{1}{8}\cdot L_e \\ 6\cdot t_{s1} + \frac{tem}{2} \\ overhang \end{pmatrix}\right) & \text{if girder = "exterior"} \end{cases}$$

modular ratio, $n := \sqrt{\frac{f'_c}{f'_{cs}}}$ $n = 1.458$

$A_{slab} := \frac{b}{n}\cdot t_{s1}$ $Y_{bs} := d_g + \frac{t_{s1}}{2}$ $AY_{bs} := A_{slab}\cdot Y_{bs}$

	Area	Y_b	$A\cdot Y_b$
slab	$A_{slab} = 461\,in^2$	$Y_{bs} = 77\,in$	$A_{slab}\cdot Y_{bs} = 35496\,in^3$
girder	$A_g = 747.7\,in^2$	$Y_{bg} = 38.02\,in$	$A_g\cdot Y_{bg} = 28428\,in^3$

$Y_b := \frac{A_{slab}\cdot Y_{bs} + A_g\cdot Y_{bg}}{A_{slab} + A_g}$ $Y_b = 52.89\,in$ @ bottom of girder

$Y_t := d_g - Y_b$ $Y_t = 20.61\,in$ @ top of girder

$Y_{ts} := t_{s1} + Y_t$ $Y_{ts} = 27.61\,in$ @ top of slab

$I_{slabc} := A_{slab}\cdot\left(Y_{ts} - \frac{t_{s1}}{2}\right)^2 + \frac{\left(\frac{b}{n}\right)\cdot t_{s1}^3}{12}$ $I_{slabc} = 269922\,in^4$

$I_{gc} := A_g\cdot\left(Y_b - Y_{bg}\right)^2 + I_g$ $I_{gc} = 712642\,in^4$

$I_c := I_{slabc} + I_{gc}$ $I_c = 982564\,in^4$

Section modulous of the composite section

$S_b := \frac{I_c}{Y_b}$ $S_b = 18579\,in^3$ @ bottom of girder

$S_t := \frac{I_c}{Y_t}$ $S_t = 47667\,in^3$ @ top of girder

$S_{ts} := \frac{n\cdot I_c}{Y_{ts}}$ $S_{ts} = 51871\,in^3$ @ top of slab (modified due to modular ratio)

6 Limit States

6.1 Service Limit States

Limit states relating to stress, deformation, and crack width under regular service conditions.

6.2 Load Factors and Combinations (§3.4.1)

Service I - Load combination relating to the normal operational use of the bridge. Compression in prestressed components is investigated using this load combination.

1.0 DC + 1.0 (LL+IM)

Service III - Load combination relating only to tension in prestressed concrete structures with the objective of crack control.

1.0 DC + 0.8 (LL+IM)

Force effects due to temperature, shrinkage and creep, because of the free movement at end piers, are considered to be zero.

Force effects due to temperature gradient, wind, friction at bearings, and settlement are ignored.

7 Vehicular Live Load

7.1 Design Live Load (§3.6.1.2.2)

AASHTO HS20-44

$M_{hs20}(L) = 2094\,kip\cdot ft$ per lane

Tandem does not control.

AASHTO Lane Load

$M_{lane} := w_{lane}\cdot\frac{L^2}{8}$ $M_{lane} = 1389\,kip\cdot ft$

7.2 Dynamic Load Allowance, IM (§3.6.2)

The dynamic load allowance shall not applied to pedestrian loads or to the design lane load.

All other components (including girder)

Fatigue and Fracture limit state IM = 15%
All other limit states

$IM := 33\cdot\%$

$M_{LL} := M_{hs20}(L)\cdot(1 + IM) + M_{lane}$ $M_{LL} = 4174\,kip\cdot ft$

7.3 Distribution of Live Load

7.3.1 D.F. for Moment (interior girder)

Range of applicability (LRFD Table 4.6.2.2.2b-1), case k

Width of deck is constant (§4.6.2.2.1)

Curvature in plan is less than the limit specified in §4.6.1.2

$\text{if}(3.5\cdot\text{ft} \le S \le 16.0\cdot\text{ft}, \text{"OK"}, \text{"NG"}) = \text{"OK"}$

$\text{if}\left(4.5\cdot\text{in} \le t_{s1} \le 12.0\cdot\text{in}, \text{"OK"}, \text{"NG"}\right) = \text{"OK"}$

$\text{if}(20\cdot\text{ft} \le L \le 240\cdot\text{ft}, \text{"OK"}, \text{"NG"}) = \text{"OK"}$

$\text{if}\left(N_b \ge 4, \text{"OK"}, \text{"NG"}\right) = \text{"OK"}$

The multiple presence factors shall not be applied except for exterior girders where special requirement applied (§3.6.1.1.2 & 4.6.2.2.2d).

e_g, distance between the centers of gravity of the basic beam and deck,

$e_g := Y_{bs} - Y_{bg}$ $\quad e_g = 39\,\text{in}$

$K_g := n\cdot\left(I_g + A_g\cdot e_g^{\,2}\right)$ $\quad K_g = 2.45\times 10^6\,\text{in}^4$ (LRFD Eq. 4.6.2.2.1-1)

$\text{if}\left(10^4\,\text{in}^4 \le K_g \le 7\cdot 10^6\,\text{in}^4, \text{"OK"}, \text{"NG"}\right) = \text{"OK"}$

D.F. for moment (interior girder, two or more design lanes loaded governs by inspection):

$$DF_i := 0.075 + \left(\frac{S}{9.5\cdot\text{ft}}\right)^{0.6}\cdot\left(\frac{S}{L}\right)^{0.2}\cdot\left(\frac{K_g}{L\cdot t_{s1}^{\,3}}\right)^{0.1} \qquad DF_i = 0.674$$

7.3.2 D.F. for moment (exterior girder)

Range of applicability (LRFD Table 4.6.2.2.2d-1), case k

$\text{if}(-1.0\cdot\text{ft} \le \text{overhang} - cw \le 5.5\cdot\text{ft}, \text{"OK"}, \text{"NG"}) = \text{"OK"}$ $\quad \text{overhang} - cw = 3\,\text{ft}$

$\text{if}\left(N_b > 3, \text{"OK"}, \text{"NG"}\right) = \text{"OK"}$

$$ee := \max\left(\begin{pmatrix} 0.77 + \dfrac{\text{overhang} - cw}{9.1\cdot\text{ft}} \\ 1.0 \end{pmatrix}\right) \qquad ee = 1.1$$

D.F. for moment (exterior girder)

$DF_e := ee\cdot DF_i$ $\quad DF_e = 0.741$ $\quad$ lever rule check (§4.6.2.2.2d) (see hand calculation) $\quad$ set $\quad DF_e := DF_e$

7.3.3 Skewed Bridges (§4.6.2.2.2e)

Applied when the difference between skew angles of two adjacent lines of supports does not exceed 10 deg.

$\text{if}\left(30\cdot\text{deg} \le \theta_{sk} \le 60\cdot\text{deg}, \text{"OK"}, \text{"NG"}\right) = \text{"OK"}$

$\text{if}(3.5\cdot\text{ft} \le S \le 16.0\cdot\text{ft}, \text{"OK"}, \text{"NG"}) = \text{"OK"}$

$\text{if}(20\cdot\text{ft} \le L \le 240\cdot\text{ft}, \text{"OK"}, \text{"NG"}) = \text{"OK"}$

$\text{if}(N_b \ge 4, \text{"OK"}, \text{"NG"}) = \text{"OK"}$

$$c_1 := \begin{cases} 0.0 & \text{if } \theta_{sk} < 30\cdot\text{deg} \\ 0.25\cdot\left(\frac{K_g}{L\cdot t_{s1}^{\,3}}\right)^{0.25}\cdot\left(\frac{S}{L}\right)^{0.5} & \text{otherwise} \end{cases} \qquad SK := \begin{cases} 1 - c_1\cdot(\tan(60\cdot\text{deg}))^{1.5} & \text{if } \theta_{sk} > 60\cdot\text{deg} \\ 1 - c_1\cdot\left(\tan\left(\theta_{sk}\right)\right)^{1.5} & \text{otherwise} \end{cases}$$

$c_1 = 0.09$ $\qquad SK = 0.93$

Reduced D.F. for moment

$$DF := \begin{cases} SK\cdot DF_i & \text{if girder = "interior"} \\ \left(SK\cdot DF_e\right) & \text{if girder = "exterior"} \end{cases} \qquad DF = 0.627$$

8 Computation of Stresses

8.1 Stresses due to Weight of Girder

$w_g := A_g\cdot w_c$ $\qquad w_g = 0.831\,\frac{\text{kip}}{\text{ft}}$

$M_g := w_g\cdot\frac{L^2}{8}$ $\qquad M_g = 1803\,\text{kip}\cdot\text{ft}$

$f_{tg} := \frac{-M_g}{S_{tg}}$ $\qquad f_{tg} = -1.4\,\text{ksi}$ $\qquad$ @ top of girder

$f_{bg} := \frac{M_g}{S_{bg}}$ $\qquad f_{bg} = 1.5\,\text{ksi}$ $\qquad$ @ bottom of girder

8.2 Stress due to Weight of Slab and Pad

$$w_s := \begin{cases} t_{s2}\cdot(S)\cdot w_c & \text{if girder = "interior"} \\ \left[t_{s2}\cdot\left(\frac{S}{2} + \text{overhang}\right)\cdot w_c\right] & \text{if girder = "exterior"} \end{cases} \qquad w_s = 0.8\,\frac{\text{kip}}{\text{ft}}$$

The depth of slab pad is fillet depth at the center line of span,

$w_{pu} := \left(A - t_{s2}\right)\cdot b_f\cdot w_c$ $\qquad w_{pu} = 0.18\,\frac{\text{kip}}{\text{ft}}$ $\qquad$ assume uniform distribution

$w_{spu} := w_s + w_{pu}$ $\qquad w_{spu} = 0.98\,\frac{\text{kip}}{\text{ft}}$

$M_{sp}(x) := w_{spu}\cdot\frac{L}{2}\cdot x - w_{spu}\cdot\frac{x^2}{2}$ $\qquad M_{sp}\left(\frac{L}{2}\right) = 2125\,\text{kip}\cdot\text{ft}$

$$f_{ts} := \frac{-M_{sp}\left(\frac{L}{2}\right)}{S_{tg}} \qquad f_{ts} = -1.65\,\text{ksi} \qquad @ \text{ at top of girder}$$

$$f_{bs} := \frac{M_{sp}\left(\frac{L}{2}\right)}{S_{bg}} \qquad f_{bs} = 1.77\,\text{ksi} \qquad @ \text{ bottom of girder}$$

8.3 Stresses due to Weight of Diaphragm

Intermediate diaphragms are not required (§5.13.2.2) for straight girders; but BDM 6.2-A5 requires intermediate diaphragms **@ 1/4 point of span for span over 120 ft.**

Number of diaphragms, $n_{diaph} := 3$

Diaphragm section (BDM 6.3-A1), $intd := 3.625\text{ft}\cdot 8\cdot\text{in}$

$$P := \begin{cases} intd\cdot\left(\frac{S - b_w}{\cos(\theta_{sk})}\right)\cdot w_c & \text{if girder = "interior"} \\ \frac{intd}{2}\cdot\left(\frac{S - b_w}{\cos(\theta_{sk})}\right)\cdot w_c & \text{if girder = "exterior"} \end{cases} \qquad P = 3.8\,\text{kip}$$

$$M_d := \begin{cases} P\cdot[\,L - (0.3 + 0.1)L\,] & \text{if } n_{diaph} = 4 \\ P\cdot\left(\frac{1.5\cdot L}{2} - \frac{L}{4}\right) & \text{if } n_{diaph} = 3 \\ P\cdot\left(\frac{L}{2} - \frac{L}{6}\right) & \text{if } n_{diaph} = 2 \\ \frac{P}{2}\cdot\left(\frac{L}{2}\right) & \text{if } n_{diaph} = 1 \\ 0\cdot\text{kip}\cdot\text{ft} & \text{otherwise} \end{cases} \qquad M_d = 250.7\,\text{kip}\cdot\text{ft}$$

$$f_{td} := \frac{-M_d}{S_{tg}} \qquad f_{td} = -0.2\,\text{ksi} \qquad @ \text{ top of girder}$$

$$f_{bd} := \frac{M_d}{S_{bg}} \qquad f_{bd} = 0.21\,\text{ksi} \qquad @ \text{ bottom of girder}$$

8.4 Concrete Stresses due to S.I.D.L. (Applied to Composite Section)

Weight of one traffic barrier is $tb := 0.47\cdot\frac{\text{kip}}{\text{ft}}$

Weight of one traffic barrier is distributed over min. of $\frac{N_b}{2} = 2.5$ girders or 3 girders.

$$w_b := \frac{tb}{\min\left(\left(N_b \cdot 0.5 \quad 3\right)\right)} \qquad w_b = 0.188\,\frac{kip}{ft}$$

$$M_b := w_b \cdot \frac{L^2}{8} \qquad M_b = 407.9\,kip \cdot ft$$

$$f_{tsb} := \frac{-M_b}{S_{ts}} \qquad f_{tsb} = -0.09\,ksi \qquad @\ \text{top of slab}$$

$$f_{tb} := \frac{-M_b}{S_t} \qquad f_{tb} = -0.1\,ksi \qquad @\ \text{top of girder}$$

$$f_{bb} := \frac{M_b}{S_b} \qquad f_{bb} = 0.26\,ksi \qquad @\ \text{bottom of girder}$$

8.5 Concrete Stress due to Live Load (Applied to Composite Section)

$$M_L := M_{LL} \cdot DF \qquad M_L = 2615\,kip \cdot ft$$

Service I

$$f_{tsL} := \frac{-M_L}{S_{ts}} \qquad f_{tsL} = -0.61\,ksi \qquad @\ \text{top of slab}$$

$$f_{tL} := \frac{-M_L}{S_t} \qquad f_{tL} = -0.66\,ksi \qquad @\ \text{top of girder}$$

Service III

$$f_{bL} := \frac{0.8 \cdot M_L}{S_b} \qquad f_{bL} = 1.35\,ksi \qquad @\ \text{bottom of girder}$$

8.6 Summary of Stresses at Mid-span

	@ top of slab	*@ top of girder*	*@ bot. of girder*
girder		$f_{tg} = -1.4\,ksi$	$f_{bg} = 1.5\,ksi$
slab+pad		$f_{ts} = -1.65\,ksi$	$f_{bs} = 1.77\,ksi$
diaphragm		$f_{td} = -0.2\,ksi$	$f_{bd} = 0.21\,ksi$
s.i.d.l.	$f_{tsb} = -0.09\,ksi$	$f_{tb} = -0.1\,ksi$	$f_{bb} = 0.26\,ksi$
LL+IM (Service I)	$f_{tsL} = -0.61\,ksi$	$f_{tL} = -0.66\,ksi$	

LL+IM (Service III) $f_{bL} = 1.35\,ksi$

Service I - 1.0 DC +1.0 (LL+IM)

$f_{tgI} := f_{tg} + f_{ts} + f_{td} + f_{tb} + f_{tL}$ $f_{tgI} = -4.01\,ksi$

Service III - 1.0 DC +0.8 (LL+IM)

$f_{bgIII} := f_{bg} + f_{bs} + f_{bd} + f_{bb} + f_{bL}$ $f_{bgIII} = 5.1\,ksi$

9 Determination of Prestressing Forces (§5.9)

9.1 Stress Limits for Prestressing Strands

$f_{pu} = 270\,ksi$ (LRFD Table 5.4.4.1-1)

$f_{py} = 243\,ksi$

$f_{pe} := 0.80 \cdot f_{py}$ $f_{pe} = 194.4\,ksi$ @ service limit state after all losses (LRFD Table 5.9.3-1)

Losses due to steel relaxation at transfer (§5.9.5.4.4b)

Curing time for concrete to attain f'ci is approximately 12 hours: set $t := 1.0$ day

$f_{pj} := 0.75 \cdot f_{pu}$ $f_{pj} = 202.5\,ksi$ immediately prior to transfer+steel relax. (LRFD Table 5.9.3-1)

$$\Delta f_{pRl} := \frac{\log(24.0 \cdot t)}{40.0} \cdot \left(\frac{f_{pj}}{f_{py}} - 0.55 \right) \cdot f_{pj} \qquad \Delta f_{pRl} = 1.98\,ksi$$

9.2 Allowable Concrete Stresses at Service Limit State

9.2.1 Compressive Stresses Limits After All Losses (§5.9.4.2.1)

Using Service I load combination

$-0.45 \cdot f'_c = -3.83\,ksi$	due to permanent loads
$-0.60 \cdot f'_c = -5.1\,ksi$	due to permanent and transient loads and during shipping and handling
$-0.40 \cdot f'_c = -3.4\,ksi$	due to live loads plus one-half the sum of effective prestress and permanent loads

9.2.2 Tensile Stress Limits (§5.9.4.2.2)

For the service load combinations which involves traffic loading, tension stress in members with bonded prestressing strands should be investigated using Service III load combination.

Tension in precompressed tensile zone assuming uncracked section

$0.190\cdot\sqrt{\frac{f'_c}{ksi}}\cdot ksi = 0.55\,ksi$ OR $0.0948\cdot\sqrt{\frac{f'_c}{ksi}}\cdot ksi = 0.28\,ksi$ (for severe corrosive conditions)

$0\cdot ksi$ WSDOT design practice

9.3 Loss of Prestress (§5.9.5)

$\Delta f_{pT} = \Delta f_{pES} + \Delta f_{pSR} + \Delta f_{pCR} + \Delta f_{pR2}$

Given: $A_p = 0.217\,in^2$

harping strands	$N_h = 16$	jacking force, $f_{pj}\cdot N_h\cdot A_p = 703.08\,kip$
straight strands	$N_s = 26$	jacking force, $f_{pj}\cdot N_s\cdot A_p = 1143\,kip$
temporary strands	$N_t = 2$	jacking force, $f_{pj}\cdot N_t\cdot A_p = 87.88\,kip$

(note: these forces include initial prestress relaxation loss, see §C5.9.5.4.4b)

$N_p := N_s + N_h$ $N_p = 42$

$A_{ps} := A_p\cdot N_p$ $A_{ps} = 9.114\,in^2$

$A_{temp} := A_p\cdot N_t$ $A_{temp} = 0.434\,in^2$

$A_{pstemp} := A_p\cdot(N_t + N_p)$ $A_{pstemp} = 9.548\,in^2$

Find E,

$$E := \begin{cases} 2\cdot in & \text{if } N_s \le 10 \\ 2\cdot in + \frac{(N_s - 10)\cdot(2\cdot in)}{N_s} & \text{if } 10 < N_s \le 18 \\ 2\cdot in + \frac{8\cdot(2\cdot in) + (N_s - 18)\cdot(4\cdot in)}{N_s} & \text{if } 18 < N_s \le 22 \\ 2\cdot in + \frac{(N_s - 14)\cdot(2\cdot in) + 4\cdot(4\cdot in)}{N_s} & \text{if } 22 < N_s \le 24 \\ 2\cdot in + \frac{10\cdot(2\cdot in) + (N_s - 20)\cdot(4\cdot in)}{N_s} & \text{otherwise} \end{cases}$$

$E = 3.69\,in$

Note: Don't use this E value for W42G girders (see std. plans).

$$F_{CL} := \text{if}\left[N_h > 12, \frac{(N_h - 12)\cdot(3\cdot\text{in})}{N_h} + 3\cdot\text{in}, 3\cdot\text{in}\right] \qquad F_{CL} = 3.75\,\text{in}$$

c.g. of straight strands to c.g. of girder, $e_s := Y_{bg} - E$ $\qquad e_s = 34.33\,\text{in}$

c.g. of harped strands to c.g. of girder, $e_h := Y_{bg} - F_{CL}$ $\qquad e_h = 34.27\,\text{in}$

c.g. of temporary strands to c.g. of girder, $e_{temp} := Y_{tg} - 2\cdot\text{in}$ $\qquad e_{temp} = 33.48\,\text{in}$

c.g. of all strands to c.g. of girder, $e_p := \dfrac{e_s\cdot N_s + e_h\cdot N_h}{N_p}$ $\qquad e_p = 34.31\,\text{in}$

$$e_{ptemp} := \frac{e_p\cdot N_p - e_{temp}\cdot N_t}{N_p + N_t} \qquad e_{ptemp} = 31.22\,\text{in}$$

9.3.1 Loss due to Elastic Shortening, Δf_{pES} (§5.9.5.2.3a)

f_{cgp}: concrete stress at c.g. of prestressing tendons due to the prestressing force at transfer and the self-weight of the member at the sections of maximum moment.

Guess values: $p_{st} := 180\cdot\text{ksi}$ prestress tendon stress at transfer (LRFD Table 5.9.3-1)

Given $$\left(f_{pj} - \Delta f_{pRl} - p_{st}\right)\cdot\frac{E_{ci}}{E_p} = -\left[\frac{-\left(p_{st}\cdot A_{pstemp}\right)}{A_g} - \left[\frac{\left(p_{st}\cdot A_{pstemp}\right)\cdot e_{ptemp}^{\,2}}{I_g}\right] + \frac{w_g\cdot(GL)^2}{8}\cdot\frac{e_{ptemp}}{I_g}\right]$$

$p_{st} := \text{Find}(p_{st})$ $\qquad p_{st} = 180.3\,\text{ksi}$

$$f_{cgp} := \frac{-\left[p_{st}\cdot\left(A_{pstemp}\right)\right]}{A_g} - \left[\frac{\left(p_{st}\cdot A_{pstemp}\right)\cdot e_{ptemp}^{\,2}}{I_g}\right] + \frac{w_g\cdot(GL)^2}{8}\cdot\frac{e_{ptemp}}{I_g} \qquad f_{cgp} = -4.11\,\text{ksi}$$

$\Delta f_{pES} := f_{pj} - \Delta f_{pRl} - p_{st}$ $\qquad \Delta f_{pES} = 20.25\,\text{ksi}$

9.3.2 Approximate Lump Sum Estimate of Time Dependent Losses (§5.9.5.3)

Time-dependent losses : $\Delta f_{pSR} + \Delta f_{pCR} + \Delta f_{pR2}$

Criteria: $f'_{ci} > 3.5\cdot\text{ksi} = 1$ **OK**

Normal density concrete
Concrete is either steam or moist cured

Prestressing is by low relaxation strands
Are sited in average exposure condition and temperatures

no partial prestressing $A_s := 0 \cdot in^2$

partial prestress ratio (LRFD Eq. 5.5.4.2.1-2) $PPR := \frac{A_{ps} \cdot f_{py}}{A_{ps} \cdot f_{py} + A_s \cdot f_y}$ $PPR = 1$

Approximate lump sum estimate of time-dependent losses (§5.9.5.3)

$$LOSS_t := 33.0 \cdot \left(1.0 \cdot ksi - 0.15 \cdot \frac{f'_c - 6.0 \cdot ksi}{6.0} \right) + 6.0 \cdot ksi \cdot PPR \qquad LOSS_t = 36.94\,ksi$$

Allowable reduction for I-girders, 6.0 ksi,

$LOSS_t := LOSS_t - 6.0 \cdot ksi$ $LOSS_t = 30.9\,ksi$

(§5.9.5.1) In pretension members where the approximate lump sum estimate of losses is used, Δf_{pR1} should be deducted from the total relaxation.
At transfer, the losses that could be accounted for are elastic shortening and steel relaxation only.

$LOSS_t := LOSS_t - \Delta f_{pRl}$ $LOSS_t = 28.96\,ksi$

9.3.3 Loss due to Creep Δf_{pCR} (§5.9.5.2.3a)

Δf_{cdp}, change in concrete stress at center of gravity of prestressing steel due to permanent loads, except the load acting at the time the prestressing force is applied. Values of Δf_{cdp} should be calculated at the same section or sections for which f_{cgp} is calculated.

c.g. of straight strands to c.g. of composite girder, $e_{sc} := Y_b - E$

$e_{sc} = 49.19\,in$

c.g. of harped strands to c.g. of composite girder, $e_{hc} := Y_b - F_{CL}$

$e_{hc} = 49.14\,in$

c.g. of all strands to c.g. of composite girder, $e_{pc} := \frac{e_{sc} \cdot N_s + e_{hc} \cdot N_h}{N_p}$

$e_{pc} = 49.17\,in$

$$\Delta f_{cdp} := \frac{\left(M_{sp}\left(\frac{L}{2}\right) + M_d \right) \cdot e_p}{I_g} + \frac{M_b \cdot e_{pc}}{I_c} \qquad \Delta f_{cdp} = 2.03\,ksi$$

$\Delta f_{pCR} := 12.0 \cdot (-f_{cgp}) - 7.0 \cdot \Delta f_{cdp}$ $\Delta f_{pCR} = 35.09\,ksi$ (note: > LOSSt sometimes)

Total loss Δf_{pT} (note: BDM assumes a 48 ksi total loss), not including Δf_{pRl},

$\Delta f_{pT} := LOSS_t + \Delta f_{pES}$ $\Delta f_{pT} = 49.21\,ksi$ **use** $\Delta f_{pT} := \Delta f_{pT}$

$f_{pe} := f_{pj} - \Delta f_{pRl} - \Delta f_{pT}$ $f_{pe} = 151.315\,ksi$ (use Modified Rate of Creep method)

$f_{pe} \le 0.80 \cdot f_{py} = 1$ OK, (LRFD Table 5.9.3-1)

$P_e := N_p \cdot A_p \cdot f_{pe}$ $P_e = 1379.1\,kip$

$-\frac{P_e}{A_g} - P_e \cdot \frac{e_p}{S_{bg}} = -5.13\,ksi$

$f_{bgIII} = 5.1\,ksi$

Tension at bottom of girder

$f_{bgIII} + \left(-\frac{P_e}{A_g} - P_e \cdot \frac{e_p}{S_{bg}}\right) = -0.03\,ksi$ < allowable $0.0948 \cdot \sqrt{\frac{f'_c}{ksi}} \cdot ksi = 0.28\,ksi$ **say OK**

$0 \cdot ksi$ (BDM)

10 Stresses at Service Limit State

10.1 Final Stresses at Midspan

Compressive stresses at top of slab

Stresses due to permanent load + prestressing

$f_{tsb} = -0.09\,ksi$ < allowable $-0.45 \cdot f'_{cs} = -1.8\,ksi$ **OK**

Stresses due to permanent and transient loads,

LL+IM (Service I) $f_{tsL} := \frac{-M_L}{S_{ts}}$ $f_{tsL} = -0.61\,ksi$

$f_{tsb} + f_{tsL} = -0.7\,ksi$ < allowable $-0.60 \cdot f'_{cs} = -2.4\,ksi$ **OK**

Stresses due to live load + one-half the sum of effective prestress and permanent loads,

$f_{tsL} + 0.5 \cdot f_{tsb} = -0.65\,ksi$ < allowable $-0.40 \cdot f'_{cs} = -1.6\,ksi$ **OK**

Stresses at top of girder

prestressing, $f_{tp} := -\frac{P_e}{A_g} + P_e \cdot \frac{e_p}{S_{tg}}$ $f_{tp} = 1.22\,ksi$

Stresses due to permanent loads,

$f_{tg} + f_{ts} + f_{td} + f_{tb} + f_{tp} = -2.13\,ksi$ < allowable $-0.45 \cdot f'_c = -3.83\,ksi$ **OK**

Stresses due to permanent and transient loads,

LL+IM (Service I) $f_{tL} := \frac{-M_L}{S_t}$ $f_{tL} = -0.66\,ksi$

$f_{tg} + f_{ts} + f_{td} + f_{tb} + f_{tL} + f_{tp} = -2.79\,ksi$ < allowable $-0.60 \cdot f'_c = -5.1\,ksi$ **OK**

Stresses due to live load + one-half the sum of effective prestress and permanent loads,

$f_{tL} + 0.5 \cdot (f_{tg} + f_{ts} + f_{td} + f_{tb} + f_{tp}) = -1.72\,ksi$ < allowable $-0.40 \cdot f'_c = -3.4\,ksi$ **OK**

10.2 Final Stresses at Harping Point

Harping location from CL of brg., $x_h := 0.4 \cdot GL - P2$ $x_h = 52.9\,ft$

Stresses at top of slab

s.i.d.l., $M_{bh} := w_b \cdot \frac{L}{2} \cdot x_h - w_b \cdot \frac{x_h^2}{2}$ $M_{bh} = 392.09\,kip \cdot ft$

$f_{tsb} := \frac{-M_{bh}}{S_{ts}}$ $f_{tsb} = -0.09\,ksi$

LL+IM (Service I)

$M_{LL} := 4025 \cdot kip \cdot ft$ (see QConBridge output)

$M_{Lh} := M_{LL} \cdot DF$ $M_{Lh} = 2522\,kip \cdot ft$

$f_{tsL} := \frac{-M_{Lh}}{S_{ts}}$ $f_{tsL} = -0.58\,ksi$

Stresses due to permanent loads,

$f_{tsb} = -0.09\,ksi$ < allowable $-0.45 \cdot f'_{cs} = -1.8\,ksi$ **OK**

Stresses due to permanent and transient loads,

$f_{tsb} + f_{tsL} = -0.67\,ksi$ < allowable $-0.60 \cdot f'_{cs} = -2.4\,ksi$ **OK**

Stresses due to live load + one-half of the permanent loads,

$f_{tsL} + 0.5 \cdot f_{tsb} = -0.63\,ksi$ < allowable $-0.40 \cdot f'_{cs} = -1.6\,ksi$ **OK**

Compressive stresses at top of girder

girder, $M_{gh} := w_g \cdot \frac{L}{2} \cdot x_h - w_g \cdot \frac{x_h^2}{2}$ $M_{gh} = 1733\,kip \cdot ft$

$f_{tg} := \frac{-M_{gh}}{S_{tg}}$ $f_{tg} = -1.35\,ksi$

slab+pad, $M_{sp}(x_h) = 2.042\,10^3 \cdot kip \cdot ft$

$f_{ts} := \frac{-M_{sp}(x_h)}{S_{tg}}$ $f_{ts} = -1.59\,ksi$

diaphragm, $M_{dh} := \begin{cases} P \cdot \left[1.5 \cdot x_h - \left(x_h - \frac{L}{4}\right)\right] & \text{if } n_{diaph} = 3 \\ P \cdot \left[x_h - \left(x_h - \frac{L}{3}\right)\right] & \text{if } n_{diaph} = 2 \\ \frac{P}{2} \cdot (x_h) & \text{if } n_{diaph} = 1 \\ 0 \cdot kip \cdot ft & \text{otherwise} \end{cases}$ $M_{dh} = 226.1\,kip \cdot ft$

$f_{td} := \frac{-M_{dh}}{S_{tg}}$ $f_{td} = -0.18\,ksi$

s.i.d.l., $f_{tb} := \frac{-M_{bh}}{S_t}$ $f_{tb} = -0.1\,ksi$

prestressing, $f_{tp} := -\frac{P_e}{A_g} + P_e \cdot \frac{e_p}{S_{tg}}$ $f_{tp} = 1.22\,ksi$

Stresses due to permanent load + prestressing,

$f_{tg} + f_{ts} + f_{td} + f_{tb} + f_{tp} = -1.99\,ksi$ < allowable $-0.45 \cdot f'_c = -3.83\,ksi$ **OK**

Stresses due to permanent and transient loads,

LL+IM (Service I) $f_{tL} := \frac{-M_{Lh}}{S_t}$ $f_{tL} = -0.63\,ksi$

$f_{tg} + f_{ts} + f_{td} + f_{tb} + f_{tp} + f_{tL} = -2.62\,ksi$ < allowable $-0.60 \cdot f'_c = -5.1\,ksi$ **OK**

Stresses due to live load + one-half the sum of effective prestress and permanent loads,

$0.5\cdot\left(f_{tg} + f_{ts} + f_{td} + f_{tb} + f_{tp}\right) + f_{tL} = -1.63\,\text{ksi}$ < allowable $-0.40\cdot f'_c = -3.4\,\text{ksi}$ **OK**

Stresses at bottom of girder

girder, $f_{bg} := \dfrac{M_{gh}}{S_{bg}}$ $f_{bg} = 1.44\,\text{ksi}$

slab+pad, $f_{bs} := \dfrac{M_{sp}(x_h)}{S_{bg}}$ $f_{bs} = 1.7\,\text{ksi}$

diaphragm, $f_{bd} := \dfrac{M_{dh}}{S_{bg}}$ $f_{bd} = 0.19\,\text{ksi}$

s.i.d.l., $f_{bb} := \dfrac{M_{bh}}{S_b}$ $f_{bb} = 0.25\,\text{ksi}$

prestressing, $f_{bp} := \dfrac{-P_e}{A_g} - P_e\cdot\dfrac{e_p}{S_{bg}}$ $f_{bp} = -5.13\,\text{ksi}$

LL+IM (Service III) $f_{bL} := \dfrac{M_{Lh}\cdot 0.8}{S_b}$ $f_{bL} = 1.3\,\text{ksi}$

Stresses due to permanent and transient load + prestressing

Tension at bottom of girder

$f_{bg} + f_{bs} + f_{bd} + f_{bb} + f_{bL} + f_{bp} = -0.24\,\text{ksi}$ < allowable $0.0948\cdot\sqrt{\dfrac{f'_c}{\text{ksi}}}\cdot\text{ksi} = 0.28\,\text{ksi}$ **OK**

$0\cdot\text{ksi}$ (BDM)

11 Stresses at Transfer

(§5.8.2.3) The prestressing force may be assumed to vary linearly from zero at free end of strand to a maximum at the transfer length.

Transfer Length, D,

$D := 60\cdot d_b$ $D = 36\,\text{in}$

11.1 Prestressing Losses at Transfer

Loss due to elastic shortening, (note: BDM assumes a 20 KSI loss at transfer),

$\Delta f_{pES} = 20.2\,\text{ksi}$

Prestress tendon stress at transfer (LRFD Table 5.9.3-1), p_{st},

$p_{st} = 180.27\,ksi$

11.2 Concrete Stress at Transfer at "D" from End of Girder

Assume the girder is supported at the both ends at transfer (per a girder fabricator),

Moment due to weight of girder,

$$M_{gD} := w_g \cdot \frac{GL}{2} \cdot D - \frac{w_g}{2} \cdot D^2 \qquad M_{gD} = 162.1\,kip \cdot ft$$

Prestressing force at transfer,

For straight strands, $P_{sis} := p_{st} \cdot N_s \cdot A_p$ $P_{sis} = 1017\,kip$

For harped strands, $P_{sih} := p_{st} \cdot N_h \cdot A_p$ $P_{sih} = 625.9\,kip$

For temporary strands, $P_{sit} := p_{st} \cdot N_t \cdot A_p$ $P_{sit} = 78.238\,kip$

$$P_{si} := P_{sis} + P_{sih} + p_{st} \cdot N_t \cdot A_p \qquad P_{si} = 1721\,kip$$

Eccentricity for harped strand at "D" from end of girder, e_{Dh},

find distance from the top of girder to the c.g. of the harped strands at the end of girder, F_o,

$$row := floor\left(\frac{N_h}{2}\right) \qquad F_o := 4 \cdot in + \frac{\left[\sum_{i=0}^{row-1} (2 \cdot i \cdot 2 \cdot in)\right] + \left(N_h - 2 \cdot row\right) \cdot (row)\, 2 \cdot in}{N_h}$$

$F_o = 11\,in$ set $F_o := 29.0 \cdot in$

harping rise, $R_h := d_g - F_o - F_{CL}$ $R_h = 40.75\,in$

harped strand slope, $slope_h := \frac{R_h}{x_h + P2}$ $slope_h = 0.064$

check harped strand slope, $if\left(\begin{array}{l} slope_h \le 0.166 \text{ if } d_b = 0.5 \cdot in \\ slope_h \le 0.125 \text{ if } d_b = 0.6 \cdot in \end{array}, "OK", "NG"\right) = "OK"$

holddown force at jacking, P_{hd},

$$P_{hd} := f_{pj} \cdot N_h \cdot A_p \cdot \sin\left(\operatorname{atan}\left(\frac{R_h}{x_h + P2}\right)\right) \qquad P_{hd} = 44.8\,kip \quad \text{(for checking shop drawing)}$$

$$e_{Dh} := \frac{R_h}{(x_h + P2)} \cdot (x_h + P2 - D) + F_{CL} - Y_{bg} \qquad e_{Dh} = 4.18\,in$$

At top of girder,

$$\left(-\frac{M_{gD}}{S_{tg}} - \frac{P_{si}}{A_g}\right) + \frac{P_{sis} \cdot e_s - P_{sih} \cdot e_{Dh} - P_{sit} \cdot e_{temp}}{S_{tg}} = -0.5\,ksi$$

Allowable tension with bonded reinforcement which is sufficient to resist 120% of the tension force in the cracked concrete computed on the basis of an uncracked section (§5.9.4.1.2).

$$0.24 \cdot \sqrt{\frac{f'_{ci}}{ksi}} \cdot ksi = 0.66\,ksi \qquad \textbf{OK}$$

or w/o bonded reinforcement (use),

$$\min\left(\begin{pmatrix} 0.0948 \cdot \sqrt{\frac{f'_{ci}}{ksi}} \cdot ksi \\ 0.200 \cdot ksi \end{pmatrix}\right) = 0.2\,ksi \qquad \textbf{OK}$$

At bottom of girder,

$$\left(\frac{M_{gD}}{S_{bg}} - \frac{P_{si}}{A_g}\right) + \frac{-P_{sis} \cdot e_s + P_{sih} \cdot e_{Dh} + P_{sit} \cdot e_{temp}}{S_{bg}} = -4.23\,ksi$$

$< \text{allowable} \quad -0.60 \cdot f'_{ci} = -4.5\,ksi \qquad \textbf{OK}$

11.3 Concrete Stresses at Transfer At Harping Point

Moment due to weight of girder,

$$M_{gth} := w_g \cdot \frac{GL}{2} \cdot (P2 + x_h) - \frac{w_g}{2} \cdot (P2 + x_h)^2 \qquad M_{gth} = 1.765 \times 10^3\,kip \cdot ft$$

For straight strands,

$P_{sis} = 1.017 \times 10^3\,kip \qquad e_s = 34.33\,in$

For harped strands,

$P_{sih} = 625.908\,kip \qquad e_h = 34.27\,in$

For temporary strands,

$P_{sit} = 78.238\,kip \qquad e_{temp} = 33.48\,in$

At top of girder,

$$\left(-\frac{M_{gth}}{S_{tg}} - \frac{P_{si}}{A_g}\right) + \frac{P_{sis}\cdot e_s + P_{sih}\cdot e_h - P_{sit}\cdot e_{temp}}{S_{tg}} = -0.19\,\text{ksi}$$

Allowable tension with bonded reinforcement which is sufficient to resist 120% of the tension force in the cracked concrete computed on the basis of an uncracked section (§5.9.4.1.2).

$$0.24\cdot\sqrt{\frac{f'_{ci}}{\text{ksi}}}\cdot\text{ksi} = 0.66\,\text{ksi} \qquad \textbf{OK}$$

or w/o bonded reinforcement (use),

$$\min\left(\begin{pmatrix} 0.0948\cdot\sqrt{\frac{f'_{ci}}{\text{ksi}}}\cdot\text{ksi} \\ 0.200\cdot\text{ksi}\end{pmatrix}\right) = 0.2\,\text{ksi} \qquad \textbf{OK}$$

At bottom of girder,

$$\left(\frac{M_{gth}}{S_{bg}} - \frac{P_{si}}{A_g}\right) + \frac{-P_{sis}\cdot e_s - P_{sih}\cdot e_h + P_{sit}\cdot e_{temp}}{S_{bg}} = -4.56\,\text{ksi}$$

$<$ allowable $\quad -0.60\cdot f'_{ci} = -4.5\,\text{ksi}$ **OK**

(Note: f'ci at lifting is more critical at lifting due to shifting of support points into mid-span)

12 Strength Limit State

Resistance factors (§5.5.4.2.1)

$\phi_f := 0.90$ for flexure and tension of reinforced concrete

$\phi_p := 1.00$ for flexure and tension of prestressed concrete

$\phi_v := 0.90$ for shear and torsion of normal weight concrete

Load Modifier

$\eta_D := 1.00$ for non-ductile components and connections (§1.3.3, for conventional design)

$\eta_R := 1.00$ for redundant members (§1.3.4, for conventional level of redundancy)

$\eta_I := 1.00$ for operationally important bridge (§1.3.5, for typical bridges)

$$\eta := \max\left(\begin{pmatrix}\eta_D\cdot\eta_R\cdot\eta_I \\ 0.95\end{pmatrix}\right) \qquad \eta = 1 \qquad (\S1.3.2)$$

12.1 Ultimate Moment Required

Strength I load combination - normal vehicular load without wind (§3.4.1).

The force effects due to temperature shrinkage and creep are ignored.

Load factors (LRFD Table 3.4.1-1):

$\gamma_p := 1.25$ for component and attachments

$\gamma_L := 1.75$ for LL

Flexural moment

Dead load moment,

$M_{DC} := M_g + M_{sp}\left(\frac{L}{2}\right) + M_d + M_b \qquad M_{DC} = 4586\,kip\cdot ft$

Live load moment,

$M_L = 2.615 \times 10^3\,kip\cdot ft$

$M_u := \eta\cdot\left(\gamma_p\cdot M_{DC} + \gamma_L\cdot M_L\right) \qquad M_u = 10309\,kip\cdot ft$

12.2 Flexural Resistance (§5.7.3)

Note: In PGSuper, moment capacity is computed using a non-linear strain-compatibility methodology.

Find stress in prestressing steel at nominal flexural resistance, f_{ps} (§5.7.3.1.1)

$f_{pe} = 151.315\,ksi \qquad 0.5\cdot f_{pu} = 135\,ksi$

$if\left(f_{pe} \geq 0.5\cdot f_{pu}, "OK", "NG"\right) = "OK"$

$k := 2\cdot\left(1.04 - \frac{f_{py}}{f_{pu}}\right) \qquad k = 0.28$ (LRFD Eq. 5.7.3.1.1-2)

$A_s := 0\cdot in^2$

$A'_s := 0\cdot in^2$ (conservatively)

$h_f := t_{s1} \qquad h_f = 7\,in$ (depth of compression flange)

d_p, distance from extreme compression fiber to the centroid of the prestressing tendons,

$d_p := t_{s1} + d_g - \left(Y_{bg} - e_p\right) \qquad d_p = 76.79\,in$

$b = 96\,in$

$b_w = 6\,in$

$$\beta_1 := \text{if}\left[f'_{cs} \le 4\cdot ksi, 0.85, 0.85 - 0.05\cdot\left(\frac{f'_{cs} - 4.0\cdot ksi}{1.0\cdot ksi}\right)\right] \qquad \beta_1 := \begin{cases} \beta_1 & \text{if } \beta_1 \ge 0.65 \\ 0.65 & \text{otherwise} \end{cases}$$

$\beta_1 = 0.85$ (§5.7.2.2)

Assume flanged section,

$$c_f := \frac{A_{ps}\cdot f_{pu} - 0.85\cdot\beta_1\cdot f'_{cs}\cdot(b - b_w)\cdot h_f}{0.85\cdot f'_{cs}\cdot\beta_1\cdot b_w + k\cdot A_{ps}\cdot\frac{f_{pu}}{d_p}} \qquad c_f = 24.33\,in$$

(for flange section, ignore the girder top flange and the modular ratio of the slab and deck concrete for simplicity)

Assume rectangular section,

$$c_r := \frac{A_{ps}\cdot f_{pu}}{0.85\cdot f'_{cs}\cdot\beta_1\cdot b + k\cdot A_{ps}\cdot\frac{f_{pu}}{d_p}} \qquad c_r = 8.59\,in$$

$$c := \begin{cases} c_r & \text{if } 0\cdot in \le c_r \le h_f \\ c_f & \text{otherwise} \end{cases} \qquad c = 24.33\,in$$

Stress in prestressing steel at nominal flexural resistance, f_{ps} (§5.7.3.1.1),

$$f_{ps} := f_{pu}\cdot\left(1 - k\cdot\frac{c}{d_p}\right) \qquad f_{ps} = 246.1\,ksi$$

Flexural Resistance (§5.7.3.2.2 & 5.7.3.2.2),

$$a := \beta_1\cdot c \qquad a = 20.68\,in$$

$$M_n := \text{if}\left[h_f < c, A_{ps}\cdot f_{ps}\cdot\left(d_p - \frac{a}{2}\right) + 0.85\cdot f'_{cs}\cdot(b - b_w)\cdot\beta_1\cdot h_f\cdot\left(\frac{a}{2} - \frac{h_f}{2}\right), A_{ps}\cdot f_{ps}\cdot\left(d_p - \frac{a}{2}\right)\right]$$

$M_n = 13455\,kip\cdot ft$

$M_r := \phi_p\cdot M_n \qquad M_r = 13455\,kip\cdot ft$

$M_u \le M_r = 1$ **OK** where $M_u = 10309\,kip\cdot ft$

13 Limit for Reinforcement

13.1 Maximum Reinforcement (§5.7.3.3.1)

$$d_e := \frac{A_{ps} \cdot f_{ps} \cdot d_p}{A_{ps} \cdot f_{ps}} \qquad d_e = 76.79\,in$$

The maximum amount of prestressed and non-prestressed reinforcement shall be such that

$$if\left(\frac{c}{d_e} \le 0.42, "OK", "NG"\right) = "OK" \qquad \text{where } \frac{c}{d_e} = 0.32$$

The section is not over-reinforced. Over-reinforced reinforced concrete sections shall not be permitted.

13.2 Minimum Reinforcement (§5.7.3.3.2)

AASHTO 9.18.2

Compressive stress in concrete due to effective prestress force (after all losses) at midspan

$$f_{peA} := \frac{P_e}{A_g} + P_e \cdot \frac{e_p}{S_{bg}} \qquad f_{peA} = 5.13\,ksi \qquad \text{(compression)}$$

Non-composite dead load moment at section, M_{dnc},

$$M_{dnc} := M_g + M_{sp}\left(\frac{L}{2}\right) + M_d \qquad M_{dnc} = 4.178 \times 10^3\,kip \cdot ft$$

$$M_{cr} := \left(f_r + f_{peA}\right) \cdot S_b - M_{dnc} \cdot \left(\frac{S_b}{S_{bg}} - 1\right) \qquad 1.2 \cdot M_{cr} = 9376\,kip \cdot ft$$

$M_r \ge 1.2 \cdot M_{cr} = 1$ **OK** where $M_r = 13455\,kip \cdot ft$

If NG, check against 1.33 Mu.

13.3 Development of Prestressing Strand (§5.11.4)

$f_{ps} = 246.05\,ksi$ $f_{pe} = 151.32\,ksi$ $d_b = 0.6\,in$

Pretensioning strand shall be bonded beyond the critical section for development length, L_d,

$$L_d := 1.6 \cdot \left(\frac{f_{ps}}{ksi} - \frac{2}{3} \cdot \frac{f_{pe}}{ksi}\right) \cdot d_b \qquad L_d = 11.61\,ft$$

14 Shear Design & Longitudinal Reinforcement Design

14.1 Shear Design Procedure (§5.8.1.1)

Distance from compression face to centroid of tension reinforcement,

$d := d_e$ $\quad d = 6.399\,ft$

Since $\frac{L}{2} = 65.875\,ft$ > $2 \cdot d = 12.798\,ft$ Use sectional model

14.2 Shear Force Effect (§5.8.3.2)

Compute effective shear depth (§5.8.2.7), d_v,

de and a need to be modified to reflect the critical section location, also at harping point location.

$d_e - \frac{a}{2} = 66.45\,in$

$0.9 \cdot d_e = 69.11\,in$

$0.72 \cdot (d_g + t_{s1}) = 57.96\,in$

$$d_v := \max\left(\begin{bmatrix} d_e - \frac{a}{2} \\ 0.9 \cdot d_e \\ 0.72 \cdot (d_g + t_{s1}) \end{bmatrix}\right) \qquad d_v = 69.11\,in$$

(§5.8.3.2) The location of critical section dc for shear shall be taken as the larger of $0.5 \cdot d_v \cdot \cot(\theta)$ or d_v from the internal face of the support. Since q, the angle of diagonal compressive stress, is not known; therefore use d_v for shear force calculations.

use $d_c := d_v$ for now

Shear at d_c from CL of bearing

Dead load

girder, $V_g := w_g \cdot \left(\frac{L}{2} - d_c\right)$ $\quad V_g = 49.94\,kip$

slab+pad, $V_{sp}(x) := w_{spu} \cdot \left(\frac{L}{2} - x\right)$ $\quad V_{sp}(d_c) = 58.86\,kip$

diaphragm, $V_d := \begin{cases} 1.5 \cdot P & \text{if } n_{diaph} = 3 \\ 1.0 \cdot P & \text{if } n_{diaph} = 2 \\ 0.5 \cdot P & \text{if } n_{diaph} = 1 \\ 0 \cdot kip & \text{otherwise} \end{cases}$ $\quad V_d = 5.71\,kip$

s.i.d.l., $V_b := w_b \cdot \left(\frac{L}{2} - d_c \right)$ $V_b = 11.3\,\text{kip}$

$V_{DC} := V_g + V_{sp}(d_c) + V_d + V_b$ $V_{DC} = 125.82\,\text{kip}$

Live Load Shear

D.F. for Shear (interior girder)

Range of applicability (LRFD Table 4.6.2.2.3a-1), case k

$\text{if}(3.5 \cdot \text{ft} \le S \le 16.0 \cdot \text{ft}, \text{"OK"}, \text{"NG"}) = \text{"OK"}$

$\text{if}(20 \cdot \text{ft} \le L \le 240 \cdot \text{ft}, \text{"OK"}, \text{"NG"}) = \text{"OK"}$

$\text{if}\left(4.5 \cdot \text{in} \le t_{s1} \le 12.0 \cdot \text{in}, \text{"OK"}, \text{"NG"}\right) = \text{"OK"}$

$\text{if}\left(N_b \ge 4, \text{"OK"}, \text{"NG"}\right) = \text{"OK"}$

For two or more design lanes loaded (interior girder):

$DF_{vi} := 0.2 + \frac{S}{12 \cdot \text{ft}} - \left(\frac{S}{35 \cdot \text{ft}} \right)^{2.0}$ $DF_{vi} = 0.814$

D.F. for Shear (exterior girder)

Range of applicability (LRFD Table 4.6.2.2.3b-1), case k,

$\text{if}(-1.0 \cdot \text{ft} \le \text{overhang} - cw \le 5.5 \cdot \text{ft}, \text{"OK"}, \text{"NG"}) = \text{"OK"}$

Correction factor,

$e4 := 0.6 + \frac{\text{overhang} - cw}{10.0 \cdot \text{ft}}$ $e4 = 0.9$

D.F. for shear (exterior girder),

$DF_{ve} := e4 \cdot DF_{vi}$ $DF_{ve} = 0.733$

Correction factor for skewed bridges (Table 4.6.2.2.3c-1)

$\text{if}\left(0 \cdot \text{deg} \le \theta_{sk} \le 60 \cdot \text{deg}, \text{"OK"}, \text{"NG"}\right) = \text{"OK"}$

$\text{if}(3.5 \cdot \text{ft} \le S \le 16.0 \cdot \text{ft}, \text{"OK"}, \text{"NG"}) = \text{"OK"}$

$\text{if}(20 \cdot \text{ft} \le L \le 240 \cdot \text{ft}, \text{"OK"}, \text{"NG"}) = \text{"OK"}$

$\text{if}\left(N_b \ge 4, \text{"OK"}, \text{"NG"}\right) = \text{"OK"}$

$SK_v := 1.0 + 0.20 \cdot \left(\frac{L \cdot t_{s1}^{\,3}}{K_g} \right)^{0.3} \cdot \tan(\theta_{sk})$ $SK_v = 1.108$

Increased D.F. for shear,

$$DF_v := \begin{cases} SK_v \cdot DF_{vi} & \text{if girder = "interior"} \\ \left(SK_v \cdot DF_{ve}\right) & \text{if girder = "exterior"} \end{cases} \qquad DF_v = 0.902$$

L.L. shear at critical section (see QconBridge output), $\frac{d_c}{L} = 0.044$

$V_{LL} := 118.5 \cdot kip$

$V_L := V_{LL} \cdot DF_v \qquad V_L = 106.94\,kip$

Shear force effect,

$V_u := \eta \cdot \left(\gamma_p \cdot V_{DC} + \gamma_L \cdot V_L\right) \qquad V_u = 344.42\,kip$

14.4.3 Determination of β and θ (§5.8.3.4.2)

V_p

a: angle of harped strands inclination

CL of bearing to end of girder, $P2 = 3.94\,in$

$\alpha := \operatorname{atan}\left(\frac{R_h}{x_h + P2}\right) \qquad \alpha = 3.65\,deg$

$P_h := f_{pe} \cdot A_p \cdot N_h \qquad P_h = 525.366\,kip$

$V_p := P_h \cdot \sin(\alpha) \qquad V_p = 33.45\,kip$

f_{po}, stress in prestressing steel when the stress in the surrounding concrete is 0.0,

Within the transfer length, f po shall be increased linearly from zero at the location where the bond commences to its full value at the end of transfer length.

since $d_c + P2 = 73.045\,in$ >= $D = 36\,in$

$f_{po} := 0.7 f_{pu} \qquad f_{po} = 189\,ksi$ (tension)

N_u, external axial forces,

$N_u := 0.0 \cdot kip$

M_u at critical section,

$M_g := w_g \cdot \frac{L}{2} \cdot d_c - w_g \cdot \frac{d_c^2}{2} \qquad M_g = 301.4\,kip \cdot ft$

$M_{sp}(d_c) = 355.2\,kip{\cdot}ft$

$M_d := V_d{\cdot}d_c$ $\quad M_d = 32.9\,kip{\cdot}ft$

$M_b := w_b{\cdot}\frac{L}{2}{\cdot}d_c - w_b{\cdot}\frac{{d_c}^2}{2}$ $\quad M_b = 68.2\,kip{\cdot}ft$

$M_{DC} := M_g + M_{sp}(d_c) + M_d + M_b$ $\quad M_{DC} = 757.709\,kip{\cdot}ft$

$M_{LL} := 759.69{\cdot}kip{\cdot}ft$ (from QconBridge output)

("it is conservative to take Mu as the highest factored moment that will occurred at the section rather than the coincident moment.")

$M_L := M_{LL}{\cdot}DF$ $\quad M_L = 475.99\,kip{\cdot}ft$

M_u, then,

$M_u := \eta{\cdot}(\gamma_p{\cdot}M_{DC} + \gamma_L{\cdot}M_L)$ $\quad M_u = 1780\,kip{\cdot}ft$

$M_u := \max((M_u \quad V_u{\cdot}d_v))$ $\quad M_u = 1983\,kip{\cdot}ft$

A_{ps}: area of prestressing steel on the flexural tension side of the member

$A_{ps} := N_s{\cdot}A_p$ $\quad A_{ps} = 5.642\,in^2$

A_s: area of non-prestressed reinforcing steel on the flexural tension side of the member (LRFD Fig. 5.8.3.4.2-3)

$A_s := 0.0{\cdot}in^2$ (conservatively)

per eq. 5.8.3.4.2-3, A_c = area of concrete on the flexural tension side of the member as shown in Figure 5.8.3.4.2-1

$A_c := 6{\cdot}in{\cdot}19{\cdot}in + 3{\cdot}in{\cdot}9.5{\cdot}in + 6{\cdot}in{\cdot}0.5(d_g + t_{s1})$ $\quad A_c = 384\,in^2$

(See design policy memo for the revised ε_{xx} equation)

$$\varepsilon_{xx} := \frac{\frac{M_u}{d_v} + 0.5{\cdot}N_u + (V_u - V_p) - A_{ps}{\cdot}f_{po}}{2{\cdot}(E_s{\cdot}A_s + E_p{\cdot}A_{ps})} \qquad \varepsilon_{xx} = -1.28 \times 10^{-3}$$

$$\varepsilon_x := \begin{cases} \varepsilon_{xx} & \text{if } \varepsilon_{xx} \geq 0.0 \\ \varepsilon_{xx}{\cdot}\frac{2{\cdot}(E_s{\cdot}A_s + E_p{\cdot}A_{ps})}{2{\cdot}(E_c{\cdot}A_c + E_s{\cdot}A_s + E_p{\cdot}A_{ps})} & \text{otherwise} \end{cases} \qquad \varepsilon_x = -8.14 \times 10^{-5}$$

LRFD Eq. 5.8.3.4.2-1

$b_v := b_w$ $\quad b_v = 6\,in$

$$v := \frac{V_u - \phi_v \cdot V_p}{\phi_v \cdot b_v \cdot d_v} \qquad v = 0.84\,ksi$$

$$\frac{v}{f'_c} = 0.099$$

From LRFD Table 5.8.3.4.2-1, with transverse reinforcement

use $\theta := 21.4 \cdot deg$

$\beta := 3.24$

Check critical section location (§5.8.3.2)

$0.5 \cdot d_v \cdot \cot(\theta) = 88.17\,in$

$d_c = 69.11\,in$ Larger governs, say OK

14.4.4 Required Shear Strength (§5.8.3.3)

$$V_c := 0.0316 \cdot \beta \cdot \sqrt{\frac{f'_c}{ksi}} \cdot ksi \cdot b_v \cdot d_v \qquad V_c = 123.77\,kip$$

$\phi_v = 0.9$

$V_u > 0.5 \cdot \phi_v \cdot (V_c + V_p) = 1$ **if positive,** transverse reinforcement req'd (§5.8.2.4)

Try two legs #4, $A_v := 0.40 \cdot in^2$ $\quad s := 18 \cdot in$ (see standard girder plan)

V_s: shear to be taken by shear reinforcement (§5.8.3.3)

$$V_s := \frac{A_v \cdot f_y \cdot d_v \cdot \cot(\theta)}{s} \qquad V_s = 235.1\,kip \qquad \begin{pmatrix} V_c + V_s + V_p \\ 0.25 \cdot f'_c \cdot b_v \cdot d_v + V_p \end{pmatrix} = \begin{pmatrix} 392.34 \\ 914.565 \end{pmatrix} kip$$

$$V_n := \min\left(\begin{pmatrix} V_c + V_s + V_p \\ 0.25 \cdot f'_c \cdot b_v \cdot d_v + V_p \end{pmatrix}\right) \qquad V_n = 392.34\,kip$$

$\text{if}\left(\phi_v \cdot V_n \geq V_u, \text{"OK"}, \text{"NG"}\right) = \text{"OK"}$ $\quad V_u = 344.42\,\text{kip}$

Check minimum shear reinforcement (§5.8.2.5)

$$\text{if}\left(A_v \geq 0.0316 \cdot \sqrt{\frac{f'_c}{\text{ksi}}} \cdot \text{ksi} \cdot \frac{b_v \cdot s}{f_y}, \text{"OK"}, \text{"NG"}\right) = \text{"OK"} \qquad 0.0316 \cdot \sqrt{\frac{f'_c}{\text{ksi}}} \cdot \text{ksi} \cdot \frac{b_v \cdot s}{f_y} = 0.17\,\text{in}^2$$

Check maximum shear reinforcement spacing (§5.8.2.7)

$$s_{max} := \text{if}\left[v < 0.125 \cdot f'_c, \min\left(\begin{pmatrix} 0.8 \cdot d_v \\ 24.0 \cdot \text{in} \end{pmatrix}\right), \min\left(\begin{pmatrix} 0.4 \cdot d_v \\ 12.0 \cdot \text{in} \end{pmatrix}\right)\right] \qquad s_{max} = 24\,\text{in}$$

$$s := \min\left(\begin{pmatrix} s_{max} \\ s \end{pmatrix}\right) \qquad s = 18\,\text{in}$$

use $A_v = 0.4\,\text{in}^2$ and $s = 18\,\text{in}$

14.4.5 Longitudinal Reinforcement at Critical Section (§5.8.3.5)

$\phi_n := 0.75$ for axial compression with spirals or ties (§5.5.4.2.1)

A_{ps}: area of prestressing steel on the flexural tension side of the member

$A_{ps} \cdot f_{ps} = 1.388 \times 10^3\,\text{kip}$

(per §C5.8.3.4.2, "it is conservative to take Mu as the highest factored moment that will occurred at the section rather than the coincident moment.")

$$\frac{M_u}{d_v \cdot \phi_p} + 0.5 \cdot \frac{N_u}{\phi_n} + \left[\frac{V_u}{\phi_v} - 0.5 \cdot \min\left(\begin{pmatrix} V_s & \frac{V_u}{\phi_v} \end{pmatrix}\right) - V_p\right] \cdot \cot(\theta) = 935.6\,\text{kip}$$

$$\text{if}\left[A_{ps} \cdot f_{ps} \geq \frac{M_u}{d_v \cdot \phi_p} + 0.5 \cdot \frac{N_u}{\phi_n} + \left[\frac{V_u}{\phi_v} - 0.5 \cdot \min\left(\begin{pmatrix} V_s & \frac{V_u}{\phi_v} \end{pmatrix}\right) - V_p\right] \cdot \cot(\theta), \text{"OK"}, \text{"NG"}\right] = \text{"OK"}$$

if true, no longitudinal reinforcement required.

14.5 Shear Design and Longitudinal Reinforcement at Harping Point

14.5.1 Factored Shear Force (§1.3.2)

Dead load girder $V_g := w_g \cdot \left(\frac{L}{2} - x_h\right)$ $\quad V_g = 10.8\,\text{kip}$

slab + pad $V_{sp}(x_h) = 12.7\,kip$

diaphragm $V_d := \begin{cases} 0.5 \cdot P & \text{if } n_{diaph} = 3 \\ 0 \cdot P & \text{if } n_{diaph} = 2 \\ 0.5 \cdot P & \text{if } n_{diaph} = 1 \\ 0 \cdot kip & \text{otherwise} \end{cases}$ $V_d = 1.9\,kip$

s.i.d.l. $V_b := w_b \cdot \left(\frac{L}{2} - x_h\right)$ $V_b = 2.4\,kip$

$V_{DC} := V_g + V_{sp}(x_h) + V_d + V_b$ $V_{DC} = 27.8\,kip$

LL shear at harping point (see QconBridge output)

$V_{LL} := 55 \cdot kip$

$V_L := V_{LL} \cdot DF_v$ $V_L = 49.6\,kip$

Shear force effect $V_u := \eta \cdot (\gamma_p \cdot V_{DC} + \gamma_L \cdot V_L)$ $V_u = 121.6\,kip$

14.5.2 Nominal Shear Resistances (§5.8.3.3)

Determination of b and q (§5.8.3.4.2)

$V_p := 0.0 \cdot kip$

f_{po}, stress in prestressing steel when the stress in the surrounding concrete is 0.0,

$f_{po} := 0.70 f_{pu}$ $f_{po} = 189\,ksi$ (tension)

N_u, external axial forces,

$N_u := 0.0 \cdot kip$

M_u at harping point,

$M_{DC} := M_{gh} + M_{sp}(x_h) + M_{dh} + M_{bh}$ $M_{DC} = 4393\,kip \cdot ft$

$M_{Lh} = 2522\,kip \cdot ft$

(per §C5.8.3.4.2, "it is conservative to take Mu as the highest factored moment that will occurred at the section rather than the coincident moment.")

M_u, then

$M_u := \eta \cdot (\gamma_p \cdot M_{DC} + \gamma_L \cdot M_{Lh})$ $M_u = 9905\,\text{kip}\cdot\text{ft}$

$M_u := \max((M_u \quad V_u \cdot d_v))$ $M_u = 9905\,\text{kip}\cdot\text{ft}$

A_{ps}: area of prestressing steel on the flexural tension side of the member

$A_{ps} := N_p \cdot A_p$ $A_{ps} = 9.114\,\text{in}^2$

A_s: area of non-prestressed reinforcing steel on the flexural tension side of the member (LRFD Fig. 5.8.3.4.2-3)

$A_s := 0.0 \cdot \text{in}^2$

(See design policy memo for the revised ε_{xx} equation)

$$\varepsilon_{xx} := \frac{\frac{M_u}{d_v} + 0.5 \cdot N_u + (V_u - V_p) - A_{ps} \cdot f_{po}}{2 \cdot (E_s \cdot A_s + E_p \cdot A_{ps})} \qquad \varepsilon_{xx} = -1.28 \times 10^{-3}$$

$$\varepsilon_x := \begin{cases} \varepsilon_{xx} & \text{if } \varepsilon_{xx} \geq 0.0 \\ \varepsilon_{xx} \cdot \dfrac{2 \cdot (E_s \cdot A_s + E_p \cdot A_{ps})}{2 \cdot (E_c \cdot A_c + E_s \cdot A_s + E_p \cdot A_{ps})} & \text{otherwise} \end{cases} \qquad \varepsilon_x = -8.14 \times 10^{-5}$$

LRFD Eq. 5.8.3.4.2-1

$$v := \frac{V_u - \phi_v \cdot V_p}{\phi_v \cdot b_v \cdot d_v} \qquad v = 0.33\,\text{ksi}$$

$$\frac{v}{f'_c} = 0.038$$

From LRFD Table 5.8.3.4.2-1, with transverse reinforcement

use $\theta := 21 \cdot \text{deg}$

$\beta := 4.1$

14.5.3 Required Shear Strength

$V_c := 0.0316 \cdot \beta \cdot \sqrt{\frac{f'_c}{ksi}} \cdot ksi \cdot b_v \cdot d_v$ $V_c = 156.6\,kip$

$V_u > 0.5 \cdot \phi_v \cdot (V_c + V_p) = 1$ **if positive,** transverse reinforcement req'd (§5.8.2.4)

Try two legs #4, $A_v := 0.40 \cdot in^2$ $s := 18 \cdot in$ (see standard girder plan)

V_s: shear to be taken by shear reinforcement (§5.8.3.3)

$V_s := \frac{A_v \cdot f_y \cdot d_v \cdot \cot(\theta)}{s}$ $V_s = 240\,kip$

$V_n := \min\left(\begin{pmatrix} V_c + V_s + V_p \\ 0.25 \cdot f'_c \cdot b_v \cdot d_v + V_p \end{pmatrix}\right)$ $V_n = 396.66\,kip$

$if(\phi_v \cdot V_n \geq V_u, "OK", "NG") = "OK"$ $V_u = 121.65\,kip$

Check Minimum Shear Reinforcement (§5.8.2.5)

$if\left(A_v \geq 0.0316 \cdot \sqrt{\frac{f'_c}{ksi}} \cdot ksi \cdot \frac{b_v \cdot s}{f_y}, "OK", "NG"\right) = "OK"$ $0.0316 \cdot \sqrt{\frac{f'_c}{ksi}} \cdot ksi \cdot \frac{b_v \cdot s}{f_y} = 0.17\,in^2$

Check Maximum Shear Reinforcement Spacing (§5.8.2.7)

$s_{max} := if\left[v < 0.125 \cdot f'_c, \min\left(\begin{pmatrix} 0.8 \cdot d_v \\ 24.0 \cdot in \end{pmatrix}\right), \min\left(\begin{pmatrix} 0.4 \cdot d_v \\ 12.0 \cdot in \end{pmatrix}\right)\right]$ $s_{max} = 24\,in$

$s := \min\left(\begin{pmatrix} s_{max} \\ s \end{pmatrix}\right)$ $s = 18\,in$ **OK**

use $A_v = 0.4\,in^2$ and $s = 18\,in$

14.5.4 Longitudinal Reinforcement at Harping Point (§5.8.3.5)

$A_s \cdot f_y + A_{ps} \cdot f_{ps} = 2.243 \times 10^3\,kip$

("it is conservative to take Mu as the highest factored moment that will occurred at the section rather than the coincident moment."; but it could be too conservative. per §C5.8.3.5, at max. moment locations, the tension in the reinforcement does not exceed that due to the maximum moment alone.)

$\frac{M_u}{d_v \cdot \phi_p} + 0.5 \cdot \frac{N_u}{\phi_n} + \left[\frac{V_u}{\phi_v} - 0.5 \cdot \min\left(\begin{pmatrix} V_s & \frac{V_u}{\phi_v} \end{pmatrix}\right) - V_p\right] \cdot \cot(\theta) = 1.896 \times 10^3\,kip$

$if\left[A_s \cdot f_y + A_{ps} \cdot f_{ps} \geq \frac{M_u}{d_v \cdot \phi_p} + 0.5 \cdot \frac{N_u}{\phi_n} + \left[\frac{V_u}{\phi_v} - 0.5 \cdot \min\left(\begin{pmatrix} V_s & \frac{V_u}{\phi_v} \end{pmatrix}\right) - V_p\right] \cdot \cot(\theta), "OK", "NG"\right] = "OK"$

if true, no longitudinal reinforcement required.

14.6 Pretension Anchorage Zone

14.6.1 Jacking Force In Service (§3.4.3)

P_j, jacking force, $P_j := f_{pj} \cdot N_p \cdot A_p$ $P_j = 1846\,\text{kip}$

check jacking force in service (§3.4.3),

V_{DC}, permanent dead reaction at bearing, $V_{DC} := w_g \cdot \frac{L}{2}$

$1.3 \cdot V_{DC} = 71.1\,\text{kip}$

$\text{if}\left(P_j \geq 1.3 \cdot V_{DC}, \text{"OK"}, \text{"NG"}\right) = \text{"OK"}$

14.6.2 Factored Bursting Resistance Pr (§5.10.10.1)

Add extra stirrups at beam ends:

Let $f_s := 20 \cdot \text{ksi}$ (conservatively)

A_s, total area of reinforcement located within the distance $\frac{d_g}{4} = 18.4\,\text{in}$ from the end of the beam

$A_s := \frac{0.04 \cdot \left(f_{pj} \cdot A_{pstemp}\right)}{f_s}$ $A_s = 3.867\,\text{in}^2$ Note: the the prestressing force prior to release (see PCI design example)

use 5 #5 U- stirrups @ 3.5" spacing at each end of beams (see standard plan).

$A_s := 5 \cdot 0.31 \cdot \text{in}^2 \cdot 2$ $A_s = 3.1\,\text{in}^2$ **say OK**

14.6.2 Confinement Reinforcement (§5.10.10.2)

For the distance within $1.5 \cdot d_g = 9.19\,\text{ft}$

from the end of the beams, the reinforcement shall not be less than #3 deformed bars, with spacing not exceeding 6", and shaped to enclose the strands in the bottom flange.

Need to modify the standard plan.

15 Lift Analysis

Allowable Stresses

Lifting

Allowable tension with bonded reinforcement which is sufficient to resist 120% of the tension force in the cracked concrete computed on the basis of an uncracked section (§5.9.4.1.2).

$$0.24\cdot\sqrt{\frac{f'_{ci}}{ksi}}\cdot ksi = 0.66\,ksi$$

or w/o bonded reinforcement,

$$\min\left(\begin{pmatrix} 0.0948\cdot\sqrt{\frac{f'_{ci}}{ksi}}\cdot ksi \\ 0.200\cdot ksi \end{pmatrix}\right) = 0.2\,ksi$$

Allowable compression (§5.9.4.1.1)

$$-0.60\cdot f'_{ci} = -4.5\,ksi$$

Shipping

Allowable tension with bonded reinforcement which is sufficient to resist 120% of the tension force in the cracked concrete computed on the basis of an uncracked section (§5.9.4.1.2).

$$0.24\cdot\sqrt{\frac{f'_{c}}{ksi}}\cdot ksi = 0.7\,ksi$$

or w/o bonded reinforcement,

$$\min\left(\begin{pmatrix} 0.0948\cdot\sqrt{\frac{f'_{c}}{ksi}}\cdot ksi \\ 0.200\cdot ksi \end{pmatrix}\right) = 0.2\,ksi$$

Allowable compression during shipping and handling (§5.9.4.2.1),

$$-0.60\cdot f'_{c} = -5.1\,ksi$$

At lifting

Distance from end of girder to CL Brg, $P2 = 3.94\,in$

Assume pick point from the end of girder, $x_L := 2.5\cdot ft$

Moment due to weight of girder at harping point, which is the critical section,

$$M_{gh} := w_g\cdot\frac{GL}{2}\cdot\left(x_h + P2 - x_L\right) - \frac{1}{2}\cdot w_g\cdot\left(x_h + P2\right)^2 \qquad M_{gh} = 1627\,kip\cdot ft$$

For straight strands at lifting,

$P_{sis} = 1017\,kip$

$e_s = 34.33\,in$

For harped strands at lifting,

$P_{sih} = 625.91\,kip$

$e_h = 34.27\,in$

At bottom of girder at lifting

$$f_c := \left(\frac{M_{gh}}{S_{bg}} - \frac{P_{si}}{A_g}\right) + \frac{-P_{sis}\cdot e_s - P_{sih}\cdot e_h + P_{sit}\cdot e_{temp}}{S_{bg}}$$

$f_c = -4.68\,ksi$ < allowable $-0.60\cdot f'_{ci} = -4.5\,ksi$

say OK

At top of girder at lifting

$$f_t := \left(-\frac{M_{gh}}{S_{tg}} - \frac{P_{si}}{A_g}\right) + \frac{P_{sis}\cdot e_s + P_{sih}\cdot e_h - P_{sit}\cdot e_{temp}}{S_{tg}} \qquad f_t = -0.08\,ksi$$

Allowable tension with bonded reinforcement which is sufficient to resist 120% of the tension force in the cracked concrete computed on the basis of an uncracked section (§5.9.4.1.2).

$$0.24\cdot\sqrt{\frac{f'_{ci}}{ksi}}\cdot ksi = 0.66\,ksi$$ **OK**

or w/o bonded reinforcement

$$\min\left(\begin{pmatrix} 0.0948\cdot\sqrt{\frac{f'_{ci}}{ksi}}\cdot ksi \\ 0.200\cdot ksi \end{pmatrix}\right) = 0.2\,ksi$$ **OK**

AT Shipping

Per standard specs 6-02.3(25)M, girder support during shipping shall meet these requirements unless otherwise shown in the plans:

Series W42G and W50MG and all bulb tee girders	$3\cdot ft$
Series W58G	$4\cdot ft$
Series W74G	$5\cdot ft$
Series W83G and W95G	$8\cdot ft$

Assume shipping support from the either end of girder, $x_S := 5\cdot ft$

Moment due to weight of girder at harping point, which is the critical section,

$$M_{gh} := w_g \cdot \frac{GL}{2} \cdot \left(x_h + P2 - x_S\right) - \frac{1}{2} \cdot w_g \cdot \left(x_h + P2\right)^2 \qquad M_{gh} = 1.489 \times 10^3 \text{ kip} \cdot \text{ft}$$

Prestress loss (per BDM 6.2.3.C and design memo), $LOSS_s := 0.75 \cdot \Delta f_{pT}$ $LOSS_s = 36.904 \text{ ksi}$

For straight strands at shipping,

$P_{ss} := N_s \cdot A_p \cdot \left(f_{pj} - LOSS_s\right)$ $P_{ss} = 934.294 \text{ kip}$

For harped strands at shipping,

$P_{sh} := N_h \cdot A_p \cdot \left(f_{pj} - LOSS_s\right)$ $P_{sh} = 575 \text{ kip}$

For temporary strands at shipping,

$P_{st} := N_t \cdot A_p \cdot \left(f_{pj} - LOSS_s\right)$ $P_{st} = 71.869 \text{ kip}$

$P_s := P_{ss} + P_{sh} + P_{st}$ $P_s = 1581.1 \text{ kip}$

Two possible shipping conditions:

I. 20% Impact (dead load, up or down) (also see §5.14.1.2.1 for 50% requirement)
II. 6% superelevation of road (normally use 6%)

set $se := 0.06$

Bottom Flange

I. 20% Impact

At bottom of girder at shipping (impact up 20%)

$$f_c := \left(\frac{0.8 \cdot M_{gh}}{S_{bg}} - \frac{P_s}{A_g}\right) + \frac{-P_{ss} \cdot e_s - P_{sh} \cdot e_h + P_{st} \cdot e_{temp}}{S_{bg}} \qquad f_c = -4.55 \text{ ksi}$$

At bottom of girder at shipping (impact down 20%)

$$\left(\frac{1.2 \cdot M_{gh}}{S_{bg}} - \frac{P_s}{A_g}\right) + \frac{-P_{ss} \cdot e_s - P_{sh} \cdot e_h + P_{st} \cdot e_{temp}}{S_{bg}} = -4.05 \text{ ksi}$$

II. Superelevation of road

$I_y := 35394 \cdot \text{in}^4$ approx. about weak axis (from PGSuper output)

Bottom flange width, $b_{bf} := 25 \cdot \text{in}$

At uphill bottom flange of girder at shipping,

$$f_c := \left(\frac{M_{gh}}{S_{bg}} - \frac{P_s}{A_g}\right) + \frac{-P_{ss} \cdot e_s - P_{sh} \cdot e_h + P_{st} \cdot e_{temp}}{S_{bg}} - \frac{se \cdot M_{gh} \cdot \left(0.5 \cdot b_{bf}\right)}{I_y} \qquad f_c = -4.68 \text{ ksi} \quad \text{(governs)}$$

$< \text{ allowable} \quad -0.60 \cdot f'_c = -5.1 \text{ ksi}$ **OK**

Top Flange

I. 20% Impact

At top of girder at shipping (impact up 20%),

$$\left(-\frac{0.8\cdot M_{gh}}{S_{tg}}-\frac{P_s}{A_g}\right)+\frac{P_{ss}\cdot e_s+P_{sh}\cdot e_h-P_{st}\cdot e_{temp}}{S_{tg}}=0.16\,\text{ksi}$$

At top of girder at shipping (impact down 20%),

$$\left(-\frac{1.2\cdot M_{gh}}{S_{tg}}-\frac{P_s}{A_g}\right)+\frac{P_{ss}\cdot e_s+P_{sh}\cdot e_h-P_{st}\cdot e_{temp}}{S_{tg}}=-0.3\,\text{ksi}$$

II. Superelevation of road

top flange width, $b_f = 3.583\,\text{ft}$

At downhill top flange of girder at shipping,

$$f_t := \left(-\frac{M_{gh}}{S_{tg}}-\frac{P_s}{A_g}\right)+\frac{P_{ss}\cdot e_s+P_{sh}\cdot e_h-P_{st}\cdot e_{temp}}{S_{tg}}+\frac{se\cdot M_{gh}\cdot(0.5\cdot b_f)}{I_y} \qquad f_t = 0.58\,\text{ksi} \quad \text{(governs)}$$

Allowable tension with bonded reinforcement which is sufficient to resist 120% of the tension force in the cracked concrete computed on the basis of an uncracked section (§5.9.4.1.2),

$$0.24\cdot\sqrt{\frac{f'_c}{\text{ksi}}}\cdot\text{ksi}=0.7\,\text{ksi}$$

OK; If NG, use temporary pre- or post-tensioning.

or w/o bonded reinforcement,

$$\min\left(\begin{pmatrix}0.0948\cdot\sqrt{\frac{f'_c}{\text{ksi}}}\cdot\text{ksi}\\ 0.200\cdot\text{ksi}\end{pmatrix}\right)=0.2\,\text{ksi}$$

NG

tension area from top of girder,

$$x := \frac{f_t}{f_t-f_c}\cdot d_g \qquad x = 8.08\,\text{in}$$

> 5.5 in. (thickness of top flange)

total tensile force (conservative), $T := f_t\cdot\frac{x}{2}\cdot b_f \qquad T = 100.5\,\text{kip}$

rebar required, $\frac{1.2T}{f_y}=2.01\,\text{in}^2$ standard plan uses 4-#6 & 2-#4, $A_s := 2.16\cdot\text{in}^2$

say OK

16 Girder Stability

Deflection β_y,

$$\beta_y := \frac{w_g \cdot GL \cdot (GL - 2 \cdot x_L)^3}{384 \cdot E_{ci} \cdot I_y} \cdot \left[\frac{5}{GL} \cdot (GL - 2 \cdot x_L) - \frac{24}{GL} \cdot \left(\frac{x_L^{\,2}}{GL - 2 \cdot x_L} \right) \right] \qquad \beta_y = 24.5\,\text{in}$$

$$FS := \frac{Y_{tg}}{0.64 \cdot \beta_y} \qquad FS = 2.26 \qquad > 2 \text{ say OK (see PCI Journal, Vol. 16, No. 3, May-June 1971, pp. 7-9)}$$

If NG, attach temporary lateral bracing to compression flange or provide strongbacks, stiffening trusses, pipe frames or rigidly attached lifting yokes.

The tilt ratio, r_{tilt}, (see January 1988, Univ. of Texas at Austin report CTR 3-2-84-381-4F)

where bottom flange width, $b_{bf} = 25\,\text{in}$

$$r_{tilt} := \frac{Y_{bg}}{0.5 \cdot b_{bf}} \qquad r_{tilt} = 3.04 \qquad \text{(tilt ratio = 3 is relatively large)}$$

The tilt ratio is relatively large, girders shall be braced laterally to prevent tipping or buckling.

17 Deflection and Camber (§5.7.3.6.2)

17.1 Camber Induced by Prestress at Transfer (moment area method)

Moment induced by harped strands

At end,

c.g. of girder to CL of harped strands $e_1 := Y_{tg} - F_o \qquad e_1 = 6.5\,\text{in}$

$M_a := -p_{st} \cdot A_p \cdot N_h \cdot e_1 \qquad M_a = -338\,\text{kip} \cdot \text{ft}$

At harping point,

c.g. of girder to CL of harped strands, $e_h = 34.27\,\text{in}$

$M_b := p_{st} \cdot A_p \cdot (N_h \cdot e_h) \qquad M_b = 1787\,\text{kip} \cdot \text{ft}$

Moment induced by straight/temporary strands

At end and harping point,

c.g. of girder to CL of straight strands, $e_s = 34.33\,\text{in}$

c.g. of girder to CL of temporary strands, $e_{temp} = 33.48\,\text{in}$

$$M_c := p_{st}\cdot A_p\cdot\left(N_s\cdot e_s - N_t\cdot e_{temp}\right) \qquad M_c = 2691\,\text{kip}\cdot\text{ft}$$

$$M_1 := M_c + M_b \qquad M_1 = 4479\,\text{kip}\cdot\text{ft}$$

$$M_2 := M_c + M_a \qquad M_2 = 2353\,\text{kip}\cdot\text{ft}$$

then,

$$C_{ps} := \frac{GL^2}{8\cdot E_{ci}\cdot I_g}\cdot\left[M_1 + \frac{M_2 - M_1}{3}\cdot\left(\frac{2\cdot x_h}{L}\right)^2\right] \qquad C_{ps} = 4.86\,\text{in} \qquad \text{(upward)}$$

Moment induced by due to release of temporary strands at bridge site

At end and harping point,

$$M_c := p_{st}\cdot A_p\cdot\left(N_t\cdot e_{temp}\right) \qquad M_c = 218.285\,\text{kip}\cdot\text{ft}$$

then,

$$C_{tps} := \frac{GL^2}{8\cdot E_c\cdot I_g}\cdot\left(M_c\right) \qquad C_{tps} = 0.25\,\text{in} \qquad \text{(upward)}$$

17.2 Deflection due to Dead Load

girder $\Delta_g := \dfrac{5\cdot w_g\cdot L^4}{384\cdot E_{ci}\cdot I_g}$ $\Delta_g = 1.78\,\text{in}$ (downward)

slab+pad $\Delta_{sp} := \left(\dfrac{5\cdot w_{spu}}{384}\right)\cdot\dfrac{L^4}{E_c\cdot I_g}$ $\Delta_{sp} = 1.97\,\text{in}$ (downward)

diaphragm (AISC P.4-189, coeff. e) $e_{coeff} = 0.05$

$\Delta_d := \dfrac{e_{coeff}\cdot P\cdot(L)^3}{E_c\cdot I_g}$ $\Delta_d = 0.22\,\text{in}$ (downward)

s.i.d.l. $\Delta_b := \dfrac{5\cdot w_b\cdot L^4}{384\cdot E_c\cdot I_c}$ $\Delta_b = 0.21\,\text{in}$ (downward)

screed setting dimension "C" $C := \Delta_{sp} + \Delta_b$ $C = 2.18\,\text{in}$

17.3 Net Deflection at Release

$C_{ps} - \Delta_g = 3.08\,\text{in}$ + upward

17.4 Deflection at Erection

"D" dimension (per BDM §6.1.8)

$$D := \begin{cases} 1.70 \cdot C_{ps} - 1.75 \cdot \Delta_g & \text{if } f'_c > 7 \cdot ksi \\ 1.80 \cdot C_{ps} - 1.85 \cdot \Delta_g & \text{otherwise} \end{cases} \qquad D = 5.15\,in \quad (+ \text{ upward})$$

Excess girder camber all. for establishing "A" dimension $D - C - \Delta_d + C_{tps} = 2.99\,in$

17.5 Deflection due to Live Load

The live load deflection shall be limited to (§2.5.2.6.2)

$$\frac{1}{800} \cdot L = 1.98\,in$$

The vehicular load shall included the dynamic allowance.

The live load deflection should be taken as the larger of (§3.6.1.3.2)

That resulting from the design truck alone, or
that resulting from 25% of the design truck taken together with the design lane load

The provision of §3.6.1.1.2 (multiple presence of live load) shall applied.

For a multi-girder bridge, the deflection shall be taken as deflection per lane times the number of lanes divided by the number of girders (§C2.5.2.6.2).

Estimate max. live load deflection at midspan with heavy truck axles closely spaced and centered in span.

For 2 heavy truck axles, $P := 32 \cdot kip$

$$a := \frac{L}{2} - 7 \cdot ft \qquad a = 58.875\,ft$$

$$\Delta_1 := \frac{P \cdot a}{24 \cdot E_c \cdot I_c} \cdot \left(3 \cdot L^2 - 4 \cdot a^2\right) \qquad \Delta_1 = 0.86\,in \qquad \text{(AISC 2nd ed. p. 4-192)}$$

For 8 kip axle $P := 8 \cdot kip$

use moment area method $a := \frac{L}{2} - 21 \cdot ft \qquad a = 44.875\,ft \qquad b := L - a$

$$M := \frac{P \cdot a \cdot (L - a)}{L} \qquad M = 2841\,kip \cdot in \qquad \text{max. moment}$$

$$M_m := \frac{M}{L - a} \cdot \frac{L}{2} \qquad M_m = 2154\,kip \cdot in \qquad \text{moment at midspan}$$

$$R_A := \frac{\frac{1}{2} \cdot M \cdot a \cdot \left(2 \cdot \frac{a}{3}\right) + \frac{1}{2} \cdot M \cdot b \cdot \left(a + \frac{b}{3}\right)}{L} \qquad R_A = 1.003 \times 10^6\,kip \cdot in^2$$

Deflection at midspan

$$\Delta_2 := \frac{R_A \cdot \frac{L}{2} - \frac{1}{2} \cdot M_m \cdot \frac{L}{2} \cdot \frac{L}{4}}{E_c \cdot I_c} \qquad \Delta_2 = 0.08\,in$$

Then, $\Delta_{hs20} := \Delta_1 + \Delta_2 \qquad \Delta_{hs20} = 0.93\,in$ per lane

Deflection due to design truck alone (per girder + impact), (ignore multiple presence factor) $\Delta_{hs20} := \Delta_{hs20} \cdot \frac{N_L}{N_b} \cdot (1 + IM)$

$$if\left(\frac{1}{800} \cdot L \geq \Delta_{hs20}, "OK", "NG"\right) = "OK" \qquad \text{where} \qquad \Delta_{hs20} = 0.74\,in$$

Deflection due to lane load

$$\Delta_{lane} := \frac{5 \cdot w_{lane} \cdot L^4}{384 \cdot E_c \cdot I_c} \qquad \Delta_{lane} = 0.72\,in \qquad \text{per lane}$$

$$\Delta_{lane} := \Delta_{lane} \cdot \frac{N_L}{N_b} \qquad \Delta_{lane} = 0.43\,in \qquad \text{per girder}$$

Deflection due to 25% truck + lane $0.25 \cdot \Delta_{hs20} + \Delta_{lane} = 0.62\,in$

$$if\left(\frac{1}{800} \cdot L \geq 0.25 \cdot \Delta_{hs20} + \Delta_{lane}, "OK", "NG"\right) = "OK"$$

18 Detail of Reinforcement

18.1 Min. spacing of prestressing tendons (§5.10.3.3.1)

The clear distance between pretensioning strands, including shielded ones, at the end of a member with the development length, for each strand shall not be less than:

$$\max\left[\begin{bmatrix} 3.0 \cdot d_b \\ 1.33 \cdot (0.375 \cdot in) \end{bmatrix}\right] = 1.8\,in$$

where the nominal diameter of the strands, $d_b = 0.6\,in$

and max. size of the aggregate is 0.375 in

The clear distance between strands at the end of a member may be decreased, if justified by performance tests of full-scale prototypes of the design.

Clear spacing used in design,

$2 \cdot in - d_b = 1.4\,in$ **say OK**

Design Example 2 Cast-in-Place Concrete Slab Design

1 Structure

Design span $L := 113.911 \cdot ft$

Roadway width $BW := 25 \cdot ft$ barrier face to barrier face

Girder spacing $S := 6.75 \cdot ft$

Skew angle $\theta := 14.96 \cdot deg$

no. of girder $N_b := 4$

curb width on deck, $cw := 11.5 \cdot in$

Deck overhang (centerline of exterior girder to end of deck)

$$overhang := \frac{BW - (N_b - 1) \cdot S}{2} + cw \qquad overhang = 3.333\,ft$$

2 Criteria and assumptions

2.1 Design Live Load for Decks

(§3.6.1.3.3, not for empirical design method) Where deck is designed using the approximate strip method, specified in §4.6.2.1, the live load shall be taken as the wheel load of the 32.0 kip axle of the design truck, without lane load, where the strips are transverse.

$$\text{if}(S \le 15 \cdot ft, \text{"OK"}, \text{"NG"}) = \text{"OK"} \qquad (§3.6.1.3.3)$$

The design truck or tandem shall be positioned transversely such that the center of any wheel load is not closer than (§3.6.1.3.1)

for the design of the deck overhang - 1 ft from the face of the curb or railing , and

for the design of all other components - 2 ft from the edge of the design lane.

(§3.6.1.3.4) For deck overhang design with a cantilever, not exceeding 6.0 ft from the centerline of the exterior girder to the face of a continuous concrete railing, the wheel loads may be replaced with a uniformly distributed line load of 1.0 KLF intensity, located 1 ft from the face of the railing.

$$\text{if}(overhang - cw \le 6 \cdot ft, \text{"OK"}, \text{"NG"}) = \text{"OK"}$$

Horizontal loads on the overhang resulting from vehicle collision with barriers shall be considered in accordance with the yield line analysis.

2.2 Dynamic Load Allowance (impact)

$IM := 0.33$ (§3.6.2.1)

2.3 Minimum Depth and Cover (§9.7.1)

slab design thickness $t_{s1} := 7 \cdot in$

for D.L. calculation $t_{s2} := 7.5 \cdot in$

min. depth $\text{if}(t_{s1} \ge 7.0 \cdot in, \text{"OK"}, \text{"NG"}) = \text{"OK"}$

top cover for epoxy-coated main reinforcing steel = 1.5 in. (up to #11 bar) (§5.12.4 & Table 5.12.3-1)
bottom concrete cover (unprotected main reinforcing) = 1 in. (up to #11 bar)
sacrificial thickness = 0.5 in. (§2.5.2.4)

2.4 Skew Deck (§9.7.1.3)

$\theta \le 25 \cdot deg = 1$ **it true,** the primary reinforcement may be placed in the direction of the skew; otherwise, it shall be placed perpendicular to the main supporting components.

3 Material Properties

3.1 Concrete

$f'_c := 4 \cdot ksi$ Use **CLASS 4000D** for bridge concrete deck (BDM 5.1.1)

$f_r := 0.24 \cdot \sqrt{\frac{f'_c}{ksi}} \cdot ksi$ $f_r = 0.48\,ksi$ (§5.4.2.6)

$w_c := 0.160 \cdot kcf$

$E_c := 33000 \cdot \left(\frac{w_c}{kcf}\right)^{1.5} \cdot \sqrt{\frac{f'_c}{ksi}} \cdot ksi$ $E_c = 4.224\,10^3 \cdot ksi$ (§5.4.2.4)

3.2 Reinforcing Steel (§5.4.3)

$f_y := 60 \cdot ksi$ $E_s := 29000 \cdot ksi$

4 Methods of Analysis

Concrete deck slabs may be analyzed by using

Approximate elastic methods of analysis, or
Refined methods of analysis, or
Empirical design.

Per office practice, concrete deck slab shall be designed and detailed for both empirical and traditional design methods.

5 Empirical Design (§9.7.2)

5.1 Limit States (§9.5.1)

For other than the deck overhang, where empirical design is used, a concrete deck maybe assumed to satisfy service, fatigue and fracture and strength limit states requirements.

Empirical design shall not be applied to overhangs (§9.7.2.2).

5.2 Design Conditions (§9.7.2.4)

For the purpose of empirical design method, the effective length S_{eff} shall be taken as (§9.7.2.3),

web thickness $b_w := 6 \cdot in$

top flange width $b_f := 25 \cdot in$ $b_f = 25\,in$

$$S_{eff} := S - b_f + \frac{b_f - b_w}{2} \qquad S_{eff} = 5.46\,ft$$

$$if\left(18.0 \geq \frac{S_{eff}}{t_{s1}} \geq 6.0, "OK", "NG"\right) = "OK" \qquad \frac{S_{eff}}{t_{s1}} = 9.357$$

core depth $if\left(t_{s2} - 2.5 \cdot in - 1 \cdot in \geq 4 \cdot in, "OK", "NG"\right) = "OK"$

$if\left(S_{eff} \leq 13.5 \cdot ft, "OK", "NG"\right) = "OK"$

$if\left(overhang \geq 3 \cdot t_{s1}, "OK", "NG"\right) = "OK"$ $overhang = 40\,in$ $3 \cdot t_{s1} = 21\,in$

$if\left(f'_c \geq 4 \cdot ksi, "OK", "NG"\right) = "OK"$

a structurally continuous concrete barrier is made composite with the overhang,

Composite construction **for steel girder (N/A)**

A minimum of two shear connectors at 2 ft centers shall be provided in the M- region of continuous steel superstructures.

5.3 Optional deflection criteria for span-to-depth ratio (LRFD Table 2.5.2.6.3.1)

Min. Depth (continuous span) where $S_{eff} = 5.458\,ft$ (slab span length):

$$if\left[\max\left(\left(\frac{S_{eff} + 10 \cdot ft}{30}\right), \left(\frac{S_{eff} + 10 \cdot ft}{0.54 \cdot ft}\right)\right) \leq t_{s2}, "OK", "NG"\right] = "OK" \qquad \max\left(\left(\frac{S_{eff} + 10 \cdot ft}{30}\right), \left(\frac{S_{eff} + 10 \cdot ft}{0.54 \cdot ft}\right)\right) = 6.5\,in$$

5.4 Reinforcement Requirement (§9.7.2.5)

Four layers of reinforcement is required in empirically designed slabs.

The amount of deck reinforcement shall be (§C9.7.2.5)

0.27 in^2/ft for each bottom layer (0.3% of the gross area of 7.5 in. slab)

0.18 in^2/ft for each top layer (0.2% of the gross area)

Try #5 @ 14 in. for bottom longitudinal and transverse, $0.31 \cdot in^2 \cdot \frac{1 \cdot ft}{14 \cdot in} = 0.27\,in^2$ per ft

#4 @ 12 in. for top longitudinal and transverse. $0.2 \cdot in^2 \cdot \frac{1 \cdot ft}{12 \cdot in} = 0.2\,in^2$ per ft

Spacing of steel shall not exceed 18 in.

$\text{if}(\theta \geq 25 \cdot \text{deg}, \text{"OK"}, \text{"NG"}) = \text{"NG"}$ if OK, double the specified reinforcement in the end zones, taken as a longitudinal distance equal to S_{eff}.

6 Traditional Design

6.1 Design Assumptions for Approx. Method of Analysis (§4.6.2)

Deck shall be subdivided into strips perpendicular to the supporting components (§4.6.2.1.1).
Continuous beam with span length as center to center of supporting elements (§4.6.2.1.6).
Wheel load may be modeled as concentrated load or load based on tire contact area.
Strips should be analyzed by classical beam theory.

6.2 Width of Equivalent Interior Strip (§4.6.2.1.3)

Strip width calculations are not needed since live load moments from Table A4-1 are used.

Spacing in secondary direction (spacing between diaphragms):

$$L_d := \frac{L}{3} \qquad L_d = 37.97\,\text{ft}$$

Spacing in primary direction (spacing between girders):

$$S = 6.75\,\text{ft}$$

Since $\text{if}\left(\frac{L_d}{S} \geq 1.50, \text{"OK"}, \text{"NG"}\right) = \text{"OK"}$, where $\frac{L_d}{S} = 5.63$ (§4.6.2.1.5)

Therefore, all the wheel load shall be applied to primary strip. Otherwise, the wheels shall be distributed between intersecting strips based on the stiffness ratio of the strip to sum of the strip stiffnesses of intersecting strips.

6.3 Limit States (§5.5.1)

Where traditional design based on flexure is used, the requirements for strength and service limit states shall be satisfied.
Extreme event limit state shall apply for the force effect transmitted from the bridge railing to bridge deck (§13.6.2).
Fatigue need not be investigated for concrete deck slabs in multi-girder applications (§5.5.3.1).

6.4 Strength Limit States

Resistance factors (§5.5.4.2.1)

$\phi_f := 0.90$ for flexure and tension of reinforced concrete

$\phi_v := 0.90$ for shear and torsion

Load Modifier

$\eta_D := 1.00$ for conventional design (§1.3.3)

$\eta_R := 1.00$ for conventional level of redundancy (§1.3.4)

$\eta_I := 1.00$ for typical bridges (§1.3.5)

$\eta := \max\left(\begin{pmatrix} \eta_D \cdot \eta_R \cdot \eta_I \\ 0.95 \end{pmatrix}\right)$ $\eta = 1$ (§1.3.2)

Strength I load combination - normal vehicular load without wind (§3.4.1)

Load factors (LRFD Table 3.4.1-1&2):

$\gamma_p := 1.25$ for component and attachments

$\gamma_L := 1.75$ for LL

Multiple presence factor (§3.6.1.1.2):

$M_1 := 1.20$ 1 truck

$M_2 := 1.00$ 2 trucks

$M_3 := 0.85$ 3 trucks (Note; 3 trucks never control for girder spacings up to 15.5 ft, per training notes)

6.4.1 Moment Force Effects Per Strip (§4.6.2.1.6)

The design section for negative moments and shear forces may be taken as follows:

Prestressed girder - shall be at 1/3 of flange width < 15 in.

Steel girder - 1/4 of flange width from the centerline of support.

Concrete box beams - at the face of the web.

web thickness $b_w = 6\,in$

top flange width $b_f = 25\,in$

Design critical section for negative moment and shear shall be at d_c, (§4.6.2.1.6)

$d_c := \min\left(\begin{pmatrix} \frac{b_f}{3} \\ 15 \cdot in \end{pmatrix}\right)$ $d_c = 8.33\,in$ from CL of girder (may be too conservative, see training notes)

Maximum factored moments **per unit width** based on Table A4-1: for $S = 6.75\,ft$

(include multiple presence factors and the dynamic load allowance)

applicability $\text{if}[\min((0.625 \cdot S \quad 6 \cdot ft)) \geq \text{overhang} - \text{cw}, \text{"OK"}, \text{"NG"}] = \text{"OK"}$

$\text{if}\left(N_b \geq 3, \text{"OK"}, \text{"NG="}\right) = \text{"OK"}$

$M_{LLp} := 5.10 \cdot \frac{kip \cdot ft}{ft}$

$M_{LLn} := 4.00 \cdot \frac{kip \cdot ft}{ft}$ (max. -M at d_c from CL of girder)

Dead load moment (STRUDL s-dl output)

$M_{DCp} := 0.56 \cdot \frac{kip \cdot ft}{ft}$ (max. +M, conservative)

$M_{DCn} := 0.008 \cdot \frac{kip \cdot ft}{ft}$ (max. -M at d_c at interior girder, conservative) $\frac{d_c}{S} = 0.103$

Factored positive moment per ft

$M_{up} := \eta \cdot (\gamma_p \cdot M_{DCp} + \gamma_L \cdot M_{LLp})$ $M_{up} = 9.62 \frac{kip \cdot ft}{ft}$

Factored negative moment

$M_{un} := \eta \cdot (\gamma_p \cdot M_{DCn} + \gamma_L \cdot M_{LLn})$ $M_{un} = 7.01 \frac{kip \cdot ft}{ft}$

6.4.2 Flexural Resistance

Normal flexural resistance of a rectangular section may be determined by using equations for a flanged section in which case b_w shall be taken as b (§5.7.3.2.3).

$\beta_1 := if\left[f'_c \le 4 \cdot ksi, 0.85, 0.85 - 0.05 \cdot \left(\frac{f'_c - 4.0 \cdot ksi}{1.0 \cdot ksi} \right) \right]$ $\beta_1 := \begin{cases} \beta_1 & \text{if } \beta_1 \ge 0.65 \\ 0.65 & \text{otherwise} \end{cases}$

$\beta_1 = 0.85$ (§5.7.2.2)

6.4.3 Design for Positive Moment Region

assume bar # $bar_p := 5$

$dia(bar) := \begin{cases} 0.5 \cdot in & \text{if } bar = 4 \\ 0.625 \cdot in & \text{if } bar = 5 \\ 0.75 \cdot in & \text{if } bar = 6 \end{cases}$

$d_p := t_{s1} - 1 \cdot in - \frac{dia(bar_p)}{2}$ $d_p = 5.7\,in$

$A_s := \frac{0.85 \cdot f'_c \cdot ft}{f_y} \cdot \left(d_p - \sqrt{d_p^2 - \frac{2 \cdot M_{up} \cdot ft}{0.85 \cdot \phi_f \cdot f'_c \cdot ft}} \right)$ $A_s = 0.4\,in^2$ per ft

use (bottom-transverse) # $bar_p = 5$ $s_p := 9 \cdot in$ (max. spa. 12 in. per BDM memo)

$A_b(bar) := \begin{cases} 0.20 \cdot in^2 & \text{if } bar = 4 \\ 0.31 \cdot in^2 & \text{if } bar = 5 \\ 0.44 \cdot in^2 & \text{if } bar = 6 \end{cases}$

$$A_{sp} := A_b(bar_p)\cdot\frac{1\cdot ft}{s_p} \qquad A_{sp} = 0.41\,in^2 \qquad \text{per ft}$$

Check max. reinforcement (§5.7.3.3.1)

The max. amount of prestressed and non-prestressed reinforcement shall be such that

where $d_e := d_p$

$$c := \frac{A_{sp}\cdot f_y}{0.85\cdot\beta_1\cdot f'_c\cdot 1\cdot ft} \qquad c = 0.72\,in$$

$$if\left(\frac{c}{d_e} \le 0.42, "OK", "NG"\right) = "OK" \qquad \frac{c}{d_e} = 0.126$$

The section is not over-reinforced. Over-reinforced concrete sections shall not be permitted.

Check min. reinforcement (§5.7.3.3.2),

$$M_{cr} := f_r\cdot\frac{1}{6}\cdot 12\cdot in\cdot t_{s2}^2 \qquad 1.2\cdot M_{cr} = 5.4\,kip\cdot ft \qquad M_{up}\cdot ft = 9.625\,kip\cdot ft$$

$$if\left(M_{up}\cdot ft \ge 1.2\cdot M_{cr}, "OK", "NG"\right) = "OK"$$

6.4.4 Design for Negative Moment Region

assume bar # $bar_n := 5$

$$d_n := t_{s1} - 2.0\cdot in - \frac{dia(bar_n)}{2} \qquad d_n = 4.69\,in$$

$$A_s := \frac{0.85\cdot f'_c\cdot ft}{f_y}\cdot\left(d_n - \sqrt{d_n^2 - \frac{2\cdot M_{un}\cdot ft}{0.85\cdot\phi_f\cdot f'_c\cdot ft}}\right) \qquad A_s = 0.35\,in^2 \qquad \text{per ft}$$

use (top-transverse) bar # $bar_n = 5$ $s_n := 9\cdot in$ (max. spa. 12 in. per BDM memo)

$$A_{sn} := A_b(bar_n)\cdot\frac{1\cdot ft}{s_n} \qquad A_{sn} = 0.41\,in^2 \qquad \text{per ft}$$

The max. amount of prestressed and non-prestressed reinforcement shall be such that

where $d_e := d_n$

$$c := \frac{A_{sn}\cdot f_y}{0.85\cdot\beta_1\cdot f'_c\cdot 1\cdot ft} \qquad c = 0.72\,in$$

$$\text{if}\left(\frac{c}{d_e} \le 0.42, \text{"OK"}, \text{"NG"}\right) = \text{"OK"} \qquad \frac{c}{d_e} = 0.153$$

The section is not over-reinforced. Over-reinforced reinforced concrete sections shall not be permitted.

$$M_{cr} := f_r \cdot \frac{1}{6} \cdot 12 \cdot in \cdot t_{s2}^{\,2} \qquad 1.2 \cdot M_{cr} = 5.4\,kip \cdot ft \qquad M_{un} \cdot ft = 7.01\,kip \cdot ft$$

$$\text{if}\left(M_{un} \cdot ft \ge 1.2 \cdot M_{cr}, \text{"OK"}, \text{"NG"}\right) = \text{"OK"}$$

6.5 Control of Cracking by Distribution of Reinforcement (§5.7.3.4)

Service I load combination is to be considered for crack width control (§3.4.1).

Combined limit state load modifier (§1.3.2)

$$\eta_s := 1$$

Load factors (LRFD Table 3.4.1-1):

$\gamma_p := 1.00$ for component and attachments

$\gamma_L := 1.00$ for LL

$$M_{sp} := \eta_s \cdot \left(\gamma_p \cdot M_{DCp} + \gamma_L \cdot M_{LLp}\right) \qquad M_{sp} = 5.66\,\frac{kip \cdot ft}{ft}$$

$$M_{sn} := \eta_s \cdot \left(\gamma_p \cdot M_{DCn} + \gamma_L \cdot M_{LLn}\right) \qquad M_{sn} = 4.01\,\frac{kip \cdot ft}{ft}$$

$$\rho_p := \frac{A_{sp}}{d_p \cdot 12 \cdot in} \qquad \rho_n := \frac{A_{sn}}{d_p \cdot 12 \cdot in}$$

$$n := \frac{E_s}{E_c} \qquad n = 6.866 \qquad n := \max[\,[\,\text{ceil}((n - 0.495))\quad 6\,]\,]$$

set $n = 7$ (round to nearest integer, §5.7.1, not less than 6)

$$k(\rho) := \sqrt{(\rho \cdot n)^2 + 2 \cdot \rho \cdot n} - \rho \cdot n \qquad k(\rho_p) = 0.252$$

$$j(\rho) := 1 - \frac{k(\rho)}{3} \qquad j(\rho_p) = 0.916$$

$$f_{sa} := \frac{M_{sp} \cdot ft}{A_{sp} \cdot j(\rho_p) \cdot d_p} \qquad f_{sa} = 31.54\,ksi$$

$Z_p := 170 \cdot \frac{kip}{in}$ crack width parameter in moderate exposure condition

$Z_n := 130 \cdot \frac{kip}{in}$ crack width parameter in severe exposure condition

for $bar_p = 5$ $s_p = 9\,in$

$d_c := (1 \cdot in) + \frac{dia(bar_p)}{2}$ $d_c = 1.3\,in$ (clear cover used to compute d_c should not be taken grater than 2 in., **OK**)

$A := 2 \cdot (d_c) \cdot s_p$ $A = 23.63\,in^2$

$$if\left[\min\left[\left[\frac{Z_p}{(d_c \cdot A)^{\frac{1}{3}}}\right], \left[\frac{Z_p}{0.6 \cdot f_y}\right]\right] \geq f_{sa}, "OK", "NG"\right] = "OK"$$ where $$\min\left[\left[\frac{Z_p}{(d_c \cdot A)^{\frac{1}{3}}}\right], \left[\frac{Z_p}{0.6 \cdot f_y}\right]\right] = 36\,ksi$$

$k(\rho_n) = 0.252$ $j(\rho_n) = 0.916$

$f_{sa} := \frac{M_{sn} \cdot ft}{A_{sn} \cdot j(\rho_n) \cdot d_n}$ $f_{sa} = 27.1\,ksi$

for $bar_n = 5$ $s_n = 9\,in$

$d_c := 2 \cdot in + \frac{dia(bar_n)}{2}$ $d_c = 2.31\,in$ (clear cover used to compute d_c should not be taken grater than 2 in., **OK**)

$A := 2 \cdot (d_c) \cdot s_n$ $A = 41.63\,in^2$

$$if\left[\min\left[\left[\frac{Z_n}{(d_c \cdot A)^{\frac{1}{3}}}\right], \left[\frac{Z_n}{0.6 \cdot f_y}\right]\right] \geq f_{sa}, "OK", "NG"\right] = "OK"$$ where $$\min\left[\left[\frac{Z_n}{(d_c \cdot A)^{\frac{1}{3}}}\right], \left[\frac{Z_n}{0.6 \cdot f_y}\right]\right] = 28.4\,ksi$$

Say OK

6.6 Shrinkage and Temperature Reinforcement (§5.10.8.2)

For components less than 48 in. thick,

where $A_g := t_{s2} \cdot 1 \cdot ft$

$A_{tem} := 0.11 \cdot \frac{A_g \cdot ksi}{f_y}$ $A_{tem} = 0.17\,in^2$ per ft

The spacing of this reinforcement shall not exceed $3 \cdot t_{s1} = 21\,in$ or 18 in (**per BDM memo 12 in.)**

top longitudinal - $bar := 4$ $s := 12 \cdot in$ $A_s := A_b(bar) \cdot \frac{1 \cdot ft}{s}$ $A_s = 0.2\,in^2$ per ft **OK**

6.7 Distribution of Reinforcement (§9.7.3.2)

The effective span length S_{eff} shall be taken as (§9.7.2.3):

$S_{eff} = 5.458\,ft$

For primary reinforcement perpendicular to traffic:

$$percent := \min\left(\left(\frac{220}{\sqrt{\frac{S_{eff}}{ft}}} \quad 67\right)\right) \qquad percent = 67$$

Bottom longitudinal reinforcement (**per BDM memo < slab thickness)**: $t_{s2} = 7.5\,in$

$A_s := \frac{percent}{100} \cdot A_{sp}$ $A_s = 0.28\,in^2$ per ft

use bar # $bar := 4$ $s := 7.5 \cdot in$ $A_s := A_b(bar) \cdot \frac{1 \cdot ft}{s}$ $A_s = 0.32\,in^2$ per ft **OK**

6.8 Maximum bar spacing (§5.10.3.2)

Unless otherwise specified, the spacing of the primary reinforcement in walls and slabs shall not exceed 1.5 times the thickness of the member or 18 in.. The maximum spacing of temperature shrinkage reinforcement shall be as specified in §5.10.8.

$1.5 \cdot t_{s1} = 10.5\,in$ **OK**

6.9 Protective Coating (§5.12.4)

Epoxy coated reinforcement shall be used for slab top layer reinforcements except when the slab is overlaid with asphalt.

7 Slab Overhang Design

(§3.6.1.3.4) Horizontal loads resulting from vehicular collision with barrier shall be considered in accordance with the provisions of LRFD Section 13.
(§13.7.3.1.2) Unless a lesser thickness can be proven satisfactory during the crash testing procedure, the min. edge thickness for concrete deck overhangs shall be taken as 8 in. for concrete deck overhangs supporting concrete parapets or barriers.

7.1 Applicable Limit States (§5.5.1)

Where traditional design based on flexure is used, the requirements for strength and service limit states shall be satisfied.

Extreme event limit state shall apply for the force effect transmitted from the bridge railing to bridge deck (§13.6.2).

7.2 Strength Limit state

Load Modifier

$\eta_D := 1.00$ for ductile components and connections (§1.3.3 & simplified)

$\eta_R := 1.00$ for redundant members (§1.3.4)

$\eta_I := 1.00$ for operationally important bridge (§1.3.5)

$\eta := \max\left(\begin{pmatrix} \eta_D \cdot \eta_R \cdot \eta_I \\ 0.95 \end{pmatrix}\right)$ $\eta = 1$ (§1.3.2)

Load factors (LRFD Table 3.4.1-1):

$\gamma_p := 1.25$ for component and attachments

$\gamma_L := 1.75$ for LL

7.3 Extreme Event Limit State II

Extreme event limit state shall apply for the force effect transmitted from the vehicular collision force.

Load Modifier

$\eta_D := 1.00$ (§1.3.3)

$\eta_R := 1.00$ (§1.3.4)

$\eta_I := 1.00$ (§1.3.5)

$\eta_e := \max\left(\begin{pmatrix} \eta_D \cdot \eta_R \cdot \eta_I \\ 0.95 \end{pmatrix}\right)$ $\eta_e = 1$ (§1.3.2)

Load factors (LRFD Table 3.4.1-1):

$\gamma_p := 1.25$ for component and attachments

$\gamma_{CT} := 1.00$ for collision force

7.4 Vehicular Collision Force (§13.7.2)

Railing test level TL-4 applies for high-speed highways, freeways, and interstate highways with a mixture of trucks and heavy vehicles.

The transverse and longitudinal loads need not be applied in conjunction with vertical loads (§A13.2). Design forces for railing test level **TL-4** (LRFD Table A13.2-1),

transverse $F_t := 54 \cdot kip$

longitudinal $F_L := 18 \cdot kip$

vertical (down) $F_v := 18 \cdot kip$

Effective Distances:

transverse $L_t := 3.50 \cdot ft$

longitudinal $L_L := 3.50 \cdot ft$

vertical $L_v := 18 \cdot ft$

Min. design height, H, 32 in. (LRFD Table A13.2-1) use $H := 34 \cdot in$

7.5 Design Procedure (§A13.3)

Yield line analysis and strength design for reinforced concrete may be used.

7.6 Nominal Railing Resistance (§A13.3)

For single-slope barriers, the approximate flexural resistance may be taken as:

Flexural capacity about vertical axis,

$$M_w := 18.5 \cdot \frac{kip \cdot ft}{ft}$$

Additional flexural resistance of beam in addition to M_w , if any, at top of wall,

$$M_b := 0.00 \cdot kip \cdot ft$$

Flexural capacity about horizontal axis,

$$M_c := 17.1 \cdot \frac{kip \cdot ft}{ft}$$

Critical wall length, over which the yield mechanism occurs, L_c , shall be taken as:

$$L_c := \frac{L_t}{2} + \sqrt{\left(\frac{L_t}{2}\right)^2 + \frac{8 \cdot H \cdot \left(M_b + M_w \cdot H\right)}{M_c}} \qquad L_c = 10.27\,ft$$

For impact within a barrier segment, the total transverse resistance of the railing may be taken as:

$$R_w := \left(\frac{2}{2 \cdot L_c - L_t}\right) \cdot \left(8 \cdot M_b + 8 \cdot M_w \cdot H + \frac{M_c \cdot {L_c}^2}{H}\right) \qquad R_w = 123.93\,kip$$

7.7 Design Load Cases (§A13.4.1)

Case 1

Transverse and longitudinal forces at extreme event limit state.

Resistance factor (§A13.4.3.2) $\phi := 1.0$

(§C13.7.3.1.2) Presently, in adequately designed bridge deck overhangs, the major crash-related damage occurs in short sections of slab areas where the barriers is hit.

a. at inside face of parapet

$M_s := \frac{\min\left(\left(R_w \quad 1.2 \cdot F_t\right)\right) \cdot H}{\left(L_c + 2 \cdot H\right)}$ moment capacity of the base of the parapet (see memo),

$M_s = 11.5 \frac{kip \cdot ft}{ft}$

$M_{DCa} := 0.55 \cdot \frac{kip \cdot ft}{ft}$ DL M- at edge of curb (see s-DL STRUDL output), $\frac{cw}{overhang} = 0.287$

design moment

$M_u := \eta_e \cdot \left(\gamma_p \cdot M_{DCa} + \gamma_{CT} \cdot M_s\right)$ $M_u = 12.2 \frac{kip \cdot ft}{ft}$

(§A13.4.2) Deck overhang may be designed to provide a flexural resistance, M_s, which is acting in coincident with tensile force, T (see memo),

$T := \frac{\min\left(\left(R_w \quad 1.2 \cdot F_t\right)\right) \cdot ft}{\left(L_c + 2 \cdot H\right)}$ $T = 4.07\,kip$ per ft

min. "haunch+slab" dimension, $A := t_{s2} + 0.75 \cdot in$ $A = 8.25\,in$

d_s, flexural moment depth at edge of curb,

assume bar # $bar_o := 5$

$d_s := \left(7 \cdot in + \frac{A - 7 \cdot in}{overhang - 0.5 \cdot b_f} \cdot cw\right) - 2.5 \cdot in - \frac{dia\left(bar_o\right)}{2}$ $d_s = 4.7\,in$

A_s required for M_u and T,

$A_s := \frac{0.85 \cdot f'_c \cdot ft}{f_y} \cdot \left(d_s - \sqrt{d_s^2 - \frac{2 \cdot M_u \cdot ft}{0.85 \cdot \phi \cdot f'_c \cdot ft}}\right) + \frac{T}{f_y}$ $A_s = 0.64\,in^2$ per ft (1)

Check max. reinforcement (§5.7.3.3.1)

The max. amount of prestressed and non-prestressed reinforcement shall be such that

where d_e $d_e := d_s$ $d_e = 4.7\,in$

$$c := \frac{A_s \cdot f_y - T}{0.85 \cdot \beta_1 \cdot f'_c \cdot 1 \cdot ft} \qquad c = 1\,in$$

$$\text{if}\left(\frac{c}{d_e} \le 0.42, \text{"OK"}, \text{"NG"}\right) = \text{"OK"} \qquad \frac{c}{d_e} = 0.209$$

The section is not over-reinforced. Over-reinforced reinforced concrete sections shall not be permitted.

b. at design section in the overhang

Design critical section for negative moment and shear shall be at d_c, (§4.6.2.1.6)

$$d_c := \min\left(\left(\frac{b_f}{3} \quad 15 \cdot in\right)\right) \qquad d_c = 8.33\,in$$

from CL of girder (may be too conservative, see training notes)

At the inside face of the parapet, the collision forces are distributed over a distance L_c for the moment and L_c + 2H for the axial force. Similarly, assume the distribution length is increased in a 30 degree angle from the base of the parapet,

Collision moment at design section,

$$M_{se} := \frac{M_s \cdot L_c}{L_c + 2 \cdot 0.577 \cdot (\text{overhang} - cw - d_c)} \qquad M_{se} = 9.69\,\frac{kip \cdot ft}{ft}$$

dead load moment @ d_c **from CL of exterior girder** (see s-slab.gts STRUDL output)

$$M_{DCb} := 1.90 \cdot \frac{kip \cdot ft}{ft}$$

design moment

$$M_u := \eta_e \cdot (\gamma_p \cdot M_{DCb} + \gamma_{CT} \cdot M_{se}) \qquad M_u = 12.07\,\frac{kip \cdot ft}{ft}$$

(§A13.4.2) design tensile force, T,

$$T := \frac{\min\left(\left(R_w \quad 1.2 \cdot F_t\right)\right) \cdot ft}{\left[L_c + 2 \cdot H + 2 \cdot 0.577 \cdot (\text{overhang} - cw - d_c)\right]} \qquad T = 3.63\,kip$$

per ft

d_s, flexural moment depth at design section in the overhang.

$$d_s := A - 2.5 \cdot in - \frac{dia(bar_o)}{2} \qquad d_s = 5.4\,in$$

A_s required for M_u and T,

$$\frac{0.85\cdot f'_c\cdot ft}{f_y}\cdot\left(d_s-\sqrt{{d_s}^2-\frac{2\cdot M_u\cdot ft}{0.85\cdot\phi\cdot f'_c\cdot ft}}\right)+\frac{T}{f_y}=0.53\,in^2 \qquad \text{per ft} \qquad \text{(doesn't control)} \qquad (2)$$

c. at design section in first span

(see training notes) The total collision moment can be treated as an applied moment at the end of a continuous strip and the ratio of the moment M2/M1 can be calculated for the transverse design strip. As an approximation, it can be taken equal to the ratio of the **moments produced by the parapet self weight** at the centerline of the first and second girder. The collision moment per unit width at the section under consideration can then be determined using the 30° distribution. Dead load at this design section can be determined by interpolation between dead moments at Centerline of girder and at 0.1S.

Collision moment at exterior girder, $M_s = 11.52\,\frac{kip\cdot ft}{ft}$

Collision moment at first interior girder (see s-slab.gtb output, barrier loading only),

$$M_{2i} := M_s\cdot\frac{0.34}{1.68} \qquad M_{2i} = 2.33\,\frac{kip\cdot ft}{ft}$$

By interpolation for a section in the first bay at d_c from the exterior girder,

$$M_{si} := M_s - d_c\cdot\frac{M_s+M_{2i}}{S} \qquad M_{si} = 10.1\,\frac{kip\cdot ft}{ft}$$

Using the 30° angle distribution, design moment

$$M_{si} := \frac{M_{si}\cdot L_c}{L_c+2\cdot 0.577\cdot(overhang-cw+d_c)} \qquad M_{si} = 7.51\,\frac{kip\cdot ft}{ft}$$

dead load moment @ this section (see s-dl.gtb output) $\frac{d_c}{S} = 0.103$

$$M_{DCi} := 2.0\cdot\frac{kip\cdot ft}{ft}$$

design moment

$$M_u := \eta_e\cdot(\gamma_p\cdot M_{DCi}+\gamma_{CT}\cdot M_{si}) \qquad M_u = 10.01\,\frac{kip\cdot ft}{ft}$$

d_s, flexural moment depth at the design section,

$$d_s := t_{s1}-2.0\cdot in-\frac{dia(bar_o)}{2} \qquad d_s = 4.69\,in$$

A_s required for M_u,

$$\frac{0.85\cdot f'_c\cdot ft}{f_y}\cdot\left(d_s-\sqrt{{d_s}^2-\frac{2\cdot M_u\cdot ft}{0.85\cdot\phi\cdot f'_c\cdot ft}}\right)=0.46\,in^2 \qquad \text{per ft} \quad \text{(doesn't control)} \qquad (3)$$

Case 2 Vertical collision force

For concrete parapets, the case of vertical collision never controls.

Case 3 Check DL + LL

Resistance factor (§1.3.2.1) $\phi_f := 0.9$

For deck overhangs, where applicable, the §3.6.1.3.4 may be used in lieu of the equivalent strip method (§4.6.2.1.3).

a. at design section in the overhang

moment arm for 1.0 kip/ft live load (§3.6.1.3.4)

$$x := overhang - cw - 1\cdot ft - d_c \qquad x = 8.17\,in$$

live load moment without impact,

$$w_L := 1.0\cdot\frac{kip}{ft}$$

$$M_{LL} := M_1\cdot w_L\cdot x \qquad M_{LL} = 0.82\,\frac{kip\cdot ft}{ft}$$

factored moment

$$M_u := \eta\cdot\left[\gamma_p\cdot M_{DCb} + \gamma_L\cdot M_{LL}\cdot(1.0 + IM)\right] \qquad M_u = 4.28\,\frac{kip\cdot ft}{ft}$$

d_s, flexural moment depth at edge of curb,

$$d_s := A - 2.5\cdot in - \frac{dia(bar_o)}{2} \qquad d_s = 5.44\,in$$

A_s required for M_u,

$$\frac{0.85\cdot f'_c\cdot ft}{f_y}\cdot\left(d_s - \sqrt{d_s^{\,2} - \frac{2\cdot M_u\cdot ft}{0.85\cdot\phi_f\cdot f'_c\cdot ft}}\right) = 0.18\,in^2 \qquad \text{per ft} \qquad \text{(doesn't control)} \qquad (4)$$

b. at design section in first span

Assume slab thickness at this section, $t_{s1} = 7\,in$

use the same D.L. + L.L moment as in previous for design (approximately)

factored moment $M_u = 4.28\,\frac{kip\cdot ft}{ft}$

d_s, flexural moment depth at edge of curb,

$$d_s := t_{s1} - 2.0\cdot in - \frac{dia(bar_o)}{2} \qquad d_s = 4.7\,in$$

A_s required for M_u,

$$\frac{0.85\cdot f'_c\cdot ft}{f_y}\cdot\left(d_s - \sqrt{{d_s}^2 - \frac{2\cdot M_u\cdot ft}{0.85\cdot\phi_f\cdot f'_c\cdot ft}}\right) = 0.21\,in^2 \qquad \text{(doesn't control)} \qquad (5)$$

The largest of (1) to (5), As required, $A_s = 0.64\,in^2$ per ft

use bar # $bar_o = 5$ @ $s := 18\cdot in$ **(top transverse) at edge of curb, bundle 1 #5 to every other top bar in the deck overhang region**

$bar_n = 5$ $s_n = 9\,in$

$$A_s := A_b(bar_o)\cdot\frac{1\cdot ft}{s} + A_b(bar_n)\cdot\frac{1\cdot ft}{s_n} \qquad A_s = 0.62\,in^2 \qquad \textbf{say OK}$$

Check max. reinforcement (§5.7.3.3.1)

The max. amount of prestressed and non-prestressed reinforcement shall be such that

where **min. d_e** $d_e := t_{s1} - 2.0\cdot in - \frac{dia(bar_n)}{2}$ $d_e = 4.7\,in$

$$c := \frac{A_s\cdot f_y}{0.85\cdot\beta_1\cdot f'_c\cdot 1\cdot ft} \qquad c = 1.07\,in$$

$$if\left(\frac{c}{d_e} \le 0.42, "OK", "NG"\right) = "OK" \qquad \frac{c}{d_e} = 0.229$$

The section is not over-reinforced. Over-reinforced reinforced concrete sections shall not be permitted.

Determine the point in the first bay of the deck where the additional bars are no longer needed,

$$A_s := A_b(bar_n)\cdot\frac{1\cdot ft}{s_n} \qquad A_s = 0.41\,in^2$$

$$c := \frac{A_s\cdot f_y}{0.85\cdot\beta_1\cdot f'_c\cdot 1\cdot ft} \qquad c = 0.7\,in$$

$$d_e := t_{s1} - 2.0\cdot in - \frac{dia(bar_n)}{2} \qquad d_e = 4.7\,in$$

$a := \beta_1\cdot c$ $a = 0.6\,in$

For the strength limit state,

$$M_{cap} := \phi_f \cdot A_s \cdot f_y \cdot \left(d_e - \frac{a}{2} \right) \qquad M_{cap} = 8.15\,\text{kip}\cdot\text{ft} \qquad \text{per ft}$$

For the extreme event limit state,

$$M_{cap} := \phi \cdot A_s \cdot f_y \cdot \left(d_e - \frac{a}{2} \right) \qquad M_{cap} = 9.06\,\text{kip}\cdot\text{ft} \qquad \text{per ft}$$

By inspection of (1) to (5), no additional bar is required beyond design section of the first bay.

Cut off length requirement (§5.11.1.2)

$15 \cdot \text{dia}(\text{bar}_o) = 0.781\,\text{ft}$ (controls by inspection)

8 Reinforcing Details

8.1 Development of Reinforcement (§5.11.2.1.1)

basic development length for #11 bar and smaller,

$$L_{db}(d_b, A_b) := \max\left(\begin{pmatrix} 1.0\cdot\text{ft} \\ \dfrac{1.25 \cdot A_b \cdot f_y \cdot \sqrt{\text{ksi}}}{\text{in}\cdot\text{ksi}\cdot\sqrt{f'_c}} \\ 0.4 \cdot d_b \cdot \dfrac{f_y}{\text{ksi}} \end{pmatrix} \right)$$

For **#5** bars, $L_{db}(0.625\cdot\text{in}, 0.31\cdot\text{in}^2) = 15\,\text{in}$

For **#6** bars, $L_{db}(0.75\cdot\text{in}, 0.44\cdot\text{in}^2) = 18\,\text{in}$

For **epoxy coated** bars (§5.11.2.1.2),

with cover less than $3d_b$ or with clear spacing less than $6d_b$ .....times 1.5

not covered above .....times 1.2

For **widely spaced** bars..... times 0.8 (§5.11.2.1.3)

bars spaced laterally not less than 150 mm center-to-center, with not less than 75 mm clear cover measured in the direction of spacing.

For **bundled** bars..... times 1.2 for a three-bar bundle (§5.11.2.3)

Lap Splices in Tension (§5.11.5.3.1)

The length of lap for tension lap splices shall not be less than either 300 mm or the following for

Class A, B, or C splices:

Class A splice ..... times 1.0
Class B splice ..... times 1.3
Class C splice ..... times 1.7

Flexural Reinforcement (§5.11.1.2)

Except at supports of simple-spans and at the free ends of cantilevers, reinforcement shall be extended beyond the point at which it is no longer required to resist flexure for a distance not less than:

the effective depth of the member,
15 times the nominal diameter of bar, or
1/20 of the clear span.

No more than 50% of the reinforcement shall be terminated at any section, and adjacent bars shall not be terminated in the same section.

Positive moment reinforcement (§5.11.1.2.2)

At least 1/3 the positive moment reinforcement in simple-span members, and 1/4 the positive moment reinforcement in continuous members, shall extend along the same face of the member beyond the centerline of the support. In beams, such extension shall not be less than 150 mm.

Negative moment reinforcement (§5.11.1.2.3)

At least 1/3 of the total tension reinforcement provided for negative moment at a support shall have an embedment length length beyond the point of inflection (DL + LL) not less than:

the effective depth of the member, d
12.0 d_b, and
0.0625 times the clear span.

Moment resisting joints (§5.11.1.2.4)

In Seismic Zones 3 and 4, joint shall be detailed to resist moments and shears resulting from horizontal loads through the joint.

Q.E.D.

Design Example 3 Precast Slab Design Stay-In-Place (SIP) Deck Panel

Design Criteria

Loading: HL-93

Concrete:

SIP Panel, $f'_{ci} := 4.0 \cdot ksi$
$f'_c := 5.0 \cdot ksi$ (f'ci + 1 ksi)

CIP slab, $f'_{cs} := 4.0 \cdot ksi$

Reinforcing Steel: (§5.4.3)

AASHTO M-31, Grade 60, $f_y := 60 \cdot ksi$ $E_s := 29000 \cdot ksi$

Prestressing Steel:

AASHTO M-203, uncoated 7 wire, low-relaxation strands (§5.4.4.1)

Nominal strand diameter, db := 0.375·in Ap := 0.085·in2

(Trends now are toward the use of 3/8in. diameter strand, per PCI J., 33(2), pp.67-109)

$f_{pu} := 270 \cdot ksi$

$f_{py} := 0.90 \cdot f_{pu}$ $f_{py} = 243$ ksi

$f_{pe} := 0.80 \cdot f_{py}$ $f_{pe} = 194.4$ ksi @ service limit state after all losses (LRFD Table 5.9.1-1)

$E_p := 28500 \cdot ksi$

Design Method: LRFD 2nd Edition

Mechanical shear ties on the top of panels are not required per PCI, special report, PCI J., 32(2), pp. 26-45.

Structure:

Design span	$L := 89.07 \cdot ft$		
Roadway width	BW 53.0·ft	barrier face to barrier face	
Girder spacing	$S := 6.75 \cdot ft$		
Skew angle	$\theta := 14.65 \cdot deg$		
no. of girder	$N_b := 8$		
curb width on deck,	$cw := 10.5 \cdot in$		
Deck overhang (CL. of exterior girder to end of deck)	$overhang := \frac{BW - (N_b - 1) \cdot S}{2} + cw$	overhang = 3.75ft	
slab design thickness	$t_s1 := 8.0 \cdot in$		
for D.L. calculation	$t_s2 := 8.5 \cdot in$		
Panel dimensions:	$W_{sip} := 8.0 \cdot ft$	$L_{sip} := 6.34 \cdot ft$	$t_{sip} := 3.5 \cdot in$
CIP composite slab:	$t_{cs}1 := t_s1 - t_{sip}$	$t_{cs}1 = 4.5in$	(used for structural design)
	$t_{cs}2 := t_s2 - t_{sip}$	$t_{cs}2 = 5in$	(actual thickness)
	$w_c := 0.160 \cdot kcf$		
future wearing surface	$t_{ws} := 0 \cdot in$		

Minimum Depth and Cover (§9.7.1)

Min. Depth $\text{if}(t_{s2} \geq 7.0 \cdot \text{in}, \text{"OK"}, \text{"NG"}) = \text{"OK"}$

Min. SIP thickness $\text{if}(0.55 \cdot t_{s2} > t_{sip} \geq 3.5 \cdot \text{in}, \text{"OK"}, \text{"NG"}) = \text{"OK"}$

top cover for epoxy-coated main reinforcing steel
= 1.5in. (up to #11 bar)
= 2.0in. (#14 & #18 bars) (§5.12.4 & Table 5.12.3-1)

sacrificial thickness = 0.5in. (§2.5.2.4)

Opitional deflection criteria for span-to-depth ratio (LRFD Table 2.5.2.6.3.1)

Min. Depth (continuous span) where S = 6.75ft (slab span length):

$$\text{if}\left[\max\left(\left(\frac{S+10\cdot\text{ft}}{30}\right)\right) \leq t_{s1}, \text{"OK"}, \text{"NG"}\right] = \text{"OK"} \qquad \max\left(\left(\frac{S+10\cdot\text{ft}}{30}\right)\right) = 6.7\text{in}$$

Skew Deck (§9.7.1.3)

$\theta \leq 25 \cdot \text{deg} = 1$ it true, the primary reinforcement may be placed in the direction of the skew; otherwise, it shall be placed perpendicular to the main supporting components.

Loads

The precast SIP panels support their own weight, any construction loads, and the weight of the CIP slabs. For superimposed dead and live loads, the precast panels are analyzed assuming that they act compositely with the CIP concrete.

Dead load per foot

SIP panel $w_{sip} := t_{sip} \cdot w_c$ $w_{sip} = 0.047 \frac{\text{kip}}{\text{ft}^2}$

CIP slab $w_{cs} := t_{cs2} \cdot w_c$ $w_{cs} = 0.067 \frac{\text{kip}}{\text{ft}^2}$

Weigth of one traffic barrier is $tb := 0.52 \cdot \frac{\text{kip}}{\text{ft}^2}$

Weigth of one sidewalk is $tside := 0.52 \cdot \frac{\text{kip}}{\text{ft}^2}$

Wearing surface & construction loads

wearing surface $w_{ws} := t_{ws} \cdot w_c \cdot \text{ft}$ $w_{ws} = 0 \frac{\text{kip}}{\text{ft}}$

construction load (applied to deck panel only) $w_{con} := 0.050 \cdot \frac{\text{kip}}{\text{ft}}$ (§9.7.4.1)

Live Loads

(§3.6.1.3, not for empircial design mthod) Where deck is designed using the approximate strip method, specified in §4.6.2.1, the live load shall be taken as the wheel load of the 32.0kip axle of the design truck, without lane load, where the strips are transverse.

$\text{if}(S \leq 15 \cdot \text{ft}, \text{"OK"}, \text{"NG"}) = \text{"OK"}$ (§3.6.1.1.1.2)

Multiple presence factor: M1 := 1.2 M2 := 1.0 (§3.6.1.1.1.2)

Dynamic Load Allowance (impact) IM := 0.33 (§3.6.2.1)

Maximum factored moments **per unit width** based on Table A4-1: for S = 2.057m
(include multiple presence factors and the dynamic load allowance)

applicability if [min((0.625·S 6·ft)) ≥ overhang - cw, "OK", "NG"] = "OK"
if ($N_b \geq 3$, "OK", "NG") = "OK"

$$M_{LLp} := 5.10 \cdot \frac{kip \cdot ft}{ft}$$

(§3.6.1.3.4) For deck overhang design with a cantilever, not exceeding 6.0ft from the centerline of the exterior girder to the face of a continuous concrete railing, the wheel loads may be replaced with a uniformly distributed line load of 1.0 KLF intensity, located 1ft from the face of the railing.

if (overhang - cw ≤ 6·ft, "OK", "NG") = "OK"

Load combination

Where traditional design based on flexure is used, the requirements for strength and service limit states shall be satisfied.

Extreme event limit state shall apply for the force effect transmitted from the bridge railing to bridge deck (§13.6.2).

Fatigue need not be investigated for concrete deck slabs in multi-girder applications (§5.5.3.1).

Strength Limit States

Load Modifier

$\eta D := 1.00$ for conventional design (§1.3.3)

$\eta R := 1.00$ for conventional level of redundancy (§1.3.4)

$\eta I := 1.00$ for typical bridges (§1.3.5)

$$\eta := \max\left(\left(\frac{\eta D \cdot \eta R \cdot \eta I}{0.95}\right)\right) \qquad \eta = 1 \qquad (§1.3.2)$$

Strength I load combination - normal vehicular load without wind (§3.4.1)

Load factors (LRFD Table 3.4.1-1 & 2):

$\gamma_p := 1.25$ for component and attachments

$\gamma DW := 1.50$ for DW

$\gamma L := 1.75$ for LL

Section Properties

Non-composite section per foot

$A_{sip} := t_{sip} \cdot 12 \cdot in$ $A_{sip} = 42\,in^2$

$I_{sip} := \frac{12 \cdot in \cdot t_{sip}^3}{12}$ $I_{sip} = 42.875\,in^4$

$Y_{bp} := \frac{t_{sip}}{2}$ $Y_{bp} = 1.75\,in$

$Y_{tp} := t_{sip} - Y_{bp}$ $S_{tp} := \frac{I_{sip}}{Y_{tp}}$ $S_{bp} := \frac{I_{sip}}{Y_{bp}}$

$Y_{tp} = 1.75\,in$ $S_{tp} = 24.5\,in^3$ $S_{bp} = 24.5\,in^3$

$E_c := 33000 \cdot \left(\frac{w_c}{kcf}\right)^{1.5} \cdot \sqrt{\frac{f'_c}{ksi}} \cdot ksi$ $E_c = 4.723 \times 10^3\ ksi$ (§5.4.2.4)

$E_{ci} := 33000 \cdot \left(\frac{w_c}{kcf}\right)^{1.5} \cdot \sqrt{\frac{f'_{ci}}{ksi}} \cdot ksi$ $E_{ci} = 4.224 \times 10^3\ ksi$

Composite Section Properties (§4.6.2.6)

$E_{cs} := 33000 \cdot \left(\frac{w_c}{kcf}\right)^{1.5} \cdot \sqrt{\frac{f'_{cs}}{ksi}} \cdot ksi$ $E_{cs} = 4.224 \times 10^3\ ksi$ (§5.4.2.4)

modular ratio, $n := \sqrt{\frac{f'_c}{f'_{cs}}}$ $n = 1.118$

$b := 12 \cdot in$

$A_{slab} := \frac{b}{n} \cdot t_{cs1}$ $Y_{bs} := t_{sip} + \frac{t_{cs1}}{2}$ $AY_{bs} := A_{slab} \cdot Y_{bs}$

	Area	Y_b	$A \cdot Y_b$
CIP slab	$A_{slab} = 48.3\ in^2$	$Y_{bs} = 5.75\ in$	$A_{slab} \cdot Y_{bs} = 277.7\ in^3$
SIP panel	$A_{sip} = 42\ in^2$	$Y_{bp} = 1.75\ in$	$A_{sip} \cdot Y_{bp} = 73.5\ in^3$

$Y_b := \frac{A_{slab} \cdot Y_{bs} + A_{sip} \cdot Y_{bp}}{A_{slab} + A_{sip}}$ $Y_b = 3.89\ in$ @ bottom of panel

$Y_t := t_{sip} - Y_b$ $Y_t = -0.39\ in$ @ top of panel

$Y_{ts} := t_{sip} + t_{cs1} - Y_b$ $Y_{ts} = 4.11\ in$ @ top of slab

$I_{slabc} := A_{slab} \cdot \left(Y_{ts} - \frac{t_{cs1}}{2}\right)^2 + \frac{\left(\frac{b}{n}\right) \cdot t_{cs1}^3}{12}$ $I_{slabc} = 248.687\ in^4$

$I_{pc} := A_{sip} \cdot \left(Y_b - Y_{bp}\right)^2 + I_{sip}$ $I_{pc} = 235.131\ in^4$

$I_c := I_{slabc} + I_{pc}$ $I_c = 483.818\ in^4$

Section modulous of the composite section

$S_b := \frac{I_c}{Y_b}$ $S_b = 124.39\ in^3$ @ bottom of panel

$S_t := \frac{I_c}{|Y_t|}$ $S_t = 1.242 \times 10^3\ in^3$ @ top of panel

$S_{ts} := n \cdot \frac{I_c}{Y_{ts}}$ $S_{ts} = 131.6\ in^3$ @ top of slab

Required Prestress

Assume the span length conservatively as the panel length, $L_{sip} = 1.932\,m$

$$M_{sip} := \frac{w_{sip} \cdot L_{sip}^2}{8} \qquad M_{sip} = 0.234\,\frac{ft \cdot kip}{ft}$$

$$M_{cip} := \frac{w_{cs} \cdot L_{sip}^2}{8} \qquad M_{cip} = 0.335\,\frac{ft \cdot kip}{ft}$$

For the superimposed dead and live loads, the force effects should be calculated based on analyzing the strip as a continuous beam supported by infinitely rigid supports (§4.6.2.1.6)

$$M_{ws} := 0 \cdot \frac{ft \cdot kip}{ft}$$

$$M_{sidl} := 0.19 \cdot \frac{kip \cdot ft}{ft} \qquad \text{(see Strudl s-dl output)}$$

$$f_b := \frac{(M_{sip} + M_{cip})\,ft}{S_{bp}} + \frac{(M_{ws} + M_{sidl} + M_{LLp}) \cdot ft}{S_b} \qquad f_b = 0.789\,ksi$$

Tensile Stress Limits

$$0.190 \cdot \sqrt{\frac{f'_c}{ksi}} \cdot ksi = 0.42\,ksi \qquad (§5.9.4.2.2)$$

$0 \cdot ksi$ WSDOT design practice

Required precompression stress at bottom fiber,

$$f_{creq} := f_b - 0 \cdot ksi \qquad f_{creq} = 0.789\,ksi$$

If P_{se} is the total effective prestress force after all losses, and the center of gravity of stands is concentric with the center of gravity of the SIP panel:

$$P_{se} := f_{creq} \cdot W_{sip} \cdot t_{sip} \qquad P_{se} = 265.184\,kip \qquad \text{per panel}$$

Assume stress at transfer,

$$f_{pi} := 0.75 \cdot f_{pu} \qquad f_{pi} = 202.5\,ksi \qquad \text{(LRFD Table 5.9.3-1)}$$

Assume 15% final losses, the final effective prestress,

$$p_{se} := f_{pi} \cdot (1 - 0.15) \qquad p_{se} = 172.125\,ksi$$

The required number of strands, $N_{req} := \frac{P_{se}}{p_{se} \cdot A_p} \qquad N_{req} = 18.125 \qquad N_p := ceil(N_{req})$

Try $N_p := 19$

Prestress Losses

Loss of Prestress (§5.9.5)

$$\Delta f_{pT} = \Delta f_{pES} + \Delta f_{pSR} + \Delta f_{pCR} + \Delta f_{pR2}$$

steel relaxation at transfer (§5.9.5.4.4b)

Curing time for concrete to attain f'ci is approximately 12 hours: set $t := 0.75$ day

Guess values: $\Delta f_{pRl} := 2.0 \cdot ksi$ $f_{pj} := 205 \cdot ksi$

Given $\Delta f_{pRl} = \frac{\log(24.0 \cdot t)}{40.0} \cdot \left(\frac{f_{pj}}{f_{py}} - 0.55 \right) \cdot f_{pj}$

$f_{pj} = 0.75 \cdot f_{pu} + \Delta f_{pRl}$ immediately prior to transfer+steel relax. (LRFD Table 5.9.3-1)

$\begin{pmatrix} f_{pj} \\ \Delta f_{pRl} \end{pmatrix} := \text{Find}(f_{pj}, \Delta f_{pRl})$ $f_{pj} = 204.4\,ksi$

$\Delta f_{pRl} = 1.87\,ksi$

Given: $A_p = 0.085\,in^2$

straight strands $N_p = 19$ jacking force, $f_{pj} \cdot N_p \cdot A_p = 330.05\,kip$

(note: these forces include initial prestress relaxation loss, see §C5.9.5.4.4b)

$A_{ps} := A_p \cdot N_p$ $A_{ps} = 1.615\,in^2$ per panel

$A_{psip} := A_{ps} \cdot \frac{ft}{W_{sip}}$ $A_{psip} = 0.202\,in^2$ per ft

c.g. of all strands to c.g. of girder, $e_p := 0 \cdot in$

Elastic Shortening, Δf_{pES} ***(§5.9.5.2.3a)***

$f_{cgp:}$ concrete stress at c.g. of prestressing tendons due to the prestressing force at transfer and the self-weight of the member at the sections of maximum moment.

Guess values: $p_{si} := 196.2 \cdot ksi$ prestress tendon stress at transfer (LRFD Table 5.9.3-1)

Given $\left(f_{pj} - \Delta f_{pRl} - p_{si}\right) \cdot \frac{E_{ci}}{E_p} = -\left[\frac{-\left(p_{si} \cdot A_{psip}\right)}{A_{sip}} \right]$ (note: used only when $e_p = 0$ in)

$p_{si} := \text{Find}(p_{si})$ $\quad p_{si} = 196.1\,\text{ksi}$

$f_{cgp} := \dfrac{-\left[p_{si}\cdot\left(A_{psip}\right)\right]}{A_{sip}}$ $\quad f_{cgp} = -0.94\,\text{ksi}$

$\Delta f_{pES} := f_{pj} - \Delta f_{pRl} - p_{si}$ $\quad \Delta f_{pES} = 6.36\,\text{ksi}$

9.3.2 Approximate Lump Sum Estimate of Time Dependent Losses (§5.9.5.3)

Time-dependent losses : $\Delta f_{pSR} + \Delta f_{pCR} + \Delta f_{pR2}$

Criteria: $\text{if}\left(f'_{ci} > 3.5\text{ksi}, \text{"OK"}, \text{"NG"}\right) = \text{"OK"}$

Normal density concrete
Concrete is either steam or moist cured
Prestressing is by low relaxation strands
Are sited in average exposure condition and temperatures

no partial prestressing $A_s := 0\cdot\text{in}^2$

partial prestress ratio (LRFD Eq. 5.5.4.2.1-2) $PPR := \dfrac{A_{ps}\cdot f_{py}}{A_{ps}\cdot f_{py} + A_s\cdot f_y}$ $\quad PPR = 1$

Approximate lump sum estimate of time-dependent losses (§5.9.5.3)

For solid slab,

$LOSS_t := 29.0\cdot\text{ksi} + 4.0\cdot\text{ksi}\cdot PPR$ (upper bound) $\quad LOSS_t = 33\,\text{ksi}$

Allowable reduction for solid slab, 6.0 ksi,

$LOSS_t := LOSS_t - 6.0\cdot\text{ksi}$ $\quad LOSS_t = 27\,\text{ksi}$

(§5.9.5.1) In pretension members where the approximate lump sum estimate of losses is used, Δf_{pR1} should be deducted from the total relaxation.

At transfer, the losses that could be accounted for are elastic shortening and steel relaxation only.

$LOSS_t := LOSS_t - \Delta f_{pRl}$ $\quad LOSS_t = 25.13\,\text{ksi}$

Loss due to Creep Δf_{pCR} ***(§5.9.5.2.3a)***

Δf_{cdp}, change in concrete stress at center of gravity of prestressing steel due to permanent loads, except the load acting at the time the prestressing force is applied. Values of Δf_{cdp} should be calculated at the same section or sections for which f_{cgp} is calculated.

$M_{cip} = 0.335\,\dfrac{\text{ft}\cdot\text{kip}}{\text{ft}}$ (act on the non-composite section)

$M_{ws} = 0\,\frac{ft \cdot kip}{ft}$ (act on the composite section)

$M_{sidl} = 0.19\,\frac{ft \cdot kip}{ft}$ (act on the composite section)

However, the weight of the CIP slab provides zero stress at the center of gravity of pretensioning force.
So, stresses due only to wearing surface and barriers are considered.

c.g. of all strands to c.g. of composite girder,

$e_{pc} := Y_b - \frac{t_{sip}}{2}$ $e_{pc} = 2.14\,in$

$\Delta f_{cdp} := \frac{(M_{sidl} + M_{ws}) \cdot ft \cdot e_{pc}}{I_c}$ $\Delta f_{cdp} = 0.01\,ksi$

$\Delta f_{pCR} := 12.0 \cdot (-f_{cgp}) - 7.0 \cdot \Delta f_{cdp}$ $\Delta f_{pCR} = 11.24\,ksi$

Total loss Δf_{pT} (note: BDM assumes a 330 MPa total loss), not including Δf_{pR1},

$\Delta f_{pT} := LOSS_t + \Delta f_{pES}$ $\Delta f_{pT} = 31.49\,ksi$

$f_{pe} := f_{pj} - \Delta f_{pRl} - \Delta f_{pT}$ $f_{pe} = 171.005\,ksi$

$\text{if}\left(f_{pe} \le 0.80 \cdot f_{py}, \text{"OK"}, \text{"NG"}\right) = \text{"OK"}$ (LRFD Table 5.9.3-1)

$P_e := \frac{N_p \cdot A_p \cdot f_{pe}}{W_{sip}}$ $P_e = 34.522\,\frac{kip}{ft}$ per foot

Stresses in the SIP Panel at Transfer

Stress Limits for Concrete

Compression: $-0.60 \cdot f'_{ci} = -2.4\,ksi$

Tension: Allowable tension with bonded reinforcement which is sufficient to resist 120% of the tension force in the cracked concrete computed on the basis of an uncracked section (§5.9.4.1.2).

$0.24 \cdot \sqrt{\frac{f'_{ci}}{ksi}} \cdot ksi = 0.48\,ksi$

or w/o bonded reinforcement,

$\min\left(\begin{pmatrix} 0.0948 \cdot \sqrt{\frac{f'_{ci}}{ksi}} \cdot ksi \\ 0.200 \cdot ksi \end{pmatrix}\right) = 0.19\,ksi$ (Controls)

Because the strand group is concentric with the precast concrete panel, the midspan section is the critical section that should be checked.

Stress at Midspan

Effective stress after transfer,

$$P_{si} := \frac{N_p \cdot A_p \cdot p_{si}}{W_{sip}} \qquad P_{si} = 39.596 \frac{kip}{ft}$$

Moment due to weight of the panel,

$$M_{sip} = 0.234 \frac{kip \cdot ft}{ft}$$

At top of the SIP panel,

$$\left(-\frac{M_{sip} \cdot ft}{S_{tp}} - \frac{P_{si} \cdot ft}{A_{sip}} \right) = -1.06\,ksi \qquad < \text{allowable} \quad -0.60 \cdot f'_{ci} = -2.4\,ksi \qquad \textbf{OK}$$

At bottom of the SIP panel,

$$\left(\frac{M_{sip} \cdot ft}{S_{bp}} - \frac{P_{si} \cdot ft}{A_{sip}} \right) = -0.83\,ksi \qquad < \text{allowable} \quad -0.60 \cdot f'_{ci} = -2.4\,ksi \qquad \textbf{OK}$$

Stresses in SIP Panel at Time of Casting Topping Slab

The total prestress after all losses,

$$P_e = 34.522 \frac{kip}{ft}$$

Stress Limits for Concrete

Flexural stresses due to unfactored construction loads shall not exceed 65% of the 28-day compressive strength for concrete in compression or the modulus of rupture in tension for prestressed concrete form panels (§9.7.4.1).

The construction load shall be taken to be less than the weight of the form and the concrete slab plus 0.050 KSF.
For load combination Service I:

Compression: $-0.65 \cdot f'_c = -3.25\,ksi$

Tension: Modulous of rupture,

$$f_r := 0.24 \cdot \sqrt{\frac{f'_c}{ksi}} \cdot ksi \qquad f_r = 0.537\,ksi$$

Stresses at Midspan after all Non-Composite Loads

$$M_{sip} = 0.234\,\frac{ft\cdot kip}{ft}$$

$$M_{cip} = 0.335\,\frac{ft\cdot kip}{ft}$$

$$M_{const} := 0.050\cdot\frac{kip}{ft^2}\,\frac{L_{sip}^{\,2}}{8} \qquad M_{const} = 0.251\,\frac{ft\cdot kip}{ft}$$

At top of the SIP panel,

$$\left[-\frac{\left(M_{sip}+M_{cip}+M_{const}\right)\cdot ft}{S_{tp}}-\frac{P_e\cdot ft}{A_{sip}}\right] = -1.22\,ksi \quad < \text{allowable} \quad -0.65\cdot f'_c = -3.25\,ksi \qquad \textbf{OK}$$

At bottom of the SIP panel,

$$\left[\frac{\left(M_{sip}+M_{cip}+M_{const}\right)\cdot ft}{S_{bp}}-\frac{P_e\cdot ft}{A_{sip}}\right] = -0.42\,ksi \quad < \text{allowable} \quad -0.65\cdot f'_c = -3.25\,ksi \qquad \textbf{OK}$$

Elastic Deformation (§9.7.4.1)

Deformation due to

$$\Delta := \frac{5}{48}\cdot\frac{\left(M_{sip}+M_{cip}\right)\cdot ft\cdot L_{sip}^{\,2}}{E_c\cdot I_{sip}} \qquad \Delta = 0.02\,in$$

$$\text{if}\left[\Delta \le \left|\begin{array}{ll}\min\left(\left(\frac{L_{sip}}{180}\quad 0.25\cdot in\right)\right) & \text{if } L_{sip}\le 10\cdot ft \quad ,\text{"OK"},\text{"NG"}\\ \min\left(\left(\frac{L_{sip}}{240}\quad 0.75\cdot in\right)\right) & \text{otherwise}\end{array}\right.\right] = \text{"OK"}$$

Stresses in SIP Panel at Service Loads

Compression:

- Stresses due to permanent loads

  $-0.45\cdot f'_c = -2.25\,ksi$ for SIP panel

  $-0.45\cdot f'_{cs} = -1.8\,ksi$ for CIP panel

- Stresses due to permanent and transient loads

  $-0.60\cdot f'_c = -3\,ksi$ for SIP panel

  $-0.60\cdot f'_{cs} = -2.4\,ksi$ for CIP panel

- Stresses due to live load + one-half of the permanent loads

$-0.40 \cdot f'_c = -2\,ksi$ for SIP panel

$-0.40 \cdot f'_{cs} = -1.6\,ksi$ for CIP panel

Tension:

$0.0948 \cdot \sqrt{\frac{f'_c}{ksi}} \cdot ksi = 0.21\,ksi$ (§5.9.4.2.2)

$0 \cdot ksi$ WSDOT design practice

Service Load Stresses at Midspan

- *Compressive stresses at top of CIP slab*

Stresses due to permanent load + prestressing

$-\frac{(M_{ws} + M_{sidl}) \cdot ft}{S_{ts}} = -0.017\,ksi$ < allowable $-0.45 \cdot f'_{cs} = -1.8\,ksi$ **OK**

Stresses due to permanent and transient loads,

$-\frac{(M_{ws} + M_{sidl} + M_{LLp}) \cdot ft}{S_{ts}} = -0.48\,ksi$ < allowable $-0.60 \cdot f'_{cs} = -2.4\,ksi$ **OK**

- *Compressive stresses at top of the SIP panel*

Stresses due to permanent load + prestressing

$-\left(\frac{P_e \cdot ft}{A_{sip}}\right) - \frac{(M_{sip} + M_{cip}) \cdot ft}{S_{tp}} - \frac{(M_{ws} + M_{sidl}) \cdot ft}{S_t} = -1.1\,ksi$ < allowable $-0.45 \cdot f'_c = -2.25\,ksi$ **OK**

Stresses due to permanent and transient loads,

$-\left(\frac{P_e \cdot ft}{A_{sip}}\right) - \frac{(M_{sip} + M_{cip}) \cdot ft}{S_{tp}} - \frac{(M_{ws} + M_{sidl} + M_{LLp}) \cdot ft}{S_t} = -1.15\,ksi$ < allowable $-0.60 \cdot f'_c = -3\,ksi$ **OK**

Stresses due to live load + one-half the sum of effective prestress and permanent loads,

$-0.5 \cdot \left(\frac{P_e \cdot ft}{A_{sip}}\right) - \frac{0.5 \cdot (M_{sip} + M_{cip}) \cdot ft}{S_{tp}} - \frac{(0.5 \cdot M_{ws} + 0.5 \cdot M_{sidl} + M_{LLp}) \cdot ft}{S_t} = -0.6\,ksi$

< allowable $-0.40 \cdot f'_c = -2\,ksi$ **OK**

- *Tensile stresses at bottom of the SIP panel*

  Stresses due to permanent and transient loads,

$$-\left(\frac{P_e \cdot ft}{A_{sip}}\right) + \frac{\left(M_{sip} + M_{cip}\right)\cdot ft}{S_{bp}} + \frac{\left(M_{ws} + M_{sidl} + M_{LLp}\right)\cdot ft}{S_b} = -0.03\,ksi$$

$$< \text{allowable} \qquad 0.0948\cdot\sqrt{\frac{f'_c}{ksi}}\cdot ksi = 0.21\,ksi \qquad \textbf{OK}$$

$$0\cdot ksi \quad \text{(BDM)}$$

9.8.11 Flexural Strength of Positive Moment Section

Resistance factors (§5.5.4.2.1)

$\phi_f := 0.90$ for flexure and tension of reinforced concrete

$\phi_p := 1.00$ for flexure and tension of prestressed concrete

$\phi_v := 0.90$ for shear and torsion

Ultimate Moment Required for Strength I

Dead load moment,

$$M_{DC} := M_{sip} + M_{cip} + M_{sidl} \qquad M_{DC} = 0.759\,\frac{kip\cdot ft}{ft}$$

Wearing surface load moment,

$$M_{ws} = 0\,\frac{kip\cdot ft}{ft}$$

Live load moment,

$$M_{LLp} = 5.1\,\frac{kip\cdot ft}{ft}$$

$$M_u := \eta\cdot\left(\gamma_p\cdot M_{DC} + \gamma_{DW}\cdot M_{ws} + \gamma_L\cdot M_{LLp}\right) \qquad M_u = 9.874\,\frac{kip\cdot ft}{ft}$$

Flexural Resistance (§5.7.3)

Find stress in prestressing steel at nominal flexural resistance, f_{ps} (§5.7.3.1.1)

$$f_{pe} = 171.005\,ksi \qquad 0.5\cdot f_{pu} = 135\,ksi$$

$$\text{if}\left(f_{pe} \geq 0.5\cdot f_{pu}, \text{"OK"}, \text{"NG"}\right) = \text{"OK"}$$

$$k := 2\cdot\left(1.04 - \frac{f_{py}}{f_{pu}}\right) \qquad k = 0.28 \qquad \text{(LRFD Eq. 5.7.3.1.1-2)}$$

$$A_s := 0\cdot in^2$$

$A'_s := 0 \cdot in^2$ (conservatively)

d_p, distance from extreme compression fiber to the centroid of the prestressing tendons,

$$d_p := t_{s1} - 0.5 \cdot t_{sip} \qquad d_p = 6.25\,in$$

$W_{sip} = 96\,in$ effective width of compression flange

$$\beta_1 := if\left[f'_{cs} \le 4 \cdot ksi, 0.85, 0.85 - 0.05 \cdot \left(\frac{f'_{cs} - 4.0 \cdot ksi}{1.0 \cdot ksi} \right) \right] \qquad \beta_1 := \begin{cases} \beta_1 & \text{if } \beta_1 \ge 0.65 \\ 0.65 & \text{otherwise} \end{cases}$$

$\beta_1 = 0.85$ (§5.7.2.2)

Assume rectangular section,

$$c := \frac{A_{ps} \cdot f_{pu}}{0.85 \cdot f'_{cs} \cdot \beta_1 \cdot W_{sip} + k \cdot A_{ps} \cdot \frac{f_{pu}}{d_p}} \qquad c = 1.47\,in$$

Stress in prestressing steel at nominal flexural resistance, f_{ps} (§5.7.3.1.1),

$$f_{ps} := f_{pu} \cdot \left(1 - k \cdot \frac{c}{d_p} \right) \qquad f_{ps} = 252.24\,ksi$$

Check stress in prestressing steel according to available development length, l_d

Available development length at midspan of the SIP panel,

$$l_d := 0.5 \cdot L_{sip} \qquad l_d = 0.966\,m$$

rearranging LRFD eq. 5.11.4.1-1

$$f_{psld} := \frac{l_d}{1.6 \cdot d_b} \cdot ksi + \frac{2}{3} \cdot f_{pe} \qquad f_{psld} = 177.404\,ksi$$ (may be too conservative)

$$f_{ps} := \min\left(\left(f_{ps} \;\; f_{psld} \right) \right) \qquad f_{ps} = 177.404\,ksi$$

Flexural Resistance (§5.7.3.2.2 & 5.7.3.2.2),

$a := \beta_1 \cdot c$ $a = 1.25\,in$ $A_{ps} = 1.615\,in^2$ per panel

$$M_n := A_{ps} \cdot f_{ps} \cdot \left(d_p - \frac{a}{2} \right)$$

$M_n = 134.3\,kip \cdot ft$

$M_r := \phi_p \cdot M_n$ $M_r = 134.3\,kip \cdot ft$ per panel

$M_r := \frac{M_r}{W_{sip}}$ $M_r = 16.79 \frac{kip \cdot ft}{ft}$ per ft

$M_u \le M_r = 1$ **OK** where $M_u = 9.874 \frac{kip \cdot ft}{ft}$

Limits of Reinforcement

Maximum Reinforcement (§5.7.3.3.1)

$d_e := \frac{A_{ps} \cdot f_{ps} \cdot d_p}{A_{ps} \cdot f_{ps}}$ $d_e = 6.25\,in$

The maximum amount of prestressed and non-prestressed reinforcement shall be such that

$\frac{c}{d_e} \le 0.42 = 1$ OK, where $\frac{c}{d_e} = 0.23$

The section is not over-reinforced. Over-reinforced reinforced concrete sections shall not be permitted.

Minimum Reinforcement (§5.7.3.3.2)

AASHTO 9.18.2

Compressive stress in concrete due to effective prestress force (after all losses) at midspan

$f_{peA} := \frac{P_e \cdot ft}{A_{sip}}$ $f_{peA} = 0.82\,ksi$ (compression)

Non-composite dead load moment at section, M_{dnc},

$M_{dnc} := M_{cip} + M_{sip}$ $M_{dnc} = 0.569 \frac{kip \cdot ft}{ft}$

$f_r = 0.537\,ksi$ use SIP panel

$M_{cr} := \left(f_r + f_{peA}\right) \cdot \frac{S_b}{ft} - M_{dnc} \cdot \left(\frac{S_b}{S_{bp}} - 1\right)$ $1.2 \cdot M_{cr} = 14.114 \frac{kip \cdot ft}{ft}$

$M_r \ge 1.2 \cdot M_{cr} = 1$ **OK** where $M_r = 16.79 \frac{kip \cdot ft}{ft}$

Negative Moment Section Over Interior Beams

Deck shall be subdivided into strips perpendicular to the supporting components (§4.6.2.1.1).
Continuous beam with span length as center to center of supporting elements (§4.6.2.1.6).
Wheel load may be modeled as concentrated load or load based on tire contact area.
Strips should be analyzed by classical beam theory.

Spacing in secondary direction (spacing between diaphragms):

$L_d := \frac{L}{1.0}$ $L_d = 27.149\,m$

Spacing in primary direction (spacing between girders):

$S = 2.057\,m$

Since $\frac{L_d}{S} \geq 1.50 = 1$, where $\frac{L_d}{S} = 13.2$ (§4.6.2.1.5)

therefore, all the wheel load shall be applied to primary strip. Otherwise, the wheels shall be distributed between intersecting strips based on the stiffness ratio of the strip to sum of the strip stiffnesses of intersecting strips.

Critical Section

The design section for negative moments and shear forces may be taken as follows:

Prestressed girder - shall be at 1/3 of flange width < 15 in.

Steel girder - 1/4 of flange width from the centerline of support.

Concrete box beams - at the face of the web.

top flange width $b_f := 15.06 \cdot in$

Design critical section for negative moment and shear shall be at d_c, (§4.6.2.1.6)

$d_c := \min\left(\left(\frac{1}{3} \cdot b_f \quad 15 \cdot in\right)\right)$ $d_c = 5\,in$ from CL of girder (may be too conservative, see training notes)

Maximum factored moments **per unit width** based on Table A4-1: for $S = 2.057\,m$

(include multiple presence factors and the dynamic load allowance)

applicability $\text{if}\left[\min\left(\left(0.625 \cdot S \quad 6 \cdot ft\right)\right) \geq \text{overhang} - cw, \text{"OK"}, \text{"NG"}\right] = \text{"OK"}$

$\text{if}\left(N_b \geq 3, \text{"OK"}, \text{"NG"}\right) = \text{"OK"}$

$M_{LLn} := 4.00 \cdot \frac{kip \cdot ft}{ft}$ (max. -M at d_c from CL of girder)

Dead load moment (STRUDL s-dl output)

$M_{DCn} := 0.18 \cdot \frac{kip \cdot ft}{ft}$ (dead load from deck overhang and sidl only, max. -M at d_c at interior girder, conservative) $\frac{d_c}{S} = 0.062$

$M_{wsn} := 0 \cdot \frac{kip \cdot ft}{ft}$

Service negative moment

$M_{sn} := M_{DCn} + M_{wsn} + M_{LLn}$ $M_{sn} = 4.18 \frac{kip \cdot ft}{ft}$

Factored negative moment

$$M_{un} := \eta \cdot \left(\gamma_p \cdot M_{DCn} + \gamma_{DW} \cdot M_{wsn} + \gamma_L \cdot M_{LLn}\right) \qquad M_{un} = 7.23 \frac{kip \cdot ft}{ft}$$

Design of Section

Normal flexural resistance of a rectangular section may be determined by using equations for a flanged section in which case b_w shall be taken as b (§5.7.3.2.3).

$$\beta_1 := if\left[f'_{cs} \le 4 \cdot ksi, 0.85, 0.85 - 0.05 \cdot \left(\frac{f'_{cs} - 4.0 \cdot ksi}{1.0 \cdot ksi}\right)\right] \qquad \beta_1 := \begin{cases} \beta_1 & \text{if } \beta_1 \ge 0.65 \\ 0.65 & \text{otherwise} \end{cases}$$

$\beta_1 = 0.85$ (§5.7.2.2) conservatively use CIP slab concrete strength

assume bar # $bar_n := 5$

$$dia(bar) := \begin{cases} 0.5 \cdot in & \text{if } bar = 4 \\ 0.625 \cdot in & \text{if } bar = 5 \\ 0.75 \cdot in & \text{if } bar = 6 \\ 0.875 \cdot in & \text{if } bar = 7 \end{cases}$$

$$d_n := t_{s2} - 2.5 \cdot in - \frac{dia(bar_n)}{2} \qquad d_n = 5.688\,in$$

$$A_s := \frac{0.85 \cdot f'_{cs} \cdot ft}{f_y} \cdot \left(d_n - \sqrt{d_n^2 - \frac{2 \cdot M_{un} \cdot ft}{0.85 \cdot \phi_f \cdot f'_{cs} \cdot ft}}\right) \qquad A_s = 0.29\,in^2 \quad \text{per ft}$$

use (top-transverse) bar # $bar_n = 5$ $s_n := 9 \cdot in$

$$A_b(bar) := \begin{cases} 0.20 \cdot in^2 & \text{if } bar = 4 \\ 0.31 \cdot in^2 & \text{if } bar = 5 \\ 0.44 \cdot in^2 & \text{if } bar = 6 \\ 0.60 \cdot in^2 & \text{if } bar = 7 \end{cases}$$

$$A_{sn} := A_b(bar_n) \cdot \frac{1 \cdot ft}{s_n} \qquad A_{sn} = 0.41\,in^2 \quad \text{per ft}$$

Maximum Reinforcement (§5.7.3.3.1)

The max. amount of prestressed and non-prestressed reinforcement shall be such that

where $d_e := d_n$

$$c := \frac{A_{sn} \cdot f_y}{0.85 \cdot \beta_1 \cdot f'_{cs} \cdot 1 \cdot ft} \qquad c = 0.72\,in$$

$$if\left(\frac{c}{d_e} \le 0.42, "OK", "NG"\right) = "OK" \qquad \frac{c}{d_e} = 0.126$$

The section is not over-reinforced. Over-reinforced reinforced concrete sections shall not be permitted.

Minimum Reinforcement (§5.7.3.3.2)

$f_{rs} := 0.24 \cdot \sqrt{\frac{f'_{cs}}{ksi}} \cdot ksi$ $\quad f_{rs} = 0.48\,ksi$ use SIP panel concrete strength

$n := \frac{E_s}{E_{cs}}$ $\quad n = 6.866$ $\quad n := max[\,[\,ceil((n - 0.495))\quad 6\,]\,]$

$n = 7$ set $n = 7$ (round to nearest integer, §5.7.1, not less than 6)

$(n - 1)A_{sn} = 2.48\,in^2$

$A_{gc} := t_{s2} \cdot ft$ $\quad A_{gc} = 102\,in^2$

$d_s := 2.5in + 0.625 \cdot in + 0.5 \cdot 0.75 \cdot in$ c.g. of reinforcement to top of slab $\quad d_s = 3.5\,in$

$$Y_{ts} := \frac{A_{gc} \cdot 0.5 \cdot t_{s2} + (n - 1) \cdot A_{sn} \cdot d_s}{A_{gc} + (n - 1) \cdot A_{sn}} \qquad Y_{ts} = 4.232\,in$$

$$I_{cg} := \frac{ft \cdot (t_{s2})^3}{12} + A_{gc} \cdot (0.5 \cdot t_{s2} - Y_{ts})^2 + (n - 1)A_{sn} \cdot (Y_{ts} - d_s)^2 \qquad I_{cg} = 615.487\,in^4$$

$$M_{cr} := \frac{f_{rs} \cdot I_{cg}}{Y_{ts}} \qquad M_{cr} = 5.817\,kip \cdot ft \qquad 1.2 \cdot M_{cr} = 6.981\,kip \cdot ft$$

$if(M_{un} \cdot ft \ge 1.2 \cdot M_{cr}, "OK", "NG") = "OK"$

Crack Control (§5.7.3.4)

$$M_{sn} = 4.18\,\frac{kip \cdot ft}{ft}$$

$n := \frac{E_s}{E_{cs}}$ $\quad n = 6.866$ $\quad n := ceil((n - 0.495))$ use slab concrete strength

set $n = 7$ (round to nearest integer, §5.7.1)

$\rho := \frac{A_{sn}}{ft \cdot d_n}$ $\rho = 6.056 \times 10^{-3}$

$k(\rho) := \sqrt{(\rho \cdot n)^2 + 2 \cdot \rho \cdot n} - \rho \cdot n$ $k(\rho) = 0.252$

$j(\rho) := 1 - \frac{k(\rho)}{3}$ $j(\rho) = 0.916$

$f_{sa} := \frac{M_{sn} \cdot ft}{A_{sn} \cdot j(\rho) \cdot d_n}$ $f_{sa} = 23.293\,ksi$

$Z := 130 \cdot \frac{kip}{in}$ crack width parameter in severe exposure condition

$d_c := 2 \cdot in + 0.5 \cdot dia(bar_n)$ $d_c = 2.313\,in$ max.

$A := 2 \cdot d_c \cdot s_n$ $A = 41.625\,in^2$

$$if\left[\min\left[\left[\frac{Z}{(d_c \cdot A)^{\frac{1}{3}}}\right], 0.6 \cdot f_y\right] \geq f_{sa}, "OK", "NG"\right] = "OK"$$ where $\min\left[\left[\frac{Z}{(d_c \cdot A)^{\frac{1}{3}}}\right], 0.6 \cdot f_y\right] = 28.366\,ksi$

say OK

Shrinkage and Temperature Reinforcement (§5.10.8.2)

For components less than 48 in. thick,

where $A_g := t_{s2} \cdot 1 \cdot ft$

$A_{tem} := 0.11 \cdot \frac{A_g \cdot ksi}{f_y}$ $A_{tem} = 0.187\,in^2$ per ft

The spacing of this reinforcement shall not exceed $3 \cdot t_{s1} = 24\,in$ or 18 in.

top longitudinal - $bar := 4$ $s := 12 \cdot in$ $A_s := A_b(bar) \cdot \frac{1 \cdot ft}{s}$ $A_s = 0.2\,in^2$ per ft **OK**

Distribution of Reinforcement (§9.7.3.2)

The effective span length S_{eff} shall be taken as (§9.7.2.3):

web thickness $b_w := 7 \cdot in$

top flange width $b_f = 15.06\,in$

$$S_{eff} := S - b_f + \frac{b_f - b_w}{2} \qquad S_{eff} = 5.831\,ft$$

For primary reinforcement perpendicular to traffic:

$$percent := \min\left(\left(\frac{220}{\sqrt{\frac{S_{eff}}{ft}}}\quad 67\right)\right) \qquad percent = 67$$

Bottom longitudinal reinforcement (convert to equivalent mild reinforcement area):

$$A_s := \frac{percent}{100}\cdot\frac{A_{ps}}{W_{sip}}\cdot\frac{f_{py}}{f_y} \qquad A_s = 0.55\,\frac{in^2}{ft} \qquad \text{per ft}$$

use bar # $bar := 5$ $s := 6.0\cdot in$ $A_s := A_b(bar)\cdot\frac{1\cdot ft}{s}$ $A_s = 0.62\,in^2$ per ft **OK**

Maximum bar spacing (§5.10.3.2)

Unless otherwise specified, the spacing of the primary reinforcement in walls and slabs shall not exceed 1.5 times the thickness of the member or 18 in.. The maximum spacing of temperature shrinkage reinforcement shall be as specified in §5.10.8.

$1.5\cdot t_{s1} = 12\,in$ **OK**

Protective Coating (§5.12.4)

Epoxy coated reinforcement shall be used for slab top layer reinforcements except when the slab is overlayed with asphalt.

Ribbed Girder Design Example
5' Wide Trideck, 65' Span Length

All dimensions are in kips and inches except bending moments which are measured in kip-feet

Material Properties

Concrete

$f_c := 8.0$

$f_{ci} := 6.5$

$E_c := 5696$

$E_{ci} := 5134$

$f_r := 0.68$

$\rho := 160$

$\mu := 0.2$

Prestressing Steel

$f_{pu} := 270$

$f_{py} := 243$

$E_p := 28500$

Reinforcing Steel

$f_y := 60$

$E_s := 29000$

Composite Action

$n := \frac{E_p}{E_c}$

$n_i := \frac{E_p}{E_{ci}}$

Geometric Properties of Tribeam

$A_g := 746$

$I_g := 46406$

$S_b := \frac{I_g}{y_b}$

$S_t := \frac{I_g}{(h - y_b)}$

$y_b := 17.16$

$h := 27$

$b := 60$ (5' wide section)

$L := 65 \cdot 12$ (65' span)

Permanent Loads

$w_{dl} := 0.829$

$w_{sdl} := 0.175$ } kips/ft (assumes 3' overlay)

Design Load Effects (calculated at midspan)

$M_{dl} := \frac{w_{dl}}{8} \cdot \left(\frac{L}{12}\right)^2$ $M_{dl} = 437.82$

$M_{sdl} := \frac{w_{sdl}}{8} \cdot \left(\frac{L}{12}\right)^2$ $M_{sdl} = 92.42$

$M_{ll} := 2 \cdot .227 \cdot 1525$ $M_{ll} = 692.35$ (LL DF for two loaded lanes)

$M_{serviceI} := M_{dl} + M_{sdl} + M_{ll}$ $M_{serviceI} = 1222.59$

$M_{serviceIII} := M_{dl} + M_{sdl} + 0.8 \cdot M_{ll}$ $M_{serviceIII} = 1084.12$

Prestressing Geometry

$A_{str} := 0.153$ $y_{bps} := 5.0$ (y_{bps} is "F")

$d_{strand} := 0.5$ $e := y_b - y_{bps}$

$N_{strand} := 33$ $A_{ps} := N_{strand} \cdot A_{str}$ $A_{ps} = 5.05$

Transformed Section Properties (between harp pts.)

$A_{net} := A_g - A_{ps}$ $A_{net} = 740.95$

$$y_{bt} := \frac{\left[y_b A_{net} + y_{bps} \cdot (n-1) \cdot A_{ps} \right]}{A_{net} + (n-1) \cdot A_{ps}} \qquad y_{bt} = 16.84$$

$I_t := I_g + A_g \cdot (y_b - y_{bt})^2 + (n-1) \cdot A_{ps} \cdot (y_{bt} - y_{bps})^2$ $I_t = 49316.07$

$$S_{bt} := \frac{I_t}{y_{bt}} \qquad S_{bt} = 2929.02$$

$$S_{tt} := \frac{I_t}{h - y_{bt}} \qquad S_{tt} = 4852.55$$

$e_t := y_{bt} - y_{bps}$ $e_t = 11.84$

Prestress Forces

$f_{pi} := 0.75 \cdot f_{pu}$

$P_{jack} := 0.75 \cdot f_{pu} \cdot A_{ps}$ $P_{jack} = 1022.42$ (strand jacking force)

$P_{si} := 0.69 \cdot f_{pu} \cdot A_{ps}$ $P_{si} = 940.63$ (initial p/s force)

Elastic Shortening Losses

$$f_{cgp} := \left(\frac{P_{si}}{A_{net}} \right) + \left(P_{si} \cdot \frac{e^2}{I_g} \right) - \left(12 M_{dl} \cdot \frac{e_t}{I_g} \right) \qquad f_{cgp} = 2.93$$

$$\Delta f_{pinstant} := \left(\frac{E_p}{E_{ci}} \right) \cdot f_{cgp} \qquad \Delta f_{pinstant} = 16.25$$

Time Dependent Losses

$$\Delta f_{td} := 37 \cdot \left[1 - 0.15 \cdot \frac{(f_c - 6)}{6} \right] \qquad \Delta f_{td} = 35.15$$

$\Delta f_{total} := \Delta f_{pinstant} + \Delta f_{td}$ $\Delta f_{total} = 51.40$

$P_{se} := (f_{pi} - \Delta f_{total}) \cdot A_{ps}$ $\boxed{P_{se} = 762.92}$ (p/s force after losses)

Service I and Service III Limit States

Bottom Fiber Stress at Midspan: (compression is negative)

$$f_b := P_{se}\cdot\left(\frac{e}{S_b} + \frac{1}{A_{net}}\right) - \left(\frac{12M_{serviceIII}}{S_{bt}}\right)$$

$f_b = 0.02$ 0 Allowable

(BDM 6.2.3-2)

Top Fiber Stress at Midspan

		Allowable
$f_{tI} := P_{se}\cdot\left(\frac{1}{A_{net}} - \frac{e}{S_t}\right) + 12\cdot\frac{M_{dl} + M_{sdl}}{S_{tt}}$	$f_{tI} = 0.37$	$0.45\cdot f_c = 3.60$
$f_{tII} := P_{se}\cdot\left(\frac{1}{A_{net}} - \frac{e}{S_t}\right) + 12\cdot\left(\frac{.5M_{dl} + M_{ll}}{S_{tt}}\right)$	$f_{tII} = 1.32$	$0.4\cdot f_c = 3.20$
$f_{tIII} := P_{se}\cdot\left(\frac{1}{A_{net}} - \frac{e}{S_t}\right) + 12\cdot\frac{M_{serviceI}}{S_{tt}}$	$f_{tIII} = 2.09$	$0.6\cdot f_c = 4.80$

(BDM 6.2.3-2)

Strength Limit State

Strength I Load Effect at Midspan

$$M_u := 1.25\cdot M_{dl} + 1.5\cdot M_{sdl} + 1.75\cdot M_{ll}$$

$M_u = 1897.51$

(LRFD 3.4.1-1)

Bonded Steel Stress

$k := 0.28$ low relaxation steel

$$c := \frac{\left(A_{ps}\cdot f_{pu}\right)}{\left[0.85\cdot 0.85\cdot f_c\cdot b + k\cdot A_{ps}\cdot\frac{f_{pu}}{\left(h - y_{bps}\right)}\right]}$$

$c = 3.74$

$a := 0.85\cdot c$

$$f_{ps} := f_{pu}\cdot\left[1 - k\cdot\frac{c}{\left(h - y_{bps}\right)}\right]$$

$f_{ps} = 257.14$

Flexural Capacity at Midspan

$\phi := 1.0$

$$\phi M_n := \phi\cdot A_{ps}\cdot f_{ps}\cdot\left(h - y_{bps} - \frac{a}{2}\right)\cdot\frac{1}{12}$$

$\phi M_n = 2208.04$

$\phi M_n > M_u$ **OK**

Service I Limit State, Prestressing Steel

$$\Delta f_{ps} := n\cdot\left(\frac{e}{y_{bt}}\right)\cdot\left[12\cdot\frac{\left(M_{ll}+M_{sdl}\right)}{S_{bt}}\right] \qquad \Delta f_{ps} = 11.62$$

$$f_{psservice} := f_{pi} - \Delta f_{total} + \Delta f_{ps} \qquad \boxed{f_{psservice} = 162.72}$$

$0.8\cdot f_{py} = 194.40$ maximum **(LRFD 5.9.3)** **OK**

Reinforcement Limits

Maximum RF

$$\frac{c}{\left(h - y_{bps}\right)} = 0.17$$ 0.42 maxmimum **(LRFD 5.7.3.3.1-1)** **OK**

Mimumum RF

$$f_{cpe} := P_{se}\cdot\left(\frac{1}{A_{net}} + \frac{e}{S_b}\right) \qquad f_{cpe} = 4.46$$

$$M_{cr} := \frac{S_{bt}\cdot\left(f_{cpe} - f_r\right)}{12} \qquad 1.2M_{cr} = 1107.22$$

$1.33\cdot M_u = 2523.69$

$\phi M_n = 2208.04$ Greater than the lesser of 1.2 M_{cr} and 1.33 M_u **(LRFD 5.7.3.3.2)** **OK**

Transformed Section at Endblock (at transfer, $E=E_{ci)}$

$y_{bsend} := 12$ (y_b of steel at end block)

$e_{end} := y_b - y_{bsend}$ $e_{end} = 5.16$

$$y_{btend} := \frac{\left[y_b A_g + \left(n_i - 1\right)\cdot y_{bsend}\cdot A_{ps}\right]}{\left(n_i - 1\right)\cdot A_{ps} + A_g} \qquad y_{btend} = 17.01$$

$$I_{tend} := I_g + A_g\cdot\left(y_b - y_{btend}\right)^2 + \left(n_i - 1\right)\cdot A_{ps}\cdot\left(y_{btend} - y_{bsend}\right)^2 \qquad I_{tend} = 46999.55$$

$$S_{btend} := \frac{I_{tend}}{y_{btend}} \qquad S_{btend} = 2763.74$$

$$S_{ttend} := \frac{I_{tend}}{h - y_{btend}} \qquad S_{ttend} = 4702.69$$

$e_{tend} := y_{btend} - y_{bsend}$ $e_{tend} = 5.01$

Concrete Stresses at Transfer

$P_i := \left(f_{pi} - \Delta f_{pinstant}\right) \cdot A_{ps}$ $P_i = 940.40$

$l_t := 60 \cdot d_{strand}$

$y_{bpslt} := y_{bps} + \left(y_{bsend} - y_{bps}\right) \cdot \left[\frac{\left(L - l_t\right)}{L}\right]$ $y_{bpslt} = 11.73$

$e_{lt} := y_{btend} - y_{bpslt}$ $e_{lt} = 5.28$

P/S Load Effects at Transfer

$M_{harp} := w_{dl} \cdot \frac{3 \cdot \left(\frac{L}{12}\right)^2}{25}$ $M_{harp} = 420.30$

$M_{lt} := \frac{w_{dl}}{144} \cdot l_t \cdot \left(L - l_t\right)$ $M_{lt} = 129.53$

Allowable Stresses:

Tension < -0.200 Compression $0.6 \cdot f_{ci} = 3.90$ **(BDM 6.2.3-2)**

Top Fiber at Transfer Length from Endblock

$f_{tlt} := P_i \cdot \left(\frac{1}{A_{net}} - \frac{e_{lt}}{S_t}\right) + 12 \cdot \frac{M_{lt}}{S_{ttend}}$ $f_{tlt} = 0.183$ **OK**

Bottom Fiber at Transfer Length

$f_{blt} := P_i \cdot \left(\frac{1}{A_{net}} + \frac{e_{lt}}{S_b}\right) - 12 \frac{M_{lt}}{S_{btend}}$ $f_{blt} = 2.54$ **OK**

Top Fiber at Harp Point

$f_{tharp} := P_i \cdot \left(\frac{1}{A_{net}} - \frac{e}{S_t}\right) + \frac{12 \cdot M_{harp}}{S_{tt}}$ $f_{tharp} = -0.12$ **OK**

Bottom Fiber at Harp Point

$f_{bharp} := P_i \cdot \left(\frac{1}{A_{net}} + \frac{e}{S_b}\right) - 12 \cdot \frac{M_{harp}}{S_{bt}}$ $f_{bharp} = 3.78$ **OK**

Camber and Deflection

At Release:

Prestress Effect:

$a := 0.3 \cdot L$

$e_h := y_b - y_{bps} - y_{bsend}$

$$\Delta_{ps} := \frac{P_{si}}{E_{ci} \cdot I_t} \cdot \left(\frac{e \cdot L^2}{8} - \frac{e_h \cdot a^2}{6} \right) \qquad \Delta_{ps} = 3.43$$

Dead Load Effect:

$$\Delta_{dl} := -\frac{5 \cdot \frac{w_{dl}}{12} \cdot L^4}{384 \cdot E_{ci} \cdot I_t} \qquad \Delta_{dl} = -1.32$$

Superimposed Loads

$$\Delta_{SDL} := \frac{-5 \cdot \frac{w_{sdl}}{12} \cdot L^4}{384 \cdot E_{ci} \cdot I_t} \qquad \Delta_{SDL} = -0.28$$

$\Delta 1$

$\Delta_1 := \Delta_{ps} + \Delta_{dl}$ $\qquad \Delta_1 = 2.12$

$\Delta 2000$

$\Delta_{2000} := 2.70 \cdot \Delta_{dl} + 2.45 \cdot \Delta_{ps}$ $\qquad \Delta_{2000} = 4.85$

ΔSDL

$\Delta_{SDL} := 3.00 \cdot \Delta_{SDL}$ $\qquad \Delta_{SDL} = -0.83$

Excess Camber: $\boxed{\Delta_{2000} + \Delta_{SDL} = 4.02}$ Multipliers from **BDM 6.1.8**

Design Example 5 Solid and Voided Slab Design

Prestressed Voided Slab Design

AASHTO LRFD Specifications

General Input								Specification Reference
Girder type:	26 Inch Prestressed Precast Voided Slab							Prelim.Plan, Sh 1
Span Length:	L =	45.00	ft	C.L. to C.L. Bearing				BDM 6.3.1A
Bridge Width:		44.00	ft	Deck Width				Prelim.Plan, Sh 1
Number of Lanes		3						"
Skew Angle:	θ_{skew} =	0.00	degrees					"
Girder Width:	b =	4.00	ft	=	48.00	in		BDM 6.6-A3-1
Girder Depth:	h or d =	26	in	=	2.17	ft	**OK**	"
Number of Voids	N_v =	2						"
Void Diameter:	dia_v =	15.7	in					"
Number of girders:	N_b =	11		Assumed ACP added =				Prelim.Plan Sh 2
Weight of barrier:	w_{TB} =	0.50	k/ft			0.20	in.	BDM 8.3-A10
Weight of Overlay (3" Asphalt)		0.040	k/ft^2	$ACP_{min.}$ =		3.00	in.	
Strength of Concrete				$ACP_{applied}$ =		3.20	in.	
Final	f_c' =	7.0	ksi	Transfer	f_{ci}' =	6.0	ksi	00 BDM 6.6-A3-2

Prestressing Input					Reference
Strand diam., d_b =	0.50 in	Area =	0.153	in^2	BDM 6.6-A3-1
Number of Bonded Strands ~2 in from Bottom			14		See Strand Layout Worksheet
Number of Bonded Strands ~4 in from Bottom			0	Eccentricity (E)	
Number of Bonded Strands ~6 in from Bottom			0	**E = 7.18 in**	
Number of Debonded Bottom Strands			4	**OK** **OK**	
Total Number of Bottom Strands			18	≤ 42	**OK**
Total Number of Top Strands			4	≤ 6	**OK**

(Back to Table of Contents)

Output				
HS20-44 Force Effect:	**Jacking Force, P_j =**	**691**	**kips**	See Section 9
Live Load Force Effect:	Moment =	878.49	ft-kips per lane	See Section 7
	Reaction =	90.30	kips per lane	

Service Limit State

		Top of Girder		Bottom of Girder		Check
Concrete Stresses at Transfe	Load Case	Calculated	Allowable	Calculated	Allowable	
At d_v	DL+P/S	-0.014	0.200	-1.249	-3.600	**OK**
Concrete Stresses at Service		**Limit State I**		**Limit State III**		
At mid-span	DL+LL+P/S	-1.407	-4.200	-0.030	0.000	**OK**
		-	-	-0.030	0.251	**OK**
	DL+P/S	-0.628	-3.150	-	-	**OK**
	LL+1/2DL+1/2P/S	-1.093	-2.800	-	-	**OK**

Strength Limit State

Moment at Mid-span, ft-kips	Mu =	978	ϕ Mn =	1351.2	**OK**

Table of Contents

Content

1 Structure:

Single Span Bridge

2 Live load

HL-93

3 Material Properties

Concrete

Precast prestressed girder

Reinforcing steel

Prestressing steel

4 Allowable Concrete Stresses at Service Lmit State

Tensile stress limit

Compressive stress limits after all losse

Stress limits for prestressing strands

5 Computation of Section Properties

Table 5-1: Section Area

Table 5-2: Moment of Inertia, I

6 Limit State

Service limit state

Load combinations and load factors

7 Vehicular Live Load

Design live load

Maximum live load force effect

Dynamic load allowance (Impact, I

Distribution of Live Load, Dfi (Beam Slab Bridges)

Distribution Factor for Moment Interior Girder, DF

Moment Distribution Factor for Exterior girder, I

Shear Distribution Factor for Interior Girder, DFV

Shear Distribution Factor for Skewed Exterior Girc

Table 7-2: Summary of Live Load Distribut

8 Computation of Stresses

Stresses due to Weight of Girder

Concrete stresses due to Traffic Barrier

Concrete stresses due to SIDL, Asphalt Overlay (DW)

Concrete stresses due to Live Load

Summary of stresses at dv (Table 8-8)

Summary of stresses at Mid-Span (Table 8-9)

9 Approximate Evaluation of Pre-Stress Losses

Time Dependent Losses

Loss due to elastic shortening

Eccentricities of Prestress Strands

Losses due to Steel Relaxation

Jacking Force

10 Stresses at Service Limit State

Concrete stresses at mid-span

Final stress at top of girder

Compressive stress limit at service - I load combinations

Prestressing stress at bottom of girder

Final stress at bottom of girder

Tensile stress limit at service - III load combination

Stresses at transfer

Determination of prestressing losses at transfer

Total loss at transfer

Concrete stress immediately after transfer at dv f

11 Strength Limit State

Resistance factor

Flexural forces — **NG Mu No Check**

Flexural resistance — **OK for rectangular section**

Nominal flexural resistance

Limit for reinforcement

Maximum reinforcement — **OK Not overreinforced**

Minimum reinforcement

Development of prestressing strand — **OK developed**

12 Shear Design

Design procedure

Effective Web Width, bv, and Effective Shear Depth, dv

Component of Prestressing Force in Direction of Shear Force, Vp

Shear Stress Ratio

Factored shear force

fpo

Factored moment

Longitudinal Strain (Flexural Tension), ε_x

Determination of β and θ

Shear strength

Required shear strength

Maximum spacing of shear reinforcement

Minimum shear reinforcement — **OK for Min. Transverse Reinf.**

Longitudinal reinforcement — **OK for Longitudinal Reinforcement**

13 Deflection and Camber

Deflection due to prestressing forces at Transfer

Deflection due to weight of Girder

Deflection due to weight of Traffic Barrier TB

Deflection due to weight of Wearing Surface SIDL

Deflection (Camber) at transfer, Ci

PS & Girder Long term Deflection

Final deflection due to all loads

Camber Summary

ACP at Piers

References

Prestressed Voided Slab Design
AASHTO LRFD Specifications

Specification Reference

1 Structure: Project XLXXXX, Name Br #XX/XX

Single Span Bridge

Span Length:	45.00	ft	C.L. / C.L. Bearing / Bkps	Prelim Plan, Sh 1
Girder Length:	45.83	ft		
Bridge Width:	44.00	ft	Deck between curbs &/or barriers	"
Girder Width:	4.00	ft		BDM6.6-A3-1
Number of girders:	11			Prelim Plan, Sh 1

(Back to Table of Contents)

2 Live load — LRFD 3.6.1

HL-93

Vehicular live load designated as " HL-93 " shall consist of a combination of : — LRFD 3.6.1.2.1

Design truck or design tandem, plus

Design lane load

Design truck is equivalent to AASHTO HS20-44 truck. — LRFD 3.6.1.2.2

The design lane shall consist of a 0.64 klf, uniformly distributed in the longitudinal direction. Design lane load shall be assumed to be uniformly distributed over 10 ft width in the transverse direction. — LRFD 3.6.1.2.4

Design tandem shall consist of a pair of 25.0 kip axles spaced at 4'-0" apart — LRFD 3.6.1.2.3

Number of design lanes: — LRFD 3.6.1.1.1

Integer part of : Width / (12 ft lane) = 3 Lanes

(Back to Table of Contents)

3 Material Properties

Concrete

LRFD Specifications allows a concrete compressive strength with a range of 2.4 to 10.0 ksi at 28 days. — LRFD 5.4.2.1

Compressive strength for prestressed concrete shall not be less than 4.0 ksi.

(Back to Table of Contents)

Precast prestressed girder

Compressive strength at 28 days,	f_c' =	7.0	ksi	2000 BDM, 6.6-A3-2
Compressive strength at transfer,	f_{ci}' =	6.0	ksi	
Unit weight, (for computing, E_c)	w_c =	0.160	kcf	

(for DL calculation) w_c = 0.160 kcf — BDM 4.1.1 & 4/18/00 Bridge Design Memo

*Modulus of Elasticity, $E_c = 33000 w_c^{1.5} \sqrt{f_c'}$ = 5587.8 ksi — LRFD Eqn 5.4.2.4-1

*LRFD states this equation is for concretes with unit weights between 0.090 and 0.155 kcf. WSDOT uses 0.160kcf. Assume this is still ok. $0.90 \le w_c \le 0.155$

Modulus of Rupture, $f_r = 0.24\sqrt{f_c'}$ = 0.635 ksi — LRFD 5.4.2.6

Poisson's ratio = μ = 0.2 — LRFD 5.4.2.5

(Back to Table of Contents)

Reinforcing steel — LRFD 5.4.3

AASHTO M-31 with yield strength of, f_y = 60.00 ksi — LRFD 5.4.3.1 & BDM 5.1.2A

Modulus of Elasticity, E_s = 29000 ksi — LRFD 5.4.3.2

(Back to Table of Contents)

Prestressing steel — LRFD 5.4.4

AASHTO M-203, Uncoated 0.5 in. or 0.6 in. diameter, Low-relaxation — LRFD 5.4.4.1

Ultimate strength, f_{pu} = 270 ksi. — LRFD Table 5.4.4.1-1

Yield strength, f_{py} = 0.9 f_{pu} = 243 ksi. — "

Modulus of elasticity, E_p = 28500 ksi. — LRFD 5.4.4.2

(Back to Table of Contents)

4 Allowable Concrete Stresses at Service Lmit State — LRFD 5.9.4

Tensile stress limit

For service loads which involve traffic loading, tensile stress in members with bonded prestressing strands shall be investigated using Service - III load combination. — LRFD 5.9.4.2.2

Tension in precompressed tensile zone assuming uncracked section:

$f_t = 0.19\sqrt{f_c'}$ Areas with bonded reinforcement — LRFD Table 5.9.4.2.2-1

$f_t = 0.0948\sqrt{f_c'}$ Components subjected to severe corrosive conditions

Current WSDOT design practice does not allow any tension at the bottom of prestressed girders, therefore:

f_t = 0.00 ksi — B.K.

(Back to Table of Contents)

Compressive stress limits after all losses — LRFD 5.9.4.2

Compression shall be investigated using Service - I load combination:

$f_c = 0.45\ f'_c$	Due to permanent loads
$f_c = 0.60\ f'_c$	Due to permanent and transient loads
$f_c = 0.40\ f'_c$	Due to transient loads and one-half of permanent loads

(Back to Table of Contents)

Stress limits for prestressing strands

Ultimate tensile strength,	f_{pu} =	270.00	ksi
Yield strength,	$f_{py} = 0.9\ f_{pu}$ =	243.00	ksi
Immediately prior to Transfer	$f_{pbt} = 0.75\ f_{pu}$ =	202.50	ksi

LRFD Table 5.4.4.1-1

Effective stress limit at Service Limit State after all losses: LRFD Table 5.9.3-1

$f_{pe} = 0.8\ f_{py}$ = 194.40 ksi

(Back to Table of Contents)

5 Computation of Section Properties

Table 5-1: Section Area

Gross Section	Width	48.00	in.
	Depth	26.00	in
Void	Number	2	in
	Diameter	15.70	in
Net Web = Width - Voids = b_v =		24.45	in

BDM 6.6-A3-1 " " " See Section 12

(Back to Table of Contents)

For both pretensioned or posttensioned members after bonding of tendons, section properties may be based on either the gross or transformed section. The following section properties are based on gross section (of the concrete). LRFD 5.9.1.4

Table 5-2: Moment of Inertia, I


	Area in^2	Moment of Inertia in^4
Gross	1248.00	70304.00
Void	387.19	5964.84
Net	860.81	64339.16

$I_{rectangle} = 1/12\ bh^3$ AISC p 7-17

$I_{circle} = 1/4\ \pi\ r^4$ AISC p 7-20

(Gross Concrete Section)

(Back to Table of Contents)



Location of the Neutral Axis:

$$y_b = \frac{\sum yA}{\sum A} = \quad 13.00 \quad \text{in}$$

$$y_t = H - y_b = \quad 13.00 \quad \text{in}$$

Section Modulus: (Bottom) $S_b = \frac{I}{y_b} =$ 4949.2 in^3 BDM 6.4-A3-1

(Top) $S_t = \frac{I}{y_t} =$ 4949.2 in^3 "

6 Limit State LRFD 1.3.1

Each component and connection shall satisfy the following equation for each limit state : LRFD Eqn. 1.3.2.1-1

$$\sum \eta_i \gamma_i Q_i \le \phi R_n = R_r$$

Where:

Load Modifier for Ductility, Redundancy, & Operational Importance

$\eta_i = \eta_i \eta_R \eta_I \ge 0.95$ for loads which a max. value of γ_i is appropriate LRFD Eqn. 1.3.2.1-2

$= \frac{1}{\eta_D \eta_R \eta_I} \le 1.00$ for loads which a min. value of γ_i is appropriate LRFD Eqn. 1.3.2.1-3

η_D = Ductility factor LRFD 1.3.3

η_R = Redundancy factor LRFD 1.3.4

η_I = Operational Importance factor LRFD 1.3.5

η_i = 1.00 WSDOT Bridge office practice: for any ordinary structure B.K.

Therefore the Limit State Equaton simplifies to:

$$\sum \gamma_i Q_i \le \phi R_n = R_r$$

Where:

γ_i = Load Factor, statistically based multiplier applied to force effects LRFD 1.3.2.1

Q_i = Force Effect (Moment or Shear)

ϕ = Resistance Factor

R_n = Nominal Resistance

R_r = Factored Resistance

Service limit state

Service limit state shall be taken as restriction on stress, deformation and crack width under regular service conditions. LRFD 1.3.2.2

(Back to Table of Contents)

Load combinations and load factors

The Total Factored Force Effect shall be taken as: LFRD Eqn. 3.4.1-1

$$Q = \sum \gamma_i Q_i$$

Where:

γ_i = Load Factors specified in Tables 1 & 2

Q_i = Force Effects from loads specified in LRFD

Strength-I load combination relating to the normal vehicle use of the bridge without wind (See Section 11). LRFD 3.4.1

Service-I load combination relating to the normal operational use of the bridge. "

Service-III load combination relating only to tension in prestressed concrete structures with the objective of crack control. "

$$Q_{Strength-I} = \gamma_{DC} DC + \gamma_{DW} DW + 1.75(LL + IM)$$ LRFD Tables 3.4.1-1 & 2

$Q_{Service-I}$ = 1.0 (DC + DW) + 1.0 (LL + IM) " "

$Q_{Service-III}$ = 1.0 (DC + DW) + 0.8 (LL + IM)

Force effects due to temperature, shrinkage, and creep because of the **free movement** at the end piers are considered to be zero.

(Back to Table of Contents)

7 Vehicular Live Load

LRFD 3.6.1

Design live load

LRFD 3.6.1.2.2

Design live load designated as HL-93 shall be taken as:

LL = Truck or tandem (1 + IM) + Lane (See Item 2) LRFD 3.6.1.2.1

Single Span Length =	45.00	ft		
HS-20 Truck Axles	32.00	32.00	8.00	kips
HS-20 Truck Axle Spacing		14.00	14.00	ft
Tandem Truck Axles	25.00	25.00	kips	
Tandem Truck Axle Spacing		4.00	ft	
Lane load density, w_L	0.64	k/ft		

Section 2 / " / " / " / LRFD 3.6.1.2.4

(Back to Table of Contents)

Maximum live load force effect

Max Shear, V_{max}, occurs at the greater horizontal distance of d_v or $0.5d_v\cot\theta$ from the face of support where d_v is the effective depth between the tensile and compressive resultant forces in the member. Assume θ_{skew} is 45 degrees and face of support is the Centerline of bearing/pier (dowel connection). Use d_v to be conservative. LRFD5.8.2.9 & LRFD5.8.3.2

Max Moment, Mmax, occurs near midspan (CL) underneath the nearest concentrated load (P1) when that load is the same distance to midspan as the center of gravity (+ CG) is to midspan. Use the Truck or Tandem (Near Midspan) and the Lane (At Midspan) maximum moments together to be conservative. AISC LRFD Steel Manual, SS General Rules, p4-205 & BDM 4.3-B1

Truck: $V_{max(Truck)}$ = 54.57 kips At 0.72h LRFD 5.8.3.2

		$M_{max(Truck)}$ =	538.71	ft-kips	Near midspan	AISC LRFD p4-205 & BDM 4.3-B1 & See Design LL Worksheet
	Tandem:	$V_{max(Tandem)}$ =	46.04	kips	At 0.72h	
		$M_{max(Tandem)}$ =	513.61	ft-kips	Near midspan	
So the	**HL-93 Live Load, LL = HS-20 Truck(1+IM)+HS-20 Lane**					**Controls**
	Lane:	$V_{max(Lane)}$ =	13.40	kips	At 0.72h	
		$M_{max(Lane)}$ =	162.00	ft-kips	At midspan	

Table 7-1: Live Load Reactions & Moments

Simple span	Reaction, kips	Moment, ft-kips	
	Support	0.72h	0.5 L
HS-20 Truck	57.1	85.1	538.7
HS-20 Lane	14.4	21.7	162.0

AASHTO HL-93 Truck 538.7 ft-kips **Truck LL Governs**

(This answer should check with AASHTO App. A Table)

AASHTO Lane load 162.0 ft-kips

(Back to Table of Contents)

Dynamic load allowance (Impact, IM) LRFD 3.6.2.1

The static effect of Design Truck LL shall be increased by the following percentage : IM = 33% For bridge components (girder) LRFD Table 3.6.2.1-1

M(LL+IM)= 538.7 x(1+ 0.33)+ 162.0 = 878.5 ft-k

R(LL+IM)= 57.1 x(1+ 0.33)+ 14.4 = 90.3 k

(Back to Table of Contents)

Distribution of Live Load, Df_i (Beam Slab Bridges) LRFD 4.6.2.2

For Multibeam deck bridges with conditions as follows, the approximate method of live load distribution applies with the following conditions : LRFD 4.6.2.2.1

- Width of deck is constant
- Number of Beams, $N_b \geq 4$
- Beams are parallel
- Beams have approximately the same stiffness
- Roadway overhang, $d_e \leq 3.0\,ft$
- Curvature in plane is less than 12 degree LRFD 4.6.1.2
- X-section is one consistent with one listed in LRFD Table 4.6.2.2.1-1

The multiple presence factor shall not be applied in conjunction with approximate load distribution except for exterior beams. LRFD 3.6.1.1.2

The typical x-section **g** applies to voided and solid slabs w/o P.T. LRFD Table 4.6.2.2.1-1

Distribution Factor for Moment Interior Girder, DF_{MInt}

LRFD 4.6.2.2.2b

For Multibeam deck bridges within the range of applicability and conditions as follows, the approximate method of live load distribution applies :

LRFD Table 4.6.2.2.2b-1

Range of applicability: Width of beam, $35 < b =$ 48 < 60 in

Span length, $20 < L =$ 45.00 < 120 ft

Number of Beams, $5 < N_b =$ 11 < 20

Regardless of the number of design Lane Loaded: " "

S/D = 0.35

$D1 = 11.5-N_L+1.4N_L(1-0.2C)^2 =$ 11.575 when C<=5

$D2 = 11.5-N_L =$ 8.50 when C>5

D = 11.57 " "

Where : k = ((1+m)I/J)^0.5 = 0.74 " "

C = k(W/L) < k = 0.7

(Solid Slabs) $I_P =$ $(d*b/12)*(b^2+d^2) =$ 309920 in^4

Calcs.Table 5-2

St Venant's Torsional Inertia

LRFD Eqn. C4.6.2.2.1-3


Voided Slab

$$J \approx \frac{4A_o^2}{\sum \frac{s}{t}} =$$ 141596 in^4

Solid Slab

$$J \approx \frac{A^4}{40.0I_p} =$$ 44292.3 in^4

J = 141596



Area enclosed by centerlines of elements

$A_o =$ $(h - t)(b - t) =$ 779 in^2

Thickness of plate-like element, t, is derived from converting the Void Area to Square Areas and centering the side vertically.

*t = $(h-s_s)/2$

where side of square, s_s, is derived from:

$A_{square} = A_{void}$

$$s_s = \sqrt{\pi\left(\frac{dia_v}{2}\right)^2} = \quad 14 \quad \text{in}$$

h = 26 in

t = 7.00 in

*Assume thickness, t, is constant throughout exterior elements, side elements, s, are exterior out-to-out girder measurements, b & h, interior element (leg between voids) is ignored.

Moment Distribution Factor for Interior girder, DF_{MInt}

One design Lane Loaded: 0.346

Skew Reduction Factor for Moments — LRFD 4.6.2.2.2e-1

Range of applicability: Skew, $0 < \theta_{skew} =$ 0.00 $< 60°$

Reduction Factor = $1.05 - 0.25 \tan(\theta) < 1.0$

Reduction Factor = 1.000

Moment Distribution Factor for Skewed Interior girder,

DF_{MInt} = 0.346

(Back to Table of Contents)

Moment Distribution Factor for Exterior girder, DF_{MExt} — LRFD 4.6.2.2.2d, LRFD 4.6.2.2.1, LRFD 2.5.2.7.1

For Multibeam deck bridges within the range of applicability and conditions as follows, the approximate method of live load distribution applies :


$DF_{MExt} = e \times DF_{MInt}$

Where Skew Reduction Factor is included in DF_{MInt} and Correction Factor — LRFD Table 4.6.2.2.2d-1

$$e = 1.04 + \frac{d_e}{25} \geq 1.0$$

Where the distance between outside face of exterior girder web to interior face of traffic barrier (LRFD overhang) is approximately equal to the distance from the centerline of the exterior girder to the inside face of traffic barrier (WSDOT) — BK

BK & RMP



barrier footprint = 18.50 in

d_e = 0.46 ft ≤ 2 ft OK — LRFD Table 4.6.2.2.2d-1

e = 1.058 > 1.0

Moment Distribution Factor for Skewed Exterior Girder,

DF_{MExt} = 0.366

(Back to Table of Contents)

Shear Distribution Factor for Interior Girder, DF_{VInt} — LRFD 4.6.2.2.3a

For Multibeam deck bridges within the range of applicability and conditions as follows, the approximate method of live load distribution applies : — LRFD Table 4.6.2.2.3a-1

Range of applicability: Width of beam,	35 < b =	48	< 60 in
Span length,	20 < L =	45.00	< 120 ft
Number of Beams,	5 < N_b =	11	< 20
St Venant Torsional Inertia,	25000 < J =	141596	< 610000 in^4
Net Moment of Inertia,	40000 < I_c =	64339	< 610000 in^4

By substituting the above pre-determined values, the approximate live load distribution factor for shear may be taken as the greater of:

One design Lane Loaded:

$$DF_{VInt} = \left(\frac{b}{130L}\right)^{0.15}\left(\frac{I_c}{J}\right)^{0.05} = 0.468$$

LRFD Table 4.6.2.2.3a-1

Two or more Lanes Loaded:

$$DF_{VInt} = \left(\frac{b}{156}\right)^{0.4}\left(\frac{b}{12.0L}\right)^{0.1}\left(\frac{I_c}{J}\right)^{0.05} = 0.471$$

" "

Skew Reduction Factor for Shear — LRFD Table 4.6.2.2.3c-1

Range of applicability Skew, $0 <$	θ_{skew} =	0.00	$< 60^{\circ}$
Span length, $20 <$	L =	45.00	< 120 ft
Depth of beam or stringer, $17 <$	d =	26	< 60 in
Width of beam, $35 <$	b =	48	< 60 in
Number of Beams, $5 <$	N_b =	11	< 20

$$RF_{\theta} = 1.0 + \frac{12.0L}{90d}\sqrt{\tan\theta} = \quad 1.000$$

Shear Distribution Factor for Skewed Interior Girder,

DF_{VInt} = 0.471

(Back to Table of Contents)

Shear Distribution Factor for Skewed Exterior Girder — LRFD 4.6.2.2.3b

For Multibeam deck bridges within the range of applicability and conditions as follows, the approximate method of live load distribution applies : — LRFD 4.6.2.2.1, LRFD 2.5.2.7.1

Range of applicability: — LRFD Table 4.6.2.2.3b-1

Overhang,	d_e =	0.46	< 2.0 ft

$DF_{VExt} = e \times DF_{VInt}$ — LRFD Table 4.6.2.2.3b-1

where : $e = 1.02 + \frac{d_e}{50} \geq 1.0$

e = 1.03 > 1.0

Shear Distribution Factor for Skewed Exterior Girder,

DF_{VExt} = 0.485

Table 7-2: Summary of Live Load Distribution Factors:

		Moment		Shear
Interior Girder	DF_{MInt} =	0.346	DF_{VInt} =	0.471
Exterior Girder	DF_{MExt} =	0.366	DF_{VExt} =	0.485

(Back to Table of Contents)

8 Computation of Stresses

Sign convention: + Tensile stress
- Compressive stress

Concrete stresses due to Dead Load, DC + DW

Dead Load of structural components, DC, includes Girder & Traffic Barrier. LRFD 3.3.2

Stresses due to Weight of Girder (DC)

Unit weight, w_g = 0.96 k/ft BDM 6.4-A3-1

At d_v: x = 0.72 h = 1.56 ft LRFD 5.8.3.2

(V_{max} Location)

$$V_G = w_G\left(\frac{L}{2} - x\right) = 20.03 \text{ kips}$$ AISC LRFD p 4-190

$$M_G = \frac{w_G x}{2}(L - x) = 32.41 \text{ ft-kips}$$ " "

At mid-span x = 0.5 L = 22.5 ft

(M_{max} Location)

$$V_G = w_G\left(\frac{L}{2} - x\right) = 0 \text{ kips}$$ " "

$$M_G = \frac{w_G L^2}{8} = 242.1 \text{ ft-kips}$$ " "

Table 8-1: Stresses due to Girder Dead Load, σ_G

		0.72h	0.5 L
Top of girder	ksi	-0.079	-0.587
Bottom of girder	ksi	0.079	0.587

(Back to Table of Contents)

Concrete stresses due to Traffic Barrier (DC)

Weight of Traffic Barrier over three girders, $w_{TB3G} = \frac{w_{TB}}{3} =$ 0.17 k/ft BDM 6.3.1B.2d

At d_v: x = 0.72 h = 1.56 ft

$$V_{TB} = w_{TB}\left(\frac{L}{2} - x\right) = 3.49 \text{ kips}$$ AISC LRFD p 4-190

$$M_{TB} = \frac{w_{TB} x}{2}(L - x) = 5.65 \text{ ft-kips}$$ " "

At mid-span x = 0.5 L = 22.50 ft

$$V_{TB} = w_{TB}\left(\frac{L}{2} - x\right) = 0.00 \text{ kips}$$ " "

$$M_{TB} = \frac{w_{TB} L^2}{8} = 42.19 \text{ ft-kips}$$ " "

Table 8-2: Stresses due to Traffic Barrier, σ_{TB}

		0.72h	0.5 L
Top of girder	ksi	-0.014	-0.102
Bottom of girder	ksi	0.014	0.102

(Back to Table of Contents)

Concrete stresses due to SIDL, Asphalt Overlay (DW)

Weight of Asphalt Overlay, w_{SIDL} = 0.16 k/ft

At d_v: x = 0.72 h = 1.56 ft

$$V_{SIDL} = w_{SIDL}\left(\frac{L}{2} - x\right) = \quad 3.35 \quad \text{kips}$$ " "

$$M_{SIDL} = \frac{w_{SIDL}x}{2}(L - x) = \quad 5.42 \quad \text{ft-kips}$$ " "

At mid-span x = 0.5 L = 22.50 ft

$$V_{SIDL} = w_{SIDL}\left(\frac{L}{2} - x\right) = \quad 0.00 \quad \text{kips}$$ " "

$$M_{SIDL} = \frac{w_{SIDL}L^2}{8} = \quad 40.50 \quad \text{ft-kips}$$ " "

Table 8-3: Stresses due to SIDL, σ_{DW}

		0.72h	0.5 L
Top of girder	ksi	-0.013	-0.098
Bottom of girder	ksi	0.013	0.098

(Back to Table of Contents)

Concrete stresses due to Live Load LRFD 3.6.1.2.1

Dynamic load allowance: IM = 33% LRFD 3.6.2.1

Table 8-4: Live Load Force Effect:

Simple span	Moment, ft-kips		Shear, kips	
	0.72h	0.5 L	0.72h	0.5 L
HS-20 Truck	85.1	538.71	54.6	6.13
HS-20 Lane	21.7	162.00	13.4	0.00

Table 8-5: HL-93 Live Load, LL = HS-20 Truck(1+IM)+HS-20 Lane

Simple span	Moment, ft-kips		Shear, kips	
	0.72h	0.5 L	0.72h	0.5 L
	134.91	878.486	85.98	8.16

Table 8-6: Distributed Live Load

Simple span	Moment, ft-kips		Shear, kips	
	0.72h	0.5 L	0.72h	0.5 L
Interior Girder	46.62	303.59	40.50	3.84
Exterior Girder	49.34	321.30	41.68	3.95

Table 8-7: Stresses in Girder due to LL+IM :

		0.72h	0.5 L
Top of Girder	ksi	-0.120	-0.779
Bottom of Girder	ksi	0.120	0.779

(Back to Table of Contents)

Summary of stresses at d_v (Table 8-8)

Stresses, ksi	Top of girder	Bottom of girder
Weight of Girder	-0.079	0.079
Weight Traffic Barrier	-0.014	0.014
Weight of SIDL	-0.013	0.013
Live Load plus Impact Service - I	-0.120	-
Live Load plus Impact Service - III	-	0.096

(Back to Table of Contents)

Summary of stresses at Mid-Span (Table 8-9)

Stresses, ksi	Top of girder	Bottom of girder
Weight of Girder	-0.587	0.587
Weight Traffic Barrier	-0.102	0.102
Weight of SIDL	-0.098	0.098
Live load plus impact Service - I	-0.779	-
Live load plus impact Service - III	-	0.623

(Back to Table of Contents)

9 Approximate Evaluation of Pre-Stress Losses

For Prestress losses in members constructed and prestressed in a single stage, relative to the stress immediately before transfer, in pretensioned members, with low relaxation strands, the **Total Lump Sum Losses** may be taken as: LRFD 5.9.5.1

$$\Delta f_{pT} = \underbrace{\Delta f_{pSR} + \Delta f_{pCR} + \Delta f_{pR}} + \Delta f_{pES}$$

Time Dependent Losses

Where losses due to Shrinkage (SR), Cracking (CR), and Steel Relaxation (R), can be determined as a Lump Sum Estimate of Time Dependent Losses. LRFD 5.9.5.3

Time Dependent Losses

For normal weight concrete pretensioned by low-relaxation strands, approximate lump-sum time dependent losses resulting from creep and shrinkage of concrete and relaxation of prestressing steel may be used as follows:

For Voided slab with 270 ksi strands,

Time Dependent Losses = $37\left[1-0.15\frac{\left(f_c^{'}-6\right)}{6}\right]=$ 36.08 ksi — BDM Table 6.1.5-1

Losses due to elastic shortening should be added to time-dependent losses to determine the total losses. — BDM 6.1.5B

(Back to Table of Contents)

Loss due to elastic shortening — LRFD 5.9.5.2.3

The loss due to elastic shortening in pretensioned members shall be

$$\Delta f_{pES} = \left(\frac{E_p}{E_{ci}}\right) f_{cgp}$$ — LRFD Eqn. 5.9.5.2.3a-1 & BDM 6.1.5B

Concrete strength at transfer: f_{ci}' = 6.0 ksi

Modulus of elasticity, concrete: E_{ci} = 5173.3 ksi

prestressing steel: E_p = 28500.0 ksi

f_{cgp} = Stress due to prestressing and girder weight at Centroid of prestressing strands, at section of maximum moment

Eccentricities of Prestress Strands

C. G. of bottom strands to bottom of girder =	2.00	in.	BDM 6.6-A3-1
C. G. of top strands to bottom of girder =	23.00	in.	"
C. G. of bonded bottom strands to C.G. of girder, e_{bb}	11.00	in.	
C. G. of debonded strands to C.G. of girder, e_{db} =	11.00	in.	
C. G. of all bottom strands to C.G. of girder, e_b =	11.00	in.	"
C. G. of top strands to C.G. of girder, e_t =	-10.00	in.	"
E = C. G. of all strands to C.G. of girder =	**7.18**	**in.**	

(Back to Table of Contents)

Concrete stress at Centroid of prestressing

$P_i = N A_{ps} f_p$ = 636.2 kips — BDM 6.1.5B

$$f_{ps} = -\frac{P_i}{A_g} - \frac{P_i e^2}{I_g} = \quad -1.25 \text{ ksi}$$

$$f_g = \frac{M_g e}{I_g} = \quad 0.32 \text{ ksi}$$

$f_{cgp} = f_g + f_{ps}$ = -0.92 ksi

Elastic shortening loss,

$$\Delta f_{pES} = \left(\frac{E_p}{E_{ci}}\right) f_{cgp} = \quad \mathbf{5.09} \quad \mathbf{ksi}$$

(Back to Table of Contents)

Losses due to Steel Relaxation LRFD 5.9.5.4.4b

Steel Relaxation Loss at Transfer,

LRFD Eqn. 5.9.5.4.4b-2

$$\Delta f_{pR1} = \frac{\log(24.0t)}{40.0}\left[\frac{f_{pj}}{f_{py}} - 0.55\right] f_{pj}$$

LRFD Table 5.4.4.1-1

f_{py} = 0.90 f_{pu} = 243.00 ksi

Curing time for concrete to attain f'_{ci} is approximately 12 hours.
Tendons are stressed shortly before concrete pouring and prestressing forces transferred to concrete shortly after curing. An approximate time of one day is reasonable for steel relaxation loss calculation at transfer.

t = 1.00 day

$f_{pj`}$ = 0.80 f_{pu} = 216.0 ksi

f_{pj} = 0.75 f_{pu} + Δf_{pR1} = 205.0 ksi

Jacking Force

$P_J = (f_{pj})(A_{ps})(N_{ps})$ = 690.1 kips

$P_J = (f_{pj})(A_{ps})(N_{ps})$ = 564.6 kips Bottom Strands

By substitution :

Δf_{pR1} = 2.53 ksi

Above relaxation losses not added to Time Dependent Losses, but will be used for Service Limit State Total Transfer PS Losses, Section 10.

Total lump-sum losses,

Δf_{pT} = 38.64 ksi

(Back to Table of Contents)

10 Stresses at Service Limit State

Concrete stresses at mid-span

Force per strand P / N = $A_{ps}(f_{pbt}-\Delta f_{pT})$ = 25.07 kips

Table 10-1: Mid-Span Prestress Force Effects

	No. of strands	Force per Strand, kips	Total force	Eccent. in.	Moment in-kip
Bottom Strands	14	25.07	350.98	11.00	3861
Debonded Strands	4	25.07	100.28	11.00	1103
Top Strands	4	25.07	100.28	-10.00	-1003
		P (kips)=	552	Mp(in-k) =	3961

Prestressing stress at top of girder

$$f_{p(top)} = -\frac{P}{A_c} + \frac{M_{ps}}{S_t} = \quad 0.16 \quad \text{ksi}$$

LRFD 5.9.4.2.1

(Back to Table of Contents)

Final stress at top of girder

Stresses due to permanent loads plus prestressing :

$f_{g(topDL+PS)}$ = -0.63 ksi

Stresses due to all loads plus prestressing :

$f_{g(topDL+LL+PS)}$ = -1.41 ksi

Stresses due to Transient loads and one-half of permanent loads plus prestressing:

$f_{g[topLL+(1/2DL+PS)]}$ = -1.09 ksi

(Back to Table of Contents)

Compressive stress limit at service - I load combinations

Due to permanent loads (DL + PS) :

LRFD Table 5.9.4.2.1-1

$f_{comp.}$ =0.45 f'$_c$ = -3.15 ksi > -0.63 ksi

Due to permanent loads and transient loads (DL + PS + LL):

$f_{comp.}$ = 0.60 f'$_c$ = -4.20 ksi > -1.41 ksi "

Due to transient loads and one-half of permanent loads (LL + 1/2DL + 1/2PS):

$f_{comp.}$ = 0.40 f'$_c$ = -2.80 ksi > -1.09 ksi "

Prestressing stress at bottom of girder

$$f_{p(bottom)} = -\frac{P}{A_c} - \frac{M_{ps}}{S_b} = \quad -1.441 \quad \text{ksi}$$

LRFD 5.9.4.2.2

(Back to Table of Contents)

Final stress at bottom of girder

Stresses due to all loads plus prestressing :

$f_{g(bottom)}$ = -0.030 ksi

Tensile stress limit at service - III load combination

LRFD Table 5.9.4.2.2-1

$$f_{tens} = 0.0948\sqrt{f_c'} = \quad 0.251 \quad \text{ksi} > \quad -0.030 \quad \text{ksi}$$

f_{tens} = 0.00 ksi > -0.030 ksi

BDM Table 6.2.3 2

per WSDOT office practice

(Back to Table of Contents)

Stresses at transfer

The prestressing force may be assumed to vary linearly from zero at free end to a maximum at transfer length, l_t.

The transfer length may be taken as 60 times strand diameter. LRFD 5.8.2.3

$l_t = 60 \times d_{strand}/12 =$ 2.50 ft = 30.00 in. LRFD 5.11.4.1

(Back to Table of Contents)

Determination of prestressing losses at transfer

At transfer the losses that could be accounted for are elastic shortening and steel relaxation only.

(Back to Table of Contents)

LRFD 5.9.5.2.3a
5.9.5.4.4b

Total loss at transfer

$\Delta f_{pt} = \Delta f_{PES} + \Delta f_{pR1} =$ 7.62 ksi

(Back to Table of Contents)

Concrete stress immediately after transfer at d_v from support

Prestressing forces at transfer = $N_{ps}A_{ps}(f_{pbt} - \Delta f_{pt})$

Force per strand, P/N = 30.2 kips

Table 10-2: Prestress Force Effects at Max. Shear Location, d_v

	No. of strands	Force k/stand	Total kips	Eccent. in.	Moment in-kips
Bottom Strands	14	30.20	422.8	11.00	4651
Debonded Strands	4	0.00	0.0	11.00	0
Top Strands	4	30.20	120.8	-10.00	-1208
		P_j =	543.7	M_{pj} =	3443

* At d_v some of the strands are Debonded

Stresses due to weight of girder :

$M_g =$ 32.41 ft-kips

Stresses: Top of girder, $\frac{M_g}{S_t} =$ -0.079 ksi

Bottom of girder, $\frac{M_g}{S_b} =$ 0.079 ksi

Prestressing stress at top of girder :

$$f_p = \frac{-P_j}{A_g} + \frac{M_{pj}}{S_t} =$$ 0.064 ksi

Final stress at top of girder : $f_{g(top)} =$ -0.014 ksi

Tensile stress limit in areas without bonded reinforcement : LRFD 5.9.4.1.2

$$f_t = 0.0948\sqrt{f'_{ci}} \leq \quad 0.200 \text{ ksi} \quad > \quad -0.014 \text{ ksi}$$ LRFD Table 5.9.4.1.2-1

Prestressing stress at bottom of girder :

$$f_p = \frac{-P_j}{A_g} - \frac{M_{pj}}{S_b} = \quad -1.33 \text{ ksi}$$

Final stress at bottom of girder : $f_{g(bot)}$ = -1.25 ksi

Compressive stress limit in pretensioned components :

$f_{ci} = 0.60 f'_{ci}$ = -3.60 ksi > -1.25 ksi LRFD 5.9.4.1.1

(Back to Table of Contents)

LRFD 5.5.4.1

11 Strength Limit State

Strength limit state shall be considered to satisfy the requirements for strength and stability. LRFD Eqn. 1.3.2.1-1

$$\eta \Sigma (\gamma i \, Qi) < \phi \, R_n = R_r$$

Resistance factor

ϕ =	0.90	Flexural in reinforced concrete	LRFD 5.5.4.2.1
ϕ =	1.00	Flexural in prestressed concrete	"
ϕ =	0.90	Shear	"
ϕ =	0.75	Axial Compression	

(Back to Table of Contents)

Flexural forces LRFD 3.4.1

Strength - I load combination is to be considered for normal vehicular load without wind. LRFD TABLE 3.4.1-1

Load factors :

γ_{DC} =	1.25	Components and attachments (Girder + TB)
γ_{DW} =	1.50	Wearing surface (SIDL or ACP)
γ_{LL} =	1.75	Vehicular load (LL + Impact)

Flexural moment = 1.0 [1.25 DC + 1.5 DW + 1.75 (LL+IM)]

M_u = 978.4 ft.-kips

Checked using QConBridge program,

M_u = 1836.0 ft.-kips NG Mu No Check QConBridge 101-145MuChk.qcb Report p 4of 5

(Back to Table of Contents)

Flexural resistance

For practical design an equivalent rectangular compressive stress distribution of 0.85 f'c overall depth of a = β_1c may be considered. LRFD 5.7.3.1.1 & 5.7.2.2

β_1 = 0.70 for f'c = 7.0 ksi

The average stress in prestressing strands, f_{ps}, may be taken as:

LRFD Eqn. 5.7.3.1.1-1

$$f_{ps} = f_{pu}\left(1 - k\frac{c}{d_p}\right)$$

$$k = 2\left(1.04 - \frac{f_{py}}{f_{pu}}\right) = \quad 0.28$$

LRFD Table C5.7.3.1.1-1

Location of neutral axis :

For rectangular section without mild reinforcement :

$$c = \frac{A_{ps}f_{pu} + A_s f_y + A_s^{'} f_y^{'}}{0.85 f_c^{'}\beta_1 b + kA_{ps}\dfrac{f_{pu}}{d_p}}$$

$A_s = A'_s = 0.0$ with no partial prestressing considered — LRFD 5.7.3.1.1

A_{ps} =	2.75	in.^{2}	Area of prestressing strands
d_p =	24.00	in.	Distance from extreme compression fiber to Centroid of prestressing strands.

By substitution : c1 = 3.565 in

OK for rectangular section

For T-section without mild reinforcement :

$$c = \frac{A_{ps}f_{pu} + A_s f_y + A_s^{'} f_y^{'} - 0.85 f_c^{`}(b - b_w)h_f}{0.85 f_c^{'}\beta_1 b_w + kA_{ps}\dfrac{f_{pu}}{d_p}}$$

b_w =	24.45	in
h_f =	7.00	in
c2 =	0.52	in
c =	3.565	in
a = β_1 c =	2.50	in < t_f

Average stress in prestressing steel : — LRFD 5.4.4.1-1

$$f_{ps} = f_{pu}\left(1 - k\frac{c}{d_p}\right) = \quad 258.8 \text{ ksi.}$$

Tensile stress limit at strength limit state, f_{pu} = 270.0 ksi

(Back to Table of Contents)

Limit for reinforcement LRFD 5.7.3.3

Maximum reinforcement LRFD 5.7.3.3.1

The maximum amount of prestressing and non-prestressing reinforcement shall be such that :

$$\frac{c}{d_e} \le 0.42$$ LRFD Eqn. 5.7.3.3.1-1

Where,

$$d_e = \frac{A_{ps} f_{ps} d_p + A_s f_y d_s}{A_{ps} f_{ps} + A_s f_y}$$ LRFD Eqn. 5.7.3.3.1-2

Since A_s = 0.0

Then $d_e = d_p$ = 24.0 in.

$\frac{c}{d_e}$ = 0.149 < 0.42 **OK Not overreinforced**

(Back to Table of Contents)

The nominal flexural resistance is primarily controlled by steel, however the behavior of the section is based on the ratio of c/de, Prestressed concrete members shall be designed so that steel is yielding as the ultimate capacity is de, Distance from extreme compression fiber to the Centroid of all tensile steel approached. This is satisfied by ductility limit requirement se as : c/de < 0.42. If the ratio of c/de > 0.42, section is considered over-reinforced and LRFD Equations C5.7.3.3.1-1&2 must LRFD C5.7.3.7.2

Nominal flexural resistance LRFD 5.7.3.2.3

Nominal flexural resistance of a rectangular section may be determined by using equations for flanged section in which case b_w shall be taken as b.

Under Reinforced Equations:

$a = \beta_1 c$ = 2.495 in.

Rectangular: $M_n = A_{ps} f_{ps}\left(d_p - \frac{a}{2}\right)$ = 1351 ft.-kips

T-shaped: $M_n = A_{ps} f_{ps}\left(d_p - \frac{a}{2}\right) + 0.85 f`_c (b - b_w)\beta_1 h_f (a/2 - h_f/2)$ =

1222 ft.-kips

M_n = 1351 ft.-kips

Over Reinforced Equations (applicable for Prestressed memebrs only):

Rectangular: $M_n = (0.36\beta_1 - 0.08\beta_1^2) f`_c b d_e^2 =$ 3432 ft.-kips

T-shaped: $M_n = (0.36\beta_1 - 0.08\beta_1^2) f`_c b d_e^2 + 0.85 f`_c (b - b_w) h_f (d_e - 0.5 h_f) =$

3424 ft.-kips

$M_n =$ 3432 ft.-kips

Flexural resistance, $M_r = \phi M_n =$ 1351 > $M_u =$ 978 ft.-kips

(Back to Table of Contents)

Minimum reinforcement LRFD 5.7.3.3.2

The amount of prestressing and non-prestressing steel shall be adequate to develop flexural resistance greater than or equal to the least 1.2 times the cracking moment or 1.33 times the factored moment required by Strength Limit State 1.

Flexural resistance,

$M_r = \phi M_n \geq$ The Lessor of: $1.2M_{cr} =$ 1027.5 ksi **governs**

$1.33M_u =$ 1301.3 ksi

$$M^*_{cr} = S_c\left(f_r + f_{pe}\right) - M_{d/nc}\left(\frac{S_c}{S_b} - 1\right)$$ 1996 AASHTO 9.18.2.1

Beams are designed to be non-composite, therefore,
$S_c = S_b$ reduces the above equation to:

$$M^*_{cr} = S_b(f_r + f_{pe})$$

$$f_r = 0.24\sqrt{f_c^{'}} =$$ 0.635 ksi LRFD 5.4.2.6

$f_{pe} =$ -1.44 Stress at extreme fiber due to prestressing

$M_{cr} =$ 856 ft.-kips

$M_r =$ 1351 >1.2 Mcr = 1027.5 ft.-kips

(Back to Table of Contents)

Development of prestressing strand 5.11.4.2

Pretensioning strand shall be bonded beyond the critical section for a development length taken as :

$$l_d \geq K\left(f_{ps} - \frac{2}{3} f_{pe} \right) d_b$$ LRFD Eqn. 5.11.4.2-1

K = 1.6

f_{ps} = 258.77 ksi

f_{pe} = 163.86 ksi

d_b = 0.50 in.

$l_d \geq$ 9.97 ft (Back to Table of Contents)

l_d = 9.97 ft < 1/2 Span L/2 = 22.50 **OK developed**

12 Shear Design

Design procedure

The shear design of prestressed members shall be based on the general procedure of AASHTO - LRFD Bridge Design Specifications article 5.8.3.4.2 using the Modified Compression Field Theory. WSDOT Design Memo LRFD Shear Design, 3/19/02

Shear design for prestressed girder will follow the (replacement) flow chart for LRFD Figure C.5.8.3.4.2-5. This procedure eliminates the need for θ angle and β factor iterations. WSDOT Design Memo, Shear Design 6/18/01

(Back to Table of Contents)

Effective Web Width, b_v, and Effective Shear Depth, d_v

Effective web width shall be taken as the minimum web width, measured parallel to the nuetral axis, between the resultants of the compressive and tensile forces due to flexure LRFD Figure C.5.8.3.4.2-5

b_v = Net Web = Width - Voids

b_v = 24.5 in.

Effective shear depth shall be taken as the distance between resultant of tensile and compressive forces due to flexure but it need not to be taken less than the greater of : 0.9de OR 0.72h. LRFD 5.8.2.9

$d_v = d_e - a/2$ = 22.8 in. **governs**

d_v = 0.9de = 21.6 in.

d_v = 0.72h = 18.7 in. LRFD 5.8.3.2

The location of critical section for shear shall be taken as the larger of 0.5 dv cot(θ) or dv from the internal face of support.

Since θ , the angle of diagonal compressive stress, is not known at this point, use d_v for shear force calculation.

use d_v = 22.8 or 1.90 ft

(Back to Table of Contents)

Component of Prestressing Force in Direction of Shear Force, V_p

LRFD Figure C.5.8.3.4.2-5

The prestressing in PCPS Slabs are horizontal only, there is no vertical component

V_p = 0.00 kips

(Back to Table of Contents)

Shear Stress Ratio

LRFD Figure C.5.8.3.4.2-5

$$\frac{v_u}{f_c'} = \mathbf{0.0305}$$

Where the Shear Stress (ksi) on the concrete is,

LRFD Eqn. 5.8.2.9-1

$$v_u = \frac{V_u - \phi V_p}{\phi b_v d_v} = 0.213 \text{ ksi}$$

(Back to Table of Contents)

Where the

Factored shear force

$$V_u = \Sigma (\eta_i \gamma_i V_i)$$

η_i =	1.00	Limit state factor for any ordinary structure
γ_{DC} =	1.25	Components and attachments (Girder + TB)
γ_{DW} =	1.50	Wearing surface (SIDL or ACP)
γ_{LL+IM} =	1.75	Vehicular load (LL + Impact)

Girder, V_g =	19.7	kips	
Traffic Barrier, V_{tb} =	3.4	kips	
V_{DC} =	23.1	kips	
ACP Overlay, V_{DW} =	3.3	kips	LRFD 3.6.1.2.1
$V_{LL+IM} \times DF_{VExt}$ =	41.7	kips	Approx. (from 0.72h)

Shear force effect,

$V_u = 1.00(1.25\ V_{DC} + 1.5\ V_{DW} + 1.75\ V_{LL+IM})$

V_u = 106.80 kips

(Back to Table of Contents)

f_{po}

LRFD Figure C.5.8.3.4.2-5

If the (critical) section (for shear) is within the transfer length of any (prestress) strands, calculate the effective value of f_{po}, the parameter taken as modulus of elasticity of prestressing tendons multiplied by the locked in difference in strain between the prestressing tendons and the surrounding concrete.

$f_{po} = 0.70 f_{pu}$

LRFD Eqn. 5.8.3.4.2-3

$$f_{po} = \left[\frac{x + d_v}{l_t}\right] 0.70 f_{pu}$$ **governs, dv is within the transfer length of the prestressed strands**

Where the distance between the edge of girder (or beginning of prestress) and the CL of Bearing (BRG)

x = 5.00 in.

BDM 6.6-A3-1

accounting for bridge skew gives a long. distance from the face of girder as,

x = 5.00 in.

f_{po} = 174.84 ksi

(Back to Table of Contents)

Longitudinal Strain (Flexural Tension), ε_x

The section contains at least the minimum transverse reinforcement as specified in Article 5.8.2.5. Longitudinal strain in the "web reinforcement" on the flexural tension side of the member,

WSDOT Design Memo Shear Design, 6/18/2001 & LRFD Eqn. 5.8.3.4.2-1

$$\varepsilon_x = \frac{\left[\frac{M_u}{d_v} + 0.5N_u + (V_u - V_p) - A_{ps} f_{po}\right]}{2(E_s A_s + E_p A_{ps})} \le 0.002$$

Where: **Factored moment** is not to be taken less than $V_u d_v$

LRFD 5.8.3.4.2

$M_u = \Sigma (\eta_i \gamma i M_i)$

Ultimate moment at d_v from support, M_u

Girder, M_g =	39.1	ft-kips	
Traffice Barrier, M_{tb} =	6.8	ft-kips	
M_{DC} =	45.9	ft-kips	
ACP (SIDL), M_{DW} =	6.5	ft-kips	
$M_{LL+IM} \times DF_{MExt}$ =	49.3	ft-kips	Approx. (from 0.72h)

Moment Force Effect,

$M_u = 1.00(1.25M_{DC} + 1.50M_{DW} + 1.75M_{LL+IM})$

M_u = 153.5 ft-kips = 1842.3 in - kips

(Back to Table of Contents)

Check which value governs:

$V_u d_v$ = 2430.1 in - kips **governs**

M_u = 1842.3 in - kips

Applied Factored Axial forces,

N_u = 0.00 kips

Factored Shear,

V_u = 106.80 kips

Vertical Component of Prestress Forces,

V_p = 0.00

Area of prestressing steel on the flexural tension side of the member,

$A_{ps(T)} = N_{bb} \times A_{ps}$ = 2.14 $in.^2$

Prestress/Concrete Modulus of Elasticity Parameter

f_{po} = 174.84 ksi

Modulus of Elasticity of Mild Reinforcement,

E_s = 29000 ksi

Area of Mild Reinforcement in flexural tension side of the member,

$A_{s(bottom)} = n_{s(bottom)} A_s$

Where there are 4 No. 4 bars

BDM 6.6-A3-1

$A_{s(bottom)}$ = 0.80 $in.^2$

Modulus of Elasticity of Prestress Strands,

E_p = 28500 ksi

Substitution gives,

ε_x = -0.0009549 **< 0, so use the following Equation 3:**

If the value of ε_x from LRFD Equations 5.8.3.4.2-1 or 2 is negative, the strain shall be taken as:

WSDOT Design Memo Shear Design, 6/18/2001 & LRFD Eqn. 5.8.3.4.2-**3**

$$\varepsilon_x = \frac{\left[\frac{M_u}{d_v} + 0.5N_u + (V_u - V_p) - A_{ps} f_{po}\right]}{2(E_c A_c + E_s A_s + E_p A_{ps})}$$

Where: Modulus of Elasticity of Concrete,

E_c = 5587.8 ksi

Area of concrete on the flexural tension side of the member,

A_c = 430.41 $in.^2$

Substitution gives,

ε_x = -0.0000323 **Equation 3 Governs**

ε_x = -0.0000323

(Back to Table of Contents)

Determination of β and θ

Shear Stress Ratio of: 0.030 Is a value just ≤ 0.075

1000 x the Long. Strain: -0.032 Is a value just ≤ 0.00

From Table 1: **θ = 21.80 deg.**

β = 3.75

LRFD Table 5.8.3.4.2-1 & See Theta and Beta Worksheet

(Back to Table of Contents)

Shear strength — LRFD 5.8.3.3

$V_r = \phi V_n$

Nominal shear strength shall be taken as:

$V_n = V_c + V_s + V_p$

Shear resistance provided by concrete :

$$V_c = 0.0316\beta\sqrt{f_c'}\,b_v d_v$$

Shear taken by shear reinforcements :

$V_s = V_n - V_c - V_p$ — LRFD 5.5.4.2

$\phi =$ 0.90 for shear

$V_n =$ Nominal shear strength — LRFD 5.8.3.4

(Back to Table of Contents)

Required shear strength — LRFD 5.8.3.3

Nominal shear strength shall be taken as the lesser of :

$V_n = V_c + V_s i + V_p =$ 288.2 kips **governs** — LRFD Eqn. 5.8.3.3-1

$V_n = 0.25 f'_c b_v d_v + V_p =$ 973.5 kips — LRFD Eqn. 5.8.3.3-2

Shear resistance provided by concrete :

$V_c = 0.0316\beta\sqrt{f_c'}\,b_v d_v =$ 174.4 kips — LRFD Eqn. 5.8.3.3-3

Shear taken by shear reinforcement: shear reinforcing not

$V_{sreq} = V_u/\phi - V_c - V_p =$ -55.7 kips based on capacity — LRFD Eqn. 5.8.3.3-1

Spacing of shear reinforcements :

Try 2 legs of # **4** Av = 0.40 $in.^2$

Required Spacing, $s_{req'd} = \dfrac{A_v f_y d_v \cot\theta}{V_s} =$ -24.49 in. — LRFD Eqn. 5.8.3.3-4

(Back to Table of Contents)

Maximum spacing of shear reinforcement — LRFD 5.8.2.7

if $v_u < 0.125 f'_c$ then $s_{max} = 0.8\ dv <$ ~~24 in.~~ 18 in. — Eqn. 5.8.2.7-1

Maximum spacing of shear reinforcement, WSDOT Practice = 18.00 in — BDM 6.2.3.E.3

if $v_u >= 0.125 f'c$ then $s < 0.4\ dv < 12$ in. — Eqn. 5.8.2.7-2

$v_u =$ 0.213 ksi

0.125 f'c = 0.875 ksi > $v_u =$ 0.213 ksi

Maximum spacing, s_{max} =	**18.0**	**in.**	***OK***
Governing spacing, s_{gov} =	**18.0**	**in.**	
$A_{v(provided)}$ =	0.40	$in.^2$	Assuming two #4 legs

$$V_s = \frac{A_v f_y d_v \cot\theta}{s_{gov}} = \quad 75.85 \quad \text{kips}$$

LRFD Eqn. 5.8.3.3-4

Shear reinforcement is required if : $0.5\phi(V_c+V_p) < V_u$

LRFD Eqn. 5.8.2.4-1

$0.5\phi(V_c+V_p) =$ 78.5 < Vu = 106.8 kips

Yes, Shear/Transverse Reinf. Is Required

(Back to Table of Contents)

Minimum shear reinforcement

LRFD 5.8.2.5

When shear reinforcement is required by design, the area of steel provided,

$$A_{v(provided)} \geq 0.0316\sqrt{f_c'}\,\frac{b_v s_{gov}}{f_y}$$

LRFD Eqn. 5.8.2.5-1

Use Spacing: 10.00 in <= 18.0 in

OK

where :

s = 10.0 in.

Required Area of Steel,

$$0.0316\sqrt{f_c'}\,\frac{b_v s_{gov}}{f_y} = \quad 0.34 \quad \text{in.}^2$$

0.40 > 0.34 in.^{2}

OK for Min. Transverse Reinf.

(Back to Table of Contents)

Longitudinal reinforcement

LRFD 5.8.3.5

Longitudinal reinforcement shall be provided so that at each section the following equations are satisfied :

$$A_s f_y + A_{ps} f_{ps}\left(\frac{d_v}{l_t}\right) \geq T = \frac{M_u}{d_v\phi} + \frac{0.5N_u}{\phi} + \left(\frac{V_u}{\phi} - 0.5V_s - V_p\right)\cot\theta$$

LRFD Eqn. 5.8.3.5-1

BDM 6.6-A3-1

A_s =	0.80	in^2	
f_y =	60.00	ksi	
A_{ps} =	2.14	in^2	Area of prestressing steel on the flexural tension side of the member(w/o unbonded)
f_{ps} =	258.77	ksi	f_{ps} multiplied by d_v/l_t ratio to account for lack of prestress development
d_v =	22.75	in.	
l_t =	2.50	ft =	30.00 in
M_u =	202.5	ft-kips	
ϕ =	1.00		Flexural in prestressed concrete
ϕ =	0.90		Shear
ϕ =	0.75		Axial Compression
N_u =	0.00		

V_u = 106.80 kips
V_s = 75.85 kips
V_p = 0.00 kips
θ = 21.80 degree

by substitution:

468.38 ≥ 308.7 kips **OK for Longitudinal Reinforcement**

(Back to Table of Contents)

13 Deflection and Camber

LRFD 5.7.3.6.2

Let downward Deflection be Positive +
Let upward Deflection, Camber, be Negative -

Deflection and camber calculations should be based on modulus of elasticity and maturity of concrete.
Instantaneous deflection should be computed for the effect of all dead loads and prestressing forces :

At 28 days:	f'_c =	7.0	ksi
	E_c =	5587.8	ksi
At final (120 days):	1.0 f'_c =	7.0	ksi
	E_c(1.0 f'_c) =	5587.8	ksi
At release:	f'_{ci} =	6.0	ksi
	E_{ci} =	5173.3	ksi

Deflection due to prestressing forces at Transfer

Deflection due to bottom strands is computed from a combination of fully bonded strands and the partially bonded or "debonded" strands which are sleeved at the ends of the girder. Each type has their own eccentricity.

$$\Delta ps_{bot.} = \Delta ps_{bb} + \Delta ps_{db}$$

$$\Delta ps_{bb} + \Delta ps_{db} = \left(P_{bb}e_{bb} + k_{db}P_{db}e_{db}\right)\frac{L^2}{8E_{ci}I_c}$$

Force and eccentricity due to the bonded bottom prestress strands are:

P_{bb} = 422.84 kips e_{bb} = 11.00 in

Reduction factor for the partially bonded or debonded strands

$$k_{db} = \frac{L - 2l_{db}}{L} = \quad 0.822$$

RMP

The average sleeved length of the debonded strands,

l_{db} = 4.0 ft = 48.0 in

BDM 6.6-A3-1

Force and eccentricity due to the debonded bottom prestress strands are:

P_{db} = 120.81 kips e_{db} = 11.00 in

$\Delta ps_{bot.}$ = -0.653 in. upward

Deflection due to top strands is computed from :

$$\Delta ps_{top} = \frac{P_t e_t L^2}{8 E_{ci} I_c}$$

Prestressing force and eccentricity of top strands.

P_t = 120.8 kips e_t = 10.00 in.

Δps_{top} = 0.137 in. downward

Total deflection due to prestressing :

$\Sigma \Delta_{ps}$ = -0.65 + 0.14 = -0.515 in. upward

(Back to Table of Contents)

Deflection due to weight of Girder

$$\Delta_g = \frac{5 w_g L^4}{384 E_{ci} I_c} =$$ 0.27 in. downward

AISC LRFD page 4-190

(Back to Table of Contents)

Deflection due to weight of Traffic Barrier TB

$$\Delta_{tb} = \frac{5 w_{tb(3G)} L^4}{384 E_c I_c}$$

Δ_{tb} = 0.04 in. downward

0.00 in. (Back to Table of Contents)

Deflection due to weight of Wearing Surface SIDL

$$\Delta_{SIDL} = \frac{5 w_{SIDL} L^4}{384 E_c I_c}$$

Δ_{SIDL} = 0.04 in. downward

(Back to Table of Contents)

Deflection (Camber) at transfer, C_i

Deflection accounted at transfer are due to prestressing and weight of girder :

At transfer : $\Sigma \Delta_i$ = -0.52 + 0.27 = -0.25 in.

$C_i = -\Delta_i$ = 0.25 in.

(Back to Table of Contents)

Final deflection due to all loads, C_F and C_{F+SIDL}

Long term deflection may be taken as four times the instantaneous deflection if calculations are based on the gross moment of inertia, Ig. — LRFD 5.7.3.6.2

Long term deflection :

4 Σ Δ = 4 (-0.52 + 0.27)= -1.00 in.

Using:

Σ Δ (long-term) = Σ Δ (elastic) X (Ψ (t, ti) + 1) — WSDOT

PS & Girder Long term Deflection

Find the Long term deflection (at 2000 days) due to Prestressing forces and Girder Self Weight only, C_F.

$$C_F = -\left[\left(\Delta_{PS} + \Delta_g\right)\left(\Psi_{(t,t_i)} + 1\right)\right]$$

Creep Coefficient : — LRFD 5.4.2.3.2

$$\Psi_{(t,t_i)} = 3.5 k_c k_f \left(1.58 - \frac{H}{120}\right) t_i^{-0.118} \frac{\left(t - t_i\right)^{0.6}}{10.0 + \left(t - t_i\right)^{0.6}}$$ — LRFD Eqn. 5.4.2.3.2-1

Factor for the effect of concrete strength,

$$k_f = \frac{1}{0.67 + \left(\frac{f_c'}{9}\right)} = \quad 0.69$$ — LRFD Eqn. 5.4.2.3.2-2

Factor for the effect of Volume-to-Surface ratio of the component specified in LRFD Figure 5.4.2.3.2-1,

$$k_c = \left[\frac{\frac{t}{26e^{0.36(V/S)} + t}}{\frac{t}{45 + t}}\right]\left[\frac{1.80 + 1.77e^{-0.54(V/S)}}{2.587}\right]$$ — LRFD (Eqn.) C5.4.2.3.2.-1

$k_c(t)$ = 0.70

$k_c(t_i)$ = 0.23

$k_c(t-t_i)$ = 0.70

Assume 1 Day of accelerated cure by radiant heat or steam. 1 Day accelerated cure = 7 normal Days of cure. Age of Concrete when load is initially applied, — LRFD 5.4.2.3.2

t_i = 7 DAY

Maturity of Concrete,

t = 2000 DAY — B.K.

Volume-to-Surface Ratio,

V/S = 5.02

Volume = lhb - Vol_{voids}

Actual length of the entire girder (endface-to-endface)

l= 550.00 in.

Volume of Voids

$Vol_{Voids} = A_{Voids} l_{Void}$

End of Void is minimum distance of **15** in. from end of girder. BDM 6.6-A2-1

l_{Void} = 520.00 in.

Vol_{Voids} = 201337 in^3

Volume = 485063 in^3

Assume the voids are exposed to atmospheric drying, but with poor ventilation with small drain holes on each end. Therefore use 50% of Void surface area. Email 2

LRFD 5.4.2.3.2

Surface Area = $A_{ends} + A_{sides} + A_{top\&bot} + 1/2A_{voids}$

Area of ends that will account for Skew Angle if any,

A_{ends} = 2496 in^2

A_{sides} = 28600 in^2

$A_{top\&bot}$ = 52800 in^2

$1/2A_{voids}$ = 12824 in^2

Surface Area = 96720 in^2

H = **80** average humidity LRFD Fig. 5.4.2.3.3-1

by substitution :

Ψ (t,ti)= 1.12

$\Sigma\Delta$ (long-term) = $\Sigma\Delta$ (elastic) X (Ψ (t, ti) + 1) = -0.53 in. upward

$$C_F = -\left[\left(\Delta_{PS} + \Delta_g\right)\left(\Psi_{(t,t_i)} + 1\right)\right] = \quad 0.53 \text{ in.} \quad \text{upward}$$

(Back to Table of Contents)

Find the deflection (at 120 days) due to Prestressing forces, Girder Self Weight, $C_{120days}$.

$$C_{120\ days} = C_F - [(\Delta_{tb} + \Delta_{SIDL})(\Psi_{(t,t_i)} + 1)]$$

Creep Coefficient for TB and ACP from 7 to 120 days:

$$\Psi_{(t,t_i)} = 3.5 k_c k_f \left(1.58 - \frac{H}{120}\right) t_i^{-0.118} \frac{(t - t_i)^{0.6}}{10.0 + (t - t_i)^{0.6}}$$

k_f = 0.69

Age of Concrete when load is applied,

t_i = 7 DAY

t = 120 DAY

$$k_c = \left[\frac{t}{\frac{26e^{0.36(V/S)}+t}{\frac{t}{45+t}}}\right]\left[\frac{1.80+1.77e^{-0.54(V/S)}}{2.587}\right]$$

Volume = 485063 in^3

Surface Area = 96720 in^2

V/S = 5.02

kc(ti) = 0.23

kc(t) = 0.44

kc(t-ti) = 0.43

H = 80 average humidity

by substitution :

Ψ (t,ti)= 0.48

$\Sigma\Delta$ (long-term) = $\Sigma\Delta$ (elastic) X (Ψ (t, ti) + 1) = -0.37 in. downward

Find the Long term deflection (at 2000 days) due to Prestressing forces, Girder Self Weight, Traffic Barrier, and ACP (SIDL), C_{F+SIDL}.

$$C_{F+SIDL} = C_F - [(\Delta_{tb} + \Delta_{SIDL})(\Psi_{(t,t_i)} + 1)]$$

Creep Coefficient for TB and ACP from 120 to 2000 days:

LRFD 5.7.3.6.2

LRFD 5.4.2.3.2

$$\Psi_{(t,t_i)} = 3.5k_c k_f \left(1.58 - \frac{H}{120}\right) t_i^{-0.118} \frac{(t-t_i)^{0.6}}{10.0+(t-t_i)^{0.6}}$$

k_f = 0.69

LRFD Fig. 5.4.2.3.2-1

Age of Concrete when load is applied,

t_i = 120 DAY

t = 2000 DAY

B.K.

$$k_c = \left[\frac{t}{\frac{26e^{0.36(V/S)}+t}{\frac{t}{45+t}}}\right]\left[\frac{1.80+1.77e^{-0.54(V/S)}}{2.587}\right]$$

Volume = 485063 in^3

Surface Area = 96720 in^2

V/S = 5.02

kc(ti) = 0.44

kc(t) = 0.70

kc(t-ti) = 0.70

H = 80 average humidity

by substitution :

Ψ (t,ti)= 0.79

$\Sigma\Delta$ (long-term) = $\Sigma\Delta$ (elastic) X (Ψ (t, ti) + 1) = 0.07 in. downward


(Back to Table of Contents)

$$C_{F+SIDL} = C_F - [(\Delta_{tb} + \Delta_{SIDL})(\Psi_{(t,t_i)} + 1)] = \quad 0.46 \quad \text{in.} \quad \text{upward}$$

Camber Summary

C_i =	0.25	in.	Upward	P/S + slab DL
$C_{120days}$ =	-0.37	in.	Upward	P/S + slab DL at 120 days
C_F =	0.53	in.	Upward	P/S + slab DL at 2000 days
C_{F+SIDL} =	0.46	in.	Upward	P/S + slab DL+TB+ ACP Overlay

(Back to Table of Contents)



ACP at Piers

ACP at Piers = **3.46** in.

(Back to Table of Contents)

References

AISC	LRFD Manual of Steel Construction (equation reference)
BDM	WSDOT Bridge Design Manual, August 2002
B.K.	WSDOT Bijan Khaleghi Concrete Design Specialist, 2002-2003
Email 1	Mel Hitzke Olympic Region Materials Engineer, 6/19/03
Email 2	Steve Seguirant of Concrete Tech, 6/04/03
LRFD	AASHTO LRFD Bridge Design Specifications, 2nd Edition 1998 with Interims thru 2002
Nilson	Design of PS Concrete, Author H. Nilson, 1987
RMP	WSDOT Richard Pawelka, 2002-2003
Prelim.Plan	West Fork Hoquiam Bridge Preliminary Plan, 2002-2003
Section	A Section Numbered in this Spreadsheet's Table of Contents
WSDOT	Washington State Dept. of Transportation Bridge & Structures office policy or memo

(Back to Table of Contents)

Design Example 6 Positive EQ Reinforcement at Interior Pier of a Prestressed Girder

Bridge Geometry and Material Properties

Girder type W74G

Sg := 7 ft Girder Spacing

Sc := 20 ft Column Spacing

Ng := 4 Number of Girders

Nc := 1 Number of Columns

es := 86 in

eg := 42 in

ds := 28 in

Skew_angle := 30 degrees

Aps := .215 in^2 per strand

fps := 270 ksi

fy := 60 ksi

$$Skew_angle := Skew_angle \cdot \frac{\pi}{180} \qquad Skew_angle = 0.524 \text{ Radians}$$

Top of the column Forces (from GTRSTRUDL):

Platic Moment, M_p (ft-kips) Mp := 12186

Plastic Shear, V_p (kips) Vp := 1200

Elastic Moment (R = 1), M_{eq} (ft-kips) Meq := 12167

Elastic Shear, V_{eq} (kips) Veq := 1157

Moment due to SIDL, M_{SIDL} (ft-kips) Msidl := 410

Connection design forces and cg of superstructure

1.2 x (The lesser of plastic hinging or elastic EQ Forces)

Mc = 1.2[Min (Mp or Meq) + Min(Vp or Veq)*es] - M_{SIDL}

$$Mc := 1.2 \cdot \left(Meq + Veq \cdot \frac{es}{12} \right) - Msidl$$

Mc = 24140.6 (ft-kips)

Vc = 1.2[Min(Vp or Veq)]

Vc := 1.2·(Veq)

Vc = 1388.4 (kips)

Distributed forces to each girder @ cg of superstructure

DF = 0.5 if $L_1 = L_2$

DF= 0.67 if $L_1 = 2 \times L_2$

Where L1 and L2 are the lengths of the Spans that are Supported by the girder

Since $L_1=L_2$, $DF := 0.5$

$Mg := DF \cdot Mc \cdot \frac{Nc}{Ng}$ $\quad Mg = 3017.58$ (ft-kips)

Bottom Strand Extension:

$Aps_total := \frac{Mg \cdot 12}{0.9 \cdot fps \cdot eg}$ $\quad Aps_total = 3.548$ in^2

$Number_of_strands := \frac{Aps_total}{Aps}$ $\quad Number_of_strands = 16.5$

Use 17 strands for bottom strand extension.

Vertical Diaphragm Stirrups

$$Av := \frac{Mg}{\left[\left(\frac{Sg}{\cos(Skew_angle)}\right) \cdot 0.9 \cdot fy \cdot \frac{ds}{12}\right]} \qquad Av = 2.963 \quad in^2/ft$$

$\mu := 1$ Coefficient of friction of normal weight concrete cast against hardened concrete

$Avf := \frac{Vc}{(2 \cdot Sg \cdot \cos(Skew_angle) \cdot fy \cdot \mu)}$ $\quad Avf = 1.909\ in^2/ft$ each side

Design Example : Positive Moment Connection for P/S Girder Bridges

Distance from Neutral axis of Girder to bottom strand of girder, $d := 38$ (in)

$eg := 6.5$ (ft)

Total Loads for the entire structure

$Mp := 12186$ (kip-ft)

$Vp := 1157$ (kips)

Per Girder Forces

$Mg := \frac{Mp}{Ng}$ $\quad Mg = 3046.5$ (kip-ft)

$Vg := \frac{Vp}{Ng}$ $\quad Vg = 289.25$ (kips)

Moment at Centroid of Crossbeam

$M := Mg + Vg \cdot eg$ $\quad M = 4926.63$ (kip-ft)

Area of Steel for Strand Extension

$$Aps_total := \frac{M \cdot 12}{0.9 \cdot fps \cdot d \cdot 2}$$

$Aps_total = 3.201 \quad in^2$

$$Number_of_strands := \frac{Aps_total}{Aps} \qquad Number_of_strands = 15$$

Moment for Fixity Reinforcment

$$Mf := (Mp + Vp \cdot eg) \cdot \frac{Sc}{Sg}$$

$Mf = 5.63 \times 10^4 \quad$ (kip-ft)

Spacing, $S := 5 \quad$ (inches)

$$Aps_totalF := \frac{Mf \cdot 12}{0.9 \cdot fy \cdot S}$$

$Aps_totalF = 2502.41 \ (in^2)$

Design Example 7 Noise Wall Type D-2K (Precast Panel on Shaft)

This design is based upon:

- AASHTO Guide Specifications for Structural Design of Sound Barriers - 1989 (including 2002 interim)
- AASHTO Standard Specifications for Highway Bridges 17th Ed. - 2002
- USS Steel Sheet Piling Design Manual - July 1984
- WSDOT Bridge Design Manual
- Caltrans Trenching and Shoring Manual - June 1995

This design doesn't account for the loads of a combined retaining wall / noisewall. A maximum of 2 ft of retained fill above the final ground line is suggested.

Concrete Properties:

$w_c := 160 \cdot pcf$ BDM 4.1.1

$f'c := 4000 \cdot psi$

$E_c := \left(\frac{w_c}{pcf}\right)^{1.5} \cdot 33 \cdot \sqrt{\frac{f'c}{psi}} \cdot psi$ $E_c = 4.224 \times 10^6\ psi$ Std Spec. 8.7.1

$\beta_1 := if\left(f'c \le 4000 \cdot psi, 0.85, \max\left(0.85 - \frac{f'c - 4000 \cdot psi}{1000 \cdot psi} \cdot 0.05, 0.65\right)\right)$ Std Spec. 8.16.2.7

$\beta_1 = 0.85$

$f_r := 7.5 \cdot \sqrt{\frac{f'c}{psi}} \cdot psi$ $f_r = 474.3\ psi$ Std Spec. 8.15.2.1.1

Reinforcement Properties:

Diameters: $dia(bar) := \begin{cases} 0.375 \cdot in & \text{if } bar = 3 \\ 0.500 \cdot in & \text{if } bar = 4 \\ 0.625 \cdot in & \text{if } bar = 5 \\ 0.750 \cdot in & \text{if } bar = 6 \\ 0.875 \cdot in & \text{if } bar = 7 \\ 1.000 \cdot in & \text{if } bar = 8 \\ 1.128 \cdot in & \text{if } bar = 9 \\ 1.270 \cdot in & \text{if } bar = 10 \\ 1.410 \cdot in & \text{if } bar = 11 \\ 1.693 \cdot in & \text{if } bar = 14 \\ 2.257 \cdot in & \text{if } bar = 18 \end{cases}$

Areas: $A_b(bar) := \begin{cases} 0.11 \cdot in^2 & \text{if } bar = 3 \\ 0.20 \cdot in^2 & \text{if } bar = 4 \\ 0.31 \cdot in^2 & \text{if } bar = 5 \\ 0.44 \cdot in^2 & \text{if } bar = 6 \\ 0.60 \cdot in^2 & \text{if } bar = 7 \\ 0.79 \cdot in^2 & \text{if } bar = 8 \\ 1.00 \cdot in^2 & \text{if } bar = 9 \\ 1.27 \cdot in^2 & \text{if } bar = 10 \\ 1.56 \cdot in^2 & \text{if } bar = 11 \\ 2.25 \cdot in^2 & \text{if } bar = 14 \\ 4.00 \cdot in^2 & \text{if } bar = 18 \end{cases}$

$f_y := 60000 \cdot psi$

$E_s := 29000000 \cdot psi$ Std. Spec. 8.7.2




FIGURE A: SHAFT LATERAL SOIL PRESSURES

Wall Geometry:

Wall Height:	H := 24·ft	H should be <= 28 ft
Half of Wall Height:	h := H·0.5	h = 12 ft
Shaft Diameter:	b := 2.50·ft	
Shaft Spacing:	L := 12·ft	

Wind Load (Guide Spec. Table 1-2.1.2.C):

WindExp := "B2" Wind Exposure B1 or B2 - Provided by the Region

WindVel := 90·mph Wind Velocity 80 or 90 mph - Provided by the Region

$$\text{WindPressure}(\text{WindExp}, \text{WindVel}) := \begin{cases} 12\cdot\text{psf} & \text{if } (\text{WindExp} = \text{"B1"} \wedge \text{WindVel} = 80\cdot\text{mph}) \\ 16\cdot\text{psf} & \text{if } (\text{WindExp} = \text{"B1"} \wedge \text{WindVel} = 90\cdot\text{mph}) \\ 20\cdot\text{psf} & \text{if } (\text{WindExp} = \text{"B2"} \wedge \text{WindVel} = 80\cdot\text{mph}) \\ 25\cdot\text{psf} & \text{if } (\text{WindExp} = \text{"B2"} \wedge \text{WindVel} = 90\cdot\text{mph}) \\ \text{"error"} & \text{otherwise} \end{cases}$$

Wind Pressure: $P_W := \text{WindPressure}(\text{WindExp}, \text{WindVel})$ $P_W = 25\,\text{psf}$

Seismic Load (Guide Spec. 1-2.1.3):

Acceleration Coefficient	$A := 0.29$		BDM 4.4-A2
DL Coefficient, Wall	$f := 0.75$		Not on bridge condition
Panel Plan Area:	$A_{pp} := 4in \cdot L + 13in \cdot 16in$	$A_{pp} = 5.44\,ft^2$	
Seismic Force EQD (perp. to wall surface):	$EQD := \max(A \cdot f, 0.1) \cdot \left(\frac{A_{pp} \cdot w_c}{L}\right)$	$EQD = 15.8\,psf$	

Factored Loads (Guide Spec. 1-2.2.2):

$Wind := 1.3 \cdot P_w \cdot 2 \cdot h \cdot L$	$Wind = 9360\,lbf$	
$EQ := 1.3 \cdot EQD \cdot 2 \cdot h \cdot L$	$EQ = 5911\,lbf$	
$P := \max(Wind, EQ)$	$P = 9360\,lbf$	Factored Design load acting at mid height of wall "h".

Soil Parameters:

Soil Friction Angle:	$\phi := 38 \cdot deg$		Provided by the Region
Soil Unit Weight:	$\gamma := 125 \cdot pcf$		Provided by the Region
Top Soil Depth:	$y := 2.0 \cdot ft$		From top of shaft to ground line
Ineffective Shaft Depth:	$d_o := 0.5 \cdot ft$		Depth of neglected soil at shaft
Isolation Factor for Shafts:	$Iso := \min\left(3.0, 0.08 \cdot \frac{\phi}{deg}, \frac{L}{b}\right)$ $Iso = 3.00$		Factor used to amplify the passive resistance based on soil wedge behavior resulting from shaft spacing - Caltrans pg 10-2.
Factor of Safety:	$FS := 1.00$		
Angle of Wall Friction:	$\underset{\sim}{\delta} := \frac{2}{3} \cdot \phi$	$\delta = 25.333\,deg$	Guide Spec. App. C pg. 33
Correction Factor for Horizontal Component of Earth Pressure:	$HC := \cos(\delta)$	$HC = 0.904$	
Foundation Strength Reduction Factors:	$\phi_{fa} := 1.00$	(Active)	Guide Spec. 1-2.2.3
	$\phi_{fp} := 0.90$	(Passive)	Guide Spec. 1-2.2.3




Fig. 5(a) — Active and passive coefficients with wall friction (sloping backfill) (after Caquot and Kerisel[21])

Side 1:

Backfill Slope Angle: $\beta_{s1} := -\text{atan}\left(\frac{1}{2}\right)$ $\beta_{s1} = -26.5651\,\text{deg}$ $\frac{\beta_{s1}}{\phi} = -0.70$

Using the USS Steel Sheet Piling Design Manual, Figure 5(a):

For ϕ = 38 deg and β_s = 0 deg:
K_a = 0.234, K_p = 14.20, R_p = 0.773

For ϕ = 32 deg and β_s = 0 deg:
K_a = 0.290, K_p = 7.85, R_p = 0.8366

For ϕ = 38 deg and β_s = -26.5651 deg:
K_a = 0.190, K_p = 3.060, R_p = 0.773

For ϕ = 32 deg and β_s = -26.5651 deg:
K_a = 0.230, K_p = 1.82, R_p = 0.8366

Active Earth Pressure Coeff: $K_{a1} := 0.190$ USS Fig. 5(a)

Passive Earth Pressure Coeff: $K_{p1} := 3.060$ USS Fig. 5(a)

Reduction for Kp: $R_{p1} := 0.773$ USS Fig. 5(a)

Active Pressure:

$\phi P_{a1} := K_{a1} \cdot \gamma \cdot HC \cdot \phi_{fa}$ $\phi P_{a1} = 21\,\frac{\text{psf}}{\text{ft}}$

Passive Pressure:

$\phi P_{p1} := \frac{K_{p1} \cdot R_{p1} \cdot \gamma \cdot HC \cdot Iso \cdot \phi_{fp}}{FS}$ $\phi P_{p1} = 722\,\frac{\text{psf}}{\text{ft}}$

Side 2:

Backfill Slope Angle: $\beta_{s2} := -\text{atan}\left(\frac{1}{2}\right)$ $\beta_{s2} = -26.565\,\text{deg}$ $\frac{\beta_{s2}}{\phi} = -0.70$

Active Earth Pressure Coeff: $K_{a2} := 0.190$ USS Fig. 5(a)

Passive Earth Pressure Coeff: $K_{p2} := 3.060$ USS Fig. 5(a)

Reduction for Kp: $R_{p2} := 0.773$ USS Fig. 5(a)

Active Pressure:

$\phi P_{a2} := K_{a2} \cdot \gamma \cdot HC \cdot \phi_{fa}$ $\phi P_{a2} = 21\,\frac{\text{psf}}{\text{ft}}$

Passive Pressure:

$\phi P_{p2} := \frac{K_{p2} \cdot R_{p2} \cdot \gamma \cdot HC \cdot Iso \cdot \phi_{fp}}{FS}$ $\phi P_{p2} = 722\,\frac{\text{psf}}{\text{ft}}$

Allowable Net Lateral Soil Pressure:

$R_1 := \phi P_{p1} - \phi P_{a2}$ $R_1 = 700\,\frac{\text{psf}}{\text{ft}}$ Side 1

$R_2 := \phi P_{p2} - \phi P_{a1}$ $R_2 = 700\,\frac{\text{psf}}{\text{ft}}$ Side 2

Depth of Shaft Required:

The function "ShaftD" finds the required shaft depth "d" by increasing the shaft depth until the sum of the moments about the base of the shaft "Msum" is nearly zero. See Figure A for a definition of terms.

$$\text{ShaftD}(d_o, P, R_1, R_2, b, h, y) :=$$

$d \leftarrow 0 \cdot ft$

$M_{sum} \leftarrow 100 \cdot lbf \cdot ft$

while $M_{sum} \geq 0.001 \cdot lbf \cdot ft$

$d \leftarrow d + 0.00001 \cdot ft$

$z \leftarrow \frac{2}{d \cdot (R_1 + R_2)} \cdot \left(\frac{R_2 \cdot d^2}{2} - \frac{R_2 \cdot d_o^{\,2}}{2} - \frac{P}{b} \right)$

$x \leftarrow \frac{R_2 \cdot z \cdot (d - z)}{R_1 \cdot d + R_2 \cdot (d - z)}$

$P1 \leftarrow (R_2 \cdot d_o) \cdot (d - d_o - z)$

$P2 \leftarrow R_2 \cdot (d - d_o - z)^2 \cdot \frac{1}{2}$

$P3 \leftarrow R_2 \cdot (d - z) \cdot x \cdot \frac{1}{2}$

$P4 \leftarrow R_1 \cdot d \cdot (z - x) \cdot \frac{1}{2}$

$X1 \leftarrow \frac{z + d - d_o}{2}$

$X2 \leftarrow \frac{2 \cdot z + d - d_o}{3}$

$X3 \leftarrow z - \frac{x}{3}$

$X4 \leftarrow \frac{1}{3} \cdot (z - x)$

$M_{sum} \leftarrow P \cdot (h + y + d) + b \cdot (-P1 \cdot X1 - P2 \cdot X2 - P3 \cdot X3 + P4 \cdot X4)$

d

Check for 2 load cases. Case 1 has load P acting as shown on Figure A. Case 2 has load P acting in the opposite direction.

Case 1:

$d_{c1} := \text{ShaftD}(d_o, P, R_1, R_2, b, h, y)$ $\quad d_{c1} = 11.18\,\text{ft}$

$z_{c1} := \frac{2}{d_{c1}\cdot(R_1 + R_2)}\cdot\left(\frac{R_2\cdot d_{c1}^{\,2}}{2} - \frac{R_2\cdot d_o^{\,2}}{2} - \frac{P}{b}\right)$ $\quad z_{c1} = 5.102\,\text{ft}$

$x_{c1} := \frac{R_2\cdot z_{c1}\cdot(d_{c1} - z_{c1})}{R_1\cdot d_{c1} + R_2\cdot(d_{c1} - z_{c1})}$ $\quad x_{c1} = 1.797\,\text{ft}$

$P4_{c1} := R_1\cdot d_{c1}\cdot(z_{c1} - x_{c1})\cdot\frac{1}{2}$ $\quad P4_{c1} = 12935\,\text{ft}^2\,\frac{\text{psf}}{\text{ft}}$

Case 2:

$d_{c2} := \text{ShaftD}(d_o, P, R_2, R_1, b, h, y)$ $\quad d_{c2} = 11.18\,\text{ft}$

$z_{c2} := \frac{2}{d_{c2}\cdot(R_1 + R_2)}\cdot\left(\frac{R_1\cdot d_{c2}^{\,2}}{2} - \frac{R_1\cdot d_o^{\,2}}{2} - \frac{P}{b}\right)$ $\quad z_{c2} = 5.102\,\text{ft}$

$x_{c2} := \frac{R_1\cdot z_{c2}\cdot(d_{c2} - z_{c2})}{R_2\cdot d_{c2} + R_1\cdot(d_{c2} - z_{c2})}$ $\quad x_{c2} = 1.797\,\text{ft}$

$P4_{c2} := R_2\cdot d_{c2}\cdot(z_{c2} - x_{c2})\cdot\frac{1}{2}$ $\quad P4_{c2} = 12935\,\text{ft}^2\,\frac{\text{psf}}{\text{ft}}$

Determine Shaft Lateral Pressures and Moment Arms for Controlling Case:

$d := \max(d_{c1}, d_{c2})$ $\quad d = 11.18\,\text{ft}$

$R_a := \text{if}(d_{c2} \geq d_{c1}, R_1, R_2)$ $\quad R_a = 700\,\frac{\text{psf}}{\text{ft}}$ $\quad R_b := \text{if}(d_{c2} \geq d_{c1}, R_2, R_1)$ $\quad R_b = 700\,\frac{\text{psf}}{\text{ft}}$

$z := \frac{2}{d\cdot(R_a + R_b)}\cdot\left(\frac{R_a\cdot d^2}{2} - \frac{R_a\cdot d_o^{\,2}}{2} - \frac{P}{b}\right)$ $\quad z = 5.102\,\text{ft}$ $\quad x := \frac{R_a\cdot z\cdot(d - z)}{R_b\cdot d + R_a\cdot(d - z)}$ $\quad x = 1.797\,\text{ft}$

$P1 := (R_a\cdot d_o)\cdot(d - d_o - z)$ $\quad P1 = 1953\,\frac{\text{lbf}}{\text{ft}}$ $\quad X1 := \frac{z + d - d_o}{2}$ $\quad X1 = 7.892\,\text{ft}$

$P2 := R_a\cdot(d - d_o - z)^2\cdot\frac{1}{2}$ $\quad P2 = 10901\,\frac{\text{lbf}}{\text{ft}}$ $\quad X2 := \frac{2\cdot z + d - d_o}{3}$ $\quad X2 = 6.962\,\text{ft}$

$P3 := R_a\cdot(d - z)\cdot x\cdot\frac{1}{2}$ $\quad P3 = 3825\,\frac{\text{lbf}}{\text{ft}}$ $\quad X3 := z - \frac{x}{3}$ $\quad X3 = 4.503\,\text{ft}$

$P4 := R_b\cdot d\cdot(z - x)\cdot\frac{1}{2}$ $\quad P4 = 12935\,\frac{\text{lbf}}{\text{ft}}$ $\quad X4 := \frac{1}{3}\cdot(z - x)$ $\quad X4 = 1.102\,\text{ft}$

$M_{sum} := P\cdot(h + y + d) + b\cdot(-P1\cdot X1 - P2\cdot X2 - P3\cdot X3 + P4\cdot X4)$ $\quad M_{sum} = -0.13163\,\text{lbf}\cdot\text{ft}$

Shaft Design Values:

The Maximum Shear will occur at the bolts or at the top of area 4 on Figure A:

$V_{shaft} := \max\left(P, P4_{c1} \cdot b, P4_{c2} \cdot b\right)$ $V_{shaft} = 32.34\,kip$

The Maximum Moment in the shaft will occur where the shear = 0.

Assume that the point where shear = 0 occurs in areas 1 and 2 on Figure A.

Check for Case 1:

$s_{c1} := -d_o + \sqrt{d_o^{\,2} + \frac{2 \cdot P}{R_2 \cdot b}}$ $s_{c1} = 2.808\,ft$

$M_{shaftc1} := P \cdot \left(h + y + d_o + s_{c1}\right) - R_2 \cdot d_o \cdot b \cdot s_{c1}^{\,2} \cdot \frac{1}{2} - R_2 \cdot b \cdot s_{c1}^{\,3} \cdot \frac{1}{6}$ $M_{shaftc1} = 152.1\,kip \cdot ft$

Check that the point where shear = 0 occurs in areas 1 and 2 on Figure A:

$Check1 := if\left[s_{c1} \le \left(d_{c1} - d_o - z_{c1}\right), "OK", "NG"\right]$ $Check1 = "OK"$

Check for Case 2:

$s_{c2} := -d_o + \sqrt{d_o^{\,2} + \frac{2 \cdot P}{R_1 \cdot b}}$ $s_{c2} = 2.808\,ft$

$M_{shaftc2} := P \cdot \left(h + y + d_o + s_{c2}\right) - R_1 \cdot d_o \cdot b \cdot s_{c2}^{\,2} \cdot \frac{1}{2} - R_1 \cdot b \cdot s_{c2}^{\,3} \cdot \frac{1}{6}$ $M_{shaftc2} = 152.09\,kip \cdot ft$

Check that the point where shear = 0 occurs in areas 1 and 2 on Figure A:

$Check2 := if\left[s_{c2} \le \left(d_{c2} - d_o - z_{c2}\right), "OK", "NG"\right]$ $Check2 = "OK"$

$M_{shaft} := \max\left(M_{shaftc1}, M_{shaftc2}\right)$ $M_{shaft} = 152.09\,kip \cdot ft$

Anchor Bolt and Panel Post Design Values:

$V_{bolt} := P$ $V_{bolt} = 9.36\,kip$

$M_{bolt} := P \cdot (h + y)$ $M_{bolt} = 131.04\,kip \cdot ft$

Panel Design Value (about a vertical axis):

Find Design Moment for a 1 ft wide strip of wall (between panel posts) for the panel flexure design

$w_{panel} := \max\left[P_w, \max(A \cdot f, 0.1) \cdot \left(4in \cdot w_c\right)\right]$ $w_{panel} = 25.0\,psf$

$M_{panel} := 1.3 \frac{w_{panel} \cdot L^2}{8}$ $M_{panel} = 585 \frac{lbf \cdot ft}{ft}$

Panel Post Resistance:

$Cl_{pa} := 1.0in$ Clear Cover to Ties

$h_{pa} := 17in$ Depth of Post

$b_{pa} := 10in$ Width of Post

$bar_A := 10$ Per Design Requirements

Check Flexural Resistance (Std. Spec. 8.16.3):

$\phi_f := 0.90$ Std. Spec. 8.16.1.2.2

$d_{pa} := h_{pa} - Cl_{pa} - dia(3) - \frac{dia(bar_A)}{2}$ $d_{pa} = 14.99\,in$ Effective depth

$A_s := 2 \cdot A_b(bar_A)$ $A_s = 2.54\,in^2$

$a := \frac{A_s \cdot f_y}{0.85 \cdot f'c \cdot b_{pa}}$ $a = 4.48\,in$

$M_n := A_s \cdot f_y \cdot \left(d_{pa} - \frac{a}{2}\right)$ $M_n = 161.91\,kip \cdot ft$

$\phi_f M_n = 145719\,lbf \cdot ft$

$Check3 := if(\phi_f M_n \geq M_{bolt}, "OK", "NG")$ $Check3 = "OK"$

Check Maximum Reinforcement (Std. Spec. 8.16.3.1):

$\rho_b := \frac{0.85 \cdot \beta_1 \cdot f'c}{f_y} \cdot \left(\frac{87000 \cdot psi}{87000 \cdot psi + f_y}\right)$ $\rho_b = 0.029$

$\rho := \frac{A_s}{b_{pa} \cdot d_{pa}}$ $\rho = 0.01694$

$Check4 := if(\rho \leq 0.75 \cdot \rho_b, "OK", "NG")$ $Check4 = "OK"$

Check Minimum Reinforcement (Std. Spec. 8.17.1.1):

$S_a := \frac{b_{pa} \cdot h_{pa}^2}{6}$ $S_a = 481.7\,in^3$

$M_{cra} := f_r \cdot S_a$ $M_{cra} = 19.04\,kip \cdot ft$

$Check5 := if(\phi_f M_n \geq \min(1.2 \cdot M_{cra}, 1.33 \cdot M_{bolt}), "OK", "NG")$ $Check5 = "OK"$

Check Shear (Std. Spec. 8.16.6) - Note: Shear Capacity of stirrups neglected:

$\phi_v := 0.85$ Std. Spec. 8.16.1.2.2

$V_{ca} := 2 \cdot \sqrt{\frac{f'c}{psi}} \cdot psi \cdot b_{pa} \cdot d_{pa}$ $V_{ca} = 18.96\,kip$

$Check6 := if(\phi_v \cdot V_{ca} \geq V_{bolt}, "OK", "NG")$ $Check6 = "OK"$

Panel Post Base Resistance:

$b_{pb} := 9in$ Width of Panel Post Base $bar_B := 9$ Per Design Requirements

$h_{pb} := 17.5in$ Depth of Panel Post Base

Check Flexural Resistance (Std. Spec. 8.16.3):

$\phi_f = 0.9$ Std. Spec. 8.16.1.2.2

$d_{pb} := h_{pb} - 0.75in$ $d_{pb} = 16.75\,in$ Effective deptl

$A_s := 2 \cdot A_b(bar_B)$ $A_s = 2\,in^2$

$a := \frac{A_s \cdot f_y}{0.85 \cdot f'c \cdot b_{pb}}$ $a = 3.92\,in$

$M_n := A_s \cdot f_y \cdot \left(d_{pb} - \frac{a}{2}\right)$ $M_n = 147.89\,kip \cdot ft$

$\phi_f \cdot M_n = 133103\,lbf \cdot ft$

$Check7 := if(\phi_f \cdot M_n \geq M_{bolt}, "OK", "NG")$ $Check7 = "OK"$

Check Maximum Reinforcement (Std. Spec. 8.16.3.1):

$\rho_b := \frac{0.85 \cdot \beta_1 \cdot f'c}{f_y} \cdot \left(\frac{87000 \cdot psi}{87000 \cdot psi + f_y}\right)$ $\rho_b = 0.029$

$\rho := \frac{A_s}{b_{pb} \cdot d_{pb}}$ $\rho = 0.01327$

$Check8 := if(\rho \leq 0.75 \cdot \rho_b, "OK", "NG")$ $Check8 = "OK"$

Check Minimum Reinforcement (Std. Spec. 8.17.1.1):

$S_b := \frac{b_{pb} \cdot h_{pb}^2}{6}$ $S_b = 459.4\,in^3$

$M_{crb} := f_r \cdot S_b$ $M_{crb} = 18.16\,kip \cdot ft$

$Check9 := if(\phi_f \cdot M_n \geq \min(1.2 \cdot M_{crb}, 1.33 \cdot M_{bolt}), "OK", "NG")$ $Check9 = "OK"$

Check Shear (Std. Spec. 8.16.6) - Note: Shear Capacity of stirrups neglected:

$\phi_v = 0.85$ Std. Spec. 8.16.1.2.2

$V_{cb} := 2 \cdot \sqrt{\frac{f'c}{psi}} \cdot psi \cdot b_{pb} \cdot d_{pb}$ $V_{cb} = 19.07\,kip$

$Check10 := if(\phi_v \cdot V_{cb} \geq V_{bolt}, "OK", "NG")$ $Check10 = "OK"$

Required Splice Length (Std. Spec. 8.25 and 8.32):

Basic Development Length (Std. Spec. 8.25.1):

$$l_{basic}(bar) := \begin{cases} \max\left(\dfrac{0.04 \cdot A_b(bar) \cdot f_y}{\sqrt{\frac{f'c}{psi}} \cdot psi \cdot in}, 0.0004 \cdot dia(bar) \cdot \dfrac{f_y}{psi}\right) & \text{if } bar \le 11 \\ \dfrac{0.085 \cdot f_y}{\sqrt{\frac{f'c}{psi}} \cdot psi} \cdot in & \text{if } bar = 14 \\ \dfrac{0.11 \cdot f_y}{\sqrt{\frac{f'c}{psi}} \cdot psi} \cdot in & \text{if } bar = 18 \\ \text{"error"} & \text{otherwise} \end{cases}$$

$l_{basicA} := l_{basic}(bar_A)$ $\quad l_{basicA} = 4.02\,ft$

$l_{basicB} := l_{basic}(bar_B)$ $\quad l_{basicB} = 3.16\,ft$

Development Length (Std. Spec. 8.25):

For top reinforcement placed with more than 12 inches of concrete cast below (Std. Spec. 8.25.2.1):

$l_{dA} := l_{basicA} \cdot 1.4$ $\quad l_{dA} = 5.62\,ft$

$l_{dB} := l_{basicB} \cdot 1.4$ $\quad l_{dB} = 4.43\,ft$

Required Lapsplice (Y):

The required lapsplice Y is the maximum of the required lap splice length of bar A (using a Class C splice), the development length of bar B, or 2'-0" per BDM 5.1.2.D.

$LapSplice := \max(1.7 \cdot l_{dA}, l_{dB}, 2 \cdot ft)$ $\quad LapSplice = 9.56\,ft$

Note: Lap Splices are not allowed for bar sizes greater than 11 per AASHTO Std. Spec. 8.32.1.1.

$Check11 := \text{if}(bar_A \le 11 \wedge bar_B \le 11, \text{"OK"}, \text{"NG"})$ $\quad Check11 = \text{"OK"}$

Anchor Bolt Resistance (Std. Spec. 10.56):

$V_{bolt} = 9360\,lbf$ $V_{bolt} = 9.36\,kip$

$M_{bolt} = 131040\,lbf \cdot ft$ $M_{bolt} = 1572.48\,kip \cdot in$

$d_{bolt} := 1.0 \cdot in$ Per Design Requirements

$A_{bolt} := \frac{\pi \cdot d_{bolt}^{2}}{4}$ $A_{bolt} = 0.785\,in^{2}$

$F_t := 30 \cdot ksi$ Std. Spec. Tbl. 10.56A for A307

$F_v := 18 \cdot ksi$ Std. Spec. Tbl. 10.56A for A307

$PanelAxialLoad := \left(4in \cdot \frac{L}{2} + 13in \cdot 10in\right) \cdot (2 \cdot h + y - 3in) \cdot w_c$ $PanelAxialLoad = 11.959\,kip$

$f_a := \frac{PanelAxialLoad}{4 \cdot A_{bolt}}$ $f_a = 3.81\,ksi$ Axial Compressive Stress

$f_v := \frac{V_{bolt}}{4 \cdot A_{bolt}}$ $f_v = 2.98\,ksi$ Shear Stress

$Check12 := if\left(f_v \le F_v, "OK", "NG"\right)$ $Check12 = "OK"$

$f_t := \frac{M_{bolt}}{13.5in} \cdot \frac{1}{2 \cdot A_{bolt}} - f_a$ $f_t = 70.35\,ksi$ Tensile Stress

$F_{t1} := if\left[\frac{f_v}{F_v} \le 0.33, F_t, F_t \cdot \sqrt{1 - \left(\frac{f_v}{F_v}\right)^{2}}\right]$ $F_{t1} = 30\,ksi$ Std. Spec. 10.56.1.3.3

$Check13 := if\left(f_t \le F_{t1}, "OK", "NG"\right)$ $Check13 = "NG"$

Design Summary:

Wall Height:	$H = 24\,ft$
Required Shaft Depth:	$d = 11.18\,ft$
Maximum Shaft Shear:	$V_{shaft} = 32339\,lbf$
Maximum Shaft Moment:	$M_{shaft} = 152094\,lbf \cdot ft$
Maximum Shaft Moment Accuracy Check (Case 1):	Check1 = "OK"
Maximum Shaft Moment Accuracy Check (Case 2):	Check2 = "OK"
Bar A:	$bar_A = 10$
Post Flexural Resistance (Bar A):	Check3 = "OK"
Maximum Reinforcement Check (Bar A):	Check4 = "OK"
Minimum Reinforcement Check (Bar A):	Check5 = "OK"
Post Shear Check (Bar A):	Check6 = "OK"
Bar B:	$bar_B = 9$
Post Flexural Resistance (Bar B):	Check7 = "OK"
Maximum Reinforcement Check (Bar B):	Check8 = "OK"
Minimum Reinforcement Check (Bar B):	Check9 = "OK"
Post Shear Check (Bar B):	Check10 = "OK"
Lap Splice Length:	$LapSplice = 9.558\,ft$
Lap Splice Allowed Check:	Check11 = "OK"
Bolt Diameter:	$d_{bolt} = 1\,in$
Anchor Bolt Shear Stress Check:	Check12 = "OK"
Anchor Bolt Tensile Stress Check:	Check13 = "NG"

Define Units: $ksi \equiv 1000 \cdot psi$ $kip \equiv 1000 \cdot lbf$ $kcf \equiv kip \cdot ft^{-3}$ $klf \equiv kip \cdot ft^{-1}$

$plf \equiv lbf \cdot ft^{-1}$ $psf \equiv lbf \cdot ft^{-2}$ $pcf \equiv lbf \cdot ft^{-3}$

Design Example 8 Construction Reinforcement in Crossbeam

Material Properties

Height of the crossbeam, h := 48 (in)

Fillet := 3 (in)

Ts := 7.5 (in)

Distance below top construction jo int in Crossbeam, d_joint := 3

Distance from Centroid of Tensile Reinforcment to Farthest Compressive Fiber,

d := h – Fillet − Ts − d_joint (in)

d := 34.5 (in)

Width of Compression Flange, b := 30 (in)

Moment of inertia of the Crossbeam during construction, $I := \left(\frac{1}{12}\right)\cdot b\cdot(h)^3$ I = 276480 (in^4)

Compressive Strength of the Concrete, f'c := 4.00 (ksi)

β1 := 0.85 for 4.00 ksi concrete

Yield Strength of the Reinforcing Stell, fy := 60 (ksi)

Resistance Factor, ϕ := 0.90

Weight of Concrete, wc := 0.160 (kcf)

Bridge Geometry

Length of the Crossbeam, L_crossbeam := 55

Number of Columns supporting the crossbeam, N_col :=2

Col_spacing :=25.0

Critical Moment Location form Left End of Crossbeam, $Crit_L := \frac{L_crossbeam}{2} - \frac{Col_spacing}{2}$

Crit_L = 15ft

Girder Overhang, G_o := 5 (ft)

Girder Spacing, G_s := 7.5 (ft)

Traffic Barrier with unit weight of Wtb := 0.980 klf located at end of crossbeam.

The design moment for construction reinforcement shall be the factored negative dead load moment due to the weight of the crossbeam and adjacent 10 feet of superstructure.

Calculation of Dead Loads of crossbeam and adjacent 10 feet of superstructure.

Distributed weight of crossbeam, $Wc := wc\cdot\left(\frac{h\cdot b}{144}\right)$ Wc = 1.6(klf)

Distributed weight of adjacent 10 feet of slab, $Ws := wc\cdot\left(\frac{Ts}{12}\right)\cdot 12$ Ws = 1 (klf)

A_girder := 2.59 (ft^2)

Weight of Girder, Wg := A_girder·wc·10

Wg = 4.144 (kips)

The Weight of the girder is applied at a distance, L1 := 10ft and L2 := 2.5ft away from the column support. (from bridge Geometry)

Weight of traffic barrier, Wtb := Wtb·10

Wtb = 9.8 (kips)

Calculation of Design Moment

Moment due to weight of crossbeam, $Mc := \frac{Crit_L^2}{2} \cdot Wc$ Mc = 180 (kip-ft)

Moment due to weight of slab, $Ms := \frac{Crit_L^2}{2} \cdot Ws$ Ms = 112.5 (kip-ft)

Moment due to Girders, Mg := Wg·(L1+ L2) Mg = 51.8 (kip-ft)

Moment due to Traffic Barriers, Mtb := Wtb·Crit_L Mtb = 147 (kip-ft)

Total Factored Negative Design Moment, Mu := 1.25·(Mc + Mg + Ms + Mtb)

Mu = 614.125 (kip-ft)

Calculation of Required Steel

Number of Bars, N_bars := 6

Rebar Size, Bar_size := 8

Area of Bars, $As := \left(\frac{Bar_size}{16}\right)^2 \cdot \pi \cdot N_bars$ As = 4.712 (in^2)

Height of compressive stress block, $a := \frac{fy \cdot As}{0.85 \cdot f'c \cdot b}$ a = 2.772 (in)

$Mr := \frac{\phi \cdot As \cdot fy}{12} \cdot \left(d - \frac{a}{2}\right)$ Mr = 702.207 kip·ft > Mu = 614.125 (kip-ft)

Check Cracking Requirements


$Yt := \left(\frac{h}{2}\right)$ Yt = 24 (in)

$Mcr := \frac{0.24}{12} \cdot \sqrt{f'c} \cdot \frac{I}{Yt}$ Mcr = 460.8 (kip-ft)


Factor := 1.2·Mcr Factor = 552.96 (kip-ft)

Since Mu >= 1.2 Mcr, the top of the Crossbeam is not going to crack during Construction.

Design Example 9 Stut and Tie Design



PLAN - PIER CAP



ELEVATION - PIER CAP

Design Loads


Group I: $P_u = 1600^k$ $H = 0$

Group VII: $P_u = 1500^k$ $H = 400^k$

Assume crossbeam dead load is included with bearing loads.

Use Section 12.4 of *AASHTO's Guide Specifications for Design and Construction of Segmental Concrete Bridges*, 1989.

Develop a Preliminary Strut-and-Tie Model:



STRUT & TIE DIAGRAM

Estimate node size at top of column:


$\phi_b (f_{cn} A_{cn}) \geq S_u$

Assuming spiral reinforcement provides confinement, use $\phi_b = 0.75$ and $f_{cn} = 0.85 f'_c$:

$0.75 (0.85 \times 5) A_{cn} \geq 2{,}400$


$A_{cn} \geq 753 \text{ in}^2$

Use the following node size at the top of column:




NODE SIZE AT TOP OF COLUMN

Determine Truss Element Forces:



Group I Strut Loads



Group VII Strut Loads

Determine Minimum Sizes of Node Regions:

$\phi_b (f_{cn} A_{cn}) \geq S_u$ where $\phi_b = 0.70$ for bearing

$f_{cn} = 0.85 f'_c$ in regions with compression only

$f_{cn} = 0.70 f'_c$ in regions with one tension tie

At base of inclined strut,

$0.70 (0.85 \times 5) A_{cn} \geq 2{,}596$

$A_{cn} \geq 873 \text{ in}^2$

depth of node $= \frac{873}{72''} = 12.1''$ $(72'' \times 12.1'')$

where width of crossbeam $= 72''$

At top of inclined strut, $A_{cn} \geq \frac{2{,}596}{0.70 (0.70 \times 5)} = 1{,}060 \text{ in}^2$

depth of node $= \frac{1{,}060}{72''} = 14.7''$ $(72'' \times 14.7'')$

For $1{,}600^k$ chord: $A_{cn} \geq \frac{1{,}600}{0.70 (0.85 \times 5)} = 538 \text{ in}^2$

depth of node $\frac{538}{72''} = 7.5''$

For 915^k chord: $A_{cn} \geq \frac{915}{1{,}600} (538) = 308 \text{ in}^2$

depth of node $\frac{308}{72''} = 4.3''$

Determine Minimum Sizes of Compression Members:

$\phi_v (f_{cu}\ A_{cs}) \geq S_u$ (inclined compressive struts)

$\phi_f (0.85 f'_c\ A_{cc} + A'_s\ f'_s) \geq S_u$ (compression chords)

For 2,596^k inclined compressive strut:

$0.85\ (0.45 \times 5)\ A_{cs} \geq 2{,}596^k$ $(f_{cu} = 0.45 f'_c)$

$$A_{cs} \geq \frac{2{,}596}{0.85\ (0.45)\ (5)} = 1{,}357\ in^2$$

and depth of strut $= \frac{1{,}357}{72} = 18.9$ in.

For 915^k inclined compressive strut:

$$A_{cs} \geq \frac{915}{2{,}596}\ (1{,}357) = 478\ in^2$$


and depth of strut $= \frac{478}{72} = 6.6$ in.

For 1,600^k compression chord:

$$A_{cs} \geq \frac{1{,}600}{0.9\ (0.85)\ (5)} = 418\ in^2$$


and depth of chord $= \frac{418}{72} = 5.8$ in.

Incorporate Node and Member Sizes Into Model:




STRUT & NODE GEOMETRY

Recalculate Truss Member Forces:



Group I Strut Loads



Group VII Strut Loads

Design Tie Member:

$$\phi_f (A_s f_{sy} + A_{ps} f_{pu}) \geq S_u$$

without prestress: $0.90\ (A_s)\ (60) \geq 2{,}240$

$$A_s \geq 41.5\ in^2$$

Try using 12 bundles of #14 top and #11 bot ($A_s = 45.7\ in^2$)

Check development length of tie bars:


For #14 bars with $f'_c = 5{,}000$ psi, $l_{dh} = 2' - 5''$

Development length available = $2' - 4'' < 2' - 5''$

For #11 bars, $l_{dh} = 1' - 5''$ ok

Therefore, total developed steel $A_s = 12\ (1.56) + 12\ (2.25)\left(\frac{28}{29}\right)$

$$A_s = 44.8\ in^2 > 41.5\ in^2 \quad \text{ok}$$



Partial Elevation-Tension Tie at Top of Pier Cap

$$x = \frac{12\ (2.25)\ (3.26) + 12\ (1.56)\ (5.97)}{45.7} = 4.37'' \approx 4''$$ estimate. ok

Determine Minimum Vertical And Horizontal Steel Using Sections 12.5.3.2 and 12.5.3.3.

For vertical reinforcing: $A_s f_y \geq 120\, b_w\, s$

where $s < \frac{d}{4}$ or $12''$

Therefore, $A_s \geq \frac{120}{60{,}000\, b_w\, s} = 0.002\, b_w\, s$

Assume 4 legs of #6 stirrups: $A_s = 1.76\ in^2$

$$s \leq \frac{A_s}{0.002\, b_w} = \frac{1.76}{0.002\,(72)}$$

$$s \leq 12.2\ in.$$

Check: $\frac{d}{4} = \frac{72 - 4.37}{4} = 16.9''$

Therefore, use 4 #6 legs at $12''$ maximum spacing.

For horizontal reinforcing: $A_s f_y \geq 120\, b_w\, s$

where $s < \frac{d}{3}$ or $12''$

For $s = 12''$, $A_s \geq 0.002\,(72)\,(12) = 1.73\ in^2$ (2 – #9 bars)

Try 2 #8 bars: $A_s = 1.58\ in^2$

$$s \leq \frac{1.58}{0.002\ (72)} = 11.0''$$

Use #8 bars at **11"** maximum spacing on side faces.

For bottom bars, use #6 at approximately $12''$ (7 – #6 bars)

Design Example 10 Crossbeam Shear and Torsion Design

Given: Pier Crossbeam with Length, Lc := 35.4ft and with two Columns support, each with centerline 8.5 feet from the end of crossbeam.

Factored Shear, Trosion, and Axial Force:

Vu := 778.3 (kip)

Tu := 722 (kip-ft)

Factored Axial force taken as positive if Tension, Nu := 0 (kips)

Concrete Class 4000. F'c := 4.0 (ksi)

Reinforcing Steel, Grade 60, fy := 60 (ksi)

Modulus of Elasticity, Es := 29000 (ksi)

Unit Weight of Concrete, wc := 0.160 (kcf)

Depth of Crossbeam, D := 48 (in)

Width of Crossbeam, W := 72 (in)

Weight of girder per foot, Wg := D·W·wc $Wg := D \cdot W \cdot \frac{wc}{144}$ $Wg = 3.84$ (kip/ft)

$\frac{Vu}{Lc} = 21.99$ (kips/ft)

$\frac{Tu}{Lc} = 20.4$ (kip-ft/ft)

Calculate the Required Longitudinal Rebar Requirements

Negative Moment Reinforcement

Factored Negative Moment at Columns, Mu := 2500 (kip-ft)

Size of Negative Moment (Top Bar), Barsize_t := 9

Area of one Bar Reinforcement, As :=1 (in^2)

Required Cover for Steel Reinforcing, Cover := 3 (in)

$d := D - Cover - \frac{Barsize_t}{16}$ $d = 44.44$ (in)

b := W $b = 72$ (in)

Number of Bars Used For Negative moment reinforcement, Nbars := 14

Total Area of Steel, Ast := Nbars·As

$a := \frac{Ast \cdot fy}{0.85 \cdot f'c \cdot b}$ $a = 3.43$ (in)

Resistance factor to Moment, $\phi := 0.90$

Flexural Resistance, $Mr := \frac{\phi \cdot Ast \cdot fy}{12} \cdot \left(d - \frac{a}{2} \right)$ $Mr = 2691.47$ (kip/ft)

Positive Moment Reinforcement

Factored Negative Moment at Columns, Mu := 1392 (kip-ft)

Size of Negative Moment (Bottom Bar), Barsize_t := 8

Area of one Bar Reinforcement, As := 0.7853 (in^2)

Required Cover for Steel Reinforcing, Cover := 3 (in)

$d := D - Cover - \frac{Barsize_t}{16}$ d = 44.5 (in)

b := W b = 72 (in)

Number of Bars Used For Negative moment reinforcement, Nbars := 10

Total Area of Steel, Ast := Nbars·As

$a := \frac{Ast \cdot fy}{0.85 \cdot f'c \cdot b}$ a = 1.92 (in)

Resistance factor to Moment, $\phi := 0.90$

Flexural Resistance, $Mr := \frac{\phi \cdot Ast \cdot fy}{12} \cdot \left(d - \frac{a}{2} \right)$ Mr = 1538.55 (kip-ft)

Calculation and Introduction of Torsion Effects

Number of legs of Closed transverse Torsion reinforcing, N_legs := 4

Bar size of Stirrups, Bss := 5

Area of one leg of Closed Transverse Torsion reinforcement, $At := \left(\frac{Bss}{16} \right)^2 \cdot \pi$

Minimum Cover Requirements, Cover := 2.5 At = 0.307 (in^2)

Perimeter of the centerline of the closed transverse torsion reinforcement, Ph

ph := 2·(w-Cover) +2·(D-cover) ph = 230 (in)

Area enclosed by centerline of exterior closed transverse torsion reinforcement, including area of holes, if any, Aoh := (W-2·Cover)·(D-2·Cover)

Aoh = 2881 (in^2)

Area enclosed by shear flow path, including any holes, Ao := 0.85·Aoh

Ao = 2448.85 (in^2) per C5.8.3.6.2 of AASHTO LRFD

For combined shear and torsion, ℇx shall be determined using Equation 5.8.3.6.2-2 of AASHTO LRFD, with Vu replaced by:

$Vu := \sqrt{Vu^2 + \left(\frac{0.9 \cdot ph \cdot Tu}{2 \cdot Ao} \right)^2}$ Vu = 778.898 (kips)

Component in the direction of the applied shear of the effective prestressing force; positive if resisting the applied shear, Vp

Since their is no prestressing inthe crossbeam, Vp := 0

Effective Shear Depth, Shall be taken as the greatest of the following per AASHTO LRFD 5.8.2.9

$dv := 0.72 \cdot D$ $\quad dv = 34.56$ (in)

$dv := 0.9 \cdot d$ $\quad dv = 40.05$ (in)

$dv := d - \frac{a}{2}$ $\quad dv = 40.05$ (in)

$dv = 43.54$ (in)

Resistance factor for shear, $\phi := 0.90$

Effective Web Width, $bv := 90$ (inch)

The angle θ shall be as specified in either Table 5.8.3.4.2-1 or Table 5.8.3.6.2-2, as appropriate. with the shear stress, v, taken as for box section:

$$v := \frac{Vu - \phi \cdot Vp}{\phi \cdot bv \cdot dv} + \frac{Tu \cdot ph}{\phi \cdot Aoh^2} \qquad v = 0.243 \text{ (kis)}$$

$\frac{v}{f'c} = 0.061$ $\quad$ Guess a value of $\varepsilon x := .001$

From Table 5.8.3.4.2-1 of AASHTO LRFD,

$\theta := 36.4$ (degrees)

$\beta := 2.23$

Calculate εx from Equation 5.8.3.4.2-1 of AASHTO LRFD and compare to guess.

Since there is no prestressing inthe Crossbeam:

$Aps := 0$ (in^2)

$fpo := 0$ (ksi)

$Eps := 285000$ (ksi)

$$\varepsilon x := \frac{\frac{Mu}{dv} + 0.5 \cdot Nu + \frac{0.5 \cdot (Vu - Vp)}{\tan\left(\frac{\pi}{180} \cdot \theta\right)} - Aps \cdot fpo}{2 \cdot (Es \cdot As + Eps \cdot Aps)} \qquad \varepsilon x = 0.0123$$

Try again with a new value of $\varepsilon x = .00125$

$\theta := 38.6$ (degrees)

$\beta := 2.09$

$$\varepsilon x := \frac{\frac{Mu}{dv} + 0.5 \cdot Nu + \frac{0.5 \cdot (Vu - Vp)}{\tan\left(\frac{\pi}{180} \cdot \theta\right)} - Aps \cdot fpo}{2 \cdot (Es \cdot As + Eps \cdot Aps)} \qquad \varepsilon x = 0.01141$$

The nominal Shear resistance, Vn, shall be determined as the lesser of:

$Vn = Vc + Vp + Vs$

$Vn = 0.25\ f'c\ bv\ dv + Vp$

$Vn_1 := \frac{Vu}{\phi}$ $\quad Vn_1 = 865.44$ (kips)

$Vn_2 := 0.25 \cdot f'c \cdot bv \cdot dv + Vp$ $\quad Vn_2 = 3918.39$ (kips)

$Vn := Vn_1$ $\quad Vn = 865.442$ (kips)

Shear Resistance Provided by Concrete, $Vc := 0.0316\sqrt{f'c \cdot bv \cdot dv}$ $\quad Vc = 247.64$ (kips)

Shear Resistance Provided by Stirrups, $Vs := Vn - Vc - Vp$ $\quad Vs = 617.8$ (kips)

$Av := At \cdot N_legs$ $\quad Av = 1.227$ (in^2)

Required Spacing of Transverse Reinforcing, $s := \frac{Av \cdot fy \cdot dv}{\tan\left(\theta \cdot \frac{\pi}{180} \cdot Vs\right)}$ $\quad s = 6.5$ (in)

Check Spacing Requirements

Check the minimum Transverse Reinforcement per AASHTO LRFD 5.8.2.5.

$Av := 0.0316 \cdot \sqrt{f'c} \cdot \frac{bv \cdot s}{fy}$ $\quad Av = 0.616$ (in^2)

Steel Provided, $As_prov := At \cdot N_legs$ $\quad As_prov = 1.227$ (in^2) $\quad$ OK

Check the maximum spacing of the transverse reinforcement per AASTHO LRFD 5.8.2.7

If $v_u < 0.125$ f'c then:

$s_{max} = 0.8 d_v \leq 24$ (in) (5.8.2.7-1)

If $v_u \geq 0.125$ f'c then:

$s_{max} = 0.4 d_v \leq 12$ (in) (5.8.2.7-2)

The supplied spacing meets the minimum required spacing.

The nominal torsional resistance shall be taken as per AASHTO LRFD 5.8.3.6.2:

$Tn := \frac{\phi \cdot 4 \cdot Ao \cdot At \cdot fy}{s \cdot \tan\left(\theta \cdot \frac{\pi}{180}\right)}$ $\quad Tn = 31274.33$(kip/in)

The transverse reinforcing for shear meets the requirements for the required torsional resistance.

Check Longitudinal Reinforcement

$$Asfy := \frac{Mu}{\phi \cdot dv} + \frac{0.5 \cdot Nu}{\phi} + \frac{1}{\tan\left(\theta \cdot \frac{\pi}{180}\right)} \cdot \left[\sqrt{\left(\frac{Vu}{\phi} - 0.5 \cdot Vs - Vp\right)^2 + \left(\frac{0.45 \cdot ph \cdot Tu}{2 \cdot Ao \cdot \phi}\right)^2}\right]$$

$(Ast + Asb) \cdot fy = 1311.18$ (kips) $\geq$ $Asfy = 733.016$ (kips) $\quad$ OK

Design Example 11 Torsion and Shear Capacity of Reinforced Concrete Beams

Concrete Properties:

$f'c := 4 \cdot ksi$

Reinforcement Properties:

Bar Diameters: Bar Areas:

$$dia(bar) := \begin{cases} 0.375 \cdot in & \text{if } bar = 3 \\ 0.500 \cdot in & \text{if } bar = 4 \\ 0.625 \cdot in & \text{if } bar = 5 \\ 0.750 \cdot in & \text{if } bar = 6 \\ 0.875 \cdot in & \text{if } bar = 7 \\ 1.000 \cdot in & \text{if } bar = 8 \\ 1.128 \cdot in & \text{if } bar = 9 \\ 1.270 \cdot in & \text{if } bar = 10 \\ 1.410 \cdot in & \text{if } bar = 11 \\ 1.693 \cdot in & \text{if } bar = 14 \\ 2.257 \cdot in & \text{if } bar = 18 \end{cases} \qquad A_b(bar) := \begin{cases} 0.11 \cdot in^2 & \text{if } bar = 3 \\ 0.20 \cdot in^2 & \text{if } bar = 4 \\ 0.31 \cdot in^2 & \text{if } bar = 5 \\ 0.44 \cdot in^2 & \text{if } bar = 6 \\ 0.60 \cdot in^2 & \text{if } bar = 7 \\ 0.79 \cdot in^2 & \text{if } bar = 8 \\ 1.00 \cdot in^2 & \text{if } bar = 9 \\ 1.27 \cdot in^2 & \text{if } bar = 10 \\ 1.56 \cdot in^2 & \text{if } bar = 11 \\ 2.25 \cdot in^2 & \text{if } bar = 14 \\ 4.00 \cdot in^2 & \text{if } bar = 18 \end{cases}$$

$f_y := 40 \cdot ksi$

$E_s := 29000ksi$ LRFD 5.4.3.2

$E_p := 28500ksi$ LRFD 5.4.4.2 for strands

$bar_{LT} := 18$ Longitudinal -Top

$bar_{LB} := 18$ Longitudinal -Bottom

$bar_T := 6$ Transverse

$d_{LT} := dia(bar_{LT})$ $d_{LT} = 2.257in$ $A_{LT} := A_b(bar_{LT})$ $A_{LT} = 4in^2$

$d_{LB} := dia(bar_{LB})$ $d_{LB} = 2.257in$ $A_{LB} := A_b(bar_{LB})$ $A_{LB} = 4in^2$

$d_T := dia(bar_T)$ $d_T = 0.75in$ $A_T := A_b(bar_T)$ $A_T = 0.44in^2$

Beam Section Properties:

$b := 37in$

$h := 90in$

$bottomcover := 1.625 \cdot in$

$sidecover := 1.625 \cdot in$

$topcover := 1.625 \cdot in$

Factored Loads:

$V_u := 450 \cdot kip$

$T_u := 500 \cdot kip \cdot ft$

$M_u := 0 \cdot kip \cdot ft$

$N_u := 0 \cdot kip$

Torsional Resistance:

The factored Torsional Resistance shall be: LRFD 5.8.2.1

$Tr = \phi \cdot T_n$

Torsion shall be investigated where:

$T_u > 0.25 \cdot \phi \cdot T_{cr}$

$\phi := 0.90$ For Torsion and Shear LRFD 5.5.4.2

$A_{cp} := b \cdot h$ $A_{cp} = 3330 in^2$

$P_c := (b + h) \cdot 2$ $P_c = 254 in$

$f_{pc} := 0 \cdot ksi$

$$T_{cr} := 0.125 \cdot \sqrt{\frac{f'c}{ksi}} \cdot \frac{\left(\frac{A_{cp}}{in^2}\right)^2}{\left(\frac{p_c}{in}\right)} \cdot \sqrt{1 + \frac{\frac{f_{pc}}{ksi}}{0.125 \cdot \sqrt{\frac{f'c}{ksi}}}} \cdot kip \cdot in \qquad T_{cr} = 10914 kip \cdot in$$

$T_{cr} = 909.5 kip \cdot ft$

$0.25 \cdot \phi \cdot T_{cr} = 204.6 kip \cdot ft$

$T_u > 0.25 \cdot \phi \cdot T_{cr} = 1$ Torsion shall be investigated.

For a section subjected to combined Shear and Torsion:

$$p_h := 2 \cdot \left[\left[b - 2 \cdot \left(sidecover + \frac{d_T}{2} \right) \right] + \left(h - topcover - bottomcover - d_T \right) \right]$$

$p_h = 238 in$

$$A_{oh} := \left[b - 2 \cdot \left(sidecover + \frac{d_T}{2} \right) \right] \cdot \left(h - topcover - bottomcover - d_T \right)$$

$A_{oh} = 2838 in^2$

$A_o := 0.85 \cdot A_{oh}$ $A_o = 2412.3 in^2$

Adjusted Shear for calculation of ε:

$$V_{ust} := \sqrt{V_u^2 + \left(\frac{0.9 \cdot p_h \cdot T_u}{2 \cdot A_o} \right)^2} \qquad V_{ust} = 522.9 kip$$ LRFD 5.8.3.6.2-2

$\theta := 36.4 \cdot deg$ Assume to begin iterations

$d_e := 90in - 30in$ $d_e = 87in$ LRFD 5.8.2.9

$d_v := \max(0.9 \cdot deg, 0.72 \cdot h)$ $d_v = 78.3in$

$b_v := b$ $b_v = 37in$

$V_p := 0 \cdot kip$ No Prestress Stands

$A_{ps} := 0 \cdot in^2$ No Prestress Stands

$A_s := 4 \cdot A_{LB}$ $A_s = 16in^2$ For 4 #18 bars

$f_{po} := 0 \cdot ksi$

LRFD 5.8.3.4.2-2

$$\varepsilon_x := \frac{\left[\frac{M_u}{d_v} + 0.5 \cdot N_u + 0.5 \cdot \left(V_{ust} - V_p\right) \cdot \cot(\theta) - A_{ps} \cdot f_{po}\right]}{E_s \cdot A_s + E_p \cdot A_{ps}}$$

$\varepsilon_x \cdot 1000 = 0.764$

LRFD 5.8.3.6.2-4

$$v_u := \sqrt{\left(\frac{V_u - \phi \cdot V_p}{\phi \cdot b_v \cdot d_v}\right)^2 + \left(\frac{T_u \cdot p_h}{\phi \cdot A_{oh}^2}\right)^2} \qquad v_u = 0.262\,ksi$$

$$\frac{v_u}{f'c} = 0.065$$

From Table 5.8.3.4.2-1, Find β and θ

$\theta := 36.4 \cdot deg$ Value is close to original guess. OK

$\beta := 2.23$

Torsional Resistance:

$A_t := A_T$ $A_t = 0.44in^2$

$s := 5 \cdot in$ Spacing of Reinforcement resisting Torsion

$T_n := \frac{2 \cdot A_o \cdot A_t \cdot f_y \cdot \cot(\theta)}{s}$ $T_n = 23035\ kip \cdot in$ LRFD 5.8.3.6.2-1

$T_n = 1920\ kip \cdot ft$

$T_r := \phi \cdot T_n$ $T_r = 20731\ kip \cdot in$ LRFD 5.8.2.1

$T_r = 1728\ kip \cdot in$

$T_r \geq T_u = 1$ OK

Shear resistance:

The factores Shear Resistance shall be: LRFD 5.8.2.1

$V_r = \phi \cdot V_n$

$V_c := 0.0316 \cdot \beta \cdot \sqrt{\frac{f'c}{ksi}} \cdot b_v \cdot d_v \cdot ksi$ $V_c = 408.3\ kip$ LRFD 5.8.3.3

$\alpha := 90 \cdot deg$

$A_v := A_T$ $A_v = 0.44 in^2$

$s := 5 \cdot in$ Spacing of Reinf. resisting Shear

$$V_s := \frac{A_v \cdot f_y \cdot d_v \cdot (\cot(\theta) + \cot(\alpha)) \cdot \sin(\alpha)}{s} \quad V_s = 373.8 \text{ kip}$$

$V_n := \min(V_c+V_s+V_p, 0.25 \cdot f'c \cdot b_v \cdot d_v+V_p)$ $V_n = 782.1$ kip

$V_r := \phi \cdot V_n$ $V_r = 703.9$ kip

$V_r \geq V_u = 1$ OK

Check for Longitudinal Reinforcement: LRFD 5.8.3.6.3

$f_{ps} := 0 \cdot ksi$

$A_s \cdot f_y + A_{ps} \cdot f_{ps} = 640.0$ kip

$$\frac{M_u}{\phi \cdot d_v} + \frac{0.5 \cdot N_u}{\phi} + \cot(\theta) \cdot \sqrt{\left(\frac{V_u}{\phi} - 0.5 \cdot V_s - V_p\right)^2 + \left(\frac{0.45 \cdot p_h \cdot T_u}{2 \cdot A_o \cdot \phi}\right)^2} = 469.7 \text{ kip}$$

640.0 kip >= 469.7 kip OK

Design Example 12 Strain Compatibility Approach for Flexural Capacity

Materials: Cast- in-place Slab

Actual thickness, tc = 8.0in

Structural thickness, height_slab :=7.5in

Concrete Strength at 28 days, f'c_slab := 4.0ksi

Precast Beams: AASHTO - PCI Bulb Tee

Concrete Strength at 28 days, f'c_beam := 6.5ksi

t_top_flange := 42in

Prestressing Strands: 1/2" Diameter, Seven Wire, Low Relaxation

Area of One Strand, Area_bars $0.153in^2$

fpu := 270ksi

Yield Strength, fpy := 0.9fpu fpy = 243ksi =

Stress Limits for prestressing strands:

At Service Limit State (after all losses) , fse < 0.80fpy = 194.4ksi

Modulus of Elasticity, Eps := 28500ksi

Total Number of Prestressing Strands, num_bars := 48

Centroid of Prestressing Strands above bottom of Girder,
center_prestressing_strands 6.9in

Non Composite Section Properties

h_beam := 72in

Step 1 Assume a neutral axis depth c and substitute in the equation below to obtain the corresponding strain in each steel layer "i". A layer "i" is defined as a group of bars or tendons with the same stress-strain properties and effective prestress, and which can be assumed to have a combined area with a s ingle centroid.

di = Depth of steel from Extreme compression fiber (in)

fse = effective prestress. For partially tensioned tendons or for non-reinforced rebars, f_{se} may be assumed = f_{pi} - 25 ksi where f_{pi} is initial tension.

c := 9.75in fse := 194.4ksi

center_prestressing_strands = 6.9in di := (h_beam+height_slab)-center_prestressing_strands

$$\varepsilon si := 0.003 \cdot \left(\frac{di}{c} - 1 \right) + \frac{fse}{Eps} \qquad \varepsilon si = 0.026$$

Step 2 Estimate the stress in each steel layer

For Low Relaxation 270 ksi Strands: $fsi := fpu - \frac{0.04ksi}{(\varepsilon si - 0.007)}$ $fsi = 267.91\,ksi$

Step 3 Use Equilibrium of Forces to Check assumed Neutral Axis Depth

$\Sigma Asifsi + \Sigma Fcj = 0$

$\Sigma Asifsi := (Area_bars \cdot num_bars) \cdot fsi \qquad \Sigma Asifsi = 1967.5\,kip$

Average the coefficient β1 over the concrete materials if the depth of the compression block is greater than the depth of the cast in place concrete slab.

$$\beta_{1avg} = \frac{\Sigma(f'c\ Ac\ \beta 1)j}{\Sigma(f'c\ Ac)_j}$$

initial guess of $\beta 1 := 0.81$ $\quad initial_a := \beta 1\ c$ $\quad initial_a := 7.897in$ $\quad width_of_slab := 60in$

$$\beta 1avg := \frac{f'c_slab \cdot width_of_slab \cdot height_slab \cdot 0.85 + f'c_beam \cdot (initial_a - height_slab) \cdot t_top_flange \cdot 0.725}{f'c_slab \cdot width_of_slab \cdot height_slab + f'c_beam \cdot (initial_a - height_slab) \cdot t_top_flange}$$

$\beta 1avg = 0.843 \qquad a := \beta 1avg \cdot c \qquad a = 8.22in$

$\Sigma Fcj := -0.85 \cdot (width_of_slab \cdot height_slab) \cdot f'c_slab - 0.85 \cdot (a - height_slab) \cdot t_top_flange \cdot f'c_beam$

$\Sigma Fcj = -1696.66kip$

$\Sigma Fcj + \Sigma Asifsi = 270.89kip$ Error is not with in 1% so repeat Procedure

Step 4 Revise "c" and repeat steps 1 through 3 as necessary By decreasing the value of "c", the area of the compressive stress block decreases. This corresponds to a much smaller compressive force. If the value of "c" is increased, the compressive force increases. After a few trials, a neutral axis that satisfied equilibrium was found. For simplicity, all intermediate iterations will be skipped.

Step 1 Final Trial

Assume new neutral axis at $c := 11.30in$ and compute strain in each stell layer.

$$\varepsilon si := 0.003 \cdot \left(\frac{di}{c} - 1\right) + \frac{fse}{Eps} \qquad \varepsilon si = 0.023$$

Step 2 Final Trial

$$fsi := fpu - \frac{0.04ksi}{(\varepsilon si - 0.007)} \qquad fsi = 267.51$$

Step 3 Final Trial

$\Sigma Asifsi := Area_bars \cdot num_bars \cdot fsi \qquad \Sigma Asifsi = 1964.63kip$

$\beta 1 := 0.824 \qquad initial_a := \beta 1 \cdot c \qquad initial_a = 9.31in$

Note: The new Value of β1 is equal to the value of β1avg of the last iteration.

$$\beta 1avg := \frac{f'c_slab \cdot width_of_slab \cdot height_slab \cdot 0.85 + f'c_beam \cdot (initial_a - height_slab) \cdot t_top_flange \cdot 0.725}{f'c_slab \cdot width_of_slab \cdot height_slab + f'c_beam \cdot (initial_a - height_slab) \cdot t_top_flange}$$

$\beta 1avg = 0.823 \qquad a := \beta 1avg \cdot c \qquad a = 9.3in$

$\Sigma Fcj := -0.85 \cdot (width_of_slab \cdot height_slab) \cdot f'c_slab - 0.85 \cdot (a - height_slab) \cdot t_top_flange \cdot f'c_beam$

$\Sigma Fcj = -1947.83kip$

$\Sigma Fcj + \Sigma Asifsi = 16.8kip$ Error is with in 1%, so equilibrium is satisfied.

Step 5 Calculate the nominal flexural capacity by summing moments of all forces about the top fiber of the compressive face.

di = distance from top of slab to the midpoint of pretensioned steel di = 72.6in

dj1 = distance from top of slab to centroid of compressive block on slab,

$$dj1 := \frac{height_slab}{2} \qquad dj1 = 3.75\,in$$

dj2 = distance from top of slab to centroid of compressive block on beam,

$$dj2 := height_slab + \frac{a - height_slab}{2} \qquad dj2 = 8.4\,in$$

Fcj1 := 0.85·width_of_slab·height_slab·f'c_slab Fcj1 = 1530kip

Fcj2 := 0.85·(a –Height_slab)·t_top_flange·f'c_beam Fcj2 = 417.83kip

ΣFcjdj := Fcj1·dj1+Fcj2·dj2 Mn := ΣAsifsi·di –ΣFcjdj Mn = 11115kip·ft

Step 6 Calculate the Design Moment Capacity, ϕMn

ϕ := 1 For Precast Concrete Fleural Members

Mr := ϕ·Mn

Mr:= 11115kip·ft

	AASHTO LRFD Specifications	Strain Compatibility
Neutral Axis Depth, c (in)	12.14	11.30
Compression Block Depth, a (in)	10.32	9.30
ϕMν	10782kip-ft	Mr =11115 kip·ft
	97%	100%

Chapter 6 Structural Steel

6.0 Structural Steel 6-1
6.0.1 Introduction 6-1
6.1 Design Considerations 6-1
6.1.1 Codes, Specification, and Standards 6-1
6.1.2 Preferred Practice 6-2
6.1.3 Preliminary Girder Proportioning 6-2
6.1.4 Estimating Structural Steel Weights 6-3
6.1.5 Bridge Steels 6-6
6.1.6 Available Plate Sizes 6-7
6.1.7 Girder Segment Sizes 6-7
6.1.8 Computer Programs 6-7
6.1.9 Fasteners 6-8
6.2 Girder Bridges 6-10
6.2.1 General 6-10
6.2.2 I-Girders 6-10
6.2.3 Tub or Box Girders 6-11
6.2.4 Special Live Load Criteria for Curved Girders 6-12
6.3 Design of I-Girders 6-13
6.3.1 Limit States for LRFD 6-13
6.3.2 Composite Section 6-13
6.3.3 Flanges 6-13
6.3.4 Webs 6-14
6.3.5 Transverse Stiffeners 6-14
6.3.6 Longitudinal Stiffeners 6-14
6.3.7 Bearing Stiffeners 6-14
6.3.8 Crossframes 6-15
6.3.9 Bottom Laterals 6-16
6.3.10 Bolted Field Splice for Girders 6-16
6.3.11 Camber 6-17
6.3.12 Roadway Slab Placement Sequence 6-18
6.3.13 Bridge Bearings for Steel Girders 6-19
6.3.14 Surface Roughness and Hardness 6-19
6.3.15 Welding 6-20
6.3.16 Shop Assembly 6-21
6.4 Plan Details 6-23
6.4.1 General 6-23
6.4.2 Structural Steel Notes 6-23
6.4.3 Framing Plan 6-23
6.4.4 Girder Elevation 6-23
6.4.5 Typical Girder Details 6-24
6.4.6 Crossframe Details 6-24
6.4.7 Camber Diagram and Bearing Stiffener Rotation 6-24
6.4.8 Roadway Slab 6-24
6.4.9 Handrail Details and Inspection Access 6-25
6.5 Shop Plan Review 6-26
6.99 References 6-26

Appendix 6-A

Figure 6-A-1	Steel Plate Girder Framing Plan	6-A-1
Figure 6-A-2	Steel Plate Girder Girder Elevation	6-A-2
Figure 6-A-3	Steel Plate Girder Girder Details	6-A-3
Figure 6-A-4	Steel Plate Girder Field Splice	6-A-4
Figure 6-A-5	Steel Plate Girder Crossframes	6-A-5
Figure 6-A-6	Steel Plate Girder Camber Diagram	6-A-6
Figure 6-A-7	Steel Plate Girder Roadway Section	6-A-7
Figure 6-A-8	Steel Plate Girder Slab Plan	6-A-8
Figure 6-A-9	Handrail	6-A-9

6.0 Structural Steel

6.0.1 Introduction

This chapter primarily covers design and construction of steel plate girder bridge superstructures. Because of their limited application, other types of steel superstructures (truss, arch, cable stayed, suspension, etc.) are not addressed.

Plate girder bridges are commonly used for river crossings and curved interchange ramps. Typical span lengths range from 150 to 300 feet. Steel girders are also being used where limited vertical clearance requires shallow superstructure depth. They may be set over busy highway lanes with a minimum of disruption and falsework, similar to precast concrete elements. Longitudinal launching of steel framing or transverse rolling of completed steel structures has been done successfully.

English units are the current standard for detailing. Metric units may be used on a case-by-case basis. Widening or rehabilitation plan units should be consistent with the original.

6.1 Design Considerations

6.1.1 Codes, Specification, and Standards

Steel highway bridges shall be designed to the following codes and specifications:

- AASHTO LRFD *Bridge Design Specifications, Third Edition*
- AASHTO *Guide Specifications for Horizontally Curved Steel Girder Highway Bridges, 2003* (use with AASHTO *Standard Specifications for Highway Bridges, 17th Edition*) See 6.2.4 for curved girder live load criteria.
- AASHTO/AWS D1.5M/D1.5:2002 *Bridge Welding Code*
- ANSI/AWS A2.4-98 *Standard Symbols for Welding, Brazing, and Nondestructive Examination*

The following codes and specifications shall govern steel bridge construction:

- WSDOT *Standard Specifications for Road, Bridge, and Municipal Construction*, latest edition
- AASHTO/AWS D1.5M/D1.5:2002 *Bridge Welding Code*
- AASHTO *Guide Specifications for Highway Bridge Fabrication with HPS70W Steel*, latest edition

The following AASHTO/NSBA Steel Bridge Collaboration publications are available to aid in the design and fabrication of steel bridges:

- *Design Drawing Presentation Guidelines*
- *Guidelines for Design for Constructibility*
- *Shop Detail Drawing Presentation Guidelines*
- *Steel Bridge Fabrication Guide Specification*
- *Steel Bridge Fabrication QC/QA Guide Specification*
- *Guide Specification for Coating Systems with Inorganic Zinc-Rich Primer*

6.1.2 Preferred Practice

Unshored, composite construction is used for most plate girder bridges. Shear connectors are placed throughout positive and negative moment regions, for full composite behavior. One percent longitudinal deck steel, placed in accordance with LRFD article 6.10.1.7, ensures adequate deck performance in negative moment regions. For service level stiffness analysis, such as calculating live load moment envelopes, the slab may be considered composite and uncracked for the entire bridge length, provided the above methods are used. See LRFD articles 6.6.1.2.1 and 6.10.1.5. For negative moment at strength limit states, the slab is ignored while reinforcing steel is included for stress and section property calculations. Where span arrangement is not well balanced, these assumptions may not apply.

Plastic design may be utilized for simple span and positive moment regions of medium to long span plate girder bridges. In negative moment regions, plastic design is only economical for short span beams.

Currently, economical design requires simplified fabrication with less emphasis on weight reduction. The number of plate thicknesses and splices should be minimized. Also, the use of fewer girder lines, spaced at a maximum of about 14 feet, saves on fabrication, shipping, painting, and future inspection. Widely spaced girders will have heavier flanges, hence, greater stability during construction. Normally, dropping a girder line will eliminate a web without the need for thickening remaining webs. The increased shear requirement can be met with a modest addition of web stiffeners.

For moderate to long spans, partially stiffened web design is the most economical. This method is a compromise between slender webs requiring transverse stiffening throughout and thicker, unstiffened webs. Stiffeners used to connect crossframes shall be welded to top and bottom flanges. Jacking stiffeners shall be used adjacent to bearing stiffeners, on girder or diaphragm webs, in order to accommodate future bearing replacement. Coordinate jack placement in substructure and girder details.

Steel framing should consist of main girders and crossframes. Bottom lateral systems should only be used when temporary bracing is not practical. Where lateral systems are needed, they should be detailed carefully for adequate fatigue life.

Standard corrosion protection for steel bridges is a three-coat paint system, west of the Cascades and where paint is required for appearance. Weathering steel should be considered for dry, eastern regions. When high performance steel is used and appearance is not critical, a single shop coat of inorganic zinc-rich primer may be considered in coastal regions.

WSDOT does not currently allow the use of steel stay-in-place deck forms.

6.1.3 Preliminary Girder Proportioning

The superstructure depth is initially determined during preliminary plan development and is based upon the span/depth ratios provided in Chapter 2 of this manual. The depth may be reduced to gain vertical clearance, but the designer should verify live load deflection requirements are met. It is office practice to limit live load deflections in accordance with the optional criteria of LRFD articles 2.5.2.6.2 and 3.6.1.3.2.


The superstructure depth is typically shown as the distance from the top of the concrete roadway slab to the bottom of the web. Web depths are generally detailed in multiples of 6 inches.

Interior and exterior girders should be detailed as equal. Spacing should be such that the distribution of wheel loads on the exterior girder is close to that of the interior girder. The number of girder lines should be minimized, with a maximum spacing of 14 feet. Three or more girders lines are considered redundant. If a non-redundant bridge is proposed, approval must be obtained from the Bridge Design Engineer.

6.1.4 Estimating Structural Steel Weights


For the preliminary quantities or preliminary girder design, an estimate of steel weights for built-up plate composite "I" girders can be obtained from Figures 6-1 through 6-3. These figures are based upon previous designs with AASHTO HS-20 live loads with no distinction between service load designs and load factor designs. These charts also provide a good double check on final quantities.

The weights shown include webs, flanges, and all secondary members (web stiffeners, diaphragms, crossframe, lateral systems, gusset plates) plus a small allowance for weld metal, bolts, and shear connectors.




Composite Welded Steel Plate "I" Girder — Simple Span

Figure 6-1



Composite Welded Steel Plate "I" Girder — Two Continuous Spans

Figure 6-2



Composite Welded Steel Plate “I” Girder — Three or More Continuous Spans
Figure 6-3

6.1.5 Bridge Steels

The most common types of steel used for bridges are now grouped in ASTM A 709 or AASHTO M 270 specifications. The following table shows equivalent designations. Grades of steel are based on minimum yield point.

ASTM	ASTM A 709	AASHTO M 270
A 36	Grade 36	Grade 36
A 572 gr 50	Grade 50	Grade 50
A 992 (W shapes)	Grade 50S	---
A 588	Grade 50W	Grade 50W
	Grade HPS50W	Grade HPS50W
A 852	Grade 70W	Grade 70W
---	Grade HPS70W	Grade HPS70W
A 514*	Grade 100*	Grade 100*
	Grade l00W*	Grade l00W*

* Minimum yield strength is 90 ksi for plate thickness greater than 2 ½".

Plates and rolled sections are available is these specifications and grades. Rolled sections include beams (W, S, and M shapes), H-piles, tees, channels, and angles. These materials are prequalified under the Bridge Welding Code. The common specification for wide flange beams is now ASTM A 992.

Use AASHTO M 270 grade 50W for plate girders. The fabricated costs of structural carbon and structural low alloy steel plate girders are about equal. AASHTO now recommends grade HPS70W instead of grade 70W for bridge use. HPS70W can be economical if used selectively in hybrid design. For moderate spans consider HPS70W for the bottom flanges throughout and top flanges near interior piers. The use of M 270 grade 100 or 100W requires approval by the Bridge Design Engineer, and should not be used until grade HPS100W is available.

All main load-carrying members or components subject to tensile stress shall be identified in the plans and be required to meet the minimum Charpy V-notch (CVN) fracture toughness values as specified in LRFD table 6.6.2-2, temperature zone 2. Fracture critical members or components shall also be designated in the plans.

Availability of weathering steel can be a problem for some sections. For example, steel suppliers do not stock angles or channels in weathering steel. Weathering steel wide flange and tee sections are difficult to locate or require a mill order. ASTM A 709 and AASHTO M 270 bridge steels are not stocked by local service centers. The use of bridge steel should be restricted to large quantities such as found in typical plate girder projects. The older ASTM specification steels, such as A 36, should be specified when a fabricator would be expected to purchase from local service centers. The older AASHTO designations, such as M183, have been dropped.

Structural tubes and pipes are covered by other specifications. See the latest edition of the AISC *Manual of Steel Construction* for selection and availability. These materials are not considered prequalified under the Bridge Welding Code. They are covered under the Structural Welding Code AWS D1.1. Structural tubing ASTM A 500 is not recommended for dynamic loading applications unless minimum CVN requirements are specified.

6.1.6 Available Plate Sizes

Readily available lengths and thicknesses of steel plates should be used to minimize costs. Tables of standard plate sizes have been published by various steel mills and should be used for guidance. These tables are available through the steel specialist, or online.

In general, an individual plate should not exceed 14 feet in width, including camber requirements, or a length of about 60 feet. If either or both of these dimensions are exceeded, a butt splice is required and should be shown or specified on the plans. Some plates may be available in lengths over 90 feet, so web splice locations should be considered optional. Quenched and tempered plates are limited to 50 feet, based on oven size.

Plate thicknesses of less than $^{5}/_{16}$ inches should not be used for bridge applications.

When metric units are used, all steel dimensions, including thickness, should be hard converted. For example, specify 25 mm, not 25.4 mm plate.

Preferred plate thicknesses, English units, are a follows:

- 5/16” to 7/8” in 1/16” increments
- 7/8” to 1 ¼” in 1/8” increments
- 1 ¼” to 4” in ¼” increments

6.1.7 Girder Segment Sizes

Locate bolted field splices so that individual girder segments can be handled, shipped, and erected without imposing unreasonable requirements on the contractor. Crane limitations need to be considered in congested areas near traffic or buildings. Transportation route options between the girder fabricator and the bridge site can affect the size and weight of girder sections allowed. Underpasses with restricted vertical clearance in sag vertical curves can be obstructions to long, tall segments shipped upright. The region should help determine the possible routes, and the restrictions they impose, during preliminary planning or early in the design phase.

Segment lengths should be limited to 150 feet, depending upon cross section. Long, slender segments can be difficult to handle and ship due to their flexibility. Horizontal curvature of girder segments may increase handling and shipping concerns. Out-to-out width of curved segments, especially box girders, should not exceed 14 feet. Weight is seldom a controlling factor for I-girders. However, 40 tons is a practical limit for some fabricators. Limit weight to a maximum of 100 tons if delivery by truck is anticipated.

Consider the structure’s span length and the above factors when determining girder segment lengths. In general, field splices should be located at dead load inflection points. When spans are short enough, some field splices can be designated optional if resulting segment lengths and weights meet the shipping criteria.

6.1.8 Computer Programs

The designer should consult the design supervisor to determine the computer program best suited for a particular bridge type. Instruction manuals for the programs are available in the Bridge Office Computer Section.

Office practice and good engineering principles require that the results of any computer program or analysis be independently verified for accuracy. Also, programs with built-in code checks must be checked for default settings. Default settings may reflect old code or office practice may supercede the code that the program was written for.

6.1.9 Fasteners

All bolted connections shall be friction type (slip-critical). Assume Class B faying surfaces where inorganic zinc primer is used. If steel will be given a full paint system in the shop, the primed faying surfaces need to be masked to maintain the Class B surface.

Properties of High-Strength Bolts

Material	Bolt Diameter	Tensile Strength ksi	Yield Strength ksi
AASHTO M 164	5/8 - 1 inc	120	92
(ASTM A325)	1 1/8 - 1 1/2 inc.	105	81
	Over 1 1/2		Not Available
ASTM A 449	1/4 - 1 inc	120	92
(No AASHTO	1 1/8 - 1 1/2 inc.	105	81
equivalent)	1 3/4 -3 inc.	90	58
	Over 3		Not Available
AASHTO			
M 314	1/4 - 3 inc	125-150	105
(ASTM F 1554)			
Grade 105			
AASHTO			
M253	5/8 - 1 1/2 inc.	150-170	130
(ASTM A 490)			
	Over 1 1/2		Not Available
ASTM A 354	1/2 - 2 1/2 inc.	150	130
Grade BD			
(No AASHTO	3 - 4 inc.	140	115
equivalent)	Over 4		Not Available

General Guidelines for Steel Bolts

A. M 164 (A325) — High strength steel, headed bolts for use in structural joints. These bolts may be hot-dip galvanized. Do not specify for anchor bolts.

B. A449 — High strength steel bolts and studs for general applications including anchor bolts. Recommended for use as anchor bolts where strengths equivalent to A325 bolts are desired. These bolts may be hot-dip galvanized. Do not use these anchor bolts for seismic applications due to low CVN impact toughness.

C. M 314 (F1554) — Grade 105 — Higher strength anchor bolts to be used for larger sizes (11/2″ to 3″). When used in seismic applications, ASTM F 1554 shall be specified, since AASHTO M 314 lacks the CVN supplemental requirements. Specify supplemental CVN requirement S5 when these are used in seismic applications (most bridge bearings that resist lateral loads). Lower grades may also be suitable for sign structure foundations. This specification should also be considered for seismic restrainer rods, and may be galvanized.

D.	M 253 (A490)	High strength alloy steel, headed bolts for use in structural joints. These bolts should not be galvanized, because of the high susceptibility to hydrogen embrittlement. In lieu of galvanizing, the application of an approved zinc rich paint may be specified. Do not specify for anchor bolts.
E.	A354	Grade BD — high strength alloy steel bolts and studs. These are suitable for anchor bolts where strengths equal to A490 bolts are desired. These bolts should not be galvanized. If used in seismic applications, specify minimum CVN toughness of 25 ft-lb at 40 deg F.

6.2 Girder Bridges

6.2.1 General

Once the material of choice, structural steel has been eclipsed by reinforced and prestressed concrete. Corrosion and fatigue cracking have contributed to unanticipated life cycle costs. Fabrication and material costs have also contributed to steel's relative cost disadvantage. Costs may be minimized by simplifying fabrication details, optimizing the number of girder lines, allowing for repetitive fabrication of components such as crossframes and stiffeners, and ensuring ease of shipping and erecting.

The specifications allow a combination of plastic design in positive moment regions and elastic design in negative moment regions. Plate girders, of the depths typically built in this state, have traditionally been designed to elastic limits or lower. Newer design methods may help reduce steel weight and narrow the cost gap between steel and concrete bridges. High performance steel can be used to advantage saving weight and painting.

6.2.2 I-Girders

Welded plate I-girders constitute the majority of steel girders designed by WSDOT. The I-girder represents an efficient use of material for maximizing stiffness. Its shortcoming is inefficiency in resisting shear. Office practice is to maintain constant web thickness and depth for short to medium span girders. Weight savings is achieved by minimizing the number of webs used for a given bridge. This also helps minimize fabrication, handling, and painting costs. Current office practice is to use a minimum of three girders to provide redundant load path structures. Two girder superstructures are considered non-redundant and hence, fracture critical.

Buckling behavior of relatively slender elements complicates steel plate girder design. Most strength calculations involve checks on buckling in some form. Local buckling can be a problem in flanges, webs, and stiffeners if compression is present. Also, overall stability needs to be insured for all stages of construction, with or without a roadway deck. The art of designing steel girders is to minimize material and fabrication expense while ensuring adequate strength, stiffness, and stability.

I-girders are an excellent shape for welding. All welds for the main components are easily accessible and visible for welding and inspection. The plates are oriented in the rolling direction to make good use of strength, ductility, and toughness of the structural steel. The web is attached to the top and bottom flanges with continuous fillet welds. Usually, they are made with automatic submerged arc welders. These welds are loaded parallel to the longitudinal axis and resist horizontal shear between the flanges and web. Minimum size welds based on plate thickness will satisfy strength and fatigue requirements in most cases. The flanges and webs are fabricated to full segment length with full penetration groove welds. These welds are inspected by ultrasound (UT) 100 percent. Tension welds, as designated in the plans, are also radiographed (RT) 100 percent. Office practice is to have flanges and webs fabricated full length before they are welded into the "I" shape. Weld splicing built-up sections results in poor fatigue strength and zones that are difficult to inspect. Quality welding and inspection requires good access for both.

6.2.3 Tub or Box Girders

Typical steel box girders for WSDOT are trapezoidal tub sections. Using single top flange plates to create true box sections is very uncommon when reinforced concrete decks are used. Tub girders will be referred to herein as box girders, as in LRFD article 6.11.

The top lateral system placed inside the girder is treated as an equivalent plate, closing the open section, to increase torsional stiffness before slab curing. Although not required by the code, it helps ensure stability that may be overlooked during construction. Partial or temporary bracing may be used provided it is properly designed and installed. Dramatic construction failures have occurred due to insufficient bracing of box girders. Stability of the shape must be ensured for all stages of construction per LRFD article 6.11.3. The cured deck serves to close the section for torsional stiffness. Internal crossframes or diaphragms are used to maintain the shape and minimize distortion loading on individual plates and welds making up the box. Box segments will have considerable torsional stiffness when top lateral bracing is provided. This may make fit-up in the field difficult.

The ability to make box girders with high torsional stiffness makes them a popular choice for short radius curved structures. Curved box girders, because of inherent torsional stiffness, behave differently than curved I-girders. Curved box girder behavior is approximated by the M/R method, rather than the V-load method. See curved girder references listed at the end of this chapter for complete description.

Straight box girders, when proportioned in accordance with LRFD article 6.11.2 may be designed without consideration of distortional stresses. The range of applicability for live load distribution is based on:

$$0.5 \le N_L/N_b \le 1.5$$

which limits the number of lanes loading each box. Wide box girder spacing, outside this range, will require additional live load analysis. Consideration must be given to differential deflection between boxes when designing the roadway deck. Generally, use of crossframes between boxes is limited to long spans with curvature.

Box girders should be detailed for single bearings per box. If bearings are located under each web, distribution of loads is uncertain. Generally, plate diaphragms with access holes are used in place of pier crossframes.

With the exception of effects from inclined webs, top flanges and webs are designed as if they were part of individual I-girders.

The combined bottom flange is unique to box girders. In order to maximize web spacing while minimizing bottom flange width, office practice is to place webs out of plumb on a slope of 1 in 4. Wide plates present two difficulties: excessive material between shop splices and buckling behavior in compression zones (interior piers). To keep weight and plate thickness within reason, it is often necessary to stiffen the bottom flange in compression with longitudinal stiffeners. Office practice is to use tee sections for longitudinal stiffeners and channel bracing at crossframe locations (transverse stiffeners). If possible, bottom flange stiffeners are terminated at field splices. Otherwise, carefully ground weld terminations are needed in tension regions with high stress range. Due to the transverse flexibility of thin wide plates, stiffener plates are welded across the bottom flange at crossframe locations, combined with web vertical stiffeners. For the design of the bottom flange in compression, see LRFD articles 6.11.8.2 and 6.11.11.2.

6.2.4 Special Live Load Criteria for Curved Girders

Refer to AASHTO Guide Specifications for Horizontally Curved Steel Girder Highway Bridges 2003, Chapter 3.5. Use HS-25 loading for strength and overload conditions. Use HS-20 loading for deflection checks.

Check live load plus impact deflections on a per bridge basis. Include the overturning effect of centrifugal force. The number of lanes, shall be calculated by rounding down to the whole number of 12 foot lanes that fit on the bridge. Include multiple lane reductions.

Impact is defined in AASHTO Guide Specifications 3.5.6.

Fatigue live load is defined in AASHTO LRFD Guide Specifications 3.5.7 and follows AASHTO LRFD Article 3.6.1.4. The AASHTO LRFD fatigue truck is a fixed axle HS-20 truck, positioned in accordance with 3.5.7.2 of the Guide Specification.

6.3 Design of I-Girders

6.3.1 Limit States for LRFD

Structural components shall be proportioned to satisfy the requirements of strength, extreme event, service, and fatigue limit states as outlined in LRFD articles 1.3.2 and 6.5.

Service limit states are included in Service I and Service II load combinations. Service I load combination is used to check the live load deflection limitations of LRFD article 2.5.2.6. Service II load combination is the LRFD equivalent of the LFD overload provisions. Service II places limits on permanent deflection no yielding, slenderness of the web in compression, and slip of bolted connections.

The fatigue live load specified in LRFD article 3.6.1.4 shall be used for checking girder details per article 6.6. A single fatigue truck, without lane loading or variable axle spacing, is placed for maximum and minimum effect to a detail under investigation. The impact is 15%, regardless of span length. The load factor is 0.75. It is generally possible to meet the constant amplitude fatigue limit (CAFL) requirement for details with good fatigue performance. Limiting twice the calculated fatigue range to the CAFL ensures infinite fatigue life. Webs shall be checked for fatigue loading in accordance with LRFD article 6.10.5.3, using twice the calculated fatigue stress range for flexure or shear. Shear connector spacing shall be according to article 6.10.10. Generally, the fatigue resistance (Zr) for 7/8" diameter shear connectors can be taken as 2.1 kips for an infinite number of cycles (CAFL = 4.2 kips).

Flanges and webs must meet strength limit state requirements for both construction and final phases. Constructibility requirements for flanges and webs are covered in article 6.10.3. Flexure resistance is specified in articles 6.10.7 and 6.10.8; shear resistance is specified in article 6.10.9

Pier crossframes shall be designed for seismic loading, extreme event load combination. Bolts are treated as bearing type connections with article 6.5.4.2 resistance factors. The resistance factor for all other members is 1.0 at extreme limit state.

6.3.2 Composite Section

Live load plus impact is applied to the transformed composite section using Es/Ec, commonly denoted n. Long-term loading (dead load of barriers, signs, luminaries, overlays, etc.) is applied to the transformed composite section using 3n. Positive moments are applied to these composite sections accordingly, both for service and strength limit states. The slab may be considered effective in negative moment regions provided tensile stresses in the deck are below the modulus of rupture. This is generally possible for Service I load combination and fatigue analysis. For strength limit state loadings, the composite section includes longitudinal reinforcing while the deck is ignored.

6.3.3 Flanges

Flange thickness is limited to 4" maximum, but the desirable maximum is 3 ½". The number of plate thicknesses used for a given project should be kept to a minimum. Generally, the bottom flange should be wider than the top flange. Flange width changes should be made at bolted field splices. Thickness transitions are best done at welded splices. LRFD article 6.13.6.1.5 requires fill plates at bolted splices to be developed, if thicker than ¼". Since this requires a significant increase in the number of bolts for thick fill plates, keeping the thickness transition ¼" or less by widening pier segment flanges can be a better solution. Between field splices, flange width should be kept constant.

6.3.4 Webs

Maintain constant web thickness throughout the structure. If different web thickness is needed, the transition should be at a welded splice. Horizontal web splices are not needed unless web height exceeds 14 feet. Vertical web splices for girders should be shown on the plans in an elevation view with additional splices made optional to the fabricator. All welded web splices on exterior faces of exterior girders and in tension zones elsewhere shall be ground smooth. Web splices of interior girders need not be ground in compression zones.

6.3.5 Transverse Stiffeners

These stiffeners shall be used in pairs at crossframe locations on interior girders and on the inside of webs of exterior girders. They shall be welded to the top flange, bottom flange and web at these locations. This detail is considered fatigue category C' for longitudinal flange stress. Stiffeners used between crossframes shall be located on one side of the web, welded to the compression flange, and cut short of the tension flange. Stiffeners located between crossframes in regions of stress reversal shall be welded to one side of the web and cut short of both flanges. Alternatively, they may be welded to both flanges if fatigue Category C' is checked. Transverse stiffeners may be dropped when not needed for strength. If crossframe spacing is less than 3 times the web depth, additional stiffeners may only be necessary near piers.

Stiffened webs require end panels to anchor the first tension field. If jacking stiffeners are placed next to bearing stiffeners, the space created may be used as the anchor panel. Otherwise, the first transverse stiffener is placed no greater than 1.5 times the web depth from the bearing stiffener.

Transverse stiffeners must be designed and detailed to meet LRFD article 6.10.11.1. Where they are used to connect crossframes, they should be a minimum width of 8" to accommodate two bolt rows.

6.3.6 Longitudinal Stiffeners

On long spans where web depths exceed 10 feet, comparative cost evaluations shall be made to determine whether the use of longitudinal stiffeners will be economical. The use of longitudinal stiffeners may be economical on webs 10 feet deep or greater. Weld terminations for longitudinal stiffeners are fatigue prone details. Longitudinal stiffener plates should be continuous, splices being made with full penetration welds before being attached to webs. Transverse stiffeners should be pieced to allow passage of longitudinal stiffeners.

Design of longitudinal stiffeners is covered by LRFD article 6.10.11.3.

6.3.7 Bearing Stiffeners

Stiffeners are required at all bearings to enable the reaction to be transmitted from the web to the bearing. These stiffeners are designated as columns, therefore, must be vertical under total dead load. The connection of the bearing stiffener to the girder bottom flange consists of full penetration groove welds to the bottom flange and fillet welding to the top flange and web. Alternatively, the bottom bearing connection may be made with mill-to-bear and fillet welds or partial penetration welds.

Pier crossframes may transfer large seismic lateral loads through top and bottom connections. Weld size must be designed to ensure adequate load path from deck and crossframes into bearings.

Design of bearing stiffeners is covered by LRFD article 6.10.11.2.

6.3.8 Crossframes

The primary function of intermediate crossframes is to provide stability to individual girders or flanges. Crossframes or diaphragms are required at each support to brace girders; they should be as near to full-depth as practical.Crossframes share live load distribution between girders with the concrete deck. The approximate LRFD live load distribution factors were based on the absence of intermediate crossframes. Where crossframes are present, the exterior girder distribution factors are also determined according to LRFD article 4.6.2.2.2d (conventional approximation for loads on piles). On curved bridges, the crossframes also resist twisting of the superstructure. Pier crossframes are subjected to lateral loads from wind, earthquake, and curvature. These forces are transmitted from the roadway slab to the bearings by way of the pier crossframes. Intermediate crossframes also resist wind load to the lower half of the girders. The primary load path for wind is the concrete deck and pier diaphragms. Wind load on the bottom flange is shed incrementally to the deck through intermediate crossframes. The essential function, however, is to brace the compression flanges for all stages of construction and service life. As such, continuous span girders require bottom flange bracing near interior supports. Office practice requires intermediate crossframes, at spacing consistent with design assumptions. The 25 foot maximum spacing of older specifications is not maintained in the LRFD code. A rectangular grid of girders and crossframes is not significantly stiff laterally before the deck is cured. Both wind and deck placement can cause noticeable deflections. In the case of deck placement, permanent sideway and rotation of the steel framing may result. Some form of temporary or permanent lateral bracing is therefore required.

Crossframes and connections should be detailed for repetitive fabrication, adjustment in the field, and openness for inspection and painting. Avoid back-to-back angles separated by gusset plates. These are difficult to repaint. Crossframes are generally patterned as K-frames or as X-frames. Typically the configuration selected is based on the most efficient geometry. The diagonals should closely approach a slope of 1:1 or 45°. Avoid conflicts with utilities passing between the girders. Detailing of crossframes should follow guidelines of economical steel bridge details promoted by the National Steel Bridge Alliance. Office practice is to bolt rather than weld individual pieces, to provide some field adjustment. Oversize holes are not allowed in crossframe connections if girders are curved.

Intermediate crossframes for straight girders with little or no skew should be designed as secondary members. Choose members that meet minimum slenderness requirements and design connections only for anticipated loads, not for 75 percent strength of member.

In general, crossframes should be installed parallel to piers for skew angles of 0° to 20°. For greater skew angles, other arrangements may be used. Consult with the design unit supervisor or the steel specialist for special requirements.

Intermediate crossframes for curved I-girders require special consideration. Curved girder systems should be designed according to AASHTO “Guide Specifications for Horizontally Curved Highway Bridges.” Crossframes for curved girder bridges are main load carrying members and tension components should be so designated in the plans. For highly curved systems, it is more efficient to keep members and connections concentric, as live loads can be significant. Welded connections should be carefully evaluated for fatigue.

Web stiffeners at crossframes shall be welded to top and bottom flanges. This practice minimizes out-of-plane bending of the girder web.

Bridge widening requires special attention to girder stability during slab placement. Lateral movement and rotation has been common with widening projects around the country. Narrow framing, such as a two girder widening, requires bracing to an existing structure. A common method for bracing is to install crossframes (in bay between existing and new girders) with only enough bolts installed to allow for differential deflection but no rotation. Remaining bolts can be installed through field-drilled holes after the slab has cured.

6.3.9 Bottom Laterals

Bottom lateral systems are expensive to install permanently. If possible, they should be avoided in favor of alternative bracing methods. They are seldom required in the completed structure, but may contribute to nuisance or dramatic fatigue cracking in the main girders.

The primary function of a bottom lateral system is to stabilize the girders against lateral loads and translation before the deck hardens. The layout pattern is based on number of girder lines, girder spacing, and crossframe spacing. Cost considerations should include geometry, repetition, number, and size of connections. If used, limit bottom laterals to one or two bays.

For both straight and curved structures, bottom laterals carry dead and live loads, in proportion to distance from the neutral axis. They should be modeled in the structure to determine the actual forces the members experience. Since they carry slab dead load, they should be accounted for when calculating camber.

Where lateral gusset plates are fillet welded to girder webs, the fatigue stress range in the girder is limited to Category E without transition radius, or Category D with carefully made transition radius. The gusset plates should be bolted to the girder web in regions of high tension stress range.

For widening projects, bottom laterals are not needed since new can be braced against existing construction. Framing which is adequately braced should not require bottom laterals.

6.3.10 Bolted Field Splice for Girders

Office practice is to use bolted field splices. Splices are usually located at the dead load inflection point to minimize the design bending moment. See LRFD articles 6.13.2 and 6.13.6.1 for bolted splice design requirements. A method for designing web splices is now outlined in LRFD article 6.13.6.1.4b. Bolted web splices should not involve thin fill material. Thickness transitions for webs, if needed, should be done with welded shop splices.

Flange splice design is outlined in LRFD article 6.13.6.1.4c. For splice plates thicker than 3/4", threads may be excluded from all shear planes for a 26% increase in strength, per article 6.13.2.7. For this to apply, threads must be clear of the nearest shear plane by two thread pitch lengths. Generally, bolts in girder field splices may be designed for double shear.

A new requirement has been added for developing fillers used in bolted splices, article 6.13.6.1.5. When fill plates are greater than ¼", the splice or filler needs to be extended for additional bolts. As filler thickness increases, the shear resistance of bolts decreases. A way of minimizing filler thickness is to transition flange width for pier segments. Using equal plate thickness by this method has the added benefit of reducing the number of plate sizes in a project.

Splice bolts shall be checked for Strength load combinations and slip at Service II load combination. When faying surfaces are blasted and primed with inorganic zinc paint, a Class B surface condition is assumed.

Fabrication of girder splices is covered by WSDOT Standard Specification 6-03.3(27) and 6-03.3(28). Method of field assembly is covered by section 6-03.3(32) and bolting inspection and installation by section 6-03.3(33). Since bolted joints have some play due to differences in bolt diameter and hole size, field splices are drilled while segments are set in proper alignment in the shop. The joint is pinned (pin diameter equals hole size to prohibit movement) for shop assembly and also during initial field fit-up. Normally, this ensures repeatability of joint alignment from shop to field.

6.3.11 Camber

Camber includes effects of profile grade, superelevation, anticipated dead load deflections, and slab shrinkage (if measurable). Permanent girder deflections shall be shown in the contract plans in the form of camber diagrams and tables. Dead load deflections are due to steel self-weight, slab dead load, and superimposed dead loads such as overlay, sidewalks, and barriers. Since fabricated camber and girder erection have inherent variability, slab form height is adjusted after steel has been set. Although a constant distance from top of web to top of deck is assumed, this will vary along the girders. Deck forms without adjustment for height are not allowed. Girders must be profiled once fully erected, and before deck forms are installed. See *Standard Specification* 6-03.3(39).

Girder camber is established at three stages of construction. First, girder webs are cut from plates so that the completed girder segment will assume the shape of reverse dead load deflections superimposed on profile grade. Only minor heat corrections may be made in the shop to meet the camber tolerance of the Bridge Welding Code AWS D1.5 chapter 3.5. Camber for plate girders is not induced by mechanical force. The fabricated girder segment will incorporate the as-cut web shape and minor amounts of welding distortion. Next, the girder segments are brought together for shop assembly. Field splices are drilled as the segments are placed in position to fit profile grade plus total dead load deflection (no load condition). Finally, the segments are erected, sometimes with supports at field splices. There may be slight angle changes at field splices, resulting in altered girder profiles. Errors at mid-span can be between one to two inches at this stage.

The following is a general outline for calculating camber and is based on girders having shear studs the full length of the bridge.

Two curves will be required, one for total dead load plus slab shrinkage and one for steel framing self-weight. The difference between these curves is used to set deck forms and adjust screed rails.

Girder dead load deflection is determined by using various computer programs. Many steel girder design programs incorporate camber calculation. Girder self-weight is assumed to include the basic section plus stiffeners, crossframes, welds, shear studs, etc. These items may be accounted for by adding an appropriate percentage of basic section weight (15% is a good rule of thumb). Total dead load camber shall consist of deflection due to:

A. Steel weight, applied to steel section.

B. Slab weight, applied to steel section. This should be the majority of dead load deflection.

C. Traffic barriers, sidewalks, and overlays, applied to long-term composite section using 3n.

D. Slab shrinkage (if ≥ ¾”).

Slab dead load deflection will require the designer to exercise some judgment concerning degree of analysis. A two or three span bridge of regular proportions, for example, should not require a rigorous analysis. The slab may be assumed to placed instantaneously on the steel section only. Generally, due to creep, deflections and stresses slowly assume a state consistent with instantaneous slab placement. For unusual girder arrangements, and especially structures with in-span hinges, an analysis coupled with a slab pour sequence may be justified. This would require an incremental analysis where previous slab pours are treated as composite sections (using a modulus of elasticity for concrete based on age at time of second pour) and successive slab pours are added on noncomposite sections. Each slab pour requires a separate deflection analysis. The total effect of slab construction is the superposition of each slab pour.

Traffic barriers, sidewalks, overlays, and other items constructed after the slab pour should be analyzed as if applied to the long-term composite section full length of the bridge. The modulus of elasticity of the slab concrete should be reduced to one third of its short term value. For example, if f'c = 4000 psi, then use a value of n = 24.

Slab shrinkage has a varying degree of effect on superstructure deflections. The designer must use some judgment in evaluating this effect on camber. Slab shrinkage should be the smallest portion of the total camber. It has greater influence on shallower girder sections, say rolled beams. Simple spans will see more effect than continuous spans. For medium to long span continuous girders (spans over 200 feet without any in-span hinges), slab shrinkage deflection can be ignored. For simple span girders between 150 and 250 feet, the deflection should not exceed 1". For calculation, apply a shrinkage strain of about 0.0002 to the long-term composite section using 3n.

In addition to girder deflections, show girder rotations at bearing stiffeners. This will allow shop plan detailers to compensate for rotations so that bearing stiffeners will be vertical in their final position.

Camber tolerance is governed by the Bridge Welding Code AWS D1.5, chapter 3.5. A note of clarification is added to the plan camber diagram: "For the purpose of measuring camber tolerance during shop assembly, assume top flanges are embedded in concrete without a designed haunch." This allows a high or low deviation from the theoretical curve. In the past, no negative camber tolerance was allowed.

6.3.12 Roadway Slab Placement Sequence

The roadway slab is placed in a prescribed sequence allowing the concrete in each segment to shrink with minor influence on other segments. Negative moment regions (segments over interior piers) must be placed after positive moment regions have had time to cure. This helps minimize shrinkage cracking and provides manageable volumes of concrete for a work shift.

Positive moment regions should be placed first, while negative moment regions are placed last. Successive segments should not be placed until previous segments attain strengths of about 2000 psi or cure 3 to 7 days. This general guideline is sufficient for typical, well balanced span arrangements. For unbalanced span arrangements, the designer should check slab tensile stresses imposed on adjoining span segments. Required concrete strength can be increased, but needless delays waiting for higher strengths should be avoided. Also, the contractor should be given the option of placing positive moment segments with little influence on each other at a convenient rate, regardless of curing time. That is, segments separated by a span could be placed the same or next day without any harm. These can be lumped in the same pour sequence.

6.3.13 Bridge Bearings for Steel Girders

Make bearing selection consistent with required motions and capacities in the following order of preference, high to low:

- No bearings (integral abutments or piers)
- Elastomeric bearings
- Fabric pad bearings
- Steel cylindrical (pin) bearings
- Disk bearings
- Spherical bearings

6.3.14 Surface Roughness and Hardness


The standard measure of surface roughness is the microinch value. Surface roughness shall be shown on the plans for all surfaces for which machining is required unless covered by the Standard Specifications or Special Provisions. Consult *Machinery's Handbook* for common machining practice. Edge finishing for steel girders is covered in *Standard Specification* 6-03.3(14). Surface hardness of thermal cut girder flanges is also controlled.

Following is a brief description of some finishes:

1000	A surface produced by thermal cutting
500	A rough surface finish typical of "as rolled" sections. Suitable for surfaces that do not contact other parts and for bearing plates on grout.
250	A fairly smooth surface. Suitable for connections and surfaces not in moving contact with other surfaces. This finish is typical of ground edges in tension zones of flanges.
125	A fine machine finish resulting from careful machine work using high speeds and taking light cuts. It may be produced by all methods of direct machining under proper conditions. Suitable for steel to steel bearing or rotational surfaces including rockers and pins.
63	A smooth machine finish suitable for high stress steel to steel bearing surfaces including roller bearings on bed plates.
32	An extremely fine machine finish suitable for steel sliding parts. This surface is generally produced by grinding.
16	A very smooth, very fine surface only used on high stress sliding bearings. This surface is generally produced by polishing.

For examples, see Figure 6-4.

For stainless steel sliding surfaces, specify a #8 mirror finish. This is a different method of measurement and reflects industry standards for polishing. No units are implied.



Surface Finish Examples
Figure 6-4

6.3.15 Welding

All structural steel and rebar welding shall be in accordance with the *Standard Specifications*, amendments thereto and the special provisions. The *Standard Specifications* currently calls for welding structural steel according to the AASHTO/AWS D1.5-2002 *Bridge Welding Code* (BWC) and the latest edition of the AWS D1.1 *Structural Weld Code*. The designers should be especially aware of current amendments to the following sections of the *Standard Specifications*, 6-03.3(25) Welding and Repair Welding and 6-03.3(25)A Welding Inspection.

Exceptions to both codes and additional requirements are shown in the *Standard Specifications* and the special provisions.

Standard symbols for welding, brazing, and nondestructive examination can be found in the ANSI/AWS A 2.4 by that name. This publication is a very good reference for definitions of abbreviations and acronyms related to welding.

The designer must consider the limits of allowable fatigue stress, specified for the various welds used to connect the main load carrying members of a steel structure. See LRFD article 6.6. Most plate girder framing can be detailed in a way that provides fatigue category C or better.

The minimum fillet weld size shall be as shown in the following table. Weld size is determined by the thicker of the two parts joined unless a larger size is required by calculated stress. The weld size need not exceed the thickness of the thinner part joined.

Base Metal Thickness of Thicker Part Joined	Minimum Size of Fillet Weld
To ¾" inclusive	¼"
Over ¾"	5/16"

In general, the maximum size fillet weld which may be made with a single pass is 5/16 inch for submerged arc (SAW), gas metal arc (GMAW), and flux-cored arc welding (FCAW) processes. The maximum size fillet weld made in a single pass is 1/4 inch for the shielded metal arc welding (SMAW) process.

The major difference between AWS D1.1 and D1.5 is the welding process qualification. The only process deemed prequalified in D1.5 is shielded metal arc (SMAW). All others must be qualified by test. Qualification of AASHTO M 270 grade 50W (ASTM A709 grade 50W) in Section 5 of D1.5 qualifies the welding of all AASHTO approved steels with a minimum specified yield of 50 ksi or less. Bridge fabricators generally qualify to M 270 grade 50W (A709 grade 50W).

All bridge welding procedure specifications (WPS) submitted for approval shall be accompanied by a procedure qualification record (PQR), a record of test specimens examination and approval except for SMAW prequalified. Some handy reference aids in checking WPS in addition to PQR are:

Matching filler metal requirements are found in BWC Section 4.

Prequalified joints are found in BWC Section 2.

AWS electrode specifications and classifications are obtained from the structural steel specialist. Many electrode specification sheets may be found online.

Lincoln Electric Arc Welding Handbook.

Many of Lincoln Electric's published materials and literature are available through those designers and supervisors who have attended Lincoln Electric's weld design seminars.

WSDOT *Standard Specifications* for preheat and interpass temperatures.

Notes: Electrogas and electroslag welding processes are not allowed in WSDOT work. Narrow gap improved electroslag welding will be allowed on a case-by-case basis.

Often in the rehabilitation of existing steel structures, it is desirable to weld, in some form, to the in-place structural steel. Often it is not possible to determine from the original contract documents whether or not the existing steel contains high or low carbon content and carbon equivalence. Small coupons from the steel can be taken for a chemical analysis. Labs are available in the Seattle and Portland areas that will do this service quickly. Suitable weld procedures can be prepared once the chemical content is measured.

6.3.16 Shop Assembly

In most cases, a simple progressive longitudinal shop assembly is sufficient to ensure proper fit of subsections, field splices, and crossframe connections, etc., in the field. Due to geometric complexity of some structures, progressive transverse assembly, in combination with progressive longitudinal assembly may be desirable. The designer shall consult with the supervisor and the steel specialist to determine the extent of shop assembly and clarification of *Standard Specifications* section 6-03.3(28)A. If other than line girder progressive assembly is required, the method must be included by special provision. High skews or curved girders should be done with some form of transverse and longitudinal assembly. Complex curved and skewed box girder framing should be done with full transverse progressive assembly. For transverse assembly,

specify crossframe and pier diaphragm connections to be completed while assembled.

During shop assembly, girder segments are blocked or supported in the no-load condition (no gravity effects). Simple line girder assembly is often done in the horizontal position. The primary reason for shop assembly is to ensure correct alignment for girder field splices. For straight bridges, crossframe connections are normally done by numerically controlled (NC) drilling (no trial shop assembly). This is generally of sufficient accuracy to allow crossframe installation in the field without corrective action such as reaming.

For curved I-girders, crossframes are to be fabricated to fit the no-load condition. During field erection, girder segments will need to be adjusted or supported to make fit-up possible. This is not unreasonable since curved girders are not self-supporting before crossframes are in place. However, the method results in out-of-plumb girders. For most cases, making theoretical compensation to arrive at plumb in final condition is not justified.

Highly skewed girders present difficult fit-up conditions. Setting screeds is also complicated because of differential deflections between neighboring girders. Design of crossframes and pier diaphragms must take into account twist and rotations of webs during construction. Often, slotted holes for crossframe connections can be used to allow settlement without undue web distortion. This situation should be carefully studied by grid or finite element analysis to determine amount and type of movement anticipated during construction. Details should be consistent. Unlike curved girders rotating away from plumb at midspan, girder webs for skewed construction should be kept plumb at piers.

6.4 Plan Details

6.4.1 General

Detailing practice should follow industry standards. Designations for structural steel can be found in Table 2-1 of AISC *Detailing for Steel Construction*. Previous plans are a good reference for detailing practices. Detailing should also conform to national unified guidelines published by AASHTO/NSBA Steel Bridge Collaboration.

Details for plate girders are continually being revised or improved to keep up with changing fabrication practice, labor and material costs, and understanding of fatigue behavior. Uses and demands for steel girder bridges are also changing. Cost benefits for individual details vary from shop to shop and even from time to time. For these reasons, previous plan details can be guides but should not be considered standards. Options should be made available to accommodate all prospective fabricators. For example, small shops prefer shorter, lighter girder segments. Some shops are able to purchase and handle plates over 90 feet long. Large shop assembly may be prohibitive for fabricators without adequate space.

In general, office practice is to favor field bolted as opposed to field welded connections. In addition, members of cross frames are shop bolted to give some degree of field adjustment. Welded assemblies have little adjustment during erection.

6.4.2 Structural Steel Notes

Due to their dynamic nature, the structural steel notes are not shown in this manual. They are available as standards in the drafting system. Since each project has unique requirements, these notes should be edited accordingly. Material specifications are constantly changing. Separate sets of notes are available for I and box girders.

6.4.3 Framing Plan

The Framing Plan gives plan locations of girders, crossframes, and attachments. Show ties between the survey line, girder lines, backs of pavement seats, and centerlines of piers. Locate panel points (crossframe locations). Show general arrangement of bottom laterals. Provide geometry, bearing lines, and transverse intermediate stiffener locations. Show field splice locations. Map out different lateral connection details. See Appendix 6-A-1.

6.4.4 Girder Elevation

The Girder Elevation is used to define flanges, webs, and their splice locations. Show shear connector spacing, location, and number across the flange. Locate transverse stiffeners and show where they are cut short of tension flanges. Show the tension regions of the girders for the purpose of ordering plate material, inspection methods (NDE), and *Bridge Welding Code* acceptance criteria. See Charpy V-notch testing requirements of the *Standard Specifications*. Identify tension welded butt splices for which radiographic examination (RT) is required. See *Standard Specifications 6-03.3(25)A*. V and X are also defined in the Structural Steel Notes. Permissible welded web splices should be shown, however, the optional welded web splice shown on the Girder Details sheet permits the fabricator to add splices subject to approval by the engineer. If there are fracture critical components, they must be clearly identified along with CVN call-outs. See Appendix 6-A-2.

6.4.5 Typical Girder Details

One or two plan sheets should be devoted to showing typical details to be used throughout the girders. Such details include the weld details, various stiffener plates and weld connections, locations of optional web splices, and drip plate details. Include field splice details here if only one type of splice will suffice for the plans. An entire sheet may be required for bridges with multiple field splice designs. See Appendix 6-A-3 and A4. Note: Do not distinguish between field bolts and shop bolts. A solid bolt symbol will suffice.

Field splices for flanges should accommodate web location tolerance of ± ¼" per BWC 3.5.1.5. Allow a minimum of ¼" for out of position web plus 3/8" for fillet weld, or a total of 5/8" minimum clear between theoretical face of web and edge of splice plate. The bottom flange splice plate should be split to allow moisture to drain (use 4 equal bottom flange splice plates). The fill plate does not need to be split.

Vertical stiffeners used to connect crossframes are generally 8" wide to accommodate two bolt rows. They must be welded to top and bottom flanges to reduce out-of-plane bending of the web. Stiffeners are coped, clipped or cut short a distance between $4t_w$ and $6t_w$ to provide web flexibility, per LRFD article 6.10.11.1.1.

6.4.6 Crossframe Details

Show member sizes, geometrics (work lines and work points), and connection details. Actual lengths of members and dimensions of connections will be determined by the shop plan detailer. Details should incorporate actual conditions such as skew and neighboring members so that geometric conflicts can be avoided. Tee sections are preferred over double angles for easier painting. If double angles are used, leave a minimum of 1 inch between legs and include fillers as needed for stability. Do not detail crossframes that require piecemeal installation. They must be complete subassemblies for field installation. For highly loaded crossframes, such as at piers or between curved girders, consider symmetric sections with little or no eccentricity in the connections. Where possible, allow for repetitive use of crossframe geometrics, especially hole patterns in stiffener connections, regardless of superelevation transitions. See Appendix 6-A-5.

Internal crossframes and top lateral systems for box girders are shop welded, primarily. All connection types should be closely examined for detail conflict and weld access. Clearance between deck forming and top lateral members must be considered.

6.4.7 Camber Diagram and Bearing Stiffener Rotation

Camber curves should be detailed using conventional practices. Dimensions should be given at tenth points. Dimensions may also be given at crossframe locations, which may be more useful in the field. In order to place bearing stiffeners in the vertical position after slab placement, it is necessary to show expected girder rotations at piers. See Appendix 6-A-6.

Office practice is to show deflection camber only. Geometric camber for profile grade and superelevation will be calculated by the shop detailer from highway alignment shown on the Layout sheets.

6.4.8 Roadway Slab

New bridge decks for steel stringers shall use Deck Protection System 1. Currently, this is a minimum 7 ½" thickness deck, with 2 ½" concrete cover over epoxy coated top mat reinforcing. Allowance for future overlay is not required for this system.

The roadway slab is detailed in section and plan views. For continuous spans, add a section showing negative moment longitudinal reinforcing. If possible, continue the positive moment region reinforcing pattern from end-to-end of the slab with the negative moment region reinforcing superimposed on it. The plan views should detail typical reinforcing and cutoff locations for negative moment steel. Avoid termination of all negative moment steel at one location. See Appendix 6-A-7 and 6-A-8.

The "pad" dimension for steel girders is treated somewhat differently than for prestressed girders. The pad dimension is assumed to be constant throughout the span length. Ideally, the girder is cambered to compensate for dead loads and vertical curves. However, fabrication and erection tolerances result in considerable deviation from theoretical elevations. The pad dimension is therefore considered only a nominal value and is adjusted as needed along the span once the steel has been erected and profiled. The screed for the slab is to be set to produce correct roadway profile. The plans should reference this procedure contained in *Standard Specification* 6-03.3(39). The pad dimension is to be noted as nominal. As a general rule of thumb, use 11" for short span bridges (spans less than 150'), 12" for short to medium span bridges (150′ to 180′), 13" for medium spans (180′ to 220′) and 14" to 15" for long spans (over 220′). These figures are only approximate. Use good engineering judgment when detailing this dimension.

6.4.9 Handrail Details and Inspection Access

If required, include handrails with typical girder details. Locations may be adjusted to avoid conflicts with other details such as large gusset plates. Handrail use shall be coordinated with the Bridge Preservation Office. Often, handrails are not needed if access to all details is possible from under bridge inspection trucks (UBIT's). Also, easy public access to girder ends and handrails may represent a nuisance. Examine the bridge and site to determine the need for handrails. Fences may be required to deny public access.

Box girders require special consideration for inspection access. Access holes or hatches shall be detailed to exclude birds and the public. They shall be positioned where ladders, as a minimum, are required to gain access. Openings through girder ends are preferred if space behind end walls permits. Bottom flange hatches are difficult to operate. Hatches through webs may reduce shear capacity but are easier to use. Pier diaphragms will require openings for easy passage. To facilitate inspection, interior paint should be light color; white is preferred. Electric lighting and outlets are also required for inspection and maintenance. One-way inspection of all interior spaces should be made possible by round trip in adjoining girders. This requires some form of walkway between boxes and hatch operation from both sides. If locks are needed, they must be keyed to one master. Air vents shall be placed along girder webs to allow fresh air to circulate. Refer to previous projects for details.

6.5 Shop Plan Review

Shop plans shall be checked for agreement with the Contract Plans, *Standard Specifications*, and the Special Provisions. The review procedure is described in Section 1.3.5 of this manual. Material specifications shall be checked along with plate sizes.

Welding procedure specifications (WPS) and procedure qualification records (PQR) shall be submitted with shop plans. If not, they shall be requested and received before shop plans are approved.

Most shop plans may be stamped:

> "GEOMETRY NOT REVIEWED
> BY THE BRIDGE & STRUCTURES OFFICE"

However, the reviewer should verify that lengths, radii, and sizes shown on shop plans are in general agreement with the contract. The effects of profile grade and camber would make exact verification difficult. Some differences in lengths, between top and bottom flange plates for example, are to be expected.

The procedures to follow in the event changes are required or requested by the fabricator can be found in Section 1.3.6 of this manual. In the past, shop plans with acceptable changes have been so noted and stamped:

> "STRUCTURALLY ACCEPTABLE, BUT DOES NOT
> CONFORM TO THE CONTRACT REQUIREMENTS"

6.99 References

The following publications can provide general guidance for the design of steel structures. Some of this material may be dated and its application should be used with caution.

1. *Highway Structures Design Handbook, Volumes I and II* by AISC Marketing, Inc., formerly by US Steel

   This is a detailed design reference for "I" girders and box girders, both straight and curved, utilizing either service load design or load factor design. This reference has good background on steel bridge details, and how to use them. Although calculations have not been updated for LRFD, the general theory is still valuable. Many shortcuts for design or modeling are presented, such as converting lateral systems into idealized thin plates, and the V load method to approximate curved I girder behavior.

2. *Composite Steel Plate Girder Superstructures,* by US Steel

   Example tables and charts for complete plate girders, standardized for 34 and 44 ft. roadways and HS-20 loading. Many span arrangements and lengths are presented.

3. *Four LRFD Design Examples of Steel Highway Bridges, Vol. II, Chapter 1B Highway Structures Design Handbook,* by AISI and NSBA

4. *Steel Structures, Design and Behavior* by Salmon and Johnson

   A textbook for steel design, formatted to AISC LRFD method. This is a good reference for structural behavior of steel members or components, in detail that is not practical for codes or other manuals.

5. *Design of Welded Structures* by Omer H. Blodgett.

   This publication is quite helpful in the calculation of section properties and the design of individual members. There are sections on bridge girders and many other welded structures. The basics of torsion analysis are included.

6. *Guide to Stability Design Criteria for Metal Structures,* by Theodore V. Galambos

7. *Curved Girder Workshop* produced by the Federal Highway Administration.

   This publication is helpful in the design of curved "I" girders and box girders with explanation of the associated lateral flange bending, torsional, and warping stresses. Approximate analysis techniques are provided.

8. *A Fatigue Primer for Structural Engineers*, by John Fisher, Geoffrey L Kulak, and Ian F. C. Smith

9. *Manual of Steel Construction, Load & Resistance Factor Design*, by AISC

   The essential reference for rolled shape properties, design tables, and specifications governing steel design and construction.

10. *Machinery's Handbook,* by Industrial Press


    A reference book for the machine shop practice; handy for thread types, machine tolerances and fits, spring design, etc.

11. *Painting of Steel Bridges and Other Structures*, by Clive H. Hare

    This is a good reference for paint systems, surface preparation, and relative costs, for both bare and previously painted steel. Explanations of how each paint system works, and comparisons of each on the basis of performance and cost are provided.


12. NCHRP Report 314, *Guidelines for the Use of Weathering Steel in Bridges*

    This reference contains detailing information if weathering steel will be used. Protection of concrete surfaces from staining and techniques for providing uniform appearance is provided.



FRAMING PLAN


Steel Plate Girder Framing Plan
Figure 6-A-1




GIRDER ELEVATION

Steel Plate Girder Girder Elevation


Figure 6-A-2




TYPICAL GIRDER SECTION




TYPICAL STIFFENER BETWEEN X-FRAMES



BEARING AND JACKING STIFFENERS




TYPICAL STIFFENER AT INTERMEDIATE X-FRAME




TENSION OR COMPRESSION FLANGE SPLICE

WELDED GIRDER SPLICE DETAILS

FABRICATOR MAY SUBSTITUTE B-L2C-S FOR B-U3C-S, SUBJECT TO THICKNESS LIMITATIONS.




TYPICAL FILLET WELD TERMINATION DETAIL




PERMISSIBLE WEB SPLICE

Steel Plate Girder Girder Details


Figure 6-A-3




ELEVATION



SECTION A




PLAN
TOP FLANGE



PLAN
BOTTOM FLANGE


NOTE:
X DESIGNATES BOLTS TO BE DETAILED SO THAT THREADS ARE EXCLUDED FROM ALL SHEAR PLANES.

Steel Plate Girder Field Splice
Figure 6-A-4



INTERMEDIATE AND PIER CROSSFRAMES


Steel Plate Girder Crossframes
Figure 6-A-5



	TENTH POINTS									PANEL POINTS						
	0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8	0.9	1	2	3	4	5	6	7
TOTAL DEAD LOAD/SLAB SHRINKAGE CAMBER (IN.)	5⅜	9⅞	13⅛	15⅛	16	15⅛	13⅛	9⅞	5⅜	0	8½	14	16	14	8½	0
CAMBER DUE TO SELF WEIGHT OF STEEL (IN.)	1	2	2½	3	3⅛	3	2½	2	1	0	1⅝	2¾	3⅛	2¾	1⅝	0

DEAD LOAD CAMBER DIAGRAM

EFFECTS OF PROFILE GRADE ARE NOT SHOWN. FOR THE PURPOSE OF MEASURING CAMBER TOLERANCES AT THE TIME OF SHOP ASSEMBLY, GIRDER TOP FLANGES ARE EMBEDDED IN CONCRETE WITHOUT A DESIGNED HAUNCH.




BEARING STIFFENER ROTATIONAL CAMBER DIAGRAM

OFFSETS TO COMPENSATE FOR TOTAL DEAD LOAD ROTATION.
DOES NOT INCLUDE EFFECTS OF PROFILE GRADE.

Steel Plate Girder Camber Diagram


Figure 6-A-6



TYPICAL ROADWAY SECTION


* POSITION SPLICE MIDWAY BETWEEN GIRDERS. STAGGER SPLICES ABOUT ℄ BRIDGE, EVERY OTHER BAR. ROTATE HOOKS AS REQUIRED TO PROVIDE MINIMUM CONCRETE COVER.

≠ DIMENSIONS MAY VARY: REFER TO STD. SPEC. 6-03.3(39).



SECTION A

Steel Plate Girder Roadway Section
Figure 6-A-7




ROADWAY SLAB REINFORCING

NOTE:
2'-0" MINIMUM REBAR LAP SPLICE LENGTH FOR ALL LONGITUDINAL BARS.


≠ LOCATION OF REBAR SPLICES AT CONTRACTORS OPTION, EXCEPT ALL SPLICES SHALL BE ALTERNATED, SO NO MORE THAN 50% OF REBAR IS SPLICED AT THE SAME LOCATION, NORMAL TO ℄ OF BRIDGE.

Steel Plate Girder Slab Plan
Figure 6-A-8




CLIP DETAIL


USE CLIP DETAIL(S) BETWEEN WEB STIFFENERS TO PROVIDE SUPPORT AT 8'-0" MAXIMUM SPACING.



END CONNECTION DETAIL




SECTION A



SECTION B

NOTES:

1. THE HANDRAIL SHALL BE ⅝"ø ROD, ASTM A36 OR A307, GALVANIZED AFTER CUTTING TO LENGTH AND THREADING. NUTS SHALL BE OVERTAPPED FOR GALVANIZING, HEAVY HEX ASTM A 593 GRADE A. USE GALVANIZED WASHERS UNDER EACH NUT. ALL NUTS SHALL BE INSTALLED SNUG TIGHT.
2. DETAIL ROD LENGTHS TO ACCOMODATE X-FRAME STIFFENER LOCATIONS, HANDLING, AND GALVANIZING. DO NOT TERMINATE AT BEARING STIFFENERS OR INTERMEDIATE CLIPS. THE MAXIMUM UNSUPPORTED LENGTH SHALL BE 8'-0". COUPLERS SHALL NOT BE USED.
3. THE INTERMEDIATE CLIPS SHALL BE ASTM A 36 OR A 992, GALVANIZED AFTER FABRICATION. HIGH STRENGTH BOLTS SHALL BE ASTM A 325, GALVANIZED. NUTS SHALL BE HEAVY HEX ASTM A 563 GRADE DH.
4. FASTEN TO BRIDGE AFTER GIRDERS ARE SHOP PAINTED. OVERSPRAY FROM FIELD PAINTING IS PERMITTED.
5. ALL HARDWARE SHALL BE HOT DIPPED GALVANIZED IN ACCORDANCE WITH ASTM A123 OR A153 AS APPLICABLE. EQUIVALENT COIL PRODUCT MAY BE USED PROVIDED THREADS ARE COATED WITH REPAIR GALVANIZING STD. SPEC. FORMULA A-9-73 AFTER THREADING.
6. SAFETY TESTING OF HANDRAIL IS PENDING. HANDRAIL IS NOT CURRENTLY RATED AS A FALL PROTECTION DEVICE. ESTIMATED MINIMUM TENSILE STRENGTH OF HANDRAIL IS 15 KIPS.



ELEVATION - GIRDER WITH HANDRAIL

Handrail
Figure 6-A-9

Chapter 7 Substructure Design

7.1 General Substructure Considerations 7-1
7.1.1 Foundation Design Process 7-1
7.1.2 Foundation Limit States and Factors 7-4
7.1.3 Substructure and Foundation Loads 7-5
7.1.3 Substructure and Foundation Loads (continued) 7-6
7.1.4 Concrete Class for Substructure 7-8
7.1.5 Foundation Seals 7-9
7.1.5.C.1 Timber Pile Footing Example 7-11
7.2 Foundation Modeling 7-12
7.2.1 General Modeling Concepts 7-12
7.2.2 Substructure Analysis Flow Chart 7-15
7.2.3 Bridge Model Section Properties 7-18
7.2.4 Bridge Model Verification 7-19
7.2.5 Deep Foundation Modeling 7-20
7.2.6 Spread Footing Modeling 7-32
7.3 Column Design 7-36
7.3.1 Preliminary Plan Stage 7-36
7.3.2 General Column Criteria 7-36
7.3.3 Column Design Flow Chart 7-37
7.3.4 Slenderness Effects 7-38
7.3.5 Moment Magnification Method 7-38
7.3.6 Second-Order Analysis 7-38
7.4 Column Reinforcement 7-40
7.4.1 Minimum Longitudinal Reinforcement Ratio 7-40
7.4.2 Longitudinal Splices 7-40
7.4.3 Ties and Spirals 7-42
7.4.4 Longitudinal Development and Confinement Steel 7-45
7.4.5 Column Hinges 7-47
7.5 Abutment Design and Details 7-49
7.5.1 Abutment Types 7-49
7.5.2 Embankment at Abutments 7-52
7.5.3 Abutment Loading 7-52
7.5.4 WSDOT Temporary Construction Load Cases 7-53
7.5.5 Abutment Bearings and Girder Stops 7-53
7.5.6 Abutment Expansion Joints 7-55
7.5.7 Open Joint Details 7-55
7.5.8 Construction Joints 7-57
7.5.9 Abutment Wall Design 7-58
7.5.10 Drainage and Backfilling 7-59
7.6 Wing/Curtain Wall at Abutments 7-61
7.6.1 Traffic Barrier Loads 7-61
7.6.2 Wingwall BDM Design 7-61
7.6.3 Wing wall Detailing 7-61
7.7 Footing Design 7-62
7.7.1 General Footing Criteria 7-62
7.7.2 Loads and Load Factors 7-63

7.7.3 Geotechnical Report Summary 7-64
7.7.4 Spread Footing Structural Design 7-65
7.7.4.A Abutment Spread Footing Force Diagram 7-65
7.7.4.B Bearing Stress 7-66
7.7.4.C Failure By Sliding 7-67
7.7.4.D Overturning Stability 7-68
7.7.4.E Footing Settlement 7-68
7.7.4.F Concrete Design 7-68
7.7.5 Footing Concrete Design on Pile Supports 7-69
7.7.5.A Pile Embedment, Clearance, and Rebar Mat Location 7-70
7.7.5.B Pile Pullout and Details 7-71
7.7.5.C Concrete Design 7-71
7.8 Drilled Shafts 7-72
7.8.1 Drilled Shaft Design 7-72
7.8.2 Lateral Load Analysis 7-73
7.9 Piles and Piling 7-74
7.9.1 Pile Types 7-74
7.9.2 Pile Design Flow Chart 7-76
7.9.3 General Pile Design 7-77
7.9.4 Pile Axial Design 7-78
7.9.5 Pile Lateral Design 7-79
7.9.6 Pile Tip Elevations and Quantities 7-79

7.1 General Substructure Considerations

Note that in the following guidelines where reference is made to AASHTO, the item can be found in the current AASHTO LRFD Bridge Design Specifications, with Interims.

7.1.1 Foundation Design Process

A flowchart is provided in Figure 7-1 which illustrates the overall design process needed to accomplish an LRFD foundation design. The Bridge Office)BO_ and the Geotechnical Branch (GB) have been abbreviated. The steps in the flowchart are defined as follows:

Conceptual Bridge Foundation Design

This design step results in an informal communication produced by the Geotechnical Branch at the request of the Bridge and Structures Office which provides a brief description of the following.

- Anticipated soil site conditions
- Maximum embankment slopes
- Foundation types and geotechnical hazards such as liquefaction

In general, these recommendations rely on existing site data. Site borings may not be available and test holes are drilled later. The geotechnical recommendations provide enough information to select a type of foundation for an initial Bridge Preliminary Plan.

Develop Site Data and Preliminary Bridge Plan

In the second phase, the Bridge and Structures Office obtains site data from the region (see WSDOT *Design Manual*) and develops the Preliminary Bridge Plan. The preliminary pier locations determine soil boring locations at this time. The Geotechnical Division will also require the following information to continue the preliminary geotechnical design.

- Structure type and magnitude of settlement the structure can tolerate (both total and differential).
- At abutments – Approximate maximum top of foundation elevation.
- At interior piers – The number of columns; Whether a single foundation element supports each column or one foundation element supports multiple columns.
- At stream crossings – Pier scour depth, if known. Typically, the Geotechnical Division will pursue this issue with the OSC Hydraulics Office.
- Any known structural constraints that affect the foundations' type, size, or location.
- Any known constraints that affect the soil resistance (utilities, construction staging, excavation, shoring and falsework).

Preliminary Foundation Design

The third phase is a request by the Bridge and Structures Office for a preliminary foundation memorandum. The Geotechnical Division memo will provide preliminary soil data required for structural analysis and modeling. This includes any subsurface conditions and the preliminary subsurface profile.

The concurrent geotechnical work at this stage includes:

- Completion of detailed boring logs and laboratory test data
- Development of foundation type, soil capacity, and foundation depth
- Development of static/seismic soil properties and ground acceleration
- Recommendations for constructability issues

Structural Analysis and Modeling

In the fourth phase, the Bridge and Structures Office performs a structural analysis of the superstructure and substructure using a bridge model and preliminary soil parameters. Through this modeling, the Bridge Engineer determines loads and sizes for the foundation based on the controlling LRFD limit states. Structural and geotechnical design continues to investigate constructability and construction staging issues during this phase.

In order to produce a Final Geotechnical Report, the Bridge and Structures Office provides the following structural feedback to the Geotechnical Engineer.


- Foundation loads for service limit state and strength limit state.
- Foundation size/diameter and depth required to meet structural design.
- Foundation details that could affect the geotechnical design of the foundations.
- Size and configuration for deep foundation groups

Final Foundation Design

The last phase completes the geotechnical report and allows the final structural design to begin. The preliminary geotechnical assumptions are checked and recommendations are modified, if necessary. The final report is complete to a PS&E format since the Project Contract will contain referenced information in the Geotechnical Report, such as:

- All geotechnical data obtained at the site (boring logs, subsurface profiles, and laboratory test data)
- All final foundation recommendations
- Final constructability and staging recommendations

The Bridge Engineer reviews the final report for new information and confirms the preliminary assumptions. With the foundation design complete, the final bridge structural design and detailing process continues to prepare the Bridge Plans.



Overall Design Process for LRFD Foundation Design

Figure 7-1

7.1.2 Foundation Limit States and Factors

The controlling limit states for WSDOT projects for Substructure Design are described as follows:

Strength I	Relating to the normal vehicular use
Strength III	Relating to the bridge exposed to wind
Strength IV	Relating to temperature fluctuations, creep, and shrinkage
Strength V	Relating to the normal vehicular use and wind
Extreme-Event I	Relating to earthquake
Service I	Relating to normal operational use and wind

The basic equation for load and resistance factor design (LRFD) states that the loads multiplied by factors to account for uncertainty, ductility, importance, and redundancy must be less than or equal to the available resistance multiplied by factors to account for variability and uncertainty per the AASHTO LRFD specifications. WSDOT current practice sets η_i equal to 1.0 for structural design. The basic equation, therefore, is as follows:

$$\Sigma\eta_i\gamma_i Q_i \leq \phi R_n$$

η_i = Factor for ductility, redundancy, and importance of structure

γ_i = Load factor

Q_i = Load (i.e., dead load, live load, seismic load, etc.)

ϕ = Resistance factor

R_n = Nominal or ultimate resistance

Substructure Load Factors

The load combinations, limit states and load factors (γ_i) used for foundation design are in accordance with AASHTO, Table 3.4.1-1. Design loads are factored after distribution to the foundation through structural analysis or modeling.

Transient Load Factors -- Live Load (γ_{EQ})

The Extreme Event-I transient load factor for live load, γ_{EQ} as specified in the LRFD Table 3.4.1-1, may vary from 0.0 up to 0.5. For WSDOT bridge designs, the live load factor, γ_{EQ} for the majority of bridges, shall be equal to 0.0. For bridges located on routes in urban areas susceptible to daily, heavy congestion, γ_{EQ} shall be equal to 0.5 unless otherwise directed by the WSDOT Bridge Design Engineer. The γ_{EQ} factor should apply to the live load force effect obtained from the bridge live load elastic analysis. Live load mass will be ignored in the dynamic analysis.

Permanent Load Factors - DD

The load factors for permanent loads (γ_p) will be in accordance with Table 3.4.1-2 of the AASHTO LRFD specifications, with the exception of downdrag (DD). Downdrag load factor (γ_{DD}) will be specified in the Geotechnical Report for the Bridge.

Response Modification Factors (R)

The Response Modification Factor for all bridges is based on the Importance Category of "Other" as specified in LRFD Table 3.10.7.1-1, unless otherwise directed by the WSDOT Bridge Design Engineer. The R-factors for column design apply only to the elastically computed moments from the seismic analysis. The R-factor for column shear design will always be 1.0.

AASHTO indicates Importance Categories of Critical, Essential and Others for The Response Modification Factor (R). Bridge columns designed and detailed in accordance with the criteria for "Other" bridges exhibit good seismic performance and it may be unnecessary and uneconomical to design bridges for Critical or Essential categories. However, if the WSDOT Bridge Design Engineer identifies a bridge as Essential or Critical, the corresponding R-factor should be used for substructure design.

A. Substructure Permanent Load Factors

Table 7-2 provides general guidelines for when to use the maximum or minimum shaft/pile/column strength limit state permanent load factors for axial capacity, uplift, and lateral loading.

In general, substructure design should use unfactored loads to obtain force distribution in the structure, and then factor the resulting moment and shear for final structural design. All forces and load factors are as defined previously.


Axial Capacity	Uplift	Lateral Loading
DC_{max}, DW_{max}	DC_{min}, DW_{min}	DC_{max}, DW_{max}
DC_{max}, DW_{max} for causing shear	DC_{max}, DW_{max} for causing shear	DC_{max}, DW_{max} causing shear
DC_{min}, DW_{min} for shear	DC_{min}, DW_{min} for resisting shear	DC_{min}, DW_{min} resisting resisting shear
DC_{max}, DW_{max} for causing moments	Use DC_{max}, DW_{max} for causing moments	Use DC_{max}, Dw_{max} for causing moments
DC_{min}, DW_{min} for resisting moments	DC_{min}, DW_{min} for resisting moments	DC_{min}, DW_{min} for resisting moments
EV_{max}	EV_{min}	EV_{max}
DD = Varies	DD = Varies	DD = Varies
EH_{max}	EH_{max} if causes uplift	EH_{max}

Maximum or Minimum Substructure Load Factors for Strength Limit State permanent Loads (γ_p)
Table 7-2

7.1.3 Substructure and Foundation Loads

Figure 7-3 below provides a common basis of understanding for load location and orientations for substructure design. This figure also shows elevations required for abutment and substructure design. Note that for shaft and some pile foundation designs, the shaft or pile may form the column as well as the foundation element.

Spread footings usually have a design orientation normal to the footing. Since bridge loads are longitudinal and transverse, skewed superstructure loads are converted (using vector components) to normal and parallel footing loads. Deep foundation analysis usually has a normal/parallel orientation to the pier in order to simplify group effects.



Substructure Directional Forces
Figure 7-3

7.1.3 Substructure and Foundation Loads (continued)

Substructure elements are to carry all of the loads specified in AASHTO. Selecting the controlling load conditions requires good judgment to minimize design time.

Bridge design will consider construction loads to ensure structural stability and prevent members from overstress. For example, temporary construction loads can overload a single column pier by placing all of the precast girders on one side. The plans will show a construction sequence and/or notes to avoid unacceptable loadings.

On curved bridges, the substructure design will consider the eccentricity resulting from the difference in girder lengths. When superstructure design uses a curved girder theory, such as the V-Load Method, the reactions from such analysis must be included in the loads applied to the substructure.

Dead Loads - DC


Substructure design will account for all anticipated dead load conditions. Sidesway effect shall be included where it tends to increase stresses.

Live Loads - LL

The dynamic allowance (IM) will be applied in accordance with AASHTO 3.6.2 and is not included in the design of buried elements of the substructure. Portions of the abutments in contact with the soil are considered buried elements.

Lane reduction factors as described in AASHTO “Reduction in Load Intensity” are applied to the number of lanes for each load case.

The HL93 loading is distributed to the substructure by placing wheel line reactions in a lane configuration that generates the maximum stress in the substructure. A wheel line reaction is ½ of the HL93 reaction. Live loads are considered to act directly on the substructure without further distribution through the superstructure, see Figure 7-4. Normally, substructure design will not consider live load torsional or lateral distribution nor any live load sidesway effects. GTSTRUDL will include live load sidesway.



Live Load Wheel Line Destribution to Substructre
Figure 7-4

For steel and prestressed concrete superstructures where the live load is transferred to substructure through bearings, cross frames or diaphragms, the girder reaction may be used for substructure design.

Live load placement is dependant on the member under design. Some examples of live load placement are as follows.

The exterior vehicle wheel is placed 2 feet from the curb for maximum crossbeam cantilever moment or maximum eccentric foundation moment.

For crossbeam design between supports, the HL93 lanes are placed to obtain the maximum moment in the member; then re-located to obtain the maximum shear or negative moment in the member.

For column design, the design lanes are placed to obtain the maximum transverse moment at the top of the column; then re-located to obtain the maximum axial force of the column.

Down Drag Force - DD

The Geotechnical Report will provide the downdrag force. The down drag force (DD) is a load applied to the pile/shaft with the load factor (γ_{DD}) specified in the Geotechnical Report. Generally, transient loads (LL) are less than the downdrag force and should be omitted when considering DD forces. In other words, the transient loads reduce downdrag forces and are ignored for the structural design. The WSDOT GDM Section 8.6.2 provides a more in-depth discussion of Down Drag.

Earthquake Loads - EQ

Earthquake loads on elements of the substructure are described in AASHTO 3.10, Earthquake Effects. The design acceleration coefficient and site coefficient will be given in the Geotechnical Report. The seismic analysis requirements are stated in AASHTO Section 4.7. The resulting loads shall be taken in any horizontal direction to give maximum design load for the substructure element.

The intermediate pier(s) of each unit of a multispan continuous structure shall be designed to resist the entire longitudinal earthquake force for that unit (unless the end piers are an integral part of the superstructure). The calculated longitudinal movement shall be used to determine the shear force developed by the pads at the abutments. The neoprene modulus of elasticity at 70°F (21°C) shall be used by determine the shear force. However, the force transmitted through a bearing pad shall be limited to the force that causes the pad to slip.

Hold-Down Devices shall be designed per AASHTO 3.10.9.6. This requires a minimum earthquake force to cause uplift on the substructure equal to 10 percent of the dead load reaction of the superstructure. Where such forces can be developed, the crossbeam, column and footing shall be designed to carry these earthquake forces.

For concrete superstructures built integrally with the substructure, the substructure elements shall be designed to carry their dead load plus all the elements below them including soil overburden as though they were suspended from the superstructure. (Seal not included). For this condition, the ultimate downward force shall be 1.0 (EQ + Uplift). For structures carried on elastomeric pads or where there is no positive vertical connection, the uplift force from the superstructure shall be neglected.

Post-tensioning Effects from Superstructure - EL

When cast-in-place, post-tensioned superstructures are constructed monolithic with the piers, the substructure design should take into account frame moments and shears caused by elastic shortening and creep of the superstructure upon application of the axial post-tensioning force at the bridge ends. Frame moments and shears thus obtained should be added algebraically to the values obtained from the primary and secondary moment diagrams applied to the superstructure.

When cast-in-place, post-tensioned superstructures are supported on sliding bearings at some of the piers, the design of those piers should include the longitudinal force from friction on the bearings generated as the superstructure shortens during jacking. When post-tensioning is complete, the full permanent reaction from this effect should be included in the governing AASHTO load combinations for the pier under design.

Wind Loads – WL and WS

Wind forces shall be applied to the substructure units in accordance with the loadings specified in AASHTO. Transverse stiffness of the superstructure may be considered, as necessary, to properly distribute loads to the substructure provided that the superstructure is capable of sustaining such loads. Vertical wind pressure, per AASHTO 3.8.2, shall be included in the design where appropriate, for example, on single column piers. Wind loads shall be applied through shear keys or other positive means from the superstructure to the substructure. Wind loads shall be distributed to the piers and abutments in accordance with the laws of statics. Transverse wind loads can be applied directly to the piers assuming the superstructure to act as a rigid beam. For large structures a more appropriate result might be obtained by considering the superstructure to act as a flexible beam on elastic supports.

7.1.4 Concrete Class for Substructure

The concrete class for the design of substructure units shall normally be Class 4000. This includes footings, pedestals, massive piers, columns, crossbeams, traffic barriers. Foundation seals will use Class 4000W.

Where retaining walls are connected directly to the bridge superstructure and color matching is important, consideration could be given to using Class 4000 in the retaining wall or using pigmented sealer in order that the concrete color will not vary from adjacent portions of the structure.

7.1.5 Foundation Seals

A concrete seal within the confines of a cofferdam permits construction of a pier footing and column in the dry. This type of underwater construction is practical to a water depth of approximately 50 feet.

Seal concrete is placed underwater with the use of a tremie. A tremie is a long pipe that extends to the bottom of the excavation and permits a head to be maintained on the concrete during placement. After the concrete has been placed and has obtained sufficient strength, the water within the cofferdam is removed. The weight of the seal concrete resists the hydrostatic pressure exerting force at the base of the seal. In Figure 7-5, some of the factors that must be considered in designing a seal are illustrated.




Figure 7-5

A. General Seal Criteria

The Normal High Water Elevation is defined as the highest water surface elevation that may normally be expected to occur during a given time period. This elevation, on the Hydraulics Data Sheet, is obtained from discussions with local residents or by observance of high water marks at the site. The normal high water is not related to any flood condition.

Seal Vent Elevation

The headquarters Hydraulics Section recommends a seal vent elevation in accordance with the following criteria:

1. Construction time period not known

   If the time period of the footing construction is not known, the vent elevation reflects the normal high water elevation that might occur at any time during the year.

2. Construction time period known.

   If the time period of the footing construction can be anticipated, the vent elevation reflects the normal high water elevation that might occur during this time period. (If the anticipated time period of construction is later changed, the Hydraulics Section shall be notified and appropriate changes made in the design.)

Scour Depth

The Headquarters Hydraulics Section determines the depth of the anticipated scour. The bottom of footing, or bottom of seal if used, shall be no higher than the scour depth elevation. After preliminary footing and seal thicknesses have been determined, the Bridge Designer shall review the anticipated scour elevation with the Hydraulics Section to ensure that excessive depths are not used.

Foundation Elevation Recommended in Geotechnical Report

Based on the results obtained from test borings at the site, the Geotechnical Engineer determines a foundation elevation, bearing capacity and settlement criteria. If other factors control, such as scour or footing cover, the final footing elevation should be adjusted as required.

Unusual Conditions

Unusual site conditions such as rock formations or deep foundations require special considerations in order to obtain the most optimum design. The proposed foundation design/construction should be discussed with both the Geotechnical Engineer and the Bridge Hydraulics Section prior to final plan preparation.

B. Spread Footing Seals

The Geotechnical Division will generally recommend whether a foundation seal may or may not be required for construction. Bearing loads are the column moments applied at the base of the footing and vertical load applied at the bottom of the seal. The seal is sized for the soil bearing, capacity, and Overturning Stability need only be checked at the base of the pier footing.

When A Seal is Required During Construction

If the footing can be raised without violating cover requirements, the bottom of the seal elevation shall be the lower of the scour elevation or the foundation elevation as recommended by the Geotechnical Engineer. Bottom of seal may be lower than the scour elevation or foundation elevation due to cover requirements. Spread footing final design will include the dead load weight of the seal.

When Seal May Not Be Required for Construction

Both methods of construction are detailed in the Plans when it is not clear if a seal is required for construction. The Plans must detail a footing with a seal and an alternate without a seal. The Plan quantities are based on the footing designed with a seal. If the alternate footing elevation is different from the footing with seal, it is also necessary to note on the plans the required changes in rebar such as length of column bars, increased number of ties, etc.

C. Pile Footing Seals

The top of footing, or pedestal, is set by the footing cover requirements. The bottom of seal elevation is based on the stream scour elevation determined by Hydraulics. A preliminary analysis is made using the estimated footing and seal weight, and the column moments and vertical load at the base of the footing to determine the number of piles and spacing. Seal size will be 1 foot 0 inches larger than the footing all around. If the seal is omitted during construction, the bottom of footing shall be set at the scour elevation and an alternate design is made. The following LFD Timber Pile Footing example re-printed in the BDM as a guideline and not intended to be used directly for design.

7.1.5.C.1 Timber Pile Footing Example

In no case shall the uplift exceed the weight of the material (buoyancy considered) surrounding the embedded portion of the pile, using a factor of safety of 1.25.

Example:

Head in feet on bottom of seal = 45.0 feet

40 Ton timber piles

Pile spacing 3-foot 3-inh centers each way

Unit submerged weight of soil $\leq$ 50 pounds per cubic foot

Unit weight water = 62.5 pounds per cubic foot fresh water; 64 pounds per cubic foot sea water

Factor of safety = 1.25

From chart, "Thickness of Foundation Seals," Appendix 9.7-A1, thickness of seal = 5.0 feet

Uplift per pile = (head) (Pile spacing)^2 (Unit weight water) minus (seal thickness) (Pile spacing)^2 (Unit weight seal concrete) plus (Volume embedded pile) (Unit weight seal concrete)

Uplift per pile = $45\ (3.25)^2\ (.0625) - (5.0)\ (3.25)^2\ (0.145) + 5.0\ (\frac{\pi}{4})\ (1.0)^2\ (0.145)$

Uplift per pile = $29.7 - 7.6 + 0.6 = 22.7^k$/pile

$$\text{Pile Extension} = \frac{\text{(Uplift per pile) (F.S.)}}{\text{(Pile spacing)}^2\ \text{(Unit submerges weight of soil)}}$$

$$\text{Pile Extension} = \frac{22.7^k\ (1.25)}{(3.25)^2\ (0.050)} = 53.7 \text{ feet (Say 54 feet)}$$

Must be shown on plans.

If it is not practical to drive piling this far, additional seal thickness must be added. Consult with your supervisor.

7.2 Foundation Modeling

7.2.1 General Modeling Concepts

Proper bridge modeling for seismic events is important to ensure that foundations remain stable and the substructure above ground remains ductile. Misinterpreted AASHTO Specifications and modeling errors can lead to a wide range of substructure sizes. Unrealistic models will likely produce unnecessary costs in substructure members. Extreme event forces will generally govern in regions of high seismic acceleration. Strength forces will generally govern in regions of low acceleration.

The bridge analysis will use unfactored loads to determine seismic load distribution. Unfactored loads and seismic response are then factored for design of substructure elements.

Liquefiable Soils

Soil liquefaction requires a separate bridge analysis used concurrently with a static soil analysis to check the design of substructure elements. Liquefied soil generally reduces the soil lateral resistance and increases the axial loads. Load cases with liquefied soils will generally govern for designs that consider deflection, such as bearings or expansion gaps. Large structures with independent segments and liquefiable soil must be investigated for seismic performance. Load cases with static soils will generally govern for design that considers forces (or strength limit states). Bridge design must check the foundation capacity and superstructure behavior for both soil conditions. Consult the Supervising Bridge Engineer if liquefiable soils lead to cost prohibitive designs.

Abutments

Most bridge models should include an effective abutment stiffness that accounts for expansion gaps and incorporates a realistic value for the embankment fill response. The abutment fill stiffness is nonlinear and is dependent upon on the soil properties. A longitudinal spring is not required for L-type abutments if seismic superstructure deflections do not impact the backwall.

Other structures such as stub abutments or L-type abutments with superstructures impacting the backwall should include a longitudinal spring for the abutment fill. Based on passive earth pressure tests and the force deflection results from large-scale abutment testing at UC Davis, the initial embankment fill stiffness is 20 Kip/in per foot of wall. The initial stiffness is adjusted proportional to the backwall/diaphragm height, as shown in Equation 7.2.1.1. Where, W_{bw} is the Width (ft) and H_{bw} is the Height (ft) of the backwall for L-type abutments, or the diaphragm for Stub abutments.


$$K_{abut} = \frac{20kip/in}{ft} \times W_{bw} \times \frac{H_{bw}}{5.5}$$

Equation 7.2.1-1

The passive pressure (P) resisting the movement at the abutment increases linearly with the displacement to a maximum passive pressure of 5.0 ksf, presented in Equation 7.2.1.2. The maximum pressure is based on the ultimate static force developed in the full scale abutment testing conducted at UC Davis [Maroney, 1995]. See CalTrans Seismic Design Criteria, Version 1.3, Feb. 2004 for more detailed information on abutment springs.


$$P_{force} = H_{bw} \times W_{bw} \times 5.0ksf \times \frac{H_{bw}}{5.5}$$

Equation 7.2.1-2




L-type Abutment Spring

Figure 7-6



Stub Abutment Spring


Figure 7-7



*where diaphragms are designed for passive pressure.

Abutment Height and Width


Figure 7-8



Abutment Width for Skewed Bridges
Figure 7-9

PY Curves and Soil Modulus

A finite element model may use non-linear springs based on PY curves to represent foundation response as shown in Figure 7.1.2-5. PY curves graph the relationship between the lateral soil resistance and the associated deflection of the soil. Generally, P stands for a force per unit length (of pile) such as kips per inch. Y is the corresponding horizontal deflection (of pile) in units such as inches.




Pile Model using a Set of Non-linear PY Curves
Figure 7-10

Node placement for springs should attempt to imitate the soil layers. Generally, the upper 1/3 of the pile in stiff soils has the most significant contribution to the lateral soil reaction. Springs in this region should be spaced at most 3 feet apart. Spacing of 2.5 feet has demonstrated results within 10% of Lpile output moment and shear. Springs for the lower 2/3 of the pile can transition to a much larger spacing. Stiff foundations in weak soils will transfer loads much deeper in the soil and more springs would be sensible.

Transverse and longitudinal springs must include group reduction factors to analyze the structure/soil response. Soil properties are modified in Lpile to account for Group Effects. Lpile then generates PY curves based on the modified soil properties and desired depths. See BDM Section 7.2.5 for Group Effects.

FEM programs will accept non-linear springs in a Force (F) vs. Deflection (L) format. P values in a PY curve must be multiplied by the pile length associated with the spring in the FEM. This converts a P value in Force/Length units to Force.



Secant Modulus Illustration
Figure 7-11

Soil Modulus - E_S

Soil Modulus is defined as the force per length (of a pile) associated with a soil deflection. As shown in Figure 7.1.2-6, E_S is a slope on the PY curve or P/Y. E_S is a secant modulus since the PY relationship is nonlinear and the modulus is a constant. The units are F/L per L or F/L^2, such as kips per square inch.

Subgrade Modulus - k_S

A closely related term is the Subgrade Modulus (or Modulus of Subgrade Reaction) provided in a Geotechnical Report. This is defined as the soil pressure associated with a soil deflection. The units are F/L^2 per L or F/L^3, such as kips per cubic inch.

7.2.2 Substructure Analysis Flow Chart

The following is a general description of the iterative process that converges to acceptable seismic design forces. See Figure 7-12 for a Substructure Seismic Flow Chart.

1. Build a Finite Element Model (FEM) in order to determine initial forces to substructure elements (EQ+DL). Assume the foundation springs are located at the ground line. A good initial support assumption for piles would be to add 10 feet to the column length in stiff soils and 15 feet to the column in soft soils. The same can be assumed for shafts. An alternate method is to use 85% of the fixed support reactions for the initial forces. If fixed supports are used for the initial foundation model, more iteration will be required to converge. Use the fully fixed forces for foundations in rock.

   Use multi-mode response spectrum analysis to generate initial Seismic Shear, Moment, & Axial Loads. Analysis will use unfactored loads. Factored analysis results are used for design.

2. Using initial model forces, determine a preliminary footing size, shaft size/length, or pile group arrangement for bridge supports.

3. The FEM and the soil/structure interaction analysis must agree or converge on soil/structure lateral response. In other words, moment and shear, deflection and rotation, and the spring values of the two programs should be within 5% or 10%. More iteration will provide convergence much less than 1%. The iteration process to converge is as follows:

   a. Apply the initial FEM loads (moment and shear) to a soil/structure lateral response program such as Lpile or S-Shaft.


   b. Calculate foundation spring values for the FEM.

c. Re-run the seismic analysis. The structural response will change. Check to insure the FEM results (M, V, Δ, θ, and spring values) in the transverse and longitudinal direction are within 5% of the previous run. This check verifies the linear spring soil response (calculated by the FEM) is close to the predicted nonlinear soil behavior (calculated by the soil response program). If the results of the FEM and the soil response program are different, recalculate springs and repeat steps (a) thru (c) until the two programs converge within 5%.

   If the fixed head boundary conditions are incorrectly assumed for a free head situation, the FEM's moment and shear may still converge to the soil response program's moment and shear. However, the soil response will be much stiffer (and incorrect). The deflections and rotations of the Soil response program will not match the FEM deflections and rotations since the boundary conditions do not match. See BDM Section 7.2.5.1.

   Designers should note the magnitude of shear and moment at the top of the shaft. The seismic design philosophy requires a plastic hinge in the substructure elements above ground (in the columns). If the column "zero" moment is close to a shaft head foundation spring, the FEM and Soil response program will not converge and plastic hinging might be below grade.

4. Revise the preliminary substructure or adjust the springs to be within structural and geotechnical limits.



Substructure Seismic Flow Chart
Figure 7-12


7.2.3 Bridge Model Section Properties

In general, gross section properties may be assumed for all FEM members, except concrete columns. The concrete unit weight for seismic analysis will be the same as for strength design, 160 pcf.

Cracked Properties for Columns

The overall seismic design goal is to achieve ductile performance and avoid bridge collapse. Columns analyzed with non-cracked properties form plastic hinges at higher stress levels, which minimize damage in an intermediate earthquake. (Minimal damage is spalling of concrete cover and small permanent deformations.) However, this assumption results in larger foundations than using the column cracked section. The seismic responses of a bridge analyzed with cracked sections have longer periods and reduce lateral forces and foundation size. The cracked column assumption will result in a higher potential damage for intermediate earthquakes, but is considered a reasonable risk. Both cracked and non-cracked column assumptions result in ductile performance using AASHTO response modification factors, R.

Concrete columns assume cracked section properties since plastic hinges are designed to form in these members. In general, column properties in FEM are rotated 90 degrees from the Global axis; and Beta angles are used to orient the column local axis to the Pier skew. In lieu of hand calculations, Figure 7-13 presents a stiffness ratio for round columns which may be used to approximate the effective moment of inertia, I_{eff} for all bridge columns. Figure 7-13 is a reprint from Figure 85, page 200, Seismic Retrofitting Manual for Highway Bridges, Pub. No. FHWA-RD-94-052, May 1995.



Effective Stiffness for Circular Bridge Columns
Figure 7-13

Torsional Properties

The torsional moment of inertia, for non-circular shapes is not the Polar Moment of Inertia (calculated by GDS). The sum of $bt^3/3$ may be used to calculate torsional stiffness of deck/I girder superstructures, where the girders are equivalent rectangular areas with the same height.

Shaft Properties

The moment of inertia for shafts will be based on the gross section (Ig) or non-cracked. The shaft concrete strength and construction methods lead to significant variation in shaft stiffness described as follows.

For a stiff substructure response:

- Use 1.5 f'c to calculate the modulus of elasticity. Since aged concrete will generally reach a strength of at least 6 ksi when using a design strength of 4 ksi, the factor of 1.5 is a reasonable estimate for an increase in stiffness.
- Increase shaft Ig by adding 6" to the shaft diameter. The WSDOT shaft special provisions allow the contractor to increase the shaft diameter up to 6" to accommodate metric sizes.
- When permanent casing is specified, increase shaft Ig using the transformed area of a ¾" thick casing. Since the contractor will determine the thickness of the casing, ¾" is a conservative estimate for design.

For a soft substructure response,

- Use 0.85 f'c to calculate the modulus of elasticity. Since the quality of shaft concrete can be suspect when placed in water, the factor of 0.85 is an estimate for a decrease in stiffness.
- Use shaft Ig.
- When permanent casing is specified, increase shaft Ig using the transformed area of a 3/8" thick casing. Since the contractor will determine the thickness of the casing, 3/8" is a minimum estimated thickness for design.

7.2.4 Bridge Model Verification

As with any FEM, the designer should review the foundation behavior to ensure the foundation springs correctly imitate the known boundary conditions and soil properties. Watch out for mismatch of units!

All finite element models must have dead load static reactions verified and boundary conditions checked for errors. The static dead loads (DL) must be compared with hand calculations or another program's results. For example, span member end moment at the supports can be released at the piers to determine simple span reactions. Then hand calculated simple span DL or PGsuper DL and LL is used to verify the model.

Crossbeam behavior must be checked to ensure the superstructure DL is correctly distributing to substructure elements. A bridge line model concentrates the superstructure mass and stresses to a point in the crossbeam. Generally, interior columns will have a much higher loading than the exterior columns. To improve the model, crossbeam I_{gross} should be increased to provide the statically correct column DL reactions. This may require increasing I_{gross} by about 1000 times. Many times this is not visible graphically and should be verified by checking numerical output.

Seismic analysis may also be verified by hand calculations. Hand calculated fundamental mode shape reactions will be approximate; but will insure design forces are of the same magnitude, (see AASHTO 4.7.4.3.2). FEM results must include enough mode shapes such that the total percent mass participation must be in excess of 90% for the transverse and longitudinal directions.

Designers should note that additional mass might have to be added to the bridge FEM for seismic analysis. For example, traffic barrier mass and crossbeam mass beyond the last column at piers may contribute significant weight to a two-lane or ramp structure.

7.2.5 Deep Foundation Modeling

A designer must assume a foundation support condition that best represents the foundation behavior. Deep foundation springs attempt to imitate the non-linear lateral behavior of several soil layers interacting with the deep foundation. The bridge FEM then uses the springs to predict the seismic structural response.

There are two accepted methods to model deep foundation lateral response. The Bridge and Structures Office prefers the first method. This models deep foundations by using linear support springs or a {6x6} matrix, if a cross couple coefficient is required. The linear springs are generated to reproduce the non-linear behavior of the soil and foundation at the maximum loading. Soil response programs, such as Lpile or S-Shaft, analyze the non-linear soil response. The results are then used to determine the linear springs.

The second method attaches non-linear springs along the length of deep foundation members in a model. See PY Curves in BDM Section 7.2.1. This method has the advantage of solving the superstructure and substructure seismic response simultaneously. The soil springs must be nonlinear PY curves and represent the soil/structure interaction.

Models using linear soil springs that are not based on non-linear soil-structure interaction are generally considered inaccurate for soil response/element stress and are not acceptable.

Spring Location

The preferred location for a foundation spring is at the ground line, which includes the column mass in the seismic analysis. For design, the column forces are provided by the FEM and the foundation forces are provided by the Geotech program. Springs may be located at the top of the column. However, the seismic analysis will not include the mass of the columns. The advantage of this location is the soil/structure analysis includes both the column and foundation design forces.

Designers should be careful to match the geometry of the FEM and Geotech program. If the location of the foundation springs (or node) in the FEM does not match the location input to the Geotech program, the two programs may not converge.

A. Boundary Conditions

To calculate spring coefficients, the designer must first identify the predicted shape, or direction of loading, of the foundation member where the spring is located in the bridge model. This will determine if one or a combination of two boundary conditions apply for the transverse and longitudinal directions of a support.

A fixed head boundary condition occurs when the FOUNDATION element is in double curvature where translation without rotation is the dominant behavior. Stated in other terms, the shear causes deflection in the opposite direction of applied moment. This is a common assumption applied to both directions of a rectangular pile group that supports a footing pile cap.

A free head boundary condition is when the FOUNDATION element is in single curvature where translation and rotation is the dominant behavior. Stated in other terms, the shear causes deflection in the same direction as the applied moment. Most large diameter shaft designs will have a single curvature below ground line and require a free head assumption. The classic example of single curvature is a single column on a single shaft. In the transverse direction, this will act like a flagpole in the wind, or free head. What is not so obvious is the same shaft will also have single curvature in the longitudinal direction (below the ground line), even though the column exhibits some double curvature behavior. Likewise, in the transverse direction of multi-column piers, the columns will have double curvature (frame action). The shafts will generally have single curvature below grade and the free head boundary condition applies. The boundary condition for large shafts with springs placed at the ground line will be free head in most cases.

The key to determine the correct boundary condition is to resolve the correct sign of the moment and shear at the top of the shaft (or point of interest for the spring location). Since multi-mode results are always positive (CQC), this can be worked out by observing the seismic moment and shear diagrams for the structure. If the sign convention is still unclear, apply a unit load in a separate static FEM run to establish sign convention at the point of interest.

The correct boundary condition is critical to the seismic response analysis. For any type of soil and a given foundation loading, a fixed boundary condition will generally provide soil springs four to five times stiffer than a free head boundary condition.


B. Linear Spring Calculation

The first step to calculate a foundation spring is to determine the shear and moment in the structural member where the spring is to be applied in the FEM. Foundation spring coefficients should be based on the maximum shear and moment from the applied longitudinal OR transverse seismic loading. The combined load case (1.0L and 0.3T) should be assumed for the design of structural members, and NOT applied to determine foundation response. For the simple case of a bridge with no skew, the longitudinal shear and moment are the result of the seismic longitudinal load, and the transverse components are ignored. This is somewhat unclear for highly skewed piers or curved structures with rotated springs, but the principle remains the same.

If Lpile is used for foundation analysis, group effects will require the geotechnical properties to be reduced before the spring values calculated. The group effects generally will be different transversely and longitudinally. The exception would be a single column with a single shaft.

1. Matrix Coordinate Systems

   The Global coordinate systems used to demonstrate matrix theory are usually similar to the system defined for substructure loads in BDM Section 7.1.3, and is shown in Figure 7-14. This is also the default Global coordinate system of GTStrudl. This coordinate system applies to this BDM Section to establish the sign convention for matrix terms. Note vertical axial load is labeled as P, and horizontal shear load is labeled as V.



Standard Global Matrix
Figure 7-14

a) **Matrix Coefficient Definitions**

The stiffness matrix containing the spring values and using the standard coordinate system is shown in Figure 7-15. The sign of the K34 and K16 terms must be determined based on the sign convention. In this case, K34 will be negative. For detailed information on cross-couple terms, see Lateral Springs using Fixed Head Boundary Conditions.

The coefficients in the stiffness matrix are generally referred using several different terms. Coefficients, spring or spring value are equivalent terms. Lateral springs are springs that resist lateral forces. Vertical springs resist vertical forces.

$$\begin{Bmatrix} & Vx & Py & Vz & Mx & My & Mz \\ Vx & K11 & 0 & 0 & 0 & 0 & K16 \\ Py & 0 & K22 & 0 & 0 & 0 & 0 \\ Vz & 0 & 0 & K33 & K34 & 0 & 0 \\ Mx & 0 & 0 & K43 & K44 & 0 & 0 \\ My & 0 & 0 & 0 & 0 & K55 & 0 \\ Mz & K61 & 0 & 0 & 0 & 0 & K66 \end{Bmatrix} \times \begin{Bmatrix} Disp. \\ \Delta x \\ \Delta y \\ \Delta z \\ \theta x \\ \theta y \\ \theta z \end{Bmatrix} = \begin{Bmatrix} Force \\ Vx \\ Py \\ Vz \\ Mx \\ My \\ Mz \end{Bmatrix}$$

Standard Global Matrix

Figure 7-15

Where the linear spring constants or K values are defined as follows using the Global Coordinates:

K11 = $+Vx_{app}/+\Delta x$ = Kip/in = Longitudinal Lateral Stiffness

K22 = AE/L = Kip/in = Vertical or Axial Stiffness

K33 = $-Vz_{app}/-\Delta z$ = Kip/in = Transverse Lateral Stiffness

K44 = $+Mx_{app}/+\theta x$ = K in/rad = Transverse Bending or Moment Stiffness

K55 = JG/L = K in/rad = Torsional Stiffness

K66 = $+Mz_{app}/+\theta z$ = K in/rad = Longitudinal Bending or Moment Stiffness

K34 = $-Vz_{ind}/+\theta_x$ = Kip /rad = Transverse Lateral Cross-couple term (Fixed Head only)

K16 = $+Vx_{ind}/+\theta_z$ = Kip /rad = Longitudinal Lateral Cross-couple term (Fixed Head only)

K43 = $+Mx_{ind}/-\Delta z$ = Kip /rad = Longitudinal Moment Cross-couple term (Fixed Head only)

K61 = $+Mz_{ind}/+\Delta x$ = Kip /rad = Transverse Moment Cross-couple term (Fixed Head only)

Diagonal Terms

The linear lateral spring constants along the diagonal represent a point on a non-linear soil/structure response curve. When calculating the spring values, the shear and moment must be applied at the same time to capture the non-linear response of the soil/structure interaction at the desired loading. These are linear approximations of the soil response for all loading applied to a structure. The springs are only accurate for the maximum loading and less accurate for loads less than maximum. This is considered acceptable for Strength and Extreme Event design.

The vertical and torsional constants (properties) are calculated based on statics.

b) Vertical Springs: K22

Vertical spring constants can be calculated from the following three assumptions. See Figure 7.2.5.2.3 and the following definitions. REF: Page 6-30, Seismic Design of Highway Bridges Workshop Manual, Pub. No. FHWA-IP-81-2, Jan 1981.


A = Cross sectional area

E = Young's modulus

L = Length of pile

F = Fraction of pile embedded

Point bearing piles: $K22 = \frac{AE}{L}$



Showing Pile Stress
Figure 7-15b

Friction piles:

1. Linearly varing skin friction: $K22 = 3\frac{AE}{L}$

2. Constant skin friction: $K22 = 2\frac{AE}{L}$

Partially embedded piles (in the soil):

1. Linearly varing skin friction: $K22 = \frac{AE}{\left(1-\frac{F}{2}\right)L}$

2. Constant skin friction: $K22 = \frac{AE}{\left(1-\frac{2F}{3}\right)L}$

c) **Torsional Springs: K55**

The S-Shaft program calculates acceptable torsional spring values for shafts and may be used for foundation springs. In general, torsional spring constants for individual piles are based on the strength of the pile. The statics equation for torsional resistance is given below.

$K55 = M/\phi = T/\phi = JG/L$

where, $G = 0.4\ E$

J = Torsional Moment of Inertia

L = Length of pile

d) **Lateral Springs using Fixed Head Boundary Condition**

If the shear and moment are OPPOSING where the spring is located, a fixed head boundary condition is required to model the loaded foundation in a finite element model.

Since applying load to a fixed end results in no reaction, a soil/structure interaction analysis will generally analyze the shear and moment simultaneously as a free head. Using the soil response results, a cross-couple correction term will be required in a FEM to produce the induced moment in the element modeling the fixed head condition. If accurate stresses in fixed head element are not required, the cross-couple term may be omitted.

There are two ways to model fixed head pile group. The most common method for a column footing is to use a group spring to model a group of piles or shafts as one set of springs. This method uses six linear springs to represent the foundation behavior. Lateral loads are resisted by Cross-couples terms do not apply and individual pile loads must be calculated from the FEM results.

The second method would be to model the individual piles. This is more helpful for analyzing local stresses in the foundation cap element and for each pile. Cross-couple terms may be included and individual pile loads are generated in the FEM.

Off-diagonal Terms (Cross-couples)

Cross-couple springs will not be symmetric for non-linear modeling foundation modeling. Since finite element programs will use matrix multiplication to generate reactions, doing the math is the easy way to show the effect of cross-couple terms. Note that K16 and K34 terms will have opposite signs.

The longitudinal reactions are:

$Vx = K11 \times \Delta_x + K16 \times \theta_z$ and $Mz = K61 \times \Delta_x + K66 \times \theta_z$

The transverse reactions are:

$Vz = K33 \times \Delta_z + K34 \times \theta_x$ and $Mx = K43 \times \Delta_z + K44 \times \theta_x$

For a true fixed head boundary condition (translation only) in the X and Z directions, there will be no rotation about the X and Z axis. θ_x and θ_z will be zero. This means the K34 and K16 cross-couple terms will not affect the shear reactions. Likewise, the K66 and K44 rotational terms zero out and do not effect the moment reaction. This leaves the K61 and K43 cross-couple terms to generate induced moments based on

the deflections in the X and Z directions. Designers should note, the cross-couple moments are applied to a fixed footing element and are resisted axially by the piles. This affects the local stress in the footing and axial loading of the pile much more than the column moment and shear, which is usually the primary focus for design.

Modeling real life features may be somewhat different than the theoretically true fixed condition. The top of a column at the superstructure or some pile and shaft applications may have opposing shear and moment, however the moment may be much less than the theoretical induced free head moment value. In other words, there may be significant rotations that need to be accounted for in the spring modeling. Designers need to be aware of this situation and use engineering judgment. The FEM would have rotations about the X and Z axis. θ_x and θ_z will NOT be zero and both the cross-couples terms and rotational springs may significantly affect the analysis.

1) Longitudinal Springs

   The following lateral spring sections describe the method to calculate a lateral, rotational, and cross couple springs for a theoretically fixed application. Axial load (Py), shear (Vx, Vz), and moment (Mx, Mz) would be provided by a FEM analysis that includes static dead load. A standard global coordinate system and sign convention applies.

   Lateral Spring: K11 = $Vx_{app}/\Delta x$


   A longitudinal lateral spring is calculated by applying the longitudinal shear (Vx) and axial load (Py) in a soil response program with the rotation at the top equal to zero. The spring value is the applied shear (Vx_{app}) divided by the resulting deflection (Δx). The shear is positive and the deflection is positive. Therefore, K11 is positive.

   Rotational Spring: K66 = $Mz_{app}/\theta z$

   A longitudinal rotational spring is calculated by applying the longitudinal moment (Mz) and axial load (Py) in a soil response program with the translation at the top equal to zero. The spring value is the applied moment (Mz_{app}) divided by the resulting rotation (θz). The moment is positive and the rotation is positive. Therefore, K66 is positive.

   Cross-couple Spring: K16 = Vx_{ind}/θ_z

   K11 and K66 alone do not predict the shape or reaction of the foundation element. The cross-couple term K16 will add a shear force to correct the applied moment deflection. The spring value is the induced shear (Vx_{ind}) divided by the associated rotation (θz). The shear is positive and the rotation is positive. Therefore, K16 is positive.



Fixed Head Springs
Figure 7-16

2) Transverse Springs

The process is the same to calculate lateral K33, rotational K44, and cross-couple K34. The significance of repeating these steps is to show the significance of the sign convention. For the transverse springs, the sign of the shear and moment are the OPPOSITE. They work against each other. For this sample, the shear (-Vz) is negative and therefore Mx has to be positive.

Lateral Spring: K33 = $Vz_{app}/\Delta z$

A transverse lateral spring is calculated by applying the transverse shear (-Vz) and axial load (Py) in a soil response program with the rotation at the top equal to zero. The spring value is the applied shear ($-Vz_{app}$) divided by the resulting deflection ($-\Delta z$). The shear is negative and the deflection is negative. Therefore, K33 is positive.

Rotational Spring: K44 = $Mx_{app}/\theta x$

A transverse rotational spring is calculated by applying the transverse moment (Mx) and axial load (Py) in a soil response program with the translation at the top equal to zero. The spring value is the applied moment (Mx_{app}) divided by the resulting rotation (θx). The moment is positive and the rotation is positive. Therefore, K44 is positive.


Cross-couple Spring: K34 = $-Vz_{ind}/\theta_x$

The cross-couple term K34 will add a shear force to correct the applied moment deflection. The spring value is the induced shear ($-Vz_{ind}$) divided by the associated rotation (θx). The shear is negative and the rotation is positive. Therefore, K34 is negative. If Mx were assumed negative, Vz would be positive and the K34 term would still be negative due to the sign convention of the coordinates. This indicates that the direction of loading does not matter to establish the sign of the cross-couple term.

e. Lateral Spring using Free Head Boundary Condition

If the shear and moment do not oppose each other a free head boundary condition is assumed to analyze a geotechnical response. Spring calculation for this boundary condition is somewhat quicker since only one geotechnical analysis is required and cross-couple terms do not apply. Spring values are calculated from the results of applying moment and shear at the same time and in the same direction to the foundation element. The lateral springs are simply V/Δ and the rotational springs are M/θ. Note when the free head shear and moment are working in the same direction, the spring values will always be positive.

Since cross-couple terms are not required, a matrix is not necessary to input spring coefficients into the finite element bridge model. Linear spring supports will yield the same results as a linear matrix.



Free Head Springs
Figure 7-17

f. Combination Free and Fixed Head Boundary Condition

An example of this case would be a single row of piles that support an abutment footing cap (at grade) with the superstructure supported on elastomeric bearings. In the transverse direction, the boundary condition is fixed head and would require a cross-couple term. In the longitudinal direction, the boundary condition is free head and the cross-couple term is zero as shown in Figure 7-18.

$$\begin{Bmatrix} & Vx & Py & Vz & Mx & My & Mz \\ Vx & K11 & 0 & 0 & 0 & 0 & 0 \\ Py & 0 & K22 & 0 & 0 & 0 & 0 \\ Vz & 0 & 0 & K33 & K34 & 0 & 0 \\ Mx & 0 & 0 & K43 & K44 & 0 & 0 \\ My & 0 & 0 & 0 & 0 & K55 & 0 \\ Mz & 0 & 0 & 0 & 0 & 0 & K66 \end{Bmatrix} \times \begin{Bmatrix} Disp. \\ \Delta x \\ \Delta y \\ \Delta z \\ \theta x \\ \theta y \\ \theta z \end{Bmatrix} = \begin{Bmatrix} Force \\ Vx \\ Py \\ Vz \\ Mx \\ My \\ Mz \end{Bmatrix}$$

Figure 7-18

The moment applied to the abutment about the longitudinal axis (Mx) is resisted axially by the piles. Therefore, the moment applied to the pile (Mx_{app}) is zero. Since the induced shear (Vz_{ind}) is also zero, the K34 term ($Vz_{ind}/\theta x$) cross-couple term should be calculated using $Mx_{ind}/\Delta z$; which is K43.

C. Group Effects

If the S-Shaft program is used for soil/structure interaction analysis, the lateral group effect is calculated based on Wedge Theory, and included in the results.

When a foundation analysis uses Lpile or an analysis using PY relationships, the Geotechnical Report will provide transverse and longitudinal multipliers that are applied to the PY curves. This will reduce the pile resistance in a linear fashion. The reduction factors for lateral resistance due to the interaction of deep foundation members is provided in the WSDOT Geotechnical Design Manual, Section 8.12.2.5.

D. Pile Footing M**atrix** using Lpile and GTStrudl:

A matrix with cross-couple terms is a valid method to model pile supported footings. The analysis assumes the piles will behave similar to a column fixed at the bottom (in the soil) with lateral translation only at the top (no rotation). This requires Fixed Head Boundary Condition to calculate spring values.

The Lpile program will solve for non-linear soil results for individual piles. See Group Effects in BDM section 7.2.5.C to reduce the soil properties of a pile in a group in both the transverse and longitudinal directions. This sample matrix calculates a foundation spring for an individual pile.

If a pile group has a large number of piles, the GPILE computer program is available to generate a spring matrix for the group. The program also computes individual pile loads and deflections from input loads. The output will contain a SEISAB {6 x 6} stiffness matrix. GTStrudl or SAP matrices have the same coefficients with a different axis orientation for the pile group.

The pile spring requires eight pile stiffness terms for a matrix as discussed in BDM Section 7.2.5.B. The following sample calculations discuss the lateral, longitudinal, and cross-couple spring coefficients for a GTStrudl local coordinate system. Axial and torsion springs, two of the eight coefficients, will not be discussed in this section.

The maximum FEM transverse and longitudinal seismic loads (Vy, Mz, Vz, My and axial Px) provide two loads cases for analysis in Lpile. The Lpile results of these two load cases will be used to calculate lateral, longitudinal, and cross-couple spring coefficients.

This sample calculation assumes there are no group effects, no differential loading between the transverse and longitudinal directions. Therefore, Vy = Vz and My = Mz. A standard global coordinate system is assumed for the bridge. This sample will also assume a GTStrudl element is used to provide the foundation spring, which requires a different local axis coordinate system to input matrix terms, as shown in Figure 7-19. When the coordinate system changes, the sign convention of shear and moment also will change. This will be expressed in a 6x6 matrix by changing the location of the spring values and in sign of any cross-couple terms.




Figure 7-19

The locations of GTStrudl matrix terms are shown in Figure 7-20. The displacements are local and this requires the spring coefficients to be moved to produce the correct local reactions. The X axis is the new vertical direction. The Y axis is the new longitudinal direction. The spring coefficient definitions and notation remains the same as defined in BDM Section 7.2.5. Note the shift in diagonal terms and locations of the cross-couple terms. K16 and K61 are now **negative**.

$$\begin{Bmatrix} & Px & Vy & Vz & Mx & My & Mz \\ Px & K22 & 0 & 0 & 0 & 0 & 0 \\ Vy & 0 & K11 & 0 & 0 & 0 & K16 \\ Vz & 0 & 0 & K33 & 0 & K34 & 0 \\ Mx & 0 & 0 & 0 & K55 & 0 & 0 \\ My & 0 & 0 & K43 & 0 & K44 & 0 \\ Mz & 0 & K61 & 0 & 0 & 0 & K66 \end{Bmatrix} \times \begin{Bmatrix} Disp. \\ \Delta x \\ \Delta y \\ \Delta z \\ \theta x \\ \theta y \\ \theta z \end{Bmatrix} \equiv \begin{Bmatrix} Force \\ Px \\ Vy \\ Vz \\ Mx \\ My \\ Mz \end{Bmatrix}$$

Figure 7-20




Figure 7-21

Where the linear spring constants or K values are defined as:

K11	= -Vy/-Δy	= positive = Kip/in	= Longitudinal Lateral Stiffness
K22	= AE/L	= positive = Kip/in	= Vertical or Axial Stiffness
K33	= -Vz/-Δz	= positive = Kip/in	= Transverse Lateral Stiffness
K44	= -My/-θy	= positive = K in/rad	= Transverse Bending or Moment Stiffness
K55	= JG/L	= positive = K in/rad	= Torsional Stiffness
K66	= Mz/θz	= positive = K in/rad	= Longitudinal Bending or Moment Stiffness
K34	= $-Vz_{ind}$ /-θ y	= positive = Kip /rad	= Trans. shear X-couple term (Fixed Head only)
K16	= $-Vy_{ind}$ /θz	= negative = Kip /rad	= Long. shear X-couple term (Fixed Head only)
K43	= $-My_{ind}$ /-Δz	= positive = Kip /rad	= Long. Moment X-couple term (Fixed Head only)
K61	= $+Mz_{ind}$ /-Δy	= negative = Kip /rad	= Trans. Moment X-couple term (Fixed Head only)

Lateral Lpile Springs: K11 and K33

The loading should apply the lateral load (shear = V) and restrain the top against rotation (slope = 0).

Boundary condition code	=	2
Lateral load at the pile head	=	0.250D+05 lbs
Slope at the pile head	=	0.000D+00 in/in
Axial load at the pile head	=	0.758D+05 lbs = P

X	Deflection	Moment	Shear	Soil Reaction	Total Stress	Flexural Rigidity
In	In	Lbs-In	Lbs	Lbs-In	Lbs/In**2	Lbs-In**2
**********	**********	**********	**********	**********	**********	**********
0.00	0.267D+01	-0.383D+07	0.250D+05	0.000D+00	0.270D+05	0.392D+11

$-Vy_{app}$ or $-Vz_{app}$ = 25 kip

$-\Delta y$ or $-\Delta z$ = 2.67”

K11 = -Vy/-Δy and is equal to K33 = -Vz/-Δz = $\frac{-25kip}{-2.67in} = 9.36\frac{kip}{in}$

Note the induced moment values for cross-couple calculation are $+Mz_{ind}$ or $-My_{ind}$ = 3830 k-in.

Moment Lpile Springs: K44 and K66

The loading should apply a moment (M) and restrain the pile top against translation (deflection = 0).

Boundary condition code	=	4
Deflection at the pile head	=	0.000D+00 in
Moment at the pile head	=	0.391D+07 in-lbs
Axial load at the pile head	=	0.103D+06 lbs

X	Deflection	Moment	Shear	Soil Reaction	Total Stress	Flexural Rigidity
In	In	Lbs-In	Lbs	Lbs-In	Lbs/In**2	Lbs-In**2
**********	**********	**********	**********	**********	**********	**********
0.00	0.000D+00	0.391D+07	0.189D+05	0.000D+00	0.281D+05	0.392D+11

$+Mz_{app}$ or $-My_{app}$ = 391 K-in

$+\theta z$ or $-\theta y$ = 0.00845 rad

K44 = +Mz/+θz and is equal to K66 = -My/-θy = $\frac{-391kip}{-0.00845rad} = 46{,}272\frac{kip}{rad}$

Note the induced shear values for cross-couple calculation are $-Vy_{ind}$ or $-Vz_{ind}$ = 18.9 kip

Cross Couple Springs: K34 and K16

Given $-Vy_{ind}$ or $-Vz_{ind}$ = 18.9 kip and $+\theta z$ or $-\theta y$ = 0.00845 rad

Given $+Mz_{ind}$ or $-My_{ind}$ = 3830 k-in and $-\Delta y$ or $-\Delta z$ = 2.67”

Transverse K34 = $-Vz_{ind}/-\theta y = \frac{-18.9 kip}{-0.00845 rad} = 2236 \frac{kip}{rad}$

Transverse K43 = $-My_{ind}/-\Delta z = \frac{-3830\ kip\ in}{-2.67\ in} = 1434 \frac{kip}{rad}$

Use average value for cross-couple: K34 = K43 = $\frac{2236 + 1434}{2} = 1835 \frac{kip}{rad}$

Longitudinal K16 = $-Vy_{ind}/+\theta z = \frac{-18.9 kip}{0.00845 rad} = -2236 \frac{kip}{rad}$

Longitudinal K61 = $+Mz_{ind}/-\Delta y = \frac{3830\ kip\ in}{-2.67\ in} = -1434 \frac{kip}{rad}$

Use average value for cross-couple: K16 = K61 = $\frac{-2236 + -1434}{} = -1835 \frac{kip}{rad}$

$$\begin{Bmatrix} & Px & Vy & Vz & Mx & My & Mz \\ Px & K22 & 0 & 0 & 0 & 0 & 0 \\ Vy & 0 & 9.36 & 0 & 0 & 0 & -1835 \\ Vz & 0 & 0 & 9.36 & 0 & 1835 & 0 \\ Mx & 0 & 0 & 0 & K55 & 0 & 0 \\ My & 0 & 0 & 1835 & 0 & 46272 & 0 \\ Mz & 0 & -1835 & 0 & 0 & 0 & 46272 \end{Bmatrix} \times \begin{Bmatrix} Disp. \\ \Delta x \\ \Delta y \\ \Delta z \\ \theta x \\ \theta y \\ \theta z \end{Bmatrix} = \begin{Bmatrix} Force \\ Px \\ Vy \\ Vz \\ Mx \\ My \\ Mz \end{Bmatrix}$$

7.2.6 *Spread Footing Modeling*

For a first trial footing configuration, Strength column moments or column plastic hinging moments may be applied to generate footing dimensions. Soil spring constants are developed using the footing plan area, embedment depth, Poisson's ratio ν, shear modulus G. Spring constants for shallow rectangular footings are obtained by modifying circular footing theory using the following Equation. This method for calculating footing springs is referenced in FHWA-IP-87-6, Section 7.2.4A, page 140.

$K = \alpha\beta\ K_o$

K = Rotational or Lateral spring

K_o = Stiffness coefficient for the equivalent circular footing, see Figure 7-22. These values are calculated using an equivalent circular footing radius. See Figure 7-32

α = Foundation shape correction factor, see Figure 7-24

β = Embedment factor, see Figure 7-25

Displacement Degree-of-Freedom	K_O
vertical translation	4GR/1*v*
horizontal translation	8GR/2-*v*
torsional rotation	$16GR^3/3$
rocking rotation	$8GR^3/3(1-v)$

Stiffness Coefficients
Figure 7-22




Figure 7-23

Figure 7-23 describes the orientation for used to calculate the equivalent radius values. The global Bridge orientation would be: Axis 2 = Axis Z or transverse to the bridge. The equations for the equivalent circular footing radius (R) are given below. The appropriate equivalent radius is used to calculate the desired spring value.

EQUIVALENT RADIUS:


TRANSLATIONAL: $R_o = \sqrt{\frac{4BL}{\pi}}$


ROTATIONAL:

$$R_1 = \left[\frac{4BL\,(4B^2 + 4L^2)}{6\pi}\right]^{1/4} \quad \text{(x-AXIS ROCKING)}$$


$$R_2 = \left[\frac{(2B)^3\,(2L)}{3\pi}\right]^{1/4} \quad \text{(y-AXIS ROCKING)}$$

$$R_3 = \left[\frac{(2B)\,(2L)^3}{3\pi}\right]^{1/4} \quad \text{(z-AXIS TORSION)}$$





Shape Factor for Rectangular Footings
Figure 7-24



Embedment Factor
Figure 7-25

7.3 Column Design

7.3.1 Preliminary Plan Stage

The preliminary plan stage determines the initial column size, column spacing, and bridge span length based on a preliminary analysis. Columns are spaced to give maximum structural benefit except where aesthetic considerations dictate otherwise. Piers normally are spaced to meet the geometric and aesthetic requirements of the site and to give maximum economy for the total structure. Good preliminary engineering judgment results in maximum economy for the total structure.

The designer may make changes after the preliminary plan stage. The supervisor will review all changes and will determine if the changes need to be reviewed by the Bridge Projects Engineer or the State Bridge and Structures Architect.

Tall piers spaced farther apart aesthetically justify longer spans. Difficult and expensive foundation conditions will also justify longer spans. Span lengths may change in the design stage if substantial structural improvement and/or cost savings can be realized. The designer should discuss the possibilities of span lengths or skew with the supervisor as soon as possible. Changes in pier spacing at this stage can have significant negative impacts to the geotechnical investigation.

Column spacing should minimize column dead load moments. Multiple columns are better suited for handling lateral loads due to wind and/or earthquake. The designer may alter column size or spacing for structural reasons or change from a single-column pier to a multicolumn pier.

7.3.2 General Column Criteria

Columns should be designed so that construction is as simple and repetitious as possible. The diameter of circular columns should be a multiple of one foot. Rectangular sections should have lengths and widths that are multiples of 3 inches. Long rectangular columns are often tapered to reduce the amount of column reinforcement required for strength. Tapers should be linear for ease of construction.

Understanding the effects on long columns due to applied loads is fundamental in their design. Loads applied to the columns consist of reactions from loads applied to the superstructure and loads applied directly to the columns. For long columns, it may be advantageous to reduce the amount of reinforcement as the applied loads decrease along the column. In these cases, load combinations need to be generated at the locations where the reinforcement is reduced.

Construction Joints

Bridge Plans will show column construction joints at the top of footing or pedestal and at the bottom of crossbeam. Optional construction joints with roughened surfaces should be provided at approximately 30-foot vertical spacing.

Modes of Failure

A column subject to axial load and moment can fail in several modes. A “short” column can fail due to crushing of the concrete or to failure of the tensile reinforcement. A “long” column can fail due to elastic buckling even though, in the initial stages, stresses are well within the normal allowable range. Long column failure is normally a combination of stability and strength failure that might occur in the following sequence:

1 Axial load is applied to the column.

2. Bending moments are applied to the column, causing an eccentric deflection.
3. Axial loads act eccentrically to the new column center line producing P-Δ moments which add directly to the applied moments.

4. P-Δ moments increase the deflection of the column and lead to more eccentricity and moments.
5. The P-Δ analysis must prove the column loading and deflection converges to a state where column stresses are acceptable. Otherwise, the column is not stable and failure can be catastrophic.

Bridge vs. Building Columns

Unlike building columns, bridge columns are required to resist lateral loads through bending and shear. As a result, these columns may be required to resist relatively large applied moments while carrying nominal axial loads. In addition, columns are often shaped for appearance. This results in complicating the analysis problem with non-prismatic sections.

7.3.3 Column Design Flow Chart

The Figure 7-26 illustrates the basic steps in the column design process.




Figure 7-26

7.3.4 Slenderness Effects

This BDM section supplements and clarifies AASHTO specifications. The goal of a slenderness analysis is to estimate the additional bending moments in the columns that are developed due to axial loads acting upon a deflected structure. Two primary analysis methods exist: the moment magnifier method and the second-order analysis. The designer must decide which method to use based upon the slenderness ratio (kL_u/r) of the column(s).

Method 1: Allowed if $kL_u/r <= 100$. BDM Section 7.3.3.2 discusses the approximate moment magnifier method that is generally more conservative and easier to apply.

Method 2: Recommended by AASHTO for all situations and is mandatory for $kL_u/r > 100$. BDM Section 7.3.6 discusses a second-order structural analysis that accounts directly for the axial forces and can lead to significant economy in the final structure.

In general, tall thin columns and piles above ground are considered unbraced and larger short columns and pilings below grade are considered braced.

Braced or Unbraced Columns

In a member with loads applied at the joints, any significant deflection "side ways" indicated the member is unbraced. The usual practice is to consider the pier columns as unbraced in the transverse direction. The superstructure engages girder stops at the abutment and resists lateral sidesway due to axial loads. However, pier lateral deflections are significant and are considered unbraced. Short spanned bridges may be an exception.

Most bridge designs provide longitudinal expansion bearings at the end piers. Intermediate columns are considered unbraced because they must resist the longitudinal loading. The only time a column is braced in the longitudinal direction is when a framed bracing member does not let the column displace more than L/1500. L is the total column length. In this case, the bracing member must be designed to take all of the horizontal forces.

7.3.5 Moment Magnification Method

The moment magnification method is described in AASHTO LRFD Section 4.5.3.2.2. The following information is required.

- Column geometry and properties: E, I, L_u, and k.
- All Strength or Extreme Event loads obtained from conventional elastic analyses using appropriate stiffness and fixity assumptions and column under strength factor (ϕ).

Computations of effective length factors, k, and buckling loads, P_c, are not required for a second-order analysis, though they may be helpful in establishing the need for such an analysis. In general, if magnification factors computed using the AASHTO Specifications are found to exceed about 1.4, then a second-order analysis may yield substantial benefits.

7.3.6 Second-Order Analysis

A second-order analysis includes the influence of axial loads on the deflected structure is required under certain circumstances, and may be advisable in others. It can lead to substantial economy in the final design of many structures. The designer should consider should discuss the situation with the supervisor before proceeding with the analysis. The ACI Building Code (ACI 318 R-02, section 10.13.4.1) should be consulted when carrying out a second-order analysis.

For columns framed together, the entire frame should be analyzed as a unit. Analyzing individual columns result in overly conservative designs for some columns and non-conservative results for others. This is a result of redistribution of the lateral loads in response to the reduced stiffness of the compression members. For example, in a bridge with long, flexible columns and with short, stiff columns both integrally connected to a continuous superstructure, the stiff columns will tend to take a larger proportion of the lateral loading as additional sidesway under axial loads occurs.

A. Design Methods for a Second-Order Analysis

The preferred method for performing a second-order analysis of an entire frame or isolated single columns is uses a nonlinear finite element program, such as GTSTRUDL, with appropriate stiffness and restraint assumptions. The factored group loads are applied to the frame, including the self-weight of the columns. The model is then analyzed using the nonlinear option available in GTSTRUDL. The final design moments are obtained directly from the analysis.

P-Δ moments are added to the applied moments using an iterative process until stability is reached. The deflections should converge within 5% of the total deflection. Analysis must include the effect of the column weight; therefore, the axial dead load must be adjusted as follows:

$$P_u = P_u + {}^1/_3 \text{ (factored column weight)}.$$

B. Applying Factored Loads

For a second-order analysis, loads are applied to the structure and the analysis results in member forces and deflections. It must be recognized that a second-order analysis is non-linear and the commonly assumed principle of superposition may not be applicable. The loads applied to the structure should be the entire set of factored loads for the load group under consideration. The analysis must be repeated for each group load of interest. The problem is complicated by the fact that it is often difficult to predict in advance which load groups will govern.

For certain loadings, column moments are sensitive to the stiffness assumptions used in the analysis. For example, loads developed as a result of thermal deformations within a structure may change significantly with changes in column, beam, and foundation stiffness. Accordingly, upper and lower bounds on the stiffness should be determined and the analysis repeated using both sets to verify the governing load has been identified.

C. Member Properties

As with a conventional linear elastic frame analysis, various assumptions and simplifications must be made concerning member stiffness, connectivity, and foundation restraint. Care must be taken to use conservative values for the slenderness analysis. Reinforcement, cracking, load duration, and their variation along the members are difficult to model while foundation restraint will be modeled using soil springs.

7.4 Column Reinforcement

7.4.1 Minimum Longitudinal Reinforcement Ratio

The reinforcement ratio is the steel area divided by the gross area of the section - A_s/A_g. The maximum reinforcement ratio shall be 0.06. The minimum reinforcement ratio shall be 0.01. The ratio may be reduced to 0.005 if all loads can be carried on a reduced section with similar shape and reinforcement ratio is equal to or greater than 0.01. The column dimensions are reduced by the same ratio to obtain the similar shape. The reduced section properties are not used for design or modeling.


7.4.2 Longitudinal Splices

Column reinforcement shall not be spliced at points of maximum moment, plastic hinge locations, or in columns less than 30 feet long between the top of footing and the bottom of crossbeam. The Bridge Plans must show splice location, length, and optional weld details. The Standard Specifications cover approved mechanical splices.

All splices of No. 7 and larger bars shall be staggered. For column intermediate construction joints, the shortest staggered lap bar shall project above the joint 60 bar diameters or 20 bar diameters for welded splices. If plans indicate the splice is OPTIONAL, the Special Provisions will define the method of payment for the splice steel. Figure 7-27 shows the standard practice for staggered lap splice locations.

Longitudinal # 11 and smaller bars will use lap slices. When space is limited, #11 and smaller bars can use welded splices, an approved mechanical butt splice, or the top bar can be bent inward (deformed by double bending) to lie inside and parallel to the bars below. When the bar size exceeds #11, a welded splice or an approved mechanical butt splice is required. The smaller bars in the splice determine the type of splice required.

AASHTO requires splices to fall within the middle one-half of the column. In extremely tall columns where a 60-foot bar cannot reach the middle half, splices should not be closer than 30 feet from the columns ends.



Column Lap Splice Locations
Figure 7-27

7.4.3 Ties and Spirals

Square stirrup ties or spirals are required in all columns to resist shear forces and to maintain the column structural integrity after catastrophic forces have cracked or removed the cover. Plans should show two section views of transverse reinforcing differentiating the column ends and the typical middle sections.

Confinement Zones

The column end section will only be used for the confinement zones, where it must both provide confinement and resist shear. Spirals and cross-ties in the confinement zones are limited in size to #6 bars. Shear reinforcement can be made up of several reinforcing elements with 135° seismic hooks extending into the core. Cross-ties have a 180° hook on one end and a 90° hook on the other. The hooks should alternate both horizontally and vertically. The tie must engage the peripheral spiral or stirrup and be tied to the longitudinal reinforcement. The designer should check to make sure the 180° hook can fit between the spiral and the longitudinal bars.

In regions between confinement zones, where confinement is not required, the transverse reinforcing needs to resist the column shear.


AASHTO Shear Requirements

The area of the transverse reinforcement required to resist the column shear is defined in Article "Column Shear and Transverse Reinforcement" of the Guide Specifications and AASHTO Article "Shear." The area of transverse reinforcement required for confinement is determined from Guide Specifications Article "Spacing of Transverse Reinforcement for Confinement" for spirals and ties. The area of transverse reinforcing in the confinement zones is the larger of the two requirements. Transverse reinforcement may be provided by spirals, hoops, or cross-ties.

Spiral Reinforcement

All circular columns are to use spirals. Standard sizes for column spiral use are #4 or #5 deformed bar, $^{1}/_{2}$-inch diameter or $^{5}/_{8}$-inch diameter plain steel bar, or W20 or W31 cold drawn wire. Plans should state all three spiral options. For example, "# 4, $^{1}/_{2}$ inch diameter, or W20 spiral". To facilitate concrete placement, the minimum spiral pitch is 1 inch or $1^{1}/_{3}$ times the maximum coarse aggregate size. Terminate column spirals at the top and the bottom with a seismic hook. Specify spiral weight in the bar list based on the full height. The fabricator will provide required splices.


A rectangular column with constant width or vertical taper and spiral reinforcement is shown in Figure 7-28. The same provisions as a spirally reinforced circular column apply.



DEFORMED BAR	PLAIN STEEL BAR	COLD DRAWN WIRE	DEFORMED WIRE
#4	½"ø	W20	D20
#5	⅝"ø	W31	D31
#6	¾"ø	W44	D44

Constant and Tapered Rectangular Column Section
Seismic Zones C and D
Figure 7-28

A rectangular or tapered column with stirrups and cross-ties is shown in Figures 7-29. The maximum vertical stirrup or cross-tie spacing in confinement zones and at lap splices is 4 inches for Seismic Performance Categories C and D and 6 inches for Seismic Performance Categories A and B. The minimum vertical spacing is 2½ inches for concrete placement. Stirrup spacing layout and detailing should be based on longitudinal lap locations.



Constant and Tapered Rectangular Column Ties
Seismic Zones A and B
Figure 7-29

7.4.4 Longitudinal Development and Confinement Steel

Columns framed a footing, crossbeam, or frame must have confinement. The confinement reinforcement lengths are the same for columns of any shape. The confinement in the horizontal members starts at the end of the straight longitudinal column bars. For hooked bars, confinement starts at the beginning of the longitudinal column bar curvature. Confinement reinforcing extends into the column the maximum of the following three criteria. Extension is measured from the bottom of crossbeam or top of footing or pedestal.

1) 1/6 the clear column height
2) Maximum horizontal column dimension – Note: for wall type piers where plastic hinging occurs only along the weak axis, use the short dimension.
3) 18 inches

Crossbeams

All column longitudinal rebar shall terminate at least 3" below the top longitudinal crossbeam reinforcement. The designer shall ensure that the development length of the column longitudinal rebar is at least equal to 1.25 L_d. This development length may be modified by the applicable modification factors from AASHTO LRFD section 5.11.2.


The top of columns in crossbeam should avoid hooks. If the crossbeam is not deep enough to develop straight bars, 180° hooks generally provide less congestion. For columns on drilled shafts, hooked layouts must allow enough room for the contractor to remove casing that is the diameter of the shaft. A detail showing horizontal lower crossbeam rebar and vertical column rebar is preferred but not required.

Footings

Longitudinal reinforcement at the bottom of a column should extend into the footing and rest on the bottom mat of footing reinforcement with standard 90° hooks. Embedment must be at least 1.25 1_{dh} (1_{dh} is development length of a standard hook). This development length may be further modified by the applicable modification factors from AASHTO LRFD Section 5.11.2.

Drilled Shafts

Longitudinal column bars in drilled shafts are typically straight. For extension of column longitudinal bars into shafts, see Figure 7-30.



COLUMN & SHAFT SPIRAL OPTIONS

DEFORMED BAR AASHTO M 31 GR. 60	PLAIN STEEL BAR AASHTO M 31 GR. 60	COLD DRAWN WIRE AASHTO M 32	DEFORMED WIRE AASHTO M225	WELD DIMENSIONS S	E	LENGTH (L)
#4	½"Ø	W20	D20	¼	⅛	4
#5	⅝"Ø	W31	D31	5/16	3/16	6
#6	¾"Ø	W44	D44	⅜	3/16	6

Confinement Layout and Longitudinal Length
Figure 7-30

7.4.5 Column Hinges

The area of the hinge bars in square inches is as follows:

$$As = \frac{\frac{(P_u)}{2} + \left[\frac{P_u^2}{4} + V_u^2\right]^{1/2}}{0.85\, F_y \cos\theta}$$

Where:

P_u is the factored axial load

V_u is the factored shear load

F_y is the reinforcing yield strength (60 ksi)

θ is the angle of the hinge bar to the vertical

The development length required for the hinge bars is 1.25 times that described in AASHTO Article "Development of Flexural Reinforcement." Figure 7-32 shows some typical hinge details. Space the ties and spirals to satisfy Article "Spacing of Transverse Reinforcement for Confinement" of the Guide Specifications, AASHTO Article "Shear," or a maximum of 12 inches (6 inches if longitudinal bars are bundled). Premolded joint filler should be used to assure the required rotational capacity. There should also be a shear key at the hinge bar location.


When the hinge reinforcement is bent, additional confinement reinforcing may be necessary to take the horizontal component from the bent hinge bars. The maximum spacing of confinement reinforcing for the hinge is the smaller of that required above and the following:

$$S_{max} = \frac{A_v F_y}{\left[\frac{P_u \tan\theta}{0.85\, l_h} + \frac{V_s}{d}\right]}$$

Where:

A_v, V_s, and d are as defined in AASHTO Article "Notations" and l_h is the distance from the hinge to where the bend begins.

Continue this spacing one-quarter of the column width (in the plane perpendicular to the hinge) past the bend in the hinge bars.



Hinge Details
Figure 7-31


7.5 Abutment Design and Details

7.5.1 Abutment Types

There are five abutment types described in the following section that have been used by the Bridge and Structures Division. The representative types are intended for guidance only and may be varied to suit the requirements of the bridge being designed.

Pile Cap Abutments

Earth pressures on some pile caps are either negligible or very small (when the lateral force on each pile is less than 6 kips), and vertical dead load and live load are the major effects. The design of this type of abutment is like that of a crossbeam, and transverse bending as well as shear shall be investigated for the spans between the piles. For the analysis of the pile cap, the wheel loads should be placed for the maximum moment on the pile cap. For the analysis of the piles, the wheel loads should be placed unsymmetrically to obtain the largest pile reaction.




Pile Cap Abutment
Figure 7-32

For narrow bridges (one-lane ramps and two-lane bridges without skew) the transverse live load moment on the abutment shall be taken about the center of gravity of the pile group assuming the abutment to be a rigid beam. The maximum pile reaction from transverse effect will then be $P/N + M_t/S$, where P is the total vertical load, N is the total number of piles, M_t is the transverse moment about the centerline of abutment and S is the transverse pile modulus. This analysis is only valid if the lateral forces from earth pressure, etc. are less than 6 kips per pile and all the piles have no batter.

For wide bridges (2 lanes with skew and wider) the abutment may be assumed to act as a flexible beam on knife-edge supports. The maximum pile live load reaction from transverse loading can be obtained by assuming the abutment acts as a simple beam between piles and each wheel load (in the design lane or approach lane) is proportionally distributed to the adjacent piles (see Figure 7-33). Transverse moments and shears may be found assuming the spans between piles as semi-simply supported: i.e. maximum positive or negative moment = 0.80 times the simple beam moment. Maximum shear = simple beam shear. This analysis is valid for piles with a stiffness much less than the pile cap.

For pile caps with lateral loads greater than 6 kips, with battered piles, or for piles with a stiffness about the same magnitude as the pile cap, such as shafts, the analysis for the pile cap should be as a crossbeam, The analysis for the piles should include the lateral capacity of the pile.



Lane Placement for Maximum Live Load Reaction (Center Pile)

Figure 7-33

Stub Abutments

Stub abutments are short abutments where the distance from the girder seat to top of footing is less than approximately 4 feet, see Figure 7-34. The footing and wall can be considered as a continuous inverted T-beam. The analysis of this type abutment shall include investigation into both bending and shear stresses parallel to centerline of bearing. If the superstructure is relatively deep, earth pressure combined with longitudinal forces from the superstructure may become significant




Figure 7-34

Cantilever Abutments

If the height of the wall from the bearing seat down to the bottom of the footing exceeds the clear distance between the girder bearings, the assumed 45° lines of influence from the girder reactions will overlap, and the dead load and live load from the superstructure can be assumed equally distributed over the abutment width. The design may then be carried out on a per foot basis as described in the BDM Section 7.5.9. The primary structural action takes place normal to the abutment, and the bending moment effect parallel to the abutment may be neglected in most cases. The wall is assumed to be a cantilever member fixed at the top of the footing and subjected to axial, shear, and bending loads.





Figure 7-35

Spill-Through Abutments

The analysis of this type of abutment is similar to that of an intermediate pier,see Figure 7-36. The crossbeam shall be investigated for vertical loading as well as earth pressure and longitudinal effects transmitted from the superstructure. Columns shall be investigated for vertical loads combined with horizontal forces acting transversely and longitudinally. For earth pressure acting on rectangular columns, assume an effective column width equal to 1.5 times the actual column width. Short, stiff columns may require a hinge at the top or bottom to relieve excessive longitudinal moments.




Spill-Through Abutment

Figure 7-36

Rigid Frame Abutments

Abutments that are part of a rigid frame are generically shown in Figure 7.5.1-6. At-Rest earth pressures (EH) will apply to these structures. The abutment design should include the live load impact factor from the superstructure. However, impact shall not be included in the footing design. The rigid frame itself should be considered restrained against sidesway for live load only. AASHTO Chapter 12 addresses loading and analysis of rigid frames that are buried (box culverts).



Rigid Frame Abutment
Figure 7-37

7.5.2 Embankment at Abutments

The minimum clearances for the embankment at the front face of abutments shall be as indicated on Standard Plan Sheet H-9. At the ends of the abutment, the fill may be contained with wing walls or in the case of concrete structures, placed against the exterior girders.

7.5.3 Abutment Loading

In general, bridge abutment loading will be in accordance with AASHTO LRFD Chapter 3. The following simplifications and assumptions may be applied to the abutment design. See Section 7.5 for a force diagram of typical loads as they are applied to an abutment spread footing.

Dead load - DC

Approach slab dead load reaction taken as 2 kips/ foot of wall applied at the pavement seat.

Active earth pressure (EH) and unit weight of backfill and toe fill (EV) will be provided in a Geotechnical Report. The toe fill should be included in the analysis for overturning if it adds to overturning.

The passive earth pressure exerted by the fill in front of the abutment is usually neglected in the design. The Geotechnical Division should be contacted to determine if passive resistance might be considered for analysis of sliding stability. Passive resistance in front of footing is not dependable due to potential for erosion, scour, or future excavation in front of footing.

Live load - LL

Live load impact does not apply to the abutment. Approach slab live load reaction (without IM) applied at the pavement seat may be assumed to be 4.5 kips per foot of wall for HL-93 loading, see BDM Section 10.5 for approach slab design assumptions. Abutment footing live loads may be reduced (by approximately one axle) if one design truck is placed at the bridge abutment with an approach span. Adding the pavement seat reaction to the bearing reaction duplicates the axle load from two different design truck configurations.

If approach slabs are not provided in the bridge plans, a live load surcharge (LS) applies.

Earthquake Load - EQ

Superstructure loads will be transmitted to the substructure through bearings, girder stops or restrainers. As an alternate, the superstructure may be rigidly attached substructure.

The horizontal earth pressure load (EQ_{soil}) will be the Mononobe-Okabe (M-O)active pressure coefficient, as described in the LRFD Chapter 11, Appendix 11.1.1.1. This applies M-O as a uniform pressure to the wall with the resultant force located at 0.5H. For more information on Mononobe-Okabe and AASHTO application, see GDM Section 15.4.2.9.

Footing supported walls and abutments that are free to translate or move during a seismic event shall use Mononobe-Okabe soil pressure. The vertical acceleration, k_v, shall be set equal to 0. This also applies to portions substructure isolated from the superstructure by bearings.

Pile or shaft walls and abutments that are not free to translate or move during a seismic event shall use a horizontal acceleration of 1.5 times peak ground acceleration. The vertical acceleration shall be set equal to 0. See GDM Section 15.4.2.7 for descriptions of flexible and non-yielding walls.

Seismic inertial force of the substructure (EQ_{abut}) is the horizontal acceleration coefficient times the weight of the abutment (including footing). This force acts horizontally in the same direction as the earth pressure, at the mass centroid of the abutment. Seismic inertia force is only applied for stability and sliding analysis. EQ_{abut} shall not be used to determine the reinforcement required in the abutment.

Bearing Forces – TG Strength and Extreme Event II

For strength design, the bearing shear forces should be based on ½ of the seasonal temperature change. This force is applied in the direction that causes the worst case loading.

For extreme event II, calculate the maximum friction force (when the bearing slips) and apply in the direction that causes the worst case loading.

7.5.4 WSDOT Temporary Construction Load Cases

Case 1: Superstructure Built after Backfill at Abutment

If the superstructure is to be built after the backfill is placed at the abutments, the resulting temporary loading would be the maximum horizontal force with the minimum vertical force. During the abutment design, a load case shall be considered to check the stability and sliding of abutments after placing backfill but prior to superstructure placement. This load case is intended as a check for a temporary construction stage, and not meant to be a controlling load case that would govern the final design of the abutment and footing. This loading will generally determine the tensile reinforcement in the top of the footing heel.

If this load case check is found to be satisfactory, a note will be added to the general notes in the contract plans and the contactor will not be required to make a submittal requesting approval for early backfill placement. This load case will include a 2-foot deep soil surcharge for the backfill placement equipment (LS) as covered by the WSDOT Standard Specifications article 2-03.3(14)I.

Case 2: Wingwall Overturning

It is usually advantageous in sizing the footing to release the false work from under the wing walls after some portion of the superstructure load is applied to the abutment. A note can cover this item, when applicable, in the sequence of construction on the plans.

7.5.5 Abutment Bearings and Girder Stops

All structures shall be provided with some means of restraint against lateral displacement at the abutments due to earthquake, temperature and shrinkage, wind, earth pressure, etc. Such restraints may be in the form of concrete hinges, concrete girder stops with or without vertical elastomeric pads, or pintles in metal bearings. Other solutions are possible. Article “Connection Design Forces” of the Guide Specifications for Seismic Design of Highway Bridges describe longitudinal linkage force and hold-down devices required.

All prestressed girder bridges in Western Washington (within and west of the Cascade mountain range) shall have girder stops between all girders at abutments and intermediate piers. This policy is based on fact that the February 28, 2001 Nisqually earthquake caused significant damage to girder stops at bridges where girder stops were not provided between all girders. In cases where girder stops were cast prior to placement of girders and the 3" grout was placed after setting the girders, the 3" grout pads were severely damaged and were displaced from their original position.

Abutment Bearings

The longitudinal forces from the superstructure are normally transferred to the abutments through the bearings. The calculated longitudinal movement shall be used to determine the shear force developed by the bearing pads at the abutments. The Modulus of Elasticity of Neoprene at 70°F (21°C) shall be used for determining the shear force. However, the force transmitted through a bearing pad shall be limited to that which causes the bearing pad to slip. Normally, the maximum load transferred through a teflon sliding bearing is 6 percent and through an elastomeric bearing pad is 20 percent of the dead load reaction of the superstructure. For Extreme Event I, assume the end diaphragm is in contact with abutment wall and no load transfer through the bearings. The bearing force shall not be added to seismic earth pressure forces.

When the force transmitted through the bearing pads is very large, the designer should consider increasing the bearing pad thickness, using TFE sliding bearings and/or utilizing the flexibility of the abutment as a means of reducing the horizontal design force. When the flexibility of the abutment is considered, it is intended that a simple approximation of the abutment deformation be made.

Bearing Seats

The bearing seats shall be wide enough to accommodate the size of the bearings used with a minimum edge dimension of 3 in. and satisfy the requirements of LRFD Section 4.7.4.4. On L-abutments, the bearing seat should be sloped away from the bearings to prevent a build up or pocket of water at the bearings. The superelevation and profile grade of the structure should be considered for drainage protection. Normally, a $^1/_4$ in. drop across the width of the bearing seat is sufficient.

Girder Stop Bearings


For skewed structures with earth pressure against the end diaphragm (see Figure 9.3.2-4), the performance of girder stop bearings shall be investigated at Service Limit State. These bearings are placed vertically against the girder stop to transfer the skew component of the earth pressure to the abutment without restricting the movement of the superstructure in the direction parallel to centerline. In some cases bearing assemblies containing sliding surfaces may be necessary to accommodate large superstructure movements.

Girder Stop Design

Some type of transverse girder stop is required for all abutments in order to transfer earthquake load from the superstructure to the abutment. The girder stop shall be designed at the Extreme Limit State for the earthquake loading, any transverse earth pressure from skewed abutments, etc. Girder stops are designed using shear friction theory. The possibility of torsion combined with horizontal shear when the load does not pass through the centroid of the girder stop shall also be investigated.

Girder Stop Detail

The detail shown in Figure 7-38 may be used for bridges with no skew. Prestressed girders should be placed in final position before girder stops are cast to eliminate alignment conflicts between prestressed girders and girder stops. All girder stops should provide $^1/_8$ in clearance between the prestressed girder flange and the girder stop.



Note:

1. Girder Stops shall be constructed after placement of prestressed girders.
2. Elastomeric pads between girder and girder stops shall be placed after constructing the girder stops. The pads shall be cemented to girder stops with approved rubber cement.


Girder Stop Details
Figure 7-38

7.5.6 Abutment Expansion Joints

For structures without expansion joints, the earth pressure against the end diaphragm is transmitted through the superstructure. The compressibility of the expansion joint shall be considered in the design of the abutment for earthquake, temperature, and shrinkage when these forces increase the design load.

7.5.7 Open Joint Details

Vertical expansion joints extending from the top of footings to the top of the abutment are usually required between abutments and adjacent retaining walls to handle anticipated movements. The expansion joint is normally filled with premolded joint filler which is not water tight. There may be circumstances when this joint must be water tight; $^{1}/_{8}$ butyl rubber may be used to cover the joint. The open joint in the barrier should contain a compression seal to create a watertight joint. Figure 7-39 shows typical details that may be used. Aesthetic considerations may require that vertical expansion joints between abutments and retaining walls be omitted. This is generally possible if the retaining wall is less than 60 feet long.




Open Joint Details between Abutment and Retaining Walls

Figure 7-39

The footing beneath the joint may be monolithic or cast with a construction joint. In addition, dowel bars may be located across the footing joint parallel to the wall elements to guard against differential settlement or deflection.

On abutments with the end diaphragm cast on the superstructure, the open joints must be protected from the fill spilling through the joint. Normally, 1/8 in. butyl rubber is used to seal the openings. Figure 7.5.7-2 and Figure 7-40 show typical details using butyl rubber. Figure 7.5.7-2 is a detail for the horizontal joint between the abutment and the bottom of the end girder diaphragm. Figure 7-40 is a detail for the vertical joints between the wing wall and the end girder diaphragm. Other methods to protect the open joints must be well detailed in the plans. The Special Provision and Estimates unit can advise as to what types of joint materials would or would not require special provisions.



End Diaphragm on Girder

Figure 7-40

7.5.8 Construction Joints

To simplify construction, vertical construction joints are often necessary, particularly between the abutment and adjacent wing walls. Construction joints should also be provided between the footing and the stem of the wall. Shear keys shall be provided at construction joints between the footing and the stem, at vertical construction joints or at any construction joint that requires shear transfer. The Standard Specifications cover the size and placement of shear keys. The location of such joints shall be detailed on the plans. Construction joints with roughened surface can be used at locations (except where needed for shear transfer) to simplify construction. These should be shown on the plans and labeled “Construction Joint With Roughened Surface.” When construction joints are located in the middle of the abutment wall, a pour strip should be used for a clean joint between pours. Details of the pour strip should be shown in the plans.


7.5.9 Abutment Wall Design

When the primary structural action is parallel to the superstructure or normal to the abutment face, the wall shall be treated as a column subjected to combined axial load and bending moment. Compressive reinforcement need not be included in the design of cantilever walls, but the possibility of bending moment in the direction of the span as well as towards the backfill shall be considered. A portion of the vertical bars may be cut off where they are no longer needed for stress.

Shrinkage and Temperature Reinforcement

The AASHTO requires a minimum temperature and shrinkage steel of 0.125 sq. in. per foot of wall. This is not sufficient to limit shrinkage cracks in thick walls. A more appropriate minimum temperature and shrinkage steel is taken from the ACI-83, minimum area of reinforcing steel per foot of the wall, in both directions on each face of the wall, shall be 0.011 times the thickness of the wall (in inches), spaced at 12 inches. On abutments that are longer than 60 feet, consideration should be given to have vertical construction joints to minimize shrinkage cracks.

The minimum cross tie reinforcement in the abutment wall is as follows. #4 tie bars with 180 degree hooks, spaced at approximately 2 feet center to center vertically and at approximately 4 feet center to center horizontally shall be furnished throughout the abutment stem in all but stub abutments, see Figure 7-41.



Cross Tie Details
Figure 7-41


7.5.10 Drainage and Backfilling

Three-inch (3 in.) weep holes shall be provided in all bridge abutment walls. These shall be located 6 inches above the final ground line at about 12 feet on centers. In cases where the vertical distance between the top of the footing and the bearing seat is greater than 10 feet, additional weep holes shall be provided 6 inches above the top of the footing. No weep holes are necessary in cantilever wing walls where a wall footing is not used.

The details for gravel backfill for walls, underdrain pipe and backfill for drains shall be indicated on the plans. The gravel backfill for walls shall be provided behind all bridge abutments. The underdrain pipe and gravel backfill for drains shall be provided behind all bridge abutments except abutments on fills with a stem wall height of 5 feet or less. When retaining walls with footings are attached to the abutment, a blockout may be required for the underdrain pipe outfall. Cooperation between Bridge and the district as to the drainage requirements is needed to guarantee proper blockout locations.

Underdrain pipe and gravel backfill for drains are not necessary behind cantilever wing walls. 3 foot thickness of gravel backfill for walls behind the cantilever wing walls shall be shown in the plans.

The backfill for walls, underdrain pipe and gravel backfill for drains are not included in bridge quantities, the size of the underdrain pipe should not be shown on the plans. Figure 7-42 illustrates backfill details.



Drainage and Backfill Details
Figure 7-42

7.6 Wing/Curtain Wall at Abutments

Particular attention should be given to the horizontal reinforcing steel required at fixed corners between abutment and wing/curtain walls. Since wall deflections are zero near the abutment, curtain walls and cantilever wing walls shall assume an At-Rest soil pressure. This increased loading can normally be reduced to an Active soil pressure at a distance (from the corner), equal to the average height of the wall under design. At this distance, the wall deflections are assumed large enough to allow the active state soil pressures to be developed. For the typical abutment, wing wall moments may be assumed to distribute stress to the outer 10 foot portion of the abutment wall. See GDM Section 15.4.2.7, "Active, Passive, and At-Rest Pressures".

7.6.1 Traffic Barrier Loads

Traffic barriers should be rigidly attached to an approach slab that is cantilevered over the top of a wing/curtain wall or Structural Earth wall. The barrier collision load is applied directly to the approach slab. The yield line theory as specified in AASHTO LRFD Specifications article A13.3 is primarily for traffic barrier on bridge deck slabs and may not be applicable to traffic barrier on less rigid supports, such as retaining walls.

7.6.2 Wingwall BDM Design

The following wingwall design items should be addressed in the Plans.

A. For Strength Design of wing walls, vertical loads and moments may be distributed over 10 feet of the abutment wall and footing.

B. Footing thickness shall be not less than 1 foot 6 inches.

C. Exterior girder top flanges should be located (at the least) inside the curb line at the end pier.

D. For skewed bridges, modify the details on the traffic barrier and approach slab sheet so the expansion joint detailing agree. List appropriate manufacturers and model numbers for the expansion joint system. Generally, a 1 inch expansion joint with a 1inch open joint in the barrier is shown in the Plans, unless the bridge expansion joint design dictates otherwise.

7.6.3 Wing wall Detailing

All wing wall reinforcement should be a vertical grid and not follow a tapered bottom of wall. This allows for the steel to be placed in two layers that fits better with abutment reinforcing. Existing MicroGDS wing wall sheets conform to the LFD specifications. For consistency in design with the other bridge components, these wing walls sheets must be re-designed in accordance with the requirements of the AASHTO LRFD Specifications.


7.7 Footing Design

7.7.1 General Footing Criteria

The provisions given in this section pertain to both spread footings and pile supported footings.

Minimum Cover and Footing Depth


Footings shall normally be rectangular in plan for both square and skewed bridges. The Geotechnical Report may specify a minimum footing depth in order to assure adequate bearing pressure. Stream crossings may require additional cover depth as protection against scour. The Hydraulic Section should be consulted on this matter. Footings set too low result in large increases in cost. The end slope on the bridge approach fill is usually set at the preliminary plan stage but affects the depth of footings placed in the fill. Figure 7-43 illustrates footing criteria when setting footing elevations.



Guidelines for Footing Cover and Depth
Figure 7-43

Pedestals

A pedestal is sometimes used as an extension of the footing in order to provide additional depth for shear near the column. Its purpose is to provide adequate structural depth while saving concrete. For proportions of pedestals, see Figure 7-44. Since additional forming is required to construct pedestals, careful thought must be given to the trade off between the cost of the extra forming involved and the cost of additional footing concrete. Also, additional foundation depth may be needed for footing cover. Whenever a pedestal is used, the plans shall note that a construction joint will be permitted between the pedestal and the footing. This construction joint should be indicated as a construction joint with roughened surface.



Pedestal Dimensions
Figure 7-44

7.7.2 Loads and Load Factors

The following Table 7-45 is a general application of minimum and maximum load factors as they apply to a generic footing design. Footing design must select the maximum or minimum Load Factors for various modes of failure for the Strength and Extreme Event Limit States.

The dead load includes the load due to structural components and non-structural attachments (DC), and the dead load of wearing surfaces and utilities (DW). The live load (LL) does not include vehicular dynamic load allowance (IM).

Designers are to note, if column design uses magnified moments, then footing design must use magnified column moments.

Sliding and Overturning, e_O	**Bearing Stress (e_C, s_V)**
$LL_{min} = 0$	LL_{max}
DC_{max}, DW_{max} for causing forces, DC_{min}, DW_{min} for resisting forces	DC_{max}, DW_{max} for causing forces, DC_{min}, DW_{min} for resisting forces
EV_{min}	EV_{max}
EH_{max}	EH_{max}
LS	LS

Load Factors
Table 7-45

7.7.3 Geotechnical Report Summary

The Geotechnical Branch will evaluate overall bridge site stability. Slope stability normally applies to steep embankments at the abutment. If stability is in question, a maximum service limit state load will be specified in the report. Bridge design will determine the maximum total service load applied to the embankment. The total load must be less than the load specified in the Geotechnical Report.

Based on the foundations required in the Preliminary Plan and structural information available at this stage, the Report provides the following geotechnical engineering results. For all design limit states, the total factored footing load must be less than factored resistance.

Plan Detailing

The Bridge Plans shall include the nominal bearing resistance in the General Notes as shown in Figure 7-46. This information is included in the Plans for future reference by the Bridge Office.

Pier	Strength and Extreme (q_n)	Service (q_{serv})
1	== KSF	== KSF
2	== KSF	== KSF

Figure 7-46

Bearing Capacity - Service, Strength and Extreme Limit States

The unfactored bearing capacity (q_n) may be increased or reduced based on previous experience for the given soils. The Geotechnical Report will contain the following information:

- Unfactored bearing capacity (q_n) for anticipated effective footing widths, which is the same for the strength and extreme event limit states
- Resistance factor for strength limit state (ϕ_b).
- Resistance factor for the extreme event limit state (ϕ_b) is 1.0
- Service bearing capacity (q_{ser}) and amount of assumed settlement
- Embedment depth requirements or footing elevations to obtain the recommended q_n

Sliding Capacity - Strength and Extreme Limit States

The Geotechnical Report will contain the following information to determine earth loads and the factored sliding resistance (Q_R). $Q_R = \phi \quad Q_n = \phi$

- Resistance factor for strength limit state (ϕ_τ)
- Soil parameters ϕ_{soil}, K_a, and γ for calculating Q_τ and active force (EH) behind abutment footings
- If passive earth pressure (Q_{ep}) is allowed at a footing,

  Soil parameters of ϕ_{soil}, K_p, γ and depth of soil in front of footing

  Resistance factor ϕ_{ep} for strength

Foundation Springs - Extreme Limit State


When a structural evaluation of soil response is required for a bridge analysis, the Geotechnical Branch will determine foundation soil/rock shear modulus and Poissons ratio (G and μ). These values will typically be determined for shear strain levels of 2% to 0.2%, which are typical strain levels for large magnitude earthquakes.

7.7.4 Spread Footing Structural Design

The following BDM Section is oriented towards abutment spread footing design. Spread footing designs for intermediate piers or other applications use the same concepts with the appropriate structural analysis. Structural designers should complete all design checks before consulting a problem with the geotechnical engineer. There may be several problem criteria that should be addressed in the solution.


7.7.4.A Abutment Spread Footing Force Diagram

Figures 7-47 and 7-48 diagram the forces that act on abutment footings. Each limit state design check will require calculation of a reaction (R) and the location (X_o) or eccentricity (e_o). The ultimate soil passive resistance (Q_{ep}) at the toe is determined by the geotechnical engineer and is project specific.



Cantilever (End Diaphragm) Abutment Force Diagram

Figure 7-47



L-Abutment Force Diagram

Figure 7-48

7.7.4.B Bearing Stress

For geotechnical and structural footings design, the bearing stress calculation assumes a uniform bearing pressure distribution. For footing designs on rock, the bearing stress is based on a triangular or trapezoidal bearing pressure distribution. The procedure to calculate bearing stress is summarized in the following outline. See Abutment Spread Footing Force Diagrams for typical loads and eccentricity.

Step 1: Calculate the Resultant force (R_{str}), location (Xo_{str}) and eccentricity for Strength (e_{str}).

Xo_{str} = (factored moments about the footing base)/(factored vertical loads)

Step 2A: For Footings on Soil:

Calculate the maximum soil stress (σ_{str}) based on a uniform pressure distribution. Note that this calculation method applies in both directions for biaxially loaded footings. See AASHTO 10.6.3.1.5 for guidance on biaxial loading. The maximum footing pressure on soil with a uniform distribution is:

σ_{str} = R/B′ = R/2Xo = R/(B-2e), where B′ is the effective footing width.

Step 2B: For Footings on Rock:

If the reaction is outside the middle 1/3 of the base, use a triangular distribution.

σ_{str} max = 2R/3 Xo, where "R" is the factored limit state Reaction.

If the reaction is within the middle 1/3 of the base, use a trapezoidal distribution.


σ_{str} max = R/B (1+ 6 e / B^2)

In addition, WSDOT limits the maximum stress (P/A) applied to rock due to vertical loads only. This is because the rock stiffness approaches infinity relative to the footing concrete. The maximum width of uniform stress is limited to C+2D as shown in Figure 7-49.

Step 3: Compare the factored bearing stress (σ_{str}) to the factored bearing capacity ($\phi_{bc}q_n$) of the soil or rock. The factored bearing stress must be less than or equal to the factored bearing capacity.

$\sigma_{str} \leq \phi_{bc}q_n$

Step 4: Repeat steps 1 thru 3 for the Extreme Event limit state. Calculate Xo_{ext}, e_{ext}, and σ_{ext} using Extreme factors and compare the factored stress to the factored bearing ($\phi_b q_n$).



Footings on Rock
Figure 7-49

7.7.4.C Failure By Sliding

The factored sliding resistance (Q_R) is comprised of a frictional component ($\phi_\tau Q_\tau$) and the Geotechnical Branch may allow a passive earth pressure component ($\phi_{ep} Q_{ep}$). The Structural Engineer will calculate Q_R based on the soil properties specified in the Geotechnical Report. The frictional component acts along the base of the footing, and the passive component acts on the vertical face of a buried footing element. The factored sliding resistance should be greater than or equal to the factored horizontal applied loads.

$Q_R = \phi_\tau Q_\tau + \phi_{ep} Q_{ep}$

The Strength Limit State ϕ_τ and ϕ_{ep} are provided in the Geotechnical Report or AASHTO 10.5.5-1. The Extreme Event Limit State ϕ_τ and ϕ_{ep} are generally equal to 1.0.

Q_τ = (R) tan δ

δ = friction angle between the footing base and the soil

δ = tan ϕ for cast-in-place concrete against soil

δ = (0.8)tan ϕ for precast concrete

R = Minimum Strength and Extreme factors are used to calculate R

ϕ = angle of internal friction for soil

7.7.4.D Overturning Stability

Calculate the locations of the overturning reaction (R) for strength and extreme limit states. Minimum load factors are applied to forces and moments resisting overturning. Maximum load factors are applied to forces and moments causing overturning. Note that for footings subjected to biaxial loading, the following eccentricity requirements apply in both directions.

Strength limit state requires R to be located in the middle 1/2 of the footing plan dimensions for soil and the middle 3/4 of the footing dimensions for rock. See AASHTO 10.6.3.1.5.

Extreme event II limit state (EQ load factor = 0) requires resultant force to be located in the middle 2/3 of the footing plan dimensions for soil and rock.

7.7.4.E Footing Settlement

The service limit state bearing capacity (q_{ser}) will be a settlement-limited value, typically 1 inch.

Bearing Stress = $\sigma_{ser} < \phi q_{ser}$ = Factored nominal bearing

Where, q_{ser} is the unfactored service limit state bearing capacity and ϕ is the service resistance factor. In general, the resistance factor (ϕ) will be equal to 1.0.

For immediate settlement (not time dependent), both permanent dead load and live load should be considered for sizing footings for the service limit state. For long-term settlement (on clays), only the permanent dead loads should be considered.

If the structural analysis yields a bearing stress (σ_{ser}) greater than the bearing capacity, then the footing must be re-evaluated. The first step would be to increase the footing size to meet bearing capacity. If this leads to a solution, recheck layout criteria and inform the geotechnical engineer the footing size has increased. If the footing size cannot be increased, consult the geotechnical engineer for other solutions.

7.7.4.F Concrete Design

Footing design will be in accordance with AASHTO Section 5.13.3 for footings and the general concrete design of AASHTO Chapter 5. The following Figure 7-50 illustrates the modes of failure checked in the footing concrete design.




Figure 7-50

Footing Thickness and Shear

The minimum footing thickness shall be 1 foot 6 inches. The minimum plan dimension shall be 4 feet 0 inches. Footing thickness may be governed by the development length of the column dowels, or by concrete shear requirements (with or without reinforcement). If concrete shear governs the thickness, it is the Engineer's judgment, based on economics, as to whether to use a thick footing unreinforced for shear or a thinner footing with shear reinforcement. Generally, shear reinforcement should be avoided but not at excessive cost in concrete, excavation, and shoring requirements. Where stirrups are required, place the first stirrup at d/2 from the face of the column or pedestal. For large footings, consider discontinuing the stirrups at the point where $v_u = v_c$.

Footing Force Distribution

The maximum shear stress in the footing concrete shall be determined based on a triangular or trapezoidal bearing pressure distribution, see AASHTO 5.13.3.6. This is the same pressure distribution as for footing on rock, see BDM Section 7.7.4B.

Vertical Reinforcement (Column or Wall)

Vertical reinforcement shall be developed into the footing to adequately transfer loads to the footing. Vertical rebar will be bent 90^{o} and extend to the top of the bottom mat of footing reinforcement. This facilitates placement and minimizes footing thickness. Bars in tension shall be developed using 1.25 Ld. Bars in compression shall develop a length of 1.25 Ld, prior to the bend. Where bars are not fully stressed, lengths may be reduced in proportion, but shall not be less than 3/4 Ld.

The concrete strength used to compute development length of the bar in the footing shall be the strength of the concrete in the footing. The concrete strength to be used to compute the section strength at the interface between footing and a column concrete shall be that of the column concrete. This is allowed because of the confinement effect of the wider footing.

Bottom Reinforcement

Concrete design will be in accordance with AASHTO. Reinforcement shall not be less than #6 bars at 12-inch centers to account for uneven soil conditions and shrinkage stresses.


Top Reinforcement

Top reinforcement shall be used in any case where tension forces in the top of the footing are developed. Where columns and bearing walls are connected to the superstructure, sufficient reinforcement shall be provided in the tops of footings to carry the weight of the footing and overburden assuming zero pressure under the footing. This is the uplift earthquake condition described under "Superstructure Loads." This assumes that the strength of the connection to the superstructure will carry such load. Where the connection to the superstructure will not support the weight of the substructure and overburden, the strength of the connection may be used as the limiting value for determining top reinforcement. For these conditions, the AASHTO requirement for minimum percentage of reinforcement will be waived. Regardless of whether or not the columns and bearing walls are connected to the superstructure, a mat of reinforcement shall normally be provided at the tops of footings. On short stub abutment walls (4 feet from girder seat to top of footing), these bars may be omitted. In this case, any tension at the top of the footing, due to the weight of the small overburden, must be taken by the concrete in tension.

Top reinforcement for column or bearing wall footings designed for two-way action shall not be less than #6 bars at 12-inch centers, in each direction while top reinforcement for bearing wall footings designed for one-way action shall not be less than #5 bars at 12-inch centers in each direction.

7.7.5 Footing Concrete Design on Pile Supports


The minimum footing thickness shall be 2 feet 0 inches. The minimum plan dimension shall be 4 feet 0 inches. Distance from center of pile to footing edge for all pile types shall be a maximum of 1.5 times the pile diameter or 1 foot 6 inches. Footing thickness may be governed by the development length of the column dowels, or by concrete shear requirements. The use of strut and tie modeling is recommended for the design of all pile caps and pile footings. Figure 7-51 identifies the modes of failure that should be investigated for general pile cap/footing design.



Pile Footing Modes of Failure
Figure 7-51

7.7.5.A Pile Embedment, Clearance, and Rebar Mat Location


All piles shall have an embedment in the concrete sufficient to resist moment, shear, and axial loads. Steel H-Pile or timber piles are embedded a minimum of 12 inches into the concrete where a moment or tension connection is not required. Cast-in-place concrete piles with reinforcing extending into footings are embedded a minimum of 6 inches. The clearance is 1½ inches between the bottom mat of footing reinforcement and the top of pile. See Figure 7.7.5.1.1 for the minimum pile clearance to the edge of footing.



Pile Embedment and Reinforcing Placement
Figure 7-52

7.7.5.B Pile Pullout and Details

Piles subject to uplifting forces must be adequately detailed to connect the footing to the pile. Figure 7.7.5.1.2 details extended reinforcement welded to the pile. Skin friction due to the bond between pile and footing is not allowed in the design of the connection.



Sample Steel Pile Anchorage
Figure 7-53

7.7.5.C Concrete Design

In determining the proportion of pile load to be used for calculation of shear stress on the footing, any pile with its center 6 inches or more outside the critical section shall be taken as fully acting on that section. Any pile with its center 6 inches or more inside the critical section shall be taken as not acting for that section. For locations in between, the pile load acting shall be proportioned between these two extremes. For calculation of moment on the footing, any pile with its center outside of the section shall be taken at full load. Any pile with its center inside of the section shall not be assumed to contribute to that amount.

7.8 Drilled Shafts

7.8.1 Drilled Shaft Design

The factored axial resistance of the drilled shaft (R) is generally composed of two parts: the nominal top resistance (R_p) and the nominal side friction resistance (R_s). The general formula is as follows, where φ is the limit state resistance factor.

$$R = \varphi_p R_p + \varphi_s R_s$$

The total factored shaft loading must be less than the factored axial resistance. R_p and R_s are treated as independent quantities although research has shown that the tip (or bearing) resistance and side resistance have some independence. The factored nominal tip and side resistance will be stated in the Geotechnical Report for the bridge.

Plan Detailing

The Bridge Plans shall include the nominal side and tip resistance for the service limit state in the General Notes, as show in Figure 7-54. This information is included in the Plans for reference by the Contractor. If the shaft has significant bearing resistance, the contractor shall take extra care to clean the bottom of the shaft before placing the shaft concrete.

Pier	Nominal Side Resistance (R_s)	Nominal Tip Resistance (R_p)
1	== KIPS	== KIPS
2	== KIPS	== KIPS

Figure 7-54

A. **Reinforcing and Concrete Strength**

Due to soil conditions and construction methods, concrete may not be placed in the dry. A reduction in concrete strength used for design shall be as follows:

1. Shaft diameter 4 feet 0 inches or less – assumed concrete compressive strength shall be 0.85 fc′. Concrete placed by tremie method is confined to small area and segregation is reduced. Cover requirement – 3-inch minimum to 6-inch maximum.
2. For shaft diameters of 4 feet 6 inches or more, use 0.6fc′. Cover requirement are 6-inch minimum to 12-inch maximum.
3. Reinforcing shall be detailed to minimize congestion. Longitudinal reinforcing extending into footing should be straight. If hooked, detail so that casing can be removed while placing concrete. Percentage of reinforcing shall be 0.5 percent minimum and 4 percent maximum. Use of two concentric circular cages shall be avoided.

B. **Design of Drilled Shafts**

The analysis will provide the design loading for the shaft concrete and reinforcement design. The following guidelines apply.

1. Column Assumptions: Normally, the soil surrounding a foundation element provides bracing against a buckling failure. For this reason, the drilled shaft can be designed as a short column when the shaft is entirely below the groundline. When the shaft extends above the ground a check for slenderness may apply. The effects of scour shall be considered in the analysis.

2. Axial Load, Bending Moment, and Shear: The axial load along the shaft varies due to the side friction. It is considered conservative, however, to design the shaft for the full axial load plus the maximum moment. The entire shaft normally is then reinforced for this axial load and moment. Longitudinal reinforcing should not be less than 0.5 percent of the area of concrete. Design shaft for axial load bending movement and shear as a column.

7.8.2 Lateral Load Analysis

Shafts must be analyzed in accordance with BDM Section 7.2, Foundation Modeling. In general, FEM bridge model analysis iteratively matches deflections and load between a non-linear soil/ structure interaction analysis.

In general, only Service Limit and EQ loading are used for the seismic bridge analysis to establish load distribution in the structure. The results then are factored for the design of the bridge components. Note, if Strength Limit state controls the design, then EQ loading would not apply.

In some cases, the depth required for shaft stability based on a lateral analysis may control the depth of shaft, rather than bearing capacity or uplift. Cases such as bridge sites with soft or liquefiable soils. Shaft or pile stability will require engineering judgment and experience.

A. For seismically controlled designs, the bigger (stiffer) the shaft the more movement can be tolerated at the shaft tip. A seismic analysis will predict the maximum deflections and stresses and the engineer must determine a safe shaft depth to survive the event. Small pile fixity generally refers to the point of fixity for column design, or the first inflection point when observing deflection. The pile tip for small shafts/piles, one to two feet in diameter, should be determined at the location of approximately the second point of inflection. An acceptable movement at the tip during an Extreme Event has yet to be determined. In general, the smaller the better. Since these shafts/piles are relatively flexible in the soil, it is possible to have pile tips at the 2nd point of inflection with little or no movement (drift) and not have deep tip elevations that are costly.

B. Medium sized shafts, three to eight feet in diameter, tipping the shafts should consider an elevation near the midpoint of the 1st and 2nd inflection points. An acceptable movement at the tip during an Extreme Event has yet to be determined. In general, past practice has been the smaller the better based on the experience of small flexible piles.

C. Large shafts, greater than 10-foot diameter, will transfer significantly more stresses to the soil and much deeper in the soil than flexible piles. Tipping for large shafts should consider an elevation between the midpoint and near the quarter point of the 1st and 2nd inflections. An acceptable movement at the tip during an Extreme Event has yet to be determined.

The static parameters represent the soil behavior for short-term transient loads such as wind, ice, temperature, and vessel impact. For earthquake loads, the seismic and static soil properties will be the same if the soils present have a stiffness which does not degrade with time during shaking.

If liquefiable soils are present, both static and liquefied soil properties are provided in the Geotechnical Report. Often, the highest acceleration the bridge sees is in the first cycles of the earthquake, and liquefaction tends to occur toward the middle or end of the earthquake. Therefore, early in the earthquake, loads are high, soil-structure stiffness is high, and deflections are low. Later in the earthquake, the soil-structure stiffness is lower and deflections higher.

If liquefaction can occur, the bridge should be analyzed twice. The first analysis uses the static soil conditions, which yields higher moment and shear to design the shaft (and column). The second analysis uses the liquefied soils to evaluate the bridge Extreme Event deflections. The intent here is to bracket the structure response. The designer will have to determine the acceptable maximum lateral deflection.

7.9 Piles and Piling

Plan Pile Resistance

The Bridge Plan General Notes shall denote pile size and Nominal Driving Resistance (or Ultimate Bearing Capacity) in Tons. This information is used by the contractor to determine the pile thickness and size the hammer to drive the piles. The resistance for several piers may be presented a table as shown in Figure 7-55. The Nominal Driving Resistance (R_{ndr}), as stated in the Geotechnical Report, will be shown in the Plans as "Ultimate Bearing Capacity". See WSDOT GDM, Section 8.12 for Geotechnical Design of the pile resistance. If overdriving the piles is required to reach the minimum tip elevation, see BDM 9.7.6, the estimated amount of overdriving (Tons) will be described in the Bridge Special Provisions.

PIER	ULTIMATE BEARING CAPACITY (Nominal Driving Resistance, R_{ndr})
1	== Tons
2	== Tons

Figure 7-55

The total factored pile axial loading must be less than ϕR_n for the pile design. Designers should note that the driving resistance might be greater than the design loading for liquefied soil conditions. This is not an overdriving condition. This is due to the resistance liquefied soils being ignored for design, but included in the driving criteria to place the piles.

7.9.1 Pile Types

This section of the BDM describes the piling used by the Bridge Office and their applications. Steel sheet piles are normally used for cofferdam and shoring and cribbing, but are usually not made a part of permanent construction. Piles should not be used where spread footings can be used at allowable basic bearing pressures of approximately 2 to 3 ton/sq. ft. or greater. Where heavy scour conditions may occur, pile foundations should be considered in lieu of spread footings. Where large amounts of excavation may be necessary to place a spread footing, pile support may be more economical.

A. Precast and Prestressed Concrete and Cast-In-Place Concrete Piles

Precast and prestressed concrete piles are no longer used for WSDOT bridge design. However, Standard Plans are available for prestressed piles. Precast Prestressed Concrete piles are hexagonal, square, or circular in cross-section and are prestressed to allow longer handling lengths. Again, close length determination at time of driving the test pile is important. Precast prestressed concrete piles are usually specified in accordance with Standard Plans such as Sheet E-4 for 13-inch diameter piles and Sheet E-4a for 16- and 18-inch diameter piles.

Cast-in-Place Concrete (CIP) Piles utilize driven steel pipe casings, which are then filled with concrete. The bottom of the casing is capped with a suitable flat plate before driving. The Geotechnical Division may specify special tips when difficult driving is expected.

Steel Pipe Casing

The Geotechnical Division will determine the minimum wall thickness based on driving conditions. The design for driving shall be based on a steel shell thickness of 1/4 inch for piles less than 14 inches in diameter, 3/8 inches for piles 14 to 18 inches in diameter, and 1/2 inch for larger piles.

Steel casing for cast-in-place piling should be designated by nominal size, not inside diameter for 24 inch and smaller pile casings. Both ASTM A53 and A252 pipe is purchased by nominal size (outside diameter) and wall thickness, see specification for dimensions. These are the commonly supplied pipe specifications. A pipe thickness should not be stated in the plans. The Standard Specifications for pile driving states the contractor shall determine the pile casing thickness required for driving and increase minimum thickness specified as necessary."

CIP Pile Design

Class 4000 P Concrete shall be specified for inside the pile. The top 10 feet of concrete in the pile is to be vibrated.

For the pile stiffness and foundation modeling, the full cross section of the steel shell minus $^{1}/_{16}$ inch for corrosion will be used in determining the pile stiffness and foundation modeling. This thickness can also be considered as confinement reinforcement for the internal cage except at pile/footing interface. The moment of inertia of the pile is computed by adding the components

$$I\ pile_{conc} = I_{conc} + (n)(I_{shell}) + (n)(I_{reinf})$$

For pile structural design, the reinforcement alone shall be sufficient to resist the total moment throughout the length of pile without considering the shell. The minimum reinforcement shall be 0.5 percent of the gross concrete area for Seismic Performance Categories A and B, and 0.75 percent for Category C as required per AASHTO Seismic Guideline Specifications, Chapter 6. No less than four No. 5 bars shall be used. The reinforcement shall extend above the pile into the footing a distance equal to 1.25 1d (tension).

A steel reinforcing cage shall be used to tie the pile to the cap/footing. The vertical steel reinforcing bars, above the top of the pile, shall be tied together with closely spaced hoops or spirals as required by the seismic guide specifications. Inside the pile, No. 4 hoops at 12-inch centers is minimum required for Category B and 9-inch centers for Category C.

B. Steel H Piles

Steel piles are normally used where there are hard layers that must be penetrated in order to reach an adequate point bearing stratum. Steel stress is generally limited to 9.0 ksi (working stress) on the tip. H piling can act efficiently as friction piling due to its large surface area. Do not use steel H piling where the soil consists of only moderately dense material. In such conditions, it may be difficult to develop the friction capacity of the H piles and excessive pile length may result. The bridge layout will denote steel piles with capacity and size, e.g., steel pile 70-ton HP 12 x 53.


C. Timber Piles

Timber piles have the lowest cost per foot of any of the pile types. Timber piles may be untreated or treated. Untreated piles are used only for temporary applications or where the entire pile will be permanently below the water line. Composite piles, treated and untreated, may be used if the pile length is long and a splice will be required. Where composite piles are used, the splice must be located below the permanent water table. If doubt exists as to the location of the permanent water table, treated timber piles shall be used.

Where dense material exists, consideration should be given to allowing jetting (with loss of uplift capacity), use of shoes, or use of other pile types.

7.9.2 Pile Design Flow Chart

Figure 7-56 provides a flowchart which illustrates the design process and the interaction between the structural and geotechnical engineers needed for pile foundation design. **Once the pile analysis and design are completed in the Bridge and Structures Office, the Geotechnical Division is to be contacted for final review and comment.**



Design Flowchart for Pile Foundation Design
Figure 7-56


7.9.3 General Pile Design

The objective of pile structural design is to determine the pile group geometry, minimum tip elevations and estimated pile quantity. The bridge structural design may include characterization of the pile foundation for purposes of modeling the overall structure, especially for seismic design.

Pile Spacing

Generalized pile spacing is shown in Section 9.6 for each type of pile. Be aware that the action of the pile group for friction piles may be quite different than for point bearing piles, in that the group can fail as a unit at a lower load than the summation of the individual pile capacities. This effect is accounted for in Chapter 4, "Modeling Pile Foundation."

For point bearing piles, the spacing is a minimum of 3 feet, except for timber piles where the minimum spacing is 3 feet 3 inches. Where the load distribution of the pile is partially point bearing and partially friction, consider using an intermediate spacing value.



Footing Pile Modes of Failure
Figure 7-57

Column Action

Consideration shall be given to the pile acting as a column. Piles that support footings or pile caps that are not in contact with the soil below them must be treated as columns subject to bending and axial load. Piles that extend above the ground surface shall be analyzed by the appropriate column design procedures. Piles that are driven through very weak soils should be designed for reduced lateral support, using information from the Geotechnical Division as appropriate. AASHTO 10.7.4.2 may be used to estimate the column length for buckling. Piles driven through firm material normally can be considered fully supported for column action (buckling not critical) below the ground.

Friction vs. Point Bearing Piles

Pile axial resistance may be friction, point bearing, or a combination of both. In the absence of a soil layer that can offer adequate resistance to develop full point bearing, normally the pile shall be considered to be acting as a friction pile. The Geotechnical Report will describe the type soil resistance that supports the pile load. The soil conditions that support the pile may affect several structural properties, such as: rate of pile elastic shortening, effects of group action and hence spacing, pile column stability, and ability to resist lateral forces.

Pile Splices

Pile splices shall be avoided where possible. If splices may be required in timber piling, a splice shall be detailed on the plans. Splices between treated and untreated timber shall always be located below the permanent water line. Concrete pile splices shall have the same strength as unspliced piles.

Uplift Capacity

The ability of a pile to carry uplift loads is highly dependent upon the strata into which it is driven. When uplift is included in pile analysis, the following items apply:

1. The pile must be a friction pile and over 10 feet in length. Whenever uplift is to be used in the pile design, the Foundation Engineer shall be consulted. Uplift will not be used for pile design when piles are full point bearing piles.
2. In all cases of uplift, the connection between the pile and the footing must be carefully designed and detailed. The bond between the pile and the seal may be considered as contributing to the uplift resistance. This bond value shall be limited to 10 psi. The pile must be adequate to carry tension throughout its length. For example, a timber pile with a splice sleeve could not be used.
3. Preboring, jetting, or spudding must not be used to aid in driving the pile and must be so noted in the plans or special provisions.

7.9.4 Pile Axial Design

The Geotechnical Report will provide the nominal axial resistance (R_n) as either a dynamic or static resistance. The factored pile load ($P_{u\ pile}$) for Strength and Extreme limit states must be less than the limit state resistance φR_n specified in the Geotechnical Report.

Axial Analysis

Generally, pile groups are assumed to act as a rigid body with rotations about the centroidal axis for strength design. Factored loads are applied to the pile cap and the pile ($P_{u\ pile}$) is determined as follows:

$$(P_{u\ pile}) = (P_{u\ pile\ group})/N + M_{u\ group}\, C/I_{group} + \varphi DD$$

where,

$M_{U\ group}$ = Factored moment applied to the pile group. This includes eccentric LL, DC, centrifugal force (CE), etc. Generally, the dynamic load allowance (IM) does not apply.

C = Distance from the centroid of the pile group to the center of the pile under consideration

I_{group} = Moment of inertia of the pile group

N = Number of piles in the pile group

$P_{U\ pile\ group}$ = Factored axial load to the pile group

φDD = Factored Down Drag forces specified in Geotechnical Report

Determine the number of piles required in the pile group such that the factored load in any pile in the pile group is not greater than the factored resistance. The pile weight will be normally neglected but may be added to the foundation dead load.

Extreme Event Design

A foundation spring support is usually required to represent the pile group in a dynamic bridge model. See BDM Section 7.2, Foundation Modeling for a method to calculate the axial or other matrix spring coefficients.

Block Failure

For the strength and extreme event limit states, if the soil is characterized as cohesive, the pile group capacity should also be checked for the potential for a "block" failure, AASHTO 10.7.3.10 applies. Compare the factored loads for each limit state to the factored block resistance. If a block failure appears likely, increase the group size so that a block failure is prevented.

Pile Uplift

Piles may be designed for uplift if specified in the Geotechnical Report.

Downdrag force

Downdrag forces are treated as load to the pile when designing for axial capacity. Do not include downdrag forces in the structural analysis of the bridge. Geotechnical Design of Down Drag loads are described in WSDOT GDM, Section 8.6.2.

7.9.5 Pile Lateral Design

The strength limit state for lateral resistance is only structural, though the determination of pile fixity is the result of soil-structure interaction. A failure of the soil does not occur; the soil will continue to displace at constant or slightly increasing resistance. Failure occurs when the pile reaches the structural limit state and this limit state is reached, in the general case, when the nominal combined bending, shear, and axial resistance is reached.

Piles resist horizontal forces by a combination of internal strength and the passive pressure resistance of the surrounding soil. The capacity of the pile to carry horizontal loads should be investigated using a soil/structural analysis. For more information on modeling individual piles or pile groups, see BDM Section 7.2, Foundation Modeling.

Battered Piles

Battered piles are not recommended to resist seismic lateral loads. The lateral force that can be resisted by a single battered pile is limited by a function of applied vertical dead load, and this must not be exceeded. Maximum batter shall be $4^1/_2$:12. Piles with batters in excess of this become very difficult to drive and the bearing values become difficult to predict. Ensure that battered piling do not intersect piling from adjacent footings within the maximum length of the piles.

7.9.6 Pile Tip Elevations and Quantities

Pile length quantities provided to PS&E are based on the estimated tip elevation given in the Geotechnical Report or the depth required for design whichever is greater. If the estimated tip elevation given in the Geotechnical Report is greater than the design tip elevation, overdriving the pile will be required. The Geotechnical Engineer should be contacted to evaluate driving conditions. A special provision to the Standard Construction Specifications is normally required to alert the contractor of the additional costs to drive these piles.

Minimum pile tip elevations provided in the Geotechnical Report may need to be adjusted to lower elevations depending on the results of the lateral, axial, and uplift analysis. This would become the minimum pile tip elevation requirement for the contract specifications. If adjustment in the minimum tip elevations is necessary, or if the pile diameter needed is different than what was assumed for the Geotechnical Report, the Geotechnical Division MUST be informed so that pile drivability can be re-evaluated. See BDM Section 9.8 for more information on tipping piles.

Note that lateral loading and uplift requirements may influence (possibly increase) the number of piles required in the group if the capacity available at a reasonable minimum tip elevation is not adequate. This will depend on the soil conditions and the loading requirements. For example, if the upper soil is very soft or will liquefy, making the minimum tip elevation deeper is unlikely to improve the lateral response of the piles enough to be adequate. Adding more piles to the group or using a larger pile diameter to increase the pile stiffness may be the only solution.

Chapter 8 Walls & Buried Structures

8.4 Retaining Walls 8-1
8.4.1 General 8-1
8.4.2 Common Types of Walls 8-1
8.4.3 Design 8-3
8.4.4 Miscellaneous Items 8-6
8.5 Miscellaneous Underground Structures 8-10
8.5.1 General 8-10
8.5.2 Design 8-10
8.5.3 References 8-13

Appendix A-8

Figure 8-A-1 SEW Wall Elevation 8-A-1
Figure 8-A-2 SEW Wall Section 8-A-2
Figure 8-A-3 Soil Nail Layout 8-A-3
Figure 8-A-4 Soil Nail Wall Fascia Panel Details 8-A-4
Figure 8-A-5 Soil Nail Wall Section 8-A-5
Figure 8-A-6 Cable Fence 8-A-6
Figure 8-A-7 Cable Fence - Top Mount 8-A-7
Figure 8-A-8 Soldier Pile/Tieback Wall Elevation 8-A-8
Figure 8-A-9 Soldier Pile/Tieback Wall Details 1 of 2 ..... 8-A-9
Figure 8-A-10 Soldier Pile/Tieback Wall Details 2 of 2 ..... 8-A-10
Figure 8-A-11 Soldier Pile/Tieback Wall Fascia Panel Details 8-A-11
Figure 8-A-12 Soldier Pile/Tieback Wall Permanent Ground Anchor Details 8-A-12
Figure 8-A-13 Pre-approved Proprietary Wall Systems 8-A-13

8.4 Retaining Walls

8.4.1 General

A retaining wall is a structure built to provide lateral support for a mass of earth or other material where a grade separation is required. Retaining walls depend either on their own weight, their own weight plus the additional weight of laterally supported material, or on a tieback system for their stability. Additional information is provided in Chapter 15 of the WSDOT Geotechnical Design Manual (GDM).

Standard designs for reinforced concrete cantilevered retaining walls, noise barrier walls (precast concrete, cast-in-place concrete, masonry, or timber), and geosynthetic walls are shown in the Standard Plans. The Region Design PE Offices are responsible for preparing the PS&E for retaining walls for which standard designs are available, in accordance with WSDOT Design Manual (DM) Section 1130.06. However, the Bridge and Structures Office may prepare PS&E for such standard type retaining walls if such retaining walls are directly related to other bridge structures being designed by the Bridge and Structures Office.

Structural earth wall (SEW) systems meeting established WSDOT design and performance criteria have been listed as "pre-approved" by the Bridge and Structures Office and the Materials Laboratory Geotechnical Division. The PS&E for "pre-approved" structural earth wall systems shall be coordinated by the Region Design PE Office with the Bridge and Structures Office, and the Materials Laboratory Geotechnical Division, in accordance with DM 1130.06.

The PS&E for minor non-structural retaining walls, such as rock walls, gravity block walls, and gabion walls, are prepared by the Region Design PE Offices in accordance with WSDOT DM 1130.06, and any other design input from the Region Materials Office or Geotechnical Division.

All other retaining walls not covered by the Standard Plans such as soil nail walls, soldier pile walls, soldier pile tieback walls and all walls beyond the scope of the designs tabulated in the Standard Plans, are designed in the Bridge and Structures Office according to the design parameters provided by the Materials Laboratory Geotechnical Division.

The Hydraulics Branch of the Design Office should be consulted for walls that subject to floodwater or are located in a flood plain. The State Bridge and Structures Architect should review the architectural features and visual impact of the walls during the Preliminary Design stage. The designer is also directed to DM 1130 and Chapter 15 of the GDM, which provide valuable information on the design of retaining walls.

8.4.2 Common Types of Walls

The majority of walls used by WSDOT are one of the following six types:

1. Proprietary Structural Earth (SE) Walls - Standard Specification Section 6-13.
2. Standard Reinforced Concrete Cantilevered Retaining Walls- Standard Plans D-1a to through D-1f and Standard Specification Section 6-11.
3. Soil Nail Walls - Standard Specification Section 6-15.
4. Soldier Pile Walls and Soldier Pile Tieback Walls - Standard Specification Sections 6-16 and 6-17.
5. Geosynthetic Walls (Temporary and Permanent) - Standard Plan D-3 and Standard Specification Section 6-14.
6. Noise Barrier Walls - Standard Plan D-2a through D-2y and Standard Specification Section 6-12.

Other wall systems, such as secant pile or cylinder pile walls, may be used based on the recommendation of the Geotechnical Division. These walls shall be designed in accordance with the current AASHTO LRFD Specifications.

A. Pre-approved Proprietary Walls

A wall specified to be supplied from a single source (patented, trademark, or copyright) is a proprietary wall. Walls are generally pre-approved for heights up to 33 ft. The Materials Laboratory Geotechnical Division will make the determination as to which pre-approved proprietary wall system is appropriate on a case-by-case basis. The following is a description of the most common types of proprietary walls:

1. Structural Earth Walls (SEW)

A structural earth wall is a flexible system consisting of concrete face panels or modular blocks that are held rigidly into place with reinforcing steel strips, steel mesh, welded wire, or geogrid extending into a select backfill mass. These walls will allow for some settlement and are best used for fill sections. The walls have two principal elements:

- Backfill or wall mass: a granular soil with good internal friction (i.e. gravel borrow).
- Facing: precast concrete panels, precast concrete blocks, or welded wire (with or without vegetation). At present, WSDOT has eight pre-approved proprietary wall systems as shown in the table in Appendix A. Design heights in excess of 33 feet shall be approved by the Materials Laboratory Geotechnical Division. If approval is granted, the designer shall contact the individual structural earth wall manufacturers for design of these walls before the project is bid so details can be included in the Plans. See sheet 8.1-A1.1 to A1.2 for details that need to be provided in the Plans for manufacturer designed walls. For additional information see the DM 1130 and Chapter 15 of the GDM. For the SEW shop drawing review procedure see Chapter 15 of the GDM.

2. Other Proprietary Walls

Other proprietary wall systems such as crib walls, bin walls, or precast cantilever walls, can offer cost reductions, reduce construction time, and provide special aesthetic features under certain project specific conditions.

For a list of these pre-approved proprietary walls and their height limitations, see Appendix A. The Region shall refer to DM 1130 for guidelines on the selection of wall types. The Materials Laboratory Geotechnical Division and the Bridge and Structures Office Preliminary Plans Unit must approve the concept prior to development of the PS&E.

B. Geosynthetic Wrapped Face Walls

Geosynthetic walls use geosynthetics for the soil reinforcement and part of the wall facing. Use of geosynthetic walls as permanent structures requires the placement of a cast-in-place or shotcrete facing. Details for construction are shown in Standard Plan D-3.

C. Standard Reinforced Concrete Cantilever Walls

Reinforced concrete cantilever walls consist of a base slab footing from which a vertical stem wall extends. These walls are suitable for heights up to 35 feet. Details for construction are given in the Standard Plans D-1a to D-1f. These Standard Plans were developed utilizing the AASHTO LFD specifications. Wall types 1 through 4 are suitable for use in Western Washington and designed for a seismic coefficient of 0.3. Wall types 5 and 6 are suitable for use only in Eastern Washington or where the seismic coefficient is less than 0.2. The maximum bearing pressure on the soil is tabulated on page DM 1130-30 for the 6 types of walls. The walls will be updated in the near future to meet the

requirements of the AASHTO LRFD Specifications. For nonstandard designs; wall design shall be designed in accordance with Section 3 and Section 11 of the LRFD specifications. The major disadvantage of these walls is the low tolerance to post-construction settlement, which may require use of deep foundations (shafts or piling) to provide adequate support.

D. Soldier Pile Walls and Soldier Pile Tieback Walls

Soldier Pile Walls utilize wide flange steel members, such as W or HP shapes. The piles are usually spaced 6 to 10 feet apart. The main horizontal members are timber lagging designed to transfer the soil loads to the piles. For additional information see GDM Chapter 15.

See sheet 8.1-A3.1 to A3.5 for typical details.

E. Soil Nail Walls

The basic concept of soil nailing is to reinforce and strengthen the existing ground by installing steel bars called "nails" into a slope or excavation as construction proceeds from the "top down". Soil nailing is a technique used to stabilize moving earth, such as a landslide, or as temporary shoring. Soil anchors are used along with the strength of the soil to provide stability. The Materials Laboratory Geotechnical Division designs the soil nail system whereas the Bridge and Structures Office designs the wall fascia. Presently, the FHWA Publication 'Manual for Design & Construction Monitoring of Soil Nail Walls' is being used for structural design of the fascia. See sheet 8.1-A2.1 to A2.5 for typical soil nail wall details.

F. Noise Barrier Walls

Noise barrier walls are primarily used in urban or residential areas to mitigate noise or to hide views of the roadway. Common types, as shown in the Standard Plans, include cast-in-place concrete panels (with or without traffic barrier), precast concrete panels (with or without traffic barrier), masonry blocks, and timber panels. The State Bridge and Structures Architect should be consulted for wall type selection. Design criteria for noise barrier walls are based on AASHTO's *Guide Specifications for Structural Design of Sound Barriers*. Details of these walls are available in the Standard Plans D-2a to D-2y. DM 1140-3, figure 1140-1, tabulates the design wind speeds and various exposure conditions used to determine the appropriate wall type.

8.4.3 Design

A. General

All designs shall follow procedures as outlined in AASHTO LRFD Specifications Chapter 11, the GDM, and the Bridge Design Manual (BDM). The Materials Laboratory Geotechnical Division will provide the earth pressure diagrams and other geotechnical design requirements for special walls to be designed in the Bridge and Structures Office. Pertinent soil data will also be provided for pre-approved proprietary structural earth walls (SEW), non-standard reinforced concrete retaining walls, and geosynthetic walls.

B. Non-Standard Reinforced Concrete Retaining Walls

In general, concrete for reinforced concrete retaining walls shall be Class 4000 Concrete with a 28-day compressive strength of 4,000 psi. Typical load combinations and load factors can be found in AASHTO LRFD Figures C11.5.5-1 and C11.5.5-2. The following chart represents additional criteria for evaluating the overall stability of the wall.

$\frac{(FS)P}{W} \leq 0.5$ (P = total horizontal force on wall) (W= total minimum vertical load)

For Standard Walls having a height (H) of 16 feet or less, the controlling load is the AASHTO LFD 10 kip collision load. This load occurs occasionally and will have a reduced factor of safety.

Wall Height, H	Overturning*		Sliding
Roadway Grade to Bottom of Footing	M abt. toe resist / M abt. toe loads	Location of Resultant*	FS(EP + Sur or 10k) / < 0.5 Weight
H, 16 feet or less for 10K collision load	greater than 1.5	within middle 1/2 of footing	F.S. = 1.2
H, 17 feet or more for all Wall load cases	greater than2.0	within middle 1/2 of footing	F.S. = 1.5
Earthquake Group VII All Heights	greater than 1.5	Within middle 1/2 of footing	FS(EP + EQ) < 0.5 Weight FS = 1.1

*Both cases shall be met for determining wall stability for the service load condition.

Factor of Safety (FS) Table
Figure 8-1

The 10 kip collision load shall be distributed over 16 feet. This is the minimum wall length allowed for Type 2 Retaining Walls in the Standard Plans. In a special design, the AASHTO LRFD Extreme Event loading for vehicular collision must be analyzed. These loads are tabulated in LRFD Table A13.2-1. Although the current yield line analysis assumptions for this loading are not applicable to retaining walls, the transverse collision load (Ft) may be distributed over the longitudinal length (Lt) at the top of barrier. At this point, the load is distributed at a 45 degree angle into the wall. Future updates to the LRFD code will address this issue.

For sliding, the passive resistance in the front of the footing may be considered if the earth is more than 2 feet deep on the top of the footing and does not slope downward away from the wall. The design soil pressure at the toe of the footing shall not exceed the allowable soil bearing capacity supplied by the Materials Laboratory Geotechnical Division. For retaining walls supported by deep foundations (shafts or piles), refer to *Bridge Design Manual* Sections 9.5.1, 9.5.2, and 9.6 (see GDM).

C. Soldier Pile Tieback Walls

1. See Principles of Anchor Design - AASHTO LRFD Specification 11.9 “Anchored Walls.” The Materials Laboratory Geotechnical Division will determine whether anchors can be used economically at a particular site based on the ability to install the anchors and develop anchor capacity. The presence of utilities or other underground facilities, and the ability to attain underground easement rights may also determine whether anchors can be installed.

   The anchor may consist of bars, wires, or strands. The choice of appropriate type is usually left to the Contractor but may be specified by the designer if special site conditions exist that preclude the use of certain anchor types. In general, strands and wires have advantages with respect to tensile strength, limited work areas, ease of transportation, and storage. However, bars are more easily protected against corrosion, and are easier to develop stress and transfer load.

   The geotechnical report will provide a reliable estimate of the nominal pullout resistances of the anchor, recommended anchor installation angles (typically 10° to 45°), no-load zone dimensions, and any other special requirements for wall stability for each project. AASHTO LRFD Section C11.9.5.1 outlines two procedures to determine the anchor design force. The capacity of each anchor shall be verified by testing. Testing shall be during the anchor installation (See Standard Specification Section 6-17.3(8) and GDM).

2. Corrosion Protection

   The Materials Laboratory Geotechnical Division will specify the appropriate protection system; the two primary types are:

   a. Simple Protection: The use of simple protection relies on Portland cement grout to protect the tendon, bar, or strand in the bond zone. The unbonded lengths are sheaths filled with anti-corrosion grease, heat shrink sleeves, and secondary grouting after stressing. Except for secondary grouting, the protection is usually in place prior to insertion of the anchor in the hole.

   b. Double Protection: a corrugated PVC, high-density polyethylene, or steel tube accomplishes complete encapsulation of the anchor tendon. The same provisions of protecting the unbonded length for simple protection are applied to those for double protection.

3. Determination of Tieback Spacing

   The preliminary anchor spacing can be determined from AASHTO LRFD C11.9.5.1. Typical pile spacing (horizontal) of 6 to 10 feet and anchor spacing (vertical) of 8 to 12 feet are commonly used. The minimum spacing of 4 feet in both directions is not recommended because it can cause a loss of effectiveness due to disturbance of the anchors during installation.

4. Design of Soldier Pile Tieback Walls

   a. Lateral Earth Pressures

      (1) Active pressure is assumed to act over one pile spacing above the base of excavation in front of the wall, and over the shaft diameter below the base of excavation in front of the wall. Passive pressure usually acts over three times the shaft diameter or pile spacing, whichever is smaller.

      (2) For permanent ground anchors, the anchor DESIGN LOAD, T, shall be according to AASHTO LRFD Specifications. For temporary ground anchors, the anchor DESIGN LOAD, T, may ignore extreme event load cases.

      (3) The lock-off load is 60 percent of the controlling factored design load for temporary and permanent walls (see GDM Chapter 15).

   b. Depth of Embedment

      For cantilever soldier piles without permanent ground anchors, the embedment should be determined to satisfy horizontal force equilibrium and moment equilibrium about the bottom of the soldier pile.

      For soldier piles with permanent ground anchors, the depth of embedment is determined by moment equilibrium of lateral force about the bottom of the soldier pile. Minimum embedment shall be 10 feet or as recommended by the Materials Laboratory Geotechnical Division.

   c. Design of Timber Lagging

      Most commonly, the lagging thickness is determined from past construction experience as related to depth of excavation, soil condition, and soldier pile spacing. In other cases the soil pressure distribution, as recommended by the Materials Laboratory Geotechnical Division, is used to determine the thickness of lagging.

A soil pressure distribution equal to 50 percent of the lateral earth pressure diagram is recommended for the design of simply supported lagging. The 50 percent reduction is due to the soil arching effect behind the wall. Neglecting the soil arching effect leads to unreasonably thick lagging for deep excavations with relatively larger soldier pile spacing. For design procedures see AASHTO LRFD 11.8.5.2.

d. Design of Concrete Fascia Panels

Concrete fascia panels shall be reinforced concrete and shall be designed according to the latest AASHTO LRFD Specifications. The minimum structural thickness of the concrete fascia panel shall be 9 inches. Architectural treatment of concrete fascia panels shall be indicated in the Plans.

Concrete strength shall not be less than 4,000 psi at 28 days. The wall is to extend 2 feet minimum below the finish ground line adjacent to the wall. Permanent drainage systems shall be provided to prevent hydrostatic pressures developing behind the wall. A cut that slopes toward the proposed wall will invariably encounter natural subsurface drainage.

Vertical chimney drains or prefabricated drainage mats can be used for normal situations to collect and transport drainage to a weep hole or pipe located at the base of the wall. Installing horizontal drains to intercept the flow at a distance well behind the wall may control concentrated areas of subsurface drainage (see GDM Chapter 15).

When concrete fascia panels are placed on soldier piles, the design earth pressure diagram and a generalized detail of lagging with a strongback (see sheet 8.1-A3.4) shall be shown in the Plans. This information will assist the Contractor in designing formwork that doesn't overstress the piles while concrete is being placed.

e. Design of Soldier Piles

The soldier piles shall be designed for shear, bending, and axial stresses according to the latest AASHTO LRFD and GDM design criteria. Due to the soil-structure interaction, a redistribution of lateral stresses is anticipated, resulting in a reduction of pressure near the center of spans between anchors and a concentration of pressure at supports.

8.4.4 Miscellaneous Items

A. Drainage

All reinforced concrete retaining walls shall have 3-inch diameter weepholes located 6 inches above final ground line and spaced about 12 feet apart. In case the vertical distance between the top of the footing and final ground line is greater than 10 feet, additional weepholes shall be provided 6 inches above the top of the footing. No weepholes are necessary in cantilever wingwalls. Drainage features shall be detailed in the Plans.

Weepholes can get clogged up or freeze up, and the water pressure behind the wall may start to increase. In order to keep the water pressure from building, it is important to have well draining gravel backfill and underdrains. Appropriate details must be shown in the Plans.

No underdrain pipe or gravel backfill for drains is necessary behind cantilever wingwalls. A 3 foot minimum thickness of gravel backfill shall be shown in the Plans behind the cantilever wingwalls. Backfill material shall be included with the civil quantities (not the bridge quantities). If it is necessary to excavate existing material for the backfill, then this excavation shall be a part of the bridge quantities for "Structure Excavation Class A Incl. Haul".

B. Joints

For cantilevered and gravity walls, joint spacing should be a maximum of 24 feet on centers. For counterfort walls, joint spacing should be a maximum of 32 feet on centers. For soldier pile and soldier pile tieback walls with concrete fascia panels, joint spacing should be 24 to 32 feet on centers. For precast units, the length of the unit depends on the height and weight of each unit. Odd panels for all types of walls shall normally be made up at the ends of the walls. Every joint in the wall shall provide for expansion. For cast-in-place construction, a minimum of 1/2 inch premolded filler should be specified in the joints. A compressible back-up strip of closed-cell foam polyethylene or butyl rubber with a sealant on the front face is used for precast concrete walls.

No joints other than construction joints shall be used in footings except at bridge abutments and where substructure changes such as spread footing to pile footing occur. In these cases, the footing shall be interrupted by a 1/2 inch premolded expansion joint through both the footing and the wall. The maximum spacing of construction joints in the footing shall be 120 feet. The footing construction joints should have a 6-inch minimum offset from the expansion joints in the wall.

C. Architectural Treatment

The type of surface treatment for retaining walls is decided on a job-to-job basis. Consult the State Bridge and Structures Architect during preliminary plan preparation. The wall should blend in with its surroundings and complement other structures in the vicinity. The tops of walls are usually smooth flowing curves in elevation view. See Retaining Wall Standard Sheets for top of wall and ground line relationship and also for cambering of front of cantilevered retaining walls.

D. Shaft Backfill for Soldier Pile Walls

1. Soldier Pile Walls without Permanent Ground Anchors

   For this application, controlled density fill (CDF, 145 pcf) should be used for the drilled portion of the pile. In this situation, the fill only needs to be strong enough to transfer active and passive loads between the soil and the soldier pile.

2. Soldier Pile Walls With Permanent Ground Anchors

   For this application, structural concrete (Concrete Class 4000P) should be used below final grade (below the cut line in front of the soldier pile wall), and CDF should be used above the bottom of the timber lagging. Concrete Class 4000P can be used in a wet hole application. Structural concrete is needed below final grade to assure vertical load transfer from the soldier pile shaft into the supporting soil. The load is applied to the soldier pile from the vertical component of the sloping permanent ground anchors.



1. SEE ST'D. PLAN D-24 FOR TYPE 3 RET. WALL.
2. SEE "ALTERNATE DETAIL" ON ST'D. PLAN D-4 FOR DRAINAGE DETAILS, GRAVEL BACKFILL FOR DRAINS, GRAVEL BACKFILL FOR WALLS & UNDERDRAIN PIPE ARE NOT INCLUDED IN BRIDGE QUANTITIES.
PLAN
ELEVATION
AHEAD ON STA.
FRONT FACE OF WALL
156'-0" REINF. CONC. RETAINING WALL AT TOP OF FOOTING - TYPE 3
(DIMENSIONS ARE ALONG FRONT FACE OF WALL AT TOP OF FOOTING)
28'-0" NORMAL TO L-LINE (TYP.)
6 SECTIONS 24'-0" = 144'-0"
STA. 10+00.00
EL. 51.67
EL. 50.5
EL. 50.0
LOC. OF FOOTING CONSTR. JOINT
INDICATES DESIGN WALL HEIGHT "H" FOR SELECTING REINFORCEMENT
P.V.I. EL. 80.73
P.V.I. EL. 62.73
50' V.C.
25' V.C.

Figure 8-2

E. Detailing of Standard Reinforced Concrete Retaining Walls

1. In general, the "H" dimension shown in the retaining wall Plans should be in foot increments. Use the actual design "H" reduced to the next lower even foot for dimensions up to 3 inches higher than the even foot.

   Examples: Actual height = 15′-3"↑, show "H" = 15' on design plans

   Actual height > 15′-3"↑, show "H" = 16' on design plans

   For walls that are not of a uniform height, "H" should be shown for each segment of the wall between expansion joints or at some other convenient location. On walls with a steep slope or vertical curve, it may be desirable to show 2 or 3 different "H" dimensions within a particular segment. The horizontal distance should be shown between changes in the "H" dimensions.

   The value for "H" shall be shown in a block in the center of the panel or segment. See Example, Figure 9.4.4-1.

2. Follow the example format shown in Figure 8.-2.
3. Calculate approximate quantities using the Standard Plans.
4. Wall dimensions shall be determined by the designer using the Standard Plans.
5. Do not show any details given in the Standard Plans.
6. Specify in the Plans all deviations from the Standard Plans.
7. Do not detail reinforcing steel, unless it deviates from the Standard Plans.

8. For pile footings, use the example format with revised footing sizes, detail any additional steel, and show pile locations. Similar plan details are required for footings supported by shafts.

8.5 Miscellaneous Underground Structures

8.5.1 General

Miscellaneous underground structures consist of box culverts, precast reinforced concrete three-sided structures, detention vaults, metal pipe arches, and tunnels. These structures are designed in accordance with the AASHTO Standard Specifications for Highway Bridges, and applicable ACI design and ASTM material specifications.

Precast reinforced concrete three sided structures, constructed in accordance with the current WSDOT General Special Provisions (GSP's) for these structures, shall be designed under the Load Factor Design (LFD) method of the AASHTO Standard Specifications For Highway Bridges. Detention vaults shall also be designed in accordance with the criteria in the ACI 350 Code Requirements for Environmental Engineering Concrete Structures. The detention vault design should satisfy the most stringent criteria of the LFD design method of AASHTO Standard Specifications for Highway Bridges and that of ACI 350. Requirements more stringent than either of these two codes may be desirable for unusual structures.

Generally, seismic design criteria does not control the design of underground structures unless the peak ground acceleration exceeds 0.3g, where g is the acceleration due to gravity. This is because the structures are supported on all sides by soil and rock, and move as a unit with the adjacent soil. See Reference by Miller and Constantino (1994). As with any structure, a geotechnical soils report with loading or pressure diagrams, settlement criteria, and ground water levels will be needed from the Materials Laboratory Geotechnical Services Branch in order to complete the design.

8.5.2 Design

A. Box Culverts

Box culverts are four-sided rigid frame structures and are either made from cast-in-place (CIP) reinforced concrete or precast concrete. In the past, standardized box culvert plan details were shown in the WSDOT Standard Plans, under the responsibility of the HQ Hydraulics Office. These former Standard Plans have been deleted and are no longer available. Now box culvert design is standardized under applicable AASHTO material specifications, and design plans are not required in the PS&E. Box culverts with less than two feet of cover shall be in accordance with AASHTO M 273. Box culverts with two feet or more of cover shall be in accordance with AASHTO M 259.

B. Precast Reinforced Concrete Three-Sided Structures

Precast reinforced concrete three-sided structures are patented or trademarked rigid frame structures made from precast concrete. Some fabricators of these systems are: Utility Vault Company, Central Pre-Mix Prestress Company, and Bridge Tek, LLC. These systems require a CIP concrete or precast footing that must provide sufficient resistance to the horizontal reaction or thrust at the base of the vertical legs.

The precast concrete fabricators are responsible for the structure design and the preparation of shop plans. The fabricators of systems which have received WSDOT pre-approval are specified in the GSP's. The bridge designer reviewing the project will be responsible for reviewing the fabricator's design calculations and details with consultation with the Construction Support Unit. Under the current GSP, precast reinforced concrete three sided structures are limited to spans of 26 feet or less. However, in special cases it may be necessary to allow longer spans, with the specific approval of the Bridge and Structures Office. Several manufacturers advertise spans over 40 feet.

C. Detention Vaults

Detention vaults are used for stormwater storage and are to be watertight. These structures can be open at the top like a swimming pool, or completely enclosed and buried below ground. Two references for tank design are the PCA publications *Rectangular Concrete Tanks*, Revised 5th Edition (1998) and *Design of Liquid-Containing Structures for Earthquake Forces* (2002).

Buoyant forces from high ground water conditions should be investigated for permanent as well as construction load cases so the vault does not float. Controlling loading conditions may include: backfilling an empty vault, filling the vault with stormwater before it is backfilled, or seasonal maintenance that requires draining the vault. The designer should check with the Region Project Engineer's Office to see if weep holes can be placed at or above the high groundwater level to relieve external hydrostatic pressure should buoyant forces be too large to resist.

ACI 350 requires Environmental Durability Factors in addition to the larger load factors of 1.4 for dead load and 1.7 for fluid pressure (ACI 350 controls over AASHTO). These factors are:

1.3 for flexure

1.65 for direct tension

1.3 for shear beyond that of the capacity provided by the concrete

The LFD strength equations become:

1. Flexural Reinforcement

   $M_n > 1.3(1.4M_{DL} + 1.7M_{EP} + 1.7\ M_{LL} + 1.7M_{FL})$

2. Direct Tension Reinforcement

   $F_n > 1.65(1.4F_{DL} + 1.7F_{EP} + 1.7\ F_{LL} + 1.7F_{FL})$

3. Stirrup Reinforcement

   The designer should increase the wall or slab thicknesses so that shear stirrups are not required.

   $\phi V_S > 1.3(V_U - \phi V_C)$

4. Concrete Shear and Compression

   $F_n > 1.3(1.4F_{DL} + 1.7F_{EP} + 1.7\ F_{LL} + 1.7F_{FL})$

ACI 350 has stricter criteria for cover, crack control, and spacing of joints than the AASHTO Specifications. Cover is not to be less than 2 inches, no metal or other material is to be within 1-1/2 inches from the formed surface, and the maximum bar spacing shall not exceed 12 inches. Crack control criteria is stricter with "z" not exceeding 115 kips per inch under normal exposure conditions; this corresponds to a crack width of 0.010 inches.

Joints in the vault's top slab, bottom slab and walls shall allow dissipation of temperature and shrinkage stresses, thereby reducing cracking. The amount of temperature and shrinkage reinforcement is a function of reinforcing steel grade " and length between joints (See Table 7.12.2-1 ACI 350). All joints shall have a shear key and a continuous and integral PVC waterstop with a 4-inch minimum width. The purpose of the waterstop is to prevent water infiltration and exfiltration.

For walls in contact with liquid that are over 10' in height, the minimum wall thickness is 12". This minimum thickness is generally good practice for all external walls, regardless of height, to allow for 2 inches of cover as well as space for concrete placement and vibration.

After the forms are placed, the void left from the form ties shall be coned shaped, at least 1 inch in diameter and 1 1/2 inches deep, to allow proper patching.

Detention vaults shall not be located within the roadway prism.

Original signed plans of all closed top detention vaults with access shall be forwarded to the Bridge Plans Engineer in the Bridge Project Unit (see Bridge Design Manual Section 12.4.10.B). This ensures that the Bridge Preservation Office will have the necessary inventory information for inspection requirements.

D. Metal Pipe Arches

Pipe arch systems are similar to precast reinforced concrete three sided structures in that these are generally proprietary systems provided by several manufacturers, and that their design includes interaction with the surrounding soil. Pipe arch systems shall be designed in accordance with Section 12 of the AASHTO Standard Specifications for Highway Bridges.

E. Tunnels

Tunnels are unique structures in that the surrounding ground material is the structural material that carries most of the ground load. Therefore, geology has even more importance in tunnel construction than with above ground bridge structures. In short, geotechnical site investigation is the most important process in planning, design and construction of a tunnel.

Tunnels are not a conventional structure, and estimation of costs is more variable as size and length increase. Ventilation, safety access, fire suppression facilities, warning signs, lighting, drainage, operation and maintenance are extremely critical issues associated with the design of tunnels and will require the expertise of geologists, tunnel experts and mechanical engineers.

For motor vehicle fire protection, a standard has been produced by the National Fire Protection Association. This document, "NFPA 502 – Standard for Road Tunnels, Bridges, and Other Limited Access Highways", uses tunnel length to dictate minimum fire protection requirements:

300 feet or less: no fire protection requirements

300 to 800 feet: minor fire protection requirements

800 feet or more: major fire protection requirements

Some recent WSDOT tunnel projects are:

I-90 Mt. Baker Ridge Tunnel Bore Contract: 3105 Bridge No: 90/24N

This 1500 foot long tunnel is part of the major improvement of Interstate 90. Work was started in 1983 and completed in 1988. The net interior diameter of the bored portion, which is sized for vehicular traffic on two levels with a bike/pedestrian corridor on the third level, is 63.5 feet. The project is the world's largest diameter tunnel in soft ground, which is predominantly stiff clay. Construction by a stacked-drift method resulted in minimal distortion of the liner and insignificant disturbance at the ground surface above.

Jct I-5 SR 526 E-N Tunnel Ramp Contract: 4372 Bridge No: 526/22E-N


This 465 foot long tunnel, an example of the cut and cover method, was constructed in 1995. The interior dimensions were sized for a 25 foot wide one lane ramp roadway with a vertical height of 18 feet. The tunnel was constructed in 3 stages. 3 and 4 foot diameter shafts for the walls were placed first, a 2 foot thick cast-in-place top slab was placed second, then the tunnel was excavated, lined and finished.

I-5 Sleater-Kinney Bike/Ped. Tunnel Contract: 6031 Bridge No: 5/335P


This 122 foot long bike and pedestrian tunnel was constructed in 2002 to link an existing path along I-5 under busy Sleater-Kinney Road. The project consisted of precast prestressed slab units and soldier pile walls. Construction was staged to minimize traffic disruptions.

8.5.3 References

1. AASHTO LRFD Bridge Design Specifications, 2nd Ed., w/Interims
2. AASHTO Standard Specifications for Highway Bridges, 17th Ed., 2002
3. ACI 350R-01 Code Requirements for Environmental Engineering Concrete Structures, ACI
4. ACI 318-95 Building code Requirements for Structural Concrete, ACI, 1995.
5. Munshi, Javeed A. *Rectangular Concrete Tanks*, Rev. 5th Ed., PCA, 1998.
6. Miller, C. A. and Constantino, C. J. "Seismic Induced Earth Pressure in Buried Vaults", PVP-Vol.271, *Natural Hazard Phenomena and Mitigation*, ASME, 1994, pp. 3-11.
7. Munshi, J. A. *Design of Liquid-Containing Concrete Structures for Earthquake Forces*, PCA, 2002.
8. NFPA 502, *Standard For Road Tunnels, Bridges, and Other Limited Access Highways*.




SEW Wall Elevation
Figure 8-A-1




TYPICAL CROSS SECTION


SEW Wall Section
Figure 8-A-2



Soil Nail Layout
Figure 8-A-3




TYPICAL SECTION




FACIAL WALL REINFORCEMENT


WWF NOT SHOWN FOR CLARITY



NOTE:

EXPANSION JOINTS TO BE LOCATED AT A MAXIMUM SPACING OF 24'-0" C. TO C., CENTERED BETWEEN NAILS, EXCEPT IF THE JOINT IS WITHIN 1'-6" OF A STEP AT THE TOP OF WALL, THE JOINT IS TO BE LOCATED AT THAT STEP.






ANCHOR PLATE DETAILS


AASHTO A 36

Soil Nail Wall Fascia Panel Details

Figure 8-A-4




TYPICAL SECTION SOIL NAIL WALL




DETAIL G

DRAIN GRATE INSTALLATION SHALL NOT DISRUPT PREFABRICATED DRAINAGE MAT




TL = TEST LOAD = (BOND LENGTH) X (DESIGN LOAD TRANSFER)

TEST NAIL DETAIL




NAIL HEAD DETAIL

*DOUBLE CORROSION PROTECTION REQUIRED FOR SOIL NAILS AT LOCATIONS SHOWN. SEE SOIL NAIL LAYOUTS FOR DETAILS




DETAIL H

TYPICAL FABRIC DRAIN CONNECTION TO UNDERDRAIN PIPE




DETAIL E

CEMENT CONCRETE GUTTER




PLAN - WALL FACE FINISH




ELEVATION - WALL FACE FINISH


Soil Nail Wall Section
Figure 8-A-5




ELEVATION - CABLE RAIL




DETAIL A



DETAIL B



VIEW D




SECTION C

NOTES:

1. ALL PIPE SHALL BE STEEL PIPE ASTM A53 GRADE B.
2. ALL STEEL PLATE SHALL BE ASTM A 36.
3. ALL PARTS EXCEPT WIRE ROPE SHALL BE HOT DIP GALVANIZED IN ACCORDANCE WITH AASHTO M111 OR M232 AFTER FABRICATION.
4. SPELTER SOCKETS AND SOCKETING PROCEDURE SHALL BE AS PER ROPE MANUFACTURER.
5. WIRE ROPE SHALL BE INSTALLED TO .4 KIP TENSION LEAVING 6" OF TAKE UP STILL AVAILABLE IN THE TURNBUCKLE.
6. EACH CONTINUOUS LENGTH OF CABLE SHALL HAVE A TURNBUCKLE AT ONE END ONLY AND BE ANCHORED TO END POST WITH BRACE AT BOTH ENDS.
7. CENTER SUPPORT NOT TO BE INSTALLED ACROSS EXPANSION JOINT.
8. ALL POSTS TO BE INSTATLLED VERTICAL.


Cable Fence
Figure 8-A-6




NOTE: ALL POSTS TO BE INSTALLED VERTICAL.

* ANGLES VARY (45° APPROX.) WITH THE SLOPE OF THE TOP OF WALL.


ELEVATION - CABLE RAIL




BASE PLATE DETAIL




DETAIL A



DETAIL B



VIEW D




SECTION C

NOTES:

1. ALL PIPE SHALL BE STEEL PIPE ASTM A53 GRADE B.
2. ALL STEEL PLATE SHALL BE ASTM A 36.
3. ALL PARTS EXCEPT WIRE ROPE SHALL BE HOT DIP GALVANIZED IN ACCORDANCE WITH AASHTO M111 OR M232 AFTER FABRICATION.
4. SPELTER SOCKETS AND SOCKETING PROCEDURE SHALL BE AS PER ROPE MANUFACTURER.
5. WIRE ROPE SHALL BE INSTALLED TO 400 LBS TENSION LEAVING A TAKE UP OF 6" STILL AVAILABLE IN THE TURNBUCKLE.
6. EACH CONTINUOUS LENGTH OF CABLE SHALL HAVE A TURNBUCKLE AT ONE END ONLY AND BE ANCHORED TO END POST WITH BRACE AT BOTH ENDS.
7. INTERMEDIATE POSTS AND BRACES SHALL NOT TO BE INSTALLED ACROSS EXPANSION JOINT.
8. ALL POSTS TO BE INSTATLLED PERPENDICULAR TO TOP OF WALL.

Cable Fence - Top Mount

Figure 8-A-7



REFLECTED DEVELOPED ELEVATION

A.P. = ANGLE POINT


GENERAL NOTES

1. ALL MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE WASHINGTON STATE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD, BRIDGE AND MUNICIPAL CONSTRUCTION-ENGLISH, DATED 2004, AND AMENDMENTS.
2. THIS STRUCTURE HAS BEEN DESIGNED IN ACCORDANCE WITH THE REQUIREMENTS OF THE AASHTO STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES SIXTEENTH EDITION - 1996 AND INTERIMS. ALL STRUCTURAL ELEMENTS HAVE BEEN DESIGNED IN ACCORDANCE WITH THE REQUIREMENTS FOR LOAD FACTOR DESIGN.
3. SOLDIER PILE SHAFTS WITH PERMANENT GROUND ANCHORS SHALL BE FILLED WITH CONCRETE CLASS 4000P BELOW THE TIMBER LAGGING. THE REMAINING PORTION OF THE SOLDIER PILE SHAFTS, INCLUDING THE FULL HEIGHT OF SOLDIER PILE SHAFTS WITHOUT PERMANENT GROUND ANCHORS, SHALL BE FILLED WITH CONTROLLED DENSITY FILL (CDF).
4. UNLESS OTHERWISE SHOWN IN THE PLANS, THE CONCRETE COVER MEASURED FROM THE FACE OF THE CONCRETE TO THE FACE OF ANY REINFORCING STEEL SHALL BE 1½".
5. SOLDIER PILES, BARS AND PLATES FOR THE SOLDIER PILE ASSEMBLY STIFFENERS AND TIE PLATES SHALL CONFORM TO ASTM A36. THE 8"ø EXTRA STRONG PIPE SHALL CONFORM TO THE REQUIREMENTS OF ASTM A53 GR. B OR A501.
6. ALL WELDING SHALL BE DONE TO MINIMIZE DISTORTION. THE WELDING SEQUENCES AND PROCEDURES TO BE USED SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PRIOR TO THE START OF WELDING.
7. ALL DIMENSIONS ARE HORIZONTAL AND VERTICAL UNLESS OTHERWISE SHOWN.
8. ALL DIMENSIONS SHOWN WITH DECIMALS ARE IN METERS AND ALL DIMENSIONS SHOWN WITHOUT DECIMALS ARE IN MILLIMETERS.

SOLDIER PILE/TIEBA

Soldier Pile/Tieback Wall Elevation

Figure 8-A-8




TYPICAL SECTION


SHOWN FOR SOLDIER PILE WITH P.G.A.
SIMILAR FOR SOLDIER PILE WITHOUT P.G.A.
P.G.A.= PERMANENT GROUND ANCHOR

TIMBER LAGGING SIZES		
(HP) - DIST. FROM TOP OF PILE IN FEET		SIZE
NO TIEBACKS	WITH TIEBACKS	
0 - 12	ALL DEPTHS	4 x
GREATER THAN 12	- -	6 x

4 x - OPTIONAL 4 x 8, 4 x 10 OR 4 x 12
6 x - OPTIONAL 6 x 8, 6 x 10 OR 6 x 12




PLAN - SOLDIER PILE WALL WITHOUT P. G. A.




PLAN - SOLDIER PILE WALL WITH P. G. A.

Soldier Pile/Tieback Wall Details 1 of 2

Figure 8-A-9




ELEVATION - SOLDIER PILE
WITH P.G.A. THRU WEB




VIEW A

Soldier Pile/Tieback Wall Details 2 of 2
Figure 8-A-10



PARTIAL WALL ELEVATION




ISOMETRIC VIEW


SECTIONAL VIEW

WEEP HOLE DRAIN DETAILS


DRAIN GRATE INSTALLATION SHALL NOT DISRUPT PREFABRICATED DRAINAGE MAT



SECTION A




DETAIL H




TYPICAL FASCIA PANEL FORMWORK

- SEE SPECIAL PROVISIONS FOR FASCIA PANEL FORMING.
- STRONGBACK(S) AND TIES SPACED AS REQUIRED TO CONTAIN POUR PRESSURE.



NOTE:
EXPANSION JOINTS SHALL BE LOCATED AS SHOWN ON BRIDGE SHEET SP1.


EXPANSION JOINT DETAIL



DETAIL C

Soldier Pile/Tieback Wall Fascia Panel Details

Figure 8-A-11



Soldier Pile/Tieback Wall Permanent Ground Anchor Details

Figure 8-A-12

Wall Supplier	System Name	System Description	ASD/ LFD or LRFD?	Height, or Other Limita-tions	Year Initially Approved	Last Approved Update
The Reinforced Earth Co. 8614 Westwood Center Drive Suite 1100 Vienna, VA 22182 (703) 821-1175	Reinforced Earth Wall	Precast concrete 5'x5' facing panels and steel strip soil reinforcement	ASD/ LFD	33 ft	1987	Approved 10/30/04 (submitted 3/29/04)
L. B. Foster Company Foster Geotechnical 1660 Hotel Circle North, Suite 304 San Diego, CA 92108-2803 (619) 688-2400	Retained Earth Wall	Precast concrete 5'x5' facing panels and steel bar mat soil reinforcement	ASD/ LFD	33 ft	Unknown	Approved 10/30/04 (submitted 12/11/03)
SSL, LLC 4740 Scotts Valley Drive, Suite E Scotts Valley, CA 95066 (831) 430-9300	MSE Plus Wall	Precast concrete 5'x5' facing panels and steel welded wire strip soil reinforcement	ASD/ LFD	33 ft	1999	Approved 10/30/04 (submitted 9/16/03)
Tensar Earth Technologies, Inc. 5883 Glenridge Drive, Suite 200 Atlanta, GA 30328 (404) 250-1290	ARES Wall	Precast concrete 5'x5' facing panels and Tensar geogrid soil reinforcement	ASD/ LFD	33 ft	1998	Approved 10/30/04 (submitted 8/6/04)
Hilfiker Retaining Walls 3900 Broadway P.O. Box 2012 Eureka, CA 95503-5707 (707) 443-5093	Eureka Reinforced Soil Wall	Precast concrete 5'x5' facing panels and welded wire mat soil reinforcement	ASD/ LFD	33 ft	Unknown	
Hilfiker Retaining Walls 3900 Broadway P.O. Box 2012 Eureka, CA 95503-5707 (707) 443-5093	Welded Wire Retaining Wall	Welded wire facing that is continuous with welded wire soil reinforcement	ASD/ LFD	33 ft	Unknown	Approved 10/30/04 (submitted 9/15/03)
Keystone Retaining Wall Systems, Inc. 4444 West 78th Street Minneapolis, MN 55435 (952) 897-1040	KeySystem I Wall	Modular dry cast concrete block facing with steel welded wire ladder strip soil reinforcement	ASD/ LFD	33 ft	2001	Approved 10/30/04 (submitted 3/31/04)

Pre-approved Proprietary Wall Systems

Figure 8-A-13

Wall Supplier	System Name	System Description	ASD/ LFD or LRFD?	Height, or Other Limita-tions	Year Initially Approved	Last Approved Update
Tensar Earth Technologies, Inc. 5883 Glenridge Drive, Suite 200 Atlanta, GA 30328 (404) 250-1290	MESA Wall	Modular dry cast concrete block facing with Tensar geogrid soil reinforcement	ASD/ LFD	33 ft	2000	Approved 10/30/04 (submitted 4/19/04 and 9/22/04)
Nelson Wall 12356 Northup Way, Suite 109 Bellevue, WA 98005 (425) 861-8292	Nelson Wall	Precast concrete gravity wall (similar to Standard Plan Concrete cantilever wall)	ASD/ LFD	28 ft	1995	Approved 10/30/04 (submitted 9/12/03)
The Neel Company	T-Wall	Precast concrete modular wall	ASD/ LFD	25 ft	1994	Approved 11/10/04 (submitted 11/05/04)

Pre-approved Proprietary Wall Systems (Continued)
Figure 8-A-13

Chapter 9 Bearings & Expansion Joints

9.1 Expansion Joints 9-1
9.1.1 General Considerations 9-1
9.1.2 General Design Criteria 9-2
9.1.3 Small Movement Range Joints 9-4
9.1.3.1 Compression Seals 9-4
9.1.3.2 Rapid-Cure Silicone Sealants 9-6
9.1.3.3 Asphaltic Plug Joints 9-8
9.1.4 Medium Movement Range Joints 9-8
9.1.4.1 Steel Sliding Plate Joints 9-8
9.1.4.2 Strip Seal Joints 9-9
9.1.4.3 Bolt-down Panel Joints 9-11
9.1.5 Large Movement Range Joints 9-12
9.1.5.1 Steel Finger Joints 9-12
9.1.5.2 Modular Expansion Joints 9-12
9.1.5.2.1 Operational Characteristics 9-13
9.1.5.2.2 Movement Design 9-14
9.1.5.2.3 Review of Shop Drawings and Structural Design Calculations 9-16
9.1.5.2.4 Construction Considerations 9-17
9.2 Bearings 9-18
9.2.1 General Considerations 9-18
9.2.2 Force Considerations 9-18
9.2.3 Movement Considerations 9-18
9.2.4 Detailing Considerations 9-19
9.2.5 Bearing Types 9-19
9.2.5.1 Elastomeric Bearings 9-19
9.2.5.2 Fabric Pad Sliding Bearings 9-21
9.2.5.3 Pin Bearings 9-23
9.2.5.4 Rocker and Roller Type Bearings 9-23
9.2.5.5 Spherical Bearings 9-23
9.2.5.6 Disk Bearings 9-24
9.2.5.7 Seismic Isolation Bearings 9-24
9.2.6 Miscellaneous Details 9-24
9.2.6.1 Temporary Support before Grouting Masonry Plate 9-24
9.2.6.2 Anchor Bolts 9-25
9.2.7 Contract Drawing Representation 9-25
9.2.8 Shop Drawing Review 9-25
9.2.9 Bearing Replacement Considerations 9-25

Appendix 9-A
Figure 9-A-1 Expansion Joint Details Compression Seal 9-A-1
Figure 9-A-2 Expansion Joint Details Strip Seal 9-A-2
Figure 9-A-3 Silicone Seal Expansion Joint Details 9-A-3

9.1 Expansion Joints

9.1.1 General Considerations

All bridges must accommodate, in some manner, environmentally and self-imposed phenomena that tend to make structures move in various ways. These movements come from several primary sources: thermal variations, concrete shrinkage, creep effects from prestressing, and elastic post-tensioning shortening. With the exception of elastic post-tensioning shortening, which generally occurs before expansion devices are installed, movements from these primary phenomenon are explicitly calculated for expansion joint selection and design. Other movement-inducing phenomena include live loading (vertical and horizontal braking), wind, seismic events, and foundation settlement. Movements associated with these phenomena are generally either not calculated or not included in total movement calculations for purposes of determining expansion joint movement capacity.

With respect to seismic movements, it is assumed that some expansion joint damage may occur, that this damage is tolerable, and that it will be subsequently repaired. In cases where seismic isolation bearings are used, the expansion joints must accommodate seismic movements in order to allow the isolation bearings to function properly.

Expansion joints must accommodate cyclic and long-term structure movements in such a way as to minimize imposition of secondary stresses in the structure. Expansion joint devices must prevent water, salt, and debris infiltration to substructure elements below. Additionally, an expansion joint device must provide a relatively smooth riding surface over a long service life.

Expansion joint devices are highly susceptible to vehicular impact that results as a consequence of their inherent discontinuity. Additionally, expansion joints have often been relegated a lower level of importance in the eyes of both designers and contractors. As a result, many of the maintenance problems associated with in-service bridges relate to expansion joints.

One solution to potential maintenance problems associated with expansion joints is to use construction procedures that eliminate the joints from the bridge deck. The two most commonly used methods are called *integral* and *semi-integral* construction. These two terms are sometimes collectively referred to as *jointless bridge* construction. In *integral* construction, concrete end diaphragms are cast monolithically with both the bridge deck and supporting pile substructure. In order to minimize secondary stresses induced in the superstructure, steel piles are generally used in their weak axis orientation relative to the direction of bridge movement. In *semi-integral* construction, concrete end diaphragms are cast monothically with the bridge deck. Supporting girders rest on elastomeric bearings within an L-type abutment. Longer *semi-integral* bridges generally have reinforced concrete approach slabs at their ends. Approach slab anchors, in conjunction with a compression seal device, connect the monolithic end diaphragm to the approach slab. Longitudinal movements are accommodated by diaphragm movement relative to the approach slab, but at the same time resisted by soil passive pressure against the end diaphragm.

Obviously, bridges cannot be built incrementally longer without eventually requiring expansion joint devices. The incidence of approach pavement distress problems increases markedly with increased movement that must be accommodated by the end diaphragm pressing against the backfill. Approach pavement distress includes pavement and backfill settlement and broken approach slab anchors.

WSDOT has implemented *jointless bridge design* by using *semi-integral* construction. Office policy for concrete and steel bridge design is as follows:

Concrete Bridges: Semi-integral design is used for bridges under 400 feet. Use L-type abutments with expansion joints at the bridge ends where bridge length exceeds 400 feet. In situations where bridge skew angle exceed 30 degrees, consult the Expansion Joint Specialist and the Bridge Design Engineer for recommendations and approval.

Steel Bridges: Use L-type abutments with expansion joints at the ends for multiple-span bridges. *Semi-integral* construction may be used in lieu of expansion joints for single span bridges with the approval of the Bridge Design Engineer. In situations where the bridge skew exceeds 30 degrees, consult the Expansion Joint Specialist and the Bridge Design Engineer for recommendations and approval.

In all instances, the use of intermediate expansion joints should be avoided wherever possible.

Because the movement restriction imposed by a bearing must be compatible with the movements allowed by the adjacent expansion joint, expansion joints and bearings must be designed interdependently and in conjunction with the anticipated behavior of the overall structure.

A plethora of manufactured devices exists to accommodate a wide range of expansion joint total movements. Expansion joints can be broadly classified into three categories based upon their total movement range as follows:

Small Movement Joints	Total Movement Range < 1-3/4”
Medium Movement Joints	1-3/4” < Total Movement Range < 5”
Large Movement Joints	Total Movement Range > 5”

9.1.2 General Design Criteria

As mentioned previously, expansion joints must be sized to accommodate the movements of several primary phenomena imposed upon the bridge following installation of its expansion joint devices. Concrete shrinkage, thermal variation, and long-term creep are the three most common primary sources of movement. Calculation of the movements associated with each of these phenomena must include the effects of superstructure type, tributary length, fixity condition between superstructure and substructure, and pier flexibilities.

A. Shrinkage Effects

Accurate calculation of shrinkage as a function of time requires that average ambient humidity, volume-to-surface ratios, and curing methods be taken in consideration as summarized in LRFD Article 5.4.2.3.3. Because expansion joint devices are generally installed in their respective blockouts at least 30 to 60 days following concrete deck placement, they must accommodate only the shrinkage that occurs from that time onward. For most situations, that shrinkage strain can be assumed to be 0.0002 for normal weight concrete in an unrestrained condition. This value must be corrected for restraint conditions imposed by various superstructure types.

$\Delta_{shrink} = \beta \cdot \mu \cdot L_{trib}$

where L_{trib} = tributary length of the structure subject to shrinkage

β = ultimate shrinkage strain after expansion joint installation; estimated as 0.0002 in lieu of more refined calculations

μ = restraint factor accounting for the restraining effect imposed by superstructure elements installed before the concrete slab is cast

= 0.0 for steel girders, 0.5 for precast prestressed concrete girders, 0.8 for concrete box girders and T-beams, 1.0 for concrete flat slabs

B. Thermal Effects

Bridges are subject to all modes of heat transfer: radiation, convection, and conduction. Each mode affects the thermal gradients generated in a bridge superstructure differently. Climatic influences vary geographically resulting in different seasonal and diurnal average temperature variations. Additionally, different types of construction have different thermal "inertia" properties. For example, a massive concrete box girder bridge will be much slower to respond to an imposed thermal stimulus, particularly a diurnal variation, than would a steel plate girder bridge composed of many relatively thin steel elements.

Variation in the superstructure average temperature produces elongation or shortening. Therefore, thermal movement range is calculated using the maximum and minimum anticipated bridge superstructure average temperatures anticipated during the structure's lifetime. The considerations in the preceding paragraph have led to the following maximum and minimum anticipated bridge superstructure average temperature guidelines for design in Washington State:

Concrete Bridges:	0° F to 100° F
Steel Bridges (Eastern Washington)	-30° F to 120° F
Steel Bridges (Western Washington)	0° F to 120° F

Total thermal movement range is then calculated as:

$\Delta_{temp} = \alpha \cdot L_{trib} \cdot \delta T$

where L_{trib} = tributary length of the structure subject to thermal variation

α = coefficient of thermal expansion; 0.000006 in./in./°F for concrete and 0.0000065 in./in./°F for steel

δT = bridge superstructure average temperature range as a function of bridge type and location, as stated previously

In accordance with WSDOT Standard Specifications, contract drawings state dimensions at a normal temperature of 64°F unless specifically noted otherwise. Construction and fabrication activities at average temperatures other than 64°F require the contractor or fabricator to adjust lengths of structural elements and concrete forms accordingly.

Some expansion joint devices are installed in pre-formed concrete blockouts some time after the completion of the bridge deck. In this case, the expansion joint device must be cast into its respective blockout with a gap setting corresponding to the ambient superstructure average temperature at the time the blockouts are filled with concrete. In order to accomplish this, expansion device gap settings must be specified on the contract drawings as a function of superstructure ambient average temperature. Generally, these settings are specified for temperatures of 40°F, 64°F, and 80°F.


9.1.3 Small Movement Range Joints

Elastomeric compression seals, poured sealants, asphaltic plugs, pre-formed closed cell foam, epoxy-bonded elastomeric glands, steel sliding plates and bolt-down elastomeric panels have all been used in the past for accommodating small movement ranges. Current policy is to use compression seals and rapid-cure silicone sealants almost exclusively.

9.1.3.1 Compression Seals

Compression seals are continuous manufactured elastomeric sections, typically with extruded internal web systems, installed within an expansion joint gap to effectively seal the joint against water and debris infiltration. Compression seals are held in place by mobilizing friction against adjacent vertical joint faces. Hence, design philosophy requires that they be sized and installed to always be in a state of compression.

Compression seals can be installed against smooth vertical concrete faces or against steel armoring. When installed against concrete, special concrete nosing material having enhanced impact resistance is typically used. Polymer concrete (both generic and proprietary), polyester concrete, and elastomeric concrete have been used with varying degrees of successful performance. Consult the *Expansion Joint Specialist* for current policy.



Compression Seal Joint
Figure 9-1

In design calculations, the minimum and maximum compressed widths of the seal are generally set at 40% and 85% of the uncompressed width. These measurements are perpendicular to the joint axis. It is generally assumed that the compressed seal width at the normal construction temperature of 64°F is 60% of its uncompressed width. For skewed joints, bridge deck movement must be separated into components perpendicular to and parallel to the joint axis. Shear displacement of the compression seal should be limited to a specified percentage of its uncompressed width, usually set at about 22%. Additionally, the expansion gap width should be set so that the compression seal can be replaced over a reasonably wide range of construction

temperatures. Manufacturers' catalogues generally specify the minimum expansion gap widths into which specific size compression seals can be installed. The expansion gap width should be specified on the contract drawings as a function of the superstructure average temperature.

Compression seal movement design relationships can be expressed as:

$\Delta_{temp\text{-}normal} = \Delta_{temp} \cdot \cos\theta$ [thermal movement normal to joint]

$\Delta_{temp\text{-}parallel} = \Delta_{temp} \cdot \sin\theta$ [thermal movement parallel to joint]

$\Delta_{shrink\text{-}normal} = \Delta_{shrink} \cdot \cos\theta$ [shrinkage movement normal to joint]

$\Delta_{shrink\text{-}parallel} = \Delta_{shrink} \cdot \sin\theta$ [shrinkage movement parallel to joint]

$$W_{min} = W_{install} - [(T_{max}\text{-}T_{install}) / (T_{max}\text{-}T_{min})] \cdot \Delta_{temp\text{-}normal} > 0.40 \cdot W$$

$$W_{max} = W_{install} + [(T_{install}\text{-}T_{min})/(T_{max}\text{-}T_{min})] \cdot \Delta_{temp\text{-}normal} + \Delta_{shrink\text{-}normal} < 0.85 \cdot W$$

where θ = skew angle of the expansion joint, measured with respect to a line perpendicular to the bridge longitudinal axis

W = uncompressed width of the compression seal

$W_{install}$ = expansion gap width at installation

$T_{install}$ = superstructure temperature at installation

W_{min} = minimum expansion gap width

W_{max} = maximum expansion gap width

T_{min} = minimum superstructure average temperature

T_{max} = maximum superstructure average temperature

Algebraic manipulation yields:

$$W > (\Delta_{temp\text{-}normal} + \Delta_{shrink\text{-}normal}) / 0.45$$

$$W > (\Delta_{temp\text{-}parallel} + \Delta_{shrink\text{-}parallel}) / 0.22$$

Now, assuming $W_{install} = 0.6 \cdot W$,

$$W_{max} = 0.6 \cdot W + [(T_{install} - T_{min})/(T_{max} - T_{min})] \cdot \Delta_{temp\text{-}normal} + \Delta_{shrink\text{-}normal} < 0.85 \cdot W$$

Rearranging yields:

$$W > 4 \cdot [(T_{install} - T_{min}) / (T_{max} - T_{min}) \cdot \Delta_{temp\text{-}normal} + \Delta_{shrink\text{-}normal}]$$

Design Example:

Given: A reinforced concrete box girder bridge has a total length of 200'. A compression seal expansion joint at each abutment will accommodate half of the total bridge movement. The abutments and expansion joints are skewed 15°. Bridge superstructure average temperatures are expected to range between 0°F and 100°F.

Find: Required compression seal size and construction gap widths at 40°F, 64°F, and 80°F.

Solution:

Step 1: Calculate temperature and shrinkage movement.

Temperature: $\Delta_{temp} = ½(.000006)(100°F)(200')(12"/') = 0.72"$
Shrinkage: $\Delta_{shrink} = ½(.0002)(0.8)(200')(12"/') = \underline{0.19"}$
Total deck movement at the joint: $= 0.91"$

$\Delta_{temp\text{-}normal} + \Delta_{shrink\text{-}normal} = (0.91")(\cos 15°) = 0.88"$

$\Delta_{temp\text{-}parallel} + \Delta_{shrink\text{-}parallel} = (0.91")(\sin 15°) = 0.24"$

Step 2: Determine compression seal width required.

$W > 0.88" / 0.45 = 1.96"$

$W > 0.24" / 0.22 = 1.07"$

$W > 4[(64°F - 0°F) / (100°F - 0°F) \cdot (0.72") + 0.19"] (\cos 15°) = 2.51"$
$\rightarrow$Use a 3" compression seal

Step 3: Evaluate construction gap widths for various temperatures for a 3" compression seal.

Construction width at 64°F = 0.6(3") = 1.80"

Construction width at 40°F = 1.80" + [(64° - 40°)/(100° + 0°)]·(0.72")·(cos 15°) = 1.97"

Construction width at 80°F = 1.80" – [(80° - 64°)/(100° + 0°)]·(0.72")·(cos 15°) = 1.69"


Conclusion: Use a 3" compression seal. Construction gap widths for installation at temperatures of 40°F, 64°F, and 80°F are 2", 1-13/16", and 1-11/16" respectively.

9.1.3.2 Rapid-Cure Silicone Sealants

Durable low-modulus poured sealants provide watertight expansion joint seals in both new construction and rehabilitation projects. Most silicone sealants possess good elastic performance over a wide range of temperatures while demonstrating high levels of resistance to ultraviolet and ozone degradation. Other desirable properties include self-leveling and self-bonding characteristics.

Rapid-curing silicone sealants are particularly good candidates for rehabilitation in situations where significant traffic disruption consequential to extended traffic lane closure is unacceptable. Additionally, unlike compression seals, rapid-cure silicone sealants do not require straight, parallel substrate surfaces in order to create a watertight seal.

Rapid-cure silicone sealants can be installed against either concrete or steel. It is extremely critical that concrete or steel substrates be thoroughly cleaned before the sealant is installed. Some manufacturers require application of specific primers onto substrate surfaces prior to sealant installation in order to enhance bonding. Consult the *Expansion Joint Specialist* for specifics



Rapid-cure Silicone Sealants Joint
Figure 9-2

Rapid-cure silicone sealants should be designed based upon the manufacturer's recommendations. Maximum and minimum working widths of the poured sealant joint are generally recommended as a percentage of the sealant width at installation. Depending upon the manufacturer, these joints can accommodate tensile movements of up to 100% and compressive movements of up to 50% of the sealant width at installation. A minimum recess is typically required between the top of the roadway surface and the top of the sealant surface. This recess is critical in assuring that tires will not contact the top surface of the sealant and initiate its debonding from substrate material.

Design Example:

Given: An existing 25-year old 160' long single span prestressed concrete girder bridge is scheduled for a concrete overlay. The existing compression seals at each non-skewed abutment are in poor condition, although the existing concrete edges on each side of each expansion joint are in relatively good condition. The expansion gaps at these abutments are 1" wide at a normal temperature of 64°F. Assume that each expansion joint will accommodate half of the total bridge movement. Bridge superstructure average temperatures are expected to range between 0°F and 100°F.

Find: Determine the feasibility of reusing the existing 1" expansion gaps for a rapid cure silicone sealant system retrofit. Assume that the sealant will be installed at an average superstructure temperature between 40°F and 80°F. Manufacturer's recommendations state that Sealant "A" can accommodate 100% tension and 50% compression and that Sealant "B" can accommodate 50% tension and 50% compression.

Solution:

Step 1: Calculate future temperature, shrinkage, and creep movements.

Temperature: Δ_{temp} = ½(.000006)(100°F)(160')(12"/') = 0.58"

Shrinkage: Δ_{shrink} = 0 (Essentially all shrinkage has already occurred.)

Creep: Δ_{creep} = 0 (Essentially all creep has already occurred.)

Step 2: Calculate existing expansion gap widths at average superstructure temperatures of 40°F and 80°F. These are estimated extreme sealant installation temperatures.

G_{40F} = 1.00" + [(64°F-40°F) / (100°F-0°F)]·(.58") = 1.14"

G_{80F} = 1.00" – [(80°F-64°F) / (100°F-0°F)]·(.58") = 0.91"

Step 3: Check sealant capacity if installed at 40°F.

Closing movement = [(100°F – 40°F) / (100°F – 0°F)](.58") = 0.35"

0.35" / 1.14" = 0.31 < 0.50 Sealants "A" and "B"

Opening movement = [(40°F – 0°F) / (100°F – 0°F)](.58") = 0.23"

0.23" / 1.14" = 0.20 < 1.00 Sealant "A"< 0.50 Sealant "B"

Step 4: Check sealant capacity if installed at 80°F.

Closing movement = [(100°F – 80°F) / (100°F – 0°F)](.58") = 0.12"

0.12" / 0.91" = 0.13 < 0.50 Sealants "A" and "B"

Opening movement = [(80°F – 0°F) / (100°F – 0°F)](.58") = 0.46"


0.46" / 0.91" = 0.50 < 1.00 Sealant "A"

= 0.50 Sealant "B"

Conclusion: The existing 1" expansion gap is acceptable for installation of a rapid cure silicone sealant system. Note that Sealant "B" would reach it's design opening limit at 0°F if it were installed at a superstructure average temperature of 80°F. Expansion gap widths at temperatures other than the normal temperature are generally not specified on rapid cure silicone sealant retrofit plans.

9.1.3.3 Asphaltic Plug Joints

Asphaltic plug joints consist of a flexible polymer modified asphalt (PMA) installed in a preformed block out atop a steel plate and backer rod. In theory, asphaltic plug joints provided a seamless smooth riding surface. However, when subjected to high traffic counts, heavy trucks, or substantial acceleration/deceleration traction, the PMS tends to creep, migrating out of the blockouts. As a consequence, we no longer specify the use of asphaltic plug joints.




Asphaltic Plug Joint
Figure 9-3

9.1.4 Medium Movement Range Joints

9.1.4.1 Steel Sliding Plate Joints

Two overlapping steel plates, one attached to the superstructure on each side of the joint, can be used to provide a smooth riding surface across an expansion joint. Unfortunately, steel sliding plates do not generally provide an effective barrier against intrusion of water and deicing chemicals into the joint and onto substructure elements. Consequently, these joints have been supplanted by newer systems, such as strip seals, with improved resistance to water penetration.



Steel Sliding Plate Joint

Figure 9-4

Before the advent of more modern systems, steel sliding plates were specified extensively. Their limited use today include the following specific applications: 1) high pedestrian use sidewalks, 2) modular expansion joint upturns at traffic barriers, 3) roadway applications involving unusual movements (translation and large rotations) not readily accommodated by modular expansion joints. In these applications, the sliding plates are generally galvanized or painted to provide corrosion resistance.


Repeated impact and corrosion have deteriorated many existing roadway sliding steel plate systems. In many instances, the anchorages connecting the sliding plate to the concrete deck have broken. When the integrity of the anchorages has been compromised, the steel sliding plates must generally be removed in their entirety and replaced with a newer, watertight system. Where the integrity of the anchorages has not been compromised, sliding plates can often be retrofitted with poured sealants or elastomeric strip seals.

9.1.4.2 Strip Seal Joints

An elastomeric strip seal system consists of a preformed elastomeric gland mechanically locked into metallic edge rails generally embedded into concrete deck on each side of an expansion joint gap. Unfolding of the elastomeric gland accommodates movement. Steel studs are generally welded to the steel extrusions constituting the edge rails to facilitate anchorage to the concrete deck. Damaged or worn glands can be replaced with minimal traffic disruption.

The metal edge rails effectively armor the edges of the expansion joint, obviating the need for a special impact resistant concrete, usually required at compression seal and poured sealant joints. The designer must select either the standard or special anchorage. The special anchorage incorporates steel reinforcement bar loops welded to intermittent steel plates, which in turn are welded to the extrusion. The special anchorage is generally used for very high traffic volumes or in applications subject to snowplow hits. In applications subject to snowplow hits and concomitant damage, the intermittent steel plates can be detailed to protrude slightly above the roadway surface in order to launch the snowplow blade and prevent it from catching on the forward extrusion.

The special anchorage requires a 9” deep blockout, as opposed to 7” deep for the standard anchorage. The standard anchorage is acceptable for high traffic volume expansion joint replacement projects where block out depth limitations exist.



Strip Seal Joints
Figure 9-5

Design Example:

Given: A steel plate girder bridge has a total length of 600’. It is symmetrical and has a strip seal expansion joint at each end. These expansion joints are skewed 10°. Interior piers provide negligible restraint against longitudinal translation. Bridge superstructure average temperatures are expected to range between –30°F and 120°F during the life of the bridge. Assume a normal installation temperature of 64°F.

Find: Required Type A and Type B strip seal sizes and construction gap widths at 40°F, 64°F, and 80°F. Type A strip seals have a ½” gap at full closure. Type B strip seals are able to fully close, leaving no gap.

Solution:

Step 1: Calculate temperature and shrinkage movement.

Temperature: Δ_{temp} = ½(.0000065)(150°F)(600’)(12”/’) = 3.51”

Shrinkage: Δ_{shrink} = 0.0 (no shrinkage; μ = 0.0 for steel bridge)

Total deck movement at each joint: = 3.51”

$\Delta_{temp\text{-}normal\text{-}closing}$ = (120°F - 64°F) / (120°F + 30°F)(3.51”)(cos 10°)

= 1.29”

$\Delta_{temp\text{-}normal\text{-}opening}$ = (64°F + 30°F) / (120°F + 30°F)(3.51”)(cos 10°)

= 2.17”

Step 2: Determine strip seal size required. Assume a minimum construction gap width of 1-1/2" at 64°F.

Type A: Construction gap width of 1-1/2" at 64°F will not accommodate 1.29" closing with a ½" gap at full closure. Therefore, minimum construction gap width at 64°F must be 1.29" + 0.50" = 1.79"

Size required = 1.79" + 2.17" = 3.96" →Use 4" strip seal

Type B: Construction width of 1-1/2" at 64°F is adequate.

Size required = 1.50" + 2.17" = 3.67" →Use 4" strip seal

Step 3: Evaluate construction gap widths for various temperatures for a 4" strip seal.

Type A: Required construction gap width at 64°F = 0.50" + 1.29"

= 1.79"

Construction gap width at 40°F = 1.79" + (64°F - 40°F) / (64°F + 30°F)·(2.17") = 2.34"

Construction gap width at 80°F = 1.79" – (80°F – 64°F) / (120°F – 64°F)·(1.29") = 1.42"

Type B: Construction gap width of 1-1/2" at 64°F is adequate.


Construction gap width at 40°F = 1.50" + (64°F - 40°F) / (64°F + 30°F)·(2.17") = 2.05"

Construction gap width at 80°F = 1.50" – (80°F – 64°F) / (120°F – 64°F)·(1.29") = 1.13"

Conclusion: Use a 4" strip seal. Construction gap widths for installation at superstructure average temperatures of 40°F, 64°F, and 80°F are 2-5/16", 1-13/16", and 1-7/16" for *Type A* and 2-1/16", 1-1/2", and 1-1/8" for *Type B*. (Note that slightly larger gap settings could be specified for the 4" *Type B* strip seal in order to permit the elastomeric glands to be replaced at lower temperatures at the expense of ride smoothness across the joint.)

9.1.4.3 Bolt-down Panel Joints

Bolt-down panel joints, sometimes referred to as expansion dams, are preformed elastomeric panels internally reinforced with steel plates. Bridging across expansion gaps, these panels are bolted into formed block outs in the concrete deck with either adhesive or expansive anchors. Expansion is accompanied by stress and strain across the width of the bolt-down panel between anchor bolts.




Bolt-down Panel Joint
Figure 9-6

Unfortunately, the anchorages are prone to loosening and breaking out under high-speed traffic. The resulting loose panels and hardware in the roadway present hazards to vehicular traffic, particularly motorcyclists. As a consequence of the increased liability, we no longer specify bolt-down panel joints. On bridge overlay and expansion joint rehabilitation projects, bolt-down panels are being replaced with rapid-cure silicone sealant joints or strip seal joints. For rehabilitation of bridges having low speed or low volume traffic, existing bolt-down panel joints may be retained and/or selective damaged panels replaced.

9.1.5 Large Movement Range Joints

9.1.5.1 Steel Finger Joints

Finger joints have been successfully used to accommodate medium and large movement ranges. They are generally fabricated from steel plate and are installed in cantilever or prop cantilever configurations. The steel fingers must be designed to support traffic loads with sufficient stiffness to preclude excessive vibration. In addition to longitudinal movement, finger joints must also accommodate any rotations or differential vertical deflection across the joint. Finger joints may be fabricated with a slight downward taper toward the ends of the fingers in order to minimize potential for snowplow blade damage. Unfortunately, finger joints do not provide an effective seal against water infiltration. Elastomeric and metal troughs have been installed beneath steel finger joints to catch and redirect runoff water. However, in the absence of routine maintenance, these troughs clog and become ineffective.



Steel Finger Joint
Figure 9-7


9.1.5.2 Modular Expansion Joints

Modular expansion joints are complex, expensive structural systems designed to provide watertight wheel load transfer across expansion joint openings. These systems were developed in Europe and introduced into the U.S. in the 1960s. To date, modular joints have been designed and fabricated to accommodate movements of up to 85”. In Washington State, the largest modular expansion joints will be those for the new Tacoma Narrows Bridge. These joints will accommodate 48” of service movement and 60” of seismic movement. Modular joints are generally shipped in a completely assembled configuration to the construction site in segments no longer than 40.’

9.1.5.2.1 Operational Characteristics

Modular expansion joints comprise a series of steel center beams oriented parallel to the expansion joint axis. Elastomeric strip seals or box-type seals attach to adjacent center beams, preventing infiltration of water and debris. The center beams are supported on support bars, which span in the primary direction of anticipated movement. The support bars are supported on sliding bearings mounted within support boxes. Polytetrafluoroethylene (PTFE) - stainless steel interfaces between elastomeric support bearings and support bars facilitate the unimpeded translation of the support bars as the expansion gap opens and closes. The support boxes rest on either cast-in-place concrete or grout pads installed into a preformed block out.

Modular joints can be classified as either *single support bar* systems or *multiple support bar* systems. In *multiple support bar* systems, a separate support bar supports each center beam. In the more complex *single support bar* system, one support bar supports all center beams at each support location. This design concept requires that each center beam be free to translate along the longitudinal axis of the support bar as the expansion gap varies. This is accomplished by attaching steel yokes to the underside of the center beams. The support bar passes through the openings in the yokes. Elastomeric springs between the underside of each center beam and the top of the support bar and between the bottom of the support bar and bottom of the yoke support each center beam and permit it to translate along the longitudinal axis of the support bar. Practical center beam span lengths limit the use of *multiple support bar* systems for larger movement range modular expansion joints. *Multiple support bar* systems typically become impractical for more than nine seals or for movement ranges exceeding 27”. Hence, the *single support bar* concept typifies these larger movement range joints.



Modular Expansion Join
Figure 9-8

The highly repetitive nature of axle loads predisposes modular joint components and connections to fatigue susceptibility, particularly at center beam to support bar connections and center beam field splices. Bolted connections of center beams to support bar have demonstrated poor fatigue endurance. Welded connections are preferred, but must be carefully designed, fatigue tested, fabricated, and inspected to assure satisfactory fatigue resistance. Our current special provision for modular expansion joints includes stringent fatigue based design criteria for modular expansion joints. This special provision also specifies criteria for manufacturing, shipping, storing, and installing modular expansion joints.

Consequential to practical shipping restraints or project staging, modular expansion joints may need to be shipped and/or installed in two or more pieces and subsequently spliced together. Splicing generally occurs after concrete is cast into the block outs. The center beams are the elements that must be connected. These field connections are either welded, bolted, or a hybrid combination of both.

Center beam field splices have historically been the weak link of modular expansion joints because of their high fatigue susceptibility and their tendency to initiate progressive zipper-type failure. Contributing to this susceptibility is the fact that the level of control that can be achieved over a field operation is significantly less than that achievable in a shop. Specific recommendations regarding center beam field splices will be subsequently discussed as they relate to shop drawing review and construction.

9.1.5.2.2 Movement Design

Calculated total movement range establishes modular expansion joint size. WSDOT policy has been to provide a 15% factor of safety on these calculated service movements. Current systems permit 3” of movement per elastomeric seal element; hence total movement rating provided will be a multiple of 3”. To minimize impact and wear on bearing elements, the maximum gap between adjacent center beams should be limited to about 3-1/2”.

To facilitate the installation of the modular joints at temperatures other than the 64°F normal temperature, the contract drawings shall specify expansion gap distance face-to-face of edge beams as a function of the superstructure temperature at the time of installation.

Modular expansion joint movement design relationships can be expressed as:

$n = MR / mr$

$G_{min} = (n-1) \cdot w + n \cdot g$

$G_{max} = G_{min} + M7R$

where MR = total movement range of the modular joint

mr = movement range per elastomeric seal

n = number of seals

n – 1 = number of center beams

w = width of each center beam

g = minimum gap per strip seal element at full closure

G_{min} = minimum distance face-to-face of edge beams

G_{max} = maximum distance face-to-face of edge beams

Design Example:

Given: Two cast-in-place post-tensioned concrete box girder bridge frames meet at an intermediate pier where they are free to translate longitudinally. Skew angle is 0° and the bridge superstructure average temperature ranges from 0°F to 120°F. A modular bridge expansion joint will be installed 60 days after post-tensioning operations have been completed. Specified creep is 150% of elastic shortening. Assume that 50% of total shrinkage has already occurred at installation time. The following longitudinal movements were calculated for each of the two frames:

	Frame A	Frame B
Shrinkage	1.18”	0.59”
Elastic Shortening	1.42”	0.79”
Creep (1.5 x Elastic Shortening)	2.13”	1.18”
Temperature Fall (64°F to 0°F)	3.00”	1.50”
Temperature Rise (64°F to 120°F)	2.60”	1.30”

Find: Modular expansion joint size required to accommodate the total calculated movements and the installation gaps measured face-to-face of edge beams at superstructure average temperatures of 40°F, 64°F, and 80°F.

Solution:

Step 1: Determine modular joint size.

Total opening movement (Frame A) = (0.5)·(1.18”) + 2.13” + 3.00”

= 5.72”

Total opening movement (Frame B) = (0.5)·(0.59”) + 1.18” + 1.50”

= 2.98”

Total opening movement (both frames) = 5.72” + 2.98” = 8.70”

Total closing movement (both frames) = 2.60” + 1.30” = 3.90”

Determine size of the modular joint, including a 15% allowance:

1.15·(8.70” + 3.90”) = 14.49” →Use a 15” movement rating joint

Step 2: Evaluate installation gaps measured face-to-face of edge beams at superstructure average temperatures of 40°F, 64°F, and 80°F.

MR = 15” (movement range)

mr = 3” (maximum movement rating per strip seal element)

n = 15”/3” = 5 strip seal elements

n - 1 = 4 center beams

w = 2.50” (center beam top flange width)

g = 0”

G_{min} = 4·(2.50”) + 4·(0”) = 10”

G_{max} = 10” + 15” = 25”

G_{64F} = G_{min} + Total closing movement from temperature rise

= 10” + 1.15·(3.90”) = 14.48” →Use 14-1/2”

G_{40F} = 14.5” + [(64°F-40°F) / (64°F-0°F)]·(3.00” + 1.50”) = 16.19”

G_{80F} = 14.5” – [(80°F-64°F) / (120°F-64°F)]·(2.60” + 1.30”) = 13.39”

Check spacing between center beams at minimum temperature:

G_{0F} = 14.50” + 8.70” = 23.20”

Spacing = [23.20” – 4(2.50”)] / 5 = 2.64” < 3-1/2” →OK

Check spacing between center beams at 64°F for seal replacement:

Spacing = [14.50” – 4(2.50”)] / 5 = 0.90” < 1.50” Therefore, the center beams must be mechanically separated in order to replace strip seal elements.

Conclusion: Use a 15” modular expansion joint. The gaps measured face-to-face of edge beams at installation temperatures of 40°F, 64°F, and 80°F are 16-3/16”, 14-1/2” and 13-3/8”, respectively.

9.1.5.2.3 Review of Shop Drawings and Structural Design Calculations

The manufacturer’s engineer generally performs structural design of modular expansion joints. The project special provisions should require that the manufacturer submit structural calculations, detailed fabrication drawings, and applicable fatigue tests for approval by the Engineer. All structural elements must be designed and detailed for both strength and fatigue. Additionally, modular expansion joints should be detailed to provide access for inspection and periodic maintenance activities, including replacement of seals, control springs, and bearing components.

Our latest special provision for modular expansion joints delineates explicit requirements for their design, fabrication, and installation. This comprehensive special provision builds upon the department’s past experience specifying modular expansion joints and incorporates the NCHRP Report 402 *Fatigue Design of Modular Bridge Expansion Joints*. The special provisions include requirements for the shop drawings, calculations, material certifications, general fabrication methods, corrosion protection, shipping and handling, storage, installation, fatigue testing, applicable welding codes and certifications, quality control, and quality assurance. It is strongly advised to carefully review this special provision before reviewing modular expansion joint shop drawings and calculations.

Any structural details, including connections, that do not clearly correspond to specific fatigue categories depicted in the LRFD shall be fatigue tested in accordance with the requirements stipulated in the special provision. Documentation of these tests shall accompany the shop drawing submittal.

As stated in the special provisions, the Contractor shall submit documentation of a quality assurance program distinctly separate from in-house quality control. Quality assurance shall be performed by an independent agency and shall be provided by the manufacturer.

Weld procedures shall be submitted for all shop and field welds. These procedures stipulate welding process employed, end preparation of the component welded, weld metal type, preheat temperature, and welder certifications. As alluded to previously, it is very critical that all welds be made in strict accordance with specifications and under very careful inspection.

Field splices of center beams require particularly careful review. Our special provision recommends several mitigating measures to minimize fatigue susceptibility of center beam field splices. These measures include reducing support box spacing and optimizing fatigue stress range at field splice locations. Keep in mind that the confined nature of the space in which a welder must work can make these welds very difficult to complete. The AWS Welding Code prequalifies certain end geometries because experience has shown that high quality welds can be achieved.

Non-prequalified center beam end geometries require the contractor to submit a Procedure Qualification Record documenting that satisfactory weld quality has been achieved using samples before welding of the actual field piece. The contractor will generally want to avoid the additional expense associated with these tests and will thus specify a prequalified end geometry.

Our special provisions require that adequate concrete consolidation can be achieved underneath all support boxes. The reviewer should ascertain that the shop drawings detail a vertical minimum of 2" between the bottom of each support box and the top of the concrete block out. Alternatively, when vertical clearance is minimal, grout pads can be cast underneath support boxes before casting the concrete within the blockout.

9.1.5.2.4 Construction Considerations

Temperature adjustment devices are temporarily welded to the modular expansion joints to permit the Contractor to adjust the modular joint width so that it is consistent with the superstructure temperature at the time concrete is placed in the block out. The temperature devices effectively lock up the modular joint. Once the concrete begins to set up, it is critical to remove these devices as soon as possible. If the modular joint is prevented from opening and closing, it will be subject to very large, potentially damaging, forces.

Prior to placement of concrete into the block out, temporary supports bridging across the expansion gap suspend the modular joint from the bridge deck surface. Following concrete placement, the modular joint is supported by bearing of the support boxes on concrete that has consolidated underneath the blockout. The inspector should assure that adequate concrete consolidation is achieved underneath and around the support boxes.

Following delivery of the modular joint to the jobsite and prior to installation, the inspector should ascertain that center beam end geometries at field weld splice locations match those shown on the approved weld procedure.

9.2 Bearings

9.2.1 General Considerations

Bridge bearings facilitate the transfer of vehicular and other environmentally imposed loads from the superstructure down to the substructure, and ultimately, to the ground. In fulfilling this function, bearings must accommodate anticipated movements (thermal expansion/contraction) while also restraining undesired movements (seismic displacements). Because the movements allowed by an adjacent expansion joint must be compatible with the movement restriction imposed by a bearing, bearings and expansion joints must be designed interdependently and in conjunction with the anticipated behavior of the overall structure.

Numerous types of bearings are used for bridges. These include steel reinforced elastomeric bearings, fabric pad sliding bearings, steel pin bearings, rocker bearings, roller bearings, steel pin bearings, pot bearings, spherical bearings, disk bearings, and seismic isolation bearings. Each of these bearings possess different characteristics vis-à-vis vertical and horizontal load carrying capacity, vertical stiffness, horizontal stiffness, and rotational stiffness. A thorough understanding of these characteristics is essential for economical bearing selection and design. Spherical bearings, disk bearings, and pot bearings are sometimes collectively referred to as high load multi-rotational (HLMR) bearings.

9.2.2 Force Considerations

Bridge bearings must be explicitly designed to transfer all anticipated loads from the superstructure to the substructure. These forces may be directed vertically, longitudinally, or transversely with respect to the global orientation of the bridge. In accordance with LRFD provisions, most bearing design calculations are based upon service limit state stresses. Impact need not be applied to live load forces in the design of bearings.

Experience has empirically led to the following practical load capacity approximations for various bearing types:

Bearing Type	Approx. Load Capacity
Standard Elastomeric (Method A)	Less than 450 kips
High-load Elastomeric (Method B)	Less than 800 kips
Fabric Pad	Less than 600 kips
Steel Pin	More than 600 kips
Spherical and Disk	More than 800 kips
Seismic Isolation	Less than 800 kips

9.2.3 Movement Considerations

Bridge bearings can be detailed to provide translational fixity, to permit free translation in any horizontal direction, or to permit guided translation. The movement restrictions thus imposed by a bearing must be compatible with the movements allowed by an adjacent expansion joint. Additionally, both bearings and expansion joints must be designed consistent with the anticipated load and deformation behavior of the overall structure. Design rotations shall be calculated as follows:

A.) Elastomeric and Fabric Pad Bearings

The maximum service limit state rotation for bearings that do not have the potential to achieve hard contact between metal components shall be taken as the sum of unfactored dead and live load rotations plus an allowance for fabrication and construction uncertainties of 0.005 radians.

B.) HLMR Bearings

The maximum strength limit state load rotation for bearings that are subject to potential hard contact between metal components shall be taken as the sum of all applicable factored load rotations plus an allowance of 0.01 radians for fabrication and installation tolerances and an allowance of 0.01 radians for other uncertainties. Such bearings include spherical, disk, pot, steel pin and some types of seismic isolation bearings.

9.2.4 Detailing Considerations

HLMR bearings shall be designed, detailed, fabricated, and installed to facilitate inspection, maintenance, and eventual replacement. Jacking points shall be identified in the contract drawings so that bearings can be reset, repaired, or replaced. In some instances, bearings may need to be reset in order to mitigate unintended displacements induced by construction sequences.

Prestressed concrete girder bridges having end type "A" (integral end diaphragms) need not be detailed to accommodate elastomeric bearing replacement at abutments. Prestressed concrete girder bridges having end type "B" (L-type abutments) shall be designed and detailed to accommodate elastomeric bearing replacement at abutments. Specifically, girder stops and end diaphragms shall be detailed to accommodate the placement of hydraulic jacks. The standard end diaphragms for long-span girders may not have sufficient flexural and shear capacity to support jacking-induced stresses. The designer shall check these and provide sufficient steel reinforcement to accommodate shear forces and moments induced by jacking. (Girder end types "A" and "B" are depicted on Figures 5-66 and 5-67.) Incidentally, intermediate piers of prestressed concrete girder bridges having steel reinforced elastomeric bearings shall also be designed and detailed to facilitate bearing replacement.

9.2.5 Bearing Types

9.2.5.1 Elastomeric Bearings

Elastomeric bearings are perhaps the simplest and most economical of all bridge bearings. They are broadly classified into four types: plain elastomeric pads, fiberglass reinforced elastomeric pads, steel reinforced elastomeric pads, and cotton duck reinforced elastomeric pads. Of these four types, only the latter two are used extensively for bridge construction. Incidentally, cotton duck reinforced elastomeric pads are generally referred to as fabric pad bearings. This subsection will address steel reinforced elastomeric bearings. A subsequent section will address fabric pad bearings.

A steel reinforced elastomeric bearing consists of discrete steel shims vulcanized between adjacent discrete layers of elastomer. The vulcanization process occurs in an autoclave under conditions of high temperature and pressure. The constituent elastomer is either natural rubber or synthetic rubber (neoprene). Steel reinforced elastomeric bearings are commonly used with prestressed concrete girder bridges and may be used with other bridge types. Because of their relative simplicity and minimal fabrication effort, steel reinforced elastomeric bearings offer significant economy relative to HLMR bearings.

Steel reinforced elastomeric bearings rely upon the inherent shear flexibility of the elastomer layers to accommodate bridge movements in any horizontal direction. This shear flexibility also enhances their rotational flexibility. The steel shims limit the tendency for the elastomer layers to bulge laterally.

Standard steel reinforced elastomeric bearings are designed by the Method A procedure delineated in the LRFD provisions. High-load steel reinforced elastomeric bearings are designed by the Method B procedure. The Method B procedure allows 60% higher compressive stress. This higher stress is justified by an additional acceptance test, specifically a long-duration compressive load test. Because of the additional expense associated with the long-duration compression test, the Method B procedure should be used only in cases where the additional vertical load carrying capacity is required.

Both Method A and Method B design procedures require determination of the optimal geometric parameters to achieve an appropriate balance of compressive, shear, and rotational stiffnesses and capacities. Fatigue susceptibility is controlled by limiting live load compressive stress. Delamination (of steel shim-elastomer interface) susceptibility is controlled by limiting total compressive stress. Assuring adequate shim thickness precludes yield and rupture of the steel shims. Excessive shear deformation is controlled and rotational flexibility is assured by providing adequate total elastomer height. Generally, total elastomer thickness shall be no less than twice the maximum anticipated lateral deformation. Overall bearing stability is controlled by limiting total bearing height relative to its plan dimensions. The most important design parameter for reinforced elastomeric bearings is the *shape factor*. The *shape factor* is defined as the plan area of the bearing divided by the area of the perimeter free to bulge (perimeter multiplied by thickness of one layer of elastomer).

In essence, elastomeric bearing design reduces to checking several mathematical equations while varying bearing plan dimensions, number of elastomeric layers and their corresponding thicknesses, and steel shim thicknesses. Because these calculations can become rather tedious, MS Excel spreadsheets have been developed and are available for designs using both Method A and Method B procedures. See the *Bearings and Expansion Joint Specialist* for these design tools.

LRFD design will often result in thicker steel reinforced elastomeric bearings than previous designs, particularly for shorter span bridges. This is consequent partially to the increased rotational flexibility required to accommodate the 0.005 radian allowance and partially to inherent conservatism built into the rotational capacity equations. NCHRP research is currently investigating the latter to determine if code changes are needed, given that elastomeric bearings designed by previous, less stringent criteria have performed quite well.

Elastomeric bearings shall conform to the requirements of AASHTO Specification M 251 *Plain and Laminated Elastomeric Bridge Bearings*. Generally, steel reinforced elastomeric bearings shall be fabricated from 60 durometer elastomer. Shims shall be fabricated from ASTM A 1011 Grade 36 steel unless noted otherwise on the plans. Bearings shall be laminated in ½ inch thick elastomeric layers with a minimum total thickness of 1 inch. For overall bearing heights less than 3 inches, a minimum of 1/8 inch of side clearance shall be provided over the steel shims. For overall heights between 3 inches and 7 inches, a minimum of ¼ inch of side clearance shall be provided. For overall heights greater than 7 inches, a minimum of ½ inch of side clearance shall be provided. Live load compressive deflection shall be limited to 1/16 inch. AASHTO Specification M 251 requires elastomeric bearings to be subjected to a series of tests, including a compression test at 150% of the total service load. For this reason, compressive dead load and live load shall be specified on the plans.

In the construction of precast prestressed concrete girder and steel girder bridges, elastomeric bearings are generally not offset to account for temperature during erection of the girders as are most other bearing systems. Girders may be set atop elastomeric bearings at temperatures other than the mean of the temperature range. This is statistically reconciled by assuming a maximum thermal movement in either direction of:

$$\Delta_{temp} = 0.75 \cdot L \cdot (T_{MaxDesign} - T_{MinDesign})$$

where $T_{MaxDesign}$ is the maximum anticipated bridge deck average temperature and $T_{MinDesign}$ is the minimum anticipated bridge deck average temperature during the life of the bridge.

For precast prestressed concrete girder bridges, the thermal movement shall be added to shrinkage and long-term creep movements to determine total bearing height required. The shrinkage movement for this bridge type shall be half that calculated for a cast-in-place concrete bridge.

For cast-in-place concrete bridges, it is assumed that the temperature of concrete at the time of casting is equal to the normal temperature, as defined by the *Standard Specifications*. Total shrinkage movement is added to thermal contraction movement to determine required total height of the elastomeric bearing, as noted in Section 9.1.2 A.

9.2.5.2 Fabric Pad Sliding Bearings

Fabric pad sliding bearings incorporate fabric pads with a polytetrafluoroethylene (PTFE) - stainless steel sliding interface to permit large translational movements. Unlike a steel reinforced elastomeric bearing, the fabric pad alone cannot accommodate translational movements. Fabric pads can accommodate very small amounts of rotational movement; less than can be accommodated by more flexible steel reinforced elastomeric bearings. Practical size considerations limit the use of fabric pad bearings to total service load reactions under about 500 kips.

PTFE, also referred to as Teflon, is available in several forms: unfilled sheet, dimpled lubricated, filled, and woven. Filled PTFE contains glass, carbon, or other chemically inert fibers that enhance its resistance to creep (cold flow) and wear. Interweaving high strength fibers through PTFE material creates woven PTFE. Dimpled PTFE contains dimples, which act as reservoirs for silicone grease lubricant.

Friction coefficients for PTFE – stainless steel surfaces vary significantly as a function of PTFE type, contact pressure, and ambient temperature. The AASHTO LRFD provides friction coefficients as a function of these variables. Dimpled lubricated PTFE at high temperatures and high contact pressures typically yield the lowest friction coefficients. Filled PTFE at low temperatures and low contact pressures yield the highest friction coefficients.

In order to minimize frictional resistance, a Number 8 (Mirror) Finish should be specified for all flat stainless steel surfaces in contact with PTFE. The low-friction characteristics of a PTFE – stainless steel interface are actually facilitated by PTFE sliding against PTFE after PTFE particles are absorbed into the asperities of the stainless steel surface.

In fabric pad sliding bearings, the PTFE is generally recessed half its depth into a steel backing plate, which is generally bonded to the top of a fabric pad. The recess provides confinement that minimizes creep (cold flow). The stainless steel sheet is typically seal welded to a steel sole plate attached to the superstructure.

Silicone grease is not recommended for non-dimpled PTFE. Any grease will squeeze out under high pressure and attract potentially detrimental dust and other debris.

A.) Fabric Pad Design

Our office design criteria for fabric pad bearings are based upon manufacturers' recommendations, supported by years of satisfactory performance. These criteria differ from AASHTO LRFD provisions in that they recognize significantly more rotational flexibility in the fabric pad. Our maximum allowable service load average bearing pressure for fabric pad bearing design is 1200 psi. Our maximum allowable service load

edge bearing pressure for fabric pad bearing design is 2000 psi. A 1200 psi compressive stress corresponds to 10% strain in the fabric pad while a 2000 psi compressive stress corresponds to 14% compressive strain. Based upon this information, the following design relationship can be established:

$$\Theta \equiv \frac{2 \cdot (.14 - .10) \cdot T}{L}$$

$$\Theta \equiv \frac{.08 \cdot T}{L}$$

$$T \equiv 12.5 \cdot \Theta \cdot L$$

where Θ = rotation due to loading plus construction tolerances

L = pad length (parallel to longitudinal axis of beam)

T = fabric pad thickness required

As an example:

Given: DL + LL = 240 kips

Rotation = 0.015 radians

Allowable bearing pad pressure = 1200 psi

f_c' = 3000 psi

Find: fabric pad plan area and thickness required

Solution:

Pad area required = 240,000 / 1200 = 200 in^2

Try a 20" wide x 10" long fabric pad

T = 12.5(.015)(10") = 1.88"

Solution: Use a 20" x 10" x 1-7/8" fabric pad.

B.) PTFE – Stainless Steel Sliding Surface Design

PTFE shall be 1/8" thick and recessed 1/16" into a ½" thick steel plate that is bonded to the top of the fabric pad. With the PTFE confined in this recess, the LRFD code permits an average contact stress of 6000 psi for all loads calculated at the strength limit state and an average contact stress of 4000 psi for permanent loads calculated at the strength limit state. The LRFD code permits slightly higher edge contact stresses.

For example, suppose:

DL = 150 kips

LL = 90 kips

A_{PTFE} > [(1.25)(150 kips) + (1.75)(90 kips)] / 6 ksi = 57.5 in^2

A_{PTFE} > (1.25)(150 kips) / 4 ksi = 46.9 in^2

Selected area of PTFE must exceed 57.5 in^2

Stainless steel sheet shall be finished to a Number 8 Finish and seal welded to the sole plate.

9.2.5.3 Pin Bearings

Steel pin bearings are generally used to support heavy reactions with moderate to high levels of rotation about a single predetermined axis. This situation generally occurs with long straight steel plate girder superstructures.

9.2.5.4 Rocker and Roller Type Bearings

Steel rocker bearings have been used extensively in the past to allow both rotation and longitudinal movement while supporting large loads. Because of their seismic vulnerability and the more extensive use of steel reinforced elastomeric bearings, rocker bearings are no longer specified for new bridges.

Steel roller bearings have also been used extensively in the past. Roller bearings permit both rotation and longitudinal movement. Pintles are generally used to connect the roller bearing to the superstructure above and to the bearing plate below. Nested roller bearings have also been used in the past. Having been supplanted by more economical steel reinforced elastomeric bearings, roller bearings are infrequently used for new bridges today.

9.2.5.5 Spherical Bearings

A spherical bearing relies upon the low-friction characteristics of a curved PTFE - stainless steel interface to provide a high level of rotational flexibility in multiple directions. An additional flat PTFE - stainless steel surface can be incorporated into the bearing to additionally provide either guided or non-guided translational movement capability.

Woven PTFE is generally used on the curved surfaces of spherical bearings. Woven PTFE exhibits enhanced creep (cold flow) resistance and durability characteristics relative to unwoven PTFE. When spherical bearings are detailed to accommodate translational movement, woven PTFE is generally specified on the flat sliding surface also. The LRFD code permits an average contact stress of 6000 psi for all loads calculated at the strength limit state and an average contact stress of 4000 psi for permanent loads calculated at the strength limit state. The LRFD code permits slightly higher edge contact stresses.

Both stainless steel sheet and solid stainless steel have been used for the convex sliding surface of spherical bearings. According to one manufacturer, sheet is generally acceptable for contact surface radii greater than 14” to 18.” For smaller radii, a solid stainless steel convex plate or a stainless steel inlay is used. The inlay is welded to the solid conventional steel. Solid stainless steel can be rather expensive. Consequently, if the total height of the convex plate exceeds about 5”, a stainless steel inlay will likely be used.

Most spherical bearings are fabricated with the concave surface oriented downward to minimize dirt infiltration between PTFE and the stainless steel surface. Finite element modeling of the overall structure must recognize that the center of rotation of the bearing is not coincident with the neutral axis of the girder above.

The contract drawings must show the diameter and height of the spherical bearing in addition to all dead, live, and seismic loadings. Total height depends upon the radius of the curved surface, diameter of the bearing, and total rotational capacity required. Consult the *Expansion Joints and Bearings Specialist* for design calculation examples. Additionally, sole plate connections, base plate, anchor bolts, and any appurtenances for horizontal force transfer must be detailed on the plans. The spherical bearing manufacturer is required to submit shop drawings and detailed structural design calculations of spherical bearing components for review by the Engineer.

9.2.5.6 Disk Bearings

A disk bearing is composed of an annular shaped urethane disk designed to provide moderate levels of rotational flexibility. A steel shear-resisting pin in the center provides resistance against lateral force. A flat PTFE - stainless steel surface can be incorporated into the bearing to also provide translational movement capability, either guided or non-guided.

9.2.5.7 Seismic Isolation Bearings

Seismic isolation bearings mitigate the potential for seismic damage by utilizing two related phenomena: dynamic isolation and energy dissipation. Dynamic isolation allows the superstructure to essentially float, to some degree, while substructure elements below move with the ground during an earthquake. The ability of some bearing materials and elements to deform in certain predictable ways allows them to dissipate earthquake energy that might otherwise damage critical structural elements.

Numerous seismic isolation bearings exist, each relying upon varying combinations of dynamic isolation and energy dissipation. These devices include lead core elastomeric bearings, high damping rubber, friction pendulum, hydraulic dampers, and various hybrid variations.

Effective seismic isolation bearing design requires a thorough understanding of the dynamic characteristics of the overall structure as well as the candidate isolation devices. Isolation devices are differentiated by maximum compressive load capability, lateral stiffness, lateral displacement range, maximum lateral load capability, energy dissipation per cycle, functionality in extreme environments, resistance to aging, fatigue and wear properties, and effects of size.

The Highway Innovative Technology Evaluation Center (HITEC) has developed guidelines for testing seismic isolation and energy dissipating devices. With the goal of disseminating objective information to design professionals, HITEC has tested and published technical reports on numerous proprietary devices. These tests include performance benchmarks, compressive load dependent characterization, frequency dependent characterization, fatigue and wear, environmental aging, dynamic performance at extreme temperatures, durability, and ultimate performance.

For further guidance, see Section 4.6.8 Base Isolation and Energy Disspation Devices.

9.2.6 Miscellaneous Details

9.2.6.1 Temporary Support before Grouting Masonry Plate

The masonry plate of a HLMR bearing is generally supported on a grout pad that is installed after the bearing and superstructure girders above have been erected. This procedure allows the contractor to level and slightly adjust the horizontal location of the bearing before effectively "locking" it in place by casting the grout pad. Several methods have been developed to temporarily support the masonry plate until the grout is placed. The two most commonly used methods will be discussed here.

A.) Shim Packs

Multiple stacks of steel shim plates can be placed atop the concrete surface to temporarily support the weight of the girders on their bearings before grouting. Engineering judgment must be used in selecting the number and plan size of the shims taking grout flowability and shim height adjustability into consideration.

B.) Two-step Grouting with Cast Sleeves

A two-step grouting procedure with cast-in-place voided cores can be used for smaller HLMRs not generally subjected to uplift. Steel studs are welded to the underside of the masonry plate to coincide with the voided cores. With temporary shims installed between the top of the concrete surface and the underside of the masonry plate, the voided cores are fully grouted. Once the first stage grout has attained strength, the shims are removed, the masonry plate is dammed, and grout is installed between the top of the concrete surface and the underside of the masonry plate.

9.2.6.2 Anchor Bolts

Anchor bolts shall be designed to resist all horizontal shear forces and direct tension force due to uplift.

Anchor bolts shall be ASTM A 449 where strengths equal to ASTM A 325 are required and ASTM A 354, Grade BD, where strengths equal to ASTM A 490 are required. ASTM F 1554 bolts with supplemental Charpy test requirements shall be specified in applications in which the bolts are subject to seismic loading.

9.2.7 Contract Drawing Representation

High load multi-rotational bearings are generally depicted schematically in the contract drawings. Each bearing manufacturer has unique fabricating methods and procedures that allow it to fabricate a bearing most economically. Depicting the bearings schematically with loads and geometric requirements provides each manufacturer the flexibility to innovatively achieve optimal economy.


9.2.8 Shop Drawing Review

The manufacturer designs and develops shop drawings for high load multi-rotational bearings. The engineer is responsible for checking and approving the calculations and shop drawings. Calculations shall verify the structural adequacy of all components of the bearing. Each bearing shall be detailed to permit inspection and replacement of components.

9.2.9 Bearing Replacement Considerations

In some situations, existing bearings, or elements thereof, must be replaced consequent to excessive wear or seismic rehabilitation. Bearing replacement operations generally require lifting of superstructure elements using hydraulic jacks. The designer is responsible for calculating anticipated lifting loads and stipulating these loads on the contract drawings. Limitations on lift height shall also be specified. Consideration shall be given to lift height as it relates to adjacent expansion joints elements and adjoining sections of railing. Stresses induced as a consequence of differential lift height between multiple hydraulic jacks are generally addressed by stipulating restrictions in the plans or special provisions.


Past experience shows that actual lifting loads nearly always exceed calculated lifting loads. Many factors may contribute to this phenomenon, including friction in the hydraulic jack system and underestimation of superstructure dead loads. Unless the Expansion Joints and Bearings Specialist or the Bridge Design Engineer approves a variance, contract documents shall require that all hydraulic jacks be sized for 200% of the calculated lifting load. In all cases, the designer shall verify from manufacturer's literature that appropriate hydraulic jacks are available to operate within the space limitations imposed by a particular design situation.



COMPRESSION SEAL

CONCRETE OPENING

1. USE ⅛" FOR ALL SEALS.
2. USE ½" FOR ALL SEALS.
3. COMPUTE "A CONSTR." PER EQUATION (12) @ 40° F, 64° f, AND 80° F
4. TO BE CHECKED BY THE DESIGNER. SHALL BE LARGE ENOUGH TO PREVENT CLOSURE UNDER THERMAL MOVEMENTS.
5. SEE BDM 8.4.1.A.1 AND EXAMPLE 8.4-B1 FOR COMPRESSION SEAL DESIGN AND SEE "COMPRESSION SEAL" TABLE ON THIS SHEET.



COMPRESSION SEAL

ARMORED OPENING.
USE IN BRIDGE WIDENINGS WITH EXISTING ARMORED JOINTS


NOTE:
DESIGNER TO USE APPROPRIATE DETAILS FROM THIS SHEET AND CONSULT WITH EXPANSION JOINT SPECIALIST FOR LATEST PLAN SHEET LAYOUT, NOTES, AND UP-TO-DATE DETAILS.

COMPRESSION SEAL TABLE


D.S. BROWN		WATSON BOWMAN ACME	
SEAL	W (in.)	SEAL	W (in.)
CV-20	2	WA-200	2
CV-2502	2½	WA-250	2½
CV-30	3	WA-300	3
CV-35	3½	WA-350	3½
CV-40	4	WA-400	4

TESTING SHALL BE PER AASHTO M-220 PRIOR TO USE.


NOTE:
COMPRESSION SEALS GREATER THAN FOUR INCHES WIDE SHOULD NOT BE USED



SECTION A—A




SEAL CUTTING DETAIL




PLAN ~ EXPANSION JOINT

Expansion Joint Details Compression Seal
Figure 9-A-1




STRIP SEAL

STANDARD ANCHORAGE
USE FOR NORMAL TRAFFIC VOLUME
EXTEND SLAB STEEL INTO THE BLOCKOUT




SECTION (A) FOR STRIP SEAL



STRIP SEAL

SPECIAL ANCHORAGE
USE FOR HIGH TRAFFIC VOLUME
REQUIRES 9" x 1'-0" MIN. BLOCKOUT
EXTEND SLAB STEEL INTO THE BLOCKOUT
EXTEND BLOCKOUT TO EDGE OF DECK

* PLACED AFTER EXPANSION JOINT IS IN POSITION. THREAD INTO PLACE FROM THE ENDS.



PLAN ~ EXPANSION JOINT

STEEL SHAPE TYPES

MANUFACTURER	ITEM NAME	S T			W V			Y X		
		TYPE	S	T	TYPE	V	W	TYPE	X	Y
D. S. BROWN	DSB STRIP SEAL	SSCM2	1¼"	8"	SSA2, *	1¼"	2"	SSE2, *	1"	1½"
WATSON BOWMAN ACME	WABO STRIP SEAL	M, R	2¾"	3¼"	A	1¼"	2"	E	1½"	1½"
R.J. WATSON, INC.	RJ STRIP SEAL	RJM	2¾"	3¼"	RJA	1¼"	2"	RJE	1¼"	1½"
HEXCEL FYFE CO.	STRIP J200-C	C	2½"	3"	A	1¼"	2"	E	1⅜"	1½"

* USE TYPE "AM2" STEEL SHAPE WITH TYPE "SEQ" SEAL. USE TYPE "SC" OR "SA" STEEL SHAPE WITH TYPE "SS" SEAL. DESIGNATION TYPE AND DIMENSIONS MAY VARY AS MANUFACTURER'S INVENTORY CHANGES

* TRIM OUTSTANDING LEGS OF SSCM2 SHAPE FOR USE IN TRAFFIC BARRIER

NOTE:
DESIGNER TO USE APPROPRIATE DETAILS FROM THIS SHEET AND CONSULT WITH EXPANSION JOINT SPECIALIST FOR LATEST PLAN SHEET LAYOUT, NOTES, AND UP-TO-DATE DETAILS.

STRIP SEAL NOTES:

1. DESIGNER SHALL INCLUDE APPROPRIATE DETAILS AND TABLES IN THE PLANS.
2. SEE BDM 8.4.1.A.2 AND EXAMPLES 8.4-B2 THROUGH B4 FOR STRIP SEAL DESIGN AND FOR DETERMINING OPENING "G" NORMAL TO THE JOINT. FILL IN AMOUNTS CALCULATED AND STEEL SHAPES SELECTED.
3. FOR SKEW ANGLE GREATER THAN 30° SEE JOINT SPECIALIST.
4. SEE JOINT SPECIALIST PRIOR TO SPECIFYING A 5" MOTION RANGE STRIP SEAL.
5. A GROUP 1 PERMITS A ⅜" GAP BETWEEN STEEL SUPPORTING ELEMENTS AT FULL CLOSURE AND A GROUP 2 STRIP SEAL PERMITS FULL CLOSURE.
6. DO NOT USE STEEL SHAPES WITH HORIZONTAL LEGS IN CURB OR BARRIER REGION.

2" MOTION RANGE

** GROUP	MANUFACTURER	ITEM NAME	OPENING "G" NORMAL TO JT.		MIN. INSTALLATION WIDTH NORMAL TO JOINT	OPENING "G" NORMAL TO JOINT			STEEL SHAPE TYPE
			MIN.	MAX.		@40°F	@64°F	@80°F	
1	D. S. BROWN	DSB STRIP SEAL A2R-400	½"	4½"	11⅝"				
2	WATSON BOWMAN ACME	WABO STRIP SEAL SE-300	0"	3"	11⅝"				
2	R.J. WATSON, INC.	R.J. STRIP SEAL 200	0"	2"	11⅝"				
1	HEXCEL FYFE CO.	STRIP J200-C ES500	¼"	5½"	11⅝"				

3" MOTION RANGE

** GROUP	MANUFACTURER	ITEM NAME	OPENING "G" NORMAL TO JT.		MIN. INSTALLATION WIDTH NORMAL TO JOINT	OPENING "G" NORMAL TO JOINT			STEEL SHAPE TYPE
			MIN.	MAX.		@40°F	@64°F	@80°F	
1	D. S. BROWN	DSB STRIP SEAL A2R-400	½"	4½"	11⅝"				
2	WATSON BOWMAN ACME	WABO STRIP SEAL SE-300	0"	3"	11⅝"				
2	R.J. WATSON, INC.	R.J. STRIP SEAL 300	0"	3"	11⅝"				
1	HEXCEL FYFE CO.	STRIP J200-C ES500	¼"	5½"	11⅝"				

4" MOTION RANGE


** GROUP	MANUFACTURER	ITEM NAME	OPENING "G" NORMAL TO JT.		MIN. INSTALLATION WIDTH NORMAL TO JOINT	OPENING "G" NORMAL TO JT.			STEEL SHAPE TYPE
			MIN.	MAX.		@40°F	@64°F	@80°F	
1	D. S. BROWN	DSB STRIP SEAL A2R-400	½"	4½"	11⅝"				
2	WATSON BOWMAN ACME	WABO STRIP SEAL SE-400	0"	4"	11⅝"				
2	R.J. WATSON, INC.	R.J. STRIP SEAL 400	0"	4"	11⅝"				
1	HEXCEL FYFE CO.	STRIP J200-C ES500	¼"	5½"	11⅝"				


5" MOTION RANGE


** GROUP	MANUFACTURER	ITEM NAME	OPENING "G" NORMAL TO JT.		MIN. INSTALLATION WIDTH NORMAL TO JOINT	OPENING "G" NORMAL TO JT.			STEEL SHAPE TYPE
			MIN.	MAX.		@40°F	@64°F	@80°F	
1	D. S. BROWN	DSB STRIP SEAL L2-500	½"	5½"	11⅝"				
2	WATSON BOWMAN ACME	WABO STRIP SEAL SE-500	0"	5"	11⅝"				
2	R.J. WATSON, INC.	R.J. STRIP SEAL 500	½"	5"	11⅝"				


** GROUP COLUMN NOT TO BE SHOWN IN CONTRACT PLANS. FOR DESIGN PURPOSES ONLY.


Expansion Joint Details Strip Seal
Figure 9-A-2




















CONSTRUCTION STEPS:

1. REMOVE EXISTING POURED RUBBER & JOINT FILLER MATERIAL FROM EXPANSION JOINT.
2. CLEAN SIDES AND BOTTOM OF JOINT OPENING TO CLEAN AND SOUND CONCRETE.
3. BLOW JOINT OPENING WITH OIL-FREE COMPRESSED AIR TO REMOVE LAITANCE AND DEBRIS FROM REMOVAL OPERATIONS.
4. PLACE FORM IN EXISTING JOINT OPENING TO A HEIGHT LEVEL WITH THE FINAL ROADWAY ELEVATION.
5. PLACE MODIFIED CONCRETE OVERLAY TO FINAL RDW'Y ELEVATION.
6. REMOVE FORM FROM JOINT OPENING AND LIGHTLY SANDBLAST TO REMOVE ALL RESIDUE.
7. PRIME VERTICAL FACES OF JOINT IN ACCORDANCE WITH SEALANT MANUFACTURER'S RECOMMENDATION.
8. PLACE AN APPROPRIATELY SIZED BACKER ROD TO THE CORRECT DEPTH IN JOINT OPENING IN ACCORDANCE WITH SEALANT MANUFACTURER'S DIRECTIONS.
9. PLACE RAPID CURE SILICON SEALANT IN ACCORDANCE WITH MANUFACTURER'S DIRECTIONS.







EXPANSION JOINT DETAIL

Silicone Seal Expansion Joint Details

Figure 9-A-3

Chapter 10 Signs, Barriers, Approach Slabs & Utilities

10.1 Sign and Luminaire Supports 10-1
10.1.1 Loads 10-1
10.1.2 Bridge Mounted Signs 10-3
10.1.3 Sign Bridges Mounted on Bridges 10-7
10.1.4 Monotube Sign Structures 10-7
10.1.5 Foundations 10-11
10.1.6 Truss Sign Bridges: Foundation Sheet Design Guidelines 10-12
10.2 Bridge Traffic Barriers 10-13
10.2.1 General Guidelines 10-13
10.2.2 Bridge Railing Test Levels 10-13
10.2.3 Available WSDOT Designs 10-13
10.2.4 Design Criteria 10-17
10.3 At Grade Cast-in-Place Barriers 10-20
10.3.1 Median Barriers 10-20
10.3.2 Shoulder Barriers 10-20
10.4 Bridge Traffic Barrier Rehabilitation 10-21
10.4.1 Policy 10-21
10.4.2 Guidelines 10-21
10.4.3 Design Criteria 10-21
10.4.4 WSDOT Bridge Inventory of Bridge Rails 10-22
10.4.5 Available Retrofit Designs 10-22
10.4.6 Available Replacement Designs 10-22
10.5 Bridge Railing 10-23
10.5.1 Design 10-23
10.5.2 Railing Types 10-23
10.6 Bridge Approach Slabs 10-24
10.6.1 Notes to Region for Preliminary Plan 10-24
10.6.2 Approach Slab Design and Detailing 10-25
10.6.3 Approach Expansion Joints 10-25
10.6.4 Skewed Approach Slabs 10-26
10.6.5 Bridge Approach Approach Detailing 10-27
10.6.6 Pavement Seats on Existing Bridges 10-27
10.7 Traffic Barrier on Approach Slabs 10-28
10.7.1 Approach Slab over Wing Walls, Cantilever Walls or Geosynthetic Walls 10-29
10.7.2 Approach Slab over SE Walls 10-29
10.8 Utilities Installed with New Construction 10-31
10.8.1 General Concepts 10-31
10.8.2 Utility Design Criteria 10-31
10.8.3 Box Girder Bridges 10-33
10.8.4 Traffic Barrier Conduit 10-34
10.8.5 Conduit Types 10-35
10.8.6 Utility Supports 10-35
10.9 Utility Review Procedure for Installation on Existing Bridges 10-37
10.9.1 Utility Review Checklist 10-37
10.10 Drainage Design 10-39

Appendix 10-A

Figure 10-A-1	Monotube Sign Structures Sign Bridge Layout	10-A-1
Figure 10-A-2	Monotube Sign Structures Cantilever Layout	10-A-2
Figure 10-A-3	Monotube Sign Structures Structural Details 1	10-A-3
Figure 10-A-4	Monotube Sign Structures Structural Details 2	10-A-4
Figure 10-A-5	Monotube Sign Structures Foundation Type 1	10-A-5
Figure 10-A-6	Monotube Sign Structures Foundation Types 2 and 3	10-A-6
Figure 10-A-7	Monotube Sign Structures Double Faced Barrier Foundation	10-A-7
Figure 10-A-8	Monotube Sign Structures Single Slope Barrier Foundation	10-A-8
Figure 10-A-9	Truss Sign Structures Double Faced Barrier Foundation	10-A-9
Figure 10-A-10	Traffic Barrier – Shape F Details 1 of 3	10-A-10
Figure 10-A-11	Traffic Barrier - Shape F Details 2 of 3	10-A-11
Figure 10-A-12	Traffic Barrier - Shape F Details 3 of 3	10-A-12
Figure 10-A-13	Traffic Barrier - Shape F Flat Slab - Details 1 of 3	10-A-13
Figure 10-A-14	Traffic Barrier - Shape F Flat Slab - Details 2 of 3	10-A-14
Figure 10-A-15	Traffic Barrier - Shape F Flat Slab - Details 3 of 3	10-A-15
Figure 10-A-16	Traffic Barrier - Single Slope Details 1 of 3	10-A-16
Figure 10-A-17	Traffic Barrier - Single Slope Details 2 of 3	10-A-17
Figure 10-A-18	Traffic Barrier - Single Slope Details 3 of 3	10-A-18
Figure 10-A-19	Pedestrian Barrier Details 1 of 3	10-A-19
Figure 10-A-20	Pedestrian Barrier Details 2 of 3	10-A-20
Figure 10-A-21	Pedestrian Barrier Details 3 of 3	10-A-21
Figure 10-A-22	Traffic Barrier - Shape F 42” Details 1 of 3	10-A-22
Figure 10-A-23	Traffic Barrier - Shape F 42” Details 2 of 3	10-A-23
Figure 10-A-24	Traffic Barrier - Shape F 42” Details 3 of 3	10-A-24
Figure 10-A-25	Traffic Barrier - Single Slope 42” Details 1 of 3	10-A-25
Figure 10-A-26	Traffic Barrier - Single Slope 42” Details 2 of 3	10-A-26
Figure 10-A-27	Traffic Barrier - Single Slope 42” Details 3 of 3	10-A-27
Figure 10-A-28	Traffic Barrier - Shape F Luminaire Anchor Details	10-A-28
Figure 10-A-29	Traffic Barrier - Single Slope Lumiaire Anchor Details	10-A-29
Figure 10-A-30	Thrie Beam Retrofit Concrete Balster	10-A-30
Figure 10-A-31	Thrie Beam Retrofit Concrete Railbase	10-A-31
Figure 10-A-32	Thrie Beam Retrofit Concrete Curb	10-A-32
Figure 10-A-33	WP Thrie Beam Retrofit SL1 - Details 1 Of 2	10-A-33
Figure 10-A-34	WP Thrie Beam Retrofit SL1 - Details 2 Of 3	10-A-34
Figure 10-A-35	Traffic Barrier - Shape F Rehabilitation Rehabilitation-Details 1 of 3	10-A-35
Figure 10-A-36	Traffic Barrier - Shape F Rehabilitation - Details 2 of 3	10-A-36
Figure 10-A-37	Traffic Barrier - Shape F Rehabilitation - Details 3 of 3	10-A-37
Figure 10-A-38	Bridge Railing Type Pedestrain Details 1 of 2	10-A-38
Figure 10-A-39	Bridge Railing Type Pedestrian Details 2 of 2	10-A-39
Figure 10-A-40	Bridge Railing Type BP Details 1 of 2	10-A-40
Figure 10-A-41	Bridge Railing Type BP Details 2 of 2	10-A-41
Figure 10-A-42	Bridge Railing Type S-BP Details 1 of 2	10-A-42
Figure 10-A-43	Bridge Railing Type S-BP Details 2 of 2	10-A-43
Figure 10-A-44	Pedestrian Railing Details 1 of 2	10-A-44
Figure 10-A-45	Pedestrian Railing Details 2 of 2	10-A-45
Figure 10-A-46	Bridge Railing Type Chain Link Snow Fence	10-A-46
Figure 10-A-47	Bridge Approach Slab Details 1 of 2	10-A-47
Figure 10-A-48	Bridge Approach Slab Details 2 of 2	10-A-48
Figure 10-A-49	Pavement Seat Repair Details	10-A-49
Figure 10-A-50	Section Pavement Seat Repair Details	10-A-50

Figure 10-A-51 Utility Hangers for Prestressed Girders 10-A-51
Figure 10-A-52 Utility Hanger Details for Concrete Box Structures 10-A-52
Figure 10-A-53 Utility Hanger Details 10-A-53
Figure 10-A-54 Bridge Drain Modification 10-A-54
Figure 10-A-55 Bridge Drains Types 2 thru 5 Modification for Overlay 10-A-55

10.1 Sign and Luminaire Supports

10.1.1 Loads

A. General

The reference used in developing the following office criteria is the AASHTO "Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals," Fourth Edition Dated 2001 including interims, and shall be the basis for analysis and design.

B. Dead Loads

Sign (incl. stiffeners)	3.25 lbs./ft.^{2}
Luminaire (effective projected area of head = 1.1 sq. ft.)	60 lbs./each
Fluorescent Lighting	3.0 lbs./ln. ft
Standard Signal Head	60 lbs./each
Mercury Vapor Lighting	6.0 lbs./ln. ft
Sign Brackets	Calc.
Structural Members	Calc.
5 foot wide maintenance walkway (incl. sign mounting brackets & handrail)	160 lbs./ln. ft.
Signal Head w/3 lenses (effective projected area = 9.2 sq ft.)	60 lbs. each

C. Wind Loads

A major change in the new AASHTO 2001 Specification wind pressure equation is the use of a 3 second gust wind speed in place of a fastest-mile wind speed used in the previous specification. The 3 second wind gust map in AASHTO is based on the wind map in ANSI/ASCE 7-95.

Basic wind speed of 90 mph shall be used in computing design wind pressure using equation 3-1 of AASHTO Section 3.8.1.

Do not use the Alternate Method of Wind Pressures given in Appendix C of the AASHTO 2001 Specifications.

D. Design Life and Recurrence Interval (Table 3-3, AASHTO 2001)

50 years for luminaire support exceeding 50 ft. in height and overhead sign structures.

25 years for luminaire support structures less than and including 50 ft. in height and traffic signal structures.

10 years for roadside sign structures.

E. Ice Loads

3 psf applied around all the surfaces of structural supports, horizontal members, and luminaires, but applied to only one face of sign panels (AASHTO Section 3.7).

F. Fatigue Design:

Fatigue design shall conform to AASSTO Section 11. Fatigue Categories are listed in Table 11-1. Sign and signal bridges do not require fatigue design. Cantilever structures, poles, and bridge mounted sign brackets shall conform to the following fatigue categories.

Fatigue Category I for overhead cantilever sign structures and bridge mounted sign brackets.

Fatigue Category II for high-level (high-mast) lighting poles in excess of 98 ft. in height

Fatigue Category III for overhead cantilever traffic signal structures

G. Live Load:

A live load consisting of a single load of 500 lb distributed over 2.0 ft. transversely to the member shall be used for designing members for walkways and platforms. The load shall be applied at the most critical location where a worker or equipment could be placed, see AASHTO 2001, Section 3.6.

F. Group Load Combinations:

Sign, luminaire, and signal support structures are designed using the maximum of the following four load groups (AASHTO Section 3.4 and Table 3-1):

Group Load	Load Combination	Percent of * Allowable Stress
I	DL	100
II	DL+W**	133
III	DL+Ice+1/2(W**)	133
IV	Fatigue	See AASHTO Section 11 for Fatigue loads and stress range


* No load reduction factors shall be applied in conjunction with these increased allowable stress.

** W—Wind Load

10.1.2 Bridge Mounted Signs

A. Vertical Clearance

The bottom of the sign lighting bracket shall be placed a minimum of 17 feet 6 inches and a maximum of 21 feet 0 inches above the lower roadway (see Figure 10-1). The minimum clearance is a requirement of the current electrical code. Region Design may approve greater or lesser clearance on an individual project basis.





Sign Vertical Clearance

Figure 10-1

B. Geometrics


1. Signs should be installed at approximate right angles to approaching motorists. For structures above a tangent section of roadway, signs may be installed parallel to the structure provided the structure skew does not exceed 10°. If the structure skew exceeds 10°, support brackets shall be designed to provide a sign skew of no more than 10° from perpendicular to the lower roadway (see Figure 10-2).






Sign Skew on Tangent Roadway
Figure 10-2

2. For structures located on or just beyond a horizontal curve of the lower roadway, signs may be installed parallel to the structure provided the structure chord-skew does not exceed 10°. If the structure chord-skew exceeds 10°, support brackets shall be designed to provide a sign chord-skew of no more than 10° from perpendicular to the chord-point determined by the approach speed (see Figure 10-3).
3. The top of the sign shall be level.



CASE A - STRUCTURE CHORD-SKEW GREATER THAN 10°




CASE B - STRUCTURE CHORD-SKEW 10° OR LESS

Sign Skew on Curved Roadway

Figure 10-3

C. Aesthetics


1. Preferably, the top of the sign and its support should not project above the bridge rail (see Figure 10-4).
2. When possible, the support structure should be hidden from view of traffic.
3. The sign support shall be detailed in such a manner that will permit the sign and lighting bracket to be installed level.
4. When the sign support will be exposed to view, special consideration is required in determining member sizes and connections to provide as pleasing an appearance as possible.



Sign Vertical Location
Figure 10-4

D. Sign Placement

1. When possible, the designer should avoid locating signs under bridge overhangs. This causes partial shading or partial exposure to the elements and problems in lifting the material into position and making the required connections. Signs shall never be placed directly under the drip-line of the structure. These conditions may result in uneven fading, discoloring, and difficulty in reading. When necessary to place a sign under a bridge due to structural or height requirements, the installation should be reviewed by the Region Traffic Design Office.
2. When sign support brackets are located on the structure, a minimum of 2 inches of clearance shall be provided between back side of the sign support and edge of the structure. See Figure 10-5.



Sign Horizontal Location
Figure 10-5

E. Installation

Expansion-type concrete anchors are not allowed for attaching sign support brackets to the structure because the loads imposed on the anchors can cause vibration and pull-out. New structures shall use either cast in place ASTM A 307 anchor rods, or resin bonded anchors. Existing structures shall use resin bonded anchors. Resin bonded anchor systems require the following notes to be included in the Plan sheets:

(a) Resin bonded archor system is to be installed using manufacturer recommendations in dry conditions.

(b) Torque resin bonded archor nuts to proof load.

F. Dimensioning

Where shown on the plans, the sign size shall be expressed in terms of horizontal by vertical dimension, i.e., X x Y, where X = horizontal dimension and Y = vertical dimension.

10.1.3 Sign Bridges Mounted on Bridges

A. Design Loads

Design loads for the supports of the sign bridges shall be calculated based on assuming a 12-foot deep sign over the entire roadway width, under the sign bridge. This will account for any signs that may be added in the future. The design loads shall follow the same criteria as described in BDM Section 10.1.1. Loads from the sign bridge shall be included in the design of the supporting bridge.

B. Vertical Clearance

Vertical clearance for sign bridges follow the same requirements as Bridge-Mounted Signs as stated in BDM Section 10.1.2 .

C. Geometrics

Sign structures shall be placed at approximate right angles to approaching motorists. Dimensions and details of sign structures are shown in the Standard Plans G-2, G-2a, G-3, G-3a and BDM sheets 10.1-A1.1, 10.1-A1.2 and 10.1-A2.1, 10.1-A2.2. When maintenance walkways are included, refer to Standard Plan G-6, G-6a and G-6b.

10.1.4 Monotube Sign Structures

A. Sign Bridge Standard Design

Table 10-6 provides the standard structural design information to be used for a Sign Bridge Layout, BDM Sheet 10.1-A1.1; along with the Structural Detail sheets, which are BDM Sheet 10.1-A2.1 and BDM Sheet 10.1-A2.2.

B. Cantilever Standard Design

Table 10-7 provides the standard structural design information to be used for a Cantilever Layout, BDM Sheet 10.1-A1.2; along with the Structural Detail sheets, which are BDM Sheet 10.1-A2.1 and BDM Sheet 10.1-A2.2.

STANDARD MONOTUBE SIGN BRIDGES

SPAN LENGTH	POSTS Ⓤ				BEAM A Ⓤ				BEAM B Ⓤ				BEAM C Ⓤ				
"S"	"H"	"A"	"B"	"T1"	"L1"	"B"	"C"	"T2"	"L2"	"B"	"C"	"T2"	"L3"	"B"	"C"	"T2"	CAMBER
LESS THAN 60'-0"	30'-0" OR LESS	1'-6"	2'-0"	½"	6'-0"	2'-0"	2'-0"	⅜"	0'-0"	-	-	-	13'-0" TO 48'-0"	2'-0"	2'-0"	⅜"	2¾"
60'-0" TO 75'-0"	30'-0" OR LESS	1'-6"	2'-3"	½"	6'-0"	2'-3"	2'-0"	⅜"	9'-0" TO 14'-0"	2'-3"	2'-0"	⅜"	30'-0" TO 35'-0"	2'-3"	2'-0"	⅜"	3¾
75'-0" TO 90'-0"	30'-0" OR LESS	1'-6"	2'-3"	⅝"	6'-0"	2'-3"	2'-0"	⅜"	14'-0" TO 19'-0"	2'-3"	2'-0"	⅜"	35'-0" TO 40'-0"	2'-3"	2'-0"	⅜"	5"
90'-0" TO 105'-0"	30'-0" OR LESS	1'-9"	2'-6"	⅝"	6'-0"	2'-6"	2'-3"	½"	19'-0" TO 26'-6"	2'-6"	2'-3"	½"	40'-0"	2'-6"	2'-3"	½"	6"
105'-0" TO 120'-0"	30'-0" OR LESS	1'-9"	2'-6"	⅝"	6'-0"	2'-6"	2'-3"	½"	26'-6" TO 34'-0"	2'-6"	2'-3"	½"	40'-0"	2'-6"	2'-3"	½"	7½"
120'-0" TO 135'-0"	30'-0" OR LESS	2'-0"	2'-6"	⅝"	6'-0"	2'-6"	2'-6"	½"	34'-0" TO 41'-6"	2'-6"	2'-6"	½"	40'-0"	2'-6"	2'-6"	½"	8½"
135'-0" TO 150'-0"	30'-0" OR LESS	2'-0"	2'-6"	⅝"	6'-0"	2'-6"	2'-6"	½"	41'-6" TO 49'-0"	2'-6"	2'-6"	½"	40'-0"	2'-6"	2'-6"	½"	10½ "

SPAN LENGTH	POST BASE Ⓤ					BOLTED SPLICE #1 L1 TO L2 AND L1 TO L3						BOLTED SPLICE #2 L2 TO L3						MAXIMUM SIGN AREA
"S"	"D1"	"S5"	"S6"	"T3"	"T6"	"S1"	"S2"	"S3"	"S4"	"T4"	"T5"	"S1"	"S2"	"S3"	"S4"	"T4"	"T5"	
LESS THAN 60'-0"	1½"	4	4	2¼"	¾"	5	-	5	-	2"	⅝"	-	-	-	-	-	-	500 SQ. FT.
60'-0" TO 75'-0"	1¾	4	4	2¼ "	¾"	6	-	5	-	2"	⅝"	6	-	5	-	2¼"	¾"	600 SQ. FT.
75'-0" TO 90'-0"	1¾"	4	4	2½"	¾"	6	-	5	-	2"	⅝"	6	-	5	-	2¼"	¾"	750 SQ. FT.
90'-0" TO 105'-0"	1¾"	4	5	2½"	1"	7	-	6	-	2"	⅝"	7	5	6	4	2½"	1"	750 SQ. FT.
105'-0" TO 120'-0"	1¾"	4	5	2½"	1"	7	-	6	-	2"	⅝"	7	5	6	4	2½"	1"	850 SQ. FT.
120'-0" TO 135'-0"	2"	4	5	2½"	1"	7	-	7	-	2"	⅝"	7	5	7	5	2½"	1"	800 SQ. FT.
135'-0" TO 150'-0"	2"	4	5	2½"	1"	7	-	7	-	2"	⅝"	7	5	7	5	2½"	1"	800 SQ. FT.

Ⓤ NOTE: DENOTES MAIN LOAD-CARRYING TENSILE MEMBERS OR TENSION COMPONENTS OF FLEXURAL MEMBERS

Table 10-6

STANDARD CANTILEVER SIGN BRIDGES

SPAN LENGTH	POST (U)				BEAM A (U)				BEAM B (U)				
"S"	"H"	"A"	"B"	"T1"	"L1"	"B"	"C"	"T2"	"L2"	"B"	"C"	"T2"	CAMBER
LESS THAN 20'-0"	30'-0" OR LESS	1'-6"	2'-0"	3/8"	6'-0"	2'-0"	2'-0"	3/8"	14'-0"	2'-0"	2'-0"	3/8"	2"
20'-0" TO 30'-0"	30'-0" OR LESS	1'-6"	2'-0"	1/2"	6'-0"	2'-0"	2'-0"	3/8"	14'-0" TO 24'-0"	2'-0"	2'-0"	3/8"	3 1/2"

SPAN LENGTH	POST BASE					BOLTED SPLICE						MAXIMUM SIGN AREA
"S"	"D1"	"S5"	"S6"	"T3"	"T6"	"S1"	"S2"	"S3"	"S4"	"T4"	"T5"	
LESS THAN 20'-0"	1 1/2"	4	4	2"	3/4"	5	-	5	-	2"	5/8"	168 SQ. FT.
20'-0" TO 30'-0"	2"	4	4	2"	3/4"	5	3	5	3	2 1/2"	5/8"	252 SQ. FT.

(U) NOTE: DENOTES MAIN LOAD-CARRYING TENSILE MEMBERS OR TENSION COMPONENTS OF FLEXURAL MEMBERS

Table 10-7

C. Monotube BDM Sheet Guidelines

The following guidelines apply when using the Monotube Sign Structure BDM sheets 10-S1-1, 10-S1-2 and 10-S2-1, 10-S2-2.

1. Each sign structure shall be detailed and must specify:
   a. Sign structure base Elevation, Station and Number.
   b. What type of foundation (1, 2, or 3) is to be used for the structure. If Foundation Type 1, 2 or 3 are not used, then the average lateral bearing pressure for each foundation shall be noted on the Layout sheet.
   c. If applicable, label the Elevation View "Looking Back on Stationing".
2. Designers shall verify the cross-referenced page numbers and details are correct.

B. Monotube BDM Quantities

Quantities for structural steel are given in Table 10-8.

Quantities ASTM A572 GR. 50 or ASTM 588	A	B	C	D	E	F	G	H	I
Post (plf)	99	132	132	144	176	204	204	215	215
Base PL (ea)	431	490	490	578	585	654	654	688	688
Beam, near Post (plf)	116	116	116	124	124	139	139	171	195
Span Beam (plf)	116	116	116	124	124	162	185	195	195
Corner Stiff. (ea set)	209	204	204	238	236	312	312	371	369
Splice PL #1 (1 pr)	482	482	482	692	692	892	883	780	780
Splice PL #2 (1 pr)	—	—	482	615	615	718	802	715	780
Brackets (ea)	60	60	60	65	65	69	69	70	70
6" Hand Hole (ea)	18	18	18	18	18	18	18	18	18
6" x 11" Hand Hole (ea)	30	30	30	30	30	30	30	30	30
Anchor Bolt Pl (ea)	175	175	175	185	185	311	311	326	326
Seal Plates (1 bridge)	217	216	316	614	612	770	674	860	860

A) 20' ≤ Cantilever
B) 20' to 30 Cantilever
C) 60' and Less Sign Bridge
D) 60' to 75' Sign Bridge
E) 75' to 90' Sign Bridge
F) 90' to 105' Sign Bridge
G) 105' to 120' Sign Bridge
H) 120' to 135' Sign Bridge
I) 135' to 150' Sign Bridge

Sign Structure Steel Quantities

Table 10-8

10.1.5 Foundations

A. Foundation Types

The Geotechnical Branch shall be consulted as to which foundation type is to be used. Standard foundation designs are provided in WSDOT Standard Plans G-2a and G-3a; and in BDM Section 10.1.5. The following paragraphs describe the four types of foundations detailed in this section of the BDM.

1. The Type 1 Foundation, a drilled shaft, is the preferred foundation for sign, luminaire, and signal supports. The standard drilled shafts are designed for a lateral bearing pressure of 2,500 psf. See BDM Sheet 10.1-A3.1 for Type 1 Foundation standard design information.
2. The Type 2 Foundation is an alternate to Type 1 when drilled shafts are not suitable to the site. Type 2 Foundations are designed for a lateral bearing pressure of 2,500 psf. See BDM Sheet 10.1-A3.2 for Type 2 Foundation standard design information.
3. The Type 3 Foundation is designed for poor soil conditions where the lateral bearing pressure is between 2,500 psf and 1,500 psf. The standard details for both Type 2 and 3 Foundations are found on BDM Sheet 10.1-A3.2. See BDM Sheet 10.1-A3.2 for Type 3 Foundation standard design information.
4. Barrier Foundation Types (1-3) are foundations that include a barrier in the top portion of the Standard foundation. Types 1, 2 and 3 have been modified to include the required Traffic Barrier shape for the project. BDM Sheet 10.1-A4.1 details a double faced "F" shape barrier. BDM Sheet 10.1-A4.2 details a single slope barrier.

Foundation Quantities for BDM Sheets 10.1-A3.1 AND 10.1-A3.2 are described below.

1. Barrier quantities are approximate and can be used for all Foundation Types:
   (Both single slope or F-shape barriers)

Class 4000 Concrete	0.289 CY/LF (over shaft foundation)
Grade 60 rebar	372 lbs.

2. Miscellaneous steel quantities for all foundation types:
   (anchor bolts, anchor plate, and template)

   60 feet & under = 1,002 pounds

   61 feet to 90 feet = 1,401 pounds

   91 feet to 120 feet = 1,503 pounds

   121 feet to 150 feet: Barrier mounted sign bridge not recommended for these spans.
3. Type 1-3 Foundation quantities for concrete, rebar and excavation are given in Table 10-9. For Sign Bridges, the quantities shown below are for one foundation and there are two foundations per sign bridge.

Sign Structure Foundation Material Quantities						
	Cantilever Signs		Sign Bridges			
Concrete Cl. 3000 (cu. yard)	20' & Under	20' – 30'	60' & Under	60' – 90'	90' – 120'	120' – 150'
Type 1	6.3	7.5	7.7	9.4	10.6	11.4
Type 2	8.0	10.5	10.0	12.2	14.1	15.0
Type 3	11.1	14.1	13.0	16.1	18.6	20.0
Rebar Gr. 60 Pounds						
Type 1	685	1,027	1,168	2,251	3,256	4,255
Type 2	772	1,233	1,190	1,724	2,385	2,838
Type 3	917	1,509	1,421	2,136	2,946	3,572
Excavation (cu. yard)						
Type 1	9.8	10.9	10.9	12.8	14.1	14.9
Type 2	20.7	25.7	24.6	29.0	32.9	34.6
Type 3	29.0	34.6	32.9	39.0	44.0	47.8

Table 10-9

10.1.6 Truss Sign Bridges: Foundation Sheet Design Guidelines

There are four items that should be addressed when using the BDM Truss Sign Bridge Barrier Foundation sheet (BDM sheet 10.1-A5.1), which are outlined below. WSDOT Standard Plan C-14i is available for use as the single slope barrier version of BDM Sheet 10-S5-1.

1. Determine conduit needs. If none exist, delete all references to conduit. If conduit is required, verify with the Region as to size and quantity.
2. Show sign bridge base elevation, number, “D” dimension and station.
3. Transition section can be 10 feet 0 inches or 12 feet 6 inches.
4. The quantities for the barrier as shown on the sheets are as follows:

Class 4000 concrete	0.185 CY/LF above foundation cap
	0.269 CY/LF outside foundation cap
Gr. 60 Rebar	Varies based on the type of foundation and the “D” dimension.

10.2 Bridge Traffic Barriers

10.2.1 General Guidelines

The design criteria for bridge traffic barriers on structures shall be in accordance with Chapter 13 of the LRFD Bridge Design Specifications adopted by AASHTO.

WSDOT's bridge traffic barrier standard test level is a TL-4.

The WSDOT Bridge and Structures standard for new bridge traffic barriers is a 32-inch high F-Shape concrete barrier. This shape is also the preferred shape by the FHWA. This shall be used on all interstate, major highway routes, and over National Highway System (NHS) routes.

Use of a Single Slope concrete bridge traffic barrier shall be limited to when there is Single Slope concrete barrier on the approach grade to a bridge or for continuity within a corridor. The Single Slope bridge traffic barrier is 34 inches high to be consistent with the heights being used on grade applications. (See WSDOT Design Manual Section 710 for additional background and criteria.)

Use the taller 42-inch high bridge traffic barriers on interstate or freeway routes only in the following circumstances:

- Accident history suggests a need.
- Large trucks make up a significant portion of the ADT
- Adverse roadway geometrics increase the possibility of hitting the traffic barrier at a high angle (such as on ramps for freeway to freeway connections with sharp curvature in the alignment).
- Protection of schools, businesses or other important facilities below the bridge.

In addition, NCHRP Report 350 was adopted by AASHTO to give specific requirements for crash testing of bridge barriers prior to their use on all new or retrofitted bridge structures. The LRFD Bridge Design Specifications differentiate crash test criteria for various test levels depending upon traffic volume, design speed, vehicle mix, and other factors which produce a vast variation in traffic railing performance needs from one site to another.

A list of crash tested traffic barrier can be found thru the FHWA at http://safety.fhwa.dot.gov/fourthlevel/pro_res_road_nchrp350.htm.

Bridge traffic barriers shall be rigidly connected to the bridge deck.

Median bridge traffic barriers shall be either rigidly connected to bridge deck or allow a minimum of two feet of slide distance between the toe of the traffic barrier and the lane pavement marking.

10.2.2 Bridge Railing Test Levels

It must be recognized that bridge traffic barrier performance needs differ greatly from site to site. Barrier designs and costs should match facility needs. This concept is embodied in the LRFD Bridge Design Specifications. Six different bridge railing test levels, TL-1 thru TL-6, and associated crash test/performance requirements are given in Chapter 13 of these design specifications along with guidance for determining the appropriate test level for a given bridge.

10.2.3 Available WSDOT Designs

A. Test Level 2


1. Service Level 1 (SL-1) Weak Post Guardrail

   This bridge traffic barrier is a crash tested weak post rail system. It was developed by Southwest Research Institute and reported in NCHRP Report 239 for low-volume rural roadways with little accident history. We have utilized this design on some of our short concrete spans and on our timber bridges. A failure mechanism is built into this rail system such that upon a 2 kip applied impact load the post will break away from


the mounting bracket. The thrie beam guardrail will contain the vehicle by virtue of its ribbon strength. This failure mechanism assures minimum damage, if any at all, to the bridge deck and stringers. The appropriate guardrail approach transition shall be a Case 14 placement as shown on Standard Plan C-2h. For complete details see Appendix 10.4-A1.

2. Texas T-411 Aesthetic Concrete Baluster

   Texas developed this standard for a section of highway that was considered to be a historic landmark. The existing deficient concrete baluster rail was replaced with a much stronger concrete baluster that satisfactorily passed the crash test performance criteria set forth by the NCHRP Report 230. For details visit TXDOT's Bridge and Structures web site at http://www.dot.state.tx.us/brg/default.htm.



SL-1 WEAK POST



TEXAS T-411

Figure 10-10

B. Test Level 4 Traffic Barriers

1. Traffic Barrier – Shape F

   This configuration was crash tested in the late 1960's, along with the New Jersey Shape, under NCHRP 230 and again recently at this test level under NCHRP 350. The steeper vertical shape actually tested better than the New Jersey face and had less of an inclination to roll vehicles over upon impact. The 3" toe of the traffic barrier is the maximum depth that an ACP or HMA overlay can be placed. For complete details see Appendix 10.2-A1 & A2.

2. Traffic Barrier – Single Slope

This concrete traffic barrier system was designed by the state of California, in the 1990's, to speed up construction by using the "slip forming" method of construction. It was tested under NCHRP 350. WSDOT has increased the height from 32" to 34" to match the approach traffic barrier height. Due to inherent problems with the "slip forming" method of traffic barrier construction WSDOT has increased the concrete cover on the traffic side from 1 ½" to 2 ½". For complete details see Appendix 10.2-A3.




Figure 10-11

3. Pedestrian Barrier

This crash tested rail system offers a simple to build concrete alternative to the New Jersey and F-Shape configurations. This system was crash tested under both NCHRP 230 and 350. Since the traffic face geometry is better for pedestrians and bicyclists, WSDOT uses this system primarily in conjunction with a sidewalk. For complete details see Appendix 10.2-A4.

4. Oregon 2-Tube Curb Mounted Traffic Barrier

This is another crash tested traffic barrier that offers a lightweight, see-through option. This system was crash tested under both NCHRP 230 and 350. A rigid thrie beam guardrail transition is required at the bridge ends. For details see the Oregon Bridge and Structure web site at http://www.odot.state.or.us/tsbbridgepub/.




Figure 10-12

C. Test Level 5 Traffic Barriers

1. Traffic Barrier – Shape F 42”

   This barrier is very similar to the 32 inch F-shape concrete barrier in that the slope of the front surface is the same except for height. This barrier and the other bridge traffic barriers within this section have been crash tested for a 50,000 lb. tractor-trailer. For complete details see Appendix 10.2-A5.

   This barrier was used on a portion of the Seattle Access project in Seattle due to the large vehicular mix of large trucks and buses and to protect buildings below the bridge structure. Another application of this barrier is on Bridge No. 101/515E-S due to the roadway alignment's sharp radius curvature.

2. Traffic Barrier – Single Slope 42”

   This crash tested option offers a simple to build alternative to the Shape F configuration. For complete details see Appendix 10.2-A6.




Figure 10-13

10.2.4 Design Criteria

A. Design Values

The WSDOT traffic barriers are reinforced based on the FHWA crash testing program as described in NCHRP Report 350. The reinforcement is based on the AASHTO LFD 10 kip load. This produces a traffic barrier system that is overdesigned when analyzed with AASHTO LRFD criteria and leads to the possibility that the deck overhang is also overdesigned.

In order to prevent this unnecessary overdesign of the deck overhang, the nominal traffic barrier resistance to transverse load, R_W found in AASHTO LRFD Specifications Section A13.3.1 transferred from the traffic barrier to deck overhang need not to be taken 120% of the design force, F_t, required for traffic barrier found in AASHTO LFRD Bridge Design Specifications table A13.2-1.

The deck overhang should be designed in accordance to the requirements of the AASHTO-LRFD Specifications Section A 13.4.2 to provide a flexural resistance M_S, acting coincident with the tensile force T. At the inside face of the barrier M_S may be taken as:

$\frac{R_w \cdot H}{L_c + 2 \cdot H}$ for an interior barrier segmen

and

$\frac{R_w \cdot H}{L_c + H}$ for an end barrier segmen

However, M_S need not to be taken greater than M_c at the base.

T shall be taken as $\frac{R_w}{L_c + 2 \cdot H}$ for an interior barrier segment

And $\frac{R_w}{L_c + H}$ for an end barrier segment

The barrier impact design forces transmitted to the deck overhang, not including the dead loads of the traffic barrier and the slab, shall be taken as:

Vehicle Impact Loadings on Traffic Barrier/Cantilevered Deck Overhang

		Type F 32 in		Single Slope		Shape F 42”		Single Slope 42”	
	Parameters	Interior	End*	Interior	End	Interior	End	Interior	End
Traffic Barrier Design	Average Mc (ft-kips/ft)	20.62	20.62	19.39	19.39	29.18	29.18	25.22	25.22
	Mc at Base (ft-kips/ft)	27.24	27.24	26.11	26.11	37.00	37.00	34.52	34.52
	MwH (ft-kips)	42.48	45.98	44.72	42.17	97.83	96.91	83.87	79.14
	Lc (ft)	8.61	4.75	9.19	4.79	14.48	9.25	14.45	9.19
	Rw (kips)	133.09	73.48	125.79	65.53	241.47	154.33	208.16	132.49
	Ft (kips)	54.00	54.00	54.00	54.00	124.00	124.00	124.00	124.00
Deck Overhand Design	1.2*Ft (kips)	64.80	64.80	64.80	64.80	148.80	148.80	148.80	148.80
	Design Rw (kips)	64.80	64.80	64.80	64.80	148.80	148.80	148.80	132.49
	Rw*H/(Lc+xH) (ft-kips/ft)	12.40	23.29	12.36	24.09	24.24	40.83	24.28	36.53
	Design Ms (ft-kips/ft)	12.40	23.29	12.36	24.09	24.24	37.00	24.28	34.52
	Design T (kips/ft)	4.65	8.74	4.36	8.50	6.93	11.67	6.94	10.44
Deck to Barrier Reinforcement	As required (in^2/ft)	0.29	0.56	0.29	0.58	0.44	0.68	0.50	0.72
	As provided (in^2/ft)	0.41	0.62	0.41	0.62	0.66	0.75	0.66	0.75
	S1 Bars	#5 @ 9in	#5 @ 6in	#5 @ 9in	#5 @ 6in	#6 @ 8in	#6 @ 7in	#6 @ 8in	#6 @ 7in
Weight Area	W (lbs/ft)	472.5		505.3		729.0		692.2	
	A (in ^2)	425.2		454.8		656.1		623.0	

* Traffic barrier cross sectional dimensions and reinforcement used for calculation of the end segment parameters are the same as interior segments. Parameters for modified end segments shall be calculated per AASHTO_LRFD article A13.3, A13.4, and the WSDOT LRFD BDM.

When an HMA overlay is required for initial construction, increase the weight for Shape F traffic barrier. See section 10.2.4.C for details.

B. Geometry

These traffic barriers have been crash tested and shall not be significantly modified unless they are retested to NCHRP 350 or approved by the FHWA as described in Chapter 13 of the AASHTO Specifications. The traffic face geometry is part of the crash test and shall not be modified. Contact WSDOT Bridge and Structure's Traffic Barrier Specialist for further guidance.

Thickening of the traffic barrier is permissible for architectural reasons. Concrete clear cover must meet minimum concrete cover requirements, but can be increased to accommodate rustication, groves, or patterns and must meet minimum concrete cover requirements.

C. Standard Detail Sheet Modifications

When designing and detailing a bridge traffic barrier on a superelevated bridge deck, the following guidelines shall be used:

- For bridge decks with a superelevation of 8% or less, the traffic barriers (and the median barrier, if any) shall be oriented perpendicular to the bridge deck.
- For bridge decks with a superelevation of more than 8%, the traffic barrier on the low side of the bridge (and median barrier, if any) shall be oriented perpendicular to an 8% superelevated bridge deck. For this situation, the traffic barrier on the high side of the bridge shall be oriented perpendicular to the bridge deck.

The standard detail sheets are generic and may need to be modified for each project. The permissible modifications are:

- Removal of the electrical conduit, junction box, and deflection fitting details.
- Removal of design notes.
- If the traffic barrier does not continue on to a wall, remove W1 and W2 rebar references.
- Removal of the non-applicable guardrail end connection details and verbiage.
- If guardrail is attached to the traffic barrier use either the thrie beam design "F" detail or the W-beam design "F" detail.

If the traffic barrier continues off the bridge, approach slab, or wall, remove the following:

- Guardrail details from all sheets
- Conduit end flare detail
- Modified end section detail and R1A or R2A rebar details from all sheets
- End section bevel
- Increase the 3" toe dimension of the Shape F traffic barriers up to 6" to accommodate HMA overlays.

D. Miscellaneous Design Information

- Show the back of Pavement Seat in the "Plan – Traffic Barrier" detail.
- At roadway expansion joints, show traffic barrier joints normal to centerline, except as shown on sheets in Chapter 9 Appendix.
- When an overlay is required, the 2'-8" minimum dimension shown in the "Typical Section – Traffic Barrier" shall be referenced to the top of the overlay.

When bridge lighting is part of the contract, include the lighting bracket anchorage detail sheet.

10.3 At Grade Cast-in-Place Barriers

10.3.1 Median Barriers

Cast-in-place (CIP) barriers at grade are sometimes required in median areas with different roadway elevations on each side. Both a safety - shape and an F-shape CIP median barrier have been crash tested successfully with a 2'- 0" or less difference in grade elevations. The Single Slope traffic barrier can be used for a difference in grade of up to 10", see the WSDOT Standard Plans for details. The minimum length will be based on general stability requirements. If a greater difference in elevations is required then the barrier shall be designed as a wall using the AASHTO LRFD barrier loading.

The top of the median traffic barrier shall have a minimum width of 6". If a luminaire or sign is to be mounted on top of the median traffic barrier, then the width shall be increased to accommodate the mounting plate and 6" of clear distance on each side of the luminaire or sign pole. The transition flare rate shall follow WSDOT Design manual.

10.3.2 Shoulder Barriers

At grade CIP shoulder barriers are sometimes used adjacent to bridge sidewalk barriers in lieu of standard precast Type 2 barriers. This barrier cross section has an equivalent mass and resisting moment for stability as the embedded double face New Jersey Traffic Barrier, which has been satisfactorily crash tested. A wire rope and pin connection shall be made at the bridge barrier end section per Standard Plan C-8. If a connection is made to an existing traffic barrier or parapet on the bridge, 15-inch long holes shall be drilled for the wire rope connection and shall be filled with an adhesive resin.

10.4 Bridge Traffic Barrier Rehabilitation

10.4.1 Policy

The bridge traffic barrier retrofit policy is: "to systematically improve or replace existing deficient rails within the limits of roadway resurfacing projects". This is accomplished by:

- Utilizing an approved crash tested rail system that is appropriate for the site or
- Designing a traffic barrier system to the strength requirements set forth by Section 2 of AASHTO Standard Specifications for Highway Bridges, 17th edition."

10.4.2 Guidelines

A strength and geometric review is required for all bridge rail rehabilitation projects. If the strength of the existing bridge rail is unable to resist an impact of 10 kips or has not been crash tested, then modifications or replacement will be required to improve its redirectional characteristics and strength. Bridges that have deficient bridge traffic barriers were designed to older codes. The AASHTO LFD load of 10 kips shall be used in the retrofit of existing traffic barrier systems constructed prior to the year 2000. The use of the AASHTO LRFD criteria to design traffic barrier rehabs will result in a bridge deck that is susceptible to damage from a traffic barrier impact load and increase the retrofit cost due to expensive deck modifications.

10.4.3 Design Criteria

Standard thrie beam guardrail post spacing is 6'- 3" except for the SL-1 Weak Post, which is at 8'- 4". Post spacing can be increased up to 10'- 0" but the thrie beam guardrail has to be nested or doubled up.

Except as otherwise noted, gaps in the guardrail are not allowed because they produce snagging hazards. The exceptions
to this are:

- Movable bridges at the expansion joints of the movable sections.
- At traffic gates and drop down net barriers.
- At stairways.
- Design F guardrail end sections will be used at the approach and trailing end of these gaps.

The following information will be needed from the Region Design office:

- Bridge Site Data Rehabilitation Sheet – Form # 235-002A.
- Photos, preferably digital Jpegs.
- Layout with existing dimensions.
- Measurements of existing ACP to top of curb, at the four corners as a minimum.
- Location of Type 3 anchors, if present.
- The proposed overlay type, quantities of removal and placement.
- For timber bridges, field measurement of the distance from the edge of bridge deck to the first and second stringer, for mounting plate modification.

Placement of the retrofit system will be determined from the WSDOT Highway Design Manual, Figure 710.15. Exceptions to this are bridges with sidewalk strength problems, pedestrian access issues, or vehicle snagging problems.

10.4.4 WSDOT Bridge Inventory of Bridge Rails

The WSDOT Bridge Preservation office maintains an inventory of all bridges in the state on the State of Washington Inventory of Bridges.

Concrete balusters are deficient for current lateral load capacity requirements. They have approximately 3 kips of capacity whereas 10 kips is required.

The combination high-base concrete parapet and metal rail may or may not be considered adequate depending upon the rail type. The metal rail Type R, S, and SB attached to the top of the high-base parapet are considered capable of resisting the required 5 kips of lateral load. Types 3, 1B, and 3A are considered inadequate. See WSDOT Highway Design Manual, Section 710 for replacement criteria.

10.4.5 Available Retrofit Designs

A. Washington Thrie Beam Retrofit of Concrete Balusters

This system consists of thrie beam guardrail stiffening of existing concrete baluster rails with timber blockouts. The Southwest Research Institute conducted full-scale crash tests of this retrofit in 1987. Results of the tests were satisfactory and complied with criteria for a Test Level 2 (TL2) category in the Guide Specifications. For complete details see details see Appendix 10.4-A1.

B. New York Thrie Beam Guardrail

This crash tested rail system can be utilized at the top of a raised concrete sidewalk to separate pedestrian traffic from the vehicular traffic or can be mounted directly to the top of the concrete deck. For complete details see Thrie Beam Retrofit Concrete Curb in Appendix 10.4-A1.

C. Concrete Parapet Retrofit

This is similar to the New York system. For complete details see Appendix 10.4-A1.

D. SL-1 Weak Post

WSDOT has utilized this design on some short concrete spans and timber bridges. A failure mechanism is built into this rail system so that upon impact, a 2 kip applied load, the post will break away from the mounting. The thrie beam guardrail will contain the vehicle by virtue of its ribbon strength. This failure mechanism assures minimal damage to the bridge deck and stringers. For complete details see Appendix 10.4-A1.

10.4.6 Available Replacement Designs

A. Traffic Barrier - Shape F Retrofit

This is WSDOT'spreferred replacement of deficient traffic barriers and parapets on high volume highways with a large truck percentage. All interstate highway bridges shall use this type. For complete details see Appendix 10.4-A2.

10.5 Bridge Railing

10.5.1 Design

WSDOT pedestrian and bike/pedestrian railings are design in accordance with Chapter 13 in the AASHTO LRFD Bridge Design Specifications.

10.5.2 Railing Types

A. Bridge Railing Type Pedestrian

This pedestrian railing is designed to sit on top of the 32” and 34” traffic barriers and to meet pedestrian height requirements of 42”. For complete details see Appendix 10.5-A1.

B. Bridge Railing Type BP and S-BP

These railings are designed to meet the minimum bicycle height requirements of 54”, and sit on top of the 32” and 34” traffic barriers. There are two versions. The BP is the standard railing and is made out of aluminum. The S-BP is the steel version designed for use in rural areas because of aluminum theft. For complete details see Appendix 10.5-A2 and 10.5-A3.

C. Pedestrian Railing

This railing is designed to sit on top of a six-inch curb on the exterior of a bridge sidewalk. It meets the bicycle height requirements of 54”. For complete details see Appendix 10.5-A4.

D. Bridge Railing Type Chain Link Snow Fence

This is designed to minimize plowed snow from falling off the bridge on to traffic below. For complete details see Appendix 10.5-A5.

10.6 Bridge Approach Slabs

Bridge approaches typically experience two types of settlement, global and local. Global settlement is consolidation of the deeper natural foundation soils. Local settlement is mainly compression of fill materials directly beneath the approach pavement due to construction. The combination of global and local settlements adjacent to the bridge end piers form the characteristic "bump" in the pavement at the bridge. The approach slab significantly reduces local settlement and will provide a transition to the long term roadway differential settlements. Generally, abutments with a deep foundation will have greater differential roadway settlements than spread footing foundations.

When are Approach Slabs Required?

Bridge approach slabs are required for all new and widened bridges, except when concurrence is reached between the Geotechnical Branch, the Region Design Project Engineer Office, and the Bridge and Structures Office, that approach slabs are not appropriate for a particular site. In accordance with WSDOT Design Manual Chapter 1120, the State Geotechnical Engineer will include a recommendation in the Geotechnical Report for a bridge on whether or not bridge approach slabs should be used at the bridge site. Factors considered while evaluating the need for bridge approach slabs include the amount of expected settlement and the type of bridge structure.

Standard Plan A-2

The Standard Plan A-2 is available for the Local Agencies (or others) to use or reference in a contract. Bridge and Structures Office designs for local agency projects may reference Standard Plan A-2. However, detailed information in a customized approach slab Plan View is preferred.

Bridge Runoff

Bridge runoff at the abutments shall be carried off and collected at least 10 feet beyond the bridge approach slab. Drainage structures such as grate inlets and catch basins shall be located in accordance with Standard Plan A-4 and the recommendations of the Hydraulics Office.

Approach Pay Item

All costs in connection with constructing bridge approach slabs are included in the unit contract price per square yard for "Bridge Approach Slab". The pay item includes steel reinforcing bars, approach slab anchors, concrete, and compression seals. For the Contractor's information, the total quantity of epoxy-coated and plain steel reinforcing bars (lbs), concrete (SY), and miscellaneous items shall be listed in the bar list sheet for each bridge.

10.6.1 Notes to Region for Preliminary Plan

All bridge preliminary plans shall show approach slabs at the ends of the bridges. In the Notes to Region in the first submittal of the Preliminary Plan to the Region, the designer shall ask the following questions:

1. Bridge approach slabs are shown for this bridge, and will be included in the Bridge PS&E. Do you concur?
2. The approach ends of the bridge approach slabs are shown (a) parallel to the back of pavement seat (b) normal to the survey line (the designer shall propose one alternative). Do you concur?
3. Please indicate the pavement type for the approach roadway.

Depending on the type and number of other roadway features present at the bridge site (such as approach curbs and barriers, drainage structures, sidewalks, utilities and conduit pipes) or special construction requirements such as staged construction, other questions in the Notes to Region pertaining to the bridge approach slabs may be appropriate.

Special staging conditions exist when the abutment skew is greater than 30 degrees and for wide roadway widths. This includes bridge widenings with (or without) existing bridge approach slabs. The preliminary plan should include details showing how these conditions are being addressed for the bridge approach slabs, and the designer shall include appropriate questions in the Notes to Region asking for concurrence with the proposed design.

10.6.2 Approach Slab Design and Detailing

All bridge preliminary plans shall show approach slabs at the ends of the bridges. In the Notes to Region in the first submittal of the Preliminary Plan to the Region, the designer shall ask the following questions:

1. The bridge approach slab is designed as a slab in accordance with AASHTO LRFD. (Strength Limit State, IM = 1.33, no skew).
2. The support at the roadway end is assumed to be a uniform soil reaction with a bearing length that is approximately 1/3 the length of the approach slab, or 25ft /3 = 8 feet.
3. The Effective Span Length (S_{eff}), regardless of approach length, is assumed to be:

   25 foot approach - 8 feet/2 to CL soil support - 10 inch seat width = 20 feet
4. Longitudinal reinforcing bars do not require modification for skewed approaches or slab lengths greater than 25 feet.
5. BDM Section 7.4.3, Abutment Loading, provides slab reactions without a dynamic allowance (IM). A dynamic allowance, IM = 1.33, should be applied to the design of a pavement seat.
6. The maximum skew accommodated detailed in the standard sheets is 30 degrees.


10.6.3 Approach Expansion Joints

For semi-integral abutments or stub abutments, the Bridge Designer must check the joint design to make sure the movement of the standard joint is not exceeded. In general, the approach slab is assumed to be stationary and the joint gap is designed to vary with the bridge movement. The BDM Approach Slab Sheet 10.6-A1.2 and Standard Plan A-2 detail a small compression seal with a 1-5/8 inch installed gap. Bridges with large expansion movements or highly skewed joints may require compression seals larger than the standard joint and are not recommended. If a larger seal is required, the approach seat should also be larger.

Approach slab anchors installed at bridge abutments should be as shown in the Bridge Plans. For bridges with semi-integral type abutments, this can be accomplished by showing the approach slab anchors in the End Diaphragm or Pavement Seat details.

L type abutments

L type abutments do not require expansion joints or approach anchors because the abutment and approach slab are both considered stationary. A pinned connection is preferred. The L TYPE ABUTMENT ANCHOR detail, as shown below, must be added to the abutment Plan Sheets. The pinned anchor for bridges with L type abutments shall be a #5 bar at one foot spacing, bent as shown, with 1’-0” embedment into both the pier and the bridge approach slab. This bar shall be included in the bar list for the bridge substructure.




L Type Abutment Anchor Detail
Figure 10-14

10.6.4 Skewed Approach Slabs

For all skewed abutments, the roadway end of the bridge approach slab shall be normal to the roadway centerline.

The Bridge Supervisor should be consulted when approach slab skew is greater than 30 degrees or significantly wide (three lanes or more). These conditions will vary the required approach slab length. The roadway end of the approach may be stepped or staggered to reduce the size or to accommodate staging construction widths.



Flared Corner Steel
Figure 10-15

In addition, for bridges with skews greater than 30 degrees additional steel reinforcing bars shall be added to the acute corners of the bridge approach slabs. Typical placement is shown in the FLARED CORNER STEEL detail. The flared corner steel should be #5 rebar, 10 feet long, epoxy coated, and placed on top of the top layer of steel.

10.6.5 Bridge Approach Approach Detailing

The bridge approach slab and length along center line of project shall be shown in the Plan View of the Bridge Layout sheet. The Bridge Plans will also include approach slab information as shown on BDM Sheets 10.6-A1.1 and 10.6-A1.2. The Approach Slab Plan sheets should be modified as appropriate to match the bridge site conditions. Generally, both anchor types shown on the second sheet are not used on the bridge. The anchor not used should be deleted.

Additional details may be required to address special roadway features and construction requirements such as: roadway curbs and barriers, sidewalks, utilities and conduits and staging. This means, if sidewalks and interior barriers (such as traffic-pedestrian barriers) are present, special details will be required in the Bridge Plans to show how the sidewalks and interior barriers are connected to and constructed upon the bridge approach slab.

10.6.6 Pavement Seats on Existing Bridges

When approach slabs are added to existing bridges, the pavement seats may require modification. If the existing pavement seat is less than 10 inches, the seat shall be replaced with an acceptable, wider pavement seat. The Bridge Design Engineer may modify this requirement on a site-specific basis. Generic pavement seat repair details are shown in the BDM Sheet 10.6-A2.1 for a concrete repair and sheet 10.6-A2.2 for a steel T-section repair. These sheets can be customized for the project and added to the Bridge Plans.

10.7 Traffic Barrier on Approach Slabs

Placing the traffic barrier on the approach slab is beneficial for the following reasons.

- The approach slab resists traffic impact loads and may reduce wing wall thickness
- Simplified construction and conduit placement
- Bridge runoff is diverted away from the abutment

Most bridges will have some long-term differential settlement between the approach roadway and the abutment. Therefore, a gap between the approach slab and wing (or wall) should be shown in the details. The minimum gap is twice the long-term settlement, or 2 inches. A 3 inch gap is also acceptable as shown in Figure 10-16.

When the traffic barrier is placed on the approach slab, the following barrier guidelines apply.

- Barrier should extend to the end of the approach slab
- Bridge railing may stop near the point where the fill is at the same elevation as the grade
- Conduit deflection or expansion fittings must be called out at the joints
- Junction box locations should start and end in the approach
- The transverse top reinforcing in the slab meets the minimum steel requirements. This is not enough reinforcement to resist barrier collision forces. Therefore, a 6’-0” (hooked) #6 epoxy coated bar should be added to the approach slab as shown in Figure 10-16.




Figure 10-16

10.7.1 Approach Slab over Wing Walls, Cantilever Walls or Geosynthetic Walls

All walls that are cast-in-place below the approach slab should continue the barrier soffit line to grade. This includes geosynthetic walls that have a cast-in-place fascia. Figure 10-16 shows a generic layout at an abutment. Note the sectional Gap Detail, Figure 10-16, applies.




Figure 10-17

10.7.2 Approach Slab over SE Walls

The tops of Structure Earth (SE) walls are uneven and must be covered with a fascia to provide a smooth soffit line. Usually SE walls extend well beyond the end of the approach slab and require a moment slab. Since SEW barrier is typically 5'-0" deep from the top of the barrier, the soffit of the SEW barrier and bridge barrier do not match. The transition point for the soffit line should be at the bridge expansion joint as shown in Figure 10-19. This requires an extended back side of the barrier at the approach slab to cover the uneven top of the SE wall.

Battered wall systems, such as block walls, use a thickened section of the curtain wall to hide some of the batter. The State Bridge and Structures Architect will provide dimensions for this transition when required.




Figure 10-18




Figure 10-19

10.8 Utilities Installed with New Construction

10.8.1 General Concepts

The utilities to be considered under this section are electrical (power and communications) volatile fluids (gas), water, and sewer/storm water pipes. The Bridge designer shall determine if the utility may be attached to the structure and the location. Bridge plans shall include all hardware specifications and details for the utility attachment as provided in any written correspondence with the utility.

The Specifications Engineer will contact the Region Utility Engineer for additional design or construction requirements that may be stipulated in the utility agreement.

Responsibilities of the Utility Company

The Region or utility company will initiate utility installations and provide design information. The utility company shall be responsible for calculating design stresses in the utility and design of the support system. Utility support design calculations with, a State of Washington Profession Engineer stamp, shall be submitted to the Bridge and Structures Office for review. The following information shall be provided by the Utility Company and shown in the final Bridge Plans.

- Location of the utility outside the limits of the bridge structure
- Number of utilities, type, size, and weight (or Class) of utility lines
- Utility minimum bending radius for the conduit or pipeline specified

Utility General Notes and Design Criteria are stated in DOT Form 224-047 "General Notes and Design Criteria for Utility Installations". This form outlines most of the general information required by the Utility Company to design their attachments. The Bridge Office will generally provide the design for lightweight hanger systems, such as electrical conduits, attached to new structures.

Confined Spaces

A confined space is any place having a limited means of exit that is subject to the accumulation of toxic or flammable contaminants or an oxygen deficient environment. Confined spaces include but are not limited to pontoons, box girder bridges, storage tanks, ventilation or exhaust ducts, utility vaults, tunnels, pipelines, and open-topped spaces more than 4 feet in depth such as pits, tubes, vaults, and vessels. The designer should provide for the following:

- A sign with "Confined Space Authorized Personnel Only."
- In the "Special Provisions Check List," alert and/or indicate that a special provision might be needed to cover confined spaces.

Coating and Corrosion Protection

When the bridge is to receive pigmented sealer, consideration shall be given to painting any exposed utility lines and hangers to match the bridge. When a pigmented sealer is not required, steel utility conduits and hangers shall be painted or galvanized for corrosion protection. The special provisions shall specify cleaning and painting procedures.

10.8.2 Utility Design Criteria

All utilities shall be designed to resist Strength and Extreme Event Limits States. This includes and not limited to dead load, expansion, surge, and earthquake forces. Designers should review DOT Form 224-047 "General Notes and Design Criteria" and the items in this section when designing a utility system or providing a review for an existing bridge attachment.

The Bridge Engineer shall review the utility design to ensure the utility support system will carry all transverse and vertical loading. Loading will include (and is not limited to): Dead Load, Temperature expansion, dynamic action (water hammer), and Seismic inertial load.

Utility Location

Utilities should be located, if possible, such that a support failure will not result in damage to the bridge, the surrounding area, or be a hazard to traffic. In most cases, the utility is installed between girders. Utilities and supports must not extend below the bottom of the superstructure. Utilities shall be installed no lower than 1 foot 0 inches above the bottom of the girders. In some cases when appurtenances are required (such as air release valves), care should be taken to provide adequate space. The utility installation shall be located so as to minimize the effect on the appearance of the structure. Utilities shall not be attached above the bridge deck nor attached to the railings or posts.

Termination at the Bridge Ends

Utility conduit and encasements shall extend 10 feet minimum beyond the ends of the structure in order to reduce effects of embankment settlement on the utility and provide protection in case of future work involving excavation near the structure. This requirement shall be shown on the plans. Utilities off the bridge must be installed prior to paving of approaches. This should be stated in the Special Provisions.

Utility Expansion

The utilities shall be designed with a suitable expansion system as required to prevent longitudinal forces from being transferred to bridge members.

Water mains generally remain a constant temperature and are anchored in the ground at the abutments. However, the bridge will move with temperature changes and seismic forces. Pipe support systems must be designed to allow for the bridge movements. For short bridges, this generally means the bridge will move and the utility will not since it is anchored at the abutments. For long bridges that require pipe expansion joints, design must carefully locate pipe expansion joints and the corresponding longitudinal load-carrying support.

Electrical conduits that use PVC should have an expansion device for every 100 foot of pipe due to the higher coefficient of expansion. If more than two joints are specified, a cable or expansion limiting device is required to keep the ends from separating.

Gas Lines or Volatile Fluids

Pipeline carrying volatile fluids shall be designed by the Utility Company, in accordance with WAC 480-93-010. The pipeline material usually specified is Schedule 40 steel or Polyethelene (PE) pipe. All pipelines carrying volatile fluids shall be encased the length of the structure in steel encasement pipe and braced for lateral loading, see WAC 480-93-115 and Title 49 Code of Federal Regulations (CFR) Section 192.323, Transportation of Natural and Other Gas by Pipeline: Minimum Safety Standards. The space between the carrying pipe and the encasement sleeve shall be effectively vented beyond the structure at each end and at high points. Normally, the utility company will make provisions to electrically insulate the gas line from its support and vent the casing. Lines carrying other volatile materials shall be supported, as required by the utility, with due care taken to protect the structure and traffic.

Generally, a PVC sleeve approximately 3 inches larger than the outside diameter of the encasement pipe shall be used to pass the utility through concrete diaphragms or abutments.

Water Lines

Water lines shall be galvanized steel pipe or ductile iron pipe. Transverse support or bracing shall be provided for all water lines to carry Strength and Extreme Event Lateral Loading. Fire control piping is a special case where unusual care must be taken to handle the inertial loads and associated deflections. Normally, the Hydraulic Section will also be involved in this case.

In box girders (closed cell), a rupture of a water line will generally flood a cell before emergency response can shut down the water main. This will be designed for as an Extreme Event II load case, where the weight of water is a dead load (DC). Additional weep holes or open grating should be considered to offset this Extreme Event (see Figure 8.3.5-3).

Sewer Lines

Normally, an appropriate encasement pipe is required for sewer lines on bridges. Sewer lines must meet the same design criteria as waterlines. See the utility agreement or the Hydraulic Section for types of sewer pipe material typically used.

Telephone and Power Conduit

Generally, telephone, television cable, and power conduit shall be galvanized steel pipe or a PVC pipe of a UL approved type and shall be Schedule 40 or heavier. Where such conduit is buried in concrete curbs or barriers or has continuous support, such support is considered to be adequate. Where hangers or brackets support conduit at intervals, the distance between supports shall be small enough to avoid excessive sag between supports. See Section 10.8.7, Pipe Supports. Generally, the conduit shall be designed to support the cable in bending without exceeding working stresses for the conduit material.

10.8.3 Box Girder Bridges

Internal illumination is required for steel box girder bridges, and appropriate conduit piper and fixtures shall be detailed as part of the bridge design. Girder cells with utilities must have access. Current practice for access is to locate hatches in the bottom flange. More than one hatch is usually required to access all sections of the cell in a bridge.

Access and ventilation shall always be provided in box girder cells containing gas lines.

Continuous Support and Concrete Pedestals

Special utilities (such as water or gas mains) in box girder bridges should use concrete pedestals. This allows the utility to be placed, inspected, and tested before the deck is cast. Concrete pedestals consist of concrete supports formed at suitable intervals and provided with some type of clamping device. A continuous support may be achieved by providing a ledge of concrete to support the conduit. Continuous supports should be avoided due to the very high cost and additional dead load to the structure.




Figure 10-20

10.8.4 Traffic Barrier Conduit

All new bridge construction will install two (2) 2-inch galvanized steel conduits in the traffic barriers. These conduits generally carry wiring for Traffic Signals (TS) and Lighting (LT). Other wiring may be installed or the conduit may be used for future applications.

Conduits shall be stubbed-out at a concrete junction box provided in the Region Plans. The Bridge Plans must show the placement of the conduits to clear the structure or any foreseeable obstructions.

The galvanized steel conduit shall be wrapped with corrosion resistant tape at least one foot inside and outside of the concrete structure, and this requirement shall be so stated on the plans. The corrosion resistant tape shall be 3M Scotch 50, Bishop 5, Nashua AVI 10, or approved equal. The usual location of the conduit throughout the remainder of the bridge should be in the traffic barrier.

Pull boxes shall be provided at a maximum spacing of 180 feet. Their size shall conform to the specifications of the National Electric Code or be a minimum of 6 inches by 6 inches by 18 inches to facilitate pulling of wires. Galvanized steel pull boxes (or junctions boxes) shall me et the specifications of the "NEMA Type 4X" standard and shall be stated on the plans. Stainless steel pull boxes shall be allowed as an option to the galvanized steel.

In the case of existing bridges, an area 2 feet in width shall be reserved for conduit beginning at a point either 4 feet or 6 feet outside the face of usable shoulder. The fastening for and location of attaching the conduit to the existing bridge should be worked out on a job-by-job basis.

10.8.5 Conduit Types

All electrical conduits shall be Rigid Galvanized Steel (RGS) or PVC pipe, Schedule 40 or greater.

Steel Pipe

All steel pipe utility conduits shall be Schedule 40 or greater. All pipe and fittings shall be galvanized except for special uses.

PVC Pipe

PVC pipe may be used with suitable considerations for deflection, placement of expansion fittings, and of freezing water within the conduits. PVC pipe should not be placed in concrete traffic barriers due to damage and pipe separation that often occurs during concrete placement of slip formed barriers.

High Density Polyethylene (HDPE)

This material may be specified by some utilities. Unless other data is available, support as for PVC. Same restrictions to traffic barriers apply.

10.8.6 Utility Supports

The following types of supports are generally used for various utilities. Selection of a particular support type should be based on the needs of the installation and the best economy. All utility installations shall address temperature expansion in the design of the system or expansion devices.

Utility supports shall be designed so that a failure will not result in damage to the bridge, the surrounding area, or be a hazard to traffic. Utility supports shall be designed so that any loads imposed by the utility installation do not overstress the conduit, supports, bridge structure, or bridge members.

Designs shall provide longitudinal and transverse support for loads from gravity, earthquakes, temperature, inertia, etc. It is especially important to provide transverse and longitudinal support for Anvil inserts and other similar inserts that cannot resist moment.

The Bridge Engineer should request calculations from the utility company for any attachment detail that may be questionable. Utility attachments, which exert moments or large forces at the supports, shall be accompanied by at least one set of calculations from the utility company. Bridge attachments designed to resist surge forces should always be accompanied by calculations.

Concrete Embedment

This is the best structural support condition and offers maximum protection to the utility. Its cost may be high for larger conduit and the conduit cannot be replaced.

Pipe Hangers

Utility lines shall be suspended by means of cast-in-place anchors, whenever possible. This is the most common type of support for utilities to be hung under the bridge deck. This allows the use of standard cast-in-place inserts and is very flexible in terms of expansion requirements. For heavy pipes over traffic (10” water main or larger), a Safety Factor of 1.5 should be used to resist vertical loads for Strength design. This is to avoid complete failure of the utility hanger system by failure of one hanger. Vertical Anvil Insert, Figure 282 or similar inserts, will not provide resistance to longitudinal forces.

Transverse supports must be provided by a second hanger extending from a girder or by a brace against the girder. The BDM Sheets 10.8-A1.1 and 10.8-A1.2 depict typical utility support installations and placement at abutments and diaphragms.

Where PVC conduit is to be supported by hangers or pedestals at intervals, the distance between supports shall be small enough to avoid excessive sag of the conduit. For recommended support spacing and tabulated properties of PVC pipe, see Table 10-21.

PROPERTIES OF PVC PIPE

The following are recommended support spacings for PVC pipe.
(Ref: Western Plastics Corporation)

PVC Schedule 40

Nominal Size Inches	MM	O.D. Inches	MM	I.D. Inches	MM	Wall Thickness Inches	MM	Pounds Per 100 Feet	Newtons Per Meter	Recom. Support Spacing* (Feet)	(M)
¾	19	1.050	26.7	.824	20.9	.113	2.87	22.0	1.80	4	1.2
1	25	1.315	33.4	1.049	26.6	.133	3.38	32.0	2.67	4½	1.4
1¼	32	1.660	42.2	1.380	35.1	.140	3.50	43.5	3.61	5	1.5
1½	38	1.900	48.3	1.610	40.9	.145	3.68	52.0	4.31	5	1.5
2	51	2.375	60.3	2.067	52.5	.154	3.91	69.5	5.78	5	1.5
2½	64	2.875	73.0	2.469	62.7	.203	5.16	109.5	9.18	6	1.8
3	75	3.500	88.9	3.068	77.9	.216	5.49	143.0	12.0	6	1.8
4	102	4.500	114.3	4.026	102.3	.237	6.02	203.5	17.1	6½	2.0
5	127 (Use 5" PVC Class 200)							276.0	23.2	7	2.1
6	152	6.625	168.3	6.065	154.1	.280	7.11	359.0	30.1	7½	2.3
8	203 (Use 8" PVC Class 160)									8	2.4
10	254									8½	2.6
12	310									9½	2.9

PVC Schedule 80

Nominal Size Inches	MM	O.D. Inches	MM	I.D. Inches	MM	Wall Thickness Inches	MM	Pounds Per 100 Feet	Newtons Per Meter	Recom. Support Spacing* (Feet)	(M)
½	13	.840	21.3	.546	13.9	.147	3.73	20.5	1.72	4½	1.4
¾	19	1.050	26.7	.742	18.8	.154	3.91	28.0	2.34	4½	1.4
1	25	1.315	33.4	.957	24.3	.179	4.55	41.0	3.45	5	1.5
1¼	32	1.660	42.2	1.278	32.5	.191	4.85	56.5	4.76	5½	1.7
1½	38	1.900	48.3	1.500	38.1	.200	5.08	68.5	5.78	5½	1.7
2	51	2.375	60.3	1.939	49.3	.218	5.54	94.5	7.99	6	1.8
2½	64	2.875	73.0	2.323	59.0	.276	7.01	144.5	12.2	6½	2.0
3	75	3.500	88.9	2.900	73.7	.300	7.62	193.0	16.3	7	2.1
4	102	4.500	114.3	3.826	97.2	.337	8.56	282.0	23.8	7½	2.3
5	127	5.563	141.3	4.813	122.3	.375	9.53	392.0	33.0	8	2.4
6	152	6.625	168.3	5.761	146.3	.432	10.97	539.0	45.4	9	2.7
8	203									9½	2.9

*Spacings shown are set for a 100° maximum temperature.

The physical properties of PVC material are:

E = 410,000 psi
Tensile Strength = 7,300 psi at 78°F
Working Stress in Bending 4.0 k/in.^{2}
Temperature Coefficient - .035 inches per 100 degrees F per foot

Table 10-21

10.9 Utility Review Procedure for Installation on Existing Bridges

It is the responsibility of the Region Utilities Engineer to forward any proposed existing bridge attachments to the Bridge Preservation Office. The Bridge Preservation Office is responsible for reviewing only those details pertaining to the bridge crossing such as attachment details or trenching details adjacent to bridge piers or abutments.

The Bridge Preservation Office reviews proposed utility attachments and either approves the attachment or Returns For Correction (RFC). A current file for most utility attachments is maintained in the Bridge Preservation Office. The turnaround time for reviewing the proposals should not exceed two weeks; however, most attachments that have simple connections with epoxy anchors can be reviewed, stamped, and responded to within one day. This is provided that corrections and additional notes are minimal.

Occasionally, a utility company will request a conceptual approval of their proposed attachment before they invest their time in detailed drawings and calculations. Often they will request this approval by sending a sketch of their proposal directly to the Bridge Office. A letter of response will be sent directly to the utility that concurs with their proposal or suggests an alternate. This letter includes instructions for them to resubmit their final proposal through the Region Utilities Engineer with a courtesy copy of this letter sent to the Region Utilities Engineer.

The Region determines the number of copies to be returned. Most Regions send five copies of the proposed utility attachment. If the proposal is approved, Bridge Preservation will file one copy in the Utility file and return four marked copies. If it has been returned for correction or not approved, one copy is placed in the utility file and two marked copies are returned, thru the Region, to the Utility. See BDM Section 10.9.1, "Utility Review Checklist".

Utility attachments, which exert moments or large forces at the supports, should be accompanied by at least one set of calculations from the utility company. Bridge attachments designed to resist surge forces should always be accompanied by calculations. The engineer may request calculations from the utility company for any attachment detail that may be questionable.

The engineer shall check the utility company's design with his own calculations. The connection detail shall be designed to successfully transfer all forces to the bridge without causing overstress in the connections or to the bridge members to which they are attached. For large utilities, the bridge itself shall have adequate capacity to carry the utility without affecting the live load capacity.

Guidelines for Utility Companies

Detailing guidelines for utility companies to follow when designing utility attachments are listed in DOT Form 224-047, "General Notes and Design Criteria for Utility Installations to Existing Bridges". Commonly used systems are detailed in the BDM Sheet 10.9-A1.1, "Utility Installation Guideline Details for Existing Bridges".

10.9.1 Utility Review Checklist

This checklist applies to all proposed utility attachments to existing bridges.

1. Complete cursory check to become familiar with the proposal.
2. Determine location of existing utilities.
    a. Check Bridge Inspection Report for any existing utilities.
    b. Check Bridge Preservation's utility file for any existing utility permits or franchises and possible as-built plans.
    c. Any existing utilities on the same side of the structure as the proposed utility should be shown on the proposal.
    d. Obtain as-built plans from bridge vault if not in an existing utility file.

3. Review the following with all comments in red:
    a. Layout that includes dimension, directions, SR number and bridge number.
    b. Adequate spacing of supports.
    c. Adequate strength of supports as attached to the bridge (calculations may be necessary).
    d. Maximum design pressure and regular operating pressure for pressure pipe systems.
    e. Adequate lateral bracing and thrust protection for pressure pipe systems.
    f. Does the utility obstruct maintenance or accessibility to key bridge components?
    g. Check Location (elevation and plan view) of the utility with respect to pier footings or abutments. If trench limits encroach within the 45° envelope from the footing edge, consult the Materials Lab.
    h. Force mains or water flow systems may require encasement if they are in excavations below the bottom of a footing.
4. Write a letter of reply or email to the Region so that a copy will be returned to you indicating that the package has been accepted and sent out.
5. Stamp and date the plans using the same date as shown on the letter of reply or email.
6. Create a file folder with the following information:
    a. Bridge no., name, utility company or utility type, and franchise or permit number.
    b. One set of approved plans and possibly one or two pages of the original design plans if necessary for quick future reference. Previous transmittals and plans not approved or returned to correction should be discarded to avoid unnecessary clutter of the files.
    c. Include the letter of submittal and a copy of the letter of reply or email after it has been accepted.
7. Give the complete package to the section supervisor for review and place the folder in the utility file after the review.

10.10 Drainage Design

Even though it is rare that poor drainage is directly responsible for a structural failure, it still must be a primary consideration in the design. Poor drainage can cause problems such as ponding on the roadway, erosion of abutments, and deterioration of structural members. Collecting the runoff and transporting it away from the bridge can prevent most of the problems. Proper geometrics during the preliminary stage is essential in order to accomplish this. The Hydraulics Section recommends placing the bridge deck drainage off of the structure. Therefore, the Bridge Design Section has adopted the policy that all expansion joints will be watertight.

Geometrics

Bridges should have adequate transverse and longitudinal slopes to allow the water to run quickly to the drains. A transverse slope of .02″/ft. and longitudinal slope of 0.5 percent for minimum valves are adequate. Avoid placing sag vertical curves and superelevation crossovers on the structure that could result in hydroplaning conditions or, in cold climates, sheets of ice from melting snow. The use of unsymmetrical vertical curves may assist the designer in shifting the low point off the structure.

Hydrology

Hydrological calculations are made using the rational equation. A 10-year storm event with a 5-minute duration is the intensity used for all inlets except for sag vertical curves where a 50-year storm intensity is required.

On Bridge Systems


Where bridge length and geometry require a bridge drain system within the bridge, the first preference is to place 5-inch diameter pipe drains that have no bars and drop straight to the ground. At other times, such as for steel structures, the straight drop drain is unacceptable and a piping system with bridge drains is required. The minimum pipe diameter should be 6 inches with no sharp bends within the system.

Construction

Bridge decks have a striated finish in accordance with the Standard Specifications listed below, however, the gutters have an untextured finish (steel trowel) for a distance of 2 feet from the curb. This untextured area provides for smooth gutter flow and a Manning n value of .015 in the design.


Standard Specification Section 6-02.3(10) — Bridge Decks

Standard Specification Section 5-05.3(11) — Approach Slabs



≠ STOCKBRIDGE TYPE 31 LBS. VIBRATION DAMPER. MOUNT ON BACKSIDE OF BEAM.

ELEVATION



BEAM CAMBER DIAGRAM

LEGEND

B / 15 — IDENTIFIES SECTION, VIEW OR DETAIL
TAKEN OR SHOWN ON BRIDGE SHEET 15

B / — TAKEN OR SHOWN ON THE SAME SHEET

GENERAL NOTES

1. ALL MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE WASHINGTON STATE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD, BRIDGE AND MUNICPAL CONSTRUCTION (ENGLISH) DATED 2002 AND AMENDMENTS.
2. ALL BUTT JOINT WELDS SHALL BE FULL PENETRATION GROOVE WELDS WITH BACK--UP PLATES OF ¼" MIN. THICKNESS.
3. THE BACK-UP PLATES FOR ALL FULL PENETRATION WELDS SHALL BE WELDED CONTINUOUSLY TO THE JOINED PIECES. THIS CAN BE DONE BY EITHER A CONTINUOUS FILLET WELD ON THE BACK SIDE OF THE PIECE, OR BY A CONTINUOUS WELD IN THE ROOT OF THE FULL PENETRATION WELD.
4. ALL BOLTS, RODS AND RELATED HARDWARE SHALL BE GALVANIZED AFTER FABRICATION PER AASHTO M 232.
5. STEEL SURFACES SHALL BE GALVANIZED AFTER FABRICATION IN ACCORDANCE WITH AASHTO M 111. ALL EXTERIOR STEEL SURFACES SHALL BE PAINTED IN ACCORDANCE WITH THE SPECIAL PROVISIONS.
6. SIGN PANELS AS SHOWN IN THE CONTRACT PLANS SHALL BE INSTALLED WITH THE SIGN STRUCTURE OR IMMEDIATELY AFTER THE SIGN STRUCTURE IS ERECTED.
7. FABRICATE BEAM TO PROVIDE SMOOTH PARABOLIC CAMBER CURVE. SEE CAMBER DIAGRAM. DO NOT SHIM AT BOLTED SPLICES.
8. FABRICATE POSTS STRAIGHT.
9. MATERIALS SPECIFICATIONS:


ALL STRUCTURAL STEEL	ASTM A572 GR. 50 OR ASTM A 588
ANCHOR RODS	ASTM F 1554 GR. 105
HANDHOLE COVER SCREWS	ASTM F 593 GR. 1
SPLICE BOLTS	AASHTO M 164
SIGN BRACKET BOLTS	ASTM A 307
MOUNTING BEAM BOLTS	AASHTO M 164
COVER PLATES	ASTM A36

10. BASE ELEVATIONS AND POST HEIGHTS SHOWN ARE APPROXIMATE. THE CONTRACTOR SHALL FIELD MEASURE ANCHOR BOLT LOCATIONS, ELEVATIONS AND ALL STEEL STRUCTURE DIMENSIONS PRIOR TO THE FABRICATION OF THE STRUCTURAL STEEL AND NOTIFY THE ENGINEER OF ANY DISCREPANCIES. FINAL VALUES WILL BE FURNISHED BY THE ENGINEER PRIOR TO FABRICATION.
11. SEE OTHER PLANS FOR CONDUIT LOCATIONS, CONDUCTOR PENETRATIONS AND ADDITIONAL HAND HOLES.
12. POSTS, BASE PLATES, BEAMS AND SPLICE PLATES ARE MAIN LOAD CARRYING TENSILE MEMBERS OR TENSION COMPONENTS OF FLEXURAL MEMBERS AND SHALL MEET THE LONGITUDINAL CHARPY V-NOTCH TESTS AS DESCRIBED IN SECTION 6-03.2 FOR AASHTO M 270 MATERIAL. NON-DESTRUCTIVE TEST ACCEPTANCE CRITERIA TO CONFORM TO TENSILE MEMBERS WITH CYCLIC LOAD.


DESIGN CRITERIA

1. THE SIGN STRUCTURE DESIGN AND ANALYSIS HAS BEEN DONE IN ACCORDANCE WITH AASHTO STANDARD SPECIFICATIONS FOR STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS, LUMINAIRES AND TRAFFIC SIGNALS - FOURTH EDITION - DATED 2001. 90 MPH BASIC WIND SPEED AND 50 YEAR DESIGN LIFE WERE ASSUMED. THE STRUCTURE CONFORMS TO FATIGUE DESIGN, CATEGORY 1.
2. THE MAXIMUM SIGN AREA ON A STRUCTURE SHALL BE AS NOTED.

Monotube Sign Structures Sign Bridge Layout
Figure 10-A-1



ELEVATION



BEAM CAMBER DIAGRAM

LEGEND

B — IDENTIFIES SECTION, VIEW OR DETAIL

B / 15 — TAKEN OR SHOWN ON BRIDGE SHEET 15

B / — — TAKEN OR SHOWN ON THE SAME SHEET

GENERAL NOTES

1. ALL MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE WASHINGTON STATE DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD, BRIDGE AND MUNICPAL CONSTRUCTION (ENGLISH) DATED 2002 AND AMENDMENTS.
2. ALL BUTT JOINT WELDS SHALL BE FULL PENETRATION GROOVE WELDS WITH BACK-UP PLATES OF ¼ INCH MIN. THICKNESS.
3. THE BACK-UP PLATES FOR ALL FULL PENETRATION WELDS SHALL BE WELDED CONTINUOUSLY TO THE JOINED PIECES. THIS CAN BE DONE BY EITHER A CONTINUOUS FILLET WELD ON THE BACK SIDE OF THE PIECE, OR BY A CONTINUOUS WELD IN THE ROOT OF THE FULL PENETRATION WELD.
4. ALL BOLTS, RODS AND RELATED HARDWARE SHALL BE GALVANIZED AFTER FABRICATION PER AASHTO M 232.
5. STEEL SURFACES SHALL BE GALVANIZED AFTER FABRICATION IN ACCORDANCE WITH AASHTO M 111. ALL EXTERIOR STEEL SURFACES SHALL BE PAINTED IN ACCORDANCE WITH THE SPECIAL PROVISIONS.
6. SIGN PANELS AS SHOWN IN THE CONTRACT PLANS SHALL BE INSTALLED WITH THE SIGN STRUCTURE OR IMMEDIATELY AFTER THE SIGN STRUCTURE IS ERECTED.
7. FABRICATE BEAM TO PROVIDE SMOOTH CAMBER. SEE CAMBER DIAGRAM. DO NOT SHIM AT BOLTED SPLICES.
8. FABRICATE POSTS STRAIGHT.
9. MATERIALS SPECIFICATIONS:


ALL STRUCTURAL STEEL EXCEPT AS OTHERWISE NOTED	ASTM A 572 GR. 50 OR ASTM A588
ANCHOR RODS	ASTM F1554 GR. 105
HANDHOLE COVER SCREWS	ASTM F 593 GR. 1
SPLICE BOLTS	AASHTO M 164
SIGN BRACKET BOLTS	ASTM A 307
MOUNTING BEAM BOLTS	AASHTO M 164
COVER PLATES	ASTM A36

10. BASE ELEVATIONS AND POST HEIGHTS SHOWN ARE APPROXIMATE. THE CONTRACTOR SHALL FIELD MEASURE ANCHOR BOLT LOCATIONS, ELEVATIONS AND ALL STEEL STRUCTURE DIMENSIONS PRIOR TO THE FABRICATION OF THE STRUCTURAL STEEL AND NOTIFY THE ENGINEER OF ANY DISCREPANCIES. FINAL VALUES WILL BE FURNISHED BY THE ENGINEER PRIOR TO FABRICATION.
11. SEE OTHER PLANS FOR CONDUIT LOCATIONS, CONDUCTOR PENETRATIONS AND ADDITIONAL HAND HOLES.
12. POSTS, BASE PLATES, BEAMS AND SPLICE PLATES ARE MAIN LOAD CARRYING TENSILE MEMBERS OR TENSION COMPONENTS OF FLEXURAL MEMBERS AND SHALL MEET THE LONGITUDINAL CHARPY V-NOTCH TESTS AS DESCRIBED IN SECTION 6-03.2 FOR AASHTO M 270 MATERIAL. NON-DESTRUCTIVE TEST ACCEPTANCE CRITERIA TO CONFORM TO TENSILE MEMBERS WITH CYCLIC LOAD.


DESIGN CRITERIA

1. THE DESIGN AND ANALYSIS OF THE SIGN STRUCTURES HAS BEEN DONE IN ACCORDANCE WITH AASHTO STANDARD SPECIFICATIONS FOR STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS, LUMINAIRES AND TRAFFIC SIGNALS - FOURTH EDITION - DATED 2001, USING BASIC WIND SPEED OF 90 MPH AND 50 YEARS OF DESIGN LIFE. FATIGUE DESIGN OF THE STRUCTURE CONFORMS TO FATIGUE CATEGORY 1 OF THE SPECIFIED AASHTO STANDARD SPECIFICATIONS.
2. THE MAXIMUM SIGN AREA ON A STRUCTURE SHALL BE AS NOTED.


Monotube Sign Structures Cantilever Layout
Figure 10-A-2



SECTION E
SEE OTHER SHEETS FOR BASES ON BARRIER FOUNDATIONS.




SECTION F
DIAGONAL STIFFENER NOT SHOWN.




DETAIL D
10.1-A1.2

FOR CANTILEVER STRUCTURES ONLY.
¼" CAP SCREWS ASTM F-593 ~ TAP REINFORCEMENT RING WITH 8 TOTAL EQUALLY SPACED AROUND COVER ℄




POST BASE DETAIL C
10.1-A1.1 & 10.1-A1.2



DETAIL A
10.1-A1.1 & 10.1-A1.2


Monotube Sign Structures Structural Details 1

Figure 10-A-3




Monotube Sign Structures Structural Details 2

Figure 10-A-4



TYPE 1 FOUNDATION TABLE					
	SPAN LENGTH ("S")	SHAFT DIAMETER	DEPTH ("Z")	FOUNDATION REINFORCEMENT	
				SIZE ("X")	NUMBER ("Y")
CANTILEVER SIGN	LESS THAN 20'-0"	4'-6"	12'-6"	9	12
	20'-0" TO 30'-0"	4'-6"	15'-0"	9	16
SIGN BRIDGE	LESS THAN 60'-0"	4'-6"	15'-6"	9	18
	60'-0" TO 90'-0"	4'-6"	19'-0"	9	20
	90'-0" TO 120'-0"	5'-0"	21'-9"	11	15 BUNDLED PAIRS
	120'-0" TO 150'-0"	5'-0"	23'-6"	11	17 BUNDLED PAIRS


SHAFT DEPTH "Z" IS BASED ON ALLOWABLE LATERAL BEARING PRESSURE OF 2500 PSF OR MORE.



SCREEN DETAIL

ANCHOR ℄ DETAIL


MATCH ANCHOR BOLT SIZE, NUMBER & PATTERN




PLAN

BAR LIST					
MARK	LOCATION	SIZE	NO. REQ'D.	LENGTH	
1	CAP VERTICAL	4	4	3'-9"	STR.
2	CAP HOOPS	5	5	"A"	
3	SHAFT VERTICAL	"X"	"Y"	"Z"-6"	STR.
4	SHAFT SPIRAL	4	1	"A"	
5	CAP TOP	5	4	"A"	

AASHTO M 31 GR. 60 "A" ~ DETERMINE FROM PLANS





VIEW

Monotube Sign Structures Foundation Type 1

Figure 10-A-5

TYPE 2 FOUNDATION TABLE**					
STRUCTURE TYPE	SPAN LENGTH ("S")	DEPTH ("Z")	REINFORCEMENT		
			SIZE ("X")	SPACING ("Y1")	SPACING ("Y2")
CANTILEVER SIGN	LESS THAN 20'-0"	7'-3"	9	8	4
	20'-0" TO 30'-0"	9'-6"	9	12	8
SIGN BRIDGE	LESS THAN 60'-0"	9'-0"	9	12	8
	60'-0" TO 90'-0"	11'-0"	9	16	12
	90'-0" TO 120'-0"	12'-9"	11	14	10
	120'-0" TO 150'-0"	13'-6"	11	16	14

* SHAFT DEPTH "Z" IS BASED ON ALLOWABLE LATERAL BEARING PRESSURE OF 2500 PSF OR MORE.


TYPE 3 FOUNDATION TABLE**					
STRUCTURE TYPE	SPAN LENGTH ("S")	** DEPTH ("Z")	REINFORCEMENT		
			SIZE ("X")	SPACING ("Y1")	SPACING ("Y2")
CANTILEVER SIGN	LESS THAN 20'-0"	11'-0"	9	8	4
	20'-0" TO 30'-0"	13'-9"	9	12	8
SIGN BRIDGE	LESS THAN 60'-0"	12'-9"	9	12	8
	60'-0" TO 90'-0"	15'-6"	9	16	12
	90'-0" TO 120'-0"	17'-9"	11	14	10
	120'-0" TO 150'-0"	19'-6"	11	16	14


** SHAFT DEPTH "Z" IS BASED ON ALLOWABLE LATERAL BEARING PRESSURE BETWEEN 1500 PSF AND 2499 PSF.

BAR LIST					
MARK	LOCATION	SIZE	NO. REQ'D.	LENGTH	
1	CAP VERTICAL	"X"	"Y1"	9'-8"	
2	CAP HOOPS	5	6	16'-0"	
3	CAP HORIZONTAL	5	6	"a"	
4	FOUNDATION HOOPS	5	16	15'-5"	STR.
5	FOUNDATION VERTICAL	"X"	"Y2"	"Z" - 6"	
6	FOUNDATION VERTICAL	"X"	"Y2"	"Z" = 4'-0"	
7	FOUNDATION VERTICAL	5	18	"a"	STR.
8	CAP TOP	5	4	10'-4"	STR.


AASHTO M 31 GR. 60

"a" ~ DETERMINE FROM PLANS






PLAN



SECTION S


ANCHOR ROD ~ "D1"ø x 4'-4" LONG THREADED ROD WITH 4 WASHERS AND 4 HEAVY HEX NUTS (TYP.). THREAD EACH END 8". GALVANIZE EXPOSED ANCHOR ROD END FOR 1'-0" MIN.

NOTE: USE A TEMPLATE TO LOCATE AND SECURE BOLTS IN PLACE DURING FOUNDATION INSTALLATION. FOR DETAILS, SEE DETAIL R, THIS SHT.




ELEVATION

* USE CONCRETE CLASS 4000W IF WATER IS PRESENT IN THE EXCAVATION.



VIEW A




ANCHOR ℄ DETAIL

MATCH ANCHOR BOLT SIZE, NUMBER & PATTERN.

Monotube Sign Structures Foundation Types 2 and 3

Figure 10-A-6



PLAN


SPAN	D	F
60' & UNDER	1½"	3'-2"
60' TO 90'	2"	3'-5"
90' TO 120'	2¼"	3'-5"
120' & OVER	N/A	N/A


BAR LIST

MARK	LOCATION	SIZE	NO. REQ'D.	LENGTH	
11	MEDIAN BARRIER ~ HORIZ.	5	10 (11*)	9'-9"	STR.
12	MEDIAN BARRIER ~ VERT.	5	14	6'-10" (VARIES*)	
13	MEDIAN BARRIER ~ VERT.	5	28 (14*)	5'-10" (VARIES*)	


AASHTO M 31 GR. 60

* DIFFERENT ROADWAY ELEVATIONS
≠ DIFFERENCE IN ROADWAY ELEVATIONS







ELEVATION




SECTION A
EQUAL ROADWAY ELEVATIONS



SECTION A
DIFFERENT ROADWAY ELEVATIONS



BASE PLATE
FOR INFORMATION NOT SHOWN SEE DETAIL C, SHEET 10.1-A2.2




ANCHOR ℄ DETAIL

NOTE:
1. FOR TYPE 1 FOUNDATION, SEE SHEET 10.1-A3.1 .
2. FOR TYPE 2 & 3 FOUNDATION, SEE SHEET 10.1-A3.2 .

Monotube Sign Structures Double Faced Barrier Foundation

Figure 10-A-7




PLAN
BARRIER TRANSITION


SPAN	D	F
60' & UNDER	1½"	3'-2"
60' TO 90'	2"	3'-5"
90' TO 120'	2¼"	3'-5"
120' & OVER	N/A	N/A

BAR LIST


MARK	LOCATION	SIZE	NO. REQ'D	LENGTH	
21	MEDIAN BARRIER HORIZONTAL	5	10	9'-9"	STR.
22	MEDIAN BARRIER VERTICAL	5	14	6'-8"	
23	MEDIAN BARRIER VERTICAL	5	28	5'-10"	

AASHTO M 31 GR. 60







ELEVATION



SECTION A



BASE PLATE
FOR INFORMATION NOT SHOWN SEE DETAIL C, SHEET 10.1-A2.2




ANCHOR ℄ DETAIL

NOTE:
TYPE 1 FOUNDATION SHOWN.
TYPE 2 & 3 FOUNDATIONS SHOWN DASHED.
FOR VALUES OF "D" AND "F" SEE TABLE THIS SHEET.


Monotube Sign Structures Single Slope Barrier Foundation

Figure 10-A-8




Truss Sign Structures Double Faced Barrier Foundation

Figure 10-A-9




Traffic Barrier – Shape F Details 1 of 3


Figure 10-A-10




END VIEW
W-BEAM SHOWN WITH "D" CONNECTION




END VIEW
THRIE BEAM SHOWN WITH "D" CONNECTION



VIEW A/1
ALL CHAMFERS ¾"




SECTION B




SLIPFORM ALTERNATE

SEE "TYPICAL SECTION - TRAFFIC BARRIER" FOR ADDITIONAL DETAILS

THE CONTRACTOR IS ADVISED THAT THE SLIPFORM CONSTRUCTION METHOD IS A PATENTED PROPRIETARY PROCESS FOR BARRIERS WITH A FRACTURED FIN FINISH.



FRACTURED FIN FINISH



DUMMY JOINT DETAIL

JUNCTION BOX LOCATIONS	
STATION	OFFSET

TRAFFIC BARRIER BAR LIST


ALL REINFORCING SHALL BE AASHTO M31, GR. 60.


MARK	SIZE	LENGTH	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
R1	5	3'-8"	
R1A	5	(A)	
R2	5	2'-11"	
R3	4	(A)	STR.
R4	6	(A)	STR.
R6	4	3'-0"	STR.
R9	5	5'-11"	

* DIMENSIONS TO POINTS OF INTERSECTION

(A) DETERMINE FROM PLANS

FOR W1 & W2 BARS SEE WINGWALL OR RETAINING WALL PLANS.
FOR S1 & S2 BARS SEE BARLIST






SECTION B BRIDGE

FOR DETAILS NOT SHOWN SEE "OUTSIDE ELEVATION" AND "TYPICAL SECTION - TRAFFIC BARRIER"


* BLOCKOUT WIDTH MAY BE INCREASED TO 6" TO ALLOW CONDUITS OF A LARGER DIAMETER THAN 2" TO EXIT BARRIER OR WALL WITHOUT REBAR STEEL CONFLICT



SECTION B WALL


DETAIL FOR RETAINING WALL OR WINGWALL. FOR REINFORCING NOT SHOWN SEE STD. PLAN D-1a & D-1b OR WINGWALL PLAN. FOR DETAILS NOT SHOWN SEE SECTION B BRIDGE

Traffic Barrier - Shape F Details 2 of 3
Figure 10-A-11



PLAN - TRAFFIC BARRIER

TYP. @ END OF MODIFIED TRAFFIC BARIER END SECTION WHERE THRIE BEAM END SECTION "DESIGN F" STD. PLAN C-7a OR GUARDRAIL END SECTION "DESIGN D OR F" STD PLAN C-5 IS USED




ELEVATION - CONDUITS & J-BOX IN TRAFFIC BARRIER

LABEL JUNCTION BOX COVER IN ACCORDANCE WITH STANDARD PLAN J-11a AND SPECIAL PROVISIONS. ADJACENT JUNCTION BOXES ARE SHOWN CENTERED BETWEEN ADJACENT DUMMY JOINTS. IF THE DISTANCE BETWEEN ADJACENT DUMMY JOINTS IS 16'-0" OR GREATER, PLACE ADJACENT JUNCTION BOXES SYMMETRICALLY ON EITHER SIDE OF THE CENTER OF ONE DUMMY PANEL WHILE MAINTAINING 8'-0" MINIMUM BETWEEN CENTER LINES OF THE JUNCTION BOXES.


NOTE TO DESIGNERS

MODIFY THE FOLLOWING TO MATCH PROJECT REQUIREMENTS:
1. BARRIER END SECTION.
2. REMOVE GUARDRAIL IF NOT CONNECTED TO BRIDGE ITEM.
3. CONDUIT ALIGNMENT




CONDUIT EXPANSION FITTING

CONDUIT FITTING - (TYPE AX FOR MOVEMENT OF ± 2") AT BRIDGE EXPANSION JOINTS



CONDUIT DEFLECTION FITTING A

CONDUIT FITTING - TYPE DX FOR DEFLECTION OF 30° AND ¾" MOVEMENT. PLACE AT CONDUIT PIPE EXIT FROM STRUCTURE




CONDUIT DEFLECTION FITTING B

CONDUIT FITTING - TYPE DX FOR DEFLECTION OF 30° AND ¾" MOVEMENT. CONDUIT PIPES PLACED THROUGH RETAIING WALL TRAFFIC BARRIER SHALL BE FITTED WITH DEFLECTION FITTINGS AT A MAXIMUM SPACING OF 120 FEET. THE DEFLECTION FITTINGS SHALL BE PLACED AT THE TRAFFIC BARRIER OPEN JOINT THAT COINCIDES WITH THE RETAINING WALL STEM EXPANSION JOINT NEAREST TO THE TRANSVERSE CONSTRUCTION JOINT IN THE WALL FOOTING.

Traffic Barrier - Shape F Details 3 of 3

Figure 10-A-12



* TOE HEIGHT MAY VARY, 2" MIN. TO 6" MAX.

** HEIGHT MAY VARY IF REQUIRED TO PROVIDE A PROFILE PLEASING TO THE EYE

*** FOR TRANSVERSE ROADWAY SLOPES GREATER THAN 8%, CHANGE THE NOTE TO THE FOLLOWING:
FOR THE LOW SIDE OF THE BRIDGE OR MEDIAN BARRIER -
"PERPENDICULAR TO 8% TRANSVERSE ROADWAY SLOPE"
FOR THE HIGH SIDE OF THE BRIDGE BARRIER -
"PERPENDICULAR TO TRANSVERSE ROADWAY SLOPE"

NOTE TO DESIGNERS

If transverse roadway slope is greater than 8%, S1 & S2 bar bends need to be modified to account for the difference between the actual slope & 8% on the low side only of the bridge or median barrier. The barrier geometry needs to be checked also.


NW REGION:
TERMINATE EACH CONDUIT PIPE AT SEPARATE TYPE 1 JUNCTION BOXES OFF END OF BRIDGE AS SHOWN ON LAYOUT.

ALL OTHER REGIONS:
STUB OUT & CAP 3'-4" FROM END OF BRIDGE BARRIER, EXCEPT TERMINATE IN JUNCTION BOX WHERE AND WHEN SHOWN ON LAYOUT.

Note to Designer: The non-applicable text should be removed from the actual bridge plans.


Traffic Barrier - Shape F Flat Slab - Details 1 of 3

Figure 10-A-13




END VIEW


WITH "D" CONNECTION




DUMMY JOINT DETAIL



ALL CHAMFERS ¾"




SECTION B — B




SLIPFORM ALTERNATE

SEE "TYPICAL SECTION - TRAFFIC BARRIER" FOR ADDITIONAL DETAILS

JUNCTION BOX LOCATIONS	
STATION	OFFSET




FRACTURED FIN FINISH



SECTION C — BRIDGE 1

FOR DETAILS NOT SHOWN SEE "OUTSIDE ELEVATION" AND "TYPICAL SECTION - TRAFFIC BARRIER"

* BLOCKOUT WIDTH MAY BE INCREASED TO 6" TO ALLOW CONDUITS OF A LARGER DIAMETER THAN 2" TO EXIT BARRIER OR WALL WITHOUT REBAR STEEL CONFLICT



*BLOCKOUT WIDTH MAY VARY 3" TO 6" TO ALLOW CONDUITS LARGER THAN 2" TO EXIT BARRIER OR WALL

SECTION C — WALL 1

DETAIL FOR CURTAIN WALL. FOR REINFORCING NOT SHOWN SEE STD. PLAN D-1a & D-1b OR CURTAIN WALL PLAN


▽ DENOTES EPOXY COATED ± DIMENSIONS TO POINTS OF INTERSECTION

TRAFFIC BARRIER BAR LIST

ALL REINFORCING SHALL BE AASHTO M31, GR. 60.

MARK	SIZE	LENGTH	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)	
R1	5	3'- 7"		
R1A	5	(A)		
R2	5	3'-1"		
R3	4	(A)		STR.
R4	6	(A)		STR.
R6	4	3'- 0"		STR.
R9	4	5'- 10"		


(A) DETERMINE FROM PLANS



FOR W1 ▽ & W2 BARS SEE WINGWALL OR RETAINING WALL PLANS.
FOR S1 ▽ & S2 BARS SEE BARLIST


Traffic Barrier - Shape F Flat Slab - Details 2 of 3

Figure 10-A-14



PLAN - TRAFFIC BARRIER

TYP. @ END OF MODIFIED TRAFFIC BARRIER END SECTION WHERE GUARDRAIL "F" CONNECTION IS USED




ELEVATION - CONDUITS & J-BOX IN TRAFFIC BARRIER

LABEL JUNCTION BOX COVER IN ACCORDANCE WITH STANDARD PLAN J-11a AND SPECIAL PROVISIONS. ADJACENT JUNCTION BOXES ARE SHOWN CENTERED BETWEEN ADJACENT DUMMY JOINTS. IF THE DISTANCE BETWEEN ADJACENT DUMMY JOINTS IS 16'-0" OR GREATER, PLACE ADJACENT JUNCTION BOXES SYMETRICALLY ON EITHER SIDE OF OF THE CENTER OF ONE DUMMY PANEL WHILE MAINTAINING A 8'-0" MINIMUM BETWEEN CENTER LINES OF THE JUNCTION BOXES.


NOTE TO DESIGNERS

MODIFY THE FOLLOWING TO MATCH PROJECT REQUIREMENTS:
1. BARRIER END SECTION.
2. REMOVE GUARDRAIL IF NOT CONNECTED TO BRIDGE ITEM.
3. CONDUIT ALIGNMENT




CONDUIT EXPANSION FITTING

CONDUIT FITTING - (TYPE AX FOR MOVEMENT OF ± 2") AT BRIDGE EXPANSION JOINTS




CONDUIT DEFLECTION FITTING A

CONDUIT FITTING - TYPE DX FOR DEFLECTION OF 30° AND ¾" MOVEMENT. PLACE AT CONDUIT PIPE EXIT FROM STRUCTURE




CONDUIT DEFLECTION FITTING B

CONDUIT FITTING - TYPE DX FOR DEFLECTION OF 30° AND ¾" MOVEMENT. CONDUIT PIPES PLACED THROUGH RETAIING WALL TRAFFIC BARRIER SHALL BE FITTED WITH DEFLECTION FITTINGS AT A MAXIMUM SPACING OF 120 FEET. THE DEFLECTION FITTINGS SHALL BE PLACED AT THE TRAFFIC BARRIER OPEN JOINT THAT COINCIDES WITH THE RETAINING WALL STEM EXPANSION JOINT NEAREST TO THE TRANSVERSE CONSTRUCTION JOINT IN THE WALL FOOTING.




Traffic Barrier - Shape F Flat Slab - Details 3 of 3

Figure 10-A-15




Traffic Barrier - Single Slope Details 1 of 3


Figure 10-A-16




END VIEW
THRIE BEAM SHOWN WITH "D" CONNECTION




END VIEW
W-BEAM SHOWN WITH "D" CONNECTION



VIEW A/1
ALL CHAMFERS ¾"




SECTION C/—




SLIPFORM ALTERNATE

SEE "TYPICAL SECTION - TRAFFIC BARRIER" FOR ADDITIONAL DETAILS.


THE CONTRACTOR IS ADVISED THAT THE SLIPFORM CONSTRUCTION METHOD IS A PATENTED PROPRIETARY PROCESS FOR BARRIERS WITH A FRACTURED FIN FINISH.



FRACTURED FIN FINISH




DUMMY JOINT DETAIL



SECTION B/— BRIDGE

DETAIL FOR BRIDGE FOR DETAILS NOT SHOWN SEE "OUTSIDE ELEVATION" AND "TYPICAL SECTION - TRAFFIC BARRIER"

* BLOCKOUT WIDTH MAY BE INCREASED TO 6" TO ALLOW CONDUITS OF A LARGER DIAMETER THAN 2" TO EXIT BARRIER OR WALL WITHOUT REBAR STEEL CONFLICT



SECTION B/— WALL

FOR DETAILS NOT SHOWN SEE "OUTSIDE ELEVATION" AND "TYPICAL SECTION - TRAFFIC BARRIER"

DETAIL FOR RETAINING WALL OR WINGWALL. FOR REINFORCING NOT SHOWN SEE STD. PLAN D-1a & D-1b OR WINGWALL PLAN.

JUNCTION BOX LOCATIONS


STATION	STATION

TRAFFIC BARRIER BAR LIST

ALL REINFORCING SHALL BE AASHTO M31, GR. 60.

MARK	SIZE	LENGTH	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT) ▽ DENOTES EPOXY COATED
R2	5	4'-3"	
R2A	5	(A)	
R3	4	(A)	STR.
R4	6	(A)	STR.
R6	4	3'-0"	STR.
R9	5	7'-5"	


(A) DETERMINE FROM PLANS



FOR W1 & W2 BARS SEE WINGWALL OR RETAINING WALL PLANS. FOR S1 ▽ & S2 BARS SEE BARLIST.


± DIMENSIONS TO POINTS OF INTERSECTION.

Traffic Barrier - Single Slope Details 2 of 3
Figure 10-A-17



PLAN - TRAFFIC BARRIER

TYP. @ END OF MODIFIED TRAFFIC BARIER END SECTION WHERE THRIE BEAM END SECTION "DESIGN F" STD. PLAN C-7a OR GUARDRAIL END SECTION "DESIGN D OR F" STD PLAN C-5 IS USED




ELEVATION - CONDUITS & J-BOX IN TRAFFIC BARRIER

LABEL JUNCTION BOX COVER IN ACCORDANCE WITH STANDARD PLAN J-11a AND SPECIAL PROVISIONS. ADJACENT JUNCTION BOXES ARE SHOWN CENTERED BETWEEN ADJACENT DUMMY JOINTS. IF THE DISTANCE BETWEEN ADJACENT DUMMY JOINTS IS 16'-0" OR GREATER, PLACE ADJACENT JUNCTION BOXES SYMMETRICALLY ON EITHER SIDE OF THE CENTER OF ONE DUMMY PANEL WHILE MAINTAINING 8'-0" MINIMUM BETWEEN CENTER LINES OF THE JUNCTION BOXES.


NOTE TO DESIGNERS

MODIFY THE FOLLOWING TO MATCH PROJECT REQUIREMENTS:
1. BARRIER END SECTION.
2. REMOVE GUARDRAIL IF NOT CONNECTED TO BRIDGE ITEM.
3. CONDUIT ALIGNMENT




CONDUIT EXPANSION FITTING

CONDUIT FITTING - (TYPE AX FOR MOVEMENT OF ± 2") AT BRIDGE EXPANSION JOINTS



CONDUIT DEFLECTION FITTING A

CONDUIT FITTING - TYPE DX FOR DEFLECTION OF 30° AND ¾" MOVEMENT. PLACE AT CONDUIT PIPE EXIT FROM STRUCTURE




CONDUIT DEFLECTION FITTING B

CONDUIT FITTING - TYPE DX FOR DEFLECTION OF 30° AND ¾" MOVEMENT. CONDUIT PIPES PLACED THROUGH RETAIING WALL TRAFFIC BARRIER SHALL BE FITTED WITH DEFLECTION FITTINGS AT A MAXIMUM SPACING OF 120 FEET. THE DEFLECTION FITTINGS SHALL BE PLACED AT THE TRAFFIC BARRIER OPEN JOINT THAT COINCIDES WITH THE RETAINING WALL STEM EXPANSION JOINT NEAREST TO THE TRANSVERSE CONSTRUCTION JOINT IN THE WALL FOOTING.


Traffic Barrier - Single Slope Details 3 of 3

Figure 10-A-18





PLAN
PEDESTRIAN BARRIER

BARRIER CONTINUOUS BETWEEN ROADWAY EXPANSION JOINTS. CONSTRUCTION JOINTS WITH SHEAR KEYS ARE PERMISSIBLE AT DUMMY JOINT LOCATIONS. FORM JOINTS BETWEEN DUMMY JOINTS SHALL NOT BE PERMITTED.




OUTSIDE ELEVATION
END OF MODIFIED PEDESTRIAN BARRIER





TYPICAL SECTION
PEDESTRIAN BARRIER



OUTSIDE ELEVATION PEDESTRIAN BARRIER GUARDRAIL CONNECTION

(WHERE SHOWN ON LAYOUT)

* MIN. HEIGHT. PEDESTRIAN BARRIER HEIGHT MAY VARY IF REQUIRED TO PROVIDE A SMOOTH PROFILE.


** Include in Barlist Superstructure.

NW REGION:
TERMINATE EACH CONDUIT PIPE AT SEPARATE JUNCTION BOXES OFF END OF BRIDGE AS SHOWN ON LAYOUT.

ALL OTHER REGIONS:
STUB OUT & CAP 3'-4" FROM END OF BRIDGE BARRIER, EXCEPT TERMINATE IN JUNCTION BOX WHERE AND WHEN SHOWN ON LAYOUT.


Note to Designer: The non-applicable text should be removed from the actual bridge plans.

Pedestrian Barrier Details 1 of 3
Figure 10-A-19




END VIEW

THRIE BEAM SHOWN WITH "D" CONNECTION




END VIEW

W-BEAM SHOWN WITH "D" CONNECTION




VIEW A


ALL CHAMFERS ¾". SEE "LAYOUT" FOR APPLICABLE SURFACE FINISH.



SECTION B




DUMMY JOINT DETAIL



SLIPFORM ALTERNATE

SEE TYPICAL SECTION - PEDESTRIAN BARRIER FOR ADDITIONAL DETAILS

THE CONTRACTOR IS ADVISED THAT THE SLIPFORM CONSTRUCTION METHOD IS A PATENTED PROPRIETARY PROCESS FOR BARRIERS WITH A FRACTURED FIN FINISH.



FRACTURED FIN FINISH

JUNCTION BOX LOCATIONS STATED BELOW ARE APPROXIMATE. CENTER JUNCTION BOX INSTALLATION BETWEEN BARRIER DUMMY JOINTS

JUNCTION BOX LOCATIONS		
STATION	OFFSET	LABEL


TS = TRAFFIC SYSTEM
LT = LIGHTING SYSTEM
INSTALL ALL CONDUIT RUNS TO DRAIN TO A BRIDGE END OR PROVIDE DRAIN AT ALL LOW POINTS IN CONDUIT RUN ON BRIDGE.

▽ EPOXY COATED

PEDESTRIAN BARRIER BAR LIST


ALL REINFORCING SHALL BE AASHTO M 31, GR. 60.

MARK	SIZE	LENGTH	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
B1	5	(a)	
B2	4	(a)	STR.
B3	4	(a)	STR.
B4	6	(a)	STR.
B8	5	(a)	




FOR S3 ▽ & S4 BARS SEE BRIDGE BARLIST, (a) DETERMINE FROM PLANS

FOR W1 & W2 BARS SEE WINGWALL OR RETAINING WALL PLANS.



SECTION C BRIDGE

FOR DETAILS NOT SHOWN SEE "OUTSIDE ELEVATION" AND "TYPICAL SECTION ~ PEDESTRIAN BARRIER"




SECTION C WALL

DETAIL FOR RETAINING WALL OR WINGWALL REINFORCING NOT SHOWN SEE STD. PLAN D-1a & D-1b OR WINGWALL PLAN.
FOR DETAILS NOT SHOWN SEE "OUTSIDE ELEVATION" AND "TYPICAL SECTION ~ PEDESTRIAN BARRIER"

* BLOCKOUT WIDTH MAY BE INCREASED TO 6" TO ALLOW CONDUITS OF A LARGER DIAMETER THAN 2" TO EXIT BARRIER OR WALL WITHOUT REBAR STEEL CONFLICT


Pedestrian Barrier Details 2 of 3

Figure 10-A-20



PLAN - TRAFFIC BARRIER

TYP. @ END OF MODIFIED TRAFFIC BARIER END SECTION WHERE THRIE BEAM END SECTION "DESIGN F" STD. PLAN C-7a OR GUARDRAIL END SECTION "DESIGN D OR F" STD PLAN C-5 IS USED




ELEVATION - CONDUITS & J-BOX IN TRAFFIC BARRIER

LABEL JUNCTION BOX COVER IN ACCORDANCE WITH STANDARD PLAN J-11a AND SPECIAL PROVISIONS. ADJACENT JUNCTION BOXES ARE SHOWN CENTERED BETWEEN ADJACENT DUMMY JOINTS. IF THE DISTANCE BETWEEN ADJACENT DUMMY JOINTS IS 16'-0" OR GREATER, PLACE ADJACENT JUNCTION BOXES SYMETRICALLY ON EITHER SIDE OF THE CENTER OF ONE DUMMY PANEL WHILE MAINTAINING 8'-0" MINIMUM BETWEEN CENTER LINES OF THE JUNCTION BOXES.


NOTE TO DESIGNERS

MODIFY THE FOLLOWING TO MATCH PROJECT REQUIREMENTS:
1. BARRIER END SECTION.
2. REMOVE GUARDRAIL IF NOT CONNECTED TO BRIDGE ITEM.
3. CONDUIT ALIGNMENT




CONDUIT EXPANSION FITTING

CONDUIT FITTING - (TYPE AX FOR MOVEMENT OF ± 2") AT BRIDGE EXPANSION JOINTS




CONDUIT DEFLECTION FITTING A

CONDUIT FITTING - TYPE DX FOR DEFLECTION OF 30° AND ¾" MOVEMENT. PLACE AT CONDUIT PIPE EXIT FROM STRUCTURE



CONDUIT DEFLECTION FITTING B


CONDUIT FITTING - TYPE DX FOR DEFLECTION OF 30° AND ¾" MOVEMENT. CONDUIT PIPES PLACED THROUGH RETAINING WALL TRAFFIC BARRIER SHALL BE FITTED WITH DEFLECTION FITTINGS AT A MAXIMUM SPACING OF 120 FEET. THE DEFLECTION FITTINGS SHALL BE PLACED AT THE TRAFFIC BARRIER OPEN JOINT THAT COINCIDES WITH THE RETAINING WALL STEM EXPANSION JOINT NEAREST TO THE TRANSVERSE CONSTRUCTION JOINT IN THE WALL FOOTING.



SECTION A


Pedestrian Barrier Details 3 of 3

Figure 10-A-21




Traffic Barrier - Shape F 42" Details 1 of 3


Figure 10-A-22




END VIEW
W-BEAM SHOWN WITH "D" CONNECTION




END VIEW
THRIE BEAM SHOWN WITH "D" CONNECTION



VIEW A/1
ALL CHAMFERS ¾"




SECTION B




SLIPFORM ALTERNATE
SEE "TYPICAL SECTION - TRAFFIC BARRIER" FOR ADDITIONAL DETAILS

THE CONTRACTOR IS ADVISED THAT THE SLIPFORM CONSTRUCTION METHOD IS A PATENTED PROPRIETARY PROCESS FOR BARRIERS WITH A FRACTURED FIN FINISH.



FRACTURED FIN FINISH



DUMMY JOINT DETAIL


JUNCTION BOX LOCATIONS	
STATION	OFFSET

TRAFFIC BARRIER BAR LIST
ALL REINFORCING SHALL BE AASHTO M31, GR. 60.


MARK	SIZE	LENGTH	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
R1	5	3'-9"	
R1A	5	(A)	
R2	5	4'-2"	
R3	4	(A)	STR.
R4	6	(A)	STR.
R6	4	3'-10⅛"	STR.
R9	5	8'-0"	

(A) DETERMINE FROM PLANS

DIMENSIONS TO POINTS OF INTERSECTION




FOR W1 & W2 BARS SEE WINGWALL OR RETAINING WALL PLANS.
FOR S1 & S2 BARS SEE BARLIST



SECTION B/? BRIDGE

FOR DETAILS NOT SHOWN SEE "OUTSIDE ELEVATION" AND "TYPICAL SECTION - TRAFFIC BARRIER"

* BLOCKOUT WIDTH MAY BE INCREASED TO 6" TO ALLOW CONDUITS OF A LARGER DIAMETER THAN 2" TO EXIT BARRIER OR WALL WITHOUT REBAR STEEL CONFLICT




SECTION B/? WALL

DETAIL FOR RETAINING WALL OR WINGWALL. FOR REINFORCING NOT SHOWN SEE STD. PLAN D-1a & D-1b OR WINGWALL PLAN. FOR DETAILS NOT SHOWN SEE SECTION B/? BRIDGE


Traffic Barrier - Shape F 42" Details 2 of 3

Figure 10-A-23



PLAN - TRAFFIC BARRIER

TYP. @ END OF MODIFIED TRAFFIC BARIER END SECTION WHERE THRIE BEAM END SECTION "DESIGN F" STD. PLAN C-7a OR GUARDRAIL END SECTION "DESIGN D OR F" STD PLAN C-5 IS USED




ELEVATION - CONDUITS & J-BOX IN TRAFFIC BARRIER

LABEL JUNCTION BOX COVER IN ACCORDANCE WITH STANDARD PLAN J-11a AND SPECIAL PROVISIONS. ADJACENT JUNCTION BOXES ARE SHOWN CENTERED BETWEEN ADJACENT DUMMY JOINTS. IF THE DISTANCE BETWEEN ADJACENT DUMMY JOINTS IS 16'-0" OR GREATER, PLACE ADJACENT JUNCTION BOXES SYMMETRICALLY ON EITHER SIDE OF THE CENTER OF ONE DUMMY PANEL WHILE MAINTAINING 8'-0" MINIMUM BETWEEN CENTER LINES OF THE JUNCTION BOXES.


NOTE TO DESIGNERS

MODIFY THE FOLLOWING TO MATCH PROJECT REQUIREMENTS:
1. BARRIER END SECTION.
2. REMOVE GUARDRAIL IF NOT CONNECTED TO BRIDGE ITEM.
3. CONDUIT ALIGNMENT




CONDUIT EXPANSION FITTING

CONDUIT FITTING - (TYPE AX FOR MOVEMENT OF ± 2") AT BRIDGE EXPANSION JOINTS



CONDUIT DEFLECTION FITTING A

CONDUIT FITTING - TYPE DX FOR DEFLECTION OF 30° AND ¾" MOVEMENT. PLACE AT CONDUIT PIPE EXIT FROM STRUCTURE




CONDUIT DEFLECTION FITTING B

CONDUIT FITTING - TYPE DX FOR DEFLECTION OF 30° AND ¾" MOVEMENT. CONDUIT PIPES PLACED THROUGH RETAINING WALL TRAFFIC BARRIER SHALL BE FITTED WITH DEFLECTION FITTINGS AT A MAXIMUM SPACING OF 120 FEET. THE DEFLECTION FITTINGS SHALL BE PLACED AT THE TRAFFIC BARRIER OPEN JOINT THAT COINCIDES WITH THE RETAINING WALL STEM EXPANSION JOINT NEAREST TO THE TRANSVERSE CONSTRUCTION JOINT IN THE WALL FOOTING.


Traffic Barrier - Shape F 42" Details 3 of 3

Figure 10-A-24




Traffic Barrier - Single Slope 42” Details 1 of 3


Figure 10-A-25




END VIEW
WITH "D" CONNECTION




END VIEW
WITH "D" CONNECTION



VIEW A/1
ALL CHAMFERS ¾"




SECTION C—C




SLIPFORM ALTERNATE

SEE "TYPICAL SECTION - TRAFFIC BARRIER" FOR ADDITIONAL DETAILS.

THE CONTRACTOR IS ADVISED THAT THE SLIPFORM CONSTRUCTION METHOD IS A PATENTED PROPRIETARY PROCESS FOR BARRIERS WITH A FRACTURED FIN FINISH.




FRACTURED FIN FINISH



DUMMY JOINT DETAIL


JUNCTION BOX LOCATIONS	
STATION	STATION



SECTION B/1 BRIDGE

DETAIL FOR BRIDGE
FOR DETAILS NOT SHOWN SEE "OUTSIDE ELEVATION" AND "TYPICAL SECTION - TRAFFIC BARRIER"

* BLOCKOUT WIDTH MAY BE INCREASED TO 6" TO ALLOW CONDUITS OF A LARGER DIAMETER THAN 2" TO EXIT BARRIER OR WALL WITHOUT REBAR STEEL CONFLICT



SECTION B/1 WALL

DETAIL FOR RETAINING WALL OR WINGWALL. FOR REINFORCING NOT SHOWN SEE STD. PLAN D-1a & D-1b OR WINGWALL PLAN. FOR DETAILS NOT SHOWN SEE SECTION B/1 BRIDGE


TRAFFIC BARRIER BAR LIST

ALL REINFORCING SHALL BE AASHTO M31, GR. 60.

▽ DENOTES EPOXY COATED

MARK	SIZE	LENGTH	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)	
R2	5	5'-1"		
R2a	5	(A)		
R3	4	(A)		STR.
R4	6	(A)		STR.
R6	4	3'-10"		STR.
R9	5	9'-1"		

(A) DETERMINE FROM PLANS




FOR R9 & W2 BARS SEE WINGWALL OR RETAINING WALL PLANS. FOR S1▽ & S2 BARS SEE BARLIST.

± DIMENSIONS TO POINTS OF INTERSECTION.


Traffic Barrier - Single Slope 42" Details 2 of 3

Figure 10-A-26



PLAN - TRAFFIC BARRIER

TYP. @ END OF MODIFIED TRAFFIC BARIER END SECTION WHERE THRIE BEAM END SECTION "DESIGN F" STD. PLAN C-7a OR GUARDRAIL END SECTION "DESIGN D OR F" STD PLAN C-5 IS USED




ELEVATION - CONDUITS & J-BOX IN TRAFFIC BARRIER

LABEL JUNCTION BOX COVER IN ACCORDANCE WITH STANDARD PLAN J-11a AND SPECIAL PROVISIONS. ADJACENT JUNCTION BOXES ARE SHOWN CENTERED BETWEEN ADJACENT DUMMY JOINTS. IF THE DISTANCE BETWEEN ADJACENT DUMMY JOINTS IS 16'-0" OR GREATER, PLACE ADJACENT JUNCTION BOXES SYMMETRICALLY ON EITHER SIDE OF THE CENTER OF ONE DUMMY PANEL WHILE MAINTAINING 8'-0" MINIMUM BETWEEN CENTER LINES OF THE JUNCTION BOXES.


NOTE TO DESIGNERS

MODIFY THE FOLLOWING TO MATCH PROJECT REQUIREMENTS:
1. BARRIER END SECTION.
2. REMOVE GUARDRAIL IF NOT CONNECTED TO BRIDGE ITEM.
3. CONDUIT ALIGNMENT




CONDUIT EXPANSION FITTING

CONDUIT FITTING - (TYPE AX FOR MOVEMENT OF ± 2") AT BRIDGE EXPANSION JOINTS



CONDUIT DEFLECTION FITTING A

CONDUIT FITTING - TYPE DX FOR DEFLECTION OF 30° AND ¾" MOVEMENT. PLACE AT CONDUIT PIPE EXIT FROM STRUCTURE




CONDUIT DEFLECTION FITTING B

CONDUIT FITTING - TYPE DX FOR DEFLECTION OF 30° AND ¾" MOVEMENT. CONDUIT PIPES PLACED THROUGH RETAINING WALL TRAFFIC BARRIER SHALL BE FITTED WITH DEFLECTION FITTINGS AT A MAXIMUM SPACING OF 120 FEET. THE DEFLECTION FITTINGS SHALL BE PLACED AT THE TRAFFIC BARRIER OPEN JOINT THAT COINCIDES WITH THE RETAINING WALL STEM EXPANSION JOINT NEAREST TO THE TRANSVERSE CONSTRUCTION JOINT IN THE WALL FOOTING.


SECTION A

Traffic Barrier - Single Slope 42" Details 3 of 3

Figure 10-A-27




ELEVATION




SECTION A


NOTE:
- ALL CONDUIT SHALL BE RIGID GALVANIZED STEEL (RGS). INSTALL ALL CONDUIT RUNS TO DRAIN TO A BRIDGE END OR PROVIDE DRAIN AT ALL LOW POINTS WITHIN CONDUIT RUN. SEE "TRAFFIC BARRIER SHEETS" FOR BARRIER DIMENSIONS.
- ALL HIGH STRENGTH (H.S.) BOLTS SHALL BE AASHTO M164. HARDENED WASHERS SHALL CONFORM TO ASTM F 436.



ANCHOR PLATE
GALVANIZE PER AASHTO M 111



ELEVATION PROFILE
LUMINAIRE SUPPORT
(SHOWN FOR BRIDGE, SIMILAR FOR WALLS)



PLAN

LUMINAIRE POLE LOCATIONS ON BRIDGE & WALLS	
STATION	OFFSET
XXX 0+000.000	0.000 RT.
XXX 0+000.000	0.000 RT.


ANCHORAGE BARLIST

ALL REINF. SHALL BE AASHTO M31, GRADE 60.


MARK #	SIZE	LENGTH	BEND TYPE
A1	6	1'-9"	STRAIGHT
A2	6	5'-0"	STRAIGHT

Traffic Barrier - Shape F Luminaire Anchor Details

Figure 10-A-28




ELEVATION




SECTION A


NOTE:
- ALL CONDUIT SHALL BE RIGID GALVANIZED STEEL (RGS). INSTALL ALL CONDUIT RUNS TO DRAIN TO A BRIDGE END OR PROVIDE DRAIN AT ALL LOW POINTS WITHIN CONDUIT RUN. SEE "TRAFFIC BARRIER SHEETS" FOR BARRIER DIMENSIONS.
- ALL HIGH STRENGTH (H.S.) BOLTS SHALL BE AASHTO M164. HARDENED WASHERS SHALL CONFORM TO ASTM F 436.



ANCHOR PLATE
GALVANIZE PER AASHTO M 111



ELEVATION PROFILE
LUMINAIRE SUPPORT
(SHOWN FOR BRIDGE, SIMILAR FOR WALLS)




PLAN

LUMINAIRE POLE LOCATIONS ON BRIDGE & WALLS	
STATION	OFFSET
XXX 0+000.000	0.000 RT.
XXX 0+000.000	0.000 RT.

ANCHORAGE BARLIST ALL REINF. SHALL BE AASHTO M31, GRADE 60.			
MARK #	SIZE	LENGTH	BEND TYPE
A1	6	1'-9"	STRAIGHT
A2	6	5'-0"	STRAIGHT


Traffic Barrier - Single Slope Luminaire Anchor Details

Figure 10-A-29



Thrie Beam Retrofit Concrete Baluster


Figure 10-A-30



TYPICAL SECTION
AT STEEL BLOCKOUT


(??? ASSEMBLIES REQUIRED)

* SEE GENERAL NOTE NO. 5 ON BRIDGE SHEET NO. ?.




BACKUP PLATE

BACKUP PLATE REQUIRED AT POST WHERE NO THRIE BEAM GUARDRAIL SPLICE OCCURS.



SECTION (A)


Thrie Beam Retrofit Concrete Railbase
Figure 10-A-31




TYPICAL STEEL POST ANCHORAGE


?? POSTS REQUIRED

* SEE GENERAL NOTE NO. 5 ON BRIDGE SHEET NO. ?.





BASE PLATE DETAIL




BACKUP PLATE

BACKUP PLATE REQUIRED AT POST WHERE NO THRIE BEAM GUARDRAIL SPLICE OCCURS.


Thrie Beam Retrofit Concrete Curb

Figure 10-A-32




GUARDRAIL POST ASSEMBLY
(??? ASSEMBLIES)


** THICKNESS OF SURFACING MATERIAL SHALL BE SUCH THAT THE TOP OF THE VERTICAL WEB OF THE MOUNTING BRACKET SHALL BE ½" BELOW WEARING COURSE SURFACE




OUTSIDE ELEVATION AT TYPICAL GUARDRAIL POST




DETAIL B



WATER BARRIER PLAN




WATER BARRIER SPLICE DETAIL



WATER BARRIER DETAIL


WP Thrie Beam Retrofit SL1 - Details 1 Of 2

Figure 10-A-33




WP Thrie Beam Retrofit SL1 - Details 2 Of 2

Figure 10-A-34




PLAN - TRAFFIC BARRIER


BARRIER CONTINUOUS BETWEEN ROADWAY EXPANSION JOINTS.
CONSTRUCTION JOINTS WITH SHEAR KEYS ARE PERMISSIBLE AT DUMMY JOINT LOCATIONS.
FORM JOINTS BETWEEN DUMMY JOINTS SHALL NOT BE PERMITTED.




OUTSIDE ELEVATION END OF MODIFIED TRAFFIC BARRIER



TYPICAL SECTION - TRAFFIC BARRIER





OUTSIDE ELEVATION TRAFFIC BARRIER GUARDRAIL CONNECTION

(WHERE SHOWN ON LAYOUT)

* TOE HEIGHT MAY VARY, 2" MIN. TO 6" MAX.

** HEIGHT MAY VARY IF REQUIRED TO PROVIDE A PROFILE PLEASING TO THE EYE

*** FOR TRANSVERSE ROADWAY SLOPES GREATER THAN 8%, CHANGE THE NOTE TO THE FOLLOWING:
FOR THE LOW SIDE OF THE BRIDGE OR MEDIAN BARRIER - "PERPENDICULAR TO 8% TRANSVERSE ROADWAY SLOPE"
FOR THE HIGH SIDE OF THE BRIDGE BARRIER - "PERPENDICULAR TO TRANSVERSE ROADWAY SLOPE"

NOTE TO DESIGNERS


If transverse roadway slope is greater than 8%, S1 & S2 bar bends need to be modified to account for the difference between the actual slope & 8% on the low side only of the bridge or median barrier. The barrier geometry needs to be checked also.

NW REGION:
TERMINATE EACH CONDUIT PIPE AT SEPARATE TYPE 1 JUNCTION BOXES OFF END OF BRIDGE AS SHOWN ON LAYOUT.


ALL OTHER REGIONS:
STUB OUT & CAP 3'-4" FROM END OF BRIDGE BARRIER, EXCEPT TERMINATE IN JUNCTION BOX WHERE AND WHEN SHOWN ON LAYOUT.

Note to Designer: The non-applicable text should be removed from the actual bridge plans.


Traffic Barrier - Shape F Rehabilitation Rehabilitation - Details 1 of 3
Figure 10-A-35




END VIEW
WBEAM SHOWN WITH "D" CONNECTION




END VIEW
THRIE BEAM SHOWN WITH "D" CONNECTION



VIEW A/1
ALL CHAMFERS ¾"




SECTION B




SLIPFORM ALTERNATE

SEE "TYPICAL SECTION - TRAFFIC BARRIER" FOR ADDITIONAL DETAILS

THE CONTRACTOR IS ADVISED THAT THE SLIPFORM CONSTRUCTION METHOD IS A PATENTED PROPRIETARY PROCESS FOR BARRIERS WITH A FRACTURED FIN FINISH.



FRACTURED FIN FINISH



DUMMY JOINT DETAIL

JUNCTION BOX LOCATIONS	
STATION	OFFSET


▽ DENOTES EPOXY COATED

± DIMENSIONS TO POINTS OF INTERSECTION

TRAFFIC BARRIER BAR LIST

ALL REINFORCING SHALL BE AASHTO M31, GR. 60.


MARK	SIZE	LENGTH	BENDING DIAGRAM (ALL DIMENSIONS ARE OUT TO OUT)
R1	5	3'- 7"	
R1A	5	(A)	
R2	4	2'- 11"	
R3	4	(A)	STR.
R4	6	(A)	STR.
R6	4	3'- 0"	STR.
R9	4	5'- 11"	
S1	6	2'- 2 ½"	
S2	4	1'- 2"	STR.



(A) DETERMINE FROM PLANS

FOR W1 ▽ & W2 BARS SEE WINGWALL OR RETAINING WALL PLANS.


FOR S1 ▽ & S2 BARS SEE BARLIST



SECTION B/? BRIDGE

FOR DETAILS NOT SHOWN SEE "OUTSIDE ELEVATION" AND "TYPICAL SECTION - TRAFFIC BARRIER"

* BLOCKOUT WIDTH MAY BE INCREASED TO 6" TO ALLOW CONDUITS OF A LARGER DIAMETER THAN 2" TO EXIT BARRIER OR WALL WITHOUT REBAR STEEL CONFLICT




SECTION B/? WALL

DETAIL FOR RETAINING WALL OR WINGWALL. FOR REINFORCING NOT SHOWN SEE STD. PLAN D-1a & D-1b OR WINGWALL PLAN. FOR DETAILS NOT SHOWN SEE SECTION B/? BRIDGE


Traffic Barrier - Shape F Rehabilitation - Details 2 of 3

Figure 10-A-36



PLAN - TRAFFIC BARRIER

TYP. @ END OF MODIFIED TRAFFIC BARIER END SECTION
WHERE THRIE BEAM END SECTION "DESIGN F" STD. PLAN C-7a
OR GUARDRAIL END SECTION "DESIGN D OR F" STD PLAN C-5 IS USED




ELEVATION - CONDUITS & J-BOX IN TRAFFIC BARRIER

LABEL JUNCTION BOX COVER IN ACCORDANCE WITH STANDARD PLAN J-11a AND SPECIAL PROVISIONS.
ADJACENT JUNCTION BOXES ARE SHOWN CENTERED BETWEEN ADJACENT DUMMY JOINTS. IF THE DISTANCE BETWEEN ADJACENT DUMMY JOINTS IS 16'-0" OR GREATER, PLACE ADJACENT JUNCTION BOXES SYMMETRICALLY ON EITHER SIDE OF THE CENTER OF ONE DUMMY PANEL WHILE MAINTAINING 8'-0" MINIMUM BETWEEN CENTER LINES OF THE JUNCTION BOXES.


NOTE TO DESIGNERS

MODIFY THE FOLLOWING TO MATCH PROJECT REQUIREMENTS:
1. BARRIER END SECTION.
2. REMOVE GUARDRAIL IF NOT CONNECTED TO BRIDGE ITEM.
3. CONDUIT ALIGNMENT




CONDUIT EXPANSION FITTING

CONDUIT FITTING - (TYPE AX FOR MOVEMENT OF ± 2") AT BRIDGE EXPANSION JOINTS




CONDUIT DEFLECTION FITTING A

CONDUIT FITTING - TYPE DX FOR DEFLECTION OF 30° AND ¾" MOVEMENT. PLACE AT CONDUIT PIPE EXIT FROM STRUCTURE




CONDUIT DEFLECTION FITTING B

CONDUIT FITTING - TYPE DX FOR DEFLECTION OF 30° AND ¾" MOVEMENT. CONDUIT PIPES PLACED THROUGH RETAINING WALL TRAFFIC BARRIER SHALL BE FITTED WITH DEFLECTION FITTINGS AT A MAXIMUM SPACING OF 120 FEET. THE DEFLECTION FITTINGS SHALL BE PLACED AT THE TRAFFIC BARRIER OPEN JOINT THAT COINCIDES WITH THE RETAINING WALL STEM EXPANSION JOINT NEAREST TO THE TRANSVERSE CONSTRUCTION JOINT IN THE WALL FOOTING.




SECTION A


Traffic Barrier - Shape F Rehabilitation - Details 3 of 3
Figure 10-A-37



ELEVATION

BALUSTER AND THRIE-BEAM GUARDRAIL ATTACHMENT DETAILS NOT SHOWN.





GENERAL DETAIL


NOTES

1. PIPE RAILING, PIPE RAILING SPLICES, COVER PLATES AND BOTTOM EXTRUDED CHANNELS SHALL BE BENT TO THE HORIZONTAL CURVE WHERE THE RADIUS OF CURVATURE IS LESS THAN 200 FEET.
2. SHOP DRAWINGS OF RAILING SHALL BE SUBMITTED FOR APPROVAL SHOWING COMPLETE DIMENSIONS AND DETAILS OF FABRICATION AND INCLUDING AN ERECTION DIAGRAM. MATERIAL BEING USED SHALL BE SPECIFIED IN THE SHOP DRAWINGS.
3. PIPE RAILING, PIPE RAILING SPLICES, COVER PLATES AND BOTTOM EXTRUDED CHANNELS MAY BE HEATED TO NOT MORE THAN 400°F FOR A PERIOD NOT TO EXCEED 30 MINUTES TO FACILITATE FORMING OR BENDING HORIZONTAL CURVATURE.
4. CUTTING SHALL BE DONE BY SAWING OR MILLING AND ALL CUTS SHALL BE TRUE AND SMOOTH. FLAME CUTTING WILL NOT BE PERMITTED.
5. WELDING OF ALUMINUM SHALL CONFORM TO STD. SPEC. SECTION 9-28.14(3).
6. AFTER FABRICATION, POSTS SHALL BE HEAT TREATED IN ACCORDANCE WITH SECTION 6.5 OF THE AASHTO STANDARD SPECIFICATIONS FOR STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS, LUMINARIES, AND TRAFFIC SIGNALS DATED 2001 AND INTERIMS THROUGH 2002.
7. ALL ALUMINUM PARTS SHALL BE GIVEN A * (CLEAR OR BRONZE) ANODIC COATING OF AT LEAST 0.0006 INCHES THICK AND SEALED TO MEET THE REQUIREMENTS OF ASTM B 580 WITH A UNIFORM FINISH.
8. PIPE RAILING, PIPE BALUSTERS, PIPE RAILING SPLICES, SHALL BE ADEQUATELY WRAPPED TO INSURE SURFACE PROTECTION DURING HANDLING AND TRANSPORTATION TO THE JOB SITE.

* NOTE TO DESIGNER:
Designer to choose color for their project in consultation with the Bridge Architect.


Bridge Railing Type Pedestrain Details 1 of 2

Figure 10-A-38




MAT'L	PART	MATERIAL SPECIFICATION
ALUMINUM	PIPES	ASTM B221- 6005-T5 ASTM B 241 OR B 429 6061-T6
	EXTRUDED CHANNELS, COVER PLATES & BAR	ASTM B221- 6005-T5
STEEL	ANCHOR BOLTS, NUTS & WASHERS	AASHTO M164 (GALVANIZE IN ACCORDANCE WITH AASHTO SPECIFICATION M232)
	STRIP	ASTM A36
	DRIVE PINS	ASTM A-276 TYPE 302 STAINLESS STEEL


Bridge Railing Type Pedestrian Details 2 of 2
Figure 10-A-39



ELEVATION

BALUSTER AND GUARDRAIL SECTION ATTACHMENT DETAILS NOT SHOWN.





GENERAL DETAIL


NOTES

1. PIPE RAILING, PIPE RAILING SPLICES, COVER PLATES AND BOTTOM EXTRUDED CHANNELS SHALL BE BENT TO THE HORIZONTAL CURVE WHERE THE RADIUS OF CURVATURE IS LESS THAN 200 FEET.
2. SHOP DRAWINGS OF RAILING SHALL BE SUBMITTED FOR APPROVAL SHOWING COMPLETE DIMENSIONS AND DETAILS OF FABRICATION AND INCLUDING AN ERECTION DIAGRAM. MATERIAL BEING USED SHALL BE SPECIFIED IN THE SHOP DRAWINGS.
3. PIPE RAILING, PIPE RAILING SPLICES, COVER PLATES AND BOTTOM EXTRUDED CHANNELS MAY BE HEATED TO NOT MORE THAN 400°F FOR A PERIOD NOT TO EXCEED 30 MINUTES TO FACILITATE FORMING OR BENDING HORIZONTAL CURVATURE.
4. CUTTING SHALL BE DONE BY SAWING OR MILLING AND ALL CUTS SHALL BE TRUE AND SMOOTH. FLAME CUTTING WILL NOT BE PERMITTED.
5. WELDING OF ALUMINUM SHALL CONFORM TO STD. SPEC. SECTION 9-28.14(3).
6. AFTER FABRICATION, POSTS SHALL BE HEAT TREATED IN ACCORDANCE WITH SECTION 6.5 OF THE AASHTO STANDARD SPECIFICATIONS FOR STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS, LUMINARIES, AND TRAFFIC SIGNALS DATED 2001 AND INTERIMS THROUGH 2002.
7. ALL ALUMINUM PARTS SHALL BE GIVEN A (CLEAR OR BRONZE) ANODIC COATING OF AT LEAST 0.0006 INCHES THICK AND SEALED TO MEET THE REQUIREMENTS OF ASTM B 580 WITH A UNIFORM FINISH.
8. PIPE RAILING, PIPE BALUSTERS, PIPE RAILING SPLICES, SHALL BE ADEQUATELY WRAPPED TO INSURE SURFACE PROTECTION DURING HANDLING AND TRANSPORTATION TO THE JOB SITE.


* NOTE TO DESIGNER:
Designer to choose color for their project in consultation with the Bridge Architect.

Bridge Railing Type BP Details 1 of 2

Figure 10-A-40




END DETAIL




DETAIL D
DRAIN HOLES NOT SHOWN

MAT'L	PART	MATERIAL SPECIFICATION
ALUMINUM	PIPES (SEE NOTE 8)	ASTM B221- 6005-T5 ASTM B 241 OR B 429 6061-T6
ALUMINUM	EXTRUDED CHANNELS, COVER PLATES & BAR	ASTM B221- 6005-T5
STEEL	ANCHOR BOLTS, NUTS & WASHERS	AASHTO M164 (GALVANIZE IN ACCORDANCE WITH AASHTO SPECIFICATION M232)
STEEL	STRIP	ASTM A36
STEEL	DRIVE PINS	ASTM A-276 TYPE 302 STAINLESS STEEL




SECTION A 1




DETAIL B
OPTION #1

* LOCATE ON OPPOSITE SIDE OF TRAFFIC. DRIVE PINS SHALL BE DRIVEN FLUSH WITH THE OUTSIDE FACE OF THE RAILING.



DETAIL B
OPTION #2

* LOCATE ON OPPOSITE SIDE OF TRAFFIC. DRIVE PINS SHALL BE DRIVEN FLUSH WITH THE OUTSIDE FACE OF THE RAILING.



DETAIL C
ANCHOR BOLTS SHALL BE POSITIONED IN A JIG DURING WELDING.


Bridge Railing Type BP Details 2 of 2

Figure 10-A-41

MAT'L	PART	MATERIAL SPECIFICATION
STEEL	PIPES	ASTM A53 GRADE B SCHEDULE 40 (STD. PIPE). GALVANIZED IN ACCORDANCE WITH AASHTO M 111.
STEEL	WASHERS	ASTM A 193 GRADE B7 GALVANIZED IN ACCORDANCE WITH AASHTO M 232.
STEEL	PLATES/BAR CHANNELS	ASTM A36 GALVANIZED IN ACCORDANCE WITH AASHTO M 111
STEEL	DRIVE PINS	ASTM A 276 TYPE 302 STAINLESS STEEL
STEEL	ANCHOR BOLTS	ASTM F 593 TYPE 302 STAINLESS STEEL
	NUTS	TAMPER-PROOF TYPE OF EITHER CLEAR ANODIZED ALUMINUM OR ZINC ALLOY


NOTES

1. PIPE RAILING, PIPE RAILING SPLICES, AND CHANNELS SHALL BE BENT TO THE HORIZONTAL CURVE WHERE THE RADIUS OF CURVATURE IS LESS THAN 200 FEET.
2. SHOP DRAWINGS OF RAILING SHALL BE SUBMITTED FOR APPROVAL SHOWING COMPLETE DIMENSIONS AND DETAILS OF FABRICATION, GALVANIZING AND INCLUDING AN ERECTION DIAGRAM. MATERIAL BEING USED SHALL BE SPECIFIED IN THE SHOP DRAWINGS.
3. THE BRIDGE RAILING SHALL BE HOT DIP GALVANIZED AFTER FABRICATION PER AASHTO M 111. ALL COMPONENTS OF RAIL PANEL, POSTS, AND SPLICE SLEEVES SHALL HAVE ALL SURFACES HOT DIP GALVANIZED PRIOR TO ASSEMBLY.
4. CUTTING SHALL BE DONE BY SAWING OR MILLING AND ALL CUTS SHALL BE TRUE AND SMOOTH.
5. PIPE RAILING, PIPE BALLUSTERS, RAILING SPLICE AND CHANNELS SHALL BE ADEQUATELY WRAPPED TO ENSURE SURFACE PROTECTION DURING HANDLING AND TRANSPORTATION TO THE JOB SITE.
6. WELDING SHALL BE DONE IN ACCORDANCE WITH AWS D1.1.
7. PIPE RAILING AND SPLICES MAY BE HEATED TO FACILITATE FORMING OR BENDING.
8. THE CONTRACTOR SHALL REPAIR ALL GALVANIZED STEEL SURFACES DAMAGED BY FIELD OPERATIONS, BY PAINTING THE DAMAGED AREAS WITH TWO COATS OF PAINT CONFORMING TO FORMULA A-9-73 AS SPECIFIED IN SECTION 9-08.2 OF THE WASHINGTON STATE STANDARD SPECIFICATIONS FOR ROAD, BRIDGE AND MUNICIPAL CONSTRUCTION.



ELEVATION


BALUSTER ATTACHMENT DETAILS NOT SHOWN




SECTION A


Bridge Railing Type S-BP Details 1 of 2

Figure 10-A-42






DRIVE PIN DETAIL
SLOTTED TYPE SPRING PIN (ANSI B18.8.2)




WASHER DETAIL
HOT DIP GALVANIZE AFTER FABRICATION



SECTION E

** LOCATE ON OPPOSITE SIDE OF TRAFFIC. DRIVE PINS SHALL BE DRIVEN FLUSH WITH THE OUTSIDE FACE OF THE RAILING


NOTE:
"E" DIMENSION EQUALS MAX. OPENING OR CLOSING OF CONC. RAIL BASE AT EXPANSION JOINTS



PART ELEVATION B

Bridge Railing Type S-BP Details 2 of 2

Figure 10-A-43



ELEVATION

BALUSTERS NORMAL TO GRADE.
TOP & BOTTOM RAILS PARALLEL TO GRADE.

MAT'L	PART	MATERIAL SPECIFICATION
ALUMINUM	PIPES	ASTM B221- 6005-T5 SCHEDULE 40 (STD. PIPE) ASTM B241 OR B429 6061-T6
	BAR	ASTM B221-6005-T5
STEEL	DRIVE PINS	ASTM A-276 TYPE 302 STAINLESS STEEL


NOTES


1. PIPE RAILING, AND PIPE RAILING SPLICES, SHALL BE BENT TO THE HORIZONTAL CURVE WHERE THE RADIUS OF CURVATURE IS LESS THAN 200 FEET.
2. SHOP DRAWINGS OF RAILING SHALL BE SUBMITTED FOR APPROVAL SHOWING COMPLETE DIMENSIONS AND DETAILS OF FABRICATION AND INCLUDING AN ERECTION DIAGRAM. MATERIAL BEING USED SHALL BE SPECIFIED IN THE SHOP DRAWINGS.
3. PIPE RAILING, AND PIPE RAILING SPLICES, MAY BE HEATED TO NOT MORE THAN 400°F FOR A PERIOD NOT TO EXCEED 30 MINUTES TO FACILITATE FORMING OR BENDING HORIZONTAL CURVATURE.
4. CUTTING SHALL BE DONE BY SAWING OR MILLING AND ALL CUTS SHALL BE TRUE AND SMOOTH. FLAME CUTTING WILL NOT BE PERMITTED.
5. WELDING OF ALUMINUM SHALL CONFORM TO STD. SPEC. SECTION 9-28.14(3).
6. AFTER FABRICATION, POSTS SHALL BE HEAT TREATED IN ACCORDANCE WITH SECTION 6.5 OF THE AASHTO STANDARD SPECIFICATIONS FOR STRUCTURAL SUPPORTS FOR HIGHWAY SIGNS, LUMINARIES, AND TRAFFIC SIGNALS DATED 2001 AND INTERIMS THROUGH 2002.
7. ALL ALUMINUM PARTS SHALL BE GIVEN A * (CLEAR OR BRONZE) ANODIC COATING OF AT LEAST 0.0006 INCHES THICK AND SEALED TO MEET THE REQUIREMENTS OF ASTM B 580 WITH A UNIFORM FINISH.
8. PIPE RAILING, PIPE BALUSTERS, PIPE RAILING SPLICES, SHALL BE ADEQUATELY WRAPPED TO INSURE SURFACE PROTECTION DURING HANDLING AND TRANSPORTATION TO THE JOB SITE.

* NOTE TO DESIGNER:
Designer to choose color for their project in consultation with the Bridge Architect.


Pedestrian Railing Details 1 of 2

Figure 10-A-44







* LOCATE ON OPPOSITE SIDE OF TRAFFIC. DRIVE PINS SHALL BE DRIVEN FLUSH WITH THE OUTSIDE FACE OF THE RAILING.




* LOCATE ON OPPOSITE SIDE OF TRAFFIC. DRIVE PINS SHALL BE DRIVEN FLUSH WITH THE OUTSIDE FACE OF THE RAILING.







Pedestrian Railing Details 2 of 2

Figure 10-A-45





ELEVATION VIEW AND POST SPACING






BRACE BAND







POST BASE PLATE DETAIL



RAILING END VIEW



TYPICAL SECTION




GENERAL NOTES


1. ALL ELEMENTS OF FENCE SHALL BE GALVANIZED AFTER FABRICATION AND COATED WITH UV INSENSITVE PLASTIC AS SPECIFIED IN THE SPECIAL PROVISIONS. STEEL PIPES FOR POSTS AND LONGITUDINAL MEMBERS SHALL CONFORM TO ASTM A53 GRADE B GALV.
2. CHAIN LINK FENCE SHALL CONFORM TO CLASS 1 REQUIREMENTS IN SECTION 9-16.1
3. FITTINGS, FABRIC BANDS, STRECHER BARS AND TIE WIRE SHALL CONFORM TO SECTION 9-16.1
4. FABRIC TIES SHALL BE INSTALLED TO ALL FRAMES IN ACCORDANCE WITH GOOD TRADE PRACTICES AT 1'-2" CENTERS MAXIMUM SPACING.
5. BOLTS, NUTS AND WASHERS SHALL CONFORM TO SECTION 9-06.5(1) AND GALVANIZED IN ACCORDANCE WITH AASHTO M 232.

Bridge Railing Type Chain Link Snow Fence

Figure 10-A-46




PLAN



LONGITUDINAL SECTION

BAR LIST FOR STANDARD 10' X 25' APPROACH SLAB QUANTITY MODULE				
LOCATION	MARK #	SIZE	NO.	LENGTH
LONGITUDINAL BOTTOM	AP1	8	24	25'-7"
LONGITUDINAL TOP	AP2	▽6	24	24'-8"
TRANSVERSE BOTTOM	AP3	5	30	9'-8"
TRANSVERSE TOP	AP4	▽5	17	9'-8"
TRANSVERSE END BAR	AP5	▽5	2	9'-8"

BENDING DETAIL FOR QUANTITIES



ALL REINFORCING BARS SHOWN ON THIS SHEET SHALL BE AASHTO M-31 UNLESS NOTED OTHERWISE.


▽ = EPOXY COATED REINFORCING STEEL

APPROXIMATE QUANTITIES (PER SY) FOR SLAB (BASED ON QUANTITY MODULE)	
SLAB EPOXY COATED REINFORCING BARS (TOP MAT)	38.52 LBS/SY
SLAB REINFORCING BARS (BOTTOM MAT)	72.38 LBS/SY
CONCRETE (CU. YDS.)	0.361 CY/SY
APPROACH ANCHORS AND PCC ROADWAY DOWELS	AS REQUIRED
10 - AP6 ▽#5 (IF REQUIRED)	105 LBS.

NOTE:
Designer to use appropriate details from this sheet and consult with Approach Slab Specialist for skews greater than 30 degrees .


NOTES:

1. ALL EDGES OF APPROACH SLAB SHALL HAVE ½" RADIUS.
2. LONGITUDINAL JOINTS SHALL BE PLACED ON LANE LINES AND SHALL BE CONSTRUCTED AND SEALED IN ACCORDANCE WITH STD. SPEC. SECTION 5-05.3(8). JOINTS MAY BE EITHER A SAW CUT CRACK CONTROL JOINT OR A CONSTRUCTION JOINT. SAWCUT JOINTS SHALL TERMINATE 1'-0" BEFORE REACHING EDGE OF SLAB AND MUST BE SAW CUT AS SOON AS POSSIBLE AFTER PLACEMENT OF CONCRETE.
   (A) APPROACH SLABS LESS THAN 40' WIDE - NO JOINT IS REQUIRED.
   (B) APPROACH SLABS WIDER THAN 40' - ONE OR MORE JOINTS ARE REQUIRED TO DIVIDE THE SLAB INTO APPROXIMATELY 24' WIDE SECTIONS.




TYPICAL PCCP ROADWAY DOWEL BAR DETAIL

INSERT DOWELS PARALLEL TO CENTER LINE ALONG TRANSVERSE CONSTRUCTION JOINT.




TYPICAL LONGITUDINAL CRACK CONTROL JOINT DETAIL




TYPICAL LONGITUDINAL CONSTRUCTION JOINT

EDGE FIRST POUR ONLY WITH ⅛" RADIUS.


Bridge Approach Slab Details 1 of 2
Figure 10-A-47



SEMI-INTEGRAL TYPE ABUTMENT




L TYPE ABUTMENT




APPROACH ANCHOR - METHOD A

SEMI-INTEGRAL TYPE ONLY




APPROACH ANCHOR - METHOD B

SEMI-INTEGRAL TYPE ONLY




L TYPE ABUTMENT ANCHOR DETAIL

NOTE:
PAINT METAL COMPONENTS OF APPROACH ANCHOR WITH ONE COAT OF INORGANIC ZINC OR FORMULA A-11-99 PAINT IN ACCORDANCE WITH STD. SPEC. 9-08.2.




ANCHOR HEAD DETAIL



COMPRESSION SEAL DETAIL


Bridge Approach Slab Details 2 of 2

Figure 10-A-48



PLAN


* THE DIMENSIONS SHOWN IN THE PLANS ARE BASED ON ORIGINAL CONSTRUCTION RECORDS TOGETHER WITH SURVEY DATA. THESE DIMENSION SHALL BE MEASURED IN THE FIELD BY THE CONTRACTOR PRIOR TO FABRICATION OF ANY COMPONENTS.




SECTION B

(EXISTING CONDITION)
TYPICAL FOR APPROACH SLAB

* THE DIMENSIONS SHOWN IN THE PLANS ARE BASED ON ORIGINAL CONSTRUCTION RECORDS TOGETHER WITH SURVEY DATA. THESE DIMENSION SHALL BE MEASURED IN THE FIELD BY THE CONTRACTOR PRIOR TO FABRICATION OF ANY COMPONENTS.



SECTION A




SECTION B

(RETROFIT CONDITION)

BAR LIST

ALL REINFORCING SHALL BE AASHTO M31, GR. 60.


MARK	SIZE	LENGTH	BENDING DIAGRAM(ALL DIMENSIONS ARE OUT TO OUT TO POINTS OF INTERSECTION)
1	6	2'-4"	
2	4	2'-4'	
3	4	(A)	STR.
6	4	1'-3"	




(A) DETERMINE FROM PLANS
BEND BARS AS REQ'D TO CONFORM TO THE CONFIGURATION OF THE ROADWAY CROWN.

Pavement Seat Repair Details


Figure 10-A-49




PAVEMENT REMOVAL DETAIL



EDGE DETAIL



PAVEMENT SEAT REPLACEMENT



TYPICAL WT 12 SECTION DETAIL

NOTE:


HARDENED WASHERS SHALL CONFORM TO ASTM F436M93 TYPE 3 GALVANIZED PER AASHTO 232.

REPAIR EXISTING PAVEMENT SEAT CONCRETE PRIOR TO INSTALLING WT SECTIONS.

PAINT METAL COMPONENTS OF APPROACH ANCHOR WITH ONE COAT OF INORGANIC ZINC OR FORMULA A-11-99 PAINT IN ACCORDANCE WITH STD. SPEC. 9-08.2.


Section Pavement Seat Repair Details

Figure 10-A-50




Utility Hangers for Prestressed Girders

Figure 10-A-51




Utility Hanger Details for Concrete Box Structures


Figure 10-A-52




BRIDGE PLAN




CONCRETE SLAB
SMALL UTILITY



CONCRETE T-BEAM OR BOX GIRDER BRIDGES




STEEL GIRDER BRIDGE




BRIDGE ELEVATION
PROVIDE BRIDGE NAME AND NUMBER.

NOTE: THE LOCATION OF EXISTING UTILITIES MUST ALSO BE SHOWN WITH RESPECT TO THE PROPOSED ATTACHMENT.




STEEL TRUSS BRIDGE


STEEL TRUSS BRIDGE




SIDEWALK ATTACHMENT




UNACCEPTABLE UTILITY LOCATIONS AND CONNECTIONS



ANCHORAGE DETAIL
RESIN BONDED ANCHORS SHALL BE USED WHEREVER POSSIBLE FOR ALL CONCRETE SUPERSTRUCTURE ATTACHMENTS.



STEEL DECK TRUSS OR ARCH BRIDGE




TIMBER BRIDGE

NAILS OR BOLTS SHALL BE FASTENED TIGHTLY. ANY UNUSED HOLES SHALL BE FILLED WITH CREOSOTE TREATED PLUGS.

THE DETAILS SHOWN HERE ARE PRESENTED AS A GUIDE ONLY. EACH PROPOSED UTILITY INSTALLATION SHALL BE SUBMITTED TO THE DEPARTMENT OF TRANSPORTATION FOR APPROVAL ON AN INDIVIDUAL BASIS. COMPLIANCE WITH THESE DETAILS DOES NOT ASSURE APPROVAL, NOR DOES VARIANCE FROM THESE DETAILS, FOR REASONABLE CAUSE, OR USE OF DETAILS NOT SHOWN HERE NECESSARILY EXCLUDE APPROVAL.

SEE "GENERAL NOTES AND DESIGN CRITERIA"



PRESTRESSED CONCRETE BEAM BRIDGES

MAY BE USED ONLY ON SIMPLE SPAN BRIDGES. UTILITY SHALL BE CARRIED BELOW DIAPHRAGMS. CORE DRILLING THROUGH THE END DIAPHRAGM OR ABUTMENT WALL MAY BE ALLOWED ON A CASE BY CASE BASIS. FOR CONTINUOUS SPAN BRIDGES ATTACHMENTS OF THIS NATURE ARE GENERALLY NOT ALLOWED BECAUSE OF INTERFERENCE WITH THE PIER DIAPHRAGMS OR CROSSBEAMS WHICH ARE CONSIDERED MAIN STRUCTURAL MEMBERS.

ACCEPTABLE UTILITY SUPPORT METHODS
ALL HANGERS SHALL HAVE A MEANS OF VERTICAL ADJUSTMENTS.

SUBMITTAL REQUIREMENTS FOR DISTRICT

A MINIMUM OF 5 PRINTS OR A REPRODUCIBLE DRAWING OF THE ATTACHMENT DETAILS SHALL BE SUBMITTED WITH THE FRANCHISE APPLICATION. ATTACHMENT DETAIL DRAWINGS SHALL INCLUDE A BRIDGE PLAN AND ELEVATION SHOWING THE LOCATION OF THE UTILITY, SUPPORTS AND EXPANSION DEVICES, AND SHALL ALSO INCLUDE DETAILS OF ATTACHMENTS, A TYPICAL CROSS SECTION AND UTILITY ROUTING AT THE BRIDGE ABUTMENTS OR PIER FOOTINGS. BRAND NAMES FOR HANGERS AND ANCHORS SHALL ALSO BE INCLUDED.

NOTE:


DOT FORM 224-047, GENERAL NOTES AND DESIGN CRITERIA. (EXAMPLE 1-18 OF THE UTILITIES MANUAL), IS TO BE PART OF, AND INCLUDED BY REFERENCE, IN ANY PERMIT OR FRANCHISE CONTAINING A BRIDGE ATTACHMENT.


REVISIONS TO THIS GUIDE FOR UTILITY INSTALLATIONS MUST BE COORDINATED WITH BOTH THE BRIDGE OFFICE AND HQ UTILITIES AND SHALL BE APPROVED BY THE BRIDGE RETROFIT ENGINEER. THE REVISION NOTE, DATE AND ENGINEER'S INITIALS ARE ENTERED INTO THE BORDER REVISION BLOCK BY THE CADD OPERATOR AFTER APPROVAL. A FULL SIZE PAPER PRINT IS THEN SENT TO "PUBLICATIONS" THROUGH THE HQ UTILITIES ENGINEER FOR REDUCTION TO 11"X17" AND DISTRIBUTION TO ALL BRIDGE DESIGN MANUAL AND UTILITY MANUAL HOLDERS. CROSS REFERENCE: BRIDGE DESIGN MANUAL - SECTION 8, APPENDIX A (YELLOW COPIES), UTILITIES MANUAL - CHAPTER 1, EXAMPLES SECTION (WHITE COPIES)

Utility Hanger Details


Figure 10-A-53

ALTERNATE MODIFICATION FOR BRIDGE DRAIN TYPES "1", "1B" & "1C"







** ACTUAL PIPE LENGTH (L) SHALL BE DETERMINED BY THE CONTRACTOR IN THE FIELD AND SHALL BE INSTALLED AS SHOWN ON THIS SHEET.




** ACTUAL PIPE LENGTH (L) SHALL BE DETERMINED BY THE CONTRACTOR IN THE FIELD AND SHALL BE INSTALLED AS SHOWN ON THIS SHEET.

OVERLAY MODIFICATION FOR BRIDGE DRAIN TYPE 6






** ACTUAL PIPE LENGTH (L) SHALL BE DETERMINED BY THE CONTRACTOR IN THE FIELD AND SHALL BE INSTALLED AS SHOWN ON THIS SHEET.



** ACTUAL PIPE LENGTH (L) SHALL BE DETERMINED BY THE CONTRACTOR IN THE FIELD AND SHALL BE INSTALLED AS SHOWN ON THIS SHEET.


DRAIN MODIFICATION BY CORE DRILLING

THIS MODIFICATION MAY BE REQUIRED WHEN THE EXISTING DRAIN IS NOT FUNCTIONAL AND CANNOT BE MADE FUNCTIONAL OR WHEN THE EXISTING DRAIN MUST BE PERMANENTLY PLUGGED AND RELOCATED, AS WITH A WIDENING.



ELEVATION VIEW STRAIGHT DROP


** ACTUAL PIPE LENGTH (L) SHALL BE DETERMINED BY THE CONTRACTOR IN THE FIELD AND SHALL BE INSTALLED AS SHOWN ON THIS SHEET.



BRIDGE DRAIN PLUG DETAIL

(LOCATIONS)


REMOVE DRAIN GRATING & GALV. STEEL CHAIN. FILL DRAIN WITH CONCRETE GROUT AFTER PLUGGING.



BRIDGE DRAIN PLUG DETAIL


(LOCATIONS)

REMOVE DRAIN GRATING & GALV. STEEL CHAIN. FILL DRAIN WITH CONCRETE GROUT AFTER PLUGGING.



ELEVATION VIEW INCLINED DROP

** ACTUAL PIPE LENGTH (L) SHALL BE DETERMINED BY THE CONTRACTOR IN THE FIELD AND SHALL BE INSTALLED AS SHOWN ON THIS SHEET.



BRIDGE DRAIN PLUG DETAL

REMOVE DRAIN GRATING & GALV. STEEL CHAIN. FILL DRAIN WITH CONCRETE GROUT AFTER PLUGGING.

NOTES

1. DIMENSIONS AND DETAILS OF EXISTING DRAIN TYPES 1 THRU 6, INCLUDING REVISIONS B, C, AND CR, ARE BASED ON "STANDARDS FOR BRIDGE CONSTRUCTION", SHEET E-13, DATED 12/29/67 AND BEFORE.
2. FOR STANDARD BRIDGE DRAINS DATED SEPTEMBER 1, 1965, AND AFTER, IT WILL BE NECESSARY TO GRIND OFF THE NIPPLE EXTRUSION ON ONE SHORT SIDE OF THE TYPICAL GRATE COVER.
3. ALL NEW STEEL EXCEPT STEEL PIPE SHALL BE AASHTO M 183. STEEL PIPE SHALL CONFORM TO ASTM A 53 GRADE B. ALL STEEL SHALL BE GALVANIZED PER AASHTO M 111.

** ACTUAL PIPE LENGTH (L) SHALL BE DETERMINED BY THE CONSTRACTOR IN THE FIELD AND SHALL BE INSTALLED AS SHOWN ON THIS SHEET.


± THESE SPACINGS ARE TYPICAL HOWEVER OTHER SPACINGS MAY EXIST

GENERAL NOTES

THIS SHEET IS INTENDED FOR USE AS A STANDARD FOR DRAIN MODIFICATIONS WHICH ARE REQUIRED WITH BRIDGE DECK OVERLAYS OF 1 " NOMINAL THICKNESS. MODIFICATIONS PERTAIN ONLY TO THE STANDARD DRAINS DESCRIBED IN NOTE 1 ABOVE.

Bridge Drain Modification

Figure 10-A-54



Bridge Drains Types 2 thru 5 Modification for Overlay

Figure 10-A-55

Chapter 11 Detailing Practice

11.1 Detailing Practice 11-1
11.1.1 Standard Office Practices 11-1
11.1.2 Bridge Office Standard Drawings and Office Examples 11-6
11.1.3 Plan Sheets 11-6
11.1.4 Structural Steel 11-9
11.1.5 Abbreviations 11-12

11.1 Detailing Practice

The following is to provide basic information on drafting and the fundamentals of Bridge and Structures Office drafting practices.

11.1.1 Standard Office Practices

A. Purpose

- The purpose of these standards is to enable the Bridge and Structures Office to produce **consistent** and **effective** plan sheets that will have uniform appearance and information.
- Designers and detailers are responsible for ensuring that these criteria are implemented.
- Deviation from these standards must be approved by the Bridge Design Engineer.

B. Planning

- The designer and the structural detailer together coordinate the **scope** of the detailing work involved in each project. Time should be allotted for checking plans for accuracy and consistency with office practices.
- Similar bridge plans and details should be reviewed and kept as **examples** for maintaining consistent detailing practices. These examples should not be older than three years.

C. Drawing Orientation and Layout Control

- Standard bridge sheet **format** is 34 inches x 22 inches with the bottom 2 inches used for title block and related information.
- Contract plans are printed, sealed, signed and submitted, half size, on 11” x 17” paper.
- Drawings shall be carefully organized so the intent of the drawing is easily understood.
- **North arrow** shall be placed on layouts and footing/foundation layouts.
- **Related details** shall be grouped together in an orderly arrangement: lined up horizontally and vertically and drawn to the same scale.
- Do not crowd the drawing with details.
- The following is a standard sheet configuration when plan, elevation, and sectional views are required.





Figure 11-1

D. Lettering

1. General

- **Lettering** shall be upper case only, slanted at approximately 68 degrees. General text is to be approximately 1/8" high.
- Text shall be **oriented** so as to be read from the **bottom** or **right edge** of the sheet.
- **Detail titles** shall be a similar font as general text, about twice as high and of a heavier weight. Underline all titles with a single line having the same weight as the lettering.
- The **mark number bubble** for reinforcing steel shall be a rectangle.
- **Epoxy coated** reinforcement shall be noted by an "E" inside a triangle:



2. Dimensioning

- A dimension shall be shown **once** on a drawing. Duplication and unnecessary dimensions should be avoided.
- All dimension figures shall be placed above the dimension line, so that they may be read from the bottom or the right edge of the sheet, as shown in the following detail:




Figure 11-2

- Reinforcing bar **clearance** need not be specified on the plans unless different from the "General Notes".
- When details or structural elements are complex, utilize two drawings, one for dimensions and the other for reinforcing bar details.
- Dimensions 12 inches or more shall be given in feet and inches unless the item dimensioned is conventionally designated in inches (for example, 16" pipe).
- In dimensions that are less than one inch over an even foot, the fraction shall be preceded by a zero (for example, 3'-0¾").
- Place dimensions outside the view, preferably to the right or below. However, in the interest of clarity and simplicity it may be necessary to place them otherwise. Examples of dimensioning placement are shown on Figure 11-9.

3. Line Work
   - All line work must be of sufficient size, weight, and clarity so that it can be easily read from a print that has been reduced to 11" x 17" or one-half the size of the original drawing.
   - The line style used for a particular structural outline, centerline, etc., shall be kept consistent wherever that line is shown within a set of bridge plans.
   - Line work shall have appropriate gradations of width to give line contrast as shown below. Care shall be taken that the thin lines are dense enough to show clearly when reproduced.




Figure 11-3

- When drawing structural sections showing reinforcing steel, the **outline** of the sections shall be a **heavier** line weight than the **rebar**.
- The order of **line precedence** (which of a pair of crossing lines is broken) is as follows:

  a. Dimension lines are never broken.

  b. Leader line from a callout.

  c. Extension line.




Figure 11-4

E. Scale

- Scales are not to be shown in the plans.
- When **selecting a scale,** it should be kept in mind that the drawing will be reduced. Generally, the minimum scale for a section detail with rebars is ⅜" = 1'. The minimum scale to be used on steel details will be ¾" = 1'.
- The contract plan sheets are not to be used to take measurements in the field. They will, however, be drawn using **scales that can be found on any standard architectural or engineering scale.**
- Care should be taken that all structural elements are **accurately** drawn to scale.
- Sections and views may be enlarged to show more detail, but the number of different scales used should be kept to a minimum.

F. Graphic Symbols

1. Graphic symbols shall be in accordance with the following:

   a. Structural steel shapes: See also AISC *Manual of Steel Construction.*

   b. Welding symbols: See Lincoln Welding Chart.

   c. Symbols for hatching different materials are shown on Figure 11-10.

G. Structural Sections, Views and Details

- A **section** cuts through the structure, a **view** is from outside the structure, a **detail** shows a structural element in more detail – usually a larger scale.
- Whenever possible, sections and views shall be taken looking to the **right, ahead on stationing,** or **down**.
- Care shall be taken to ensure that the **orientation** of a detail drawing is identical to that of the plan, elevation, etc., from which it is taken. Where there is a **skew** in the bridge any sections should be taken from **plan** views.
- The default is to be looking ahead on stationing. The only mention of view orientation is if the view is looking back on stationing.
- On plan and elevation drawings where there is insufficient space to show cut sections and details, the section and detail drawing should be on the plan sheet immediately following the plan and elevation drawing unless there are a series of related plans. If it is impractical to show details on a section drawing, a detail sheet should immediately follow the section drawing. In other words, the order of plan sheets should be from general plan to more minute detail.
- Structural sections, views, and details shall be identified by a circle divided into upper and lower halves. Examples are shown in Figure 11-11.
- Breaks in lines are allowable provided that their intent is clear.

H. Miscellaneous

- **Callout arrows** are to come off either the beginning or end of the sentence. This means the top line of text for arrows coming off the left of the callout or the bottom line of text for arrows pointing right.
- Except for the Layout, **wall elevations** are to show the exposed face regardless of direction of stationing. The Layout sheet stationing will read increasing left to right. The elevation sheets will represent the view in the field as the wall is being built.




Figure 11-5

- Do not detail a bridge element in more than one location. If the element is changed there is a danger that only one of the details is updated.
- Call out each rebar only twice; the spacing for the bar is shown in one view and the bar is pointed to in a view taken from a different angle. The **spacing** for a bar must go on a dimension line with extension lines, do not point to a single bar and call out the spacing.

- When calling out a rebar spacing always give a distance. If the distance needed is an odd number give a maximum spacing. **Do not** use **"equal spaces"** as in "23 equal spaces = 18'-9"," the steel workers should not have to calculate the spacing. Also **do not** use the word **"about"** as in **"**23 spaces @ about 10" = 18'-9" **"**this is open to too much interpretation. Instead these should read **"23 spaces @ 10" max. = 18'-9"**."
- Centerline callouts shall be normal to the line itself approximately an eighth inch from the end of the line:




Figure 11-6

I. Revisions

- **Addendums** are made after general distribution and project ad but before the contract is awarded. Changes made to the plan sheets during this time shall be **shaded**.
- **Change orders** are made after the contract has been awarded. Changes will be marked with a number inside a circle inside a **triangle**. 

- Both addendums and change orders will be noted in the **revision block** at the bottom of the sheet.

11.1.2 Bridge Office Standard Drawings and Office Examples

A. General

- The Bridge Office provides standard drawings and example sheets of various common bridge elements.

B. Use of Standards

- The Standard Drawings are to be considered as nothing more than **examples** of items like girders or traffic barriers which are often used and are very similar from job to job.
- They are to be **copied** to a structure project and **modified to fit** the particular aspects of the structure. They are not intended to be included in a contract plan set without close scrutiny for applicability to the job.

C. Changes to Standards

- New standard drawings and revisions to existing drawings shall be approved by the Bridge Design Engineer and shall be made according to the same office practices as contract plan sheets.

11.1.3 Plan Sheets

Plan sheets should be assembled in the **order of construction** listed below:

- Layout
- Footing/Foundation Layout
- Abutment
- Pier/Bent
- Bearing Details
- Framing Plan

Typical Section

- Girders
- Roadway Slab Reinforcement (Plan and transverse section)
- Expansion Joints (if needed)
- Traffic Barrier
- Approach Slab
- Barlist

A. Layout

- The Layout sheet shall contain, but is not limited to:

  Plan View with ascending stations from left to right

  Elevation View shown as an outside view of the bridge and shall be visually aligned with the plan view.

- The original preliminary plan will be copied to create the final layout. Views, data, and notes may be repositioned to improve the final product.
- Items on the preliminary plan, which should **not** appear on the final layout are as follows:
  - Typical roadway sections.
  - Vertical curve, Superelevation and curve data for other than the main line.
  - Other information that was preliminary or that will be found elsewhere in the plans.
- Items not normally found on the preliminary plan, which should be **added**:
  - **Test hole locations** (designated by 3/16 inch circles, quartered) to plan view.
  - Elevation view of **footings, seals, piles,** etc. Show elevation at Bottom of footing and, if applicable, the type and size of piling.
  - **General notes** above legend on right hand side, usually in place of the typical section.
  - Title "LAYOUT" in the title block and sheet number in the space provided.
  - Other features, such as lighting, conduit, signs, excavation, riprap, etc. as determined by the designer.
  - The preliminary plan checklist in Appendix A, Chapter 2 can be used for reference.

B. Footing Layout

- An abutment with a **spread footing** has a Footing Layout. An abutment with **piles** and **pile cap** has a Foundation Layout.
- The Footing Layout is a plan of the bridge whose details are limited to those needed to **locate the footings**. The intent of the footing layout is to minimize the possibility of error at this initial stage of construction.
- The Foundation Layout is a plan of the bridge whose details are limited to those needed to **locate the shafts or piles**. The intent of the Foundation layout is to minimize the possibility of error at this initial stage of construction.

- Other related information and/or details such as pedestal sizes, and column sizes are considered part of the pier drawing and **should not be included** in the footing layout.
- The Footing Layout should be shown on the layout sheet if space allows. It need not be in the same scale. When the general notes and footing layout cannot be included on the first (layout) sheet, the footing layout should be included on the second sheet.
- Longitudinally, footings should be located using the **survey line** to reference such items as the footing, centerline pier, centerline column, or centerline bearing, etc.
- When **seals** are required, their locations and sizes should be clearly indicated on the footing layout.
- The Wall Foundation Plan for retaining walls is similar to the Footing Plan for bridges except that it also shows dimensions to the front face of wall.
- Figure 11-12 is an example of a footing layout showing:
  - The basic information needed.
  - The method of detailing from the survey line.

C. Abutment

- Bridge elements which have not yet been built will not be shown. For example, the superstructure is not to be shown, dashed or not, on any substructure details.
- Elevation information for seals and piles or shafts may be shown on the abutment or pier sheets.
- Views are to be oriented so that they represent what the contractor or inspector would most likely see on the ground. Pier 1 elevation is often shown looking back on stationing. A note should be added under the Elevation Pier 1 title saying “Shown looking back on stationing”.

D. Pier/Bent

- Each pier shall be detailed separately as a general rule. If the intermediate piers are identical except for height, then they can be shown together.

E. Bearing Details

F. Framing Plan

- Girder Lines must be identified in the plan view (Gir. A, Gir. B, etc.).

Typical Section

- Girder spacing, which is tied to the bridge construction baseline
- Roadway slab thickness, as well as web and bottom slab thicknesses for box girders
- “A” dimension
- Limits of pigmented sealer
- Profile grade and pivot point and cross slopes
- Utility locations
- Curb to curb roadway width
- Soffit and drip groove geometry

G. Girders

- Prestressed girder sheets can be copied from the Bridge Office library but they must be modified to match the project requirements.

H. Roadway Slab Reinforcement

Plan and transverse section views

I. Expansion Joints

J. Traffic Barrier

- Traffic barrier sheets can be copied from the Bridge Office library but they must be modified to match the project requirements.

K. Approach Slab

- Approach slab sheets can be copied from the Bridge Office library and modified as necessary for the project.

L. Barlist

- The barlist sheets do not require stamping because they are not officially part of the contract plan set.

11.1.4 Structural Steel

A. General

- Flat pieces of steel are termed plates, bars, sheets or strips, depending on the dimensions.

B. Bars

- Up to 6 inches wide, 0.203 in. (3/16 inch) and over in thickness, or 6 inches to 8 inches wide, 0.230 in. (7/32 inch) and over in thickness.

C. Plates

- Over 8 inches wide, 0.230 in. (7/32 inch) and over in thickness, or over 48 inches wide, 0.180 in (11/64 inch) and over in thickness.

D. Strips

- Thinner pieces up to 12 inches wide are strips and over 12 inches are sheets. A complete table of classification may be found in the *AISC Manual of Steel Construction*, 8th Ed. Page 6-3.

E. Labeling

- The following table shows the usual method of labeling some of the most frequently used structural steel shapes. Note that the inches symbol (“) is omitted, but the foot symbol (‘) is used for length including lengths less than a foot.



PLATES
PL ½ x 34 x 5'-6
GROUP SYMBOL
THICKNESS IN INCHES
WIDTH IN INCHES
LENGTH IN FEET AND INCHES
ANGLES
L 6 x 5 x ¾ x 2'-1
GROUP SYMBOL
LONG LEG IN INCHES
SHORT LEG IN INCHES
THICKNESS IN INCHES
LENGTH IN FEET AND INCHES
FLAT BARS
BAR 2 x ¾ x 0'-6
GROUP SYMBOL
WIDTH IN INCHES
THICKNESS IN INCHES
LENGTH IN FEET AND INCHES
RECTANGULAR HSS
HSS 6 x 5 x ¼ x 3'-2
GROUP SYMBOL
WIDTH IN INCHES
WIDTH IN INCHES
WALL THICKNESS IN INCHES
LENGTH IN FEET AND INCHES
SQUARE BARS
BAR 2 □ x 3'-4
GROUP SYMBOL
SIZE IN INCHES
CONVENTION FOR "SQUARE"
LENGTH IN FEET AND INCHES
CIRCULAR HSS
HSS 3.000 x 0.250 x 2'-5
GROUP SYMBOL
OUTSIDE DIAM. IN INCHES
WALL THICKNESS IN INCHES
LENGTH IN FEET AND INCHES
ROUND BARS
BAR 2 ø x 0'-4
GROUP SYMBOL
SIZE IN INCHES
CONVENTION FOR "ROUND"
LENGTH IN FEET AND INCHES
PIPES
1½"ø STD PIPE
NOMINAL DIAM. IN INCHES
DESIGNATION
GROUP SYMBOL

Figure 11-7

SECTION	DESIGNATION	EXAMPLE
I-Beams	I DEPTH x WT	14 x 3.28
Wide-Flange Sections	WF DEPTH x WT	WF4 x 4.76
Wide-Flange Sections, Army-Navy Series	WF(A-N) DEPTH x WT	WF(A-N)4 x 1.79
American Standard Channels	C DEPTH x WT	C4 x 1.85
Special Channels	CS DEPTH x WT	CS4 x 3.32
Wing Channels	CS(WING) WIDTH x WT	CS(WING)4 x 0.90
Army-Navy Channels	C(A-N) DEPTH x WT	C(A-N)4 x 1.58
Angles	L LL x LL x TH	L3 x 3 x 0.25
Square End Angles	LS LL x LL x TH	LS2 x 2 x 0.187
Bulb Angles	BULB L LL1 x LL2 x TH1 x TH2	BULB L4 x 3.5 x 0.375 x 0.375
Bulb Angle, Army-Navy Series	BULB L(A-N) LL1 x LL2 x TH1 x TH2	BULB L(A-N) 3 x 2 x 0.188 x 0.188
Tees	T DEPTH x WIDTH x WT	T4 x 4 x 3.43
Army-Navy Tees	T(A-N) DEPTH x WIDTH x WT	T(A-N)4 x 4 x 2.27
Zees	Z DEPTH x WIDTH x WT	Z4 x 3.06 x 2.85
Plates	PL TH x WIDTH	PL¼ x 8
Rods	RD DIA	RD 1
Square Bars	SQ SDIM	SQ 4
Rectangle Bars	RECT TH x WIDTH	RECT¼ x 4
Round Tubes	ODIA OD x TH WALL	4OD x 0.125 WALL
Square Tubes	ODIM SQ x TH WALL	3SQ x 0.219 WALL
Rectangle Tubes	DEPTH x WIDTH RECT x TH WALL	4 x 1.5 RECT x 0.104 WALL

The designations used in the tables are suggested for general use.

WT - WEIGHT in LB/FT based on density of 0.098

TH - THICKNESS, LL - LEG LENGTH, DIA – DIAMETER

ODIA - OUTSIDE DIAMETER, ODIM - OUTSIDE DIMENSION

SDIM - SIDE DIMENSION

All lengths in inches

Aluminum Section Designations
Figure 11-8

11.1.5 Abbreviations

General

- Abbreviations, as a rule, are to be **avoided**.
- Because different words sometimes have identical abbreviations, the word should be spelled out where the meaning may be in doubt.
- A few **standard signs** are in common use in the Bridge and Structures Office. These are listed with the abbreviations.
- A **period** should be placed after all abbreviations, except as listed below.
- **Apostrophes** are usually not used. Exceptions: pav't., req'd.
- Abbreviations for **plurals** are usually the same as the singular. Exceptions: figs., no., ctrs., pp.
- **No** abbreviations in titles.

List of abbreviations commonly used on bridge plan sheets:

A

Abutment	ABUT.
Adjust, Adjacent	ADJ.
Aggregate	AGG.
Alternate	ALT.
Ahead	AHD.
Aluminum	AL.
American Society for Testing and Materials	ASTM
American Association of State Highway and Transportation Officials	AASHTO
And	&
Angle Point	A.P.
Approved	APPRD.
Approximate	APPROX.
Area	A
Asbestos Cement Pipe	ASB. CP
Asphalt Concrete	AC
Asphalt Treated Base	ATB
At	@ (used only to indicate spacing or pricing, otherwise spell it out)
Avenue	AVE.
Average	AVG.

B

Back	BK.
Back of Pavement Seat	B.P.S.
Bearing	BRG.
Begin Horizontal Curve (Point of Curvature)	P.C.
Begin Vertical Curve	BVC
Bench Mark	BM

Between	BTWN.
Bituminous Surface Treatment	BST
Bottom	BOT.
Boulevard	BLVD.
Bridge	BR.
Bridge Drain	BR. DR.
Building	BLDG.
Buried Cable	BC

C

Cast-In-Place	CIP
Cast Iron Pipe	(C.I.P.)
Center, Centers	CTR., CTRS.
Centerline	℄
Center of Gravity	CG
Center to Center	CTR. TO CTR., C/C
Celsius (formerly Centigrade)	C
Cement Treated Base	CTB
Centimeters	CM.
Class	Cl.
Clearance, Clear	CLR.
Compression, Compressive	COMP.
Column	COL.
Concrete	CONC.
Conduit	COND.
Concrete Pavement (Portland Cement Concrete Pavement)	PCCP
Construction	CONST. Or CONSTR.
Continuous	CONT. or CONTIN.
Corrugated	CORR.
Corrugated Metal	CM
Corrugated Steel Pipe	CSP
Countersink	CSK.
County	CO.
Creek	CR.
Cross Beam	X-BM.
Crossing	XING
Cross Section	X-SECT.
Cubic Feet	CF or CU. FT. or $FT.^3$
Cubic Inch	CU. IN. or $IN.^3$
Cubic Yard	CY or CU. YD. or YD^3
Culvert	CULV.

D

Degrees, Angular	º or DEG.
Degrees, Thermal	C or F
Diagonals(s)	DIAG.
Diameter	DIAM. or ø
Diaphragm	DIAPH.
Dimension	DIM.
Double	DBL.
Drive	DR.

E

Each	EA.
Each Face	E.F.
Easement	EASE., ESMT.
East	E.
Edge of Pavement	EP
Edge of Shoulder	ES
Endwall	EW
Electric	ELECT
Elevation	EL. or ELEV.
Embankment	EMB.
End horizontal curve (Point of Tangency)	P.T.
End Vertical Curve	EVC
Engineer	ENGR.
Equal(s)	EQ. (as in eq. spaces) or = (mathematical result)
Estimate(d)	EST.
Excavation	EXC.
Excluding	EXCL.
Expansion	EXP., EXPAN.
Existing	EXIST.
Exterior	EXT.

F

Fahrenheit	F
Far Face	FF
Far Side	FS
Feet (foot)	FT. or ’
Feet per Foot	FT./FT. or ’/’ or ’/FT.
Field Splice	F.S.
Figure, Figures	FIG., FIGS.
Flat Head	F.H.
Foot Kips	FT-KIPS
Foot Pounds	FT-LB
Footing	FTG.
Forward	FWD.
Freeway	FWY.

G

Gallon(s)	GAL.
Galvanized	GALV.
Galvanized Steel Pipe	GSP
Gauge	GA.
General Special Provisions	GSP
Girder	GIR.
Ground	GR.
Guard Railing	GR

H

Hanger	HGR.
Height	HT.
Height (retaining wall)	H
Hexagonal	HEX.
High Strength	H.S.
High Water	H.W.
High Water Mark	H.W.M.
Highway	HWY.
Horizontal	HORIZ.
Hot Mix Asphalt	HMA
Hour(s)	HR.
Hundred(s)	HUND.

I

Included, Including	INCL.
Inche(s)	IN. or “
Inside Diameter	I.D.
Inside Face	I.F.
Interior	INT.
Intermediate	INTERM.
Interstate	I
Invert	INV.

J

Joint	JT.
Junction	JCT.

K

Kilometer(s)	KM.
Kilopounds	KIPS, K.

L

Layout	LO
Left	LT.
Length of Curve	L.C.
Linear Feet	L.F.
Longitudinal	LONGIT.
Lump Sum	L.S.

M

Maintenance	MAINT.
Malleable	MALL.
Manhole	MH
Manufacturer	MFR.
Maximum	MAX.
Mean High Water	MHW
Mean Higher High Water	MHHW
Mean Low Water	MLW
Mean Lower Low Water	MLLW
Meters	M.
Mile(s)	MI.
Mmiles Per Hour	MPH
Millimeters	MM.
Minimum	MIN.
Minute(s)	MIN. or ‘
Miscellaneous	MISC.
Modified	MOD.
Monument	MON.

N

National Geodetic Vertical datum	N.G.V.D.
Near Face	NF
Near Side	NS
North	N.
Northbound	NB
Not To Scale	NTS
Number; Numbers	#, NO., NOS.

O

Or	/
Original Ground	O.G.
Ounce(s)	OZ.
Outside Diameter	O.D.
Outside Face	O.F.
Out to Out	O to O
Overcrossing	O-XING
Overhead	OH

P

Page; Pages	P.; PP.
Pavement	PAV’T
Pedestrian	PED.
Per Cent	%
Pivot Point	PP
Plans, Specifications and Estimates	PS&E
Plate	ℙ or PL

Point	PT.
Point of Compound Curve	PCC
Point of Curvature	P.C.
Point of Intersection	P.I.
Point of Intersection Vertical Curve	P.I.V.C
Point of Reverse Curve	PRC
Point of Tangency	P.T.
Point of Vertical Curve	PVC
Point of Horizontal Curve	POC
Point of Tangent	POT
Polyvinyl Chloride	PVC
Portland Cement Concrete	PCC
Pound, Pounds	LB., LBS., #
Pounds Per Square Foot	PSF, LBS./FT.², LBS./ ‘,or #/’
Pounds Per Square Inch	PSI, LBS./IN.², LBS./ “,or #/”
Power Pole	PP
Precast	P.C.
Pressure	PRES.
Prestressed	P.S.
Prestressed Concrete Pipe	P.C.P.
Puget Sound Power and Light	P.S.P.&L.

Q

Quantity	QUANT.
Quart	QT.

R

Radius	R.
Railroad	RR
Railway	RWY.
Range	R.
Regulator	REG.
Reinforced, Reinforcing	REINF.
Reinforced Concrete	RC
Reinforced Concrete Box	RCB
Reinforced Concrete Pipe	RCP
Required	REQ’D
Retaining Wall	RET. WALL
Revised (date)	REV.
Right	RT.
Right of Way	R/W
Road	RD.
Roadway	RDWY.
Route	RTE.

S

Seconds	SEC. or “
Section (map location)	SEC.
Section (of drawing)	SECT.
Sheet	SHT.
Shoulder	SHLD. or SH.
Sidewalk	SW. or SDWK
South	S.
Southbound	SB
Space(s)	SPA.
Splice	SPL.
Specification	SPEC.
Square Foot (feet)	SQ. FT. or FT.^{2}
Square Inch	SQ. IN. or IN.^{2}
Square Yard	SY, SQ. YD. or YD.^{2}
Station	STA.
Standard	STD.
State Route	SR
Stiffener	STIFF.
Stirrup	STIRR.
Structure, Structural	STR.
Support	SUPP.
Surface, Surfacing	SURF.
Symmetrical	SYMM.

T

Tangent	TAN. or T.
Telephone	TEL.
Temporary	TEMP.
Test Hole	T.H.
Thick(ness)	TH.
Thousand	M
Thousand (feet) Board Measure	MBM
Ton(s)	T.
Total	TOT.
Township	T.
Transition	TRANS.
Transportation	TRANSP.
Transverse	TRANSV.
Treatment	TR.
Typical	TYP.

U

Ultimate	ULT.
Undercrossing	U-XING

V

Variable, Varies	VAR.
Vertical	VERT.
Vertical Curve	V.C.
Vitrified Clay Pipe	VCP
Volume	VOL. or V

W

Water Surface	W.S.
Weight(s)	WT.
Welded Steel Pipe	WSP
Welded Wire Fabric	W.W.F.
West	W.
Willamette Meridian	W.M.
Wingwall	WW
With	W/
Without	W/O

Y

Yard, Yards	YD., YDS.
Year(s)	YR.





BREAK LINE FOR
DIMENSION ARROW
3'-0"
6"
8½"
CLR.
⅜" TO ½" SPA.
FOR "STACKED"
DIMENSIONS
ONLY WHEN
SPACE IS
TOO SMALL
⅛" OVERSHOOT
1'-3"
2'-0"
1/16" UNDERSHOOT
2'-0"
4'-0"
NOT LESS
THAN ½"
4'-0"
6'-0"
10'-0"
1'-6"
1'-6"
1'-6"
1'-0"
3" (TYP.)
9"
(TYP.)
2'-0"
PL ¾
1"ø DRILLED
HOLE (TYP.)
3'-0"
1'-6"
5'-1½"
2'-6¾"
PL ½
2'-0"
4'-0"
1'-0"
OR R=10'
R=10'


Figure 11-9




TYPICAL CONCRETE DETAIL



TYPICAL REMOVAL DETAIL



TYPICAL STEEL DETAIL



TYPICAL TIMBER DETAIL

Figure 11-10




LEGEND
B
15
IDENTIFIES SECTION, VIEW OR DETAIL
TAKEN OR SHOWN ON BRIDGE SHEET 15
USE DASH WHERE SECTION, VIEW OR DETAIL IS TAKEN AND SHOWN ON THE SAME SHEET
B
B
TAKEN OR SHOWN ON BRIDGE SHEETS 15, 17 OR 23
15, 17 & 23
A
15
A
15
A
15
USE WITH LARGE OR STAGGERED CUT SECTION OR VIEW
SEE DETAIL A
SECTIONS AND DETAIL ON THIS BRIDGE SHEET ARE SHOWN ON BRIDGE SHEET NO. 15
BRIDGE SHEET NO.
14
SHEET
OF
SHEETS
USE WITH A SMALLER CUT SECTION OR VIEW
SECTION A 15
DETAIL A 15
VIEW A 15
SECTIONS AND DETAIL ON THIS BRIDGE SHEET ARE TAKEN ON BRIDGE SHEET NO. 15
BRIDGE SHEET NO.
14
SHEET
OF
SHEETS
PILE TIP ELEV.
2½"
3/8
SIZE AS APPROPRIATE

Figure 11-11



Footing Layout
Figure 11-12

Chapter 12 Quantities, Costs & Specifications

12.1 Quantities - General 12-1
12.1.1 Cost Estimating Quantities 12-1
12.1.2 Not Included in Bridge Quantities List 12-1
12.2 Computation of Quantities 12-2
12.2.1 Responsibilities 12-2
12.2.2 Procedure for Computation 12-2
12.2.3 Data Source 12-3
12.2.4 Accuracy 12-3
12.2.5 Excavation 12-3
12.2.6 Shoring or Extra Excavation, Class A 12-7
12.2.7 Piling 12-9
12.3 Construction Costs 12-9
12.3.1 Introduction 12-9
12.3.2 Factors Affecting Costs 12-9
12.3.2.1 Type of Structure 12-9
12.3.2.2 Location of Project Site 12-9
12.3.2.3 Size of Project Contract 12-10
12.3.2.4 Foundation Requirements 12-10
12.3.2.5 Sequencing of Project 12-10
12.3.3 Development of Cost Estimates 12-10
12.3.3.1 Types 12-10
12.3.3.2 Responsibilities 12-11
12.3.3.3 Documentation 12-11
12.3.3.4 Cost Data 12-11
12.4 Construction Specifications and Estimates 12-12
12.4.1 General 12-12
12.4.2 Definitions 12-12
12.4.3 General Bridge S&E Process 12-13
12.4.4 Reviewing Bridge Plans 12-14
12.4.5 Preparing the Bridge Cost Estimates 12-15
12.4.6 Preparing the Bridge Specifications 12-16
12.4.7 Preparing the Bridge Working Day Schedule 12-17
12.4.8 Reviewing Projects Prepared by Consultants 12-17
12.4.9 Submitting the PS&E Package 12-18
12.4.10 PS&E Review Period and Turn-in for AD Copy 12-19

Appendix 12-A

Figure 12-A-1 Not Included In Bridge Quantities List 12-A-1
Figure 12-A-2 Bridge Quantities (Page 1 of 6) 12-A-2
Figure 12-A-2 Bridge Quantities (Continued Page 2 of 6) 12-A-3
Figure 12-A-2 Bridge Quantities (Continued Page 3 of 6) 12-A-4
Figure 12-A-2 Bridge Quantities (Continued Page 4 of 6) 12-A-5
Figure 12-A-2 Bridge Quantities (Continued Page 5 of 6) 12-A-6
Figure 12-A-2 Bridge Quantities (Continued Page 6 of 6) 12-A-7
Figure 12-A-3 Bridge and Structures 12-A-8
Figure 12-A-3 Bridge and Structures (Continued) 12-A-9
Figure 12-A-4 Substructure 12-A-10

Figure 12-A-5 Superstructre 12-A-11
Figure 12-A-6 Miscellaneous..... 12-A-12
Figure 12-A-7 Construction Time Rates..... 12-A-13
Appendix 12-B
Figure 12-B-1 Cost Estimate Summary..... 12-B-1
Figure 12-B-2 Construction Working Day Schedule..... 12-B-2

12.1 Quantities - General

The quantities of the various materials and work items involved in the construction of a project that includes bridges and structures are needed for establishing the estimated cost of the project throughout the design process, and for establishing a basis for comparison of the contractor's bids.

12.1.1 Cost Estimating Quantities

Quantities for establishing cost estimates are often necessary during various stages of project development and are required at the completion of the Bridge PS&E. These quantities should be calculated from the best information available at the time (see BDM Section 12.2.3). The policy regarding the preparation of quantity calculations is as follows:

A. Conceptual Stage

During the conceptual stage of a project, estimated quantities may be required to arrive at an estimated cost. The need for conceptual stage quantities will be determined by the Bridge Projects Unit.

B. Preliminary Plan Stage

Upon completion of the preliminary plan, estimated quantities may be required to arrive at an estimated cost. The need for preliminary plan stage quantities will be determined by the Bridge Projects Unit.

C. Design Stage

If requested, quantity calculations shall be made, reviewed, and submitted to the Bridge Projects Unit by the Bridge Design Unit as the design progresses. The first submittal of estimated quantities shall be made as soon as the major dimensions of the structure are determined. As refinements in the design are made, quantities varying more than 10 percent from those previously submitted shall be resubmitted.

D. Final Contract Quantities

Upon completion of structural design and plans, the quantities of materials and work items involved in the construction of the project shall be computed. See BDM Sections 12.2.2 and 12.2.4 B.

12.1.2 Not Included in Bridge Quantities List

Items of work which appear in the bridge plan sheets, but for which details, specifications, and quantities are not included in the Bridge PS&E, shall be listed in the "Not Included in Bridge Quantities List" (Form 230-038 and Figure 12-A-1). This list is required for every bridge, even if no items of work are shown in the Plans that are in this category. (In this case, fill out the bridge information at the top of the form and write "NONE" across the form.) This form is transmitted to the Region Design PE Office with all Preliminary Plan submittals, all Bridge PS&E distributions, and at various milestone points during the design process, to ensure that the responsibility for all PS&E items is clear. Particular care shall be taken in the preparation of this list as omissions can result in an incomplete project PS&E with missing information for work items, or conflicting overlapping information for work items.

12.2 Computation of Quantities

12.2.1 Responsibilities

A. Design Unit

The Design Unit is responsible for calculating quantities required for cost estimates for Preliminary Plans prepared in Design Units, calculating preliminary quantities at various milestones during the design process, and calculating quantities for the final Bridge PS&E. The Design Unit is responsible for notifying the Region Design PE Office and the Bridge Projects Unit whenever structural design changes and alterations are made to the design features and quantities which affect the cost of the structure, especially following the distribution of the initial Preliminary Plan.

B. Bridge Projects Unit

The Bridge Projects Unit is responsible for computing quantities for conceptual stage cost estimates, and cost estimates for Preliminary Plans prepared in the Bridge Projects Unit. The Bridge Projects Unit is responsible for ensuring that the quantities listed in the AD Copy Bid Proposal correspond to those received from the Design Unit.

12.2.2 Procedure for Computation

Quantities are to be computed and checked independently. The designer/originator and checker shall separately summarize their calculated quantities on the "Bridge Quantities" Form 230-031 (See Figure 12-A-2) in the units shown thereon. The two summaries shall be submitted to the Design Unit Supervisor for comparison. The designer/originator and checker shall use identical breakdowns for each quantity. For example, the designer/originator's quantities for excavation for each of Piers 1, 2, and 3 should be compared separately against the corresponding quantities made by the checker.

When the desired accuracy is achieved, a Supervisor's Bridge Quantities form shall be prepared and submitted to the Bridge Projects Unit along with the 90 percent Bridge Plans submittal. (This form is the same as previously mentioned except that it is labeled "Supervisor's Bridge Quantities" and is completed by the unit supervisor or designee. If the unit supervisor elects, the designer/originator's or the checker's Bridge Quantities form may be designated as "Supervisor's Bridge Quantities.") This form is used by the Bridge Projects Unit to prepare the final bridge cost estimate.

All quantity calculations and bridge quantities forms are to be filed in the job file for the structure or the PS&E file for the project. All subsequent revisions shall be handled in the same manner as the original quantities. On the "Bridge Quantities" form, any revision to the original figure should not be erased but crossed out and replaced by the new figure using a different colored pencil. If there are too many revisions, the old summary sheet should be marked void, left in the file, and a new sheet made out, marked "Revised," dated, and the original forwarded to the Bridge Projects Unit.

Mistakes in quantities can be very costly to Contracting Agency. The designer/originator and checker must account for all items of work on the "Bridge Quantities" form, and must also be careful to enter an item of work only once (e.g., concrete or steel rebar in the superstructure should not be entered both in the lump sum superstructure breakdown and in the unit bid item quantity).

12.2.3 Data Source

Quantities of materials for use in preliminary cost estimates can often be obtained from the quantities calculated for previous similar designs. This information is available from the Bridge Projects Unit.

12.2.4 Accuracy

A. Preliminary Quantities

Quantities used for cost estimates prepared during the conceptual stage of the design are expected to have an accuracy of ± 10 percent. The first iteration of quantities, after the preliminary plan has been completed, is expected to have an accuracy of ± 5 percent.

B. Final Quantities

Final quantities in the Bridge PS&E submittal, including bar list quantities, to be listed in the Special Provisions and Bid Proposal sheet of the AD Copy, are to be calculated to have an accuracy of ± 1 percent.

12.2.5 Excavation

A. Structure Excavation, Class A

Excavation necessary for the construction of bridge piers and reinforced concrete retaining walls is classified as Structure Excavation, Class A (see the definition as specified in Standard Specification Section 2-09.3(2)). Payment for such excavation is generally by volume measurement. The quantity of excavation to be paid for is measured as specified in Standard Specification Section 2-09.4, and computation of this quantity shall conform to these specifications. If the construction circumstances for the project require structure excavation limits that do not conform to the Standard Specification definition, then the modified structure excavation limits shall be shown in details in the Plans.

Structure excavation for footings and seals shall be computed using a horizontal limit of 1 foot 0 inches outside and parallel to the neat lines of the footing or seal or as shown in the Plans. The upper limit shall be the ground surface or stream bed as it exists at the time the excavation is started. See Figure 12-1(A), (B), and (C).




Figure 12-1

Structure excavation for the construction of wing walls shall be computed using limits shown in Figure 12-2.




Figure 12-2




Figure 12-3

When bridge approach fills are to be constructed in the same contract as the bridge, and the foundation conditions do not require full height fills to be placed prior to the construction of the pier, the approach fill is constructed in two stages, i.e., constructed up to the bottom of footing or 1 foot above the bottom of footing, and then completed after the bridge construction. (The Materials Laboratory Geotechnical Services Branch shall be consulted on the staging method.) The structure excavation shall be computed from the top of the first stage fill.

The bottom of a spread footing will be placed 1 foot 0 inches below the top of the first stage fill. See Figure 12-4(A). The bottom of footings supported on piling will be placed at the top of the first stage fill; therefore no structure excavation is required (see Figure 12-4(B)).

The limits for stage fills shall be shown in the Plans with the structure excavation, if any.




Figure 12-4

Prior to pier construction, when (1) a full height fill with or without surcharge is required for settlement, or (2) the original ground line is above the finish grade line, the upper limit of structure excavation shall be computed to 1 foot 0 inches below the finish grade (pavement) line (see Figure 12-5).




Figure 12-5

B. Special Excavation

The excavation necessary for placement of riprap around bridge piers is called Special Excavation (see Figure 12-6).

Special excavation shall be computed from the top of the seal to the existing stream bed or ground line along the slopes indicated in the Plans. Special excavation will only include excavation outside the limits of structure excavation.

The limits for special excavation shall be shown in the Plans.




Figure 12-6

C. Shaft Excavation

Excavation necessary for the construction of shaft foundations is measured by volume and paid for at the unit contract price per cubic yard or cubic meter for "Soil Excavation For Shaft Including Haul."

The usual limits for computing shaft excavation shall be the neat lines of the shaft diameter as shown in the Plans, the bottom elevation of the shaft as shown in the Plans, and the top of the ground surface, defined as the highest existing ground point as shown in the Plans within the shaft diameter.

The methods of measurement and payment and the limits for shaft excavation shall be specified in the Special Provisions.

12.2.6 Shoring or Extra Excavation, Class A

Shoring, cofferdams or caissons, or extra excavation required for construction of bridge footings and reinforced concrete retaining walls constructed in the wet or dry is classified as Shoring or Extra Excavation, Class A. See Standard Specification Section 2-09.3(3).

Structural shoring (for dry excavation) or cofferdams (for wet excavation) is required for all excavations near completed structures (foundations of bridges, walls, or buildings), near underground utilities, near railroad tracks, and near pavement. All other excavation four feet or more in depth shall be either shored with structural shoring or cofferdams, or shall meet the open-pit excavation requirements as specified in Standard Specification Section 2-09.3(3)B.

For the purpose of estimating the cost for shoring or extra excavation, Class A, it is necessary to compute the peripheral area of an assumed sheet pile enclosure of the excavated area.

While payment for Shoring or Extra Excavation, Class A, is made at a lump sum contract price, the costs are a function of the overall height of excavation. In general, each side of the excavation for each pier shall be categorized into an average overall height range as shown on Form 230-031 (i.e., less than 6 feet, 6 to 10 feet, 10 to 20 feet, or greater than 20 feet), the area for the side computed using the appropriate width times the average overall height, the overall area for the side shall be entered in the category that matches the side's average overall height. These calculations are required for each pier of the bridge as applicable. See accompanying Figure 12-7 and sample calculation.

For excavation in the dry, the peripheral area shall be the perimeter of the horizontal limits of structure excavation times the height from the bottom of the footing to the ground surface at the time of excavation.

For excavation in water, the peripheral area shall be the perimeter of the horizontal limits of structure excavation times the height from the bottom of the seal to 2 feet above the seal vent elevation.

For shaft-type excavations, it is not normally necessary to compute the area for shoring because the shoring is usually accommodated by the work items for permanent casing, temporary casing, and casing shoring.




Figure 12-7

Sample Calculation:

For this pier (Figure 12-7):

Side A: average height = (4 + 6)/2 = 5 feet
width = 15 feet
area = 5 X 15 = 75 square feet

Side B: average height = (6 + 15)/2 = 10.5 feet
width = 20 feet
area = 10.5 X 20 = 210 square feet

Side C: average height = (10 + 15)/2 = 12.5 feet
width = 15 feet
area = 12.5 X 15 = 187.5 square feet

Side D: average height = (4 + 10)/2 = 7 feet
width = 20 feet
area = 7 X 20 = 140 square feet

For this example

height category	***area***
less than 6 feet	75 square feet
6 feet to 10 feet	140 square feet
10 feet to 20 feet	210 + 188 = 398 square feet
greater than 20 feet	N.A.

These numbers would be entered on Form 230-031 as follows:

Std. Item No. 4012	**Item Use** Std. Item		**Item Description** Shoring or Extra Excavation, Class A Dry: Average Overall Height		**Quant.** (Enter Total for Bridge Here)		**Unit of Meas.** L.S.	
Pier	6 ft.		6 ft. to 10 ft.		10 ft.* to 20 ft.		20 ft.	S.F.
Example	75	S.F.	140	S.F.	398 (11.5*) S.F.	S.F.	—	S.F.
		S.F.		S.F.		S.F.		S.F.
		S.F.		S.F.		S.F.		S.F.
		S.F.		S.F.		S.F.		S.F.

* Indicate Average Height

12.2.7 Piling

The piling quantities are to be measured and paid for in accordance with Standard Specification Sections 6-05.4 and 6-05.5. Computation of piling quantities shall follow the same provisions.

Timber test piles are driven outside the structure limits and are extra or additional piling beyond the required number of production piling. See Standard Specification Section 6-05.3(10).

Concrete or steel test piles are driven within the structure limits and take the place of production piling. In this case, the quantities for number and length of production piling is reduced by the number and length of test piling.

The quantity for "Furnishing _____ Piling _____" is the linear measurement of production piling below cut-off to the "estimated" pile tip (not "minimum" tip) specified in the Geotechnical report. (Does not include test piles.)

The quantity for "Driving _____ Pile _____" is the number of production piling driven. (Does not include test piles.)

Pile tips are required if so specified in the Geotechnical report. The tips on the test piles are incidental to the test pile; therefore, the number of pile tips reported on the Bridge Quantities Form 230-031 should not include the number of pile tips required on the test piles.

12.3 Construction Costs

12.3.1 Introduction

The construction costs itemized in Appendix 12-A-3, 12-A-4, 12-A-5, and 12-A-6 are to aid the user in estimating the cost of bridge and structure projects. The costs are based on historical data maintained by the Bridge and Structures Office and retrieved from recent WSDOT Contracts.

Requests for cost estimates from WSDOT Region offices and other Local Agency offices should be submitted in writing (hard copy or e-mail) to the Bridge Projects Unit, and a written or e-mail response will be returned within a reasonable time based on the schedule needs of the requesting office. Scoping or prospectus type cost estimates, and other cost estimates based upon deck area cost history and other readily available geotechnical information and project parameters can be prepared relatively quickly. Estimates requiring input from the Bridge Design Unit, either for preparation of preliminary quantities or other preliminary structural analysis will take longer to prepare.

Telephone requests for cost estimates from WSDOT Region offices and other Local Agency shall be referred to the Bridge Projects Unit for response.

All cost estimates prepared by the Bridge and Structures Office should have the concurrence of the Bridge Projects Engineer.

12.3.2 Factors Affecting Costs

12.3.2.1 Type of Structure

Many factors, as outlined in BDM Section 2.2.3, must be considered in the selection of the type, size, and location of a bridge or wall.

Common structures with conventional details will be within the low end and mid-range of costs. Unique or complex structures will be within the high end.

12.3.2.2 Location of Project Site

Projects in remote areas or with difficult access will generally be within or above the high end of the cost range.

12.3.2.3 Size of Project Contract

Small projects tend to be within the high end of the cost range while large projects tend to be within the low end of the cost range.

12.3.2.4 Foundation Requirements

Foundation requirements greatly affect costs. Water crossings requiring pier construction within the waterway are generally very expensive. Scour requirements can push the costs even higher. The earlier foundation information can be made available the more accurate the cost estimate will be. The Bridge Projects Unit should be made aware of unusual foundation requirements or changes to foundation type as soon as possible for updating of the estimate.

12.3.2.5 Sequencing of Project

Projects with stage construction, detours, temporary construction, etc., will be more expensive.

12.3.3 Development of Cost Estimates

Estimates prepared by the Bridge and Structures Office shall include 10 percent mobilization but not sales tax, engineering, construction contingencies, or inflation.

12.3.3.1 Types

A. Prospectus and Project Summary Estimates

Conceptual cost estimates are prepared when little information about the project is available. Use the construction costs in Appendix A, assuming the worst case conditions, unless actual conditions are known. An example of a worst case condition is deep foundation substructure (pile supported footings or shaft foundations). In remote areas, or for small projects, use the high end of the cost range. Use mid-range costs for usual conditions.

To cover unforeseen project modifications, add a 20 percent estimate contingency to a prospectus estimate and a 10 percent estimate contingency to a project summary estimate. These contingencies can be adjusted depending on the preliminary information available.

B. Preliminary Design Estimates

Preliminary design estimates are prepared during the preliminary design stage when the type and size of bridge is known. Limited foundation information is sometimes available at this stage. The construction costs in Appendix A shall be used with an appropriate inflation factor, assuming the worst case conditions, unless foundation conditions are known, along with a minimum of 10 percent contingency to cover scope creep.

C. Estimate Updates During Design

During the design period, the designer should keep the Bridge Projects Unit informed of significant changes to the design that might affect the cost. Examples of significant changes are: deeper than expected footing and seals, use of deep foundations (shafts or piles) when none were previously expected, change of substructure types, and changes to superstructure. This is a critical element in the project budgeting process.

D. Contract Estimates

The contract estimate is prepared by the Bridge Projects Unit after the Plans and Final Quantities have been submitted to the Bridge Projects Unit for preparation of the final Bridge PS&E. The contract estimate is prepared using the quantities furnished by the Bridge Design Unit, unit bid prices from Appendix A, other historical data, and the judgment of the engineer preparing the estimate. Unique, one-of-a-kind projects require special consideration and should include an appropriate construction cost contingency.

12.3.3.2 Responsibilities

A. Bridge Projects Unit

The Bridge Projects Unit is responsible for preparing the prospectus, project summary, preliminary, and final contract estimates and updating the preliminary estimate as needed during the design phase of the project.

The Bridge Projects Unit assists the WSDOT Region offices and other outside Local Agency offices, such as counties and cities, to prepare prospectus and project summary estimates when requested in writing.

B. Designer

The designer is responsible for providing preliminary quantities and final quantities to the Bridge Projects Unit to aid in the updating of preliminary estimates and the preparation of contract estimates.

12.3.3.3 Documentation

Whenever a cost estimate is prepared by the Bridge and Structures Office for an outside office, a Cost Estimate Summary sheet (Form 230-040 and Appendix 12-B-1) shall be filled out by the Engineer preparing the estimate. The Cost Estimate Summary shall be maintained in the Job File. During the design stage, the summary sheet shall be maintained by the Bridge Design Unit. At a minimum, the Cost Estimate Summary should list the initial and all subsequent cost estimates for each Preliminary Plan distribution made. It is the design unit supervisor's responsibility to ensure the summary sheet is up to date when the job file is submitted to the Bridge Projects Unit for preparation of the Bridge PS&E.

12.3.3.4 Cost Data

A. General

The Bridge costs summarized in Appendix A represent common highway, railroad, and water crossings. Consult the Bridge Projects Unit for structures spanning across large rivers or canyons and other structures requiring high clearances or special design and construction features.

The square foot costs are useful in the conceptual and preliminary design stages when details or quantities are not available. The various factors affecting costs as outlined in BDM Section 12.3.2 must be considered in selecting the square foot cost for a particular project. As a general rule, projects including none or few of the high-cost factors will be close to the mid-range of the cost figures. Projects including many of the high-cost factors will be on the high side. The user must exercise good judgment to determine reasonable costs. During the preliminary stage, it is better to be on the prudently conservative side for budgeting purposes.

B. Deck or Wall Face Area

The area to be used for cost estimates based upon deck or wall face area shall be computed as follows:

Bridge Widenings and New Bridges

The deck area of bridges is based on the actual width of the new portion of the roadway slab constructed (measured to the outside edge of the roadway slab) times the length, measured from end of wingwall to end of wingwall, end of curtain wall to end of curtain wall, or back to back of pavement seat if there are no wingwalls or curtain

walls. Wingwalls are defined as walls without footings which are cast monolithically with the bridge abutment wall and may extend past the abutment footing. Curtain walls are defined as walls that are cast monolithically with the bridge abutment wall and footing and only extend to the edge of footing.

Bridge Rail Replacement

The bridge rail and curb removal is based on the total length of the rail and curb removed.

Bridge Lengths With Unequal Wingwalls

If a bridge has wingwalls or curtain walls of unequal length on opposite sides at a bridge end of wingwalls or curtain walls on one side of a pier only, the length used in computing the square foot area is the average length of the walls. If the wingwalls are not parallel to the centerline of the bridge, the measurement is taken from a projected line from the end of the wingwall normal to the centerline of the roadway.

Retaining Walls

If retaining walls (walls that are not monolithic with the abutment) extend from the end of the bridge, the cost of these walls is computed separately. The area of the wall is based on the overall length of the wall, and the height from the top of footing to the top of the wall.

12.4 Construction Specifications and Estimates

12.4.1 General

The Bridge Projects Unit prepares the specifications and estimates (S&E) for all structural projects designed or reviewed by the Bridge and Structures Office. The preparation includes distributing review sets, reviewing the job file, plans, PS&E check list, "Not Included in Bridge Quantities List," and Geotechnical report; preparing the cost estimates, specifications, and working day schedules; and submitting the PS&E package to the Region.

12.4.2 Definitions

A. Standard Specifications

The Standard Specifications for Road, Bridge and Municipal Construction is published biannually by the WSDOT Engineering Publications Office, is maintained by the WSDOT Construction Office, and is used as the governing construction specification for all WSDOT construction projects.

B. Amendments

Amendments are revisions to specific sections of the Standard Specifications, which are approved and enacted during the two year period that a specific edition of the Standard Specifications is in force. Amendments are published normally three times during a calendar year – April, August, and December.

C. Special Provisions

Special Provisions are supplemental specifications and modifications to the Standard Specifications, including Amendments, which apply to a specific project.

D. Addendum

A written or graphic document, issued to all bidders and identified as an addendum prior to bid opening, which modifies or supplements the bid documents and becomes a part of the contract.

E. AD Copy

The AD copy is the contract document advertised to prospective bidders. The AD Copy may include, but not be limited to, the following as component parts: Bid Proposal Form, Special Provisions, Amendments, Plans, and Appendicies including test hole boring logs, and environmental permit conditions.

F. As defined in Standard Specification Section 1-02.4, the order of precedence of AD Copy components is as follows: Addenda, Bid Proposal Form, Special Provisions, Plans, Amendments, Standard Specifications, and Standard Plans.

12.4.3 General Bridge S&E Process

A. Typical Reviews and Milestone Dates

The Ad Date, as established by the Region, is the anchor for all project schedule dates.

The Bridge PS&E turn-in date is the date the Bridge PS&E package is due to the Region, and serves to note the beginning of the PS&E review period. Typically, the Bridge PS&E turn-in date is ten weeks prior to the scheduled Ad Date. When a longer PS&E review period is desired by the Region, the Bridge PS&E turn-in date can be as much as 12 to 14 weeks prior to the scheduled Ad Date.

The Bridge Plans turn-in date is the date the Bridge Plans are due to the Bridge Projects Unit from the Bridge Design Unit or Bridge Consultant assigned to the project, and serves to note the beginning of the Bridge S&E preparation period. Typically, the Bridge Plans turn-in date is four weeks prior to the scheduled Bridge PS&E turn-in date.

For some projects, the Region may schedule Constructability Reviews at times prior to the scheduled Bridge Plans turn-in date. These Constructability Reviews typically include plan sheets as developed to date, and in some cases may include draft Special Provisions. For most of the few projects with Constructability Reviews, the coordination of submittals and reviews will be through the specific Bridge Design Unit involved. However, if the Constructability Review requires Special Provisions, the Bridge Projects Unit should be included in the process.

For hydraulic, mechanical, and electrical rehabilitation projects for movable bridges, the Bridge Preservation Office takes a lead role in managing the design process for the project. These projects will typically include additional review periods similar to those described above for Constructability Reviews.

B. Bridge Plans Distribution

Once the Bridge Projects Unit receives the Bridge Plans from the Bridge Design Unit or Bridge Consultant assigned to the project, the Bridge Scheduling Engineer will assign the project to a specific Bridge Specifications and Estimates Engineer, and will create a Bridge PS&E file for the project.

The Bridge Specifications and Estimates Engineer will distribute the Bridge Plans, along with a Not Included in Bridge Quantities List, under a cover letter addressed to the Region Design Project Engineer (Olympic and Northwest Regions) or Region Project Development Engineer (all other Regions). The distribution list also includes the FHWA Washington Division Bridge Engineer, WSDOT Bridge Construction Engineer, and the Region Project Development and Region Plans Engineer (except for Olympic Region).

For new bridges and bridge widenings, internal Bridge and Structures Office distribution includes the Bridge Design Engineer, Bridge Projects Engineer, and the Bridge Design Unit Supervisor. The Bridge Plans may be distributed to other offices such as the Materials Laboratory Geotechnical Services Branch and the Bridge Preservation Office depending on the scope of the project and the value of the added review.

The Bridge Plan distribution will specify a due date for the return of review comments to the Bridge Specifications and Estimates Engineer. This date is typically one week prior to the scheduled Bridge PS&E turn-in date, but can be modified to suit project specific schedule considerations.

C. Bridge PS&E Development

Following the distribution of the Bridge Plans, the Bridge Specifications and Estimates Engineer will review the Bridge Plans, develop the Bridge Special Provisions and Bridge Cost Estimate, and prepare the bridge working day schedule. See BDM Sections 12.4.4, 12.4.5, 12.4.6, and 12.4.7.

D. Bridge PS&E Distribution

At the completion of the Bridge PS&E package, or at the scheduled Bridge PS&E turn-in date, whichever comes first, the Bridge Specifications and Estimates Engineer will distribute the Bridge PS&E. The Bridge PS&E package should include the items specified in BDM Section 12.4.9 A, and should be distributed to those identified in BDM Section 12.4.9 B.

12.4.4 Reviewing Bridge Plans

The Bridge Specifications and Estimates Engineer performs the following tasks after receiving the Bridge Plans submittal:

A. Job File

Review correspondence and e-mails in the job file for the items of work and other commitments which need to be included in the Bridge PS&E. Identify items that need special provisions and bid item references. Identify items that require additional research by, and information from, the bridge designer, Region designers, or others. Confirm that the job file fly leaf information has been completed by the designer (Form 221-076).

B. PS&E Check List (Form 230-037)

Review the form as completed by the bridge designer for identified needs for special materials, construction requirements, permits, etc., which may need Special Provisions such as:

- Permits: United States Coast Guard
- Agreements: utilities on bridge, etc.
- Materials: high strength structural steel, high-strength concrete, polyester and polymer concrete, carbon fiber wrap, high-load elastomeric bearing pads and other high capacity bridge bearings, etc.
- Construction Requirements: temporary access, stage construction, construction over railroad, special welding and welding inspection requirements, and other special construction requirements
- Special Items: modified concrete overlay or special architectural, paint, and sealer treatments

- Proprietary Materials: identification of, and justification for use of, products and materials which are specified in the Bridge Plans by specific manufacturer and model, instead of generic manufacture

C. Summary of Quantities (Form 230-031 and Appendix 12-A-2)

Verify that the Summary of Quantities is labeled as "Supervisor's Bridge Quantities." See BDM Section 12.2.2. Quantities listed in this form are used to develop the Bridge Cost Estimate for the project.

D. Plans

Review the plans for consistency with the special needs identified by the bridge designer in the PS&E check list form (subsection B above), use of standard notes and General Notes, completeness of title block information, and use of terminology consistent with the Standard Specifications, Standard Plans, and Standard Bid Items.

E. Not Included in Bridge Quantities List (Form 230-038 and Figure 12-A-1)

Review the form completed by the bridge designer and compare with the Bridge Plans for items shownin the Bridge Plans that may be missing from the list. See BDM Section 12.1.2.

F. Geotechnical Report

Review the Geotechnical Report for the project to confirm that the foundation types, sizes, and elevations shown in the Bridge Plans are consistent with the recommendations specified in the Geotechnical Report. Obtain a copy of the final Geotechnical Report for the S&E file. Review the Geotechnical Report for construction consideration requirements which may need to be noted in the Special Provisions, such as shaft casing requirements, bridge embankment settlement periods, special excavation, etc. Compare the number of test holes and the locations shown in the layout sheets for all bridges against number and locations of test holes identified in the final Geotechnical Report.

12.4.5 Preparing the Bridge Cost Estimates

A. General

From the quantities shown in the Summary of Quantities form submitted with the Bridge Plans, the Bridge Specifications and Cost Estimates Engineer develops the Bridge Cost Estimate for the project. The Bridge Projects Unit uses a standard spreadsheet format for Cost Estimates. This spreadsheet includes the tabulation of all bridge bid items, a breakdown for each lump sum item, and square foot cost of the structure.

B. Procedure

Each quantity shown in the Summary of Quantities form is to be matched with an appropriate unit bid item or lump sum bid item. These can be Standard Bid Items from the Standard Bid Item Table, or project specific non-standard bid items.

Pricing for the bid items above can be based on the Construction Cost Estimating Aids listed in Appendix 12-A-3, 12-A-4, 12-A-5, and 12-A-6, bid tabulations from previous contracts, and the Unit Bid Analysis and Standard Item Table listing available through the WSDOT Contract Ad & Award Office web site. The Bridge Specifications and Estimates Engineer uses appropriate engineering judgment to make appropriate adjustments for inflation, site location, quantities involved, total of the work involved, etc.

All Standard Bid Items listed in the spreadsheet shall include the Standard Bid Item number assigned to that bid item. All non-standard bid items shall be identified by the appropriate pre-qualification code for the bid item work. The pre-qualification codes specified in the Standard Item Table should be reviewed to help establish the appropriate code for non-standard bid items. When in doubt, the general Bridge and Structures pre-qualification code of (B0) should be used.

All bridge cost estimates shall include mobilization, but do not include sales tax, engineering, contingencies or inflation.

12.4.6 Preparing the Bridge Specifications

A. General

There are three categories of Special Provisions:

1. General Special Provisions (GSP's) are supplemental specifications which are standardized and approved for Statewide use by the WSDOT Construction Office. The library of GSP's is maintained by the WSDOT Design Office. GSP's are formatted to supplement specific Standard Specification Sections. GSP's are identified by their publication and effective date in parenthesis immediately preceding the GSP text. GSP's are published normally three times during a calendar year – April, August, and December.

2. Bridge Special Provisions (BSP's) are supplemental specifications which are standardized and approved for Statewide use by the WSDOT Bridge and Structures Office. The library of BSP's is maintained by WSDOT Bridge and Structures Office through the WSDOT Design Office. BSP's are formatted to supplement specific Standard Specification Sections. BSP's are identified by the acronym "BSP" followed by their publication and effective date in parenthesis immediately preceding the BSP text. BSP's are published periodically throughout the year.

3. Project Specific Special Provisions include all supplemental specifications which are not GSP's nor BSP's. Project Specific Special Provisions, as the name implies, are intended for project specific use, whether one time or infrequent. The vast majority of Project Specific Special Provisions are formatted to supplement specific Standard Specification Sections. However, in rare cases, they can be formatted as "stand-alone" following the "**Description** / **Materials** / **Construction Requirements** / **Measurement** / **Payment** format. Project Specific Special Provisions are identified by six asterisks in parenthesis immediately preceding the text or heading. A Project Specific Special Provision that sees frequent use can be standardized and elevated to BSP or GSP status.

B. Procedure

Based on review of the Bridge Plans and the PS&E Check List, the Bridge Specifications and Estimates Engineer determines the items of work which are not already covered by the Standard Specifications and for which supplemental specifications are needed. Based on this determination, and review of the current list of Amendments, GSP's, and BSP's, a Bridge Special Provision runlist is prepared, listing the code numbers of the applicable Amendment, GSP, and BSP documents needed for the project. Current Amendment, GSP, and BSP documents are listed in the WSDOT Design Office Project Development web site.

These documents are listed following the Section order of the Standard Specifications, Amendments first, followed by the Special Provisions. Fill-in blanks for BSP's and GSP's requiring project specific information can be completed at this time.

When the Standard Specifications, Amendments, GSP's and BSP's are insufficient to cover project specific requirements, Project Specific Special Provisions are developed, and added by name at the appropriate location in the runlist.

See Division 6 of the WSDOT Plans Preparation Manual for further discussion and example flow charts.

When the Bridge Special Provision file is complete with all Special Provisions needed to accompany the Bridge Plans, the Bridge Specifications and Estimates Engineer requests a single space document of the Bridge Special Provision file for use in the Bridge PS&E distribution.

12.4.7 Preparing the Bridge Working Day Schedule

A. General

The Bridge Specifications and Estimates Engineer calculates the number of the working days necessary to construct the bridge portion of the contract, based on the quantities shown in the Summary of Quantities form submitted with the Bridge Plans, and enters the time in the special provision "Time for Completion." The working days are defined in the Section 1-08.5 of the Standard Specifications.

B. Procedure

The first task of estimating the number of working days is to list all the construction activities involved in the project. These include all actual construction activities such as excavation, forming, concrete placement, and curing; and the nonconstruction activities such as mobilization, material and shop plan approval. Special conditions such as staging, limited access near wetlands, limited construction windows for work in rivers and streams, limited working hours due to traffic and noise restrictions, require additional time.

The second task is to assign the number of working days to each construction activity above (see Figure 12-B-2). The "Construction Time Rate" table can be used as a guide to estimate construction time required. This table shows the average rate of output for a single shift, work day only. Adjustment to the rates of this table should be made based on project size, type of work involved, location of the project, etc. In general, larger project will have higher production rates than smaller projects, new construction will have higher production rates than widening, and unstaged work will have higher production rates than stages work.

The last step is to arrange construction activities, with corresponding working days, into a construction schedule on a bar chart, either by hand on the Construction Working Day Schedule Form 230-041 (see Appendix 12-B-2) or by computer using a scheduling program. List the activities in a logical construction sequence, starting from the substructure to the superstructure. Items shall overlap where practical and the critical path shall be identified.

12.4.8 Reviewing Projects Prepared by Consultants

A. General

Consultants preparing Bridge Plans are required to submit their 90 percent complete design package to the Bridge and Structures Office on or before the scheduled Bridge Plan turn-in date, and with all associated information (files, forms, lists, and reports), as specified in BDM Sections 12.4.3 and 12.4.4.

The package shall be in the same format as those prepared by the Bridge and Structures Office.

B. Procedure

The Bridge Specifications and Estimates Engineer reviews the consultant's Bridge Plans following the process as specified in BDM Sections 12.4.3 and 12.4.4. The review comments of the Bridge Specifications and Estimates Engineer should be combined with review comments from the Bridge Design Unit assigned to review the project, and returned to the consultant in a timely manner through the Bridge Consultant Liaison Engineer, allowing the consultant to meet the scheduled turn-in date for the Bridge PS&E. After the consultant addresses all review comments and resubmits the package as 100 percent complete, the Bridge Specifications and Estimates Engineer compiles the Bridge PS&E package (See BDM Section 12.4.9).

Except for hydraulic, mechanical, and electrical rehabilitation projects for movable bridges, and other unique bridge projects where specifically approved by the Bridge Projects Engineer, all Bridge Special Provisions shall be prepared by the Bridge Projects Unit. The Bridge Cost Estimate and working day schedule should be prepared by the Bridge Specifications and Estimates Engineer with assistance from the consultant as appropriate.

12.4.9 Submitting the PS&E Package

A. General

The PS&E package includes:

1. Cover transmittal memo to the Bridge Design Engineer (for new bridges and bridge widenings only)
2. Cover letter to the Region.
3. Bridge Construction Cost Estimate for each separate structure
4. Cost Estimate Summary for each separate structure (see Appendix 12-B-1)
5. Not Included in Bridge Quantity List
6. Construction Working Day Schedule
7. Single space document of Bridge Special Provision file with runlist
8. Log of Test Borings
9. One Plan Set (11" by 17")

B. Procedure

The cover memorandum should be addressed to either the Region Plans Engineer (all Regions except for Olympic Region) or the Region Design Project Engineer (Olympic Region only). Others that should be included as cc's in the distribution are as follows:

1. FHWA Washington Division Bridge Engineer.
2. Region Design Project Engineer (except for Olympic Region – already addressed above).
3. Region Construction Project Engineer (if known and if different from the Region Design Project Engineer).
4. Northwest Region Area Engineering Manager (Northwest Region only).
5. Region Project Development Engineer (Eastern, North Central, South Central, and Southwest Regions only).
5. Bridge Construction Engineer.

6. Materials Laboratory.
7. Bridge Preservation Office.
8. Bridge Management Engineer (for all Bridge Replacement, Seismic Retrofit, and Bridge Repair projects).
9. All Bridge Design Unit Supervisors whose units contributed Bridge Plans to the project.
10. All bridge consultants who contributed Bridge Plans to the project.
11. Bridge Consultant Liaison Engineer (when bridge consultants contribute Bridge Plans to the project).

Modifications to the distribution list should be made by the Bridge Specifications and Estimates Engineer based on Region involved, and project specific requirements.

12.4.10 PS&E Review Period and Turn-in for AD Copy

A. Description

The PS&E Review Period between Bridge PS&E turn-in and Ad Date is used to allow the Region to compile PS&E from their Design PE Office and all support groups into a Review PS&E set that can be distributed to all interested parties for review and comment. The process ensures that all parts of the PS&E are compatible, complete, and constructable.

B. Procedure

Each Region has its own specific process, but the general procedure is similar. The Bridge and Structures Office review set is addressed to the Bridge Projects Engineer. This occurs shortly after the Bridge PS&E turn-in date. Upon receipt in the Bridge and Structures Office, the Review PS&E set is delivered to the Bridge Specifications and Estimates Engineer assigned to the project. The review is to be performed, and comments returned to the Region, by the due date specified in the distribution letter. Review comments should be returned to both the Region Plan Reviewer and the Region Design PE contact assigned to the project, as identified in the distribution letter.

Depending on the scope of the project, and the Region responsible for the project, there may be a meeting to discuss review comments. If such a meeting is held (generally about halfway through the PS&E review period), the Bridge Specifications and Estimates Engineer and others from the Bridge Design Unit responsible for the project, should consider attending if discussion of Bridge PS&E review comments is likely.

Shortly after the specified due date for review comments passes, Region comments on the Bridge PS&E should be received by the Bridge Specifications and Estimates Engineer and/or the bridge designer(s) in the Bridge Design Unit. These review comments on the Bridge PS&E should be addressed before the final Bridge PS&E is turned-in for AD Copy printing. The Bridge Specifications and Estimates Engineer makes all necessary revisions to the Bridge Cost Estimate and Bridge Special Provisions, and notifies the appropriate contacts in the Region Design PE Office and the Region Plans Office when these changes are complete. This should be completed at least two weeks prior to the scheduled Ad Date.

After the Bridge Design Unit has completed all necessary revisions to the Bridge Plans, the Bridge Plans are signed and dated in blue ink by the appropriate engineers, and the signed originals turned in to the Bridge Specifications Engineer. Copies of these signed plans are sent to the Region for use in the AD Copy PS&E. This should be completed one to two weeks prior to the scheduled Ad Date. The original signed plans are forwarded to the Bridge Plans Engineer in the Bridge Projects Unit.

Washington State
Department of Transportation
Environmental And Engineering Service Center
Bridge and Structures Office

Not Included In Bridge Quantities List

SR	Job Number	Project Title	
Designed By	Checked By	Date	Supervisor
Type of Structure			

The following is a list of items for which the Bridge and Structures Office is relying on the Region to furnish plans, specifications and estimates.

1.
2.
3.
4.
5.
6.
7.
8.
9.
10.
11.
12.
13.
14.
15.
16.
17.

DOT Form 230-038 EF
Revised 2/97

Not Included In Bridge Quantities List
Figure 12-A-1

Washington State Department of Transportation
Bridge and Structures

Bridge Quantities

✓ **Indicate Unit of Measure:** ☐ **English** ☐ **Metric**

St. Item No.	Item Use	Item Description	Quantity	Unit of Measure
0001(E) 0001(M)	Std. Item	Mobilization	_____	L.S.
0061 0061	GSP Item	Removing Portion of Existing Bridge Type _____ Area _____ SF/SM	_____	L.S.

Drilled Holes: *Less than 12"/305 mm long:* *Greater than 12"/305 mm long:*

Number	Diameter	Number	Diameter	Length
_____	_____ Inch/mm	_____	_____ Inch/mm	_____ LF/M
_____	_____ Inch/mm	_____	_____ Inch/mm	_____ LF/M
_____	_____ Inch/mm	_____	_____ Inch/mm	_____ LF/M

Core Drilled Holes: *Less than 12"/305 mm long:* *Greater than 12"/305 mm long:*

Number	Diameter	Number	Diameter	Length
_____	_____ Inch/mm	_____	_____ Inch/mm	_____ LF/M
_____	_____ Inch/mm	_____	_____ Inch/mm	_____ LF/M
_____	_____ Inch/mm	_____	_____ Inch/mm	_____ LF/M

0071 0071	GSP Item	Removing Existing Bridge Type _____ Area _____ SF/SM	_____	L.S.
	Sp. Prov.	Removing Temporary Structure Type _____ Area _____ SF/SM	_____	L.S.
4006/8331	Std. Item	Structure Excavation Class A Incl. Haul	_____	CY/M3

Unsuitable:

Pier	Soil
_____	_____ CY/M3
_____	_____ CY/M3
_____	_____ CY/M3
_____	_____ CY/M3

Cofferdam:

Pier	Soil	Rock
_____	_____ CY/M3	_____ CY/M3
_____	_____ CY/M3	_____ CY/M3
_____	_____ CY/M3	_____ CY/M3
_____	_____ CY/M3	_____ CY/M3

4010/8835	GSP Item	Special Excavation	_____	CY/M3

Pier	Soil
_____	_____ CY/M3
_____	_____ CY/M3
_____	_____ CY/M3
_____	_____ CY/M3

DOT Form 230-031 EF
Revised 6/2002

Bridge Quantities (Page 1 of 6)
Figure 12-A-2

St. Item No.	Item Use	Item Description	Quantity	Unit of Measure
4013/4013	Std. Item	Shoring or Extra Excavation Class A	_____	L.S.

Dry:

AVERAGE OVERALL HEIGHT

Pier	<6 ft./2 m	6 ft./2 m to 10 ft./3 m	10 ft./3 m to * 20 ft./6 m	>20 ft./6 m *
_____	_____ SF/SM	_____ SF/SM	_____ SF/SM	_____ SF/SM
_____	_____ SF/SM	_____ SF/SM	_____ SF/SM	_____ SF/SM
_____	_____ SF/SM	_____ SF/SM	_____ SF/SM	_____ SF/SM
_____	_____ SF/SM	_____ SF/SM	_____ SF/SM	_____ SF/SM

Cofferdam:

AVERAGE OVERALL HEIGHT

Pier	<6 ft./2 m	6 ft./2 m to 10 ft./3 m	10 ft./3 m to * 20 ft./6 m	>20 ft./6 m *
_____	_____ SF/SM	_____ SF/SM	_____ SF/SM	_____ SF/SM
_____	_____ SF/SM	_____ SF/SM	_____ SF/SM	_____ SF/SM
_____	_____ SF/SM	_____ SF/SM	_____ SF/SM	_____ SF/SM
_____	_____ SF/SM	_____ SF/SM	_____ SF/SM	_____ SF/SM

*INDICATE AVERAGE HEIGHT

4030	GSP Item	Rock Bolt	_____	Each
--	Sp. Prov.	Soil Excavation For Shaft Including Haul	_____	CY/M3
--	Sp. Prov.	Rock Excavation For Shaft Including Haul	_____	CY/M3
--	Sp. Prov.	Furnishing and Placing Temp. Casing For _____ Diam. Shaft	_____	LF/M
--	Sp. Prov.	Furnishing Permanent Casing For _____ Diam. Shaft	_____	LF/M
--	Sp. Prov.	Placing Permanent Casing For _____ Diam. Shaft	_____	Each
--	Sp. Prov.	Casing Shoring	_____	LF/M
--	Sp. Prov.	Shoring or Extra Excavation Cl. A	_____	L.S.
--	Sp. Prov.	CSL Access Tube	_____	LF/M
4151/8426	Std. Item	St. Reinf. Bar For Shaft	_____	LB/KG
--	Sp. Prov.	Conc. Class 4000P For Shaft	_____	CY/M3
--	Sp. Prov.	Removing Obstructions	_____	Est.
--	GSP Item	Excavation For Piling	_____	LF/M
4055/8355	Std. Item	Preboring For Pile	_____	LF/M
4060/4060	Std. Item	Furnishing and Driving Concrete Test Pile	_____	Each
4070/8363	Std. Item	Furnishing Concrete Piling - _____ Diameter	_____	LF/M
4080/4080	Std. Item	Driving Concrete Pile - _____ Diameter	_____	Each
4085/4085	Std. Item	Furnishing and Driving Steel Test Pile	_____	Each
4090/8373	Std. Item	Furnishing Steel Piling	_____	LF/M
4095/4095	Std. Item	Driving Steel Pile	_____	Each
4100/4100	Std. Item	Furnishing and Driving Timber Test Pile	_____	Each
4105/8381	Std. Item	Furnishing Timber Piling - Untreated	_____	LF/M
4106/8383	Std. Item	Furnishing Timber Piling - Creosote Treated	_____	LF/M
4108/4108	Std. Item	Driving Timber Pile - Untreated	_____	Each
4110/4110	Std. Item	Driving Timber Pile - Creosote Treated	_____	Each
4116/4116	Std. Item	Pile Splice - Timber	_____	Each
--	Sp. Prov.	Pile Tip	_____	Each

DOT Form 230-031 EF
Revised 6/2002

Bridge Quantities (Continued Page 2 of 6)

Figure 12-A-2

St. Item No.	Item Use	Item Description	Quantity	Unit of Measure
4120/8393	Std. Item	Furnishing Prestressed Hollow Concrete Piling _____	_____	LF/M
4130/4130	Std. Item	Placing Prestressed Hollow Concrete Pile _____	_____	Each
4140/4140	Std. Item	Driving Prestressed Hollow Concrete Pile _____	_____	Each
4145/4145	Sp. Prov.	Pile Loading Test	_____	LF/M
		No. of Tests _____ Each Pile Size _____ Ton/Tonne		
4147/8410	Std. Item	Epoxy-Coated St. Reinf. Bar For _____	_____	LB/KG
4147/8410	Std. Item	Epoxy-Coated St. Reinf. Bar For Traffic Barrier	_____	LB/KG
4148/8412	Std. Item	Epoxy-Coated St. Reinf. Bar For Bridge	_____	LB/KG
4149/8420	Std. Item	St. Reinf. Bar For Bridge	_____	LB/KG
4151/8426	Std. Item	St. Reinf. Bar For Traffic Barrier	_____	LB/KG
4151/8426	Std. Item	St. Reinf. Bar For _____	_____	LB/KG
4165/8428	Std. Item	Wire Mesh _____	_____	SY/SM
4166/8430	Std. Item	Lean Concrete _____	_____	CY/M3
--	GSP Item	Conc. Class _____	_____	CY/M3
4322/8452	Std. Item	Conc. Class 4000/28 for Bridge	_____	CY/M3
4202/8442	Std. Item	Conc. Class 4000/28 for Traffic Barrier	_____	CY/M3
4202/8442	Std. Item	Conc. Class 4000/28 for _____	_____	CY/M3
4320/8441	Std. Item	Conc. Class 3000/20 for Bridge	_____	CY/M3
4200/8440	Std. Item	Conc. Class 3000/20 for _____	_____	CY/M3
4325/8477	Std. Item	Conc. Class 5000/35 for Bridge	_____	CY/M3
4205/8475	Std. Item	Conc. Class 5000/35 for _____	_____	CY/M3
4324/8468	Std. Item	Conc. Class 4000W/28W for Bridge	_____	CY/M3
4204/8466	Std. Item	Conc. Class 4000W/28W for _____	_____	CY/M3
4183/4183	GSP Item	Conc. Class EA	_____	CY/M3
4185/4185	GSP Item	Conc. Class HE	_____	CY/M3
--	Std. Item	Conc. Class _____ LS	_____	CY/M3
4184/4184	GSP Item	Cylinder Concrete	_____	CY/M3
4188/4188	GSP Item	Fractured Fin Finish	_____	SY/SM
4230/4230	Std. Item	Structural Carbon Steel	_____	LB/KG
4235/4235	Std. Item	Structural Low Alloy Steel	_____	LB/KG
4240/4240	Std. Item	Structural High Strength Steel	_____	LB/KG
4246/4536	Std. Item	Cast Steel	_____	LB/KG
4251/8540	Std. Item	Forged Steel	_____	LB/KG
4256/8546	Std. Item	Cast Iron	_____	LB/KG
4261/8549	Std. Item	Malleable Iron	_____	LB/KG
4267/8552	Std. Item	Ductile Iron	_____	LB/KG
4271/8555	Std. Item	Cast Bronze	_____	LB/KG

DOT Form 230-031 EF
Revised 6/2002

Bridge Quantities (Continued Page 3 of 6)
Figure 12-A-2

St. Item No.	Item Use	Item Description	Quantity	Unit of Measure
4280/8560	Std. Item	Timber and Lumber - Untreated	_____	MBM/M3
4282/8582	Std. Item	Timber and Lumber - Creosote Treated	_____	MBM/M3
4284/8584	Std. Item	Timber and Lumber - Salts Treated	_____	MBM/M3
4300/4300	Std. Item	Superstructure Bridge Plan Area _____ SF/SM	_____	LS
4311/4311	Std. Item	Roadway Deck Bridge Plan Area _____ SF/SM	_____	LF/M
4390/8595	GSP Item	Electrical Conduit Diameter _____ Inch Length _____ LF/M	_____	LF/M
4400/8600	GSP Item	Steel Handrail	_____	LF/M
4405	GSP Item	Bridge Rail - Low Fence Type	_____	LF/M
4406	GSP Item	Bridge Rail - High Fence Type	_____	LF/M
4410/8605	GSP Item	Bridge Railing Type _____	_____	LF/M
4420	GSP Item	Bridge Grate Inlet	_____	Each
4453/4453	GSP Item	Pigmented Sealer	_____	SY/SM
7169/9572	Sp. Prov.	Structural Earth Wall	_____	SF/SM
--	Sp. Prov.	_____	_____	_____
--	Sp. Prov.	_____	_____	_____

DOT Form 230-031 EF
Revised 6/2002

Bridge Quantities (Continued Page 4 of 6)

Figure 12-A-2

Breakdown of Items for Superstructure or Roadway Deck

St. Item No.	Item Use	Item Description	Quantity	Unit of Measure
--	Std. Item	Epoxy-Coated Steel Reinforcing Bar	_____	LB/KG
--	Std. Item	Epoxy-Coated Steel Reinforcing Bar (Traffic Barrier)	_____	LB/KG
--	Std. Item	Steel Reinforcing Bar	_____	LB/KG
--	Std. Item	Steel Reinforcing Bar (Traffic Barrier)	_____	LB/KG
--	GSP Item	Conc. Class _____	_____	CY/M3
--	Std. Item	Conc. Class 4000D/28D	_____	CY/M3
--	Std. Item	Conc. Class 4000/28	_____	CY/M3
--	Std. Item	Conc. Class 4000/28 (Traffic Barrier)	_____	CY/M3
--	Std. Item	Conc. Class 5000/35	_____	CY/M3
--	Std. Item	Conc. Class _____ LS	_____	CY/M3
--	GSP Item	Fractured Fin Finish	_____	SY/SM
--	Std. Item	Structural Carbon Steel	_____	LB/KG
--	Std. Item	Structural Low Alloy Steel	_____	LB/KG
--	Std. Item	Structural High Strength Steel	_____	LB/KG
--	Std. Item	Cast Steel	_____	LB/KG
--	Std. Item	Forged Steel	_____	LB/KG
--	Std. Item	Cast Iron	_____	LB/KG
--	Std. Item	Malleable Iron	_____	LB/KG
--	Std. Item	Ductile Iron	_____	LB/KG
--	Std. Item	Cast Bronze	_____	LB/KG
--	Std. Item	Timber and Lumber - Untreated	_____	MBM/M3
--	Std. Item	Timber and Lumber - Creosote Treated	_____	MBM/M3
--	Std. Item	Timber and Lumber - Salts Treated	_____	MBM/M3
--	Sp. Prov.	Glulam Deck Panels	_____	MBM/M3
--	Std. Item	Electrical Conduit	_____	LF/M
		Diameter _____ Inch Length _____ LF/M		
--	GSP Item	Steel Handrail	_____	LF/M
--	GSP Item	Bridge Rail - Low Fence Type	_____	LF/M
--	GSP Item	Bridge Rail - High Fence Type	_____	LF/M
--	Std. Item	Bridge Railing Type _____	_____	LF/M
--	GSP Item	Traffic Barrier	_____	LF/M
4430/4430	GSP Item	Special Bridge Drain	_____	Each
4433/4433	Sp. Prov.	Modify Bridge Drain	_____	Each
4434/4434	Sp. Prov.	Plugging Existing Bridge Drain	_____	Each
4420/4420	GSP Item	Bridge Grate Inlet	_____	Each

DOT Form 230-031 EF
Revised 6/2002

Page 5 of 6

Bridge Quantities (Continued Page 5 of 6)
Figure 12-A-2

St. Item No.	Item Use	Item Description	Quantity	Unit of Measure
--	GSP Item	Expansion Joint System Type _____ Length _____ LF/M Type _____ Length _____ LF/M Type _____ Length _____ LF/M	_____	LF/M
4444/8634	Sp. Prov.	Expansion Joint Modification Type _____ Length _____ LF/M	_____	LF/M
4232/8515	Sp. Prov.	Modified Concrete Overlay	_____	CF/M3
4233/8516	Sp. Prov.	Finishing and Curing Modified Concrete Overlay		SY/SM
4456/8644	Sp. Prov.	Scarifying Concrete Surface	_____	SY/SM
	Sp. Prov.	Polymer Concrete Overlay	_____	SY/SM
	Sp. Prov.	Further Deck Preparation Volume _____ CF/CM Avg. Depth _____ Inch/mm	_____	L.S.
4445/4445	GSP Item	Bridge Deck Repair Volume _____ CF/CM Avg. Depth _____ Inch/mm	_____	L.S.
--	GSP Item	Pigment Sealer	_____	SY/SM
4455/8643	GSP Item	Membrane Waterproofing (Deck Seal)	_____	SY/SM
--	Sp. Prov.	Pot Bearing	_____	Each
--	Sp. Prov.	Disc Bearing	_____	Each
--	Sp. Prov.	Spherical Bearing	_____	Each
--	Sp. Prov.	Cylindrical Bearing	_____	Each
--	Std. Item	Elastomeric Bearing Pad	_____	Each
--	GSP Item	Fabric Pad Bearing	_____	Each
--	Std. Item	Prestressed Conc. Girder Series W42G/W42MG	_____	LF/M
--	Std. Item	Prestressed Conc. Girder Series W50G/W50MG	_____	LF/M
--	Std. Item	Prestressed Conc. Girder Series W58G/W58MG	_____	LF/M
--	Std. Item	Prestressed Conc. Girder Series W74G/W74MG	_____	LF/M
--	Std. Item	Prestressed Conc. Girder Series W83G/W83MG	_____	LF/M
--	Std. Item	Prestressed Conc. Girder Series W95G/W95MG	_____	LF/M
--	Std. Item	Prestressing	_____	LB/KG
--	Sp. Prov.	Precast Prestressed Slab Volume _____ CF/CM Length _____ LF/M	_____	SF/SM
--	Sp. Prov.	Precast Prestressed Tri Beam Volume _____ CF/CM Length _____ LF/M	_____	SF/SM
--	Sp. Prov.	Precast Prestressed Double Tee Beam Volume _____ CF/CM Length _____ LF/M	_____	SF/SM
--	Sp. Prov.	Precast Segment Volume _____ CY/CM	_____	LF/M
--	Sp. Prov.	_____	_____	_____
--	Sp. Prov.	_____	_____	_____

DOT Form 230-031 EF
Revised 6/2002

Bridge Quantities (Continued Page 6 of 6)

Figure 12-A-2

Before using these structure unit costs for any official WSDOT project cost estimate, contact the Bridge and Structures Office at (360) 705-7201 to discuss the specific project criteria and constructability related risks, so an appropriate structures construction cost can be provided.

(Note: Unit struture costs include mobilization but do not include sales tax, engineering, or contingency)

		LOW	AVERAGE	HIGH ΔΔ
PRESTRESSED CONCRETE GIRDERS SPAN 50-175 FT.				
Water Crossing w/piling	SF	$100.00	$125.00	$150.00
Water Crossing w/spread footings	SF	85.00	100.00	120.00
Dry Crossing w/piling	SF	90.00	110.00	135.00
Dry Crossing w/spread footings	SF	70.00	80.00	100.00
REINFORCED CONCRETE AND POST-TENSIONED CONCRETE BOX GIRDER-SPAN 50-200 FT.				
Water Crossing w/piling	SF	100.00	120.00	150.00
Water Crossing w/spread footings	SF	90.00	110.00	135.00
Dry Crossing w/piling	SF	95.00	115.00	140.00
Dry Crossing w/spread footings	SF	80.00	105.00	130.00
REINFORCED CONCRETE FLAT SLAB SPAN 20-60 FT.	SF	60.00	80.00	100.00
PRESTRESSED CONCRETE SLABS SPAN 13-69 FT.	SF	70.00	85.00	110.00
PRESTRESSED CONCRETE DECKED BULB-TEE GIRDER SPAN 40-115 FT.	SF	95.00	105.00	130.00
STEEL GIRDER — SPAN 60-400 FT.	SF	110.00	135.00	200.00
STEEL TRUSS — SPAN 300-700 FT.			160.00*	
STEEL ARCH — SPAN 30-400 FT.			175.00*	
CONCRETE BRIDGE REMOVAL		10.00	25.00	40.00
WIDENING EXISTING CONCRETE BRIDGES (Including Removal)		140.00	160.00	250.00
RAILROAD UNDERCROSSING — SINGLE TRACK	LF	$8,000.00* (Steel Underdeck Girder) $9,000.00* (Steel Thru-Girder)		
RAILROAD UNDERCROSSING — DOUBLE TRACK	LF	$12,000.00*		
PEDESTRIAN BRIDGE — REINFORCED CONCRETE	SF	150.00	250.00	500.00
REINFORCED CONCRETE RIGID FRAME (TUNNEL)	SF		90.00*	
REPLACING EXISTING CURBS & BARRIER WITH NEW JERSEY BARRIER (INCLUDING REMOVAL)	LF	110.00	165.00	225.00
REINFORCED CONCRETE RETAINING WALL (EXPOSED AREA)	SF	40.00	60.00	75.00
SOLDIER PILE TIEBACK WALL (EXPOSED AREA)	SF	110.00	130.00	165.00

Bridge and Structures
Figure 12-A-3

		LOW	AVERAGE	HIGH ΔΔ
SE WALL PRECAST CONCRETE PANELS	SF	17	30	40
SE WALL WELDED WIRE	SF	15	23	28
SE WALL CIP CONCRETE FACE	SF	33	40	50
SOIL NAIL WALL	SF	50	60	80
CONCRETE FACING PERMANENT GEOSYNTHETIC WALL	SF	13	22	35
CONCRETE CRIB WALL CONCRETE HEADERS	SF	22	35	45

*Based on limited cost data. Check with the Bridge PS&E Engineer.

Bridge areas are computed as follows:

Typical Bridges: Width x Length

Width: Total width of deck, including portion under the barrier.

Length: Distance between back of pavement seats, or for a bridge having wingwalls, 3'-0" behind the top of the embankment slope; typically end of wingwall to end of wingwall, reference Standard Plans H9.

Special Cases:

Widenings — Actual area of new construction.

Tunnel — Outside dimension from top of footing to top of footing over the tunnel roof, i.e., including walls and top width.

ΔΔ For small jobs (less than $100,000), use the high end of the cost range as a starting point.

Bridge and Structures (Continued)
Figure 12-A-3

BID ITEMS	UNIT	COST/UNIT ΔΔ		
Structure Excavation Class A Incl. Haul				
Earth	CY	$ 12.00	—	30.00
Rock	CY	100.00	—	220.00
Inside Cofferdam — Earth	CY	22.00	—	33.00
— Rock	CY	110.00	—	190.00
Shoring Extra Excavation Class A				
Dry — Depth under 6′	SF	3.00	—	8.00
Dry — 6′ - 10′	SF	7.00	—	11.00
Dry — 10′ - 20′	SF	11.00	—	22.00
Cofferdam	SF	30.00	—	40.00
Preboring For Standard Piles	LF	35.00	—	60.00
Furnishing & Driving Test Piles				
Concrete	Each	5,000.00	—	10,000.00
Steel	Each	4,000.00	—	8,000.00
Timber	Each	2,000.00	—	3,000.00
Furnishing Piling				
Conc. _____ Diam.	LF	35.00	—	45.00
Steel — TYP HP 12x53	LF	30.00	—	35.00
Timber — Creosote Treated	LF	10.00	—	12.00
Timber — Untreated	LF	8.00	—	10.00
**Pile Tip				
CIP Concrete (Steel Casing — Short Tip)	Each	200.00	—	250.00
CIP Concrete (Steel Casing — 10 Stinger)	Each	4,500.00	—	5,500.00
Steel (H-Pile)	Each	120.00	—	220.00
Timber (Arrow Tip)	Each	25.00	—	45.00
Driving Piles (40′ - 70′ Lengths)				
Concrete _____ Diam.	Each	500.00	—	1,000.00
Steel	Each	350.00	—	800.00
Timber	Each	225.00	—	450.00
Shafts				
Soil Excavtion Class A For Shaft Including Haul	CY	200.00		450.00
Rock Excavation For Shaft Incl. Haul	CY	500.00		700.00
Furnishing & Placing Temp. Casing For Shaft	LF	125.00		350.00
Casing Shoring	LF	125.00		350.00
Furnishing Permanent Casing For Shaft	LF	150.00		600.00
Placing Permanent Casing For Shaft	Each	1,500.00		2,000.00
Shoring or Extra Excavation CL.A — Shaft	Est.	10,000.00		25,000.00
Conc. Class 4000P For Shaft	CY	175.00		250.00
St. Reinf. Bar For Shaft	Lbs.	.60		.80
CSL Access Tubes	LF	5.00		10.00
Remvoing Obstrucitons	Est.	10% of all of above shaft ____		
St. Reinf. Bar For Bridge	Lbs.	.60	—	.80
Epoxy-Coated St. Reinf. Bar For Bridge	Lbs.	.75	—	1.00
Conc. Class 4000W	CY	150.00	—	225.00
Conc. Class 4000P	CY	150.00	—	225.00
Conc. Class 4000 (Footings)	CY	325.00	—	450.00
Conc. Class 4000 (Abut. & Ret. Walls)	CY	380.00	—	500.00
Conc. Class 5000	CY	400.00	—	500.00
Lean Concrete	CY	130.00	—	150.00
Concrete Class 4000 P (CIP Piling)	CY	130.00	—	200.00

** Pile ultimate capacity will affect these prices. Check with Bridge PS&E Engineer if unsure.

Substructure

Figure 12-A-4

BID ITEMS	UNIT	COST/UNIT ΔΔ		
Elastomeric Bearing Pads				
Girder Seat	Each	$ 100.00	—	$ 150.00
Girder Stop	Each	60.00	—	80.00
Spherical and Disc, Bearings (In place with plates)	Kip	10.00	—	12.00
Fabric Pad Bearing (In place, including all plates, TFE, etc.)	Each	1,500.00	—	2,500.00
Prestressed Concrete Girder				
W42G (Series 6)	LF	120.00		
W50G (Series 8)	LF	130.00		
W58G (Series 10)	LF	140.00		
W74G (Series 14)	LF	160.00		
W83G	LF	230.00		
W95G	LF	250.00		
Structural Carbon Steel (Steel girder, etc. when large amount of steel is involved)	Lbs.	1.0	—	1.50
Structural Low Alloy Steel (Steel girder, etc. when large amount of steel is involved)	Lbs.	1.25	—	1.75
Structural Steel (Sign supports, etc. when small amounts of steel are involved)	Lbs.	4.00	—	6.00
Timber & Lumber	MBM	1,750.00	—	2,500.00
Creosote Treated	MBM	2,000.00	—	2,800.00
Salts Treated	MBM	1,200.00	—	1,700.00
Untreated	MBM	1,500.00	—	2,000.00
Lagging (in place) Untreated	MBM	2,000.00	—	2,800.00
Expansion Joint Modification	LF	350.00	—	450.00
Expansion Joint System				
Compression Seal	LF	40.00	—	60.00
Modular (Approx. $100 per inch of movement)	LF	850.00	—	3,000.00
Strip Seal	LF	140.00	—	275.00
Bridge Drains	Each	300.00	—	500.00
Bridge Grate Inlets	Each	1,200.00	—	1,500.00
Conc. Class 5000	CY	550.00	—	700.00
Con. Class 5000 (Segmental Constr.)	CY	700.00	—	800.00
Con. Class 4000D (Deck Only)	CY	550.00	—	650.00
Conc. Class 4000	CY	500.00	—	600.00
Concrete Class EA (Exposed Aggregate)	CY	350.00	—	500.00
Concrete Class 4000 LS (Low Shrinkage)	CY	300.00	—	400.00
Concrete Class 5000 LS	CY	400.00	—	500.00
St. Reinf. Bar	Lbs.	.60	—	.80
Epoxy-Coated Steel Reinforcing Bar	Lbs.	.75	—	1.00
Post-tensioning Prestressing Steel (Includes Anchorages)	Lbs.	2.50	—	4.00
Traffic Barrier	LF	65.00	—	85.00
Bridge Railing Type BP & BP-S	LF	40	—	65.00
Bridge Railing Type Thrie Beam	LF	45	—	70.00
Modified Conc. Overlay	C.F.	30.00	—	70.00
Furnishing and Curing Modified Conc. Overlay	SY	45.00	—	75.00
Scarifying Conc. Overlay	SY	10.00	—	15.00
Polymer Concrete	SY	50.00	—	110.00
Polyeste Concrete	C.F.	100.00	—	200.00

Superstructre

Figure 12-A-5

BID ITEMS	UNIT	COST/UNIT ΔΔ		
Electrical Conduit, metal 2	LF	$ 8.00	—	$ 15.00
Sign Support (Brackets, Mono, or Truss Sign Bridges)	Lbs.	2.50	—	5.00
Concrete Surface Finishes				
Fractured Fin Finish	SY	18.00	—	30.00
Exposed Aggregate Finish*	SY	18.00	—	25.00
Pigmented Sealer	SY	6.00	—	9.00
*Requires the use of concrete Class EA				
Painting Existing Steel Bridges (Lead Base)	Ton. (Steel)	550.00	—	750.00
Painting New Steel Bridges	Lbs. (Steel)	.09	—	.11
Mobilization				
Masonry Drilling Δ				
Holes up to 1 foot deep				
1" diameter	25.00			
1 ½"	27.00			
2"	30.00			
2 ½"	32.00			
3"	35.00			
3 ½"	45.00			
4"	50.00			
5"	55.00			
6"	65.00			
7"	85.00			

Δ For holes greater than 1-foot deep up to 20 feet deep, use 1.5 x above prices.
If drilling through steel reinforcing, add $16.00 per lineal inch of steel drilled.

Removal of Rails and Curbs	LF	$ 80.00	—	$ 130.00
Removal of Rails, Curbs, and Slab	SF	25.00	—	50.00
Further Deck Preparation	CF	100.00	—	150.00
Bridge Deck Repair	CF	110.00	—	160.00
Removing ACP from bridge deck	SY	7.00	—	12.00

Miscellaneous
Figure 12-A-6

Operation	UNIT**	Minimum Output	Maximum Output	Average Output
Substructure				
Structure Exc. & Shoring	C.Y./Day	20	150	80
*Seals	C.Y./Day	10	20	15
*Footings	C.Y./Day	6	14	10
*Abutment Walls	C.Y./Day	4	19	7
*Wingwalls	C.Y./Day	1	2	1.5
*Retaining Walls with Footings	C.Y./Day	4	17	11
*Columns	C.Y./Day	3	8	4
Falsework for X-beams	C.Y./Day	13	4	10
*X-beams	C.Y./Day	16	20	18
Driving Test Piles	Each/Day	1	2	1
Furnishing Piles				
Precast Concrete	Days	40	20	30
Cast-in-Place Concrete	Days	15	2	5
Steel	Days	30	2	10
Timber	Days	20	2	5
Driving Piles				
Concrete	L.F./Day	100	200	150
Steel	L.F./Day	100	200	150
Timber	L.F./Day	100	200	150
Superstructure				
Prestressed Girders				
Girder Fabrication	Days	70	35	45
Set Girders	L.F./Day	200	1,450	550
*Slab & Diaphragms	C.Y./Day	6	18	11
Box Girders				
Span Falsework	S.F./Day	150	900	700
*Bottom Slab	C.Y./Day	3	11	8
*Webs, Diaphragms, and X-beams	C.Y./Day	5	25	18
*Top Slab	C.Y./Day	7	12	9
Stress and Grout Strands	LBS/Day	4,500	8,000	6,000
Strip Falsework	S.F./Day	1,500	3,000	2,200
T-Beam				
Span Falsework	S.F./Day	500	1,000	700
*Girders, Diaphragms, and Slab	C.Y./Day	6	15	10
Strip Falsework	S.F./Day	1,000	2,000	1,500
Flat Slab				
Span Falsework	S.F./Day	100	600	250
*Slab and X-beams	C.Y./Day	6	15	10
Strip Falsework	S.F./Day	300	1,000	500
Steel Girder				
Girder Fabrication	Days	200	110	150
Girder Erection	L.F./Day	50	200	100
*Slab	C.Y./Day	6	15	10
Painting	S.F./Day	1,000	3,000	2,000
Miscellaneous				
*Traffic Barrier	L.F./Day	20	80	40
*Traffic Railing & Sidewalk	L.F./Day	15	60	35
*Concrete Overlay	S.Y./Day	200	300	250
Expansion Joint Replacement	Days/Lane Closure	4	6	8

* Concrete

** All times are based on 8-hour work days

Construction Time Rates

Figure 12-A-7

SR 162 7002 Carbon
River Bridge 162/14

Date of Transmittal	Estimate of Cost	Assume Accuracy %	Estimate Made By	Available Data								Copies Sent To			Remarks
				Field Data (Dated)	Date Layout Made	Foundation Date Rec.	Preliminary Quantities	Final Quantities	Estimate By Sq. Ft. Area	District	Design Branch	Program Development	
10-2-91	$517,000.00	±15%	DMJ	8-91			—		✓	3	✓	✓	Please See Cover Transmittal
1-9-92	$692,000.00	±10%	LHT					✓		✓	✓	✓	

Cost Estimate Summary

Figure 12-B-1

Construction Working Day Schedule
Figure 12-B-2

Chapter 13 Bridge Load Rating

13.1 General 13-1
13.1.1 WSDOT Rating (LRFR) 13-1
13.1.1.1 Strength Method (LRFR) 13-2
13.1.1.2 Service Method (LRFR) 13-2
13.1.1.3 Resistance Factors (LRFR) 13-4
13.1.1.4 Load Factors (LRFR) 13-4
13.1.1.5 Impact (LRFR) 13-4
13.1.1.6 Live Load Reduction Factors (LRFR) 13-4
13.1.1.7 Live Loads (LRFR) 13-5
13.1.1.8 Rating Trucks 13-5
13.1.2 NBI Rating (LFR) 13-7
13.1.2.1 Strength Method (LFR) 13-7
13.1.2.2 Service Method (LFR) 13-8
13.1.2.3 Resistance Factors (LFR) 13-8
13.1.2.4 Live Loads 13-8
13.1.2.5 Impact (LFR) 13-9
13.1.2.6 Live Load Reduction Factors (LFR) 13-9
13.2 Special Rating Criteria 13-10
13.2.1 Dead Loads 13-10
13.2.2 Live Load Distribution Factors 13-10
13.2.3 Reinforced Concrete Structures 13-10
13.2.4 Concrete Decks 13-10
13.2.5 Concrete Crossbeams 13-10
13.2.6 In-Span Hinges 13-10
13.2.7 Concrete Box Girder Structures 13-11
13.2.8 Prestressed Concrete Girder Structures 13-11
13.2.9 Concrete Slab Structures 13-11
13.2.10 Steel Structures 13-11
13.2.11 Steel Floor Systems 13-11
13.2.12 Steel Truss Structures 13-11
13.2.13 Timber Structures 13-11
13.2.14 Widened or Rehabilitated Structures 13-12
13.3 Load Rating Software 13-13
13.4 Load Rating Reports 13-14
13.5 Bibliography 13-15
Appendix 13-A
Figure 13-A-1 Bridge Rating Summary 13-A-1

13.1 General

Bridge Load Rating is a procedure to evaluate the adequacy of various structural components to carry predetermined live loads. The Bridge Load Rating Engineer in the WSDOT Bridge Preservation Office is responsible for the bridge inventory and load rating of existing and new bridges in accordance with the NBIS and the AASHTO Manual for Condition Evaluation of Bridges, latest edition. As presently required, only elements of the superstructure will be rated. Generally, the superstructure shall be defined as all structural elements above the column tops including drop crossbeams.

In order to provide a baseline rating for new bridges, load ratings are required for all new bridges, widened (one lane width or more throughout the length of the bridge), or rehabilitated bridges where the rehabilitation alters the load carrying capacity of the structure. The carrying capacity of a widened or rehabilitated structure shall equal or exceed the capacity of the existing structure.

The Bridge Design Section does not load rate new bridges during the design phase. However, copies of the computer models used in the design process shall be submitted to the Bridge Load Rating Engineer in the Bridge Preservation Section for the more complex structures where computer models were used in the design process.

The Bridge Preservation Office is responsible for maintaining an updated bridge load rating throughout the life of the bridge based on current bridge condition. Conditions of existing bridges change over time, resulting in the need for reevaluation of the load rating. Such changes may be caused by damage to structural elements, extensive maintenance or rehabilitative work, or any other deterioration identified by the Bridge Preservation Office through their regular inspection program.

This criteria applies only to concrete and steel bridges. For timber bridges, rating procedure shall be as per Chapters 6 and 7 of the 1994 AASHTO *Manual for Condition Evaluation of Bridges*.

Structural elements as defined above shall be evaluated for flexural, vertical shear, and torsional capacities based on Load Resistance Factor Design (LRFR) as outlined in the AASHTO 1989 *Guide Specifications for Strength Evaluation of Existing Steel and Concrete Bridges* and Load Factor Design (LFD) as outlined in the latest AASHTO *Manual for Condition Evaluation of Bridges*. Consider all reinforcing, including temperature/distribution reinforcement, in the rating analysis.

By definition, the adequacy or inadequacy of a structural element to carry a specified truck load will be indicated by the value of its rating factor (RF); that is, whether it is greater or smaller than 1.0. For a specific loading, the lowest RF value of the structural elements will be the overall rating of the bridge.

13.1.1 WSDOT Rating (LRFR)

Ratings shall be performed per the 1989 AASHTO *Guide Specifications for Strength Evaluation of Existing Steel and Concrete Bridges*. All bridges, except timber, shall be rated based on the Strength method.

13.1.1.1 Strength Method (LRFR)

The basic rating equations shall be:

$$R.F. = \frac{\Phi M_n - \gamma_{DL} M_{DL} \pm \gamma_P M_P}{\gamma_L M_{L(1+I)}}$$

$$R.F. = \frac{\Phi V_n - \gamma_{DL} V_{DL} \pm \gamma_P V_P}{\gamma_L V_{L(1+I)}}$$

When rating the full section of a bridge, like box girders, or crossbeams, which have two or more lanes, the following formulas apply for the overload trucks:

$$R.F. = \frac{\Phi M_n - \gamma_{DL} M_{DL} \pm \gamma_P M_P - \gamma_L M_{L(1+I)Legal\ Load}}{\gamma_L M_{L(1+I)}}$$

$$R.F. = \frac{\Phi V_n - \gamma_{DL} V_{DL} \pm \gamma_P V_P - \gamma_L V_{L(1+I)Legal\ Load}}{\gamma_L V_{L(1+I)}}$$

The formulas for the overloads assume that there is one overload truck in one lane, and legal trucks occupy the remaining lanes. Trucks shall be placed, in the lanes, in a manner that produces the maximum forces.

Where:

	R.F.	=	Rating Factor (Ratio of Capacity to Demand)
	M_n	=	Nominal Moment Strength of a Section
*	M_{DL}	=	Calculated Dead Load Bending Moment
	M_P	=	Secondary Bending Moment due to Prestressing
*	$M_{L(1+I)}$	=	Calculated Live Load, including Impact, Bending Moment
	Φ	=	Resistance Factor (Capacity Reduction Factor)
	γ_{DL}	=	Dead Load Factor.
	γ_L	=	Live Load Factor
	γ_P	=	Prestress Factor
	I	=	Impact
	V_n	=	Nominal Shear Strength
	V_{DL}	=	Calculated Dead Load Shear Force
	V_P	=	Calculated Prestressing Shear Force
	$V_{L(1+I)}$	=	Calculated Live Load, including Impact, Shear Force

*For continuous structures, a one-half support width moment increase is to be used.

13.1.1.2 Service Method (LRFR)

Prestressed and Post- tensioned Members

Prestressed and post-tensioned members in positive moment regions, and where post-tensioning is continuous over the supports, shall also be rated based on allowable stresses at service loads. The lowest rating factors between Service and Strength methods shall be the governing rating. The rating equations shall be:

Concrete Tension:

$$R.F. = \frac{F_A - (F_D + F_P + F_S)}{F_{L(1+I)}}$$

Concrete Compression:

$$R.F. = \frac{F_A - (F_D + F_P + F_S)}{F_{L(1+I)}}$$

$$R.F. = \frac{F_A - 1/2\,(F_D + F_P + F_S)}{F_{L(1+I)}}$$

Prestressing Steel:

$$R.F. = \frac{F_A - (F_D + F_P + F_S)}{F_{L(1+I)}}$$

R.F. = Rating Factor (Ratio of Capacity to Demand)

Allowable Concrete Tensile Stress:

F_A = $6\sqrt{f'_c}$

= $3\sqrt{f'_c}$ for severe corrosive exposure

= 0 for members without bonded reinforcement

Allowable Concrete compressive Stress:

F_A = $0.6\ f'_c$

= $0.4\ f'_c$ when checking live load plus one half of the dead and prestress compressive stresses.

Allowable Prestressing Tensile Stress

F_A = $0.80f^*_y$ (Allowable Prestressing Tensile Stress) where f^*_y is the yield stress of the prestressing.

F_D = Dead Load Stress

F_p = Stress due to Prestress Force after all losses

F_S = Stress due to Secondary Prestress forces

$F_{L(1+I)}$ = Stress due to Live Load including Impact

For all loadings, prestress losses shall be per design or current Bridge Design Manual.

For the overload trucks, the allowable stresses shall be increased by 15 percent.

When the bending moment rating for the overload vehicles is less than 1.0 based on the Service Method, and greater than 1.0 based on the Strength Method, the moment rating shall be calculated by dividing the strength rating factor by 1.30, and the result cannot exceed 1.0.

Timber Members

$$R.F. = \frac{F_A - F_D}{F_L}$$

R.F. = Rating Factor (Ratio of Capacity to Demand)

F_A = Allowable bending stress

F_D = Dead Load Stress

F_L = Stress due to Live Load, does not include Impact

F_A is per AASHTO Standard Specs. with an increase of 33%.

13.1.1.3 Resistance Factors (LRFR)

The resistance factors shall be per Table 3b or Figure 4 of the 1989 AASHTO *Guide Specifications for Strength Evaluation of Existing Steel and Concrete Bridges*. The resistance factors can be increased up to a maximum of 0.95, or decreased, depending on the condition, redundancy, type of inspection, and type of maintenance. For state owned bridges, assume careful inspection and vigorous maintenance and for local agency bridges, consult with the agency's Bridge Engineer.

Following are the NBI and BMS condition codes and their interpretation:

For NBI Codes > or = 6 (BMS States 1 and 2) — no deterioration
For NBI Codes = 5 (BMS State 3) — some deterioration
For NBI Codes < 5 (BMS State 4) — heavy deterioration

The BMS coding shall be used to identify the conditions of the elements being rated, and the appropriate resistance factors shall be applied.

When rating members that have section loss identified in the inspection report, the members should be modeled using the reduced section. Then, use the resistance factors for members in satisfactory condition.

13.1.1.4 Load Factors (LRFR)

Dead Load $\gamma D = 1.20$

Prestress Load $\gamma P = 1.00$

Live Load

1. Low volume roadways (ADTT less than 1,000), significant sources of over weight trucks without effective enforcement. $\gamma L = 1.65$
2. Heavy volume roadways (ADTT equal to or greater than 1,000), significant sources of over weight trucks without effective enforcement. $\gamma L = 1.80$
3. OL-1 and OL-2 (or other permit vehicles). $\gamma L = 1.30$

If ADTT is unavailable from traffic data, it may be estimated as 20 percent of ADT. The listed factors are essentially the same as Table 2 of AASHTO *Guide Specifications* except that Live Load Category 1 and 2 have been eliminated based on the assumption that Washington State does not have effective enforcement or control of overloads.

13.1.1.5 Impact (LRFR)

For new bridge designs, impact shall be 10 percent (0.1).

For existing bridges, the impact factor shall be determined by the approach roadway and the deck condition. For approach roadway condition codes 6 or greater, assume 10 percent impact; for codes less than 6, assume 20 percent impact. If the bridge deck condition is 6 or greater or has 0 to 4 percent scaling, assume 10 percent impact; if the deck condition is 5 or has between 5 and 15 percent scaling, assume 20 percent impact; if the deck condition is 4 or less and has greater than 15 percent scaling, assume 30 percent impact.

13.1.1.6 Live Load Reduction Factors (LRFR)

Number of Loaded Lanes	Reduction Factor
One or two lanes	1.0
Three lanes	0.8
Four lanes or more	0.7


13.1.1.7 Live Loads (LRFR)

The moving loads for the rating shall be the HS-20 truck/lane loading (Figure 13-1), three legal trucks/ lane load (Figure 13-2), and two overload trucks. (Figure 13-3). The legal lane load shall be used to rate structures with spans between 200 feet and 300 feet. For the two overload trucks (OL-1 and OL-2), use only one overload truck occupying one lane in combination with one of the AASHTO legal trucks in each of the remaining lanes, when modeling the full section of the bridge or cross-beams. The number of lanes used shall be the actual striped lanes at the time of rating.


The three legal trucks and legal lane load, Type 3, Type 3S2, and Type 3–3, are to be used to determine posting limits. The two overload vehicles represent extremes in the limits of permitted vehicles in Washington State.

13.1.1.8 Rating Trucks

Design Trucks



HS-20 Truck




HS-20 Lane Load


* In negative moment regions of continuous spans, place an equivalent load in the other span to produce the maximum effect.

Figure 13-1


Legal Trucks



Type 3 Truck



Type 3S2 Truck



Type 3-3 Truck





Figure 13-2

Overload Trucks



Overload 1




Figure 13-3

13.1.2 NBI Rating (LFR)

Ratings shall be performed per the latest AASHTO *Manual for Condition Evaluation of Bridges*. All bridges, except timber, shall be rated based on the Load Factor method. The HS20 Truck/ Lane shall be used to calculate the Inventory and Operating Ratings.

13.1.2.1 Strength Method (LFR)

The basic equation shall be:

$$R.F. = \frac{\Phi R_n - \gamma_{DL} D \pm S}{\gamma_L L_{(1+I)}}$$

Where:

R.F. = Rating Factor (Ratio of Capacity to Demand)

R_n = Nominal Capacity of the Member

Φ = Resistance Factor (Per AASHTO Standard Specs.)

D = Unfactored Dead Load Moment or Shear

L = Unfactored Live Load Moment or Shear

S = Unfactored Prestress Secondary Moment or Shear

I = Impact Factor, Span dependant (Per AASHTO Standard Specs.)

γ_{DL} = 1.3 (Dead Load Factor)

γ_L = 2.17 for Inventory (Live Load Factor)

= 1.30 for Operating

Truck/Lane shall be used to calculate the Inventory and Operating Ratings.

13.1.2.2 Service Method (LFR)

Prestressed and Post-tensioned Members

Prestressed and post-tensioned members in positive moment regions, and where post-tensioning is continuous over the supports, shall also be rated based on allowable stresses at service loads. The lowest rating factor between Service and Load Factor methods shall be the governing Inventory rating. The Operating rating shall be based on the load factor method using a Live Load factor of 1.30. Service ratings for the HS20 shall be the same as stated in Section 13.1.1.2, except the impact factor shall be span dependant.

Timber Members

$$R.F. = \frac{F_A - F_D}{F_L}$$

R.F. = Rating Factor (Ratio of Capacity to Demand)

F_A = Allowable bending stress

F_D = Dead Load Stress

F_L = Stress due to Live Load, does not include Impact

* F_A, for Inventory rating shall be per AASHTO Standard Specifications. For Operating Ratings, F_A shall be per AASHTO Standard Specifications with a 33% increase in the allowable stress.

13.1.2.3 Resistance Factors (LFR)

The resistance factors for NBI ratings shall be per the latest AASHTO Standard Specifications. Following are the NBI resistance factors:

Steel Members:	1.00 (Flexure) 1.00 (Shear)
Prestressed Concrete	1.00 (Flexure, Positive moment) 0.90 (Shear)
Post-tensioned, Cast in place:	0.95 (Flexure, Positive moment) 0.90 (Shear)
Reinforced Concrete:	0.90 (Flexure) 0.85 (Shear)

For prestressed and post-tensioned members, where reinforcing steel is used to resist negative moment, the resistance factors for reinforced concrete section shall be used in the ratings.

13.1.2.4 Live Loads

The HS-20 truck or lane shall be used to load rate bridge members. The number of lanes shall be per AASHTO Standard Specifications, Section 3.6. When multiple lanes are considered, apply the appropriate multilane reduction factor given in Section 13.1.2.6. Load distribution methods are discussed under specific bridge types. Do not consider sidewalk live loads in rating analysis.

13.1.2.5 Impact (LFR)

Impact is expressed as a fraction of the live load stress, and shall be determined by the following formula:

$$I = \frac{50}{125 + L}$$

I = Rating Factor (Ratio of Capacity to Demand)

L = Length in feet of the portion of the span that is loaded to produce the maximum stress in the member.

*AASHTO Standard Specifications for Highway Bridges 3.8.2.1.

13.1.2.6 Live Load Reduction Factors (LFR)

Number of Loaded Lanes	Reduction Factor
One or two lanes	1.0
Three lanes	0.9
Four lanes or more	0.75

13.2 Special Rating Criteria

13.2.1 Dead Loads

Dead Loads shall be as defined in the AASHTO *Standard Specifications for Highway Bridges*, except concrete weight shall be 155 pcf.

13.2.2 Live Load Distribution Factors

Live Load distribution factors shall be per Chapter 3 of the AASHTO *Standard Specifications for Highway Bridges.* Distribution factors are selected assuming one traffic lane where the roadway is less than 20 feet wide or two or more traffic lanes where the roadway is 20 feet or wider.

13.2.3 Reinforced Concrete Structures

For conventional reinforced concrete members of existing bridges, checking of serviceability shall not be part of the rating evaluation.

Rating for shear in the longitudinal direction shall begin at a distance $h/2$ from the centerline of the bearing or face of integral cross beams (h= total depth).

13.2.4 Concrete Decks

For all concrete bridge decks, except flat slab bridges, that are designed per current AASHTO criteria for HS-20 loading or heavier, loading will be considered structurally sufficient and need not be rated. However, for existing bridge decks having any of the following conditions, rating of the deck is required:

1. Deck was designed for live loads lighter than HS-20.
2. Deck overhang is more than half the girder spacing.
3. Bridge Inspection Report Code is 4 or below.
4. When the original traffic barrier(s) or rail have been replaced by heavier barrier.

When rating of the deck is required, live load shall include all vehicular loads as specified in Section 13.1.1.8. Live load moments for the HS20 truck shall be per Section 3.24.3.1 of the AASHTO *Standard Specifications*. Live load moments for the legal and overload trucks shall be per the AASHTO *Manual for Maintenance Inspection of Bridges*.

13.2.5 Concrete Crossbeams

Live loads can be applied to the crossbeam as moving point loads at any location between curbs that produce the maximum effect.

When rating for shear in crossbeams, current AASHTO *Design Specifications* requires shear design to be at the face of support if there is a concentrated load within a distance “d” from the face of support. This requirement is new relative to earlier editions of AASHTO *Design Specifications* that allowed shear reinforcement design to be at a distance “d” from the face of support. When rating existing crossbeams that show no indication of distress on the latest inspection report, but have a rating factor of less than one (1.0), a more detailed/accurate shear analysis should be performed. One acceptable method is the “Strut and Tie” model analysis. For existing box girders and T-beams integral with the crossbeams, in lieu of this detailed analysis, dead and live loads can be assumed as uniformly distributed and the shear rating performed at a distance “d” from the face of support.

13.2.6 In-Span Hinges

For in-span hinges, rating for shear and bending moment should be performed based on the reduced cross-sections at the hinge seat. Diagonal hairpin bars are part of this rating as they provide primary reinforcement through the shear plane.

13.2.7 Concrete Box Girder Structures

Bridges with spread box girders shall be rated on a per box basis. Otherwise, the rating shall be on the per bridge basis for all applied loads.

13.2.8 Prestressed Concrete Girder Structures

Rate on a per member basis.

13.2.9 Concrete Slab Structures

Rate cast-in-place solid slabs on a per foot of width basis. Rate precast panels on a per panel basis. Rate cast-in-place voided slabs based on a width of slab equal to the predominant center-to-center spacing of voids.

When rating flat slabs on concrete piling, assume pin-supports at the slab/pile interface of interior piers and the slab continuous over the supports. If ratings using this assumption are less than 1.0, the piles should be modeled as columns with fixity assumed at 10 feet below the ground surface.

Pile caps are to be rated if deemed critical by the engineer.

13.2.10 Steel Structures

On existing bridges, checking of fatigue and serviceability shall not be part of the rating evaluation.

13.2.11 Steel Floor Systems

Floorbeams and stringers shall be rated as if they are simply supported. Assume the distance from outside face to outside face of end connections as the lengths for the analysis. Live loads can be applied to the floorbeam as moving point loads at any location between curbs, which produce the maximum effect.

Rating of connections is not required unless there is evidence of deterioration.

13.2.12 Steel Truss Structures

The capacity of steel truss spans, regardless of length, shall follow the AASHTO *Guide Specifications for Strength Design of Truss Bridges* (Load Factor Design) and the AASHTO *Standard Design Specifications*. In the event the two specifications are contradictory, the guide specification shall be followed.

Rate on a per truss basis or perform a 3-D analysis or simplified distribution methods. Assume nonredundancy of truss members and pinned connections.

In general, rate chords, diagonals, verticals, end posts, stringers, and floorbeams. Do not rate connections unless there is evidence of deterioration, except for pinned connections with trusses. For pin-connected trusses, also analyze pins for shear, and the side plates for bearing capacity.

For truss members that have been heat-straightened three or more times, deduct 0.1 from ϕ(Phi).

13.2.13 Timber Structures

Unless the species and grade is known, assume Douglas fir, select structural for members installed prior to 1955 and Douglas fir, No. 1 after 1955. The allowable stresses for beams and stringers shall be as listed in the AASHTO *Standard Specifications*.

The nominal dimensions should be used to calculate dead load, and the net dimensions to calculate section modulus. If the member is charred, it may be assumed the $^1/_4$-inch of material is lost on all surfaces. Unless the member is notched or otherwise suspect, shear need not be calculated.

When calculating loads, no impact is assumed.

13.2.14 Widened or Rehabilitated Structures

For widened bridges, rate crossbeams in all cases.

Longitudinal rating for the widened portion will be required only when the width of the widened portion on one side of the structure is greater than or equal to 10′-0” or more throughout the length of the structure.

For rehabilitated bridges, a load rating will be required if the load carrying capacity of the structure is altered by the rehabilitation.

13.3 Load Rating Software

Rating of State bridges shall be performed using the BRIDG for Windows software, latest version.

For more complex structures such as Steel Curved girders and Arches, different software may be used to analyze the loads after obtaining approval from the Load Rating Engineer.

13.4 Load Rating Reports

Rating reports shall consist of:

1. A Bridge Rating summary sheet, as shown on page 13-A1 reflecting the lowest rating factor, including superstructure components not analyzed by BRIDG, for each loading condition. The summary sheet shall be stamped and signed by a professional engineer licensed in the state of Washington.
2. A brief report of any anomalies in the ratings and an explanation of the cause of any rating factor below 1.0.
3. Hard copy of computer output files (RPT files) used for rating, and any other calculations or special analysis required.
4. A complete set of plans for the bridge.
5. One 3.5-inch data diskettes or compact disk which contains the final versions of all input and output files, and other calculations created in performing the load rating.

All reports shall be bound in Accopress-type binders.

When the load rating calculations are produced as part of a design project (new, widening, or rehabilitation,) the load rating report and design calculations shall be bound separately.

13.5 Bibliography

1. AASHTO Guide Specifications For Strength Evaluation of Existing Steel and Concrete Structures, 1989.
2. AASHTO Manual for Condition Evaluation of Bridges, Second Edition.
3. AASHTO Guide Specifications for Strength Design of Truss Bridges, Load Factor Design, 1985.
4. AASHTO Manual for Maintenance Inspection of Bridges.
5. AASHTO Standard Specifications for Highway Bridges, 17th edition.

PE Stamp Here

BRIDGE RATING SUMMARY

Bridge Name: _____
Bridge Number: _____
Span Types: _____
Bridge Length: _____
Design Load: _____
Rated By: _____
Checked By: _____
Date: _____

Truck	RF	γ	Controlling Point
HS-20			
AASHTO 1			
AASHTO 2			
3AASHTO 3			
OL-1			
OL-2			

NBI Rating	RF	Tons (US)	Controlling Point
Inventory			
Operating			

Remarks:

Bridge Rating Summary
Figure 13-A-1